
The Python Library Reference

출시 버전 2.7.17

**Guido van Rossum
and the Python development team**

4월 06, 2020

1	소개	3
2	내장 함수	5
3	Non-essential Built-in Functions	27
4	내장 상수	29
4.1	site 모듈에 의해 추가된 상수들	30
5	내장형	31
5.1	논리값 검사	31
5.2	논리 연산— and, or, not	32
5.3	비교	32
5.4	Numeric Types — int, float, long, complex	33
5.5	이터레이터 형	37
5.6	Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange	37
5.7	집합 형 — set, frozenset	49
5.8	매핑 형 — dict	52
5.9	File Objects	56
5.10	memoryview type	60
5.11	컨텍스트 관리자 형	61
5.12	기타 내장형	62
5.13	특수 어트리뷰트	65
6	내장 예외	67
6.1	예외 계층 구조	72
7	String Services	75
7.1	string — Common string operations	75
7.2	re — Regular expression operations	88
7.3	struct — Interpret strings as packed binary data	104
7.4	difflib — Helpers for computing deltas	109
7.5	StringIO — Read and write strings as files	119
7.6	cStringIO — Faster version of StringIO	120
7.7	textwrap — Text wrapping and filling	120
7.8	codecs — Codec registry and base classes	123
7.9	unicodedata — Unicode Database	138

7.10	stringprep — Internet String Preparation	139
7.11	fpformat — Floating point conversions	141
8	Data Types	143
8.1	datetime — Basic date and time types	143
8.2	calendar — General calendar-related functions	168
8.3	collections — High-performance container datatypes	172
8.4	heapq — Heap queue algorithm	187
8.5	bisect — Array bisection algorithm	191
8.6	array — Efficient arrays of numeric values	193
8.7	sets — Unordered collections of unique elements	196
8.8	sched — Event scheduler	199
8.9	mutex — Mutual exclusion support	201
8.10	Queue — A synchronized queue class	202
8.11	weakref — Weak references	204
8.12	UserDict — Class wrapper for dictionary objects	208
8.13	UserList — Class wrapper for list objects	209
8.14	UserString — Class wrapper for string objects	210
8.15	types — Names for built-in types	211
8.16	new — Creation of runtime internal objects	213
8.17	copy — Shallow and deep copy operations	214
8.18	pprint — Data pretty printer	215
8.19	repr — Alternate repr() implementation	218
9	숫자와 수학 모듈	221
9.1	numbers — 숫자 추상 베이스 클래스	221
9.2	math — Mathematical functions	224
9.3	cmath — Mathematical functions for complex numbers	229
9.4	decimal — Decimal fixed point and floating point arithmetic	231
9.5	fractions — Rational numbers	257
9.6	random — Generate pseudo-random numbers	259
9.7	itertools — Functions creating iterators for efficient looping	263
9.8	functools — Higher-order functions and operations on callable objects	277
9.9	operator — Standard operators as functions	280
10	File and Directory Access	289
10.1	os.path — Common pathname manipulations	289
10.2	fileinput — Iterate over lines from multiple input streams	293
10.3	stat — Interpreting stat() results	295
10.4	statvfs — Constants used with os.statvfs()	299
10.5	filecmp — File and Directory Comparisons	300
10.6	tempfile — Generate temporary files and directories	302
10.7	glob — Unix style pathname pattern expansion	305
10.8	fnmatch — Unix filename pattern matching	306
10.9	linecache — Random access to text lines	307
10.10	shutil — High-level file operations	307
10.11	dircache — Cached directory listings	312
10.12	macpath — Mac OS 9 path manipulation functions	312
11	Data Persistence	313
11.1	pickle — Python object serialization	313
11.2	cPickle — A faster pickle	324
11.3	copy_reg — Register pickle support functions	324
11.4	shelve — Python object persistence	325
11.5	marshal — Internal Python object serialization	328

11.6	<code>anydbm</code> — Generic access to DBM-style databases	329
11.7	<code>whichdb</code> — Guess which DBM module created a database	330
11.8	<code>dbm</code> — Simple «database» interface	331
11.9	<code>gdbm</code> — GNU’s reinterpretation of <code>dbm</code>	332
11.10	<code>dbhash</code> — DBM-style interface to the BSD database library	333
11.11	<code>bsddb</code> — Interface to Berkeley DB library	334
11.12	<code>dumbdbm</code> — Portable DBM implementation	337
11.13	<code>sqlite3</code> — DB-API 2.0 interface for SQLite databases	338
12	Data Compression and Archiving	359
12.1	<code>zlib</code> — Compression compatible with gzip	359
12.2	<code>gzip</code> — Support for gzip files	362
12.3	<code>bz2</code> — Compression compatible with bzip2	364
12.4	<code>zipfile</code> — Work with ZIP archives	366
12.5	<code>tarfile</code> — Read and write tar archive files	372
13	File Formats	383
13.1	<code>csv</code> — CSV File Reading and Writing	383
13.2	<code>ConfigParser</code> — Configuration file parser	391
13.3	<code>robotparser</code> — Parser for <code>robots.txt</code>	398
13.4	<code>netrc</code> — <code>netrc</code> file processing	399
13.5	<code>xdrllib</code> — Encode and decode XDR data	400
13.6	<code>plistlib</code> — Generate and parse Mac OS X <code>.plist</code> files	403
14	Cryptographic Services	405
14.1	<code>hashlib</code> — Secure hashes and message digests	405
14.2	<code>hmac</code> — Keyed-Hashing for Message Authentication	408
14.3	<code>md5</code> — MD5 message digest algorithm	409
14.4	<code>sha</code> — SHA-1 message digest algorithm	410
15	Generic Operating System Services	411
15.1	<code>os</code> — Miscellaneous operating system interfaces	411
15.2	<code>io</code> — Core tools for working with streams	440
15.3	<code>time</code> — Time access and conversions	452
15.4	<code>argparse</code> — Parser for command-line options, arguments and sub-commands	458
15.5	<code>optparse</code> — Parser for command line options	487
15.6	<code>getopt</code> — C-style parser for command line options	515
15.7	<code>logging</code> — Logging facility for Python	517
15.8	<code>logging.config</code> — Logging configuration	529
15.9	<code>logging.handlers</code> — Logging handlers	539
15.10	<code>getpass</code> — Portable password input	548
15.11	<code>curses</code> — Terminal handling for character-cell displays	548
15.12	<code>curses.textpad</code> — Text input widget for <code>curses</code> programs	565
15.13	<code>curses.ascii</code> — Utilities for ASCII characters	567
15.14	<code>curses.panel</code> — A panel stack extension for <code>curses</code>	569
15.15	<code>platform</code> — Access to underlying platform’s identifying data	570
15.16	<code>errno</code> — Standard <code>errno</code> system symbols	574
15.17	<code>ctypes</code> — A foreign function library for Python	580
16	Optional Operating System Services	615
16.1	<code>select</code> — Waiting for I/O completion	615
16.2	<code>threading</code> — Higher-level threading interface	620
16.3	<code>thread</code> — Multiple threads of control	630
16.4	<code>dummy_threading</code> — Drop-in replacement for the <code>threading</code> module	632
16.5	<code>dummy_thread</code> — Drop-in replacement for the <code>thread</code> module	632

16.6	<code>multiprocessing</code> — Process-based «threading» interface	633
16.7	<code>mmap</code> — Memory-mapped file support	686
16.8	<code>readline</code> — GNU readline interface	689
16.9	<code>rlcompleter</code> — Completion function for GNU readline	693
17	Interprocess Communication and Networking	695
17.1	<code>subprocess</code> — Subprocess management	695
17.2	<code>socket</code> — Low-level networking interface	707
17.3	<code>ssl</code> — TLS/SSL wrapper for socket objects	719
17.4	<code>signal</code> — Set handlers for asynchronous events	744
17.5	<code>popen2</code> — Subprocesses with accessible I/O streams	747
17.6	<code>asyncore</code> — Asynchronous socket handler	749
17.7	<code>asynchat</code> — Asynchronous socket command/response handler	753
18	Internet Data Handling	757
18.1	<code>email</code> — An email and MIME handling package	757
18.2	<code>json</code> — JSON encoder and decoder	788
18.3	<code>mailcap</code> — Mailcap file handling	796
18.4	<code>mailbox</code> — Manipulate mailboxes in various formats	797
18.5	<code>mhlib</code> — Access to MH mailboxes	817
18.6	<code>mimetools</code> — Tools for parsing MIME messages	819
18.7	<code>mimetypes</code> — Map filenames to MIME types	820
18.8	<code>MimeWriter</code> — Generic MIME file writer	823
18.9	<code>mimify</code> — MIME processing of mail messages	824
18.10	<code>multifile</code> — Support for files containing distinct parts	825
18.11	<code>rfc822</code> — Parse RFC 2822 mail headers	827
18.12	<code>base64</code> — RFC 3548: Base16, Base32, Base64 Data Encodings	831
18.13	<code>binhex</code> — Encode and decode binhex4 files	833
18.14	<code>binascii</code> — Convert between binary and ASCII	833
18.15	<code>quopri</code> — Encode and decode MIME quoted-printable data	835
18.16	<code>uu</code> — Encode and decode uuencode files	836
19	Structured Markup Processing Tools	837
19.1	<code>HTMLParser</code> — Simple HTML and XHTML parser	837
19.2	<code>sgmllib</code> — Simple SGML parser	842
19.3	<code>htmllib</code> — A parser for HTML documents	845
19.4	<code>htmlentitydefs</code> — Definitions of HTML general entities	847
19.5	<code>XML Processing Modules</code>	847
19.6	<code>XML vulnerabilities</code>	848
19.7	<code>xml.etree.ElementTree</code> — The ElementTree XML API	849
19.8	<code>xml.dom</code> — The Document Object Model API	862
19.9	<code>xml.dom.minidom</code> — Minimal DOM implementation	873
19.10	<code>xml.dom.pulldom</code> — Support for building partial DOM trees	878
19.11	<code>xml.sax</code> — Support for SAX2 parsers	878
19.12	<code>xml.sax.handler</code> — Base classes for SAX handlers	880
19.13	<code>xml.sax.saxutils</code> — SAX Utilities	885
19.14	<code>xml.sax.xmlreader</code> — Interface for XML parsers	886
19.15	<code>xml.parsers.expat</code> — Fast XML parsing using Expat	890
20	Internet Protocols and Support	899
20.1	<code>webbrowser</code> — Convenient Web-browser controller	899
20.2	<code>cgi</code> — Common Gateway Interface support	902
20.3	<code>cgitb</code> — Traceback manager for CGI scripts	909
20.4	<code>wsgiref</code> — WSGI Utilities and Reference Implementation	910
20.5	<code>urllib</code> — Open arbitrary resources by URL	918

20.6	<code>urllib2</code> — extensible library for opening URLs	925
20.7	<code>httpplib</code> — HTTP protocol client	937
20.8	<code>ftplib</code> — FTP protocol client	943
20.9	<code>poplib</code> — POP3 protocol client	948
20.10	<code>imaplib</code> — IMAP4 protocol client	950
20.11	<code>nntplib</code> — NNTP protocol client	956
20.12	<code>smtplib</code> — SMTP protocol client	960
20.13	<code>smtpd</code> — SMTP Server	964
20.14	<code>telnetlib</code> — Telnet client	965
20.15	<code>uuid</code> — UUID objects according to RFC 4122	968
20.16	<code>urlparse</code> — Parse URLs into components	971
20.17	<code>SocketServer</code> — A framework for network servers	975
20.18	<code>BaseHTTPServer</code> — Basic HTTP server	983
20.19	<code>SimpleHTTPServer</code> — Simple HTTP request handler	987
20.20	<code>CGIHTTPServer</code> — CGI-capable HTTP request handler	988
20.21	<code>cookielib</code> — Cookie handling for HTTP clients	989
20.22	<code>Cookie</code> — HTTP state management	998
20.23	<code>xmlrpclib</code> — XML-RPC client access	1002
20.24	<code>SimpleXMLRPCServer</code> — Basic XML-RPC server	1010
20.25	<code>DocXMLRPCServer</code> — Self-documenting XML-RPC server	1014
21	Multimedia Services	1017
21.1	<code>audioop</code> — Manipulate raw audio data	1017
21.2	<code>imageop</code> — Manipulate raw image data	1020
21.3	<code>aifc</code> — Read and write AIFF and AIFC files	1021
21.4	<code>sunau</code> — Read and write Sun AU files	1024
21.5	<code>wave</code> — Read and write WAV files	1026
21.6	<code>chunk</code> — Read IFF chunked data	1028
21.7	<code>colorsys</code> — Conversions between color systems	1030
21.8	<code>imghdr</code> — Determine the type of an image	1030
21.9	<code>sndhdr</code> — Determine type of sound file	1031
21.10	<code>ossaudiodev</code> — Access to OSS-compatible audio devices	1032
22	Internationalization	1037
22.1	<code>gettext</code> — Multilingual internationalization services	1037
22.2	<code>locale</code> — Internationalization services	1047
23	Program Frameworks	1055
23.1	<code>cmd</code> — Support for line-oriented command interpreters	1055
23.2	<code>shlex</code> — Simple lexical analysis	1058
24	Graphical User Interfaces with Tk	1063
24.1	<code>Tkinter</code> — Python interface to Tcl/Tk	1063
24.2	<code>ttk</code> — Tk themed widgets	1074
24.3	<code>Tix</code> — Extension widgets for Tk	1093
24.4	<code>ScrolledText</code> — Scrolled Text Widget	1098
24.5	<code>turtle</code> — Turtle graphics for Tk	1098
24.6	<code>IDLE</code>	1129
24.7	Other Graphical User Interface Packages	1137
25	Development Tools	1139
25.1	<code>pydoc</code> — Documentation generator and online help system	1139
25.2	<code>doctest</code> — Test interactive Python examples	1140
25.3	<code>unittest</code> — Unit testing framework	1165
25.4	<code>2to3</code> - Automated Python 2 to 3 code translation	1190

25.5	<code>test</code> — Regression tests package for Python	1195
25.6	<code>test.support</code> — Utility functions for tests	1197
26	Debugging and Profiling	1203
26.1	<code>bdb</code> — Debugger framework	1203
26.2	<code>pdb</code> — The Python Debugger	1207
26.3	Debugger Commands	1209
26.4	The Python Profilers	1212
26.5	<code>hotshot</code> — High performance logging profiler	1220
26.6	<code>timeit</code> — Measure execution time of small code snippets	1222
26.7	<code>trace</code> — Trace or track Python statement execution	1226
27	Software Packaging and Distribution	1231
27.1	<code>distutils</code> — Building and installing Python modules	1231
27.2	<code>ensurepip</code> — Bootstrapping the <code>pip</code> installer	1232
28	파이썬 실행시간 서비스	1235
28.1	<code>sys</code> — System-specific parameters and functions	1235
28.2	<code>sysconfig</code> — Provide access to Python’s configuration information	1247
28.3	<code>__builtin__</code> — Built-in objects	1251
28.4	<code>future_builtins</code> — Python 3 builtins	1251
28.5	<code>__main__</code> — 최상위 스크립트 환경	1252
28.6	<code>warnings</code> — Warning control	1252
28.7	<code>contextlib</code> — Utilities for <code>with</code> -statement contexts	1257
28.8	<code>abc</code> — Abstract Base Classes	1259
28.9	<code>atexit</code> — Exit handlers	1262
28.10	<code>traceback</code> — Print or retrieve a stack traceback	1263
28.11	<code>__future__</code> — Future statement definitions	1267
28.12	<code>gc</code> — Garbage Collector interface	1268
28.13	<code>inspect</code> — Inspect live objects	1271
28.14	<code>site</code> — Site-specific configuration hook	1277
28.15	<code>user</code> — User-specific configuration hook	1279
28.16	<code>fpectl</code> — Floating point exception control	1280
29	Custom Python Interpreters	1283
29.1	<code>code</code> — Interpreter base classes	1283
29.2	<code>codeop</code> — Compile Python code	1285
30	Restricted Execution	1287
30.1	<code>rexec</code> — Restricted execution framework	1288
30.2	<code>Bastion</code> — Restricting access to objects	1291
31	Importing Modules	1293
31.1	<code>imp</code> — Access the <code>import</code> internals	1293
31.2	<code>importlib</code> — Convenience wrappers for <code>__import__()</code>	1297
31.3	<code>imputil</code> — Import utilities	1297
31.4	<code>zipimport</code> — Import modules from Zip archives	1300
31.5	<code>pkgutil</code> — Package extension utility	1302
31.6	<code>modulefinder</code> — Find modules used by a script	1304
31.7	<code>runpy</code> — Locating and executing Python modules	1306
32	Python Language Services	1309
32.1	<code>parser</code> — Access Python parse trees	1309
32.2	<code>ast</code> — Abstract Syntax Trees	1313
32.3	<code>symtable</code> — Access to the compiler’s symbol tables	1319

32.4	<code>symbol</code> — Constants used with Python parse trees	1321
32.5	<code>token</code> — Constants used with Python parse trees	1321
32.6	<code>keyword</code> — Testing for Python keywords	1323
32.7	<code>tokenize</code> — Tokenizer for Python source	1323
32.8	<code>tabnanny</code> — Detection of ambiguous indentation	1325
32.9	<code>pyclbr</code> — Python class browser support	1326
32.10	<code>py_compile</code> — Compile Python source files	1327
32.11	<code>compileall</code> — Byte-compile Python libraries	1327
32.12	<code>dis</code> — Disassembler for Python bytecode	1329
32.13	<code>pickletools</code> — Tools for pickle developers	1338
33	Python compiler package	1339
33.1	The basic interface	1339
33.2	Limitations	1340
33.3	Python Abstract Syntax	1340
33.4	Using Visitors to Walk ASTs	1346
33.5	Bytecode Generation	1346
34	Miscellaneous Services	1347
34.1	<code>formatter</code> — Generic output formatting	1347
35	MS Windows Specific Services	1353
35.1	<code>msilib</code> — Read and write Microsoft Installer files	1353
35.2	<code>msvcrt</code> — Useful routines from the MS VC++ runtime	1359
35.3	<code>_winreg</code> — Windows registry access	1361
35.4	<code>winsound</code> — Sound-playing interface for Windows	1369
36	Unix Specific Services	1371
36.1	<code>posix</code> — The most common POSIX system calls	1371
36.2	<code>pwd</code> — The password database	1372
36.3	<code>spwd</code> — The shadow password database	1373
36.4	<code>grp</code> — The group database	1374
36.5	<code>crypt</code> — Function to check Unix passwords	1374
36.6	<code>dl</code> — Call C functions in shared objects	1375
36.7	<code>termios</code> — POSIX style tty control	1376
36.8	<code>tty</code> — Terminal control functions	1377
36.9	<code>pty</code> — Pseudo-terminal utilities	1378
36.10	<code>fcntl</code> — The <code>fcntl</code> and <code>ioctl</code> system calls	1378
36.11	<code>pipes</code> — Interface to shell pipelines	1380
36.12	<code>posixfile</code> — File-like objects with locking support	1382
36.13	<code>resource</code> — Resource usage information	1384
36.14	<code>nis</code> — Interface to Sun's NIS (Yellow Pages)	1386
36.15	<code>syslog</code> — Unix syslog library routines	1387
36.16	<code>commands</code> — Utilities for running commands	1388
37	Mac OS X specific services	1391
37.1	<code>ic</code> — Access to the Mac OS X Internet Config	1391
37.2	<code>MacOS</code> — Access to Mac OS interpreter features	1393
37.3	<code>macostools</code> — Convenience routines for file manipulation	1394
37.4	<code>findertools</code> — The finder 's Apple Events interface	1395
37.5	<code>EasyDialogs</code> — Basic Macintosh dialogs	1395
37.6	<code>FrameWork</code> — Interactive application framework	1398
37.7	<code>autoGIL</code> — Global Interpreter Lock handling in event loops	1401
37.8	<code>Mac OS Toolbox Modules</code>	1402
37.9	<code>ColorPicker</code> — Color selection dialog	1405

38 MacPython OSA Modules	1407
38.1 gensuitemodule — Generate OSA stub packages	1408
38.2 aetools — OSA client support	1409
38.3 aepack — Conversion between Python variables and AppleEvent data containers	1410
38.4 aetypes — AppleEvent objects	1411
38.5 MiniAEFrame — Open Scripting Architecture server support	1412
39 SGI IRIX Specific Services	1415
39.1 al — Audio functions on the SGI	1415
39.2 AL — Constants used with the al module	1417
39.3 cd — CD-ROM access on SGI systems	1417
39.4 fl — FORMS library for graphical user interfaces	1421
39.5 FL — Constants used with the fl module	1425
39.6 flp — Functions for loading stored FORMS designs	1426
39.7 fm — <i>Font Manager</i> interface	1426
39.8 gl — <i>Graphics Library</i> interface	1427
39.9 DEVICE — Constants used with the gl module	1429
39.10 GL — Constants used with the gl module	1429
39.11 imgfile — Support for SGI imglib files	1429
39.12 jpeg — Read and write JPEG files	1430
40 SunOS Specific Services	1431
40.1 sunaudiodev — Access to Sun audio hardware	1431
40.2 SUNAUDIODEV — Constants used with sunaudiodev	1433
41 Undocumented Modules	1435
41.1 Miscellaneous useful utilities	1435
41.2 Platform specific modules	1435
41.3 Multimedia	1436
41.4 Undocumented Mac OS modules	1436
41.5 Obsolete	1437
41.6 SGI-specific Extension modules	1438
A 용어집	1439
B About these documents	1449
B.1 Contributors to the Python Documentation	1449
C History and License	1451
C.1 History of the software	1451
C.2 Terms and conditions for accessing or otherwise using Python	1452
C.3 Licenses and Acknowledgements for Incorporated Software	1455
D 저작권	1467
Bibliography	1469
Python 모듈 목록	1471
색인	1477

reference-index 는 파이썬 언어의 정확한 문법과 의미를 설명하고 있지만, 이 라이브러리 레퍼런스 설명서는 파이썬과 함께 배포되는 표준 라이브러리를 설명합니다. 또한, 파이썬 배포판에 일반적으로 포함되어있는 선택적 구성 요소 중 일부를 설명합니다.

파이썬의 표준 라이브러리는 매우 광범위하며, 아래 나열된 긴 목록에 표시된 대로 다양한 기능을 제공합니다. 라이브러리에는 일상적인 프로그래밍에서 발생하는 많은 문제에 대한 표준적인 해결책을 제공하는 파이썬으로 작성된 모듈뿐만 아니라, 파일 I/O와 같은 시스템 기능에 액세스하는 (C로 작성된) 내장 모듈들이 포함됩니다 (이 모듈들이 없다면 파이썬 프로그래머가 액세스할 방법은 없습니다). 이 모듈 중 일부는 플랫폼 관련 사항을 플랫폼 중립적인 API들로 추상화시킴으로써, 파이썬 프로그램의 이식성을 권장하고 개선하도록 명시적으로 설계되었습니다.

윈도우 플랫폼용 파이썬 설치 프로그램은 일반적으로 전체 표준 라이브러리를 포함하며 종종 많은 추가 구성 요소도 포함합니다. 유닉스와 같은 운영체제의 경우, 파이썬은 일반적으로 패키지 모음으로 제공되기 때문에, 운영 체제와 함께 제공되는 패키지 도구를 사용하여 선택적 구성 요소의 일부 또는 전부를 구해야 할 수 있습니다.

표준 라이브러리 외에도, 수천 가지 컴포넌트(개별 프로그램과 모듈부터 패키지 및 전체 응용 프로그램 개발 프레임워크까지)가 늘어나고 있는데, [파이썬 패키지 색인](#) 에서 얻을 수 있습니다.

CHAPTER 1

소개

《파이썬 라이브러리》에는 여러 가지 구성 요소가 포함되어 있습니다.

여기에는 일반적으로 숫자 및 리스트와 같이 언어의 《핵심》 부분으로 간주하는 데이터형이 포함됩니다. 이러한 형의 경우, 파이썬 언어 핵심은 리터럴의 형식을 정의하고 그 의미에 몇 가지 제약을 가하지만, 의미를 완전히 정의하지는 않습니다. (반면에, 언어 핵심은 연산자의 철자법과 우선순위와 같은 문법적 속성을 정의합니다.)

라이브러리는 또한 내장 함수와 예외를 포함합니다 — `import` 문을 쓰지 않고도 모든 파이썬 코드에서 사용할 수 있는 객체들입니다. 이들 중 일부는 언어 핵심에 의해 정의되지만, 핵심 의미에 필수적인 것은 아니며 여기에서 설명합니다.

그러나 라이브러리 대부분은 모듈 컬렉션으로 구성됩니다. 이 컬렉션을 나누는 데는 여러 가지 방법이 있습니다. 일부 모듈은 C로 작성되고 파이썬 인터프리터에 내장되어 있습니다; 다른 것은 파이썬으로 작성되고 소스 형식으로 임포트됩니다. 일부 모듈은 스택 추적 인쇄와 같이 파이썬에 매우 특정한 인터페이스를 제공합니다; 일부는 특정 하드웨어에 대한 액세스와 같이 운영 체제에 특정한 인터페이스를 제공합니다; 다른 것은 월드 와이드 웹과 같은 응용 프로그램 영역에 특정한 인터페이스를 제공합니다. 일부 모듈은 파이썬의 모든 버전과 이식에서 사용할 수 있습니다; 다른 것은 하위 시스템이 지원하거나 요구할 때만 사용할 수 있습니다; 그러나 다른 것들은 파이썬이 컴파일되고 설치될 때 특정 설정 옵션이 선택되었을 때만 사용할 수 있습니다.

This manual is organized 《from the inside out:》 it first describes the built-in data types, then the built-in functions and exceptions, and finally the modules, grouped in chapters of related modules. The ordering of the chapters as well as the ordering of the modules within each chapter is roughly from most relevant to least important.

즉, 처음부터 이 설명서를 읽고, 지루할 때 다음 장으로 건너뛰면, 파이썬 라이브러리가 지원하는 사용 가능한 모듈과 응용 프로그램 영역에 대한 적당한 개요를 얻게 됩니다. 물론 소설처럼 읽을 필요는 없습니다. (설명서 앞에 있는) 목차를 검색하거나, (뒤에 있는) 색인에서 특정 함수, 모듈 또는 용어를 찾을 수도 있습니다. 그리고 마지막으로, 무작위 주제에 대해 배우는 것을 즐긴다면, 임의의 페이지 번호 (모듈 `random` 참조)를 선택하고 한두 섹션을 읽으면 됩니다. 이 설명서의 섹션을 읽는 순서와 관계없이, **내장 함수** 장에서 시작하는 것이 도움이 되는데, 설명서의 나머지 부분은 이 내용에 익숙하다고 가정하기 때문입니다.

쇼를 시작합시다!

CHAPTER 2

내장 함수

The Python interpreter has a number of functions built into it that are always available. They are listed here in alphabetical order.

		내장 함수		
<code>abs()</code>	<code>divmod()</code>	<code>input()</code>	<code>open()</code>	<code>staticmethod()</code>
<code>all()</code>	<code>enumerate()</code>	<code>int()</code>	<code>ord()</code>	<code>str()</code>
<code>any()</code>	<code>eval()</code>	<code>isinstance()</code>	<code>pow()</code>	<code>sum()</code>
<code>basestring()</code>	<code>execfile()</code>	<code>issubclass()</code>	<code>print()</code>	<code>super()</code>
<code>bin()</code>	<code>file()</code>	<code>iter()</code>	<code>property()</code>	<code>tuple()</code>
<code>bool()</code>	<code>filter()</code>	<code>len()</code>	<code>range()</code>	<code>type()</code>
<code>bytearray()</code>	<code>float()</code>	<code>list()</code>	<code>raw_input()</code>	<code>unichr()</code>
<code>callable()</code>	<code>format()</code>	<code>locals()</code>	<code>reduce()</code>	<code>unicode()</code>
<code>chr()</code>	<code>frozenset()</code>	<code>long()</code>	<code>reload()</code>	<code>vars()</code>
<code>classmethod()</code>	<code>getattr()</code>	<code>map()</code>	<code>repr()</code>	<code>xrange()</code>
<code>cmp()</code>	<code>globals()</code>	<code>max()</code>	<code>reversed()</code>	<code>zip()</code>
<code>compile()</code>	<code>hasattr()</code>	<code>memoryview()</code>	<code>round()</code>	<code>__import__()</code>
<code>complex()</code>	<code>hash()</code>	<code>min()</code>	<code>set()</code>	
<code>delattr()</code>	<code>help()</code>	<code>next()</code>	<code>setattr()</code>	
<code>dict()</code>	<code>hex()</code>	<code>object()</code>	<code>slice()</code>	
<code>dir()</code>	<code>id()</code>	<code>oct()</code>	<code>sorted()</code>	

In addition, there are other four built-in functions that are no longer considered essential: `apply()`, `buffer()`, `coerce()`, and `intern()`. They are documented in the *Non-essential Built-in Functions* section.

abs(*x*)

Return the absolute value of a number. The argument may be a plain or long integer or a floating point number. If the argument is a complex number, its magnitude is returned.

all(*iterable*)

*iterable*의 모든 요소가 참이면 (또는 *iterable*이 비어있으면) True를 돌려줍니다. 다음과 동등합니다:

```
def all(iterable):
    for element in iterable:
        if not element:
            return False
    return True
```

버전 2.5에 추가.

any(*iterable*)

*iterable*의 요소 중 어느 하나라도 참이면 *True*를 돌려줍니다. *iterable*이 비어 있으면 *False*를 돌려줍니다. 다음과 동등합니다:

```
def any(iterable):
    for element in iterable:
        if element:
            return True
    return False
```

버전 2.5에 추가.

basestring()

This abstract type is the superclass for *str* and *unicode*. It cannot be called or instantiated, but it can be used to test whether an object is an instance of *str* or *unicode*. *isinstance*(obj, basestring) is equivalent to *isinstance*(obj, (str, unicode)).

버전 2.3에 추가.

bin(*x*)

Convert an integer number to a binary string. The result is a valid Python expression. If *x* is not a Python *int* object, it has to define an *__index__*() method that returns an integer.

버전 2.6에 추가.

class bool([*x*])

Return a Boolean value, i.e. one of *True* or *False*. *x* is converted using the standard truth testing procedure. If *x* is false or omitted, this returns *False*; otherwise it returns *True*. *bool* is also a class, which is a subclass of *int*. Class *bool* cannot be subclassed further. Its only instances are *False* and *True*.

버전 2.2.1에 추가.

버전 2.3에서 변경: If no argument is given, this function returns *False*.

class bytearray([*source*[, *encoding*[, *errors*]]])

Return a new array of bytes. The *bytearray* class is a mutable sequence of integers in the range $0 \leq x < 256$. It has most of the usual methods of mutable sequences, described in 가변 시퀀스 형, as well as most methods that the *str* type has, see 문자열 메서드.

선택적 *source* 파라미터는 몇 가지 다른 방법으로 배열을 초기화하는 데 사용할 수 있습니다:

- If it is *unicode*, you must also give the *encoding* (and optionally, *errors*) parameters; *bytearray*() then converts the unicode to bytes using *unicode.encode*() .
- 정수 면, 배열은 그 크기를 갖고, 널 바이트로 초기화됩니다.
- 버퍼(*buffer*) 인터페이스를 제공하는 객체면, 객체의 읽기 전용 버퍼가 바이트 배열을 초기화하는 데 사용됩니다.
- 이터러블 이면, 범위 $0 \leq x < 256$ 의 정수를 제공하는 이터러블이어야 하고, 그 값들이 배열의 초기 내용물로 사용됩니다.

인자가 없으면 크기 0의 배열이 만들어집니다.

버전 2.6에 추가.

callable (*object*)

Return *True* if the *object* argument appears callable, *False* if not. If this returns true, it is still possible that a call fails, but if it is false, calling *object* will never succeed. Note that classes are callable (calling a class returns a new instance); class instances are callable if they have a `__call__()` method.

chr (*i*)

Return a string of one character whose ASCII code is the integer *i*. For example, `chr(97)` returns the string `'a'`. This is the inverse of `ord()`. The argument must be in the range `[0..255]`, inclusive; *ValueError* will be raised if *i* is outside that range. See also `unichr()`.

classmethod (*function*)

Return a class method for *function*.

인스턴스 메서드가 인스턴스를 받는 것처럼, 클래스 메서드는 클래스를 묵시적인 첫 번째 인자로 받습니다. 클래스 메서드를 선언하려면 이 관용구를 사용합니다:

```
class C(object):
    @classmethod
    def f(cls, arg1, arg2, ...):
        ...
```

The `@classmethod` form is a function *decorator* – see function for details.

A class method can be called either on the class (such as `C.f()`) or on an instance (such as `C().f()`). The instance is ignored except for its class. If a class method is called for a derived class, the derived class object is passed as the implied first argument.

Class methods are different than C++ or Java static methods. If you want those, see `staticmethod()`.

For more information on class methods, see types.

버전 2.2에 추가.

버전 2.4에서 변경: Function decorator syntax added.

cmp (*x*, *y*)

Compare the two objects *x* and *y* and return an integer according to the outcome. The return value is negative if *x* < *y*, zero if *x* == *y* and strictly positive if *x* > *y*.

compile (*source*, *filename*, *mode* [, *flags* [, *dont_inherit*]])

Compile the *source* into a code or AST object. Code objects can be executed by an `exec` statement or evaluated by a call to `eval()`. *source* can either be a Unicode string, a *Latin-1* encoded string or an AST object. Refer to the *ast* module documentation for information on how to work with AST objects.

filename 인자는 코드를 읽은 파일을 제공해야 합니다; 파일에서 읽지 않으면 인식 가능한 값을 전달합니다 ('<string>' 이 일반적으로 사용됩니다).

mode 인자는 컴파일해야 하는 코드 종류를 지정합니다; *source* 가 문장의 시퀀스로 구성되어 있다면 `exec`, 단일 표현식으로 구성되어 있다면 `'eval'`, 단일 대화형 문장으로 구성되면 `'single'` 이 될 수 있습니다 (마지막의 경우 `None` 이외의 값으로 구해지는 표현식 문은 인쇄됩니다).

선택적 인자 *flags* 와 *dont_inherit* 는 어떤 퓨처 문 (PEP 236 참조) 이 *source* 의 컴파일에 영향을 미칠지 제어합니다. 둘 다 제공되지 않는 경우 (또는 둘 다 0의 경우), 코드는 `compile()` 을 호출하는 코드에 적용되고 있는 퓨처 문으로 컴파일됩니다. *flags* 인자가 주어지고, *dont_inherit* 가 없으면 (또는 0) 원래 사용될 것에 더해 *flags* 인자로 지정된 퓨처 문이 사용됩니다. *dont_inherit* 가 0이 아닌 정수면 *flags* 인자가 사용됩니다 – `compile` 을 호출하는 코드에 적용되는 퓨처 문은 무시됩니다.

퓨처 문은 여러 개의 문장을 지정하기 위해 비트 OR 될 수 있는 비트에 의해 지정됩니다. 주어진 기능을 지정하는 데 필요한 비트 필드는 `__future__` 모듈의 `_Feature` 인스턴스에서 `compiler_flag` 어트리뷰트로 찾을 수 있습니다.

This function raises *SyntaxError* if the compiled source is invalid, and *TypeError* if the source contains null bytes.

파이썬 코드를 AST 표현으로 파싱하려면, `ast.parse()` 를 보세요.

참고: 'single' 또는 'eval' mode로 여러 줄 코드를 가진 문자열을 컴파일할 때, 적어도 하나의 개행 문자로 입력을 끝내야 합니다. 이것은 `code` 모듈에서 문장이 불완전한지 완전한지를 쉽게 탐지하게 하기 위함입니다.

경고: 파이썬의 AST 컴파일러에서 스택 깊이 제한으로 인해, AST 객체로 컴파일할 때 충분히 크고 복잡한 문자열로 파이썬 인터프리터가 크래시를 일으키도록 만들 수 있습니다.

버전 2.3에서 변경: The *flags* and *dont_inherit* arguments were added.

버전 2.6에서 변경: Support for compiling AST objects.

버전 2.7에서 변경: Allowed use of Windows and Mac newlines. Also input in 'exec' mode does not have to end in a newline anymore.

class complex ([*real*[, *imag*]])

Return a complex number with the value *real* + *imag**1j or convert a string or number to a complex number. If the first parameter is a string, it will be interpreted as a complex number and the function must be called without a second parameter. The second parameter can never be a string. Each argument may be any numeric type (including complex). If *imag* is omitted, it defaults to zero and the function serves as a numeric conversion function like `int()`, `long()` and `float()`. If both arguments are omitted, returns 0j.

참고: 문자열을 변환할 때, 문자열은 중앙의 + 또는 - 연산자 주위에 공백을 포함해서는 안 됩니다. 예를 들어, `complex('1+2j')` 는 괜찮지만 `complex('1 + 2j')` 는 *ValueError* 를 일으킵니다.

복소수 형은 *Numeric Types — int, float, long, complex* 에서 설명합니다.

delattr (*object*, *name*)

이것은 `setattr()` 의 친척입니다. 인자는 객체와 문자열입니다. 문자열은 객체의 어트리뷰트 중 하나의 이름이어야 합니다. 이 함수는 객체가 허용하는 경우 명명된 어트리뷰트를 삭제합니다. 예를 들어, `delattr(x, 'foobar')` 는 `del x.foobar` 와 동등합니다.

class dict (**kwarg)

class dict (*mapping*, **kwarg)

class dict (*iterable*, **kwarg)

새 딕셔너리를 만듭니다. *dict* 객체는 딕셔너리 클래스입니다. 이 클래스에 대한 문서는 *dict* 및 매핑 형 — *dict* 을 보세요.

다른 컨테이너의 경우 *list*, *set* 및 *tuple* 클래스와 *collections* 모듈을 보세요.

dir ([*object*])

인자가 없으면, 현재 지역 스코프에 있는 이름들의 리스트를 돌려줍니다. 인자가 있으면, 해당 객체에 유효한 어트리뷰트들의 리스트를 돌려주려고 시도합니다.

객체에 `__dir__()` 메서드가 있으면, 이 메서드가 호출되는데, 반드시 어트리뷰트 리스트를 돌려줘야 합니다. 이렇게 하면 커스텀 `__getattr__()` 또는 `__getattribute__()` 함수를 구현하는 객체가 `dir()` 이 어트리뷰트들을 보고하는 방법을 커스터마이징할 수 있습니다.

객체가 `__dir__()` 을 제공하지 않으면, 함수는 (정의되었다면) 객체의 `__dict__` 어트리뷰트와 형 객체로부터 정보를 수집하기 위해 최선을 다합니다. 결과로 얻어지는 리스트는 반드시 완전하지는 않으며, 객체가 커스텀 `__getattr__()` 을 가질 때 부정확할 수도 있습니다.

기본 `dir()` 메커니즘은 다른 형의 객체에 대해서 다르게 동작하는데, 완전한 정보보다는 가장 적절한 정보를 만들려고 시도하기 때문입니다:

- 객체가 모듈 객체면, 리스트에는 모듈 어트리뷰트의 이름이 포함됩니다.
- 객체가 형 또는 클래스 객체면, 리스트에는 그것의 어트리뷰트 이름과 베이스의 어트리뷰트 이름들이 재귀적으로 포함됩니다.
- 그 밖의 경우, 리스트에는 객체의 어트리뷰트 이름, 해당 클래스의 어트리뷰트 이름 및 해당 클래스의 베이스 클래스들의 어트리뷰트 이름을 재귀적으로 포함합니다.

결과 리스트는 알파벳 순으로 정렬됩니다. 예를 들어:

```
>>> import struct
>>> dir()      # show the names in the module namespace
['__builtins__', '__doc__', '__name__', 'struct']
>>> dir(struct) # show the names in the struct module
['Struct', '__builtins__', '__doc__', '__file__', '__name__',
 '__package__', '__clearcache', 'calcsize', 'error', 'pack', 'pack_into',
 'unpack', 'unpack_from']
>>> class Shape(object):
    def __dir__(self):
        return ['area', 'perimeter', 'location']
>>> s = Shape()
>>> dir(s)
['area', 'perimeter', 'location']
```

참고: `dir()` 은 주로 대화형 프롬프트에서의 사용 편의를 위해 제공되기 때문에, 엄격하거나 일관되게 정의된 이름 집합을 제공하기보다 흥미로운 이름 집합을 제공하려고 시도하며, 상세한 동작은 배포마다 변경될 수 있습니다. 예를 들어, 인자가 클래스면 메타 클래스 어트리뷰트는 결과 리스트에 없습니다.

`divmod(a, b)`

Take two (non complex) numbers as arguments and return a pair of numbers consisting of their quotient and remainder when using long division. With mixed operand types, the rules for binary arithmetic operators apply. For plain and long integers, the result is the same as $(a // b, a \% b)$. For floating point numbers the result is $(q, a \% b)$, where q is usually `math.floor(a / b)` but may be 1 less than that. In any case $q * b + a \% b$ is very close to a , if $a \% b$ is non-zero it has the same sign as b , and $0 \leq \text{abs}(a \% b) < \text{abs}(b)$.

버전 2.3에서 변경: Using `divmod()` with complex numbers is deprecated.

`enumerate(sequence, start=0)`

Return an enumerate object. *sequence* must be a sequence, an *iterator*, or some other object which supports iteration. The next() method of the iterator returned by `enumerate()` returns a tuple containing a count (from *start* which defaults to 0) and the values obtained from iterating over *sequence*:

```
>>> seasons = ['Spring', 'Summer', 'Fall', 'Winter']
>>> list(enumerate(seasons))
[(0, 'Spring'), (1, 'Summer'), (2, 'Fall'), (3, 'Winter')]
>>> list(enumerate(seasons, start=1))
[(1, 'Spring'), (2, 'Summer'), (3, 'Fall'), (4, 'Winter')]
```

다음과 동등합니다:

```
def enumerate(sequence, start=0):
    n = start
    for elem in sequence:
        yield n, elem
        n += 1
```

버전 2.3에 추가.

버전 2.6에서 변경 : The *start* parameter was added.

eval (*expression*[, *globals*[, *locals*]])

The arguments are a Unicode or *Latin-1* encoded string and optional *globals* and *locals*. If provided, *globals* must be a dictionary. If provided, *locals* can be any mapping object.

버전 2.4에서 변경 : formerly *locals* was required to be a dictionary.

The *expression* argument is parsed and evaluated as a Python expression (technically speaking, a condition list) using the *globals* and *locals* dictionaries as global and local namespace. If the *globals* dictionary is present and lacks `<__builtins__>`, the current *globals* are copied into *globals* before *expression* is parsed. This means that *expression* normally has full access to the standard `__builtin__` module and restricted environments are propagated. If the *locals* dictionary is omitted it defaults to the *globals* dictionary. If both dictionaries are omitted, the expression is executed in the environment where `eval()` is called. The return value is the result of the evaluated expression. Syntax errors are reported as exceptions. Example:

```
>>> x = 1
>>> print eval('x+1')
2
```

이 함수는 임의의 코드 객체 (`compile()`로 만든 것과 같은)를 실행하는 데에도 사용할 수 있습니다. 이 경우 문자열 대신 코드 객체를 전달합니다. 코드 객체가 `mode` 인자 'exec'로 컴파일되었다면, `eval()`의 반환 값은 `None`입니다.

Hints: dynamic execution of statements is supported by the `exec` statement. Execution of statements from a file is supported by the `execfile()` function. The `globals()` and `locals()` functions returns the current global and local dictionary, respectively, which may be useful to pass around for use by `eval()` or `execfile()`.

리터럴 만 포함된 표현식의 값을 안전하게 구할 수 있는 함수 `ast.literal_eval()`를 보세요.

execfile (*filename*[, *globals*[, *locals*]])

This function is similar to the `exec` statement, but parses a file instead of a string. It is different from the `import` statement in that it does not use the module administration — it reads the file unconditionally and does not create a new module.¹

The arguments are a file name and two optional dictionaries. The file is parsed and evaluated as a sequence of Python statements (similarly to a module) using the *globals* and *locals* dictionaries as global and local namespace. If provided, *locals* can be any mapping object. Remember that at module level, *globals* and *locals* are the same dictionary. If two separate objects are passed as *globals* and *locals*, the code will be executed as if it were embedded in a class definition.

버전 2.4에서 변경 : formerly *locals* was required to be a dictionary.

If the *locals* dictionary is omitted it defaults to the *globals* dictionary. If both dictionaries are omitted, the expression is executed in the environment where `execfile()` is called. The return value is `None`.

참고 : The default *locals* act as described for function `locals()` below: modifications to the default *locals* dictionary should not be attempted. Pass an explicit *locals* dictionary if you need to see effects of the code on *locals* after function `execfile()` returns. `execfile()` cannot be used reliably to modify a function's *locals*.

file (*name*[, *mode*[, *buffering*]])

Constructor function for the *file* type, described further in section *File Objects*. The constructor's arguments are the same as those of the `open()` built-in function described below.

¹ It is used relatively rarely so does not warrant being made into a statement.

When opening a file, it's preferable to use `open()` instead of invoking this constructor directly. `file` is more suited to type testing (for example, writing `isinstance(f, file)`).

버전 2.2에 추가.

filter (*function*, *iterable*)

Construct a list from those elements of *iterable* for which *function* returns true. *iterable* may be either a sequence, a container which supports iteration, or an iterator. If *iterable* is a string or a tuple, the result also has that type; otherwise it is always a list. If *function* is `None`, the identity function is assumed, that is, all elements of *iterable* that are false are removed.

Note that `filter(function, iterable)` is equivalent to `[item for item in iterable if function(item)]` if *function* is not `None` and `[item for item in iterable if item]` if *function* is `None`.

See `itertools.ifilter()` and `itertools.ifilterfalse()` for iterator versions of this function, including a variation that filters for elements where the *function* returns false.

class float ([*x*])

숫자 또는 문자열 *x* 로 부터 실수를 만들어 돌려줍니다.

If the argument is a string, it must contain a possibly signed decimal or floating point number, possibly embedded in whitespace. The argument may also be `[+-]nan` or `[+-]inf`. Otherwise, the argument may be a plain or long integer or a floating point number, and a floating point number with the same value (within Python's floating point precision) is returned. If no argument is given, returns `0.0`.

참고: When passing in a string, values for NaN and Infinity may be returned, depending on the underlying C library. Float accepts the strings `nan`, `inf` and `-inf` for NaN and positive or negative infinity. The case and a leading `+` are ignored as well as a leading `-` is ignored for NaN. Float always represents NaN and infinity as `nan`, `inf` or `-inf`.

float 형은 *Numeric Types — int, float, long, complex* 에 설명되어 있습니다.

format (*value* [, *format_spec*])

format_spec 의 제어에 따라, *value* 를 《포맷된》 표현으로 변환합니다. *format_spec* 의 해석은 *value* 인자의 형에 의존하지만, 대부분의 내장형에 의해 사용되는 표준 포매팅 문법이 있습니다: *Format Specification Mini-Language*.

참고: `format(value, format_spec)` merely calls `value.__format__(format_spec)`.

버전 2.6에 추가.

class frozenset ([*iterable*])

새 *frozenset* 객체를 돌려주는데, 선택적으로 *iterable* 에서 가져온 요소를 포함합니다. *frozenset* 은 내장 클래스입니다. 이 클래스에 대한 문서는 *frozenset* 과 집합 형 — *set, frozenset* 을 보세요.

다른 컨테이너의 경우 *set*, *list*, *tuple* 및 *dict* 클래스와 *collections* 모듈을 보세요.

버전 2.4에 추가.

getattr (*object*, *name* [, *default*])

주어진 이름의 *object* 어트리뷰트를 돌려줍니다. *name* 은 문자열이어야 합니다. 문자열이 객체의 어트리뷰트 중 하나의 이름이면, 결과는 그 어트리뷰트의 값입니다. 예를 들어, `getattr(x, 'foobar')` 는 `x.foobar` 와 동등합니다. 명명된 어트리뷰트가 없으면, *default* 가 제공되는 경우 그 값이 반환되고, 그렇지 않으면 *AttributeError* 가 발생합니다.

globals ()

현재 전역 심볼 테이블을 나타내는 딕셔너리를 돌려줍니다. 이것은 항상 현재 모듈의 딕셔너리입니다 (함수 또는 메서드 내에서, 이 모듈은 그것들을 호출하는 모듈이 아니라, 그것들이 정의된 모듈입니다).

hasattr (*object*, *name*)

The arguments are an object and a string. The result is `True` if the string is the name of one of the object's attributes, `False` if not. (This is implemented by calling `getattr(object, name)` and seeing whether it raises an exception or not.)

hash (*object*)

Return the hash value of the object (if it has one). Hash values are integers. They are used to quickly compare dictionary keys during a dictionary lookup. Numeric values that compare equal have the same hash value (even if they are of different types, as is the case for 1 and 1.0).

help ([*object*])

내장 도움말 시스템을 호출합니다. (이 함수는 대화형 사용을 위한 것입니다.) 인자가 제공되지 않으면, 인터프리터 콘솔에서 대화형 도움말 시스템이 시작됩니다. 인자가 문자열이면 문자열은 모듈, 함수, 클래스, 메서드, 키워드 또는 문헌테이션 주제의 이름으로 조회되고, 도움말 페이지가 콘솔에 인쇄됩니다. 인자가 다른 종류의 객체면, 객체에 대한 도움말 페이지가 만들어집니다.

이 함수는 `site` 모듈에 의해 내장 이름 공간에 추가됩니다.

버전 2.2에 추가.

hex (*x*)

Convert an integer number (of any size) to a lowercase hexadecimal string prefixed with `0x`, for example:

```
>>> hex(255)
'0xff'
>>> hex(-42)
'-0x2a'
>>> hex(1L)
'0x1L'
```

If *x* is not a Python `int` or `long` object, it has to define a `__hex__()` method that returns a string.

16진수 문자열을 진수 16을 사용해서 정수로 변환하려면 `int()` 도 보세요.

참고: `float`에 대한 16진수 문자열 표현을 얻으려면, `float.hex()` 메서드를 사용하세요.

버전 2.4에서 변경: Formerly only returned an unsigned literal.

id (*object*)

Return the «identity» of an object. This is an integer (or long integer) which is guaranteed to be unique and constant for this object during its lifetime. Two objects with non-overlapping lifetimes may have the same `id()` value.

CPython implementation detail: This is the address of the object in memory.

input ([*prompt*])

Equivalent to `eval(raw_input(prompt))`.

This function does not catch user errors. If the input is not syntactically valid, a `SyntaxError` will be raised. Other exceptions may be raised if there is an error during evaluation.

`readline` 모듈이 로드되었다면, `input()` 은 그것을 사용하여 정교한 줄 편집과 히스토리 기능을 제공합니다.

Consider using the `raw_input()` function for general input from users.

class int (*x=0*)**class int** (*x*, *base=10*)

Return an integer object constructed from a number or string *x*, or return 0 if no arguments are given. If *x* is a

number, it can be a plain integer, a long integer, or a floating point number. If *x* is floating point, the conversion truncates towards zero. If the argument is outside the integer range, the function returns a long object instead.

If *x* is not a number or if *base* is given, then *x* must be a string or Unicode object representing an integer literal in radix *base*. Optionally, the literal can be preceded by + or - (with no space in between) and surrounded by whitespace. A base-*n* literal consists of the digits 0 to *n*-1, with a to z (or A to Z) having values 10 to 35. The default *base* is 10. The allowed values are 0 and 2–36. Base-2, -8, and -16 literals can be optionally prefixed with 0b/0B, 0o/0O/0, or 0x/0X, as with integer literals in code. Base 0 means to interpret the string exactly as an integer literal, so that the actual base is 2, 8, 10, or 16.

정수 형은 *Numeric Types — int, float, long, complex* 에 설명되어 있습니다.

isinstance (*object*, *classinfo*)

Return true if the *object* argument is an instance of the *classinfo* argument, or of a (direct, indirect or *virtual*) subclass thereof. Also return true if *classinfo* is a type object (new-style class) and *object* is an object of that type or of a (direct, indirect or *virtual*) subclass thereof. If *object* is not a class instance or an object of the given type, the function always returns false. If *classinfo* is a tuple of class or type objects (or recursively, other such tuples), return true if *object* is an instance of any of the classes or types. If *classinfo* is not a class, type, or tuple of classes, types, and such tuples, a *TypeError* exception is raised.

버전 2.2에서 변경 : Support for a tuple of type information was added.

issubclass (*class*, *classinfo*)

class 가 *classinfo* 의 서브 클래스 (직접, 간접 또는 가상) 면 참을 돌려줍니다. 클래스는 그 자체의 서브 클래스로 간주합니다. *classinfo* 는 클래스 객체의 튜플 일 수 있습니다. 이 경우 *classinfo* 의 모든 항목이 검사됩니다. 다른 모든 경우에는, *TypeError* 예외가 발생합니다.

버전 2.3에서 변경 : Support for a tuple of type information was added.

iter (*o*[, *sentinel*])

Return an *iterator* object. The first argument is interpreted very differently depending on the presence of the second argument. Without a second argument, *o* must be a collection object which supports the iteration protocol (the `__iter__()` method), or it must support the sequence protocol (the `__getitem__()` method with integer arguments starting at 0). If it does not support either of those protocols, *TypeError* is raised. If the second argument, *sentinel*, is given, then *o* must be a callable object. The iterator created in this case will call *o* with no arguments for each call to its `next()` method; if the value returned is equal to *sentinel*, *StopIteration* will be raised, otherwise the value will be returned.

두 번째 형태의 `iter()` 의 유용한 응용은 특정 줄에 도달할 때까지 파일의 줄을 읽는 것입니다. 다음의 예는 `readline()` 메서드가 빈 문자열을 돌려줄 때까지 파일을 읽습니다:

```
with open('mydata.txt') as fp:
    for line in iter(fp.readline, ''):
        process_line(line)
```

버전 2.2에 추가.

len (*s*)

객체의 길이 (항목 수)를 돌려줍니다. 인자는 시퀀스 (문자열, 바이트열, 튜플, 리스트 또는 range 같은) 또는 컬렉션 (딕셔너리, 집합 또는 불변 집합 같은) 일 수 있습니다.

class list ([*iterable*])

Return a list whose items are the same and in the same order as *iterable*'s items. *iterable* may be either a sequence, a container that supports iteration, or an iterator object. If *iterable* is already a list, a copy is made and returned, similar to `iterable[:]`. For instance, `list('abc')` returns `['a', 'b', 'c']` and `list((1, 2, 3))` returns `[1, 2, 3]`. If no argument is given, returns a new empty list, `[]`.

`list` is a mutable sequence type, as documented in *Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange*. For other containers see the built in *dict*, *set*, and *tuple* classes, and the *collections* module.

locals()

현재 지역 심볼 테이블을 나타내는 딕셔너리를 갱신하고 돌려줍니다. `locals()` 이 함수 블록에서 호출될 때 자유 변수를 돌려주지만, 클래스 블록에서 호출할 때는 그렇지 않습니다.

참고: 이 딕셔너리의 내용은 수정해서는 안 됩니다. 변경 사항은 인터프리터가 사용하는 지역 및 자유 변수의 값에 영향을 미치지 않을 수 있습니다.

class long (*x*=0)**class long** (*x*, *base*=10)

Return a long integer object constructed from a string or number *x*. If the argument is a string, it must contain a possibly signed number of arbitrary size, possibly embedded in whitespace. The *base* argument is interpreted in the same way as for `int()`, and may only be given when *x* is a string. Otherwise, the argument may be a plain or long integer or a floating point number, and a long integer with the same value is returned. Conversion of floating point numbers to integers truncates (towards zero). If no arguments are given, returns 0L.

The long type is described in *Numeric Types — int, float, long, complex*.

map (*function*, *iterable*, ...)

Apply *function* to every item of *iterable* and return a list of the results. If additional *iterable* arguments are passed, *function* must take that many arguments and is applied to the items from all iterables in parallel. If one iterable is shorter than another it is assumed to be extended with None items. If *function* is None, the identity function is assumed; if there are multiple arguments, `map()` returns a list consisting of tuples containing the corresponding items from all iterables (a kind of transpose operation). The *iterable* arguments may be a sequence or any iterable object; the result is always a list.

max (*iterable*[, *key*])**max** (*arg1*, *arg2*, **args*[, *key*])

iterable 에서 가장 큰 항목이나 두 개 이상의 인자 중 가장 큰 것을 돌려줍니다.

If one positional argument is provided, *iterable* must be a non-empty iterable (such as a non-empty string, tuple or list). The largest item in the iterable is returned. If two or more positional arguments are provided, the largest of the positional arguments is returned.

The optional *key* argument specifies a one-argument ordering function like that used for `list.sort()`. The *key* argument, if supplied, must be in keyword form (for example, `max(a, b, c, key=func)`).

버전 2.5에서 변경: Added support for the optional *key* argument.

memoryview (*obj*)

지정된 인자로부터 만들어진 《메모리 뷰》 객체를 돌려줍니다. 자세한 정보는 *memoryview type* 를 보세요.

min (*iterable*[, *key*])**min** (*arg1*, *arg2*, **args*[, *key*])

iterable 에서 가장 작은 항목이나 두 개 이상의 인자 중 가장 작은 것을 돌려줍니다.

If one positional argument is provided, *iterable* must be a non-empty iterable (such as a non-empty string, tuple or list). The smallest item in the iterable is returned. If two or more positional arguments are provided, the smallest of the positional arguments is returned.

The optional *key* argument specifies a one-argument ordering function like that used for `list.sort()`. The *key* argument, if supplied, must be in keyword form (for example, `min(a, b, c, key=func)`).

버전 2.5에서 변경: Added support for the optional *key* argument.

next (*iterator*[, *default*])

Retrieve the next item from the *iterator* by calling its `next()` method. If *default* is given, it is returned if the iterator is exhausted, otherwise *StopIteration* is raised.

버전 2.6에 추가.

class object

Return a new featureless object. *object* is a base for all new style classes. It has the methods that are common to all instances of new style classes.

버전 2.2에 추가.

버전 2.3에서 변경: This function does not accept any arguments. Formerly, it accepted arguments but ignored them.

oct (*x*)

Convert an integer number (of any size) to an octal string. The result is a valid Python expression.

버전 2.4에서 변경: Formerly only returned an unsigned literal.

open (*name* [, *mode* [, *buffering*]])

Open a file, returning an object of the *file* type described in section *File Objects*. If the file cannot be opened, *IOError* is raised. When opening a file, it's preferable to use *open()* instead of invoking the *file* constructor directly.

The first two arguments are the same as for *stdio*'s *fopen()*: *name* is the file name to be opened, and *mode* is a string indicating how the file is to be opened.

The most commonly-used values of *mode* are 'r' for reading, 'w' for writing (truncating the file if it already exists), and 'a' for appending (which on *some* Unix systems means that *all* writes append to the end of the file regardless of the current seek position). If *mode* is omitted, it defaults to 'r'. The default is to use text mode, which may convert '\n' characters to a platform-specific representation on writing and back on reading. Thus, when opening a binary file, you should append 'b' to the *mode* value to open the file in binary mode, which will improve portability. (Appending 'b' is useful even on systems that don't treat binary and text files differently, where it serves as documentation.) See below for more possible values of *mode*.

The optional *buffering* argument specifies the file's desired buffer size: 0 means unbuffered, 1 means line buffered, any other positive value means use a buffer of (approximately) that size (in bytes). A negative *buffering* means to use the system default, which is usually line buffered for tty devices and fully buffered for other files. If omitted, the system default is used.²

Modes 'r+', 'w+' and 'a+' open the file for updating (reading and writing); note that 'w+' truncates the file. Append 'b' to the mode to open the file in binary mode, on systems that differentiate between binary and text files; on systems that don't have this distinction, adding the 'b' has no effect.

In addition to the standard *fopen()* values *mode* may be 'U' or 'rU'. Python is usually built with *universal newlines* support; supplying 'U' opens the file as a text file, but lines may be terminated by any of the following: the Unix end-of-line convention '\n', the Macintosh convention '\r', or the Windows convention '\r\n'. All of these external representations are seen as '\n' by the Python program. If Python is built without universal newlines support a *mode* with 'U' is the same as normal text mode. Note that file objects so opened also have an attribute called *newlines* which has a value of *None* (if no newlines have yet been seen), '\n', '\r', '\r\n', or a tuple containing all the newline types seen.

Python enforces that the mode, after stripping 'U', begins with 'r', 'w' or 'a'.

Python provides many file handling modules including *fileinput*, *os*, *os.path*, *tempfile*, and *shutil*.

버전 2.5에서 변경: Restriction on first letter of mode string introduced.

ord (*c*)

Given a string of length one, return an integer representing the Unicode code point of the character when the argument is a unicode object, or the value of the byte when the argument is an 8-bit string. For example, *ord('a')* returns the integer 97, *ord(u'\u2020')* returns 8224. This is the inverse of *chr()* for 8-bit strings and of *unichr()* for unicode objects. If a unicode argument is given and Python was built with UCS2 Unicode, then

² Specifying a buffer size currently has no effect on systems that don't have *setvbuf()*. The interface to specify the buffer size is not done using a method that calls *setvbuf()*, because that may dump core when called after any I/O has been performed, and there's no reliable way to determine whether this is the case.

the character's code point must be in the range [0..65535] inclusive; otherwise the string length is two, and a `TypeError` will be raised.

pow (*x*, *y*[, *z*])

*x*의 *y* 거듭제곱을 돌려줍니다; *z*가 있는 경우, *x*의 *y* 거듭제곱의 모듈로 *z*를 돌려줍니다 (`pow(x, y) % z`보다 더 빠르게 계산됩니다). 두 개의 인자 형식인 `pow(x, y)`는 거듭제곱 연산자를 사용하는 것과 동등합니다: `x ** y`.

The arguments must have numeric types. With mixed operand types, the coercion rules for binary arithmetic operators apply. For int and long int operands, the result has the same type as the operands (after coercion) unless the second argument is negative; in that case, all arguments are converted to float and a float result is delivered. For example, `10**2` returns 100, but `10**-2` returns 0.01. (This last feature was added in Python 2.2. In Python 2.1 and before, if both arguments were of integer types and the second argument was negative, an exception was raised.) If the second argument is negative, the third argument must be omitted. If *z* is present, *x* and *y* must be of integer types, and *y* must be non-negative. (This restriction was added in Python 2.2. In Python 2.1 and before, floating 3-argument `pow()` returned platform-dependent results depending on floating-point rounding accidents.)

print (**objects*, *sep*=' ', *end*='\n', *file*=`sys.stdout`)

Print *objects* to the stream *file*, separated by *sep* and followed by *end*. *sep*, *end* and *file*, if present, must be given as keyword arguments.

모든 비 키워드 인자는 `str()`이 하듯이 문자열로 변환된 후 스트림에 쓰이는데, *sep*로 구분되고 *end*를 뒤에 붙입니다. *sep*과 *end*는 모두 문자열이어야 합니다; None일 수도 있는데, 기본값을 사용한다는 뜻입니다. *objects*가 주어지지 않으면 `print()`는 *end*만 씁니다.

The *file* argument must be an object with a `write(string)` method; if it is not present or None, `sys.stdout` will be used. Output buffering is determined by *file*. Use `file.flush()` to ensure, for instance, immediate appearance on a screen.

참고: This function is not normally available as a built-in since the name `print` is recognized as the `print` statement. To disable the statement and use the `print()` function, use this future statement at the top of your module:

```
from __future__ import print_function
```

버전 2.6에 추가.

class property ([*fget*[, *fset*[, *fdel*[, *doc*]]]])

Return a property attribute for *new-style classes* (classes that derive from *object*).

*fget*은 어트리뷰트 값을 얻는 함수입니다. *fset*은 어트리뷰트 값을 설정하는 함수입니다. *fdel*은 어트리뷰트 값을 삭제하는 함수입니다. 그리고 *doc*은 어트리뷰트의 독스트링을 만듭니다.

전형적인 사용은 관리되는 어트리뷰트 *x*를 정의하는 것입니다:

```
class C(object):
    def __init__(self):
        self._x = None

    def getx(self):
        return self._x

    def setx(self, value):
        self._x = value

    def delx(self):
        del self._x
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
x = property(getx, setx, delx, "I'm the 'x' property.")
```

c 가 *C* 의 인스턴스면, *c.x* 는 게터 (getter) 를 호출하고, *cx = value* 는 세터 (setter) 를 호출하고, *del c.x* 는 딜리터 (deleter) 를 호출합니다.

주어진 경우, *doc* 은 프로퍼티 어트리뷰트의 독스트링이 됩니다. 그렇지 않으면, *fget* 의 독스트링 (있는 경우) 이 복사됩니다. 이렇게 하면 *property()* 를 데코레이터로 사용하여 읽기 전용 프로퍼티를 쉽게 만들 수 있습니다:

```
class Parrot(object):
    def __init__(self):
        self._voltage = 100000

    @property
    def voltage(self):
        """Get the current voltage."""
        return self._voltage
```

@property 데코레이터는 *voltage()* 메서드를 같은 이름의 읽기 전용 어트리뷰트에 대한 《게터》로 바꾸고, *voltage* 에 대한 독스트링을 《Get the current voltage.》로 설정합니다.

프로퍼티 객체는 데코레이터로 사용할 수 있는 *getter*, *setter* 및 *deleter* 메서드를 갖는데, 해당 접근자 함수를 데코레이트 된 함수로 설정한 프로퍼티의 사본을 만듭니다. 이것은 예제로 가장 잘 설명됩니다:

```
class C(object):
    def __init__(self):
        self._x = None

    @property
    def x(self):
        """I'm the 'x' property."""
        return self._x

    @x.setter
    def x(self, value):
        self._x = value

    @x.deleter
    def x(self):
        del self._x
```

이 코드는 첫 번째 예제와 정확히 동등합니다. 추가적인 함수들에 원래 프로퍼티 (이 경우 *x*) 와 같은 이름을 사용해야 합니다.

반환된 프로퍼티 객체는 생성자 인자에 해당하는 *fget*, *fset* 및 *fdel* 어트리뷰트를 가집니다.

버전 2.2에 추가.

버전 2.5에서 변경: Use *fget*'s docstring if no *doc* given.

버전 2.6에서 변경: The *getter*, *setter*, and *deleter* attributes were added.

range (*stop*)

range (*start*, *stop* [, *step*])

This is a versatile function to create lists containing arithmetic progressions. It is most often used in *for* loops. The arguments must be plain integers. If the *step* argument is omitted, it defaults to 1. If the *start* argument is omitted, it defaults to 0. The full form returns a list of plain integers [*start*, *start* + *step*, *start* +

`2 * step, ...]`. If *step* is positive, the last element is the largest `start + i * step` less than *stop*; if *step* is negative, the last element is the smallest `start + i * step` greater than *stop*. *step* must not be zero (or else `ValueError` is raised). Example:

```
>>> range(10)
[0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
>>> range(1, 11)
[1, 2, 3, 4, 5, 6, 7, 8, 9, 10]
>>> range(0, 30, 5)
[0, 5, 10, 15, 20, 25]
>>> range(0, 10, 3)
[0, 3, 6, 9]
>>> range(0, -10, -1)
[0, -1, -2, -3, -4, -5, -6, -7, -8, -9]
>>> range(0)
[]
>>> range(1, 0)
[]
```

`raw_input([prompt])`

If the *prompt* argument is present, it is written to standard output without a trailing newline. The function then reads a line from input, converts it to a string (stripping a trailing newline), and returns that. When EOF is read, `EOFError` is raised. Example:

```
>>> s = raw_input('--> ')
--> Monty Python's Flying Circus
>>> s
"Monty Python's Flying Circus"
```

If the `readline` module was loaded, then `raw_input()` will use it to provide elaborate line editing and history features.

`reduce(function, iterable[, initializer])`

Apply *function* of two arguments cumulatively to the items of *iterable*, from left to right, so as to reduce the iterable to a single value. For example, `reduce(lambda x, y: x+y, [1, 2, 3, 4, 5])` calculates `(((1+2)+3)+4)+5`. The left argument, *x*, is the accumulated value and the right argument, *y*, is the update value from the *iterable*. If the optional *initializer* is present, it is placed before the items of the iterable in the calculation, and serves as a default when the iterable is empty. If *initializer* is not given and *iterable* contains only one item, the first item is returned. Roughly equivalent to:

```
def reduce(function, iterable, initializer=None):
    it = iter(iterable)
    if initializer is None:
        try:
            initializer = next(it)
        except StopIteration:
            raise TypeError('reduce() of empty sequence with no initial value')
    accum_value = initializer
    for x in it:
        accum_value = function(accum_value, x)
    return accum_value
```

`reload(module)`

Reload a previously imported *module*. The argument must be a module object, so it must have been successfully imported before. This is useful if you have edited the module source file using an external editor and want to try out the new version without leaving the Python interpreter. The return value is the module object (the same as the *module* argument).

When `reload(module)` is executed:

- Python modules' code is recompiled and the module-level code reexecuted, defining a new set of objects which are bound to names in the module's dictionary. The `init` function of extension modules is not called a second time.
- As with all other objects in Python the old objects are only reclaimed after their reference counts drop to zero.
- The names in the module namespace are updated to point to any new or changed objects.
- Other references to the old objects (such as names external to the module) are not rebound to refer to the new objects and must be updated in each namespace where they occur if that is desired.

There are a number of other caveats:

When a module is reloaded, its dictionary (containing the module's global variables) is retained. Redefinitions of names will override the old definitions, so this is generally not a problem. If the new version of a module does not define a name that was defined by the old version, the old definition remains. This feature can be used to the module's advantage if it maintains a global table or cache of objects — with a `try` statement it can test for the table's presence and skip its initialization if desired:

```
try:
    cache
except NameError:
    cache = {}
```

It is generally not very useful to reload built-in or dynamically loaded modules. Reloading `sys`, `__main__`, `builtins` and other key modules is not recommended. In many cases extension modules are not designed to be initialized more than once, and may fail in arbitrary ways when reloaded.

If a module imports objects from another module using `from ... import ...`, calling `reload()` for the other module does not redefine the objects imported from it — one way around this is to re-execute the `from` statement, another is to use `import` and qualified names (`module.*name*`) instead.

If a module instantiates instances of a class, reloading the module that defines the class does not affect the method definitions of the instances — they continue to use the old class definition. The same is true for derived classes.

repr (*object*)

Return a string containing a printable representation of an object. This is the same value yielded by conversions (reverse quotes). It is sometimes useful to be able to access this operation as an ordinary function. For many types, this function makes an attempt to return a string that would yield an object with the same value when passed to `eval()`, otherwise the representation is a string enclosed in angle brackets that contains the name of the type of the object together with additional information often including the name and address of the object. A class can control what this function returns for its instances by defining a `__repr__()` method.

reversed (*seq*)

역 이터레이터를 돌려줍니다. *seq* 는 `__reversed__()` 메서드를 가졌거나 시퀀스 프로토콜 (`__len__()` 메서드와 0 에서 시작하는 정수 인자를 받는 `__getitem__()` 메서드)을 지원하는 객체여야 합니다.

버전 2.4에 추가.

버전 2.6에서 변경: Added the possibility to write a custom `__reversed__()` method.

round (*number*, [*ndigits*])

Return the floating point value *number* rounded to *ndigits* digits after the decimal point. If *ndigits* is omitted, it defaults to zero. The result is a floating point number. Values are rounded to the closest multiple of 10 to the power minus *ndigits*; if two multiples are equally close, rounding is done away from 0 (so, for example, `round(0.5)` is 1.0 and `round(-0.5)` is -1.0).

참고: float에 대한 `round()`의 동작은 예상과 다를 수 있습니다: 예를 들어, `round(2.675, 2)`는 2.68 대신에 2.67을 제공합니다. 이것은 버그가 아닙니다: 대부분의 십진 소수가 float로 정확히 표현될 수 없다는 사실로부터 오는 결과입니다. 자세한 정보는 `tut-fp-issues`를 보세요.

class set (`[iterable]`)

새 `set` 객체를 돌려줍니다. 선택적으로 `iterable`에서 가져온 요소를 갖습니다. `set`은 내장 클래스입니다. 이 클래스에 대한 문헌 페이지는 `set` 및 집합형 — `set`, `frozenset`을 보세요.

다른 컨테이너의 경우 내장 `frozenset`, `list`, `tuple` 및 `dict` 클래스와 `collections` 모듈을 보세요.

버전 2.4에 추가.

setattr (`object, name, value`)

이것은 `getattr()`과 한 쌍입니다. 인자는 객체, 문자열 및 임의의 값입니다. 문자열은 기존 어트리뷰트 또는 새 어트리뷰트의 이름을 지정할 수 있습니다. 이 함수는 객체가 허용하는 경우 값을 어트리뷰트에 대입합니다. 예를 들어, `setattr(x, 'foobar', 123)`는 `x.foobar = 123`과 동등합니다.

class slice (`stop`)

class slice (`start, stop[, step]`)

`range(start, stop, step)`에 의해 지정된 인덱스 세트를 나타내는 슬라이스 객체를 돌려줍니다. `start` 및 `step` 인자의 기본값은 `None`입니다. 슬라이스 객체는 단지 인자 값 (또는 기본값)을 돌려주는 `start`, `stop` 및 `step`의 읽기 전용 데이터 어트리뷰트를 갖습니다. 다른 명시적 기능은 없습니다; 그러나 Numerical Python과 다른 제삼자 확장이 사용합니다. 슬라이스 객체는 확장 인덱싱 문법을 사용할 때도 만들어집니다. 예를 들어: `a[start:stop:step]` 또는 `a[start:stop, i]`. 이터레이터를 돌려주는 대안 버전은 `itertools.islice()`를 보세요.

sorted (`iterable[, cmp[, key[, reverse]]]`)

`iterable`의 항목들로 새 정렬된 리스트를 돌려줍니다.

The optional arguments `cmp`, `key`, and `reverse` have the same meaning as those for the `list.sort()` method (described in section [가변 시퀀스 형](#)).

`cmp` specifies a custom comparison function of two arguments (iterable elements) which should return a negative, zero or positive number depending on whether the first argument is considered smaller than, equal to, or larger than the second argument: `cmp=lambda x, y: cmp(x.lower(), y.lower())`. The default value is `None`.

`key`는 하나의 인자를 받는 함수를 지정하는데, 각 리스트 요소들로부터 비교 키를 추출하는 데 사용됩니다: `key = str.lower`. 기본값은 `None`입니다 (요소를 직접 비교합니다).

`reverse`는 논리값입니다. `True`로 설정되면, 각 비교가 뒤집힌 것처럼 리스트 요소들이 정렬됩니다.

In general, the `key` and `reverse` conversion processes are much faster than specifying an equivalent `cmp` function. This is because `cmp` is called multiple times for each list element while `key` and `reverse` touch each element only once. Use `functools.cmp_to_key()` to convert an old-style `cmp` function to a `key` function.

내장 `sorted()` 함수는 안정적 (stable) 임이 보장됩니다. 정렬은 같다고 비교되는 요소의 상대적 순서를 변경하지 않으면 안정적입니다 — 이는 여러 번 정렬할 때 유용합니다 (예를 들어, 부서별로 정렬한 후에 급여 등급별로 정렬하기).

정렬 예제와 간단한 정렬 자습서는 `sortinghowto`를 보세요.

버전 2.4에 추가.

staticmethod (`function`)

Return a static method for `function`.

정적 메서드는 묵시적인 첫 번째 인자를 받지 않습니다. 정적 메서드를 선언하려면, 이 관용구를 사용하세요:

```
class C(object):
    @staticmethod
    def f(arg1, arg2, ...):
        ...
```

The `@staticmethod` form is a function *decorator* – see function for details.

A static method can be called either on the class (such as `C.f()`) or on an instance (such as `C().f()`).

파이썬의 정적 메서드는 자바 또는 C++ 에서 발견되는 정적 메서드와 비슷합니다. 대체 클래스 생성자를 만드는 데 유용한 변형을 보려면 `classmethod()` 도 보세요.

For more information on static methods, see *types*.

버전 2.2에 추가.

버전 2.4에서 변경: Function decorator syntax added.

class `str` (*object*="")

Return a string containing a nicely printable representation of an object. For strings, this returns the string itself. The difference with `repr(object)` is that `str(object)` does not always attempt to return a string that is acceptable to `eval()`; its goal is to return a printable string. If no argument is given, returns the empty string, ''.

For more information on strings see *Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange* which describes sequence functionality (strings are sequences), and also the string-specific methods described in the *문자열 메서드* section. To output formatted strings use template strings or the `%` operator described in the *String Formatting Operations* section. In addition see the *String Services* section. See also `unicode()`.

sum (*iterable*[, *start*])

start 및 *iterable* 의 항목들을 왼쪽에서 오른쪽으로 합하고 합계를 돌려줍니다. *start* 의 기본값은 0 입니다. *iterable* 의 항목은 일반적으로 숫자며 시작 값은 문자열이 될 수 없습니다.

어떤 경우에는 `sum()` 에 대한 좋은 대안이 있습니다. 문자열의 시퀀스를 연결하는 가장 선호되고 빠른 방법은 `''.join(sequence)` 를 호출하는 것입니다. 확장된 정밀도로 부동 소수점 값을 더하려면 `math.fsum()` 를 보세요. 일련의 이터러블들을 연결하려면 `itertools.chain()` 를 고려해보세요.

버전 2.3에 추가.

super (*type*[, *object-or-type*])

메서드 호출을 *type* 의 부모나 형제 클래스에 위임하는 프락시 객체를 돌려줍니다. 이는 클래스에서 재정의된 상속된 메서드를 액세스할 때 유용합니다. 검색 순서는 *type* 자체를 건너뛰는 것을 제외하면, `getattr()` 에 의해 사용된 순서와 같습니다.

type 의 `__mro__` 어트리뷰트는 메서드 결정 검색 순서를 나열하는데 `getattr()` 과 `super()` 에서 사용됩니다. 이 어트리뷰트는 동적이며 상속 계층 구조가 변경될 때마다 바뀔 수 있습니다.

두 번째 인자가 생략되면, 반환되는 슈퍼 객체는 연결되지 않았습다(*unbound*). 두 번째 인자가 객체면, `isinstance(obj, type)` 는 참이어야 합니다. 두 번째 인자가 형이면, `issubclass(type2, type)` 는 참이어야 합니다(이것은 클래스 메서드에 유용합니다).

참고: `super()` only works for *new-style classes*.

`super` 에는 두 가지 일반적인 사용 사례가 있습니다. 단일 상속 클래스 계층 구조에서는, `super` 를 사용하여 명시적으로 이름을 지정하지 않고 부모 클래스를 참조할 수 있으므로, 코드를 더 유지 관리하기 쉽게 만들 수 있습니다. 이 사용은 다른 프로그래밍 언어에서 `super` 를 쓰는 것과 매우 유사합니다.

두 번째 사용 사례는 동적 실행 환경에서 협력적 다중 상속을 지원하는 것입니다. 이 사례는 파이썬에 고유하며 정적으로 컴파일되는 언어 또는 단일 상속만 지원하는 언어에서는 찾을 수 없습니다. 이것은 여러 베이스 클래스가 같은 메서드를 구현하는 《다이아몬드 다이어그램》을 구현할 수 있게 합니다.

좋은 설계는 모든 경우에 이 메서드가 같은 호출 시그니처를 갖도록 하는 것입니다(호출 순서는 실행 시간에 결정되기 때문에, 그 순서가 클래스 계층 구조의 변경에 적응하기 때문에, 그리고 그 순서가 실행 시간 전에 미리 알려지지 않은 형제 클래스를 포함할 수 있으므로).

두 경우 모두, 일반적인 슈퍼 클래스 호출은 이런 식입니다:

```
class C(B):
    def method(self, arg):
        super(C, self).method(arg)
```

`super()` 는 `super().__getitem__(name)` 과 같은 명시적인 점으로 구분된 어트리뷰트 조회를 위한 연결 절차의 일부로 구현됨에 주의하세요. 이것은 협력적인 다중 상속을 지원하는 예측 가능한 순서로 클래스를 검색하기 위해 자체 `__getattr__()` 메서드를 구현함으로써 그렇게 합니다. 따라서, `super()` 는 `super()[name]` 과같이 문장이나 연산자를 사용하는 묵시적 조회에 대해서는 정의되지 않았습니다.

Also note that `super()` is not limited to use inside methods. The two argument form specifies the arguments exactly and makes the appropriate references.

`super()` 를 사용하여 협력적 클래스를 설계하는 방법에 대한 실용적인 제안은 [super\(\) 사용 안내](#) 를 보세요.

버전 2.2에 추가.

`tuple([iterable])`

Return a tuple whose items are the same and in the same order as *iterable*'s items. *iterable* may be a sequence, a container that supports iteration, or an iterator object. If *iterable* is already a tuple, it is returned unchanged. For instance, `tuple('abc')` returns `('a', 'b', 'c')` and `tuple([1, 2, 3])` returns `(1, 2, 3)`. If no argument is given, returns a new empty tuple, `()`.

`tuple` is an immutable sequence type, as documented in [Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange](#). For other containers see the built in `dict`, `list`, and `set` classes, and the `collections` module.

`class type(object)`

`class type(name, bases, dict)`

With one argument, return the type of an *object*. The return value is a type object. The `isinstance()` built-in function is recommended for testing the type of an object.

With three arguments, return a new type object. This is essentially a dynamic form of the `class` statement. The *name* string is the class name and becomes the `__name__` attribute; the *bases* tuple itemizes the base classes and becomes the `__bases__` attribute; and the *dict* dictionary is the namespace containing definitions for class body and becomes the `__dict__` attribute. For example, the following two statements create identical `type` objects:

```
>>> class X(object):
...     a = 1
...
>>> X = type('X', (object,), dict(a=1))
```

버전 2.2에 추가.

`unichr(i)`

Return the Unicode string of one character whose Unicode code is the integer *i*. For example, `unichr(97)` returns the string `u'a'`. This is the inverse of `ord()` for Unicode strings. The valid range for the argument depends how Python was configured – it may be either UCS2 `[0..0xFFFF]` or UCS4 `[0..0xFFFFFFFF]`. `ValueError` is raised otherwise. For ASCII and 8-bit strings see `chr()`.

버전 2.0에 추가.

`unicode(object=)`

unicode (*object* [, *encoding* [, *errors*]])

Return the Unicode string version of *object* using one of the following modes:

If *encoding* and/or *errors* are given, `unicode()` will decode the object which can either be an 8-bit string or a character buffer using the codec for *encoding*. The *encoding* parameter is a string giving the name of an encoding; if the encoding is not known, `LookupError` is raised. Error handling is done according to *errors*; this specifies the treatment of characters which are invalid in the input encoding. If *errors* is 'strict' (the default), a `ValueError` is raised on errors, while a value of 'ignore' causes errors to be silently ignored, and a value of 'replace' causes the official Unicode replacement character, U+FFFD, to be used to replace input characters which cannot be decoded. See also the `codecs` module.

If no optional parameters are given, `unicode()` will mimic the behaviour of `str()` except that it returns Unicode strings instead of 8-bit strings. More precisely, if *object* is a Unicode string or subclass it will return that Unicode string without any additional decoding applied.

For objects which provide a `__unicode__()` method, it will call this method without arguments to create a Unicode string. For all other objects, the 8-bit string version or representation is requested and then converted to a Unicode string using the codec for the default encoding in 'strict' mode.

For more information on Unicode strings see *Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange* which describes sequence functionality (Unicode strings are sequences), and also the string-specific methods described in the *문자열 메서드* section. To output formatted strings use template strings or the % operator described in the *String Formatting Operations* section. In addition see the *String Services* section. See also `str()`.

버전 2.0에 추가.

버전 2.2에서 변경: Support for `__unicode__()` added.

vars ([*object*])

모듈, 클래스, 인스턴스 또는 `__dict__` 어트리뷰트가 있는 다른 객체의 `__dict__` 어트리뷰트를 돌려줍니다.

Objects such as modules and instances have an updateable `__dict__` attribute; however, other objects may have write restrictions on their `__dict__` attributes (for example, new-style classes use a dictproxy to prevent direct dictionary updates).

인자가 없으면, `vars()` 는 `locals()` 처럼 동작합니다. `locals` 딕셔너리에 대한 변경이 무시되기 때문에 `locals` 딕셔너리는 읽기에만 유용하다는 것에 주의하세요.

xrange (*stop*)

xrange (*start*, *stop* [, *step*])

This function is very similar to `range()`, but returns an *xrange object* instead of a list. This is an opaque sequence type which yields the same values as the corresponding list, without actually storing them all simultaneously. The advantage of `xrange()` over `range()` is minimal (since `xrange()` still has to create the values when asked for them) except when a very large range is used on a memory-starved machine or when all of the range's elements are never used (such as when the loop is usually terminated with `break`). For more information on xrange objects, see *XRange Type* and *Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange*.

CPython implementation detail: `xrange()` is intended to be simple and fast. Implementations may impose restrictions to achieve this. The C implementation of Python restricts all arguments to native C longs (《short》 Python integers), and also requires that the number of elements fit in a native C long. If a larger range is needed, an alternate version can be crafted using the `itertools` module: `islice(count(start, step), (stop-start+step-1+2*(step<0))//step)`.

zip ([*iterable*, ...])

This function returns a list of tuples, where the *i*-th tuple contains the *i*-th element from each of the argument sequences or iterables. The returned list is truncated in length to the length of the shortest argument sequence. When there are multiple arguments which are all of the same length, `zip()` is similar to `map()` with an initial argument of `None`. With a single sequence argument, it returns a list of 1-tuples. With no arguments, it returns an empty list.

The left-to-right evaluation order of the iterables is guaranteed. This makes possible an idiom for clustering a data series into n-length groups using `zip(*[iter(s)]*n)`.

`zip()`을 * 연산자와 함께 쓰면 리스트를 unzip 할 수 있습니다:

```
>>> x = [1, 2, 3]
>>> y = [4, 5, 6]
>>> zipped = zip(x, y)
>>> zipped
[(1, 4), (2, 5), (3, 6)]
>>> x2, y2 = zip(*zipped)
>>> x == list(x2) and y == list(y2)
True
```

버전 2.0에 추가.

버전 2.4에서 변경: Formerly, `zip()` required at least one argument and `zip()` raised a `TypeError` instead of returning an empty list.

`__import__`(`name`[, `globals`[, `locals`[, `fromlist`[, `level`]]]])

참고: 이것은 `importlib.import_module()` 과 달리 일상적인 파이썬 프로그래밍에서는 필요하지 않은 고급 함수입니다.

This function is invoked by the `import` statement. It can be replaced (by importing the `__builtin__` module and assigning to `__builtin__.__import__`) in order to change semantics of the `import` statement, but nowadays it is usually simpler to use import hooks (see [PEP 302](#)). Direct use of `__import__()` is rare, except in cases where you want to import a module whose name is only known at runtime.

함수는 모듈 `name` 을 임포트 하는데, 잠재적으로 패키지 문맥에서 이름을 해석하는 방법을 결정하는데 주어진 `globals` 와 `locals` 를 사용합니다. `fromlist` 는 `name` 에 의해 주어진 모듈로부터 임포트 되어야 하는 객체 또는 서브 모듈의 이름을 제공합니다. 표준 구현은 `locals` 인자를 전혀 사용하지 않고, `import` 문의 패키지 문맥을 결정할 때만 `globals` 를 사용합니다.

`level` specifies whether to use absolute or relative imports. The default is `-1` which indicates both absolute and relative imports will be attempted. `0` means only perform absolute imports. Positive values for `level` indicate the number of parent directories to search relative to the directory of the module calling `__import__()`.

`name` 변수가 `package.module` 형식일 때, 일반적으로 `name` 에 의해 명명된 모듈이 아니라, 최상위 패키지(첫 번째 점까지의 이름)가 반환됩니다. 그러나 비어 있지 않은 `fromlist` 인자가 주어지면 `name` 에 의해 명명된 모듈이 반환됩니다.

예를 들어, 문장 `import spam` 은 다음 코드를 닮은 바이트 코드를 생성합니다:

```
spam = __import__('spam', globals(), locals(), [], -1)
```

문장 `import spam.ham` 은 이런 호출로 이어집니다:

```
spam = __import__('spam.ham', globals(), locals(), [], -1)
```

여기에서 `__import__()` 가 최상위 모듈을 돌려주는 것에 주목하세요. 이것이 `import` 문에 의해 이름에 연결되는 객체이기 때문입니다.

반면에, 문장 `from spam.ham import eggs, sausage as saus` 는 이런 결과를 줍니다:

```
_temp = __import__('spam.ham', globals(), locals(), ['eggs', 'sausage'], -1)
eggs = _temp.eggs
saus = _temp.sausage
```

여기서 `spam.ham` 모듈이 `__import__()` 에서 반환됩니다. 이 객체로부터, 임포트할 이름들을 가져온 후 해당 이름들로 대입됩니다.

단순히 이름으로 모듈을 임포트 하기 원한다면 (잠재적으로 패키지 내에서), `importlib.import_module()` 을 사용하세요.

버전 2.5에서 변경: The level parameter was added.

버전 2.5에서 변경: Keyword support for parameters was added.

Non-essential Built-in Functions

There are several built-in functions that are no longer essential to learn, know or use in modern Python programming. They have been kept here to maintain backwards compatibility with programs written for older versions of Python.

Python programmers, trainers, students and book writers should feel free to bypass these functions without concerns about missing something important.

apply (*function*, *args*[, *keywords*])

The *function* argument must be a callable object (a user-defined or built-in function or method, or a class object) and the *args* argument must be a sequence. The *function* is called with *args* as the argument list; the number of arguments is the length of the tuple. If the optional *keywords* argument is present, it must be a dictionary whose keys are strings. It specifies keyword arguments to be added to the end of the argument list. Calling `apply()` is different from just calling `function(args)`, since in that case there is always exactly one argument. The use of `apply()` is equivalent to `function(*args, **keywords)`.

버전 2.3부터 폐지: Use `function(*args, **keywords)` instead of `apply(function, args, keywords)` (see `tut-unpacking-arguments`).

buffer (*object*[, *offset*[, *size*]])

The *object* argument must be an object that supports the buffer call interface (such as strings, arrays, and buffers). A new buffer object will be created which references the *object* argument. The buffer object will be a slice from the beginning of *object* (or from the specified *offset*). The slice will extend to the end of *object* (or will have a length given by the *size* argument).

coerce (*x*, *y*)

Return a tuple consisting of the two numeric arguments converted to a common type, using the same rules as used by arithmetic operations. If coercion is not possible, raise `TypeError`.

intern (*string*)

Enter *string* in the table of «interned» strings and return the interned string – which is *string* itself or a copy. Interning strings is useful to gain a little performance on dictionary lookup – if the keys in a dictionary are interned, and the lookup key is interned, the key comparisons (after hashing) can be done by a pointer compare instead of a string compare. Normally, the names used in Python programs are automatically interned, and the dictionaries used to hold module, class or instance attributes have interned keys.

버전 2.3에서 변경: Interned strings are not immortal (like they used to be in Python 2.2 and before); you must keep a reference to the return value of `intern()` around to benefit from it.

작은 개수의 상수가 내장 이름 공간에 있습니다. 그것들은:

False

The false value of the *bool* type.

버전 2.3에 추가.

True

The true value of the *bool* type.

버전 2.3에 추가.

None

The sole value of *types.NoneType*. *None* is frequently used to represent the absence of a value, as when default arguments are not passed to a function.

버전 2.4에서 변경: Assignments to *None* are illegal and raise a *SyntaxError*.

NotImplemented

Special value which can be returned by the 《rich comparison》 special methods (*__eq__()*, *__lt__()*, and friends), to indicate that the comparison is not implemented with respect to the other type.

Ellipsis

Special value used in conjunction with extended slicing syntax.

__debug__

이 상수는 파이썬이 -O 옵션으로 시작되지 않았다면 참이 됩니다. *assert* 문도 불 필요가 있습니다.

참고: The names *None* and *__debug__* cannot be reassigned (assignments to them, even as an attribute name, raise *SyntaxError*), so they can be considered 《true》 constants.

버전 2.7에서 변경: Assignments to *__debug__* as an attribute became illegal.

4.1 `site` 모듈에 의해 추가된 상수들

`site` 모듈(`-S` 명령행 옵션이 주어진 경우를 제외하고는, 시작할 때 자동으로 임포트 됩니다)은 내장 이름 공간에 여러 상수를 추가합니다. 대화형 인터프리터 셸에 유용하고 프로그램에서 사용해서는 안 됩니다.

quit (`[code=None]`)

exit (`[code=None]`)

인쇄될 때, 《Use quit() or Ctrl-D (i.e. EOF) to exit》과 같은 메시지를 인쇄하고, 호출될 때, 지정된 종료 코드로 `SystemExit` 를 일으키는 객체.

copyright

credits

인쇄하거나 호출할 때, 각각 저작권 또는 크레딧 텍스트를 인쇄하는 객체입니다.

license

인쇄될 때 《Type license() to see the full license text》와 같은 메시지를 인쇄하고, 호출될 때 전체 라이선스 텍스트를 페이지 생성기와 같은 방식(한 번에 한 화면씩)으로 표시하는 객체입니다.

다음 섹션에서는 인터프리터에 내장된 표준형에 관해 설명합니다.

참고: Historically (until release 2.2), Python's built-in types have differed from user-defined types because it was not possible to use the built-in types as the basis for object-oriented inheritance. This limitation no longer exists.

The principal built-in types are numerics, sequences, mappings, files, classes, instances and exceptions.

Some operations are supported by several object types; in particular, practically all objects can be compared, tested for truth value, and converted to a string (with the `repr()` function or the slightly different `str()` function). The latter function is implicitly used when an object is written by the `print()` function.

5.1 논리값 검사

Any object can be tested for truth value, for use in an `if` or `while` condition or as operand of the Boolean operations below. The following values are considered false:

- `None`
- `False`
- zero of any numeric type, for example, `0`, `0L`, `0.0`, `0j`.
- any empty sequence, for example, `' '`, `()`, `[]`.
- any empty mapping, for example, `{}`.
- instances of user-defined classes, if the class defines a `__nonzero__()` or `__len__()` method, when that method returns the integer zero or `bool` value `False`.¹

¹ 이 특수 메서드에 대한 추가 정보는 파이썬 레퍼런스 설명서(customization)에서 찾을 수 있습니다.

All other values are considered true — so objects of many types are always true.

논리값을 돌려주는 연산과 내장 함수는 달리 명시하지 않는 한 항상 거짓의 경우 0 이나 False 를, 참이면 1 이나 True 를 돌려줍니다. (중요한 예외: 논리 연산 or 와 and 는 항상 피연산자 중 하나를 돌려줍니다.)

5.2 논리 연산 — and, or, not

이것들은 우선순위에 따라 오름차순으로 정렬된 논리 연산들입니다:

연산	결과	노트
<code>x or y</code>	<code>x</code> 가 거짓이면 <code>y</code> , 그렇지 않으면 <code>x</code>	(1)
<code>x and y</code>	<code>x</code> 가 거짓이면 <code>*x</code> , 그렇지 않으면 <code>y</code>	(2)
<code>not x</code>	<code>x</code> 가 거짓이면 True, 그렇지 않으면 False	(3)

노트:

- (1) 이것은 단락-회로 연산자이므로 첫 번째 인자가 거짓일 때만 두 번째의 값을 구합니다.
- (2) 이것은 단락-회로 연산자이므로 첫 번째 인자가 참일 때만 두 번째의 값을 구합니다.
- (3) `not` 은 비논리 연산자들보다 낮은 우선순위를 갖습니다. 그래서, `not a == b` 는 `not (a == b)` 로 해석되고, `a == not b` 는 문법 오류입니다.

5.3 비교

Comparison operations are supported by all objects. They all have the same priority (which is higher than that of the Boolean operations). Comparisons can be chained arbitrarily; for example, `x < y <= z` is equivalent to `x < y` and `y <= z`, except that `y` is evaluated only once (but in both cases `z` is not evaluated at all when `x < y` is found to be false).

이 표는 비교 연산을 요약합니다:

연산	뜻	노트
<code><</code>	엄격히 작다	
<code><=</code>	작거나 같다	
<code>></code>	엄격히 크다	
<code>>=</code>	크거나 같다	
<code>==</code>	같다	
<code>!=</code>	같지 않다	(1)
<code>is</code>	객체 아이덴티티	
<code>is not</code>	부정된 객체 아이덴티티	

노트:

- (1) `!=` can also be written `<>`, but this is an obsolete usage kept for backwards compatibility only. New code should always use `!=`.

Objects of different types, except different numeric types and different string types, never compare equal; such objects are ordered consistently but arbitrarily (so that sorting a heterogeneous array yields a consistent result). Furthermore, some types (for example, file objects) support only a degenerate notion of comparison where any two objects of that type are unequal. Again, such objects are ordered arbitrarily but consistently. The `<`, `<=`, `>` and `>=` operators will raise a `TypeError` exception when any operand is a complex number.

Non-identical instances of a class normally compare as non-equal unless the class defines the `__eq__()` method or the `__cmp__()` method.

Instances of a class cannot be ordered with respect to other instances of the same class, or other types of object, unless the class defines either enough of the rich comparison methods (`__lt__()`, `__le__()`, `__gt__()`, and `__ge__()`) or the `__cmp__()` method.

CPython implementation detail: Objects of different types except numbers are ordered by their type names; objects of the same types that don't support proper comparison are ordered by their address.

Two more operations with the same syntactic priority, `in` and `not in`, are supported only by sequence types (below).

5.4 Numeric Types — `int`, `float`, `long`, `complex`

There are four distinct numeric types: *plain integers*, *long integers*, *floating point numbers*, and *complex numbers*. In addition, Booleans are a subtype of plain integers. Plain integers (also just called *integers*) are implemented using `long` in C, which gives them at least 32 bits of precision (`sys.maxint` is always set to the maximum plain integer value for the current platform, the minimum value is `-sys.maxint - 1`). Long integers have unlimited precision. Floating point numbers are usually implemented using `double` in C; information about the precision and internal representation of floating point numbers for the machine on which your program is running is available in `sys.float_info`. Complex numbers have a real and imaginary part, which are each a floating point number. To extract these parts from a complex number `z`, use `z.real` and `z.imag`. (The standard library includes additional numeric types, *fractions* that hold rationals, and *decimal* that hold floating-point numbers with user-definable precision.)

Numbers are created by numeric literals or as the result of built-in functions and operators. Unadorned integer literals (including binary, hex, and octal numbers) yield plain integers unless the value they denote is too large to be represented as a plain integer, in which case they yield a long integer. Integer literals with an `'L'` or `'l'` suffix yield long integers (`'L'` is preferred because `11` looks too much like eleven!). Numeric literals containing a decimal point or an exponent sign yield floating point numbers. Appending `'j'` or `'J'` to a numeric literal yields an imaginary number (a complex number with a zero real part) which you can add to an integer or float to get a complex number with real and imaginary parts.

Python fully supports mixed arithmetic: when a binary arithmetic operator has operands of different numeric types, the operand with the «narrower» type is widened to that of the other, where plain integer is narrower than long integer is narrower than floating point is narrower than complex. Comparisons between numbers of mixed type use the same rule.² The constructors `int()`, `long()`, `float()`, and `complex()` can be used to produce numbers of a specific type.

All built-in numeric types support the following operations. See power and later sections for the operators' priorities.

² 결과적으로, 리스트 `[1, 2]` 는 `[1.0, 2.0]` 과 같다고 취급되고, 튜플도 마찬가지입니다.

연산	결과	노트
$x + y$	x 와 y 의 합	
$x - y$	x 와 y 의 차	
$x * y$	x 와 y 의 곱	
x / y	x 와 y 의 몫	(1)
$x // y$	(floored) quotient of x and y	(4)(5)
$x \% y$	x / y 의 나머지	(4)
$-x$	음의 x	
$+x$	x 그대로	
<code>abs(x)</code>	x 의 절댓값 또는 크기	(3)
<code>int(x)</code>	정수로 변환된 x	(2)
<code>long(x)</code>	x converted to long integer	(2)
<code>float(x)</code>	실수로 변환된 x	(6)
<code>complex(re, im)</code>	실수부 re 와 허수부 im 으로 구성된 복소수. im 의 기본값은 0입니다.	
<code>c.conjugate()</code>	conjugate of the complex number c . (Identity on real numbers)	
<code>divmod(x, y)</code>	쌍 ($x // y$, $x \% y$)	(3)(4)
<code>pow(x, y)</code>	x 의 y 거듭제곱	(3)(7)
$x ** y$	x 의 y 거듭제곱	(7)

노트:

- (1) For (plain or long) integer division, the result is an integer. The result is always rounded towards minus infinity: $1/2$ is 0, $(-1)/2$ is -1, $1/(-2)$ is -1, and $(-1)/(-2)$ is 0. Note that the result is a long integer if either operand is a long integer, regardless of the numeric value.
- (2) Conversion from floats using `int()` or `long()` truncates toward zero like the related function, `math.trunc()`. Use the function `math.floor()` to round downward and `math.ceil()` to round upward.
- (3) See [내장 함수](#) for a full description.
- (4) 버전 2.3부터 폐지: The floor division operator, the modulo operator, and the `divmod()` function are no longer defined for complex numbers. Instead, convert to a floating point number using the `abs()` function if appropriate.
- (5) Also referred to as integer division. The resultant value is a whole integer, though the result's type is not necessarily `int`.
- (6) float는 또한 숫자가 아님(NaN)과 양 또는 음의 무한대를 나타내는 문자열 `«nan»` 과 접두사 `«+»` 나 `«-»` 가 선택적으로 붙을 수 있는 `«inf»` 를 받아들입니다.
버전 2.6에 추가.
- (7) 파이썬은 프로그래밍 언어들에서 흔히 그렇듯이, 있는 것처럼 `pow(0, 0)` 와 `0 ** 0` 이 1 이 되도록 정의합니다.

All `numbers.Real` types (`int`, `long`, and `float`) also include the following operations:

연산	결과
<code>math.trunc(x)</code>	x 는 <i>Integral</i> 로 잘립니다
<code>round(x[, n])</code>	x rounded to n digits, rounding ties away from zero. If n is omitted, it defaults to 0.
<code>math.floor(x)</code>	the greatest integer as a float $\leq x$
<code>math.ceil(x)</code>	the least integer as a float $\geq x$

5.4.1 정수 형에 대한 비트 연산

Bitwise operations only make sense for integers. Negative numbers are treated as their 2's complement value (this assumes a sufficiently large number of bits that no overflow occurs during the operation).

이진 비트 연산의 우선순위는 모두 숫자 연산보다 낮고 비교보다 높습니다; 일항 연산 `~` 은 다른 일항 연산들 (`+` 와 `-`) 과 같은 우선순위를 가집니다.

이 표는 비트 연산을 나열하는데, 우선순위에 따라 오름차순으로 정렬되어 있습니다:

연산	결과	노트
<code>x y</code>	<code>x</code> 와 <code>y</code> 의 비트별 <i>or</i>	
<code>x ^ y</code>	<code>x</code> 와 <code>y</code> 의 비트별 배타적 <i>or</i> (<i>exclusive or</i>)	
<code>x & y</code>	<code>x</code> 와 <code>y</code> 의 비트별 <i>and</i>	
<code>x << n</code>	<code>x</code> 를 <code>n</code> 비트만큼 왼쪽으로 시프트	(1)(2)
<code>x >> n</code>	<code>x</code> 를 <code>n</code> 비트만큼 오른쪽으로 시프트	(1)(3)
<code>~x</code>	<code>x</code> 의 비트 반전	

노트:

- (1) 음의 시프트 수는 허락되지 않고 `ValueError` 를 일으킵니다.
- (2) A left shift by `n` bits is equivalent to multiplication by `pow(2, n)`. A long integer is returned if the result exceeds the range of plain integers.
- (3) A right shift by `n` bits is equivalent to division by `pow(2, n)`.

5.4.2 정수 형에 대한 추가 메서드

The integer types implement the `numbers.Integral abstract base class`. In addition, they provide one more method:

`int.bit_length()`

`long.bit_length()`

부호와 선행 0을 제외하고, 이진수로 정수를 나타내는 데 필요한 비트 수를 돌려줍니다:

```
>>> n = -37
>>> bin(n)
'-0b100101'
>>> n.bit_length()
6
```

좀 더 정확하게 말하자면, `x` 가 0이 아니면, `x.bit_length()` 는 $2^{(k-1)} \leq \text{abs}(x) < 2^k$ 를 만족하는 유일한 양의 정수 `k` 입니다. 동등하게, `abs(x)` 가 정확하게 반올림된 로그값을 가질 만큼 아주 작으면, `k = 1 + int(log(abs(x), 2))` 가 됩니다. `x` 가 0이면, `x.bit_length()` 는 0 을 돌려줍니다.

다음 코드와 동등합니다:

```
def bit_length(self):
    s = bin(self)          # binary representation: bin(-37) --> '-0b100101'
    s = s.lstrip('-0b')    # remove leading zeros and minus sign
    return len(s)          # len('100101') --> 6
```

버전 2.7에 추가.

5.4.3 실수에 대한 추가 메서드

`float` 형은 `numbers.Real` 추상 베이스 클래스를 구현합니다. 또한, `float`는 다음과 같은 추가 메서드를 갖습니다.

`float.as_integer_ratio()`

비율이 원래 `float`와 정확히 같고 양의 분모를 갖는 정수 쌍을 돌려줍니다. 무한대에는 `OverflowError`를, NaN에는 `ValueError`를 일으킵니다.

버전 2.6에 추가.

`float.is_integer()`

`float` 인스턴스가 정숫값을 가진 유한이면 `True`를, 그렇지 않으면 `False`를 돌려줍니다:

```
>>> (-2.0).is_integer()
True
>>> (3.2).is_integer()
False
```

버전 2.6에 추가.

두 가지 메서드가 16진수 문자열과의 변환을 지원합니다. 파이썬의 `float`는 내부적으로 이진수로 저장되기 때문에 `float`를 십진수 문자열로 또는 그 반대로 변환하는 것은 보통 반올림 오류를 수반합니다. 이에 반해, 16진수 문자열은 부동 소수점 숫자의 정확한 표현과 지정을 가능하게 합니다. 이것은 디버깅 및 수치 작업에 유용할 수 있습니다.

`float.hex()`

부동 소수점의 16진수 문자열 표현을 돌려줍니다. 유한 부동 소수점의 경우, 이 표현은 항상 선행하는 `0x`와 후행하는 `p`와 지수를 포함합니다.

버전 2.6에 추가.

`float.fromhex(s)`

16진수 문자열 `s`로 표현되는 `float`를 돌려주는 클래스 메서드. 문자열 `s`는 앞뒤 공백을 가질 수 있습니다.

버전 2.6에 추가.

`float.hex()`는 인스턴스 메서드인 반면, `float.fromhex()`는 클래스 메서드임에 주의하세요.

16진수 문자열은 다음과 같은 형식을 취합니다:

```
[sign] ['0x'] integer ['.' fraction] ['p' exponent]
```

선택적인 `sign`은 `+`나 `-`가 될 수 있고, `integer`와 `fraction`은 16진수 문자열이고, `exponent`는 선택적인 선행 부호가 붙을 수 있는 십진수입니다. 대소문자는 중요하지 않으며 `integer`나 `fraction` 중 어느 하나에 적어도 하나의 16진수가 있어야 합니다. 이 문법은 C99 표준의 6.4.4.2 절에 지정된 문법과 비슷하며, 자바 1.5 이상에서 사용되는 문법과도 비슷합니다. 특히, `float.hex()`의 출력은 C 또는 자바 코드에서 16진수의 부동 소수점 리터럴로 사용할 수 있으며, C의 `%a` 포맷 문자나 자바의 `Double.toHexString`가 만들어내는 16진수 문자열은 `float.fromhex()`가 받아들입니다.

지수는 16진수가 아닌 십진수로 쓰이고, 숫자에 곱해지는 2의 거듭제곱을 제공한다는 점에 유의하십시오. 예를 들어, 16진수 문자열 `0x3.a7p10`는 부동 소수점 숫자 $(3 + 10./16 + 7./16**2) * 2.0**10$ 또는 `3740.0`를 나타냅니다:

```
>>> float.fromhex('0x3.a7p10')
3740.0
```

`3740.0`에 역변환을 적용하면 같은 숫자를 나타내는 다른 16진수 문자열을 얻을 수 있습니다:

```
>>> float.hex(3740.0)
'0x1.d380000000000p+11'
```

5.5 이터레이터 형

버전 2.2에 추가.

파이썬은 컨테이너에 대한 이터레이션 개념을 지원합니다. 이것은 두 개의 메서드를 사용해서 구현됩니다; 이것들은 사용자 정의 클래스가 이터레이션을 지원할 수 있도록 하는 데 사용됩니다. 아래에서 더 자세히 설명할 시퀀스는 항상 이터레이션 메서드를 지원합니다.

컨테이너 객체가 이터레이션 지원을 제공하려면 한가지 메서드를 정의할 필요가 있습니다.:

`container.__iter__()`

이터레이터 객체를 돌려줍니다. 이 객체는 아래에서 설명하는 이터레이터 프로토콜을 지원해야 합니다. 컨테이너가 여러 유형의 이터레이션을 지원하는 경우, 이터레이션 유형에 대한 이터레이터를 구체적으로 요구하는 추가 메서드를 제공할 수 있습니다. (여러 형태의 이터레이션을 지원하는 객체의 예로 너비 우선과 깊이 우선 탐색을 모두 지원하는 트리 구조를 들 수 있습니다.) 이 메서드는 파이썬/C API에서 파이썬 객체를 위한 구조체의 `tp_iter` 슬롯에 대응합니다.

이터레이터 객체 자체는 다음과 같은 두 가지 메서드를 지원해야 하는데, 둘이 함께 이터레이터 프로토콜 (*iterator protocol*) 를 이룹니다.:

`iterator.__iter__()`

이터레이터 객체 자신을 돌려줍니다. 이는 `for` 와 `in` 문에 컨테이너와 이터레이터 모두 사용될 수 있게 하는 데 필요합니다. 이 메서드는 파이썬/C API에서 파이썬 객체를 위한 구조체의 `tp_iter` 슬롯에 대응합니다.

`iterator.next()`

컨테이너의 다음 항목을 돌려줍니다. 더 항목이 없으면 `StopIteration` 예외를 일으킵니다. 이 메서드는 파이썬/C API에서 파이썬 객체를 위한 구조체의 `tp_iternext` 슬롯에 대응합니다.

파이썬은 일반적이거나 특정한 시퀀스 형, 딕셔너리, 기타 더 특화된 형태에 대한 이터레이션을 지원하기 위해 여러 이터레이터 객체를 정의합니다. 이터레이터 프로토콜의 구현을 넘어서 개별적인 형이 중요하지는 않습니다.

The intention of the protocol is that once an iterator's `next()` method raises `StopIteration`, it will continue to do so on subsequent calls. Implementations that do not obey this property are deemed broken. (This constraint was added in Python 2.3; in Python 2.2, various iterators are broken according to this rule.)

5.5.1 제너레이터 형

Python's *generators* provide a convenient way to implement the iterator protocol. If a container object's `__iter__()` method is implemented as a generator, it will automatically return an iterator object (technically, a generator object) supplying the `__iter__()` and `next()` methods. More information about generators can be found in the documentation for the `yield` expression.

5.6 Sequence Types — `str`, `unicode`, `list`, `tuple`, `bytearray`, `buffer`, `xrange`

There are seven sequence types: strings, Unicode strings, lists, tuples, bytearrays, buffers, and xrange objects.

For other containers see the built in `dict` and `set` classes, and the `collections` module.

String literals are written in single or double quotes: `'xyzzzy'`, `"frobozz"`. See strings for more about string literals. Unicode strings are much like strings, but are specified in the syntax using a preceding `'u'` character: `u'abc'`, `u"def"`. In addition to the functionality described here, there are also string-specific methods described in the `문자열 메서드` section. Lists are constructed with square brackets, separating items with commas: `[a, b, c]`. Tuples are constructed

by the comma operator (not within square brackets), with or without enclosing parentheses, but an empty tuple must have the enclosing parentheses, such as `a, b, c` or `()`. A single item tuple must have a trailing comma, such as `(d,)`.

Bytearray objects are created with the built-in function `bytearray()`.

Buffer objects are not directly supported by Python syntax, but can be created by calling the built-in function `buffer()`. They don't support concatenation or repetition.

Objects of type `xrange` are similar to buffers in that there is no specific syntax to create them, but they are created using the `xrange()` function. They don't support slicing, concatenation or repetition, and using `in`, `not in`, `min()` or `max()` on them is inefficient.

Most sequence types support the following operations. The `in` and `not in` operations have the same priorities as the comparison operations. The `+` and `*` operations have the same priority as the corresponding numeric operations.³ Additional methods are provided for 가변 시퀀스 형.

This table lists the sequence operations sorted in ascending priority. In the table, *s* and *t* are sequences of the same type; *n*, *i* and *j* are integers:

연산	결과	노트
<code>x in s</code>	<i>s</i> 의 항목 중 하나가 <i>x</i> 와 같으면 <code>True</code> , 그렇지 않으면 <code>False</code>	(1)
<code>x not in s</code>	<i>s</i> 의 항목 중 하나가 <i>x</i> 와 같으면 <code>False</code> , 그렇지 않으면 <code>True</code>	(1)
<code>s + t</code>	<i>s</i> 와 <i>t</i> 의 이어 붙이기	(6)
<code>s * n, n * s</code>	<i>s</i> 를 그 자신에 <i>n</i> 번 더하는 것과 같습니다	(2)
<code>s[i]</code>	<i>s</i> 의 <i>i</i> 번째 항목, 0에서 시작합니다	(3)
<code>s[i:j]</code>	<i>s</i> 의 <i>i</i> 에서 <i>j</i> 까지의 슬라이스	(3)(4)
<code>s[i:j:k]</code>	<i>s</i> 의 <i>i</i> 에서 <i>j</i> 까지 스텝 <i>k</i> 의 슬라이스	(3)(5)
<code>len(s)</code>	<i>s</i> 의 길이	
<code>min(s)</code>	<i>s</i> 의 가장 작은 항목	
<code>max(s)</code>	<i>s</i> 의 가장 큰 항목	
<code>s.index(x)</code>	index of the first occurrence of <i>x</i> in <i>s</i>	
<code>s.count(x)</code>	<i>s</i> 등장하는 <i>x</i> 의 총수	

Sequence types also support comparisons. In particular, tuples and lists are compared lexicographically by comparing corresponding elements. This means that to compare equal, every element must compare equal and the two sequences must be of the same type and have the same length. (For full details see comparisons in the language reference.)

노트:

- (1) When *s* is a string or Unicode string object the `in` and `not in` operations act like a substring test. In Python versions before 2.3, *x* had to be a string of length 1. In Python 2.3 and beyond, *x* may be a string of any length.
- (2) Values of *n* less than 0 are treated as 0 (which yields an empty sequence of the same type as *s*). Note that items in the sequence *s* are not copied; they are referenced multiple times. This often haunts new Python programmers; consider:

```
>>> lists = [[]] * 3
>>> lists
[[], [], []]
>>> lists[0].append(3)
>>> lists
[[3], [3], [3]]
```

What has happened is that `[[]]` is a one-element list containing an empty list, so all three elements of `[[]] * 3` are references to this single empty list. Modifying any of the elements of `lists` modifies this single list. You can create a list of different lists this way:

³ 파서가 피연산자 유형을 알 수 없으므로 그럴 수밖에 없습니다.


```
>>> lists = [[] for i in range(3)]
>>> lists[0].append(3)
>>> lists[1].append(5)
>>> lists[2].append(7)
>>> lists
[[3], [5], [7]]
```

더 자세한 설명은 FAQ 항목 [faq-multidimensional-list](#)에서 얻을 수 있습니다.

- (3) i 또는 j 가 음수인 경우, 인덱스는 시퀀스 s 의 끝에 상대적입니다: $\text{len}(s) + i$ 이나 $\text{len}(s) + j$ 로 치환됩니다. 하지만 -0 은 여전히 0 입니다.
- (4) i 에서 j 까지의 s 의 슬라이스는 $i \leq k < j$ 를 만족하는 인덱스 k 의 항목들로 구성된 시퀀스로 정의됩니다. i 또는 j 가 $\text{len}(s)$ 보다 크면 $\text{len}(s)$ 을 사용합니다. i 가 생략되거나 None 이라면 0 을 사용합니다. j 가 생략되거나 None 이면 $\text{len}(s)$ 을 사용합니다. i 가 j 보다 크거나 같으면 빈 슬라이스가 됩니다.
- (5) 스텝 k 가 있는 i 에서 j 까지의 슬라이스는 $0 \leq n < (j-i)/k$ 를 만족하는 인덱스 $x = i + n*k$ 의 항목들로 구성된 시퀀스로 정의됩니다. 다시 말하면, 인덱스는 $i, i+k, i+2*k, i+3*k$ 등이며 j 에 도달할 때 멈춥니다(하지만 절대 j 를 포함하지는 않습니다). k 가 양수면 i 와 j 는 더 큰 경우 $\text{len}(s)$ 로 줄어듭니다. k 가 음수면, i 와 j 는 더 큰 경우 $\text{len}(s) - 1$ 로 줄어듭니다. i 또는 j 가 생략되거나 None 이면, 그것들은 《끝》 값이 됩니다(끝은 k 의 부호에 따라 달라집니다). k 는 0 일 수 없음에 주의하세요. k 가 None 이면 1 로 취급됩니다.
- (6) **CPython implementation detail:** If s and t are both strings, some Python implementations such as CPython can usually perform an in-place optimization for assignments of the form $s = s + t$ or $s += t$. When applicable, this optimization makes quadratic run-time much less likely. This optimization is both version and implementation dependent. For performance sensitive code, it is preferable to use the `str.join()` method which assures consistent linear concatenation performance across versions and implementations.

버전 2.4에서 변경: Formerly, string concatenation never occurred in-place.

5.6.1 문자열 메서드

Below are listed the string methods which both 8-bit strings and Unicode objects support. Some of them are also available on `bytearray` objects.

In addition, Python's strings support the sequence type methods described in the [Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange](#) section. To output formatted strings use template strings or the `%` operator described in the [String Formatting Operations](#) section. Also, see the [re](#) module for string functions based on regular expressions.

`str.capitalize()`

첫 문자가 대문자이고 나머지가 소문자인 문자열의 복사본을 돌려줍니다.

For 8-bit strings, this method is locale-dependent.

`str.center(width[, fillchar])`

Return centered in a string of length *width*. Padding is done using the specified *fillchar* (default is a space).

버전 2.4에서 변경: Support for the *fillchar* argument.

`str.count(sub[, start[, end]])`

범위 $[start, end]$ 에서 서브 스트링 *sub* 가 중첩되지 않고 등장하는 횟수를 돌려줍니다. 선택적 인자 *start* 와 *end* 는 슬라이스 표기법으로 해석됩니다.

`str.decode([encoding[, errors]])`

Decodes the string using the codec registered for *encoding*. *encoding* defaults to the default string encoding. *errors* may be given to set a different error handling scheme. The default is 'strict', meaning that encoding errors

raise *UnicodeError*. Other possible values are 'ignore', 'replace' and any other name registered via *codecs.register_error()*, see section *Codec Base Classes*.

버전 2.2에 추가.

버전 2.3에서 변경: Support for other error handling schemes added.

버전 2.7에서 변경: 키워드 인자 지원이 추가되었습니다.

str.encode(*[encoding[, errors]]*)

Return an encoded version of the string. Default encoding is the current default string encoding. *errors* may be given to set a different error handling scheme. The default for *errors* is 'strict', meaning that encoding errors raise a *UnicodeError*. Other possible values are 'ignore', 'replace', 'xmlcharrefreplace', 'backslashreplace' and any other name registered via *codecs.register_error()*, see section *Codec Base Classes*. For a list of possible encodings, see section *Standard Encodings*.

버전 2.0에 추가.

버전 2.3에서 변경: Support for 'xmlcharrefreplace' and 'backslashreplace' and other error handling schemes added.

버전 2.7에서 변경: 키워드 인자 지원이 추가되었습니다.

str.endswith(*suffix[, start[, end]]*)

문자열이 지정된 *suffix* 로 끝나면 True 를 돌려주고, 그렇지 않으면 False 를 돌려줍니다. *suffix* 는 찾고자 하는 접미사들의 튜플이 될 수도 있습니다. 선택적 *start* 가 제공되면 그 위치에서 검사를 시작합니다. 선택적 *end* 를 사용하면 해당 위치에서 비교를 중단합니다.

버전 2.5에서 변경: Accept tuples as *suffix*.

str.expandtabs(*[tabsize]*)

모든 탭 문자들을 현재의 열과 주어진 탭 크기에 따라 하나나 그 이상의 스페이스로 치환한 문자열의 복사본을 돌려줍니다. 탭 위치는 *tabsize* 문자마다 발생합니다 (기본값은 8이고, 열 0, 8, 16 등에 탭 위치를 지정합니다). 문자열을 확장하기 위해 현재 열이 0으로 설정되고 문자열을 문자 단위로 검사합니다. 문자가 탭 (\t) 이면, 현재 열이 다음 탭 위치와 같아질 때까지 하나 이상의 스페이스 문자가 삽입됩니다. (탭 문자 자체는 복사되지 않습니다.) 문자가 개행 문자 (\n) 또는 캐리지 리턴 (\r) 이면 복사되고 현재 열은 0으로 재설정됩니다. 다른 문자는 변경되지 않고 복사되고 현재 열은 인쇄할 때 문자가 어떻게 표시되는지에 관계없이 1씩 증가합니다.

```
>>> '01\t012\t0123\t01234'.expandtabs()
'01      012      0123      01234'
>>> '01\t012\t0123\t01234'.expandtabs(4)
'01  012 0123  01234'
```

str.find(*sub[, start[, end]]*)

서브 스트링 *sub* 가 슬라이스 *s[start:end]* 내에 등장하는 가장 작은 문자열의 인덱스를 돌려줍니다. 선택적 인자 *start* 와 *end* 는 슬라이스 표기법으로 해석됩니다. *sub* 가 없으면 -1 을 돌려줍니다.

참고: *find()* 메서드는 *sub* 의 위치를 알아야 할 경우에만 사용해야 합니다. *sub* 가 서브 스트링인지 확인하려면 *in* 연산자를 사용하십시오:

```
>>> 'Py' in 'Python'
True
```

str.format(**args, **kwargs*)

문자열 포맷 연산을 수행합니다. 이 메서드가 호출되는 문자열은 리터럴 텍스트나 중괄호 {} 로 구분된 치환 필드를 포함할 수 있습니다. 각 치환 필드는 위치 인자의 숫자 인덱스나 키워드 인자의 이름을 가질 수 있습니다. 각 치환 필드를 해당 인자의 문자열 값으로 치환한 문자열의 사본을 돌려줍니다.

```
>>> "The sum of 1 + 2 is {0}".format(1+2)
'The sum of 1 + 2 is 3'
```

포맷 문자열에 지정할 수 있는 다양한 포맷 옵션에 대한 설명은 [Format String Syntax](#) 을 참조하십시오.

This method of string formatting is the new standard in Python 3, and should be preferred to the % formatting described in [String Formatting Operations](#) in new code.

버전 2.6에 추가.

str.index(sub[, start[, end]])

Like [find\(\)](#), but raise [ValueError](#) when the substring is not found.

str.isalnum()

Return true if all characters in the string are alphanumeric and there is at least one character, false otherwise.

For 8-bit strings, this method is locale-dependent.

str.isalpha()

Return true if all characters in the string are alphabetic and there is at least one character, false otherwise.

For 8-bit strings, this method is locale-dependent.

str.isdigit()

Return true if all characters in the string are digits and there is at least one character, false otherwise.

For 8-bit strings, this method is locale-dependent.

str.islower()

문자열 내의 모든 케이스 문자가⁴ 소문자이고, 적어도 하나의 케이스 문자가 존재하는 경우 참을 돌려주고, 그렇지 않으면 거짓을 돌려줍니다.

For 8-bit strings, this method is locale-dependent.

str.isspace()

Return true if there are only whitespace characters in the string and there is at least one character, false otherwise.

For 8-bit strings, this method is locale-dependent.

str.istitle()

문자열이 제목 케이스 문자열이고 하나 이상의 문자가 있는 경우 참을 돌려줍니다. 예를 들어 대문자 앞에는 케이스 없는 문자만 올 수 있고 소문자는 케이스 문자 뒤에만 올 수 있습니다. 그렇지 않은 경우는 거짓을 돌려줍니다.

For 8-bit strings, this method is locale-dependent.

str.isupper()

문자열 내의 모든 케이스 문자가⁴ 대문자이고, 적어도 하나의 케이스 문자가 존재하는 경우 참을 돌려주고, 그렇지 않으면 거짓을 돌려줍니다.

For 8-bit strings, this method is locale-dependent.

str.join(iterable)

Return a string which is the concatenation of the strings in *iterable*. If there is any Unicode object in *iterable*, return a Unicode instead. A [TypeError](#) will be raised if there are any non-string or non Unicode object values in *iterable*. The separator between elements is the string providing this method.

str.ljust(width[, fillchar])

Return the string left justified in a string of length *width*. Padding is done using the specified *fillchar* (default is a space). The original string is returned if *width* is less than or equal to `len(s)`.

버전 2.4에서 변경: Support for the *fillchar* argument.

⁴ 케이스 문자는 일반 범주 속성이 <Lu> (Letter, 대문자), <Ll> (Letter, 소문자), <Lt> (Letter, 제목 문자) 중 한 가지인 경우입니다.

`str.lower()`

모든 케이스 문자⁴가 소문자로 변환된 문자열의 복사본을 돌려줍니다.

For 8-bit strings, this method is locale-dependent.

`str.lstrip([chars])`

Return a copy of the string with leading characters removed. The *chars* argument is a string specifying the set of characters to be removed. If omitted or `None`, the *chars* argument defaults to removing whitespace. The *chars* argument is not a prefix; rather, all combinations of its values are stripped:

```
>>> '   spacious   '.lstrip()
'spacious   '
>>> 'www.example.com'.lstrip('cmowz.')
'example.com'
```

버전 2.2.2에서 변경: Support for the *chars* argument.

`str.partition(sep)`

*sep*가 처음 나타나는 위치에서 문자열을 나누고, 구분자 앞에 있는 부분, 구분자 자체, 구분자 뒤에 오는 부분으로 구성된 3-튜플을 돌려줍니다. 구분자가 발견되지 않으면, 문자열 자신과 그 뒤를 따르는 두 개의 빈 문자열로 구성된 3-튜플을 돌려줍니다.

버전 2.5에 추가.

`str.replace(old, new[, count])`

모든 서브 스트링 *old*가 *new*로 치환된 문자열의 복사본을 돌려줍니다. 선택적 인자 *count*가 주어지면, 앞의 *count*개만 치환됩니다.

`str.rfind(sub[, start[, end]])`

서브 스트링 *sub*가 *s[start:end]* 내에 등장하는 가장 큰 문자열의 인덱스를 돌려줍니다. 선택적 인자 *start*와 *end*는 슬라이스 표기법으로 해석됩니다. 실패하면 -1을 돌려줍니다.

`str.rindex(sub[, start[, end]])`

*rfind()*와 비슷하지만, 서브 스트링 *sub*를 찾을 수 없는 경우 *ValueError*를 일으킵니다.

`str.rjust(width[, fillchar])`

Return the string right justified in a string of length *width*. Padding is done using the specified *fillchar* (default is a space). The original string is returned if *width* is less than or equal to `len(s)`.

버전 2.4에서 변경: Support for the *fillchar* argument.

`str.rpartition(sep)`

*sep*가 마지막으로 나타나는 위치에서 문자열을 나누고, 구분자 앞에 있는 부분, 구분자 자체, 구분자 뒤에 오는 부분으로 구성된 3-튜플을 돌려줍니다. 구분자가 발견되지 않으면, 두 개의 빈 문자열과 그 뒤를 따르는 문자열 자신으로 구성된 3-튜플을 돌려줍니다.

버전 2.5에 추가.

`str.rsplit([sep[, maxsplit]])`

*sep*를 구분자 문자열로 사용하여 문자열에 있는 단어들의 리스트를 돌려줍니다. *maxsplit*이 주어지면 가장 오른쪽에서 최대 *maxsplit*번의 분할이 수행됩니다. *sep*이 지정되지 않거나 `None`이면, 구분자로 모든 공백 문자가 사용됩니다. 오른쪽에서 분리하는 것을 제외하면, *rsplit()*는 아래에서 자세히 설명될 *split()*처럼 동작합니다.

버전 2.4에 추가.

`str.rstrip([chars])`

Return a copy of the string with trailing characters removed. The *chars* argument is a string specifying the set of characters to be removed. If omitted or `None`, the *chars* argument defaults to removing whitespace. The *chars* argument is not a suffix; rather, all combinations of its values are stripped:

```
>>> '   spacious   '.rstrip()
'   spacious'
>>> 'mississippi'.rstrip('ipz')
'mississ'
```

버전 2.2.2에서 변경: Support for the *chars* argument.

str.split([sep[, maxsplit]])

sep 를 구분자 문자열로 사용하여 문자열에 있는 단어들의 리스트를 돌려줍니다. *maxsplit* 이 주어지면 최대 *maxsplit* 번의 분할이 수행됩니다(따라서, 리스트는 최대 *maxsplit*+1 개의 요소를 가지게 됩니다). *maxsplit* 이 지정되지 않았거나 -1 이라면 분할 수에 제한이 없습니다(가능한 모든 분할이 만들어집니다).

sep 이 주어지면, 연속된 구분자는 묶이지 않고 빈 문자열을 구분하는 것으로 간주합니다(예를 들어, '1,2'.split(',') 는 ['1', '', '2'] 를 돌려줍니다). *sep* 인자는 여러 문자로 구성될 수 있습니다(예를 들어, '1<>2<>3'.split('<>') 는 ['1', '2', '3'] 를 돌려줍니다). 지정된 구분자로 빈 문자열을 나누면 [''] 를 돌려줍니다.

sep 이 지정되지 않거나 None 이면, 다른 분할 알고리즘이 적용됩니다: 연속된 공백 문자는 단일한 구분자로 간주하고, 문자열이 선행이나 후행 공백을 포함해도 결과는 시작과 끝에 빈 문자열을 포함하지 않습니다. 결과적으로, 빈 문자열이나 공백만으로 구성된 문자열을 None 구분자로 나누면 [] 를 돌려줍니다.

For example, ' 1 2 3 '.split() returns ['1', '2', '3'], and ' 1 2 3 '.split(None, 1) returns ['1', '2 3 '].

str.splitlines([keepends])

Return a list of the lines in the string, breaking at line boundaries. This method uses the *universal newlines* approach to splitting lines. Line breaks are not included in the resulting list unless *keepends* is given and true.

Python recognizes "\r", "\n", and "\r\n" as line boundaries for 8-bit strings.

예를 들면:

```
>>> 'ab c\n\nde fg\rkl\r\n'.splitlines()
['ab c', '', 'de fg', 'kl']
>>> 'ab c\n\nde fg\rkl\r\n'.splitlines(True)
['ab c\n', '\n', 'de fg\r', 'kl\r\n']
```

구분자 문자열 *sep* 이 주어졌을 때 *split()* 와 달리, 이 메서드는 빈 문자열에 대해서 빈 리스트를 돌려주고, 마지막 줄 바꿈은 새 줄을 만들지 않습니다:

```
>>> "".splitlines()
[]
>>> "One line\n".splitlines()
['One line']
```

비교해 보면, split('\n') 는 이렇게 됩니다:

```
>>> ''.split('\n')
['']
>>> 'Two lines\n'.split('\n')
['Two lines', '']
```

unicode.splitlines([keepends])

Return a list of the lines in the string, like *str.splitlines()*. However, the Unicode method splits on the following line boundaries, which are a superset of the *universal newlines* recognized for 8-bit strings.

표현	설명
\n	줄 넘김
\r	캐리지 리턴
\r\n	캐리지 리턴 + 줄 넘김
\v 또는 \x0b	수직 탭
\f 또는 \x0c	폼 피드
\x1c	파일 구분자
\x1d	그룹 구분자
\x1e	레코드 구분자
\x85	다음 줄 (C1 제어 코드)
\u2028	줄 구분자
\u2029	문단 구분자

버전 2.7에서 변경: \v 와 \f 를 줄 경계 목록에 추가했습니다.

`str.startswith(prefix[, start[, end]])`

문자열이 지정된 *prefix* 로 시작하면 True 를 돌려주고, 그렇지 않으면 False 를 돌려줍니다. *prefix* 는 찾고자 하는 접두사들의 튜플이 될 수도 있습니다. 선택적 *start* 가 제공되면 그 위치에서 검사를 시작합니다. 선택적 *end* 를 사용하면 해당 위치에서 비교를 중단합니다.

버전 2.5에서 변경: Accept tuples as *prefix*.

`str.strip([chars])`

Return a copy of the string with the leading and trailing characters removed. The *chars* argument is a string specifying the set of characters to be removed. If omitted or None, the *chars* argument defaults to removing whitespace. The *chars* argument is not a prefix or suffix; rather, all combinations of its values are stripped:

```
>>> '   spacious   '.strip()
'spacious'
>>> 'www.example.com'.strip('cmowz.')
'example'
```

버전 2.2.2에서 변경: Support for the *chars* argument.

`str.swapcase()`

Return a copy of the string with uppercase characters converted to lowercase and vice versa.

For 8-bit strings, this method is locale-dependent.

`str.title()`

단어가 대문자로 시작하고 나머지 문자는 소문자가 되도록 문자열의 제목 케이스 버전을 돌려줍니다.

이 알고리즘은 단어를 글자들의 연속으로 보는 간단한 언어 독립적 정의를 사용합니다. 이 정의는 여러 상황에서 작동하지만, 축약과 소유의 아포스트로피가 단어 경계를 형성한다는 것을 의미하고, 이는 원하는 결과가 아닐 수도 있습니다:

```
>>> "they're bill's friends from the UK".title()
'They'Re Bill'S Friends From The Uk'
```

정규식을 사용하여 아포스트로피에 대한 해결 방법을 구성할 수 있습니다:

```
>>> import re
>>> def titlecase(s):
...     return re.sub(r'[A-Za-z]+(''[A-Za-z]+'')?',
...                   lambda mo: mo.group(0)[0].upper() +
...                               mo.group(0)[1:].lower(),
...                   s)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
...
>>> titlecase("they're bill's friends.")
'They're Bill's Friends.'
```

For 8-bit strings, this method is locale-dependent.

`str.translate(table[, deletechars])`

Return a copy of the string where all characters occurring in the optional argument *deletechars* are removed, and the remaining characters have been mapped through the given translation table, which must be a string of length 256.

You can use the `maketrans()` helper function in the `string` module to create a translation table. For string objects, set the *table* argument to `None` for translations that only delete characters:

```
>>> 'read this short text'.translate(None, 'aeiou')
'rd ths shrt txt'
```

버전 2.6에 추가: Support for a `None` *table* argument.

For Unicode objects, the `translate()` method does not accept the optional *deletechars* argument. Instead, it returns a copy of the *s* where all characters have been mapped through the given translation table which must be a mapping of Unicode ordinals to Unicode ordinals, Unicode strings or `None`. Unmapped characters are left untouched. Characters mapped to `None` are deleted. Note, a more flexible approach is to create a custom character mapping codec using the `codecs` module (see `encodings.cp1251` for an example).

`str.upper()`

Return a copy of the string with all the cased characters⁴ converted to uppercase. Note that `s.upper().isupper()` might be `False` if *s* contains uncased characters or if the Unicode category of the resulting character(s) is not «Lu» (Letter, uppercase), but e.g. «Lt» (Letter, titlecase).

For 8-bit strings, this method is locale-dependent.

`str.zfill(width)`

Return the numeric string left filled with zeros in a string of length *width*. A sign prefix is handled correctly. The original string is returned if *width* is less than or equal to `len(s)`.

버전 2.2.2에 추가.

The following methods are present only on unicode objects:

`unicode.isnumeric()`

Return `True` if there are only numeric characters in *S*, `False` otherwise. Numeric characters include digit characters, and all characters that have the Unicode numeric value property, e.g. U+2155, VULGAR FRACTION ONE FIFTH.

`unicode.isdecimal()`

Return `True` if there are only decimal characters in *S*, `False` otherwise. Decimal characters include digit characters, and all characters that can be used to form decimal-radix numbers, e.g. U+0660, ARABIC-INDIC DIGIT ZERO.

5.6.2 String Formatting Operations

String and Unicode objects have one unique built-in operation: the `%` operator (modulo). This is also known as the string *formatting* or *interpolation* operator. Given `format % values` (where *format* is a string or Unicode object), `%` conversion specifications in *format* are replaced with zero or more elements of *values*. The effect is similar to the using `sprintf()` in the C language. If *format* is a Unicode object, or if any of the objects being converted using the `%s` conversion are Unicode objects, the result will also be a Unicode object.

format 이 하나의 인자를 요구하면, *values* 는 하나의 비 튜플 객체 일 수 있습니다.⁵ 그렇지 않으면, *values* 는 *format* 문자열이 지정하는 항목의 수와 같은 튜플이거나 단일 매핑 객체 (예를 들어, 딕셔너리) 이어야 합니다.

변환 명세는 두 개 이상의 문자를 포함하며 다음과 같은 구성 요소들을 포함하는데, 반드시 이 순서대로 나와야 합니다:

1. `'%'` 문자: 명세의 시작을 나타냅니다.
2. 매핑 키 (선택 사항): 괄호로 둘러싸인 문자들의 시퀀스로 구성됩니다 (예를 들어, `(somename)`).
3. 변환 플래그 (선택 사항): 일부 변환 유형의 결과에 영향을 줍니다.
4. 최소 필드 폭 (선택 사항): `'*'` (애스터리스크) 로 지정하면, 실제 폭은 *values* 튜플의 다음 요소에서 읽히고, 변환할 객체는 최소 필드 폭과 선택적 정밀도 뒤에 옵니다.
5. Precision (optional), given as a `'.'` (dot) followed by the precision. If specified as `'*'` (an asterisk), the actual width is read from the next element of the tuple in *values*, and the value to convert comes after the precision.
6. 길이 수정자 (선택 사항).
7. 변환 유형.

오른쪽 인자가 딕셔너리 (또는 다른 매핑 형) 인 경우, 문자열에 있는 변환 명세는 반드시 `'%'` 문자 바로 뒤에 그 딕셔너리의 매핑 키를 괄호로 둘러싼 형태로 포함해야 합니다. 매핑 키는 포맷할 값을 매핑으로 부터 선택합니다. 예를 들어:

```
>>> print '%(language)s has %(number)03d quote types.' % \
...      {"language": "Python", "number": 2}
Python has 002 quote types.
```

이 경우 `*` 지정자를 사용할 수 없습니다 (순차적인 파라미터 목록이 필요하기 때문입니다).

변환 플래그 문자는 다음과 같습니다:

플래그	뜻
<code>'#'</code>	값 변환에 《대체 형식》(아래에 정의되어 있습니다) 을 사용합니다.
<code>'0'</code>	변환은 숫자 값의 경우 0으로 채웁니다.
<code>'-'</code>	변환된 값은 왼쪽으로 정렬됩니다 (둘 다 주어진다면 <code>'0'</code> 변환보다 우선 합니다).
<code>' '</code>	(스페이스) 부호 있는 변환 때문에 만들어진 양수 앞에 빈칸을 남겨둡니다 (음수면 빈 문자열입니다).
<code>'+'</code>	부호 문자 (<code>'+' or '-'</code>) 가 변환 앞에 놓입니다 (<code>' '</code> 플래그에 우선합니다).

길이 수정자 (`h`, `l`, `L`) 를 제공할 수는 있지만, 파이썬에서 필요하지 않기 때문에 무시됩니다 – 예를 들어 `%ld` 는 `%d` 와 같습니다.

변환 유형은 다음과 같습니다:

⁵ 그래서, 튜플만을 포맷팅하려면 포맷할 튜플 하나만을 포함하는 1-튜플을 제공해야 합니다.

변환	뜻	노트
'd'	부호 있는 정수 십진 표기.	
'i'	부호 있는 정수 십진 표기.	
'o'	부호 있는 8진수 값.	(1)
'u'	쓸데없는 유형 - 'd' 와 같습니다.	(7)
'x'	부호 있는 16진수 (소문자).	(2)
'X'	부호 있는 16진수 (대문자).	(2)
'e'	부동 소수점 지수 형식 (소문자).	(3)
'E'	부동 소수점 지수 형식 (대문자).	(3)
'f'	부동 소수점 십진수 형식.	(3)
'F'	부동 소수점 십진수 형식.	(3)
'g'	부동 소수점 형식. 지수가 -4보다 작거나 정밀도 보다 작지 않으면 소문자 지수형식을 사용하고, 그렇지 않으면 십진수 형식을 사용합니다.	(4)
'G'	부동 소수점 형식. 지수가 -4보다 작거나 정밀도 보다 작지 않으면 대문자 지수형식을 사용하고, 그렇지 않으면 십진수 형식을 사용합니다.	(4)
'c'	단일 문자 (정수 또는 길이 1인 문자열을 허용합니다).	
'r'	String (converts any Python object using repr()).	(5)
's'	문자열 (str() 을 사용하여 파이썬 객체를 변환합니다).	(6)
'%'	인자는 변환되지 않고, 결과에 '%' 문자가 표시됩니다.	

노트:

- (1) The alternate form causes a leading zero ('0') to be inserted between left-hand padding and the formatting of the number if the leading character of the result is not already a zero.
- (2) 대체 형식은 첫 번째 숫자 앞에 선행 '0x' 또는 '0X' ('x' 나 'X' 유형 중 어느 것을 사용하느냐에 따라 달라집니다) 를 삽입합니다.
- (3) 대체 형식은 그 뒤에 숫자가 나오지 않더라도 항상 소수점을 포함합니다.
정밀도는 소수점 이하 자릿수를 결정하며 기본값은 6입니다.
- (4) 대체 형식은 결과에 항상 소수점을 포함하고 뒤에 오는 0은 제거되지 않습니다.
정밀도는 소수점 앞뒤의 유효 자릿수를 결정하며 기본값은 6입니다.
- (5) The %r conversion was added in Python 2.0.
The precision determines the maximal number of characters used.
- (6) If the object or format provided is a [unicode](#) string, the resulting string will also be [unicode](#).
The precision determines the maximal number of characters used.
- (7) [PEP 237](#)을 참조하세요.

파이썬 문자열은 명시적인 길이를 가지고 있으므로, %s 변환은 문자열의 끝이 '\0' 이라고 가정하지 않습니다.

버전 2.7에서 변경: 절댓값이 1e50 을 넘는 숫자에 대한 %f 변환은 더는 %g 변환으로 대체되지 않습니다.

Additional string operations are defined in standard modules [string](#) and [re](#).

5.6.3 xrange Type

The `xrange` type is an immutable sequence which is commonly used for looping. The advantage of the `xrange` type is that an `xrange` object will always take the same amount of memory, no matter the size of the range it represents. There are no consistent performance advantages.

XRange objects have very little behavior: they only support indexing, iteration, and the `len()` function.

5.6.4 가변 시퀀스 형

List and `bytearray` objects support additional operations that allow in-place modification of the object. Other mutable sequence types (when added to the language) should also support these operations. Strings and tuples are immutable sequence types: such objects cannot be modified once created. The following operations are defined on mutable sequence types (where `x` is an arbitrary object):

연산	결과	노트
<code>s[i] = x</code>	<code>s</code> 의 항목 <code>i</code> 를 <code>x</code> 로 대체합니다	
<code>s[i:j] = t</code>	<code>i</code> 에서 <code>j</code> 까지의 <code>s</code> 슬라이스가 이터러블 <code>t</code> 의 내용으로 대체됩니다	
<code>del s[i:j]</code>	<code>s[i:j] = []</code> 와 같습니다	
<code>s[i:j:k] = t</code>	<code>s[i:j:k]</code> 의 항목들이 <code>t</code> 의 항목들로 대체됩니다	(1)
<code>del s[i:j:k]</code>	리스트에서 <code>s[i:j:k]</code> 의 항목들을 제거합니다	
<code>s.append(x)</code>	same as <code>s[len(s):len(s)] = [x]</code>	(2)
<code>s.extend(t)</code> 또는 <code>s += t</code>	for the most part the same as <code>s[len(s):len(s)] = t</code>	(3)
<code>s *= n</code>	내용이 <code>n</code> 번 반복되도록 <code>s</code> 를 갱신합니다	(11)
<code>s.count(x)</code>	return number of <code>i</code> 's for which <code>s[i] == x</code>	
<code>s.index(x[, i[, j]])</code>	return smallest <code>k</code> such that <code>s[k] == x</code> and <code>i <= k < j</code>	(4)
<code>s.insert(i, x)</code>	same as <code>s[i:i] = [x]</code>	(5)
<code>s.pop([i])</code>	same as <code>x = s[i]; del s[i]; return x</code>	(6)
<code>s.remove(x)</code>	same as <code>del s[s.index(x)]</code>	(4)
<code>s.reverse()</code>	제자리에서 <code>s</code> 의 항목들의 순서를 뒤집습니다	(7)
<code>s.sort([cmp[, key[, reverse]])</code>	sort the items of <code>s</code> in place	(7)(8)(9)(10)

노트:

- (1) `t` must have the same length as the slice it is replacing.
- (2) The C implementation of Python has historically accepted multiple parameters and implicitly joined them into a tuple; this no longer works in Python 2.0. Use of this misfeature has been deprecated since Python 1.4.
- (3) `t` can be any iterable object.
- (4) Raises `ValueError` when `x` is not found in `s`. When a negative index is passed as the second or third parameter to the `index()` method, the list length is added, as for slice indices. If it is still negative, it is truncated to zero, as for slice indices.
버전 2.3에서 변경: Previously, `index()` didn't have arguments for specifying start and stop positions.
- (5) When a negative index is passed as the first parameter to the `insert()` method, the list length is added, as for slice indices. If it is still negative, it is truncated to zero, as for slice indices.
버전 2.3에서 변경: Previously, all negative indices were truncated to zero.
- (6) The `pop()` method's optional argument `i` defaults to `-1`, so that by default the last item is removed and returned.

- (7) The `sort()` and `reverse()` methods modify the list in place for economy of space when sorting or reversing a large list. To remind you that they operate by side effect, they don't return the sorted or reversed list.
- (8) The `sort()` method takes optional arguments for controlling the comparisons.

cmp specifies a custom comparison function of two arguments (list items) which should return a negative, zero or positive number depending on whether the first argument is considered smaller than, equal to, or larger than the second argument: `cmp=lambda x,y: cmp(x.lower(), y.lower())`. The default value is `None`.

key specifies a function of one argument that is used to extract a comparison key from each list element: `key=str.lower`. The default value is `None`.

reverse 는 논리값입니다. `True` 로 설정되면, 각 비교가 역전된 것처럼 리스트 요소들이 정렬됩니다.

In general, the *key* and *reverse* conversion processes are much faster than specifying an equivalent *cmp* function. This is because *cmp* is called multiple times for each list element while *key* and *reverse* touch each element only once. Use `functools.cmp_to_key()` to convert an old-style *cmp* function to a *key* function.

버전 2.3에서 변경: Support for `None` as an equivalent to omitting *cmp* was added.

버전 2.4에서 변경: Support for *key* and *reverse* was added.

- (9) Starting with Python 2.3, the `sort()` method is guaranteed to be stable. A sort is stable if it guarantees not to change the relative order of elements that compare equal — this is helpful for sorting in multiple passes (for example, sort by department, then by salary grade).
- (10) **CPython implementation detail:** While a list is being sorted, the effect of attempting to mutate, or even inspect, the list is undefined. The C implementation of Python 2.3 and newer makes the list appear empty for the duration, and raises `ValueError` if it can detect that the list has been mutated during a sort.
- (11) The value *n* is an integer, or an object implementing `__index__()`. Zero and negative values of *n* clear the sequence. Items in the sequence are not copied; they are referenced multiple times, as explained for `s * n` under *Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange*.

5.7 집합형 — set, frozenset

A *set* object is an unordered collection of distinct *hashable* objects. Common uses include membership testing, removing duplicates from a sequence, and computing mathematical operations such as intersection, union, difference, and symmetric difference. (For other containers see the built in *dict*, *list*, and *tuple* classes, and the *collections* module.)

버전 2.4에 추가.

다른 컬렉션과 마찬가지로, 집합은 `x in set`, `len(set)`, `for x in set` 을 지원합니다. 순서가 없는 컬렉션이므로, 집합은 원소의 위치나 삽입 순서를 기록하지 않습니다. 따라서 집합은 인덱싱, 슬라이싱 또는 기타 시퀀스와 유사한 동작을 지원하지 않습니다.

현재 두 가지 내장형이 있습니다, *set*과 *frozenset*. *set* 형은 가변입니다 — 내용을 `add()` 나 `remove()` 와 같은 메서드를 사용하여 변경할 수 있습니다. 가변이기 때문에, 해시값이 없으며 딕셔너리 키 또는 다른 집합의 원소로 사용할 수 없습니다. *frozenset* 형은 불변이고 해시 가능 합니다 — 만들어진 후에는 내용을 바꿀 수 없습니다; 따라서 딕셔너리 키 또는 다른 집합의 원소로 사용할 수 있습니다.

As of Python 2.7, non-empty sets (not frozensets) can be created by placing a comma-separated list of elements within braces, for example: `{'jack', 'sjoerd'}`, in addition to the *set* constructor.

두 클래스의 생성자는 같게 작동합니다:

```
class set ([iterable])
class frozenset ([iterable])
```

iterable 에서 요소를 취하는 새 *set* 또는 *frozenset* 객체를 돌려줍니다. 집합의 원소는 반드시 해시 가능

해야 합니다. 집합의 집합을 표현하려면, 포함되는 집합은 반드시 *frozenset* 객체여야 합니다. *iterable* 을 지정하지 않으면 새 빈 집합을 돌려줍니다.

*set*과 *frozenset*의 인스턴스는 다음과 같은 연산을 제공합니다:

len(s)

집합 *s*의 원소 수(*s*의 크기)를 돌려줍니다.

x in s

*s*에 대해 *x*의 멤버십을 검사합니다.

x not in s

*s*에 대해 *x*의 비 멤버십을 검사합니다.

isdisjoint(other)

집합이 *other*와 공통 원소를 갖지 않는 경우 True을 돌려줍니다. 집합은 교집합이 공집합일 때, 그리고 그때만 서로소(disjoint)라고 합니다.

버전 2.6에 추가.

issubset(other)

set <= other

집합의 모든 원소가 *other*에 포함되는지 검사합니다.

set < other

집합이 *other*의 진부분집합인지 검사합니다, 즉, *set <= other* and *set != other*.

issuperset(other)

set >= other

*other*의 모든 원소가 집합에 포함되는지 검사합니다.

set > other

집합이 *other*의 진상위집합인지 검사합니다, 즉, *set >= other* and *set != other*.

union(*others)

set | other | ...

집합과 모든 *others*에 있는 원소들로 구성된 새 집합을 돌려줍니다.

버전 2.6에서 변경: Accepts multiple input iterables.

intersection(*others)

set & other & ...

집합과 모든 *others*의 공통 원소들로 구성된 새 집합을 돌려줍니다.

버전 2.6에서 변경: Accepts multiple input iterables.

difference(*others)

set - other - ...

집합에는 포함되었으나 *others*에는 포함되지 않은 원소들로 구성된 새 집합을 돌려줍니다.

버전 2.6에서 변경: Accepts multiple input iterables.

symmetric_difference(other)

set ^ other

집합이나 *other*에 포함되어 있으나 둘 모두에 포함되지 않은 원소들로 구성된 새 집합을 돌려줍니다.

copy()

Return a shallow copy of the set.

참 고 로, 연 산 자 가 아 닌 버 전 의 *union()*, *intersection()*, *difference()*, *symmetric_difference()*, *issubset()*, *issuperset()* 메서드는 임의의 이터러블을 인자로 받아들입니다. 대조적으로, 연산자를 기반으로 하는 대응 연산들은 인자가 집합일 것을 요구합

니다. 이것은 오류가 발생하기 쉬운 `set('abc') & 'cbs'` 와 같은 구성을 배제하고 더 읽기 쉬운 `set('abc').intersection('cbs')` 를 선호합니다.

`set`과 `frozenset` 모두 집합 간의 비교를 지원합니다. 두 집합은 각 집합의 모든 원소가 다른 집합에 포함되어있는 경우에만 같습니다(서로 다른 집합의 부분집합입니다). 집합이 다른 집합의 진부분집합(부분집합이지만 같지는 않은 경우)일 때만 첫 번째 집합이 두 번째 집합보다 작습니다. 집합이 다른 집합의 진상위집합(상위집합이지만 같지는 않은 경우)일 때만 첫 번째 집합이 두 번째 집합보다 큼니다.

`set`의 인스턴스는 그 원소를 기반으로 `frozenset`의 인스턴스와 비교됩니다. 예를 들어, `set('abc') == frozenset('abc')`는 `True`를 돌려주고 `set('abc') in set([frozenset('abc')])`도 마찬가지입니다.

The subset and equality comparisons do not generalize to a total ordering function. For example, any two non-empty disjoint sets are not equal and are not subsets of each other, so *all* of the following return `False`: `a < b`, `a == b`, or `a > b`. Accordingly, sets do not implement the `__cmp__()` method.

집합은 부분 순서(부분 집합 관계)만 정의하기 때문에, 집합의 리스트에 대한 `list.sort()` 메서드의 결과는 정의되지 않습니다.

딕셔너리 키처럼, 집합의 원소는 반드시 해시 가능해야 합니다.

`set` 인스턴스와 `frozenset`을 혼합한 이항 연산은 첫 번째 피연산자의 형을 돌려줍니다. 예를 들어: `frozenset('ab') | set('bc')`는 `frozenset`의 인스턴스를 돌려줍니다.

다음 표는 `frozenset`의 불변 인스턴스에는 적용되지 않고 `set`에서만 사용할 수 있는 연산들을 나열합니다:

update (*others)

set |= other | ...

집합을 갱신해서, 모든 others의 원소들을 더합니다.

버전 2.6에서 변경: Accepts multiple input iterables.

intersection_update (*others)

set &= other & ...

집합을 갱신해서, 그 집합과 others에 공통으로 포함된 원소들만 남깁니다.

버전 2.6에서 변경: Accepts multiple input iterables.

difference_update (*others)

set -= other | ...

집합을 갱신해서, others에 있는 원소들을 제거합니다.

버전 2.6에서 변경: Accepts multiple input iterables.

symmetric_difference_update (other)

set ^= other

집합을 갱신해서, 두 집합의 어느 한 곳에만 포함된 원소들만 남깁니다.

add (elem)

원소 elem을 집합에 추가합니다.

remove (elem)

원소 elem을 집합에서 제거합니다. elem가 집합에 포함되어 있지 않으면 `KeyError`를 일으킵니다.

discard (elem)

원소 elem이 집합에 포함되어 있으면 제거합니다.

pop ()

집합으로부터 임의의 원소를 제거해 돌려줍니다. 집합이 비어있는 경우 `KeyError`를 일으킵니다.

clear ()

집합의 모든 원소를 제거합니다.

참 고 로, `update()`, `intersection_update()`, `difference_update()`, `symmetric_difference_update()` 메서드의 비 연산자 버전은 임의의 이터러블을 인자로 받아들입니다.

참고로, `__contains__()`, `remove()`, `discard()` 메서드로 제공되는 *elem* 인자는 set 일 수 있습니다. 동등한 frozenset 검색을 지원하기 위해, *elem* 으로 임시 frozenset 을 만듭니다.

더 보기:

Comparison to the built-in set types Differences between the *sets* module and the built-in set types.

5.8 매핑 형 — dict

A *mapping* object maps *hashable* values to arbitrary objects. Mappings are mutable objects. There is currently only one standard mapping type, the *dictionary*. (For other containers see the built in *list*, *set*, and *tuple* classes, and the *collections* module.)

딕셔너리의 키는 거의 임의의 값입니다. 해시 가능 하지 않은 값들, 즉, 리스트, 딕셔너리 또는 다른 가변형 (객체 아이덴티티 대신 값으로 비교됩니다) 은 키로 사용할 수 없습니다. 키에 사용되는 숫자 형은 숫자 비교를 위한 일반적인 규칙을 따릅니다: 두 숫자가 같다고 비교되는 경우 (1 과 1.0 처럼) 같은 딕셔너리 항목을 인덱싱하는데 서로 교환하여 사용할 수 있습니다. (그러나 컴퓨터는 부동 소수점 숫자를 근삿값으로 저장하므로 이것들을 딕셔너리 키로 사용하는 것은 현명하지 않습니다.)

딕셔너리는 *dict* 생성자뿐만 아니라 중괄호 안에 쉼표로 구분된 key: value 쌍을 나열해서 만들 수 있습니다, 예를 들어: {'jack': 4098, 'sjoerd': 4127} 또는 {4098: 'jack', 4127: 'sjoerd'}.

class dict (**kwarg)

class dict (mapping, **kwarg)

class dict (iterable, **kwarg)

선택적 위치 인자와 (비어있을 수 있는) 키워드 인자들의 집합으로부터 초기화된 새 딕셔너리를 돌려줍니다.

위치 인자가 제공되지 않으면 빈 딕셔너리가 만들어집니다. 위치 인자가 지정되고 매핑 객체인 경우, 매핑 객체와 같은 키-값 쌍을 갖는 딕셔너리가 만들어집니다. 그렇지 않으면, 위치 인자는 이터러블 객체여야 합니다. 이터러블의 각 항목은 그 자체로 정확하게 두 개의 객체가 있는 이터러블이어야 합니다. 각 항목의 첫 번째 객체는 새 딕셔너리의 키가 되고, 두 번째 객체는 해당 값이 됩니다. 키가 두 번 이상 나타나면, 그 키의 마지막 값이 새 딕셔너리의 해당 값이 됩니다.

키워드 인자가 제공되면, 키워드 인자와 해당 값이 위치 인자로부터 만들어진 딕셔너리에 추가됩니다. 추가되는 키가 이미 존재하면, 키워드 인자에서 온 값이 위치 인자에게서 온 값을 대체합니다.

예를 들어, 다음 예제는 모두 {"one": 1, "two": 2, "three": 3} 와 같은 딕셔너리를 돌려줍니다:

```
>>> a = dict(one=1, two=2, three=3)
>>> b = {'one': 1, 'two': 2, 'three': 3}
>>> c = dict(zip(['one', 'two', 'three'], [1, 2, 3]))
>>> d = dict([('two', 2), ('one', 1), ('three', 3)])
>>> e = dict({'three': 3, 'one': 1, 'two': 2})
>>> a == b == c == d == e
True
```

첫 번째 예제에서와같이 키워드 인자는 유효한 파이썬 식별자인 키에 대해서만 작동합니다. 그 외의 경우는 모든 유효한 키를 사용할 수 있습니다.

버전 2.2에 추가.

버전 2.3에서 변경: Support for building a dictionary from keyword arguments added.

이것들은 딕셔너리가 지원하는 연산들입니다 (그러므로, 사용자 정의 매핑 형도 지원해야 합니다):

len(d)

딕셔너리 *d* 에 있는 항목의 수를 돌려줍니다.

d[key]

키 *key* 인 *d* 의 항목을 돌려줍니다. *key* 가 매핑에 없는 경우 *KeyError* 를 일으킵니다.

dict 의 서브 클래스가 method `__missing__()` 을 정의하고 *key* 가 존재하지 않는다면, *d[key]* 연산은 키 *key* 를 인자로 하여 그 메서드를 호출합니다. 그런 다음 *d[key]* 연산은 `__missing__(key)` 호출이 반환한 값이나 일으킨 예외를 그대로 반환하거나 일으킵니다. 다른 연산이나 메서드는 `__missing__()` 을 호출하지 않습니다. `__missing__()` 이 정의되어 있지 않으면 *KeyError* 를 일으킵니다. `__missing__()` 은 메서드여야 합니다; 인스턴스 변수가 될 수 없습니다:

```
>>> class Counter(dict):
...     def __missing__(self, key):
...         return 0
>>> c = Counter()
>>> c['red']
0
>>> c['red'] += 1
>>> c['red']
1
```

위의 예는 `collections.Counter` 구현 일부를 보여줍니다. 다른 `__missing__` 메서드가 `collections.defaultdict` 에서 사용됩니다.

버전 2.5에 추가: Recognition of `__missing__` methods of dict subclasses.

d[key] = value

d[key] 를 *value* 로 설정합니다.

del d[key]

d 에서 *d[key]* 를 제거합니다. *key* 가 매핑에 없는 경우 *KeyError* 를 일으킵니다.

key in d

d 에 키 *key* 가 있으면 *True* 를, 그렇지 않으면 *False* 를 돌려줍니다.

버전 2.2에 추가.

key not in d

`not key in d` 와 동등합니다.

버전 2.2에 추가.

iter(d)

Return an iterator over the keys of the dictionary. This is a shortcut for `iterkeys()`.

clear()

딕셔너리에서 모든 항목을 제거합니다.

copy()

딕셔너리의 얇은 복사본을 돌려줍니다.

fromkeys(seq[, value])

seq 가 제공하는 값들을 키로 사용하고 모든 값을 *value* 로 설정한 새 딕셔너리를 돌려줍니다.

`fromkeys()` is a class method that returns a new dictionary. *value* defaults to *None*.

버전 2.3에 추가.

get(key[, default])

key 가 딕셔너리에 있는 경우 *key* 에 대응하는 값을 돌려주고, 그렇지 않으면 *default* 를 돌려줍니다.

default 가 주어지지 않으면 기본값 `None` 이 사용됩니다. 그래서 이 메서드는 절대로 `KeyError` 를 일으키지 않습니다.

has_key (*key*)

Test for the presence of *key* in the dictionary. *has_key()* is deprecated in favor of `key in d`.

items ()

Return a copy of the dictionary's list of (*key*, *value*) pairs.

CPython implementation detail: Keys and values are listed in an arbitrary order which is non-random, varies across Python implementations, and depends on the dictionary's history of insertions and deletions.

If *items()*, *keys()*, *values()*, *iteritems()*, *iterkeys()*, and *itervalues()* are called with no intervening modifications to the dictionary, the lists will directly correspond. This allows the creation of (*value*, *key*) pairs using *zip()*: `pairs = zip(d.values(), d.keys())`. The same relationship holds for the *iterkeys()* and *itervalues()* methods: `pairs = zip(d.itervalues(), d.iterkeys())` provides the same value for pairs. Another way to create the same list is `pairs = [(v, k) for (k, v) in d.iteritems()]`.

iteritems ()

Return an iterator over the dictionary's (*key*, *value*) pairs. See the note for *dict.items()*.

Using *iteritems()* while adding or deleting entries in the dictionary may raise a `RuntimeError` or fail to iterate over all entries.

버전 2.2에 추가.

iterkeys ()

Return an iterator over the dictionary's keys. See the note for *dict.items()*.

Using *iterkeys()* while adding or deleting entries in the dictionary may raise a `RuntimeError` or fail to iterate over all entries.

버전 2.2에 추가.

itervalues ()

Return an iterator over the dictionary's values. See the note for *dict.items()*.

Using *itervalues()* while adding or deleting entries in the dictionary may raise a `RuntimeError` or fail to iterate over all entries.

버전 2.2에 추가.

keys ()

Return a copy of the dictionary's list of keys. See the note for *dict.items()*.

pop (*key* [, *default*])

key 가 딕셔너리에 있으면 제거하고 그 값을 돌려줍니다. 그렇지 않으면 *default* 를 돌려줍니다. *default* 가 주어지지 않고 *key* 가 딕셔너리에 없으면 `KeyError` 를 일으킵니다.

버전 2.3에 추가.

popitem ()

딕셔너리에서 임의의 (*key*, *value*) 쌍을 제거하고 돌려줍니다.

popitem() is useful to destructively iterate over a dictionary, as often used in set algorithms. If the dictionary is empty, calling *popitem()* raises a `KeyError`.

setdefault (*key* [, *default*])

key 가 딕셔너리에 있으면 해당 값을 돌려줍니다. 그렇지 않으면, *default* 값을 갖는 *key* 를 삽입한 후 *default* 를 돌려줍니다. *default* 의 기본값은 `None` 입니다.

update ([*other*])

other 가 제공하는 키/값 쌍으로 사전을 갱신합니다. 기존 키는 덮어씁니다. `None` 을 돌려줍니다.

`update()` accepts either another dictionary object or an iterable of key/value pairs (as tuples or other iterables of length two). If keyword arguments are specified, the dictionary is then updated with those key/value pairs: `d.update(red=1, blue=2)`.

버전 2.4에서 변경: Allowed the argument to be an iterable of key/value pairs and allowed keyword arguments.

values()

Return a copy of the dictionary's list of values. See the note for `dict.items()`.

viewitems()

Return a new view of the dictionary's items ((key, value) pairs). See below for documentation of view objects.

버전 2.7에 추가.

viewkeys()

Return a new view of the dictionary's keys. See below for documentation of view objects.

버전 2.7에 추가.

viewvalues()

Return a new view of the dictionary's values. See below for documentation of view objects.

버전 2.7에 추가.

Dictionaries compare equal if and only if they have the same (key, value) pairs.

5.8.1 딕셔너리 뷰 객체

The objects returned by `dict.viewkeys()`, `dict.viewvalues()` and `dict.viewitems()` are *view objects*. They provide a dynamic view on the dictionary's entries, which means that when the dictionary changes, the view reflects these changes.

딕셔너리 뷰는 이터레이션을 통해 각각의 데이터를 산출할 수 있고, 멤버십 검사를 지원합니다:

len(dictview)

딕셔너리에 있는 항목 수를 돌려줍니다.

iter(dictview)

딕셔너리에서 키, 값, 항목((key, value) 튜플로 표현됩니다)에 대한 이터레이터를 돌려줍니다.

키와 값은 무작위는 아니지만, 임의의 순서(파이썬 구현에 따라 달라집니다)로 이터레이션 되고, 딕셔너리의 삽입 및 삭제 이력에 따라 달라집니다. 키, 값 및 항목 뷰를 이터레이션 하는 도중에 딕셔너리를 수정하지 않으면, 항목들의 순서는 모두 일치합니다. 이 때문에 `zip()`을 사용해서 (value, key) 쌍을 만들 수 있습니다: `pairs = zip(d.values(), d.keys())`. 같은 리스트를 만드는 다른 방법은 `pairs = [(v, k) for (k, v) in d.items()]` 입니다.

딕셔너리에 항목을 추가하거나 삭제하는 동안 뷰를 이터레이션 하면 `RuntimeError`를 일으키거나 모든 항목을 이터레이션 하지 못할 수 있습니다.

x in dictview

`x`가 하부 딕셔너리의 키, 값, 항목에 있는 경우 `True`를 돌려줍니다(마지막의 경우 `x`는 (key, value) 튜플이어야 합니다).

Keys views are set-like since their entries are unique and hashable. If all values are hashable, so that (key, value) pairs are unique and hashable, then the items view is also set-like. (Values views are not treated as set-like since the entries are generally not unique.) Then these set operations are available (《other》 refers either to another view or a set):

dictview & other

Return the intersection of the dictview and the other object as a new set.

dictview | other

Return the union of the dictview and the other object as a new set.

dictview - other

Return the difference between the dictview and the other object (all elements in *dictview* that aren't in *other*) as a new set.

dictview ^ other

Return the symmetric difference (all elements either in *dictview* or *other*, but not in both) of the dictview and the other object as a new set.

딕셔너리 뷰 사용의 예:

```
>>> dishes = {'eggs': 2, 'sausage': 1, 'bacon': 1, 'spam': 500}
>>> keys = dishes.viewkeys()
>>> values = dishes.viewvalues()

>>> # iteration
>>> n = 0
>>> for val in values:
...     n += val
>>> print(n)
504

>>> # keys and values are iterated over in the same order
>>> list(keys)
['eggs', 'bacon', 'sausage', 'spam']
>>> list(values)
[2, 1, 1, 500]

>>> # view objects are dynamic and reflect dict changes
>>> del dishes['eggs']
>>> del dishes['sausage']
>>> list(keys)
['spam', 'bacon']

>>> # set operations
>>> keys & {'eggs', 'bacon', 'salad'}
{'bacon'}
```

5.9 File Objects

File objects are implemented using C's `stdio` package and can be created with the built-in `open()` function. File objects are also returned by some other built-in functions and methods, such as `os.popen()` and `os.fdopen()` and the `makefile()` method of socket objects. Temporary files can be created using the `tempfile` module, and high-level file operations such as copying, moving, and deleting files and directories can be achieved with the `shutil` module.

When a file operation fails for an I/O-related reason, the exception `IOError` is raised. This includes situations where the operation is not defined for some reason, like `seek()` on a tty device or writing a file opened for reading.

Files have the following methods:

file.close()

Close the file. A closed file cannot be read or written any more. Any operation which requires that the file be open will raise a `ValueError` after the file has been closed. Calling `close()` more than once is allowed.

As of Python 2.5, you can avoid having to call this method explicitly if you use the `with` statement. For example, the following code will automatically close `f` when the `with` block is exited:

```
from __future__ import with_statement # This isn't required in Python 2.6

with open("hello.txt") as f:
    for line in f:
        print line,
```

In older versions of Python, you would have needed to do this to get the same effect:

```
f = open("hello.txt")
try:
    for line in f:
        print line,
finally:
    f.close()
```

참고: Not all «file-like» types in Python support use as a context manager for the `with` statement. If your code is intended to work with any file-like object, you can use the function `contextlib.closing()` instead of using the object directly.

`file.flush()`

Flush the internal buffer, like `stdio`'s `fflush()`. This may be a no-op on some file-like objects.

참고: `flush()` does not necessarily write the file's data to disk. Use `flush()` followed by `os.fsync()` to ensure this behavior.

`file.fileno()`

Return the integer «file descriptor» that is used by the underlying implementation to request I/O operations from the operating system. This can be useful for other, lower level interfaces that use file descriptors, such as the `fcntl` module or `os.read()` and friends.

참고: File-like objects which do not have a real file descriptor should *not* provide this method!

`file.isatty()`

Return `True` if the file is connected to a tty(-like) device, else `False`.

참고: If a file-like object is not associated with a real file, this method should *not* be implemented.

`file.next()`

A file object is its own iterator, for example `iter(f)` returns `f` (unless `f` is closed). When a file is used as an iterator, typically in a `for` loop (for example, `for line in f: print line.strip()`), the `next()` method is called repeatedly. This method returns the next input line, or raises `StopIteration` when EOF is hit when the file is open for reading (behavior is undefined when the file is open for writing). In order to make a `for` loop the most efficient way of looping over the lines of a file (a very common operation), the `next()` method uses a hidden read-ahead buffer. As a consequence of using a read-ahead buffer, combining `next()` with other file methods (like `readline()`) does not work right. However, using `seek()` to reposition the file to an absolute position will flush the read-ahead buffer.

버전 2.3에 추가.

`file.read([size])`

Read at most *size* bytes from the file (less if the read hits EOF before obtaining *size* bytes). If the *size* argument is negative or omitted, read all data until EOF is reached. The bytes are returned as a string object. An empty string is returned when EOF is encountered immediately. (For certain files, like ttys, it makes sense to continue reading after an EOF is hit.) Note that this method may call the underlying C function `fread()` more than once in an effort to acquire as close to *size* bytes as possible. Also note that when in non-blocking mode, less data than was requested may be returned, even if no *size* parameter was given.

참고: This function is simply a wrapper for the underlying `fread()` C function, and will behave the same in corner cases, such as whether the EOF value is cached.

`file.readline([size])`

Read one entire line from the file. A trailing newline character is kept in the string (but may be absent when a file ends with an incomplete line).⁶ If the *size* argument is present and non-negative, it is a maximum byte count (including the trailing newline) and an incomplete line may be returned. When *size* is not 0, an empty string is returned *only* when EOF is encountered immediately.

참고: Unlike `stdio`'s `fgets()`, the returned string contains null characters (`'\0'`) if they occurred in the input.

`file.readlines([sizehint])`

Read until EOF using `readline()` and return a list containing the lines thus read. If the optional *sizehint* argument is present, instead of reading up to EOF, whole lines totalling approximately *sizehint* bytes (possibly after rounding up to an internal buffer size) are read. Objects implementing a file-like interface may choose to ignore *sizehint* if it cannot be implemented, or cannot be implemented efficiently.

`file.xreadlines()`

This method returns the same thing as `iter(f)`.

버전 2.1에 추가.

버전 2.3부터 폐지: Use `for line in file` instead.

`file.seek(offset[, whence])`

Set the file's current position, like `stdio`'s `fseek()`. The *whence* argument is optional and defaults to `os.SEEK_SET` or 0 (absolute file positioning); other values are `os.SEEK_CUR` or 1 (seek relative to the current position) and `os.SEEK_END` or 2 (seek relative to the file's end). There is no return value.

For example, `f.seek(2, os.SEEK_CUR)` advances the position by two and `f.seek(-3, os.SEEK_END)` sets the position to the third to last.

Note that if the file is opened for appending (mode `'a'` or `'a+'`), any `seek()` operations will be undone at the next write. If the file is only opened for writing in append mode (mode `'a'`), this method is essentially a no-op, but it remains useful for files opened in append mode with reading enabled (mode `'a+'`). If the file is opened in text mode (without `'b'`), only offsets returned by `tell()` are legal. Use of other offsets causes undefined behavior.

Note that not all file objects are seekable.

버전 2.6에서 변경: Passing float values as offset has been deprecated.

`file.tell()`

Return the file's current position, like `stdio`'s `ftell()`.

⁶ The advantage of leaving the newline on is that returning an empty string is then an unambiguous EOF indication. It is also possible (in cases where it might matter, for example, if you want to make an exact copy of a file while scanning its lines) to tell whether the last line of a file ended in a newline or not (yes this happens!).

참고: On Windows, `tell()` can return illegal values (after an `fgets()`) when reading files with Unix-style line-endings. Use binary mode (`'rb'`) to circumvent this problem.

`file.truncate([size])`

Truncate the file's size. If the optional *size* argument is present, the file is truncated to (at most) that size. The size defaults to the current position. The current file position is not changed. Note that if a specified size exceeds the file's current size, the result is platform-dependent: possibilities include that the file may remain unchanged, increase to the specified size as if zero-filled, or increase to the specified size with undefined new content. Availability: Windows, many Unix variants.

`file.write(str)`

Write a string to the file. There is no return value. Due to buffering, the string may not actually show up in the file until the `flush()` or `close()` method is called.

`file.writelines(sequence)`

Write a sequence of strings to the file. The sequence can be any iterable object producing strings, typically a list of strings. There is no return value. (The name is intended to match `readlines()`; `writelines()` does not add line separators.)

Files support the iterator protocol. Each iteration returns the same result as `readline()`, and iteration ends when the `readline()` method returns an empty string.

File objects also offer a number of other interesting attributes. These are not required for file-like objects, but should be implemented if they make sense for the particular object.

`file.closed`

bool indicating the current state of the file object. This is a read-only attribute; the `close()` method changes the value. It may not be available on all file-like objects.

`file.encoding`

The encoding that this file uses. When Unicode strings are written to a file, they will be converted to byte strings using this encoding. In addition, when the file is connected to a terminal, the attribute gives the encoding that the terminal is likely to use (that information might be incorrect if the user has misconfigured the terminal). The attribute is read-only and may not be present on all file-like objects. It may also be `None`, in which case the file uses the system default encoding for converting Unicode strings.

버전 2.3에 추가.

`file.errors`

The Unicode error handler used along with the encoding.

버전 2.6에 추가.

`file.mode`

The I/O mode for the file. If the file was created using the `open()` built-in function, this will be the value of the *mode* parameter. This is a read-only attribute and may not be present on all file-like objects.

`file.name`

If the file object was created using `open()`, the name of the file. Otherwise, some string that indicates the source of the file object, of the form `<...>`. This is a read-only attribute and may not be present on all file-like objects.

`file.newlines`

If Python was built with *universal newlines* enabled (the default) this read-only attribute exists, and for files opened in universal newline read mode it keeps track of the types of newlines encountered while reading the file. The values it can take are `'\r'`, `'\n'`, `'\r\n'`, `None` (unknown, no newlines read yet) or a tuple containing all the newline types seen, to indicate that multiple newline conventions were encountered. For files not opened in universal newlines read mode the value of this attribute will be `None`.

file.softspace

Boolean that indicates whether a space character needs to be printed before another value when using the `print` statement. Classes that are trying to simulate a file object should also have a writable `softspace` attribute, which should be initialized to zero. This will be automatic for most classes implemented in Python (care may be needed for objects that override attribute access); types implemented in C will have to provide a writable `softspace` attribute.

참고: This attribute is not used to control the `print` statement, but to allow the implementation of `print` to keep track of its internal state.

5.10 memoryview type

버전 2.7에 추가.

`memoryview` objects allow Python code to access the internal data of an object that supports the buffer protocol without copying. Memory is generally interpreted as simple bytes.

class memoryview(obj)

Create a `memoryview` that references *obj*. *obj* must support the buffer protocol. Built-in objects that support the buffer protocol include `str` and `bytearray` (but not `unicode`).

A `memoryview` has the notion of an *element*, which is the atomic memory unit handled by the originating object *obj*. For many simple types such as `str` and `bytearray`, an element is a single byte, but other third-party types may expose larger elements.

`len(view)` returns the total number of elements in the memoryview, *view*. The `itemsize` attribute will give you the number of bytes in a single element.

A `memoryview` supports slicing to expose its data. Taking a single index will return a single element as a `str` object. Full slicing will result in a subview:

```
>>> v = memoryview('abcefg')
>>> v[1]
'b'
>>> v[-1]
'g'
>>> v[1:4]
<memory at 0x77ab28>
>>> v[1:4].tobytes()
'bce'
```

If the object the memoryview is over supports changing its data, the memoryview supports slice assignment:

```
>>> data = bytearray('abcefg')
>>> v = memoryview(data)
>>> v.readonly
False
>>> v[0] = 'z'
>>> data
bytearray(b'zbcefg')
>>> v[1:4] = '123'
>>> data
bytearray(b'z123fg')
>>> v[2] = 'spam'
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ValueError: cannot modify size of memoryview object
```

Notice how the size of the memoryview object cannot be changed.

`memoryview` has two methods:

tobytes()

Return the data in the buffer as a bytestring (an object of class `str`).

```
>>> m = memoryview("abc")
>>> m.tobytes()
'abc'
```

tolist()

Return the data in the buffer as a list of integers.

```
>>> memoryview("abc").tolist()
[97, 98, 99]
```

몇 가지 읽기 전용 어트리뷰트도 사용할 수 있습니다:

format

A string containing the format (in `struct` module style) for each element in the view. This defaults to 'B', a simple bytestring.

itemsize

The size in bytes of each element of the memoryview.

shape

N-차원 배열로서의 메모리의 모양을 가리키는, 길이 `ndim` 인 정수의 튜플입니다.

ndim

메모리가 나타내는 다차원 배열의 차원 수를 나타내는 정수.

strides

배열의 각 차원에 대해 각 요소를 참조하는데 필요한 바이트 수를 제공하는, 길이 `ndim` 인 정수의 튜플입니다.

readonly

메모리가 읽기 전용인지 여부를 나타내는 논리값.

5.11 컨텍스트 관리자 형

버전 2.5에 추가.

Python's `with` statement supports the concept of a runtime context defined by a context manager. This is implemented using two separate methods that allow user-defined classes to define a runtime context that is entered before the statement body is executed and exited when the statement ends.

The *context management protocol* consists of a pair of methods that need to be provided for a context manager object to define a runtime context:

`contextmanager.__enter__()`

실행시간 컨텍스트에 진입하고 이 객체 자신이나 실행 시간 컨텍스트와 관련된 다른 객체를 돌려줍니다. 이 메서드가 돌려주는 값은, 이 컨텍스트 관리자를 사용하는 `with` 문의 `as` 절의 식별자에 연결됩니다.

An example of a context manager that returns itself is a file object. File objects return themselves from `__enter__()` to allow `open()` to be used as the context expression in a `with` statement.

관련 객체를 돌려주는 컨텍스트 관리자의 예는 `decimal.localcontext()` 가 돌려주는 것입니다. 이 관리자들은 활성 십진 소수 컨텍스트를 원래 십진 소수 컨텍스트의 복사본으로 설정한 다음 복사본을 돌려줍니다. 이것은 `with` 문 바깥의 코드에 영향을 주지 않으면서 `with` 문 바디에 있는 현재 십진 소수 컨텍스트를 변경할 수 있게 합니다.

`contextmanager.__exit__(exc_type, exc_val, exc_tb)`

실행 시간 컨텍스트를 탈출하고 발생한 예외를 막아야 하는지를 가리키는 논리 플래그를 돌려줍니다. `with` 문의 바디를 실행하는 동안 예외가 발생하면, 인자에 예외 형, 값 및 추적 정보가 포함됩니다. 그렇지 않으면, 세 가지 인자 모두 `None` 입니다.

이 메서드에서 참 값을 돌려주면 `with` 문이 예외를 막고 `with` 문 바로 뒤에 오는 문장에서 계속 실행됩니다. 그 이외의 경우, 이 메서드의 실행이 완료된 후에 예외는 계속 퍼집니다. 이 메서드의 실행 중에 발생하는 예외는 `with` 문의 바디에서 발생한 모든 예외를 대체합니다.

The exception passed in should never be reraised explicitly - instead, this method should return a false value to indicate that the method completed successfully and does not want to suppress the raised exception. This allows context management code (such as `contextlib.nested`) to easily detect whether or not an `__exit__()` method has actually failed.

파이썬은 쉬운 스레드 동기화, 파일이나 다른 객체의 신속한 닫기, 그리고 활성 십진 소수 산술 컨텍스트의 보다 간단한 조작을 지원하기 위해 몇 가지 컨텍스트 관리자를 정의합니다. 컨텍스트 관리 프로토콜의 구현을 넘어 구체적인 형은 특별히 취급되지 않습니다. 몇 가지 예제는 `contextlib` 모듈을 보십시오.

Python's *generators* and the `contextlib.contextmanager` *decorator* provide a convenient way to implement these protocols. If a generator function is decorated with the `contextlib.contextmanager` decorator, it will return a context manager implementing the necessary `__enter__()` and `__exit__()` methods, rather than the iterator produced by an undecorated generator function.

파이썬/C API의 파이썬 객체에 대한 형 구조체에는 이러한 메서드들을 위해 준비된 슬롯이 없다는 점에 유의하십시오. 이러한 메서드를 정의하고자 하는 확장형은 일반적인 파이썬 액세스가 가능한 메서드로 제공해야 합니다. 실행 시간 컨텍스트를 설정하는 오버헤드와 비교할 때 한 번의 클래스 디서너리 조회의 오버헤드는 무시할 수 있습니다.

5.12 기타 내장형

인터프리터는 여러 가지 다른 객체를 지원합니다. 이것들 대부분은 한두 가지 연산만 지원합니다.

5.12.1 모듈

모듈에 대한 유일한 특별한 연산은 어트리뷰트 액세스입니다: `m.name`. 여기서 `m` 은 모듈이고 `name` 은 `m` 의 심볼 테이블에 정의된 이름에 액세스합니다. 모듈 어트리뷰트는 대입할 수 있습니다. (`import` 문은 엄밀히 말하면 모듈 객체에 대한 연산이 아닙니다; `import foo` 는 `foo` 라는 이름의 모듈 객체가 존재할 것을 요구하지 않고, 어딘가에 있는 `foo` 라는 이름의 (외부) 정의 를 요구합니다.

모든 모듈의 특수 어트리뷰트는 `__dict__` 입니다. 이것은 모듈의 심볼 테이블을 저장하는 딕셔너리입니다. 이 딕셔너리를 수정하면 모듈의 심볼 테이블이 실제로 변경되지만, `__dict__` 어트리뷰트에 대한 직접 대입은 불가능합니다 (`m.__dict__['a'] = 1` 라고 쓸 수 있고, `m.a` 가 1 이 되지만, `m.__dict__ = {}` 라고 쓸 수는 없습니다). `__dict__` 의 직접적인 수정은 추천하지 않습니다.

인터프리터에 내장된 모듈은 다음과 같이 쓰입니다: `<module 'sys' (built-in)>`. 파일에서 로드되면, `<module 'os' from '/usr/local/lib/pythonX.Y/os.pyc'>` 처럼 쓰입니다.

5.12.2 클래스와 클래스 인스턴스

여기에 대해서는 objects와 class를 참조하세요.

5.12.3 함수

함수 객체는 함수 정의로 만들어집니다. 함수 객체에 대한 유일한 연산은 호출하는 것입니다: `func(argument-list)`.

함수 객체에는 내장 함수와 사용자 정의 함수라는 두 가지 종류가 있습니다. 두 함수 모두 같은 연산(함수 호출)을 지원하지만, 구현이 다르므로 서로 다른 객체 형입니다.

자세한 정보는 `function`을 보십시오.

5.12.4 메서드

메서드는 어트리뷰트 표기법을 사용하여 호출되는 함수입니다. 두 가지 종류가 있습니다: 내장 메서드(리스트의 `append()` 같은 것들)와 클래스 인스턴스 메서드. 내장 메서드는 이를 지원하는 형에서 설명됩니다.

The implementation adds two special read-only attributes to class instance methods: `m.im_self` is the object on which the method operates, and `m.im_func` is the function implementing the method. Calling `m(arg-1, arg-2, ..., arg-n)` is completely equivalent to calling `m.im_func(m.im_self, arg-1, arg-2, ..., arg-n)`.

Class instance methods are either *bound* or *unbound*, referring to whether the method was accessed through an instance or a class, respectively. When a method is unbound, its `im_self` attribute will be `None` and if called, an explicit `self` object must be passed as the first argument. In this case, `self` must be an instance of the unbound method's class (or a subclass of that class), otherwise a `TypeError` is raised.

Like function objects, methods objects support getting arbitrary attributes. However, since method attributes are actually stored on the underlying function object (`meth.im_func`), setting method attributes on either bound or unbound methods is disallowed. Attempting to set an attribute on a method results in an `AttributeError` being raised. In order to set a method attribute, you need to explicitly set it on the underlying function object:

```
>>> class C:
...     def method(self):
...         pass
...
>>> c = C()
>>> c.method.whoami = 'my name is method' # can't set on the method
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
AttributeError: 'instancemethod' object has no attribute 'whoami'
>>> c.method.im_func.whoami = 'my name is method'
>>> c.method.whoami
'my name is method'
```

자세한 정보는 `types`를 보십시오.

5.12.5 코드 객체

Code objects are used by the implementation to represent 《pseudo-compiled》 executable Python code such as a function body. They differ from function objects because they don't contain a reference to their global execution environment. Code objects are returned by the built-in `compile()` function and can be extracted from function objects through their `func_code` attribute. See also the `code` module.

A code object can be executed or evaluated by passing it (instead of a source string) to the `exec` statement or the built-in `eval()` function.

자세한 정보는 `types`를 보십시오.

5.12.6 형 객체

형 객체는 다양한 객체 형을 나타냅니다. 객체의 형은 내장 함수 `type()`으로 액세스할 수 있습니다. 형에는 특별한 연산이 없습니다. 표준 모듈 `types`는 모든 표준 내장형의 이름을 정의합니다.

Types are written like this: `<type 'int'>`.

5.12.7 널 객체

This object is returned by functions that don't explicitly return a value. It supports no special operations. There is exactly one null object, named `None` (a built-in name).

`None` 이라고 씁니다.

5.12.8 Ellipsis 객체

This object is used by extended slice notation (see slicings). It supports no special operations. There is exactly one ellipsis object, named `Ellipsis` (a built-in name).

It is written as `Ellipsis`. When in a subscript, it can also be written as `...`, for example `seq[...]`.

5.12.9 NotImplemented 객체

This object is returned from comparisons and binary operations when they are asked to operate on types they don't support. See comparisons for more information.

`NotImplemented` 로 씁니다.

5.12.10 논리값

논리값은 두 개의 상수 객체인 `False`와 `True`입니다. 이것들은 논리값을 나타내기 위해 사용됩니다 (하지만 다른 값도 거짓 또는 참으로 간주 될 수 있습니다). 숫자 컨텍스트(예를 들어, 산술 연산자의 인자로 사용될 때)에서는 각각 정수 0과 1처럼 작동합니다. 내장 함수 `bool()`은 값이 논리값으로 해석될 수 있는 경우 모든 값을 논리값으로 변환하는 데 사용할 수 있습니다 (위의 논리값 검사 절을 참조하세요).

각각 `False`과 `True`로 씁니다.

5.12.11 내부 객체

여기에 관한 정보는 `types`를 참조하십시오. 스택 프레임 객체, 트레이스백 객체 및 슬라이스 객체에 대해 설명합니다.

5.13 특수 어트리뷰트

관련성이 있을 때, 구현은 몇 가지 객체 유형에 몇 가지 특수 읽기 전용 어트리뷰트를 추가합니다. 이 중 일부는 `dir()` 내장 함수에 의해 보고되지 않습니다.

`object.__dict__`

객체의 (쓰기 가능한) 어트리뷰트를 저장하는 데 사용되는 딕셔너리나 또는 기타 매핑 객체.

`object.__methods__`

버전 2.2부터 폐지: Use the built-in function `dir()` to get a list of an object's attributes. This attribute is no longer available.

`object.__members__`

버전 2.2부터 폐지: Use the built-in function `dir()` to get a list of an object's attributes. This attribute is no longer available.

`instance.__class__`

클래스 인스턴스가 속한 클래스.

`class.__bases__`

클래스 객체의 베이스 클래스들의 튜플.

`definition.__name__`

The name of the class, type, function, method, descriptor, or generator instance.

The following attributes are only supported by *new-style classes*.

`class.__mro__`

이 어트리뷰트는 메서드 결정 중에 베이스 클래스를 찾을 때 고려되는 클래스들의 튜플입니다.

`class.mro()`

이 메서드는 인스턴스의 메서드 결정 순서를 사용자 정의하기 위해 메타클래스가 재정의할 수 있습니다. 클래스 인스턴스를 만들 때 호출되며 그 결과는 `__mro__`에 저장됩니다.

`class.__subclasses__()`

Each new-style class keeps a list of weak references to its immediate subclasses. This method returns a list of all those references still alive. Example:

```
>>> int.__subclasses__()
[<type 'bool'>]
```

내장 예외

Exceptions should be class objects. The exceptions are defined in the module `exceptions`. This module never needs to be imported explicitly: the exceptions are provided in the built-in namespace as well as the `exceptions` module.

For class exceptions, in a `try` statement with an `except` clause that mentions a particular class, that clause also handles any exception classes derived from that class (but not exception classes from which *it* is derived). Two exception classes that are not related via subclassing are never equivalent, even if they have the same name.

The built-in exceptions listed below can be generated by the interpreter or built-in functions. Except where mentioned, they have an 《associated value》 indicating the detailed cause of the error. This may be a string or a tuple containing several items of information (e.g., an error code and a string explaining the code). The associated value is the second argument to the `raise` statement. If the exception class is derived from the standard root class `BaseException`, the associated value is present as the exception instance's `args` attribute.

사용자 코드는 내장 예외를 일으킬 수 있습니다. 이것은 예외 처리기를 검사하거나 인터프리터가 같은 예외를 발생시키는 상황과 《같은》 에러 조건을 보고하는 데 사용할 수 있습니다. 그러나 사용자 코드가 부적절한 에러를 발생시키는 것을 막을 방법이 없음을 유의하십시오.

내장 예외 클래스는 새 예외를 정의하기 위해 서브 클래스링 될 수 있습니다. `BaseException` 이 아니라 `Exception` 클래스 나 그 서브 클래스 중 하나에서 새로운 예외를 파생시킬 것을 권장합니다. 예외 정의에 대한 더 많은 정보는 파이썬 자습서의 `tut-userexceptions` 에 있습니다.

The following exceptions are only used as base classes for other exceptions.

exception `BaseException`

The base class for all built-in exceptions. It is not meant to be directly inherited by user-defined classes (for that, use `Exception`). If `str()` or `unicode()` is called on an instance of this class, the representation of the argument(s) to the instance are returned, or the empty string when there were no arguments.

버전 2.5에 추가.

args

The tuple of arguments given to the exception constructor. Some built-in exceptions (like `IOError`) expect a certain number of arguments and assign a special meaning to the elements of this tuple, while others are usually called only with a single string giving an error message.

exception Exception

모든 시스템 종료 외의 내장 예외는 이 클래스 파생됩니다. 모든 사용자 정의 예외도 이 클래스에서 파생되어야 합니다.

버전 2.5에서 변경: Changed to inherit from *BaseException*.

exception StandardError

The base class for all built-in exceptions except *StopIteration*, *GeneratorExit*, *KeyboardInterrupt* and *SystemExit*. *StandardError* itself is derived from *Exception*.

exception ArithmeticError

다양한 산술 예러가 일으키는 내장 예외들의 베이스 클래스: *OverflowError*, *ZeroDivisionError*, *FloatingPointError*.

exception BufferError

버퍼 관련 연산을 수행할 수 없을 때 발생합니다.

exception LookupError

매핑 또는 시퀀스에 사용된 키 나 인덱스가 잘못되었을 때 발생하는 예외의 베이스 클래스: *IndexError*, *KeyError*. *codecs.lookup()* 은 이 예외를 직접 일으킬 수 있습니다.

exception EnvironmentError

The base class for exceptions that can occur outside the Python system: *IOError*, *OSError*. When exceptions of this type are created with a 2-tuple, the first item is available on the instance's *errno* attribute (it is assumed to be an error number), and the second item is available on the *strerror* attribute (it is usually the associated error message). The tuple itself is also available on the *args* attribute.

버전 1.5.2에 추가.

When an *EnvironmentError* exception is instantiated with a 3-tuple, the first two items are available as above, while the third item is available on the *filename* attribute. However, for backwards compatibility, the *args* attribute contains only a 2-tuple of the first two constructor arguments.

The *filename* attribute is *None* when this exception is created with other than 3 arguments. The *errno* and *strerror* attributes are also *None* when the instance was created with other than 2 or 3 arguments. In this last case, *args* contains the verbatim constructor arguments as a tuple.

The following exceptions are the exceptions that are actually raised.

exception AssertionError

assert 문이 실패할 때 발생합니다.

exception AttributeError

어트리뷰트 참조 (attribute-references를 보세요) 나 대입이 실패할 때 발생합니다. (객체가 어트리뷰트 참조나 어트리뷰트 대입을 아예 지원하지 않으면 *TypeError* 가 발생합니다.)

exception EOFError

Raised when one of the built-in functions (*input()* or *raw_input()*) hits an end-of-file condition (EOF) without reading any data. (N.B.: the *file.read()* and *file.readline()* methods return an empty string when they hit EOF.)

exception FloatingPointError

부동 소수점 연산이 실패할 때 발생합니다. 이 예외는 항상 정의되어 있지만, 파이썬이 *--with-fpectl* 옵션으로 설정되었거나, *WANT_SIGFPE_HANDLER* 심볼이 *pyconfig.h* 파일에 정의되어 있을 때만 발생합니다.

exception GeneratorExit

Raised when a *generator*'s *close()* method is called. It directly inherits from *BaseException* instead of *StandardError* since it is technically not an error.

버전 2.5에 추가.

버전 2.6에서 변경: Changed to inherit from *BaseException*.

exception IOError

Raised when an I/O operation (such as a `print` statement, the built-in `open()` function or a method of a file object) fails for an I/O-related reason, e.g., `«file not found»` or `«disk full»`.

This class is derived from *EnvironmentError*. See the discussion above for more information on exception instance attributes.

버전 2.6에서 변경: Changed `socket.error` to use this as a base class.

exception ImportError

Raised when an `import` statement fails to find the module definition or when a `from ... import` fails to find a name that is to be imported.

exception IndexError

Raised when a sequence subscript is out of range. (Slice indices are silently truncated to fall in the allowed range; if an index is not a plain integer, *TypeError* is raised.)

exception KeyError

매핑 (딕셔너리) 키가 기존 키 집합에서 발견되지 않을 때 발생합니다.

exception KeyboardInterrupt

Raised when the user hits the interrupt key (normally `Control-C` or `Delete`). During execution, a check for interrupts is made regularly. Interrupts typed when a built-in function `input()` or `raw_input()` is waiting for input also raise this exception. The exception inherits from *BaseException* so as to not be accidentally caught by code that catches *Exception* and thus prevent the interpreter from exiting.

버전 2.5에서 변경: Changed to inherit from *BaseException*.

exception MemoryError

작업에 메모리가 부족하지만, 상황이 여전히 (일부 객체를 삭제해서) 복구될 수 있는 경우 발생합니다. 연관된 값은 어떤 종류의 (내부) 연산이 메모리를 다 써 버렸는지를 나타내는 문자열입니다. 하부 메모리 관리 아키텍처(C의 `malloc()` 함수) 때문에, 인터프리터가 항상 이 상황을 완벽하게 복구할 수 있는 것은 아닙니다; 그런데도 통제를 벗어난 프로그램이 원인인 경우를 위해, 스택 트레이스백을 인쇄할 수 있도록 예외를 일으킵니다.

exception NameError

지역 또는 전역 이름을 찾을 수 없을 때 발생합니다. 이는 정규화되지 않은 이름에만 적용됩니다. 연관된 값은 찾을 수 없는 이름을 포함하는 예외 메시지입니다.

exception NotImplementedError

This exception is derived from *RuntimeError*. In user defined base classes, abstract methods should raise this exception when they require derived classes to override the method.

버전 1.5.2에 추가.

exception OSError

This exception is derived from *EnvironmentError*. It is raised when a function returns a system-related error (not for illegal argument types or other incidental errors). The `errno` attribute is a numeric error code from `errno`, and the `strerror` attribute is the corresponding string, as would be printed by the C function `perror()`. See the module `errno`, which contains names for the error codes defined by the underlying operating system.

For exceptions that involve a file system path (such as `chdir()` or `unlink()`), the exception instance will contain a third attribute, `filename`, which is the file name passed to the function.

버전 1.5.2에 추가.

exception OverflowError

Raised when the result of an arithmetic operation is too large to be represented. This cannot occur for long integers (which would rather raise *MemoryError* than give up) and for most operations with plain integers, which return a

long integer instead. Because of the lack of standardization of floating point exception handling in C, most floating point operations also aren't checked.

exception ReferenceError

이 예외는 `weakref.proxy()` 함수가 만든 약한 참조 프락시가 이미 가비지 수집된 참조 대상의 어트리뷰트를 액세스하는 데 사용될 때 발생합니다. 약한 참조에 대한 더 자세한 정보는 `weakref` 모듈을 보십시오.

버전 2.2에 추가: Previously known as the `weakref.ReferenceError` exception.

exception RuntimeError

다른 범주에 속하지 않는 예외가 감지될 때 발생합니다. 연관된 값은 정확히 무엇이 잘못되었는지를 나타내는 문자열입니다.

exception StopIteration

Raised by an `iterator`'s `next()` method to signal that there are no further values. This is derived from `Exception` rather than `StandardError`, since this is not considered an error in its normal application.

버전 2.2에 추가.

exception SyntaxError

Raised when the parser encounters a syntax error. This may occur in an `import` statement, in an `exec` statement, in a call to the built-in function `eval()` or `input()`, or when reading the initial script or standard input (also interactively).

세부 사항을 쉽게 확인할 수 있도록, 이 클래스의 인스턴스에는 `filename`, `lineno`, `offset` 및 `text` 어트리뷰트가 있습니다. 예외 인스턴스의 `str()`은 메시지만 돌려줍니다.

exception IndentationError

잘못된 들여쓰기와 관련된 문법 오류의 베이스 클래스입니다. `SyntaxError`의 서브 클래스입니다.

exception TabError

들여쓰기가 일관성없는 탭과 스페이스 사용을 포함하는 경우 발생합니다. `IndentationError`의 서브 클래스입니다.

exception SystemError

인터프리터가 내부 에러를 발견했지만, 모든 희망을 포기할 만큼 상황이 심각해 보이지는 않을 때 발생합니다. 연관된 값은 무엇이 잘못되었는지 (저수준의 용어로) 나타내는 문자열입니다.

이것을 파이썬 인터프리터의 저자 또는 관리자에게 알려야 합니다. 파이썬 인터프리터의 버전 (`sys.version`; 대화식 파이썬 세션의 시작 부분에도 출력됩니다), 정확한 에러 메시지 (예외의 연관된 값) 그리고 가능하다면 에러를 일으킨 프로그램의 소스를 제공해 주십시오.

exception SystemExit

This exception is raised by the `sys.exit()` function. When it is not handled, the Python interpreter exits; no stack traceback is printed. If the associated value is a plain integer, it specifies the system exit status (passed to C's `exit()` function); if it is `None`, the exit status is zero; if it has another type (such as a string), the object's value is printed and the exit status is one.

Instances have an attribute `code` which is set to the proposed exit status or error message (defaulting to `None`). Also, this exception derives directly from `BaseException` and not `StandardError`, since it is not technically an error.

`sys.exit()`에 대한 호출은 예외로 변환되어 뒷정리 처리기 (try 문의 `finally` 절)가 실행될 수 있도록 합니다. 그래서 디버거는 제어권을 잃을 위험 없이 스크립트를 실행할 수 있습니다. 즉시 종료가 절대적으로 필요한 경우에는 `os._exit()` 함수를 사용할 수 있습니다 (예를 들어, `os.fork()` 호출 후의 자식 프로세스에서).

The exception inherits from `BaseException` instead of `StandardError` or `Exception` so that it is not accidentally caught by code that catches `Exception`. This allows the exception to properly propagate up and cause the interpreter to exit.

버전 2.5에서 변경: Changed to inherit from *BaseException*.

exception TypeError

연산이나 함수가 부적절한 형의 객체에 적용될 때 발생합니다. 연관된 값은 형 불일치에 대한 세부 정보를 제공하는 문자열입니다.

exception UnboundLocalError

함수 나 메서드에서 지역 변수를 참조하지만, 해당 변수에 값이 연결되지 않으면 발생합니다. 이것은 *NameError* 의 서브 클래스입니다.

버전 2.0에 추가.

exception UnicodeError

유니코드 관련 인코딩 또는 디코딩 에러가 일어날 때 발생합니다. *ValueError* 의 서브 클래스입니다.

UnicodeError 는 인코딩이나 디코딩 에러를 설명하는 어트리뷰트를 가지고 있습니다. 예를 들어, `err.object[err.start:err.end]` 는 코텍이 실패한 잘못된 입력을 제공합니다.

encoding

에러를 발생시킨 인코딩의 이름입니다.

reason

구체적인 코텍 오류를 설명하는 문자열입니다.

object

코텍이 인코딩 또는 디코딩하려고 시도한 객체입니다.

start

object 에 있는 잘못된 데이터의 최초 인덱스입니다.

end

object 에 있는 마지막으로 잘못된 데이터의 바로 다음 인덱스입니다.

버전 2.0에 추가.

exception UnicodeEncodeError

인코딩 중에 유니코드 관련 에러가 일어나면 발생합니다. *UnicodeError* 의 서브 클래스입니다.

버전 2.3에 추가.

exception UnicodeDecodeError

디코딩 중에 유니코드 관련 에러가 일어나면 발생합니다. *UnicodeError* 의 서브 클래스입니다.

버전 2.3에 추가.

exception UnicodeTranslateError

번역 중에 유니코드 관련 에러가 일어나면 발생합니다. *UnicodeError* 의 서브 클래스입니다.

버전 2.3에 추가.

exception ValueError

Raised when an operation or function receives an argument that has the right type but an inappropriate value, and the situation is not described by a more precise exception such as *IndexError*.

exception VMSError

Only available on VMS. Raised when a VMS-specific error occurs.

exception WindowsError

Raised when a Windows-specific error occurs or when the error number does not correspond to an `errno` value. The `winerror` and `strerror` values are created from the return values of the `GetLastError()` and `FormatMessage()` functions from the Windows Platform API. The `errno` value maps the `winerror` value to corresponding `errno.h` values. This is a subclass of *OSError*.

버전 2.0에 추가.

버전 2.5에서 변경: Previous versions put the `GetLastError()` codes into *errno*.

exception ZeroDivisionError

나누기 또는 모듈로 연산의 두 번째 인자가 0일 때 발생합니다. 연관된 값은 피연산자의 형과 연산을 나타내는 문자열입니다.

다음 예외는 경고 범주로 사용됩니다; 자세한 정보는 *warnings* 모듈을 보십시오.

exception Warning

경고 범주의 베이스 클래스입니다.

exception UserWarning

사용자 코드에 의해 만들어지는 경고의 베이스 클래스입니다.

exception DeprecationWarning

폐지된 기능에 대한 경고의 베이스 클래스입니다.

exception PendingDeprecationWarning

장래에 폐지될 기능에 관한 경고의 베이스 클래스입니다.

exception SyntaxWarning

모호한 문법에 대한 경고의 베이스 클래스입니다.

exception RuntimeWarning

모호한 실행 시간 동작에 대한 경고의 베이스 클래스입니다.

exception FutureWarning

장래에 의미상으로 변경되는 구조물에 관한 경고의 베이스 클래스입니다.

exception ImportError

모듈 임포트에 있을 수 있는 실수에 대한 경고의 베이스 클래스입니다.

버전 2.5에 추가.

exception UnicodeWarning

유니코드와 관련된 경고의 베이스 클래스입니다.

버전 2.5에 추가.

exception BytesWarning

Base class for warnings related to bytes and bytearray.

버전 2.6에 추가.

6.1 예외 계층 구조

내장 예외의 클래스 계층 구조는 다음과 같습니다:

```
BaseException
+-- SystemExit
+-- KeyboardInterrupt
+-- GeneratorExit
+-- Exception
    +-- StopIteration
    +-- StandardError
        +-- BufferError
        +-- ArithmeticError
            +-- FloatingPointError
            +-- OverflowError
            +-- ZeroDivisionError
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

|   +-- AssertionError
|   +-- AttributeError
|   +-- EnvironmentError
|       |   +-- IOError
|       |   +-- OSError
|       |       +-- WindowsError (Windows)
|       |       +-- VMSError (VMS)
|   +-- EOFError
|   +-- ImportError
|   +-- LookupError
|       |   +-- IndexError
|       |   +-- KeyError
|   +-- MemoryError
|   +-- NameError
|       |   +-- UnboundLocalError
|   +-- ReferenceError
|   +-- RuntimeError
|       |   +-- NotImplementedError
|   +-- SyntaxError
|       |   +-- IndentationError
|       |   +-- TabError
|   +-- SystemError
|   +-- TypeError
|   +-- ValueError
|       |   +-- UnicodeError
|       |       +-- UnicodeDecodeError
|       |       +-- UnicodeEncodeError
|       |       +-- UnicodeTranslateError
+-- Warning
    +-- DeprecationWarning
    +-- PendingDeprecationWarning
    +-- RuntimeWarning
    +-- SyntaxWarning
    +-- UserWarning
    +-- FutureWarning
    +-- ImportWarning
    +-- UnicodeWarning
    +-- BytesWarning

```


The modules described in this chapter provide a wide range of string manipulation operations.

In addition, Python's built-in string classes support the sequence type methods described in the *Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange* section, and also the string-specific methods described in the *문자열 메서드* section. To output formatted strings use template strings or the `%` operator described in the *String Formatting Operations* section. Also, see the *re* module for string functions based on regular expressions.

7.1 string — Common string operations

Source code: [Lib/string.py](#)

The *string* module contains a number of useful constants and classes, as well as some deprecated legacy functions that are also available as methods on strings. In addition, Python's built-in string classes support the sequence type methods described in the *Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange* section, and also the string-specific methods described in the *문자열 메서드* section. To output formatted strings use template strings or the `%` operator described in the *String Formatting Operations* section. Also, see the *re* module for string functions based on regular expressions.

7.1.1 String constants

The constants defined in this module are:

`string.ascii_letters`

The concatenation of the *ascii_lowercase* and *ascii_uppercase* constants described below. This value is not locale-dependent.

`string.ascii_lowercase`

The lowercase letters `'abcdefghijklmnopqrstuvwxyz'`. This value is not locale-dependent and will not change.

string.ascii_uppercase

The uppercase letters 'ABCDEFGHIJKLMNOPQRSTUVWXYZ'. This value is not locale-dependent and will not change.

string.digits

The string '0123456789'.

string.hexdigits

The string '0123456789abcdefABCDEF'.

string.letters

The concatenation of the strings *lowercase* and *uppercase* described below. The specific value is locale-dependent, and will be updated when *locale.setlocale()* is called.

string.lowercase

A string containing all the characters that are considered lowercase letters. On most systems this is the string 'abcdefghijklmnopqrstuvwxyz'. The specific value is locale-dependent, and will be updated when *locale.setlocale()* is called.

string.octdigits

The string '01234567'.

string.punctuation

String of ASCII characters which are considered punctuation characters in the C locale.

string.printable

String of characters which are considered printable. This is a combination of *digits*, *letters*, *punctuation*, and *whitespace*.

string.uppercase

A string containing all the characters that are considered uppercase letters. On most systems this is the string 'ABCDEFGHIJKLMNOPQRSTUVWXYZ'. The specific value is locale-dependent, and will be updated when *locale.setlocale()* is called.

string.whitespace

A string containing all characters that are considered whitespace. On most systems this includes the characters space, tab, linefeed, return, formfeed, and vertical tab.

7.1.2 Custom String Formatting

버전 2.6에 추가.

The built-in str and unicode classes provide the ability to do complex variable substitutions and value formatting via the *str.format()* method described in **PEP 3101**. The *Formatter* class in the *string* module allows you to create and customize your own string formatting behaviors using the same implementation as the built-in *format()* method.

class string.Formatter

The *Formatter* class has the following public methods:

format (*format_string*, **args*, ***kwargs*)

The primary API method. It takes a format string and an arbitrary set of positional and keyword arguments. It is just a wrapper that calls *vformat()*.

vformat (*format_string*, *args*, *kwargs*)

This function does the actual work of formatting. It is exposed as a separate function for cases where you want to pass in a predefined dictionary of arguments, rather than unpacking and repacking the dictionary as individual arguments using the **args* and ***kwargs* syntax. *vformat()* does the work of breaking up the format string into character data and replacement fields. It calls the various methods described below.

In addition, the *Formatter* defines a number of methods that are intended to be replaced by subclasses:

parse (*format_string*)

Loop over the *format_string* and return an iterable of tuples (*literal_text*, *field_name*, *format_spec*, *conversion*). This is used by *vformat()* to break the string into either literal text, or replacement fields.

The values in the tuple conceptually represent a span of literal text followed by a single replacement field. If there is no literal text (which can happen if two replacement fields occur consecutively), then *literal_text* will be a zero-length string. If there is no replacement field, then the values of *field_name*, *format_spec* and *conversion* will be *None*.

get_field (*field_name*, *args*, *kwargs*)

Given *field_name* as returned by *parse()* (see above), convert it to an object to be formatted. Returns a tuple (obj, *used_key*). The default version takes strings of the form defined in **PEP 3101**, such as `<0[name]>` or `<label.title>`. *args* and *kwargs* are as passed in to *vformat()*. The return value *used_key* has the same meaning as the *key* parameter to *get_value()*.

get_value (*key*, *args*, *kwargs*)

Retrieve a given field value. The *key* argument will be either an integer or a string. If it is an integer, it represents the index of the positional argument in *args*; if it is a string, then it represents a named argument in *kwargs*.

The *args* parameter is set to the list of positional arguments to *vformat()*, and the *kwargs* parameter is set to the dictionary of keyword arguments.

For compound field names, these functions are only called for the first component of the field name; Subsequent components are handled through normal attribute and indexing operations.

So for example, the field expression `<0.name>` would cause *get_value()* to be called with a *key* argument of 0. The `name` attribute will be looked up after *get_value()* returns by calling the built-in *getattr()* function.

If the index or keyword refers to an item that does not exist, then an *IndexError* or *KeyError* should be raised.

check_unused_args (*used_args*, *args*, *kwargs*)

Implement checking for unused arguments if desired. The arguments to this function is the set of all argument keys that were actually referred to in the format string (integers for positional arguments, and strings for named arguments), and a reference to the *args* and *kwargs* that was passed to *vformat*. The set of unused args can be calculated from these parameters. *check_unused_args()* is assumed to raise an exception if the check fails.

format_field (*value*, *format_spec*)

format_field() simply calls the global *format()* built-in. The method is provided so that subclasses can override it.

convert_field (*value*, *conversion*)

Converts the value (returned by *get_field()*) given a conversion type (as in the tuple returned by the *parse()* method). The default version understands `<s>` (str), `<r>` (repr) and `<a>` (ascii) conversion types.

7.1.3 Format String Syntax

The *str.format()* method and the *Formatter* class share the same syntax for format strings (although in the case of *Formatter*, subclasses can define their own format string syntax).

Format strings contain `<replacement fields>` surrounded by curly braces `{ }`. Anything that is not contained in braces is considered literal text, which is copied unchanged to the output. If you need to include a brace character in the literal text, it can be escaped by doubling: `{{` and `}}`.

The grammar for a replacement field is as follows:

```

replacement_field ::= "{" [field_name] ["!" conversion] [":" format_spec] "}"
field_name         ::= arg_name ("." attribute_name | "[" element_index "]")*
arg_name           ::= [identifier | integer]
attribute_name     ::= identifier
element_index      ::= integer | index_string
index_string       ::= <any source character except "]"> +
conversion         ::= "r" | "s"
format_spec        ::= <described in the next section>

```

In less formal terms, the replacement field can start with a *field_name* that specifies the object whose value is to be formatted and inserted into the output instead of the replacement field. The *field_name* is optionally followed by a *conversion* field, which is preceded by an exclamation point '!', and a *format_spec*, which is preceded by a colon ':'. These specify a non-default format for the replacement value.

See also the *Format Specification Mini-Language* section.

The *field_name* itself begins with an *arg_name* that is either a number or a keyword. If it's a number, it refers to a positional argument, and if it's a keyword, it refers to a named keyword argument. If the numerical *arg_names* in a format string are 0, 1, 2, ... in sequence, they can all be omitted (not just some) and the numbers 0, 1, 2, ... will be automatically inserted in that order. Because *arg_name* is not quote-delimited, it is not possible to specify arbitrary dictionary keys (e.g., the strings '10' or ':-]') within a format string. The *arg_name* can be followed by any number of index or attribute expressions. An expression of the form '.name' selects the named attribute using *getattr()*, while an expression of the form '[index]' does an index lookup using *__getitem__()*.

버전 2.7에서 변경: The positional argument specifiers can be omitted for *str.format()* and *unicode.format()*, so '{} {}' is equivalent to '{0} {1}', u'{} {}' is equivalent to u'{0} {1}'.

Some simple format string examples:

```

"First, thou shalt count to {0}" # References first positional argument
"Bring me a {}"                 # Implicitly references the first positional_
↪ argument
"From {} to {}"                 # Same as "From {0} to {1}"
"My quest is {name}"            # References keyword argument 'name'
"Weight in tons {0.weight}"     # 'weight' attribute of first positional arg
"Units destroyed: {players[0]}" # First element of keyword argument 'players'.

```

The *conversion* field causes a type coercion before formatting. Normally, the job of formatting a value is done by the *__format__()* method of the value itself. However, in some cases it is desirable to force a type to be formatted as a string, overriding its own definition of formatting. By converting the value to a string before calling *__format__()*, the normal formatting logic is bypassed.

Two conversion flags are currently supported: '!s' which calls *str()* on the value, and '!r' which calls *repr()*.

Some examples:

```

"Harold's a clever {0!s}"        # Calls str() on the argument first
"Bring out the holy {name!r}"    # Calls repr() on the argument first

```

The *format_spec* field contains a specification of how the value should be presented, including such details as field width, alignment, padding, decimal precision and so on. Each value type can define its own 《formatting mini-language》 or interpretation of the *format_spec*.

Most built-in types support a common formatting mini-language, which is described in the next section.

A *format_spec* field can also include nested replacement fields within it. These nested replacement fields may contain a field name, conversion flag and format specification, but deeper nesting is not allowed. The replacement fields within

the `format_spec` are substituted before the `format_spec` string is interpreted. This allows the formatting of a value to be dynamically specified.

See the [Format examples](#) section for some examples.

Format Specification Mini-Language

《Format specifications》are used within replacement fields contained within a format string to define how individual values are presented (see [Format String Syntax](#)). They can also be passed directly to the built-in `format()` function. Each formattable type may define how the format specification is to be interpreted.

Most built-in types implement the following options for format specifications, although some of the formatting options are only supported by the numeric types.

A general convention is that an empty format string (`" "`) produces the same result as if you had called `str()` on the value. A non-empty format string typically modifies the result.

The general form of a *standard format specifier* is:

```
format_spec ::=  [[fill]align][sign][#][0][width][,][.precision][type]
fill         ::=  <any character>
align        ::=  "<" | ">" | "=" | "^"
sign         ::=  "+" | "-" | " "
width        ::=  integer
precision    ::=  integer
type         ::=  "b" | "c" | "d" | "e" | "E" | "f" | "F" | "g" | "G" | "n" | "o" | "s" |
```

If a valid *align* value is specified, it can be preceded by a *fill* character that can be any character and defaults to a space if omitted. It is not possible to use a literal curly brace (`<{>` or `<}>`) as the *fill* character when using the `str.format()` method. However, it is possible to insert a curly brace with a nested replacement field. This limitation doesn't affect the `format()` function.

The meaning of the various alignment options is as follows:

Op- tion	Meaning
'<'	Forces the field to be left-aligned within the available space (this is the default for most objects).
'>'	Forces the field to be right-aligned within the available space (this is the default for numbers).
'='	Forces the padding to be placed after the sign (if any) but before the digits. This is used for printing fields in the form <code><+000000120></code> . This alignment option is only valid for numeric types. It becomes the default when <code><0></code> immediately precedes the field width.
'^'	Forces the field to be centered within the available space.

Note that unless a minimum field width is defined, the field width will always be the same size as the data to fill it, so that the alignment option has no meaning in this case.

The *sign* option is only valid for number types, and can be one of the following:

Op- tion	Meaning
'+'	indicates that a sign should be used for both positive as well as negative numbers.
'-'	indicates that a sign should be used only for negative numbers (this is the default behavior).
space	indicates that a leading space should be used on positive numbers, and a minus sign on negative numbers.

The '#' option is only valid for integers, and only for binary, octal, or hexadecimal output. If present, it specifies that the output will be prefixed by '0b', '0o', or '0x', respectively.

The ',' option signals the use of a comma for a thousands separator. For a locale aware separator, use the 'n' integer presentation type instead.

버전 2.7에서 변경: Added the ',' option (see also [PEP 378](#)).

width is a decimal integer defining the minimum field width. If not specified, then the field width will be determined by the content.

When no explicit alignment is given, preceding the *width* field by a zero ('0') character enables sign-aware zero-padding for numeric types. This is equivalent to a *fill* character of '0' with an *alignment* type of '='.

The *precision* is a decimal number indicating how many digits should be displayed after the decimal point for a floating point value formatted with 'f' and 'F', or before and after the decimal point for a floating point value formatted with 'g' or 'G'. For non-number types the field indicates the maximum field size - in other words, how many characters will be used from the field content. The *precision* is not allowed for integer values.

Finally, the *type* determines how the data should be presented.

The available string presentation types are:

Type	Meaning
's'	String format. This is the default type for strings and may be omitted.
None	The same as 's'.

The available integer presentation types are:

Type	Meaning
'b'	Binary format. Outputs the number in base 2.
'c'	Character. Converts the integer to the corresponding unicode character before printing.
'd'	Decimal Integer. Outputs the number in base 10.
'o'	Octal format. Outputs the number in base 8.
'x'	Hex format. Outputs the number in base 16, using lower- case letters for the digits above 9.
'X'	Hex format. Outputs the number in base 16, using upper- case letters for the digits above 9.
'n'	Number. This is the same as 'd', except that it uses the current locale setting to insert the appropriate number separator characters.
None	The same as 'd'.

In addition to the above presentation types, integers can be formatted with the floating point presentation types listed below (except 'n' and None). When doing so, `float()` is used to convert the integer to a floating point number before formatting.

The available presentation types for floating point and decimal values are:

Type	Meaning
'e'	Exponent notation. Prints the number in scientific notation using the letter <e> to indicate the exponent. The default precision is 6.
'E'	Exponent notation. Same as 'e' except it uses an upper case <E> as the separator character.
'f'	Fixed-point notation. Displays the number as a fixed-point number. The default precision is 6.
'F'	Fixed point notation. Same as 'f'.
'g'	General format. For a given precision $p \geq 1$, this rounds the number to p significant digits and then formats the result in either fixed-point format or in scientific notation, depending on its magnitude. The precise rules are as follows: suppose that the result formatted with presentation type 'e' and precision $p-1$ would have exponent exp . Then if $-4 \leq exp < p$, the number is formatted with presentation type 'f' and precision $p-1-exp$. Otherwise, the number is formatted with presentation type 'e' and precision $p-1$. In both cases insignificant trailing zeros are removed from the significand, and the decimal point is also removed if there are no remaining digits following it. Positive and negative infinity, positive and negative zero, and nans, are formatted as <code>inf</code> , <code>-inf</code> , <code>0</code> , <code>-0</code> and <code>nan</code> respectively, regardless of the precision. A precision of 0 is treated as equivalent to a precision of 1. The default precision is 6.
'G'	General format. Same as 'g' except switches to 'E' if the number gets too large. The representations of infinity and NaN are uppercased, too.
'n'	Number. This is the same as 'g', except that it uses the current locale setting to insert the appropriate number separator characters.
'%'	Percentage. Multiplies the number by 100 and displays in fixed ('f') format, followed by a percent sign.
None	The same as 'g'.

Format examples

This section contains examples of the `str.format()` syntax and comparison with the old %-formatting.

In most of the cases the syntax is similar to the old %-formatting, with the addition of the `{}` and with `:` used instead of `%`. For example, `'%03.2f'` can be translated to `'{:03.2f}'`.

The new format syntax also supports new and different options, shown in the following examples.

Accessing arguments by position:

```
>>> '{0}, {1}, {2}'.format('a', 'b', 'c')
'a, b, c'
>>> '{}, {}, {}'.format('a', 'b', 'c')    # 2.7+ only
'a, b, c'
>>> '{2}, {1}, {0}'.format('a', 'b', 'c')
'c, b, a'
>>> '{2}, {1}, {0}'.format(*'abc')         # unpacking argument sequence
'c, b, a'
>>> '{0}{1}{0}'.format('abra', 'cad')     # arguments' indices can be repeated
'abracadabra'
```

Accessing arguments by name:

```
>>> 'Coordinates: {latitude}, {longitude}'.format(latitude='37.24N', longitude='-115.
↳ 81W')
'Coordinates: 37.24N, -115.81W'
>>> coord = {'latitude': '37.24N', 'longitude': '-115.81W'}
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> 'Coordinates: {latitude}, {longitude}'.format(**coord)
'Coordinates: 37.24N, -115.81W'
```

Accessing arguments › attributes:

```
>>> c = 3-5j
>>> ('The complex number {0} is formed from the real part {0.real} '
... 'and the imaginary part {0.imag}.').format(c)
'The complex number (3-5j) is formed from the real part 3.0 and the imaginary part -5.
↪0.'
>>> class Point(object):
...     def __init__(self, x, y):
...         self.x, self.y = x, y
...     def __str__(self):
...         return 'Point({self.x}, {self.y})'.format(self=self)
...
>>> str(Point(4, 2))
'Point(4, 2)'
```

Accessing arguments › items:

```
>>> coord = (3, 5)
>>> 'X: {0[0]}; Y: {0[1]}'.format(coord)
'X: 3; Y: 5'
```

Replacing %s and %r:

```
>>> "repr() shows quotes: {!r}; str() doesn't: {!s}".format('test1', 'test2')
'repr() shows quotes: 'test1'; str() doesn't: test2'
```

Aligning the text and specifying a width:

```
>>> '{:<30}'.format('left aligned')
'left aligned'
>>> '{:>30}'.format('right aligned')
'right aligned'
>>> '{:^30}'.format('centered')
'centered'
>>> '{:*^30}'.format('centered') # use '*' as a fill char
'*****centered*****'
```

Replacing %+f, %-f, and % f and specifying a sign:

```
>>> '{:+f}; {:+f}'.format(3.14, -3.14) # show it always
'+3.140000; -3.140000'
>>> '{: f}; {: f}'.format(3.14, -3.14) # show a space for positive numbers
' 3.140000; -3.140000'
>>> '{:-f}; {-f}'.format(3.14, -3.14) # show only the minus -- same as '{:f}; {:f}'
'3.140000; -3.140000'
```

Replacing %x and %o and converting the value to different bases:

```
>>> # format also supports binary numbers
>>> "int: {0:d}; hex: {0:x}; oct: {0:o}; bin: {0:b}".format(42)
'int: 42; hex: 2a; oct: 52; bin: 101010'
>>> # with 0x, 0o, or 0b as prefix:
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> "int: {0:d}; hex: {0:#x}; oct: {0:#o}; bin: {0:#b}".format(42)
'int: 42; hex: 0x2a; oct: 0o52; bin: 0b101010'
```

Using the comma as a thousands separator:

```
>>> '{:,}'.format(1234567890)
'1,234,567,890'
```

Expressing a percentage:

```
>>> points = 19.5
>>> total = 22
>>> 'Correct answers: {:.2%}'.format(points/total)
'Correct answers: 88.64%'
```

Using type-specific formatting:

```
>>> import datetime
>>> d = datetime.datetime(2010, 7, 4, 12, 15, 58)
>>> '{:%Y-%m-%d %H:%M:%S}'.format(d)
'2010-07-04 12:15:58'
```

Nesting arguments and more complex examples:

```
>>> for align, text in zip('<^>', ['left', 'center', 'right']):
...     '{0:{fill}{align}16}'.format(text, fill=align, align=align)
...
'left<<<<<<<<<<'
'^^^^^center^^^^^'
'>>>>>>>>>>right'
>>>
>>> octets = [192, 168, 0, 1]
>>> '{:02X}{:02X}{:02X}{:02X}'.format(*octets)
'COA80001'
>>> int(_, 16)
3232235521
>>>
>>> width = 5
>>> for num in range(5,12):
...     for base in 'dXob':
...         print '{0:{width}{base}}'.format(num, base=base, width=width),
...         print
...
5      5      5      101
6      6      6      110
7      7      7      111
8      8      10     1000
9      9      11     1001
10     A      12     1010
11     B      13     1011
```

7.1.4 Template strings

버전 2.4에 추가.

Templates provide simpler string substitutions as described in [PEP 292](#). Instead of the normal %-based substitutions, Templates support \$-based substitutions, using the following rules:

- `$$` is an escape; it is replaced with a single `$`.
- `$identifier` names a substitution placeholder matching a mapping key of `"identifier"`. By default, `"identifier"` must spell a Python identifier. The first non-identifier character after the `$` character terminates this placeholder specification.
- `${identifier}` is equivalent to `$identifier`. It is required when valid identifier characters follow the placeholder but are not part of the placeholder, such as `"${noun}ification"`.

Any other appearance of `$` in the string will result in a `ValueError` being raised.

The `string` module provides a `Template` class that implements these rules. The methods of `Template` are:

class `string.Template(template)`

The constructor takes a single argument which is the template string.

substitute(mapping[, **kws])

Performs the template substitution, returning a new string. `mapping` is any dictionary-like object with keys that match the placeholders in the template. Alternatively, you can provide keyword arguments, where the keywords are the placeholders. When both `mapping` and `kws` are given and there are duplicates, the placeholders from `kws` take precedence.

safe_substitute(mapping[, **kws])

Like `substitute()`, except that if placeholders are missing from `mapping` and `kws`, instead of raising a `KeyError` exception, the original placeholder will appear in the resulting string intact. Also, unlike with `substitute()`, any other appearances of the `$` will simply return `$` instead of raising `ValueError`.

While other exceptions may still occur, this method is called 《safe》 because it always tries to return a usable string instead of raising an exception. In another sense, `safe_substitute()` may be anything other than safe, since it will silently ignore malformed templates containing dangling delimiters, unmatched braces, or placeholders that are not valid Python identifiers.

`Template` instances also provide one public data attribute:

template

This is the object passed to the constructor's `template` argument. In general, you shouldn't change it, but read-only access is not enforced.

Here is an example of how to use a `Template`:

```
>>> from string import Template
>>> s = Template('$who likes $what')
>>> s.substitute(who='tim', what='kung pao')
'tim likes kung pao'
>>> d = dict(who='tim')
>>> Template('Give $who $100').substitute(d)
Traceback (most recent call last):
...
ValueError: Invalid placeholder in string: line 1, col 11
>>> Template('$who likes $what').substitute(d)
Traceback (most recent call last):
...
KeyError: 'what'
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> Template('$who likes $what').safe_substitute(d)
'tim likes $what'
```

Advanced usage: you can derive subclasses of `Template` to customize the placeholder syntax, delimiter character, or the entire regular expression used to parse template strings. To do this, you can override these class attributes:

- *delimiter* – This is the literal string describing a placeholder introducing delimiter. The default value is `$`. Note that this should *not* be a regular expression, as the implementation will call `re.escape()` on this string as needed.
- *idpattern* – This is the regular expression describing the pattern for non-braced placeholders (the braces will be added automatically as appropriate). The default value is the regular expression `[_a-z][_a-z0-9]*`.

Alternatively, you can provide the entire regular expression pattern by overriding the class attribute *pattern*. If you do this, the value must be a regular expression object with four named capturing groups. The capturing groups correspond to the rules given above, along with the invalid placeholder rule:

- *escaped* – This group matches the escape sequence, e.g. `$$`, in the default pattern.
- *named* – This group matches the unbraced placeholder name; it should not include the delimiter in capturing group.
- *braced* – This group matches the brace enclosed placeholder name; it should not include either the delimiter or braces in the capturing group.
- *invalid* – This group matches any other delimiter pattern (usually a single delimiter), and it should appear last in the regular expression.

7.1.5 String functions

The following functions are available to operate on string and Unicode objects. They are not available as string methods.

`string.capwords(s[, sep])`

Split the argument into words using `str.split()`, capitalize each word using `str.capitalize()`, and join the capitalized words using `str.join()`. If the optional second argument *sep* is absent or `None`, runs of whitespace characters are replaced by a single space and leading and trailing whitespace are removed, otherwise *sep* is used to split and join the words.

`string.maketrans(from, to)`

Return a translation table suitable for passing to `translate()`, that will map each character in *from* into the character at the same position in *to*; *from* and *to* must have the same length.

참고: Don't use strings derived from `lowercase` and `uppercase` as arguments; in some locales, these don't have the same length. For case conversions, always use `str.lower()` and `str.upper()`.

7.1.6 Deprecated string functions

The following list of functions are also defined as methods of string and Unicode objects; see section [문자열 메서드](#) for more information on those. You should consider these functions as deprecated, although they will not be removed until Python 3. The functions defined in this module are:

`string.atof(s)`

버전 2.0부터 폐지: Use the `float()` built-in function.

Convert a string to a floating point number. The string must have the standard syntax for a floating point literal in Python, optionally preceded by a sign (+ or -). Note that this behaves identical to the built-in function `float()` when passed a string.

참고: When passing in a string, values for NaN and Infinity may be returned, depending on the underlying C library. The specific set of strings accepted which cause these values to be returned depends entirely on the C library and is known to vary.

`string.atoi(s[, base])`

버전 2.0부터 폐지: Use the `int()` built-in function.

Convert string *s* to an integer in the given *base*. The string must consist of one or more digits, optionally preceded by a sign (+ or -). The *base* defaults to 10. If it is 0, a default base is chosen depending on the leading characters of the string (after stripping the sign): 0x or 0X means 16, 0 means 8, anything else means 10. If *base* is 16, a leading 0x or 0X is always accepted, though not required. This behaves identically to the built-in function `int()` when passed a string. (Also note: for a more flexible interpretation of numeric literals, use the built-in function `eval()`.)

`string.atol(s[, base])`

버전 2.0부터 폐지: Use the `long()` built-in function.

Convert string *s* to a long integer in the given *base*. The string must consist of one or more digits, optionally preceded by a sign (+ or -). The *base* argument has the same meaning as for `atoi()`. A trailing l or L is not allowed, except if the base is 0. Note that when invoked without *base* or with *base* set to 10, this behaves identical to the built-in function `long()` when passed a string.

`string.capitalize(word)`

Return a copy of *word* with only its first character capitalized.

`string.expandtabs(s[, tabsize])`

Expand tabs in a string replacing them by one or more spaces, depending on the current column and the given tab size. The column number is reset to zero after each newline occurring in the string. This doesn't understand other non-printing characters or escape sequences. The tab size defaults to 8.

`string.find(s, sub[, start[, end]])`

Return the lowest index in *s* where the substring *sub* is found such that *sub* is wholly contained in *s*[*start*:*end*]. Return -1 on failure. Defaults for *start* and *end* and interpretation of negative values is the same as for slices.

`string.rfind(s, sub[, start[, end]])`

Like `find()` but find the highest index.

`string.index(s, sub[, start[, end]])`

Like `find()` but raise `ValueError` when the substring is not found.

`string.rindex(s, sub[, start[, end]])`

Like `rfind()` but raise `ValueError` when the substring is not found.

`string.count(s, sub[, start[, end]])`

Return the number of (non-overlapping) occurrences of substring *sub* in string *s*[*start*:*end*]. Defaults for *start* and *end* and interpretation of negative values are the same as for slices.

`string.lower(s)`

Return a copy of *s*, but with upper case letters converted to lower case.

`string.split(s[, sep[, maxsplit]])`

Return a list of the words of the string *s*. If the optional second argument *sep* is absent or `None`, the words are separated by arbitrary strings of whitespace characters (space, tab, newline, return, formfeed). If the second argument *sep* is present and not `None`, it specifies a string to be used as the word separator. The returned list will then have one more item than the number of non-overlapping occurrences of the separator in the string. If *maxsplit* is given, at most *maxsplit* number of splits occur, and the remainder of the string is returned as the final element of the list (thus, the list will have at most *maxsplit*+1 elements). If *maxsplit* is not specified or -1, then there is no limit on the number of splits (all possible splits are made).

The behavior of `split` on an empty string depends on the value of `sep`. If `sep` is not specified, or specified as `None`, the result will be an empty list. If `sep` is specified as any string, the result will be a list containing one element which is an empty string.

`string.rsplitleft(s[, sep[, maxsplit]])`

Return a list of the words of the string `s`, scanning `s` from the end. To all intents and purposes, the resulting list of words is the same as returned by `split()`, except when the optional third argument `maxsplit` is explicitly specified and nonzero. If `maxsplit` is given, at most `maxsplit` number of splits – the *rightmost* ones – occur, and the remainder of the string is returned as the first element of the list (thus, the list will have at most `maxsplit+1` elements).

버전 2.4에 추가.

`string.splitfields(s[, sep[, maxsplit]])`

This function behaves identically to `split()`. (In the past, `split()` was only used with one argument, while `splitfields()` was only used with two arguments.)

`string.join(words[, sep])`

Concatenate a list or tuple of words with intervening occurrences of `sep`. The default value for `sep` is a single space character. It is always true that `string.join(string.split(s, sep), sep)` equals `s`.

`string.joinfields(words[, sep])`

This function behaves identically to `join()`. (In the past, `join()` was only used with one argument, while `joinfields()` was only used with two arguments.) Note that there is no `joinfields()` method on string objects; use the `join()` method instead.

`string.lstrip(s[, chars])`

Return a copy of the string with leading characters removed. If `chars` is omitted or `None`, whitespace characters are removed. If given and not `None`, `chars` must be a string; the characters in the string will be stripped from the beginning of the string this method is called on.

버전 2.2.3에서 변경: The `chars` parameter was added. The `chars` parameter cannot be passed in earlier 2.2 versions.

`string.rstrip(s[, chars])`

Return a copy of the string with trailing characters removed. If `chars` is omitted or `None`, whitespace characters are removed. If given and not `None`, `chars` must be a string; the characters in the string will be stripped from the end of the string this method is called on.

버전 2.2.3에서 변경: The `chars` parameter was added. The `chars` parameter cannot be passed in earlier 2.2 versions.

`string.strip(s[, chars])`

Return a copy of the string with leading and trailing characters removed. If `chars` is omitted or `None`, whitespace characters are removed. If given and not `None`, `chars` must be a string; the characters in the string will be stripped from the both ends of the string this method is called on.

버전 2.2.3에서 변경: The `chars` parameter was added. The `chars` parameter cannot be passed in earlier 2.2 versions.

`string.swapcase(s)`

Return a copy of `s`, but with lower case letters converted to upper case and vice versa.

`string.translate(s, table[, deletechars])`

Delete all characters from `s` that are in `deletechars` (if present), and then translate the characters using `table`, which must be a 256-character string giving the translation for each character value, indexed by its ordinal. If `table` is `None`, then only the character deletion step is performed.

`string.upper(s)`

Return a copy of `s`, but with lower case letters converted to upper case.

`string.ljust(s, width[, fillchar])`

```
string.rjust(s, width[, fillchar])  
string.center(s, width[, fillchar])
```

These functions respectively left-justify, right-justify and center a string in a field of given width. They return a string that is at least *width* characters wide, created by padding the string *s* with the character *fillchar* (default is a space) until the given width on the right, left or both sides. The string is never truncated.

```
string.zfill(s, width)
```

Pad a numeric string *s* on the left with zero digits until the given *width* is reached. Strings starting with a sign are handled correctly.

```
string.replace(s, old, new[, maxreplace])
```

Return a copy of string *s* with all occurrences of substring *old* replaced by *new*. If the optional argument *maxreplace* is given, the first *maxreplace* occurrences are replaced.

7.2 re — Regular expression operations

This module provides regular expression matching operations similar to those found in Perl. Both patterns and strings to be searched can be Unicode strings as well as 8-bit strings.

Regular expressions use the backslash character ('\\') to indicate special forms or to allow special characters to be used without invoking their special meaning. This collides with Python's usage of the same character for the same purpose in string literals; for example, to match a literal backslash, one might have to write '\\\\' as the pattern string, because the regular expression must be \\, and each backslash must be expressed as \\ inside a regular Python string literal.

The solution is to use Python's raw string notation for regular expression patterns; backslashes are not handled in any special way in a string literal prefixed with 'r'. So r"\n" is a two-character string containing '\' and 'n', while "\n" is a one-character string containing a newline. Usually patterns will be expressed in Python code using this raw string notation.

It is important to note that most regular expression operations are available as module-level functions and *RegexObject* methods. The functions are shortcuts that don't require you to compile a regex object first, but miss some fine-tuning parameters.

더 보기:

The third-party *regex* module, which has an API compatible with the standard library *re* module, but offers additional functionality and a more thorough Unicode support.

7.2.1 Regular Expression Syntax

A regular expression (or RE) specifies a set of strings that matches it; the functions in this module let you check if a particular string matches a given regular expression (or if a given regular expression matches a particular string, which comes down to the same thing).

Regular expressions can be concatenated to form new regular expressions; if *A* and *B* are both regular expressions, then *AB* is also a regular expression. In general, if a string *p* matches *A* and another string *q* matches *B*, the string *pq* will match *AB*. This holds unless *A* or *B* contain low precedence operations; boundary conditions between *A* and *B*; or have numbered group references. Thus, complex expressions can easily be constructed from simpler primitive expressions like the ones described here. For details of the theory and implementation of regular expressions, consult the Friedl book referenced above, or almost any textbook about compiler construction.

A brief explanation of the format of regular expressions follows. For further information and a gentler presentation, consult the *regex-howto*.

Regular expressions can contain both special and ordinary characters. Most ordinary characters, like 'A', 'a', or '0', are the simplest regular expressions; they simply match themselves. You can concatenate ordinary characters, so *last*

matches the string 'last'. (In the rest of this section, we'll write RE's in this special style, usually without quotes, and strings to be matched 'in single quotes'.)

Some characters, like '|' or '(', are special. Special characters either stand for classes of ordinary characters, or affect how the regular expressions around them are interpreted. Regular expression pattern strings may not contain null bytes, but can specify the null byte using the `\number` notation, e.g., `'\x00'`.

Repetition qualifiers (`*`, `+`, `?`, `{m, n}`, etc) cannot be directly nested. This avoids ambiguity with the non-greedy modifier suffix `?`, and with other modifiers in other implementations. To apply a second repetition to an inner repetition, parentheses may be used. For example, the expression `(?:a{6})*` matches any multiple of six 'a' characters.

The special characters are:

- '.' (Dot.) In the default mode, this matches any character except a newline. If the `DOTALL` flag has been specified, this matches any character including a newline.
- '^' (Caret.) Matches the start of the string, and in `MULTILINE` mode also matches immediately after each newline.
- '\$' Matches the end of the string or just before the newline at the end of the string, and in `MULTILINE` mode also matches before a newline. `foo` matches both `<foo>` and `<foobar>`, while the regular expression `foo$` matches only `<foo>`. More interestingly, searching for `foo.$` in `'foo1\nfoo2\n'` matches `<foo2>` normally, but `<foo1>` in `MULTILINE` mode; searching for a single `$` in `'foo\n'` will find two (empty) matches: one just before the newline, and one at the end of the string.
- '*' Causes the resulting RE to match 0 or more repetitions of the preceding RE, as many repetitions as are possible. `ab*` will match `<a>`, `<ab>`, or `<a>` followed by any number of `<b's>`.
- '+' Causes the resulting RE to match 1 or more repetitions of the preceding RE. `ab+` will match `<a>` followed by any non-zero number of `<b's>`; it will not match just `<a>`.
- '?' Causes the resulting RE to match 0 or 1 repetitions of the preceding RE. `ab?` will match either `<a>` or `<ab>`.
- `*, +, ?` The `'*'`, `'+'`, and `'?'` qualifiers are all *greedy*; they match as much text as possible. Sometimes this behaviour isn't desired; if the RE `<.*>` is matched against `<a> b <c>`, it will match the entire string, and not just `<a>`. Adding `?` after the qualifier makes it perform the match in *non-greedy* or *minimal* fashion; as few characters as possible will be matched. Using the RE `<.*?>` will match only `<a>`.
- `{m}` Specifies that exactly *m* copies of the previous RE should be matched; fewer matches cause the entire RE not to match. For example, `a{6}` will match exactly six 'a' characters, but not five.
- `{m, n}` Causes the resulting RE to match from *m* to *n* repetitions of the preceding RE, attempting to match as many repetitions as possible. For example, `a{3, 5}` will match from 3 to 5 'a' characters. Omitting *m* specifies a lower bound of zero, and omitting *n* specifies an infinite upper bound. As an example, `a{4, }b` will match `aaaab` or a thousand 'a' characters followed by a `b`, but not `aaab`. The comma may not be omitted or the modifier would be confused with the previously described form.
- `{m, n}?` Causes the resulting RE to match from *m* to *n* repetitions of the preceding RE, attempting to match as few repetitions as possible. This is the non-greedy version of the previous qualifier. For example, on the 6-character string `'aaaaaa'`, `a{3, 5}` will match 5 'a' characters, while `a{3, 5}?` will only match 3 characters.
- '\' Either escapes special characters (permitting you to match characters like `'*'`, `'?'`, and so forth), or signals a special sequence; special sequences are discussed below.

If you're not using a raw string to express the pattern, remember that Python also uses the backslash as an escape sequence in string literals; if the escape sequence isn't recognized by Python's parser, the backslash and subsequent character are included in the resulting string. However, if Python would recognize the resulting sequence, the backslash should be repeated twice. This is complicated and hard to understand, so it's highly recommended that you use raw strings for all but the simplest expressions.

[] Used to indicate a set of characters. In a set:

- Characters can be listed individually, e.g. `[amk]` will match 'a', 'm', or 'k'.

- Ranges of characters can be indicated by giving two characters and separating them by a `'-'`, for example `[a-z]` will match any lowercase ASCII letter, `[0-5][0-9]` will match all the two-digits numbers from 00 to 59, and `[0-9A-Fa-f]` will match any hexadecimal digit. If `-` is escaped (e.g. `[a\ -z]`) or if it's placed as the first or last character (e.g. `[a-]`), it will match a literal `'-'`.
- Special characters lose their special meaning inside sets. For example, `[(+*)]` will match any of the literal characters `'('`, `'+'`, `'*'`, or `')'`.
- Character classes such as `\w` or `\S` (defined below) are also accepted inside a set, although the characters they match depends on whether *LOCALE* or *UNICODE* mode is in force.
- Characters that are not within a range can be matched by *complementing* the set. If the first character of the set is `'^'`, all the characters that are *not* in the set will be matched. For example, `[^5]` will match any character except `'5'`, and `[^^]` will match any character except `'^'`. `^` has no special meaning if it's not the first character in the set.
- To match a literal `' '` inside a set, precede it with a backslash, or place it at the beginning of the set. For example, both `[() \{ }]` and `[] () [{ }]` will both match a parenthesis.

`'|'` `A|B`, where `A` and `B` can be arbitrary REs, creates a regular expression that will match either `A` or `B`. An arbitrary number of REs can be separated by the `'|'` in this way. This can be used inside groups (see below) as well. As the target string is scanned, REs separated by `'|'` are tried from left to right. When one pattern completely matches, that branch is accepted. This means that once `A` matches, `B` will not be tested further, even if it would produce a longer overall match. In other words, the `'|'` operator is never greedy. To match a literal `'|'`, use `\|`, or enclose it inside a character class, as in `[|]`.

(...) Matches whatever regular expression is inside the parentheses, and indicates the start and end of a group; the contents of a group can be retrieved after a match has been performed, and can be matched later in the string with the `\number` special sequence, described below. To match the literals `'('` or `')'`, use `\(` or `\)`, or enclose them inside a character class: `[()]`.

(?...) This is an extension notation (a `'?'` following a `'('` is not meaningful otherwise). The first character after the `'?'` determines what the meaning and further syntax of the construct is. Extensions usually do not create a new group; `(?P<name>...)` is the only exception to this rule. Following are the currently supported extensions.

(?iLmsux) (One or more letters from the set `'i', 'L', 'm', 's', 'u', 'x'`.) The group matches the empty string; the letters set the corresponding flags: *re.I* (ignore case), *re.L* (locale dependent), *re.M* (multi-line), *re.S* (dot matches all), *re.U* (Unicode dependent), and *re.X* (verbose), for the entire regular expression. (The flags are described in *Module Contents*.) This is useful if you wish to include the flags as part of the regular expression, instead of passing a *flag* argument to the *re.compile()* function.

Note that the `(?x)` flag changes how the expression is parsed. It should be used first in the expression string, or after one or more whitespace characters. If there are non-whitespace characters before the flag, the results are undefined.

(?:...) A non-capturing version of regular parentheses. Matches whatever regular expression is inside the parentheses, but the substring matched by the group *cannot* be retrieved after performing a match or referenced later in the pattern.

(?P<name>...) Similar to regular parentheses, but the substring matched by the group is accessible via the symbolic group name *name*. Group names must be valid Python identifiers, and each group name must be defined only once within a regular expression. A symbolic group is also a numbered group, just as if the group were not named.

Named groups can be referenced in three contexts. If the pattern is `(?P<quote>['"])*?(?P=quote)` (i.e. matching a string quoted with either single or double quotes):

Context of reference to group «quote»	Ways to reference it
in the same pattern itself	<ul style="list-style-type: none"> • (<code>?P=quote</code>) (as shown) • <code>\1</code>
when processing match object <code>m</code>	<ul style="list-style-type: none"> • <code>m.group('quote')</code> • <code>m.end('quote')</code> (etc.)
in a string passed to the <code>repl</code> argument of <code>re.sub()</code>	<ul style="list-style-type: none"> • <code>\g<quote></code> • <code>\g<1></code> • <code>\1</code>

(`?P=name`) A backreference to a named group; it matches whatever text was matched by the earlier group named *name*.

(`?#...`) A comment; the contents of the parentheses are simply ignored.

(`?=...`) Matches if `...` matches next, but doesn't consume any of the string. This is called a *lookahead assertion*. For example, `Isaac (?=Asimov)` will match `'Isaac '` only if it's followed by `'Asimov'`.

(`?!...`) Matches if `...` doesn't match next. This is a *negative lookahead assertion*. For example, `Isaac (?!Asimov)` will match `'Isaac '` only if it's *not* followed by `'Asimov'`.

(`?<=...`) Matches if the current position in the string is preceded by a match for `...` that ends at the current position. This is called a *positive lookbehind assertion*. `(?<=abc)def` will find a match in `abcdef`, since the lookbehind will back up 3 characters and check if the contained pattern matches. The contained pattern must only match strings of some fixed length, meaning that `abc` or `a|b` are allowed, but `a*` and `a{3,4}` are not. Group references are not supported even if they match strings of some fixed length. Note that patterns which start with positive lookbehind assertions will not match at the beginning of the string being searched; you will most likely want to use the `search()` function rather than the `match()` function:

```
>>> import re
>>> m = re.search('(?!<=abc)def', 'abcdef')
>>> m.group(0)
'def'
```

This example looks for a word following a hyphen:

```
>>> m = re.search('(?!<=)\w+', 'spam-egg')
>>> m.group(0)
'egg'
```

(`?<!...`) Matches if the current position in the string is not preceded by a match for `...`. This is called a *negative lookbehind assertion*. Similar to positive lookbehind assertions, the contained pattern must only match strings of some fixed length and shouldn't contain group references. Patterns which start with negative lookbehind assertions may match at the beginning of the string being searched.

(`?(id/name)yes-pattern|no-pattern`) Will try to match with `yes-pattern` if the group with given *id* or *name* exists, and with `no-pattern` if it doesn't. `no-pattern` is optional and can be omitted. For example, `(<)?(\w+@\w+(?:\.\w+)+)(?(1)>)` is a poor email matching pattern, which will match with `'<user@host.com>'` as well as `'user@host.com'`, but not with `'<user@host.com'`.

버전 2.4에 추가.

The special sequences consist of `'\'` and a character from the list below. If the ordinary character is not on the list, then the resulting RE will match the second character. For example, `\$` matches the character `'$'`.

\number Matches the contents of the group of the same number. Groups are numbered starting from 1. For example, `(.+) \1` matches `'the the'` or `'55 55'`, but not `'thethe'` (note the space after the group). This special sequence can only be used to match one of the first 99 groups. If the first digit of *number* is 0, or *number* is 3 octal digits long, it will not be interpreted as a group match, but as the character with octal value *number*. Inside the `'[' and ']'` of a character class, all numeric escapes are treated as characters.

\A Matches only at the start of the string.

\b Matches the empty string, but only at the beginning or end of a word. A word is defined as a sequence of alphanumeric or underscore characters, so the end of a word is indicated by whitespace or a non-alphanumeric, non-underscore character. Note that formally, `\b` is defined as the boundary between a `\w` and a `\W` character (or vice versa), or between `\w` and the beginning/end of the string, so the precise set of characters deemed to be alphanumeric depends on the values of the `UNICODE` and `LOCALE` flags. For example, `r'\bfoo\b'` matches `'foo'`, `'foo.'`, `'(foo)'`, `'bar foo baz'` but not `'foobar'` or `'foo3'`. Inside a character range, `\b` represents the backspace character, for compatibility with Python's string literals.

\B Matches the empty string, but only when it is *not* at the beginning or end of a word. This means that `r'py\B'` matches `'python'`, `'py3'`, `'py2'`, but not `'py'`, `'py.'`, or `'py!'`. `\B` is just the opposite of `\b`, so is also subject to the settings of `LOCALE` and `UNICODE`.

\d When the `UNICODE` flag is not specified, matches any decimal digit; this is equivalent to the set `[0-9]`. With `UNICODE`, it will match whatever is classified as a decimal digit in the Unicode character properties database.

\D When the `UNICODE` flag is not specified, matches any non-digit character; this is equivalent to the set `[^0-9]`. With `UNICODE`, it will match anything other than character marked as digits in the Unicode character properties database.

\s When the `UNICODE` flag is not specified, it matches any whitespace character, this is equivalent to the set `[\t\n\r\f\v]`. The `LOCALE` flag has no extra effect on matching of the space. If `UNICODE` is set, this will match the characters `[\t\n\r\f\v]` plus whatever is classified as space in the Unicode character properties database.

\S When the `UNICODE` flag is not specified, matches any non-whitespace character; this is equivalent to the set `[^\t\n\r\f\v]`. The `LOCALE` flag has no extra effect on non-whitespace match. If `UNICODE` is set, then any character not marked as space in the Unicode character properties database is matched.

\w When the `LOCALE` and `UNICODE` flags are not specified, matches any alphanumeric character and the underscore; this is equivalent to the set `[a-zA-Z0-9_]`. With `LOCALE`, it will match the set `[0-9_]` plus whatever characters are defined as alphanumeric for the current locale. If `UNICODE` is set, this will match the characters `[0-9_]` plus whatever is classified as alphanumeric in the Unicode character properties database.

\W When the `LOCALE` and `UNICODE` flags are not specified, matches any non-alphanumeric character; this is equivalent to the set `[^a-zA-Z0-9_]`. With `LOCALE`, it will match any character not in the set `[0-9_]`, and not defined as alphanumeric for the current locale. If `UNICODE` is set, this will match anything other than `[0-9_]` plus characters classified as not alphanumeric in the Unicode character properties database.

\Z Matches only at the end of the string.

If both `LOCALE` and `UNICODE` flags are included for a particular sequence, then `LOCALE` flag takes effect first followed by the `UNICODE`.

Most of the standard escapes supported by Python string literals are also accepted by the regular expression parser:

<code>\a</code>	<code>\b</code>	<code>\f</code>	<code>\n</code>
<code>\r</code>	<code>\t</code>	<code>\v</code>	<code>\x</code>
<code>\\</code>			

(Note that `\b` is used to represent word boundaries, and means «backspace» only inside character classes.)

Octal escapes are included in a limited form: If the first digit is a 0, or if there are three octal digits, it is considered an octal escape. Otherwise, it is a group reference. As for string literals, octal escapes are always at most three digits in length.

더 보기:

Mastering Regular Expressions Book on regular expressions by Jeffrey Friedl, published by O'Reilly. The second edition of the book no longer covers Python at all, but the first edition covered writing good regular expression patterns in great detail.

7.2.2 Module Contents

The module defines several functions, constants, and an exception. Some of the functions are simplified versions of the full featured methods for compiled regular expressions. Most non-trivial applications always use the compiled form.

`re.compile(pattern, flags=0)`

Compile a regular expression pattern into a regular expression object, which can be used for matching using its `match()` and `search()` methods, described below.

The expression's behaviour can be modified by specifying a `flags` value. Values can be any of the following variables, combined using bitwise OR (the `|` operator).

The sequence

```
prog = re.compile(pattern)
result = prog.match(string)
```

is equivalent to

```
result = re.match(pattern, string)
```

but using `re.compile()` and saving the resulting regular expression object for reuse is more efficient when the expression will be used several times in a single program.

참고: The compiled versions of the most recent patterns passed to `re.match()`, `re.search()` or `re.compile()` are cached, so programs that use only a few regular expressions at a time needn't worry about compiling regular expressions.

`re.DEBUG`

Display debug information about compiled expression.

`re.I`

`re.IGNORECASE`

Perform case-insensitive matching; expressions like `[A-Z]` will match lowercase letters, too. This is not affected by the current locale. To get this effect on non-ASCII Unicode characters such as `ü` and `Û`, add the `UNICODE` flag.

`re.L`

`re.LOCALE`

Make `\w`, `\W`, `\b`, `\B`, `\s` and `\S` dependent on the current locale.

`re.M`

`re.MULTILINE`

When specified, the pattern character `^` matches at the beginning of the string and at the beginning of each line (immediately following each newline); and the pattern character `$` matches at the end of the string and at the end of each line (immediately preceding each newline). By default, `^` matches only at the beginning of the string, and `$` only at the end of the string and immediately before the newline (if any) at the end of the string.

`re.S`

`re.DOTALL`

Make the `.` special character match any character at all, including a newline; without this flag, `.` will match anything *except* a newline.

`re.U``re.UNICODE`

Make the `\w`, `\W`, `\b`, `\B`, `\d`, `\D`, `\s` and `\S` sequences dependent on the Unicode character properties database. Also enables non-ASCII matching for `IGNORECASE`.

버전 2.0에 추가.

`re.X``re.VERBOSE`

This flag allows you to write regular expressions that look nicer and are more readable by allowing you to visually separate logical sections of the pattern and add comments. Whitespace within the pattern is ignored, except when in a character class, or when preceded by an unescaped backslash, or within tokens like `*?`, `(?:` or `(?P<...>`. When a line contains a `#` that is not in a character class and is not preceded by an unescaped backslash, all characters from the leftmost such `#` through the end of the line are ignored.

This means that the two following regular expression objects that match a decimal number are functionally equal:

```
a = re.compile(r"""\d + # the integral part
                  \.   # the decimal point
                  \d * # some fractional digits""", re.X)
b = re.compile(r"\d+\.\d*")
```

`re.search(pattern, string, flags=0)`

Scan through *string* looking for the first location where the regular expression *pattern* produces a match, and return a corresponding *MatchObject* instance. Return `None` if no position in the string matches the pattern; note that this is different from finding a zero-length match at some point in the string.

`re.match(pattern, string, flags=0)`

If zero or more characters at the beginning of *string* match the regular expression *pattern*, return a corresponding *MatchObject* instance. Return `None` if the string does not match the pattern; note that this is different from a zero-length match.

Note that even in *MULTILINE* mode, `re.match()` will only match at the beginning of the string and not at the beginning of each line.

If you want to locate a match anywhere in *string*, use `search()` instead (see also `search()` vs. `match()`).

`re.split(pattern, string, maxsplit=0, flags=0)`

Split *string* by the occurrences of *pattern*. If capturing parentheses are used in *pattern*, then the text of all groups in the pattern are also returned as part of the resulting list. If *maxsplit* is nonzero, at most *maxsplit* splits occur, and the remainder of the string is returned as the final element of the list. (Incompatibility note: in the original Python 1.5 release, *maxsplit* was ignored. This has been fixed in later releases.)

```
>>> re.split('\W+', 'Words, words, words.')
['Words', 'words', 'words', '']
>>> re.split('(\W+)', 'Words, words, words.')
['Words', ',', 'words', ',', 'words', ',', '']
>>> re.split('\W+', 'Words, words, words.', 1)
['Words', 'words, words.']
>>> re.split('[a-f]+', '0a3B9', flags=re.IGNORECASE)
['0', '3', '9']
```

If there are capturing groups in the separator and it matches at the start of the string, the result will start with an empty string. The same holds for the end of the string:

```
>>> re.split('(\W+)', '...words, words...')
['', '...', 'words', ',', 'words', '...', '']
```


That way, separator components are always found at the same relative indices within the result list (e.g., if there's one capturing group in the separator, the 0th, the 2nd and so forth).

Note that *split* will never split a string on an empty pattern match. For example:

```
>>> re.split('x*', 'foo')
['foo']
>>> re.split("(?m)^$", "foo\n\nbar\n")
['foo\n\nbar\n']
```

버전 2.7에서 변경: Added the optional flags argument.

re.findall (*pattern*, *string*, *flags*=0)

Return all non-overlapping matches of *pattern* in *string*, as a list of strings. The *string* is scanned left-to-right, and matches are returned in the order found. If one or more groups are present in the pattern, return a list of groups; this will be a list of tuples if the pattern has more than one group. Empty matches are included in the result.

참고: Due to the limitation of the current implementation the character following an empty match is not included in a next match, so `findall(r'^|\w+', 'two words')` returns `['', 'wo', 'words']` (note missed `<t>`). This is changed in Python 3.7.

버전 1.5.2에 추가.

버전 2.4에서 변경: Added the optional flags argument.

re.finditer (*pattern*, *string*, *flags*=0)

Return an *iterator* yielding *MatchObject* instances over all non-overlapping matches for the RE *pattern* in *string*. The *string* is scanned left-to-right, and matches are returned in the order found. Empty matches are included in the result. See also the note about *findall* ().

버전 2.2에 추가.

버전 2.4에서 변경: Added the optional flags argument.

re.sub (*pattern*, *repl*, *string*, *count*=0, *flags*=0)

Return the string obtained by replacing the leftmost non-overlapping occurrences of *pattern* in *string* by the replacement *repl*. If the pattern isn't found, *string* is returned unchanged. *repl* can be a string or a function; if it is a string, any backslash escapes in it are processed. That is, `\n` is converted to a single newline character, `\r` is converted to a carriage return, and so forth. Unknown escapes such as `\j` are left alone. Backreferences, such as `\6`, are replaced with the substring matched by group 6 in the pattern. For example:

```
>>> re.sub(r'def\s+([a-zA-Z_][a-zA-Z_0-9]*)\s*\(\s*\):',
...       r'static PyObject*\np_\1(void)\n{',
...       'def myfunc():')
'static PyObject*\np_myfunc(void)\n{'
```

If *repl* is a function, it is called for every non-overlapping occurrence of *pattern*. The function takes a single match object argument, and returns the replacement string. For example:

```
>>> def dashrepl(matchobj):
...     if matchobj.group(0) == '-': return ' '
...     else: return '-'
>>> re.sub('-{1,2}', dashrepl, 'pro---gram-files')
'pro--gram files'
>>> re.sub(r'\sAND\s', ' & ', 'Baked Beans And Spam', flags=re.IGNORECASE)
'Baked Beans & Spam'
```

The pattern may be a string or an RE object.

The optional argument *count* is the maximum number of pattern occurrences to be replaced; *count* must be a non-negative integer. If omitted or zero, all occurrences will be replaced. Empty matches for the pattern are replaced only when not adjacent to a previous match, so `sub('x*', '-', 'abc')` returns `'-a-b-c-'`.

In string-type *repl* arguments, in addition to the character escapes and backreferences described above, `\g<name>` will use the substring matched by the group named *name*, as defined by the `(?P<name>...)` syntax. `\g<number>` uses the corresponding group number; `\g<2>` is therefore equivalent to `\2`, but isn't ambiguous in a replacement such as `\g<2>0`. `\20` would be interpreted as a reference to group 20, not a reference to group 2 followed by the literal character `'0'`. The backreference `\g<0>` substitutes in the entire substring matched by the RE.

버전 2.7에서 변경: Added the optional flags argument.

re.subn (*pattern*, *repl*, *string*, *count=0*, *flags=0*)

Perform the same operation as `sub()`, but return a tuple (*new_string*, *number_of_subs_made*).

버전 2.7에서 변경: Added the optional flags argument.

re.escape (*pattern*)

Escape all the characters in *pattern* except ASCII letters and numbers. This is useful if you want to match an arbitrary literal string that may have regular expression metacharacters in it. For example:

```
>>> print re.escape('python.exe')
python\.exe

>>> legal_chars = string.ascii_lowercase + string.digits + "!#$%&'*+-.^_`|~:"
>>> print "[%s]+" % re.escape(legal_chars)
[abcdefghijklmnopqrstuvwxyz0123456789\!#$%&'*\+|-\.^_\`|\~\:]+

>>> operators = ['+', '-', '*', '/', '**']
>>> print '|'.join(map(re.escape, sorted(operators, reverse=True)))
\|\/\-\|\/\+|\*\*\|\/\*
```

re.purge ()

Clear the regular expression cache.

exception re.error

Exception raised when a string passed to one of the functions here is not a valid regular expression (for example, it might contain unmatched parentheses) or when some other error occurs during compilation or matching. It is never an error if a string contains no match for a pattern.

7.2.3 Regular Expression Objects

class re.RegexObject

The *RegexObject* class supports the following methods and attributes:

search (*string*[, *pos*[, *endpos*]])

Scan through *string* looking for a location where this regular expression produces a match, and return a corresponding *MatchObject* instance. Return *None* if no position in the string matches the pattern; note that this is different from finding a zero-length match at some point in the string.

The optional second parameter *pos* gives an index in the string where the search is to start; it defaults to 0. This is not completely equivalent to slicing the string; the `'^'` pattern character matches at the real beginning of the string and at positions just after a newline, but not necessarily at the index where the search is to start.

The optional parameter *endpos* limits how far the string will be searched; it will be as if the string is *endpos* characters long, so only the characters from *pos* to *endpos* - 1 will be searched for a match. If *endpos* is less than *pos*, no match will be found, otherwise, if *rx* is a compiled regular expression object, `rx.search(string, 0, 50)` is equivalent to `rx.search(string[:50], 0)`.

```
>>> pattern = re.compile("d")
>>> pattern.search("dog")      # Match at index 0
<_sre.SRE_Match object at ...>
>>> pattern.search("dog", 1)   # No match; search doesn't include the "d"
```

match (*string* [, *pos* [, *endpos*]])

If zero or more characters at the *beginning* of *string* match this regular expression, return a corresponding *MatchObject* instance. Return *None* if the string does not match the pattern; note that this is different from a zero-length match.

The optional *pos* and *endpos* parameters have the same meaning as for the *search()* method.

```
>>> pattern = re.compile("o")
>>> pattern.match("dog")       # No match as "o" is not at the start of "dog".
>>> pattern.match("dog", 1)    # Match as "o" is the 2nd character of "dog".
<_sre.SRE_Match object at ...>
```

If you want to locate a match anywhere in *string*, use *search()* instead (see also *search()* vs. *match()*).

split (*string*, *maxsplit*=0)

Identical to the *split()* function, using the compiled pattern.

findall (*string* [, *pos* [, *endpos*]])

Similar to the *findall()* function, using the compiled pattern, but also accepts optional *pos* and *endpos* parameters that limit the search region like for *match()*.

finditer (*string* [, *pos* [, *endpos*]])

Similar to the *finditer()* function, using the compiled pattern, but also accepts optional *pos* and *endpos* parameters that limit the search region like for *match()*.

sub (*repl*, *string*, *count*=0)

Identical to the *sub()* function, using the compiled pattern.

subn (*repl*, *string*, *count*=0)

Identical to the *subn()* function, using the compiled pattern.

flags

The regex matching flags. This is a combination of the flags given to *compile()* and any (?...) inline flags in the pattern.

groups

The number of capturing groups in the pattern.

groupindex

A dictionary mapping any symbolic group names defined by (?P<id>) to group numbers. The dictionary is empty if no symbolic groups were used in the pattern.

pattern

The pattern string from which the RE object was compiled.

7.2.4 Match Objects

`class re.MatchObject`

Match objects always have a boolean value of `True`. Since `match()` and `search()` return `None` when there is no match, you can test whether there was a match with a simple `if` statement:

```
match = re.search(pattern, string)
if match:
    process(match)
```

Match objects support the following methods and attributes:

`expand(template)`

Return the string obtained by doing backslash substitution on the template string *template*, as done by the `sub()` method. Escapes such as `\n` are converted to the appropriate characters, and numeric backreferences (`\1`, `\2`) and named backreferences (`\g<1>`, `\g<name>`) are replaced by the contents of the corresponding group.

`group([group1, ...])`

Returns one or more subgroups of the match. If there is a single argument, the result is a single string; if there are multiple arguments, the result is a tuple with one item per argument. Without arguments, *group1* defaults to zero (the whole match is returned). If a *groupN* argument is zero, the corresponding return value is the entire matching string; if it is in the inclusive range `[1..99]`, it is the string matching the corresponding parenthesized group. If a group number is negative or larger than the number of groups defined in the pattern, an `IndexError` exception is raised. If a group is contained in a part of the pattern that did not match, the corresponding result is `None`. If a group is contained in a part of the pattern that matched multiple times, the last match is returned.

```
>>> m = re.match(r"(\w+) (\w+)", "Isaac Newton, physicist")
>>> m.group(0)          # The entire match
'Isaac Newton'
>>> m.group(1)          # The first parenthesized subgroup.
'Isaac'
>>> m.group(2)          # The second parenthesized subgroup.
'Newton'
>>> m.group(1, 2)       # Multiple arguments give us a tuple.
('Isaac', 'Newton')
```

If the regular expression uses the `(?P<name>...)` syntax, the *groupN* arguments may also be strings identifying groups by their group name. If a string argument is not used as a group name in the pattern, an `IndexError` exception is raised.

A moderately complicated example:

```
>>> m = re.match(r"(?P<first_name>\w+) (?P<last_name>\w+)", "Malcolm Reynolds")
>>> m.group('first_name')
'Malcolm'
>>> m.group('last_name')
'Reynolds'
```

Named groups can also be referred to by their index:

```
>>> m.group(1)
'Malcolm'
>>> m.group(2)
'Reynolds'
```

If a group matches multiple times, only the last match is accessible:

```
>>> m = re.match(r"(..)+", "a1b2c3") # Matches 3 times.
>>> m.group(1)                        # Returns only the last match.
'c3'
```

`groups([default])`

Return a tuple containing all the subgroups of the match, from 1 up to however many groups are in the pattern. The *default* argument is used for groups that did not participate in the match; it defaults to `None`. (Incompatibility note: in the original Python 1.5 release, if the tuple was one element long, a string would be returned instead. In later versions (from 1.5.1 on), a singleton tuple is returned in such cases.)

For example:

```
>>> m = re.match(r"(\d+)\.(\d+)", "24.1632")
>>> m.groups()
('24', '1632')
```

If we make the decimal place and everything after it optional, not all groups might participate in the match. These groups will default to `None` unless the *default* argument is given:

```
>>> m = re.match(r"(\d+)\.?(\d+)?", "24")
>>> m.groups() # Second group defaults to None.
('24', None)
>>> m.groups('0') # Now, the second group defaults to '0'.
('24', '0')
```

`groupdict([default])`

Return a dictionary containing all the *named* subgroups of the match, keyed by the subgroup name. The *default* argument is used for groups that did not participate in the match; it defaults to `None`. For example:

```
>>> m = re.match(r"(?P<first_name>\w+) (?P<last_name>\w+)", "Malcolm Reynolds")
>>> m.groupdict()
{'first_name': 'Malcolm', 'last_name': 'Reynolds'}
```

`start([group])`

`end([group])`

Return the indices of the start and end of the substring matched by *group*; *group* defaults to zero (meaning the whole matched substring). Return `-1` if *group* exists but did not contribute to the match. For a match object *m*, and a group *g* that did contribute to the match, the substring matched by group *g* (equivalent to `m.group(g)`) is

```
m.string[m.start(g):m.end(g)]
```

Note that `m.start(group)` will equal `m.end(group)` if *group* matched a null string. For example, after `m = re.search('b(c?)', 'cba')`, `m.start(0)` is 1, `m.end(0)` is 2, `m.start(1)` and `m.end(1)` are both 2, and `m.start(2)` raises an *IndexError* exception.

An example that will remove *remove_this* from email addresses:

```
>>> email = "tony@tiremove_thisger.net"
>>> m = re.search("remove_this", email)
>>> email[:m.start()] + email[m.end():]
'tony@tiger.net'
```

`span([group])`

For *MatchObject* *m*, return the 2-tuple `(m.start(group), m.end(group))`. Note that if *group*

did not contribute to the match, this is `(-1, -1)`. `group` defaults to zero, the entire match.

pos

The value of `pos` which was passed to the `search()` or `match()` method of the `RegexObject`. This is the index into the string at which the RE engine started looking for a match.

endpos

The value of `endpos` which was passed to the `search()` or `match()` method of the `RegexObject`. This is the index into the string beyond which the RE engine will not go.

lastindex

The integer index of the last matched capturing group, or `None` if no group was matched at all. For example, the expressions `(a)b`, `((a)(b))`, and `((ab))` will have `lastindex == 1` if applied to the string `'ab'`, while the expression `(a)(b)` will have `lastindex == 2`, if applied to the same string.

lastgroup

The name of the last matched capturing group, or `None` if the group didn't have a name, or if no group was matched at all.

re

The regular expression object whose `match()` or `search()` method produced this `MatchObject` instance.

string

The string passed to `match()` or `search()`.

7.2.5 Examples

Checking For a Pair

In this example, we'll use the following helper function to display match objects a little more gracefully:

```
def displaymatch(match):
    if match is None:
        return None
    return '<Match: %r, groups=%r>' % (match.group(), match.groups())
```

Suppose you are writing a poker program where a player's hand is represented as a 5-character string with each character representing a card, `⟨a⟩` for ace, `⟨k⟩` for king, `⟨q⟩` for queen, `⟨j⟩` for jack, `⟨t⟩` for 10, and `⟨2⟩` through `⟨9⟩` representing the card with that value.

To see if a given string is a valid hand, one could do the following:

```
>>> valid = re.compile(r"[a2-9tjqk]{5}$")
>>> displaymatch(valid.match("akt5q")) # Valid.
'<Match: 'akt5q', groups=()>'
>>> displaymatch(valid.match("akt5e")) # Invalid.
'<Match: 'akt5e', groups=()>'
>>> displaymatch(valid.match("akt")) # Invalid.
'<Match: 'akt', groups=()>'
>>> displaymatch(valid.match("727ak")) # Valid.
'<Match: '727ak', groups=()>'
```

That last hand, `"727ak"`, contained a pair, or two of the same valued cards. To match this with a regular expression, one could use backreferences as such:

```
>>> pair = re.compile(r".*(.)\1")
>>> displaymatch(pair.match("717ak")) # Pair of 7s.
'<Match: '717', groups=('7',)>'
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> displaymatch(pair.match("718ak"))      # No pairs.
>>> displaymatch(pair.match("354aa"))      # Pair of aces.
"<Match: '354aa', groups=('a',)>"
```

To find out what card the pair consists of, one could use the `group()` method of `MatchObject` in the following manner:

```
>>> pair.match("717ak").group(1)
'7'

# Error because re.match() returns None, which doesn't have a group() method:
>>> pair.match("718ak").group(1)
Traceback (most recent call last):
  File "<pysHELL#23>", line 1, in <module>
    re.match(r".*(.)*\1", "718ak").group(1)
AttributeError: 'NoneType' object has no attribute 'group'

>>> pair.match("354aa").group(1)
'a'
```

Simulating scanf()

Python does not currently have an equivalent to `scanf()`. Regular expressions are generally more powerful, though also more verbose, than `scanf()` format strings. The table below offers some more-or-less equivalent mappings between `scanf()` format tokens and regular expressions.

scanf() Token	Regular Expression
%c	.
%5c	.{5}
%d	[+-]?\d+
%e, %E, %f, %g	[+-]?(\d+(\.\d*)? \.\d+)([eE][+-]?\d+)?
%i	[+-]?(0[xX] [\dA-Fa-f]+ 0[0-7]* \d+)
%o	[+-]?[0-7]+
%s	\S+
%u	\d+
%x, %X	[+-]?(0[xX])?[\dA-Fa-f]+

To extract the filename and numbers from a string like

```
/usr/sbin/sendmail - 0 errors, 4 warnings
```

you would use a `scanf()` format like

```
%s - %d errors, %d warnings
```

The equivalent regular expression would be

```
(\S+) - (\d+) errors, (\d+) warnings
```

search() vs. match()

Python offers two different primitive operations based on regular expressions: `re.match()` checks for a match only at the beginning of the string, while `re.search()` checks for a match anywhere in the string (this is what Perl does by default).

For example:

```
>>> re.match("c", "abcdef")      # No match
>>> re.search("c", "abcdef")     # Match
<_sre.SRE_Match object at ...>
```

Regular expressions beginning with `'^'` can be used with `search()` to restrict the match at the beginning of the string:

```
>>> re.match("c", "abcdef")      # No match
>>> re.search("^c", "abcdef")    # No match
>>> re.search("^a", "abcdef")    # Match
<_sre.SRE_Match object at ...>
```

Note however that in `MULTILINE` mode `match()` only matches at the beginning of the string, whereas using `search()` with a regular expression beginning with `'^'` will match at the beginning of each line.

```
>>> re.match('X', 'A\nB\nX', re.MULTILINE) # No match
>>> re.search('X', 'A\nB\nX', re.MULTILINE) # Match
<_sre.SRE_Match object at ...>
```

Making a Phonebook

`split()` splits a string into a list delimited by the passed pattern. The method is invaluable for converting textual data into data structures that can be easily read and modified by Python as demonstrated in the following example that creates a phonebook.

First, here is the input. Normally it may come from a file, here we are using triple-quoted string syntax:

```
>>> text = """Ross McFluff: 834.345.1254 155 Elm Street
...
... Ronald Heathmore: 892.345.3428 436 Finley Avenue
... Frank Burger: 925.541.7625 662 South Dogwood Way
...
...
... Heather Albrecht: 548.326.4584 919 Park Place"""
```

The entries are separated by one or more newlines. Now we convert the string into a list with each nonempty line having its own entry:

```
>>> entries = re.split("\n+", text)
>>> entries
['Ross McFluff: 834.345.1254 155 Elm Street',
 'Ronald Heathmore: 892.345.3428 436 Finley Avenue',
 'Frank Burger: 925.541.7625 662 South Dogwood Way',
 'Heather Albrecht: 548.326.4584 919 Park Place']
```

Finally, split each entry into a list with first name, last name, telephone number, and address. We use the `maxsplit` parameter of `split()` because the address has spaces, our splitting pattern, in it:


```
>>> [re.split("?:? ", entry, 3) for entry in entries]
[['Ross', 'McFluff', '834.345.1254', '155 Elm Street'],
 ['Ronald', 'Heathmore', '892.345.3428', '436 Finley Avenue'],
 ['Frank', 'Burger', '925.541.7625', '662 South Dogwood Way'],
 ['Heather', 'Albrecht', '548.326.4584', '919 Park Place']]
```

The `?:?` pattern matches the colon after the last name, so that it does not occur in the result list. With a `maxsplit` of 4, we could separate the house number from the street name:

```
>>> [re.split("?:? ", entry, 4) for entry in entries]
[['Ross', 'McFluff', '834.345.1254', '155', 'Elm Street'],
 ['Ronald', 'Heathmore', '892.345.3428', '436', 'Finley Avenue'],
 ['Frank', 'Burger', '925.541.7625', '662', 'South Dogwood Way'],
 ['Heather', 'Albrecht', '548.326.4584', '919', 'Park Place']]
```

Text Munging

`sub()` replaces every occurrence of a pattern with a string or the result of a function. This example demonstrates using `sub()` with a function to 《munge》 text, or randomize the order of all the characters in each word of a sentence except for the first and last characters:

```
>>> def repl(m):
...     inner_word = list(m.group(2))
...     random.shuffle(inner_word)
...     return m.group(1) + "".join(inner_word) + m.group(3)
>>> text = "Professor Abdolmalek, please report your absences promptly."
>>> re.sub(r"(\w)(\w+)(\w)", repl, text)
'Poefsrosr Aealmlodbk, pslae reorpt your abnseces plmrptoy.'
>>> re.sub(r"(\w)(\w+)(\w)", repl, text)
'Pofsroser Aodlambelk, plasee reorpt yuor asnebces potlmrpy.'
```

Finding all Adverbs

`findall()` matches *all* occurrences of a pattern, not just the first one as `search()` does. For example, if a writer wanted to find all of the adverbs in some text, they might use `findall()` in the following manner:

```
>>> text = "He was carefully disguised but captured quickly by police."
>>> re.findall(r"\w+ly", text)
['carefully', 'quickly']
```

Finding all Adverbs and their Positions

If one wants more information about all matches of a pattern than the matched text, `finditer()` is useful as it provides instances of `MatchObject` instead of strings. Continuing with the previous example, if a writer wanted to find all of the adverbs *and their positions* in some text, they would use `finditer()` in the following manner:

```
>>> text = "He was carefully disguised but captured quickly by police."
>>> for m in re.finditer(r"\w+ly", text):
...     print '%02d-%02d: %s' % (m.start(), m.end(), m.group(0))
07-16: carefully
40-47: quickly
```

Raw String Notation

Raw string notation (`r"text"`) keeps regular expressions sane. Without it, every backslash (`'\'`) in a regular expression would have to be prefixed with another one to escape it. For example, the two following lines of code are functionally identical:

```
>>> re.match(r"\W(.)\1\W", " ff ")
<_sre.SRE_Match object at ...>
>>> re.match("\\W(.)\\1\\W", " ff ")
<_sre.SRE_Match object at ...>
```

When one wants to match a literal backslash, it must be escaped in the regular expression. With raw string notation, this means `r"\"`. Without raw string notation, one must use `"\\\"`, making the following lines of code functionally identical:

```
>>> re.match(r"\\", r"\\")
<_sre.SRE_Match object at ...>
>>> re.match("\\\\", r"\\")
<_sre.SRE_Match object at ...>
```

7.3 struct — Interpret strings as packed binary data

This module performs conversions between Python values and C structs represented as Python strings. This can be used in handling binary data stored in files or from network connections, among other sources. It uses *Format Strings* as compact descriptions of the layout of the C structs and the intended conversion to/from Python values.

참고: By default, the result of packing a given C struct includes pad bytes in order to maintain proper alignment for the C types involved; similarly, alignment is taken into account when unpacking. This behavior is chosen so that the bytes of a packed struct correspond exactly to the layout in memory of the corresponding C struct. To handle platform-independent data formats or omit implicit pad bytes, use *standard* size and alignment instead of *native* size and alignment: see *Byte Order, Size, and Alignment* for details.

7.3.1 Functions and Exceptions

The module defines the following exception and functions:

exception `struct.error`

Exception raised on various occasions; argument is a string describing what is wrong.

struct.pack (*fmt*, *v1*, *v2*, ...)

Return a string containing the values *v1*, *v2*, ... packed according to the given format. The arguments must match the values required by the format exactly.

struct.pack_into (*fmt*, *buffer*, *offset*, *v1*, *v2*, ...)

Pack the values *v1*, *v2*, ... according to the given format, write the packed bytes into the writable *buffer* starting at *offset*. Note that the offset is a required argument.

버전 2.5에 추가.

struct.unpack (*fmt*, *string*)

Unpack the string (presumably packed by `pack(fmt, ...)`) according to the given format. The result is a tuple even if it contains exactly one item. The string must contain exactly the amount of data required by the format (`len(string)` must equal `calcsz(fmt)`).

```
struct.unpack_from(fmt, buffer[, offset=0])
```

Unpack the *buffer* according to the given format. The result is a tuple even if it contains exactly one item. The *buffer* must contain at least the amount of data required by the format (`len(buffer[offset:])` must be at least `calcsize(fmt)`).

버전 2.5에 추가.

```
struct.calcsize(fmt)
```

Return the size of the struct (and hence of the string) corresponding to the given format.

7.3.2 Format Strings

Format strings are the mechanism used to specify the expected layout when packing and unpacking data. They are built up from *Format Characters*, which specify the type of data being packed/unpacked. In addition, there are special characters for controlling the *Byte Order, Size, and Alignment*.

Byte Order, Size, and Alignment

By default, C types are represented in the machine's native format and byte order, and properly aligned by skipping pad bytes if necessary (according to the rules used by the C compiler).

Alternatively, the first character of the format string can be used to indicate the byte order, size and alignment of the packed data, according to the following table:

Character	Byte order	Size	Alignment
@	native	native	native
=	native	standard	none
<	little-endian	standard	none
>	big-endian	standard	none
!	network (= big-endian)	standard	none

If the first character is not one of these, '@' is assumed.

Native byte order is big-endian or little-endian, depending on the host system. For example, Intel x86 and AMD64 (x86-64) are little-endian; Motorola 68000 and PowerPC G5 are big-endian; ARM and Intel Itanium feature switchable endianness (bi-endian). Use `sys.byteorder` to check the endianness of your system.

Native size and alignment are determined using the C compiler's `sizeof` expression. This is always combined with native byte order.

Standard size depends only on the format character; see the table in the *Format Characters* section.

Note the difference between '@' and '=': both use native byte order, but the size and alignment of the latter is standardized.

The form '!' is available for those poor souls who claim they can't remember whether network byte order is big-endian or little-endian.

There is no way to indicate non-native byte order (force byte-swapping); use the appropriate choice of '<' or '>'.

Notes:

- (1) Padding is only automatically added between successive structure members. No padding is added at the beginning or the end of the encoded struct.
- (2) No padding is added when using non-native size and alignment, e.g. with '<>', '>>', '<=>', and '<!'>'.

- (3) To align the end of a structure to the alignment requirement of a particular type, end the format with the code for that type with a repeat count of zero. See [Examples](#).

Format Characters

Format characters have the following meaning; the conversion between C and Python values should be obvious given their types. The `<Standard size>` column refers to the size of the packed value in bytes when using standard size; that is, when the format string starts with one of `'<'`, `'>'`, `'!'` or `'='`. When using native size, the size of the packed value is platform-dependent.

Format	C Type	Python type	Standard size	Notes
x	pad byte	no value		
c	char	string of length 1	1	
b	signed char	integer	1	(3)
B	unsigned char	integer	1	(3)
?	_Bool	bool	1	(1)
h	short	integer	2	(3)
H	unsigned short	integer	2	(3)
i	int	integer	4	(3)
I	unsigned int	integer	4	(3)
l	long	integer	4	(3)
L	unsigned long	integer	4	(3)
q	long long	integer	8	(2), (3)
Q	unsigned long long	integer	8	(2), (3)
f	float	float	4	(4)
d	double	float	8	(4)
s	char[]	string		
p	char[]	string		
P	void *	integer		(5), (3)

Notes:

- (1) The `'?'` conversion code corresponds to the `_Bool` type defined by C99. If this type is not available, it is simulated using a `char`. In standard mode, it is always represented by one byte.

버전 2.6에 추가.

- (2) The `'q'` and `'Q'` conversion codes are available in native mode only if the platform C compiler supports C long long, or, on Windows, `__int64`. They are always available in standard modes.

버전 2.2에 추가.

- (3) When attempting to pack a non-integer using any of the integer conversion codes, if the non-integer has a `__index__()` method then that method is called to convert the argument to an integer before packing. If no `__index__()` method exists, or the call to `__index__()` raises `TypeError`, then the `__int__()` method is tried. However, the use of `__int__()` is deprecated, and will raise `DeprecationWarning`.

버전 2.7에서 변경: Use of the `__index__()` method for non-integers is new in 2.7.

버전 2.7에서 변경: Prior to version 2.7, not all integer conversion codes would use the `__int__()` method to convert, and `DeprecationWarning` was raised only for float arguments.

- (4) For the `'f'` and `'d'` conversion codes, the packed representation uses the IEEE 754 binary32 (for `'f'`) or binary64 (for `'d'`) format, regardless of the floating-point format used by the platform.

- (5) The 'P' format character is only available for the native byte ordering (selected as the default or with the '@' byte order character). The byte order character '=' chooses to use little- or big-endian ordering based on the host system. The struct module does not interpret this as native ordering, so the 'P' format is not available.

A format character may be preceded by an integral repeat count. For example, the format string '4h' means exactly the same as 'hhhh'.

Whitespace characters between formats are ignored; a count and its format must not contain whitespace though.

For the 's' format character, the count is interpreted as the size of the string, not a repeat count like for the other format characters; for example, '10s' means a single 10-byte string, while '10c' means 10 characters. If a count is not given, it defaults to 1. For packing, the string is truncated or padded with null bytes as appropriate to make it fit. For unpacking, the resulting string always has exactly the specified number of bytes. As a special case, '0s' means a single, empty string (while '0c' means 0 characters).

The 'p' format character encodes a 《Pascal string》, meaning a short variable-length string stored in a *fixed number of bytes*, given by the count. The first byte stored is the length of the string, or 255, whichever is smaller. The bytes of the string follow. If the string passed in to `pack()` is too long (longer than the count minus 1), only the leading `count-1` bytes of the string are stored. If the string is shorter than `count-1`, it is padded with null bytes so that exactly `count` bytes in all are used. Note that for `unpack()`, the 'p' format character consumes `count` bytes, but that the string returned can never contain more than 255 characters.

For the 'P' format character, the return value is a Python integer or long integer, depending on the size needed to hold a pointer when it has been cast to an integer type. A *NULL* pointer will always be returned as the Python integer 0. When packing pointer-sized values, Python integer or long integer objects may be used. For example, the Alpha and Merced processors use 64-bit pointer values, meaning a Python long integer will be used to hold the pointer; other platforms use 32-bit pointers and will use a Python integer.

For the '?' format character, the return value is either *True* or *False*. When packing, the truth value of the argument object is used. Either 0 or 1 in the native or standard bool representation will be packed, and any non-zero value will be *True* when unpacking.

Examples

참고: All examples assume a native byte order, size, and alignment with a big-endian machine.

A basic example of packing/unpacking three integers:

```
>>> from struct import *
>>> pack('hhl', 1, 2, 3)
'\x00\x01\x00\x02\x00\x00\x00\x03'
>>> unpack('hhl', '\x00\x01\x00\x02\x00\x00\x00\x03')
(1, 2, 3)
>>> calcsize('hhl')
8
```

Unpacked fields can be named by assigning them to variables or by wrapping the result in a named tuple:

```
>>> record = 'raymond \x32\x12\x08\x01\x08'
>>> name, serialnum, school, gradelevel = unpack('<10sHHb', record)

>>> from collections import namedtuple
>>> Student = namedtuple('Student', 'name serialnum school gradelevel')
>>> Student._make(unpack('<10sHHb', record))
Student(name='raymond ', serialnum=4658, school=264, gradelevel=8)
```

The ordering of format characters may have an impact on size since the padding needed to satisfy alignment requirements is different:

```
>>> pack('ci', '*', 0x12131415)
'*\x00\x00\x00\x12\x13\x14\x15'
>>> pack('ic', 0x12131415, '*')
'\x12\x13\x14\x15*'
>>> calcsize('ci')
8
>>> calcsize('ic')
5
```

The following format 'llh01' specifies two pad bytes at the end, assuming longs are aligned on 4-byte boundaries:

```
>>> pack('llh01', 1, 2, 3)
'\x00\x00\x00\x01\x00\x00\x00\x02\x00\x03\x00\x00'
```

This only works when native size and alignment are in effect; standard size and alignment does not enforce any alignment.

더 보기:

Module `array` Packed binary storage of homogeneous data.

Module `xdrlib` Packing and unpacking of XDR data.

7.3.3 Classes

The `struct` module also defines the following type:

class `struct.Struct` (*format*)

Return a new Struct object which writes and reads binary data according to the format string *format*. Creating a Struct object once and calling its methods is more efficient than calling the `struct` functions with the same format since the format string only needs to be compiled once.

버전 2.5에 추가.

Compiled Struct objects support the following methods and attributes:

pack (*v1*, *v2*, ...)

Identical to the `pack()` function, using the compiled format. (`len(result)` will equal `self.size`.)

pack_into (*buffer*, *offset*, *v1*, *v2*, ...)

Identical to the `pack_into()` function, using the compiled format.

unpack (*string*)

Identical to the `unpack()` function, using the compiled format. (`len(string)` must equal `self.size`).

unpack_from (*buffer*, *offset*=0)

Identical to the `unpack_from()` function, using the compiled format. (`len(buffer[offset:])` must be at least `self.size`).

format

The format string used to construct this Struct object.

size

The calculated size of the struct (and hence of the string) corresponding to *format*.

7.4 difflib — Helpers for computing deltas

버전 2.1에 추가.

This module provides classes and functions for comparing sequences. It can be used for example, for comparing files, and can produce difference information in various formats, including HTML and context and unified diffs. For comparing directories and files, see also, the *filecmp* module.

class difflib.SequenceMatcher

This is a flexible class for comparing pairs of sequences of any type, so long as the sequence elements are *hashable*. The basic algorithm predates, and is a little fancier than, an algorithm published in the late 1980's by Ratcliff and Obershelp under the hyperbolic name «gestalt pattern matching.» The idea is to find the longest contiguous matching subsequence that contains no «junk» elements (the Ratcliff and Obershelp algorithm doesn't address junk). The same idea is then applied recursively to the pieces of the sequences to the left and to the right of the matching subsequence. This does not yield minimal edit sequences, but does tend to yield matches that «look right» to people.

Timing: The basic Ratcliff-Obershelp algorithm is cubic time in the worst case and quadratic time in the expected case. *SequenceMatcher* is quadratic time for the worst case and has expected-case behavior dependent in a complicated way on how many elements the sequences have in common; best case time is linear.

Automatic junk heuristic: *SequenceMatcher* supports a heuristic that automatically treats certain sequence items as junk. The heuristic counts how many times each individual item appears in the sequence. If an item's duplicates (after the first one) account for more than 1% of the sequence and the sequence is at least 200 items long, this item is marked as «popular» and is treated as junk for the purpose of sequence matching. This heuristic can be turned off by setting the *autojunk* argument to *False* when creating the *SequenceMatcher*.

버전 2.7.1에 추가: The *autojunk* parameter.

class difflib.Differ

This is a class for comparing sequences of lines of text, and producing human-readable differences or deltas. Differ uses *SequenceMatcher* both to compare sequences of lines, and to compare sequences of characters within similar (near-matching) lines.

Each line of a *Differ* delta begins with a two-letter code:

Code	Meaning
'- '	line unique to sequence 1
'+' '	line unique to sequence 2
' ' '	line common to both sequences
'?' '	line not present in either input sequence

Lines beginning with «?» attempt to guide the eye to intraline differences, and were not present in either input sequence. These lines can be confusing if the sequences contain tab characters.

class difflib.HtmlDiff

This class can be used to create an HTML table (or a complete HTML file containing the table) showing a side by side, line by line comparison of text with inter-line and intra-line change highlights. The table can be generated in either full or contextual difference mode.

The constructor for this class is:

__init__ (*tabsize=8, wrapcolumn=None, linejunk=None, charjunk=IS_CHARACTER_JUNK*)

Initializes instance of *HtmlDiff*.

tabsize is an optional keyword argument to specify tab stop spacing and defaults to 8.

wrapcolumn is an optional keyword to specify column number where lines are broken and wrapped, defaults to *None* where lines are not wrapped.

linejunk and *charjunk* are optional keyword arguments passed into *ndiff()* (used by *HtmlDiff* to generate the side by side HTML differences). See *ndiff()* documentation for argument default values and descriptions.

The following methods are public:

make_file (*fromlines*, *tolines* [, *fromdesc*][, *todesc*][, *context*][, *numlines*])

Compares *fromlines* and *tolines* (lists of strings) and returns a string which is a complete HTML file containing a table showing line by line differences with inter-line and intra-line changes highlighted.

fromdesc and *todesc* are optional keyword arguments to specify from/to file column header strings (both default to an empty string).

context and *numlines* are both optional keyword arguments. Set *context* to `True` when contextual differences are to be shown, else the default is `False` to show the full files. *numlines* defaults to 5. When *context* is `True` *numlines* controls the number of context lines which surround the difference highlights. When *context* is `False` *numlines* controls the number of lines which are shown before a difference highlight when using the `<next>` hyperlinks (setting to zero would cause the `<next>` hyperlinks to place the next difference highlight at the top of the browser without any leading context).

make_table (*fromlines*, *tolines* [, *fromdesc*][, *todesc*][, *context*][, *numlines*])

Compares *fromlines* and *tolines* (lists of strings) and returns a string which is a complete HTML table showing line by line differences with inter-line and intra-line changes highlighted.

The arguments for this method are the same as those for the *make_file()* method.

`Tools/scripts/diff.py` is a command-line front-end to this class and contains a good example of its use.

버전 2.4에 추가.

`difflib.context_diff(a, b[, fromfile][, tofile][, fromfiledate][, tofiledate][, n][, lineterm])`

Compare *a* and *b* (lists of strings); return a delta (a *generator* generating the delta lines) in context diff format.

Context diffs are a compact way of showing just the lines that have changed plus a few lines of context. The changes are shown in a before/after style. The number of context lines is set by *n* which defaults to three.

By default, the diff control lines (those with `***` or `---`) are created with a trailing newline. This is helpful so that inputs created from *file.readlines()* result in diffs that are suitable for use with *file.writelines()* since both the inputs and outputs have trailing newlines.

For inputs that do not have trailing newlines, set the *lineterm* argument to `" "` so that the output will be uniformly newline free.

The context diff format normally has a header for filenames and modification times. Any or all of these may be specified using strings for *fromfile*, *tofile*, *fromfiledate*, and *tofiledate*. The modification times are normally expressed in the ISO 8601 format. If not specified, the strings default to blanks.

```
>>> s1 = ['bacon\n', 'eggs\n', 'ham\n', 'guido\n']
>>> s2 = ['python\n', 'eggy\n', 'hamster\n', 'guido\n']
>>> for line in context_diff(s1, s2, fromfile='before.py', tofile='after.py'):
...     sys.stdout.write(line)
*** before.py
--- after.py
*****
*** 1,4 ****
! bacon
! eggs
! ham
! guido
--- 1,4 ----
! python
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
! eggy
! hamster
guido
```

See [A command-line interface to difflib](#) for a more detailed example.

버전 2.3에 추가.

`difflib.get_close_matches(word, possibilities[, n][, cutoff])`

Return a list of the best 《good enough》 matches. *word* is a sequence for which close matches are desired (typically a string), and *possibilities* is a list of sequences against which to match *word* (typically a list of strings).

Optional argument *n* (default 3) is the maximum number of close matches to return; *n* must be greater than 0.

Optional argument *cutoff* (default 0.6) is a float in the range [0, 1]. Possibilities that don't score at least that similar to *word* are ignored.

The best (no more than *n*) matches among the possibilities are returned in a list, sorted by similarity score, most similar first.

```
>>> get_close_matches('appel', ['ape', 'apple', 'peach', 'puppy'])
['apple', 'ape']
>>> import keyword
>>> get_close_matches('wheel', keyword.kwlist)
['while']
>>> get_close_matches('apple', keyword.kwlist)
[]
>>> get_close_matches('accept', keyword.kwlist)
['except']
```

`difflib.ndiff(a, b[, linejunk][, charjunk])`

Compare *a* and *b* (lists of strings); return a *Differ*-style delta (a *generator* generating the delta lines).

Optional keyword parameters *linejunk* and *charjunk* are for filter functions (or *None*):

linejunk: A function that accepts a single string argument, and returns true if the string is junk, or false if not. The default is (*None*), starting with Python 2.3. Before then, the default was the module-level function `IS_LINE_JUNK()`, which filters out lines without visible characters, except for at most one pound character ('#'). As of Python 2.3, the underlying *SequenceMatcher* class does a dynamic analysis of which lines are so frequent as to constitute noise, and this usually works better than the pre-2.3 default.

charjunk: A function that accepts a character (a string of length 1), and returns if the character is junk, or false if not. The default is module-level function `IS_CHARACTER_JUNK()`, which filters out whitespace characters (a blank or tab; note: bad idea to include newline in this!).

`Tools/scripts/ndiff.py` is a command-line front-end to this function.

```
>>> diff = ndiff('one\ntwo\nthree\n'.splitlines(1),
...             'ore\ntree\nemu\n'.splitlines(1))
>>> print ''.join(diff),
- one
? ^
+ ore
? ^
- two
- three
? -
+ tree
+ emu
```

`difflib.restore(sequence, which)`

Return one of the two sequences that generated a delta.

Given a *sequence* produced by `Differ.compare()` or `ndiff()`, extract lines originating from file 1 or 2 (parameter *which*), stripping off line prefixes.

Example:

```
>>> diff = ndiff('one\ntwo\nthree\n'.splitlines(1),
...             'ore\ntree\nemu\n'.splitlines(1))
>>> diff = list(diff) # materialize the generated delta into a list
>>> print ''.join	restore(diff, 1)),
one
two
three
>>> print ''.join	restore(diff, 2)),
ore
tree
emu
```

`difflib.unified_diff(a, b[, fromfile][, tofile][, fromfiledate][, tofiledate][, n][, lineterm])`

Compare *a* and *b* (lists of strings); return a delta (a *generator* generating the delta lines) in unified diff format.

Unified diffs are a compact way of showing just the lines that have changed plus a few lines of context. The changes are shown in an inline style (instead of separate before/after blocks). The number of context lines is set by *n* which defaults to three.

By default, the diff control lines (those with `---`, `+++`, or `@@`) are created with a trailing newline. This is helpful so that inputs created from `file.readlines()` result in diffs that are suitable for use with `file.writelines()` since both the inputs and outputs have trailing newlines.

For inputs that do not have trailing newlines, set the *lineterm* argument to `" "` so that the output will be uniformly newline free.

The context diff format normally has a header for filenames and modification times. Any or all of these may be specified using strings for *fromfile*, *tofile*, *fromfiledate*, and *tofiledate*. The modification times are normally expressed in the ISO 8601 format. If not specified, the strings default to blanks.

```
>>> s1 = ['bacon\n', 'eggs\n', 'ham\n', 'guido\n']
>>> s2 = ['python\n', 'eggy\n', 'hamster\n', 'guido\n']
>>> for line in unified_diff(s1, s2, fromfile='before.py', tofile='after.py'):
...     sys.stdout.write(line)
--- before.py
+++ after.py
@@ -1,4 +1,4 @@
-bacon
-eggs
-ham
+python
+eggy
+hamster
 guido
```

See [A command-line interface to difflib](#) for a more detailed example.

버전 2.3에 추가.

`difflib.IS_LINE_JUNK(line)`

Return true for ignorable lines. The line *line* is ignorable if *line* is blank or contains a single `'#'`, otherwise it is not ignorable. Used as a default for parameter *linejunk* in `ndiff()` before Python 2.3.

`difflib.IS_CHARACTER_JUNK(ch)`

Return true for ignorable characters. The character *ch* is ignorable if *ch* is a space or tab, otherwise it is not ignorable. Used as a default for parameter *charjunk* in `ndiff()`.

더 보기:

Pattern Matching: The Gestalt Approach Discussion of a similar algorithm by John W. Ratcliff and D. E. Metzener. This was published in *Dr. Dobbs's Journal* in July, 1988.

7.4.1 SequenceMatcher Objects

The *SequenceMatcher* class has this constructor:

class `difflib.SequenceMatcher` (*isjunk=None*, *a=""*, *b=""*, *autojunk=True*)

Optional argument *isjunk* must be `None` (the default) or a one-argument function that takes a sequence element and returns true if and only if the element is 《junk》 and should be ignored. Passing `None` for *isjunk* is equivalent to passing `lambda x: 0`; in other words, no elements are ignored. For example, pass:

```
lambda x: x in " \t"
```

if you're comparing lines as sequences of characters, and don't want to synch up on blanks or hard tabs.

The optional arguments *a* and *b* are sequences to be compared; both default to empty strings. The elements of both sequences must be *hashable*.

The optional argument *autojunk* can be used to disable the automatic junk heuristic.

버전 2.7.1에 추가: The *autojunk* parameter.

SequenceMatcher objects have the following methods:

set_seqs (*a*, *b*)

Set the two sequences to be compared.

SequenceMatcher computes and caches detailed information about the second sequence, so if you want to compare one sequence against many sequences, use `set_seq2()` to set the commonly used sequence once and call `set_seq1()` repeatedly, once for each of the other sequences.

set_seq1 (*a*)

Set the first sequence to be compared. The second sequence to be compared is not changed.

set_seq2 (*b*)

Set the second sequence to be compared. The first sequence to be compared is not changed.

find_longest_match (*alo*, *ahi*, *blo*, *bhi*)

Find longest matching block in `a[alo:ahi]` and `b[blo:bhi]`.

If *isjunk* was omitted or `None`, `find_longest_match()` returns (*i*, *j*, *k*) such that `a[i:i+k]` is equal to `b[j:j+k]`, where `alo <= i <= i+k <= ahi` and `blo <= j <= j+k <= bhi`. For all (*i'*, *j'*, *k'*) meeting those conditions, the additional conditions `k >= k'`, `i <= i'`, and if `i == i'`, `j <= j'` are also met. In other words, of all maximal matching blocks, return one that starts earliest in *a*, and of all those maximal matching blocks that start earliest in *a*, return the one that starts earliest in *b*.

```
>>> s = SequenceMatcher(None, "abcd", "abcd abcd")
>>> s.find_longest_match(0, 5, 0, 9)
Match(a=0, b=4, size=5)
```

If *isjunk* was provided, first the longest matching block is determined as above, but with the additional restriction that no junk element appears in the block. Then that block is extended as far as possible by matching

(only) junk elements on both sides. So the resulting block never matches on junk except as identical junk happens to be adjacent to an interesting match.

Here's the same example as before, but considering blanks to be junk. That prevents ' abcd' from matching the ' abcd' at the tail end of the second sequence directly. Instead only the 'abcd' can match, and matches the leftmost 'abcd' in the second sequence:

```
>>> s = SequenceMatcher(lambda x: x==" ", " abcd", "abcd abcd")
>>> s.find_longest_match(0, 5, 0, 9)
Match(a=1, b=0, size=4)
```

If no blocks match, this returns (a_{lo}, b_{lo}, 0).

버전 2.6에서 변경: This method returns a *named tuple* Match(a, b, size).

get_matching_blocks()

Return list of triples describing non-overlapping matching subsequences. Each triple is of the form (i, j, n), and means that a[i:i+n] == b[j:j+n]. The triples are monotonically increasing in i and j.

The last triple is a dummy, and has the value (len(a), len(b), 0). It is the only triple with n == 0. If (i, j, n) and (i', j', n') are adjacent triples in the list, and the second is not the last triple in the list, then i+n < i' or j+n < j'; in other words, adjacent triples always describe non-adjacent equal blocks.

버전 2.5에서 변경: The guarantee that adjacent triples always describe non-adjacent blocks was implemented.

```
>>> s = SequenceMatcher(None, "abxcd", "abcd")
>>> s.get_matching_blocks()
[Match(a=0, b=0, size=2), Match(a=3, b=2, size=2), Match(a=5, b=4, size=0)]
```

get_opcodes()

Return list of 5-tuples describing how to turn a into b. Each tuple is of the form (tag, i1, i2, j1, j2). The first tuple has i1 == j1 == 0, and remaining tuples have i1 equal to the i2 from the preceding tuple, and, likewise, j1 equal to the previous j2.

The tag values are strings, with these meanings:

Value	Meaning
'replace'	a[i1:i2] should be replaced by b[j1:j2].
'delete'	a[i1:i2] should be deleted. Note that j1 == j2 in this case.
'insert'	b[j1:j2] should be inserted at a[i1:i1]. Note that i1 == i2 in this case.
'equal'	a[i1:i2] == b[j1:j2] (the sub-sequences are equal).

For example:

```
>>> a = "qabxcd"
>>> b = "abycdf"
>>> s = SequenceMatcher(None, a, b)
>>> for tag, i1, i2, j1, j2 in s.get_opcodes():
...     print ("%7s a[%d:%d] (%s) b[%d:%d] (%s)" %
...             (tag, i1, i2, a[i1:i2], j1, j2, b[j1:j2]))
delete a[0:1] (q) b[0:0] ()
equal a[1:3] (ab) b[0:2] (ab)
replace a[3:4] (x) b[2:3] (y)
equal a[4:6] (cd) b[3:5] (cd)
insert a[6:6] () b[5:6] (f)
```

get_grouped_opcodes (*n*)

Return a *generator* of groups with up to *n* lines of context.

Starting with the groups returned by *get_opcodes* (), this method splits out smaller change clusters and eliminates intervening ranges which have no changes.

The groups are returned in the same format as *get_opcodes* ().

버전 2.3에 추가.

ratio ()

Return a measure of the sequences' similarity as a float in the range [0, 1].

Where T is the total number of elements in both sequences, and M is the number of matches, this is $2.0 * M / T$. Note that this is 1.0 if the sequences are identical, and 0.0 if they have nothing in common.

This is expensive to compute if *get_matching_blocks* () or *get_opcodes* () hasn't already been called, in which case you may want to try *quick_ratio* () or *real_quick_ratio* () first to get an upper bound.

quick_ratio ()

Return an upper bound on *ratio* () relatively quickly.

real_quick_ratio ()

Return an upper bound on *ratio* () very quickly.

The three methods that return the ratio of matching to total characters can give different results due to differing levels of approximation, although *quick_ratio* () and *real_quick_ratio* () are always at least as large as *ratio* ():

```
>>> s = SequenceMatcher(None, "abcd", "bcde")
>>> s.ratio()
0.75
>>> s.quick_ratio()
0.75
>>> s.real_quick_ratio()
1.0
```

7.4.2 SequenceMatcher Examples

This example compares two strings, considering blanks to be «junk»:

```
>>> s = SequenceMatcher(lambda x: x == " ",
...                       "private Thread currentThread;",
...                       "private volatile Thread currentThread;")
```

ratio () returns a float in [0, 1], measuring the similarity of the sequences. As a rule of thumb, a *ratio* () value over 0.6 means the sequences are close matches:

```
>>> print round(s.ratio(), 3)
0.866
```

If you're only interested in where the sequences match, *get_matching_blocks* () is handy:

```
>>> for block in s.get_matching_blocks():
...     print "a[%d] and b[%d] match for %d elements" % block
a[0] and b[0] match for 8 elements
a[8] and b[17] match for 21 elements
a[29] and b[38] match for 0 elements
```

Note that the last tuple returned by `get_matching_blocks()` is always a dummy, `(len(a), len(b), 0)`, and this is the only case in which the last tuple element (number of elements matched) is 0.

If you want to know how to change the first sequence into the second, use `get_opcodes()`:

```
>>> for opcode in s.get_opcodes():
...     print "%6s a[%d:%d] b[%d:%d]" % opcode
equal a[0:8] b[0:8]
insert a[8:8] b[8:17]
equal a[8:29] b[17:38]
```

더 보기:

- The `get_close_matches()` function in this module which shows how simple code building on `SequenceMatcher` can be used to do useful work.
- Simple version control recipe for a small application built with `SequenceMatcher`.

7.4.3 Differ Objects

Note that `Differ`-generated deltas make no claim to be **minimal** diffs. To the contrary, minimal diffs are often counter-intuitive, because they synch up anywhere possible, sometimes accidental matches 100 pages apart. Restricting synch points to contiguous matches preserves some notion of locality, at the occasional cost of producing a longer diff.

The `Differ` class has this constructor:

```
class difflib.Differ([linejunk[, charjunk]])
```

Optional keyword parameters `linejunk` and `charjunk` are for filter functions (or `None`):

`linejunk`: A function that accepts a single string argument, and returns true if the string is junk. The default is `None`, meaning that no line is considered junk.

`charjunk`: A function that accepts a single character argument (a string of length 1), and returns true if the character is junk. The default is `None`, meaning that no character is considered junk.

`Differ` objects are used (deltas generated) via a single method:

```
compare(a, b)
```

Compare two sequences of lines, and generate the delta (a sequence of lines).

Each sequence must contain individual single-line strings ending with newlines. Such sequences can be obtained from the `readlines()` method of file-like objects. The delta generated also consists of newline-terminated strings, ready to be printed as-is via the `writelines()` method of a file-like object.

7.4.4 Differ Example

This example compares two texts. First we set up the texts, sequences of individual single-line strings ending with newlines (such sequences can also be obtained from the `readlines()` method of file-like objects):

```
>>> text1 = ''' 1. Beautiful is better than ugly.
... 2. Explicit is better than implicit.
... 3. Simple is better than complex.
... 4. Complex is better than complicated.
... '''.splitlines(1)
>>> len(text1)
4
>>> text1[0][-1]
'\n'
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> text2 = ''' 1. Beautiful is better than ugly.
... 3.   Simple is better than complex.
... 4. Complicated is better than complex.
... 5. Flat is better than nested.
... '''.splitlines(1)
```

Next we instantiate a `Differ` object:

```
>>> d = Differ()
```

Note that when instantiating a `Differ` object we may pass functions to filter out line and character «junk.» See the `Differ()` constructor for details.

Finally, we compare the two:

```
>>> result = list(d.compare(text1, text2))
```

`result` is a list of strings, so let's pretty-print it:

```
>>> from pprint import pprint
>>> pprint(result)
[' 1. Beautiful is better than ugly.\n',
'- 2. Explicit is better than implicit.\n',
'- 3. Simple is better than complex.\n',
'+ 3.   Simple is better than complex.\n',
'?   ++\n',
'- 4. Complex is better than complicated.\n',
'?      ^          ---- ^\n',
'+ 4. Complicated is better than complex.\n',
'?      ++++ ^          ^\n',
'+ 5. Flat is better than nested.\n']
```

As a single multi-line string it looks like this:

```
>>> import sys
>>> sys.stdout.writelines(result)
 1. Beautiful is better than ugly.
- 2. Explicit is better than implicit.
- 3. Simple is better than complex.
+ 3.   Simple is better than complex.
?   ++
- 4. Complex is better than complicated.
?      ^          ---- ^
+ 4. Complicated is better than complex.
?      ++++ ^          ^
+ 5. Flat is better than nested.
```

7.4.5 A command-line interface to difflib

This example shows how to use difflib to create a diff-like utility. It is also contained in the Python source distribution, as Tools/scripts/diff.py.

```
""" Command line interface to difflib.py providing diffs in four formats:

* ndiff:    lists every line and highlights interline changes.
* context:  highlights clusters of changes in a before/after format.
* unified:  highlights clusters of changes in an inline format.
* html:     generates side by side comparison with change highlights.

"""

import sys, os, time, difflib, optparse

def main():
    # Configure the option parser
    usage = "usage: %prog [options] fromfile tofile"
    parser = optparse.OptionParser(usage)
    parser.add_option("-c", action="store_true", default=False,
                      help='Produce a context format diff (default)')
    parser.add_option("-u", action="store_true", default=False,
                      help='Produce a unified format diff')
    hlp = 'Produce HTML side by side diff (can use -c and -l in conjunction)'
    parser.add_option("-m", action="store_true", default=False, help=hlp)
    parser.add_option("-n", action="store_true", default=False,
                      help='Produce a ndiff format diff')
    parser.add_option("-l", "--lines", type="int", default=3,
                      help='Set number of context lines (default 3)')
    (options, args) = parser.parse_args()

    if len(args) == 0:
        parser.print_help()
        sys.exit(1)
    if len(args) != 2:
        parser.error("need to specify both a fromfile and tofile")

    n = options.lines
    fromfile, tofile = args # as specified in the usage string

    # we're passing these as arguments to the diff function
    fromdate = time.ctime(os.stat(fromfile).st_mtime)
    todater = time.ctime(os.stat(tofile).st_mtime)
    with open(fromfile, 'U') as f:
        fromlines = f.readlines()
    with open(tofile, 'U') as f:
        tolines = f.readlines()

    if options.u:
        diff = difflib.unified_diff(fromlines, tolines, fromfile, tofile,
                                    fromdate, todater, n=n)
    elif options.n:
        diff = difflib.ndiff(fromlines, tolines)
    elif options.m:
        diff = difflib.HtmlDiff().make_file(fromlines, tolines, fromfile,
                                              tofile, context=options.c,
                                              numlines=n)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

else:
    diff = difflib.context_diff(fromlines, tolines, fromfile, tofile,
                                fromdate, todate, n=n)

    # we're using writelines because diff is a generator
    sys.stdout.writelines(diff)

if __name__ == '__main__':
    main()

```

7.5 StringIO — Read and write strings as files

This module implements a file-like class, *StringIO*, that reads and writes a string buffer (also known as *memory files*). See the description of file objects for operations (section *File Objects*). (For standard strings, see *str* and *unicode*.)

class StringIO.**StringIO**([*buffer*])

When a *StringIO* object is created, it can be initialized to an existing string by passing the string to the constructor. If no string is given, the *StringIO* will start empty. In both cases, the initial file position starts at zero.

The *StringIO* object can accept either Unicode or 8-bit strings, but mixing the two may take some care. If both are used, 8-bit strings that cannot be interpreted as 7-bit ASCII (that use the 8th bit) will cause a *UnicodeError* to be raised when *getvalue()* is called.

The following methods of *StringIO* objects require special mention:

StringIO.**getvalue**()

Retrieve the entire contents of the «file» at any time before the *StringIO* object's *close()* method is called. See the note above for information about mixing Unicode and 8-bit strings; such mixing can cause this method to raise *UnicodeError*.

StringIO.**close**()

Free the memory buffer. Attempting to do further operations with a closed *StringIO* object will raise a *ValueError*.

Example usage:

```

import StringIO

output = StringIO.StringIO()
output.write('First line.\n')
print >>output, 'Second line.'

# Retrieve file contents -- this will be
# 'First line.\nSecond line.\n'
contents = output.getvalue()

# Close object and discard memory buffer --
# .getvalue() will now raise an exception.
output.close()

```

7.6 cStringIO — Faster version of StringIO

The module *cStringIO* provides an interface similar to that of the *StringIO* module. Heavy use of *StringIO*. *StringIO* objects can be made more efficient by using the function *StringIO()* from this module instead.

`cStringIO.StringIO([s])`

Return a StringIO-like stream for reading or writing.

Since this is a factory function which returns objects of built-in types, there's no way to build your own version using subclassing. It's not possible to set attributes on it. Use the original *StringIO* module in those cases.

Unlike the *StringIO* module, this module is not able to accept Unicode strings that cannot be encoded as plain ASCII strings.

Another difference from the *StringIO* module is that calling *StringIO()* with a string parameter creates a read-only object. Unlike an object created without a string parameter, it does not have write methods. These objects are not generally visible. They turn up in tracebacks as *StringI* and *StringO*.

The following data objects are provided as well:

`cStringIO.InputType`

The type object of the objects created by calling *StringIO()* with a string parameter.

`cStringIO.OutputType`

The type object of the objects returned by calling *StringIO()* with no parameters.

There is a C API to the module as well; refer to the module source for more information.

Example usage:

```
import cStringIO

output = cStringIO.StringIO()
output.write('First line.\n')
print >>output, 'Second line.'

# Retrieve file contents -- this will be
# 'First line.\nSecond line.\n'
contents = output.getvalue()

# Close object and discard memory buffer --
# .getvalue() will now raise an exception.
output.close()
```

7.7 textwrap — Text wrapping and filling

버전 2.3에 추가.

Source code: `Lib/textwrap.py`

The *textwrap* module provides two convenience functions, *wrap()* and *fill()*, as well as *TextWrapper*, the class that does all the work, and a utility function *dedent()*. If you're just wrapping or filling one or two text strings, the convenience functions should be good enough; otherwise, you should use an instance of *TextWrapper* for efficiency.

`textwrap.wrap(text[, width[, ...]])`

Wraps the single paragraph in *text* (a string) so every line is at most *width* characters long. Returns a list of output lines, without final newlines.

Optional keyword arguments correspond to the instance attributes of *TextWrapper*, documented below. *width* defaults to 70.

See the *TextWrapper.wrap()* method for additional details on how *wrap()* behaves.

`textwrap.fill(text[, width[, ...]])`

Wraps the single paragraph in *text*, and returns a single string containing the wrapped paragraph. *fill()* is shorthand for

```
"\n".join(wrap(text, ...))
```

In particular, *fill()* accepts exactly the same keyword arguments as *wrap()*.

Both *wrap()* and *fill()* work by creating a *TextWrapper* instance and calling a single method on it. That instance is not reused, so for applications that wrap/fill many text strings, it will be more efficient for you to create your own *TextWrapper* object.

Text is preferably wrapped on whitespaces and right after the hyphens in hyphenated words; only then will long words be broken if necessary, unless *TextWrapper.break_long_words* is set to false.

An additional utility function, *dedent()*, is provided to remove indentation from strings that have unwanted whitespace to the left of the text.

`textwrap.dedent(text)`

Remove any common leading whitespace from every line in *text*.

This can be used to make triple-quoted strings line up with the left edge of the display, while still presenting them in the source code in indented form.

Note that tabs and spaces are both treated as whitespace, but they are not equal: the lines " hello" and "\thello" are considered to have no common leading whitespace. (This behaviour is new in Python 2.5; older versions of this module incorrectly expanded tabs before searching for common leading whitespace.)

Lines containing only whitespace are ignored in the input and normalized to a single newline character in the output.

For example:

```
def test():
    # end first line with \ to avoid the empty line!
    s = '''\
hello
    world
'''
    print repr(s)          # prints 'hello\n    world\n'
    print repr(dedent(s))  # prints 'hello\nworld\n'
```

class `textwrap.TextWrapper(...)`

The *TextWrapper* constructor accepts a number of optional keyword arguments. Each argument corresponds to one instance attribute, so for example

```
wrapper = TextWrapper(initial_indent="* ")
```

is the same as

```
wrapper = TextWrapper()
wrapper.initial_indent = "* "
```

You can re-use the same *TextWrapper* object many times, and you can change any of its options through direct assignment to instance attributes between uses.

The *TextWrapper* instance attributes (and keyword arguments to the constructor) are as follows:

width

(default: 70) The maximum length of wrapped lines. As long as there are no individual words in the input text longer than *width*, *TextWrapper* guarantees that no output line will be longer than *width* characters.

expand_tabs

(default: True) If true, then all tab characters in *text* will be expanded to spaces using the `expandtabs()` method of *text*.

replace_whitespace

(default: True) If true, after tab expansion but before wrapping, the `wrap()` method will replace each whitespace character with a single space. The whitespace characters replaced are as follows: tab, newline, vertical tab, formfeed, and carriage return (`'\t\n\v\f\r'`).

참고: If *expand_tabs* is false and *replace_whitespace* is true, each tab character will be replaced by a single space, which is *not* the same as tab expansion.

참고: If *replace_whitespace* is false, newlines may appear in the middle of a line and cause strange output. For this reason, text should be split into paragraphs (using `str.splitlines()` or similar) which are wrapped separately.

drop_whitespace

(default: True) If true, whitespace at the beginning and ending of every line (after wrapping but before indenting) is dropped. Whitespace at the beginning of the paragraph, however, is not dropped if non-whitespace follows it. If whitespace being dropped takes up an entire line, the whole line is dropped.

버전 2.6에 추가: Whitespace was always dropped in earlier versions.

initial_indent

(default: `' '`) String that will be prepended to the first line of wrapped output. Counts towards the length of the first line. The empty string is not indented.

subsequent_indent

(default: `' '`) String that will be prepended to all lines of wrapped output except the first. Counts towards the length of each line except the first.

fix_sentence_endings

(default: False) If true, *TextWrapper* attempts to detect sentence endings and ensure that sentences are always separated by exactly two spaces. This is generally desired for text in a monospaced font. However, the sentence detection algorithm is imperfect: it assumes that a sentence ending consists of a lowercase letter followed by one of `'.'`, `'!'`, or `'?'`, possibly followed by one of `'\"'` or `'\"'`, followed by a space. One problem with this algorithm is that it is unable to detect the difference between `«Dr.»` in

```
[...] Dr. Frankenstein's monster [...]
```

and `«Spot.»` in

```
[...] See Spot. See Spot run [...]
```

fix_sentence_endings is false by default.

Since the sentence detection algorithm relies on `string.lowercase` for the definition of `«lowercase letter, »` and a convention of using two spaces after a period to separate sentences on the same line, it is specific to English-language texts.

break_long_words

(default: True) If true, then words longer than *width* will be broken in order to ensure that no lines are

longer than *width*. If it is false, long words will not be broken, and some lines may be longer than *width*. (Long words will be put on a line by themselves, in order to minimize the amount by which *width* is exceeded.)

break_on_hyphens

(default: `True`) If true, wrapping will occur preferably on whitespaces and right after hyphens in compound words, as it is customary in English. If false, only whitespaces will be considered as potentially good places for line breaks, but you need to set *break_long_words* to false if you want truly insecable words. Default behaviour in previous versions was to always allow breaking hyphenated words.

버전 2.6에 추가.

TextWrapper also provides two public methods, analogous to the module-level convenience functions:

wrap (*text*)

Wraps the single paragraph in *text* (a string) so every line is at most *width* characters long. All wrapping options are taken from instance attributes of the *TextWrapper* instance. Returns a list of output lines, without final newlines. If the wrapped output has no content, the returned list is empty.

fill (*text*)

Wraps the single paragraph in *text*, and returns a single string containing the wrapped paragraph.

7.8 codecs — Codec registry and base classes

This module defines base classes for standard Python codecs (encoders and decoders) and provides access to the internal Python codec registry which manages the codec and error handling lookup process.

It defines the following functions:

`codecs.encode` (*obj*[, *encoding*[, *errors*]])

Encodes *obj* using the codec registered for *encoding*. The default encoding is 'ascii'.

Errors may be given to set the desired error handling scheme. The default error handler is 'strict' meaning that encoding errors raise *ValueError* (or a more codec specific subclass, such as *UnicodeEncodeError*). Refer to *Codec Base Classes* for more information on codec error handling.

버전 2.4에 추가.

`codecs.decode` (*obj*[, *encoding*[, *errors*]])

Decodes *obj* using the codec registered for *encoding*. The default encoding is 'ascii'.

Errors may be given to set the desired error handling scheme. The default error handler is 'strict' meaning that decoding errors raise *ValueError* (or a more codec specific subclass, such as *UnicodeDecodeError*). Refer to *Codec Base Classes* for more information on codec error handling.

버전 2.4에 추가.

`codecs.register` (*search_function*)

Register a codec search function. Search functions are expected to take one argument, the encoding name in all lower case letters, and return a *CodecInfo* object having the following attributes:

- *name* The name of the encoding;
- *encode* The stateless encoding function;
- *decode* The stateless decoding function;
- *incrementalencoder* An incremental encoder class or factory function;
- *incrementaldecoder* An incremental decoder class or factory function;
- *streamwriter* A stream writer class or factory function;

- `streamreader` A stream reader class or factory function.

The various functions or classes take the following arguments:

encode and *decode*: These must be functions or methods which have the same interface as the *encode()*/*decode()* methods of Codec instances (see *Codec Interface*). The functions/methods are expected to work in a stateless mode.

incrementalencoder and *incrementaldecoder*: These have to be factory functions providing the following interface:

```
factory(errors='strict')
```

The factory functions must return objects providing the interfaces defined by the base classes *IncrementalEncoder* and *IncrementalDecoder*, respectively. Incremental codecs can maintain state.

streamreader and *streamwriter*: These have to be factory functions providing the following interface:

```
factory(stream, errors='strict')
```

The factory functions must return objects providing the interfaces defined by the base classes *StreamReader* and *StreamWriter*, respectively. Stream codecs can maintain state.

Possible values for errors are

- 'strict': raise an exception in case of an encoding error
- 'replace': replace malformed data with a suitable replacement marker, such as '?' or '\ufffd'
- 'ignore': ignore malformed data and continue without further notice
- 'xmlcharrefreplace': replace with the appropriate XML character reference (for encoding only)
- 'backslashreplace': replace with backslashed escape sequences (for encoding only)

as well as any other error handling name defined via *register_error()*.

In case a search function cannot find a given encoding, it should return `None`.

`codecs.lookup(encoding)`

Looks up the codec info in the Python codec registry and returns a *CodecInfo* object as defined above.

Encodings are first looked up in the registry's cache. If not found, the list of registered search functions is scanned. If no *CodecInfo* object is found, a *LookupError* is raised. Otherwise, the *CodecInfo* object is stored in the cache and returned to the caller.

To simplify access to the various codecs, the module provides these additional functions which use *lookup()* for the codec lookup:

`codecs.getencoder(encoding)`

Look up the codec for the given encoding and return its encoder function.

Raises a *LookupError* in case the encoding cannot be found.

`codecs.getdecoder(encoding)`

Look up the codec for the given encoding and return its decoder function.

Raises a *LookupError* in case the encoding cannot be found.

`codecs.getincrementalencoder(encoding)`

Look up the codec for the given encoding and return its incremental encoder class or factory function.

Raises a *LookupError* in case the encoding cannot be found or the codec doesn't support an incremental encoder.

버전 2.5에 추가.

`codecs.getincrementaldecoder(encoding)`

Look up the codec for the given encoding and return its incremental decoder class or factory function.

Raises a `LookupError` in case the encoding cannot be found or the codec doesn't support an incremental decoder.

버전 2.5에 추가.

`codecs.getreader(encoding)`

Look up the codec for the given encoding and return its `StreamReader` class or factory function.

Raises a `LookupError` in case the encoding cannot be found.

`codecs.getwriter(encoding)`

Look up the codec for the given encoding and return its `StreamWriter` class or factory function.

Raises a `LookupError` in case the encoding cannot be found.

`codecs.register_error(name, error_handler)`

Register the error handling function `error_handler` under the name `name`. `error_handler` will be called during encoding and decoding in case of an error, when `name` is specified as the `errors` parameter.

For encoding `error_handler` will be called with a `UnicodeEncodeError` instance, which contains information about the location of the error. The error handler must either raise this or a different exception or return a tuple with a replacement for the unencodable part of the input and a position where encoding should continue. The encoder will encode the replacement and continue encoding the original input at the specified position. Negative position values will be treated as being relative to the end of the input string. If the resulting position is out of bound an `IndexError` will be raised.

Decoding and translating works similar, except `UnicodeDecodeError` or `UnicodeTranslateError` will be passed to the handler and that the replacement from the error handler will be put into the output directly.

`codecs.lookup_error(name)`

Return the error handler previously registered under the name `name`.

Raises a `LookupError` in case the handler cannot be found.

`codecs.strict_errors(exception)`

Implements the `strict` error handling: each encoding or decoding error raises a `UnicodeError`.

`codecs.replace_errors(exception)`

Implements the `replace` error handling: malformed data is replaced with a suitable replacement character such as `'?'` in bytestrings and `'\ufffd'` in Unicode strings.

`codecs.ignore_errors(exception)`

Implements the `ignore` error handling: malformed data is ignored and encoding or decoding is continued without further notice.

`codecs.xmlcharrefreplace_errors(exception)`

Implements the `xmlcharrefreplace` error handling (for encoding only): the unencodable character is replaced by an appropriate XML character reference.

`codecs.backslashreplace_errors(exception)`

Implements the `backslashreplace` error handling (for encoding only): the unencodable character is replaced by a backslashed escape sequence.

To simplify working with encoded files or stream, the module also defines these utility functions:

`codecs.open(filename, mode[, encoding[, errors[, buffering]]])`

Open an encoded file using the given `mode` and return a wrapped version providing transparent encoding/decoding. The default file mode is `'r'` meaning to open the file in read mode.

참고: The wrapped version will only accept the object format defined by the codecs, i.e. Unicode objects for most built-in codecs. Output is also codec-dependent and will usually be Unicode as well.

참고: Files are always opened in binary mode, even if no binary mode was specified. This is done to avoid data loss due to encodings using 8-bit values. This means that no automatic conversion of `'\n'` is done on reading and writing.

encoding specifies the encoding which is to be used for the file.

errors may be given to define the error handling. It defaults to `'strict'` which causes a `ValueError` to be raised in case an encoding error occurs.

buffering has the same meaning as for the built-in `open()` function. It defaults to line buffered.

`codecs.EncodedFile` (*file*, *input*[, *output*[, *errors*]])

Return a wrapped version of file which provides transparent encoding translation.

Strings written to the wrapped file are interpreted according to the given *input* encoding and then written to the original file as strings using the *output* encoding. The intermediate encoding will usually be Unicode but depends on the specified codecs.

If *output* is not given, it defaults to *input*.

errors may be given to define the error handling. It defaults to `'strict'`, which causes `ValueError` to be raised in case an encoding error occurs.

`codecs.iterencode` (*iterable*, *encoding*[, *errors*])

Uses an incremental encoder to iteratively encode the input provided by *iterable*. This function is a *generator*. *errors* (as well as any other keyword argument) is passed through to the incremental encoder.

버전 2.5에 추가.

`codecs.iterdecode` (*iterable*, *encoding*[, *errors*])

Uses an incremental decoder to iteratively decode the input provided by *iterable*. This function is a *generator*. *errors* (as well as any other keyword argument) is passed through to the incremental decoder.

버전 2.5에 추가.

The module also provides the following constants which are useful for reading and writing to platform dependent files:

```
codecs.BOM
codecs.BOM_BE
codecs.BOM_LE
codecs.BOM_UTF8
codecs.BOM_UTF16
codecs.BOM_UTF16_BE
codecs.BOM_UTF16_LE
codecs.BOM_UTF32
codecs.BOM_UTF32_BE
codecs.BOM_UTF32_LE
```

These constants define various encodings of the Unicode byte order mark (BOM) used in UTF-16 and UTF-32 data streams to indicate the byte order used in the stream or file and in UTF-8 as a Unicode signature. `BOM_UTF16` is either `BOM_UTF16_BE` or `BOM_UTF16_LE` depending on the platform's native byte order, `BOM` is an alias for `BOM_UTF16`, `BOM_LE` for `BOM_UTF16_LE` and `BOM_BE` for `BOM_UTF16_BE`. The others represent the BOM in UTF-8 and UTF-32 encodings.

7.8.1 Codec Base Classes

The `codecs` module defines a set of base classes which define the interface and can also be used to easily write your own codecs for use in Python.

Each codec has to define four interfaces to make it usable as codec in Python: stateless encoder, stateless decoder, stream reader and stream writer. The stream reader and writers typically reuse the stateless encoder/decoder to implement the file protocols.

The `Codec` class defines the interface for stateless encoders/decoders.

To simplify and standardize error handling, the `encode()` and `decode()` methods may implement different error handling schemes by providing the `errors` string argument. The following string values are defined and implemented by all standard Python codecs:

Value	Meaning
'strict'	Raise <code>UnicodeError</code> (or a subclass); this is the default.
'ignore'	Ignore the character and continue with the next.
'replace'	Replace with a suitable replacement character; Python will use the official U+FFFD REPLACEMENT CHARACTER for the built-in Unicode codecs on decoding and <code><?></code> on encoding.
'xmlcharrefreplace'	Replace with the appropriate XML character reference (only for encoding).
'backslashreplace'	Replace with backslashed escape sequences (only for encoding).

The set of allowed values can be extended via `register_error()`.

Codec Objects

The `Codec` class defines these methods which also define the function interfaces of the stateless encoder and decoder:

`Codec.encode(input[, errors])`

Encodes the object `input` and returns a tuple (output object, length consumed). While codecs are not restricted to use with Unicode, in a Unicode context, encoding converts a Unicode object to a plain string using a particular character set encoding (e.g., cp1252 or iso-8859-1).

`errors` defines the error handling to apply. It defaults to 'strict' handling.

The method may not store state in the `Codec` instance. Use `StreamWriter` for codecs which have to keep state in order to make encoding efficient.

The encoder must be able to handle zero length input and return an empty object of the output object type in this situation.

`Codec.decode(input[, errors])`

Decodes the object `input` and returns a tuple (output object, length consumed). In a Unicode context, decoding converts a plain string encoded using a particular character set encoding to a Unicode object.

`input` must be an object which provides the `bf_getreadbuf` buffer slot. Python strings, buffer objects and memory mapped files are examples of objects providing this slot.

`errors` defines the error handling to apply. It defaults to 'strict' handling.

The method may not store state in the `Codec` instance. Use `StreamReader` for codecs which have to keep state in order to make decoding efficient.

The decoder must be able to handle zero length input and return an empty object of the output object type in this situation.

The *IncrementalEncoder* and *IncrementalDecoder* classes provide the basic interface for incremental encoding and decoding. Encoding/decoding the input isn't done with one call to the stateless encoder/decoder function, but with multiple calls to the *encode()*/*decode()* method of the incremental encoder/decoder. The incremental encoder/decoder keeps track of the encoding/decoding process during method calls.

The joined output of calls to the *encode()*/*decode()* method is the same as if all the single inputs were joined into one, and this input was encoded/decoded with the stateless encoder/decoder.

IncrementalEncoder Objects

버전 2.5에 추가.

The *IncrementalEncoder* class is used for encoding an input in multiple steps. It defines the following methods which every incremental encoder must define in order to be compatible with the Python codec registry.

class `codecs.IncrementalEncoder` (*errors*)

Constructor for an *IncrementalEncoder* instance.

All incremental encoders must provide this constructor interface. They are free to add additional keyword arguments, but only the ones defined here are used by the Python codec registry.

The *IncrementalEncoder* may implement different error handling schemes by providing the *errors* keyword argument. These parameters are predefined:

- 'strict' Raise *ValueError* (or a subclass); this is the default.
- 'ignore' Ignore the character and continue with the next.
- 'replace' Replace with a suitable replacement character
- 'xmlcharrefreplace' Replace with the appropriate XML character reference
- 'backslashreplace' Replace with backslashed escape sequences.

The *errors* argument will be assigned to an attribute of the same name. Assigning to this attribute makes it possible to switch between different error handling strategies during the lifetime of the *IncrementalEncoder* object.

The set of allowed values for the *errors* argument can be extended with *register_error()*.

encode (*object* [, *final*])

Encodes *object* (taking the current state of the encoder into account) and returns the resulting encoded object. If this is the last call to *encode()* *final* must be true (the default is false).

reset ()

Reset the encoder to the initial state.

IncrementalDecoder Objects

The *IncrementalDecoder* class is used for decoding an input in multiple steps. It defines the following methods which every incremental decoder must define in order to be compatible with the Python codec registry.

class `codecs.IncrementalDecoder` (*errors*)

Constructor for an *IncrementalDecoder* instance.

All incremental decoders must provide this constructor interface. They are free to add additional keyword arguments, but only the ones defined here are used by the Python codec registry.

The *IncrementalDecoder* may implement different error handling schemes by providing the *errors* keyword argument. These parameters are predefined:

- 'strict' Raise *ValueError* (or a subclass); this is the default.

- 'ignore' Ignore the character and continue with the next.
- 'replace' Replace with a suitable replacement character.

The *errors* argument will be assigned to an attribute of the same name. Assigning to this attribute makes it possible to switch between different error handling strategies during the lifetime of the *IncrementalDecoder* object.

The set of allowed values for the *errors* argument can be extended with *register_error()*.

decode (*object* [, *final*])

Decodes *object* (taking the current state of the decoder into account) and returns the resulting decoded object. If this is the last call to *decode()* *final* must be true (the default is false). If *final* is true the decoder must decode the input completely and must flush all buffers. If this isn't possible (e.g. because of incomplete byte sequences at the end of the input) it must initiate error handling just like in the stateless case (which might raise an exception).

reset ()

Reset the decoder to the initial state.

The *StreamWriter* and *StreamReader* classes provide generic working interfaces which can be used to implement new encoding submodules very easily. See `encodings.utf_8` for an example of how this is done.

StreamWriter Objects

The *StreamWriter* class is a subclass of *Codec* and defines the following methods which every stream writer must define in order to be compatible with the Python codec registry.

class `codecs.StreamWriter` (*stream* [, *errors*])

Constructor for a *StreamWriter* instance.

All stream writers must provide this constructor interface. They are free to add additional keyword arguments, but only the ones defined here are used by the Python codec registry.

stream must be a file-like object open for writing binary data.

The *StreamWriter* may implement different error handling schemes by providing the *errors* keyword argument. These parameters are predefined:

- 'strict' Raise *ValueError* (or a subclass); this is the default.
- 'ignore' Ignore the character and continue with the next.
- 'replace' Replace with a suitable replacement character
- 'xmlcharrefreplace' Replace with the appropriate XML character reference
- 'backslashreplace' Replace with backslashed escape sequences.

The *errors* argument will be assigned to an attribute of the same name. Assigning to this attribute makes it possible to switch between different error handling strategies during the lifetime of the *StreamWriter* object.

The set of allowed values for the *errors* argument can be extended with *register_error()*.

write (*object*)

Writes the object's contents encoded to the stream.

writelines (*list*)

Writes the concatenated list of strings to the stream (possibly by reusing the *write()* method).

reset ()

Flushes and resets the codec buffers used for keeping state.

Calling this method should ensure that the data on the output is put into a clean state that allows appending of new fresh data without having to rescan the whole stream to recover state.

In addition to the above methods, the *StreamWriter* must also inherit all other methods and attributes from the underlying stream.

StreamReader Objects

The *StreamReader* class is a subclass of *Codec* and defines the following methods which every stream reader must define in order to be compatible with the Python codec registry.

class `codecs.StreamReader` (*stream*[, *errors*])
Constructor for a *StreamReader* instance.

All stream readers must provide this constructor interface. They are free to add additional keyword arguments, but only the ones defined here are used by the Python codec registry.

stream must be a file-like object open for reading (binary) data.

The *StreamReader* may implement different error handling schemes by providing the *errors* keyword argument. These parameters are defined:

- 'strict' Raise *ValueError* (or a subclass); this is the default.
- 'ignore' Ignore the character and continue with the next.
- 'replace' Replace with a suitable replacement character.

The *errors* argument will be assigned to an attribute of the same name. Assigning to this attribute makes it possible to switch between different error handling strategies during the lifetime of the *StreamReader* object.

The set of allowed values for the *errors* argument can be extended with *register_error()*.

read ([*size*[, *chars*[, *firstline*]]])

Decodes data from the stream and returns the resulting object.

chars indicates the number of characters to read from the stream. *read()* will never return more than *chars* characters, but it might return less, if there are not enough characters available.

size indicates the approximate maximum number of bytes to read from the stream for decoding purposes. The decoder can modify this setting as appropriate. The default value -1 indicates to read and decode as much as possible. *size* is intended to prevent having to decode huge files in one step.

firstline indicates that it would be sufficient to only return the first line, if there are decoding errors on later lines.

The method should use a greedy read strategy meaning that it should read as much data as is allowed within the definition of the encoding and the given size, e.g. if optional encoding endings or state markers are available on the stream, these should be read too.

버전 2.4에서 변경: *chars* argument added.

버전 2.4.2에서 변경: *firstline* argument added.

readline ([*size*[, *keepends*]])

Read one line from the input stream and return the decoded data.

size, if given, is passed as size argument to the stream's *read()* method.

If *keepends* is false line-endings will be stripped from the lines returned.

버전 2.4에서 변경: *keepends* argument added.

readlines ([*sizehint*[, *keepends*]])

Read all lines available on the input stream and return them as a list of lines.

Line-endings are implemented using the codec's decoder method and are included in the list entries if *keep-ends* is true.

sizehint, if given, is passed as the *size* argument to the stream's *read()* method.

reset()

Resets the codec buffers used for keeping state.

Note that no stream repositioning should take place. This method is primarily intended to be able to recover from decoding errors.

In addition to the above methods, the *StreamReader* must also inherit all other methods and attributes from the underlying stream.

The next two base classes are included for convenience. They are not needed by the codec registry, but may provide useful in practice.

StreamReaderWriter Objects

The *StreamReaderWriter* allows wrapping streams which work in both read and write modes.

The design is such that one can use the factory functions returned by the *lookup()* function to construct the instance.

class `codecs.StreamReaderWriter` (*stream*, *Reader*, *Writer*, *errors*)

Creates a *StreamReaderWriter* instance. *stream* must be a file-like object. *Reader* and *Writer* must be factory functions or classes providing the *StreamReader* and *StreamWriter* interface resp. Error handling is done in the same way as defined for the stream readers and writers.

StreamReaderWriter instances define the combined interfaces of *StreamReader* and *StreamWriter* classes. They inherit all other methods and attributes from the underlying stream.

StreamRecoder Objects

The *StreamRecoder* provide a frontend - backend view of encoding data which is sometimes useful when dealing with different encoding environments.

The design is such that one can use the factory functions returned by the *lookup()* function to construct the instance.

class `codecs.StreamRecoder` (*stream*, *encode*, *decode*, *Reader*, *Writer*, *errors*)

Creates a *StreamRecoder* instance which implements a two-way conversion: *encode* and *decode* work on the frontend (the input to *read()* and output of *write()*) while *Reader* and *Writer* work on the backend (reading and writing to the stream).

You can use these objects to do transparent direct recodings from e.g. Latin-1 to UTF-8 and back.

stream must be a file-like object.

encode, *decode* must adhere to the *Codec* interface. *Reader*, *Writer* must be factory functions or classes providing objects of the *StreamReader* and *StreamWriter* interface respectively.

encode and *decode* are needed for the frontend translation, *Reader* and *Writer* for the backend translation. The intermediate format used is determined by the two sets of codecs, e.g. the Unicode codecs will use Unicode as the intermediate encoding.

Error handling is done in the same way as defined for the stream readers and writers.

StreamRecoder instances define the combined interfaces of *StreamReader* and *StreamWriter* classes. They inherit all other methods and attributes from the underlying stream.

7.8.2 Encodings and Unicode

Unicode strings are stored internally as sequences of code points (to be precise as `Py_UNICODE` arrays). Depending on the way Python is compiled (either via `--enable-unicode=ucs2` or `--enable-unicode=ucs4`, with the former being the default) `Py_UNICODE` is either a 16-bit or 32-bit data type. Once a Unicode object is used outside of CPU and memory, CPU endianness and how these arrays are stored as bytes become an issue. Transforming a unicode object into a sequence of bytes is called encoding and recreating the unicode object from the sequence of bytes is known as decoding. There are many different methods for how this transformation can be done (these methods are also called encodings). The simplest method is to map the code points 0–255 to the bytes 0x0–0xff. This means that a unicode object that contains code points above U+00FF can't be encoded with this method (which is called 'latin-1' or 'iso-8859-1'). `unicode.encode()` will raise a `UnicodeEncodeError` that looks like this: `UnicodeEncodeError: 'latin-1' codec can't encode character u'\u1234' in position 3: ordinal not in range(256)`.

There's another group of encodings (the so called charmap encodings) that choose a different subset of all unicode code points and how these code points are mapped to the bytes 0x0–0xff. To see how this is done simply open e.g. `encodings/cp1252.py` (which is an encoding that is used primarily on Windows). There's a string constant with 256 characters that shows you which character is mapped to which byte value.

All of these encodings can only encode 256 of the 1114112 code points defined in unicode. A simple and straightforward way that can store each Unicode code point, is to store each code point as four consecutive bytes. There are two possibilities: store the bytes in big endian or in little endian order. These two encodings are called UTF-32-BE and UTF-32-LE respectively. Their disadvantage is that if e.g. you use UTF-32-BE on a little endian machine you will always have to swap bytes on encoding and decoding. UTF-32 avoids this problem: bytes will always be in natural endianness. When these bytes are read by a CPU with a different endianness, then bytes have to be swapped though. To be able to detect the endianness of a UTF-16 or UTF-32 byte sequence, there's the so called BOM (《Byte Order Mark》). This is the Unicode character U+FEFF. This character can be prepended to every UTF-16 or UTF-32 byte sequence. The byte swapped version of this character (0xFFFE) is an illegal character that may not appear in a Unicode text. So when the first character in an UTF-16 or UTF-32 byte sequence appears to be a U+FFFE the bytes have to be swapped on decoding. Unfortunately the character U+FEFF had a second purpose as a ZERO WIDTH NO-BREAK SPACE: a character that has no width and doesn't allow a word to be split. It can e.g. be used to give hints to a ligature algorithm. With Unicode 4.0 using U+FEFF as a ZERO WIDTH NO-BREAK SPACE has been deprecated (with U+2060 (WORD JOINER) assuming this role). Nevertheless Unicode software still must be able to handle U+FEFF in both roles: as a BOM it's a device to determine the storage layout of the encoded bytes, and vanishes once the byte sequence has been decoded into a Unicode string; as a ZERO WIDTH NO-BREAK SPACE it's a normal character that will be decoded like any other.

There's another encoding that is able to encoding the full range of Unicode characters: UTF-8. UTF-8 is an 8-bit encoding, which means there are no issues with byte order in UTF-8. Each byte in a UTF-8 byte sequence consists of two parts: marker bits (the most significant bits) and payload bits. The marker bits are a sequence of zero to four 1 bits followed by a 0 bit. Unicode characters are encoded like this (with x being payload bits, which when concatenated give the Unicode character):

Range	Encoding
U-00000000 ... U-0000007F	0xxxxxxx
U-00000080 ... U-000007FF	110xxxxx 10xxxxxx
U-00000800 ... U-0000FFFF	1110xxxx 10xxxxxx 10xxxxxx
U-00010000 ... U-0010FFFF	11110xxx 10xxxxxx 10xxxxxx 10xxxxxx

The least significant bit of the Unicode character is the rightmost x bit.

As UTF-8 is an 8-bit encoding no BOM is required and any U+FEFF character in the decoded Unicode string (even if it's the first character) is treated as a ZERO WIDTH NO-BREAK SPACE.

Without external information it's impossible to reliably determine which encoding was used for encoding a Unicode string. Each charmap encoding can decode any random byte sequence. However that's not possible with UTF-8, as

UTF-8 byte sequences have a structure that doesn't allow arbitrary byte sequences. To increase the reliability with which a UTF-8 encoding can be detected, Microsoft invented a variant of UTF-8 (that Python 2.5 calls "utf-8-sig") for its Notepad program: Before any of the Unicode characters is written to the file, a UTF-8 encoded BOM (which looks like this as a byte sequence: `0xef, 0xbb, 0xbf`) is written. As it's rather improbable that any charmap encoded file starts with these byte values (which would e.g. map to

LATIN SMALL LETTER I WITH DIAERESIS
RIGHT-POINTING DOUBLE ANGLE QUOTATION MARK
INVERTED QUESTION MARK

in iso-8859-1), this increases the probability that a utf-8-sig encoding can be correctly guessed from the byte sequence. So here the BOM is not used to be able to determine the byte order used for generating the byte sequence, but as a signature that helps in guessing the encoding. On encoding the utf-8-sig codec will write `0xef, 0xbb, 0xbf` as the first three bytes to the file. On decoding utf-8-sig will skip those three bytes if they appear as the first three bytes in the file. In UTF-8, the use of the BOM is discouraged and should generally be avoided.

7.8.3 Standard Encodings

Python comes with a number of codecs built-in, either implemented as C functions or with dictionaries as mapping tables. The following table lists the codecs by name, together with a few common aliases, and the languages for which the encoding is likely used. Neither the list of aliases nor the list of languages is meant to be exhaustive. Notice that spelling alternatives that only differ in case or use a hyphen instead of an underscore are also valid aliases; therefore, e.g. 'utf-8' is a valid alias for the 'utf_8' codec.

Many of the character sets support the same languages. They vary in individual characters (e.g. whether the EURO SIGN is supported or not), and in the assignment of characters to code positions. For the European languages in particular, the following variants typically exist:

- an ISO 8859 codeset
- a Microsoft Windows code page, which is typically derived from an 8859 codeset, but replaces control characters with additional graphic characters
- an IBM EBCDIC code page
- an IBM PC code page, which is ASCII compatible

Codec	Aliases	Languages
ascii	646, us-ascii	English
big5	big5-tw, csbig5	Traditional Chinese
big5hkscs	big5-hkscs, hkscs	Traditional Chinese
cp037	IBM037, IBM039	English
cp424	EBCDIC-CP-HE, IBM424	Hebrew
cp437	437, IBM437	English
cp500	EBCDIC-CP-BE, EBCDIC-CP-CH, IBM500	Western Europe
cp720		Arabic
cp737		Greek
cp775	IBM775	Baltic languages
cp850	850, IBM850	Western Europe
cp852	852, IBM852	Central and Eastern Europe
cp855	855, IBM855	Bulgarian, Byelorussian, Macedonian, Russian, Serbian
cp856		Hebrew

다음 페이지에 계속

표 3 - 이전 페이지에서 계속

Codec	Aliases	Languages
cp857	857, IBM857	Turkish
cp858	858, IBM858	Western Europe
cp860	860, IBM860	Portuguese
cp861	861, CP-IS, IBM861	Icelandic
cp862	862, IBM862	Hebrew
cp863	863, IBM863	Canadian
cp864	IBM864	Arabic
cp865	865, IBM865	Danish, Norwegian
cp866	866, IBM866	Russian
cp869	869, CP-GR, IBM869	Greek
cp874		Thai
cp875		Greek
cp932	932, ms932, mskanji, ms-kanji	Japanese
cp949	949, ms949, uhc	Korean
cp950	950, ms950	Traditional Chinese
cp1006		Urdu
cp1026	ibm1026	Turkish
cp1140	ibm1140	Western Europe
cp1250	windows-1250	Central and Eastern Europe
cp1251	windows-1251	Bulgarian, Byelorussian, Macedonian, Russian, Serbian
cp1252	windows-1252	Western Europe
cp1253	windows-1253	Greek
cp1254	windows-1254	Turkish
cp1255	windows-1255	Hebrew
cp1256	windows-1256	Arabic
cp1257	windows-1257	Baltic languages
cp1258	windows-1258	Vietnamese
euc_jp	eucjp, ujis, u-jis	Japanese
euc_jis_2004	jisx0213, eucjis2004	Japanese
euc_jisx0213	eucjisx0213	Japanese
euc_kr	euckr, korean, ksc5601, ks_c-5601, ks_c-5601-1987, ksx1001, ks_x-1001	Korean
gb2312	chinese, csiso58gb231280, euc-cn, eucn, eucgb2312-cn, gb2312-1980, gb2312-80, iso-ir-58	Simplified Chinese
gbk	936, cp936, ms936	Unified Chinese
gb18030	gb18030-2000	Unified Chinese
hz	hzgb, hz-gb, hz-gb-2312	Simplified Chinese
iso2022_jp	csiso2022jp, iso2022jp, iso-2022-jp	Japanese
iso2022_jp_1	iso2022jp-1, iso-2022-jp-1	Japanese
iso2022_jp_2	iso2022jp-2, iso-2022-jp-2	Japanese, Korean, Simplified Chinese, Western Europe, Greek
iso2022_jp_2004	iso2022jp-2004, iso-2022-jp-2004	Japanese
iso2022_jp_3	iso2022jp-3, iso-2022-jp-3	Japanese
iso2022_jp_ext	iso2022jp-ext, iso-2022-jp-ext	Japanese
iso2022_kr	csiso2022kr, iso2022kr, iso-2022-kr	Korean

다음 페이지에 계속

표 3 - 이전 페이지에서 계속

Codec	Aliases	Languages
latin_1	iso-8859-1, iso8859-1, 8859, cp819, latin, latin1, L1	West Europe
iso8859_2	iso-8859-2, latin2, L2	Central and Eastern Europe
iso8859_3	iso-8859-3, latin3, L3	Esperanto, Maltese
iso8859_4	iso-8859-4, latin4, L4	Baltic languages
iso8859_5	iso-8859-5, cyrillic	Bulgarian, Byelorussian, Macedonian, Russian, Serbian
iso8859_6	iso-8859-6, arabic	Arabic
iso8859_7	iso-8859-7, greek, greek8	Greek
iso8859_8	iso-8859-8, hebrew	Hebrew
iso8859_9	iso-8859-9, latin5, L5	Turkish
iso8859_10	iso-8859-10, latin6, L6	Nordic languages
iso8859_11	iso-8859-11, thai	Thai languages
iso8859_13	iso-8859-13, latin7, L7	Baltic languages
iso8859_14	iso-8859-14, latin8, L8	Celtic languages
iso8859_15	iso-8859-15, latin9, L9	Western Europe
iso8859_16	iso-8859-16, latin10, L10	South-Eastern Europe
johab	cp1361, ms1361	Korean
koi8_r		Russian
koi8_u		Ukrainian
mac_cyrillic	maccyrillic	Bulgarian, Byelorussian, Macedonian, Russian, Serbian
mac_greek	macgreek	Greek
mac_iceland	maciceland	Icelandic
mac_latin2	maclatin2, maccentraleurope	Central and Eastern Europe
mac_roman	macroman	Western Europe
mac_turkish	macturkish	Turkish
ptcp154	csptcp154, pt154, cp154, cyrillic-asian	Kazakh
shift_jis	csshiftjis, shiftjis, sjis, s_jis	Japanese
shift_jis_2004	shiftjis2004, sjis_2004, sjis2004	Japanese
shift_jisx0213	shiftjisx0213, sjisx0213, s_jisx0213	Japanese
utf_32	U32, utf32	all languages
utf_32_be	UTF-32BE	all languages
utf_32_le	UTF-32LE	all languages
utf_16	U16, utf16	all languages
utf_16_be	UTF-16BE	all languages (BMP only)
utf_16_le	UTF-16LE	all languages (BMP only)
utf_7	U7, unicode-1-1-utf-7	all languages
utf_8	U8, UTF, utf8	all languages
utf_8_sig		all languages

7.8.4 Python Specific Encodings

A number of predefined codecs are specific to Python, so their codec names have no meaning outside Python. These are listed in the tables below based on the expected input and output types (note that while text encodings are the most common use case for codecs, the underlying codec infrastructure supports arbitrary data transforms rather than just text encodings). For asymmetric codecs, the stated purpose describes the encoding direction.

The following codecs provide unicode-to-str encoding¹ and str-to-unicode decoding², similar to the Unicode text encodings.

Codec	Aliases	Purpose
idna		Implements RFC 3490 , see also encodings.idna
mbcs	dbcs	Windows only: Encode operand according to the ANSI codepage (CP_ACP)
palms		Encoding of PalmOS 3.5
punycode		Implements RFC 3492
raw_unicode_escape		Produce a string that is suitable as raw Unicode literal in Python source code
rot_13	rot13	Returns the Caesar-cypher encryption of the operand
undefined		Raise an exception for all conversions. Can be used as the system encoding if no automatic coercion between byte and Unicode strings is desired.
unicode_escape		Produce a string that is suitable as Unicode literal in Python source code
unicode_internal		Return the internal representation of the operand

버전 2.3에 추가: The `idna` and `punycode` encodings.

The following codecs provide str-to-str encoding and decoding².

Codec	Aliases	Purpose	Encoder/decoder
base64_codec	base64, base-64	Convert operand to multiline MIME base64 (the result always includes a trailing '\n')	base64.encodestring() , base64.decodestring()
bz2_codec	bz2	Compress the operand using bz2	bz2.compress() , bz2.decompress()
hex_codec	hex	Convert operand to hexadecimal representation, with two digits per byte	binascii.b2a_hex() , binascii.a2b_hex()
quopri_codec	quopri, quoted-printable, quotedprintable	Convert operand to MIME quoted printable	quopri.encode() with <code>quotetabs=True</code> , quopri.decode()
string_escape		Produce a string that is suitable as string literal in Python source code	
uu_codec	uu	Convert the operand using uuencode	uu.encode() , uu.decode()
zlib_codec	zip, zlib	Compress the operand using gzip	zlib.compress() , zlib.decompress()

¹ str objects are also accepted as input in place of unicode objects. They are implicitly converted to unicode by decoding them using the default encoding. If this conversion fails, it may lead to encoding operations raising `UnicodeDecodeError`.

² unicode objects are also accepted as input in place of str objects. They are implicitly converted to str by encoding them using the default encoding. If this conversion fails, it may lead to decoding operations raising `UnicodeEncodeError`.

7.8.5 `encodings.idna` — Internationalized Domain Names in Applications

버전 2.3에 추가.

This module implements [RFC 3490](#) (Internationalized Domain Names in Applications) and [RFC 3492](#) (Nameprep: A Stringprep Profile for Internationalized Domain Names (IDN)). It builds upon the `punycode` encoding and `stringprep`.

These RFCs together define a protocol to support non-ASCII characters in domain names. A domain name containing non-ASCII characters (such as `www.Alliancefranaise.nu`) is converted into an ASCII-compatible encoding (ACE, such as `www.xn--alliancefranaise-npb.nu`). The ACE form of the domain name is then used in all places where arbitrary characters are not allowed by the protocol, such as DNS queries, HTTP *Host* fields, and so on. This conversion is carried out in the application; if possible invisible to the user: The application should transparently convert Unicode domain labels to IDNA on the wire, and convert back ACE labels to Unicode before presenting them to the user.

Python supports this conversion in several ways: the `idna` codec performs conversion between Unicode and ACE, separating an input string into labels based on the separator characters defined in [section 3.1 \(1\)](#) of [RFC 3490](#) and converting each label to ACE as required, and conversely separating an input byte string into labels based on the `.` separator and converting any ACE labels found into unicode. Furthermore, the `socket` module transparently converts Unicode host names to ACE, so that applications need not be concerned about converting host names themselves when they pass them to the socket module. On top of that, modules that have host names as function parameters, such as `httplib` and `ftplib`, accept Unicode host names (`httplib` then also transparently sends an IDNA hostname in the *Host* field if it sends that field at all).

When receiving host names from the wire (such as in reverse name lookup), no automatic conversion to Unicode is performed: Applications wishing to present such host names to the user should decode them to Unicode.

The module `encodings.idna` also implements the nameprep procedure, which performs certain normalizations on host names, to achieve case-insensitivity of international domain names, and to unify similar characters. The nameprep functions can be used directly if desired.

`encodings.idna.nameprep(label)`

Return the nameprepped version of *label*. The implementation currently assumes query strings, so `AllowUnassigned` is true.

`encodings.idna.ToASCII(label)`

Convert a label to ASCII, as specified in [RFC 3490](#). `UseSTD3ASCIIRules` is assumed to be false.

`encodings.idna.ToUnicode(label)`

Convert a label to Unicode, as specified in [RFC 3490](#).

7.8.6 `encodings.utf_8_sig` — UTF-8 codec with BOM signature

버전 2.5에 추가.

This module implements a variant of the UTF-8 codec: On encoding a UTF-8 encoded BOM will be prepended to the UTF-8 encoded bytes. For the stateful encoder this is only done once (on the first write to the byte stream). For decoding an optional UTF-8 encoded BOM at the start of the data will be skipped.

7.9 unicodedata — Unicode Database

This module provides access to the Unicode Character Database which defines character properties for all Unicode characters. The data in this database is based on the `UnicodeData.txt` file version 5.2.0 which is publicly available from <ftp://ftp.unicode.org/>.

The module uses the same names and symbols as defined by the UnicodeData File Format 5.2.0 (see <https://www.unicode.org/reports/tr44/>). It defines the following functions:

`unicodedata.lookup(name)`

Look up character by name. If a character with the given name is found, return the corresponding Unicode character. If not found, `KeyError` is raised.

`unicodedata.name(unichr[, default])`

Returns the name assigned to the Unicode character *unichr* as a string. If no name is defined, *default* is returned, or, if not given, `ValueError` is raised.

`unicodedata.decimal(unichr[, default])`

Returns the decimal value assigned to the Unicode character *unichr* as integer. If no such value is defined, *default* is returned, or, if not given, `ValueError` is raised.

`unicodedata.digit(unichr[, default])`

Returns the digit value assigned to the Unicode character *unichr* as integer. If no such value is defined, *default* is returned, or, if not given, `ValueError` is raised.

`unicodedata.numeric(unichr[, default])`

Returns the numeric value assigned to the Unicode character *unichr* as float. If no such value is defined, *default* is returned, or, if not given, `ValueError` is raised.

`unicodedata.category(unichr)`

Returns the general category assigned to the Unicode character *unichr* as string.

`unicodedata.bidirectional(unichr)`

Returns the bidirectional class assigned to the Unicode character *unichr* as string. If no such value is defined, an empty string is returned.

`unicodedata.combining(unichr)`

Returns the canonical combining class assigned to the Unicode character *unichr* as integer. Returns 0 if no combining class is defined.

`unicodedata.east_asian_width(unichr)`

Returns the east asian width assigned to the Unicode character *unichr* as string.

버전 2.4에 추가.

`unicodedata.mirrored(unichr)`

Returns the mirrored property assigned to the Unicode character *unichr* as integer. Returns 1 if the character has been identified as a 《mirrored》 character in bidirectional text, 0 otherwise.

`unicodedata.decomposition(unichr)`

Returns the character decomposition mapping assigned to the Unicode character *unichr* as string. An empty string is returned in case no such mapping is defined.

`unicodedata.normalize(form, unistr)`

Return the normal form *form* for the Unicode string *unistr*. Valid values for *form* are 《NFC》, 《NFKC》, 《NFD》, and 《NFKD》.

The Unicode standard defines various normalization forms of a Unicode string, based on the definition of canonical equivalence and compatibility equivalence. In Unicode, several characters can be expressed in various way. For example, the character U+00C7 (LATIN CAPITAL LETTER C WITH CEDILLA) can also be expressed as the sequence U+0043 (LATIN CAPITAL LETTER C) U+0327 (COMBINING CEDILLA).

For each character, there are two normal forms: normal form C and normal form D. Normal form D (NFD) is also known as canonical decomposition, and translates each character into its decomposed form. Normal form C (NFC) first applies a canonical decomposition, then composes pre-combined characters again.

In addition to these two forms, there are two additional normal forms based on compatibility equivalence. In Unicode, certain characters are supported which normally would be unified with other characters. For example, U+2160 (ROMAN NUMERAL ONE) is really the same thing as U+0049 (LATIN CAPITAL LETTER I). However, it is supported in Unicode for compatibility with existing character sets (e.g. gb2312).

The normal form KD (NFKD) will apply the compatibility decomposition, i.e. replace all compatibility characters with their equivalents. The normal form KC (NFKC) first applies the compatibility decomposition, followed by the canonical composition.

Even if two unicode strings are normalized and look the same to a human reader, if one has combining characters and the other doesn't, they may not compare equal.

버전 2.3에 추가.

In addition, the module exposes the following constant:

`unicodedata.unidata_version`

The version of the Unicode database used in this module.

버전 2.3에 추가.

`unicodedata.ucd_3_2_0`

This is an object that has the same methods as the entire module, but uses the Unicode database version 3.2 instead, for applications that require this specific version of the Unicode database (such as IDNA).

버전 2.5에 추가.

Examples:

```
>>> import unicodedata
>>> unicodedata.lookup('LEFT CURLY BRACKET')
u'{'
>>> unicodedata.name(u'/')
'SOLIDUS'
>>> unicodedata.decimal(u'9')
9
>>> unicodedata.decimal(u'a')
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ValueError: not a decimal
>>> unicodedata.category(u'A') # 'L'etter, 'u'ppercase
'Lu'
>>> unicodedata.bidirectional(u'\u0660') # 'A'rabic, 'N'umber
'AN'
```

7.10 stringprep — Internet String Preparation

버전 2.3에 추가.

When identifying things (such as host names) in the internet, it is often necessary to compare such identifications for 《equality》. Exactly how this comparison is executed may depend on the application domain, e.g. whether it should be case-insensitive or not. It may be also necessary to restrict the possible identifications, to allow only identifications consisting of 《printable》 characters.

RFC 3454 defines a procedure for 《preparing》 Unicode strings in internet protocols. Before passing strings onto the wire, they are processed with the preparation procedure, after which they have a certain normalized form. The RFC defines a set of tables, which can be combined into profiles. Each profile must define which tables it uses, and what other optional parts of the `stringprep` procedure are part of the profile. One example of a `stringprep` profile is `nameprep`, which is used for internationalized domain names.

The module `stringprep` only exposes the tables from RFC 3454. As these tables would be very large to represent them as dictionaries or lists, the module uses the Unicode character database internally. The module source code itself was generated using the `mkstringprep.py` utility.

As a result, these tables are exposed as functions, not as data structures. There are two kinds of tables in the RFC: sets and mappings. For a set, `stringprep` provides the 《characteristic function》, i.e. a function that returns true if the parameter is part of the set. For mappings, it provides the mapping function: given the key, it returns the associated value. Below is a list of all functions available in the module.

`stringprep.in_table_a1 (code)`
Determine whether *code* is in tableA.1 (Unassigned code points in Unicode 3.2).

`stringprep.in_table_b1 (code)`
Determine whether *code* is in tableB.1 (Commonly mapped to nothing).

`stringprep.map_table_b2 (code)`
Return the mapped value for *code* according to tableB.2 (Mapping for case-folding used with NFKC).

`stringprep.map_table_b3 (code)`
Return the mapped value for *code* according to tableB.3 (Mapping for case-folding used with no normalization).

`stringprep.in_table_c11 (code)`
Determine whether *code* is in tableC.1.1 (ASCII space characters).

`stringprep.in_table_c12 (code)`
Determine whether *code* is in tableC.1.2 (Non-ASCII space characters).

`stringprep.in_table_c11_c12 (code)`
Determine whether *code* is in tableC.1 (Space characters, union of C.1.1 and C.1.2).

`stringprep.in_table_c21 (code)`
Determine whether *code* is in tableC.2.1 (ASCII control characters).

`stringprep.in_table_c22 (code)`
Determine whether *code* is in tableC.2.2 (Non-ASCII control characters).

`stringprep.in_table_c21_c22 (code)`
Determine whether *code* is in tableC.2 (Control characters, union of C.2.1 and C.2.2).

`stringprep.in_table_c3 (code)`
Determine whether *code* is in tableC.3 (Private use).

`stringprep.in_table_c4 (code)`
Determine whether *code* is in tableC.4 (Non-character code points).

`stringprep.in_table_c5 (code)`
Determine whether *code* is in tableC.5 (Surrogate codes).

`stringprep.in_table_c6 (code)`
Determine whether *code* is in tableC.6 (Inappropriate for plain text).

`stringprep.in_table_c7 (code)`
Determine whether *code* is in tableC.7 (Inappropriate for canonical representation).

`stringprep.in_table_c8 (code)`
Determine whether *code* is in tableC.8 (Change display properties or are deprecated).

`stringprep.in_table_c9(code)`

Determine whether *code* is in tableC.9 (Tagging characters).

`stringprep.in_table_d1(code)`

Determine whether *code* is in tableD.1 (Characters with bidirectional property 《R》 or 《AL》).

`stringprep.in_table_d2(code)`

Determine whether *code* is in tableD.2 (Characters with bidirectional property 《L》).

7.11 `fpformat` — Floating point conversions

버전 2.6부터 폐지: The `fpformat` module has been removed in Python 3.

The `fpformat` module defines functions for dealing with floating point numbers representations in 100% pure Python.

참고: This module is unnecessary: everything here can be done using the `%` string interpolation operator described in the *String Formatting Operations* section.

The `fpformat` module defines the following functions and an exception:

`fpformat.fix(x, digs)`

Format *x* as `[-]ddd.ddd` with *digs* digits after the point and at least one digit before. If *digs* \leq 0, the decimal point is suppressed.

x can be either a number or a string that looks like one. *digs* is an integer.

Return value is a string.

`fpformat.sci(x, digs)`

Format *x* as `[-]d.dddE[+-]ddd` with *digs* digits after the point and exactly one digit before. If *digs* \leq 0, one digit is kept and the point is suppressed.

x can be either a real number, or a string that looks like one. *digs* is an integer.

Return value is a string.

exception `fpformat.NotANumber`

Exception raised when a string passed to `fix()` or `sci()` as the *x* parameter does not look like a number. This is a subclass of `ValueError` when the standard exceptions are strings. The exception value is the improperly formatted string that caused the exception to be raised.

Example:

```
>>> import fpformat
>>> fpformat.fix(1.23, 1)
'1.2'
```


The modules described in this chapter provide a variety of specialized data types such as dates and times, fixed-type arrays, heap queues, synchronized queues, and sets.

Python also provides some built-in data types, in particular, *dict*, *list*, *set* (which along with *frozenset*, replaces the deprecated *sets* module), and *tuple*. The *str* class can be used to handle binary data and 8-bit text, and the *unicode* class to handle Unicode text.

The following modules are documented in this chapter:

8.1 *datetime* — Basic date and time types

버전 2.3에 추가.

The *datetime* module supplies classes for manipulating dates and times in both simple and complex ways. While date and time arithmetic is supported, the focus of the implementation is on efficient attribute extraction for output formatting and manipulation. For related functionality, see also the *time* and *calendar* modules.

There are two kinds of date and time objects: *naive* and *aware*.

An aware object has sufficient knowledge of applicable algorithmic and political time adjustments, such as time zone and daylight saving time information, to locate itself relative to other aware objects. An aware object is used to represent a specific moment in time that is not open to interpretation¹.

A naive object does not contain enough information to unambiguously locate itself relative to other date/time objects. Whether a naive object represents Coordinated Universal Time (UTC), local time, or time in some other timezone is purely up to the program, just like it's up to the program whether a particular number represents metres, miles, or mass. Naive objects are easy to understand and to work with, at the cost of ignoring some aspects of reality.

For applications requiring aware objects, *datetime* and *time* objects have an optional time zone information attribute, *tzinfo*, that can be set to an instance of a subclass of the abstract *tzinfo* class. These *tzinfo* objects capture information about the offset from UTC time, the time zone name, and whether Daylight Saving Time is in effect. Note that no concrete *tzinfo* classes are supplied by the *datetime* module. Supporting timezones at whatever level of

¹ If, that is, we ignore the effects of Relativity

detail is required is up to the application. The rules for time adjustment across the world are more political than rational, and there is no standard suitable for every application.

The `datetime` module exports the following constants:

`datetime.MINYEAR`

The smallest year number allowed in a `date` or `datetime` object. `MINYEAR` is 1.

`datetime.MAXYEAR`

The largest year number allowed in a `date` or `datetime` object. `MAXYEAR` is 9999.

더 보기:

Module `calendar` General calendar related functions.

Module `time` Time access and conversions.

8.1.1 Available Types

class `datetime.date`

An idealized naive date, assuming the current Gregorian calendar always was, and always will be, in effect. Attributes: `year`, `month`, and `day`.

class `datetime.time`

An idealized time, independent of any particular day, assuming that every day has exactly 24*60*60 seconds (there is no notion of 《leap seconds》 here). Attributes: `hour`, `minute`, `second`, `microsecond`, and `tzinfo`.

class `datetime.datetime`

A combination of a date and a time. Attributes: `year`, `month`, `day`, `hour`, `minute`, `second`, `microsecond`, and `tzinfo`.

class `datetime.timedelta`

A duration expressing the difference between two `date`, `time`, or `datetime` instances to microsecond resolution.

class `datetime.tzinfo`

An abstract base class for time zone information objects. These are used by the `datetime` and `time` classes to provide a customizable notion of time adjustment (for example, to account for time zone and/or daylight saving time).

Objects of these types are immutable.

Objects of the `date` type are always naive.

An object of type `time` or `datetime` may be naive or aware. A `datetime` object `d` is aware if `d.tzinfo` is not `None` and `d.tzinfo.utcoffset(d)` does not return `None`. If `d.tzinfo` is `None`, or if `d.tzinfo` is not `None` but `d.tzinfo.utcoffset(d)` returns `None`, `d` is naive. A `time` object `t` is aware if `t.tzinfo` is not `None` and `t.tzinfo.utcoffset(None)` does not return `None`. Otherwise, `t` is naive.

The distinction between naive and aware doesn't apply to `timedelta` objects.

Subclass relationships:

```
object
  timedelta
  tzinfo
  time
  date
    datetime
```

8.1.2 timedelta Objects

A *timedelta* object represents a duration, the difference between two dates or times.

```
class datetime.timedelta ([days [, seconds [, microseconds [, milliseconds [, minutes [, hours [, weeks ] ] ] ] ] ] ] )
```

All arguments are optional and default to 0. Arguments may be ints, longs, or floats, and may be positive or negative.

Only *days*, *seconds* and *microseconds* are stored internally. Arguments are converted to those units:

- A millisecond is converted to 1000 microseconds.
- A minute is converted to 60 seconds.
- An hour is converted to 3600 seconds.
- A week is converted to 7 days.

and *days*, *seconds* and *microseconds* are then normalized so that the representation is unique, with

- $0 \leq \text{microseconds} < 1000000$
- $0 \leq \text{seconds} < 3600 \times 24$ (the number of seconds in one day)
- $-999999999 \leq \text{days} \leq 999999999$

If any argument is a float and there are fractional microseconds, the fractional microseconds left over from all arguments are combined and their sum is rounded to the nearest microsecond. If no argument is a float, the conversion and normalization processes are exact (no information is lost).

If the normalized value of *days* lies outside the indicated range, *OverflowError* is raised.

Note that normalization of negative values may be surprising at first. For example,

```
>>> from datetime import timedelta
>>> d = timedelta(microseconds=-1)
>>> (d.days, d.seconds, d.microseconds)
(-1, 86399, 999999)
```

Class attributes are:

timedelta.min

The most negative *timedelta* object, *timedelta*(-999999999).

timedelta.max

The most positive *timedelta* object, *timedelta*(days=999999999, hours=23, minutes=59, seconds=59, microseconds=999999).

timedelta.resolution

The smallest possible difference between non-equal *timedelta* objects, *timedelta*(microseconds=1).

Note that, because of normalization, *timedelta.max* > -*timedelta.min*. -*timedelta.max* is not representable as a *timedelta* object.

Instance attributes (read-only):

Attribute	Value
<i>days</i>	Between -999999999 and 999999999 inclusive
<i>seconds</i>	Between 0 and 86399 inclusive
<i>microseconds</i>	Between 0 and 999999 inclusive

Supported operations:

Operation	Result
<code>t1 = t2 + t3</code>	Sum of <i>t2</i> and <i>t3</i> . Afterwards <i>t1-t2</i> == <i>t3</i> and <i>t1-t3</i> == <i>t2</i> are true. (1)
<code>t1 = t2 - t3</code>	Difference of <i>t2</i> and <i>t3</i> . Afterwards <i>t1</i> == <i>t2 - t3</i> and <i>t2</i> == <i>t1 + t3</i> are true. (1)
<code>t1 = t2 * i</code> or <code>t1 = i * t2</code>	Delta multiplied by an integer or long. Afterwards <i>t1</i> // <i>i</i> == <i>t2</i> is true, provided <i>i</i> != 0.
	In general, <i>t1</i> * <i>i</i> == <i>t1</i> * (<i>i</i> -1) + <i>t1</i> is true. (1)
<code>t1 = t2 // i</code>	The floor is computed and the remainder (if any) is thrown away. (3)
<code>+t1</code>	Returns a <i>timedelta</i> object with the same value. (2)
<code>-t1</code>	equivalent to <i>timedelta</i> (- <i>t1</i> .days, - <i>t1</i> .seconds, - <i>t1</i> .microseconds), and to <i>t1</i> * -1. (1)(4)
<code>abs(t)</code>	equivalent to <i>+t</i> when <i>t</i> .days >= 0, and to <i>-t</i> when <i>t</i> .days < 0. (2)
<code>str(t)</code>	Returns a string in the form [D day[s],][H]H:MM:SS[.UUUUUU], where D is negative for negative <i>t</i> . (5)
<code>repr(t)</code>	Returns a string in the form <code>datetime.timedelta(D[, S[, U]])</code> , where D is negative for negative <i>t</i> . (5)

Notes:

- (1) This is exact, but may overflow.
- (2) This is exact, and cannot overflow.
- (3) Division by 0 raises *ZeroDivisionError*.
- (4) *-timedelta.max* is not representable as a *timedelta* object.
- (5) String representations of *timedelta* objects are normalized similarly to their internal representation. This leads to somewhat unusual results for negative timedeltas. For example:

```
>>> timedelta(hours=-5)
datetime.timedelta(-1, 68400)
>>> print(_)
-1 day, 19:00:00
```

In addition to the operations listed above *timedelta* objects support certain additions and subtractions with *date* and *datetime* objects (see below).

Comparisons of *timedelta* objects are supported with the *timedelta* object representing the smaller duration considered to be the smaller *timedelta*. In order to stop mixed-type comparisons from falling back to the default comparison by object address, when a *timedelta* object is compared to an object of a different type, *TypeError* is raised unless the comparison is == or !=. The latter cases return *False* or *True*, respectively.

timedelta objects are *hashable* (usable as dictionary keys), support efficient pickling, and in Boolean contexts, a *timedelta* object is considered to be true if and only if it isn't equal to `timedelta(0)`.

Instance methods:

`timedelta.total_seconds()`

Return the total number of seconds contained in the duration. Equivalent to `(td.microseconds + (td.seconds + td.days * 24 * 3600) * 10**6) / 10**6` computed with true division enabled.

Note that for very large time intervals (greater than 270 years on most platforms) this method will lose microsecond accuracy.

버전 2.7에 추가.

Example usage:

```

>>> from datetime import timedelta
>>> year = timedelta(days=365)
>>> another_year = timedelta(weeks=40, days=84, hours=23,
...                          minutes=50, seconds=600) # adds up to 365 days
>>> year.total_seconds()
31536000.0
>>> year == another_year
True
>>> ten_years = 10 * year
>>> ten_years, ten_years.days // 365
(datetime.timedelta(3650), 10)
>>> nine_years = ten_years - year
>>> nine_years, nine_years.days // 365
(datetime.timedelta(3285), 9)
>>> three_years = nine_years // 3;
>>> three_years, three_years.days // 365
(datetime.timedelta(1095), 3)
>>> abs(three_years - ten_years) == 2 * three_years + year
True

```

8.1.3 date Objects

A *date* object represents a date (year, month and day) in an idealized calendar, the current Gregorian calendar indefinitely extended in both directions. January 1 of year 1 is called day number 1, January 2 of year 1 is called day number 2, and so on. This matches the definition of the 《proleptic Gregorian》 calendar in Dershowitz and Reingold’s book *Calendrical Calculations*, where it’s the base calendar for all computations. See the book for algorithms for converting between proleptic Gregorian ordinals and many other calendar systems.

class `datetime.date` (*year, month, day*)

All arguments are required. Arguments may be ints or longs, in the following ranges:

- `MINYEAR <= year <= MAXYEAR`
- `1 <= month <= 12`
- `1 <= day <= number of days in the given month and year`

If an argument outside those ranges is given, *ValueError* is raised.

Other constructors, all class methods:

classmethod `date.today()`

Return the current local date. This is equivalent to `date.fromtimestamp(time.time())`.

classmethod `date.fromtimestamp(timestamp)`

Return the local date corresponding to the POSIX timestamp, such as is returned by `time.time()`. This may raise *ValueError*, if the timestamp is out of the range of values supported by the platform C `localtime()` function. It’s common for this to be restricted to years from 1970 through 2038. Note that on non-POSIX systems that include leap seconds in their notion of a timestamp, leap seconds are ignored by `fromtimestamp()`.

classmethod `date.fromordinal(ordinal)`

Return the date corresponding to the proleptic Gregorian ordinal, where January 1 of year 1 has ordinal 1. *ValueError* is raised unless `1 <= ordinal <= date.max.toordinal()`. For any date *d*, `date.fromordinal(d.toordinal()) == d`.

Class attributes:

`date.min`

The earliest representable date, `date(MINYEAR, 1, 1)`.

`date.max`

The latest representable date, `date(MAXYEAR, 12, 31)`.

`date.resolution`

The smallest possible difference between non-equal date objects, `timedelta(days=1)`.

Instance attributes (read-only):

`date.year`

Between `MINYEAR` and `MAXYEAR` inclusive.

`date.month`

Between 1 and 12 inclusive.

`date.day`

Between 1 and the number of days in the given month of the given year.

Supported operations:

Operation	Result
<code>date2 = date1 + timedelta</code>	<i>date2</i> is <code>timedelta.days</code> days removed from <i>date1</i> . (1)
<code>date2 = date1 - timedelta</code>	Computes <i>date2</i> such that <code>date2 + timedelta == date1</code> . (2)
<code>timedelta = date1 - date2</code>	(3)
<code>date1 < date2</code>	<i>date1</i> is considered less than <i>date2</i> when <i>date1</i> precedes <i>date2</i> in time. (4)

Notes:

- (1) *date2* is moved forward in time if `timedelta.days > 0`, or backward if `timedelta.days < 0`. Afterward `date2 - date1 == timedelta.days`. `timedelta.seconds` and `timedelta.microseconds` are ignored. `OverflowError` is raised if `date2.year` would be smaller than `MINYEAR` or larger than `MAXYEAR`.
- (2) This isn't quite equivalent to `date1 + (-timedelta)`, because `-timedelta` in isolation can overflow in cases where `date1 - timedelta` does not. `timedelta.seconds` and `timedelta.microseconds` are ignored.
- (3) This is exact, and cannot overflow. `timedelta.seconds` and `timedelta.microseconds` are 0, and `date2 + timedelta == date1` after.
- (4) In other words, `date1 < date2` if and only if `date1.toordinal() < date2.toordinal()`. In order to stop comparison from falling back to the default scheme of comparing object addresses, date comparison normally raises `TypeError` if the other comparand isn't also a `date` object. However, `NotImplemented` is returned instead if the other comparand has a `timetuple()` attribute. This hook gives other kinds of date objects a chance at implementing mixed-type comparison. If not, when a `date` object is compared to an object of a different type, `TypeError` is raised unless the comparison is `==` or `!=`. The latter cases return `False` or `True`, respectively.

Dates can be used as dictionary keys. In Boolean contexts, all `date` objects are considered to be true.

Instance methods:

`date.replace(year, month, day)`

Return a date with the same value, except for those parameters given new values by whichever keyword arguments are specified. For example, if `d == date(2002, 12, 31)`, then `d.replace(day=26) == date(2002, 12, 26)`.

`date.timetuple()`

Return a `time.struct_time` such as returned by `time.localtime()`. The hours, minutes and seconds are 0, and the DST flag is -1. `d.timetuple()` is equivalent to `time.struct_time((d.year, d.month,`

`d.day, 0, 0, 0, d.weekday(), yday, -1)`, where `yday = d.toordinal() - date(d.year, 1, 1).toordinal() + 1` is the day number within the current year starting with 1 for January 1st.

`date.toordinal()`

Return the proleptic Gregorian ordinal of the date, where January 1 of year 1 has ordinal 1. For any *date* object *d*, `date.fromordinal(d.toordinal()) == d`.

`date.weekday()`

Return the day of the week as an integer, where Monday is 0 and Sunday is 6. For example, `date(2002, 12, 4).weekday() == 2`, a Wednesday. See also *isoweekday()*.

`date.isoweekday()`

Return the day of the week as an integer, where Monday is 1 and Sunday is 7. For example, `date(2002, 12, 4).isoweekday() == 3`, a Wednesday. See also *weekday()*, *isocalendar()*.

`date.isocalendar()`

Return a 3-tuple, (ISO year, ISO week number, ISO weekday).

The ISO calendar is a widely used variant of the Gregorian calendar. See <https://www.staff.science.uu.nl/~gent0113/calendar/isocalendar.htm> for a good explanation.

The ISO year consists of 52 or 53 full weeks, and where a week starts on a Monday and ends on a Sunday. The first week of an ISO year is the first (Gregorian) calendar week of a year containing a Thursday. This is called week number 1, and the ISO year of that Thursday is the same as its Gregorian year.

For example, 2004 begins on a Thursday, so the first week of ISO year 2004 begins on Monday, 29 Dec 2003 and ends on Sunday, 4 Jan 2004, so that `date(2003, 12, 29).isocalendar() == (2004, 1, 1)` and `date(2004, 1, 4).isocalendar() == (2004, 1, 7)`.

`date.isoformat()`

Return a string representing the date in ISO 8601 format, `<YYYY-MM-DD>`. For example, `date(2002, 12, 4).isoformat() == '2002-12-04'`.

`date.__str__()`

For a date *d*, `str(d)` is equivalent to `d.isoformat()`.

`date.ctime()`

Return a string representing the date, for example `date(2002, 12, 4).ctime() == 'Wed Dec 4 00:00:00 2002'`. `d.ctime()` is equivalent to `time.ctime(time.mktime(d.timetuple()))` on platforms where the native C `ctime()` function (which *time.ctime()* invokes, but which *date.ctime()* does not invoke) conforms to the C standard.

`date.strftime(format)`

Return a string representing the date, controlled by an explicit format string. Format codes referring to hours, minutes or seconds will see 0 values. For a complete list of formatting directives, see section *strftime() and strptime() Behavior*.

`date.__format__(format)`

Same as *date.strftime()*. This makes it possible to specify a format string for a *date* object when using *str.format()*. See section *strftime() and strptime() Behavior*.

Example of counting days to an event:

```
>>> import time
>>> from datetime import date
>>> today = date.today()
>>> today
datetime.date(2007, 12, 5)
>>> today == date.fromtimestamp(time.time())
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

True
>>> my_birthday = date(today.year, 6, 24)
>>> if my_birthday < today:
...     my_birthday = my_birthday.replace(year=today.year + 1)
>>> my_birthday
datetime.date(2008, 6, 24)
>>> time_to_birthday = abs(my_birthday - today)
>>> time_to_birthday.days
202

```

Example of working with *date*:

```

>>> from datetime import date
>>> d = date.fromordinal(730920) # 730920th day after 1. 1. 0001
>>> d
datetime.date(2002, 3, 11)
>>> t = d.timetuple()
>>> for i in t:
...     print i
2002          # year
3             # month
11            # day
0
0
0
0             # weekday (0 = Monday)
70            # 70th day in the year
-1
>>> ic = d.isocalendar()
>>> for i in ic:
...     print i
2002          # ISO year
11            # ISO week number
1             # ISO day number ( 1 = Monday )
>>> d.isoformat()
'2002-03-11'
>>> d.strftime("%d/%m/%y")
'11/03/02'
>>> d.strftime("%A %d. %B %Y")
'Monday 11. March 2002'
>>> 'The {1} is {0:%d}, the {2} is {0:%B}.'.format(d, "day", "month")
'The day is 11, the month is March.'

```

8.1.4 datetime Objects

A *datetime* object is a single object containing all the information from a *date* object and a *time* object. Like a *date* object, *datetime* assumes the current Gregorian calendar extended in both directions; like a *time* object, *datetime* assumes there are exactly 3600*24 seconds in every day.

Constructor:

```
class datetime.datetime (year, month, day[, hour[, minute[, second[, microsecond[, tzinfo]]]]])
```

The year, month and day arguments are required. *tzinfo* may be *None*, or an instance of a *tzinfo* subclass. The remaining arguments may be ints or longs, in the following ranges:

- MINYEAR <= year <= MAXYEAR

- `1 <= month <= 12`
- `1 <= day <= number of days in the given month and year`
- `0 <= hour < 24`
- `0 <= minute < 60`
- `0 <= second < 60`
- `0 <= microsecond < 1000000`

If an argument outside those ranges is given, `ValueError` is raised.

Other constructors, all class methods:

classmethod `datetime.today()`

Return the current local datetime, with `tzinfo` `None`. This is equivalent to `datetime.fromtimestamp(time.time())`. See also `now()`, `fromtimestamp()`.

classmethod `datetime.now([tz])`

Return the current local date and time. If optional argument `tz` is `None` or not specified, this is like `today()`, but, if possible, supplies more precision than can be gotten from going through a `time.time()` timestamp (for example, this may be possible on platforms supplying the C `gettimeofday()` function).

If `tz` is not `None`, it must be an instance of a `tzinfo` subclass, and the current date and time are converted to `tz`'s time zone. In this case the result is equivalent to `tz.fromutc(datetime.utcnow()).replace(tzinfo=tz)`. See also `today()`, `utcnow()`.

classmethod `datetime.utcnow()`

Return the current UTC date and time, with `tzinfo` `None`. This is like `now()`, but returns the current UTC date and time, as a naive `datetime` object. See also `now()`.

classmethod `datetime.fromtimestamp(timestamp[, tz])`

Return the local date and time corresponding to the POSIX timestamp, such as is returned by `time.time()`. If optional argument `tz` is `None` or not specified, the timestamp is converted to the platform's local date and time, and the returned `datetime` object is naive.

If `tz` is not `None`, it must be an instance of a `tzinfo` subclass, and the timestamp is converted to `tz`'s time zone. In this case the result is equivalent to `tz.fromutc(datetime.utcfromtimestamp(timestamp)).replace(tzinfo=tz)`.

`fromtimestamp()` may raise `ValueError`, if the timestamp is out of the range of values supported by the platform C `localtime()` or `gmtime()` functions. It's common for this to be restricted to years in 1970 through 2038. Note that on non-POSIX systems that include leap seconds in their notion of a timestamp, leap seconds are ignored by `fromtimestamp()`, and then it's possible to have two timestamps differing by a second that yield identical `datetime` objects. See also `utcfromtimestamp()`.

classmethod `datetime.utcfromtimestamp(timestamp)`

Return the UTC `datetime` corresponding to the POSIX timestamp, with `tzinfo` `None`. This may raise `ValueError`, if the timestamp is out of the range of values supported by the platform C `gmtime()` function. It's common for this to be restricted to years in 1970 through 2038. See also `fromtimestamp()`.

classmethod `datetime.fromordinal(ordinal)`

Return the `datetime` corresponding to the proleptic Gregorian ordinal, where January 1 of year 1 has ordinal 1. `ValueError` is raised unless `1 <= ordinal <= datetime.max.toordinal()`. The hour, minute, second and microsecond of the result are all 0, and `tzinfo` is `None`.

classmethod `datetime.combine(date, time)`

Return a new `datetime` object whose date components are equal to the given `date` object's, and whose time components and `tzinfo` attributes are equal to the given `time` object's. For any `datetime` object `d`, `d ==`

`datetime.combine(d.date(), d.timetz())`. If `date` is a *datetime* object, its time components and *tzinfo* attributes are ignored.

classmethod `datetime.strptime(date_string, format)`

Return a *datetime* corresponding to *date_string*, parsed according to *format*. This is equivalent to `datetime(*(time.strptime(date_string, format)[0:6]))`. *ValueError* is raised if the *date_string* and *format* can't be parsed by *time.strptime()* or if it returns a value which isn't a time tuple. For a complete list of formatting directives, see section *strptime() and strftime() Behavior*.

버전 2.5에 추가.

Class attributes:

`datetime.min`

The earliest representable *datetime*, `datetime(MINYEAR, 1, 1, tzinfo=None)`.

`datetime.max`

The latest representable *datetime*, `datetime(MAXYEAR, 12, 31, 23, 59, 59, 999999, tzinfo=None)`.

`datetime.resolution`

The smallest possible difference between non-equal *datetime* objects, `timedelta(microseconds=1)`.

Instance attributes (read-only):

`datetime.year`

Between *MINYEAR* and *MAXYEAR* inclusive.

`datetime.month`

Between 1 and 12 inclusive.

`datetime.day`

Between 1 and the number of days in the given month of the given year.

`datetime.hour`

In range (24).

`datetime.minute`

In range (60).

`datetime.second`

In range (60).

`datetime.microsecond`

In range (1000000).

`datetime.tzinfo`

The object passed as the *tzinfo* argument to the *datetime* constructor, or *None* if none was passed.

Supported operations:

Operation	Result
<code>datetime2 = datetime1 + timedelta</code>	(1)
<code>datetime2 = datetime1 - timedelta</code>	(2)
<code>timedelta = datetime1 - datetime2</code>	(3)
<code>datetime1 < datetime2</code>	Compares <i>datetime</i> to <i>datetime</i> . (4)

- (1) `datetime2` is a duration of `timedelta` removed from `datetime1`, moving forward in time if `timedelta.days > 0`, or backward if `timedelta.days < 0`. The result has the same *tzinfo* attribute as the input *datetime*, and `datetime2 - datetime1 == timedelta` after. *OverflowError* is raised if `datetime2.year` would be smaller than *MINYEAR* or larger than *MAXYEAR*. Note that no time zone adjustments are done even if the input is an aware object.

- (2) Computes the `datetime2` such that `datetime2 + timedelta == datetime1`. As for addition, the result has the same `tzinfo` attribute as the input `datetime`, and no time zone adjustments are done even if the input is aware. This isn't quite equivalent to `datetime1 + (-timedelta)`, because `-timedelta` in isolation can overflow in cases where `datetime1 - timedelta` does not.

- (3) Subtraction of a `datetime` from a `datetime` is defined only if both operands are naive, or if both are aware. If one is aware and the other is naive, `TypeError` is raised.

If both are naive, or both are aware and have the same `tzinfo` attribute, the `tzinfo` attributes are ignored, and the result is a `timedelta` object `t` such that `datetime2 + t == datetime1`. No time zone adjustments are done in this case.

If both are aware and have different `tzinfo` attributes, `a-b` acts as if `a` and `b` were first converted to naive UTC datetimes first. The result is `(a.replace(tzinfo=None) - a.utcoffset()) - (b.replace(tzinfo=None) - b.utcoffset())` except that the implementation never overflows.

- (4) `datetime1` is considered less than `datetime2` when `datetime1` precedes `datetime2` in time.

If one comparand is naive and the other is aware, `TypeError` is raised. If both comparands are aware, and have the same `tzinfo` attribute, the common `tzinfo` attribute is ignored and the base datetimes are compared. If both comparands are aware and have different `tzinfo` attributes, the comparands are first adjusted by subtracting their UTC offsets (obtained from `self.utcoffset()`).

참고: In order to stop comparison from falling back to the default scheme of comparing object addresses, `datetime` comparison normally raises `TypeError` if the other comparand isn't also a `datetime` object. However, `NotImplemented` is returned instead if the other comparand has a `timetuple()` attribute. This hook gives other kinds of date objects a chance at implementing mixed-type comparison. If not, when a `datetime` object is compared to an object of a different type, `TypeError` is raised unless the comparison is `==` or `!=`. The latter cases return `False` or `True`, respectively.

`datetime` objects can be used as dictionary keys. In Boolean contexts, all `datetime` objects are considered to be true.

Instance methods:

`datetime.date()`

Return `date` object with same year, month and day.

`datetime.time()`

Return `time` object with same hour, minute, second and microsecond. `tzinfo` is `None`. See also method `timetz()`.

`datetime.timetz()`

Return `time` object with same hour, minute, second, microsecond, and `tzinfo` attributes. See also method `time()`.

`datetime.replace([year[, month[, day[, hour[, minute[, second[, microsecond[, tzinfo]]]]]]])`

Return a `datetime` with the same attributes, except for those attributes given new values by whichever keyword arguments are specified. Note that `tzinfo=None` can be specified to create a naive `datetime` from an aware `datetime` with no conversion of date and time data.

`datetime.astimezone(tz)`

Return a `datetime` object with new `tzinfo` attribute `tz`, adjusting the date and time data so the result is the same UTC time as `self`, but in `tz`'s local time.

`tz` must be an instance of a `tzinfo` subclass, and its `utcoffset()` and `dst()` methods must not return `None`. `self` must be aware (`self.tzinfo` must not be `None`, and `self.utcoffset()` must not return `None`).

If `self.tzinfo` is `tz`, `self.astimezone(tz)` is equal to `self`: no adjustment of date or time data is performed. Else the result is local time in time zone `tz`, representing the same UTC time as `self`: after `astz = dt.astimezone(tz)`, `astz - astz.utcoffset()` will usually have the same date and time data as `dt - dt.utcoffset()`. The discussion of class `tzinfo` explains the cases at Daylight Saving Time transition boundaries where this cannot be achieved (an issue only if `tz` models both standard and daylight time).

If you merely want to attach a time zone object `tz` to a datetime `dt` without adjustment of date and time data, use `dt.replace(tzinfo=tz)`. If you merely want to remove the time zone object from an aware datetime `dt` without conversion of date and time data, use `dt.replace(tzinfo=None)`.

Note that the default `tzinfo.fromutc()` method can be overridden in a `tzinfo` subclass to affect the result returned by `astimezone()`. Ignoring error cases, `astimezone()` acts like:

```
def astimezone(self, tz):
    if self.tzinfo is tz:
        return self
    # Convert self to UTC, and attach the new time zone object.
    utc = (self - self.utcoffset()).replace(tzinfo=tz)
    # Convert from UTC to tz's local time.
    return tz.fromutc(utc)
```

`datetime.utcoffset()`

If `tzinfo` is `None`, returns `None`, else returns `self.tzinfo.utcoffset(self)`, and raises an exception if the latter doesn't return `None`, or a `timedelta` object representing a whole number of minutes with magnitude less than one day.

`datetime.dst()`

If `tzinfo` is `None`, returns `None`, else returns `self.tzinfo.dst(self)`, and raises an exception if the latter doesn't return `None`, or a `timedelta` object representing a whole number of minutes with magnitude less than one day.

`datetime.tzname()`

If `tzinfo` is `None`, returns `None`, else returns `self.tzinfo.tzname(self)`, raises an exception if the latter doesn't return `None` or a string object,

`datetime.timetuple()`

Return a `time.struct_time` such as returned by `time.localtime()`. `d.timetuple()` is equivalent to `time.struct_time((d.year, d.month, d.day, d.hour, d.minute, d.second, d.weekday(), yday, dst))`, where `yday = d.toordinal() - date(d.year, 1, 1).toordinal() + 1` is the day number within the current year starting with 1 for January 1st. The `tm_isdst` flag of the result is set according to the `dst()` method: `tzinfo` is `None` or `dst()` returns `None`, `tm_isdst` is set to -1; else if `dst()` returns a non-zero value, `tm_isdst` is set to 1; else `tm_isdst` is set to 0.

`datetime.utctimetuple()`

If `datetime` instance `d` is naive, this is the same as `d.timetuple()` except that `tm_isdst` is forced to 0 regardless of what `d.dst()` returns. DST is never in effect for a UTC time.

If `d` is aware, `d` is normalized to UTC time, by subtracting `d.utcoffset()`, and a `time.struct_time` for the normalized time is returned. `tm_isdst` is forced to 0. Note that the result's `tm_year` member may be `MINYEAR-1` or `MAXYEAR+1`, if `d.year` was `MINYEAR` or `MAXYEAR` and UTC adjustment spills over a year boundary.

`datetime.toordinal()`

Return the proleptic Gregorian ordinal of the date. The same as `self.date().toordinal()`.

`datetime.weekday()`

Return the day of the week as an integer, where Monday is 0 and Sunday is 6. The same as `self.date().weekday()`. See also `isoweekday()`.

`datetime.isoweekday()`

Return the day of the week as an integer, where Monday is 1 and Sunday is 7. The same as `self.date().isoweekday()`. See also `weekday()`, `isocalendar()`.

`datetime.isocalendar()`

Return a 3-tuple, (ISO year, ISO week number, ISO weekday). The same as `self.date().isocalendar()`.

`datetime.isoformat([sep])`

Return a string representing the date and time in ISO 8601 format, YYYY-MM-DDTHH:MM:SS.mmmmmmm or, if `microsecond` is 0, YYYY-MM-DDTHH:MM:SS

If `utcoffset()` does not return None, a 6-character string is appended, giving the UTC offset in (signed) hours and minutes: YYYY-MM-DDTHH:MM:SS.mmmmmmm+HH:MM or, if `microsecond` is 0 YYYY-MM-DDTHH:MM:SS+HH:MM

The optional argument `sep` (default 'T') is a one-character separator, placed between the date and time portions of the result. For example,

```
>>> from datetime import tzinfo, timedelta, datetime
>>> class TZ(tzinfo):
...     def utcoffset(self, dt): return timedelta(minutes=-399)
...
>>> datetime(2002, 12, 25, tzinfo=TZ()).isoformat(' ')
'2002-12-25 00:00:00-06:39'
```

`datetime.__str__()`

For a `datetime` instance `d`, `str(d)` is equivalent to `d.isoformat(' ')`.

`datetime.ctime()`

Return a string representing the date and time, for example `datetime(2002, 12, 4, 20, 30, 40).ctime() == 'Wed Dec 4 20:30:40 2002'`. `d.ctime()` is equivalent to `time.ctime(time.mktime(d.timetuple()))` on platforms where the native C `ctime()` function (which `time.ctime()` invokes, but which `datetime.ctime()` does not invoke) conforms to the C standard.

`datetime.strftime(format)`

Return a string representing the date and time, controlled by an explicit format string. For a complete list of formatting directives, see section *strftime() and strptime() Behavior*.

`datetime.__format__(format)`

Same as `datetime.strftime()`. This makes it possible to specify a format string for a `datetime` object when using `str.format()`. See section *strftime() and strptime() Behavior*.

Examples of working with datetime objects:

```
>>> from datetime import datetime, date, time
>>> # Using datetime.combine()
>>> d = date(2005, 7, 14)
>>> t = time(12, 30)
>>> datetime.combine(d, t)
datetime.datetime(2005, 7, 14, 12, 30)
>>> # Using datetime.now() or datetime.utcnow()
>>> datetime.now()
datetime.datetime(2007, 12, 6, 16, 29, 43, 79043) # GMT +1
>>> datetime.utcnow()
datetime.datetime(2007, 12, 6, 15, 29, 43, 79060)
>>> # Using datetime.strptime()
>>> dt = datetime.strptime("21/11/06 16:30", "%d/%m/%y %H:%M")
>>> dt
datetime.datetime(2006, 11, 21, 16, 30)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

>>> # Using datetime.timetuple() to get tuple of all attributes
>>> tt = dt.timetuple()
>>> for it in tt:
...     print it
...
2006      # year
11        # month
21        # day
16        # hour
30        # minute
0         # second
1         # weekday (0 = Monday)
325       # number of days since 1st January
-1        # dst - method tzinfo.dst() returned None
>>> # Date in ISO format
>>> ic = dt.isocalendar()
>>> for it in ic:
...     print it
...
2006      # ISO year
47        # ISO week
2         # ISO weekday
>>> # Formatting datetime
>>> dt.strftime("%A, %d. %B %Y %I:%M%p")
'Tuesday, 21. November 2006 04:30PM'
>>> 'The {1} is {0:%d}, the {2} is {0:%B}, the {3} is {0:%I:%M%p}.'.format(dt, "day",
↪ "month", "time")
'The day is 21, the month is November, the time is 04:30PM.'

```

Using datetime with tzinfo:

```

>>> from datetime import timedelta, datetime, tzinfo
>>> class GMT1(tzinfo):
...     def utcoffset(self, dt):
...         return timedelta(hours=1) + self.dst(dt)
...     def dst(self, dt):
...         # DST starts last Sunday in March
...         d = datetime(dt.year, 4, 1) # ends last Sunday in October
...         self.dston = d - timedelta(days=d.weekday() + 1)
...         d = datetime(dt.year, 11, 1)
...         self.dstoff = d - timedelta(days=d.weekday() + 1)
...         if self.dston <= dt.replace(tzinfo=None) < self.dstoff:
...             return timedelta(hours=1)
...         else:
...             return timedelta(0)
...     def tzname(self, dt):
...         return "GMT +1"
...
>>> class GMT2(tzinfo):
...     def utcoffset(self, dt):
...         return timedelta(hours=2) + self.dst(dt)
...     def dst(self, dt):
...         d = datetime(dt.year, 4, 1)
...         self.dston = d - timedelta(days=d.weekday() + 1)
...         d = datetime(dt.year, 11, 1)
...         self.dstoff = d - timedelta(days=d.weekday() + 1)

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

...         if self.dston <= dt.replace(tzinfo=None) < self.dstoff:
...             return timedelta(hours=1)
...         else:
...             return timedelta(0)
...     def tzname(self, dt):
...         return "GMT +2"
...
>>> gmt1 = GMT1()
>>> # Daylight Saving Time
>>> dt1 = datetime(2006, 11, 21, 16, 30, tzinfo=gmt1)
>>> dt1.dst()
datetime.timedelta(0)
>>> dt1.utcoffset()
datetime.timedelta(0, 3600)
>>> dt2 = datetime(2006, 6, 14, 13, 0, tzinfo=gmt1)
>>> dt2.dst()
datetime.timedelta(0, 3600)
>>> dt2.utcoffset()
datetime.timedelta(0, 7200)
>>> # Convert datetime to another time zone
>>> dt3 = dt2.astimezone(GMT2())
>>> dt3
datetime.datetime(2006, 6, 14, 14, 0, tzinfo=<GMT2 object at 0x...>)
>>> dt2
datetime.datetime(2006, 6, 14, 13, 0, tzinfo=<GMT1 object at 0x...>)
>>> dt2.utctimetuple() == dt3.utctimetuple()
True

```

8.1.5 time Objects

A time object represents a (local) time of day, independent of any particular day, and subject to adjustment via a *tzinfo* object.

class `datetime.time([hour[, minute[, second[, microsecond[, tzinfo]]]])`

All arguments are optional. *tzinfo* may be `None`, or an instance of a *tzinfo* subclass. The remaining arguments may be ints or longs, in the following ranges:

- `0 <= hour < 24`
- `0 <= minute < 60`
- `0 <= second < 60`
- `0 <= microsecond < 1000000`.

If an argument outside those ranges is given, *ValueError* is raised. All default to 0 except *tzinfo*, which defaults to *None*.

Class attributes:

`time.min`

The earliest representable *time*, `time(0, 0, 0, 0)`.

`time.max`

The latest representable *time*, `time(23, 59, 59, 999999)`.

`time.resolution`

The smallest possible difference between non-equal *time* objects, `timedelta(microseconds=1)`, although

note that arithmetic on `time` objects is not supported.

Instance attributes (read-only):

`time.hour`
In range (24).

`time.minute`
In range (60).

`time.second`
In range (60).

`time.microsecond`
In range (1000000).

`time.tzinfo`
The object passed as the `tzinfo` argument to the `time` constructor, or `None` if none was passed.

Supported operations:

- comparison of `time` to `time`, where *a* is considered less than *b* when *a* precedes *b* in time. If one comparand is naive and the other is aware, `TypeError` is raised. If both comparands are aware, and have the same `tzinfo` attribute, the common `tzinfo` attribute is ignored and the base times are compared. If both comparands are aware and have different `tzinfo` attributes, the comparands are first adjusted by subtracting their UTC offsets (obtained from `self.utcoffset()`). In order to stop mixed-type comparisons from falling back to the default comparison by object address, when a `time` object is compared to an object of a different type, `TypeError` is raised unless the comparison is `==` or `!=`. The latter cases return `False` or `True`, respectively.
- hash, use as dict key
- efficient pickling
- in Boolean contexts, a `time` object is considered to be true if and only if, after converting it to minutes and subtracting `utcoffset()` (or 0 if that's `None`), the result is non-zero.

Instance methods:

`time.replace([hour[, minute[, second[, microsecond[, tzinfo]]]])`
Return a `time` with the same value, except for those attributes given new values by whichever keyword arguments are specified. Note that `tzinfo=None` can be specified to create a naive `time` from an aware `time`, without conversion of the time data.

`time.isoformat()`
Return a string representing the time in ISO 8601 format, HH:MM:SS.mmmmmmm or, if `self.microsecond` is 0, HH:MM:SS. If `utcoffset()` does not return `None`, a 6-character string is appended, giving the UTC offset in (signed) hours and minutes: HH:MM:SS.mmmmmmm+HH:MM or, if `self.microsecond` is 0, HH:MM:SS+HH:MM

`time.__str__()`
For a time *t*, `str(t)` is equivalent to `t.isoformat()`.

`time.strftime(format)`
Return a string representing the time, controlled by an explicit format string. For a complete list of formatting directives, see section *strftime() and strptime() Behavior*.

`time.__format__(format)`
Same as `time.strftime()`. This makes it possible to specify a format string for a `time` object when using `str.format()`. See section *strftime() and strptime() Behavior*.

`time.utcoffset()`
If `tzinfo` is `None`, returns `None`, else returns `self.tzinfo.utcoffset(None)`, and raises an exception if the latter doesn't return `None` or a `timedelta` object representing a whole number of minutes with magnitude less than one day.

`time.dst()`

If `tzinfo` is `None`, returns `None`, else returns `self.tzinfo.dst(None)`, and raises an exception if the latter doesn't return `None`, or a `timedelta` object representing a whole number of minutes with magnitude less than one day.

`time.tzname()`

If `tzinfo` is `None`, returns `None`, else returns `self.tzinfo.tzname(None)`, or raises an exception if the latter doesn't return `None` or a string object.

Example:

```
>>> from datetime import time, tzinfo, timedelta
>>> class GMT1(tzinfo):
...     def utcoffset(self, dt):
...         return timedelta(hours=1)
...     def dst(self, dt):
...         return timedelta(0)
...     def tzname(self, dt):
...         return "Europe/Prague"
...
>>> t = time(12, 10, 30, tzinfo=GMT1())
>>> t
datetime.time(12, 10, 30, tzinfo=<GMT1 object at 0x...>)
>>> gmt = GMT1()
>>> t.isoformat()
'12:10:30+01:00'
>>> t.dst()
datetime.timedelta(0)
>>> t.tzname()
'Europe/Prague'
>>> t.strftime("%H:%M:%S %Z")
'12:10:30 Europe/Prague'
>>> 'The {} is {:%H:%M}'.format("time", t)
'The time is 12:10.'
```

8.1.6 tzinfo Objects

class `datetime.tzinfo`

This is an abstract base class, meaning that this class should not be instantiated directly. You need to derive a concrete subclass, and (at least) supply implementations of the standard `tzinfo` methods needed by the `datetime` methods you use. The `datetime` module does not supply any concrete subclasses of `tzinfo`.

An instance of (a concrete subclass of) `tzinfo` can be passed to the constructors for `datetime` and `time` objects. The latter objects view their attributes as being in local time, and the `tzinfo` object supports methods revealing offset of local time from UTC, the name of the time zone, and DST offset, all relative to a date or time object passed to them.

Special requirement for pickling: A `tzinfo` subclass must have an `__init__()` method that can be called with no arguments, else it can be pickled but possibly not unpickled again. This is a technical requirement that may be relaxed in the future.

A concrete subclass of `tzinfo` may need to implement the following methods. Exactly which methods are needed depends on the uses made of aware `datetime` objects. If in doubt, simply implement all of them.

`tzinfo.utcoffset(self, dt)`

Return offset of local time from UTC, in minutes east of UTC. If local time is west of UTC, this should be negative. Note that this is intended to be the total offset from UTC; for example, if a `tzinfo` object represents both time zone and DST adjustments, `utcoffset()` should return their sum. If the UTC offset isn't known, return `None`.

Else the value returned must be a `timedelta` object specifying a whole number of minutes in the range -1439 to 1439 inclusive (1440 = 24*60; the magnitude of the offset must be less than one day). Most implementations of `utcoffset()` will probably look like one of these two:

```
return CONSTANT          # fixed-offset class
return CONSTANT + self.dst(dt) # daylight-aware class
```

If `utcoffset()` does not return `None`, `dst()` should not return `None` either.

The default implementation of `utcoffset()` raises `NotImplementedError`.

`tzinfo.dst(self, dt)`

Return the daylight saving time (DST) adjustment, in minutes east of UTC, or `None` if DST information isn't known. Return `timedelta(0)` if DST is not in effect. If DST is in effect, return the offset as a `timedelta` object (see `utcoffset()` for details). Note that DST offset, if applicable, has already been added to the UTC offset returned by `utcoffset()`, so there's no need to consult `dst()` unless you're interested in obtaining DST info separately. For example, `datetime.timetuple()` calls its `tzinfo` attribute's `dst()` method to determine how the `tm_isdst` flag should be set, and `tzinfo.fromutc()` calls `dst()` to account for DST changes when crossing time zones.

An instance `tz` of a `tzinfo` subclass that models both standard and daylight times must be consistent in this sense:

```
tz.utcoffset(dt) - tz.dst(dt)
```

must return the same result for every `datetime dt` with `dt.tzinfo == tz`. For sane `tzinfo` subclasses, this expression yields the time zone's «standard offset», which should not depend on the date or the time, but only on geographic location. The implementation of `datetime.astimezone()` relies on this, but cannot detect violations; it's the programmer's responsibility to ensure it. If a `tzinfo` subclass cannot guarantee this, it may be able to override the default implementation of `tzinfo.fromutc()` to work correctly with `astimezone()` regardless.

Most implementations of `dst()` will probably look like one of these two:

```
def dst(self, dt):
    # a fixed-offset class: doesn't account for DST
    return timedelta(0)
```

or

```
def dst(self, dt):
    # Code to set dston and dstoff to the time zone's DST
    # transition times based on the input dt.year, and expressed
    # in standard local time. Then

    if dston <= dt.replace(tzinfo=None) < dstoff:
        return timedelta(hours=1)
    else:
        return timedelta(0)
```

The default implementation of `dst()` raises `NotImplementedError`.

`tzinfo.tzname(self, dt)`

Return the time zone name corresponding to the `datetime` object `dt`, as a string. Nothing about string names is defined by the `datetime` module, and there's no requirement that it mean anything in particular. For example, «GMT», «UTC», «-500», «-5:00», «EDT», «US/Eastern», «America/New York» are all valid replies. Return `None` if a string name isn't known. Note that this is a method rather than a fixed string primarily because some `tzinfo` subclasses will wish to return different names depending on the specific value of `dt` passed, especially if the `tzinfo` class is accounting for daylight time.

The default implementation of `tzname()` raises `NotImplementedError`.

These methods are called by a `datetime` or `time` object, in response to their methods of the same names. A `datetime` object passes itself as the argument, and a `time` object passes `None` as the argument. A `tzinfo` subclass's methods should therefore be prepared to accept a `dt` argument of `None`, or of class `datetime`.

When `None` is passed, it's up to the class designer to decide the best response. For example, returning `None` is appropriate if the class wishes to say that time objects don't participate in the `tzinfo` protocols. It may be more useful for `utcoffset(None)` to return the standard UTC offset, as there is no other convention for discovering the standard offset.

When a `datetime` object is passed in response to a `datetime` method, `dt.tzinfo` is the same object as `self`. `tzinfo` methods can rely on this, unless user code calls `tzinfo` methods directly. The intent is that the `tzinfo` methods interpret `dt` as being in local time, and not need worry about objects in other timezones.

There is one more `tzinfo` method that a subclass may wish to override:

`tzinfo.fromutc(self, dt)`

This is called from the default `datetime.astimezone()` implementation. When called from that, `dt.tzinfo` is `self`, and `dt`'s date and time data are to be viewed as expressing a UTC time. The purpose of `fromutc()` is to adjust the date and time data, returning an equivalent datetime in `self`'s local time.

Most `tzinfo` subclasses should be able to inherit the default `fromutc()` implementation without problems. It's strong enough to handle fixed-offset time zones, and time zones accounting for both standard and daylight time, and the latter even if the DST transition times differ in different years. An example of a time zone the default `fromutc()` implementation may not handle correctly in all cases is one where the standard offset (from UTC) depends on the specific date and time passed, which can happen for political reasons. The default implementations of `astimezone()` and `fromutc()` may not produce the result you want if the result is one of the hours straddling the moment the standard offset changes.

Skipping code for error cases, the default `fromutc()` implementation acts like:

```
def fromutc(self, dt):
    # raise ValueError error if dt.tzinfo is not self
    dtoff = dt.utcoffset()
    dtdst = dt.dst()
    # raise ValueError if dtoff is None or dtdst is None
    delta = dtoff - dtdst # this is self's standard offset
    if delta:
        dt += delta # convert to standard local time
        dtdst = dt.dst()
        # raise ValueError if dtdst is None
    if dtdst:
        return dt + dtdst
    else:
        return dt
```

Example `tzinfo` classes:

```
from datetime import tzinfo, timedelta, datetime

ZERO = timedelta(0)
HOUR = timedelta(hours=1)

# A UTC class.

class UTC(tzinfo):
    """UTC"""

    def utcoffset(self, dt):
        return ZERO
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

def tzname(self, dt):
    return "UTC"

def dst(self, dt):
    return ZERO

utc = UTC()

# A class building tzinfo objects for fixed-offset time zones.
# Note that FixedOffset(0, "UTC") is a different way to build a
# UTC tzinfo object.

class FixedOffset(tzinfo):
    """Fixed offset in minutes east from UTC."""

    def __init__(self, offset, name):
        self.__offset = timedelta(minutes = offset)
        self.__name = name

    def utcoffset(self, dt):
        return self.__offset

    def tzname(self, dt):
        return self.__name

    def dst(self, dt):
        return ZERO

# A class capturing the platform's idea of local time.

import time as _time

STDOFFSET = timedelta(seconds = -_time.timezone)
if _time.daylight:
    DSTOFFSET = timedelta(seconds = -_time.altzone)
else:
    DSTOFFSET = STDOFFSET

DSTDIFF = DSTOFFSET - STDOFFSET

class LocalTimezone(tzinfo):

    def utcoffset(self, dt):
        if self._isdst(dt):
            return DSTOFFSET
        else:
            return STDOFFSET

    def dst(self, dt):
        if self._isdst(dt):
            return DSTDIFF
        else:
            return ZERO

    def tzname(self, dt):

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

        return _time.tzname[self._isdst(dt)]

    def _isdst(self, dt):
        tt = (dt.year, dt.month, dt.day,
              dt.hour, dt.minute, dt.second,
              dt.weekday(), 0, 0)
        stamp = _time.mktime(tt)
        tt = _time.localtime(stamp)
        return tt.tm_isdst > 0

Local = LocalTimezone()

# A complete implementation of current DST rules for major US time zones.

def first_sunday_on_or_after(dt):
    days_to_go = 6 - dt.weekday()
    if days_to_go:
        dt += timedelta(days_to_go)
    return dt

# US DST Rules
#
# This is a simplified (i.e., wrong for a few cases) set of rules for US
# DST start and end times. For a complete and up-to-date set of DST rules
# and timezone definitions, visit the Olson Database (or try pytz):
# http://www.twinsun.com/tz/tz-link.htm
# http://sourceforge.net/projects/pytz/ (might not be up-to-date)
#
# In the US, since 2007, DST starts at 2am (standard time) on the second
# Sunday in March, which is the first Sunday on or after Mar 8.
DSTSTART_2007 = datetime(1, 3, 8, 2)
# and ends at 2am (DST time; 1am standard time) on the first Sunday of Nov.
DSTEND_2007 = datetime(1, 11, 1, 1)
# From 1987 to 2006, DST used to start at 2am (standard time) on the first
# Sunday in April and to end at 2am (DST time; 1am standard time) on the last
# Sunday of October, which is the first Sunday on or after Oct 25.
DSTSTART_1987_2006 = datetime(1, 4, 1, 2)
DSTEND_1987_2006 = datetime(1, 10, 25, 1)
# From 1967 to 1986, DST used to start at 2am (standard time) on the last
# Sunday in April (the one on or after April 24) and to end at 2am (DST time;
# 1am standard time) on the last Sunday of October, which is the first Sunday
# on or after Oct 25.
DSTSTART_1967_1986 = datetime(1, 4, 24, 2)
DSTEND_1967_1986 = DSTEND_1987_2006

class USTimeZone(tzinfo):

    def __init__(self, hours, reprname, stdname, dstname):
        self.stdoffset = timedelta(hours=hours)
        self.reprname = reprname
        self.stdname = stdname
        self.dstname = dstname

    def __repr__(self):

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    return self.reprname

def tzname(self, dt):
    if self.dst(dt):
        return self.dstname
    else:
        return self.stdname

def utcoffset(self, dt):
    return self.stdoffset + self.dst(dt)

def dst(self, dt):
    if dt is None or dt.tzinfo is None:
        # An exception may be sensible here, in one or both cases.
        # It depends on how you want to treat them. The default
        # fromutc() implementation (called by the default astimezone()
        # implementation) passes a datetime with dt.tzinfo is self.
        return ZERO
    assert dt.tzinfo is self

    # Find start and end times for US DST. For years before 1967, return
    # ZERO for no DST.
    if 2006 < dt.year:
        dststart, dstend = DSTSTART_2007, DSTEND_2007
    elif 1986 < dt.year < 2007:
        dststart, dstend = DSTSTART_1987_2006, DSTEND_1987_2006
    elif 1966 < dt.year < 1987:
        dststart, dstend = DSTSTART_1967_1986, DSTEND_1967_1986
    else:
        return ZERO

    start = first_sunday_on_or_after(dststart.replace(year=dt.year))
    end = first_sunday_on_or_after(dstend.replace(year=dt.year))

    # Can't compare naive to aware objects, so strip the timezone from
    # dt first.
    if start <= dt.replace(tzinfo=None) < end:
        return HOUR
    else:
        return ZERO

Eastern = USTimeZone(-5, "Eastern", "EST", "EDT")
Central = USTimeZone(-6, "Central", "CST", "CDT")
Mountain = USTimeZone(-7, "Mountain", "MST", "MDT")
Pacific = USTimeZone(-8, "Pacific", "PST", "PDT")

```

Note that there are unavoidable subtleties twice per year in a `tzinfo` subclass accounting for both standard and daylight time, at the DST transition points. For concreteness, consider US Eastern (UTC -0500), where EDT begins the minute after 1:59 (EST) on the second Sunday in March, and ends the minute after 1:59 (EDT) on the first Sunday in November:

UTC	3:MM	4:MM	5:MM	6:MM	7:MM	8:MM
EST	22:MM	23:MM	0:MM	1:MM	2:MM	3:MM
EDT	23:MM	0:MM	1:MM	2:MM	3:MM	4:MM
start	22:MM	23:MM	0:MM	1:MM	3:MM	4:MM
end	23:MM	0:MM	1:MM	1:MM	2:MM	3:MM

When DST starts (the «start» line), the local wall clock leaps from 1:59 to 3:00. A wall time of the form 2:MM doesn't really make sense on that day, so `astimezone(Eastern)` won't deliver a result with `hour == 2` on the day DST begins. In order for `astimezone()` to make this guarantee, the `tzinfo.dst()` method must consider times in the «missing hour» (2:MM for Eastern) to be in daylight time.

When DST ends (the «end» line), there's a potentially worse problem: there's an hour that can't be spelled unambiguously in local wall time: the last hour of daylight time. In Eastern, that's times of the form 5:MM UTC on the day daylight time ends. The local wall clock leaps from 1:59 (daylight time) back to 1:00 (standard time) again. Local times of the form 1:MM are ambiguous. `astimezone()` mimics the local clock's behavior by mapping two adjacent UTC hours into the same local hour then. In the Eastern example, UTC times of the form 5:MM and 6:MM both map to 1:MM when converted to Eastern. In order for `astimezone()` to make this guarantee, the `tzinfo.dst()` method must consider times in the «repeated hour» to be in standard time. This is easily arranged, as in the example, by expressing DST switch times in the time zone's standard local time.

Applications that can't bear such ambiguities should avoid using hybrid `tzinfo` subclasses; there are no ambiguities when using UTC, or any other fixed-offset `tzinfo` subclass (such as a class representing only EST (fixed offset -5 hours), or only EDT (fixed offset -4 hours)).

더 보기:

pytz The standard library has no `tzinfo` instances, but there exists a third-party library which brings the *IANA timezone database* (also known as the Olson database) to Python: `pytz`.

`pytz` contains up-to-date information and its usage is recommended.

IANA timezone database The Time Zone Database (often called tz or zoneinfo) contains code and data that represent the history of local time for many representative locations around the globe. It is updated periodically to reflect changes made by political bodies to time zone boundaries, UTC offsets, and daylight-saving rules.

8.1.7 `strftime()` and `strptime()` Behavior

`date`, `datetime`, and `time` objects all support a `strftime(format)` method, to create a string representing the time under the control of an explicit format string. Broadly speaking, `d.strftime(fmt)` acts like the `time` module's `time.strftime(fmt, d.timetuple())` although not all objects support a `timetuple()` method.

Conversely, the `datetime.strptime()` class method creates a `datetime` object from a string representing a date and time and a corresponding format string. `datetime.strptime(date_string, format)` is equivalent to `datetime(*(time.strptime(date_string, format)[0:6]))`, except when the format includes sub-second components or timezone offset information, which are supported in `datetime.strptime` but are discarded by `time.strptime`.

For `time` objects, the format codes for year, month, and day should not be used, as time objects have no such values. If they're used anyway, 1900 is substituted for the year, and 1 for the month and day.

For `date` objects, the format codes for hours, minutes, seconds, and microseconds should not be used, as `date` objects have no such values. If they're used anyway, 0 is substituted for them.

The full set of format codes supported varies across platforms, because Python calls the platform C library's `strftime()` function, and platform variations are common. To see the full set of format codes supported on your platform, consult the `strftime(3)` documentation.

For the same reason, handling of format strings containing Unicode code points that can't be represented in the charset of the current locale is also platform-dependent. On some platforms such code points are preserved intact in the output, while on others `strftime` may raise `UnicodeError` or return an empty string instead.

The following is a list of all the format codes that the C standard (1989 version) requires, and these work on all platforms with a standard C implementation. Note that the 1999 version of the C standard added additional format codes.

The exact range of years for which `strftime()` works also varies across platforms. Regardless of platform, years before 1900 cannot be used.

Directive	Meaning	Example	Notes
%a	Weekday as locale's abbreviated name.	Sun, Mon, ..., Sat (en_US); So, Mo, ..., Sa (de_DE)	(1)
%A	Weekday as locale's full name.	Sunday, Monday, ..., Saturday (en_US); Sonntag, Montag, ..., Samstag (de_DE)	(1)
%w	Weekday as a decimal number, where 0 is Sunday and 6 is Saturday.	0, 1, ..., 6	
%d	Day of the month as a zero-padded decimal number.	01, 02, ..., 31	
%b	Month as locale's abbreviated name.	Jan, Feb, ..., Dec (en_US); Jan, Feb, ..., Dez (de_DE)	(1)
%B	Month as locale's full name.	January, February, ..., December (en_US); Januar, Februar, ..., Dezember (de_DE)	(1)
%m	Month as a zero-padded decimal number.	01, 02, ..., 12	
%y	Year without century as a zero-padded decimal number.	00, 01, ..., 99	
%Y	Year with century as a decimal number.	1970, 1988, 2001, 2013	
%H	Hour (24-hour clock) as a zero-padded decimal number.	00, 01, ..., 23	
%I	Hour (12-hour clock) as a zero-padded decimal number.	01, 02, ..., 12	
%p	Locale's equivalent of either AM or PM.	AM, PM (en_US); am, pm (de_DE)	(1), (2)
%M	Minute as a zero-padded decimal number.	00, 01, ..., 59	
%S	Second as a zero-padded decimal number.	00, 01, ..., 59	(3)
%f	Microsecond as a decimal number, zero-padded on	000000, 000001, ..., 999999	(4)
8.1. datetime — Basic date and time types			167
%z	UTC offset in the form +HHMM or -HHMM (empty string if the	(empty), +0000, -0400, +1030	(5)

Notes:

- (1) Because the format depends on the current locale, care should be taken when making assumptions about the output value. Field orderings will vary (for example, 《month/day/year》 versus 《day/month/year》), and the output may contain Unicode characters encoded using the locale's default encoding (for example, if the current locale is `ja_JP`, the default encoding could be any one of `eucJP`, `SJIS`, or `utf-8`; use `locale.getlocale()` to determine the current locale's encoding).
- (2) When used with the `strptime()` method, the `%p` directive only affects the output hour field if the `%I` directive is used to parse the hour.
- (3) Unlike the `time` module, the `datetime` module does not support leap seconds.
- (4) `%f` is an extension to the set of format characters in the C standard (but implemented separately in datetime objects, and therefore always available). When used with the `strptime()` method, the `%f` directive accepts from one to six digits and zero pads on the right.

버전 2.6에 추가.

- (5) For a naive object, the `%z` and `%Z` format codes are replaced by empty strings.

For an aware object:

%z `utcoffset()` is transformed into a 5-character string of the form `+HHMM` or `-HHMM`, where `HH` is a 2-digit string giving the number of UTC offset hours, and `MM` is a 2-digit string giving the number of UTC offset minutes. For example, if `utcoffset()` returns `timedelta(hours=-3, minutes=-30)`, `%z` is replaced with the string `'-0330'`.

%Z If `tzname()` returns `None`, `%Z` is replaced by an empty string. Otherwise `%Z` is replaced by the returned value, which must be a string.

- (6) When used with the `strptime()` method, `%U` and `%W` are only used in calculations when the day of the week and the year are specified.

8.2 calendar — General calendar-related functions

Source code: [Lib/calendar.py](#)

This module allows you to output calendars like the Unix `cal` program, and provides additional useful functions related to the calendar. By default, these calendars have Monday as the first day of the week, and Sunday as the last (the European convention). Use `setfirstweekday()` to set the first day of the week to Sunday (6) or to any other weekday. Parameters that specify dates are given as integers. For related functionality, see also the `datetime` and `time` modules.

Most of these functions and classes rely on the `datetime` module which uses an idealized calendar, the current Gregorian calendar indefinitely extended in both directions. This matches the definition of the 《proleptic Gregorian》 calendar in Dershowitz and Reingold's book 《Calendrical Calculations》, where it's the base calendar for all computations.

class `calendar.Calendar`(`[firstweekday]`)

Creates a `Calendar` object. `firstweekday` is an integer specifying the first day of the week. 0 is Monday (the default), 6 is Sunday.

A `Calendar` object provides several methods that can be used for preparing the calendar data for formatting. This class doesn't do any formatting itself. This is the job of subclasses.

버전 2.5에 추가.

`Calendar` instances have the following methods:

iterweekdays ()

Return an iterator for the week day numbers that will be used for one week. The first value from the iterator will be the same as the value of the `firstweekday` property.

itermonthdates (year, month)

Return an iterator for the month *month* (1–12) in the year *year*. This iterator will return all days (as `datetime.date` objects) for the month and all days before the start of the month or after the end of the month that are required to get a complete week.

itermonthdays2 (year, month)

Return an iterator for the month *month* in the year *year* similar to `itermonthdates ()`. Days returned will be tuples consisting of a day number and a week day number.

itermonthdays (year, month)

Return an iterator for the month *month* in the year *year* similar to `itermonthdates ()`. Days returned will simply be day numbers.

monthdatescalendar (year, month)

Return a list of the weeks in the month *month* of the *year* as full weeks. Weeks are lists of seven `datetime.date` objects.

monthdays2calendar (year, month)

Return a list of the weeks in the month *month* of the *year* as full weeks. Weeks are lists of seven tuples of day numbers and weekday numbers.

monthdayscalendar (year, month)

Return a list of the weeks in the month *month* of the *year* as full weeks. Weeks are lists of seven day numbers.

yeardatescalendar (year[, width])

Return the data for the specified year ready for formatting. The return value is a list of month rows. Each month row contains up to *width* months (defaulting to 3). Each month contains between 4 and 6 weeks and each week contains 1–7 days. Days are `datetime.date` objects.

yeardays2calendar (year[, width])

Return the data for the specified year ready for formatting (similar to `yeardatescalendar ()`). Entries in the week lists are tuples of day numbers and weekday numbers. Day numbers outside this month are zero.

yeardayscalendar (year[, width])

Return the data for the specified year ready for formatting (similar to `yeardatescalendar ()`). Entries in the week lists are day numbers. Day numbers outside this month are zero.

class calendar.TextCalendar ([firstweekday])

This class can be used to generate plain text calendars.

버전 2.5에 추가.

`TextCalendar` instances have the following methods:

formatmonth (theyear, themonth[, w[, l]])

Return a month's calendar in a multi-line string. If *w* is provided, it specifies the width of the date columns, which are centered. If *l* is given, it specifies the number of lines that each week will use. Depends on the first weekday as specified in the constructor or set by the `setfirstweekday ()` method.

prmonth (theyear, themonth[, w[, l]])

Print a month's calendar as returned by `formatmonth ()`.

formatyear (theyear[, w[, l[, c[, m]]]])

Return a *m*-column calendar for an entire year as a multi-line string. Optional parameters *w*, *l*, and *c* are for date column width, lines per week, and number of spaces between month columns, respectively. Depends on the first weekday as specified in the constructor or set by the `setfirstweekday ()` method. The earliest year for which a calendar can be generated is platform-dependent.

pryear (*theyear* [, *w* [, *l* [, *c* [, *m*]]]]])

Print the calendar for an entire year as returned by `formatyear()`.

class `calendar.HTMLCalendar` ([*firstweekday*])

This class can be used to generate HTML calendars.

버전 2.5에 추가.

`HTMLCalendar` instances have the following methods:

formatmonth (*theyear*, *themoth* [, *withyear*])

Return a month's calendar as an HTML table. If *withyear* is true the year will be included in the header, otherwise just the month name will be used.

formatyear (*theyear* [, *width*])

Return a year's calendar as an HTML table. *width* (defaulting to 3) specifies the number of months per row.

formatyearpage (*theyear* [, *width* [, *css* [, *encoding*]]]])

Return a year's calendar as a complete HTML page. *width* (defaulting to 3) specifies the number of months per row. *css* is the name for the cascading style sheet to be used. *None* can be passed if no style sheet should be used. *encoding* specifies the encoding to be used for the output (defaulting to the system default encoding).

class `calendar.LocaleTextCalendar` ([*firstweekday* [, *locale*]])

This subclass of `TextCalendar` can be passed a locale name in the constructor and will return month and weekday names in the specified locale. If this locale includes an encoding all strings containing month and weekday names will be returned as unicode.

버전 2.5에 추가.

class `calendar.LocaleHTMLCalendar` ([*firstweekday* [, *locale*]])

This subclass of `HTMLCalendar` can be passed a locale name in the constructor and will return month and weekday names in the specified locale. If this locale includes an encoding all strings containing month and weekday names will be returned as unicode.

버전 2.5에 추가.

참고: The `formatweekday()` and `formatmonthname()` methods of these two classes temporarily change the current locale to the given *locale*. Because the current locale is a process-wide setting, they are not thread-safe.

For simple text calendars this module provides the following functions.

`calendar.setfirstweekday` (*weekday*)

Sets the weekday (0 is Monday, 6 is Sunday) to start each week. The values MONDAY, TUESDAY, WEDNESDAY, THURSDAY, FRIDAY, SATURDAY, and SUNDAY are provided for convenience. For example, to set the first weekday to Sunday:

```
import calendar
calendar.setfirstweekday(calendar.SUNDAY)
```

버전 2.0에 추가.

`calendar.firstweekday` ()

Returns the current setting for the weekday to start each week.

버전 2.0에 추가.

`calendar.isleap` (*year*)

Returns *True* if *year* is a leap year, otherwise *False*.

`calendar.leapdays` (*y1*, *y2*)

Returns the number of leap years in the range from *y1* to *y2* (exclusive), where *y1* and *y2* are years.

버전 2.0에서 변경: This function didn't work for ranges spanning a century change in Python 1.5.2.

`calendar.weekday(year, month, day)`

Returns the day of the week (0 is Monday) for *year* (1970–...), *month* (1–12), *day* (1–31).

`calendar.weekheader(n)`

Return a header containing abbreviated weekday names. *n* specifies the width in characters for one weekday.

`calendar.monthrange(year, month)`

Returns weekday of first day of the month and number of days in month, for the specified *year* and *month*.

`calendar.monthcalendar(year, month)`

Returns a matrix representing a month's calendar. Each row represents a week; days outside of the month are represented by zeros. Each week begins with Monday unless set by `setfirstweekday()`.

`calendar.prmnth(theyear, themonth[, w[, l]])`

Prints a month's calendar as returned by `month()`.

`calendar.month(theyear, themonth[, w[, l]])`

Returns a month's calendar in a multi-line string using the `formatmonth()` of the `TextCalendar` class.

버전 2.0에 추가.

`calendar.prcal(year[, w[, l[c]]])`

Prints the calendar for an entire year as returned by `calendar()`.

`calendar.calendar(year[, w[, l[c]]])`

Returns a 3-column calendar for an entire year as a multi-line string using the `formatyear()` of the `TextCalendar` class.

버전 2.0에 추가.

`calendar.timegm(tuple)`

An unrelated but handy function that takes a time tuple such as returned by the `gmtime()` function in the `time` module, and returns the corresponding Unix timestamp value, assuming an epoch of 1970, and the POSIX encoding. In fact, `time.gmtime()` and `timegm()` are each others' inverse.

버전 2.0에 추가.

The `calendar` module exports the following data attributes:

`calendar.day_name`

An array that represents the days of the week in the current locale.

`calendar.day_abbr`

An array that represents the abbreviated days of the week in the current locale.

`calendar.month_name`

An array that represents the months of the year in the current locale. This follows normal convention of January being month number 1, so it has a length of 13 and `month_name[0]` is the empty string.

`calendar.month_abbr`

An array that represents the abbreviated months of the year in the current locale. This follows normal convention of January being month number 1, so it has a length of 13 and `month_abbr[0]` is the empty string.

더 보기:

Module `datetime` Object-oriented interface to dates and times with similar functionality to the `time` module.

Module `time` Low-level time related functions.

8.3 collections — High-performance container datatypes

버전 2.4에 추가.

Source code: `Lib/collections.py` and `Lib/_abcoll.py`

This module implements specialized container datatypes providing alternatives to Python’s general purpose built-in containers, *dict*, *list*, *set*, and *tuple*.

<code>namedtuple()</code>	factory function for creating tuple subclasses with named fields	버전 2.6에 추가.
<code>deque</code>	list-like container with fast appends and pops on either end	버전 2.4에 추가.
<code>Counter</code>	dict subclass for counting hashable objects	버전 2.7에 추가.
<code>OrderedDict</code>	dict subclass that remembers the order entries were added	버전 2.7에 추가.
<code>defaultdict</code>	dict subclass that calls a factory function to supply missing values	버전 2.5에 추가.

In addition to the concrete container classes, the collections module provides *abstract base classes* that can be used to test whether a class provides a particular interface, for example, whether it is hashable or a mapping.

8.3.1 Counter objects

A counter tool is provided to support convenient and rapid tallies. For example:

```
>>> # Tally occurrences of words in a list
>>> cnt = Counter()
>>> for word in ['red', 'blue', 'red', 'green', 'blue', 'blue']:
...     cnt[word] += 1
>>> cnt
Counter({'blue': 3, 'red': 2, 'green': 1})

>>> # Find the ten most common words in Hamlet
>>> import re
>>> words = re.findall(r'\w+', open('hamlet.txt').read().lower())
>>> Counter(words).most_common(10)
[('the', 1143), ('and', 966), ('to', 762), ('of', 669), ('i', 631),
 ('you', 554), ('a', 546), ('my', 514), ('hamlet', 471), ('in', 451)]
```

class `collections.Counter` (*[iterable-or-mapping]*)

A *Counter* is a *dict* subclass for counting hashable objects. It is an unordered collection where elements are stored as dictionary keys and their counts are stored as dictionary values. Counts are allowed to be any integer value including zero or negative counts. The *Counter* class is similar to bags or multisets in other languages.

Elements are counted from an *iterable* or initialized from another *mapping* (or counter):

```
>>> c = Counter()                                # a new, empty counter
>>> c = Counter('gallahad')                      # a new counter from an iterable
>>> c = Counter({'red': 4, 'blue': 2})           # a new counter from a mapping
>>> c = Counter(cats=4, dogs=8)                 # a new counter from keyword args
```

Counter objects have a dictionary interface except that they return a zero count for missing items instead of raising a *KeyError*:

```
>>> c = Counter(['eggs', 'ham'])
>>> c['bacon']                                # count of a missing element is zero
0
```

Setting a count to zero does not remove an element from a counter. Use `del` to remove it entirely:

```
>>> c['sausage'] = 0          # counter entry with a zero count
>>> del c['sausage']          # del actually removes the entry
```

버전 2.7에 추가.

Counter objects support three methods beyond those available for all dictionaries:

elements()

Return an iterator over elements repeating each as many times as its count. Elements are returned in arbitrary order. If an element's count is less than one, `elements()` will ignore it.

```
>>> c = Counter(a=4, b=2, c=0, d=-2)
>>> list(c.elements())
['a', 'a', 'a', 'a', 'b', 'b']
```

most_common([n])

Return a list of the *n* most common elements and their counts from the most common to the least. If *n* is omitted or None, `most_common()` returns *all* elements in the counter. Elements with equal counts are ordered arbitrarily:

```
>>> Counter('abracadabra').most_common(3)
[('a', 5), ('r', 2), ('b', 2)]
```

subtract([iterable-or-mapping])

Elements are subtracted from an *iterable* or from another *mapping* (or counter). Like `dict.update()` but subtracts counts instead of replacing them. Both inputs and outputs may be zero or negative.

```
>>> c = Counter(a=4, b=2, c=0, d=-2)
>>> d = Counter(a=1, b=2, c=3, d=4)
>>> c.subtract(d)
>>> c
Counter({'a': 3, 'b': 0, 'c': -3, 'd': -6})
```

The usual dictionary methods are available for `Counter` objects except for two which work differently for counters.

fromkeys(iterable)

This class method is not implemented for `Counter` objects.

update([iterable-or-mapping])

Elements are counted from an *iterable* or added-in from another *mapping* (or counter). Like `dict.update()` but adds counts instead of replacing them. Also, the *iterable* is expected to be a sequence of elements, not a sequence of (key, value) pairs.

Common patterns for working with `Counter` objects:

```
sum(c.values())          # total of all counts
c.clear()                 # reset all counts
list(c)                   # list unique elements
set(c)                    # convert to a set
dict(c)                   # convert to a regular dictionary
c.items()                 # convert to a list of (elem, cnt) pairs
Counter(dict(list_of_pairs)) # convert from a list of (elem, cnt) pairs
c.most_common()[:n-1:-1]  # n least common elements
c += Counter()            # remove zero and negative counts
```

Several mathematical operations are provided for combining `Counter` objects to produce multisets (counters that have counts greater than zero). Addition and subtraction combine counters by adding or subtracting the counts of corresponding elements. Intersection and union return the minimum and maximum of corresponding counts. Each operation can accept inputs with signed counts, but the output will exclude results with counts of zero or less.

```
>>> c = Counter(a=3, b=1)
>>> d = Counter(a=1, b=2)
>>> c + d                                # add two counters together: c[x] + d[x]
Counter({'a': 4, 'b': 3})
>>> c - d                                # subtract (keeping only positive counts)
Counter({'a': 2})
>>> c & d                                # intersection: min(c[x], d[x])
Counter({'a': 1, 'b': 1})
>>> c | d                                # union: max(c[x], d[x])
Counter({'a': 3, 'b': 2})
```

참고: Counters were primarily designed to work with positive integers to represent running counts; however, care was taken to not unnecessarily preclude use cases needing other types or negative values. To help with those use cases, this section documents the minimum range and type restrictions.

- The `Counter` class itself is a dictionary subclass with no restrictions on its keys and values. The values are intended to be numbers representing counts, but you *could* store anything in the value field.
- The `most_common()` method requires only that the values be orderable.
- For in-place operations such as `c[key] += 1`, the value type need only support addition and subtraction. So fractions, floats, and decimals would work and negative values are supported. The same is also true for `update()` and `subtract()` which allow negative and zero values for both inputs and outputs.
- The multiset methods are designed only for use cases with positive values. The inputs may be negative or zero, but only outputs with positive values are created. There are no type restrictions, but the value type needs to support addition, subtraction, and comparison.
- The `elements()` method requires integer counts. It ignores zero and negative counts.

더 보기:

- `Counter` class adapted for Python 2.5 and an early `Bag` recipe for Python 2.4.
- `Bag` class in Smalltalk.
- Wikipedia entry for `Multisets`.
- C++ multisets tutorial with examples.
- For mathematical operations on multisets and their use cases, see *Knuth, Donald. The Art of Computer Programming Volume II, Section 4.6.3, Exercise 19.*
- To enumerate all distinct multisets of a given size over a given set of elements, see `itertools.combinations_with_replacement()`.

```
map(Counter, combinations_with_replacement('ABC', 2)) -> AA AB AC BB BC CC
```


8.3.2 deque objects

class `collections.deque` (`[iterable[, maxlen]]`)

Returns a new deque object initialized left-to-right (using `append()`) with data from *iterable*. If *iterable* is not specified, the new deque is empty.

Deques are a generalization of stacks and queues (the name is pronounced 《deck》 and is short for 《double-ended queue》). Deques support thread-safe, memory efficient appends and pops from either side of the deque with approximately the same $O(1)$ performance in either direction.

Though `list` objects support similar operations, they are optimized for fast fixed-length operations and incur $O(n)$ memory movement costs for `pop(0)` and `insert(0, v)` operations which change both the size and position of the underlying data representation.

버전 2.4에 추가.

If *maxlen* is not specified or is `None`, deques may grow to an arbitrary length. Otherwise, the deque is bounded to the specified maximum length. Once a bounded length deque is full, when new items are added, a corresponding number of items are discarded from the opposite end. Bounded length deques provide functionality similar to the `tail` filter in Unix. They are also useful for tracking transactions and other pools of data where only the most recent activity is of interest.

버전 2.6에서 변경: Added *maxlen* parameter.

Deque objects support the following methods:

append (*x*)

Add *x* to the right side of the deque.

appendleft (*x*)

Add *x* to the left side of the deque.

clear ()

Remove all elements from the deque leaving it with length 0.

count (*x*)

Count the number of deque elements equal to *x*.

버전 2.7에 추가.

extend (*iterable*)

Extend the right side of the deque by appending elements from the *iterable* argument.

extendleft (*iterable*)

Extend the left side of the deque by appending elements from *iterable*. Note, the series of left appends results in reversing the order of elements in the *iterable* argument.

pop ()

Remove and return an element from the right side of the deque. If no elements are present, raises an `IndexError`.

popleft ()

Remove and return an element from the left side of the deque. If no elements are present, raises an `IndexError`.

remove (*value*)

Remove the first occurrence of *value*. If not found, raises a `ValueError`.

버전 2.5에 추가.

reverse ()

Reverse the elements of the deque in-place and then return `None`.

버전 2.7에 추가.

rotate (*n=1*)

Rotate the deque *n* steps to the right. If *n* is negative, rotate to the left.

When the deque is not empty, rotating one step to the right is equivalent to `d.appendleft(d.pop())`, and rotating one step to the left is equivalent to `d.append(d.popleft())`.

Deque objects also provide one read-only attribute:

maxlen

Maximum size of a deque or None if unbounded.

버전 2.7에 추가.

In addition to the above, deques support iteration, pickling, `len(d)`, `reversed(d)`, `copy.copy(d)`, `copy.deepcopy(d)`, membership testing with the `in` operator, and subscript references such as `d[-1]`. Indexed access is $O(1)$ at both ends but slows to $O(n)$ in the middle. For fast random access, use lists instead.

Example:

```
>>> from collections import deque
>>> d = deque('ghi')                # make a new deque with three items
>>> for elem in d:                  # iterate over the deque's elements
...     print elem.upper()
G
H
I

>>> d.append('j')                   # add a new entry to the right side
>>> d.appendleft('f')               # add a new entry to the left side
>>> d                               # show the representation of the deque
deque(['f', 'g', 'h', 'i', 'j'])

>>> d.pop()                         # return and remove the rightmost item
'j'
>>> d.popleft()                     # return and remove the leftmost item
'f'
>>> list(d)                         # list the contents of the deque
['g', 'h', 'i']
>>> d[0]                           # peek at leftmost item
'g'
>>> d[-1]                          # peek at rightmost item
'i'

>>> list(reversed(d))              # list the contents of a deque in reverse
['i', 'h', 'g']
>>> 'h' in d                       # search the deque
True
>>> d.extend('jkl')                # add multiple elements at once
>>> d
deque(['g', 'h', 'i', 'j', 'k', 'l'])
>>> d.rotate(1)                     # right rotation
>>> d
deque(['l', 'g', 'h', 'i', 'j', 'k'])
>>> d.rotate(-1)                   # left rotation
>>> d
deque(['g', 'h', 'i', 'j', 'k', 'l'])

>>> deque(reversed(d))              # make a new deque in reverse order
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

deque(['l', 'k', 'j', 'i', 'h', 'g'])
>>> d.clear()                                # empty the deque
>>> d.pop()                                  # cannot pop from an empty deque
Traceback (most recent call last):
  File "<pyshell#6>", line 1, in -toplevel-
    d.pop()
IndexError: pop from an empty deque

>>> d.extendleft('abc')                      # extendleft() reverses the input order
>>> d
deque(['c', 'b', 'a'])

```

deque Recipes

This section shows various approaches to working with deques.

Bounded length deques provide functionality similar to the `tail` filter in Unix:

```

def tail(filename, n=10):
    'Return the last n lines of a file'
    return deque(open(filename), n)

```

Another approach to using deques is to maintain a sequence of recently added elements by appending to the right and popping to the left:

```

def moving_average(iterable, n=3):
    # moving_average([40, 30, 50, 46, 39, 44]) --> 40.0 42.0 45.0 43.0
    # http://en.wikipedia.org/wiki/Moving_average
    it = iter(iterable)
    d = deque(itertools.islice(it, n-1))
    d.appendleft(0)
    s = sum(d)
    for elem in it:
        s += elem - d.popleft()
        d.append(elem)
        yield s / float(n)

```

The `rotate()` method provides a way to implement *deque* slicing and deletion. For example, a pure Python implementation of `del d[n]` relies on the `rotate()` method to position elements to be popped:

```

def delete_nth(d, n):
    d.rotate(-n)
    d.popleft()
    d.rotate(n)

```

To implement *deque* slicing, use a similar approach applying `rotate()` to bring a target element to the left side of the deque. Remove old entries with `popleft()`, add new entries with `extend()`, and then reverse the rotation. With minor variations on that approach, it is easy to implement Forth style stack manipulations such as `dup`, `drop`, `swap`, `over`, `pick`, `rot`, and `roll`.

8.3.3 defaultdict objects

class `collections.defaultdict` (`[default_factory[, ...]]`)

Returns a new dictionary-like object. `defaultdict` is a subclass of the built-in `dict` class. It overrides one method and adds one writable instance variable. The remaining functionality is the same as for the `dict` class and is not documented here.

The first argument provides the initial value for the `default_factory` attribute; it defaults to `None`. All remaining arguments are treated the same as if they were passed to the `dict` constructor, including keyword arguments.

버전 2.5에 추가.

`defaultdict` objects support the following method in addition to the standard `dict` operations:

`__missing__` (`key`)

If the `default_factory` attribute is `None`, this raises a `KeyError` exception with the `key` as argument.

If `default_factory` is not `None`, it is called without arguments to provide a default value for the given `key`, this value is inserted in the dictionary for the `key`, and returned.

If calling `default_factory` raises an exception this exception is propagated unchanged.

This method is called by the `__getitem__()` method of the `dict` class when the requested key is not found; whatever it returns or raises is then returned or raised by `__getitem__()`.

Note that `__missing__()` is *not* called for any operations besides `__getitem__()`. This means that `get()` will, like normal dictionaries, return `None` as a default rather than using `default_factory`.

`defaultdict` objects support the following instance variable:

`default_factory`

This attribute is used by the `__missing__()` method; it is initialized from the first argument to the constructor, if present, or to `None`, if absent.

defaultdict Examples

Using `list` as the `default_factory`, it is easy to group a sequence of key-value pairs into a dictionary of lists:

```
>>> s = [('yellow', 1), ('blue', 2), ('yellow', 3), ('blue', 4), ('red', 1)]
>>> d = defaultdict(list)
>>> for k, v in s:
...     d[k].append(v)
...
>>> d.items()
[('blue', [2, 4]), ('red', [1]), ('yellow', [1, 3])]
```

When each key is encountered for the first time, it is not already in the mapping; so an entry is automatically created using the `default_factory` function which returns an empty `list`. The `list.append()` operation then attaches the value to the new list. When keys are encountered again, the look-up proceeds normally (returning the list for that key) and the `list.append()` operation adds another value to the list. This technique is simpler and faster than an equivalent technique using `dict.setdefault()`:

```
>>> d = {}
>>> for k, v in s:
...     d.setdefault(k, []).append(v)
...
>>> d.items()
[('blue', [2, 4]), ('red', [1]), ('yellow', [1, 3])]
```

Setting the `default_factory` to `int` makes the `defaultdict` useful for counting (like a bag or multiset in other languages):

```
>>> s = 'mississippi'
>>> d = defaultdict(int)
>>> for k in s:
...     d[k] += 1
...
>>> d.items()
[('i', 4), ('p', 2), ('s', 4), ('m', 1)]
```

When a letter is first encountered, it is missing from the mapping, so the `default_factory` function calls `int()` to supply a default count of zero. The increment operation then builds up the count for each letter.

The function `int()` which always returns zero is just a special case of constant functions. A faster and more flexible way to create constant functions is to use `itertools.repeat()` which can supply any constant value (not just zero):

```
>>> def constant_factory(value):
...     return itertools.repeat(value).next
>>> d = defaultdict(constant_factory('<missing>'))
>>> d.update(name='John', action='ran')
>>> '%(name)s %(action)s to %(object)s' % d
'John ran to <missing>'
```

Setting the `default_factory` to `set` makes the `defaultdict` useful for building a dictionary of sets:

```
>>> s = [('red', 1), ('blue', 2), ('red', 3), ('blue', 4), ('red', 1), ('blue', 4)]
>>> d = defaultdict(set)
>>> for k, v in s:
...     d[k].add(v)
...
>>> d.items()
[('blue', set([2, 4])), ('red', set([1, 3]))]
```

8.3.4 `namedtuple()` Factory Function for Tuples with Named Fields

Named tuples assign meaning to each position in a tuple and allow for more readable, self-documenting code. They can be used wherever regular tuples are used, and they add the ability to access fields by name instead of position index.

`collections.namedtuple`(*typename*, *field_names*[, *verbose=False*][, *rename=False*])

Returns a new tuple subclass named *typename*. The new subclass is used to create tuple-like objects that have fields accessible by attribute lookup as well as being indexable and iterable. Instances of the subclass also have a helpful docstring (with *typename* and *field_names*) and a helpful `__repr__()` method which lists the tuple contents in a `name=value` format.

The *field_names* are a sequence of strings such as `['x', 'y']`. Alternatively, *field_names* can be a single string with each fieldname separated by whitespace and/or commas, for example `'x y'` or `'x, y'`.

Any valid Python identifier may be used for a fieldname except for names starting with an underscore. Valid identifiers consist of letters, digits, and underscores but do not start with a digit or underscore and cannot be a *keyword* such as `class`, `for`, `return`, `global`, `pass`, `print`, or `raise`.

If *rename* is true, invalid fieldnames are automatically replaced with positional names. For example, `['abc', 'def', 'ghi', 'abc']` is converted to `['abc', '_1', 'ghi', '_3']`, eliminating the keyword `def` and the duplicate fieldname `abc`.

If *verbose* is true, the class definition is printed just before being built.

Named tuple instances do not have per-instance dictionaries, so they are lightweight and require no more memory than regular tuples.

버전 2.6에 추가.

버전 2.7에서 변경: added support for *rename*.

Example:

```
>>> Point = namedtuple('Point', ['x', 'y'], verbose=True)
class Point(tuple):
    'Point(x, y)'

    __slots__ = ()

    _fields = ('x', 'y')

    def __new__(_cls, x, y):
        'Create new instance of Point(x, y)'
        return _tuple.__new__(_cls, (x, y))

    @classmethod
    def _make(cls, iterable, new=tuple.__new__, len=len):
        'Make a new Point object from a sequence or iterable'
        result = new(cls, iterable)
        if len(result) != 2:
            raise TypeError('Expected 2 arguments, got %d' % len(result))
        return result

    def __repr__(self):
        'Return a nicely formatted representation string'
        return 'Point(x=%r, y=%r)' % self

    def _asdict(self):
        'Return a new OrderedDict which maps field names to their values'
        return OrderedDict(zip(self._fields, self))

    def _replace(_self, **kwds):
        'Return a new Point object replacing specified fields with new values'
        result = _self._make(map(kwds.pop, ('x', 'y'), _self))
        if kwds:
            raise ValueError('Got unexpected field names: %r' % kwds.keys())
        return result

    def __getnewargs__(self):
        'Return self as a plain tuple. Used by copy and pickle.'
        return tuple(self)

    __dict__ = _property(_asdict)

    def __getstate__(self):
        'Exclude the OrderedDict from pickling'
        pass

    x = _property(_itemgetter(0), doc='Alias for field number 0')
    y = _property(_itemgetter(1), doc='Alias for field number 1')
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

>>> p = Point(11, y=22)      # instantiate with positional or keyword arguments
>>> p[0] + p[1]              # indexable like the plain tuple (11, 22)
33
>>> x, y = p                 # unpack like a regular tuple
>>> x, y
(11, 22)
>>> p.x + p.y                # fields also accessible by name
33
>>> p                        # readable __repr__ with a name=value style
Point(x=11, y=22)

```

Named tuples are especially useful for assigning field names to result tuples returned by the *csv* or *sqlite3* modules:

```

EmployeeRecord = namedtuple('EmployeeRecord', 'name, age, title, department, paygrade
↪')

import csv
for emp in map(EmployeeRecord._make, csv.reader(open("employees.csv", "rb"))):
    print emp.name, emp.title

import sqlite3
conn = sqlite3.connect('/companydata')
cursor = conn.cursor()
cursor.execute('SELECT name, age, title, department, paygrade FROM employees')
for emp in map(EmployeeRecord._make, cursor.fetchall()):
    print emp.name, emp.title

```

In addition to the methods inherited from tuples, named tuples support three additional methods and one attribute. To prevent conflicts with field names, the method and attribute names start with an underscore.

classmethod `somenamedtuple._make(iterable)`

Class method that makes a new instance from an existing sequence or iterable.

```

>>> t = [11, 22]
>>> Point._make(t)
Point(x=11, y=22)

```

`somenamedtuple._asdict()`

Return a new *OrderedDict* which maps field names to their corresponding values:

```

>>> p = Point(x=11, y=22)
>>> p._asdict()
OrderedDict([('x', 11), ('y', 22)])

```

버전 2.7에서 변경: Returns an *OrderedDict* instead of a regular *dict*.

`somenamedtuple._replace(**kwargs)`

Return a new instance of the named tuple replacing specified fields with new values:

```

>>> p = Point(x=11, y=22)
>>> p._replace(x=33)
Point(x=33, y=22)

>>> for partnum, record in inventory.items():
...     inventory[partnum] = record._replace(price=newprices[partnum], ↪
↪timestamp=time.now())

```

`somenamedtuple._fields`

Tuple of strings listing the field names. Useful for introspection and for creating new named tuple types from existing named tuples.

```
>>> p._fields           # view the field names
('x', 'y')

>>> Color = namedtuple('Color', 'red green blue')
>>> Pixel = namedtuple('Pixel', Point._fields + Color._fields)
>>> Pixel(11, 22, 128, 255, 0)
Pixel(x=11, y=22, red=128, green=255, blue=0)
```

To retrieve a field whose name is stored in a string, use the `getattr()` function:

```
>>> getattr(p, 'x')
11
```

To convert a dictionary to a named tuple, use the double-star-operator (as described in [tut-unpacking-arguments](#)):

```
>>> d = {'x': 11, 'y': 22}
>>> Point(**d)
Point(x=11, y=22)
```

Since a named tuple is a regular Python class, it is easy to add or change functionality with a subclass. Here is how to add a calculated field and a fixed-width print format:

```
>>> class Point(namedtuple('Point', 'x y')):
...     __slots__ = ()
...     @property
...     def hypot(self):
...         return (self.x ** 2 + self.y ** 2) ** 0.5
...     def __str__(self):
...         return 'Point: x=%6.3f y=%6.3f hypot=%6.3f' % (self.x, self.y, self.
↪hypot)
...
>>> for p in Point(3, 4), Point(14, 5/7.):
...     print p
Point: x= 3.000 y= 4.000 hypot= 5.000
Point: x=14.000 y= 0.714 hypot=14.018
```

The subclass shown above sets `__slots__` to an empty tuple. This helps keep memory requirements low by preventing the creation of instance dictionaries.

Subclassing is not useful for adding new, stored fields. Instead, simply create a new named tuple type from the `_fields` attribute:

```
>>> Point3D = namedtuple('Point3D', Point._fields + ('z',))
```

Default values can be implemented by using `_replace()` to customize a prototype instance:

```
>>> Account = namedtuple('Account', 'owner balance transaction_count')
>>> default_account = Account('<owner name>', 0.0, 0)
>>> johns_account = default_account._replace(owner='John')
```

Enumerated constants can be implemented with named tuples, but it is simpler and more efficient to use a simple class declaration:


```
>>> Status = namedtuple('Status', 'open pending closed')._make(range(3))
>>> Status.open, Status.pending, Status.closed
(0, 1, 2)
>>> class Status:
...     open, pending, closed = range(3)
```

더 보기:

Named tuple recipe adapted for Python 2.4.

8.3.5 OrderedDict objects

Ordered dictionaries are just like regular dictionaries but they remember the order that items were inserted. When iterating over an ordered dictionary, the items are returned in the order their keys were first added.

class `collections.OrderedDict` (`[items]`)

Return an instance of a dict subclass, supporting the usual *dict* methods. An *OrderedDict* is a dict that remembers the order that keys were first inserted. If a new entry overwrites an existing entry, the original insertion position is left unchanged. Deleting an entry and reinserting it will move it to the end.

버전 2.7에 추가.

`OrderedDict.popitem` (`last=True`)

The *popitem()* method for ordered dictionaries returns and removes a (key, value) pair. The pairs are returned in LIFO order if *last* is true or FIFO order if false.

In addition to the usual mapping methods, ordered dictionaries also support reverse iteration using *reversed()*.

Equality tests between *OrderedDict* objects are order-sensitive and are implemented as `list(od1.items())==list(od2.items())`. Equality tests between *OrderedDict* objects and other *Mapping* objects are order-insensitive like regular dictionaries. This allows *OrderedDict* objects to be substituted anywhere a regular dictionary is used.

The *OrderedDict* constructor and *update()* method both accept keyword arguments, but their order is lost because Python's function call semantics pass-in keyword arguments using a regular unordered dictionary.

더 보기:

Equivalent *OrderedDict* recipe that runs on Python 2.4 or later.

OrderedDict Examples and Recipes

Since an ordered dictionary remembers its insertion order, it can be used in conjunction with sorting to make a sorted dictionary:

```
>>> # regular unsorted dictionary
>>> d = {'banana': 3, 'apple': 4, 'pear': 1, 'orange': 2}

>>> # dictionary sorted by key
>>> OrderedDict(sorted(d.items(), key=lambda t: t[0]))
OrderedDict([('apple', 4), ('banana', 3), ('orange', 2), ('pear', 1)])

>>> # dictionary sorted by value
>>> OrderedDict(sorted(d.items(), key=lambda t: t[1]))
OrderedDict([('pear', 1), ('orange', 2), ('banana', 3), ('apple', 4)])

>>> # dictionary sorted by length of the key string
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> OrderedDict(sorted(d.items(), key=lambda t: len(t[0])))
OrderedDict([('pear', 1), ('apple', 4), ('orange', 2), ('banana', 3)])
```

The new sorted dictionaries maintain their sort order when entries are deleted. But when new keys are added, the keys are appended to the end and the sort is not maintained.

It is also straight-forward to create an ordered dictionary variant that remembers the order the keys were *last* inserted. If a new entry overwrites an existing entry, the original insertion position is changed and moved to the end:

```
class LastUpdatedOrderedDict(OrderedDict):
    'Store items in the order the keys were last added'

    def __setitem__(self, key, value):
        if key in self:
            del self[key]
        OrderedDict.__setitem__(self, key, value)
```

An ordered dictionary can be combined with the `Counter` class so that the counter remembers the order elements are first encountered:

```
class OrderedCounter(Counter, OrderedDict):
    'Counter that remembers the order elements are first encountered'

    def __repr__(self):
        return '%s(%r)' % (self.__class__.__name__, OrderedDict(self))

    def __reduce__(self):
        return self.__class__, (OrderedDict(self),)
```

8.3.6 Collections Abstract Base Classes

The collections module offers the following *ABCs*:

ABC	Inherits from	Abstract Methods	Mixin Methods
<i>Container</i>		<code>__contains__</code>	
<i>Hashable</i>		<code>__hash__</code>	
<i>Iterable</i>		<code>__iter__</code>	
<i>Iterator</i>	<i>Iterable</i>	<code>next</code>	<code>__iter__</code>
<i>Sized</i>		<code>__len__</code>	
<i>Callable</i>		<code>__call__</code>	
<i>Sequence</i>	<i>Sized</i> , <i>Iterable</i> , <i>Container</i>	<code>__getitem__</code> , <code>__len__</code>	<code>__contains__</code> , <code>__iter__</code> , <code>__reversed__</code> , <code>index</code> , and <code>count</code>
<i>MutableSequence</i>	<i>Sequence</i>	<code>__getitem__</code> , <code>__setitem__</code> , <code>__delitem__</code> , <code>__len__</code> , <code>insert</code>	Inherited <i>Sequence</i> methods and <code>append</code> , <code>reverse</code> , <code>extend</code> , <code>pop</code> , <code>remove</code> , and <code>__iadd__</code>
<i>Set</i>	<i>Sized</i> , <i>Iterable</i> , <i>Container</i>	<code>__contains__</code> , <code>__iter__</code> , <code>__len__</code>	<code>__le__</code> , <code>__lt__</code> , <code>__eq__</code> , <code>__ne__</code> , <code>__gt__</code> , <code>__ge__</code> , <code>__and__</code> , <code>__or__</code> , <code>__sub__</code> , <code>__xor__</code> , and <code>isdisjoint</code>
<i>MutableSet</i>	<i>Set</i>	<code>__contains__</code> , <code>__iter__</code> , <code>__len__</code> , <code>add</code> , <code>discard</code>	Inherited <i>Set</i> methods and <code>clear</code> , <code>pop</code> , <code>remove</code> , <code>__ior__</code> , <code>__iand__</code> , <code>__ixor__</code> , and <code>__isub__</code>
<i>Mapping</i>	<i>Sized</i> , <i>Iterable</i> , <i>Container</i>	<code>__getitem__</code> , <code>__iter__</code> , <code>__len__</code>	<code>__contains__</code> , <code>keys</code> , <code>items</code> , <code>values</code> , <code>get</code> , <code>__eq__</code> , and <code>__ne__</code>
<i>MutableMapping</i>	<i>Mapping</i>	<code>__getitem__</code> , <code>__setitem__</code> , <code>__delitem__</code> , <code>__iter__</code> , <code>__len__</code>	Inherited <i>Mapping</i> methods and <code>pop</code> , <code>popitem</code> , <code>clear</code> , <code>update</code> , and <code>setdefault</code>
<i>MappingView</i>	<i>Sized</i>		<code>__len__</code>
<i>ItemsView</i>	<i>MappingView</i> , <i>Set</i>		<code>__contains__</code> , <code>__iter__</code>
<i>KeysView</i>	<i>MappingView</i> , <i>Set</i>		<code>__contains__</code> , <code>__iter__</code>
<i>ValuesView</i>	<i>MappingView</i>		<code>__contains__</code> , <code>__iter__</code>

class `collections.Container`

class `collections.Hashable`

class `collections.Sized`

class `collections.Callable`

ABCs for classes that provide respectively the methods `__contains__()`, `__hash__()`, `__len__()`, and `__call__()`.

class `collections.Iterable`

ABC for classes that provide the `__iter__()` method. See also the definition of *iterable*.

class `collections.Iterator`

ABC for classes that provide the `__iter__()` and `next()` methods. See also the definition of *iterator*.

class `collections.Sequence`

class `collections.MutableSequence`

ABCs for read-only and mutable *sequences*.

class `collections.Set`

class `collections.MutableSet`

ABCs for read-only and mutable sets.

```

class collections.Mapping
class collections.MutableMapping
    ABCs for read-only and mutable mappings.

class collections.MappingView
class collections.ItemsView
class collections.KeysView
class collections.ValuesView
    ABCs for mapping, items, keys, and values views.

```

These ABCs allow us to ask classes or instances if they provide particular functionality, for example:

```

size = None
if isinstance(myvar, collections.Sized):
    size = len(myvar)

```

Several of the ABCs are also useful as mixins that make it easier to develop classes supporting container APIs. For example, to write a class supporting the full *Set* API, it only necessary to supply the three underlying abstract methods: `__contains__()`, `__iter__()`, and `__len__()`. The ABC supplies the remaining methods such as `__and__()` and `isdisjoint()`

```

class ListBasedSet(collections.Set):
    ''' Alternate set implementation favoring space over speed
        and not requiring the set elements to be hashable. '''
    def __init__(self, iterable):
        self.elements = lst = []
        for value in iterable:
            if value not in lst:
                lst.append(value)

    def __iter__(self):
        return iter(self.elements)

    def __contains__(self, value):
        return value in self.elements

    def __len__(self):
        return len(self.elements)

s1 = ListBasedSet('abcdef')
s2 = ListBasedSet('defghi')
overlap = s1 & s2           # The __and__() method is supported automatically

```

Notes on using *Set* and *MutableSet* as a mixin:

- (1) Since some set operations create new sets, the default mixin methods need a way to create new instances from an iterable. The class constructor is assumed to have a signature in the form `ClassName(iterable)`. That assumption is factored-out to an internal classmethod called `__from_iterable()` which calls `cls(iterable)` to produce a new set. If the *Set* mixin is being used in a class with a different constructor signature, you will need to override `__from_iterable()` with a classmethod that can construct new instances from an iterable argument.
- (2) To override the comparisons (presumably for speed, as the semantics are fixed), redefine `__le__()` and `__ge__()`, then the other operations will automatically follow suit.
- (3) The *Set* mixin provides a `__hash__()` method to compute a hash value for the set; however, `__hash__()` is not defined because not all sets are hashable or immutable. To add set hashability using mixins, inherit from both *Set()* and *Hashable()*, then define `__hash__ = Set.__hash__`.

더 보기:

- [OrderedSet](#) recipe for an example built on *MutableSet*.
- For more about ABCs, see the [abc](#) module and [PEP 3119](#).

8.4 heapq — Heap queue algorithm

버전 2.3에 추가.

Source code: [Lib/heapq.py](#)

This module provides an implementation of the heap queue algorithm, also known as the priority queue algorithm.

Heaps are binary trees for which every parent node has a value less than or equal to any of its children. This implementation uses arrays for which `heap[k] <= heap[2*k+1]` and `heap[k] <= heap[2*k+2]` for all *k*, counting elements from zero. For the sake of comparison, non-existing elements are considered to be infinite. The interesting property of a heap is that its smallest element is always the root, `heap[0]`.

The API below differs from textbook heap algorithms in two aspects: (a) We use zero-based indexing. This makes the relationship between the index for a node and the indexes for its children slightly less obvious, but is more suitable since Python uses zero-based indexing. (b) Our pop method returns the smallest item, not the largest (called a «min heap» in textbooks; a «max heap» is more common in texts because of its suitability for in-place sorting).

These two make it possible to view the heap as a regular Python list without surprises: `heap[0]` is the smallest item, and `heap.sort()` maintains the heap invariant!

To create a heap, use a list initialized to `[]`, or you can transform a populated list into a heap via function `heapify()`.

The following functions are provided:

`heapq.heappush(heap, item)`

Push the value *item* onto the *heap*, maintaining the heap invariant.

`heapq.heappop(heap)`

Pop and return the smallest item from the *heap*, maintaining the heap invariant. If the heap is empty, `IndexError` is raised. To access the smallest item without popping it, use `heap[0]`.

`heapq.heappushpop(heap, item)`

Push *item* on the heap, then pop and return the smallest item from the *heap*. The combined action runs more efficiently than `heappush()` followed by a separate call to `heappop()`.

버전 2.6에 추가.

`heapq.heapify(x)`

Transform list *x* into a heap, in-place, in linear time.

`heapq.heapreplace(heap, item)`

Pop and return the smallest item from the *heap*, and also push the new *item*. The heap size doesn't change. If the heap is empty, `IndexError` is raised.

This one step operation is more efficient than a `heappop()` followed by `heappush()` and can be more appropriate when using a fixed-size heap. The pop/push combination always returns an element from the heap and replaces it with *item*.

The value returned may be larger than the *item* added. If that isn't desired, consider using `heappushpop()` instead. Its push/pop combination returns the smaller of the two values, leaving the larger value on the heap.

The module also offers three general purpose functions based on heaps.

`heapq.merge(*iterables)`

Merge multiple sorted inputs into a single sorted output (for example, merge timestamped entries from multiple log files). Returns an *iterator* over the sorted values.

Similar to `sorted(itertools.chain(*iterables))` but returns an iterable, does not pull the data into memory all at once, and assumes that each of the input streams is already sorted (smallest to largest).

버전 2.6에 추가.

`heapq.nlargest(n, iterable[, key])`

Return a list with the *n* largest elements from the dataset defined by *iterable*. *key*, if provided, specifies a function of one argument that is used to extract a comparison key from each element in the iterable: `key=str.lower`
Equivalent to: `sorted(iterable, key=key, reverse=True)[:n]`

버전 2.4에 추가.

버전 2.5에서 변경: Added the optional *key* argument.

`heapq.nsmallest(n, iterable[, key])`

Return a list with the *n* smallest elements from the dataset defined by *iterable*. *key*, if provided, specifies a function of one argument that is used to extract a comparison key from each element in the iterable: `key=str.lower`
Equivalent to: `sorted(iterable, key=key)[:n]`

버전 2.4에 추가.

버전 2.5에서 변경: Added the optional *key* argument.

The latter two functions perform best for smaller values of *n*. For larger values, it is more efficient to use the `sorted()` function. Also, when `n==1`, it is more efficient to use the built-in `min()` and `max()` functions. If repeated usage of these functions is required, consider turning the iterable into an actual heap.

8.4.1 Basic Examples

A *heapsort* can be implemented by pushing all values onto a heap and then popping off the smallest values one at a time:

```
>>> def heapsort(iterable):
...     h = []
...     for value in iterable:
...         heappush(h, value)
...     return [heappop(h) for i in range(len(h))]
...
>>> heapsort([1, 3, 5, 7, 9, 2, 4, 6, 8, 0])
[0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
```

This is similar to `sorted(iterable)`, but unlike `sorted()`, this implementation is not stable.

Heap elements can be tuples. This is useful for assigning comparison values (such as task priorities) alongside the main record being tracked:

```
>>> h = []
>>> heappush(h, (5, 'write code'))
>>> heappush(h, (7, 'release product'))
>>> heappush(h, (1, 'write spec'))
>>> heappush(h, (3, 'create tests'))
>>> heappop(h)
(1, 'write spec')
```

8.4.2 Priority Queue Implementation Notes

A **priority queue** is common use for a heap, and it presents several implementation challenges:

- Sort stability: how do you get two tasks with equal priorities to be returned in the order they were originally added?
- In the future with Python 3, tuple comparison breaks for (priority, task) pairs if the priorities are equal and the tasks do not have a default comparison order.
- If the priority of a task changes, how do you move it to a new position in the heap?
- Or if a pending task needs to be deleted, how do you find it and remove it from the queue?

A solution to the first two challenges is to store entries as 3-element list including the priority, an entry count, and the task. The entry count serves as a tie-breaker so that two tasks with the same priority are returned in the order they were added. And since no two entry counts are the same, the tuple comparison will never attempt to directly compare two tasks.

The remaining challenges revolve around finding a pending task and making changes to its priority or removing it entirely. Finding a task can be done with a dictionary pointing to an entry in the queue.

Removing the entry or changing its priority is more difficult because it would break the heap structure invariants. So, a possible solution is to mark the existing entry as removed and add a new entry with the revised priority:

```

pq = []                                # list of entries arranged in a heap
entry_finder = {}                      # mapping of tasks to entries
REMOVED = '<removed-task>'            # placeholder for a removed task
counter = itertools.count()           # unique sequence count

def add_task(task, priority=0):
    'Add a new task or update the priority of an existing task'
    if task in entry_finder:
        remove_task(task)
    count = next(counter)
    entry = [priority, count, task]
    entry_finder[task] = entry
    heappush(pq, entry)

def remove_task(task):
    'Mark an existing task as REMOVED. Raise KeyError if not found.'
    entry = entry_finder.pop(task)
    entry[-1] = REMOVED


def pop_task():
    'Remove and return the lowest priority task. Raise KeyError if empty.'
    while pq:
        priority, count, task = heappop(pq)
        if task is not REMOVED:
            del entry_finder[task]
            return task
    raise KeyError('pop from an empty priority queue')

```

8.4.3 Theory

Heaps are arrays for which $a[k] \leq a[2k+1]$ and $a[k] \leq a[2k+2]$ for all k , counting elements from 0. For the sake of comparison, non-existing elements are considered to be infinite. The interesting property of a heap is that $a[0]$ is always its smallest element.

The strange invariant above is meant to be an efficient memory representation for a tournament. The numbers below are k , not $a[k]$:



In the tree above, each cell k is topping $2k+1$ and $2k+2$. In a usual binary tournament we see in sports, each cell is the winner over the two cells it tops, and we can trace the winner down the tree to see all opponents s/he had. However, in many computer applications of such tournaments, we do not need to trace the history of a winner. To be more memory efficient, when a winner is promoted, we try to replace it by something else at a lower level, and the rule becomes that a cell and the two cells it tops contain three different items, but the top cell «wins» over the two topped cells.

If this heap invariant is protected at all time, index 0 is clearly the overall winner. The simplest algorithmic way to remove it and find the «next» winner is to move some loser (let's say cell 30 in the diagram above) into the 0 position, and then percolate this new 0 down the tree, exchanging values, until the invariant is re-established. This is clearly logarithmic on the total number of items in the tree. By iterating over all items, you get an $O(n \log n)$ sort.

A nice feature of this sort is that you can efficiently insert new items while the sort is going on, provided that the inserted items are not «better» than the last 0'th element you extracted. This is especially useful in simulation contexts, where the tree holds all incoming events, and the «win» condition means the smallest scheduled time. When an event schedules other events for execution, they are scheduled into the future, so they can easily go into the heap. So, a heap is a good structure for implementing schedulers (this is what I used for my MIDI sequencer :-).

Various structures for implementing schedulers have been extensively studied, and heaps are good for this, as they are reasonably speedy, the speed is almost constant, and the worst case is not much different than the average case. However, there are other representations which are more efficient overall, yet the worst cases might be terrible.

Heaps are also very useful in big disk sorts. You most probably all know that a big sort implies producing «runs» (which are pre-sorted sequences, whose size is usually related to the amount of CPU memory), followed by a merging passes for these runs, which merging is often very cleverly organised¹. It is very important that the initial sort produces the longest runs possible. Tournaments are a good way to achieve that. If, using all the memory available to hold a tournament, you replace and percolate items that happen to fit the current run, you'll produce runs which are twice the size of the memory for random input, and much better for input fuzzily ordered.

Moreover, if you output the 0'th item on disk and get an input which may not fit in the current tournament (because the value «wins» over the last output value), it cannot fit in the heap, so the size of the heap decreases. The freed memory could be cleverly reused immediately for progressively building a second heap, which grows at exactly the same rate the first heap is melting. When the first heap completely vanishes, you switch heaps and start a new run. Clever and quite effective!

¹ The disk balancing algorithms which are current, nowadays, are more annoying than clever, and this is a consequence of the seeking capabilities of the disks. On devices which cannot seek, like big tape drives, the story was quite different, and one had to be very clever to ensure (far in advance) that each tape movement will be the most effective possible (that is, will best participate at «progressing» the merge). Some tapes were even able to read backwards, and this was also used to avoid the rewinding time. Believe me, real good tape sorts were quite spectacular to watch! From all times, sorting has always been a Great Art! :-)

In a word, heaps are useful memory structures to know. I use them in a few applications, and I think it is good to keep a `<heap>` module around. :-)

8.5 bisect — Array bisection algorithm

버전 2.1에 추가.

Source code: [Lib/bisect.py](#)

This module provides support for maintaining a list in sorted order without having to sort the list after each insertion. For long lists of items with expensive comparison operations, this can be an improvement over the more common approach. The module is called *bisect* because it uses a basic bisection algorithm to do its work. The source code may be most useful as a working example of the algorithm (the boundary conditions are already right!).

The following functions are provided:

`bisect.bisect_left(a, x, lo=0, hi=len(a))`

Locate the insertion point for *x* in *a* to maintain sorted order. The parameters *lo* and *hi* may be used to specify a subset of the list which should be considered; by default the entire list is used. If *x* is already present in *a*, the insertion point will be before (to the left of) any existing entries. The return value is suitable for use as the first parameter to `list.insert()` assuming that *a* is already sorted.

The returned insertion point *i* partitions the array *a* into two halves so that `all(val < x for val in a[lo:i])` for the left side and `all(val >= x for val in a[i:hi])` for the right side.

`bisect.bisect_right(a, x, lo=0, hi=len(a))`

`bisect.bisect(a, x, lo=0, hi=len(a))`

Similar to `bisect_left()`, but returns an insertion point which comes after (to the right of) any existing entries of *x* in *a*.

The returned insertion point *i* partitions the array *a* into two halves so that `all(val <= x for val in a[lo:i])` for the left side and `all(val > x for val in a[i:hi])` for the right side.

`bisect.insort_left(a, x, lo=0, hi=len(a))`

Insert *x* in *a* in sorted order. This is equivalent to `a.insert(bisect.bisect_left(a, x, lo, hi), x)` assuming that *a* is already sorted. Keep in mind that the $O(\log n)$ search is dominated by the slow $O(n)$ insertion step.

`bisect.insort_right(a, x, lo=0, hi=len(a))`

`bisect.insort(a, x, lo=0, hi=len(a))`

Similar to `insort_left()`, but inserting *x* in *a* after any existing entries of *x*.

더 보기:

[SortedCollection recipe](#) that uses `bisect` to build a full-featured collection class with straight-forward search methods and support for a key-function. The keys are precomputed to save unnecessary calls to the key function during searches.

8.5.1 Searching Sorted Lists

The above `bisect()` functions are useful for finding insertion points but can be tricky or awkward to use for common searching tasks. The following five functions show how to transform them into the standard lookups for sorted lists:

```
def index(a, x):
    'Locate the leftmost value exactly equal to x'
    i = bisect_left(a, x)
    if i != len(a) and a[i] == x:
        return i
    raise ValueError

def find_lt(a, x):
    'Find rightmost value less than x'
    i = bisect_left(a, x)
    if i:
        return a[i-1]
    raise ValueError

def find_le(a, x):
    'Find rightmost value less than or equal to x'
    i = bisect_right(a, x)
    if i:
        return a[i-1]
    raise ValueError

def find_gt(a, x):
    'Find leftmost value greater than x'
    i = bisect_right(a, x)
    if i != len(a):
        return a[i]
    raise ValueError

def find_ge(a, x):
    'Find leftmost item greater than or equal to x'
    i = bisect_left(a, x)
    if i != len(a):
        return a[i]
    raise ValueError
```

8.5.2 Other Examples

The `bisect()` function can be useful for numeric table lookups. This example uses `bisect()` to look up a letter grade for an exam score (say) based on a set of ordered numeric breakpoints: 90 and up is an `<A>`, 80 to 89 is a ``, and so on:

```
>>> def grade(score, breakpoints=[60, 70, 80, 90], grades='FDCBA'):
    i = bisect(breakpoints, score)
    return grades[i]

>>> [grade(score) for score in [33, 99, 77, 70, 89, 90, 100]]
['F', 'A', 'C', 'C', 'B', 'A', 'A']
```

Unlike the `sorted()` function, it does not make sense for the `bisect()` functions to have `key` or `reversed` arguments because that would lead to an inefficient design (successive calls to `bisect` functions would not «remember» all of the previous key lookups).

Instead, it is better to search a list of precomputed keys to find the index of the record in question:

```
>>> data = [('red', 5), ('blue', 1), ('yellow', 8), ('black', 0)]
>>> data.sort(key=lambda r: r[1])
>>> keys = [r[1] for r in data]           # precomputed list of keys
>>> data[bisect_left(keys, 0)]
('black', 0)
>>> data[bisect_left(keys, 1)]
('blue', 1)
>>> data[bisect_left(keys, 5)]
('red', 5)
>>> data[bisect_left(keys, 8)]
('yellow', 8)
```

8.6 array — Efficient arrays of numeric values

This module defines an object type which can compactly represent an array of basic values: characters, integers, floating point numbers. Arrays are sequence types and behave very much like lists, except that the type of objects stored in them is constrained. The type is specified at object creation time by using a *type code*, which is a single character. The following type codes are defined:

Type code	C Type	Python Type	Minimum size in bytes
'c'	char	character	1
'b'	signed char	int	1
'B'	unsigned char	int	1
'u'	Py_UNICODE	Unicode character	2 (see note)
'h'	signed short	int	2
'H'	unsigned short	int	2
'i'	signed int	int	2
'I'	unsigned int	long	2
'l'	signed long	int	4
'L'	unsigned long	long	4
'f'	float	float	4
'd'	double	float	8

참고: The 'u' typecode corresponds to Python's unicode character. On narrow Unicode builds this is 2-bytes, on wide builds this is 4-bytes.

The actual representation of values is determined by the machine architecture (strictly speaking, by the C implementation). The actual size can be accessed through the `itemsize` attribute. The values stored for 'L' and 'I' items will be represented as Python long integers when retrieved, because Python's plain integer type cannot represent the full range of C's unsigned (long) integers.

The module defines the following type:

class `array.array`(*typecode*[, *initializer*])

A new array whose items are restricted by *typecode*, and initialized from the optional *initializer* value, which must be a list, string, or iterable over elements of the appropriate type.

버전 2.4에서 변경: Formerly, only lists or strings were accepted.

If given a list or string, the initializer is passed to the new array's `fromlist()`, `fromstring()`, or `fromunicode()` method (see below) to add initial items to the array. Otherwise, the iterable initializer is passed to the `extend()` method.

array.ArrayType

Obsolete alias for `array`.

Array objects support the ordinary sequence operations of indexing, slicing, concatenation, and multiplication. When using slice assignment, the assigned value must be an array object with the same type code; in all other cases, `TypeError` is raised. Array objects also implement the buffer interface, and may be used wherever buffer objects are supported.

The following data items and methods are also supported:

array.typecode

The typecode character used to create the array.

array.itemsize

The length in bytes of one array item in the internal representation.

array.append(x)

Append a new item with value *x* to the end of the array.

array.buffer_info()

Return a tuple (*address*, *length*) giving the current memory address and the length in elements of the buffer used to hold array's contents. The size of the memory buffer in bytes can be computed as `array.buffer_info()[1] * array.itemsize`. This is occasionally useful when working with low-level (and inherently unsafe) I/O interfaces that require memory addresses, such as certain `ioctl()` operations. The returned numbers are valid as long as the array exists and no length-changing operations are applied to it.

참고: When using array objects from code written in C or C++ (the only way to effectively make use of this information), it makes more sense to use the buffer interface supported by array objects. This method is maintained for backward compatibility and should be avoided in new code. The buffer interface is documented in `bufferobjects`.

array.byteswap()

《Byteswap》 all items of the array. This is only supported for values which are 1, 2, 4, or 8 bytes in size; for other types of values, `RuntimeError` is raised. It is useful when reading data from a file written on a machine with a different byte order.

array.count(x)

Return the number of occurrences of *x* in the array.

array.extend(iterable)

Append items from *iterable* to the end of the array. If *iterable* is another array, it must have *exactly* the same type code; if not, `TypeError` will be raised. If *iterable* is not an array, it must be iterable and its elements must be the right type to be appended to the array.

버전 2.4에서 변경: Formerly, the argument could only be another array.

array.fromfile(f, n)

Read *n* items (as machine values) from the file object *f* and append them to the end of the array. If less than *n* items are available, `EOFError` is raised, but the items that were available are still inserted into the array. *f* must be a real built-in file object; something else with a `read()` method won't do.

array.fromlist(list)

Append items from the list. This is equivalent to `for x in list: a.append(x)` except that if there is a type error, the array is unchanged.

array.fromstring(s)

Appends items from the string, interpreting the string as an array of machine values (as if it had been read from a

file using the `fromfile()` method).

`array.fromunicode(s)`

Extends this array with data from the given unicode string. The array must be a type 'u' array; otherwise a `ValueError` is raised. Use `array.fromstring(unicodestring.encode(enc))` to append Unicode data to an array of some other type.

`array.index(x)`

Return the smallest *i* such that *i* is the index of the first occurrence of *x* in the array.

`array.insert(i, x)`

Insert a new item with value *x* in the array before position *i*. Negative values are treated as being relative to the end of the array.

`array.pop([i])`

Removes the item with the index *i* from the array and returns it. The optional argument defaults to `-1`, so that by default the last item is removed and returned.

`array.read(f, n)`

버전 1.5.1부터 폐지: Use the `fromfile()` method.

Read *n* items (as machine values) from the file object *f* and append them to the end of the array. If less than *n* items are available, `EOFError` is raised, but the items that were available are still inserted into the array. *f* must be a real built-in file object; something else with a `read()` method won't do.

`array.remove(x)`

Remove the first occurrence of *x* from the array.

`array.reverse()`

Reverse the order of the items in the array.

`array.tofile(f)`

Write all items (as machine values) to the file object *f*.

`array.tolist()`

Convert the array to an ordinary list with the same items.

`array.tostring()`

Convert the array to an array of machine values and return the string representation (the same sequence of bytes that would be written to a file by the `tofile()` method.)

`array.tounicode()`

Convert the array to a unicode string. The array must be a type 'u' array; otherwise a `ValueError` is raised. Use `array.tostring().decode(enc)` to obtain a unicode string from an array of some other type.

`array.write(f)`

버전 1.5.1부터 폐지: Use the `tofile()` method.

Write all items (as machine values) to the file object *f*.

When an array object is printed or converted to a string, it is represented as `array(typecode, initializer)`. The *initializer* is omitted if the array is empty, otherwise it is a string if the *typecode* is 'c', otherwise it is a list of numbers. The string is guaranteed to be able to be converted back to an array with the same type and value using `eval()`, so long as the `array` class has been imported using `from array import array`. Examples:

```
array('l')
array('c', 'hello world')
array('u', u'hello \u2641')
array('l', [1, 2, 3, 4, 5])
array('d', [1.0, 2.0, 3.14])
```

더 보기:

Module *struct* Packing and unpacking of heterogeneous binary data.

Module *xdrlib* Packing and unpacking of External Data Representation (XDR) data as used in some remote procedure call systems.

The Numerical Python Documentation The Numeric Python extension (NumPy) defines another array type; see <http://www.numpy.org/> for further information about Numerical Python.

8.7 sets — Unordered collections of unique elements

버전 2.3에 추가.

버전 2.6부터 폐지: The built-in *set/frozenset* types replace this module.

The *sets* module provides classes for constructing and manipulating unordered collections of unique elements. Common uses include membership testing, removing duplicates from a sequence, and computing standard math operations on sets such as intersection, union, difference, and symmetric difference.

Like other collections, sets support `x in set`, `len(set)`, and `for x in set`. Being an unordered collection, sets do not record element position or order of insertion. Accordingly, sets do not support indexing, slicing, or other sequence-like behavior.

Most set applications use the *Set* class which provides every set method except for `__hash__()`. For advanced applications requiring a hash method, the *ImmutableSet* class adds a `__hash__()` method but omits methods which alter the contents of the set. Both *Set* and *ImmutableSet* derive from *BaseSet*, an abstract class useful for determining whether something is a set: `isinstance(obj, BaseSet)`.

The set classes are implemented using dictionaries. Accordingly, the requirements for set elements are the same as those for dictionary keys; namely, that the element defines both `__eq__()` and `__hash__()`. As a result, sets cannot contain mutable elements such as lists or dictionaries. However, they can contain immutable collections such as tuples or instances of *ImmutableSet*. For convenience in implementing sets of sets, inner sets are automatically converted to immutable form, for example, `Set([Set(['dog'])])` is transformed to `Set([ImmutableSet(['dog'])])`.

class `sets.Set([iterable])`

Constructs a new empty *Set* object. If the optional *iterable* parameter is supplied, updates the set with elements obtained from iteration. All of the elements in *iterable* should be immutable or be transformable to an immutable using the protocol described in section *Protocol for automatic conversion to immutable*.

class `sets.ImmutableSet([iterable])`

Constructs a new empty *ImmutableSet* object. If the optional *iterable* parameter is supplied, updates the set with elements obtained from iteration. All of the elements in *iterable* should be immutable or be transformable to an immutable using the protocol described in section *Protocol for automatic conversion to immutable*.

Because *ImmutableSet* objects provide a `__hash__()` method, they can be used as set elements or as dictionary keys. *ImmutableSet* objects do not have methods for adding or removing elements, so all of the elements must be known when the constructor is called.

8.7.1 Set Objects

Instances of *Set* and *ImmutableSet* both provide the following operations:

Operation	Equivalent	Result
<code>len(s)</code>		number of elements in set <i>s</i> (cardinality)
<code>x in s</code>		test <i>x</i> for membership in <i>s</i>
<code>x not in s</code>		test <i>x</i> for non-membership in <i>s</i>
<code>s.issubset(t)</code>	$s \leq t$	test whether every element in <i>s</i> is in <i>t</i>
<code>s.issuperset(t)</code>	$s \geq t$	test whether every element in <i>t</i> is in <i>s</i>
<code>s.union(t)</code>	$s \mid t$	new set with elements from both <i>s</i> and <i>t</i>
<code>s.intersection(t)</code>	$s \& t$	new set with elements common to <i>s</i> and <i>t</i>
<code>s.difference(t)</code>	$s - t$	new set with elements in <i>s</i> but not in <i>t</i>
<code>s.symmetric_difference(t)</code>	$s \wedge t$	new set with elements in either <i>s</i> or <i>t</i> but not both
<code>s.copy()</code>		new set with a shallow copy of <i>s</i>

Note, the non-operator versions of `union()`, `intersection()`, `difference()`, and `symmetric_difference()` will accept any iterable as an argument. In contrast, their operator based counterparts require their arguments to be sets. This precludes error-prone constructions like `Set('abc') & 'cbs'` in favor of the more readable `Set('abc').intersection('cbs')`.

버전 2.3.1에서 변경: Formerly all arguments were required to be sets.

In addition, both *Set* and *ImmutableSet* support set to set comparisons. Two sets are equal if and only if every element of each set is contained in the other (each is a subset of the other). A set is less than another set if and only if the first set is a proper subset of the second set (is a subset, but is not equal). A set is greater than another set if and only if the first set is a proper superset of the second set (is a superset, but is not equal).

The subset and equality comparisons do not generalize to a complete ordering function. For example, any two disjoint sets are not equal and are not subsets of each other, so *all* of the following return `False`: `a < b`, `a == b`, or `a > b`. Accordingly, sets do not implement the `__cmp__()` method.

Since sets only define partial ordering (subset relationships), the output of the `list.sort()` method is undefined for lists of sets.

The following table lists operations available in *ImmutableSet* but not found in *Set*:

Operation	Result
<code>hash(s)</code>	returns a hash value for <i>s</i>

The following table lists operations available in *Set* but not found in *ImmutableSet*:

Operation	Equivalent	Result
<code>s.update(t)</code>	$s \models t$	return set <i>s</i> with elements added from <i>t</i>
<code>s.intersection_update(t)</code>	$s \&= t$	return set <i>s</i> keeping only elements also found in <i>t</i>
<code>s.difference_update(t)</code>	$s -= t$	return set <i>s</i> after removing elements found in <i>t</i>
<code>s.symmetric_difference_update(t)</code>	$s \wedge t$	return set <i>s</i> with elements from <i>s</i> or <i>t</i> but not both
<code>s.add(x)</code>		add element <i>x</i> to set <i>s</i>
<code>s.remove(x)</code>		remove <i>x</i> from set <i>s</i> ; raises <i>KeyError</i> if not present
<code>s.discard(x)</code>		removes <i>x</i> from set <i>s</i> if present
<code>s.pop()</code>		remove and return an arbitrary element from <i>s</i> ; raises <i>KeyError</i> if empty
<code>s.clear()</code>		remove all elements from set <i>s</i>

Note, the non-operator versions of `update()`, `intersection_update()`, `difference_update()`, and `symmetric_difference_update()` will accept any iterable as an argument.

버전 2.3.1에서 변경: Formerly all arguments were required to be sets.

Also note, the module also includes a `union_update()` method which is an alias for `update()`. The method is included for backwards compatibility. Programmers should prefer the `update()` method because it is supported by the built-in `set()` and `frozenset()` types.

8.7.2 Example

```
>>> from sets import Set
>>> engineers = Set(['John', 'Jane', 'Jack', 'Janice'])
>>> programmers = Set(['Jack', 'Sam', 'Susan', 'Janice'])
>>> managers = Set(['Jane', 'Jack', 'Susan', 'Zack'])
>>> employees = engineers | programmers | managers           # union
>>> engineering_management = engineers & managers           # intersection
>>> fulltime_management = managers - engineers - programmers # difference
>>> engineers.add('Marvin')                                  # add element
>>> print engineers
Set(['Jane', 'Marvin', 'Janice', 'John', 'Jack'])
>>> employees.issuperset(engineers)                          # superset test
False
>>> employees.update(engineers)                               # update from another set
>>> employees.issuperset(engineers)
True
>>> for group in [engineers, programmers, managers, employees]:
...     group.discard('Susan')                               # unconditionally remove element
...     print group
...
Set(['Jane', 'Marvin', 'Janice', 'John', 'Jack'])
Set(['Janice', 'Jack', 'Sam'])
Set(['Jane', 'Zack', 'Jack'])
Set(['Jack', 'Sam', 'Jane', 'Marvin', 'Janice', 'John', 'Zack'])
```

8.7.3 Protocol for automatic conversion to immutable

Sets can only contain immutable elements. For convenience, mutable `Set` objects are automatically copied to an `ImmutableSet` before being added as a set element.

The mechanism is to always add a *hashable* element, or if it is not hashable, the element is checked to see if it has an `__as_immutable__()` method which returns an immutable equivalent.

Since `Set` objects have a `__as_immutable__()` method returning an instance of `ImmutableSet`, it is possible to construct sets of sets.

A similar mechanism is needed by the `__contains__()` and `remove()` methods which need to hash an element to check for membership in a set. Those methods check an element for hashability and, if not, check for a `__as_temporarily_immutable__()` method which returns the element wrapped by a class that provides temporary methods for `__hash__()`, `__eq__()`, and `__ne__()`.

The alternate mechanism spares the need to build a separate copy of the original mutable object.

`Set` objects implement the `__as_temporarily_immutable__()` method which returns the `Set` object wrapped by a new class `_TemporarilyImmutableSet`.

The two mechanisms for adding hashability are normally invisible to the user; however, a conflict can arise in a multi-threaded environment where one thread is updating a set while another has temporarily wrapped it in `_TemporarilyImmutableSet`. In other words, sets of mutable sets are not thread-safe.

8.7.4 Comparison to the built-in set types

The built-in `set` and `frozenset` types were designed based on lessons learned from the `sets` module. The key differences are:

- `Set` and `ImmutableSet` were renamed to `set` and `frozenset`.
- There is no equivalent to `BaseSet`. Instead, use `isinstance(x, (set, frozenset))`.
- The hash algorithm for the built-ins performs significantly better (fewer collisions) for most datasets.
- The built-in versions have more space efficient pickles.
- The built-in versions do not have a `union_update()` method. Instead, use the `update()` method which is equivalent.
- The built-in versions do not have a `__repr__(sorted=True)` method. Instead, use the built-in `repr()` and `sorted()` functions: `repr(sorted(s))`.
- The built-in version does not have a protocol for automatic conversion to immutable. Many found this feature to be confusing and no one in the community reported having found real uses for it.

8.8 sched — Event scheduler

Source code: `Lib/sched.py`

The `sched` module defines a class which implements a general purpose event scheduler:

class `sched.scheduler` (*timefunc*, *delayfunc*)

The `scheduler` class defines a generic interface to scheduling events. It needs two functions to actually deal with the «outside world» — *timefunc* should be callable without arguments, and return a number (the «time», in any units whatsoever). The *delayfunc* function should be callable with one argument, compatible with the output of *timefunc*, and should delay that many time units. *delayfunc* will also be called with the argument 0 after each event is run to allow other threads an opportunity to run in multi-threaded applications.

Example:

```
>>> import sched, time
>>> s = sched.scheduler(time.time, time.sleep)
>>> def print_time(): print "From print_time", time.time()
...
>>> def print_some_times():
...     print time.time()
...     s.enter(5, 1, print_time, ())
...     s.enter(10, 1, print_time, ())
...     s.run()
...     print time.time()
...
>>> print_some_times()
930343690.257
From print_time 930343695.274
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
From print_time 930343700.273
930343700.276
```

In multi-threaded environments, the `scheduler` class has limitations with respect to thread-safety, inability to insert a new task before the one currently pending in a running scheduler, and holding up the main thread until the event queue is empty. Instead, the preferred approach is to use the `threading.Timer` class instead.

Example:

```
>>> import time
>>> from threading import Timer
>>> def print_time():
...     print "From print_time", time.time()
...
>>> def print_some_times():
...     print time.time()
...     Timer(5, print_time, ()).start()
...     Timer(10, print_time, ()).start()
...     time.sleep(11) # sleep while time-delay events execute
...     print time.time()
...
>>> print_some_times()
930343690.257
From print_time 930343695.274
From print_time 930343700.273
930343701.301
```

8.8.1 Scheduler Objects

`scheduler` instances have the following methods and attributes:

`scheduler.enterabs` (*time*, *priority*, *action*, *argument*)

Schedule a new event. The *time* argument should be a numeric type compatible with the return value of the *timefunc* function passed to the constructor. Events scheduled for the same *time* will be executed in the order of their *priority*. A lower number represents a higher priority.

Executing the event means executing `action(*argument)`. *argument* must be a sequence holding the parameters for *action*.

Return value is an event which may be used for later cancellation of the event (see `cancel()`).

`scheduler.enter` (*delay*, *priority*, *action*, *argument*)

Schedule an event for *delay* more time units. Other than the relative time, the other arguments, the effect and the return value are the same as those for `enterabs()`.

`scheduler.cancel` (*event*)

Remove the event from the queue. If *event* is not an event currently in the queue, this method will raise a `ValueError`.

`scheduler.empty` ()

Return true if the event queue is empty.

`scheduler.run` ()

Run all scheduled events. This function will wait (using the `delayfunc()` function passed to the constructor) for the next event, then execute it and so on until there are no more scheduled events.

Either *action* or *delayfunc* can raise an exception. In either case, the scheduler will maintain a consistent state and propagate the exception. If an exception is raised by *action*, the event will not be attempted in future calls to *run()*.

If a sequence of events takes longer to run than the time available before the next event, the scheduler will simply fall behind. No events will be dropped; the calling code is responsible for canceling events which are no longer pertinent.

`scheduler.queue`

Read-only attribute returning a list of upcoming events in the order they will be run. Each event is shown as a *named tuple* with the following fields: time, priority, action, argument.

버전 2.6에 추가.

8.9 mutex — Mutual exclusion support

버전 2.6부터 폐지: The *mutex* module has been removed in Python 3.

The *mutex* module defines a class that allows mutual-exclusion via acquiring and releasing locks. It does not require (or imply) *threading* or multi-tasking, though it could be useful for those purposes.

The *mutex* module defines the following class:

class `mutex.mutex`

Create a new (unlocked) mutex.

A mutex has two pieces of state — a «locked» bit and a queue. When the mutex is not locked, the queue is empty. Otherwise, the queue contains zero or more (*function*, *argument*) pairs representing functions (or methods) waiting to acquire the lock. When the mutex is unlocked while the queue is not empty, the first queue entry is removed and its *function(argument)* pair called, implying it now has the lock.

Of course, no multi-threading is implied – hence the funny interface for *lock()*, where a function is called once the lock is acquired.

8.9.1 Mutex Objects

mutex objects have following methods:

`mutex.test()`

Check whether the mutex is locked.

`mutex.testandset()`

«Atomic» test-and-set, grab the lock if it is not set, and return *True*, otherwise, return *False*.

`mutex.lock(function, argument)`

Execute *function(argument)*, unless the mutex is locked. In the case it is locked, place the function and argument on the queue. See *unlock()* for explanation of when *function(argument)* is executed in that case.

`mutex.unlock()`

Unlock the mutex if queue is empty, otherwise execute the first element in the queue.

8.10 queue — A synchronized queue class

참고: The `Queue` module has been renamed to `queue` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

Source code: [Lib/Queue.py](#)

The `Queue` module implements multi-producer, multi-consumer queues. It is especially useful in threaded programming when information must be exchanged safely between multiple threads. The `Queue` class in this module implements all the required locking semantics. It depends on the availability of thread support in Python; see the `threading` module.

The module implements three types of queue, which differ only in the order in which the entries are retrieved. In a FIFO queue, the first tasks added are the first retrieved. In a LIFO queue, the most recently added entry is the first retrieved (operating like a stack). With a priority queue, the entries are kept sorted (using the `heapq` module) and the lowest valued entry is retrieved first.

The `Queue` module defines the following classes and exceptions:

class `Queue.Queue` (*maxsize=0*)

Constructor for a FIFO queue. *maxsize* is an integer that sets the upperbound limit on the number of items that can be placed in the queue. Insertion will block once this size has been reached, until queue items are consumed. If *maxsize* is less than or equal to zero, the queue size is infinite.

class `Queue.LifoQueue` (*maxsize=0*)

Constructor for a LIFO queue. *maxsize* is an integer that sets the upperbound limit on the number of items that can be placed in the queue. Insertion will block once this size has been reached, until queue items are consumed. If *maxsize* is less than or equal to zero, the queue size is infinite.

버전 2.6에 추가.

class `Queue.PriorityQueue` (*maxsize=0*)

Constructor for a priority queue. *maxsize* is an integer that sets the upperbound limit on the number of items that can be placed in the queue. Insertion will block once this size has been reached, until queue items are consumed. If *maxsize* is less than or equal to zero, the queue size is infinite.

The lowest valued entries are retrieved first (the lowest valued entry is the one returned by `sorted(list(entries))[0]`). A typical pattern for entries is a tuple in the form: `(priority_number, data)`.

버전 2.6에 추가.

exception `Queue.Empty`

Exception raised when non-blocking `get()` (or `get_nowait()`) is called on a `Queue` object which is empty.

exception `Queue.Full`

Exception raised when non-blocking `put()` (or `put_nowait()`) is called on a `Queue` object which is full.

더 보기:

`collections.deque` is an alternative implementation of unbounded queues with fast atomic `append()` and `popleft()` operations that do not require locking.

8.10.1 Queue Objects

Queue objects (*Queue*, *LifoQueue*, or *PriorityQueue*) provide the public methods described below.

`Queue.qsize()`

Return the approximate size of the queue. Note, `qsize() > 0` doesn't guarantee that a subsequent `get()` will not block, nor will `qsize() < maxsize` guarantee that `put()` will not block.

`Queue.empty()`

Return `True` if the queue is empty, `False` otherwise. If `empty()` returns `True` it doesn't guarantee that a subsequent call to `put()` will not block. Similarly, if `empty()` returns `False` it doesn't guarantee that a subsequent call to `get()` will not block.

`Queue.full()`

Return `True` if the queue is full, `False` otherwise. If `full()` returns `True` it doesn't guarantee that a subsequent call to `get()` will not block. Similarly, if `full()` returns `False` it doesn't guarantee that a subsequent call to `put()` will not block.

`Queue.put(item[, block[, timeout]])`

Put *item* into the queue. If optional args *block* is true and *timeout* is `None` (the default), block if necessary until a free slot is available. If *timeout* is a positive number, it blocks at most *timeout* seconds and raises the `Full` exception if no free slot was available within that time. Otherwise (*block* is false), put an item on the queue if a free slot is immediately available, else raise the `Full` exception (*timeout* is ignored in that case).

버전 2.3에 추가: The *timeout* parameter.

`Queue.put_nowait(item)`

Equivalent to `put(item, False)`.

`Queue.get([block[, timeout]])`

Remove and return an item from the queue. If optional args *block* is true and *timeout* is `None` (the default), block if necessary until an item is available. If *timeout* is a positive number, it blocks at most *timeout* seconds and raises the `Empty` exception if no item was available within that time. Otherwise (*block* is false), return an item if one is immediately available, else raise the `Empty` exception (*timeout* is ignored in that case).

버전 2.3에 추가: The *timeout* parameter.

`Queue.get_nowait()`

Equivalent to `get(False)`.

Two methods are offered to support tracking whether enqueued tasks have been fully processed by daemon consumer threads.

`Queue.task_done()`

Indicate that a formerly enqueued task is complete. Used by queue consumer threads. For each `get()` used to fetch a task, a subsequent call to `task_done()` tells the queue that the processing on the task is complete.

If a `join()` is currently blocking, it will resume when all items have been processed (meaning that a `task_done()` call was received for every item that had been `put()` into the queue).

Raises a `ValueError` if called more times than there were items placed in the queue.

버전 2.5에 추가.

`Queue.join()`

Blocks until all items in the queue have been gotten and processed.

The count of unfinished tasks goes up whenever an item is added to the queue. The count goes down whenever a consumer thread calls `task_done()` to indicate that the item was retrieved and all work on it is complete. When the count of unfinished tasks drops to zero, `join()` unblocks.

버전 2.5에 추가.

Example of how to wait for enqueued tasks to be completed:

```
def worker():
    while True:
        item = q.get()
        do_work(item)
        q.task_done()

q = Queue()
for i in range(num_worker_threads):
    t = Thread(target=worker)
    t.daemon = True
    t.start()

for item in source():
    q.put(item)

q.join()          # block until all tasks are done
```

8.11 weakref — Weak references

버전 2.1에 추가.

Source code: [Lib/weakref.py](#)

The *weakref* module allows the Python programmer to create *weak references* to objects.

In the following, the term *referent* means the object which is referred to by a weak reference.

A weak reference to an object is not enough to keep the object alive: when the only remaining references to a referent are weak references, *garbage collection* is free to destroy the referent and reuse its memory for something else. A primary use for weak references is to implement caches or mappings holding large objects, where it's desired that a large object not be kept alive solely because it appears in a cache or mapping.

For example, if you have a number of large binary image objects, you may wish to associate a name with each. If you used a Python dictionary to map names to images, or images to names, the image objects would remain alive just because they appeared as values or keys in the dictionaries. The *WeakKeyDictionary* and *WeakValueDictionary* classes supplied by the *weakref* module are an alternative, using weak references to construct mappings that don't keep objects alive solely because they appear in the mapping objects. If, for example, an image object is a value in a *WeakValueDictionary*, then when the last remaining references to that image object are the weak references held by weak mappings, garbage collection can reclaim the object, and its corresponding entries in weak mappings are simply deleted.

WeakKeyDictionary and *WeakValueDictionary* use weak references in their implementation, setting up call-back functions on the weak references that notify the weak dictionaries when a key or value has been reclaimed by garbage collection. Most programs should find that using one of these weak dictionary types is all they need – it's not usually necessary to create your own weak references directly. The low-level machinery used by the weak dictionary implementations is exposed by the *weakref* module for the benefit of advanced uses.

Not all objects can be weakly referenced; those objects which can include class instances, functions written in Python (but not in C), methods (both bound and unbound), sets, frozensets, file objects, *generators*, type objects, *DBcursor* objects from the *bsddb* module, sockets, arrays, dequeues, regular expression pattern objects, and code objects.

버전 2.4에서 변경: Added support for files, sockets, arrays, and patterns.

버전 2.7에서 변경: Added support for thread.lock, threading.Lock, and code objects.

Several built-in types such as `list` and `dict` do not directly support weak references but can add support through subclassing:

```
class Dict(dict):
    pass

obj = Dict(red=1, green=2, blue=3)  # this object is weak referenceable
```

CPython implementation detail: Other built-in types such as `tuple` and `long` do not support weak references even when subclassed.

Extension types can easily be made to support weak references; see `weakref-support`.

class `weakref.ref(object[, callback])`

Return a weak reference to *object*. The original object can be retrieved by calling the reference object if the referent is still alive; if the referent is no longer alive, calling the reference object will cause `None` to be returned. If *callback* is provided and not `None`, and the returned weakref object is still alive, the callback will be called when the object is about to be finalized; the weak reference object will be passed as the only parameter to the callback; the referent will no longer be available.

It is allowable for many weak references to be constructed for the same object. Callbacks registered for each weak reference will be called from the most recently registered callback to the oldest registered callback.

Exceptions raised by the callback will be noted on the standard error output, but cannot be propagated; they are handled in exactly the same way as exceptions raised from an object's `__del__()` method.

Weak references are *hashable* if the *object* is hashable. They will maintain their hash value even after the *object* was deleted. If `hash()` is called the first time only after the *object* was deleted, the call will raise `TypeError`.

Weak references support tests for equality, but not ordering. If the referents are still alive, two references have the same equality relationship as their referents (regardless of the *callback*). If either referent has been deleted, the references are equal only if the reference objects are the same object.

버전 2.4에서 변경: This is now a subclassable type rather than a factory function; it derives from `object`.

weakref.proxy(object[, callback])

Return a proxy to *object* which uses a weak reference. This supports use of the proxy in most contexts instead of requiring the explicit dereferencing used with weak reference objects. The returned object will have a type of either `ProxyType` or `CallableProxyType`, depending on whether *object* is callable. Proxy objects are not *hashable* regardless of the referent; this avoids a number of problems related to their fundamentally mutable nature, and prevent their use as dictionary keys. *callback* is the same as the parameter of the same name to the `ref()` function.

weakref.getweakrefcount(object)

Return the number of weak references and proxies which refer to *object*.

weakref.getweakrefs(object)

Return a list of all weak reference and proxy objects which refer to *object*.

class `weakref.WeakKeyDictionary([dict])`

Mapping class that references keys weakly. Entries in the dictionary will be discarded when there is no longer a strong reference to the key. This can be used to associate additional data with an object owned by other parts of an application without adding attributes to those objects. This can be especially useful with objects that override attribute accesses.

참고: Caution: Because a `WeakKeyDictionary` is built on top of a Python dictionary, it must not change size when iterating over it. This can be difficult to ensure for a `WeakKeyDictionary` because actions performed by the program during iteration may cause items in the dictionary to vanish 《by magic》 (as a side effect of garbage

collection).

WeakKeyDictionary objects have the following additional methods. These expose the internal references directly. The references are not guaranteed to be 《live》 at the time they are used, so the result of calling the references needs to be checked before being used. This can be used to avoid creating references that will cause the garbage collector to keep the keys around longer than needed.

`WeakKeyDictionary.iterkeyrefs()`

Return an iterable of the weak references to the keys.

버전 2.5에 추가.

`WeakKeyDictionary.keyrefs()`

Return a list of weak references to the keys.

버전 2.5에 추가.

class `weakref.WeakValueDictionary([dict])`

Mapping class that references values weakly. Entries in the dictionary will be discarded when no strong reference to the value exists any more.

참고: Caution: Because a *WeakValueDictionary* is built on top of a Python dictionary, it must not change size when iterating over it. This can be difficult to ensure for a *WeakValueDictionary* because actions performed by the program during iteration may cause items in the dictionary to vanish 《by magic》 (as a side effect of garbage collection).

WeakValueDictionary objects have the following additional methods. These methods have the same issues as the `iterkeyrefs()` and `keyrefs()` methods of *WeakKeyDictionary* objects.

`WeakValueDictionary.itervaluerefs()`

Return an iterable of the weak references to the values.

버전 2.5에 추가.

`WeakValueDictionary.valuerefs()`

Return a list of weak references to the values.

버전 2.5에 추가.

class `weakref.WeakSet([elements])`

Set class that keeps weak references to its elements. An element will be discarded when no strong reference to it exists any more.

버전 2.7에 추가.

`weakref.ReferenceType`

The type object for weak references objects.

`weakref.ProxyType`

The type object for proxies of objects which are not callable.

`weakref.CallableProxyType`

The type object for proxies of callable objects.

`weakref.ProxyTypes`

Sequence containing all the type objects for proxies. This can make it simpler to test if an object is a proxy without being dependent on naming both proxy types.

exception `weakref.ReferenceError`

Exception raised when a proxy object is used but the underlying object has been collected. This is the same as the standard `ReferenceError` exception.

더 보기:

PEP 205 - Weak References The proposal and rationale for this feature, including links to earlier implementations and information about similar features in other languages.

8.11.1 Weak Reference Objects

Weak reference objects have no attributes or methods, but do allow the referent to be obtained, if it still exists, by calling it:

```
>>> import weakref
>>> class Object:
...     pass
...
>>> o = Object()
>>> r = weakref.ref(o)
>>> o2 = r()
>>> o is o2
True
```

If the referent no longer exists, calling the reference object returns `None`:

```
>>> del o, o2
>>> print r()
None
```

Testing that a weak reference object is still live should be done using the expression `ref() is not None`. Normally, application code that needs to use a reference object should follow this pattern:

```
# r is a weak reference object
o = r()
if o is None:
    # referent has been garbage collected
    print "Object has been deallocated; can't frobnicate."
else:
    print "Object is still live!"
    o.do_something_useful()
```

Using a separate test for «liveness» creates race conditions in threaded applications; another thread can cause a weak reference to become invalidated before the weak reference is called; the idiom shown above is safe in threaded applications as well as single-threaded applications.

Specialized versions of `ref` objects can be created through subclassing. This is used in the implementation of the `WeakValueDictionary` to reduce the memory overhead for each entry in the mapping. This may be most useful to associate additional information with a reference, but could also be used to insert additional processing on calls to retrieve the referent.

This example shows how a subclass of `ref` can be used to store additional information about an object and affect the value that's returned when the referent is accessed:

```
import weakref

class ExtendedRef(weakref.ref):
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

def __init__(self, ob, callback=None, **annotations):
    super(ExtendedRef, self).__init__(ob, callback)
    self.__counter = 0
    for k, v in annotations.iteritems():
        setattr(self, k, v)

def __call__(self):
    """Return a pair containing the referent and the number of
    times the reference has been called.
    """
    ob = super(ExtendedRef, self).__call__()
    if ob is not None:
        self.__counter += 1
        ob = (ob, self.__counter)
    return ob

```

8.11.2 Example

This simple example shows how an application can use object IDs to retrieve objects that it has seen before. The IDs of the objects can then be used in other data structures without forcing the objects to remain alive, but the objects can still be retrieved by ID if they do.

```

import weakref

_id2obj_dict = weakref.WeakValueDictionary()

def remember(obj):
    oid = id(obj)
    _id2obj_dict[oid] = obj
    return oid

def id2obj(oid):
    return _id2obj_dict[oid]

```

8.12 UserDict — Class wrapper for dictionary objects

Source code: [Lib/UserDict.py](#)

The module defines a mixin, *DictMixin*, defining all dictionary methods for classes that already have a minimum mapping interface. This greatly simplifies writing classes that need to be substitutable for dictionaries (such as the *shelve* module).

This module also defines a class, *UserDict*, that acts as a wrapper around dictionary objects. The need for this class has been largely supplanted by the ability to subclass directly from *dict* (a feature that became available starting with Python version 2.2). Prior to the introduction of *dict*, the *UserDict* class was used to create dictionary-like sub-classes that obtained new behaviors by overriding existing methods or adding new ones.

The *UserDict* module defines the *UserDict* class and *DictMixin*:

```

class UserDict.UserDict([initialdata])
    Class that simulates a dictionary. The instance's contents are kept in a regular dictionary, which is accessible via

```

the `data` attribute of `UserDict` instances. If `initialdata` is provided, `data` is initialized with its contents; note that a reference to `initialdata` will not be kept, allowing it be used for other purposes.

참고: For backward compatibility, instances of `UserDict` are not iterable.

class `UserDict.IterableUserDict` (`[initialdata]`)

Subclass of `UserDict` that supports direct iteration (e.g. `for key in myDict`).

In addition to supporting the methods and operations of mappings (see section [매핑 형 — dict](#)), `UserDict` and `IterableUserDict` instances provide the following attribute:

`IterableUserDict.data`

A real dictionary used to store the contents of the `UserDict` class.

class `UserDict.DictMixin`

Mixin defining all dictionary methods for classes that already have a minimum dictionary interface including `__getitem__()`, `__setitem__()`, `__delitem__()`, and `keys()`.

This mixin should be used as a superclass. Adding each of the above methods adds progressively more functionality. For instance, defining all but `__delitem__()` will preclude only `pop()` and `popitem()` from the full interface.

In addition to the four base methods, progressively more efficiency comes with defining `__contains__()`, `__iter__()`, and `iteritems()`.

Since the mixin has no knowledge of the subclass constructor, it does not define `__init__()` or `copy()`.

Starting with Python version 2.6, it is recommended to use `collections.MutableMapping` instead of `DictMixin`.

Note that `DictMixin` does not implement the `viewkeys()`, `viewvalues()`, or `viewitems()` methods.

8.13 UserList — Class wrapper for list objects

참고: When Python 2.2 was released, many of the use cases for this class were subsumed by the ability to subclass `list` directly. However, a handful of use cases remain.

This module provides a list-interface around an underlying data store. By default, that data store is a `list`; however, it can be used to wrap a list-like interface around other objects (such as persistent storage).

In addition, this class can be mixed-in with built-in classes using multiple inheritance. This can sometimes be useful. For example, you can inherit from `UserList` and `str` at the same time. That would not be possible with both a real `list` and a real `str`.

This module defines a class that acts as a wrapper around list objects. It is a useful base class for your own list-like classes, which can inherit from them and override existing methods or add new ones. In this way one can add new behaviors to lists.

The `UserList` module defines the `UserList` class:

class `UserList.UserList` (`[list]`)

Class that simulates a list. The instance's contents are kept in a regular list, which is accessible via the `data` attribute of `UserList` instances. The instance's contents are initially set to a copy of `list`, defaulting to the empty list `[]`. `list` can be any iterable, e.g. a real Python list or a `UserList` object.

참고: The `UserList` class has been moved to the `collections` module in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

In addition to supporting the methods and operations of mutable sequences (see section *Sequence Types — str, unicode, list, tuple, bytearray, buffer, xrange*), `UserList` instances provide the following attribute:

`UserList.data`

A real Python list object used to store the contents of the `UserList` class.

Subclassing requirements: Subclasses of `UserList` are expected to offer a constructor which can be called with either no arguments or one argument. List operations which return a new sequence attempt to create an instance of the actual implementation class. To do so, it assumes that the constructor can be called with a single parameter, which is a sequence object used as a data source.

If a derived class does not wish to comply with this requirement, all of the special methods supported by this class will need to be overridden; please consult the sources for information about the methods which need to be provided in that case.

버전 2.0에서 변경: Python versions 1.5.2 and 1.6 also required that the constructor be callable with no parameters, and offer a mutable `data` attribute. Earlier versions of Python did not attempt to create instances of the derived class.

8.14 UserString — Class wrapper for string objects

참고: This `UserString` class from this module is available for backward compatibility only. If you are writing code that does not need to work with versions of Python earlier than Python 2.2, please consider subclassing directly from the built-in `str` type instead of using `UserString` (there is no built-in equivalent to `MutableString`).

This module defines a class that acts as a wrapper around string objects. It is a useful base class for your own string-like classes, which can inherit from them and override existing methods or add new ones. In this way one can add new behaviors to strings.

It should be noted that these classes are highly inefficient compared to real string or Unicode objects; this is especially the case for `MutableString`.

The `UserString` module defines the following classes:

class `UserString.UserString([sequence])`

Class that simulates a string or a Unicode string object. The instance's content is kept in a regular string or Unicode string object, which is accessible via the `data` attribute of `UserString` instances. The instance's contents are initially set to a copy of `sequence`. `sequence` can be either a regular Python string or Unicode string, an instance of `UserString` (or a subclass) or an arbitrary sequence which can be converted into a string using the built-in `str()` function.

참고: The `UserString` class has been moved to the `collections` module in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

class `UserString.MutableString([sequence])`

This class is derived from the `UserString` above and redefines strings to be *mutable*. Mutable strings can't be used as dictionary keys, because dictionaries require *immutable* objects as keys. The main intention of this class is to serve as an educational example for inheritance and necessity to remove (override) the `__hash__()` method in order to trap attempts to use a mutable object as dictionary key, which would be otherwise very error prone and hard to track down.

버전 2.6부터 폐지: The *MutableString* class has been removed in Python 3.

In addition to supporting the methods and operations of string and Unicode objects (see section 문자열 메서드), *UserString* instances provide the following attribute:

MutableString.**data**

A real Python string or Unicode object used to store the content of the *UserString* class.

8.15 types — Names for built-in types

Source code: [Lib/types.py](#)

This module defines names for some object types that are used by the standard Python interpreter, but not for the types defined by various extension modules. Also, it does not include some of the types that arise during processing such as the *listiterator* type. It is safe to use `from types import *` — the module does not export any names besides the ones listed here. New names exported by future versions of this module will all end in *Type*.

Typical use is for functions that do different things depending on their argument types, like the following:

```
from types import *
def delete(mylist, item):
    if type(item) is IntType:
        del mylist[item]
    else:
        mylist.remove(item)
```

Starting in Python 2.2, built-in factory functions such as *int()* and *str()* are also names for the corresponding types. This is now the preferred way to access the type instead of using the *types* module. Accordingly, the example above should be written as follows:

```
def delete(mylist, item):
    if isinstance(item, int):
        del mylist[item]
    else:
        mylist.remove(item)
```

The module defines the following names:

types.NoneType

The type of *None*.

types.TypeType

The type of type objects (such as returned by *type()*); alias of the built-in *type*.

types.BooleanType

The type of the *bool* values *True* and *False*; alias of the built-in *bool*.

버전 2.3에 추가.

types.IntType

The type of integers (e.g. *1*); alias of the built-in *int*.

types.LongType

The type of long integers (e.g. *1L*); alias of the built-in *long*.

types.FloatType

The type of floating point numbers (e.g. *1.0*); alias of the built-in *float*.

types.ComplexType

The type of complex numbers (e.g. `1.0j`). This is not defined if Python was built without complex number support.

types.StringType

The type of character strings (e.g. `'Spam'`); alias of the built-in `str`.

types.UnicodeType

The type of Unicode character strings (e.g. `u'Spam'`). This is not defined if Python was built without Unicode support. It's an alias of the built-in `unicode`.

types.TupleType

The type of tuples (e.g. `(1, 2, 3, 'Spam')`); alias of the built-in `tuple`.

types.ListType

The type of lists (e.g. `[0, 1, 2, 3]`); alias of the built-in `list`.

types.DictType

The type of dictionaries (e.g. `{'Bacon': 1, 'Ham': 0}`); alias of the built-in `dict`.

types.DictionaryType

An alternate name for `DictType`.

types.FunctionType

types.LambdaType

The type of user-defined functions and functions created by `lambda` expressions.

types.GeneratorType

The type of *generator*-iterator objects, produced by calling a generator function.

버전 2.2에 추가.

types.CodeType

The type for code objects such as returned by `compile()`.

types.ClassType

The type of user-defined old-style classes.

types.InstanceType

The type of instances of user-defined old-style classes.

types.MethodType

The type of methods of user-defined class instances.

types.UnboundMethodType

An alternate name for `MethodType`.

types.BuiltinFunctionType

types.BuiltinMethodType

The type of built-in functions like `len()` or `sys.exit()`, and methods of built-in classes. (Here, the term «built-in» means «written in C».)

types.ModuleType

The type of modules.

types.FileType

The type of open file objects such as `sys.stdout`; alias of the built-in `file`.

types.XRangeType

The type of range objects returned by `xrange()`; alias of the built-in `xrange`.

types.SliceType

The type of objects returned by `slice()`; alias of the built-in `slice`.

`types.EllipsisType`

The type of `Ellipsis`.

`types.TracebackType`

The type of traceback objects such as found in `sys.exc_traceback`.

`types.FrameType`

The type of frame objects such as found in `tb.tb_frame` if `tb` is a traceback object.

`types.BufferType`

The type of buffer objects created by the `buffer()` function.

`types.DictProxyType`

The type of dict proxies, such as `TypeType.__dict__`.

`types.NotImplementedType`

The type of `NotImplemented`

`types.GetSetDescriptorType`

The type of objects defined in extension modules with `PyGetSetDef`, such as `FrameType.f_locals` or `array.array.typecode`. This type is used as descriptor for object attributes; it has the same purpose as the `property` type, but for classes defined in extension modules.

버전 2.5에 추가.

`types.MemberDescriptorType`

The type of objects defined in extension modules with `PyMemberDef`, such as `datetime.timedelta.days`. This type is used as descriptor for simple C data members which use standard conversion functions; it has the same purpose as the `property` type, but for classes defined in extension modules.

CPython implementation detail: In other implementations of Python, this type may be identical to `GetSetDescriptorType`.

버전 2.5에 추가.

`types.StringTypes`

A sequence containing `StringType` and `UnicodeType` used to facilitate easier checking for any string object. Using this is more portable than using a sequence of the two string types constructed elsewhere since it only contains `UnicodeType` if it has been built in the running version of Python. For example: `isinstance(s, types.StringTypes)`.

버전 2.2에 추가.

8.16 new — Creation of runtime internal objects

버전 2.6부터 폐지: The `new` module has been removed in Python 3. Use the `types` module's classes instead.

The `new` module allows an interface to the interpreter object creation functions. This is for use primarily in marshal-type functions, when a new object needs to be created 《magically》 and not by using the regular creation functions. This module provides a low-level interface to the interpreter, so care must be exercised when using this module. It is possible to supply non-sensical arguments which crash the interpreter when the object is used.

The `new` module defines the following functions:

`new.instance(class[, dict])`

This function creates an instance of `class` with dictionary `dict` without calling the `__init__()` constructor. If `dict` is omitted or `None`, a new, empty dictionary is created for the new instance. Note that there are no guarantees that the object will be in a consistent state.

`new.instancemethod (function, instance, class)`

This function will return a method object, bound to *instance*, or unbound if *instance* is *None*. *function* must be callable.

`new.function (code, globals[, name[, argdefs[, closure]]])`

Returns a (Python) function with the given code and globals. If *name* is given, it must be a string or *None*. If it is a string, the function will have the given name, otherwise the function name will be taken from `code.co_name`. If *argdefs* is given, it must be a tuple and will be used to determine the default values of parameters. If *closure* is given, it must be *None* or a tuple of cell objects containing objects to bind to the names in `code.co_freevars`.

`new.code (argcount, nlocals, stacksize, flags, codestring, constants, names, varnames, filename, name, firstlineno, lnotab)`

This function is an interface to the `PyCode_New()` C function.

`new.module (name[, doc])`

This function returns a new module object with name *name*. *name* must be a string. The optional *doc* argument can have any type.

`new.classobj (name, baseclasses, dict)`

This function returns a new class object, with name *name*, derived from *baseclasses* (which should be a tuple of classes) and with namespace *dict*.

8.17 copy — Shallow and deep copy operations

Assignment statements in Python do not copy objects, they create bindings between a target and an object. For collections that are mutable or contain mutable items, a copy is sometimes needed so one can change one copy without changing the other. This module provides generic shallow and deep copy operations (explained below).

Interface summary:

`copy.copy (x)`

Return a shallow copy of *x*.

`copy.deepcopy (x)`

Return a deep copy of *x*.

exception `copy.error`

Raised for module specific errors.

The difference between shallow and deep copying is only relevant for compound objects (objects that contain other objects, like lists or class instances):

- A *shallow copy* constructs a new compound object and then (to the extent possible) inserts *references* into it to the objects found in the original.
- A *deep copy* constructs a new compound object and then, recursively, inserts *copies* into it of the objects found in the original.

Two problems often exist with deep copy operations that don't exist with shallow copy operations:

- Recursive objects (compound objects that, directly or indirectly, contain a reference to themselves) may cause a recursive loop.
- Because deep copy copies everything it may copy too much, such as data which is intended to be shared between copies.

The `deepcopy()` function avoids these problems by:

- keeping a 《memo》 dictionary of objects already copied during the current copying pass; and
- letting user-defined classes override the copying operation or the set of components copied.

This module does not copy types like module, method, stack trace, stack frame, file, socket, window, array, or any similar types. It does `copy` functions and classes (shallow and deeply), by returning the original object unchanged; this is compatible with the way these are treated by the `pickle` module.

Shallow copies of dictionaries can be made using `dict.copy()`, and of lists by assigning a slice of the entire list, for example, `copied_list = original_list[:]`.

버전 2.5에서 변경: Added copying functions.

Classes can use the same interfaces to control copying that they use to control pickling. See the description of module `pickle` for information on these methods. The `copy` module does not use the `copy_reg` registration module.

In order for a class to define its own copy implementation, it can define special methods `__copy__()` and `__deepcopy__()`. The former is called to implement the shallow copy operation; no additional arguments are passed. The latter is called to implement the deep copy operation; it is passed one argument, the memo dictionary. If the `__deepcopy__()` implementation needs to make a deep copy of a component, it should call the `deepcopy()` function with the component as first argument and the memo dictionary as second argument.

더 보기:

Module `pickle` Discussion of the special methods used to support object state retrieval and restoration.

8.18 pprint — Data pretty printer

Source code: [Lib/pprint.py](#)

The `pprint` module provides a capability to `pretty-print` arbitrary Python data structures in a form which can be used as input to the interpreter. If the formatted structures include objects which are not fundamental Python types, the representation may not be loadable. This may be the case if objects such as files, sockets, classes, or instances are included, as well as many other built-in objects which are not representable as Python constants.

The formatted representation keeps objects on a single line if it can, and breaks them onto multiple lines if they don't fit within the allowed width. Construct `PrettyPrinter` objects explicitly if you need to adjust the width constraint.

버전 2.5에서 변경: Dictionaries are sorted by key before the display is computed; before 2.5, a dictionary was sorted only if its display required more than one line, although that wasn't documented.

버전 2.6에서 변경: Added support for `set` and `frozenset`.

The `pprint` module defines one class:

class `pprint.PrettyPrinter` (*indent=1, width=80, depth=None, stream=None*)

Construct a `PrettyPrinter` instance. This constructor understands several keyword parameters. An output stream may be set using the `stream` keyword; the only method used on the stream object is the file protocol's `write()` method. If not specified, the `PrettyPrinter` adopts `sys.stdout`. Three additional parameters may be used to control the formatted representation. The keywords are *indent*, *depth*, and *width*. The amount of indentation added for each recursive level is specified by *indent*; the default is one. Other values can cause output to look a little odd, but can make nesting easier to spot. The number of levels which may be printed is controlled by *depth*; if the data structure being printed is too deep, the next contained level is replaced by `...`. By default, there is no constraint on the depth of the objects being formatted. The desired output width is constrained using the *width* parameter; the default is 80 characters. If a structure cannot be formatted within the constrained width, a best effort will be made.

```
>>> import pprint
>>> stuff = ['spam', 'eggs', 'lumberjack', 'knights', 'ni']
>>> stuff.insert(0, stuff[:])
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

>>> pp = pprint.PrettyPrinter(indent=4)
>>> pp.pprint(stuff)
[ ['spam', 'eggs', 'lumberjack', 'knights', 'ni'],
  'spam',
  'eggs',
  'lumberjack',
  'knights',
  'ni']
>>> tup = ('spam', ('eggs', ('lumberjack', ('knights', ('ni', ('dead',
... ('parrot', ('fresh fruit',)))))))
>>> pp = pprint.PrettyPrinter(depth=6)
>>> pp.pprint(tup)
('spam', ('eggs', ('lumberjack', ('knights', ('ni', ('dead', (...)))))))

```

The `PrettyPrinter` class supports several derivative functions:

`pprint.pformat(object, indent=1, width=80, depth=None)`

Return the formatted representation of *object* as a string. *indent*, *width* and *depth* will be passed to the `PrettyPrinter` constructor as formatting parameters.

버전 2.4에서 변경: The parameters *indent*, *width* and *depth* were added.

`pprint.pprint(object, stream=None, indent=1, width=80, depth=None)`

Prints the formatted representation of *object* on *stream*, followed by a newline. If *stream* is `None`, `sys.stdout` is used. This may be used in the interactive interpreter instead of a `print` statement for inspecting values. *indent*, *width* and *depth* will be passed to the `PrettyPrinter` constructor as formatting parameters.

```

>>> import pprint
>>> stuff = ['spam', 'eggs', 'lumberjack', 'knights', 'ni']
>>> stuff.insert(0, stuff)
>>> pprint.pprint(stuff)
[<Recursion on list with id=...>,
  'spam',
  'eggs',
  'lumberjack',
  'knights',
  'ni']

```

버전 2.4에서 변경: The parameters *indent*, *width* and *depth* were added.

`pprint.isreadable(object)`

Determine if the formatted representation of *object* is 《readable, 》 or can be used to reconstruct the value using `eval()`. This always returns `False` for recursive objects.

```

>>> pprint.isreadable(stuff)
False

```

`pprint.isrecursive(object)`

Determine if *object* requires a recursive representation.

One more support function is also defined:

`pprint.saferepr(object)`

Return a string representation of *object*, protected against recursive data structures. If the representation of *object* exposes a recursive entry, the recursive reference will be represented as `<Recursion on typename with id=number>`. The representation is not otherwise formatted.

```
>>> pprint.saferepr(stuff)
"[<Recursion on list with id=...>, 'spam', 'eggs', 'lumberjack', 'knights', 'ni']"
```

8.18.1 PrettyPrinter Objects

PrettyPrinter instances have the following methods:

PrettyPrinter.**pformat** (*object*)

Return the formatted representation of *object*. This takes into account the options passed to the *PrettyPrinter* constructor.

PrettyPrinter.**pprint** (*object*)

Print the formatted representation of *object* on the configured stream, followed by a newline.

The following methods provide the implementations for the corresponding functions of the same names. Using these methods on an instance is slightly more efficient since new *PrettyPrinter* objects don't need to be created.

PrettyPrinter.**isreadable** (*object*)

Determine if the formatted representation of the object is 《readable,》 or can be used to reconstruct the value using *eval()*. Note that this returns *False* for recursive objects. If the *depth* parameter of the *PrettyPrinter* is set and the object is deeper than allowed, this returns *False*.

PrettyPrinter.**isrecursive** (*object*)

Determine if the object requires a recursive representation.

This method is provided as a hook to allow subclasses to modify the way objects are converted to strings. The default implementation uses the internals of the *saferepr()* implementation.

PrettyPrinter.**format** (*object*, *context*, *maxlevels*, *level*)

Returns three values: the formatted version of *object* as a string, a flag indicating whether the result is readable, and a flag indicating whether recursion was detected. The first argument is the object to be presented. The second is a dictionary which contains the *id()* of objects that are part of the current presentation context (direct and indirect containers for *object* that are affecting the presentation) as the keys; if an object needs to be presented which is already represented in *context*, the third return value should be *True*. Recursive calls to the *format()* method should add additional entries for containers to this dictionary. The third argument, *maxlevels*, gives the requested limit to recursion; this will be 0 if there is no requested limit. This argument should be passed unmodified to recursive calls. The fourth argument, *level*, gives the current level; recursive calls should be passed a value less than that of the current call.

버전 2.3에 추가.

8.18.2 pprint Example

This example demonstrates several uses of the *pprint()* function and its parameters.

```
>>> import pprint
>>> tup = ('spam', ('eggs', ('lumberjack', ('knights', ('ni', ('dead',
... ('parrot', ('fresh fruit',)))))))
>>> stuff = ['a' * 10, tup, ['a' * 30, 'b' * 30], ['c' * 20, 'd' * 20]]
>>> pprint.pprint(stuff)
['aaaaaaaaaa',
 ('spam',
 ('eggs',
 ('lumberjack',
 ('knights', ('ni', ('dead', ('parrot', ('fresh fruit',))))))),
 ('c' * 20, 'd' * 20)]
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

['aaaaaaaaaaaaaaaaaaaaaaaaaaaaa', 'bbbbbbbbbbbbbbbbbbbbbbbbbbbbbb'],
['cccccccccccccccccccc', 'dddddddddddddddddd']]
>>> pprint.pprint(stuff, depth=3)
['aaaaaaaa',
 ('spam', ('eggs', (...))),
 ['aaaaaaaaaaaaaaaaaaaaaaaaaaaaa', 'bbbbbbbbbbbbbbbbbbbbbbbbbbbbbb'],
 ['cccccccccccccccccccc', 'dddddddddddddddddd']]
>>> pprint.pprint(stuff, width=60)
['aaaaaaaa',
 ('spam',
  ('eggs',
   ('lumberjack',
    ('knights',
     ('ni', ('dead', ('parrot', ('fresh fruit',))))))),
 ['aaaaaaaaaaaaaaaaaaaaaaaaaaaaa',
  'bbbbbbbbbbbbbbbbbbbbbbbbbbbbbb'],
 ['cccccccccccccccccccc', 'dddddddddddddddddd']]

```

8.19 repr — Alternate repr() implementation

참고: The `repr` module has been renamed to `reprlib` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

Source code: [Lib/repr.py](#)

The `repr` module provides a means for producing object representations with limits on the size of the resulting strings. This is used in the Python debugger and may be useful in other contexts as well.

This module provides a class, an instance, and a function:

class repr.Repr

Class which provides formatting services useful in implementing functions similar to the built-in `repr()`; size limits for different object types are added to avoid the generation of representations which are excessively long.

`repr.aRepr`

This is an instance of `Repr` which is used to provide the `repr()` function described below. Changing the attributes of this object will affect the size limits used by `repr()` and the Python debugger.

`repr.repr(obj)`

This is the `repr()` method of `aRepr`. It returns a string similar to that returned by the built-in function of the same name, but with limits on most sizes.

8.19.1 Repr Objects

Repr instances provide several attributes which can be used to provide size limits for the representations of different object types, and methods which format specific object types.

Repr.**maxlevel**

Depth limit on the creation of recursive representations. The default is 6.

Repr.**maxdict**

Repr.**maxlist**

Repr.**maxtuple**

Repr.**maxset**

Repr.**maxfrozenset**

Repr.**maxdeque**

Repr.**maxarray**

Limits on the number of entries represented for the named object type. The default is 4 for *maxdict*, 5 for *maxarray*, and 6 for the others.

버전 2.4에 추가: *maxset*, *maxfrozenset*, and *set*.

Repr.**maxlong**

Maximum number of characters in the representation for a long integer. Digits are dropped from the middle. The default is 40.

Repr.**maxstring**

Limit on the number of characters in the representation of the string. Note that the 《normal》 representation of the string is used as the character source: if escape sequences are needed in the representation, these may be mangled when the representation is shortened. The default is 30.

Repr.**maxother**

This limit is used to control the size of object types for which no specific formatting method is available on the *Repr* object. It is applied in a similar manner as *maxstring*. The default is 20.

Repr.**repr** (*obj*)

The equivalent to the built-in *repr*() that uses the formatting imposed by the instance.

Repr.**repr1** (*obj*, *level*)

Recursive implementation used by *repr*() . This uses the type of *obj* to determine which formatting method to call, passing it *obj* and *level*. The type-specific methods should call *repr1*() to perform recursive formatting, with *level* - 1 for the value of *level* in the recursive call.

Repr.**repr_TYPE** (*obj*, *level*)

Formatting methods for specific types are implemented as methods with a name based on the type name. In the method name, **TYPE** is replaced by *string.join(string.split(type(obj).__name__, '_'))*. Dispatch to these methods is handled by *repr1*() . Type-specific methods which need to recursively format a value should call *self.repr1(subobj, level - 1)*.

8.19.2 Subclassing Repr Objects

The use of dynamic dispatching by *Repr.repr1*() allows subclasses of *Repr* to add support for additional built-in object types or to modify the handling of types already supported. This example shows how special support for file objects could be added:

```
import repr as reprlib
import sys

class MyRepr(reprlib.Repr):
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
def repr_file(self, obj, level):
    if obj.name in ['<stdin>', '<stdout>', '<stderr>']:
        return obj.name
    else:
        return repr(obj)

aRepr = MyRepr()
print aRepr.repr(sys.stdin)          # prints '<stdin>'
```

숫자와 수학 모듈

The modules described in this chapter provide numeric and math-related functions and data types. The `numbers` module defines an abstract hierarchy of numeric types. The `math` and `cmath` modules contain various mathematical functions for floating-point and complex numbers. For users more interested in decimal accuracy than in speed, the `decimal` module supports exact representations of decimal numbers.

이 장에는 다음과 같은 모듈이 설명되어 있습니다:

9.1 `numbers` — 숫자 추상 베이스 클래스

버전 2.6에 추가.

`numbers` 모듈 (PEP 3141)은 숫자에 대한 추상 베이스 클래스의 계층 구조를 정의합니다. 계층 구조가 깊어 질수록 더 많은 연산이 정의되어 있습니다. 이 모듈에 정의된 모든 형은 인스턴스로 만들 수 없습니다.

class `numbers.Number`

숫자 계층의 최상위 클래스입니다. 형에 상관없이 인자 `x`가 숫자인지 확인하려면 `isinstance(x, Number)`를 사용하세요.

9.1.1 숫자 계층

class `numbers.Complex`

이 서브 클래스는 복소수를 표현하고 내장 `complex` 형에 사용되는 연산을 포함합니다. 여기에는 `complex`와 `bool` 형으로의 변환과 `real`, `imag`, `+`, `-`, `*`, `/`, `abs()`, `conjugate()`, `==`, `!=`이 포함됩니다. `-`와 `!=`를 제외하고는 모두 추상입니다.

real

추상. 복소수의 실수부를 반환합니다.

imag

추상. 복소수의 허수부를 반환합니다.

conjugate()

추상 메서드. 켄레 복소수를 반환합니다. 예를 들어 `(1+3j).conjugate() == (1-3j)` 입니다.

class numbers.Real

Real 클래스는 *Complex* 클래스에 실수 연산을 추가합니다.

요약하면 *float* 로의 변환과 `math.trunc()`, `round()`, `math.floor()`, `math.ceil()`, `divmod()`, `//`, `%`, `<`, `<=`, `>`, `>=` 가 포함됩니다.

이 클래스는 또한 `complex()`, `real`, `imag`, `conjugate()` 를 위한 기본값을 제공합니다.

class numbers.Rational

Real 의 하위 형이고 *numerator* 와 *denominator* 프로퍼티가 추가됩니다. 이 프로퍼티는 기약 분수의 값이어야 합니다. 또한 `float()` 함수를 위한 기본값으로 사용됩니다.

numerator

프로퍼티(추상 메서드)

denominator

프로퍼티(추상 메서드)

class numbers.Integral

Rational 의 하위 형이고 *int* 클래스로 변환 기능이 추가됩니다. `float()`, `numerator`, `denominator` 를 위한 기본값을 제공합니다. `**` 를 위한 메서드와 비트 연산 `<<`, `>>`, `&`, `^`, `|`, `~` 를 추가합니다.

9.1.2 형 구현을 위한 주의 사항

구현자는 동일한 숫자가 같게 취급되고 같은 값으로 해싱되도록 해야 합니다. 만약 종류가 다른 실수의 하위 형이 있는 경우 조금 까다로울 수 있습니다. 예를 들어 `fractions.Fraction` 클래스는 `hash()` 함수를 다음과 같이 구현합니다:

```
def __hash__(self):
    if self.denominator == 1:
        # Get integers right.
        return hash(self.numerator)
    # Expensive check, but definitely correct.
    if self == float(self):
        return hash(float(self))
    else:
        # Use tuple's hash to avoid a high collision rate on
        # simple fractions.
        return hash((self.numerator, self.denominator))
```

더 많은 숫자 추상 베이스 클래스(ABC) 추가

물론 숫자를 위한 ABC를 추가하는 것이 가능합니다. 그렇지 않으면 엉망으로 상속 계층이 구현될 것입니다. *Complex* 와 *Real* 사이에 다음과 같이 `MyFoo` 를 추가할 수 있습니다:

```
class MyFoo(Complex): ...
MyFoo.register(Real)
```


산술 연산 구현

다른 형에 대한 연산은 두 인자의 형에 관해 알고 있는 구현을 호출하거나 두 인자를 가장 비슷한 내장형으로 변환하여 연산하도록 산술 연산을 구현하는 것이 좋습니다. `Integral` 클래스의 하위 형일 경우에 `__add__()` 와 `__radd__()` 메서드는 다음과 같이 정의되어야 함을 의미합니다:

```
class MyIntegral(Integral):

    def __add__(self, other):
        if isinstance(other, MyIntegral):
            return do_my_adding_stuff(self, other)
        elif isinstance(other, OtherTypeIKnowAbout):
            return do_my_other_adding_stuff(self, other)
        else:
            return NotImplemented

    def __radd__(self, other):
        if isinstance(other, MyIntegral):
            return do_my_adding_stuff(other, self)
        elif isinstance(other, OtherTypeIKnowAbout):
            return do_my_other_adding_stuff(other, self)
        elif isinstance(other, Integral):
            return int(other) + int(self)
        elif isinstance(other, Real):
            return float(other) + float(self)
        elif isinstance(other, Complex):
            return complex(other) + complex(self)
        else:
            return NotImplemented
```

`Complex` 클래스의 서브클래스에는 다섯 가지의 서로 다른 혼합형 연산이 있습니다. 위의 코드에서 `MyIntegral` 와 `OtherTypeIKnowAbout` 를 제외한 나머지를 기본구조라고 하겠습니다. `a` 는 `Complex` 의 하위 형인 `A` 의 인스턴스입니다(즉 `a : A <: Complex` 입니다). 비슷하게 `b : B <: Complex` 입니다. `a + b` 인 경우를 생각해 보겠습니다:

1. 만약 `A` 가 `b` 를 받는 `__add__()` 메서드를 정의했다면 모든 것이 문제없이 처리됩니다.
2. `A` 가 기본구조 코드로 진입하고 `__add__()` 로 부터 어떤 값을 반환한다면 `B` 가 똑똑하게 정의한 `__radd__()` 메서드를 놓칠 수 있습니다. 이를 피하려면 기본구조는 `__add__()` 에서 `NotImplemented` 를 반환해야 합니다. (또는 `A` 가 `__add__()` 메서드를 전혀 구현하지 않을 수도 있습니다.)
3. 그다음 `B` 의 `__radd__()` 메서드가 기회를 얻습니다. 이 메서드가 `a` 를 받을 수 있다면 모든 것이 문제없이 처리됩니다.
4. 기본구조 코드로 돌아온다면 더 시도해 볼 수 있는 메서드가 없으므로 기본적으로 수행될 구현을 작성해야 합니다.
5. 만약 `B <: A` 라면 파이썬은 `A.__add__` 메서드 전에 `B.__radd__` 를 시도합니다. `A` 에 대해서 알고 `B` 가 구현되었기 때문에 이런 행동은 문제없습니다. 따라서 `Complex` 에 위임하기 전에 이 인스턴스를 처리할 수 있습니다.

만약 어떤 것도 공유하지 않는 `A <: Complex` 와 `B <: Real` 라면 적절한 공유 연산(shared operation)은 내장 `complex` 클래스에 연관된 것입니다. 양쪽의 `__radd__()` 메서드가 여기에 해당하므로 `a+b == b+a` 가 됩니다.

대부분 주어진 어떤 형에 대한 연산은 매우 비슷하므로, 주어진 연산자의 정방향(forward) 인스턴스와 역방향(reverse) 인스턴스를 생성하는 헬퍼 함수를 정의하는 것이 유용합니다. 예를 들어 `fractions.Fraction` 클래스는 다음과 같이 사용합니다:

```

def _operator_fallbacks(monomorphic_operator, fallback_operator):
    def forward(a, b):
        if isinstance(b, (int, long, Fraction)):
            return monomorphic_operator(a, b)
        elif isinstance(b, float):
            return fallback_operator(float(a), b)
        elif isinstance(b, complex):
            return fallback_operator(complex(a), b)
        else:
            return NotImplemented
    forward.__name__ = '__' + fallback_operator.__name__ + '__'
    forward.__doc__ = monomorphic_operator.__doc__

    def reverse(b, a):
        if isinstance(a, Rational):
            # Includes ints.
            return monomorphic_operator(a, b)
        elif isinstance(a, numbers.Real):
            return fallback_operator(float(a), float(b))
        elif isinstance(a, numbers.Complex):
            return fallback_operator(complex(a), complex(b))
        else:
            return NotImplemented
    reverse.__name__ = '__r' + fallback_operator.__name__ + '__'
    reverse.__doc__ = monomorphic_operator.__doc__

    return forward, reverse

def _add(a, b):
    """a + b"""
    return Fraction(a.numerator * b.denominator +
                    b.numerator * a.denominator,
                    a.denominator * b.denominator)

__add__, __radd__ = _operator_fallbacks(_add, operator.add)

# ...

```

9.2 math — Mathematical functions

This module is always available. It provides access to the mathematical functions defined by the C standard.

These functions cannot be used with complex numbers; use the functions of the same name from the `cmath` module if you require support for complex numbers. The distinction between functions which support complex numbers and those which don't is made since most users do not want to learn quite as much mathematics as required to understand complex numbers. Receiving an exception instead of a complex result allows earlier detection of the unexpected complex number used as a parameter, so that the programmer can determine how and why it was generated in the first place.

The following functions are provided by this module. Except when explicitly noted otherwise, all return values are floats.

9.2.1 Number-theoretic and representation functions

`math.ceil(x)`

Return the ceiling of x as a float, the smallest integer value greater than or equal to x .

`math.copysign(x, y)`

Return x with the sign of y . On a platform that supports signed zeros, `copysign(1.0, -0.0)` returns `-1.0`.

버전 2.6에 추가.

`math.fabs(x)`

Return the absolute value of x .

`math.factorial(x)`

Return x factorial. Raises `ValueError` if x is not integral or is negative.

버전 2.6에 추가.

`math.floor(x)`

Return the floor of x as a float, the largest integer value less than or equal to x .

`math.fmod(x, y)`

Return `fmod(x, y)`, as defined by the platform C library. Note that the Python expression `x % y` may not return the same result. The intent of the C standard is that `fmod(x, y)` be exactly (mathematically; to infinite precision) equal to $x - n*y$ for some integer n such that the result has the same sign as x and magnitude less than `abs(y)`. Python's `x % y` returns a result with the sign of y instead, and may not be exactly computable for float arguments. For example, `fmod(-1e-100, 1e100)` is `-1e-100`, but the result of Python's `-1e-100 % 1e100` is `1e100-1e-100`, which cannot be represented exactly as a float, and rounds to the surprising `1e100`. For this reason, function `fmod()` is generally preferred when working with floats, while Python's `x % y` is preferred when working with integers.

`math.frexp(x)`

Return the mantissa and exponent of x as the pair (m, e) . m is a float and e is an integer such that $x == m * 2**e$ exactly. If x is zero, returns `(0.0, 0)`, otherwise $0.5 \leq \text{abs}(m) < 1$. This is used to 《pick apart》 the internal representation of a float in a portable way.

`math.fsum(iterable)`

Return an accurate floating point sum of values in the iterable. Avoids loss of precision by tracking multiple intermediate partial sums:

```
>>> sum([.1, .1, .1, .1, .1, .1, .1, .1, .1, .1])
0.9999999999999999
>>> fsum([.1, .1, .1, .1, .1, .1, .1, .1, .1, .1])
1.0
```

The algorithm's accuracy depends on IEEE-754 arithmetic guarantees and the typical case where the rounding mode is half-even. On some non-Windows builds, the underlying C library uses extended precision addition and may occasionally double-round an intermediate sum causing it to be off in its least significant bit.

For further discussion and two alternative approaches, see the [ASPN cookbook recipes for accurate floating point summation](#).

버전 2.6에 추가.

`math.isinf(x)`

Check if the float x is positive or negative infinity.

버전 2.6에 추가.

`math.isnan(x)`

Check if the float x is a NaN (not a number). For more information on NaNs, see the IEEE 754 standards.

버전 2.6에 추가.

`math.ldexp(x, i)`

Return $x * (2^{**i})$. This is essentially the inverse of function `frexp()`.

`math.modf(x)`

Return the fractional and integer parts of x . Both results carry the sign of x and are floats.

`math.trunc(x)`

Return the *Real* value x truncated to an *Integral* (usually a long integer). Uses the `__trunc__` method.

버전 2.6에 추가.

Note that `frexp()` and `modf()` have a different call/return pattern than their C equivalents: they take a single argument and return a pair of values, rather than returning their second return value through an `<output parameter>` (there is no such thing in Python).

For the `ceil()`, `floor()`, and `modf()` functions, note that *all* floating-point numbers of sufficiently large magnitude are exact integers. Python floats typically carry no more than 53 bits of precision (the same as the platform C double type), in which case any float x with `abs(x) >= 2**52` necessarily has no fractional bits.

9.2.2 Power and logarithmic functions

`math.exp(x)`

Return e^{**x} .

`math.expm1(x)`

Return $e^{**x} - 1$. For small floats x , the subtraction in $\exp(x) - 1$ can result in a significant loss of precision; the `expm1()` function provides a way to compute this quantity to full precision:

```
>>> from math import exp, expm1
>>> exp(1e-5) - 1 # gives result accurate to 11 places
1.0000050000069649e-05
>>> expm1(1e-5) # result accurate to full precision
1.0000050000166668e-05
```

버전 2.7에 추가.

`math.log(x[, base])`

With one argument, return the natural logarithm of x (to base e).

With two arguments, return the logarithm of x to the given *base*, calculated as $\log(x) / \log(\text{base})$.

버전 2.3에서 변경: *base* argument added.

`math.log1p(x)`

Return the natural logarithm of $1+x$ (base e). The result is calculated in a way which is accurate for x near zero.

버전 2.6에 추가.

`math.log10(x)`

Return the base-10 logarithm of x . This is usually more accurate than `log(x, 10)`.

`math.pow(x, y)`

Return x raised to the power y . Exceptional cases follow Annex `<F>` of the C99 standard as far as possible. In particular, `pow(1.0, x)` and `pow(x, 0.0)` always return `1.0`, even when x is a zero or a NaN. If both x and y are finite, x is negative, and y is not an integer then `pow(x, y)` is undefined, and raises `ValueError`.

Unlike the built-in `**` operator, `math.pow()` converts both its arguments to type `float`. Use `**` or the built-in `pow()` function for computing exact integer powers.

버전 2.6에서 변경: The outcome of `1**nan` and `nan**0` was undefined.

`math.sqrt(x)`
Return the square root of x .

9.2.3 Trigonometric functions

`math.acos(x)`
Return the arc cosine of x , in radians.

`math.asin(x)`
Return the arc sine of x , in radians.

`math.atan(x)`
Return the arc tangent of x , in radians.

`math.atan2(y, x)`
Return `atan(y / x)`, in radians. The result is between $-\pi$ and π . The vector in the plane from the origin to point (x, y) makes this angle with the positive X axis. The point of `atan2()` is that the signs of both inputs are known to it, so it can compute the correct quadrant for the angle. For example, `atan(1)` and `atan2(1, 1)` are both $\pi/4$, but `atan2(-1, -1)` is $-3\pi/4$.

`math.cos(x)`
Return the cosine of x radians.

`math.hypot(x, y)`
Return the Euclidean norm, `sqrt(x*x + y*y)`. This is the length of the vector from the origin to point (x, y) .

`math.sin(x)`
Return the sine of x radians.

`math.tan(x)`
Return the tangent of x radians.

9.2.4 Angular conversion

`math.degrees(x)`
Convert angle x from radians to degrees.

`math.radians(x)`
Convert angle x from degrees to radians.

9.2.5 Hyperbolic functions

`math.acosh(x)`
Return the inverse hyperbolic cosine of x .
버전 2.6에 추가.

`math.asinh(x)`
Return the inverse hyperbolic sine of x .
버전 2.6에 추가.

`math.atanh(x)`
Return the inverse hyperbolic tangent of x .
버전 2.6에 추가.

`math.cosh(x)`
Return the hyperbolic cosine of x .

`math.sinh(x)`
Return the hyperbolic sine of x .

`math.tanh(x)`
Return the hyperbolic tangent of x .

9.2.6 Special functions

`math.erf(x)`
Return the error function at x .
버전 2.7에 추가.

`math.erfc(x)`
Return the complementary error function at x .
버전 2.7에 추가.

`math.gamma(x)`
Return the Gamma function at x .
버전 2.7에 추가.

`math.lgamma(x)`
Return the natural logarithm of the absolute value of the Gamma function at x .
버전 2.7에 추가.

9.2.7 Constants

`math.pi`
The mathematical constant $\pi = 3.141592\dots$, to available precision.

`math.e`
The mathematical constant $e = 2.718281\dots$, to available precision.

CPython implementation detail: The `math` module consists mostly of thin wrappers around the platform C math library functions. Behavior in exceptional cases follows Annex F of the C99 standard where appropriate. The current implementation will raise `ValueError` for invalid operations like `sqrt(-1.0)` or `log(0.0)` (where C99 Annex F recommends signaling invalid operation or divide-by-zero), and `OverflowError` for results that overflow (for example, `exp(1000.0)`). A NaN will not be returned from any of the functions above unless one or more of the input arguments was a NaN; in that case, most functions will return a NaN, but (again following C99 Annex F) there are some exceptions to this rule, for example `pow(float('nan'), 0.0)` or `hypot(float('nan'), float('inf'))`.

Note that Python makes no effort to distinguish signaling NaNs from quiet NaNs, and behavior for signaling NaNs remains unspecified. Typical behavior is to treat all NaNs as though they were quiet.

버전 2.6에서 변경: Behavior in special cases now aims to follow C99 Annex F. In earlier versions of Python the behavior in special cases was loosely specified.

더 보기:

Module `cmath` Complex number versions of many of these functions.

9.3 cmath — Mathematical functions for complex numbers

This module is always available. It provides access to mathematical functions for complex numbers. The functions in this module accept integers, floating-point numbers or complex numbers as arguments. They will also accept any Python object that has either a `__complex__()` or a `__float__()` method: these methods are used to convert the object to a complex or floating-point number, respectively, and the function is then applied to the result of the conversion.

참고: On platforms with hardware and system-level support for signed zeros, functions involving branch cuts are continuous on *both* sides of the branch cut: the sign of the zero distinguishes one side of the branch cut from the other. On platforms that do not support signed zeros the continuity is as specified below.

9.3.1 Conversions to and from polar coordinates

A Python complex number z is stored internally using *rectangular* or *Cartesian* coordinates. It is completely determined by its *real part* `z.real` and its *imaginary part* `z.imag`. In other words:

```
z == z.real + z.imag*1j
```

Polar coordinates give an alternative way to represent a complex number. In polar coordinates, a complex number z is defined by the modulus r and the phase angle ϕ . The modulus r is the distance from z to the origin, while the phase ϕ is the counterclockwise angle, measured in radians, from the positive x -axis to the line segment that joins the origin to z .

The following functions can be used to convert from the native rectangular coordinates to polar coordinates and back.

`cmath.phase(x)`

Return the phase of x (also known as the *argument* of x), as a float. `phase(x)` is equivalent to `math.atan2(x.imag, x.real)`. The result lies in the range $[-\pi, \pi]$, and the branch cut for this operation lies along the negative real axis, continuous from above. On systems with support for signed zeros (which includes most systems in current use), this means that the sign of the result is the same as the sign of `x.imag`, even when `x.imag` is zero:

```
>>> phase(complex(-1.0, 0.0))
3.1415926535897931
>>> phase(complex(-1.0, -0.0))
-3.1415926535897931
```

버전 2.6에 추가.

참고: The modulus (absolute value) of a complex number x can be computed using the built-in `abs()` function. There is no separate `cmath` module function for this operation.

`cmath.polar(x)`

Return the representation of x in polar coordinates. Returns a pair (r, ϕ) where r is the modulus of x and ϕ is the phase of x . `polar(x)` is equivalent to `(abs(x), phase(x))`.

버전 2.6에 추가.

`cmath.rect(r, phi)`

Return the complex number x with polar coordinates r and ϕ . Equivalent to `r * (math.cos(phi) + math.sin(phi)*1j)`.

버전 2.6에 추가.

9.3.2 Power and logarithmic functions

`cmath.exp(x)`

Return the exponential value e^{**x} .

`cmath.log(x[, base])`

Returns the logarithm of x to the given *base*. If the *base* is not specified, returns the natural logarithm of x . There is one branch cut, from 0 along the negative real axis to $-\infty$, continuous from above.

버전 2.4에서 변경: *base* argument added.

`cmath.log10(x)`

Return the base-10 logarithm of x . This has the same branch cut as `log()`.

`cmath.sqrt(x)`

Return the square root of x . This has the same branch cut as `log()`.

9.3.3 Trigonometric functions

`cmath.acos(x)`

Return the arc cosine of x . There are two branch cuts: One extends right from 1 along the real axis to ∞ , continuous from below. The other extends left from -1 along the real axis to $-\infty$, continuous from above.

`cmath.asin(x)`

Return the arc sine of x . This has the same branch cuts as `acos()`.

`cmath.atan(x)`

Return the arc tangent of x . There are two branch cuts: One extends from $1j$ along the imaginary axis to ∞j , continuous from the right. The other extends from $-1j$ along the imaginary axis to $-\infty j$, continuous from the left.

버전 2.6에서 변경: direction of continuity of upper cut reversed

`cmath.cos(x)`

Return the cosine of x .

`cmath.sin(x)`

Return the sine of x .

`cmath.tan(x)`

Return the tangent of x .

9.3.4 Hyperbolic functions

`cmath.acosh(x)`

Return the inverse hyperbolic cosine of x . There is one branch cut, extending left from 1 along the real axis to $-\infty$, continuous from above.

`cmath.asinh(x)`

Return the inverse hyperbolic sine of x . There are two branch cuts: One extends from $1j$ along the imaginary axis to ∞j , continuous from the right. The other extends from $-1j$ along the imaginary axis to $-\infty j$, continuous from the left.

버전 2.6에서 변경: branch cuts moved to match those recommended by the C99 standard

`cmath.atanh(x)`

Return the inverse hyperbolic tangent of x . There are two branch cuts: One extends from 1 along the real axis to ∞ , continuous from below. The other extends from -1 along the real axis to $-\infty$, continuous from above.

버전 2.6에서 변경: direction of continuity of right cut reversed

`cmath.cosh(x)`
Return the hyperbolic cosine of x .

`cmath.sinh(x)`
Return the hyperbolic sine of x .

`cmath.tanh(x)`
Return the hyperbolic tangent of x .

9.3.5 Classification functions

`cmath.isinf(x)`
Return `True` if the real or the imaginary part of x is positive or negative infinity.

버전 2.6에 추가.

`cmath.isnan(x)`
Return `True` if the real or imaginary part of x is not a number (NaN).

버전 2.6에 추가.

9.3.6 Constants

`cmath.pi`
The mathematical constant π , as a float.

`cmath.e`
The mathematical constant e , as a float.

Note that the selection of functions is similar, but not identical, to that in module `math`. The reason for having two modules is that some users aren't interested in complex numbers, and perhaps don't even know what they are. They would rather have `math.sqrt(-1)` raise an exception than return a complex number. Also note that the functions defined in `cmath` always return a complex number, even if the answer can be expressed as a real number (in which case the complex number has an imaginary part of zero).

A note on branch cuts: They are curves along which the given function fails to be continuous. They are a necessary feature of many complex functions. It is assumed that if you need to compute with complex functions, you will understand about branch cuts. Consult almost any (not too elementary) book on complex variables for enlightenment. For information of the proper choice of branch cuts for numerical purposes, a good reference should be the following:

더 보기:

Kahan, W: Branch cuts for complex elementary functions; or, Much ado about nothing's sign bit. In Iserles, A., and Powell, M. (eds.), The state of the art in numerical analysis. Clarendon Press (1987) pp165–211.

9.4 decimal — Decimal fixed point and floating point arithmetic

버전 2.4에 추가.

The `decimal` module provides support for decimal floating point arithmetic. It offers several advantages over the `float` datatype:

- Decimal 《is based on a floating-point model which was designed with people in mind, and necessarily has a paramount guiding principle – computers must provide an arithmetic that works in the same way as the arithmetic that people learn at school.》 – excerpt from the decimal arithmetic specification.

- Decimal numbers can be represented exactly. In contrast, numbers like 1.1 and 2.2 do not have exact representations in binary floating point. End users typically would not expect $1.1 + 2.2$ to display as 3.3000000000000003 as it does with binary floating point.
- The exactness carries over into arithmetic. In decimal floating point, $0.1 + 0.1 + 0.1 - 0.3$ is exactly equal to zero. In binary floating point, the result is $5.5511151231257827e-017$. While near to zero, the differences prevent reliable equality testing and differences can accumulate. For this reason, decimal is preferred in accounting applications which have strict equality invariants.
- The decimal module incorporates a notion of significant places so that $1.30 + 1.20$ is 2.50. The trailing zero is kept to indicate significance. This is the customary presentation for monetary applications. For multiplication, the 《schoolbook》 approach uses all the figures in the multiplicands. For instance, $1.3 * 1.2$ gives 1.56 while $1.30 * 1.20$ gives 1.5600.
- Unlike hardware based binary floating point, the decimal module has a user alterable precision (defaulting to 28 places) which can be as large as needed for a given problem:

```
>>> from decimal import *
>>> getcontext().prec = 6
>>> Decimal(1) / Decimal(7)
Decimal('0.142857')
>>> getcontext().prec = 28
>>> Decimal(1) / Decimal(7)
Decimal('0.1428571428571428571428571428571429')
```

- Both binary and decimal floating point are implemented in terms of published standards. While the built-in float type exposes only a modest portion of its capabilities, the decimal module exposes all required parts of the standard. When needed, the programmer has full control over rounding and signal handling. This includes an option to enforce exact arithmetic by using exceptions to block any inexact operations.
- The decimal module was designed to support 《without prejudice, both exact unrounded decimal arithmetic (sometimes called fixed-point arithmetic) and rounded floating-point arithmetic.》 – excerpt from the decimal arithmetic specification.

The module design is centered around three concepts: the decimal number, the context for arithmetic, and signals.

A decimal number is immutable. It has a sign, coefficient digits, and an exponent. To preserve significance, the coefficient digits do not truncate trailing zeros. Decimals also include special values such as *Infinity*, *-Infinity*, and *NaN*. The standard also differentiates -0 from $+0$.

The context for arithmetic is an environment specifying precision, rounding rules, limits on exponents, flags indicating the results of operations, and trap enablers which determine whether signals are treated as exceptions. Rounding options include *ROUND_CEILING*, *ROUND_DOWN*, *ROUND_FLOOR*, *ROUND_HALF_DOWN*, *ROUND_HALF_EVEN*, *ROUND_HALF_UP*, *ROUND_UP*, and *ROUND_05UP*.

Signals are groups of exceptional conditions arising during the course of computation. Depending on the needs of the application, signals may be ignored, considered as informational, or treated as exceptions. The signals in the decimal module are: *Clamped*, *InvalidOperation*, *DivisionByZero*, *Inexact*, *Rounded*, *Subnormal*, *Overflow*, and *Underflow*.

For each signal there is a flag and a trap enabler. When a signal is encountered, its flag is set to one, then, if the trap enabler is set to one, an exception is raised. Flags are sticky, so the user needs to reset them before monitoring a calculation.

더 보기:

- IBM's General Decimal Arithmetic Specification, [The General Decimal Arithmetic Specification](#).

9.4.1 Quick-start Tutorial

The usual start to using decimals is importing the module, viewing the current context with `getcontext()` and, if necessary, setting new values for precision, rounding, or enabled traps:

```
>>> from decimal import *
>>> getcontext()
Context(prec=28, rounding=ROUND_HALF_EVEN, Emin=-999999999, Emax=999999999,
        capitals=1, flags=[], traps=[Overflow, DivisionByZero,
        InvalidOperation])

>>> getcontext().prec = 7           # Set a new precision
```

Decimal instances can be constructed from integers, strings, floats, or tuples. Construction from an integer or a float performs an exact conversion of the value of that integer or float. Decimal numbers include special values such as NaN which stands for 《Not a number》, positive and negative Infinity, and -0 .

```
>>> getcontext().prec = 28
>>> Decimal(10)
Decimal('10')
>>> Decimal('3.14')
Decimal('3.14')
>>> Decimal(3.14)
Decimal('3.140000000000000124344978758017532527446746826171875')
>>> Decimal((0, (3, 1, 4), -2))
Decimal('3.14')
>>> Decimal(str(2.0 ** 0.5))
Decimal('1.41421356237')
>>> Decimal(2) ** Decimal('0.5')
Decimal('1.414213562373095048801688724')
>>> Decimal('NaN')
Decimal('NaN')
>>> Decimal('-Infinity')
Decimal('-Infinity')
```

The significance of a new Decimal is determined solely by the number of digits input. Context precision and rounding only come into play during arithmetic operations.

```
>>> getcontext().prec = 6
>>> Decimal('3.0')
Decimal('3.0')
>>> Decimal('3.1415926535')
Decimal('3.1415926535')
>>> Decimal('3.1415926535') + Decimal('2.7182818285')
Decimal('5.85987')
>>> getcontext().rounding = ROUND_UP
>>> Decimal('3.1415926535') + Decimal('2.7182818285')
Decimal('5.85988')
```

Decimals interact well with much of the rest of Python. Here is a small decimal floating point flying circus:

```
>>> data = map(Decimal, '1.34 1.87 3.45 2.35 1.00 0.03 9.25'.split())
>>> max(data)
Decimal('9.25')
>>> min(data)
Decimal('0.03')
>>> sorted(data)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
[Decimal('0.03'), Decimal('1.00'), Decimal('1.34'), Decimal('1.87'),
 Decimal('2.35'), Decimal('3.45'), Decimal('9.25')]
>>> sum(data)
Decimal('19.29')
>>> a,b,c = data[:3]
>>> str(a)
'1.34'
>>> float(a)
1.34
>>> round(a, 1)      # round() first converts to binary floating point
1.3
>>> int(a)
1
>>> a * 5
Decimal('6.70')
>>> a * b
Decimal('2.5058')
>>> c % a
Decimal('0.77')
```

And some mathematical functions are also available to Decimal:

```
>>> getcontext().prec = 28
>>> Decimal(2).sqrt()
Decimal('1.414213562373095048801688724')
>>> Decimal(1).exp()
Decimal('2.718281828459045235360287471')
>>> Decimal('10').ln()
Decimal('2.302585092994045684017991455')
>>> Decimal('10').log10()
Decimal('1')
```

The `quantize()` method rounds a number to a fixed exponent. This method is useful for monetary applications that often round results to a fixed number of places:

```
>>> Decimal('7.325').quantize(Decimal('.01'), rounding=ROUND_DOWN)
Decimal('7.32')
>>> Decimal('7.325').quantize(Decimal('1.'), rounding=ROUND_UP)
Decimal('8')
```

As shown above, the `getcontext()` function accesses the current context and allows the settings to be changed. This approach meets the needs of most applications.

For more advanced work, it may be useful to create alternate contexts using the `Context()` constructor. To make an alternate active, use the `setcontext()` function.

In accordance with the standard, the `decimal` module provides two ready to use standard contexts, `BasicContext` and `ExtendedContext`. The former is especially useful for debugging because many of the traps are enabled:

```
>>> myothercontext = Context(prec=60, rounding=ROUND_HALF_DOWN)
>>> setcontext(myothercontext)
>>> Decimal(1) / Decimal(7)
Decimal('0.142857142857142857142857142857142857142857142857142857')

>>> ExtendedContext
Context(prec=9, rounding=ROUND_HALF_EVEN, Emin=-999999999, Emax=999999999,
       capitals=1, flags=[], traps=[])
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> setcontext(ExtendedContext)
>>> Decimal(1) / Decimal(7)
Decimal('0.142857143')
>>> Decimal(42) / Decimal(0)
Decimal('Infinity')

>>> setcontext(BasicContext)
>>> Decimal(42) / Decimal(0)
Traceback (most recent call last):
  File "<pyshell#143>", line 1, in -toplevel-
    Decimal(42) / Decimal(0)
DivisionByZero: x / 0
```

Contexts also have signal flags for monitoring exceptional conditions encountered during computations. The flags remain set until explicitly cleared, so it is best to clear the flags before each set of monitored computations by using the `clear_flags()` method.

```
>>> setcontext(ExtendedContext)
>>> getcontext().clear_flags()
>>> Decimal(355) / Decimal(113)
Decimal('3.14159292')
>>> getcontext()
Context(prec=9, rounding=ROUND_HALF_EVEN, Emin=-999999999, Emax=999999999,
        capitals=1, flags=[Rounded, Inexact], traps=[])
```

The *flags* entry shows that the rational approximation to π was rounded (digits beyond the context precision were thrown away) and that the result is inexact (some of the discarded digits were non-zero).

Individual traps are set using the dictionary in the *traps* field of a context:

```
>>> setcontext(ExtendedContext)
>>> Decimal(1) / Decimal(0)
Decimal('Infinity')
>>> getcontext().traps[DivisionByZero] = 1
>>> Decimal(1) / Decimal(0)
Traceback (most recent call last):
  File "<pyshell#112>", line 1, in -toplevel-
    Decimal(1) / Decimal(0)
DivisionByZero: x / 0
```

Most programs adjust the current context only once, at the beginning of the program. And, in many applications, data is converted to *Decimal* with a single cast inside a loop. With context set and decimals created, the bulk of the program manipulates the data no differently than with other Python numeric types.

9.4.2 Decimal objects

class `decimal.Decimal` (`[value[, context]]`)

Construct a new *Decimal* object based from *value*.

value can be an integer, string, tuple, *float*, or another *Decimal* object. If no *value* is given, returns `Decimal('0')`. If *value* is a string, it should conform to the decimal numeric string syntax after leading and trailing whitespace characters are removed:

```
sign      ::= '+' | '-'
digit     ::= '0' | '1' | '2' | '3' | '4' | '5' | '6' | '7' | '8' | '9'
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

indicator      ::= 'e' | 'E'
digits         ::= digit [digit]...
decimal-part   ::= digits '.' [digits] | ['.'] digits
exponent-part  ::= indicator [sign] digits
infinity       ::= 'Infinity' | 'Inf'
nan            ::= 'NaN' [digits] | 'sNaN' [digits]
numeric-value  ::= decimal-part [exponent-part] | infinity
numeric-string ::= [sign] numeric-value | [sign] nan

```

If *value* is a unicode string then other Unicode decimal digits are also permitted where *digit* appears above. These include decimal digits from various other alphabets (for example, Arabic-Indic and Devanāgarī digits) along with the fullwidth digits `u'\uff10'` through `u'\uff19'`.

If *value* is a *tuple*, it should have three components, a sign (0 for positive or 1 for negative), a *tuple* of digits, and an integer exponent. For example, `Decimal((0, (1, 4, 1, 4), -3))` returns `Decimal('1.414')`.

If *value* is a *float*, the binary floating point value is losslessly converted to its exact decimal equivalent. This conversion can often require 53 or more digits of precision. For example, `Decimal(float('1.1'))` converts to `Decimal('1.100000000000000088817841970012523233890533447265625')`.

The *context* precision does not affect how many digits are stored. That is determined exclusively by the number of digits in *value*. For example, `Decimal('3.00000')` records all five zeros even if the context precision is only three.

The purpose of the *context* argument is determining what to do if *value* is a malformed string. If the context traps *InvalidOperation*, an exception is raised; otherwise, the constructor returns a new *Decimal* with the value of NaN.

Once constructed, *Decimal* objects are immutable.

버전 2.6에서 변경: leading and trailing whitespace characters are permitted when creating a *Decimal* instance from a string.

버전 2.7에서 변경: The argument to the constructor is now permitted to be a *float* instance.

Decimal floating point objects share many properties with the other built-in numeric types such as *float* and *int*. All of the usual math operations and special methods apply. Likewise, decimal objects can be copied, pickled, printed, used as dictionary keys, used as set elements, compared, sorted, and coerced to another type (such as *float* or *long*).

There are some small differences between arithmetic on *Decimal* objects and arithmetic on integers and floats. When the remainder operator `%` is applied to *Decimal* objects, the sign of the result is the sign of the *dividend* rather than the sign of the divisor:

```

>>> (-7) % 4
1
>>> Decimal(-7) % Decimal(4)
Decimal('-3')

```

The integer division operator `//` behaves analogously, returning the integer part of the true quotient (truncating towards zero) rather than its floor, so as to preserve the usual identity `x == (x // y) * y + x % y`:

```

>>> -7 // 4
-2
>>> Decimal(-7) // Decimal(4)
Decimal('-1')

```

The `%` and `//` operators implement the remainder and divide-integer operations (respectively) as described in the specification.

Decimal objects cannot generally be combined with floats in arithmetic operations: an attempt to add a *Decimal* to a *float*, for example, will raise a *TypeError*. There's one exception to this rule: it's possible to use Python's comparison operators to compare a *float* instance *x* with a *Decimal* instance *y*. Without this exception, comparisons between *Decimal* and *float* instances would follow the general rules for comparing objects of different types described in the expressions section of the reference manual, leading to confusing results.

버전 2.7에서 변경: A comparison between a *float* instance *x* and a *Decimal* instance *y* now returns a result based on the values of *x* and *y*. In earlier versions *x* < *y* returned the same (arbitrary) result for any *Decimal* instance *x* and any *float* instance *y*.

In addition to the standard numeric properties, decimal floating point objects also have a number of specialized methods:

adjusted()

Return the adjusted exponent after shifting out the coefficient's rightmost digits until only the lead digit remains: `Decimal('321e+5').adjusted()` returns seven. Used for determining the position of the most significant digit with respect to the decimal point.

as_tuple()

Return a *named tuple* representation of the number: `DecimalTuple(sign, digits, exponent)`.

버전 2.6에서 변경: Use a named tuple.

canonical()

Return the canonical encoding of the argument. Currently, the encoding of a *Decimal* instance is always canonical, so this operation returns its argument unchanged.

버전 2.6에 추가.

compare(other[, context])

Compare the values of two Decimal instances. This operation behaves in the same way as the usual comparison method `__cmp__()`, except that `compare()` returns a Decimal instance rather than an integer, and if either operand is a NaN then the result is a NaN:

```
a or b is a NaN ==> Decimal('NaN')
a < b           ==> Decimal('-1')
a == b          ==> Decimal('0')
a > b           ==> Decimal('1')
```

compare_signal(other[, context])

This operation is identical to the `compare()` method, except that all NaNs signal. That is, if neither operand is a signaling NaN then any quiet NaN operand is treated as though it were a signaling NaN.

버전 2.6에 추가.

compare_total(other)

Compare two operands using their abstract representation rather than their numerical value. Similar to the `compare()` method, but the result gives a total ordering on *Decimal* instances. Two *Decimal* instances with the same numeric value but different representations compare unequal in this ordering:

```
>>> Decimal('12.0').compare_total(Decimal('12'))
Decimal('-1')
```

Quiet and signaling NaNs are also included in the total ordering. The result of this function is `Decimal('0')` if both operands have the same representation, `Decimal('-1')` if the first operand is lower in the total order than the second, and `Decimal('1')` if the first operand is higher in the total order than the second operand. See the specification for details of the total order.

버전 2.6에 추가.

compare_total_mag (*other*)

Compare two operands using their abstract representation rather than their value as in `compare_total()`, but ignoring the sign of each operand. `x.compare_total_mag(y)` is equivalent to `x.copy_abs().compare_total(y.copy_abs())`.

버전 2.6에 추가.

conjugate ()

Just returns self, this method is only to comply with the Decimal Specification.

버전 2.6에 추가.

copy_abs ()

Return the absolute value of the argument. This operation is unaffected by the context and is quiet: no flags are changed and no rounding is performed.

버전 2.6에 추가.

copy_negate ()

Return the negation of the argument. This operation is unaffected by the context and is quiet: no flags are changed and no rounding is performed.

버전 2.6에 추가.

copy_sign (*other*)

Return a copy of the first operand with the sign set to be the same as the sign of the second operand. For example:

```
>>> Decimal('2.3').copy_sign(Decimal('-1.5'))
Decimal('-2.3')
```

This operation is unaffected by the context and is quiet: no flags are changed and no rounding is performed.

버전 2.6에 추가.

exp ([*context*])

Return the value of the (natural) exponential function e^{**x} at the given number. The result is correctly rounded using the ROUND_HALF_EVEN rounding mode.

```
>>> Decimal(1).exp()
Decimal('2.718281828459045235360287471')
>>> Decimal(321).exp()
Decimal('2.561702493119680037517373933E+139')
```

버전 2.6에 추가.

from_float (*f*)

Classmethod that converts a float to a decimal number, exactly.

Note `Decimal.from_float(0.1)` is not the same as `Decimal(0.1)`. Since 0.1 is not exactly representable in binary floating point, the value is stored as the nearest representable value which is $0x1.999999999999ap-4$. That equivalent value in decimal is $0.1000000000000000055511151231257827021181583404541015625$.

참고: From Python 2.7 onwards, a `Decimal` instance can also be constructed directly from a `float`.

```
>>> Decimal.from_float(0.1)
Decimal('0.1000000000000000055511151231257827021181583404541015625')
>>> Decimal.from_float(float('nan'))
Decimal('NaN')
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> Decimal.from_float(float('inf'))
Decimal('Infinity')
>>> Decimal.from_float(float('-inf'))
Decimal('-Infinity')
```

버전 2.7에 추가.

fma (other, third[, context])

Fused multiply-add. Return `self*other+third` with no rounding of the intermediate product `self*other`.

```
>>> Decimal(2).fma(3, 5)
Decimal('11')
```

버전 2.6에 추가.

is_canonical ()

Return *True* if the argument is canonical and *False* otherwise. Currently, a *Decimal* instance is always canonical, so this operation always returns *True*.

버전 2.6에 추가.

is_finite ()

Return *True* if the argument is a finite number, and *False* if the argument is an infinity or a NaN.

버전 2.6에 추가.

is_infinite ()

Return *True* if the argument is either positive or negative infinity and *False* otherwise.

버전 2.6에 추가.

is_nan ()

Return *True* if the argument is a (quiet or signaling) NaN and *False* otherwise.

버전 2.6에 추가.

is_normal ()

Return *True* if the argument is a *normal* finite non-zero number with an adjusted exponent greater than or equal to *Emin*. Return *False* if the argument is zero, subnormal, infinite or a NaN. Note, the term *normal* is used here in a different sense with the *normalize* () method which is used to create canonical values.

버전 2.6에 추가.

is_qnan ()

Return *True* if the argument is a quiet NaN, and *False* otherwise.

버전 2.6에 추가.

is_signed ()

Return *True* if the argument has a negative sign and *False* otherwise. Note that zeros and NaNs can both carry signs.

버전 2.6에 추가.

is_snan ()

Return *True* if the argument is a signaling NaN and *False* otherwise.

버전 2.6에 추가.

is_subnormal ()

Return *True* if the argument is subnormal, and *False* otherwise. A number is subnormal if it is nonzero, finite, and has an adjusted exponent less than *Emin*.

버전 2.6에 추가.

is_zero()

Return *True* if the argument is a (positive or negative) zero and *False* otherwise.

버전 2.6에 추가.

ln([context])

Return the natural (base e) logarithm of the operand. The result is correctly rounded using the ROUND_HALF_EVEN rounding mode.

버전 2.6에 추가.

log10([context])

Return the base ten logarithm of the operand. The result is correctly rounded using the ROUND_HALF_EVEN rounding mode.

버전 2.6에 추가.

logb([context])

For a nonzero number, return the adjusted exponent of its operand as a *Decimal* instance. If the operand is a zero then *Decimal('-Infinity')* is returned and the *DivisionByZero* flag is raised. If the operand is an infinity then *Decimal('Infinity')* is returned.

버전 2.6에 추가.

logical_and(other[, context])

logical_and() is a logical operation which takes two *logical operands* (see *Logical operands*). The result is the digit-wise and of the two operands.

버전 2.6에 추가.

logical_invert([context])

logical_invert() is a logical operation. The result is the digit-wise inversion of the operand.

버전 2.6에 추가.

logical_or(other[, context])

logical_or() is a logical operation which takes two *logical operands* (see *Logical operands*). The result is the digit-wise or of the two operands.

버전 2.6에 추가.

logical_xor(other[, context])

logical_xor() is a logical operation which takes two *logical operands* (see *Logical operands*). The result is the digit-wise exclusive or of the two operands.

버전 2.6에 추가.

max(other[, context])

Like *max(self, other)* except that the context rounding rule is applied before returning and that NaN values are either signaled or ignored (depending on the context and whether they are signaling or quiet).

max_mag(other[, context])

Similar to the *max()* method, but the comparison is done using the absolute values of the operands.

버전 2.6에 추가.

min(other[, context])

Like *min(self, other)* except that the context rounding rule is applied before returning and that NaN values are either signaled or ignored (depending on the context and whether they are signaling or quiet).

min_mag(other[, context])

Similar to the *min()* method, but the comparison is done using the absolute values of the operands.

버전 2.6에 추가.

next_minus ([*context*])

Return the largest number representable in the given context (or in the current thread's context if no context is given) that is smaller than the given operand.

버전 2.6에 추가.

next_plus ([*context*])

Return the smallest number representable in the given context (or in the current thread's context if no context is given) that is larger than the given operand.

버전 2.6에 추가.

next_toward (*other*[, *context*])

If the two operands are unequal, return the number closest to the first operand in the direction of the second operand. If both operands are numerically equal, return a copy of the first operand with the sign set to be the same as the sign of the second operand.

버전 2.6에 추가.

normalize ([*context*])

Normalize the number by stripping the rightmost trailing zeros and converting any result equal to `Decimal('0')` to `Decimal('0e0')`. Used for producing canonical values for attributes of an equivalence class. For example, `Decimal('32.100')` and `Decimal('0.321000e+2')` both normalize to the equivalent value `Decimal('32.1')`.

number_class ([*context*])

Return a string describing the *class* of the operand. The returned value is one of the following ten strings.

- `"-Infinity"`, indicating that the operand is negative infinity.
- `"-Normal"`, indicating that the operand is a negative normal number.
- `"-Subnormal"`, indicating that the operand is negative and subnormal.
- `"-Zero"`, indicating that the operand is a negative zero.
- `"+Zero"`, indicating that the operand is a positive zero.
- `"+Subnormal"`, indicating that the operand is positive and subnormal.
- `"+Normal"`, indicating that the operand is a positive normal number.
- `"+Infinity"`, indicating that the operand is positive infinity.
- `"NaN"`, indicating that the operand is a quiet NaN (Not a Number).
- `"sNaN"`, indicating that the operand is a signaling NaN.

버전 2.6에 추가.

quantize (*exp*[, *rounding*[, *context*[, *watchexp*]]])

Return a value equal to the first operand after rounding and having the exponent of the second operand.

```
>>> Decimal('1.41421356').quantize(Decimal('1.000'))
Decimal('1.414')
```

Unlike other operations, if the length of the coefficient after the quantize operation would be greater than precision, then an *InvalidOperation* is signaled. This guarantees that, unless there is an error condition, the quantized exponent is always equal to that of the right-hand operand.

Also unlike other operations, quantize never signals Underflow, even if the result is subnormal and inexact.

If the exponent of the second operand is larger than that of the first then rounding may be necessary. In this case, the rounding mode is determined by the `rounding` argument if given, else by the given `context` argument; if neither argument is given the rounding mode of the current thread's context is used.

If `watchexp` is set (default), then an error is returned whenever the resulting exponent is greater than `Emax` or less than `Etiny`.

radix()

Return `Decimal(10)`, the radix (base) in which the `Decimal` class does all its arithmetic. Included for compatibility with the specification.

버전 2.6에 추가.

remainder_near(*other*[, *context*])

Return the remainder from dividing *self* by *other*. This differs from `self % other` in that the sign of the remainder is chosen so as to minimize its absolute value. More precisely, the return value is `self - n * other` where *n* is the integer nearest to the exact value of `self / other`, and if two integers are equally near then the even one is chosen.

If the result is zero then its sign will be the sign of *self*.

```
>>> Decimal(18).remainder_near(Decimal(10))
Decimal('-2')
>>> Decimal(25).remainder_near(Decimal(10))
Decimal('5')
>>> Decimal(35).remainder_near(Decimal(10))
Decimal('-5')
```

rotate(*other*[, *context*])

Return the result of rotating the digits of the first operand by an amount specified by the second operand. The second operand must be an integer in the range `-precision` through `precision`. The absolute value of the second operand gives the number of places to rotate. If the second operand is positive then rotation is to the left; otherwise rotation is to the right. The coefficient of the first operand is padded on the left with zeros to length `precision` if necessary. The sign and exponent of the first operand are unchanged.

버전 2.6에 추가.

same_quantum(*other*[, *context*])

Test whether *self* and *other* have the same exponent or whether both are NaN.

scaleb(*other*[, *context*])

Return the first operand with exponent adjusted by the second. Equivalently, return the first operand multiplied by `10**other`. The second operand must be an integer.

버전 2.6에 추가.

shift(*other*[, *context*])

Return the result of shifting the digits of the first operand by an amount specified by the second operand. The second operand must be an integer in the range `-precision` through `precision`. The absolute value of the second operand gives the number of places to shift. If the second operand is positive then the shift is to the left; otherwise the shift is to the right. Digits shifted into the coefficient are zeros. The sign and exponent of the first operand are unchanged.

버전 2.6에 추가.

sqrt([*context*])

Return the square root of the argument to full precision.

to_eng_string([*context*])

Convert to a string, using engineering notation if an exponent is needed.

Engineering notation has an exponent which is a multiple of 3. This can leave up to 3 digits to the left of the decimal place and may require the addition of either one or two trailing zeros.

For example, this converts `Decimal('123E+1')` to `Decimal('1.23E+3')`.

`to_integral` (`[rounding[, context]]`)

Identical to the `to_integral_value()` method. The `to_integral` name has been kept for compatibility with older versions.

`to_integral_exact` (`[rounding[, context]]`)

Round to the nearest integer, signaling *Inexact* or *Rounded* as appropriate if rounding occurs. The rounding mode is determined by the `rounding` parameter if given, else by the given `context`. If neither parameter is given then the rounding mode of the current context is used.

버전 2.6에 추가.

`to_integral_value` (`[rounding[, context]]`)

Round to the nearest integer without signaling *Inexact* or *Rounded*. If given, applies *rounding*; otherwise, uses the rounding method in either the supplied *context* or the current context.

버전 2.6에서 변경: renamed from `to_integral` to `to_integral_value`. The old name remains valid for compatibility.

Logical operands

The `logical_and()`, `logical_invert()`, `logical_or()`, and `logical_xor()` methods expect their arguments to be *logical operands*. A *logical operand* is a *Decimal* instance whose exponent and sign are both zero, and whose digits are all either 0 or 1.

9.4.3 Context objects

Contexts are environments for arithmetic operations. They govern precision, set rules for rounding, determine which signals are treated as exceptions, and limit the range for exponents.

Each thread has its own current context which is accessed or changed using the `getcontext()` and `setcontext()` functions:

`decimal.getcontext()`

Return the current context for the active thread.

`decimal.setcontext(c)`

Set the current context for the active thread to *c*.

Beginning with Python 2.5, you can also use the `with` statement and the `localcontext()` function to temporarily change the active context.

`decimal.localcontext(c)`

Return a context manager that will set the current context for the active thread to a copy of *c* on entry to the `with`-statement and restore the previous context when exiting the `with`-statement. If no context is specified, a copy of the current context is used.

버전 2.5에 추가.

For example, the following code sets the current decimal precision to 42 places, performs a calculation, and then automatically restores the previous context:

```

from decimal import localcontext

with localcontext() as ctx:
    ctx.prec = 42    # Perform a high precision calculation
    s = calculate_something()
s = +s    # Round the final result back to the default precision

with localcontext(BasicContext):    # temporarily use the BasicContext
    print Decimal(1) / Decimal(7)
    print Decimal(355) / Decimal(113)

```

New contexts can also be created using the `Context` constructor described below. In addition, the module provides three pre-made contexts:

class decimal.BasicContext

This is a standard context defined by the General Decimal Arithmetic Specification. Precision is set to nine. Rounding is set to `ROUND_HALF_UP`. All flags are cleared. All traps are enabled (treated as exceptions) except *Inexact*, *Rounded*, and *Subnormal*.

Because many of the traps are enabled, this context is useful for debugging.

class decimal.ExtendedContext

This is a standard context defined by the General Decimal Arithmetic Specification. Precision is set to nine. Rounding is set to `ROUND_HALF_EVEN`. All flags are cleared. No traps are enabled (so that exceptions are not raised during computations).

Because the traps are disabled, this context is useful for applications that prefer to have result value of NaN or Infinity instead of raising exceptions. This allows an application to complete a run in the presence of conditions that would otherwise halt the program.

class decimal.DefaultContext

This context is used by the `Context` constructor as a prototype for new contexts. Changing a field (such as precision) has the effect of changing the default for new contexts created by the `Context` constructor.

This context is most useful in multi-threaded environments. Changing one of the fields before threads are started has the effect of setting system-wide defaults. Changing the fields after threads have started is not recommended as it would require thread synchronization to prevent race conditions.

In single threaded environments, it is preferable to not use this context at all. Instead, simply create contexts explicitly as described below.

The default values are precision=28, rounding=ROUND_HALF_EVEN, and enabled traps for Overflow, Invalid-Operation, and DivisionByZero.

In addition to the three supplied contexts, new contexts can be created with the `Context` constructor.

class decimal.Context (*prec=None, rounding=None, traps=None, flags=None, Emin=None, Emax=None, capitals=1*)

Creates a new context. If a field is not specified or is *None*, the default values are copied from the *DefaultContext*. If the *flags* field is not specified or is *None*, all flags are cleared.

The *prec* field is a positive integer that sets the precision for arithmetic operations in the context.

The *rounding* option is one of:

- `ROUND_CEILING` (towards Infinity),
- `ROUND_DOWN` (towards zero),
- `ROUND_FLOOR` (towards -Infinity),
- `ROUND_HALF_DOWN` (to nearest with ties going towards zero),

- `ROUND_HALF_EVEN` (to nearest with ties going to nearest even integer),
- `ROUND_HALF_UP` (to nearest with ties going away from zero), or
- `ROUND_UP` (away from zero).
- `ROUND_05UP` (away from zero if last digit after rounding towards zero would have been 0 or 5; otherwise towards zero)

The *traps* and *flags* fields list any signals to be set. Generally, new contexts should only set traps and leave the flags clear.

The *Emin* and *Emax* fields are integers specifying the outer limits allowable for exponents.

The *capitals* field is either 0 or 1 (the default). If set to 1, exponents are printed with a capital E; otherwise, a lowercase e is used: `Decimal('6.02e+23')`.

버전 2.6에서 변경: The `ROUND_05UP` rounding mode was added.

The *Context* class defines several general purpose methods as well as a large number of methods for doing arithmetic directly in a given context. In addition, for each of the *Decimal* methods described above (with the exception of the `adjusted()` and `as_tuple()` methods) there is a corresponding *Context* method. For example, for a *Context* instance *C* and *Decimal* instance *x*, `C.exp(x)` is equivalent to `x.exp(context=C)`. Each *Context* method accepts a Python integer (an instance of *int* or *long*) anywhere that a *Decimal* instance is accepted.

clear_flags()

Resets all of the flags to 0.

copy()

Return a duplicate of the context.

copy_decimal(num)

Return a copy of the *Decimal* instance *num*.

create_decimal(num)

Creates a new *Decimal* instance from *num* but using *self* as context. Unlike the *Decimal* constructor, the context precision, rounding method, flags, and traps are applied to the conversion.

This is useful because constants are often given to a greater precision than is needed by the application. Another benefit is that rounding immediately eliminates unintended effects from digits beyond the current precision. In the following example, using unrounded inputs means that adding zero to a sum can change the result:

```
>>> getcontext().prec = 3
>>> Decimal('3.4445') + Decimal('1.0023')
Decimal('4.45')
>>> Decimal('3.4445') + Decimal(0) + Decimal('1.0023')
Decimal('4.44')
```

This method implements the to-number operation of the IBM specification. If the argument is a string, no leading or trailing whitespace is permitted.

create_decimal_from_float(f)

Creates a new *Decimal* instance from a float *f* but rounding using *self* as the context. Unlike the *Decimal.from_float()* class method, the context precision, rounding method, flags, and traps are applied to the conversion.

```
>>> context = Context(prec=5, rounding=ROUND_DOWN)
>>> context.create_decimal_from_float(math.pi)
Decimal('3.1415')
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> context = Context(prec=5, traps=[Inexact])
>>> context.create_decimal_from_float(math.pi)
Traceback (most recent call last):
...
Inexact: None
```

버전 2.7에 추가.

Etiny()

Returns a value equal to $E_{\min} - \text{prec} + 1$ which is the minimum exponent value for subnormal results. When underflow occurs, the exponent is set to *Etiny*.

Etop()

Returns a value equal to $E_{\max} - \text{prec} + 1$.

The usual approach to working with decimals is to create *Decimal* instances and then apply arithmetic operations which take place within the current context for the active thread. An alternative approach is to use context methods for calculating within a specific context. The methods are similar to those for the *Decimal* class and are only briefly recounted here.

abs(x)

Returns the absolute value of x .

add(x, y)

Return the sum of x and y .

canonical(x)

Returns the same *Decimal* object x .

compare(x, y)

Compares x and y numerically.

compare_signal(x, y)

Compares the values of the two operands numerically.

compare_total(x, y)

Compares two operands using their abstract representation.

compare_total_mag(x, y)

Compares two operands using their abstract representation, ignoring sign.

copy_abs(x)

Returns a copy of x with the sign set to 0.

copy_negate(x)

Returns a copy of x with the sign inverted.

copy_sign(x, y)

Copies the sign from y to x .

divide(x, y)

Return x divided by y .

divide_int(x, y)

Return x divided by y , truncated to an integer.

divmod(x, y)

Divides two numbers and returns the integer part of the result.

exp(x)

Returns $e^{**}x$.

fma (*x*, *y*, *z*)
Returns *x* multiplied by *y*, plus *z*.

is_canonical (*x*)
Returns `True` if *x* is canonical; otherwise returns `False`.

is_finite (*x*)
Returns `True` if *x* is finite; otherwise returns `False`.

is_infinite (*x*)
Returns `True` if *x* is infinite; otherwise returns `False`.

is_nan (*x*)
Returns `True` if *x* is a qNaN or sNaN; otherwise returns `False`.

is_normal (*x*)
Returns `True` if *x* is a normal number; otherwise returns `False`.

is_qnan (*x*)
Returns `True` if *x* is a quiet NaN; otherwise returns `False`.

is_signed (*x*)
Returns `True` if *x* is negative; otherwise returns `False`.

is_snan (*x*)
Returns `True` if *x* is a signaling NaN; otherwise returns `False`.

is_subnormal (*x*)
Returns `True` if *x* is subnormal; otherwise returns `False`.

is_zero (*x*)
Returns `True` if *x* is a zero; otherwise returns `False`.

ln (*x*)
Returns the natural (base *e*) logarithm of *x*.

log10 (*x*)
Returns the base 10 logarithm of *x*.

logb (*x*)
Returns the exponent of the magnitude of the operand's MSD.

logical_and (*x*, *y*)
Applies the logical operation *and* between each operand's digits.

logical_invert (*x*)
Invert all the digits in *x*.

logical_or (*x*, *y*)
Applies the logical operation *or* between each operand's digits.

logical_xor (*x*, *y*)
Applies the logical operation *xor* between each operand's digits.

max (*x*, *y*)
Compares two values numerically and returns the maximum.

max_mag (*x*, *y*)
Compares the values numerically with their sign ignored.

min (*x*, *y*)
Compares two values numerically and returns the minimum.

min_mag (*x*, *y*)

Compares the values numerically with their sign ignored.

minus (*x*)

Minus corresponds to the unary prefix minus operator in Python.

multiply (*x*, *y*)

Return the product of *x* and *y*.

next_minus (*x*)

Returns the largest representable number smaller than *x*.

next_plus (*x*)

Returns the smallest representable number larger than *x*.

next_toward (*x*, *y*)

Returns the number closest to *x*, in direction towards *y*.

normalize (*x*)

Reduces *x* to its simplest form.

number_class (*x*)

Returns an indication of the class of *x*.

plus (*x*)

Plus corresponds to the unary prefix plus operator in Python. This operation applies the context precision and rounding, so it is *not* an identity operation.

power (*x*, *y*[, *modulo*])

Return *x* to the power of *y*, reduced modulo *modulo* if given.

With two arguments, compute $x^{**}y$. If *x* is negative then *y* must be integral. The result will be inexact unless *y* is integral and the result is finite and can be expressed exactly in $\langle \text{precision} \rangle$ digits. The result should always be correctly rounded, using the rounding mode of the current thread's context.

With three arguments, compute $(x^{**}y) \% \text{modulo}$. For the three argument form, the following restrictions on the arguments hold:

- all three arguments must be integral
- *y* must be nonnegative
- at least one of *x* or *y* must be nonzero
- *modulo* must be nonzero and have at most $\langle \text{precision} \rangle$ digits

The value resulting from `Context.power(x, y, modulo)` is equal to the value that would be obtained by computing $(x^{**}y) \% \text{modulo}$ with unbounded precision, but is computed more efficiently. The exponent of the result is zero, regardless of the exponents of *x*, *y* and *modulo*. The result is always exact.

버전 2.6에서 변경: *y* may now be nonintegral in $x^{**}y$. Stricter requirements for the three-argument version.

quantize (*x*, *y*)

Returns a value equal to *x* (rounded), having the exponent of *y*.

radix ()

Just returns 10, as this is Decimal, :)

remainder (*x*, *y*)

Returns the remainder from integer division.

The sign of the result, if non-zero, is the same as that of the original dividend.

remainder_near (*x*, *y*)
Returns $x - y * n$, where *n* is the integer nearest the exact value of x / y (if the result is 0 then its sign will be the sign of *x*).

rotate (*x*, *y*)
Returns a rotated copy of *x*, *y* times.

same_quantum (*x*, *y*)
Returns `True` if the two operands have the same exponent.

scaleb (*x*, *y*)
Returns the first operand after adding the second value its exp.

shift (*x*, *y*)
Returns a shifted copy of *x*, *y* times.

sqrt (*x*)
Square root of a non-negative number to context precision.

subtract (*x*, *y*)
Return the difference between *x* and *y*.

to_eng_string (*x*)
Convert to a string, using engineering notation if an exponent is needed.

Engineering notation has an exponent which is a multiple of 3. This can leave up to 3 digits to the left of the decimal place and may require the addition of either one or two trailing zeros.

to_integral_exact (*x*)
Rounds to an integer.

to_sci_string (*x*)
Converts a number to a string using scientific notation.

9.4.4 Signals

Signals represent conditions that arise during computation. Each corresponds to one context flag and one context trap enabler.

The context flag is set whenever the condition is encountered. After the computation, flags may be checked for informational purposes (for instance, to determine whether a computation was exact). After checking the flags, be sure to clear all flags before starting the next computation.

If the context's trap enabler is set for the signal, then the condition causes a Python exception to be raised. For example, if the *DivisionByZero* trap is set, then a *DivisionByZero* exception is raised upon encountering the condition.

class `decimal.Clamped`

Altered an exponent to fit representation constraints.

Typically, clamping occurs when an exponent falls outside the context's *Emin* and *Emax* limits. If possible, the exponent is reduced to fit by adding zeros to the coefficient.

class `decimal.DecimalException`

Base class for other signals and a subclass of *ArithmeticError*.

class `decimal.DivisionByZero`

Signals the division of a non-infinite number by zero.

Can occur with division, modulo division, or when raising a number to a negative power. If this signal is not trapped, returns *Infinity* or *-Infinity* with the sign determined by the inputs to the calculation.

class decimal.Inexact

Indicates that rounding occurred and the result is not exact.

Signals when non-zero digits were discarded during rounding. The rounded result is returned. The signal flag or trap is used to detect when results are inexact.

class decimal.InvalidOperation

An invalid operation was performed.

Indicates that an operation was requested that does not make sense. If not trapped, returns NaN. Possible causes include:

```
Infinity - Infinity
0 * Infinity
Infinity / Infinity
x % 0
Infinity % x
x._rescale( non-integer )
sqrt(-x) and x > 0
0 ** 0
x ** (non-integer)
x ** Infinity
```

class decimal.Overflow

Numerical overflow.

Indicates the exponent is larger than *E_{max}* after rounding has occurred. If not trapped, the result depends on the rounding mode, either pulling inward to the largest representable finite number or rounding outward to *Infinity*. In either case, *Inexact* and *Rounded* are also signaled.

class decimal.Rounded

Rounding occurred though possibly no information was lost.

Signaled whenever rounding discards digits; even if those digits are zero (such as rounding 5.00 to 5.0). If not trapped, returns the result unchanged. This signal is used to detect loss of significant digits.

class decimal.Subnormal

Exponent was lower than *E_{min}* prior to rounding.

Occurs when an operation result is subnormal (the exponent is too small). If not trapped, returns the result unchanged.

class decimal.Underflow

Numerical underflow with result rounded to zero.

Occurs when a subnormal result is pushed to zero by rounding. *Inexact* and *Subnormal* are also signaled.

The following table summarizes the hierarchy of signals:

```
exceptions.ArithmeticError(exceptions.StandardError)
    DecimalException
        Clamped
        DivisionByZero(DecimalException, exceptions.ZeroDivisionError)
        Inexact
            Overflow(Inexact, Rounded)
            Underflow(Inexact, Rounded, Subnormal)
        InvalidOperation
        Rounded
        Subnormal
```

9.4.5 Floating Point Notes

Mitigating round-off error with increased precision

The use of decimal floating point eliminates decimal representation error (making it possible to represent 0.1 exactly); however, some operations can still incur round-off error when non-zero digits exceed the fixed precision.

The effects of round-off error can be amplified by the addition or subtraction of nearly offsetting quantities resulting in loss of significance. Knuth provides two instructive examples where rounded floating point arithmetic with insufficient precision causes the breakdown of the associative and distributive properties of addition:

```
# Examples from Seminumerical Algorithms, Section 4.2.2.
>>> from decimal import Decimal, getcontext
>>> getcontext().prec = 8

>>> u, v, w = Decimal(11111113), Decimal(-11111111), Decimal('7.51111111')
>>> (u + v) + w
Decimal('9.5111111')
>>> u + (v + w)
Decimal('10')
```

```
>>> u, v, w = Decimal(20000), Decimal(-6), Decimal('6.0000003')
>>> (u*v) + (u*w)
Decimal('0.01')
>>> u * (v+w)
Decimal('0.0060000')
```

The `decimal` module makes it possible to restore the identities by expanding the precision sufficiently to avoid loss of significance:

```
>>> getcontext().prec = 20
>>> u, v, w = Decimal(11111113), Decimal(-11111111), Decimal('7.51111111')
>>> (u + v) + w
Decimal('9.51111111')
>>> u + (v + w)
Decimal('9.51111111')
>>>
>>> u, v, w = Decimal(20000), Decimal(-6), Decimal('6.0000003')
>>> (u*v) + (u*w)
Decimal('0.0060000')
>>> u * (v+w)
Decimal('0.0060000')
```

Special values

The number system for the `decimal` module provides special values including NaN, sNaN, -Infinity, Infinity, and two zeros, +0 and -0.

Infinities can be constructed directly with: `Decimal('Infinity')`. Also, they can arise from dividing by zero when the `DivisionByZero` signal is not trapped. Likewise, when the `Overflow` signal is not trapped, infinity can result from rounding beyond the limits of the largest representable number.

The infinities are signed (affine) and can be used in arithmetic operations where they get treated as very large, indeterminate numbers. For instance, adding a constant to infinity gives another infinite result.

Some operations are indeterminate and return NaN, or if the `InvalidOperation` signal is trapped, raise an exception. For example, 0/0 returns NaN which means «not a number». This variety of NaN is quiet and, once created, will flow

through other computations always resulting in another NaN. This behavior can be useful for a series of computations that occasionally have missing inputs — it allows the calculation to proceed while flagging specific results as invalid.

A variant is `sNaN` which signals rather than remaining quiet after every operation. This is a useful return value when an invalid result needs to interrupt a calculation for special handling.

The behavior of Python's comparison operators can be a little surprising where a NaN is involved. A test for equality where one of the operands is a quiet or signaling NaN always returns `False` (even when doing `Decimal('NaN')==Decimal('NaN')`), while a test for inequality always returns `True`. An attempt to compare two Decimals using any of the `<`, `<=`, `>` or `>=` operators will raise the `InvalidOperation` signal if either operand is a NaN, and return `False` if this signal is not trapped. Note that the General Decimal Arithmetic specification does not specify the behavior of direct comparisons; these rules for comparisons involving a NaN were taken from the IEEE 854 standard (see Table 3 in section 5.7). To ensure strict standards-compliance, use the `compare()` and `compare-signal()` methods instead.

The signed zeros can result from calculations that underflow. They keep the sign that would have resulted if the calculation had been carried out to greater precision. Since their magnitude is zero, both positive and negative zeros are treated as equal and their sign is informational.

In addition to the two signed zeros which are distinct yet equal, there are various representations of zero with differing precisions yet equivalent in value. This takes a bit of getting used to. For an eye accustomed to normalized floating point representations, it is not immediately obvious that the following calculation returns a value equal to zero:

```
>>> 1 / Decimal('Infinity')
Decimal('0E-10000000026')
```

9.4.6 Working with threads

The `getcontext()` function accesses a different `Context` object for each thread. Having separate thread contexts means that threads may make changes (such as `getcontext().prec=10`) without interfering with other threads.

Likewise, the `setcontext()` function automatically assigns its target to the current thread.

If `setcontext()` has not been called before `getcontext()`, then `getcontext()` will automatically create a new context for use in the current thread.

The new context is copied from a prototype context called `DefaultContext`. To control the defaults so that each thread will use the same values throughout the application, directly modify the `DefaultContext` object. This should be done *before* any threads are started so that there won't be a race condition between threads calling `getcontext()`. For example:

```
# Set applicationwide defaults for all threads about to be launched
DefaultContext.prec = 12
DefaultContext.rounding = ROUND_DOWN
DefaultContext.traps = ExtendedContext.traps.copy()
DefaultContext.traps[InvalidOperation] = 1
setcontext(DefaultContext)

# Afterwards, the threads can be started
t1.start()
t2.start()
t3.start()
. . .
```

9.4.7 Recipes

Here are a few recipes that serve as utility functions and that demonstrate ways to work with the *Decimal* class:

```
def moneyfmt(value, places=2, curr='', sep=',', dp='.',
             pos='', neg='-', trailneg=''):
    """Convert Decimal to a money formatted string.

    places:  required number of places after the decimal point
    curr:    optional currency symbol before the sign (may be blank)
    sep:     optional grouping separator (comma, period, space, or blank)
    dp:      decimal point indicator (comma or period)
             only specify as blank when places is zero
    pos:     optional sign for positive numbers: '+', space or blank
    neg:     optional sign for negative numbers: '-', '(', space or blank
    trailneg: optional trailing minus indicator:  '-', ')', space or blank

    >>> d = Decimal('-1234567.8901')
    >>> moneyfmt(d, curr='$')
    '-$1,234,567.89'
    >>> moneyfmt(d, places=0, sep='.', dp='', neg='', trailneg='-')
    '1.234.568-'
    >>> moneyfmt(d, curr='$', neg='(', trailneg=')')
    '($1,234,567.89)'
    >>> moneyfmt(Decimal(123456789), sep=' ')
    '123 456 789.00'
    >>> moneyfmt(Decimal('-0.02'), neg='<', trailneg='>')
    '<0.02>'

    """
    q = Decimal(10) ** -places        # 2 places --> '0.01'
    sign, digits, exp = value.quantize(q).as_tuple()
    result = []
    digits = map(str, digits)
    build, next = result.append, digits.pop
    if sign:
        build(trailneg)
    for i in range(places):
        build(next() if digits else '0')
    build(dp)
    if not digits:
        build('0')
    i = 0
    while digits:
        build(next())
        i += 1
        if i == 3 and digits:
            i = 0
            build(sep)
    build(curr)
    build(neg if sign else pos)
    return ''.join(reversed(result))

def pi():
    """Compute Pi to the current precision.

    >>> print pi()
    3.141592653589793238462643383
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

"""
getcontext().prec += 2 # extra digits for intermediate steps
three = Decimal(3)    # substitute "three=3.0" for regular floats
lasts, t, s, n, na, d, da = 0, three, 3, 1, 0, 0, 24
while s != lasts:
    lasts = s
    n, na = n+na, na+8
    d, da = d+da, da+32
    t = (t * n) / d
    s += t
getcontext().prec -= 2
return +s              # unary plus applies the new precision

def exp(x):
    """Return e raised to the power of x.  Result type matches input type.

    >>> print exp(Decimal(1))
    2.718281828459045235360287471
    >>> print exp(Decimal(2))
    7.389056098930650227230427461
    >>> print exp(2.0)
    7.38905609893
    >>> print exp(2+0j)
    (7.38905609893+0j)

    """
    getcontext().prec += 2
    i, lasts, s, fact, num = 0, 0, 1, 1, 1
    while s != lasts:
        lasts = s
        i += 1
        fact *= i
        num *= x
        s += num / fact
    getcontext().prec -= 2
    return +s

def cos(x):
    """Return the cosine of x as measured in radians.

    >>> print cos(Decimal('0.5'))
    0.8775825618903727161162815826
    >>> print cos(0.5)
    0.87758256189
    >>> print cos(0.5+0j)
    (0.87758256189+0j)

    """
    getcontext().prec += 2
    i, lasts, s, fact, num, sign = 0, 0, 1, 1, 1, 1
    while s != lasts:
        lasts = s
        i += 2
        fact *= i * (i-1)
        num *= x * x

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

        sign *= -1
        s += num / fact * sign
    getcontext().prec -= 2
    return +s

def sin(x):
    """Return the sine of x as measured in radians.

    >>> print sin(Decimal('0.5'))
    0.4794255386042030002732879352
    >>> print sin(0.5)
    0.479425538604
    >>> print sin(0.5+0j)
    (0.479425538604+0j)

    """
    getcontext().prec += 2
    i, lasts, s, fact, num, sign = 1, 0, x, 1, x, 1
    while s != lasts:
        lasts = s
        i += 2
        fact *= i * (i-1)
        num *= x * x
        sign *= -1
        s += num / fact * sign
    getcontext().prec -= 2
    return +s

```

9.4.8 Decimal FAQ

Q. It is cumbersome to type `decimal.Decimal('1234.5')`. Is there a way to minimize typing when using the interactive interpreter?

A. Some users abbreviate the constructor to just a single letter:

```

>>> D = decimal.Decimal
>>> D('1.23') + D('3.45')
Decimal('4.68')

```

Q. In a fixed-point application with two decimal places, some inputs have many places and need to be rounded. Others are not supposed to have excess digits and need to be validated. What methods should be used?

A. The `quantize()` method rounds to a fixed number of decimal places. If the *Inexact* trap is set, it is also useful for validation:

```

>>> TWOPLACES = Decimal(10) ** -2           # same as Decimal('0.01')

```

```

>>> # Round to two places
>>> Decimal('3.214').quantize(TWOPLACES)
Decimal('3.21')

```

```

>>> # Validate that a number does not exceed two places
>>> Decimal('3.21').quantize(TWOPLACES, context=Context(traps=[Inexact]))
Decimal('3.21')

```

```
>>> Decimal('3.214').quantize(TWOPLACES, context=Context(traps=[Inexact]))
Traceback (most recent call last):
...
Inexact: None
```

Q. Once I have valid two place inputs, how do I maintain that invariant throughout an application?

A. Some operations like addition, subtraction, and multiplication by an integer will automatically preserve fixed point. Others operations, like division and non-integer multiplication, will change the number of decimal places and need to be followed-up with a `quantize()` step:

```
>>> a = Decimal('102.72')           # Initial fixed-point values
>>> b = Decimal('3.17')
>>> a + b                           # Addition preserves fixed-point
Decimal('105.89')
>>> a - b
Decimal('99.55')
>>> a * 42                          # So does integer multiplication
Decimal('4314.24')
>>> (a * b).quantize(TWOPLACES)      # Must quantize non-integer multiplication
Decimal('325.62')
>>> (b / a).quantize(TWOPLACES)      # And quantize division
Decimal('0.03')
```

In developing fixed-point applications, it is convenient to define functions to handle the `quantize()` step:

```
>>> def mul(x, y, fp=TWOPLACES):
...     return (x * y).quantize(fp)
>>> def div(x, y, fp=TWOPLACES):
...     return (x / y).quantize(fp)
```

```
>>> mul(a, b)                       # Automatically preserve fixed-point
Decimal('325.62')
>>> div(b, a)
Decimal('0.03')
```

Q. There are many ways to express the same value. The numbers 200, 200.000, 2E2, and 02E+4 all have the same value at various precisions. Is there a way to transform them to a single recognizable canonical value?

A. The `normalize()` method maps all equivalent values to a single representative:

```
>>> values = map(Decimal, '200 200.000 2E2 .02E+4'.split())
>>> [v.normalize() for v in values]
[Decimal('2E+2'), Decimal('2E+2'), Decimal('2E+2'), Decimal('2E+2')]
```

Q. Some decimal values always print with exponential notation. Is there a way to get a non-exponential representation?

A. For some values, exponential notation is the only way to express the number of significant places in the coefficient. For example, expressing 5.0E+3 as 5000 keeps the value constant but cannot show the original's two-place significance.

If an application does not care about tracking significance, it is easy to remove the exponent and trailing zeros, losing significance, but keeping the value unchanged:

```
def remove_exponent(d):
    '''Remove exponent and trailing zeros.

    >>> remove_exponent(Decimal('5E+3'))
    Decimal('5000')
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
'''
return d.quantize(Decimal(1)) if d == d.to_integral() else d.normalize()
```

Q. Is there a way to convert a regular float to a *Decimal*?

A. Yes, any binary floating point number can be exactly expressed as a *Decimal* though an exact conversion may take more precision than intuition would suggest:

```
>>> Decimal(math.pi)
Decimal('3.141592653589793115997963468544185161590576171875')
```

Q. Within a complex calculation, how can I make sure that I haven't gotten a spurious result because of insufficient precision or rounding anomalies.

A. The decimal module makes it easy to test results. A best practice is to re-run calculations using greater precision and with various rounding modes. Widely differing results indicate insufficient precision, rounding mode issues, ill-conditioned inputs, or a numerically unstable algorithm.

Q. I noticed that context precision is applied to the results of operations but not to the inputs. Is there anything to watch out for when mixing values of different precisions?

A. Yes. The principle is that all values are considered to be exact and so is the arithmetic on those values. Only the results are rounded. The advantage for inputs is that 《what you type is what you get》. A disadvantage is that the results can look odd if you forget that the inputs haven't been rounded:

```
>>> getcontext().prec = 3
>>> Decimal('3.104') + Decimal('2.104')
Decimal('5.21')
>>> Decimal('3.104') + Decimal('0.000') + Decimal('2.104')
Decimal('5.20')
```

The solution is either to increase precision or to force rounding of inputs using the unary plus operation:

```
>>> getcontext().prec = 3
>>> +Decimal('1.23456789')      # unary plus triggers rounding
Decimal('1.23')
```

Alternatively, inputs can be rounded upon creation using the *Context.create_decimal()* method:

```
>>> Context(prec=5, rounding=ROUND_DOWN).create_decimal('1.2345678')
Decimal('1.2345')
```

9.5 fractions — Rational numbers

버전 2.6에 추가.

Source code: [Lib/fractions.py](#)

The *fractions* module provides support for rational number arithmetic.

A *Fraction* instance can be constructed from a pair of integers, from another rational number, or from a string.

```
class fractions.Fraction (numerator=0, denominator=1)
class fractions.Fraction (other_fraction)
```

```
class fractions.Fraction(float)
class fractions.Fraction(decimal)
class fractions.Fraction(string)
```

The first version requires that *numerator* and *denominator* are instances of `numbers.Rational` and returns a new `Fraction` instance with value *numerator*/*denominator*. If *denominator* is 0, it raises a `ZeroDivisionError`. The second version requires that *other_fraction* is an instance of `numbers.Rational` and returns a `Fraction` instance with the same value. The next two versions accept either a `float` or a `decimal.Decimal` instance, and return a `Fraction` instance with exactly the same value. Note that due to the usual issues with binary floating-point (see `tut-fp-issues`), the argument to `Fraction(1.1)` is not exactly equal to 11/10, and so `Fraction(1.1)` does *not* return `Fraction(11, 10)` as one might expect. (But see the documentation for the `limit_denominator()` method below.) The last version of the constructor expects a string or unicode instance. The usual form for this instance is:

```
[sign] numerator ['/' denominator]
```

where the optional sign may be either `<+>` or `<->` and *numerator* and *denominator* (if present) are strings of decimal digits. In addition, any string that represents a finite value and is accepted by the `float` constructor is also accepted by the `Fraction` constructor. In either form the input string may also have leading and/or trailing whitespace. Here are some examples:

```
>>> from fractions import Fraction
>>> Fraction(16, -10)
Fraction(-8, 5)
>>> Fraction(123)
Fraction(123, 1)
>>> Fraction()
Fraction(0, 1)
>>> Fraction('3/7')
Fraction(3, 7)
>>> Fraction('-3/7 ')
Fraction(-3, 7)
>>> Fraction('1.414213 \t\n')
Fraction(1414213, 1000000)
>>> Fraction('-.125')
Fraction(-1, 8)
>>> Fraction('7e-6')
Fraction(7, 1000000)
>>> Fraction(2.25)
Fraction(9, 4)
>>> Fraction(1.1)
Fraction(2476979795053773, 2251799813685248)
>>> from decimal import Decimal
>>> Fraction(Decimal('1.1'))
Fraction(11, 10)
```

The `Fraction` class inherits from the abstract base class `numbers.Rational`, and implements all of the methods and operations from that class. `Fraction` instances are hashable, and should be treated as immutable. In addition, `Fraction` has the following methods:

버전 2.7에서 변경: The `Fraction` constructor now accepts `float` and `decimal.Decimal` instances.

from_float(*flt*)

This class method constructs a `Fraction` representing the exact value of *flt*, which must be a `float`. Beware that `Fraction.from_float(0.3)` is not the same value as `Fraction(3, 10)`.

참고: From Python 2.7 onwards, you can also construct a `Fraction` instance directly from a `float`.

from_decimal (*dec*)

This class method constructs a *Fraction* representing the exact value of *dec*, which must be a *decimal.Decimal*.

참고: From Python 2.7 onwards, you can also construct a *Fraction* instance directly from a *decimal.Decimal* instance.

limit_denominator (*max_denominator=1000000*)

Finds and returns the closest *Fraction* to self that has denominator at most *max_denominator*. This method is useful for finding rational approximations to a given floating-point number:

```
>>> from fractions import Fraction
>>> Fraction('3.1415926535897932').limit_denominator(1000)
Fraction(355, 113)
```

or for recovering a rational number that's represented as a float:

```
>>> from math import pi, cos
>>> Fraction(cos(pi/3))
Fraction(4503599627370497, 9007199254740992)
>>> Fraction(cos(pi/3)).limit_denominator()
Fraction(1, 2)
>>> Fraction(1.1).limit_denominator()
Fraction(11, 10)
```

fractions.gcd (*a*, *b*)

Return the greatest common divisor of the integers *a* and *b*. If either *a* or *b* is nonzero, then the absolute value of *gcd(a, b)* is the largest integer that divides both *a* and *b*. *gcd(a, b)* has the same sign as *b* if *b* is nonzero; otherwise it takes the sign of *a*. *gcd(0, 0)* returns 0.

더 보기:

Module *numbers* The abstract base classes making up the numeric tower.

9.6 random — Generate pseudo-random numbers

Source code: [Lib/random.py](#)

This module implements pseudo-random number generators for various distributions.

For integers, uniform selection from a range. For sequences, uniform selection of a random element, a function to generate a random permutation of a list in-place, and a function for random sampling without replacement.

On the real line, there are functions to compute uniform, normal (Gaussian), lognormal, negative exponential, gamma, and beta distributions. For generating distributions of angles, the von Mises distribution is available.

Almost all module functions depend on the basic function *random()*, which generates a random float uniformly in the semi-open range [0.0, 1.0). Python uses the Mersenne Twister as the core generator. It produces 53-bit precision floats and has a period of $2^{19937}-1$. The underlying implementation in C is both fast and threadsafe. The Mersenne Twister is one of the most extensively tested random number generators in existence. However, being completely deterministic, it is not suitable for all purposes, and is completely unsuitable for cryptographic purposes.

The functions supplied by this module are actually bound methods of a hidden instance of the *random.Random* class. You can instantiate your own instances of *Random* to get generators that don't share state. This is especially useful

for multi-threaded programs, creating a different instance of `Random` for each thread, and using the `jumpahead()` method to make it likely that the generated sequences seen by each thread don't overlap.

Class `Random` can also be subclassed if you want to use a different basic generator of your own devising: in that case, override the `random()`, `seed()`, `getstate()`, `setstate()` and `jumpahead()` methods. Optionally, a new generator can supply a `getrandbits()` method — this allows `randrange()` to produce selections over an arbitrarily large range.

버전 2.4에 추가: the `getrandbits()` method.

As an example of subclassing, the `random` module provides the `WichmannHill` class that implements an alternative generator in pure Python. The class provides a backward compatible way to reproduce results from earlier versions of Python, which used the Wichmann-Hill algorithm as the core generator. Note that this Wichmann-Hill generator can no longer be recommended: its period is too short by contemporary standards, and the sequence generated is known to fail some stringent randomness tests. See the references below for a recent variant that repairs these flaws.

버전 2.3에서 변경: MersenneTwister replaced Wichmann-Hill as the default generator.

The `random` module also provides the `SystemRandom` class which uses the system function `os.urandom()` to generate random numbers from sources provided by the operating system.

경고: The pseudo-random generators of this module should not be used for security purposes. Use `os.urandom()` or `SystemRandom` if you require a cryptographically secure pseudo-random number generator.

Bookkeeping functions:

`random.seed(a=None)`

Initialize internal state of the random number generator.

`None` or no argument seeds from current time or from an operating system specific randomness source if available (see the `os.urandom()` function for details on availability).

If `a` is not `None` or an `int` or a `long`, then `hash(a)` is used instead. Note that the hash values for some types are nondeterministic when `PYTHONHASHSEED` is enabled.

버전 2.4에서 변경: formerly, operating system resources were not used.

`random.getstate()`

Return an object capturing the current internal state of the generator. This object can be passed to `setstate()` to restore the state.

버전 2.1에 추가.

버전 2.6에서 변경: State values produced in Python 2.6 cannot be loaded into earlier versions.

`random.setstate(state)`

`state` should have been obtained from a previous call to `getstate()`, and `setstate()` restores the internal state of the generator to what it was at the time `getstate()` was called.

버전 2.1에 추가.

`random.jumpahead(n)`

Change the internal state to one different from and likely far away from the current state. `n` is a non-negative integer which is used to scramble the current state vector. This is most useful in multi-threaded programs, in conjunction with multiple instances of the `Random` class: `setstate()` or `seed()` can be used to force all instances into the same internal state, and then `jumpahead()` can be used to force the instances' states far apart.

버전 2.1에 추가.

버전 2.3에서 변경: Instead of jumping to a specific state, `n` steps ahead, `jumpahead(n)` jumps to another state likely to be separated by many steps.

`random.getrandbits(k)`

Returns a python *long* int with *k* random bits. This method is supplied with the MersenneTwister generator and some other generators may also provide it as an optional part of the API. When available, `getrandbits()` enables `randrange()` to handle arbitrarily large ranges.

버전 2.4에 추가.

Functions for integers:

`random.randrange(stop)`

`random.randrange(start, stop[, step])`

Return a randomly selected element from `range(start, stop, step)`. This is equivalent to `choice(range(start, stop, step))`, but doesn't actually build a range object.

버전 1.5.2에 추가.

`random.randint(a, b)`

Return a random integer *N* such that $a \leq N \leq b$.

Functions for sequences:

`random.choice(seq)`

Return a random element from the non-empty sequence *seq*. If *seq* is empty, raises `IndexError`.

`random.shuffle(x[, random])`

Shuffle the sequence *x* in place. The optional argument *random* is a 0-argument function returning a random float in [0.0, 1.0); by default, this is the function `random()`.

Note that for even rather small `len(x)`, the total number of permutations of *x* is larger than the period of most random number generators; this implies that most permutations of a long sequence can never be generated.

`random.sample(population, k)`

Return a *k* length list of unique elements chosen from the population sequence. Used for random sampling without replacement.

버전 2.3에 추가.

Returns a new list containing elements from the population while leaving the original population unchanged. The resulting list is in selection order so that all sub-slices will also be valid random samples. This allows raffle winners (the sample) to be partitioned into grand prize and second place winners (the subslices).

Members of the population need not be *hashable* or unique. If the population contains repeats, then each occurrence is a possible selection in the sample.

To choose a sample from a range of integers, use an `xrange()` object as an argument. This is especially fast and space efficient for sampling from a large population: `sample(xrange(10000000), 60)`.

The following functions generate specific real-valued distributions. Function parameters are named after the corresponding variables in the distribution's equation, as used in common mathematical practice; most of these equations can be found in any statistics text.

`random.random()`

Return the next random floating point number in the range [0.0, 1.0).

`random.uniform(a, b)`

Return a random floating point number *N* such that $a \leq N \leq b$ for $a \leq b$ and $b \leq N \leq a$ for $b < a$.

The end-point value *b* may or may not be included in the range depending on floating-point rounding in the equation $a + (b-a) * \text{random}()$.

`random.triangular(low, high, mode)`

Return a random floating point number *N* such that $low \leq N \leq high$ and with the specified *mode* between

those bounds. The *low* and *high* bounds default to zero and one. The *mode* argument defaults to the midpoint between the bounds, giving a symmetric distribution.

버전 2.6에 추가.

`random.betavariate(alpha, beta)`

Beta distribution. Conditions on the parameters are $\alpha > 0$ and $\beta > 0$. Returned values range between 0 and 1.

`random.expovariate(lambd)`

Exponential distribution. *lambd* is 1.0 divided by the desired mean. It should be nonzero. (The parameter would be called $\langle \lambda \rangle$, but that is a reserved word in Python.) Returned values range from 0 to positive infinity if *lambd* is positive, and from negative infinity to 0 if *lambd* is negative.

`random.gammavariate(alpha, beta)`

Gamma distribution. (*Not* the gamma function!) Conditions on the parameters are $\alpha > 0$ and $\beta > 0$.

The probability distribution function is:

$$\text{pdf}(x) = \frac{x^{(\alpha - 1)} * \text{math.exp}(-x / \beta)}{\text{math.gamma}(\alpha) * \beta^{\alpha}}$$

`random.gauss(mu, sigma)`

Gaussian distribution. *mu* is the mean, and *sigma* is the standard deviation. This is slightly faster than the `normalvariate()` function defined below.

`random.lognormvariate(mu, sigma)`

Log normal distribution. If you take the natural logarithm of this distribution, you'll get a normal distribution with mean *mu* and standard deviation *sigma*. *mu* can have any value, and *sigma* must be greater than zero.

`random.normalvariate(mu, sigma)`

Normal distribution. *mu* is the mean, and *sigma* is the standard deviation.

`random.vonmisesvariate(mu, kappa)`

mu is the mean angle, expressed in radians between 0 and 2π , and *kappa* is the concentration parameter, which must be greater than or equal to zero. If *kappa* is equal to zero, this distribution reduces to a uniform random angle over the range 0 to 2π .

`random.paretovariate(alpha)`

Pareto distribution. *alpha* is the shape parameter.

`random.weibullvariate(alpha, beta)`

Weibull distribution. *alpha* is the scale parameter and *beta* is the shape parameter.

Alternative Generators:

`class random.WichmannHill([seed])`

Class that implements the Wichmann-Hill algorithm as the core generator. Has all of the same methods as `Random` plus the `whseed()` method described below. Because this class is implemented in pure Python, it is not threadsafe and may require locks between calls. The period of the generator is 6,953,607,871,644 which is small enough to require care that two independent random sequences do not overlap.

`random.whseed([x])`

This is obsolete, supplied for bit-level compatibility with versions of Python prior to 2.1. See `seed()` for details. `whseed()` does not guarantee that distinct integer arguments yield distinct internal states, and can yield no more than about 2^{24} distinct internal states in all.

`class random.SystemRandom([seed])`

Class that uses the `os.urandom()` function for generating random numbers from sources provided by the operating system. Not available on all systems. Does not rely on software state and sequences are not reproducible.

Accordingly, the `seed()` and `jumpahead()` methods have no effect and are ignored. The `getstate()` and `setstate()` methods raise `NotImplementedError` if called.

버전 2.4에 추가.

Examples of basic usage:

```
>>> random.random()           # Random float x, 0.0 <= x < 1.0
0.37444887175646646
>>> random.uniform(1, 10)     # Random float x, 1.0 <= x < 10.0
1.1800146073117523
>>> random.randint(1, 10)     # Integer from 1 to 10, endpoints included
7
>>> random.randrange(0, 101, 2) # Even integer from 0 to 100
26
>>> random.choice('abcdefghij') # Choose a random element
'c'

>>> items = [1, 2, 3, 4, 5, 6, 7]
>>> random.shuffle(items)
>>> items
[7, 3, 2, 5, 6, 4, 1]

>>> random.sample([1, 2, 3, 4, 5], 3) # Choose 3 elements
[4, 1, 5]
```

더 보기:

M. Matsumoto and T. Nishimura, 《Mersenne Twister: A 623-dimensionally equidistributed uniform pseudorandom number generator》, ACM Transactions on Modeling and Computer Simulation Vol. 8, No. 1, January pp.3–30 1998.

Wichmann, B. A. & Hill, I. D., 《Algorithm AS 183: An efficient and portable pseudo-random number generator》, Applied Statistics 31 (1982) 188-190.

[Complementary-Multiply-with-Carry recipe](#) for a compatible alternative random number generator with a long period and comparatively simple update operations.

9.7 itertools — Functions creating iterators for efficient looping

버전 2.3에 추가.

This module implements a number of *iterator* building blocks inspired by constructs from APL, Haskell, and SML. Each has been recast in a form suitable for Python.

The module standardizes a core set of fast, memory efficient tools that are useful by themselves or in combination. Together, they form an 《iterator algebra》 making it possible to construct specialized tools succinctly and efficiently in pure Python.

For instance, SML provides a tabulation tool: `tabulate(f)` which produces a sequence `f(0), f(1), ...`. The same effect can be achieved in Python by combining `imap()` and `count()` to form `imap(f, count())`.

These tools and their built-in counterparts also work well with the high-speed functions in the *operator* module. For example, the multiplication operator can be mapped across two vectors to form an efficient dot-product: `sum(imap(operator.mul, vector1, vector2))`.

Infinite Iterators:

Iterator	Arguments	Results	Example
<code>count()</code>	start, [step]	start, start+step, start+2*step, ...	<code>count(10)</code> --> 10 11 12 13 14 ...
<code>cycle()</code>	p	p0, p1, ... plast, p0, p1, ...	<code>cycle('ABCD')</code> --> A B C D A B C D ...
<code>repeat()</code>	elem [,n]	elem, elem, elem, ... endlessly or up to n times	<code>repeat(10, 3)</code> --> 10 10 10

Iterators terminating on the shortest input sequence:

Iterator	Arguments	Results	Example
<code>chain()</code>	p, q, ...	p0, p1, ... plast, q0, q1, ...	<code>chain('ABC', 'DEF')</code> --> A B C D E F
<code>compress()</code>	data, selectors	(d[0] if s[0]), (d[1] if s[1]), ...	<code>compress('ABCDEF', [1,0,1,0,1,1])</code> --> A C E F
<code>dropwhile()</code>	pred, seq	seq[n], seq[n+1], starting when pred fails	<code>dropwhile(lambda x: x<5, [1,4,6,4,1])</code> --> 6 4 1
<code>groupby()</code>	iterable[, key-func]	sub-iterators grouped by value of keyfunc(v)	
<code>ifilter()</code>	pred, seq	elements of seq where pred(elem) is true	<code>ifilter(lambda x: x%2, range(10))</code> --> 1 3 5 7 9
<code>ifilterfalse()</code>	pred, seq	elements of seq where pred(elem) is false	<code>ifilterfalse(lambda x: x%2, range(10))</code> --> 0 2 4 6 8
<code>islice()</code>	seq, [start,] stop [, step]	elements from seq[start:stop:step]	<code>islice('ABCDEFGH', 2, None)</code> --> C D E F G
<code>imap()</code>	func, p, q, ...	func(p0, q0), func(p1, q1), ...	<code>imap(pow, (2,3,10), (5,2,3))</code> --> 32 9 1000
<code>starmap()</code>	func, seq	func(*seq[0]), func(*seq[1]), ...	<code>starmap(pow, [(2,5), (3,2), (10,3)])</code> --> 32 9 1000
<code>tee()</code>	it, n	it1, it2, ... itn splits one iterator into n	
<code>takewhile()</code>	pred, seq	seq[0], seq[1], until pred fails	<code>takewhile(lambda x: x<5, [1,4,6,4,1])</code> --> 1 4
<code>izip()</code>	p, q, ...	(p[0], q[0]), (p[1], q[1]), ...	<code>izip('ABCD', 'xy')</code> --> Ax By
<code>izip_longest()</code>	p, q, ...	(p[0], q[0]), (p[1], q[1]), ...	<code>izip_longest('ABCD', 'xy', fillvalue='-')</code> --> Ax By C- D-

Combinatoric generators:

Iterator	Arguments	Results
<code>product()</code>	<code>p, q, ... [repeat=1]</code>	cartesian product, equivalent to a nested for-loop
<code>permutations()</code>	<code>p[, r]</code>	<code>r</code> -length tuples, all possible orderings, no repeated elements
<code>combinations()</code>	<code>p, r</code>	<code>r</code> -length tuples, in sorted order, no repeated elements
<code>combinations_with_replacement()</code>	<code>p, r</code>	<code>r</code> -length tuples, in sorted order, with repeated elements
<code>product('ABCD', repeat=2)</code>		AA AB AC AD BA BB BC BD CA CB CC CD DA DB DC DD
<code>permutations('ABCD', 2)</code>		AB AC AD BA BC BD CA CB CD DA DB DC
<code>combinations('ABCD', 2)</code>		AB AC AD BC BD CD
<code>combinations_with_replacement('ABCD', 2)</code>		AA AB AC AD BB BC BD CC CD DD

9.7.1 Itertool functions

The following module functions all construct and return iterators. Some provide streams of infinite length, so they should only be accessed by functions or loops that truncate the stream.

`itertools.chain(*iterables)`

Make an iterator that returns elements from the first iterable until it is exhausted, then proceeds to the next iterable, until all of the iterables are exhausted. Used for treating consecutive sequences as a single sequence. Roughly equivalent to:

```
def chain(*iterables):
    # chain('ABC', 'DEF') --> A B C D E F
    for it in iterables:
        for element in it:
            yield element
```

`classmethod chain.from_iterable(iterable)`

Alternate constructor for `chain()`. Gets chained inputs from a single iterable argument that is evaluated lazily. Roughly equivalent to:

```
def from_iterable(iterables):
    # chain.from_iterable(['ABC', 'DEF']) --> A B C D E F
    for it in iterables:
        for element in it:
            yield element
```

버전 2.6에 추가.

`itertools.combinations(iterable, r)`

Return `r` length subsequences of elements from the input *iterable*.

Combinations are emitted in lexicographic sort order. So, if the input *iterable* is sorted, the combination tuples will be produced in sorted order.

Elements are treated as unique based on their position, not on their value. So if the input elements are unique, there will be no repeat values in each combination.

Roughly equivalent to:

```
def combinations(iterable, r):
    # combinations('ABCD', 2) --> AB AC AD BC BD CD
    # combinations(range(4), 3) --> 012 013 023 123
    pool = tuple(iterable)
    n = len(pool)
    if r > n:
        return
    indices = range(r)
    yield tuple(pool[i] for i in indices)
    while True:
        for i in reversed(range(r)):
            if indices[i] != i + n - r:
                break
        else:
            return
        indices[i] += 1
        for j in range(i+1, r):
            indices[j] = indices[j-1] + 1
        yield tuple(pool[i] for i in indices)
```

The code for `combinations()` can be also expressed as a subsequence of `permutations()` after filtering entries where the elements are not in sorted order (according to their position in the input pool):

```
def combinations(iterable, r):
    pool = tuple(iterable)
    n = len(pool)
    for indices in permutations(range(n), r):
        if sorted(indices) == list(indices):
            yield tuple(pool[i] for i in indices)
```

The number of items returned is $n! / r! / (n-r)!$ when $0 \leq r \leq n$ or zero when $r > n$.

버전 2.6에 추가.

`itertools.combinations_with_replacement(iterable, r)`

Return r length subsequences of elements from the input *iterable* allowing individual elements to be repeated more than once.

Combinations are emitted in lexicographic sort order. So, if the input *iterable* is sorted, the combination tuples will be produced in sorted order.

Elements are treated as unique based on their position, not on their value. So if the input elements are unique, the generated combinations will also be unique.

Roughly equivalent to:

```
def combinations_with_replacement(iterable, r):
    # combinations_with_replacement('ABC', 2) --> AA AB AC BB BC CC
    pool = tuple(iterable)
    n = len(pool)
    if not n and r:
        return
    indices = [0] * r
    yield tuple(pool[i] for i in indices)
    while True:
        for i in reversed(range(r)):
            if indices[i] != n - 1:
                break
        else:
            return
        indices[i] += 1
        yield tuple(pool[i] for i in indices)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    return
    indices[i:] = [indices[i] + 1] * (r - i)
    yield tuple(pool[i] for i in indices)

```

The code for `combinations_with_replacement()` can be also expressed as a subsequence of `product()` after filtering entries where the elements are not in sorted order (according to their position in the input pool):

```

def combinations_with_replacement(iterable, r):
    pool = tuple(iterable)
    n = len(pool)
    for indices in product(range(n), repeat=r):
        if sorted(indices) == list(indices):
            yield tuple(pool[i] for i in indices)

```

The number of items returned is $(n+r-1)! / r! / (n-1)!$ when $n > 0$.

버전 2.7에 추가.

`itertools.compress(data, selectors)`

Make an iterator that filters elements from *data* returning only those that have a corresponding element in *selectors* that evaluates to True. Stops when either the *data* or *selectors* iterables has been exhausted. Roughly equivalent to:

```

def compress(data, selectors):
    # compress('ABCDEF', [1,0,1,0,1,1]) --> A C E F
    return (d for d, s in izip(data, selectors) if s)

```

버전 2.7에 추가.

`itertools.count(start=0, step=1)`

Make an iterator that returns evenly spaced values starting with *n*. Often used as an argument to `imap()` to generate consecutive data points. Also, used with `izip()` to add sequence numbers. Equivalent to:

```

def count(start=0, step=1):
    # count(10) --> 10 11 12 13 14 ...
    # count(2.5, 0.5) -> 2.5 3.0 3.5 ...
    n = start
    while True:
        yield n
        n += step

```

When counting with floating point numbers, better accuracy can sometimes be achieved by substituting multiplicative code such as: `(start + step * i for i in count())`.

버전 2.7에서 변경: added *step* argument and allowed non-integer arguments.

`itertools.cycle(iterable)`

Make an iterator returning elements from the iterable and saving a copy of each. When the iterable is exhausted, return elements from the saved copy. Repeats indefinitely. Roughly equivalent to:

```

def cycle(iterable):
    # cycle('ABCD') --> A B C D A B C D A B C D ...
    saved = []
    for element in iterable:
        yield element
        saved.append(element)

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

while saved:
    for element in saved:
        yield element

```

Note, this member of the toolkit may require significant auxiliary storage (depending on the length of the iterable).

`itertools.dropwhile` (*predicate, iterable*)

Make an iterator that drops elements from the iterable as long as the predicate is true; afterwards, returns every element. Note, the iterator does not produce *any* output until the predicate first becomes false, so it may have a lengthy start-up time. Roughly equivalent to:

```

def dropwhile(predicate, iterable):
    # dropwhile(lambda x: x<5, [1,4,6,4,1]) --> 6 4 1
    iterable = iter(iterable)
    for x in iterable:
        if not predicate(x):
            yield x
            break
    for x in iterable:
        yield x

```

`itertools.groupby` (*iterable*[, *key*])

Make an iterator that returns consecutive keys and groups from the *iterable*. The *key* is a function computing a key value for each element. If not specified or is `None`, *key* defaults to an identity function and returns the element unchanged. Generally, the iterable needs to already be sorted on the same key function.

The operation of `groupby()` is similar to the `uniq` filter in Unix. It generates a break or new group every time the value of the key function changes (which is why it is usually necessary to have sorted the data using the same key function). That behavior differs from SQL's GROUP BY which aggregates common elements regardless of their input order.

The returned group is itself an iterator that shares the underlying iterable with `groupby()`. Because the source is shared, when the `groupby()` object is advanced, the previous group is no longer visible. So, if that data is needed later, it should be stored as a list:

```

groups = []
uniquekeys = []
data = sorted(data, key=keyfunc)
for k, g in groupby(data, keyfunc):
    groups.append(list(g))      # Store group iterator as a list
    uniquekeys.append(k)

```

`groupby()` is roughly equivalent to:

```

class groupby(object):
    # [k for k, g in groupby('AAAABBBCCDAABBB')] --> A B C D A B
    # [list(g) for k, g in groupby('AAAABBBCCD')] --> AAAA BBB CC D
    def __init__(self, iterable, key=None):
        if key is None:
            key = lambda x: x
        self.keyfunc = key
        self.it = iter(iterable)
        self.tgtkey = self.currkey = self.currvalue = object()
    def __iter__(self):
        return self
    def next(self):

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

while self.currkey == self.tgtkey:
    self.currvalue = next(self.it)    # Exit on StopIteration
    self.currkey = self.keyfunc(self.currvalue)
    self.tgtkey = self.currkey
return (self.currkey, self._grouper(self.tgtkey))
def _grouper(self, tgtkey):
    while self.currkey == tgtkey:
        yield self.currvalue
        self.currvalue = next(self.it)    # Exit on StopIteration
        self.currkey = self.keyfunc(self.currvalue)

```

버전 2.4에 추가.

`itertools.ifilter` (*predicate, iterable*)

Make an iterator that filters elements from *iterable* returning only those for which the *predicate* is True. If *predicate* is None, return the items that are true. Roughly equivalent to:

```

def ifilter(predicate, iterable):
    # ifilter(lambda x: x%2, range(10)) --> 1 3 5 7 9
    if predicate is None:
        predicate = bool
    for x in iterable:
        if predicate(x):
            yield x

```

`itertools.ifilterfalse` (*predicate, iterable*)

Make an iterator that filters elements from *iterable* returning only those for which the *predicate* is False. If *predicate* is None, return the items that are false. Roughly equivalent to:

```

def ifilterfalse(predicate, iterable):
    # ifilterfalse(lambda x: x%2, range(10)) --> 0 2 4 6 8
    if predicate is None:
        predicate = bool
    for x in iterable:
        if not predicate(x):
            yield x

```

`itertools.imap` (*function, *iterables*)

Make an iterator that computes the function using arguments from each of the iterables. If *function* is set to None, then *imap()* returns the arguments as a tuple. Like *map()* but stops when the shortest iterable is exhausted instead of filling in None for shorter iterables. The reason for the difference is that infinite iterator arguments are typically an error for *map()* (because the output is fully evaluated) but represent a common and useful way of supplying arguments to *imap()*. Roughly equivalent to:

```

def imap(function, *iterables):
    # imap(pow, (2,3,10), (5,2,3)) --> 32 9 1000
    iterables = map(iter, iterables)
    while True:
        args = [next(it) for it in iterables]
        if function is None:
            yield tuple(args)
        else:
            yield function(*args)

```

`itertools.islice` (*iterable, stop*)

`itertools.islice` (*iterable, start, stop[, step]*)

Make an iterator that returns selected elements from the iterable. If *start* is non-zero, then elements from the iterable

are skipped until start is reached. Afterward, elements are returned consecutively unless *step* is set higher than one which results in items being skipped. If *stop* is None, then iteration continues until the iterator is exhausted, if at all; otherwise, it stops at the specified position. Unlike regular slicing, *islice()* does not support negative values for *start*, *stop*, or *step*. Can be used to extract related fields from data where the internal structure has been flattened (for example, a multi-line report may list a name field on every third line). Roughly equivalent to:

```
def islice(iterable, *args):
    # islice('ABCDEFGH', 2) --> A B
    # islice('ABCDEFGH', 2, 4) --> C D
    # islice('ABCDEFGH', 2, None) --> C D E F G
    # islice('ABCDEFGH', 0, None, 2) --> A C E G
    s = slice(*args)
    start, stop, step = s.start or 0, s.stop or sys.maxint, s.step or 1
    it = iter(xrange(start, stop, step))
    try:
        nexti = next(it)
    except StopIteration:
        # Consume *iterable* up to the *start* position.
        for i, element in izip(xrange(start), iterable):
            pass
        return
    try:
        for i, element in enumerate(iterable):
            if i == nexti:
                yield element
                nexti = next(it)
    except StopIteration:
        # Consume to *stop*.
        for i, element in izip(xrange(i + 1, stop), iterable):
            pass
```

If *start* is None, then iteration starts at zero. If *step* is None, then the step defaults to one.

버전 2.5에서 변경: accept None values for default *start* and *step*.

`itertools.izip(*iterables)`

Make an iterator that aggregates elements from each of the iterables. Like *zip()* except that it returns an iterator instead of a list. Used for lock-step iteration over several iterables at a time. Roughly equivalent to:

```
def izip(*iterables):
    # izip('ABCD', 'xy') --> Ax By
    iterators = map(iter, iterables)
    while iterators:
        yield tuple(map(next, iterators))
```

버전 2.4에서 변경: When no iterables are specified, returns a zero length iterator instead of raising a *TypeError* exception.

The left-to-right evaluation order of the iterables is guaranteed. This makes possible an idiom for clustering a data series into n-length groups using *izip(*[iter(s)]*n)*.

izip() should only be used with unequal length inputs when you don't care about trailing, unmatched values from the longer iterables. If those values are important, use *izip_longest()* instead.

`itertools.izip_longest(*iterables[, fillvalue])`

Make an iterator that aggregates elements from each of the iterables. If the iterables are of uneven length, missing values are filled-in with *fillvalue*. Iteration continues until the longest iterable is exhausted. Roughly equivalent to:


```

class ZipExhausted(Exception):
    pass

def izip_longest(*args, **kwargs):
    # izip_longest('ABCD', 'xy', fillvalue='-') --> Ax By C- D-
    fillvalue = kwargs.get('fillvalue')
    counter = [len(args) - 1]
    def sentinel():
        if not counter[0]:
            raise ZipExhausted
        counter[0] -= 1
        yield fillvalue
    fillers = repeat(fillvalue)
    iterators = [chain(it, sentinel(), fillers) for it in args]
    try:
        while iterators:
            yield tuple(map(next, iterators))
    except ZipExhausted:
        pass

```

If one of the iterables is potentially infinite, then the `izip_longest()` function should be wrapped with something that limits the number of calls (for example `islice()` or `takewhile()`). If not specified, `fillvalue` defaults to `None`.

버전 2.6에 추가.

`itertools.permutations(iterable[, r])`

Return successive *r* length permutations of elements in the *iterable*.

If *r* is not specified or is `None`, then *r* defaults to the length of the *iterable* and all possible full-length permutations are generated.

Permutations are emitted in lexicographic sort order. So, if the input *iterable* is sorted, the permutation tuples will be produced in sorted order.

Elements are treated as unique based on their position, not on their value. So if the input elements are unique, there will be no repeat values in each permutation.

Roughly equivalent to:

```

def permutations(iterable, r=None):
    # permutations('ABCD', 2) --> AB AC AD BA BC BD CA CB CD DA DB DC
    # permutations(range(3)) --> 012 021 102 120 201 210
    pool = tuple(iterable)
    n = len(pool)
    r = n if r is None else r
    if r > n:
        return
    indices = range(n)
    cycles = range(n, n-r, -1)
    yield tuple(pool[i] for i in indices[:r])
    while n:
        for i in reversed(range(r)):
            cycles[i] -= 1
            if cycles[i] == 0:
                indices[i:] = indices[i+1:] + indices[i:i+1]
                cycles[i] = n - i
            else:
                j = cycles[i]

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

        indices[i], indices[-j] = indices[-j], indices[i]
        yield tuple(pool[i] for i in indices[:r])
        break
    else:
        return

```

The code for `permutations()` can be also expressed as a subsequence of `product()`, filtered to exclude entries with repeated elements (those from the same position in the input pool):

```

def permutations(iterable, r=None):
    pool = tuple(iterable)
    n = len(pool)
    r = n if r is None else r
    for indices in product(range(n), repeat=r):
        if len(set(indices)) == r:
            yield tuple(pool[i] for i in indices)

```

The number of items returned is $n! / (n-r)!$ when $0 \leq r \leq n$ or zero when $r > n$.

버전 2.6에 추가.

`itertools.product(*iterables[, repeat])`
 Cartesian product of input iterables.

Roughly equivalent to nested for-loops in a generator expression. For example, `product(A, B)` returns the same as `((x,y) for x in A for y in B)`.

The nested loops cycle like an odometer with the rightmost element advancing on every iteration. This pattern creates a lexicographic ordering so that if the input's iterables are sorted, the product tuples are emitted in sorted order.

To compute the product of an iterable with itself, specify the number of repetitions with the optional `repeat` keyword argument. For example, `product(A, repeat=4)` means the same as `product(A, A, A, A)`.

This function is roughly equivalent to the following code, except that the actual implementation does not build up intermediate results in memory:

```

def product(*args, **kwargs):
    # product('ABCD', 'xy') --> Ax Ay Bx By Cx Cy Dx Dy
    # product(range(2), repeat=3) --> 000 001 010 011 100 101 110 111
    pools = map(tuple, args) * kwargs.get('repeat', 1)
    result = [[]]
    for pool in pools:
        result = [x+[y] for x in result for y in pool]
    for prod in result:
        yield tuple(prod)

```

버전 2.6에 추가.

`itertools.repeat(object[, times])`

Make an iterator that returns `object` over and over again. Runs indefinitely unless the `times` argument is specified. Used as argument to `imap()` for invariant function parameters. Also used with `izip()` to create constant fields in a tuple record. Roughly equivalent to:

```

def repeat(object, times=None):
    # repeat(10, 3) --> 10 10 10
    if times is None:
        while True:

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

        yield object
    else:
        for i in xrange(times):
            yield object

```

A common use for *repeat* is to supply a stream of constant values to *imap* or *zip*:

```

>>> list(imap(pow, xrange(10), repeat(2)))
[0, 1, 4, 9, 16, 25, 36, 49, 64, 81]

```

`itertools.starmap` (*function, iterable*)

Make an iterator that computes the function using arguments obtained from the iterable. Used instead of *imap*() when argument parameters are already grouped in tuples from a single iterable (the data has been 《pre-zipped》). The difference between *imap*() and *starmap*() parallels the distinction between `function(a,b)` and `function(*c)`. Roughly equivalent to:

```

def starmap(function, iterable):
    # starmap(pow, [(2,5), (3,2), (10,3)]) --> 32 9 1000
    for args in iterable:
        yield function(*args)

```

버전 2.6에서 변경: Previously, *starmap*() required the function arguments to be tuples. Now, any iterable is allowed.

`itertools.takewhile` (*predicate, iterable*)

Make an iterator that returns elements from the iterable as long as the predicate is true. Roughly equivalent to:

```

def takewhile(predicate, iterable):
    # takewhile(lambda x: x<5, [1,4,6,4,1]) --> 1 4
    for x in iterable:
        if predicate(x):
            yield x
        else:
            break

```

`itertools.tee` (*iterable*[, *n*=2])

Return *n* independent iterators from a single iterable. Roughly equivalent to:

```

def tee(iterable, n=2):
    it = iter(iterable)
    deques = [collections.deque() for i in range(n)]
    def gen(mydeque):
        while True:
            if not mydeque:
                # when the local deque is empty
                newval = next(it)
                # fetch a new value and
                for d in deques:
                    # load it to all the deques
                    d.append(newval)
            yield mydeque.popleft()
    return tuple(gen(d) for d in deques)

```

Once *tee*() has made a split, the original *iterable* should not be used anywhere else; otherwise, the *iterable* could get advanced without the tee objects being informed.

tee iterators are not threadsafe. A *RuntimeError* may be raised when using simultaneously iterators returned by the same *tee*() call, even if the original *iterable* is threadsafe.

This *itertool* may require significant auxiliary storage (depending on how much temporary data needs to be stored).

In general, if one iterator uses most or all of the data before another iterator starts, it is faster to use `list()` instead of `tee()`.

버전 2.4에 추가.

9.7.2 Recipes

This section shows recipes for creating an extended toolset using the existing `itertools` as building blocks.

The extended tools offer the same high performance as the underlying toolset. The superior memory performance is kept by processing elements one at a time rather than bringing the whole iterable into memory all at once. Code volume is kept small by linking the tools together in a functional style which helps eliminate temporary variables. High speed is retained by preferring 《vectorized》 building blocks over the use of `for`-loops and *generators* which incur interpreter overhead.

```
def take(n, iterable):
    "Return first n items of the iterable as a list"
    return list(islice(iterable, n))

def tabulate(function, start=0):
    "Return function(0), function(1), ..."
    return imap(function, count(start))

def consume(iterator, n=None):
    "Advance the iterator n-steps ahead. If n is None, consume entirely."
    # Use functions that consume iterators at C speed.
    if n is None:
        # feed the entire iterator into a zero-length deque
        collections.deque(iterator, maxlen=0)
    else:
        # advance to the empty slice starting at position n
        next(islice(iterator, n, n), None)

def nth(iterable, n, default=None):
    "Returns the nth item or a default value"
    return next(islice(iterable, n, None), default)

def all_equal(iterable):
    "Returns True if all the elements are equal to each other"
    g = groupby(iterable)
    return next(g, True) and not next(g, False)

def quantify(iterable, pred=bool):
    "Count how many times the predicate is true"
    return sum(imap(pred, iterable))

def padnone(iterable):
    """Returns the sequence elements and then returns None indefinitely.

    Useful for emulating the behavior of the built-in map() function.
    """
    return chain(iterable, repeat(None))

def ncycles(iterable, n):
    "Returns the sequence elements n times"
    return chain.from_iterable(repeat(tuple(iterable), n))

def dotproduct(vec1, vec2):
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    return sum(imap(operator.mul, vec1, vec2))

def flatten(listOfLists):
    "Flatten one level of nesting"
    return chain.from_iterable(listOfLists)

def repeatfunc(func, times=None, *args):
    """Repeat calls to func with specified arguments.

    Example:  repeatfunc(random.random)
    """
    if times is None:
        return starmap(func, repeat(args))
    return starmap(func, repeat(args, times))

def pairwise(iterable):
    "s -> (s0,s1), (s1,s2), (s2, s3), ..."
    a, b = tee(iterable)
    next(b, None)
    return izip(a, b)

def grouper(iterable, n, fillvalue=None):
    "Collect data into fixed-length chunks or blocks"
    # grouper('ABCDEFG', 3, 'x') --> ABC DEF Gxx
    args = [iter(iterable)] * n
    return izip_longest(fillvalue=fillvalue, *args)

def roundrobin(*iterables):
    "roundrobin('ABC', 'D', 'EF') --> A D E B F C"
    # Recipe credited to George Sakkis
    pending = len(iterables)
    nexts = cycle(iter(it).next for it in iterables)
    while pending:
        try:
            for next in nexts:
                yield next()
        except StopIteration:
            pending -= 1
            nexts = cycle(islice(nexts, pending))

def powerset(iterable):
    "powerset([1,2,3]) --> () (1,) (2,) (3,) (1,2) (1,3) (2,3) (1,2,3)"
    s = list(iterable)
    return chain.from_iterable(combinations(s, r) for r in range(len(s)+1))

def unique_everseen(iterable, key=None):
    "List unique elements, preserving order. Remember all elements ever seen."
    # unique_everseen('AAAABBBCCDAABBB') --> A B C D
    # unique_everseen('ABBCcAD', str.lower) --> A B C D
    seen = set()
    seen_add = seen.add
    if key is None:
        for element in ifilterfalse(seen.__contains__, iterable):
            seen_add(element)
            yield element
    else:

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    for element in iterable:
        k = key(element)
        if k not in seen:
            seen_add(k)
            yield element

def unique_justseen(iterable, key=None):
    """List unique elements, preserving order. Remember only the element just seen.
    # unique_justseen('AAAABBBCCDAABBB') --> A B C D A B
    # unique_justseen('ABBCCAD', str.lower) --> A B C A D
    return imap(next, imap(itemgetter(1), groupby(iterable, key)))

def iter_except(func, exception, first=None):
    """ Call a function repeatedly until an exception is raised.

    Converts a call-until-exception interface to an iterator interface.
    Like __builtin__.iter(func, sentinel) but uses an exception instead
    of a sentinel to end the loop.

    Examples:
    bsddbiter = iter_except(db.next, bsddb.error, db.first)
    heapiter = iter_except(functools.partial(heapop, h), IndexError)
    dictiter = iter_except(d.popitem, KeyError)
    dequeiter = iter_except(d.popleft, IndexError)
    queueiter = iter_except(q.get_nowait, Queue.Empty)
    setiter = iter_except(s.pop, KeyError)

    """
    try:
        if first is not None:
            yield first()
        while 1:
            yield func()
    except exception:
        pass

def random_product(*args, **kwds):
    """Random selection from itertools.product(*args, **kwds)"""
    pools = map(tuple, args) * kwds.get('repeat', 1)
    return tuple(random.choice(pool) for pool in pools)

def random_permutation(iterable, r=None):
    """Random selection from itertools.permutations(iterable, r)"""
    pool = tuple(iterable)
    r = len(pool) if r is None else r
    return tuple(random.sample(pool, r))

def random_combination(iterable, r):
    """Random selection from itertools.combinations(iterable, r)"""
    pool = tuple(iterable)
    n = len(pool)
    indices = sorted(random.sample(xrange(n), r))
    return tuple(pool[i] for i in indices)

def random_combination_with_replacement(iterable, r):
    """Random selection from itertools.combinations_with_replacement(iterable, r)"""

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

pool = tuple(iterable)
n = len(pool)
indices = sorted(random.randrange(n) for i in xrange(r))
return tuple(pool[i] for i in indices)

def tee_lookahead(t, i):
    """Inspect the i-th upcoming value from a tee object
    while leaving the tee object at its current position.

    Raise an IndexError if the underlying iterator doesn't
    have enough values.

    """
    for value in islice(t.__copy__(), i, None):
        return value
    raise IndexError(i)

```

Note, many of the above recipes can be optimized by replacing global lookups with local variables defined as default values. For example, the *dotproduct* recipe can be written as:

```

def dotproduct(vec1, vec2, sum=sum, imap=imap, mul=operator.mul):
    return sum(imap(mul, vec1, vec2))

```

9.8 functools — Higher-order functions and operations on callable objects

버전 2.5에 추가.

Source code: [Lib/functools.py](#)

The *functools* module is for higher-order functions: functions that act on or return other functions. In general, any callable object can be treated as a function for the purposes of this module.

The *functools* module defines the following functions:

`functools.cmp_to_key(func)`

Transform an old-style comparison function to a *key function*. Used with tools that accept key functions (such as `sorted()`, `min()`, `max()`, `heapq.nlargest()`, `heapq.nsmallest()`, `itertools.groupby()`). This function is primarily used as a transition tool for programs being converted to Python 3 where comparison functions are no longer supported.

A comparison function is any callable that accept two arguments, compares them, and returns a negative number for less-than, zero for equality, or a positive number for greater-than. A key function is a callable that accepts one argument and returns another value to be used as the sort key.

Example:

```
sorted(iterable, key=cmp_to_key(locale.strcoll)) # locale-aware sort order
```

For sorting examples and a brief sorting tutorial, see [sortinghowto](#).

버전 2.7에 추가.

`functools.total_ordering(cls)`

Given a class defining one or more rich comparison ordering methods, this class decorator supplies the rest. This simplifies the effort involved in specifying all of the possible rich comparison operations:

The class must define one of `__lt__()`, `__le__()`, `__gt__()`, or `__ge__()`. In addition, the class should supply an `__eq__()` method.

For example:

```
@total_ordering
class Student:
    def __eq__(self, other):
        return ((self.lastname.lower(), self.firstname.lower()) ==
                (other.lastname.lower(), other.firstname.lower()))
    def __lt__(self, other):
        return ((self.lastname.lower(), self.firstname.lower()) <
                (other.lastname.lower(), other.firstname.lower()))
```

버전 2.7에 추가.

`functools.reduce(function, iterable[, initializer])`

This is the same function as `reduce()`. It is made available in this module to allow writing code more forward-compatible with Python 3.

버전 2.6에 추가.

`functools.partial(func[, *args][, **keywords])`

Return a new *partial object* which when called will behave like *func* called with the positional arguments *args* and keyword arguments *keywords*. If more arguments are supplied to the call, they are appended to *args*. If additional keyword arguments are supplied, they extend and override *keywords*. Roughly equivalent to:

```
def partial(func, *args, **keywords):
    def newfunc(*fargs, **fkeywords):
        newkeywords = keywords.copy()
        newkeywords.update(fkeywords)
        return func(*(args + fargs), **newkeywords)
    newfunc.func = func
    newfunc.args = args
    newfunc.keywords = keywords
    return newfunc
```

The `partial()` is used for partial function application which 《freezes》 some portion of a function's arguments and/or keywords resulting in a new object with a simplified signature. For example, `partial()` can be used to create a callable that behaves like the `int()` function where the *base* argument defaults to two:

```
>>> from functools import partial
>>> basetwo = partial(int, base=2)
>>> basetwo.__doc__ = 'Convert base 2 string to an int.'
>>> basetwo('10010')
18
```

`functools.update_wrapper(wrapper, wrapped[, assigned][, updated])`

Update a *wrapper* function to look like the *wrapped* function. The optional arguments are tuples to specify which attributes of the original function are assigned directly to the matching attributes on the wrapper function and which attributes of the wrapper function are updated with the corresponding attributes from the original function. The default values for these arguments are the module level constants `WRAPPER_ASSIGNMENTS` (which assigns to the wrapper function's `__name__`, `__module__` and `__doc__`, the documentation string) and `WRAPPER_UPDATES` (which updates the wrapper function's `__dict__`, i.e. the instance dictionary).

The main intended use for this function is in *decorator* functions which wrap the decorated function and return the wrapper. If the wrapper function is not updated, the metadata of the returned function will reflect the wrapper definition rather than the original function definition, which is typically less than helpful.

`functools.wraps(wrapped[, assigned][, updated])`

This is a convenience function for invoking `update_wrapper()` as a function decorator when defining a wrapper function. It is equivalent to `partial(update_wrapper, wrapped=wrapped, assigned=assigned, updated=updated)`. For example:

```
>>> from functools import wraps
>>> def my_decorator(f):
...     @wraps(f)
...     def wrapper(*args, **kwargs):
...         print 'Calling decorated function'
...         return f(*args, **kwargs)
...     return wrapper
...
>>> @my_decorator
... def example():
...     """Docstring"""
...     print 'Called example function'
...
>>> example()
Calling decorated function
Called example function
>>> example.__name__
'example'
>>> example.__doc__
'Docstring'
```

Without the use of this decorator factory, the name of the example function would have been 'wrapper', and the docstring of the original `example()` would have been lost.

9.8.1 partial Objects

partial objects are callable objects created by `partial()`. They have three read-only attributes:

`partial.func`

A callable object or function. Calls to the *partial* object will be forwarded to *func* with new arguments and keywords.

`partial.args`

The leftmost positional arguments that will be prepended to the positional arguments provided to a *partial* object call.

`partial.keywords`

The keyword arguments that will be supplied when the *partial* object is called.

partial objects are like function objects in that they are callable, weak referencable, and can have attributes. There are some important differences. For instance, the `__name__` and `__doc__` attributes are not created automatically. Also, *partial* objects defined in classes behave like static methods and do not transform into bound methods during instance attribute look-up.

9.9 operator — Standard operators as functions

The `operator` module exports a set of efficient functions corresponding to the intrinsic operators of Python. For example, `operator.add(x, y)` is equivalent to the expression `x+y`. The function names are those used for special class methods; variants without leading and trailing `__` are also provided for convenience.

The functions fall into categories that perform object comparisons, logical operations, mathematical operations, sequence operations, and abstract type tests.

The object comparison functions are useful for all objects, and are named after the rich comparison operators they support:

```
operator.lt(a, b)
operator.le(a, b)
operator.eq(a, b)
operator.ne(a, b)
operator.ge(a, b)
operator.gt(a, b)
operator.__lt__(a, b)
operator.__le__(a, b)
operator.__eq__(a, b)
operator.__ne__(a, b)
operator.__ge__(a, b)
operator.__gt__(a, b)
```

Perform 《rich comparisons》 between *a* and *b*. Specifically, `lt(a, b)` is equivalent to `a < b`, `le(a, b)` is equivalent to `a <= b`, `eq(a, b)` is equivalent to `a == b`, `ne(a, b)` is equivalent to `a != b`, `gt(a, b)` is equivalent to `a > b` and `ge(a, b)` is equivalent to `a >= b`. Note that unlike the built-in `cmp()`, these functions can return any value, which may or may not be interpretable as a Boolean value. See comparisons for more information about rich comparisons.

버전 2.2에 추가.

The logical operations are also generally applicable to all objects, and support truth tests, identity tests, and boolean operations:

```
operator.not_(obj)
operator.__not__(obj)
```

Return the outcome of `not obj`. (Note that there is no `__not__()` method for object instances; only the interpreter core defines this operation. The result is affected by the `__nonzero__()` and `__len__()` methods.)

```
operator.truth(obj)
```

Return `True` if *obj* is true, and `False` otherwise. This is equivalent to using the `bool` constructor.

```
operator.is_(a, b)
```

Return `a is b`. Tests object identity.

버전 2.3에 추가.

```
operator.is_not(a, b)
```

Return `a is not b`. Tests object identity.

버전 2.3에 추가.

The mathematical and bitwise operations are the most numerous:

```
operator.abs(obj)
operator.__abs__(obj)
```

Return the absolute value of *obj*.

```
operator.add(a, b)
```

`operator.__add__(a, b)`
Return $a + b$, for a and b numbers.

`operator.and_(a, b)`
`operator.__and__(a, b)`
Return the bitwise and of a and b .

`operator.div(a, b)`
`operator.__div__(a, b)`
Return a / b when `__future__.division` is not in effect. This is also known as 《classic》 division.

`operator.floordiv(a, b)`
`operator.__floordiv__(a, b)`
Return $a // b$.
버전 2.2에 추가.

`operator.index(a)`
`operator.__index__(a)`
Return a converted to an integer. Equivalent to $a.__index__()$.
버전 2.5에 추가.

`operator.inv(obj)`
`operator.invert(obj)`
`operator.__inv__(obj)`
`operator.__invert__(obj)`
Return the bitwise inverse of the number obj . This is equivalent to $\sim obj$.
버전 2.0에 추가: The names `invert()` and `__invert__()`.

`operator.lshift(a, b)`
`operator.__lshift__(a, b)`
Return a shifted left by b .

`operator.mod(a, b)`
`operator.__mod__(a, b)`
Return $a \% b$.

`operator.mul(a, b)`
`operator.__mul__(a, b)`
Return $a * b$, for a and b numbers.

`operator.neg(obj)`
`operator.__neg__(obj)`
Return obj negated ($-obj$).

`operator.or_(a, b)`
`operator.__or__(a, b)`
Return the bitwise or of a and b .

`operator.pos(obj)`
`operator.__pos__(obj)`
Return obj positive ($+obj$).

`operator.pow(a, b)`
`operator.__pow__(a, b)`
Return $a ** b$, for a and b numbers.
버전 2.3에 추가.

`operator.rshift(a, b)`

`operator.__rshift__(a, b)`

Return a shifted right by b .

`operator.sub(a, b)`

`operator.__sub__(a, b)`

Return $a - b$.

`operator.truediv(a, b)`

`operator.__truediv__(a, b)`

Return a / b when `__future__.division` is in effect. This is also known as 《true》 division.

버전 2.2에 추가.

`operator.xor(a, b)`

`operator.__xor__(a, b)`

Return the bitwise exclusive or of a and b .

Operations which work with sequences (some of them with mappings too) include:

`operator.concat(a, b)`

`operator.__concat__(a, b)`

Return $a + b$ for a and b sequences.

`operator.contains(a, b)`

`operator.__contains__(a, b)`

Return the outcome of the test $b \text{ in } a$. Note the reversed operands.

버전 2.0에 추가: The name `__contains__()`.

`operator.countOf(a, b)`

Return the number of occurrences of b in a .

`operator.delitem(a, b)`

`operator.__delitem__(a, b)`

Remove the value of a at index b .

`operator.delslice(a, b, c)`

`operator.__delslice__(a, b, c)`

Delete the slice of a from index b to index $c-1$.

버전 2.6부터 폐지: This function is removed in Python 3.x. Use `delitem()` with a slice index.

`operatorgetitem(a, b)`

`operator.__getitem__(a, b)`

Return the value of a at index b .

`operator.getslice(a, b, c)`

`operator.__getitem__(a, b, c)`

Return the slice of a from index b to index $c-1$.

버전 2.6부터 폐지: This function is removed in Python 3.x. Use `getitem()` with a slice index.

`operator.indexof(a, b)`

Return the index of the first of occurrence of b in a .

`operator.repeat(a, b)`

`operator.__repeat__(a, b)`

버전 2.7부터 폐지: Use `__mul__()` instead.

Return $a * b$ where a is a sequence and b is an integer.

`operator.sequenceIncludes(...)`

버전 2.0부터 폐지: Use `contains()` instead.

Alias for `contains()`.

```
operator.setitem(a, b, c)
operator.__setitem__(a, b, c)
```

Set the value of `a` at index `b` to `c`.

```
operator.setslice(a, b, c, v)
operator.__setslice__(a, b, c, v)
```

Set the slice of `a` from index `b` to index `c-1` to the sequence `v`.

버전 2.6부터 폐지: This function is removed in Python 3.x. Use `setitem()` with a slice index.

Example use of operator functions:

```
>>> # Elementwise multiplication
>>> map(mul, [0, 1, 2, 3], [10, 20, 30, 40])
[0, 20, 60, 120]

>>> # Dot product
>>> sum(map(mul, [0, 1, 2, 3], [10, 20, 30, 40]))
200
```

Many operations have an «in-place» version. The following functions provide a more primitive access to in-place operators than the usual syntax does; for example, the *statement* `x += y` is equivalent to `x = operator.iadd(x, y)`. Another way to put it is to say that `z = operator.iadd(x, y)` is equivalent to the compound statement `z = x; z += y`.

```
operator.iadd(a, b)
operator.__iadd__(a, b)
```

`a = iadd(a, b)` is equivalent to `a += b`.

버전 2.5에 추가.

```
operator.iand(a, b)
operator.__iand__(a, b)
```

`a = iand(a, b)` is equivalent to `a &= b`.

버전 2.5에 추가.

```
operator.iconcat(a, b)
operator.__iconcat__(a, b)
```

`a = iconcat(a, b)` is equivalent to `a += b` for `a` and `b` sequences.

버전 2.5에 추가.

```
operator.idiv(a, b)
operator.__idiv__(a, b)
```

`a = idiv(a, b)` is equivalent to `a /= b` when `__future__.division` is not in effect.

버전 2.5에 추가.

```
operator.ifloordiv(a, b)
operator.__ifloordiv__(a, b)
```

`a = ifloordiv(a, b)` is equivalent to `a //= b`.

버전 2.5에 추가.

```
operator.ilshift(a, b)
operator.__ilshift__(a, b)
```

`a = ilshift(a, b)` is equivalent to `a <<= b`.

버전 2.5에 추가.

`operator.imod(a, b)`
`operator.__imod__(a, b)`
`a = imod(a, b)` is equivalent to `a %= b`.

버전 2.5에 추가.

`operator.imul(a, b)`
`operator.__imul__(a, b)`
`a = imul(a, b)` is equivalent to `a *= b`.

버전 2.5에 추가.

`operator.ior(a, b)`
`operator.__ior__(a, b)`
`a = ior(a, b)` is equivalent to `a |= b`.

버전 2.5에 추가.

`operator.ipow(a, b)`
`operator.__ipow__(a, b)`
`a = ipow(a, b)` is equivalent to `a **= b`.

버전 2.5에 추가.

`operator.irepeat(a, b)`
`operator.__irepeat__(a, b)`
버전 2.7부터 폐지: Use `__imul__()` instead.
`a = irepeat(a, b)` is equivalent to `a *= b` where *a* is a sequence and *b* is an integer.

버전 2.5에 추가.

`operator.irshift(a, b)`
`operator.__irshift__(a, b)`
`a = irshift(a, b)` is equivalent to `a >>= b`.

버전 2.5에 추가.

`operator.isub(a, b)`
`operator.__isub__(a, b)`
`a = isub(a, b)` is equivalent to `a -= b`.

버전 2.5에 추가.

`operator.itruediv(a, b)`
`operator.__itruediv__(a, b)`
`a = itrueidiv(a, b)` is equivalent to `a /= b` when `__future__.division` is in effect.

버전 2.5에 추가.

`operator.ixor(a, b)`
`operator.__ixor__(a, b)`
`a = ixor(a, b)` is equivalent to `a ^= b`.

버전 2.5에 추가.

The `operator` module also defines a few predicates to test the type of objects; however, these are not all reliable. It is preferable to test abstract base classes instead (see `collections` and `numbers` for details).

`operator.isCallable(obj)`
버전 2.0부터 폐지: Use `isinstance(x, collections.Callable)` instead.

Returns true if the object *obj* can be called like a function, otherwise it returns false. True is returned for functions, bound and unbound methods, class objects, and instance objects which support the `__call__()` method.

`operator.isMappingType(obj)`

버전 2.7부터 폐지: Use `isinstance(x, collections.Mapping)` instead.

Returns true if the object *obj* supports the mapping interface. This is true for dictionaries and all instance objects defining `__getitem__()`.

`operator.isNumberType(obj)`

버전 2.7부터 폐지: Use `isinstance(x, numbers.Number)` instead.

Returns true if the object *obj* represents a number. This is true for all numeric types implemented in C.

`operator.isSequenceType(obj)`

버전 2.7부터 폐지: Use `isinstance(x, collections.Sequence)` instead.

Returns true if the object *obj* supports the sequence protocol. This returns true for all objects which define sequence methods in C, and for all instance objects defining `__getitem__()`.

The `operator` module also defines tools for generalized attribute and item lookups. These are useful for making fast field extractors as arguments for `map()`, `sorted()`, `itertools.groupby()`, or other functions that expect a function argument.

`operator.attrgetter(attr)`

`operator.attrgetter(*attrs)`

Return a callable object that fetches *attr* from its operand. If more than one attribute is requested, returns a tuple of attributes. The attribute names can also contain dots. For example:

- After `f = attrgetter('name')`, the call `f(b)` returns `b.name`.
- After `f = attrgetter('name', 'date')`, the call `f(b)` returns `(b.name, b.date)`.
- After `f = attrgetter('name.first', 'name.last')`, the call `f(b)` returns `(b.name.first, b.name.last)`.

Equivalent to:

```
def attrgetter(*items):
    if len(items) == 1:
        attr = items[0]
        def g(obj):
            return resolve_attr(obj, attr)
    else:
        def g(obj):
            return tuple(resolve_attr(obj, attr) for attr in items)
    return g

def resolve_attr(obj, attr):
    for name in attr.split("."):
        obj = getattr(obj, name)
    return obj
```

버전 2.4에 추가.

버전 2.5에서 변경: Added support for multiple attributes.

버전 2.6에서 변경: Added support for dotted attributes.

`operator.itemgetter(item)`

`operator.itemgetter(*items)`

Return a callable object that fetches *item* from its operand using the operand's `__getitem__()` method. If multiple items are specified, returns a tuple of lookup values. For example:

- After `f = itemgetter(2)`, the call `f(r)` returns `r[2]`.

- After `g = itemgetter(2, 5, 3)`, the call `g(r)` returns `(r[2], r[5], r[3])`.

Equivalent to:

```
def itemgetter(*items):
    if len(items) == 1:
        item = items[0]
        def g(obj):
            return obj[item]
    else:
        def g(obj):
            return tuple(obj[item] for item in items)
    return g
```

The items can be any type accepted by the operand's `__getitem__()` method. Dictionaries accept any hashable value. Lists, tuples, and strings accept an index or a slice:

```
>>> itemgetter(1)('ABCDEFGH')
'B'
>>> itemgetter(1,3,5)('ABCDEFGH')
('B', 'D', 'F')
>>> itemgetter(slice(2,None))('ABCDEFGH')
'CDEFGH'
```

버전 2.4에 추가.

버전 2.5에서 변경 : Added support for multiple item extraction.

Example of using `itemgetter()` to retrieve specific fields from a tuple record:

```
>>> inventory = [('apple', 3), ('banana', 2), ('pear', 5), ('orange', 1)]
>>> getcount = itemgetter(1)
>>> map(getcount, inventory)
[3, 2, 5, 1]
>>> sorted(inventory, key=getcount)
[('orange', 1), ('banana', 2), ('apple', 3), ('pear', 5)]
```

`operator.methodcaller(name[, args...])`

Return a callable object that calls the method `name` on its operand. If additional arguments and/or keyword arguments are given, they will be given to the method as well. For example:

- After `f = methodcaller('name')`, the call `f(b)` returns `b.name()`.
- After `f = methodcaller('name', 'foo', bar=1)`, the call `f(b)` returns `b.name('foo', bar=1)`.

Equivalent to:

```
def methodcaller(name, *args, **kwargs):
    def caller(obj):
        return getattr(obj, name)(*args, **kwargs)
    return caller
```

버전 2.6에 추가.

9.9.1 Mapping Operators to Functions

This table shows how abstract operations correspond to operator symbols in the Python syntax and the functions in the `operator` module.

Operation	Syntax	Function
Addition	<code>a + b</code>	<code>add(a, b)</code>
Concatenation	<code>seq1 + seq2</code>	<code>concat(seq1, seq2)</code>
Containment Test	<code>obj in seq</code>	<code>contains(seq, obj)</code>
Division	<code>a / b</code>	<code>div(a, b)</code> (without <code>__future__.division</code>)
Division	<code>a / b</code>	<code>truediv(a, b)</code> (with <code>__future__.division</code>)
Division	<code>a // b</code>	<code>floordiv(a, b)</code>
Bitwise And	<code>a & b</code>	<code>and_(a, b)</code>
Bitwise Exclusive Or	<code>a ^ b</code>	<code>xor(a, b)</code>
Bitwise Inversion	<code>~ a</code>	<code>invert(a)</code>
Bitwise Or	<code>a b</code>	<code>or_(a, b)</code>
Exponentiation	<code>a ** b</code>	<code>pow(a, b)</code>
Identity	<code>a is b</code>	<code>is_(a, b)</code>
Identity	<code>a is not b</code>	<code>is_not(a, b)</code>
Indexed Assignment	<code>obj[k] = v</code>	<code>setitem(obj, k, v)</code>
Indexed Deletion	<code>del obj[k]</code>	<code>delitem(obj, k)</code>
Indexing	<code>obj[k]</code>	<code>getitem(obj, k)</code>
Left Shift	<code>a << b</code>	<code>lshift(a, b)</code>
Modulo	<code>a % b</code>	<code>mod(a, b)</code>
Multiplication	<code>a * b</code>	<code>mul(a, b)</code>
Negation (Arithmetic)	<code>- a</code>	<code>neg(a)</code>
Negation (Logical)	<code>not a</code>	<code>not_(a)</code>
Positive	<code>+ a</code>	<code>pos(a)</code>
Right Shift	<code>a >> b</code>	<code>rshift(a, b)</code>
Sequence Repetition	<code>seq * i</code>	<code>repeat(seq, i)</code>
Slice Assignment	<code>seq[i:j] = values</code>	<code>setitem(seq, slice(i, j), values)</code>
Slice Deletion	<code>del seq[i:j]</code>	<code>delitem(seq, slice(i, j))</code>
Slicing	<code>seq[i:j]</code>	<code>getitem(seq, slice(i, j))</code>
String Formatting	<code>s % obj</code>	<code>mod(s, obj)</code>
Subtraction	<code>a - b</code>	<code>sub(a, b)</code>
Truth Test	<code>obj</code>	<code>truth(obj)</code>
Ordering	<code>a < b</code>	<code>lt(a, b)</code>
Ordering	<code>a <= b</code>	<code>le(a, b)</code>
Equality	<code>a == b</code>	<code>eq(a, b)</code>
Difference	<code>a != b</code>	<code>ne(a, b)</code>
Ordering	<code>a >= b</code>	<code>ge(a, b)</code>
Ordering	<code>a > b</code>	<code>gt(a, b)</code>

File and Directory Access

The modules described in this chapter deal with disk files and directories. For example, there are modules for reading the properties of files, manipulating paths in a portable way, and creating temporary files. The full list of modules in this chapter is:

10.1 `os.path` — Common pathname manipulations

This module implements some useful functions on pathnames. To read or write files see `open()`, and for accessing the filesystem see the `os` module.

참고: On Windows, many of these functions do not properly support UNC pathnames. `splitunc()` and `ismount()` do handle them correctly.

Unlike a unix shell, Python does not do any *automatic* path expansions. Functions such as `expanduser()` and `expandvars()` can be invoked explicitly when an application desires shell-like path expansion. (See also the `glob` module.)

참고: Since different operating systems have different path name conventions, there are several versions of this module in the standard library. The `os.path` module is always the path module suitable for the operating system Python is running on, and therefore usable for local paths. However, you can also import and use the individual modules if you want to manipulate a path that is *always* in one of the different formats. They all have the same interface:

- `posixpath` for UNIX-style paths
 - `ntpath` for Windows paths
 - `macpath` for old-style MacOS paths
 - `os2emxpath` for OS/2 EMX paths
-

`os.path.abspath(path)`

Return a normalized absolutized version of the pathname *path*. On most platforms, this is equivalent to calling the function `normpath()` as follows: `normpath(join(os.getcwd(), path))`.

버전 1.5.2에 추가.

`os.path.basename(path)`

Return the base name of pathname *path*. This is the second element of the pair returned by passing *path* to the function `split()`. Note that the result of this function is different from the Unix **basename** program; where **basename** for `'/foo/bar/'` returns `'bar'`, the `basename()` function returns an empty string `('')`.

`os.path.commonprefix(list)`

Return the longest path prefix (taken character-by-character) that is a prefix of all paths in *list*. If *list* is empty, return the empty string `('')`. Note that this may return invalid paths because it works a character at a time.

`os.path.dirname(path)`

Return the directory name of pathname *path*. This is the first element of the pair returned by passing *path* to the function `split()`.

`os.path.exists(path)`

Return True if *path* refers to an existing path. Returns False for broken symbolic links. On some platforms, this function may return False if permission is not granted to execute `os.stat()` on the requested file, even if the *path* physically exists.

`os.path.lexists(path)`

Return True if *path* refers to an existing path. Returns True for broken symbolic links. Equivalent to `exists()` on platforms lacking `os.lstat()`.

버전 2.4에 추가.

`os.path.expanduser(path)`

On Unix and Windows, return the argument with an initial component of `~` or `~user` replaced by that *user*'s home directory.

On Unix, an initial `~` is replaced by the environment variable `HOME` if it is set; otherwise the current user's home directory is looked up in the password directory through the built-in module `pwd`. An initial `~user` is looked up directly in the password directory.

On Windows, `HOME` and `USERPROFILE` will be used if set, otherwise a combination of `HOMEPATH` and `HOMEDRIVE` will be used. An initial `~user` is handled by stripping the last directory component from the created user path derived above.

If the expansion fails or if the path does not begin with a tilde, the path is returned unchanged.

`os.path.expandvars(path)`

Return the argument with environment variables expanded. Substrings of the form `$name` or `${name}` are replaced by the value of environment variable *name*. Malformed variable names and references to non-existing variables are left unchanged.

On Windows, `%name%` expansions are supported in addition to `$name` and `${name}`.

`os.path.getatime(path)`

Return the time of last access of *path*. The return value is a number giving the number of seconds since the epoch (see the `time` module). Raise `os.error` if the file does not exist or is inaccessible.

버전 1.5.2에 추가.

버전 2.3에서 변경: If `os.stat_float_times()` returns True, the result is a floating point number.

`os.path.getmtime(path)`

Return the time of last modification of *path*. The return value is a number giving the number of seconds since the epoch (see the `time` module). Raise `os.error` if the file does not exist or is inaccessible.

버전 1.5.2에 추가.

버전 2.3에서 변경: If `os.stat_float_times()` returns `True`, the result is a floating point number.

`os.path.getctime(path)`

Return the system's ctime which, on some systems (like Unix) is the time of the last metadata change, and, on others (like Windows), is the creation time for *path*. The return value is a number giving the number of seconds since the epoch (see the `time` module). Raise `os.error` if the file does not exist or is inaccessible.

버전 2.3에 추가.

`os.path.getsize(path)`

Return the size, in bytes, of *path*. Raise `os.error` if the file does not exist or is inaccessible.

버전 1.5.2에 추가.

`os.path.isabs(path)`

Return `True` if *path* is an absolute pathname. On Unix, that means it begins with a slash, on Windows that it begins with a (back)slash after chopping off a potential drive letter.

`os.path.isfile(path)`

Return `True` if *path* is an existing regular file. This follows symbolic links, so both `islink()` and `isfile()` can be true for the same path.

`os.path.isdir(path)`

Return `True` if *path* is an existing directory. This follows symbolic links, so both `islink()` and `isdir()` can be true for the same path.

`os.path.islink(path)`

Return `True` if *path* refers to a directory entry that is a symbolic link. Always `False` if symbolic links are not supported by the Python runtime.

`os.path.ismount(path)`

Return `True` if pathname *path* is a *mount point*: a point in a file system where a different file system has been mounted. The function checks whether *path*'s parent, `path/..`, is on a different device than *path*, or whether `path/..` and *path* point to the same i-node on the same device — this should detect mount points for all Unix and POSIX variants.

`os.path.join(path, *paths)`

Join one or more path components intelligently. The return value is the concatenation of *path* and any members of **paths* with exactly one directory separator (`os.sep`) following each non-empty part except the last, meaning that the result will only end in a separator if the last part is empty. If a component is an absolute path, all previous components are thrown away and joining continues from the absolute path component.

On Windows, the drive letter is not reset when an absolute path component (e.g., `r'\foo'`) is encountered. If a component contains a drive letter, all previous components are thrown away and the drive letter is reset. Note that since there is a current directory for each drive, `os.path.join("c:", "foo")` represents a path relative to the current directory on drive C: (`c:foo`), not `c:\foo`.

`os.path.normcase(path)`

Normalize the case of a pathname. On Unix and Mac OS X, this returns the path unchanged; on case-insensitive filesystems, it converts the path to lowercase. On Windows, it also converts forward slashes to backward slashes.

`os.path.normpath(path)`

Normalize a pathname by collapsing redundant separators and up-level references so that `A//B`, `A/B/`, `A/./B` and `A/foo/.. /B` all become `A/B`. This string manipulation may change the meaning of a path that contains symbolic links. On Windows, it converts forward slashes to backward slashes. To normalize case, use `normcase()`.

`os.path.realpath(path)`

Return the canonical path of the specified filename, eliminating any symbolic links encountered in the path (if they are supported by the operating system).

버전 2.2에 추가.

`os.path.relpath(path[, start])`

Return a relative filepath to *path* either from the current directory or from an optional *start* directory. This is a path computation: the filesystem is not accessed to confirm the existence or nature of *path* or *start*.

start defaults to `os.curdir`.

Availability: Windows, Unix.

버전 2.6에 추가.

`os.path.samefile(path1, path2)`

Return True if both pathname arguments refer to the same file or directory (as indicated by device number and i-node number). Raise an exception if an `os.stat()` call on either pathname fails.

Availability: Unix.

`os.path.sameopenfile(fp1, fp2)`

Return True if the file descriptors *fp1* and *fp2* refer to the same file.

Availability: Unix.

`os.path.samestat(stat1, stat2)`

Return True if the stat tuples *stat1* and *stat2* refer to the same file. These structures may have been returned by `os.fstat()`, `os.lstat()`, or `os.stat()`. This function implements the underlying comparison used by `samefile()` and `sameopenfile()`.

Availability: Unix.

`os.path.split(path)`

Split the pathname *path* into a pair, (*head*, *tail*) where *tail* is the last pathname component and *head* is everything leading up to that. The *tail* part will never contain a slash; if *path* ends in a slash, *tail* will be empty. If there is no slash in *path*, *head* will be empty. If *path* is empty, both *head* and *tail* are empty. Trailing slashes are stripped from *head* unless it is the root (one or more slashes only). In all cases, `join(head, tail)` returns a path to the same location as *path* (but the strings may differ). Also see the functions `dirname()` and `basename()`.

`os.path.splitdrive(path)`

Split the pathname *path* into a pair (*drive*, *tail*) where *drive* is either a drive specification or the empty string. On systems which do not use drive specifications, *drive* will always be the empty string. In all cases, *drive* + *tail* will be the same as *path*.

버전 1.3에 추가.

`os.path.splitext(path)`

Split the pathname *path* into a pair (*root*, *ext*) such that *root* + *ext* == *path*, and *ext* is empty or begins with a period and contains at most one period. Leading periods on the basename are ignored; `splitext('.cshrc')` returns `('cshrc', '')`.

버전 2.6에서 변경: Earlier versions could produce an empty root when the only period was the first character.

`os.path.splitunc(path)`

Split the pathname *path* into a pair (*unc*, *rest*) so that *unc* is the UNC mount point (such as `r'\\host\mount'`), if present, and *rest* the rest of the path (such as `r'\path\file.ext'`). For paths containing drive letters, *unc* will always be the empty string.

Availability: Windows.

`os.path.walk(path, visit, arg)`

Calls the function *visit* with arguments (*arg*, *dirname*, *names*) for each directory in the directory tree rooted at *path* (including *path* itself, if it is a directory). The argument *dirname* specifies the visited directory, the argument *names* lists the files in the directory (gotten from `os.listdir(dirname)`). The *visit* function may

modify *names* to influence the set of directories visited below *dirname*, e.g. to avoid visiting certain parts of the tree. (The object referred to by *names* must be modified in place, using `del` or slice assignment.)

참고: Symbolic links to directories are not treated as subdirectories, and that `walk()` therefore will not visit them. To visit linked directories you must identify them with `os.path.islink(file)` and `os.path.isdir(file)`, and invoke `walk()` as necessary.

참고: This function is deprecated and has been removed in Python 3 in favor of `os.walk()`.

`os.path.supports_unicode_filenames`

True if arbitrary Unicode strings can be used as file names (within limitations imposed by the file system).

버전 2.3에 추가.

10.2 fileinput — Iterate over lines from multiple input streams

Source code: [Lib/fileinput.py](#)

This module implements a helper class and functions to quickly write a loop over standard input or a list of files. If you just want to read or write one file see `open()`.

The typical use is:

```
import fileinput
for line in fileinput.input():
    process(line)
```

This iterates over the lines of all files listed in `sys.argv[1:]`, defaulting to `sys.stdin` if the list is empty. If a filename is '-', it is also replaced by `sys.stdin`. To specify an alternative list of filenames, pass it as the first argument to `input()`. A single file name is also allowed.

All files are opened in text mode by default, but you can override this by specifying the *mode* parameter in the call to `input()` or `FileInput()`. If an I/O error occurs during opening or reading a file, `IOError` is raised.

If `sys.stdin` is used more than once, the second and further use will return no lines, except perhaps for interactive use, or if it has been explicitly reset (e.g. using `sys.stdin.seek(0)`).

Empty files are opened and immediately closed; the only time their presence in the list of filenames is noticeable at all is when the last file opened is empty.

Lines are returned with any newlines intact, which means that the last line in a file may not have one.

You can control how files are opened by providing an opening hook via the *openhook* parameter to `fileinput.input()` or `FileInput()`. The hook must be a function that takes two arguments, *filename* and *mode*, and returns an accordingly opened file-like object. Two useful hooks are already provided by this module.

The following function is the primary interface of this module:

`fileinput.input([files[, inplace[, backup[, bufsize[, mode[, openhook]]]])`

Create an instance of the `FileInput` class. The instance will be used as global state for the functions of this module, and is also returned to use during iteration. The parameters to this function will be passed along to the constructor of the `FileInput` class.

버전 2.5에서 변경: Added the *mode* and *openhook* parameters.

버전 2.7.12에서 변경: The *bufsize* parameter is no longer used.

The following functions use the global state created by `fileinput.input()`; if there is no active state, `RuntimeError` is raised.

`fileinput.filename()`

Return the name of the file currently being read. Before the first line has been read, returns `None`.

`fileinput.fileno()`

Return the integer 《file descriptor》 for the current file. When no file is opened (before the first line and between files), returns `-1`.

버전 2.5에 추가.

`fileinput.lineno()`

Return the cumulative line number of the line that has just been read. Before the first line has been read, returns `0`. After the last line of the last file has been read, returns the line number of that line.

`fileinput.filelineno()`

Return the line number in the current file. Before the first line has been read, returns `0`. After the last line of the last file has been read, returns the line number of that line within the file.

`fileinput.isfirstline()`

Returns `true` if the line just read is the first line of its file, otherwise returns `false`.

`fileinput.isstdin()`

Returns `true` if the last line was read from `sys.stdin`, otherwise returns `false`.

`fileinput.nextfile()`

Close the current file so that the next iteration will read the first line from the next file (if any); lines not read from the file will not count towards the cumulative line count. The filename is not changed until after the first line of the next file has been read. Before the first line has been read, this function has no effect; it cannot be used to skip the first file. After the last line of the last file has been read, this function has no effect.

`fileinput.close()`

Close the sequence.

The class which implements the sequence behavior provided by the module is available for subclassing as well:

class `fileinput.FileInput` (`[files[, inplace[, backup[, bufsize[, mode[, openhook]]]]]`)

Class `FileInput` is the implementation; its methods `filename()`, `fileno()`, `lineno()`, `filelineno()`, `isfirstline()`, `isstdin()`, `nextfile()` and `close()` correspond to the functions of the same name in the module. In addition it has a `readline()` method which returns the next input line, and a `__getitem__()` method which implements the sequence behavior. The sequence must be accessed in strictly sequential order; random access and `readline()` cannot be mixed.

With *mode* you can specify which file mode will be passed to `open()`. It must be one of `'r'`, `'rU'`, `'U'` and `'rb'`.

The *openhook*, when given, must be a function that takes two arguments, *filename* and *mode*, and returns an accordingly opened file-like object. You cannot use *inplace* and *openhook* together.

버전 2.5에서 변경: Added the *mode* and *openhook* parameters.

버전 2.7.12에서 변경: The *bufsize* parameter is no longer used.

Optional in-place filtering: if the keyword argument `inplace=1` is passed to `fileinput.input()` or to the `FileInput` constructor, the file is moved to a backup file and standard output is directed to the input file (if a file of the same name as the backup file already exists, it will be replaced silently). This makes it possible to write a filter that rewrites its input file in place. If the *backup* parameter is given (typically as `backup='.<some extension>'`), it specifies the extension for the backup file, and the backup file remains around; by default, the extension is `'.bak'` and it is deleted when the output file is closed. In-place filtering is disabled when standard input is read.

참고: The current implementation does not work for MS-DOS 8+3 filesystems.

The two following opening hooks are provided by this module:

`fileinput.hook_compressed(filename, mode)`

Transparently opens files compressed with `gzip` and `bzip2` (recognized by the extensions `'.gz'` and `'.bz2'`) using the `gzip` and `bz2` modules. If the filename extension is not `'.gz'` or `'.bz2'`, the file is opened normally (ie, using `open()` without any decompression).

Usage example: `fi = fileinput.FileInput(openhook=fileinput.hook_compressed)`

버전 2.5에 추가.

`fileinput.hook_encoded(encoding)`

Returns a hook which opens each file with `io.open()`, using the given `encoding` to read the file.

Usage example: `fi = fileinput.FileInput(openhook=fileinput.hook_encoded("iso-8859-1"))`

참고: With this hook, `FileInput` might return Unicode strings depending on the specified `encoding`.

버전 2.5에 추가.

10.3 stat — Interpreting `stat()` results

Source code: [Lib/stat.py](#)

The `stat` module defines constants and functions for interpreting the results of `os.stat()`, `os.fstat()` and `os.lstat()` (if they exist). For complete details about the `stat()`, `fstat()` and `lstat()` calls, consult the documentation for your system.

The `stat` module defines the following functions to test for specific file types:

`stat.S_ISDIR(mode)`

Return non-zero if the mode is from a directory.

`stat.S_ISCHR(mode)`

Return non-zero if the mode is from a character special device file.

`stat.S_ISBLK(mode)`

Return non-zero if the mode is from a block special device file.

`stat.S_ISREG(mode)`

Return non-zero if the mode is from a regular file.

`stat.S_ISFIFO(mode)`

Return non-zero if the mode is from a FIFO (named pipe).

`stat.S_ISLNK(mode)`

Return non-zero if the mode is from a symbolic link.

`stat.S_ISSOCK(mode)`

Return non-zero if the mode is from a socket.

Two additional functions are defined for more general manipulation of the file's mode:

`stat.S_IMODE(mode)`

Return the portion of the file's mode that can be set by `os.chmod()`—that is, the file's permission bits, plus the sticky bit, set-group-id, and set-user-id bits (on systems that support them).

`stat.S_IFMT(mode)`

Return the portion of the file's mode that describes the file type (used by the `S_IS*`() functions above).

Normally, you would use the `os.path.is*()` functions for testing the type of a file; the functions here are useful when you are doing multiple tests of the same file and wish to avoid the overhead of the `stat()` system call for each test. These are also useful when checking for information about a file that isn't handled by `os.path`, like the tests for block and character devices.

Example:

```
import os, sys
from stat import *

def walktree(top, callback):
    '''recursively descend the directory tree rooted at top,
    calling the callback function for each regular file'''

    for f in os.listdir(top):
        pathname = os.path.join(top, f)
        mode = os.stat(pathname).st_mode
        if S_ISDIR(mode):
            # It's a directory, recurse into it
            walktree(pathname, callback)
        elif S_ISREG(mode):
            # It's a file, call the callback function
            callback(pathname)
        else:
            # Unknown file type, print a message
            print 'Skipping %s' % pathname

def visitfile(file):
    print 'visiting', file

if __name__ == '__main__':
    walktree(sys.argv[1], visitfile)
```

All the variables below are simply symbolic indexes into the 10-tuple returned by `os.stat()`, `os.fstat()` or `os.lstat()`.

`stat.ST_MODE`

Inode protection mode.

`stat.ST_INO`

Inode number.

`stat.ST_DEV`

Device inode resides on.

`stat.ST_NLINK`

Number of links to the inode.

`stat.ST_UID`

User id of the owner.

`stat.ST_GID`

Group id of the owner.

`stat.ST_SIZE`

Size in bytes of a plain file; amount of data waiting on some special files.

`stat.ST_ATIME`

Time of last access.

`stat.ST_MTIME`

Time of last modification.

`stat.ST_CTIME`

The `ctime` as reported by the operating system. On some systems (like Unix) is the time of the last metadata change, and, on others (like Windows), is the creation time (see platform documentation for details).

The interpretation of `file size` changes according to the file type. For plain files this is the size of the file in bytes. For FIFOs and sockets under most flavors of Unix (including Linux in particular), the `size` is the number of bytes waiting to be read at the time of the call to `os.stat()`, `os.fstat()`, or `os.lstat()`; this can sometimes be useful, especially for polling one of these special files after a non-blocking open. The meaning of the size field for other character and block devices varies more, depending on the implementation of the underlying system call.

The variables below define the flags used in the `ST_MODE` field.

Use of the functions above is more portable than use of the first set of flags:

`stat.S_IFSOCK`

Socket.

`stat.S_IFLNK`

Symbolic link.

`stat.S_IFREG`

Regular file.

`stat.S_IFBLK`

Block device.

`stat.S_IFDIR`

Directory.

`stat.S_IFCHR`

Character device.

`stat.S_IFIFO`

FIFO.

The following flags can also be used in the `mode` argument of `os.chmod()`:

`stat.S_ISUID`

Set UID bit.

`stat.S_ISGID`

Set-group-ID bit. This bit has several special uses. For a directory it indicates that BSD semantics is to be used for that directory: files created there inherit their group ID from the directory, not from the effective group ID of the creating process, and directories created there will also get the `S_ISGID` bit set. For a file that does not have the group execution bit (`S_IXGRP`) set, the set-group-ID bit indicates mandatory file/record locking (see also `S_ENFMT`).

`stat.S_ISVTX`

Sticky bit. When this bit is set on a directory it means that a file in that directory can be renamed or deleted only by the owner of the file, by the owner of the directory, or by a privileged process.

`stat.S_IRWXU`

Mask for file owner permissions.

`stat.S_IRUSR`
Owner has read permission.

`stat.S_IWUSR`
Owner has write permission.

`stat.S_IXUSR`
Owner has execute permission.

`stat.S_IRWXG`
Mask for group permissions.

`stat.S_IRGRP`
Group has read permission.

`stat.S_IWGRP`
Group has write permission.

`stat.S_IXGRP`
Group has execute permission.

`stat.S_IRWXO`
Mask for permissions for others (not in group).

`stat.S_IROTH`
Others have read permission.

`stat.S_IWOTH`
Others have write permission.

`stat.S_IXOTH`
Others have execute permission.

`stat.S_ENFMT`
System V file locking enforcement. This flag is shared with `S_ISGID`: file/record locking is enforced on files that do not have the group execution bit (`S_IXGRP`) set.

`stat.S_IREAD`
Unix V7 synonym for `S_IRUSR`.

`stat.S_IWRITE`
Unix V7 synonym for `S_IWUSR`.

`stat.S_IEXEC`
Unix V7 synonym for `S_IXUSR`.

The following flags can be used in the *flags* argument of `os.chflags()`:

`stat.UF_NODUMP`
Do not dump the file.

`stat.UF_IMMUTABLE`
The file may not be changed.

`stat.UF_APPEND`
The file may only be appended to.

`stat.UF_OPAQUE`
The directory is opaque when viewed through a union stack.

`stat.UF_NOUNLINK`
The file may not be renamed or deleted.

`stat.UF_COMPRESSED`

The file is stored compressed (Mac OS X 10.6+).

`stat.UF_HIDDEN`

The file should not be displayed in a GUI (Mac OS X 10.5+).

`stat.SF_ARCHIVED`

The file may be archived.

`stat.SF_IMMUTABLE`

The file may not be changed.

`stat.SF_APPEND`

The file may only be appended to.

`stat.SF_NOUNLINK`

The file may not be renamed or deleted.

`stat.SF_SNAPSHOT`

The file is a snapshot file.

See the *BSD or Mac OS systems man page *chflags(2)* for more information.

10.4 statvfs — Constants used with `os.statvfs()`

버전 2.6부터 폐지: The *statvfs* module has been removed in Python 3.

The *statvfs* module defines constants so interpreting the result if *os.statvfs()*, which returns a tuple, can be made without remembering 《magic numbers.》 Each of the constants defined in this module is the *index* of the entry in the tuple returned by *os.statvfs()* that contains the specified information.

`statvfs.F_BSIZE`

Preferred file system block size.

`statvfs.F_FRSIZE`

Fundamental file system block size.

`statvfs.F_BLOCKS`

Total number of blocks in the filesystem.

`statvfs.F_BFREE`

Total number of free blocks.

`statvfs.F_BAVAIL`

Free blocks available to non-super user.

`statvfs.F_FILES`

Total number of file nodes.

`statvfs.F_FFREE`

Total number of free file nodes.

`statvfs.F_FAVAIL`

Free nodes available to non-super user.

`statvfs.F_FLAG`

Flags. System dependent: see *statvfs()* man page.

`statvfs.F_NAMEMAX`

Maximum file name length.

10.5 filecmp — File and Directory Comparisons

Source code: [Lib/filecmp.py](#)

The `filecmp` module defines functions to compare files and directories, with various optional time/correctness trade-offs. For comparing files, see also the `difflib` module.

The `filecmp` module defines the following functions:

`filecmp.cmp(f1, f2[, shallow])`

Compare the files named *f1* and *f2*, returning `True` if they seem equal, `False` otherwise.

Unless *shallow* is given and is false, files with identical `os.stat()` signatures are taken to be equal.

Files that were compared using this function will not be compared again unless their `os.stat()` signature changes.

Note that no external programs are called from this function, giving it portability and efficiency.

`filecmp.cmpfiles(dir1, dir2, common[, shallow])`

Compare the files in the two directories *dir1* and *dir2* whose names are given by *common*.

Returns three lists of file names: *match*, *mismatch*, *errors*. *match* contains the list of files that match, *mismatch* contains the names of those that don't, and *errors* lists the names of files which could not be compared. Files are listed in *errors* if they don't exist in one of the directories, the user lacks permission to read them or if the comparison could not be done for some other reason.

The *shallow* parameter has the same meaning and default value as for `filecmp.cmp()`.

For example, `cmpfiles('a', 'b', ['c', 'd/e'])` will compare *a/c* with *b/c* and *a/d/e* with *b/d/e*. *'c'* and *'d/e'* will each be in one of the three returned lists.

Example:

```
>>> import filecmp
>>> filecmp.cmp('undoc.rst', 'undoc.rst')
True
>>> filecmp.cmp('undoc.rst', 'index.rst')
False
```

10.5.1 The `dircmp` class

`dircmp` instances are built using this constructor:

class `filecmp.dircmp(a, b[, ignore[, hide]])`

Construct a new directory comparison object, to compare the directories *a* and *b*. *ignore* is a list of names to ignore, and defaults to `['RCS', 'CVS', 'tags']`. *hide* is a list of names to hide, and defaults to `[os.curdir, os.pardir]`.

The `dircmp` class compares files by doing *shallow* comparisons as described for `filecmp.cmp()`.

The `dircmp` class provides the following methods:

report()

Print (to `sys.stdout`) a comparison between *a* and *b*.

report_partial_closure()

Print a comparison between *a* and *b* and common immediate subdirectories.

report_full_closure()

Print a comparison between *a* and *b* and common subdirectories (recursively).

The `dircmp` class offers a number of interesting attributes that may be used to get various bits of information about the directory trees being compared.

Note that via `__getattr__()` hooks, all attributes are computed lazily, so there is no speed penalty if only those attributes which are lightweight to compute are used.

left

The directory *a*.

right

The directory *b*.

left_list

Files and subdirectories in *a*, filtered by *hide* and *ignore*.

right_list

Files and subdirectories in *b*, filtered by *hide* and *ignore*.

common

Files and subdirectories in both *a* and *b*.

left_only

Files and subdirectories only in *a*.

right_only

Files and subdirectories only in *b*.

common_dirs

Subdirectories in both *a* and *b*.

common_files

Files in both *a* and *b*

common_funny

Names in both *a* and *b*, such that the type differs between the directories, or names for which `os.stat()` reports an error.

same_files

Files which are identical in both *a* and *b*, using the class's file comparison operator.

diff_files

Files which are in both *a* and *b*, whose contents differ according to the class's file comparison operator.

funny_files

Files which are in both *a* and *b*, but could not be compared.

subdirs

A dictionary mapping names in `common_dirs` to `dircmp` objects.

Here is a simplified example of using the `subdirs` attribute to search recursively through two directories to show common different files:

```
>>> from filecmp import dircmp
>>> def print_diff_files(dcmp):
...     for name in dcmp.diff_files:
...         print "diff_file %s found in %s and %s" % (name, dcmp.left,
...             dcmp.right)
...     for sub_dcmp in dcmp.subdirs.values():
...         print_diff_files(sub_dcmp)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
...
>>> dcmp = dircmp('dir1', 'dir2')
>>> print_diff_files(dcmp)
```

10.6 tempfile — Generate temporary files and directories

Source code: [Lib/tempfile.py](#)

This module generates temporary files and directories. It works on all supported platforms.

In version 2.3 of Python, this module was overhauled for enhanced security. It now provides three new functions, `NamedTemporaryFile()`, `mkstemp()`, and `mkdtemp()`, which should eliminate all remaining need to use the insecure `mktemp()` function. Temporary file names created by this module no longer contain the process ID; instead a string of six random characters is used.

Also, all the user-callable functions now take additional arguments which allow direct control over the location and name of temporary files. It is no longer necessary to use the global `tempdir` and `template` variables. To maintain backward compatibility, the argument order is somewhat odd; it is recommended to use keyword arguments for clarity.

The module defines the following user-callable functions:

`tempfile.TemporaryFile([mode='w+b', bufsize=-1, suffix='', prefix='tmp', dir=None])`

Return a file-like object that can be used as a temporary storage area. The file is created using `mkstemp()`. It will be destroyed as soon as it is closed (including an implicit close when the object is garbage collected). Under Unix, the directory entry for the file is removed immediately after the file is created. Other platforms do not support this; your code should not rely on a temporary file created using this function having or not having a visible name in the file system.

The `mode` parameter defaults to `'w+b'` so that the file created can be read and written without being closed. Binary mode is used so that it behaves consistently on all platforms without regard for the data that is stored. `bufsize` defaults to `-1`, meaning that the operating system default is used.

The `dir`, `prefix` and `suffix` parameters are passed to `mkstemp()`.

The returned object is a true file object on POSIX platforms. On other platforms, it is a file-like object whose `file` attribute is the underlying true file object. This file-like object can be used in a `with` statement, just like a normal file.

`tempfile.NamedTemporaryFile([mode='w+b', bufsize=-1, suffix='', prefix='tmp', dir=None, delete=True])`

This function operates exactly as `TemporaryFile()` does, except that the file is guaranteed to have a visible name in the file system (on Unix, the directory entry is not unlinked). That name can be retrieved from the `name` attribute of the returned file-like object. Whether the name can be used to open the file a second time, while the named temporary file is still open, varies across platforms (it can be so used on Unix; it cannot on Windows NT or later). If `delete` is true (the default), the file is deleted as soon as it is closed.

The returned object is always a file-like object whose `file` attribute is the underlying true file object. This file-like object can be used in a `with` statement, just like a normal file.

버전 2.3에 추가.

버전 2.6에 추가: The `delete` parameter.

`tempfile.SpooledTemporaryFile([max_size=0, mode='w+b', bufsize=-1, suffix='', prefix='tmp', dir=None])`

This function operates exactly as `TemporaryFile()` does, except that data is spooled in memory until the file

size exceeds *max_size*, or until the file's `fileno()` method is called, at which point the contents are written to disk and operation proceeds as with `TemporaryFile()`. Also, its `truncate` method does not accept a *size* argument.

The resulting file has one additional method, `rollover()`, which causes the file to roll over to an on-disk file regardless of its size.

The returned object is a file-like object whose `_file` attribute is either a `StringIO` object or a true file object, depending on whether `rollover()` has been called. This file-like object can be used in a `with` statement, just like a normal file.

버전 2.6에 추가.

```
tempfile.mkstemp([suffix="", prefix='tmp', dir=None, text=False])
```

Creates a temporary file in the most secure manner possible. There are no race conditions in the file's creation, assuming that the platform properly implements the `os.O_EXCL` flag for `os.open()`. The file is readable and writable only by the creating user ID. If the platform uses permission bits to indicate whether a file is executable, the file is executable by no one. The file descriptor is not inherited by child processes.

Unlike `TemporaryFile()`, the user of `mkstemp()` is responsible for deleting the temporary file when done with it.

If *suffix* is specified, the file name will end with that suffix, otherwise there will be no suffix. `mkstemp()` does not put a dot between the file name and the suffix; if you need one, put it at the beginning of *suffix*.

If *prefix* is specified, the file name will begin with that prefix; otherwise, a default prefix is used.

If *dir* is specified, the file will be created in that directory; otherwise, a default directory is used. The default directory is chosen from a platform-dependent list, but the user of the application can control the directory location by setting the `TMPDIR`, `TEMP` or `TMP` environment variables. There is thus no guarantee that the generated filename will have any nice properties, such as not requiring quoting when passed to external commands via `os.popen()`.

If *text* is specified, it indicates whether to open the file in binary mode (the default) or text mode. On some platforms, this makes no difference.

`mkstemp()` returns a tuple containing an OS-level handle to an open file (as would be returned by `os.open()`) and the absolute pathname of that file, in that order.

버전 2.3에 추가.

```
tempfile.mkdtemp([suffix="", prefix='tmp', dir=None])
```

Creates a temporary directory in the most secure manner possible. There are no race conditions in the directory's creation. The directory is readable, writable, and searchable only by the creating user ID.

The user of `mkdtemp()` is responsible for deleting the temporary directory and its contents when done with it.

The *prefix*, *suffix*, and *dir* arguments are the same as for `mkstemp()`.

`mkdtemp()` returns the absolute pathname of the new directory.

버전 2.3에 추가.

```
tempfile.mktemp([suffix="", prefix='tmp', dir=None])
```

버전 2.3부터 폐지: Use `mkstemp()` instead.

Return an absolute pathname of a file that did not exist at the time the call is made. The *prefix*, *suffix*, and *dir* arguments are the same as for `mkstemp()`.

경고: Use of this function may introduce a security hole in your program. By the time you get around to doing anything with the file name it returns, someone else may have beaten you to the punch. `mktemp()` usage can be replaced easily with `NamedTemporaryFile()`, passing it the `delete=False` parameter:

```
>>> f = NamedTemporaryFile(delete=False)
>>> f
<open file '<fdopen>', mode 'w+b' at 0x384698>
>>> f.name
'/var/folders/5q/5qTPn6xq2RaWqk+1Ytw3-U+++TI/-Tmp-/tmpG7V1Y0'
>>> f.write("Hello World!\n")
>>> f.close()
>>> os.unlink(f.name)
>>> os.path.exists(f.name)
False
```

The module uses a global variable that tell it how to construct a temporary name. They are initialized at the first call to any of the functions above. The caller may change them, but this is discouraged; use the appropriate function arguments, instead.

`tempfile.tempdir`

When set to a value other than `None`, this variable defines the default value for the *dir* argument to all the functions defined in this module.

If `tempdir` is unset or `None` at any call to any of the above functions, Python searches a standard list of directories and sets *tempdir* to the first one which the calling user can create files in. The list is:

1. The directory named by the `TMPDIR` environment variable.
2. The directory named by the `TEMP` environment variable.
3. The directory named by the `TMP` environment variable.
4. A platform-specific location:
 - On RiscOS, the directory named by the `Wimp$ScrapDir` environment variable.
 - On Windows, the directories `C:\TEMP`, `C:\TMP`, `\TEMP`, and `\TMP`, in that order.
 - On all other platforms, the directories `/tmp`, `/var/tmp`, and `/usr/tmp`, in that order.
5. As a last resort, the current working directory.

`tempfile.gettempdir()`

Return the directory currently selected to create temporary files in. If *tempdir* is not `None`, this simply returns its contents; otherwise, the search described above is performed, and the result returned.

버전 2.3에 추가.

`tempfile.template`

버전 2.0부터 폐지: Use `gettempprefix()` instead.

When set to a value other than `None`, this variable defines the prefix of the final component of the filenames returned by `mktemp()`. A string of six random letters and digits is appended to the prefix to make the filename unique. The default prefix is `tmp`.

Older versions of this module used to require that `template` be set to `None` after a call to `os.fork()`; this has not been necessary since version 1.5.2.

`tempfile.gettempprefix()`

Return the filename prefix used to create temporary files. This does not contain the directory component. Using this function is preferred over reading the *template* variable directly.

버전 1.5.2에 추가.

10.7 glob — Unix style pathname pattern expansion

Source code: `Lib/glob.py`

The `glob` module finds all the pathnames matching a specified pattern according to the rules used by the Unix shell, although results are returned in arbitrary order. No tilde expansion is done, but `*`, `?`, and character ranges expressed with `[]` will be correctly matched. This is done by using the `os.listdir()` and `fnmatch.fnmatch()` functions in concert, and not by actually invoking a subshell. Note that unlike `fnmatch.fnmatch()`, `glob` treats filenames beginning with a dot (`.`) as special cases. (For tilde and shell variable expansion, use `os.path.expanduser()` and `os.path.expandvars()`.)

For a literal match, wrap the meta-characters in brackets. For example, `'[?]'` matches the character `'?'`.

`glob.glob(pathname)`

Return a possibly-empty list of path names that match *pathname*, which must be a string containing a path specification. *pathname* can be either absolute (like `/usr/src/Python-1.5/Makefile`) or relative (like `.././Tools/*/*.gif`), and can contain shell-style wildcards. Broken symlinks are included in the results (as in the shell).

`glob.iglob(pathname)`

Return an *iterator* which yields the same values as `glob()` without actually storing them all simultaneously.

버전 2.5에 추가.

For example, consider a directory containing only the following files: `1.gif`, `2.txt`, and `card.gif`. `glob()` will produce the following results. Notice how any leading components of the path are preserved.

```
>>> import glob
>>> glob.glob('./[0-9].*')
['./1.gif', './2.txt']
>>> glob.glob('*.gif')
['1.gif', 'card.gif']
>>> glob.glob('?.gif')
['1.gif']
```

If the directory contains files starting with `.` they won't be matched by default. For example, consider a directory containing `card.gif` and `.card.gif`:

```
>>> import glob
>>> glob.glob('*.gif')
['card.gif']
>>> glob.glob('.c*')
['.card.gif']
```

더 보기:

Module `fnmatch` Shell-style filename (not path) expansion

10.8 fnmatch — Unix filename pattern matching

Source code: [Lib/fnmatch.py](#)

This module provides support for Unix shell-style wildcards, which are *not* the same as regular expressions (which are documented in the [re](#) module). The special characters used in shell-style wildcards are:

Pattern	Meaning
*	matches everything
?	matches any single character
[seq]	matches any character in <i>seq</i>
[!seq]	matches any character not in <i>seq</i>

For a literal match, wrap the meta-characters in brackets. For example, '[?]' matches the character '?'.
 Note that the filename separator ('/' on Unix) is *not* special to this module. See module [glob](#) for pathname expansion ([glob](#) uses [filter\(\)](#) to match pathname segments). Similarly, filenames starting with a period are not special for this module, and are matched by the * and ? patterns.

fnmatch.fnmatch(*filename*, *pattern*)

Test whether the *filename* string matches the *pattern* string, returning *True* or *False*. Both parameters are case-normalized using [os.path.normcase\(\)](#). [fnmatchcase\(\)](#) can be used to perform a case-sensitive comparison, regardless of whether that's standard for the operating system.

This example will print all file names in the current directory with the extension `.txt`:

```
import fnmatch
import os

for file in os.listdir('.'):
    if fnmatch.fnmatch(file, '*.txt'):
        print file
```

fnmatch.fnmatchcase(*filename*, *pattern*)

Test whether *filename* matches *pattern*, returning *True* or *False*; the comparison is case-sensitive and does not apply [os.path.normcase\(\)](#).

fnmatch.filter(*names*, *pattern*)

Return the subset of the list of *names* that match *pattern*. It is the same as `[n for n in names if fnmatch(n, pattern)]`, but implemented more efficiently.

버전 2.2에 추가.

fnmatch.translate(*pattern*)

Return the shell-style *pattern* converted to a regular expression for using with [re.match\(\)](#).

Example:

```
>>> import fnmatch, re
>>>
>>> regex = fnmatch.translate('*.txt')
>>> regex
'.*\\.txt\\Z(?ms)'
>>> reobj = re.compile(regex)
>>> reobj.match('foobar.txt')
<_sre.SRE_Match object at 0x...>
```

더 보기:

Module *glob* Unix shell-style path expansion.

10.9 linecache — Random access to text lines

Source code: [Lib/linecache.py](#)

The *linecache* module allows one to get any line from any file, while attempting to optimize internally, using a cache, the common case where many lines are read from a single file. This is used by the *traceback* module to retrieve source lines for inclusion in the formatted traceback.

The *linecache* module defines the following functions:

`linecache.getline(filename, lineno[, module_globals])`

Get line *lineno* from file named *filename*. This function will never raise an exception — it will return `' '` on errors (the terminating newline character will be included for lines that are found).

If a file named *filename* is not found, the function will look for it in the module search path, `sys.path`, after first checking for a **PEP 302** `__loader__` in *module_globals*, in case the module was imported from a zipfile or other non-filesystem import source.

버전 2.5에 추가: The *module_globals* parameter was added.

`linecache.clearcache()`

Clear the cache. Use this function if you no longer need lines from files previously read using *getline()*.

`linecache.checkcache([filename])`

Check the cache for validity. Use this function if files in the cache may have changed on disk, and you require the updated version. If *filename* is omitted, it will check all the entries in the cache.

Example:

```
>>> import linecache
>>> linecache.getline('/etc/passwd', 4)
'sys:x:3:3:sys:/dev:/bin/sh\n'
```

10.10 shutil — High-level file operations

Source code: [Lib/shutil.py](#)

The *shutil* module offers a number of high-level operations on files and collections of files. In particular, functions are provided which support file copying and removal. For operations on individual files, see also the *os* module.

경고: Even the higher-level file copying functions (*shutil.copy()*, *shutil.copy2()*) can't copy all file metadata.

On POSIX platforms, this means that file owner and group are lost as well as ACLs. On Mac OS, the resource fork and other metadata are not used. This means that resources will be lost and file type and creator codes will not be correct. On Windows, file owners, ACLs and alternate data streams are not copied.

10.10.1 Directory and files operations

`shutil.copyfileobj(fsrc, fdst[, length])`

Copy the contents of the file-like object *fsrc* to the file-like object *fdst*. The integer *length*, if given, is the buffer size. In particular, a negative *length* value means to copy the data without looping over the source data in chunks; by default the data is read in chunks to avoid uncontrolled memory consumption. Note that if the current file position of the *fsrc* object is not 0, only the contents from the current file position to the end of the file will be copied.

`shutil.copyfile(src, dst)`

Copy the contents (no metadata) of the file named *src* to a file named *dst*. *dst* must be the complete target file name; look at `shutil.copy()` for a copy that accepts a target directory path. If *src* and *dst* are the same files, `Error` is raised. The destination location must be writable; otherwise, an `IOError` exception will be raised. If *dst* already exists, it will be replaced. Special files such as character or block devices and pipes cannot be copied with this function. *src* and *dst* are path names given as strings.

`shutil.copymode(src, dst)`

Copy the permission bits from *src* to *dst*. The file contents, owner, and group are unaffected. *src* and *dst* are path names given as strings.

`shutil.copystat(src, dst)`

Copy the permission bits, last access time, last modification time, and flags from *src* to *dst*. The file contents, owner, and group are unaffected. *src* and *dst* are path names given as strings.

`shutil.copy(src, dst)`

Copy the file *src* to the file or directory *dst*. If *dst* is a directory, a file with the same basename as *src* is created (or overwritten) in the directory specified. Permission bits are copied. *src* and *dst* are path names given as strings.

`shutil.copy2(src, dst)`

Identical to `copy()` except that `copy2()` also attempts to preserve file metadata.

`copy2()` uses `copystat()` to copy the file metadata. Please see `copystat()` for more information.

`shutil.ignore_patterns(*patterns)`

This factory function creates a function that can be used as a callable for `copytree()`'s *ignore* argument, ignoring files and directories that match one of the glob-style *patterns* provided. See the example below.

버전 2.6에 추가.

`shutil.copytree(src, dst, symlinks=False, ignore=None)`

Recursively copy an entire directory tree rooted at *src*. The destination directory, named by *dst*, must not already exist; it will be created as well as missing parent directories. Permissions and times of directories are copied with `copystat()`, individual files are copied using `shutil.copy2()`.

If *symlinks* is true, symbolic links in the source tree are represented as symbolic links in the new tree, but the metadata of the original links is NOT copied; if false or omitted, the contents and metadata of the linked files are copied to the new tree.

If *ignore* is given, it must be a callable that will receive as its arguments the directory being visited by `copytree()`, and a list of its contents, as returned by `os.listdir()`. Since `copytree()` is called recursively, the *ignore* callable will be called once for each directory that is copied. The callable must return a sequence of directory and file names relative to the current directory (i.e. a subset of the items in its second argument); these names will then be ignored in the copy process. `ignore_patterns()` can be used to create such a callable that ignores names based on glob-style patterns.

If exception(s) occur, an `Error` is raised with a list of reasons.

The source code for this should be considered an example rather than the ultimate tool.

버전 2.3에서 변경: `Error` is raised if any exceptions occur during copying, rather than printing a message.

버전 2.5에서 변경: Create intermediate directories needed to create *dst*, rather than raising an error. Copy permissions and times of directories using `copystat()`.

버전 2.6에서 변경: Added the *ignore* argument to be able to influence what is being copied.

`shutil.rmtree(path[, ignore_errors[, onerror]])`

Delete an entire directory tree; *path* must point to a directory (but not a symbolic link to a directory). If *ignore_errors* is true, errors resulting from failed removals will be ignored; if false or omitted, such errors are handled by calling a handler specified by *onerror* or, if that is omitted, they raise an exception.

If *onerror* is provided, it must be a callable that accepts three parameters: *function*, *path*, and *excinfo*. The first parameter, *function*, is the function which raised the exception; it will be `os.path.islink()`, `os.listdir()`, `os.remove()` or `os.rmdir()`. The second parameter, *path*, will be the path name passed to *function*. The third parameter, *excinfo*, will be the exception information return by `sys.exc_info()`. Exceptions raised by *onerror* will not be caught.

버전 2.6에서 변경: Explicitly check for *path* being a symbolic link and raise `OSError` in that case.

`shutil.move(src, dst)`

Recursively move a file or directory (*src*) to another location (*dst*).

If the destination is an existing directory, then *src* is moved inside that directory. If the destination already exists but is not a directory, it may be overwritten depending on `os.rename()` semantics.

If the destination is on the current filesystem, then `os.rename()` is used. Otherwise, *src* is copied (using `shutil.copy2()`) to *dst* and then removed.

버전 2.3에 추가.

exception `shutil.Error`

This exception collects exceptions that are raised during a multi-file operation. For `copytree()`, the exception argument is a list of 3-tuples (*srcname*, *dstname*, *exception*).

버전 2.3에 추가.

copytree example

This example is the implementation of the `copytree()` function, described above, with the docstring omitted. It demonstrates many of the other functions provided by this module.

```
def copytree(src, dst, symlinks=False, ignore=None):
    names = os.listdir(src)
    if ignore is not None:
        ignored_names = ignore(src, names)
    else:
        ignored_names = set()

    os.makedirs(dst)
    errors = []
    for name in names:
        if name in ignored_names:
            continue
        srcname = os.path.join(src, name)
        dstname = os.path.join(dst, name)
        try:
            if symlinks and os.path.islink(srcname):
                linkto = os.readlink(srcname)
                os.symlink(linkto, dstname)
            elif os.path.isdir(srcname):
                copytree(srcname, dstname, symlinks, ignore)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

        copytree(srcname, dstname, symlinks, ignore)
    else:
        copy2(srcname, dstname)
        # XXX What about devices, sockets etc.?
    except (IOError, os.error) as why:
        errors.append((srcname, dstname, str(why)))
    # catch the Error from the recursive copytree so that we can
    # continue with other files
    except Error as err:
        errors.extend(err.args[0])
try:
    copystat(src, dst)
except WindowsError:
    # can't copy file access times on Windows
    pass
except OSError as why:
    errors.extend((src, dst, str(why)))
if errors:
    raise Error(errors)

```

Another example that uses the `ignore_patterns()` helper:

```

from shutil import copytree, ignore_patterns

copytree(source, destination, ignore=ignore_patterns('*.pyc', 'tmp*'))

```

This will copy everything except `.pyc` files and files or directories whose name starts with `tmp`.

Another example that uses the `ignore` argument to add a logging call:

```

from shutil import copytree
import logging

def _logpath(path, names):
    logging.info('Working in %s' % path)
    return [] # nothing will be ignored

copytree(source, destination, ignore=_logpath)

```

10.10.2 Archiving operations

High-level utilities to create and read compressed and archived files are also provided. They rely on the `zipfile` and `tarfile` modules.

`shutil.make_archive(base_name, format[, root_dir[, base_dir[, verbose[, dry_run[, owner[, group[, logger]]]])])`

Create an archive file (eg. zip or tar) and returns its name.

`base_name` is the name of the file to create, including the path, minus any format-specific extension. `format` is the archive format: one of `«zip»` (if the `zlib` module or external `zip` executable is available), `«tar»`, `«gztar»` (if the `zlib` module is available), or `«bztar»` (if the `bz2` module is available).

`root_dir` is a directory that will be the root directory of the archive; ie. we typically `chdir` into `root_dir` before creating the archive.

`base_dir` is the directory where we start archiving from; ie. `base_dir` will be the common prefix of all files and directories in the archive.

root_dir and *base_dir* both default to the current directory.

owner and *group* are used when creating a tar archive. By default, uses the current owner and group.

logger must be an object compatible with **PEP 282**, usually an instance of `logging.Logger`.

버전 2.7에 추가.

`shutil.get_archive_formats()`

Return a list of supported formats for archiving. Each element of the returned sequence is a tuple (name, description).

By default *shutil* provides these formats:

- *zip*: ZIP file (if the *zlib* module or external *zip* executable is available).
- *tar*: uncompressed tar file.
- *gztar*: gzip'ed tar-file (if the *zlib* module is available).
- *bztar*: bzip2'ed tar-file (if the *bz2* module is available).

You can register new formats or provide your own archiver for any existing formats, by using `register_archive_format()`.

버전 2.7에 추가.

`shutil.register_archive_format(name, function[, extra_args[, description]])`

Register an archiver for the format *name*. *function* is a callable that will be used to invoke the archiver.

If given, *extra_args* is a sequence of (name, value) that will be used as extra keywords arguments when the archiver callable is used.

description is used by `get_archive_formats()` which returns the list of archivers. Defaults to an empty list.

버전 2.7에 추가.

`shutil.unregister_archive_format(name)`

Remove the archive format *name* from the list of supported formats.

버전 2.7에 추가.

Archiving example

In this example, we create a gzip'ed tar-file archive containing all files found in the `.ssh` directory of the user:

```
>>> from shutil import make_archive
>>> import os
>>> archive_name = os.path.expanduser(os.path.join('~', 'myarchive'))
>>> root_dir = os.path.expanduser(os.path.join('~', '.ssh'))
>>> make_archive(archive_name, 'gztar', root_dir)
'/Users/tarek/myarchive.tar.gz'
```

The resulting archive contains:

```
$ tar -tzvf /Users/tarek/myarchive.tar.gz
drwx----- tarek/staff      0 2010-02-01 16:23:40 ./
-rw-r--r-- tarek/staff    609 2008-06-09 13:26:54 ./authorized_keys
-rwxr-xr-x tarek/staff     65 2008-06-09 13:26:54 ./config
-rwx----- tarek/staff    668 2008-06-09 13:26:54 ./id_dsa
-rwxr-xr-x tarek/staff    609 2008-06-09 13:26:54 ./id_dsa.pub
-rw----- tarek/staff   1675 2008-06-09 13:26:54 ./id_rsa
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
-rw-r--r-- tarek/staff      397 2008-06-09 13:26:54 ./id_rsa.pub
-rw-r--r-- tarek/staff    37192 2010-02-06 18:23:10 ./known_hosts
```

10.11 dircache — Cached directory listings

버전 2.6부터 폐지: The *dircache* module has been removed in Python 3.

The *dircache* module defines a function for reading directory listing using a cache, and cache invalidation using the *mtime* of the directory. Additionally, it defines a function to annotate directories by appending a slash.

The *dircache* module defines the following functions:

`dircache.reset()`

Resets the directory cache.

`dircache.listdir(path)`

Return a directory listing of *path*, as gotten from *os.listdir()*. Note that unless *path* changes, further call to *listdir()* will not re-read the directory structure.

Note that the list returned should be regarded as read-only. (Perhaps a future version should change it to return a tuple?)

`dircache.opendir(path)`

Same as *listdir()*. Defined for backwards compatibility.

`dircache.annotate(head, list)`

Assume *list* is a list of paths relative to *head*, and append, in place, a '/' to each path which points to a directory.

```
>>> import dircache
>>> a = dircache.listdir('/')
>>> a = a[:] # Copy the return value so we can change 'a'
>>> a
['bin', 'boot', 'cdrom', 'dev', 'etc', 'floppy', 'home', 'initrd', 'lib', 'lost+
found', 'mnt', 'proc', 'root', 'sbin', 'tmp', 'usr', 'var', 'vmlinuz']
>>> dircache.annotate('/', a)
>>> a
['bin/', 'boot/', 'cdrom/', 'dev/', 'etc/', 'floppy/', 'home/', 'initrd/', 'lib/
', 'lost+found/', 'mnt/', 'proc/', 'root/', 'sbin/', 'tmp/', 'usr/', 'var/', 'vm
linuz']
```

10.12 macpath — Mac OS 9 path manipulation functions

This module is the Mac OS 9 (and earlier) implementation of the *os.path* module. It can be used to manipulate old-style Macintosh pathnames on Mac OS X (or any other platform).

The following functions are available in this module: *normcase()*, *normpath()*, *isabs()*, *join()*, *split()*, *isdir()*, *isfile()*, *walk()*, *exists()*. For other functions available in *os.path* dummy counterparts are available.

더 보기:

Section *File Objects* A description of Python's built-in file objects.

Module *os* Operating system interfaces, including functions to work with files at a lower level than the built-in file object.

The modules described in this chapter support storing Python data in a persistent form on disk. The `pickle` and `marshal` modules can turn many Python data types into a stream of bytes and then recreate the objects from the bytes. The various DBM-related modules support a family of hash-based file formats that store a mapping of strings to other strings. The `bsddb` module also provides such disk-based string-to-string mappings based on hashing, and also supports B-Tree and record-based formats.

The list of modules described in this chapter is:

11.1 `pickle` — Python object serialization

The `pickle` module implements a fundamental, but powerful algorithm for serializing and de-serializing a Python object structure. «Pickling» is the process whereby a Python object hierarchy is converted into a byte stream, and «unpickling» is the inverse operation, whereby a byte stream is converted back into an object hierarchy. Pickling (and unpickling) is alternatively known as «serialization», «marshalling»,¹ or «flattening», however, to avoid confusion, the terms used here are «pickling» and «unpickling».

This documentation describes both the `pickle` module and the `cPickle` module.

경고: The `pickle` module is not secure against erroneous or maliciously constructed data. Never unpickle data received from an untrusted or unauthenticated source.

¹ Don't confuse this with the `marshal` module

11.1.1 Relationship to other Python modules

The `pickle` module has an optimized cousin called the `cPickle` module. As its name implies, `cPickle` is written in C, so it can be up to 1000 times faster than `pickle`. However it does not support subclassing of the `Pickler()` and `Unpickler()` classes, because in `cPickle` these are functions, not classes. Most applications have no need for this functionality, and can benefit from the improved performance of `cPickle`. Other than that, the interfaces of the two modules are nearly identical; the common interface is described in this manual and differences are pointed out where necessary. In the following discussions, we use the term «pickle» to collectively describe the `pickle` and `cPickle` modules.

The data streams the two modules produce are guaranteed to be interchangeable.

Python has a more primitive serialization module called `marshal`, but in general `pickle` should always be the preferred way to serialize Python objects. `marshal` exists primarily to support Python's `.pyc` files.

The `pickle` module differs from `marshal` in several significant ways:

- The `pickle` module keeps track of the objects it has already serialized, so that later references to the same object won't be serialized again. `marshal` doesn't do this.

This has implications both for recursive objects and object sharing. Recursive objects are objects that contain references to themselves. These are not handled by `marshal`, and in fact, attempting to marshal recursive objects will crash your Python interpreter. Object sharing happens when there are multiple references to the same object in different places in the object hierarchy being serialized. `pickle` stores such objects only once, and ensures that all other references point to the master copy. Shared objects remain shared, which can be very important for mutable objects.

- `marshal` cannot be used to serialize user-defined classes and their instances. `pickle` can save and restore class instances transparently, however the class definition must be importable and live in the same module as when the object was stored.
- The `marshal` serialization format is not guaranteed to be portable across Python versions. Because its primary job in life is to support `.pyc` files, the Python implementers reserve the right to change the serialization format in non-backwards compatible ways should the need arise. The `pickle` serialization format is guaranteed to be backwards compatible across Python releases.

Note that serialization is a more primitive notion than persistence; although `pickle` reads and writes file objects, it does not handle the issue of naming persistent objects, nor the (even more complicated) issue of concurrent access to persistent objects. The `pickle` module can transform a complex object into a byte stream and it can transform the byte stream into an object with the same internal structure. Perhaps the most obvious thing to do with these byte streams is to write them onto a file, but it is also conceivable to send them across a network or store them in a database. The module `shelve` provides a simple interface to pickle and unpickle objects on DBM-style database files.

11.1.2 Data stream format

The data format used by `pickle` is Python-specific. This has the advantage that there are no restrictions imposed by external standards such as XDR (which can't represent pointer sharing); however it means that non-Python programs may not be able to reconstruct pickled Python objects.

By default, the `pickle` data format uses a printable ASCII representation. This is slightly more voluminous than a binary representation. The big advantage of using printable ASCII (and of some other characteristics of `pickle`'s representation) is that for debugging or recovery purposes it is possible for a human to read the pickled file with a standard text editor.

There are currently 3 different protocols which can be used for pickling.

- Protocol version 0 is the original ASCII protocol and is backwards compatible with earlier versions of Python.
- Protocol version 1 is the old binary format which is also compatible with earlier versions of Python.

- Protocol version 2 was introduced in Python 2.3. It provides much more efficient pickling of *new-style classes*.

Refer to [PEP 307](#) for more information.

If a *protocol* is not specified, protocol 0 is used. If *protocol* is specified as a negative value or *HIGHEST_PROTOCOL*, the highest protocol version available will be used.

버전 2.3에서 변경: Introduced the *protocol* parameter.

A binary format, which is slightly more efficient, can be chosen by specifying a *protocol* version ≥ 1 .

11.1.3 Usage

To serialize an object hierarchy, you first create a pickler, then you call the pickler's *dump()* method. To de-serialize a data stream, you first create an unpickler, then you call the unpickler's *load()* method. The *pickle* module provides the following constant:

`pickle.HIGHEST_PROTOCOL`

The highest protocol version available. This value can be passed as a *protocol* value.

버전 2.3에 추가.

참고: Be sure to always open pickle files created with protocols ≥ 1 in binary mode. For the old ASCII-based pickle protocol 0 you can use either text mode or binary mode as long as you stay consistent.

A pickle file written with protocol 0 in binary mode will contain lone linefeeds as line terminators and therefore will look 《funny》 when viewed in Notepad or other editors which do not support this format.

The *pickle* module provides the following functions to make the pickling process more convenient:

`pickle.dump(obj, file[, protocol])`

Write a pickled representation of *obj* to the open file object *file*. This is equivalent to `Pickler(file, protocol).dump(obj)`.

If the *protocol* parameter is omitted, protocol 0 is used. If *protocol* is specified as a negative value or *HIGHEST_PROTOCOL*, the highest protocol version will be used.

버전 2.3에서 변경: Introduced the *protocol* parameter.

file must have a `write()` method that accepts a single string argument. It can thus be a file object opened for writing, a *StringIO* object, or any other custom object that meets this interface.

`pickle.load(file)`

Read a string from the open file object *file* and interpret it as a pickle data stream, reconstructing and returning the original object hierarchy. This is equivalent to `Unpickler(file).load()`.

file must have two methods, a `read()` method that takes an integer argument, and a `readline()` method that requires no arguments. Both methods should return a string. Thus *file* can be a file object opened for reading, a *StringIO* object, or any other custom object that meets this interface.

This function automatically determines whether the data stream was written in binary mode or not.

`pickle.dumps(obj[, protocol])`

Return the pickled representation of the object as a string, instead of writing it to a file.

If the *protocol* parameter is omitted, protocol 0 is used. If *protocol* is specified as a negative value or *HIGHEST_PROTOCOL*, the highest protocol version will be used.

버전 2.3에서 변경: The *protocol* parameter was added.

`pickle.loads(string)`

Read a pickled object hierarchy from a string. Characters in the string past the pickled object's representation are ignored.

The `pickle` module also defines three exceptions:

exception `pickle.PickleError`

A common base class for the other exceptions defined below. This inherits from `Exception`.

exception `pickle.PicklingError`

This exception is raised when an unpicklable object is passed to the `dump()` method.

exception `pickle.UnpicklingError`

This exception is raised when there is a problem unpickling an object. Note that other exceptions may also be raised during unpickling, including (but not necessarily limited to) `AttributeError`, `EOFError`, `ImportError`, and `IndexError`.

The `pickle` module also exports two callables², `Pickler` and `Unpickler`:

class `pickle.Pickler(file[, protocol])`

This takes a file-like object to which it will write a pickle data stream.

If the `protocol` parameter is omitted, protocol 0 is used. If `protocol` is specified as a negative value or `HIGHEST_PROTOCOL`, the highest protocol version will be used.

버전 2.3에서 변경: Introduced the `protocol` parameter.

`file` must have a `write()` method that accepts a single string argument. It can thus be an open file object, a `StringIO` object, or any other custom object that meets this interface.

`Pickler` objects define one (or two) public methods:

dump(obj)

Write a pickled representation of `obj` to the open file object given in the constructor. Either the binary or ASCII format will be used, depending on the value of the `protocol` argument passed to the constructor.

clear_memo()

Clears the pickler's «memo». The memo is the data structure that remembers which objects the pickler has already seen, so that shared or recursive objects pickled by reference and not by value. This method is useful when re-using picklers.

참고: Prior to Python 2.3, `clear_memo()` was only available on the picklers created by `cPickle`. In the `pickle` module, picklers have an instance variable called `memo` which is a Python dictionary. So to clear the memo for a `pickle` module pickler, you could do the following:

```
mypickler.memo.clear()
```

Code that does not need to support older versions of Python should simply use `clear_memo()`.

It is possible to make multiple calls to the `dump()` method of the same `Pickler` instance. These must then be matched to the same number of calls to the `load()` method of the corresponding `Unpickler` instance. If the same object is pickled by multiple `dump()` calls, the `load()` will all yield references to the same object.³

`Unpickler` objects are defined as:

² In the `pickle` module these callables are classes, which you could subclass to customize the behavior. However, in the `cPickle` module these callables are factory functions and so cannot be subclassed. One common reason to subclass is to control what objects can actually be unpickled. See section *Subclassing Unpicklers* for more details.

³ **Warning:** this is intended for pickling multiple objects without intervening modifications to the objects or their parts. If you modify an object and then pickle it again using the same `Pickler` instance, the object is not pickled again — a reference to it is pickled and the `Unpickler` will return the old value, not the modified one. There are two problems here: (1) detecting changes, and (2) marshalling a minimal set of changes. Garbage Collection may also become a problem here.

class `pickle.Unpickler` (*file*)

This takes a file-like object from which it will read a pickle data stream. This class automatically determines whether the data stream was written in binary mode or not, so it does not need a flag as in the *Pickler* factory.

file must have two methods, a `read()` method that takes an integer argument, and a `readline()` method that requires no arguments. Both methods should return a string. Thus *file* can be a file object opened for reading, a *StringIO* object, or any other custom object that meets this interface.

Unpickler objects have one (or two) public methods:

load()

Read a pickled object representation from the open file object given in the constructor, and return the reconstituted object hierarchy specified therein.

This method automatically determines whether the data stream was written in binary mode or not.

noload()

This is just like `load()` except that it doesn't actually create any objects. This is useful primarily for finding what's called 《persistent ids》 that may be referenced in a pickle data stream. See section *The pickle protocol* below for more details.

Note: the `noload()` method is currently only available on *Unpickler* objects created with the *cPickle* module. *pickle* module *Unpicklers* do not have the `noload()` method.

11.1.4 What can be pickled and unpickled?

The following types can be pickled:

- `None`, `True`, and `False`
- integers, long integers, floating point numbers, complex numbers
- normal and Unicode strings
- tuples, lists, sets, and dictionaries containing only picklable objects
- functions defined at the top level of a module
- built-in functions defined at the top level of a module
- classes that are defined at the top level of a module
- instances of such classes whose `__dict__` or the result of calling `__getstate__()` is picklable (see section *The pickle protocol* for details).

Attempts to pickle unpicklable objects will raise the *PicklingError* exception; when this happens, an unspecified number of bytes may have already been written to the underlying file. Trying to pickle a highly recursive data structure may exceed the maximum recursion depth, a *RuntimeError* will be raised in this case. You can carefully raise this limit with `sys.setrecursionlimit()`.

Note that functions (built-in and user-defined) are pickled by 《fully qualified》 name reference, not by value. This means that only the function name is pickled, along with the name of the module the function is defined in. Neither the function's code, nor any of its function attributes are pickled. Thus the defining module must be importable in the unpickling environment, and the module must contain the named object, otherwise an exception will be raised.⁴

Similarly, classes are pickled by named reference, so the same restrictions in the unpickling environment apply. Note that none of the class's code or data is pickled, so in the following example the class attribute `attr` is not restored in the unpickling environment:

⁴ The exception raised will likely be an *ImportError* or an *AttributeError* but it could be something else.

```
class Foo:
    attr = 'a class attr'

picklestring = pickle.dumps(Foo)
```

These restrictions are why picklable functions and classes must be defined in the top level of a module.

Similarly, when class instances are pickled, their class's code and data are not pickled along with them. Only the instance data are pickled. This is done on purpose, so you can fix bugs in a class or add methods to the class and still load objects that were created with an earlier version of the class. If you plan to have long-lived objects that will see many versions of a class, it may be worthwhile to put a version number in the objects so that suitable conversions can be made by the class's `__setstate__()` method.

11.1.5 The pickle protocol

This section describes the 《pickling protocol》 that defines the interface between the pickler/unpickler and the objects that are being serialized. This protocol provides a standard way for you to define, customize, and control how your objects are serialized and de-serialized. The description in this section doesn't cover specific customizations that you can employ to make the unpickling environment slightly safer from untrusted pickle data streams; see section [Subclassing Unpicklers](#) for more details.

Pickling and unpickling normal class instances

`object.__getinitargs__()`

When a pickled class instance is unpickled, its `__init__()` method is normally *not* invoked. If it is desirable that the `__init__()` method be called on unpickling, an old-style class can define a method `__getinitargs__()`, which should return a *tuple* of positional arguments to be passed to the class constructor (`__init__()` for example). Keyword arguments are not supported. The `__getinitargs__()` method is called at pickle time; the tuple it returns is incorporated in the pickle for the instance.

`object.__getnewargs__()`

New-style types can provide a `__getnewargs__()` method that is used for protocol 2. Implementing this method is needed if the type establishes some internal invariants when the instance is created, or if the memory allocation is affected by the values passed to the `__new__()` method for the type (as it is for tuples and strings). Instances of a *new-style class* `C` are created using

```
obj = C.__new__(C, *args)
```

where `args` is the result of calling `__getnewargs__()` on the original object; if there is no `__getnewargs__()`, an empty tuple is assumed.

`object.__getstate__()`

Classes can further influence how their instances are pickled; if the class defines the method `__getstate__()`, it is called and the return state is pickled as the contents for the instance, instead of the contents of the instance's dictionary. If there is no `__getstate__()` method, the instance's `__dict__` is pickled.

`object.__setstate__(state)`

Upon unpickling, if the class also defines the method `__setstate__()`, it is called with the unpickled state.⁵ If there is no `__setstate__()` method, the pickled state must be a dictionary and its items are assigned to the new instance's dictionary. If a class defines both `__getstate__()` and `__setstate__()`, the state object needn't be a dictionary and these methods can do what they want.⁶

⁵ These methods can also be used to implement copying class instances.

⁶ This protocol is also used by the shallow and deep copying operations defined in the `copy` module.

참고: For *new-style classes*, if `__getstate__()` returns a false value, the `__setstate__()` method will not be called.

참고: At unpickling time, some methods like `__getattr__()`, `__getattribute__()`, or `__setattr__()` may be called upon the instance. In case those methods rely on some internal invariant being true, the type should implement either `__getinitargs__()` or `__getnewargs__()` to establish such an invariant; otherwise, neither `__new__()` nor `__init__()` will be called.

Pickling and unpickling extension types

`object.__reduce__()`

When the `Pickler` encounters an object of a type it knows nothing about — such as an extension type — it looks in two places for a hint of how to pickle it. One alternative is for the object to implement a `__reduce__()` method. If provided, at pickling time `__reduce__()` will be called with no arguments, and it must return either a string or a tuple.

If a string is returned, it names a global variable whose contents are pickled as normal. The string returned by `__reduce__()` should be the object's local name relative to its module; the pickle module searches the module namespace to determine the object's module.

When a tuple is returned, it must be between two and five elements long. Optional elements can either be omitted, or `None` can be provided as their value. The contents of this tuple are pickled as normal and used to reconstruct the object at unpickling time. The semantics of each element are:

- A callable object that will be called to create the initial version of the object. The next element of the tuple will provide arguments for this callable, and later elements provide additional state information that will subsequently be used to fully reconstruct the pickled data.

In the unpickling environment this object must be either a class, a callable registered as a «safe constructor» (see below), or it must have an attribute `__safe_for_unpickling__` with a true value. Otherwise, an `UnpicklingError` will be raised in the unpickling environment. Note that as usual, the callable itself is pickled by name.

- A tuple of arguments for the callable object.

버전 2.5에서 변경: Formerly, this argument could also be `None`.

- Optionally, the object's state, which will be passed to the object's `__setstate__()` method as described in section *Pickling and unpickling normal class instances*. If the object has no `__setstate__()` method, then, as above, the value must be a dictionary and it will be added to the object's `__dict__`.
- Optionally, an iterator (and not a sequence) yielding successive list items. These list items will be pickled, and appended to the object using either `obj.append(item)` or `obj.extend(list_of_items)`. This is primarily used for list subclasses, but may be used by other classes as long as they have `append()` and `extend()` methods with the appropriate signature. (Whether `append()` or `extend()` is used depends on which pickle protocol version is used as well as the number of items to append, so both must be supported.)
- Optionally, an iterator (not a sequence) yielding successive dictionary items, which should be tuples of the form `(key, value)`. These items will be pickled and stored to the object using `obj[key] = value`. This is primarily used for dictionary subclasses, but may be used by other classes as long as they implement `__setitem__()`.

`object.__reduce_ex__(protocol)`

It is sometimes useful to know the protocol version when implementing `__reduce__()`. This can be done by implementing a method named `__reduce_ex__()` instead of `__reduce__()`. `__reduce_ex__()`, when

it exists, is called in preference over `__reduce__()` (you may still provide `__reduce__()` for backwards compatibility). The `__reduce_ex__()` method will be called with a single integer argument, the protocol version.

The `object` class implements both `__reduce__()` and `__reduce_ex__()`; however, if a subclass overrides `__reduce__()` but not `__reduce_ex__()`, the `__reduce_ex__()` implementation detects this and calls `__reduce__()`.

An alternative to implementing a `__reduce__()` method on the object to be pickled, is to register the callable with the `copy_reg` module. This module provides a way for programs to register 《reduction functions》 and constructors for user-defined types. Reduction functions have the same semantics and interface as the `__reduce__()` method described above, except that they are called with a single argument, the object to be pickled.

The registered constructor is deemed a 《safe constructor》 for purposes of unpickling as described above.

Pickling and unpickling external objects

For the benefit of object persistence, the `pickle` module supports the notion of a reference to an object outside the pickled data stream. Such objects are referenced by a 《persistent id》, which is just an arbitrary string of printable ASCII characters. The resolution of such names is not defined by the `pickle` module; it will delegate this resolution to user defined functions on the pickler and unpickler.⁷

To define external persistent id resolution, you need to set the `persistent_id` attribute of the pickler object and the `persistent_load` attribute of the unpickler object.

To pickle objects that have an external persistent id, the pickler must have a custom `persistent_id()` method that takes an object as an argument and returns either `None` or the persistent id for that object. When `None` is returned, the pickler simply pickles the object as normal. When a persistent id string is returned, the pickler will pickle that string, along with a marker so that the unpickler will recognize the string as a persistent id.

To unpickle external objects, the unpickler must have a custom `persistent_load()` function that takes a persistent id string and returns the referenced object.

Here's a silly example that *might* shed more light:

```
import pickle
from cStringIO import StringIO

src = StringIO()
p = pickle.Pickler(src)

def persistent_id(obj):
    if hasattr(obj, 'x'):
        return 'the value %d' % obj.x
    else:
        return None

p.persistent_id = persistent_id

class Integer:
    def __init__(self, x):
        self.x = x
    def __str__(self):
        return 'My name is integer %d' % self.x
```

(다음 페이지에 계속)

⁷ The actual mechanism for associating these user defined functions is slightly different for `pickle` and `cPickle`. The description given here works the same for both implementations. Users of the `pickle` module could also use subclassing to effect the same results, overriding the `persistent_id()` and `persistent_load()` methods in the derived classes.

(이전 페이지에서 계속)

```

i = Integer(7)
print i
p.dump(i)

datastream = src.getvalue()
print repr(datastream)
dst = StringIO(datastream)

up = pickle.Unpickler(dst)

class FancyInteger(Integer):
    def __str__(self):
        return 'I am the integer %d' % self.x

def persistent_load(persid):
    if persid.startswith('the value '):
        value = int(persid.split()[2])
        return FancyInteger(value)
    else:
        raise pickle.UnpicklingError, 'Invalid persistent id'

up.persistent_load = persistent_load

j = up.load()
print j

```

In the `cPickle` module, the unpickler's `persistent_load` attribute can also be set to a Python list, in which case, when the unpickler reaches a persistent id, the persistent id string will simply be appended to this list. This functionality exists so that a pickle data stream can be «sniffed» for object references without actually instantiating all the objects in a pickle.⁸ Setting `persistent_load` to a list is usually used in conjunction with the `no_load()` method on the Unpickler.

11.1.6 Subclassing Unpicklers

By default, unpickling will import any class that it finds in the pickle data. You can control exactly what gets unpickled and what gets called by customizing your unpickler. Unfortunately, exactly how you do this is different depending on whether you're using `pickle` or `cPickle`.⁹

In the `pickle` module, you need to derive a subclass from `Unpickler`, overriding the `load_global()` method. `load_global()` should read two lines from the pickle data stream where the first line will be the name of the module containing the class and the second line will be the name of the instance's class. It then looks up the class, possibly importing the module and digging out the attribute, then it appends what it finds to the unpickler's stack. Later on, this class will be assigned to the `__class__` attribute of an empty class, as a way of magically creating an instance without calling its class's `__init__()`. Your job (should you choose to accept it), would be to have `load_global()` push onto the unpickler's stack, a known safe version of any class you deem safe to unpickle. It is up to you to produce such a class. Or you could raise an error if you want to disallow all unpickling of instances. If this sounds like a hack, you're right. Refer to the source code to make this work.

Things are a little cleaner with `cPickle`, but not by much. To control what gets unpickled, you can set the unpickler's `find_global` attribute to a function or `None`. If it is `None` then any attempts to unpickle instances will raise an `UnpicklingError`. If it is a function, then it should accept a module name and a class name, and return the

⁸ We'll leave you with the image of Guido and Jim sitting around sniffing pickles in their living rooms.

⁹ A word of caution: the mechanisms described here use internal attributes and methods, which are subject to change in future versions of Python. We intend to someday provide a common interface for controlling this behavior, which will work in either `pickle` or `cPickle`.

corresponding class object. It is responsible for looking up the class and performing any necessary imports, and it may raise an error to prevent instances of the class from being unpickled.

The moral of the story is that you should be really careful about the source of the strings your application unpickles.

11.1.7 Example

For the simplest code, use the `dump()` and `load()` functions. Note that a self-referencing list is pickled and restored correctly.

```
import pickle

data1 = {'a': [1, 2.0, 3, 4+6j],
        'b': ('string', u'Unicode string'),
        'c': None}

selfref_list = [1, 2, 3]
selfref_list.append(selfref_list)

output = open('data.pkl', 'wb')

# Pickle dictionary using protocol 0.
pickle.dump(data1, output)

# Pickle the list using the highest protocol available.
pickle.dump(selfref_list, output, -1)

output.close()
```

The following example reads the resulting pickled data. When reading a pickle-containing file, you should open the file in binary mode because you can't be sure if the ASCII or binary format was used.

```
import pprint, pickle

pkl_file = open('data.pkl', 'rb')

data1 = pickle.load(pkl_file)
pprint.pprint(data1)

data2 = pickle.load(pkl_file)
pprint.pprint(data2)

pkl_file.close()
```

Here's a larger example that shows how to modify pickling behavior for a class. The `TextReader` class opens a text file, and returns the line number and line contents each time its `readline()` method is called. If a `TextReader` instance is pickled, all attributes *except* the file object member are saved. When the instance is unpickled, the file is reopened, and reading resumes from the last location. The `__setstate__()` and `__getstate__()` methods are used to implement this behavior.

```
#!/usr/local/bin/python

class TextReader:
    """Print and number lines in a text file."""
    def __init__(self, file):
        self.file = file
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

self.fh = open(file)
self.lineno = 0

def readline(self):
    self.lineno = self.lineno + 1
    line = self.fh.readline()
    if not line:
        return None
    if line.endswith("\n"):
        line = line[:-1]
    return "%d: %s" % (self.lineno, line)

def __getstate__(self):
    odict = self.__dict__.copy() # copy the dict since we change it
    del odict['fh']              # remove filehandle entry
    return odict

def __setstate__(self, dict):
    fh = open(dict['file'])      # reopen file
    count = dict['lineno']       # read from file...
    while count:                # until line count is restored
        fh.readline()
        count = count - 1
    self.__dict__.update(dict)  # update attributes
    self.fh = fh                # save the file object

```

A sample usage might be something like this:

```

>>> import TextReader
>>> obj = TextReader.TextReader("TextReader.py")
>>> obj.readline()
'1: #!/usr/local/bin/python'
>>> obj.readline()
'2: '
>>> obj.readline()
'3: class TextReader:'
>>> import pickle
>>> pickle.dump(obj, open('save.p', 'wb'))

```

If you want to see that *pickle* works across Python processes, start another Python session, before continuing. What follows can happen from either the same process or a new process.

```

>>> import pickle
>>> reader = pickle.load(open('save.p', 'rb'))
>>> reader.readline()
'4:     """Print and number lines in a text file."""'

```

더 보기:

Module *copy_reg* Pickle interface constructor registration for extension types.

Module *shelve* Indexed databases of objects; uses *pickle*.

Module *copy* Shallow and deep object copying.

Module *marshal* High-performance serialization of built-in types.

11.2 cPickle — A faster pickle

The `cPickle` module supports serialization and de-serialization of Python objects, providing an interface and functionality nearly identical to the `pickle` module. There are several differences, the most important being performance and subclassability.

First, `cPickle` can be up to 1000 times faster than `pickle` because the former is implemented in C. Second, in the `cPickle` module the callables `Pickler()` and `Unpickler()` are functions, not classes. This means that you cannot use them to derive custom pickling and unpickling subclasses. Most applications have no need for this functionality and should benefit from the greatly improved performance of the `cPickle` module.

The pickle data stream produced by `pickle` and `cPickle` are identical, so it is possible to use `pickle` and `cPickle` interchangeably with existing pickles.¹⁰

There are additional minor differences in API between `cPickle` and `pickle`, however for most applications, they are interchangeable. More documentation is provided in the `pickle` module documentation, which includes a list of the documented differences.

11.3 copy_reg — Register pickle support functions

참고: The `copy_reg` module has been renamed to `copyreg` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

The `copy_reg` module offers a way to define functions used while pickling specific objects. The `pickle`, `cPickle`, and `copy` modules use those functions when pickling/copying those objects. The module provides configuration information about object constructors which are not classes. Such constructors may be factory functions or class instances.

`copy_reg.constructor(object)`

Declares *object* to be a valid constructor. If *object* is not callable (and hence not valid as a constructor), raises `TypeError`.

`copy_reg.pickle(type, function[, constructor])`

Declares that *function* should be used as a «reduction» function for objects of type *type*; *type* must not be a «classic» class object. (Classic classes are handled differently; see the documentation for the `pickle` module for details.) *function* should return either a string or a tuple containing two or three elements.

The optional *constructor* parameter, if provided, is a callable object which can be used to reconstruct the object when called with the tuple of arguments returned by *function* at pickling time. `TypeError` will be raised if *object* is a class or *constructor* is not callable.

See the `pickle` module for more details on the interface expected of *function* and *constructor*.

¹⁰ Since the pickle data format is actually a tiny stack-oriented programming language, and some freedom is taken in the encodings of certain objects, it is possible that the two modules produce different data streams for the same input objects. However it is guaranteed that they will always be able to read each other's data streams.

11.3.1 Example

The example below would like to show how to register a pickle function and how it will be used:

```
>>> import copy_reg, copy, pickle
>>> class C(object):
...     def __init__(self, a):
...         self.a = a
...
>>> def pickle_c(c):
...     print("pickling a C instance...")
...     return C, (c.a,)
...
>>> copy_reg.pickle(C, pickle_c)
>>> c = C(1)
>>> d = copy.copy(c)
pickling a C instance...
>>> p = pickle.dumps(c)
pickling a C instance...
```

11.4 shelve — Python object persistence

Source code: [Lib/shelve.py](#)

A `shelve` is a persistent, dictionary-like object. The difference with `dbm` databases is that the values (not the keys!) in a shelf can be essentially arbitrary Python objects — anything that the `pickle` module can handle. This includes most class instances, recursive data types, and objects containing lots of shared sub-objects. The keys are ordinary strings.

`shelve.open(filename, flag='c', protocol=None, writeback=False)`

Open a persistent dictionary. The filename specified is the base filename for the underlying database. As a side-effect, an extension may be added to the filename and more than one file may be created. By default, the underlying database file is opened for reading and writing. The optional `flag` parameter has the same interpretation as the `flag` parameter of `anydbm.open()`.

By default, version 0 pickles are used to serialize values. The version of the pickle protocol can be specified with the `protocol` parameter.

버전 2.3에서 변경: The `protocol` parameter was added.

Because of Python semantics, a shelf cannot know when a mutable persistent-dictionary entry is modified. By default modified objects are written *only* when assigned to the shelf (see [Example](#)). If the optional `writeback` parameter is set to `True`, all entries accessed are also cached in memory, and written back on `sync()` and `close()`; this can make it handier to mutate mutable entries in the persistent dictionary, but, if many entries are accessed, it can consume vast amounts of memory for the cache, and it can make the close operation very slow since all accessed entries are written back (there is no way to determine which accessed entries are mutable, nor which ones were actually mutated).

Like file objects, shelf objects should be closed explicitly to ensure that the persistent data is flushed to disk.

경고: Because the `shelve` module is backed by `pickle`, it is insecure to load a shelf from an untrusted source. Like with `pickle`, loading a shelf can execute arbitrary code.

Shelf objects support most of the methods supported by dictionaries. This eases the transition from dictionary based scripts to those requiring persistent storage.

Note, the Python 3 transition methods (`viewkeys()`, `viewvalues()`, and `viewitems()`) are not supported.

Two additional methods are supported:

`Shelf.sync()`

Write back all entries in the cache if the shelf was opened with `writeback` set to `True`. Also empty the cache and synchronize the persistent dictionary on disk, if feasible. This is called automatically when the shelf is closed with `close()`.

`Shelf.close()`

Synchronize and close the persistent `dict` object. Operations on a closed shelf will fail with a `ValueError`.

더 보기:

[Persistent dictionary recipe](#) with widely supported storage formats and having the speed of native dictionaries.

11.4.1 Restrictions

- The choice of which database package will be used (such as `dbm`, `gdbm` or `bsddb`) depends on which interface is available. Therefore it is not safe to open the database directly using `dbm`. The database is also (unfortunately) subject to the limitations of `dbm`, if it is used — this means that (the pickled representation of) the objects stored in the database should be fairly small, and in rare cases key collisions may cause the database to refuse updates.
- The `shelve` module does not support *concurrent* read/write access to shelved objects. (Multiple simultaneous read accesses are safe.) When a program has a shelf open for writing, no other program should have it open for reading or writing. Unix file locking can be used to solve this, but this differs across Unix versions and requires knowledge about the database implementation used.

class `shelve.Shelf` (*dict*, *protocol=None*, *writeback=False*)

A subclass of `UserDict.DictMixin` which stores pickled values in the *dict* object.

By default, version 0 pickles are used to serialize values. The version of the pickle protocol can be specified with the *protocol* parameter. See the [pickle](#) documentation for a discussion of the pickle protocols.

버전 2.3에서 변경: The *protocol* parameter was added.

If the *writeback* parameter is `True`, the object will hold a cache of all entries accessed and write them back to the *dict* at sync and close times. This allows natural operations on mutable entries, but can consume much more memory and make sync and close take a long time.

class `shelve.BsddbShelf` (*dict*, *protocol=None*, *writeback=False*)

A subclass of `Shelf` which exposes `first()`, `next()`, `previous()`, `last()` and `set_location()` which are available in the `bsddb` module but not in other database modules. The *dict* object passed to the constructor must support those methods. This is generally accomplished by calling one of `bsddb.hashopen()`, `bsddb.btopen()` or `bsddb.rnopen()`. The optional *protocol* and *writeback* parameters have the same interpretation as for the `Shelf` class.

class `shelve.DbfilenameShelf` (*filename*, *flag='c'*, *protocol=None*, *writeback=False*)

A subclass of `Shelf` which accepts a *filename* instead of a dict-like object. The underlying file will be opened using `anydbm.open()`. By default, the file will be created and opened for both read and write. The optional *flag* parameter has the same interpretation as for the `open()` function. The optional *protocol* and *writeback* parameters have the same interpretation as for the `Shelf` class.

11.4.2 Example

To summarize the interface (key is a string, data is an arbitrary object):

```
import shelve

d = shelve.open(filename) # open -- file may get suffix added by low-level
                           # library

d[key] = data             # store data at key (overwrites old data if
                           # using an existing key)
data = d[key]             # retrieve a COPY of data at key (raise KeyError if no
                           # such key)
del d[key]                # delete data stored at key (raises KeyError
                           # if no such key)
flag = d.has_key(key)     # true if the key exists
klist = d.keys()          # a list of all existing keys (slow!)

# as d was opened WITHOUT writeback=True, beware:
d['xx'] = range(4)        # this works as expected, but...
d['xx'].append(5)         # *this doesn't!* -- d['xx'] is STILL range(4)!

# having opened d without writeback=True, you need to code carefully:
temp = d['xx']             # extracts the copy
temp.append(5)            # mutates the copy
d['xx'] = temp            # stores the copy right back, to persist it

# or, d=shelve.open(filename,writeback=True) would let you just code
# d['xx'].append(5) and have it work as expected, BUT it would also
# consume more memory and make the d.close() operation slower.

d.close()                 # close it
```

더 보기:

Module *anydbm* Generic interface to dbm-style databases.

Module *bsddb* BSD db database interface.

Module *dbhash* Thin layer around the *bsddb* which provides an *open()* function like the other database modules.

Module *dbm* Standard Unix database interface.

Module *dumbdbm* Portable implementation of the dbm interface.

Module *gdbm* GNU database interface, based on the dbm interface.

Module *pickle* Object serialization used by *shelve*.

Module *cPickle* High-performance version of *pickle*.

11.5 marshal — Internal Python object serialization

This module contains functions that can read and write Python values in a binary format. The format is specific to Python, but independent of machine architecture issues (e.g., you can write a Python value to a file on a PC, transport the file to a Sun, and read it back there). Details of the format are undocumented on purpose; it may change between Python versions (although it rarely does).¹

This is not a general «persistence» module. For general persistence and transfer of Python objects through RPC calls, see the modules *pickle* and *shelve*. The *marshal* module exists mainly to support reading and writing the «pseudo-compiled» code for Python modules of .pyc files. Therefore, the Python maintainers reserve the right to modify the marshal format in backward incompatible ways should the need arise. If you're serializing and de-serializing Python objects, use the *pickle* module instead – the performance is comparable, version independence is guaranteed, and pickle supports a substantially wider range of objects than marshal.

경고: The *marshal* module is not intended to be secure against erroneous or maliciously constructed data. Never unmarshal data received from an untrusted or unauthenticated source.

Not all Python object types are supported; in general, only objects whose value is independent from a particular invocation of Python can be written and read by this module. The following types are supported: booleans, integers, long integers, floating point numbers, complex numbers, strings, Unicode objects, tuples, lists, sets, frozensets, dictionaries, and code objects, where it should be understood that tuples, lists, sets, frozensets and dictionaries are only supported as long as the values contained therein are themselves supported; and recursive lists, sets and dictionaries should not be written (they will cause infinite loops). The singletons *None*, *Ellipsis* and *StopIteration* can also be marshalled and unmarshalled.

경고: On machines where C's `long int` type has more than 32 bits (such as the DEC Alpha), it is possible to create plain Python integers that are longer than 32 bits. If such an integer is marshaled and read back in on a machine where C's `long int` type has only 32 bits, a Python long integer object is returned instead. While of a different type, the numeric value is the same. (This behavior is new in Python 2.2. In earlier versions, all but the least-significant 32 bits of the value were lost, and a warning message was printed.)

There are functions that read/write files as well as functions operating on strings.

The module defines these functions:

`marshal.dump(value, file[, version])`

Write the value on the open file. The value must be a supported type. The file must be an open file object such as `sys.stdout` or returned by `open()` or `os.popen()`. It may not be a wrapper such as `TemporaryFile` on Windows. It must be opened in binary mode ('wb' or 'w+b').

If the value has (or contains an object that has) an unsupported type, a *ValueError* exception is raised — but garbage data will also be written to the file. The object will not be properly read back by `load()`.

버전 2.4에 추가: The *version* argument indicates the data format that `dump` should use (see below).

`marshal.load(file)`

Read one value from the open file and return it. If no valid value is read (e.g. because the data has a different Python version's incompatible marshal format), raise *EOFError*, *ValueError* or *TypeError*. The file must be an open file object opened in binary mode ('rb' or 'r+b').

¹ The name of this module stems from a bit of terminology used by the designers of Modula-3 (amongst others), who use the term «marshalling» for shipping of data around in a self-contained form. Strictly speaking, «to marshal» means to convert some data from internal to external form (in an RPC buffer for instance) and «unmarshalling» for the reverse process.

참고: If an object containing an unsupported type was marshalled with `dump()`, `load()` will substitute `None` for the unmarshallable type.

`marshal.dumps(value[, version])`

Return the string that would be written to a file by `dump(value, file)`. The value must be a supported type. Raise a `ValueError` exception if value has (or contains an object that has) an unsupported type.

버전 2.4에 추가: The `version` argument indicates the data format that `dumps` should use (see below).

`marshal.loads(string)`

Convert the string to a value. If no valid value is found, raise `EOFError`, `ValueError` or `TypeError`. Extra characters in the string are ignored.

In addition, the following constants are defined:

`marshal.version`

Indicates the format that the module uses. Version 0 is the historical format, version 1 (added in Python 2.4) shares interned strings and version 2 (added in Python 2.5) uses a binary format for floating point numbers. The current version is 2.

버전 2.4에 추가.

11.6 anydbm — Generic access to DBM-style databases

참고: The `anydbm` module has been renamed to `dbm` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

`anydbm` is a generic interface to variants of the DBM database — `dbhash` (requires `bsddb`), `gdbm`, or `dbm`. If none of these modules is installed, the slow-but-simple implementation in module `dumbdbm` will be used.

`anydbm.open(filename[, flag[, mode]])`

Open the database file `filename` and return a corresponding object.

If the database file already exists, the `whichdb` module is used to determine its type and the appropriate module is used; if it does not exist, the first module listed above that can be imported is used.

The optional `flag` argument must be one of these values:

Value	Meaning
'r'	Open existing database for reading only (default)
'w'	Open existing database for reading and writing
'c'	Open database for reading and writing, creating it if it doesn't exist
'n'	Always create a new, empty database, open for reading and writing

If not specified, the default value is 'r'.

The optional `mode` argument is the Unix mode of the file, used only when the database has to be created. It defaults to octal 0666 (and will be modified by the prevailing umask).

exception `anydbm.error`

A tuple containing the exceptions that can be raised by each of the supported modules, with a unique exception also named `anydbm.error` as the first item — the latter is used when `anydbm.error` is raised.

The object returned by `open()` supports most of the same functionality as dictionaries; keys and their corresponding values can be stored, retrieved, and deleted, and the `has_key()` and `keys()` methods are available. Keys and values must always be strings.

The following example records some hostnames and a corresponding title, and then prints out the contents of the database:

```
import anydbm

# Open database, creating it if necessary.
db = anydbm.open('cache', 'c')

# Record some values
db['www.python.org'] = 'Python Website'
db['www.cnn.com'] = 'Cable News Network'

# Loop through contents. Other dictionary methods
# such as .keys(), .values() also work.
for k, v in db.iteritems():
    print k, '\t', v

# Storing a non-string key or value will raise an exception (most
# likely a TypeError).
db['www.yahoo.com'] = 4

# Close when done.
db.close()
```

In addition to the dictionary-like methods, `anydbm` objects provide the following method:

`anydbm.close()`
Close the `anydbm` database.

더 보기:

Module `dbhash` BSD db database interface.

Module `dbm` Standard Unix database interface.

Module `dumbdbm` Portable implementation of the `dbm` interface.

Module `gdbm` GNU database interface, based on the `dbm` interface.

Module `shelve` General object persistence built on top of the Python `dbm` interface.

Module `whichdb` Utility module used to determine the type of an existing database.

11.7 `whichdb` — Guess which DBM module created a database

참고: The `whichdb` module's only function has been put into the `dbm` module in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

The single function in this module attempts to guess which of the several simple database modules available—`dbm`, `gdbm`, or `dbhash`—should be used to open a given file.

`whichdb.whichdb(filename)`

Returns one of the following values: `None` if the file can't be opened because it's unreadable or doesn't exist; the empty string ('') if the file's format can't be guessed; or a string containing the required module name, such as 'dbm' or 'gdbm'.

11.8 dbm — Simple 《database》 interface

참고: The *dbm* module has been renamed to `dbm.ndbm` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

The *dbm* module provides an interface to the Unix 《(n)dbm》 library. Dbm objects behave like mappings (dictionaries), except that keys and values are always strings. Printing a dbm object doesn't print the keys and values, and the `items()` and `values()` methods are not supported.

This module can be used with the 《classic》 ndbm interface, the BSD DB compatibility interface, or the GNU GDBM compatibility interface. On Unix, the **configure** script will attempt to locate the appropriate header file to simplify building this module.

The module defines the following:

exception `dbm.error`

Raised on dbm-specific errors, such as I/O errors. *KeyError* is raised for general mapping errors like specifying an incorrect key.

dbm.library

Name of the ndbm implementation library used.

dbm.open (*filename*[, *flag*[, *mode*]])

Open a dbm database and return a dbm object. The *filename* argument is the name of the database file (without the `.dir` or `.pag` extensions; note that the BSD DB implementation of the interface will append the extension `.db` and only create one file).

The optional *flag* argument must be one of these values:

Value	Meaning
'r'	Open existing database for reading only (default)
'w'	Open existing database for reading and writing
'c'	Open database for reading and writing, creating it if it doesn't exist
'n'	Always create a new, empty database, open for reading and writing

The optional *mode* argument is the Unix mode of the file, used only when the database has to be created. It defaults to octal 0666 (and will be modified by the prevailing umask).

In addition to the dictionary-like methods, dbm objects provide the following method:

dbm.close ()

Close the dbm database.

더 보기:

Module *anydbm* Generic interface to dbm-style databases.

Module *gdbm* Similar interface to the GNU GDBM library.

Module *whichdb* Utility module used to determine the type of an existing database.

11.9 gdbm — GNU's reinterpretation of dbm

참고: The `gdbm` module has been renamed to `dbm.gnu` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

This module is quite similar to the `dbm` module, but uses `gdbm` instead to provide some additional functionality. Please note that the file formats created by `gdbm` and `dbm` are incompatible.

The `gdbm` module provides an interface to the GNU DBM library. `gdbm` objects behave like mappings (dictionaries), except that keys and values are always strings. Printing a `gdbm` object doesn't print the keys and values, and the `items()` and `values()` methods are not supported.

The module defines the following constant and functions:

exception `gdbm.error`

Raised on `gdbm`-specific errors, such as I/O errors. `KeyError` is raised for general mapping errors like specifying an incorrect key.

`gdbm.open(filename[, flag[, mode]])`

Open a `gdbm` database and return a `gdbm` object. The *filename* argument is the name of the database file.

The optional *flag* argument can be:

Value	Meaning
'r'	Open existing database for reading only (default)
'w'	Open existing database for reading and writing
'c'	Open database for reading and writing, creating it if it doesn't exist
'n'	Always create a new, empty database, open for reading and writing

The following additional characters may be appended to the flag to control how the database is opened:

Value	Meaning
'f'	Open the database in fast mode. Writes to the database will not be synchronized.
's'	Synchronized mode. This will cause changes to the database to be immediately written to the file.
'u'	Do not lock database.

Not all flags are valid for all versions of `gdbm`. The module constant `open_flags` is a string of supported flag characters. The exception `error` is raised if an invalid flag is specified.

The optional *mode* argument is the Unix mode of the file, used only when the database has to be created. It defaults to octal 0666.

In addition to the dictionary-like methods, `gdbm` objects have the following methods:

`gdbm.firstkey()`

It's possible to loop over every key in the database using this method and the `nextkey()` method. The traversal is ordered by `gdbm`'s internal hash values, and won't be sorted by the key values. This method returns the starting key.

`gdbm.nextkey(key)`

Returns the key that follows *key* in the traversal. The following code prints every key in the database `db`, without having to create a list in memory that contains them all:

```
k = db.firstkey()
while k != None:
    print k
    k = db.nextkey(k)
```

`gdbm.reorganize()`

If you have carried out a lot of deletions and would like to shrink the space used by the `gdbm` file, this routine will reorganize the database. `gdbm` will not shorten the length of a database file except by using this reorganization; otherwise, deleted file space will be kept and reused as new (key, value) pairs are added.

`gdbm.sync()`

When the database has been opened in fast mode, this method forces any unwritten data to be written to the disk.

`gdbm.close()`

Close the `gdbm` database.

더 보기:

Module `anydbm` Generic interface to dbm-style databases.

Module `whichdb` Utility module used to determine the type of an existing database.

11.10 `dbhash` — DBM-style interface to the BSD database library

버전 2.6부터 폐지: The `dbhash` module has been removed in Python 3.

The `dbhash` module provides a function to open databases using the BSD `db` library. This module mirrors the interface of the other Python database modules that provide access to DBM-style databases. The `bsddb` module is required to use `dbhash`.

This module provides an exception and a function:

exception `dbhash.error`

Exception raised on database errors other than `KeyError`. It is a synonym for `bsddb.error`.

`dbhash.open(path[, flag[, mode]])`

Open a `db` database and return the database object. The `path` argument is the name of the database file.

The `flag` argument can be:

Value	Meaning
'r'	Open existing database for reading only (default)
'w'	Open existing database for reading and writing
'c'	Open database for reading and writing, creating it if it doesn't exist
'n'	Always create a new, empty database, open for reading and writing

For platforms on which the BSD `db` library supports locking, an 'l' can be appended to indicate that locking should be used.

The optional `mode` parameter is used to indicate the Unix permission bits that should be set if a new database must be created; this will be masked by the current `umask` value for the process.

더 보기:

Module `anydbm` Generic interface to dbm-style databases.

Module `bsddb` Lower-level interface to the BSD `db` library.

Module `whichdb` Utility module used to determine the type of an existing database.

11.10.1 Database Objects

The database objects returned by `open()` provide the methods common to all the DBM-style databases and mapping objects. The following methods are available in addition to the standard methods.

`dbhash.first()`

It's possible to loop over every key/value pair in the database using this method and the `next()` method. The traversal is ordered by the databases internal hash values, and won't be sorted by the key values. This method returns the starting key.

`dbhash.last()`

Return the last key/value pair in a database traversal. This may be used to begin a reverse-order traversal; see `previous()`.

`dbhash.next()`

Returns the key next key/value pair in a database traversal. The following code prints every key in the database `db`, without having to create a list in memory that contains them all:

```
print db.first()
for i in xrange(1, len(db)):
    print db.next()
```

`dbhash.previous()`

Returns the previous key/value pair in a forward-traversal of the database. In conjunction with `last()`, this may be used to implement a reverse-order traversal.

`dbhash.sync()`

This method forces any unwritten data to be written to the disk.

11.11 bsddb — Interface to Berkeley DB library

버전 2.6부터 폐지: The `bsddb` module has been removed in Python 3.

The `bsddb` module provides an interface to the Berkeley DB library. Users can create hash, btree or record based library files using the appropriate open call. Bsddb objects behave generally like dictionaries. Keys and values must be strings, however, so to use other objects as keys or to store other kinds of objects the user must serialize them somehow, typically using `marshal.dumps()` or `pickle.dumps()`.

The `bsddb` module requires a Berkeley DB library version from 4.0 thru 4.7.

더 보기:

<http://www.jcea.es/programacion/pybsddb.htm> The website with documentation for the `bsddb.db` Python Berkeley DB interface that closely mirrors the object oriented interface provided in Berkeley DB 4.x itself.

<http://www.oracle.com/database/berkeley-db/> The Berkeley DB library.

A more modern DB, DBEnv and DBSequence object interface is available in the `bsddb.db` module which closely matches the Berkeley DB C API documented at the above URLs. Additional features provided by the `bsddb.db` API include fine tuning, transactions, logging, and multiprocess concurrent database access.

The following is a description of the legacy `bsddb` interface compatible with the old Python bsddb module. Starting in Python 2.5 this interface should be safe for multithreaded access. The `bsddb.db` API is recommended for threading users as it provides better control.

The `bsddb` module defines the following functions that create objects that access the appropriate type of Berkeley DB file. The first two arguments of each function are the same. For ease of portability, only the first two arguments should be used in most instances.

`bsddb.hashopen(filename[, flag[, mode[, pgsz[, ffactor[, nelem[, cachesize[, lorder[, hflags]]]]]]])`

Open the hash format file named *filename*. Files never intended to be preserved on disk may be created by passing `None` as the *filename*. The optional *flag* identifies the mode used to open the file. It may be 'r' (read only), 'w' (read-write), 'c' (read-write - create if necessary; the default) or 'n' (read-write - truncate to zero length). The other arguments are rarely used and are just passed to the low-level `dbopen()` function. Consult the Berkeley DB documentation for their use and interpretation.

`bsddb.btopen(filename[, flag[, mode[, btflags[, cachesize[, maxkeypage[, minkeypage[, pgsz[, lorder]]]]]])`

Open the btree format file named *filename*. Files never intended to be preserved on disk may be created by passing `None` as the *filename*. The optional *flag* identifies the mode used to open the file. It may be 'r' (read only), 'w' (read-write), 'c' (read-write - create if necessary; the default) or 'n' (read-write - truncate to zero length). The other arguments are rarely used and are just passed to the low-level `dbopen` function. Consult the Berkeley DB documentation for their use and interpretation.

`bsddb.rnopen(filename[, flag[, mode[, rnflags[, cachesize[, pgsz[, lorder[, rlen[, delim[, source[, pad]]]]]])`

Open a DB record format file named *filename*. Files never intended to be preserved on disk may be created by passing `None` as the *filename*. The optional *flag* identifies the mode used to open the file. It may be 'r' (read only), 'w' (read-write), 'c' (read-write - create if necessary; the default) or 'n' (read-write - truncate to zero length). The other arguments are rarely used and are just passed to the low-level `dbopen` function. Consult the Berkeley DB documentation for their use and interpretation.

참고: Beginning in 2.3 some Unix versions of Python may have a `bsddb185` module. This is present *only* to allow backwards compatibility with systems which ship with the old Berkeley DB 1.85 database library. The `bsddb185` module should never be used directly in new code. The module has been removed in Python 3. If you find you still need it look in PyPI.

더 보기:

Module `dbhash` DBM-style interface to the `bsddb`

11.11.1 Hash, BTree and Record Objects

Once instantiated, hash, btree and record objects support the same methods as dictionaries. In addition, they support the methods listed below.

버전 2.3.1에서 변경: Added dictionary methods.

`bsddbobject.close()`

Close the underlying file. The object can no longer be accessed. Since there is no open `open()` method for these objects, to open the file again a new `bsddb` module open function must be called.

`bsddbobject.keys()`

Return the list of keys contained in the DB file. The order of the list is unspecified and should not be relied on. In particular, the order of the list returned is different for different file formats.

`bsddbobject.has_key(key)`

Return 1 if the DB file contains the argument as a key.

`bsddbobject.set_location(key)`

Set the cursor to the item indicated by *key* and return a tuple containing the key and its value. For binary tree databases (opened using `btopen()`), if *key* does not actually exist in the database, the cursor will point to the next item in sorted order and return that key and value. For other databases, `KeyError` will be raised if *key* is not found in the database.

`bsddbobject.first()`

Set the cursor to the first item in the DB file and return it. The order of keys in the file is unspecified, except in the case of B-Tree databases. This method raises `bsddb.error` if the database is empty.

`bsddbobject.next()`

Set the cursor to the next item in the DB file and return it. The order of keys in the file is unspecified, except in the case of B-Tree databases.

`bsddbobject.previous()`

Set the cursor to the previous item in the DB file and return it. The order of keys in the file is unspecified, except in the case of B-Tree databases. This is not supported on hashtable databases (those opened with `hashopen()`).

`bsddbobject.last()`

Set the cursor to the last item in the DB file and return it. The order of keys in the file is unspecified. This is not supported on hashtable databases (those opened with `hashopen()`). This method raises `bsddb.error` if the database is empty.

`bsddbobject.sync()`

Synchronize the database on disk.

Example:

```
>>> import bsddb
>>> db = bsddb.btopen('spam.db', 'c')
>>> for i in range(10): db['%d'%i] = '%d'% (i*i)
...
>>> db['3']
'9'
>>> db.keys()
['0', '1', '2', '3', '4', '5', '6', '7', '8', '9']
>>> db.first()
('0', '0')
>>> db.next()
('1', '1')
>>> db.last()
('9', '81')
>>> db.set_location('2')
('2', '4')
>>> db.previous()
('1', '1')
>>> for k, v in db.iteritems():
...     print k, v
0 0
1 1
2 4
3 9
4 16
5 25
6 36
7 49
8 64
9 81
>>> '8' in db
True
>>> db.sync()
0
```

11.12 dumbdbm — Portable DBM implementation

참고: The `dumbdbm` module has been renamed to `dbm.dumb` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

참고: The `dumbdbm` module is intended as a last resort fallback for the `anydbm` module when no more robust module is available. The `dumbdbm` module is not written for speed and is not nearly as heavily used as the other database modules.

The `dumbdbm` module provides a persistent dictionary-like interface which is written entirely in Python. Unlike other modules such as `gdbm` and `bsddb`, no external library is required. As with other persistent mappings, the keys and values must always be strings.

The module defines the following:

exception `dumbdbm.error`

Raised on dumbdbm-specific errors, such as I/O errors. `KeyError` is raised for general mapping errors like specifying an incorrect key.

`dumbdbm.open(filename[, flag[, mode]])`

Open a dumbdbm database and return a dumbdbm object. The *filename* argument is the basename of the database file (without any specific extensions). When a dumbdbm database is created, files with `.dat` and `.dir` extensions are created.

The optional *flag* argument is currently ignored; the database is always opened for update, and will be created if it does not exist.

The optional *mode* argument is the Unix mode of the file, used only when the database has to be created. It defaults to octal 0666 (and will be modified by the prevailing umask).

버전 2.2에서 변경: The *mode* argument was ignored in earlier versions.

In addition to the dictionary-like methods, dumbdbm objects provide the following method:

`dumbdbm.close()`

Close the dumbdbm database.

더 보기:

Module `anydbm` Generic interface to dbm-style databases.

Module `dbm` Similar interface to the DBM/NDBM library.

Module `gdbm` Similar interface to the GNU GDBM library.

Module `shelve` Persistence module which stores non-string data.

Module `whichdb` Utility module used to determine the type of an existing database.

11.12.1 Dumbdbm Objects

In addition to the methods provided by the `UserDict.DictMixin` class, dumbdbm objects provide the following methods.

`dumbdbm.sync()`

Synchronize the on-disk directory and data files. This method is called by the `sync()` method of `Shelve` objects.

11.13 sqlite3 — DB-API 2.0 interface for SQLite databases

버전 2.5에 추가.

SQLite is a C library that provides a lightweight disk-based database that doesn't require a separate server process and allows accessing the database using a nonstandard variant of the SQL query language. Some applications can use SQLite for internal data storage. It's also possible to prototype an application using SQLite and then port the code to a larger database such as PostgreSQL or Oracle.

The sqlite3 module was written by Gerhard Häring. It provides a SQL interface compliant with the DB-API 2.0 specification described by [PEP 249](#).

To use the module, you must first create a `Connection` object that represents the database. Here the data will be stored in the `example.db` file:

```
import sqlite3
conn = sqlite3.connect('example.db')
```

You can also supply the special name `:memory:` to create a database in RAM.

Once you have a `Connection`, you can create a `Cursor` object and call its `execute()` method to perform SQL commands:

```
c = conn.cursor()

# Create table
c.execute('CREATE TABLE stocks
          (date text, trans text, symbol text, qty real, price real)')

# Insert a row of data
c.execute("INSERT INTO stocks VALUES ('2006-01-05', 'BUY', 'RHAT', 100, 35.14)")

# Save (commit) the changes
conn.commit()

# We can also close the connection if we are done with it.
# Just be sure any changes have been committed or they will be lost.
conn.close()
```

The data you've saved is persistent and is available in subsequent sessions:

```
import sqlite3
conn = sqlite3.connect('example.db')
c = conn.cursor()
```

Usually your SQL operations will need to use values from Python variables. You shouldn't assemble your query using Python's string operations because doing so is insecure; it makes your program vulnerable to an SQL injection attack (see <https://xkcd.com/327/> for humorous example of what can go wrong).

Instead, use the DB-API's parameter substitution. Put `?` as a placeholder wherever you want to use a value, and then provide a tuple of values as the second argument to the cursor's `execute()` method. (Other database modules may use a different placeholder, such as `%s` or `:1`.) For example:

```
# Never do this -- insecure!
symbol = 'RHAT'
c.execute("SELECT * FROM stocks WHERE symbol = '%s'" % symbol)

# Do this instead
t = ('RHAT',)
c.execute('SELECT * FROM stocks WHERE symbol=?', t)
print c.fetchone()

# Larger example that inserts many records at a time
purchases = [('2006-03-28', 'BUY', 'IBM', 1000, 45.00),
              ('2006-04-05', 'BUY', 'MSFT', 1000, 72.00),
              ('2006-04-06', 'SELL', 'IBM', 500, 53.00),
              ]
c.executemany('INSERT INTO stocks VALUES (?, ?, ?, ?, ?)', purchases)
```

To retrieve data after executing a `SELECT` statement, you can either treat the cursor as an *iterator*, call the cursor's `fetchone()` method to retrieve a single matching row, or call `fetchall()` to get a list of the matching rows.

This example uses the iterator form:

```
>>> for row in c.execute('SELECT * FROM stocks ORDER BY price'):
      print row

(u'2006-01-05', u'BUY', u'RHAT', 100, 35.14)
(u'2006-03-28', u'BUY', u'IBM', 1000, 45.0)
(u'2006-04-06', u'SELL', u'IBM', 500, 53.0)
(u'2006-04-05', u'BUY', u'MSFT', 1000, 72.0)
```

더 보기:

<https://github.com/ghaering/pysqlite> The `pysqlite` web page – `sqlite3` is developed externally under the name `《pysqlite》`.

<https://www.sqlite.org> The `SQLite` web page; the documentation describes the syntax and the available data types for the supported `SQL` dialect.

<http://www.w3schools.com/sql/> Tutorial, reference and examples for learning `SQL` syntax.

PEP 249 - Database API Specification 2.0 PEP written by Marc-André Lemburg.

11.13.1 Module functions and constants

`sqlite3.version`

The version number of this module, as a string. This is not the version of the `SQLite` library.

`sqlite3.version_info`

The version number of this module, as a tuple of integers. This is not the version of the `SQLite` library.

`sqlite3.sqlite_version`

The version number of the run-time `SQLite` library, as a string.

`sqlite3.sqlite_version_info`

The version number of the run-time `SQLite` library, as a tuple of integers.

sqlite3.PARSE_DECLTYPES

This constant is meant to be used with the *detect_types* parameter of the *connect()* function.

Setting it makes the *sqlite3* module parse the declared type for each column it returns. It will parse out the first word of the declared type, i. e. for `«integer primary key»`, it will parse out `«integer»`, or for `«number(10)»` it will parse out `«number»`. Then for that column, it will look into the converters dictionary and use the converter function registered for that type there.

sqlite3.PARSE_COLNAMES

This constant is meant to be used with the *detect_types* parameter of the *connect()* function.

Setting this makes the SQLite interface parse the column name for each column it returns. It will look for a string formed `[mytype]` in there, and then decide that `«mytype»` is the type of the column. It will try to find an entry of `«mytype»` in the converters dictionary and then use the converter function found there to return the value. The column name found in *Cursor.description* is only the first word of the column name, i. e. if you use something like `'as "x [datetime]"'` in your SQL, then we will parse out everything until the first blank for the column name: the column name would simply be `«x»`.

sqlite3.connect(*database*[, *timeout*, *detect_types*, *isolation_level*, *check_same_thread*, *factory*,
cached_statements])

Opens a connection to the SQLite database file *database*. You can use `":memory:"` to open a database connection to a database that resides in RAM instead of on disk.

When a database is accessed by multiple connections, and one of the processes modifies the database, the SQLite database is locked until that transaction is committed. The *timeout* parameter specifies how long the connection should wait for the lock to go away until raising an exception. The default for the timeout parameter is 5.0 (five seconds).

For the *isolation_level* parameter, please see the *Connection.isolation_level* property of *Connection* objects.

SQLite natively supports only the types TEXT, INTEGER, REAL, BLOB and NULL. If you want to use other types you must add support for them yourself. The *detect_types* parameter and the using custom **converters** registered with the module-level *register_converter()* function allow you to easily do that.

detect_types defaults to 0 (i. e. off, no type detection), you can set it to any combination of *PARSE_DECLTYPES* and *PARSE_COLNAMES* to turn type detection on.

By default, the *sqlite3* module uses its *Connection* class for the connect call. You can, however, subclass the *Connection* class and make *connect()* use your class instead by providing your class for the *factory* parameter.

Consult the section *SQLite and Python types* of this manual for details.

The *sqlite3* module internally uses a statement cache to avoid SQL parsing overhead. If you want to explicitly set the number of statements that are cached for the connection, you can set the *cached_statements* parameter. The currently implemented default is to cache 100 statements.

sqlite3.register_converter(*typename*, *callable*)

Registers a callable to convert a bytestring from the database into a custom Python type. The callable will be invoked for all database values that are of the type *typename*. Confer the parameter *detect_types* of the *connect()* function for how the type detection works. Note that *typename* and the name of the type in your query are matched in case-insensitive manner.

sqlite3.register_adapter(*type*, *callable*)

Registers a callable to convert the custom Python type *type* into one of SQLite's supported types. The callable *callable* accepts as single parameter the Python value, and must return a value of the following types: int, long, float, str (UTF-8 encoded), unicode or buffer.

sqlite3.complete_statement(*sql*)

Returns *True* if the string *sql* contains one or more complete SQL statements terminated by semicolons. It does

not verify that the SQL is syntactically correct, only that there are no unclosed string literals and the statement is terminated by a semicolon.

This can be used to build a shell for SQLite, as in the following example:

```
# A minimal SQLite shell for experiments

import sqlite3

con = sqlite3.connect(":memory:")
con.isolation_level = None
cur = con.cursor()

buffer = ""

print "Enter your SQL commands to execute in sqlite3."
print "Enter a blank line to exit."

while True:
    line = raw_input()
    if line == "":
        break
    buffer += line
    if sqlite3.complete_statement(buffer):
        try:
            buffer = buffer.strip()
            cur.execute(buffer)

            if buffer.lstrip().upper().startswith("SELECT"):
                print cur.fetchall()
        except sqlite3.Error as e:
            print "An error occurred:", e.args[0]
        buffer = ""

con.close()
```

`sqlite3.enable_callback_tracebacks(flag)`

By default you will not get any tracebacks in user-defined functions, aggregates, converters, authorizer callbacks etc. If you want to debug them, you can call this function with *flag* set to `True`. Afterwards, you will get tracebacks from callbacks on `sys.stderr`. Use `False` to disable the feature again.

11.13.2 Connection Objects

class `sqlite3.Connection`

A SQLite database connection has the following attributes and methods:

isolation_level

Get or set the current isolation level. `None` for autocommit mode or one of «DEFERRED», «IMMEDIATE» or «EXCLUSIVE». See section [Controlling Transactions](#) for a more detailed explanation.

cursor (*factory=Cursor*)

The cursor method accepts a single optional parameter *factory*. If supplied, this must be a callable returning an instance of `Cursor` or its subclasses.

commit()

This method commits the current transaction. If you don't call this method, anything you did since the last

call to `commit()` is not visible from other database connections. If you wonder why you don't see the data you've written to the database, please check you didn't forget to call this method.

rollback()

This method rolls back any changes to the database since the last call to `commit()`.

close()

This closes the database connection. Note that this does not automatically call `commit()`. If you just close your database connection without calling `commit()` first, your changes will be lost!

execute(sql[, parameters])

This is a nonstandard shortcut that creates an intermediate cursor object by calling the cursor method, then calls the cursor's `execute` method with the parameters given.

executemany(sql[, parameters])

This is a nonstandard shortcut that creates an intermediate cursor object by calling the cursor method, then calls the cursor's `executemany` method with the parameters given.

executescript(sql_script)

This is a nonstandard shortcut that creates an intermediate cursor object by calling the cursor method, then calls the cursor's `executescript` method with the parameters given.

create_function(name, num_params, func)

Creates a user-defined function that you can later use from within SQL statements under the function name *name*. *num_params* is the number of parameters the function accepts, and *func* is a Python callable that is called as the SQL function.

The function can return any of the types supported by SQLite: unicode, str, int, long, float, buffer and None.

Example:

```
import sqlite3
import md5

def md5sum(t):
    return md5.md5(t).hexdigest()

con = sqlite3.connect(":memory:")
con.create_function("md5", 1, md5sum)
cur = con.cursor()
cur.execute("select md5(?)", ("foo",))
print cur.fetchone()[0]
```

create_aggregate(name, num_params, aggregate_class)

Creates a user-defined aggregate function.

The aggregate class must implement a `step` method, which accepts the number of parameters *num_params*, and a `finalize` method which will return the final result of the aggregate.

The `finalize` method can return any of the types supported by SQLite: unicode, str, int, long, float, buffer and None.

Example:

```
import sqlite3

class MySum:
    def __init__(self):
        self.count = 0
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

def step(self, value):
    self.count += value

def finalize(self):
    return self.count

con = sqlite3.connect(":memory:")
con.create_aggregate("mysum", 1, MySum)
cur = con.cursor()
cur.execute("create table test(i)")
cur.execute("insert into test(i) values (1)")
cur.execute("insert into test(i) values (2)")
cur.execute("select mysum(i) from test")
print cur.fetchone()[0]

```

create_collation (*name*, *callable*)

Creates a collation with the specified *name* and *callable*. The callable will be passed two string arguments. It should return -1 if the first is ordered lower than the second, 0 if they are ordered equal and 1 if the first is ordered higher than the second. Note that this controls sorting (ORDER BY in SQL) so your comparisons don't affect other SQL operations.

Note that the callable will get its parameters as Python bytestrings, which will normally be encoded in UTF-8.

The following example shows a custom collation that sorts 《the wrong way》:

```

import sqlite3

def collate_reverse(string1, string2):
    return -cmp(string1, string2)

con = sqlite3.connect(":memory:")
con.create_collation("reverse", collate_reverse)

cur = con.cursor()
cur.execute("create table test(x)")
cur.executemany("insert into test(x) values (?)", [("a",), ("b",)])
cur.execute("select x from test order by x collate reverse")
for row in cur:
    print row
con.close()

```

To remove a collation, call `create_collation` with `None` as callable:

```
con.create_collation("reverse", None)
```

interrupt ()

You can call this method from a different thread to abort any queries that might be executing on the connection. The query will then abort and the caller will get an exception.

set_authorizer (*authorizer_callback*)

This routine registers a callback. The callback is invoked for each attempt to access a column of a table in the database. The callback should return `SQLITE_OK` if access is allowed, `SQLITE_DENY` if the entire SQL statement should be aborted with an error and `SQLITE_IGNORE` if the column should be treated as a NULL value. These constants are available in the `sqlite3` module.

The first argument to the callback signifies what kind of operation is to be authorized. The second and third argument will be arguments or `None` depending on the first argument. The 4th argument is the name of the

database (《main》, 《temp》, etc.) if applicable. The 5th argument is the name of the inner-most trigger or view that is responsible for the access attempt or *None* if this access attempt is directly from input SQL code.

Please consult the SQLite documentation about the possible values for the first argument and the meaning of the second and third argument depending on the first one. All necessary constants are available in the *sqlite3* module.

set_progress_handler (*handler*, *n*)

This routine registers a callback. The callback is invoked for every *n* instructions of the SQLite virtual machine. This is useful if you want to get called from SQLite during long-running operations, for example to update a GUI.

If you want to clear any previously installed progress handler, call the method with *None* for *handler*.

버전 2.6에 추가.

enable_load_extension (*enabled*)

This routine allows/disallows the SQLite engine to load SQLite extensions from shared libraries. SQLite extensions can define new functions, aggregates or whole new virtual table implementations. One well-known extension is the fulltext-search extension distributed with SQLite.

Loadable extensions are disabled by default. See¹.

버전 2.7에 추가.

```
import sqlite3

con = sqlite3.connect(":memory:")

# enable extension loading
con.enable_load_extension(True)

# Load the fulltext search extension
con.execute("select load_extension('./fts3.so')")

# alternatively you can load the extension using an API call:
# con.load_extension("./fts3.so")

# disable extension loading again
con.enable_load_extension(False)

# example from SQLite wiki
con.execute("create virtual table recipe using fts3(name, ingredients)")
con.executescript("""
    insert into recipe (name, ingredients) values ('broccoli stew', 'broccoli
↪peppers cheese tomatoes');
    insert into recipe (name, ingredients) values ('pumpkin stew', 'pumpkin
↪onions garlic celery');
    insert into recipe (name, ingredients) values ('broccoli pie', 'broccoli
↪cheese onions flour');
    insert into recipe (name, ingredients) values ('pumpkin pie', 'pumpkin
↪sugar flour butter');
""")
for row in con.execute("select rowid, name, ingredients from recipe where
↪name match 'pie')":
    print row
```

¹ The *sqlite3* module is not built with loadable extension support by default, because some platforms (notably Mac OS X) have SQLite libraries which are compiled without this feature. To get loadable extension support, you must modify *setup.py* and remove the line that sets *SQLITE_OMIT_LOAD_EXTENSION*.

load_extension (*path*)

This routine loads a SQLite extension from a shared library. You have to enable extension loading with `enable_load_extension()` before you can use this routine.

Loadable extensions are disabled by default. See¹.

버전 2.7에 추가.

row_factory

You can change this attribute to a callable that accepts the cursor and the original row as a tuple and will return the real result row. This way, you can implement more advanced ways of returning results, such as returning an object that can also access columns by name.

Example:

```
import sqlite3

def dict_factory(cursor, row):
    d = {}
    for idx, col in enumerate(cursor.description):
        d[col[0]] = row[idx]
    return d

con = sqlite3.connect(":memory:")
con.row_factory = dict_factory
cur = con.cursor()
cur.execute("select 1 as a")
print cur.fetchone() ["a"]
```

If returning a tuple doesn't suffice and you want name-based access to columns, you should consider setting `row_factory` to the highly-optimized `sqlite3.Row` type. `Row` provides both index-based and case-insensitive name-based access to columns with almost no memory overhead. It will probably be better than your own custom dictionary-based approach or even a `db_row` based solution.

text_factory

Using this attribute you can control what objects are returned for the TEXT data type. By default, this attribute is set to `unicode` and the `sqlite3` module will return Unicode objects for TEXT. If you want to return bytestrings instead, you can set it to `str`.

For efficiency reasons, there's also a way to return Unicode objects only for non-ASCII data, and bytestrings otherwise. To activate it, set this attribute to `sqlite3.OptimizedUnicode`.

You can also set it to any other callable that accepts a single bytestring parameter and returns the resulting object.

See the following example code for illustration:

```
import sqlite3

con = sqlite3.connect(":memory:")
cur = con.cursor()

AUSTRIA = u"\xd6sterreich"

# by default, rows are returned as Unicode
cur.execute("select ?", (AUSTRIA,))
row = cur.fetchone()
assert row[0] == AUSTRIA

# but we can make sqlite3 always return bytestrings ...
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

con.text_factory = str
cur.execute("select ?", (AUSTRIA,))
row = cur.fetchone()
assert type(row[0]) is str
# the bytestrings will be encoded in UTF-8, unless you stored garbage in the
# database ...
assert row[0] == AUSTRIA.encode("utf-8")

# we can also implement a custom text_factory ...
# here we implement one that will ignore Unicode characters that cannot be
# decoded from UTF-8
con.text_factory = lambda x: unicode(x, "utf-8", "ignore")
cur.execute("select ?", ("this is latin1 and would normally create errors" +
                        u"\xe4\xf6\xfc".encode("latin1"),))
row = cur.fetchone()
assert type(row[0]) is unicode

# sqlite3 offers a built-in optimized text_factory that will return bytestring
# objects, if the data is in ASCII only, and otherwise return unicode objects
con.text_factory = sqlite3.OptimizedUnicode
cur.execute("select ?", (AUSTRIA,))
row = cur.fetchone()
assert type(row[0]) is unicode

cur.execute("select ?", ("Germany",))
row = cur.fetchone()
assert type(row[0]) is str

```

total_changes

Returns the total number of database rows that have been modified, inserted, or deleted since the database connection was opened.

iterdump

Returns an iterator to dump the database in an SQL text format. Useful when saving an in-memory database for later restoration. This function provides the same capabilities as the `.dump` command in the **sqlite3** shell.

버전 2.6에 추가.

Example:

```

# Convert file existing_db.db to SQL dump file dump.sql
import sqlite3, os

con = sqlite3.connect('existing_db.db')
with open('dump.sql', 'w') as f:
    for line in con.iterdump():
        f.write('%s\n' % line)

```

11.13.3 Cursor Objects

class `sqlite3.Cursor`

A *Cursor* instance has the following attributes and methods.

execute (*sql* [, *parameters*])

Executes an SQL statement. The SQL statement may be parameterized (i. e. placeholders instead of SQL literals). The *sqlite3* module supports two kinds of placeholders: question marks (qmark style) and named placeholders (named style).

Here's an example of both styles:

```
import sqlite3

con = sqlite3.connect(":memory:")
cur = con.cursor()
cur.execute("create table people (name_last, age)")

who = "Yeltsin"
age = 72

# This is the qmark style:
cur.execute("insert into people values (?, ?)", (who, age))

# And this is the named style:
cur.execute("select * from people where name_last=:who and age=:age", {"who": who, "age": age})

print cur.fetchone()
```

execute() will only execute a single SQL statement. If you try to execute more than one statement with it, it will raise a Warning. Use *executescript()* if you want to execute multiple SQL statements with one call.

executemany (*sql*, *seq_of_parameters*)

Executes an SQL command against all parameter sequences or mappings found in the sequence *sql*. The *sqlite3* module also allows using an *iterator* yielding parameters instead of a sequence.

```
import sqlite3

class IterChars:
    def __init__(self):
        self.count = ord('a')

    def __iter__(self):
        return self

    def next(self):
        if self.count > ord('z'):
            raise StopIteration
        self.count += 1
        return (chr(self.count - 1),) # this is a 1-tuple

con = sqlite3.connect(":memory:")
cur = con.cursor()
cur.execute("create table characters(c)")

theIter = IterChars()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
cur.executemany("insert into characters(c) values (?)", theIter)

cur.execute("select c from characters")
print cur.fetchall()
```

Here's a shorter example using a *generator*:

```
import sqlite3
import string

def char_generator():
    for c in string.lowercase:
        yield (c,)

con = sqlite3.connect(":memory:")
cur = con.cursor()
cur.execute("create table characters(c)")

cur.executemany("insert into characters(c) values (?)", char_generator())

cur.execute("select c from characters")
print cur.fetchall()
```

executescript (*sql_script*)

This is a nonstandard convenience method for executing multiple SQL statements at once. It issues a COMMIT statement first, then executes the SQL script it gets as a parameter.

sql_script can be a bytestring or a Unicode string.

Example:

```
import sqlite3

con = sqlite3.connect(":memory:")
cur = con.cursor()
cur.executescript("""
    create table person(
        firstname,
        lastname,
        age
    );

    create table book(
        title,
        author,
        published
    );

    insert into book(title, author, published)
    values (
        'Dirk Gently's Holistic Detective Agency',
        'Douglas Adams',
        1987
    );
""")
```

fetchone ()

Fetches the next row of a query result set, returning a single sequence, or *None* when no more data is available.

fetchmany (*[size=cursor.arraysize]*)

Fetches the next set of rows of a query result, returning a list. An empty list is returned when no more rows are available.

The number of rows to fetch per call is specified by the *size* parameter. If it is not given, the cursor's *arraysize* determines the number of rows to be fetched. The method should try to fetch as many rows as indicated by the *size* parameter. If this is not possible due to the specified number of rows not being available, fewer rows may be returned.

Note there are performance considerations involved with the *size* parameter. For optimal performance, it is usually best to use the *arraysize* attribute. If the *size* parameter is used, then it is best for it to retain the same value from one *fetchmany()* call to the next.

fetchall ()

Fetches all (remaining) rows of a query result, returning a list. Note that the cursor's *arraysize* attribute can affect the performance of this operation. An empty list is returned when no rows are available.

rowcount

Although the *Cursor* class of the *sqlite3* module implements this attribute, the database engine's own support for the determination of «rows affected»/«rows selected» is quirky.

For *executemany()* statements, the number of modifications are summed up into *rowcount*.

As required by the Python DB API Spec, the *rowcount* attribute «is -1 in case no *executeXX()* has been performed on the cursor or the rowcount of the last operation is not determinable by the interface». This includes *SELECT* statements because we cannot determine the number of rows a query produced until all rows were fetched.

With SQLite versions before 3.6.5, *rowcount* is set to 0 if you make a *DELETE FROM table* without any condition.

lastrowid

This read-only attribute provides the rowid of the last modified row. It is only set if you issued an *INSERT* statement using the *execute()* method. For operations other than *INSERT* or when *executemany()* is called, *lastrowid* is set to *None*.

description

This read-only attribute provides the column names of the last query. To remain compatible with the Python DB API, it returns a 7-tuple for each column where the last six items of each tuple are *None*.

It is set for *SELECT* statements without any matching rows as well.

connection

This read-only attribute provides the SQLite database *Connection* used by the *Cursor* object. A *Cursor* object created by calling *con.cursor()* will have a *connection* attribute that refers to *con*:

```
>>> con = sqlite3.connect(":memory:")
>>> cur = con.cursor()
>>> cur.connection == con
True
```

11.13.4 Row Objects

class `sqlite3.Row`

A *Row* instance serves as a highly optimized *row_factory* for *Connection* objects. It tries to mimic a tuple in most of its features.

It supports mapping access by column name and index, iteration, representation, equality testing and `len()`.

If two *Row* objects have exactly the same columns and their members are equal, they compare equal.

버전 2.6에서 변경: Added iteration and equality (hashability).

keys()

This method returns a list of column names. Immediately after a query, it is the first member of each tuple in *Cursor.description*.

버전 2.6에 추가.

Let's assume we initialize a table as in the example given above:

```
conn = sqlite3.connect(":memory:")
c = conn.cursor()
c.execute('create table stocks
(date text, trans text, symbol text,
 qty real, price real)')
c.execute("""insert into stocks
          values ('2006-01-05', 'BUY', 'RHAT', 100, 35.14) """)
conn.commit()
c.close()
```

Now we plug *Row* in:

```
>>> conn.row_factory = sqlite3.Row
>>> c = conn.cursor()
>>> c.execute('select * from stocks')
<sqlite3.Cursor object at 0x7f4e7dd8fa80>
>>> r = c.fetchone()
>>> type(r)
<type 'sqlite3.Row'>
>>> r
(u'2006-01-05', u'BUY', u'RHAT', 100.0, 35.14)
>>> len(r)
5
>>> r[2]
u'RHAT'
>>> r.keys()
['date', 'trans', 'symbol', 'qty', 'price']
>>> r['qty']
100.0
>>> for member in r:
...     print member
...
2006-01-05
BUY
RHAT
100.0
35.14
```


11.13.5 SQLite and Python types

Introduction

SQLite natively supports the following types: NULL, INTEGER, REAL, TEXT, BLOB.

The following Python types can thus be sent to SQLite without any problem:

Python type	SQLite type
<i>None</i>	NULL
<i>int</i>	INTEGER
<i>long</i>	INTEGER
<i>float</i>	REAL
<i>str</i> (UTF8-encoded)	TEXT
<i>unicode</i>	TEXT
<i>buffer</i>	BLOB

This is how SQLite types are converted to Python types by default:

SQLite type	Python type
NULL	<i>None</i>
INTEGER	<i>int</i> or <i>long</i> , depending on size
REAL	<i>float</i>
TEXT	depends on <i>text_factory</i> , <i>unicode</i> by default
BLOB	<i>buffer</i>

The type system of the *sqlite3* module is extensible in two ways: you can store additional Python types in a SQLite database via object adaptation, and you can let the *sqlite3* module convert SQLite types to different Python types via converters.

Using adapters to store additional Python types in SQLite databases

As described before, SQLite supports only a limited set of types natively. To use other Python types with SQLite, you must **adapt** them to one of the *sqlite3* module's supported types for SQLite: one of *NoneType*, *int*, *long*, *float*, *str*, *unicode*, *buffer*.

There are two ways to enable the *sqlite3* module to adapt a custom Python type to one of the supported ones.

Letting your object adapt itself

This is a good approach if you write the class yourself. Let's suppose you have a class like this:

```
class Point(object):
    def __init__(self, x, y):
        self.x, self.y = x, y
```

Now you want to store the point in a single SQLite column. First you'll have to choose one of the supported types first to be used for representing the point. Let's just use *str* and separate the coordinates using a semicolon. Then you need to give your class a method `__conform__(self, protocol)` which must return the converted value. The parameter *protocol* will be *PrepareProtocol*.

```
import sqlite3

class Point(object):
    def __init__(self, x, y):
        self.x, self.y = x, y

    def __conform__(self, protocol):
        if protocol is sqlite3.PrepareProtocol:
            return "%f;%f" % (self.x, self.y)

con = sqlite3.connect(":memory:")
cur = con.cursor()

p = Point(4.0, -3.2)
cur.execute("select ?", (p,))
print cur.fetchone()[0]
```

Registering an adapter callable

The other possibility is to create a function that converts the type to the string representation and register the function with `register_adapter()`.

참고: The type/class to adapt must be a *new-style class*, i. e. it must have *object* as one of its bases.

```
import sqlite3

class Point(object):
    def __init__(self, x, y):
        self.x, self.y = x, y

def adapt_point(point):
    return "%f;%f" % (point.x, point.y)

sqlite3.register_adapter(Point, adapt_point)

con = sqlite3.connect(":memory:")
cur = con.cursor()

p = Point(4.0, -3.2)
cur.execute("select ?", (p,))
print cur.fetchone()[0]
```

The `sqlite3` module has two default adapters for Python's built-in `datetime.date` and `datetime.datetime` types. Now let's suppose we want to store `datetime.datetime` objects not in ISO representation, but as a Unix timestamp.

```
import sqlite3
import datetime, time

def adapt_datetime(ts):
    return time.mktime(ts.timetuple())

sqlite3.register_adapter(datetime.datetime, adapt_datetime)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

con = sqlite3.connect(":memory:")
cur = con.cursor()

now = datetime.datetime.now()
cur.execute("select ?", (now,))
print cur.fetchone()[0]

```

Converting SQLite values to custom Python types

Writing an adapter lets you send custom Python types to SQLite. But to make it really useful we need to make the Python to SQLite to Python roundtrip work.

Enter converters.

Let's go back to the `Point` class. We stored the `x` and `y` coordinates separated via semicolons as strings in SQLite.

First, we'll define a converter function that accepts the string as a parameter and constructs a `Point` object from it.

참고: Converter functions **always** get called with a string, no matter under which data type you sent the value to SQLite.

```

def convert_point(s):
    x, y = map(float, s.split(";"))
    return Point(x, y)

```

Now you need to make the `sqlite3` module know that what you select from the database is actually a point. There are two ways of doing this:

- Implicitly via the declared type
- Explicitly via the column name

Both ways are described in section *Module functions and constants*, in the entries for the constants `PARSE_DECLTYPES` and `PARSE_COLNAMES`.

The following example illustrates both approaches.

```

import sqlite3

class Point(object):
    def __init__(self, x, y):
        self.x, self.y = x, y

    def __repr__(self):
        return "(%f;%f)" % (self.x, self.y)

def adapt_point(point):
    return "%f;%f" % (point.x, point.y)

def convert_point(s):
    x, y = map(float, s.split(";"))
    return Point(x, y)

# Register the adapter
sqlite3.register_adapter(Point, adapt_point)

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
# Register the converter
sqlite3.register_converter("point", convert_point)

p = Point(4.0, -3.2)

#####
# 1) Using declared types
con = sqlite3.connect(":memory:", detect_types=sqlite3.PARSE_DECLTYPES)
cur = con.cursor()
cur.execute("create table test(p point)")

cur.execute("insert into test(p) values (?)", (p,))
cur.execute("select p from test")
print "with declared types:", cur.fetchone()[0]
cur.close()
con.close()

#####
# 1) Using column names
con = sqlite3.connect(":memory:", detect_types=sqlite3.PARSE_COLNAMES)
cur = con.cursor()
cur.execute("create table test(p)")

cur.execute("insert into test(p) values (?)", (p,))
cur.execute('select p as "p [point]" from test')
print "with column names:", cur.fetchone()[0]
cur.close()
con.close()
```

Default adapters and converters

There are default adapters for the date and datetime types in the datetime module. They will be sent as ISO dates/ISO timestamps to SQLite.

The default converters are registered under the name `date` for `datetime.date` and under the name `timestamp` for `datetime.datetime`.

This way, you can use date/timestamps from Python without any additional fiddling in most cases. The format of the adapters is also compatible with the experimental SQLite date/time functions.

The following example demonstrates this.

```
import sqlite3
import datetime

con = sqlite3.connect(":memory:", detect_types=sqlite3.PARSE_DECLTYPES|sqlite3.PARSE_
    ↳COLNAMES)
cur = con.cursor()
cur.execute("create table test(d date, ts timestamp)")

today = datetime.date.today()
now = datetime.datetime.now()

cur.execute("insert into test(d, ts) values (?, ?)", (today, now))
cur.execute("select d, ts from test")
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

row = cur.fetchone()
print today, ">=", row[0], type(row[0])
print now, ">=", row[1], type(row[1])

cur.execute('select current_date as "d [date]", current_timestamp as "ts [timestamp]"
↪')
row = cur.fetchone()
print "current_date", row[0], type(row[0])
print "current_timestamp", row[1], type(row[1])

```

If a timestamp stored in SQLite has a fractional part longer than 6 numbers, its value will be truncated to microsecond precision by the timestamp converter.

11.13.6 Controlling Transactions

By default, the *sqlite3* module opens transactions implicitly before a Data Modification Language (DML) statement (i.e. INSERT/UPDATE/DELETE/REPLACE), and commits transactions implicitly before a non-DML, non-query statement (i. e. anything other than SELECT or the aforementioned).

So if you are within a transaction and issue a command like CREATE TABLE ..., VACUUM, PRAGMA, the *sqlite3* module will commit implicitly before executing that command. There are two reasons for doing that. The first is that some of these commands don't work within transactions. The other reason is that *sqlite3* needs to keep track of the transaction state (if a transaction is active or not).

You can control which kind of BEGIN statements *sqlite3* implicitly executes (or none at all) via the *isolation_level* parameter to the *connect()* call, or via the *isolation_level* property of connections.

If you want **autocommit mode**, then set *isolation_level* to None.

Otherwise leave it at its default, which will result in a plain <BEGIN> statement, or set it to one of SQLite's supported isolation levels: <DEFERRED>, <IMMEDIATE> or <EXCLUSIVE>.

11.13.7 Using *sqlite3* efficiently

Using shortcut methods

Using the nonstandard *execute()*, *executemany()* and *executescript()* methods of the *Connection* object, your code can be written more concisely because you don't have to create the (often superfluous) *Cursor* objects explicitly. Instead, the *Cursor* objects are created implicitly and these shortcut methods return the cursor objects. This way, you can execute a SELECT statement and iterate over it directly using only a single call on the *Connection* object.

```

import sqlite3

persons = [
    ("Hugo", "Boss"),
    ("Calvin", "Klein")
]

con = sqlite3.connect(":memory:")

# Create the table
con.execute("create table person(firstname, lastname)")

# Fill the table

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
con.executemany("insert into person(firstname, lastname) values (?, ?)", persons)

# Print the table contents
for row in con.execute("select firstname, lastname from person"):
    print row

print "I just deleted", con.execute("delete from person").rowcount, "rows"
```

Accessing columns by name instead of by index

One useful feature of the `sqlite3` module is the built-in `sqlite3.Row` class designed to be used as a row factory.

Rows wrapped with this class can be accessed both by index (like tuples) and case-insensitively by name:

```
import sqlite3

con = sqlite3.connect(":memory:")
con.row_factory = sqlite3.Row

cur = con.cursor()
cur.execute("select 'John' as name, 42 as age")
for row in cur:
    assert row[0] == row["name"]
    assert row["name"] == row["nAmE"]
    assert row[1] == row["age"]
    assert row[1] == row["AgE"]
```

Using the connection as a context manager

버전 2.6에 추가.

Connection objects can be used as context managers that automatically commit or rollback transactions. In the event of an exception, the transaction is rolled back; otherwise, the transaction is committed:

```
import sqlite3

con = sqlite3.connect(":memory:")
con.execute("create table person (id integer primary key, firstname varchar unique)")

# Successful, con.commit() is called automatically afterwards
with con:
    con.execute("insert into person(firstname) values (?)", ("Joe",))

# con.rollback() is called after the with block finishes with an exception, the
# exception is still raised and must be caught
try:
    with con:
        con.execute("insert into person(firstname) values (?)", ("Joe",))
except sqlite3.IntegrityError:
    print "couldn't add Joe twice"
```

11.13.8 Common issues

Multithreading

Older SQLite versions had issues with sharing connections between threads. That's why the Python module disallows sharing connections and cursors between threads. If you still try to do so, you will get an exception at runtime.

The only exception is calling the `interrupt()` method, which only makes sense to call from a different thread.

Data Compression and Archiving

The modules described in this chapter support data compression with the `zlib`, `gzip`, and `bzip2` algorithms, and the creation of ZIP- and tar-format archives. See also *Archiving operations* provided by the `shutil` module.

12.1 `zlib` — Compression compatible with `gzip`

For applications that require data compression, the functions in this module allow compression and decompression, using the `zlib` library. The `zlib` library has its own home page at <http://www.zlib.net>. There are known incompatibilities between the Python module and versions of the `zlib` library earlier than 1.1.3; 1.1.3 has a security vulnerability, so we recommend using 1.1.4 or later.

`zlib`'s functions have many options and often need to be used in a particular order. This documentation doesn't attempt to cover all of the permutations; consult the `zlib` manual at <http://www.zlib.net/manual.html> for authoritative information.

For reading and writing `.gz` files see the `gzip` module.

The available exception and functions in this module are:

exception `zlib.error`

Exception raised on compression and decompression errors.

`zlib.adler32(data[, value])`

Computes an Adler-32 checksum of *data*. (An Adler-32 checksum is almost as reliable as a CRC32 but can be computed much more quickly.) If *value* is present, it is used as the starting value of the checksum; otherwise, a fixed default value is used. This allows computing a running checksum over the concatenation of several inputs. The algorithm is not cryptographically strong, and should not be used for authentication or digital signatures. Since the algorithm is designed for use as a checksum algorithm, it is not suitable for use as a general hash algorithm.

This function always returns an integer object.

참고: To generate the same numeric value across all Python versions and platforms use `adler32(data) & 0xffffffff`. If you are only using the checksum in packed binary format this is not necessary as the return value is the correct 32bit binary representation regardless of sign.

버전 2.6에서 변경: The return value is in the range $[-2^{31}, 2^{31}-1]$ regardless of platform. In older versions the value is signed on some platforms and unsigned on others.

버전 3.0에서 변경: The return value is unsigned and in the range $[0, 2^{32}-1]$ regardless of platform.

`zlib.compress(string[, level])`

Compresses the data in *string*, returning a string contained compressed data. *level* is an integer from 0 to 9 controlling the level of compression; 1 is fastest and produces the least compression, 9 is slowest and produces the most. 0 is no compression. The default value is 6. Raises the `error` exception if any error occurs.

`zlib.compressobj([level[, method[, wbits[, memlevel[, strategy]]]])`

Returns a compression object, to be used for compressing data streams that won't fit into memory at once. *level* is an integer from 0 to 9 or -1, controlling the level of compression; 1 is fastest and produces the least compression, 9 is slowest and produces the most. 0 is no compression. The default value is -1 (`Z_DEFAULT_COMPRESSION`). `Z_DEFAULT_COMPRESSION` represents a default compromise between speed and compression (currently equivalent to level 6).

method is the compression algorithm. Currently, the only supported value is `DEFLATED`.

The *wbits* argument controls the size of the history buffer (or the «window size») used when compressing data, and whether a header and trailer is included in the output. It can take several ranges of values. The default is 15.

- +9 to +15: The base-two logarithm of the window size, which therefore ranges between 512 and 32768. Larger values produce better compression at the expense of greater memory usage. The resulting output will include a zlib-specific header and trailer.
- -9 to -15: Uses the absolute value of *wbits* as the window size logarithm, while producing a raw output stream with no header or trailing checksum.
- +25 to +31 = 16 + (9 to 15): Uses the low 4 bits of the value as the window size logarithm, while including a basic **gzip** header and trailing checksum in the output.

memlevel controls the amount of memory used for internal compression state. Valid values range from 1 to 9. Higher values using more memory, but are faster and produce smaller output. The default is 8.

strategy is used to tune the compression algorithm. Possible values are `Z_DEFAULT_STRATEGY`, `Z_FILTERED`, and `Z_HUFFMAN_ONLY`. The default is `Z_DEFAULT_STRATEGY`.

`zlib.crc32(data[, value])`

Computes a CRC (Cyclic Redundancy Check) checksum of *data*. If *value* is present, it is used as the starting value of the checksum; otherwise, a fixed default value is used. This allows computing a running checksum over the concatenation of several inputs. The algorithm is not cryptographically strong, and should not be used for authentication or digital signatures. Since the algorithm is designed for use as a checksum algorithm, it is not suitable for use as a general hash algorithm.

This function always returns an integer object.

참고: To generate the same numeric value across all Python versions and platforms use `crc32(data) & 0xffffffff`. If you are only using the checksum in packed binary format this is not necessary as the return value is the correct 32bit binary representation regardless of sign.

버전 2.6에서 변경: The return value is in the range $[-2^{31}, 2^{31}-1]$ regardless of platform. In older versions the value would be signed on some platforms and unsigned on others.

버전 3.0에서 변경: The return value is unsigned and in the range $[0, 2^{32}-1]$ regardless of platform.

`zlib.decompress(string[, wbits[, bufsize]])`

Decompresses the data in *string*, returning a string containing the uncompressed data. The *wbits* parameter depends on the format of *string*, and is discussed further below. If *bufsize* is given, it is used as the initial size of the output buffer. Raises the `error` exception if any error occurs.

The *wbits* parameter controls the size of the history buffer (or « window size »), and what header and trailer format is expected. It is similar to the parameter for `compressobj()`, but accepts more ranges of values:

- +8 to +15: The base-two logarithm of the window size. The input must include a zlib header and trailer.
- 0: Automatically determine the window size from the zlib header. Only supported since zlib 1.2.3.5.
- -8 to -15: Uses the absolute value of *wbits* as the window size logarithm. The input must be a raw stream with no header or trailer.
- +24 to +31 = 16 + (8 to 15): Uses the low 4 bits of the value as the window size logarithm. The input must include a gzip header and trailer.
- +40 to +47 = 32 + (8 to 15): Uses the low 4 bits of the value as the window size logarithm, and automatically accepts either the zlib or gzip format.

When decompressing a stream, the window size must not be smaller than the size originally used to compress the stream; using a too-small value may result in an `error` exception. The default *wbits* value is 15, which corresponds to the largest window size and requires a zlib header and trailer to be included.

bufsize is the initial size of the buffer used to hold decompressed data. If more space is required, the buffer size will be increased as needed, so you don't have to get this value exactly right; tuning it will only save a few calls to `malloc()`. The default size is 16384.

`zlib.decompressobj([wbits])`

Returns a decompression object, to be used for decompressing data streams that won't fit into memory at once.

The *wbits* parameter controls the size of the history buffer (or the « window size »), and what header and trailer format is expected. It has the same meaning as *described for decompress()*.

Compression objects support the following methods:

`Compress.compress(string)`

Compress *string*, returning a string containing compressed data for at least part of the data in *string*. This data should be concatenated to the output produced by any preceding calls to the `compress()` method. Some input may be kept in internal buffers for later processing.

`Compress.flush([mode])`

All pending input is processed, and a string containing the remaining compressed output is returned. *mode* can be selected from the constants `Z_SYNC_FLUSH`, `Z_FULL_FLUSH`, or `Z_FINISH`, defaulting to `Z_FINISH`. `Z_SYNC_FLUSH` and `Z_FULL_FLUSH` allow compressing further strings of data, while `Z_FINISH` finishes the compressed stream and prevents compressing any more data. After calling `flush()` with *mode* set to `Z_FINISH`, the `compress()` method cannot be called again; the only realistic action is to delete the object.

`Compress.copy()`

Returns a copy of the compression object. This can be used to efficiently compress a set of data that share a common initial prefix.

버전 2.5에 추가.

Decompression objects support the following methods, and two attributes:

`Decompress.unused_data`

A string which contains any bytes past the end of the compressed data. That is, this remains "" until the last byte that contains compression data is available. If the whole string turned out to contain compressed data, this is "", the empty string.

The only way to determine where a string of compressed data ends is by actually decompressing it. This means that when compressed data is contained part of a larger file, you can only find the end of it by reading data and feeding it followed by some non-empty string into a decompression object's `decompress()` method until the `unused_data` attribute is no longer the empty string.

Decompress.unconsumed_tail

A string that contains any data that was not consumed by the last `decompress()` call because it exceeded the limit for the uncompressed data buffer. This data has not yet been seen by the zlib machinery, so you must feed it (possibly with further data concatenated to it) back to a subsequent `decompress()` method call in order to get correct output.

Decompress.decompress (*string* [, *max_length*])

Decompress *string*, returning a string containing the uncompressed data corresponding to at least part of the data in *string*. This data should be concatenated to the output produced by any preceding calls to the `decompress()` method. Some of the input data may be preserved in internal buffers for later processing.

If the optional parameter *max_length* is non-zero then the return value will be no longer than *max_length*. This may mean that not all of the compressed input can be processed; and unconsumed data will be stored in the attribute `unconsumed_tail`. This string must be passed to a subsequent call to `decompress()` if decompression is to continue. If *max_length* is not supplied then the whole input is decompressed, and `unconsumed_tail` is an empty string.

Decompress.flush ([*length*])

All pending input is processed, and a string containing the remaining uncompressed output is returned. After calling `flush()`, the `decompress()` method cannot be called again; the only realistic action is to delete the object.

The optional parameter *length* sets the initial size of the output buffer.

Decompress.copy ()

Returns a copy of the decompression object. This can be used to save the state of the decompressor midway through the data stream in order to speed up random seeks into the stream at a future point.

버전 2.5에 추가.

더 보기:

Module `gzip` Reading and writing **gzip**-format files.

<http://www.zlib.net> The zlib library home page.

<http://www.zlib.net/manual.html> The zlib manual explains the semantics and usage of the library's many functions.

12.2 gzip — Support for gzip files

Source code: [Lib/gzip.py](#)

This module provides a simple interface to compress and decompress files just like the GNU programs **gzip** and **gunzip** would.

The data compression is provided by the `zlib` module.

The `gzip` module provides the `GzipFile` class which is modeled after Python's File Object. The `GzipFile` class reads and writes **gzip**-format files, automatically compressing or decompressing the data so that it looks like an ordinary file object.

Note that additional file formats which can be decompressed by the **gzip** and **gunzip** programs, such as those produced by **compress** and **pack**, are not supported by this module.

The module defines the following items:

class `gzip.GzipFile` ([*filename* [, *mode* [, *compresslevel* [, *fileobj* [, *mtime*]]]]])

Constructor for the `GzipFile` class, which simulates most of the methods of a file object, with the exception of

the `readinto()` and `truncate()` methods. At least one of *fileobj* and *filename* must be given a non-trivial value.

The new class instance is based on *fileobj*, which can be a regular file, a *StringIO* object, or any other object which simulates a file. It defaults to `None`, in which case *filename* is opened to provide a file object.

When *fileobj* is not `None`, the *filename* argument is only used to be included in the **gzip** file header, which may include the original filename of the uncompressed file. It defaults to the filename of *fileobj*, if discernible; otherwise, it defaults to the empty string, and in this case the original filename is not included in the header.

The *mode* argument can be any of `'r'`, `'rb'`, `'a'`, `'ab'`, `'w'`, or `'wb'`, depending on whether the file will be read or written. The default is the mode of *fileobj* if discernible; otherwise, the default is `'rb'`. If not given, the `` flag will be added to the mode to ensure the file is opened in binary mode for cross-platform portability.

The *compresslevel* argument is an integer from 0 to 9 controlling the level of compression; 1 is fastest and produces the least compression, and 9 is slowest and produces the most compression. 0 is no compression. The default is 9.

The *mtime* argument is an optional numeric timestamp to be written to the stream when compressing. All **gzip** compressed streams are required to contain a timestamp. If omitted or `None`, the current time is used. This module ignores the timestamp when decompressing; however, some programs, such as **gunzip**, make use of it. The format of the timestamp is the same as that of the return value of `time.time()` and of the `st_mtime` attribute of the object returned by `os.stat()`.

Calling a *GzipFile* object's `close()` method does not close *fileobj*, since you might wish to append more material after the compressed data. This also allows you to pass a *StringIO* object opened for writing as *fileobj*, and retrieve the resulting memory buffer using the *StringIO* object's `getvalue()` method.

GzipFile supports iteration and the `with` statement.

버전 2.7에서 변경: Support for the `with` statement was added.

버전 2.7에서 변경: Support for zero-padded files was added.

버전 2.7에 추가: The *mtime* argument.

`gzip.open(filename[, mode[, compresslevel]])`

This is a shorthand for `GzipFile(filename, mode, compresslevel)`. The *filename* argument is required; *mode* defaults to `'rb'` and *compresslevel* defaults to 9.

12.2.1 Examples of usage

Example of how to read a compressed file:

```
import gzip
with gzip.open('file.txt.gz', 'rb') as f:
    file_content = f.read()
```

Example of how to create a compressed GZIP file:

```
import gzip
content = "Lots of content here"
with gzip.open('file.txt.gz', 'wb') as f:
    f.write(content)
```

Example of how to GZIP compress an existing file:

```
import gzip
import shutil
with open('file.txt', 'rb') as f_in, gzip.open('file.txt.gz', 'wb') as f_out:
    shutil.copyfileobj(f_in, f_out)
```

더 보기:

Module `zlib` The basic data compression module needed to support the `gzip` file format.

12.3 bz2 — Compression compatible with bzip2

버전 2.3에 추가.

This module provides a comprehensive interface for the bz2 compression library. It implements a complete file interface, one-shot (de)compression functions, and types for sequential (de)compression.

Here is a summary of the features offered by the bz2 module:

- `BZ2File` class implements a complete file interface, including `readline()`, `readlines()`, `writelines()`, `seek()`, etc;
- `BZ2File` class implements emulated `seek()` support;
- `BZ2File` class implements universal newline support;
- `BZ2File` class offers an optimized line iteration using the readahead algorithm borrowed from file objects;
- Sequential (de)compression supported by `BZ2Compressor` and `BZ2Decompressor` classes;
- One-shot (de)compression supported by `compress()` and `decompress()` functions;
- Thread safety uses individual locking mechanism.

참고: Handling of multi-stream bzip2 files is not supported. Modules such as `bz2file` let you overcome this.

12.3.1 (De)compression of files

Handling of compressed files is offered by the `BZ2File` class.

class `bz2.BZ2File` (*filename*`[, mode``[, buffering``[, compresslevel``]]`)

Open a bz2 file. Mode can be either 'r' or 'w', for reading (default) or writing. When opened for writing, the file will be created if it doesn't exist, and truncated otherwise. If *buffering* is given, 0 means unbuffered, and larger numbers specify the buffer size; the default is 0. If *compresslevel* is given, it must be a number between 1 and 9; the default is 9. Add a 'U' to mode to open the file for input in *universal newlines* mode. Any line ending in the input file will be seen as a '\n' in Python. Also, a file so opened gains the attribute `newlines`; the value for this attribute is one of `None` (no newline read yet), '\r', '\n', '\r\n' or a tuple containing all the newline types seen. Universal newlines are available only when reading. Instances support iteration in the same way as normal *file* instances.

`BZ2File` supports the `with` statement.

버전 2.7에서 변경: Support for the `with` statement was added.

참고: This class does not support input files containing multiple streams (such as those produced by the `pbzip2` tool). When reading such an input file, only the first stream will be accessible. If you require support for multi-stream files, consider using the third-party `bz2file` module (available from `PyPI`). This module provides a backport of Python 3.3's `BZ2File` class, which does support multi-stream files.

close()

Close the file. Sets data attribute `closed` to true. A closed file cannot be used for further I/O operations. `close()` may be called more than once without error.

read([size])

Read at most *size* uncompressed bytes, returned as a string. If the *size* argument is negative or omitted, read until EOF is reached.

readline([size])

Return the next line from the file, as a string, retaining newline. A non-negative *size* argument limits the maximum number of bytes to return (an incomplete line may be returned then). Return an empty string at EOF.

readlines([size])

Return a list of lines read. The optional *size* argument, if given, is an approximate bound on the total number of bytes in the lines returned.

xreadlines()

For backward compatibility. `BZ2File` objects now include the performance optimizations previously implemented in the `xreadlines` module.

버전 2.3부터 폐지: This exists only for compatibility with the method by this name on `file` objects, which is deprecated. Use `for line in file` instead.

seek(offset[, whence])

Move to new file position. Argument *offset* is a byte count. Optional argument *whence* defaults to `os.SEEK_SET` or 0 (offset from start of file; offset should be ≥ 0); other values are `os.SEEK_CUR` or 1 (move relative to current position; offset can be positive or negative), and `os.SEEK_END` or 2 (move relative to end of file; offset is usually negative, although many platforms allow seeking beyond the end of a file).

Note that seeking of bz2 files is emulated, and depending on the parameters the operation may be extremely slow.

tell()

Return the current file position, an integer (may be a long integer).

write(data)

Write string *data* to file. Note that due to buffering, `close()` may be needed before the file on disk reflects the data written.

writelines(sequence_of_strings)

Write the sequence of strings to the file. Note that newlines are not added. The sequence can be any iterable object producing strings. This is equivalent to calling `write()` for each string.

12.3.2 Sequential (de)compression

Sequential compression and decompression is done using the classes `BZ2Compressor` and `BZ2Decompressor`.

class bz2.BZ2Compressor([compresslevel])

Create a new compressor object. This object may be used to compress data sequentially. If you want to compress data in one shot, use the `compress()` function instead. The *compresslevel* parameter, if given, must be a number between 1 and 9; the default is 9.

compress(data)

Provide more data to the compressor object. It will return chunks of compressed data whenever possible. When you've finished providing data to compress, call the `flush()` method to finish the compression process, and return what is left in internal buffers.

flush()

Finish the compression process and return what is left in internal buffers. You must not use the compressor object after calling this method.

class bz2.BZ2Decompressor

Create a new decompressor object. This object may be used to decompress data sequentially. If you want to decompress data in one shot, use the `decompress()` function instead.

decompress(data)

Provide more data to the decompressor object. It will return chunks of decompressed data whenever possible. If you try to decompress data after the end of stream is found, `EOFError` will be raised. If any data was found after the end of stream, it'll be ignored and saved in `unused_data` attribute.

12.3.3 One-shot (de)compression

One-shot compression and decompression is provided through the `compress()` and `decompress()` functions.

bz2.compress(data[, compresslevel])

Compress *data* in one shot. If you want to compress data sequentially, use an instance of `BZ2Compressor` instead. The `compresslevel` parameter, if given, must be a number between 1 and 9; the default is 9.

bz2.decompress(data)

Decompress *data* in one shot. If you want to decompress data sequentially, use an instance of `BZ2Decompressor` instead.

12.4 zipfile — Work with ZIP archives

버전 1.6에 추가.

Source code: [Lib/zipfile.py](#)

The ZIP file format is a common archive and compression standard. This module provides tools to create, read, write, append, and list a ZIP file. Any advanced use of this module will require an understanding of the format, as defined in [PKZIP Application Note](#).

This module does not currently handle multi-disk ZIP files. It can handle ZIP files that use the ZIP64 extensions (that is ZIP files that are more than 4 GByte in size). It supports decryption of encrypted files in ZIP archives, but it currently cannot create an encrypted file. Decryption is extremely slow as it is implemented in native Python rather than C.

The module defines the following items:

exception zipfile.BadZipfile

The error raised for bad ZIP files (old name: `zipfile.error`).

exception zipfile.LargeZipFile

The error raised when a ZIP file would require ZIP64 functionality but that has not been enabled.

class zipfile.ZipFile

The class for reading and writing ZIP files. See section [ZipFile Objects](#) for constructor details.

class zipfile.PyZipFile

Class for creating ZIP archives containing Python libraries.

class zipfile.ZipInfo([filename[, date_time]])

Class used to represent information about a member of an archive. Instances of this class are returned by the `getinfo()` and `infolist()` methods of `ZipFile` objects. Most users of the `zipfile` module will not

need to create these, but only use those created by this module. *filename* should be the full name of the archive member, and *date_time* should be a tuple containing six fields which describe the time of the last modification to the file; the fields are described in section *ZipInfo Objects*.

`zipfile.is_zipfile(filename)`

Returns `True` if *filename* is a valid ZIP file based on its magic number, otherwise returns `False`. *filename* may be a file or file-like object too.

버전 2.7에서 변경: Support for file and file-like objects.

`zipfile.ZIP_STORED`

The numeric constant for an uncompressed archive member.

`zipfile.ZIP_DEFLATED`

The numeric constant for the usual ZIP compression method. This requires the *zlib* module. No other compression methods are currently supported.

더 보기:

PKZIP Application Note Documentation on the ZIP file format by Phil Katz, the creator of the format and algorithms used.

Info-ZIP Home Page Information about the Info-ZIP project's ZIP archive programs and development libraries.

12.4.1 ZipFile Objects

class `zipfile.ZipFile(file[, mode[, compression[, allowZip64]]])`

Open a ZIP file, where *file* can be either a path to a file (a string) or a file-like object. The *mode* parameter should be 'r' to read an existing file, 'w' to truncate and write a new file, or 'a' to append to an existing file. If *mode* is 'a' and *file* refers to an existing ZIP file, then additional files are added to it. If *file* does not refer to a ZIP file, then a new ZIP archive is appended to the file. This is meant for adding a ZIP archive to another file (such as `python.exe`).

버전 2.6에서 변경: If *mode* is a and the file does not exist at all, it is created.

compression is the ZIP compression method to use when writing the archive, and should be `ZIP_STORED` or `ZIP_DEFLATED`; unrecognized values will cause `RuntimeError` to be raised. If `ZIP_DEFLATED` is specified but the *zlib* module is not available, `RuntimeError` is also raised. The default is `ZIP_STORED`. If *allowZip64* is `True` *zipfile* will create ZIP files that use the ZIP64 extensions when the zipfile is larger than 2 GB. If it is false (the default) *zipfile* will raise an exception when the ZIP file would require ZIP64 extensions. ZIP64 extensions are disabled by default because the default `zip` and `unzip` commands on Unix (the InfoZIP utilities) don't support these extensions.

버전 2.7.1에서 변경: If the file is created with mode 'a' or 'w' and then *closed* without adding any files to the archive, the appropriate ZIP structures for an empty archive will be written to the file.

`ZipFile` is also a context manager and therefore supports the `with` statement. In the example, *myzip* is closed after the `with` statement's suite is finished—even if an exception occurs:

```
with ZipFile('spam.zip', 'w') as myzip:
    myzip.write('eggs.txt')
```

버전 2.7에 추가: Added the ability to use *ZipFile* as a context manager.

`ZipFile.close()`

Close the archive file. You must call `close()` before exiting your program or essential records will not be written.

`ZipFile.getinfo(name)`

Return a *ZipInfo* object with information about the archive member *name*. Calling `getinfo()` for a name not currently contained in the archive will raise a `KeyError`.

`ZipFile.infolist()`

Return a list containing a *ZipInfo* object for each member of the archive. The objects are in the same order as their entries in the actual ZIP file on disk if an existing archive was opened.

`ZipFile.namelist()`

Return a list of archive members by name.

`ZipFile.open(name[, mode[, pwd]])`

Extract a member from the archive as a file-like object (*ZipExtFile*). *name* is the name of the file in the archive, or a *ZipInfo* object. The *mode* parameter, if included, must be one of the following: 'r' (the default), 'U', or 'rU'. Choosing 'U' or 'rU' will enable *universal newline* support in the read-only object. *pwd* is the password used for encrypted files. Calling *open()* on a closed *ZipFile* will raise a *RuntimeError*.

참고: The file-like object is read-only and provides the following methods: *read()*, *readline()*, *readlines()*, *__iter__()*, *next()*.

참고: If the *ZipFile* was created by passing in a file-like object as the first argument to the constructor, then the object returned by *open()* shares the *ZipFile*'s file pointer. Under these circumstances, the object returned by *open()* should not be used after any additional operations are performed on the *ZipFile* object. If the *ZipFile* was created by passing in a string (the filename) as the first argument to the constructor, then *open()* will create a new file object that will be held by the *ZipExtFile*, allowing it to operate independently of the *ZipFile*.

참고: The *open()*, *read()* and *extract()* methods can take a filename or a *ZipInfo* object. You will appreciate this when trying to read a ZIP file that contains members with duplicate names.

버전 2.6에 추가.

`ZipFile.extract(member[, path[, pwd]])`

Extract a member from the archive to the current working directory; *member* must be its full name or a *ZipInfo* object). Its file information is extracted as accurately as possible. *path* specifies a different directory to extract to. *member* can be a filename or a *ZipInfo* object. *pwd* is the password used for encrypted files.

Returns the normalized path created (a directory or new file).

버전 2.6에 추가.

참고: If a member filename is an absolute path, a drive/UNC sharepoint and leading (back)slashes will be stripped, e.g.: *///foo/bar* becomes *foo/bar* on Unix, and *C:\foo\bar* becomes *foo\bar* on Windows. And all "." components in a member filename will be removed, e.g.: *../..../foo../..../ba..r* becomes *foo../ba..r*. On Windows illegal characters (:, <, >, |, ", ?, and *) replaced by underscore (_).

`ZipFile.extractall([path[, members[, pwd]]])`

Extract all members from the archive to the current working directory. *path* specifies a different directory to extract to. *members* is optional and must be a subset of the list returned by *namelist()*. *pwd* is the password used for encrypted files.

경고: Never extract archives from untrusted sources without prior inspection. It is possible that files are created outside of *path*, e.g. members that have absolute filenames starting with "/" or filenames with two dots ".".

버전 2.7.4에서 변경: The `zipfile` module attempts to prevent that. See `extract()` note.

버전 2.6에 추가.

`ZipFile.printdir()`

Print a table of contents for the archive to `sys.stdout`.

`ZipFile.setpassword(pwd)`

Set `pwd` as default password to extract encrypted files.

버전 2.6에 추가.

`ZipFile.read(name[, pwd])`

Return the bytes of the file `name` in the archive. `name` is the name of the file in the archive, or a `ZipInfo` object. The archive must be open for read or append. `pwd` is the password used for encrypted files and, if specified, it will override the default password set with `setpassword()`. Calling `read()` on a closed `ZipFile` will raise a `RuntimeError`.

버전 2.6에서 변경: `pwd` was added, and `name` can now be a `ZipInfo` object.

`ZipFile.testzip()`

Read all the files in the archive and check their CRC's and file headers. Return the name of the first bad file, or else return `None`. Calling `testzip()` on a closed `ZipFile` will raise a `RuntimeError`.

`ZipFile.write(filename[, arcname[, compress_type]])`

Write the file named `filename` to the archive, giving it the archive name `arcname` (by default, this will be the same as `filename`, but without a drive letter and with leading path separators removed). If given, `compress_type` overrides the value given for the `compression` parameter to the constructor for the new entry. The archive must be open with mode 'w' or 'a' – calling `write()` on a `ZipFile` created with mode 'r' will raise a `RuntimeError`. Calling `write()` on a closed `ZipFile` will raise a `RuntimeError`.

참고: There is no official file name encoding for ZIP files. If you have unicode file names, you must convert them to byte strings in your desired encoding before passing them to `write()`. WinZip interprets all file names as encoded in CP437, also known as DOS Latin.

참고: Archive names should be relative to the archive root, that is, they should not start with a path separator.

참고: If `arcname` (or `filename`, if `arcname` is not given) contains a null byte, the name of the file in the archive will be truncated at the null byte.

`ZipFile.writestr(zinfo_or_arcname, bytes[, compress_type])`

Write the string `bytes` to the archive; `zinfo_or_arcname` is either the file name it will be given in the archive, or a `ZipInfo` instance. If it's an instance, at least the filename, date, and time must be given. If it's a name, the date and time is set to the current date and time. The archive must be opened with mode 'w' or 'a' – calling `writestr()` on a `ZipFile` created with mode 'r' will raise a `RuntimeError`. Calling `writestr()` on a closed `ZipFile` will raise a `RuntimeError`.

If given, `compress_type` overrides the value given for the `compression` parameter to the constructor for the new entry, or in the `zinfo_or_arcname` (if that is a `ZipInfo` instance).

참고: When passing a `ZipInfo` instance as the `zinfo_or_arcname` parameter, the compression method used will be that specified in the `compress_type` member of the given `ZipInfo` instance. By default, the `ZipInfo` constructor sets this member to `ZIP_STORED`.

버전 2.7에서 변경: The *compress_type* argument.

The following data attributes are also available:

ZipFile.debug

The level of debug output to use. This may be set from 0 (the default, no output) to 3 (the most output). Debugging information is written to `sys.stdout`.

ZipFile.comment

The comment text associated with the ZIP file. If assigning a comment to a *ZipFile* instance created with mode `<a>` or `<w>`, this should be a string no longer than 65535 bytes. Comments longer than this will be truncated in the written archive when *close()* is called.

12.4.2 PyZipFile Objects

The *PyZipFile* constructor takes the same parameters as the *ZipFile* constructor. Instances have one method in addition to those of *ZipFile* objects.

PyZipFile.writepy (*pathname*[, *basename*])

Search for files `*.py` and add the corresponding file to the archive. The corresponding file is a `*.pyo` file if available, else a `*.pyc` file, compiling if necessary. If the *pathname* is a file, the filename must end with `.py`, and just the (corresponding `*.py[co]`) file is added at the top level (no path information). If the *pathname* is a file that does not end with `.py`, a *RuntimeError* will be raised. If it is a directory, and the directory is not a package directory, then all the files `*.py[co]` are added at the top level. If the directory is a package directory, then all `*.py[co]` are added under the package name as a file path, and if any subdirectories are package directories, all of these are added recursively. *basename* is intended for internal use only. The *writepy()* method makes archives with file names like this:

```
string.pyc                # Top level name
test/__init__.pyc         # Package directory
test/test_support.pyc     # Module test.test_support
test/bogus/__init__.pyc   # Subpackage directory
test/bogus/myfile.pyc     # Submodule test.bogus.myfile
```

12.4.3 ZipInfo Objects

Instances of the *ZipInfo* class are returned by the *getinfo()* and *infolist()* methods of *ZipFile* objects. Each object stores information about a single member of the ZIP archive.

Instances have the following attributes:

ZipInfo.filename

Name of the file in the archive.

ZipInfo.date_time

The time and date of the last modification to the archive member. This is a tuple of six values:

Index	Value
0	Year (≥ 1980)
1	Month (one-based)
2	Day of month (one-based)
3	Hours (zero-based)
4	Minutes (zero-based)
5	Seconds (zero-based)

참고: The ZIP file format does not support timestamps before 1980.

`ZipInfo.compress_type`
Type of compression for the archive member.

`ZipInfo.comment`
Comment for the individual archive member.

`ZipInfo.extra`
Expansion field data. The [PKZIP Application Note](#) contains some comments on the internal structure of the data contained in this string.

`ZipInfo.create_system`
System which created ZIP archive.

`ZipInfo.create_version`
PKZIP version which created ZIP archive.

`ZipInfo.extract_version`
PKZIP version needed to extract archive.

`ZipInfo.reserved`
Must be zero.

`ZipInfo.flag_bits`
ZIP flag bits.

`ZipInfo.volume`
Volume number of file header.

`ZipInfo.internal_attr`
Internal attributes.

`ZipInfo.external_attr`
External file attributes.

`ZipInfo.header_offset`
Byte offset to the file header.

`ZipInfo.CRC`
CRC-32 of the uncompressed file.

`ZipInfo.compress_size`
Size of the compressed data.

`ZipInfo.file_size`
Size of the uncompressed file.

12.4.4 Command-Line Interface

The `zipfile` module provides a simple command-line interface to interact with ZIP archives.

If you want to create a new ZIP archive, specify its name after the `-c` option and then list the filename(s) that should be included:

```
$ python -m zipfile -c monty.zip spam.txt eggs.txt
```

Passing a directory is also acceptable:

```
$ python -m zipfile -c monty.zip life-of-brian_1979/
```

If you want to extract a ZIP archive into the specified directory, use the `-e` option:

```
$ python -m zipfile -e monty.zip target-dir/
```

For a list of the files in a ZIP archive, use the `-l` option:

```
$ python -m zipfile -l monty.zip
```

Command-line options

- `-l <zipfile>`
List files in a zipfile.
- `-c <zipfile> <source1> ... <sourceN>`
Create zipfile from source files.
- `-e <zipfile> <output_dir>`
Extract zipfile into target directory.
- `-t <zipfile>`
Test whether the zipfile is valid or not.

12.5 tarfile — Read and write tar archive files

버전 2.3에 추가.

Source code: [Lib/tarfile.py](#)

The `tarfile` module makes it possible to read and write tar archives, including those using gzip or bz2 compression. Use the `zipfile` module to read or write `.zip` files, or the higher-level functions in `shutil`.

Some facts and figures:

- reads and writes `gzip` and `bz2` compressed archives if the respective modules are available.
- read/write support for the POSIX.1-1988 (ustar) format.
- read/write support for the GNU tar format including *longname* and *longlink* extensions, read-only support for the *sparse* extension.
- read/write support for the POSIX.1-2001 (pax) format.

버전 2.6에 추가.

- handles directories, regular files, hardlinks, symbolic links, fifos, character devices and block devices and is able to acquire and restore file information like timestamp, access permissions and owner.

참고: Handling of multi-stream bz2 files is not supported. Modules such as `bz2file` let you overcome this.

`tarfile.open` (*name=None, mode='r', fileobj=None, bufsize=10240, **kwargs*)

Return a `TarFile` object for the pathname *name*. For detailed information on `TarFile` objects and the keyword arguments that are allowed, see *TarFile Objects*.

mode has to be a string of the form 'filemode[:compression]', it defaults to 'r'. Here is a full list of mode combinations:

mode	action
'r' or 'r:*'	Open for reading with transparent compression (recommended).
'r:'	Open for reading exclusively without compression.
'r:gz'	Open for reading with gzip compression.
'r:bz2'	Open for reading with bzip2 compression.
'a' or 'a:'	Open for appending with no compression. The file is created if it does not exist.
'w' or 'w:'	Open for uncompressed writing.
'w:gz'	Open for gzip compressed writing.
'w:bz2'	Open for bzip2 compressed writing.

Note that 'a:gz' or 'a:bz2' is not possible. If *mode* is not suitable to open a certain (compressed) file for reading, `ReadError` is raised. Use *mode* 'r' to avoid this. If a compression method is not supported, `CompressionError` is raised.

If *fileobj* is specified, it is used as an alternative to a file object opened for *name*. It is supposed to be at position 0.

For modes 'w:gz', 'r:gz', 'w:bz2', 'r:bz2', `tarfile.open()` accepts the keyword argument *compresslevel* (default 9) to specify the compression level of the file.

For special purposes, there is a second format for *mode*: 'filemode|[compression]'. `tarfile.open()` will return a `TarFile` object that processes its data as a stream of blocks. No random seeking will be done on the file. If given, *fileobj* may be any object that has a `read()` or `write()` method (depending on the *mode*). *bufsize* specifies the blocksize and defaults to 20 * 512 bytes. Use this variant in combination with e.g. `sys.stdin`, a socket file object or a tape device. However, such a `TarFile` object is limited in that it does not allow random access, see *Examples*. The currently possible modes:

Mode	Action
'r *'	Open a <i>stream</i> of tar blocks for reading with transparent compression.
'r '	Open a <i>stream</i> of uncompressed tar blocks for reading.
'r gz'	Open a gzip compressed <i>stream</i> for reading.
'r bz2'	Open a bzip2 compressed <i>stream</i> for reading.
'w '	Open an uncompressed <i>stream</i> for writing.
'w gz'	Open a gzip compressed <i>stream</i> for writing.
'w bz2'	Open a bzip2 compressed <i>stream</i> for writing.

class tarfile.TarFile

Class for reading and writing tar archives. Do not use this class directly, better use `tarfile.open()` instead. See *TarFile Objects*.

`tarfile.is_tarfile(name)`

Return `True` if *name* is a tar archive file, that the `tarfile` module can read.

class tarfile.TarFileCompat (filename, mode='r', compression=TAR_PLAIN)

Class for limited access to tar archives with a `zipfile`-like interface. Please consult the documentation of the `zipfile` module for more details. *compression* must be one of the following constants:

TAR_PLAIN

Constant for an uncompressed tar archive.

TAR_GZIPPED

Constant for a `gzip` compressed tar archive.

버전 2.6부터 폐지: The `TarFileCompat` class has been removed in Python 3.

exception `tarfile.TarError`

Base class for all `tarfile` exceptions.

exception `tarfile.ReadError`

Is raised when a tar archive is opened, that either cannot be handled by the `tarfile` module or is somehow invalid.

exception `tarfile.CompressionError`

Is raised when a compression method is not supported or when the data cannot be decoded properly.

exception `tarfile.StreamError`

Is raised for the limitations that are typical for stream-like `TarFile` objects.

exception `tarfile.ExtractError`

Is raised for *non-fatal* errors when using `TarFile.extract()`, but only if `TarFile.errorlevel== 2`.

The following constants are available at the module level:

`tarfile.ENCODING`

The default character encoding: 'utf-8' on Windows, the value returned by `sys.getfilesystemencoding()` otherwise.

exception `tarfile.HeaderError`

Is raised by `TarInfo.frombuf()` if the buffer it gets is invalid.

버전 2.6에 추가.

Each of the following constants defines a tar archive format that the `tarfile` module is able to create. See section *Supported tar formats* for details.

`tarfile.USTAR_FORMAT`

POSIX.1-1988 (ustar) format.

`tarfile.GNU_FORMAT`

GNU tar format.

`tarfile.PAX_FORMAT`

POSIX.1-2001 (pax) format.

`tarfile.DEFAULT_FORMAT`

The default format for creating archives. This is currently `GNU_FORMAT`.

더 보기:

Module `zipfile` Documentation of the `zipfile` standard module.

Archiving operations Documentation of the higher-level archiving facilities provided by the standard `shutil` module.

GNU tar manual, Basic Tar Format Documentation for tar archive files, including GNU tar extensions.

12.5.1 TarFile Objects

The `TarFile` object provides an interface to a tar archive. A tar archive is a sequence of blocks. An archive member (a stored file) is made up of a header block followed by data blocks. It is possible to store a file in a tar archive several times. Each archive member is represented by a `TarInfo` object, see *TarInfo Objects* for details.

A `TarFile` object can be used as a context manager in a `with` statement. It will automatically be closed when the block is completed. Please note that in the event of an exception an archive opened for writing will not be finalized; only the internally used file object will be closed. See the *Examples* section for a use case.

버전 2.7에 추가: Added support for the context management protocol.


```
class tarfile.TarFile(name=None, mode='r', fileobj=None, format=DEFAULT_FORMAT, tar-
                        info=TarInfo, dereference=False, ignore_zeros=False, encoding=ENCODING,
                        errors=None, pax_headers=None, debug=0, errorlevel=0)
```

All following arguments are optional and can be accessed as instance attributes as well.

name is the pathname of the archive. It can be omitted if *fileobj* is given. In this case, the file object's name attribute is used if it exists.

mode is either 'r' to read from an existing archive, 'a' to append data to an existing file or 'w' to create a new file overwriting an existing one.

If *fileobj* is given, it is used for reading or writing data. If it can be determined, *mode* is overridden by *fileobj*'s mode. *fileobj* will be used from position 0.

참고: *fileobj* is not closed, when *TarFile* is closed.

format controls the archive format. It must be one of the constants *USTAR_FORMAT*, *GNU_FORMAT* or *PAX_FORMAT* that are defined at module level.

버전 2.6에 추가.

The *tarinfo* argument can be used to replace the default *TarInfo* class with a different one.

버전 2.6에 추가.

If *dereference* is *False*, add symbolic and hard links to the archive. If it is *True*, add the content of the target files to the archive. This has no effect on systems that do not support symbolic links.

If *ignore_zeros* is *False*, treat an empty block as the end of the archive. If it is *True*, skip empty (and invalid) blocks and try to get as many members as possible. This is only useful for reading concatenated or damaged archives.

debug can be set from 0 (no debug messages) up to 3 (all debug messages). The messages are written to `sys.stderr`.

If *errorlevel* is 0, all errors are ignored when using *TarFile.extract()*. Nevertheless, they appear as error messages in the debug output, when debugging is enabled. If 1, all *fatal* errors are raised as *OSError* or *IOError* exceptions. If 2, all *non-fatal* errors are raised as *TarError* exceptions as well.

The *encoding* and *errors* arguments control the way strings are converted to unicode objects and vice versa. The default settings will work for most users. See section *Unicode issues* for in-depth information.

버전 2.6에 추가.

The *pax_headers* argument is an optional dictionary of unicode strings which will be added as a pax global header if *format* is *PAX_FORMAT*.

버전 2.6에 추가.

```
classmethod TarFile.open(...)
```

Alternative constructor. The *tarfile.open()* function is actually a shortcut to this classmethod.

```
TarFile.getmember(name)
```

Return a *TarInfo* object for member *name*. If *name* can not be found in the archive, *KeyError* is raised.

참고: If a member occurs more than once in the archive, its last occurrence is assumed to be the most up-to-date version.

`TarFile.getmembers()`

Return the members of the archive as a list of `TarInfo` objects. The list has the same order as the members in the archive.

`TarFile.getnames()`

Return the members as a list of their names. It has the same order as the list returned by `getmembers()`.

`TarFile.list(verbose=True)`

Print a table of contents to `sys.stdout`. If `verbose` is `False`, only the names of the members are printed. If it is `True`, output similar to that of `ls -l` is produced.

`TarFile.next()`

Return the next member of the archive as a `TarInfo` object, when `TarFile` is opened for reading. Return `None` if there is no more available.

`TarFile.extractall(path=".", members=None)`

Extract all members from the archive to the current working directory or directory `path`. If optional `members` is given, it must be a subset of the list returned by `getmembers()`. Directory information like owner, modification time and permissions are set after all members have been extracted. This is done to work around two problems: A directory's modification time is reset each time a file is created in it. And, if a directory's permissions do not allow writing, extracting files to it will fail.

경고: Never extract archives from untrusted sources without prior inspection. It is possible that files are created outside of `path`, e.g. members that have absolute filenames starting with `"/"` or filenames with two dots `".."`.

버전 2.5에 추가.

`TarFile.extract(member, path="")`

Extract a member from the archive to the current working directory, using its full name. Its file information is extracted as accurately as possible. `member` may be a filename or a `TarInfo` object. You can specify a different directory using `path`.

참고: The `extract()` method does not take care of several extraction issues. In most cases you should consider using the `extractall()` method.

경고: See the warning for `extractall()`.

`TarFile.extractfile(member)`

Extract a member from the archive as a file object. `member` may be a filename or a `TarInfo` object. If `member` is a regular file, a file-like object is returned. If `member` is a link, a file-like object is constructed from the link's target. If `member` is none of the above, `None` is returned.

참고: The file-like object is read-only. It provides the methods `read()`, `readline()`, `readlines()`, `seek()`, `tell()`, and `close()`, and also supports iteration over its lines.

`TarFile.add(name, arcname=None, recursive=True, exclude=None, filter=None)`

Add the file `name` to the archive. `name` may be any type of file (directory, fifo, symbolic link, etc.). If given, `arcname` specifies an alternative name for the file in the archive. Directories are added recursively by default. This can be avoided by setting `recursive` to `False`. If `exclude` is given it must be a function that takes one filename argument and returns a boolean value. Depending on this value the respective file is either excluded (`True`) or

added (*False*). If *filter* is specified it must be a function that takes a *TarInfo* object argument and returns the changed *TarInfo* object. If it instead returns *None* the *TarInfo* object will be excluded from the archive. See *Examples* for an example.

버전 2.6에서 변경 : Added the *exclude* parameter.

버전 2.7에서 변경 : Added the *filter* parameter.

버전 2.7부터 폐지 : The *exclude* parameter is deprecated, please use the *filter* parameter instead. For maximum portability, *filter* should be used as a keyword argument rather than as a positional argument so that code won't be affected when *exclude* is ultimately removed.

`TarFile.addfile (tarinfo, fileobj=None)`

Add the *TarInfo* object *tarinfo* to the archive. If *fileobj* is given, *tarinfo.size* bytes are read from it and added to the archive. You can create *TarInfo* objects directly, or by using *gettinfo()*.

참고 : On Windows platforms, *fileobj* should always be opened with mode 'rb' to avoid irritation about the file size.

`TarFile.gettarinfo (name=None, arcname=None, fileobj=None)`

Create a *TarInfo* object from the result of *os.stat()* or equivalent on an existing file. The file is either named by *name*, or specified as a file object *fileobj* with a file descriptor. If given, *arcname* specifies an alternative name for the file in the archive, otherwise, the name is taken from *fileobj*'s *name* attribute, or the *name* argument.

You can modify some of the *TarInfo*'s attributes before you add it using *addfile()*. If the file object is not an ordinary file object positioned at the beginning of the file, attributes such as *size* may need modifying. This is the case for objects such as *GzipFile*. The *name* may also be modified, in which case *arcname* could be a dummy string.

`TarFile.close ()`

Close the *TarFile*. In write mode, two finishing zero blocks are appended to the archive.

`TarFile.posix`

Setting this to *True* is equivalent to setting the *format* attribute to *USTAR_FORMAT*, *False* is equivalent to *GNU_FORMAT*.

버전 2.4에서 변경 : *posix* defaults to *False*.

버전 2.6부터 폐지 : Use the *format* attribute instead.

`TarFile.pax_headers`

A dictionary containing key-value pairs of pax global headers.

버전 2.6에 추가.

12.5.2 TarInfo Objects

A *TarInfo* object represents one member in a *TarFile*. Aside from storing all required attributes of a file (like file type, size, time, permissions, owner etc.), it provides some useful methods to determine its type. It does *not* contain the file's data itself.

TarInfo objects are returned by *TarFile*'s methods *getmember()*, *getmembers()* and *gettinfo()*.

class `tarfile.TarInfo (name='')`

Create a *TarInfo* object.

`TarInfo.frombuf (buf)`

Create and return a *TarInfo* object from string buffer *buf*.

버전 2.6에 추가: Raises *HeaderError* if the buffer is invalid..

`TarInfo.fromtarfile(tarfile)`

Read the next member from the *TarFile* object *tarfile* and return it as a *TarInfo* object.

버전 2.6에 추가.

`TarInfo.tobuf(format=DEFAULT_FORMAT, encoding=ENCODING, errors='strict')`

Create a string buffer from a *TarInfo* object. For information on the arguments see the constructor of the *TarFile* class.

버전 2.6에서 변경: The arguments were added.

A *TarInfo* object has the following public data attributes:

`TarInfo.name`

Name of the archive member.

`TarInfo.size`

Size in bytes.

`TarInfo.mtime`

Time of last modification.

`TarInfo.mode`

Permission bits.

`TarInfo.type`

File type. *type* is usually one of these constants: *REGTYPE*, *AREGTYPE*, *LNKTYPE*, *SYMTYPE*, *DIRTYPE*, *FIFOTYPE*, *CONTTYPE*, *CHRTYPE*, *BLKTYPE*, *GNUTYPE_SPARSE*. To determine the type of a *TarInfo* object more conveniently, use the *is*()* methods below.

`TarInfo.linkname`

Name of the target file name, which is only present in *TarInfo* objects of type *LNKTYPE* and *SYMTYPE*.

`TarInfo.uid`

User ID of the user who originally stored this member.

`TarInfo.gid`

Group ID of the user who originally stored this member.

`TarInfo.uname`

User name.

`TarInfo.gname`

Group name.

`TarInfo.pax_headers`

A dictionary containing key-value pairs of an associated pax extended header.

버전 2.6에 추가.

A *TarInfo* object also provides some convenient query methods:

`TarInfo.isfile()`

Return *True* if the *TarInfo* object is a regular file.

`TarInfo.isreg()`

Same as *isfile()*.

`TarInfo.isdir()`

Return *True* if it is a directory.

`TarInfo.issym()`

Return *True* if it is a symbolic link.

```
TarInfo.islnk()
    Return True if it is a hard link.

TarInfo.ischr()
    Return True if it is a character device.

TarInfo.isblk()
    Return True if it is a block device.

TarInfo.isfifo()
    Return True if it is a FIFO.

TarInfo.isdev()
    Return True if it is one of character device, block device or FIFO.
```

12.5.3 Examples

How to extract an entire tar archive to the current working directory:

```
import tarfile
tar = tarfile.open("sample.tar.gz")
tar.extractall()
tar.close()
```

How to extract a subset of a tar archive with `TarFile.extractall()` using a generator function instead of a list:

```
import os
import tarfile

def py_files(members):
    for tarinfo in members:
        if os.path.splitext(tarinfo.name)[1] == ".py":
            yield tarinfo

tar = tarfile.open("sample.tar.gz")
tar.extractall(members=py_files(tar))
tar.close()
```

How to create an uncompressed tar archive from a list of filenames:

```
import tarfile
tar = tarfile.open("sample.tar", "w")
for name in ["foo", "bar", "quux"]:
    tar.add(name)
tar.close()
```

The same example using the `with` statement:

```
import tarfile
with tarfile.open("sample.tar", "w") as tar:
    for name in ["foo", "bar", "quux"]:
        tar.add(name)
```

How to read a gzip compressed tar archive and display some member information:

```
import tarfile
tar = tarfile.open("sample.tar.gz", "r:gz")
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
for tarinfo in tar:
    print tarinfo.name, "is", tarinfo.size, "bytes in size and is",
    if tarinfo.isreg():
        print "a regular file."
    elif tarinfo.isdir():
        print "a directory."
    else:
        print "something else."
tar.close()
```

How to create an archive and reset the user information using the *filter* parameter in `TarFile.add()`:

```
import tarfile
def reset(tarinfo):
    tarinfo.uid = tarinfo.gid = 0
    tarinfo.uname = tarinfo.gname = "root"
    return tarinfo
tar = tarfile.open("sample.tar.gz", "w:gz")
tar.add("foo", filter=reset)
tar.close()
```

12.5.4 Supported tar formats

There are three tar formats that can be created with the `tarfile` module:

- The POSIX.1-1988 ustar format (`USTAR_FORMAT`). It supports filenames up to a length of at best 256 characters and linknames up to 100 characters. The maximum file size is 8 gigabytes. This is an old and limited but widely supported format.
- The GNU tar format (`GNU_FORMAT`). It supports long filenames and linknames, files bigger than 8 gigabytes and sparse files. It is the de facto standard on GNU/Linux systems. `tarfile` fully supports the GNU tar extensions for long names, sparse file support is read-only.
- The POSIX.1-2001 pax format (`PAX_FORMAT`). It is the most flexible format with virtually no limits. It supports long filenames and linknames, large files and stores pathnames in a portable way. However, not all tar implementations today are able to handle pax archives properly.

The *pax* format is an extension to the existing *ustar* format. It uses extra headers for information that cannot be stored otherwise. There are two flavours of pax headers: Extended headers only affect the subsequent file header, global headers are valid for the complete archive and affect all following files. All the data in a pax header is encoded in *UTF-8* for portability reasons.

There are some more variants of the tar format which can be read, but not created:

- The ancient V7 format. This is the first tar format from Unix Seventh Edition, storing only regular files and directories. Names must not be longer than 100 characters, there is no user/group name information. Some archives have miscalculated header checksums in case of fields with non-ASCII characters.
- The SunOS tar extended format. This format is a variant of the POSIX.1-2001 pax format, but is not compatible.

12.5.5 Unicode issues

The tar format was originally conceived to make backups on tape drives with the main focus on preserving file system information. Nowadays tar archives are commonly used for file distribution and exchanging archives over networks. One problem of the original format (that all other formats are merely variants of) is that there is no concept of supporting different character encodings. For example, an ordinary tar archive created on a *UTF-8* system cannot be read correctly on a *Latin-1* system if it contains non-ASCII characters. Names (i.e. filenames, linknames, user/group names) containing these characters will appear damaged. Unfortunately, there is no way to autodetect the encoding of an archive.

The pax format was designed to solve this problem. It stores non-ASCII names using the universal character encoding *UTF-8*. When a pax archive is read, these *UTF-8* names are converted to the encoding of the local file system.

The details of unicode conversion are controlled by the *encoding* and *errors* keyword arguments of the *TarFile* class.

The default value for *encoding* is the local character encoding. It is deduced from *sys.getfilesystemencoding()* and *sys.getdefaultencoding()*. In read mode, *encoding* is used exclusively to convert unicode names from a pax archive to strings in the local character encoding. In write mode, the use of *encoding* depends on the chosen archive format. In case of *PAX_FORMAT*, input names that contain non-ASCII characters need to be decoded before being stored as *UTF-8* strings. The other formats do not make use of *encoding* unless unicode objects are used as input names. These are converted to 8-bit character strings before they are added to the archive.

The *errors* argument defines how characters are treated that cannot be converted to or from *encoding*. Possible values are listed in section *Codec Base Classes*. In read mode, there is an additional scheme `'utf-8'` which means that bad characters are replaced by their *UTF-8* representation. This is the default scheme. In write mode the default value for *errors* is `'strict'` to ensure that name information is not altered unnoticed.

The modules described in this chapter parse various miscellaneous file formats that aren't markup languages or are related to e-mail.

13.1 `csv` — CSV File Reading and Writing

버전 2.3에 추가.

The so-called CSV (Comma Separated Values) format is the most common import and export format for spreadsheets and databases. There is no 《CSV standard》, so the format is operationally defined by the many applications which read and write it. The lack of a standard means that subtle differences often exist in the data produced and consumed by different applications. These differences can make it annoying to process CSV files from multiple sources. Still, while the delimiters and quoting characters vary, the overall format is similar enough that it is possible to write a single module which can efficiently manipulate such data, hiding the details of reading and writing the data from the programmer.

The `csv` module implements classes to read and write tabular data in CSV format. It allows programmers to say, 《write this data in the format preferred by Excel, 》 or 《read data from this file which was generated by Excel, 》 without knowing the precise details of the CSV format used by Excel. Programmers can also describe the CSV formats understood by other applications or define their own special-purpose CSV formats.

The `csv` module's `reader` and `writer` objects read and write sequences. Programmers can also read and write data in dictionary form using the `DictReader` and `DictWriter` classes.

참고: This version of the `csv` module doesn't support Unicode input. Also, there are currently some issues regarding ASCII NUL characters. Accordingly, all input should be UTF-8 or printable ASCII to be safe; see the examples in section *Examples*.

더 보기:

PEP 305 - CSV File API The Python Enhancement Proposal which proposed this addition to Python.

13.1.1 Module Contents

The `csv` module defines the following functions:

`csv.reader(csvfile, dialect='excel', **fmtparams)`

Return a reader object which will iterate over lines in the given *csvfile*. *csvfile* can be any object which supports the *iterator* protocol and returns a string each time its `next()` method is called — file objects and list objects are both suitable. If *csvfile* is a file object, it must be opened with the `` flag on platforms where that makes a difference. An optional *dialect* parameter can be given which is used to define a set of parameters specific to a particular CSV dialect. It may be an instance of a subclass of the *Dialect* class or one of the strings returned by the `list_dialects()` function. The other optional *fmtparams* keyword arguments can be given to override individual formatting parameters in the current dialect. For full details about the dialect and formatting parameters, see section *Dialects and Formatting Parameters*.

Each row read from the csv file is returned as a list of strings. No automatic data type conversion is performed.

A short usage example:

```
>>> import csv
>>> with open('eggs.csv', 'rb') as csvfile:
...     spamreader = csv.reader(csvfile, delimiter=' ', quotechar='|')
...     for row in spamreader:
...         print ', '.join(row)
Spam, Spam, Spam, Spam, Spam, Baked Beans
Spam, Lovely Spam, Wonderful Spam
```

버전 2.5에서 변경: The parser is now stricter with respect to multi-line quoted fields. Previously, if a line ended within a quoted field without a terminating newline character, a newline would be inserted into the returned field. This behavior caused problems when reading files which contained carriage return characters within fields. The behavior was changed to return the field without inserting newlines. As a consequence, if newlines embedded within fields are important, the input should be split into lines in a manner which preserves the newline characters.

`csv.writer(csvfile, dialect='excel', **fmtparams)`

Return a writer object responsible for converting the user's data into delimited strings on the given file-like object. *csvfile* can be any object with a `write()` method. If *csvfile* is a file object, it must be opened with the `` flag on platforms where that makes a difference. An optional *dialect* parameter can be given which is used to define a set of parameters specific to a particular CSV dialect. It may be an instance of a subclass of the *Dialect* class or one of the strings returned by the `list_dialects()` function. The other optional *fmtparams* keyword arguments can be given to override individual formatting parameters in the current dialect. For full details about the dialect and formatting parameters, see section *Dialects and Formatting Parameters*. To make it as easy as possible to interface with modules which implement the DB API, the value *None* is written as the empty string. While this isn't a reversible transformation, it makes it easier to dump SQL NULL data values to CSV files without preprocessing the data returned from a `cursor.fetch*` call. Floats are stringified with `repr()` before being written. All other non-string data are stringified with `str()` before being written.

A short usage example:

```
import csv
with open('eggs.csv', 'wb') as csvfile:
    spamwriter = csv.writer(csvfile, delimiter=' ',
                           quotechar='|', quoting=csv.QUOTE_MINIMAL)
    spamwriter.writerow(['Spam'] * 5 + ['Baked Beans'])
    spamwriter.writerow(['Spam', 'Lovely Spam', 'Wonderful Spam'])
```

`csv.register_dialect(name[, dialect], **fmtparams)`

Associate *dialect* with *name*. *name* must be a string or Unicode object. The dialect can be specified either by passing a sub-class of *Dialect*, or by *fmtparams* keyword arguments, or both, with keyword arguments overriding

parameters of the dialect. For full details about the dialect and formatting parameters, see section [Dialects and Formatting Parameters](#).

`CSV.unregister_dialect(name)`

Delete the dialect associated with *name* from the dialect registry. An *Error* is raised if *name* is not a registered dialect name.

`CSV.get_dialect(name)`

Return the dialect associated with *name*. An *Error* is raised if *name* is not a registered dialect name.

버전 2.5에서 변경: This function now returns an immutable *Dialect*. Previously an instance of the requested dialect was returned. Users could modify the underlying class, changing the behavior of active readers and writers.

`CSV.list_dialects()`

Return the names of all registered dialects.

`CSV.field_size_limit([new_limit])`

Returns the current maximum field size allowed by the parser. If *new_limit* is given, this becomes the new limit.

버전 2.5에 추가.

The *csv* module defines the following classes:

class `CSV.DictReader(f, fieldnames=None, restkey=None, restval=None, dialect='excel', *args, **kwargs)`

Create an object which operates like a regular reader but maps the information read into a dict whose keys are given by the optional *fieldnames* parameter. The *fieldnames* parameter is a *sequence* whose elements are associated with the fields of the input data in order. These elements become the keys of the resulting dictionary. If the *fieldnames* parameter is omitted, the values in the first row of the file *f* will be used as the fieldnames. If the row read has more fields than the fieldnames sequence, the remaining data is added as a sequence keyed by the value of *restkey*. If the row read has fewer fields than the fieldnames sequence, the remaining keys take the value of the optional *restval* parameter. Any other optional or keyword arguments are passed to the underlying *reader* instance.

A short usage example:

```
>>> import csv
>>> with open('names.csv') as csvfile:
...     reader = csv.DictReader(csvfile)
...     for row in reader:
...         print(row['first_name'], row['last_name'])
...
Baked Beans
Lovely Spam
Wonderful Spam
```

class `CSV.DictWriter(f, fieldnames, restval="", extrasaction='raise', dialect='excel', *args, **kwargs)`

Create an object which operates like a regular writer but maps dictionaries onto output rows. The *fieldnames* parameter is a *sequence* of keys that identify the order in which values in the dictionary passed to the *writerow()* method are written to the file *f*. The optional *restval* parameter specifies the value to be written if the dictionary is missing a key in *fieldnames*. If the dictionary passed to the *writerow()* method contains a key not found in *fieldnames*, the optional *extrasaction* parameter indicates what action to take. If it is set to 'raise' a *ValueError* is raised. If it is set to 'ignore', extra values in the dictionary are ignored. Any other optional or keyword arguments are passed to the underlying *writer* instance.

Note that unlike the *DictReader* class, the *fieldnames* parameter of the *DictWriter* is not optional. Since Python's *dict* objects are not ordered, there is not enough information available to deduce the order in which the row should be written to the file *f*.

A short usage example:

```
import csv

with open('names.csv', 'w') as csvfile:
    fieldnames = ['first_name', 'last_name']
    writer = csv.DictWriter(csvfile, fieldnames=fieldnames)

    writer.writeheader()
    writer.writerow({'first_name': 'Baked', 'last_name': 'Beans'})
    writer.writerow({'first_name': 'Lovely', 'last_name': 'Spam'})
    writer.writerow({'first_name': 'Wonderful', 'last_name': 'Spam'})
```

class csv.Dialect

The *Dialect* class is a container class relied on primarily for its attributes, which are used to define the parameters for a specific *reader* or *writer* instance.

class csv.excel

The *excel* class defines the usual properties of an Excel-generated CSV file. It is registered with the dialect name 'excel'.

class csv.excel_tab

The *excel_tab* class defines the usual properties of an Excel-generated TAB-delimited file. It is registered with the dialect name 'excel-tab'.

class csv.Sniffer

The *Sniffer* class is used to deduce the format of a CSV file.

The *Sniffer* class provides two methods:

sniff (*sample*, *delimiters=None*)

Analyze the given *sample* and return a *Dialect* subclass reflecting the parameters found. If the optional *delimiters* parameter is given, it is interpreted as a string containing possible valid delimiter characters.

has_header (*sample*)

Analyze the sample text (presumed to be in CSV format) and return *True* if the first row appears to be a series of column headers.

An example for *Sniffer* use:

```
with open('example.csv', 'rb') as csvfile:
    dialect = csv.Sniffer().sniff(csvfile.read(1024))
    csvfile.seek(0)
    reader = csv.reader(csvfile, dialect)
    # ... process CSV file contents here ...
```

The *csv* module defines the following constants:

csv.QUOTE_ALL

Instructs *writer* objects to quote all fields.

csv.QUOTE_MINIMAL

Instructs *writer* objects to only quote those fields which contain special characters such as *delimiter*, *quotechar* or any of the characters in *lineterminator*.

csv.QUOTE_NONNUMERIC

Instructs *writer* objects to quote all non-numeric fields.

Instructs the reader to convert all non-quoted fields to type *float*.

csv.QUOTE_NONE

Instructs *writer* objects to never quote fields. When the current *delimiter* occurs in output data it is preceded by

the current *escapechar* character. If *escapechar* is not set, the writer will raise *Error* if any characters that require escaping are encountered.

Instructs *reader* to perform no special processing of quote characters.

The *csv* module defines the following exception:

exception *csv.Error*

Raised by any of the functions when an error is detected.

13.1.2 Dialects and Formatting Parameters

To make it easier to specify the format of input and output records, specific formatting parameters are grouped together into dialects. A dialect is a subclass of the *Dialect* class having a set of specific methods and a single *validate()* method. When creating *reader* or *writer* objects, the programmer can specify a string or a subclass of the *Dialect* class as the dialect parameter. In addition to, or instead of, the *dialect* parameter, the programmer can also specify individual formatting parameters, which have the same names as the attributes defined below for the *Dialect* class.

Dialects support the following attributes:

Dialect.delimiter

A one-character string used to separate fields. It defaults to *','*.

Dialect.doublequote

Controls how instances of *quotechar* appearing inside a field should themselves be quoted. When *True*, the character is doubled. When *False*, the *escapechar* is used as a prefix to the *quotechar*. It defaults to *True*.

On output, if *doublequote* is *False* and no *escapechar* is set, *Error* is raised if a *quotechar* is found in a field.

Dialect.escapechar

A one-character string used by the writer to escape the *delimiter* if *quoting* is set to *QUOTE_NONE* and the *quotechar* if *doublequote* is *False*. On reading, the *escapechar* removes any special meaning from the following character. It defaults to *None*, which disables escaping.

Dialect.lineterminator

The string used to terminate lines produced by the *writer*. It defaults to *'\\r\\n'*.

참고: The *reader* is hard-coded to recognise either *'\\r'* or *'\\n'* as end-of-line, and ignores *lineterminator*. This behavior may change in the future.

Dialect.quotechar

A one-character string used to quote fields containing special characters, such as the *delimiter* or *quotechar*, or which contain new-line characters. It defaults to *'\"'*.

Dialect.quoting

Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the *QUOTE_** constants (see section *Module Contents*) and defaults to *QUOTE_MINIMAL*.

Dialect.skipinitialspace

When *True*, whitespace immediately following the *delimiter* is ignored. The default is *False*.

Dialect.strict

When *True*, raise exception *Error* on bad CSV input. The default is *False*.

13.1.3 Reader Objects

Reader objects (*DictReader* instances and objects returned by the *reader()* function) have the following public methods:

`csvreader.next()`

Return the next row of the reader's iterable object as a list, parsed according to the current dialect.

Reader objects have the following public attributes:

`csvreader.dialect`

A read-only description of the dialect in use by the parser.

`csvreader.line_num`

The number of lines read from the source iterator. This is not the same as the number of records returned, as records can span multiple lines.

버전 2.5에 추가.

DictReader objects have the following public attribute:

`csvreader.fieldnames`

If not passed as a parameter when creating the object, this attribute is initialized upon first access or when the first record is read from the file.

버전 2.6에서 변경.

13.1.4 Writer Objects

Writer objects (*DictWriter* instances and objects returned by the *writer()* function) have the following public methods. A *row* must be a sequence of strings or numbers for *Writer* objects and a dictionary mapping fieldnames to strings or numbers (by passing them through *str()* first) for *DictWriter* objects. Note that complex numbers are written out surrounded by parens. This may cause some problems for other programs which read CSV files (assuming they support complex numbers at all).

`csvwriter.writerow(row)`

Write the *row* parameter to the writer's file object, formatted according to the current dialect.

`csvwriter.writerows(rows)`

Write all elements in *rows* (an iterable of *row* objects as described above) to the writer's file object, formatted according to the current dialect.

Writer objects have the following public attribute:

`csvwriter.dialect`

A read-only description of the dialect in use by the writer.

DictWriter objects have the following public method:

`DictWriter.writeheader()`

Write a row with the field names (as specified in the constructor).

버전 2.7에 추가.

13.1.5 Examples

The simplest example of reading a CSV file:

```
import csv
with open('some.csv', 'rb') as f:
    reader = csv.reader(f)
    for row in reader:
        print row
```

Reading a file with an alternate format:

```
import csv
with open('passwd', 'rb') as f:
    reader = csv.reader(f, delimiter=':', quoting=csv.QUOTE_NONE)
    for row in reader:
        print row
```

The corresponding simplest possible writing example is:

```
import csv
with open('some.csv', 'wb') as f:
    writer = csv.writer(f)
    writer.writerows(someiterable)
```

Registering a new dialect:

```
import csv
csv.register_dialect('unixpwd', delimiter=':', quoting=csv.QUOTE_NONE)
with open('passwd', 'rb') as f:
    reader = csv.reader(f, 'unixpwd')
```

A slightly more advanced use of the reader — catching and reporting errors:

```
import csv, sys
filename = 'some.csv'
with open(filename, 'rb') as f:
    reader = csv.reader(f)
    try:
        for row in reader:
            print row
    except csv.Error as e:
        sys.exit('file %s, line %d: %s' % (filename, reader.line_num, e))
```

And while the module doesn't directly support parsing strings, it can easily be done:

```
import csv
for row in csv.reader(['one,two,three']):
    print row
```

The `csv` module doesn't directly support reading and writing Unicode, but it is 8-bit-clean save for some problems with ASCII NUL characters. So you can write functions or classes that handle the encoding and decoding for you as long as you avoid encodings like UTF-16 that use NULs. UTF-8 is recommended.

`unicode_csv_reader()` below is a *generator* that wraps `csv.reader` to handle Unicode CSV data (a list of Unicode strings). `utf_8_encoder()` is a *generator* that encodes the Unicode strings as UTF-8, one string (or row) at a time. The encoded strings are parsed by the CSV reader, and `unicode_csv_reader()` decodes the UTF-8-encoded cells back into Unicode:

```
import csv

def unicode_csv_reader(unicode_csv_data, dialect=csv.excel, **kwargs):
    # csv.py doesn't do Unicode; encode temporarily as UTF-8:
    csv_reader = csv.reader(utf_8_encoder(unicode_csv_data),
                            dialect=dialect, **kwargs)
    for row in csv_reader:
        # decode UTF-8 back to Unicode, cell by cell:
        yield [unicode(cell, 'utf-8') for cell in row]

def utf_8_encoder(unicode_csv_data):
    for line in unicode_csv_data:
        yield line.encode('utf-8')
```

For all other encodings the following `UnicodeReader` and `UnicodeWriter` classes can be used. They take an additional *encoding* parameter in their constructor and make sure that the data passes the real reader or writer encoded as UTF-8:

```
import csv, codecs, cStringIO

class UTF8Recoder:
    """
    Iterator that reads an encoded stream and reencodes the input to UTF-8
    """
    def __init__(self, f, encoding):
        self.reader = codecs.getreader(encoding)(f)

    def __iter__(self):
        return self

    def next(self):
        return self.reader.next().encode("utf-8")

class UnicodeReader:
    """
    A CSV reader which will iterate over lines in the CSV file "f",
    which is encoded in the given encoding.
    """
    def __init__(self, f, dialect=csv.excel, encoding="utf-8", **kwds):
        f = UTF8Recoder(f, encoding)
        self.reader = csv.reader(f, dialect=dialect, **kwds)

    def next(self):
        row = self.reader.next()
        return [unicode(s, "utf-8") for s in row]

    def __iter__(self):
        return self

class UnicodeWriter:
    """
    A CSV writer which will write rows to CSV file "f",
    which is encoded in the given encoding.
    """
    def __init__(self, f, dialect=csv.excel, encoding="utf-8", **kwds):
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

# Redirect output to a queue
self.queue = cStringIO.StringIO()
self.writer = csv.writer(self.queue, dialect=dialect, **kwargs)
self.stream = f
self.encoder = codecs.getincrementalencoder(encoding)()

def writerow(self, row):
    self.writer.writerow([s.encode("utf-8") for s in row])
    # Fetch UTF-8 output from the queue ...
    data = self.queue.getvalue()
    data = data.decode("utf-8")
    # ... and reencode it into the target encoding
    data = self.encoder.encode(data)
    # write to the target stream
    self.stream.write(data)
    # empty queue
    self.queue.truncate(0)

def writerows(self, rows):
    for row in rows:
        self.writerow(row)

```

13.2 ConfigParser — Configuration file parser

참고: The `ConfigParser` module has been renamed to `configparser` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

This module defines the class `ConfigParser`. The `ConfigParser` class implements a basic configuration file parser language which provides a structure similar to what you would find on Microsoft Windows INI files. You can use this to write Python programs which can be customized by end users easily.

참고: This library does *not* interpret or write the value-type prefixes used in the Windows Registry extended version of INI syntax.

더 보기:

Module `shlex` Support for creating Unix shell-like mini-languages which can be used as an alternate format for application configuration files.

Module `json` The `json` module implements a subset of JavaScript syntax which can also be used for this purpose.

The configuration file consists of sections, led by a `[section]` header and followed by `name: value` entries, with continuations in the style of **RFC 822** (see section 3.1.1, «LONG HEADER FIELDS»); `name=value` is also accepted. Note that leading whitespace is removed from values. The optional values can contain format strings which refer to other values in the same section, or values in a special `DEFAULT` section. Additional defaults can be provided on initialization and retrieval. Lines beginning with `'#'` or `';'` are ignored and may be used to provide comments.

Configuration files may include comments, prefixed by specific characters (`#` and `;`). Comments may appear on their own in an otherwise empty line, or may be entered in lines holding values or section names. In the latter case, they need to be preceded by a whitespace character to be recognized as a comment. (For backwards compatibility, only `;` starts an inline comment, while `#` does not.)

On top of the core functionality, *SafeConfigParser* supports interpolation. This means values can contain format strings which refer to other values in the same section, or values in a special `DEFAULT` section. Additional defaults can be provided on initialization.

For example:

```
[My Section]
foodir: %(dir)s/whatever
dir=frob
long: this value continues
    in the next line
```

would resolve the `%(dir)s` to the value of `dir` (`frob` in this case). All reference expansions are done on demand.

Default values can be specified by passing them into the *ConfigParser* constructor as a dictionary. Additional defaults may be passed into the `get()` method which will override all others.

Sections are normally stored in a built-in dictionary. An alternative dictionary type can be passed to the *ConfigParser* constructor. For example, if a dictionary type is passed that sorts its keys, the sections will be sorted on write-back, as will be the keys within each section.

class *ConfigParser.RawConfigParser* ([*defaults* [, *dict_type* [, *allow_no_value*]]])

The basic configuration object. When *defaults* is given, it is initialized into the dictionary of intrinsic defaults. When *dict_type* is given, it will be used to create the dictionary objects for the list of sections, for the options within a section, and for the default values. When *allow_no_value* is true (default: `False`), options without values are accepted; the value presented for these is `None`.

This class does not support the magical interpolation behavior.

All option names are passed through the *optionxform()* method. Its default implementation converts option names to lower case.

버전 2.3에 추가.

버전 2.6에서 변경: *dict_type* was added.

버전 2.7에서 변경: The default *dict_type* is *collections.OrderedDict*. *allow_no_value* was added.

class *ConfigParser.ConfigParser* ([*defaults* [, *dict_type* [, *allow_no_value*]]])

Derived class of *RawConfigParser* that implements the magical interpolation feature and adds optional arguments to the *get()* and *items()* methods. The values in *defaults* must be appropriate for the `%()s` string interpolation. Note that `__name__` is an intrinsic default; its value is the section name, and will override any value provided in *defaults*.

All option names used in interpolation will be passed through the *optionxform()* method just like any other option name reference. Using the default implementation of *optionxform()*, the values `foo %(bar)s` and `foo %(BAR)s` are equivalent.

버전 2.3에 추가.

버전 2.6에서 변경: *dict_type* was added.

버전 2.7에서 변경: The default *dict_type* is *collections.OrderedDict*. *allow_no_value* was added.

class *ConfigParser.SafeConfigParser* ([*defaults* [, *dict_type* [, *allow_no_value*]]])

Derived class of *ConfigParser* that implements a more-sane variant of the magical interpolation feature. This implementation is more predictable as well. New applications should prefer this version if they don't need to be compatible with older versions of Python.

버전 2.3에 추가.

버전 2.6에서 변경: *dict_type* was added.

버전 2.7에서 변경: The default *dict_type* is *collections.OrderedDict*. *allow_no_value* was added.

exception `ConfigParser.Error`

Base class for all other configparser exceptions.

exception `ConfigParser.NoSectionError`

Exception raised when a specified section is not found.

exception `ConfigParser.DuplicateSectionError`

Exception raised if `add_section()` is called with the name of a section that is already present.

exception `ConfigParser.NoOptionError`

Exception raised when a specified option is not found in the specified section.

exception `ConfigParser.InterpolationError`

Base class for exceptions raised when problems occur performing string interpolation.

exception `ConfigParser.InterpolationDepthError`

Exception raised when string interpolation cannot be completed because the number of iterations exceeds `MAX_INTERPOLATION_DEPTH`. Subclass of `InterpolationError`.

exception `ConfigParser.InterpolationMissingOptionError`

Exception raised when an option referenced from a value does not exist. Subclass of `InterpolationError`.

버전 2.3에 추가.

exception `ConfigParser.InterpolationSyntaxError`

Exception raised when the source text into which substitutions are made does not conform to the required syntax. Subclass of `InterpolationError`.

버전 2.3에 추가.

exception `ConfigParser.MissingSectionHeaderError`

Exception raised when attempting to parse a file which has no section headers.

exception `ConfigParser.ParsingError`

Exception raised when errors occur attempting to parse a file.

`ConfigParser.MAX_INTERPOLATION_DEPTH`

The maximum depth for recursive interpolation for `get()` when the `raw` parameter is false. This is relevant only for the `ConfigParser` class.

더 보기:

Module `shlex` Support for a creating Unix shell-like mini-languages which can be used as an alternate format for application configuration files.

13.2.1 RawConfigParser Objects

`RawConfigParser` instances have the following methods:

`RawConfigParser.defaults()`

Return a dictionary containing the instance-wide defaults.

`RawConfigParser.sections()`

Return a list of the sections available; `DEFAULT` is not included in the list.

`RawConfigParser.add_section(section)`

Add a section named `section` to the instance. If a section by the given name already exists, `DuplicateSectionError` is raised. If the name `DEFAULT` (or any of its case-insensitive variants) is passed, `ValueError` is raised.

`RawConfigParser.has_section(section)`

Indicates whether the named section is present in the configuration. The `DEFAULT` section is not acknowledged.

`RawConfigParser.options(section)`

Returns a list of options available in the specified *section*.

`RawConfigParser.has_option(section, option)`

If the given section exists, and contains the given option, return *True*; otherwise return *False*.

버전 1.6에 추가.

`RawConfigParser.read(filenames)`

Attempt to read and parse a list of filenames, returning a list of filenames which were successfully parsed. If *filenames* is a string or Unicode string, it is treated as a single filename. If a file named in *filenames* cannot be opened, that file will be ignored. This is designed so that you can specify a list of potential configuration file locations (for example, the current directory, the user's home directory, and some system-wide directory), and all existing configuration files in the list will be read. If none of the named files exist, the *ConfigParser* instance will contain an empty dataset. An application which requires initial values to be loaded from a file should load the required file or files using *readfp()* before calling *read()* for any optional files:

```
import ConfigParser, os

config = ConfigParser.ConfigParser()
config.readfp(open('defaults.cfg'))
config.read(['site.cfg', os.path.expanduser('~/.myapp.cfg')])
```

버전 2.4에서 변경: Returns list of successfully parsed filenames.

`RawConfigParser.readfp(fp[, filename])`

Read and parse configuration data from the file or file-like object in *fp* (only the *readline()* method is used). If *filename* is omitted and *fp* has a *name* attribute, that is used for *filename*; the default is *<??>*.

`RawConfigParser.get(section, option)`

Get an *option* value for the named *section*.

`RawConfigParser.getint(section, option)`

A convenience method which coerces the *option* in the specified *section* to an integer.

`RawConfigParser.getfloat(section, option)`

A convenience method which coerces the *option* in the specified *section* to a floating point number.

`RawConfigParser.getboolean(section, option)`

A convenience method which coerces the *option* in the specified *section* to a Boolean value. Note that the accepted values for the option are "1", "yes", "true", and "on", which cause this method to return *True*, and "0", "no", "false", and "off", which cause it to return *False*. These string values are checked in a case-insensitive manner. Any other value will cause it to raise *ValueError*.

`RawConfigParser.items(section)`

Return a list of (name, value) pairs for each option in the given *section*.

`RawConfigParser.set(section, option, value)`

If the given section exists, set the given option to the specified value; otherwise raise *NoSectionError*. While it is possible to use *RawConfigParser* (or *ConfigParser* with *raw* parameters set to true) for *internal* storage of non-string values, full functionality (including interpolation and output to files) can only be achieved using string values.

버전 1.6에 추가.

`RawConfigParser.write(fileobject)`

Write a representation of the configuration to the specified file object. This representation can be parsed by a future *read()* call.

버전 1.6에 추가.

`RawConfigParser.remove_option(section, option)`

Remove the specified *option* from the specified *section*. If the section does not exist, raise `NoSectionError`. If the option existed to be removed, return `True`; otherwise return `False`.

버전 1.6에 추가.

`RawConfigParser.remove_section(section)`

Remove the specified *section* from the configuration. If the section in fact existed, return `True`. Otherwise return `False`.

`RawConfigParser.optionxform(option)`

Transforms the option name *option* as found in an input file or as passed in by client code to the form that should be used in the internal structures. The default implementation returns a lower-case version of *option*; subclasses may override this or client code can set an attribute of this name on instances to affect this behavior.

You don't necessarily need to subclass a `ConfigParser` to use this method, you can also re-set it on an instance, to a function that takes a string argument. Setting it to `str`, for example, would make option names case sensitive:

```
cfgparser = ConfigParser()
...
cfgparser.optionxform = str
```

Note that when reading configuration files, whitespace around the option names are stripped before `optionxform()` is called.

13.2.2 ConfigParser Objects

The `ConfigParser` class extends some methods of the `RawConfigParser` interface, adding some optional arguments.

`ConfigParser.get(section, option[, raw[, vars]])`

Get an *option* value for the named *section*. If *vars* is provided, it must be a dictionary. The *option* is looked up in *vars* (if provided), *section*, and in *defaults* in that order.

All the `'%'` interpolations are expanded in the return values, unless the *raw* argument is true. Values for interpolation keys are looked up in the same manner as the option.

`ConfigParser.items(section[, raw[, vars]])`

Return a list of (*name*, *value*) pairs for each option in the given *section*. Optional arguments have the same meaning as for the `get()` method.

버전 2.3에 추가.

13.2.3 SafeConfigParser Objects

The `SafeConfigParser` class implements the same extended interface as `ConfigParser`, with the following addition:

`SafeConfigParser.set(section, option, value)`

If the given section exists, set the given option to the specified value; otherwise raise `NoSectionError`. *value* must be a string (`str` or `unicode`); if not, `TypeError` is raised.

버전 2.4에 추가.

13.2.4 Examples

An example of writing to a configuration file:

```
import ConfigParser

config = ConfigParser.RawConfigParser()

# When adding sections or items, add them in the reverse order of
# how you want them to be displayed in the actual file.
# In addition, please note that using RawConfigParser's and the raw
# mode of ConfigParser's respective set functions, you can assign
# non-string values to keys internally, but will receive an error
# when attempting to write to a file or when you get it in non-raw
# mode. SafeConfigParser does not allow such assignments to take place.
config.add_section('Section1')
config.set('Section1', 'an_int', '15')
config.set('Section1', 'a_bool', 'true')
config.set('Section1', 'a_float', '3.1415')
config.set('Section1', 'baz', 'fun')
config.set('Section1', 'bar', 'Python')
config.set('Section1', 'foo', '%(bar)s is %(baz)s!')

# Writing our configuration file to 'example.cfg'
with open('example.cfg', 'wb') as configfile:
    config.write(configfile)
```

An example of reading the configuration file again:

```
import ConfigParser

config = ConfigParser.RawConfigParser()
config.read('example.cfg')

# getfloat() raises an exception if the value is not a float
# getint() and getboolean() also do this for their respective types
a_float = config.getfloat('Section1', 'a_float')
an_int = config.getint('Section1', 'an_int')
print a_float + an_int

# Notice that the next output does not interpolate '%(bar)s' or '%(baz)s'.
# This is because we are using a RawConfigParser().
if config.getboolean('Section1', 'a_bool'):
    print config.get('Section1', 'foo')
```

To get interpolation, you will need to use a *ConfigParser* or *SafeConfigParser*:

```
import ConfigParser

config = ConfigParser.ConfigParser()
config.read('example.cfg')

# Set the third, optional argument of get to 1 if you wish to use raw mode.
print config.get('Section1', 'foo', 0) # -> "Python is fun!"
print config.get('Section1', 'foo', 1) # -> "%(bar)s is %(baz)s!"

# The optional fourth argument is a dict with members that will take
# precedence in interpolation.
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
print config.get('Section1', 'foo', 0, {'bar': 'Documentation',
                                       'baz': 'evil'})
```

Defaults are available in all three types of ConfigParsers. They are used in interpolation if an option used is not defined elsewhere.

```
import ConfigParser

# New instance with 'bar' and 'baz' defaulting to 'Life' and 'hard' each
config = ConfigParser.SafeConfigParser({'bar': 'Life', 'baz': 'hard'})
config.read('example.cfg')

print config.get('Section1', 'foo') # -> "Python is fun!"
config.remove_option('Section1', 'bar')
config.remove_option('Section1', 'baz')
print config.get('Section1', 'foo') # -> "Life is hard!"
```

The function `opt_move` below can be used to move options between sections:

```
def opt_move(config, section1, section2, option):
    try:
        config.set(section2, option, config.get(section1, option, 1))
    except ConfigParser.NoSectionError:
        # Create non-existent section
        config.add_section(section2)
        opt_move(config, section1, section2, option)
    else:
        config.remove_option(section1, option)
```

Some configuration files are known to include settings without values, but which otherwise conform to the syntax supported by `ConfigParser`. The `allow_no_value` parameter to the constructor can be used to indicate that such values should be accepted:

```
>>> import ConfigParser
>>> import io

>>> sample_config = """
... [mysqld]
... user = mysql
... pid-file = /var/run/mysqld/mysqld.pid
... skip-external-locking
... old_passwords = 1
... skip-bdb
... skip-innodb
... """
>>> config = ConfigParser.RawConfigParser(allow_no_value=True)
>>> config.readfp(io.BytesIO(sample_config))

>>> # Settings with values are treated as before:
>>> config.get("mysqld", "user")
'mysql'

>>> # Settings without values provide None:
>>> config.get("mysqld", "skip-bdb")

>>> # Settings which aren't specified still raise an error:
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> config.get("mysqld", "does-not-exist")
Traceback (most recent call last):
...
ConfigParser.NoOptionError: No option 'does-not-exist' in section: 'mysqld'
```

13.3 robotparser — Parser for robots.txt

참고: The `robotparser` module has been renamed `urllib.robotparser` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

This module provides a single class, `RobotFileParser`, which answers questions about whether or not a particular user agent can fetch a URL on the Web site that published the `robots.txt` file. For more details on the structure of `robots.txt` files, see <http://www.robotstxt.org/orig.html>.

class `robotparser.RobotFileParser` (*url*="")

This class provides methods to read, parse and answer questions about the `robots.txt` file at *url*.

set_url (*url*)

Sets the URL referring to a `robots.txt` file.

read ()

Reads the `robots.txt` URL and feeds it to the parser.

parse (*lines*)

Parses the lines argument.

can_fetch (*useragent*, *url*)

Returns True if the *useragent* is allowed to fetch the *url* according to the rules contained in the parsed `robots.txt` file.

mtime ()

Returns the time the `robots.txt` file was last fetched. This is useful for long-running web spiders that need to check for new `robots.txt` files periodically.

modified ()

Sets the time the `robots.txt` file was last fetched to the current time.

The following example demonstrates basic use of the `RobotFileParser` class.

```
>>> import robotparser
>>> rp = robotparser.RobotFileParser()
>>> rp.set_url("http://www.musi-cal.com/robots.txt")
>>> rp.read()
>>> rp.can_fetch("*", "http://www.musi-cal.com/cgi-bin/search?city=San+Francisco")
False
>>> rp.can_fetch("*", "http://www.musi-cal.com/")
True
```


13.4 netrc — netrc file processing

버전 1.5.2에 추가.

Source code: [Lib/netrc.py](#)

The `netrc` class parses and encapsulates the netrc file format used by the Unix `ftp` program and other FTP clients.

class `netrc.netrc` (`[file]`)

A `netrc` instance or subclass instance encapsulates data from a netrc file. The initialization argument, if present, specifies the file to parse. If no argument is given, the file `.netrc` in the user's home directory will be read. Parse errors will raise `NetrcParseError` with diagnostic information including the file name, line number, and terminating token. If no argument is specified on a POSIX system, the presence of passwords in the `.netrc` file will raise a `NetrcParseError` if the file ownership or permissions are insecure (owned by a user other than the user running the process, or accessible for read or write by any other user). This implements security behavior equivalent to that of `ftp` and other programs that use `.netrc`.

버전 2.7.6에서 변경: Added the POSIX permissions check.

exception `netrc.NetrcParseError`

Exception raised by the `netrc` class when syntactical errors are encountered in source text. Instances of this exception provide three interesting attributes: `msg` is a textual explanation of the error, `filename` is the name of the source file, and `lineno` gives the line number on which the error was found.

13.4.1 netrc Objects

A `netrc` instance has the following methods:

`netrc.authenticators` (`host`)

Return a 3-tuple (`login`, `account`, `password`) of authenticators for `host`. If the netrc file did not contain an entry for the given host, return the tuple associated with the `<default>` entry. If neither matching host nor default entry is available, return `None`.

`netrc.__repr__` ()

Dump the class data as a string in the format of a netrc file. (This discards comments and may reorder the entries.)

Instances of `netrc` have public instance variables:

`netrc.hosts`

Dictionary mapping host names to (`login`, `account`, `password`) tuples. The `<default>` entry, if any, is represented as a pseudo-host by that name.

`netrc.macros`

Dictionary mapping macro names to string lists.

참고: Passwords are limited to a subset of the ASCII character set. Versions of this module prior to 2.3 were extremely limited. Starting with 2.3, all ASCII punctuation is allowed in passwords. However, note that whitespace and non-printable characters are not allowed in passwords. This is a limitation of the way the `.netrc` file is parsed and may be removed in the future.

13.5 `xdrlib` — Encode and decode XDR data

Source code: [Lib/xdrlib.py](#)

The `xdrlib` module supports the External Data Representation Standard as described in [RFC 1014](#), written by Sun Microsystems, Inc. June 1987. It supports most of the data types described in the RFC.

The `xdrlib` module defines two classes, one for packing variables into XDR representation, and another for unpacking from XDR representation. There are also two exception classes.

class `xdrlib.Packer`

Packer is the class for packing data into XDR representation. The *Packer* class is instantiated with no arguments.

class `xdrlib.Unpacker` (*data*)

Unpacker is the complementary class which unpacks XDR data values from a string buffer. The input buffer is given as *data*.

더 보기:

RFC 1014 - XDR: External Data Representation Standard This RFC defined the encoding of data which was XDR at the time this module was originally written. It has apparently been obsoleted by [RFC 1832](#).

RFC 1832 - XDR: External Data Representation Standard Newer RFC that provides a revised definition of XDR.

13.5.1 Packer Objects

Packer instances have the following methods:

`Packer.get_buffer()`

Returns the current pack buffer as a string.

`Packer.reset()`

Resets the pack buffer to the empty string.

In general, you can pack any of the most common XDR data types by calling the appropriate `pack_type()` method. Each method takes a single argument, the value to pack. The following simple data type packing methods are supported: `pack_uint()`, `pack_int()`, `pack_enum()`, `pack_bool()`, `pack_uhyper()`, and `pack_hyper()`.

`Packer.pack_float(value)`

Packs the single-precision floating point number *value*.

`Packer.pack_double(value)`

Packs the double-precision floating point number *value*.

The following methods support packing strings, bytes, and opaque data:

`Packer.pack_fstring(n, s)`

Packs a fixed length string, *s*. *n* is the length of the string but it is *not* packed into the data buffer. The string is padded with null bytes if necessary to guaranteed 4 byte alignment.

`Packer.pack_fopaque(n, data)`

Packs a fixed length opaque data stream, similarly to `pack_fstring()`.

`Packer.pack_string(s)`

Packs a variable length string, *s*. The length of the string is first packed as an unsigned integer, then the string data is packed with `pack_fstring()`.

`Packer.pack_opaque(data)`

Packs a variable length opaque data string, similarly to `pack_string()`.

`Packer.pack_bytes(bytes)`

Packs a variable length byte stream, similarly to `pack_string()`.

The following methods support packing arrays and lists:

`Packer.pack_list(list, pack_item)`

Packs a *list* of homogeneous items. This method is useful for lists with an indeterminate size; i.e. the size is not available until the entire list has been walked. For each item in the list, an unsigned integer 1 is packed first, followed by the data value from the list. `pack_item` is the function that is called to pack the individual item. At the end of the list, an unsigned integer 0 is packed.

For example, to pack a list of integers, the code might appear like this:

```
import xdrlib
p = xdrlib.Packer()
p.pack_list([1, 2, 3], p.pack_int)
```

`Packer.pack_farray(n, array, pack_item)`

Packs a fixed length list (*array*) of homogeneous items. *n* is the length of the list; it is *not* packed into the buffer, but a `ValueError` exception is raised if `len(array)` is not equal to *n*. As above, `pack_item` is the function used to pack each element.

`Packer.pack_array(list, pack_item)`

Packs a variable length *list* of homogeneous items. First, the length of the list is packed as an unsigned integer, then each element is packed as in `pack_farray()` above.

13.5.2 Unpacker Objects

The `Unpacker` class offers the following methods:

`Unpacker.reset(data)`

Resets the string buffer with the given *data*.

`Unpacker.get_position()`

Returns the current unpack position in the data buffer.

`Unpacker.set_position(position)`

Sets the data buffer unpack position to *position*. You should be careful about using `get_position()` and `set_position()`.

`Unpacker.get_buffer()`

Returns the current unpack data buffer as a string.

`Unpacker.done()`

Indicates unpack completion. Raises an `Error` exception if all of the data has not been unpacked.

In addition, every data type that can be packed with a `Packer`, can be unpacked with an `Unpacker`. Unpacking methods are of the form `unpack_type()`, and take no arguments. They return the unpacked object.

`Unpacker.unpack_float()`

Unpacks a single-precision floating point number.

`Unpacker.unpack_double()`

Unpacks a double-precision floating point number, similarly to `unpack_float()`.

In addition, the following methods unpack strings, bytes, and opaque data:

`Unpacker.unpack_fstring(n)`

Unpacks and returns a fixed length string. *n* is the number of characters expected. Padding with null bytes to guaranteed 4 byte alignment is assumed.

`Unpacker.unpack_fopaque(n)`

Unpacks and returns a fixed length opaque data stream, similarly to `unpack_fstring()`.

`Unpacker.unpack_string()`

Unpacks and returns a variable length string. The length of the string is first unpacked as an unsigned integer, then the string data is unpacked with `unpack_fstring()`.

`Unpacker.unpack_opaque()`

Unpacks and returns a variable length opaque data string, similarly to `unpack_string()`.

`Unpacker.unpack_bytes()`

Unpacks and returns a variable length byte stream, similarly to `unpack_string()`.

The following methods support unpacking arrays and lists:

`Unpacker.unpack_list(unpack_item)`

Unpacks and returns a list of homogeneous items. The list is unpacked one element at a time by first unpacking an unsigned integer flag. If the flag is 1, then the item is unpacked and appended to the list. A flag of 0 indicates the end of the list. *unpack_item* is the function that is called to unpack the items.

`Unpacker.unpack_farray(n, unpack_item)`

Unpacks and returns (as a list) a fixed length array of homogeneous items. *n* is number of list elements to expect in the buffer. As above, *unpack_item* is the function used to unpack each element.

`Unpacker.unpack_array(unpack_item)`

Unpacks and returns a variable length *list* of homogeneous items. First, the length of the list is unpacked as an unsigned integer, then each element is unpacked as in `unpack_farray()` above.

13.5.3 Exceptions

Exceptions in this module are coded as class instances:

exception `xdrlib.Error`

The base exception class. *Error* has a single public attribute `msg` containing the description of the error.

exception `xdrlib.ConversionError`

Class derived from *Error*. Contains no additional instance variables.

Here is an example of how you would catch one of these exceptions:

```
import xdrlib
p = xdrlib.Packer()
try:
    p.pack_double(8.01)
except xdrlib.ConversionError as instance:
    print 'packing the double failed:', instance.msg
```

13.6 plistlib — Generate and parse Mac OS X .plist files

버전 2.6에서 변경: This module was previously only available in the Mac-specific library, it is now available for all platforms.

Source code: [Lib/plistlib.py](#)

This module provides an interface for reading and writing the 《property list》XML files used mainly by Mac OS X.

The property list (`.plist`) file format is a simple XML pickle supporting basic object types, like dictionaries, lists, numbers and strings. Usually the top level object is a dictionary.

Values can be strings, integers, floats, booleans, tuples, lists, dictionaries (but only with string keys), `Data` or `datetime.datetime` objects. String values (including dictionary keys) may be unicode strings – they will be written out as UTF-8.

The `<data>` plist type is supported through the `Data` class. This is a thin wrapper around a Python string. Use `Data` if your strings contain control characters.

더 보기:

PList manual page Apple’s documentation of the file format.

This module defines the following functions:

`plistlib.readPlist(pathOrFile)`

Read a plist file. *pathOrFile* may either be a file name or a (readable) file object. Return the unpacked root object (which usually is a dictionary).

The XML data is parsed using the Expat parser from `xml.parsers.expat` – see its documentation for possible exceptions on ill-formed XML. Unknown elements will simply be ignored by the plist parser.

`plistlib.writePlist(rootObject, pathOrFile)`

Write *rootObject* to a plist file. *pathOrFile* may either be a file name or a (writable) file object.

A `TypeError` will be raised if the object is of an unsupported type or a container that contains objects of unsupported types.

`plistlib.readPlistFromString(data)`

Read a plist from a string. Return the root object.

`plistlib.writePlistToString(rootObject)`

Return *rootObject* as a plist-formatted string.

`plistlib.readPlistFromResource(path, restype='plst', resid=0)`

Read a plist from the resource with type *restype* from the resource fork of *path*. Availability: Mac OS X.

참고: In Python 3.x, this function has been removed.

`plistlib.writePlistToResource(rootObject, path, restype='plst', resid=0)`

Write *rootObject* as a resource with type *restype* to the resource fork of *path*. Availability: Mac OS X.

참고: In Python 3.x, this function has been removed.

The following class is available:

class plistlib.**Data**(*data*)

Return a «data» wrapper object around the string *data*. This is used in functions converting from/to plists to represent the <data> type available in plists.

It has one attribute, *data*, that can be used to retrieve the Python string stored in it.

13.6.1 Examples

Generating a plist:

```
pl = dict(
    aString="Doodah",
    aList=["A", "B", 12, 32.1, [1, 2, 3]],
    aFloat = 0.1,
    anInt = 728,
    aDict=dict(
        anotherString="<hello & hi there!>",
        aUnicodeValue=u'M\xe4ssig, Ma\xdf',
        aTrueValue=True,
        aFalseValue=False,
    ),
    someData = Data("<binary gunk>"),
    someMoreData = Data("<lots of binary gunk>" * 10),
    aDate = datetime.datetime.fromtimestamp(time.mktime(time.gmtime())),
)
# unicode keys are possible, but a little awkward to use:
pl[u'\xc5benraa'] = "That was a unicode key."
writePlist(pl, fileName)
```

Parsing a plist:

```
pl = readPlist(pathOrFile)
print pl["aKey"]
```

The modules described in this chapter implement various algorithms of a cryptographic nature. They are available at the discretion of the installation. Here's an overview:

14.1 `hashlib` — Secure hashes and message digests

버전 2.5에 추가.

Source code: [Lib/hashlib.py](#)

This module implements a common interface to many different secure hash and message digest algorithms. Included are the FIPS secure hash algorithms SHA1, SHA224, SHA256, SHA384, and SHA512 (defined in FIPS 180-2) as well as RSA's MD5 algorithm (defined in Internet [RFC 1321](#)). The terms secure hash and message digest are interchangeable. Older algorithms were called message digests. The modern term is secure hash.

참고: If you want the `adler32` or `crc32` hash functions, they are available in the [`zlib`](#) module.

경고: Some algorithms have known hash collision weaknesses, refer to the [《See also》](#) section at the end.

There is one constructor method named for each type of *hash*. All return a hash object with the same simple interface. For example: use `sha1()` to create a SHA1 hash object. You can now feed this object with arbitrary strings using the `update()` method. At any point you can ask it for the *digest* of the concatenation of the strings fed to it so far using the `digest()` or `hexdigest()` methods.

Constructors for hash algorithms that are always present in this module are `md5()`, `sha1()`, `sha224()`, `sha256()`, `sha384()`, and `sha512()`. Additional algorithms may also be available depending upon the OpenSSL library that Python uses on your platform.

For example, to obtain the digest of the string `'Nobody inspects the spammish repetition'`:

```
>>> import hashlib
>>> m = hashlib.md5()
>>> m.update("Nobody inspects")
>>> m.update(" the spammish repetition")
>>> m.digest()
'\xbbd\x9c\x83\xdd\x1e\xa5\xc9\xd9\xde\xc9\xa1\x8d\xf0\xff\xe9'
>>> m.digest_size
16
>>> m.block_size
64
```

More condensed:

```
>>> hashlib.sha224("Nobody inspects the spammish repetition").hexdigest()
'a4337bc45a8fc544c03f52dc550cd6e1e87021bc896588bd79e901e2'
```

A generic `new()` constructor that takes the string name of the desired algorithm as its first parameter also exists to allow access to the above listed hashes as well as any other algorithms that your OpenSSL library may offer. The named constructors are much faster than `new()` and should be preferred.

Using `new()` with an algorithm provided by OpenSSL:

```
>>> h = hashlib.new('ripemd160')
>>> h.update("Nobody inspects the spammish repetition")
>>> h.hexdigest()
'cc4a5ce1b3df48aec5d22d1f16b894a0b894eccc'
```

This module provides the following constant attribute:

hashlib.algorithms

A tuple providing the names of the hash algorithms guaranteed to be supported by this module.

버전 2.7에 추가.

hashlib.algorithms_guaranteed

A set containing the names of the hash algorithms guaranteed to be supported by this module on all platforms.

버전 2.7.9에 추가.

hashlib.algorithms_available

A set containing the names of the hash algorithms that are available in the running Python interpreter. These names will be recognized when passed to `new()`. `algorithms_guaranteed` will always be a subset. The same algorithm may appear multiple times in this set under different names (thanks to OpenSSL).

버전 2.7.9에 추가.

The following values are provided as constant attributes of the hash objects returned by the constructors:

hash.digest_size

The size of the resulting hash in bytes.

hash.block_size

The internal block size of the hash algorithm in bytes.

A hash object has the following methods:

hash.update(*arg*)

Update the hash object with the string *arg*. Repeated calls are equivalent to a single call with the concatenation of all the arguments: `m.update(a) ; m.update(b)` is equivalent to `m.update(a+b)`.

버전 2.7에서 변경 : The Python GIL is released to allow other threads to run while hash updates on data larger than 2048 bytes is taking place when using hash algorithms supplied by OpenSSL.

`hash.digest()`

Return the digest of the strings passed to the `update()` method so far. This is a string of `digest_size` bytes which may contain non-ASCII characters, including null bytes.

`hash.hexdigest()`

Like `digest()` except the digest is returned as a string of double length, containing only hexadecimal digits. This may be used to exchange the value safely in email or other non-binary environments.

`hash.copy()`

Return a copy (《clone》) of the hash object. This can be used to efficiently compute the digests of strings that share a common initial substring.

14.1.1 Key derivation

Key derivation and key stretching algorithms are designed for secure password hashing. Naive algorithms such as `sha1(password)` are not resistant against brute-force attacks. A good password hashing function must be tunable, slow, and include a `salt`.

`hashlib.pbkdf2_hmac(name, password, salt, rounds, dklen=None)`

The function provides PKCS#5 password-based key derivation function 2. It uses HMAC as pseudorandom function.

The string `name` is the desired name of the hash digest algorithm for HMAC, e.g. `<sha1>` or `<sha256>`. `password` and `salt` are interpreted as buffers of bytes. Applications and libraries should limit `password` to a sensible value (e.g. 1024). `salt` should be about 16 or more bytes from a proper source, e.g. `os.urandom()`.

The number of `rounds` should be chosen based on the hash algorithm and computing power. As of 2013, at least 100,000 rounds of SHA-256 is suggested.

`dklen` is the length of the derived key. If `dklen` is `None` then the digest size of the hash algorithm `name` is used, e.g. 64 for SHA-512.

```
>>> import hashlib, binascii
>>> dk = hashlib.pbkdf2_hmac('sha256', b'password', b'salt', 100000)
>>> binascii.hexlify(dk)
b'0394a2ede332c9a13eb82e9b24631604c31df978b4e2f0fbd2c549944f9d79a5'
```

버전 2.7.8에 추가.

참고: A fast implementation of `pbkdf2_hmac` is available with OpenSSL. The Python implementation uses an inline version of `hmac`. It is about three times slower and doesn't release the GIL.

더 보기:

Module `hmac` A module to generate message authentication codes using hashes.

Module `base64` Another way to encode binary hashes for non-binary environments.

<http://csrc.nist.gov/publications/fips/fips180-2/fips180-2.pdf> The FIPS 180-2 publication on Secure Hash Algorithms.

https://en.wikipedia.org/wiki/Cryptographic_hash_function#Cryptographic_hash_algorithms Wikipedia article with information on which algorithms have known issues and what that means regarding their use.

14.2 hmac — Keyed-Hashing for Message Authentication

버전 2.2에 추가.

Source code: [Lib/hmac.py](#)

This module implements the HMAC algorithm as described by [RFC 2104](#).

`hmac.new(key[, msg[, digestmod]])`

Return a new hmac object. If *msg* is present, the method call `update(msg)` is made. *digestmod* is the digest constructor or module for the HMAC object to use. It defaults to the `hashlib.md5` constructor.

An HMAC object has the following methods:

`HMAC.update(msg)`

Update the hmac object with the string *msg*. Repeated calls are equivalent to a single call with the concatenation of all the arguments: `m.update(a); m.update(b)` is equivalent to `m.update(a + b)`.

`HMAC.digest()`

Return the digest of the strings passed to the `update()` method so far. This string will be the same length as the *digest_size* of the digest given to the constructor. It may contain non-ASCII characters, including NUL bytes.

경고: When comparing the output of `digest()` to an externally-supplied digest during a verification routine, it is recommended to use the `compare_digest()` function instead of the `==` operator to reduce the vulnerability to timing attacks.

`HMAC.hexdigest()`

Like `digest()` except the digest is returned as a string twice the length containing only hexadecimal digits. This may be used to exchange the value safely in email or other non-binary environments.

경고: When comparing the output of `hexdigest()` to an externally-supplied digest during a verification routine, it is recommended to use the `compare_digest()` function instead of the `==` operator to reduce the vulnerability to timing attacks.

`HMAC.copy()`

Return a copy (《clone》) of the hmac object. This can be used to efficiently compute the digests of strings that share a common initial substring.

This module also provides the following helper function:

`hmac.compare_digest(a, b)`

Return `a == b`. This function uses an approach designed to prevent timing analysis by avoiding content-based short circuiting behaviour, making it appropriate for cryptography. *a* and *b* must both be of the same type: either *unicode* or a *bytes-like object*.

참고: If *a* and *b* are of different lengths, or if an error occurs, a timing attack could theoretically reveal information about the types and lengths of *a* and *b*—but not their values.

버전 2.7.7에 추가.

더 보기:

Module [hashlib](#) The Python module providing secure hash functions.

14.3 md5 — MD5 message digest algorithm

버전 2.5부터 폐지: Use the *hashlib* module instead.

This module implements the interface to RSA's MD5 message digest algorithm (see also Internet [RFC 1321](#)). Its use is quite straightforward: use *new()* to create an md5 object. You can now feed this object with arbitrary strings using the *update()* method, and at any point you can ask it for the *digest* (a strong kind of 128-bit checksum, a.k.a. «fingerprint») of the concatenation of the strings fed to it so far using the *digest()* method.

For example, to obtain the digest of the string 'Nobody inspects the spammish repetition':

```
>>> import md5
>>> m = md5.new()
>>> m.update("Nobody inspects")
>>> m.update(" the spammish repetition")
>>> m.digest()
'\xbbd\x9c\x83\xdd\x1e\xa5\xc9\xd9\xde\xc9\xa1\x8d\xf0\xff\xe9'
```

More condensed:

```
>>> md5.new("Nobody inspects the spammish repetition").digest()
'\xbbd\x9c\x83\xdd\x1e\xa5\xc9\xd9\xde\xc9\xa1\x8d\xf0\xff\xe9'
```

The following values are provided as constants in the module and as attributes of the md5 objects returned by *new()*:

md5.digest_size

The size of the resulting digest in bytes. This is always 16.

The md5 module provides the following functions:

md5.new([arg])

Return a new md5 object. If *arg* is present, the method call *update(arg)* is made.

md5.md5([arg])

For backward compatibility reasons, this is an alternative name for the *new()* function.

An md5 object has the following methods:

md5.update(arg)

Update the md5 object with the string *arg*. Repeated calls are equivalent to a single call with the concatenation of all the arguments: *m.update(a) ; m.update(b)* is equivalent to *m.update(a+b)*.

md5.digest()

Return the digest of the strings passed to the *update()* method so far. This is a 16-byte string which may contain non-ASCII characters, including null bytes.

md5.hexdigest()

Like *digest()* except the digest is returned as a string of length 32, containing only hexadecimal digits. This may be used to exchange the value safely in email or other non-binary environments.

md5.copy()

Return a copy («clone») of the md5 object. This can be used to efficiently compute the digests of strings that share a common initial substring.

더 보기:

Module *sha* Similar module implementing the Secure Hash Algorithm (SHA). The SHA algorithm is considered a more secure hash.

14.4 sha — SHA-1 message digest algorithm

버전 2.5부터 폐지: Use the [hashlib](#) module instead.

This module implements the interface to NIST's secure hash algorithm, known as SHA-1. SHA-1 is an improved version of the original SHA hash algorithm. It is used in the same way as the [md5](#) module: use [new\(\)](#) to create an sha object, then feed this object with arbitrary strings using the [update\(\)](#) method, and at any point you can ask it for the *digest* of the concatenation of the strings fed to it so far. SHA-1 digests are 160 bits instead of MD5's 128 bits.

`sha.new([string])`

Return a new sha object. If *string* is present, the method call `update(string)` is made.

The following values are provided as constants in the module and as attributes of the sha objects returned by [new\(\)](#):

`sha.blocksize`

Size of the blocks fed into the hash function; this is always 1. This size is used to allow an arbitrary string to be hashed.

`sha.digest_size`

The size of the resulting digest in bytes. This is always 20.

An sha object has the same methods as md5 objects:

`sha.update(arg)`

Update the sha object with the string *arg*. Repeated calls are equivalent to a single call with the concatenation of all the arguments: `m.update(a) ; m.update(b)` is equivalent to `m.update(a+b)`.

`sha.digest()`

Return the digest of the strings passed to the [update\(\)](#) method so far. This is a 20-byte string which may contain non-ASCII characters, including null bytes.

`sha.hexdigest()`

Like [digest\(\)](#) except the digest is returned as a string of length 40, containing only hexadecimal digits. This may be used to exchange the value safely in email or other non-binary environments.

`sha.copy()`

Return a copy (《clone》) of the sha object. This can be used to efficiently compute the digests of strings that share a common initial substring.

더 보기:

Secure Hash Standard The Secure Hash Algorithm is defined by NIST document FIPS PUB 180-2: [Secure Hash Standard](#), published in August 2002.

Cryptographic Toolkit (Secure Hashing) [Links from NIST to various information on secure hashing.](#)

Generic Operating System Services

The modules described in this chapter provide interfaces to operating system features that are available on (almost) all operating systems, such as files and a clock. The interfaces are generally modeled after the Unix or C interfaces, but they are available on most other systems as well. Here's an overview:

15.1 `os` — Miscellaneous operating system interfaces

This module provides a portable way of using operating system dependent functionality. If you just want to read or write a file see `open()`, if you want to manipulate paths, see the `os.path` module, and if you want to read all the lines in all the files on the command line see the `fileinput` module. For creating temporary files and directories see the `tempfile` module, and for high-level file and directory handling see the `shutil` module.

Notes on the availability of these functions:

- The design of all built-in operating system dependent modules of Python is such that as long as the same functionality is available, it uses the same interface; for example, the function `os.stat(path)` returns stat information about `path` in the same format (which happens to have originated with the POSIX interface).
- Extensions peculiar to a particular operating system are also available through the `os` module, but using them is of course a threat to portability.
- An «Availability: Unix» note means that this function is commonly found on Unix systems. It does not make any claims about its existence on a specific operating system.
- If not separately noted, all functions that claim «Availability: Unix» are supported on Mac OS X, which builds on a Unix core.

참고: All functions in this module raise `OSError` in the case of invalid or inaccessible file names and paths, or other arguments that have the correct type, but are not accepted by the operating system.

exception `os.error`

An alias for the built-in `OSError` exception.

os.name

The name of the operating system dependent module imported. The following names have currently been registered: 'posix', 'nt', 'os2', 'ce', 'java', 'riscos'.

더 보기:

`sys.platform` has a finer granularity. `os.uname()` gives system-dependent version information.

The `platform` module provides detailed checks for the system's identity.

15.1.1 Process Parameters

These functions and data items provide information and operate on the current process and user.

os.environ

A *mapping* object representing the string environment. For example, `environ['HOME']` is the pathname of your home directory (on some platforms), and is equivalent to `getenv("HOME")` in C.

This mapping is captured the first time the `os` module is imported, typically during Python startup as part of processing `site.py`. Changes to the environment made after this time are not reflected in `os.environ`, except for changes made by modifying `os.environ` directly.

If the platform supports the `putenv()` function, this mapping may be used to modify the environment as well as query the environment. `putenv()` will be called automatically when the mapping is modified.

참고: Calling `putenv()` directly does not change `os.environ`, so it's better to modify `os.environ`.

참고: On some platforms, including FreeBSD and Mac OS X, setting `environ` may cause memory leaks. Refer to the system documentation for `putenv()`.

If `putenv()` is not provided, a modified copy of this mapping may be passed to the appropriate process-creation functions to cause child processes to use a modified environment.

If the platform supports the `unsetenv()` function, you can delete items in this mapping to unset environment variables. `unsetenv()` will be called automatically when an item is deleted from `os.environ`, and when one of the `pop()` or `clear()` methods is called.

버전 2.6에서 변경: Also unset environment variables when calling `os.environ.clear()` and `os.environ.pop()`.

os.chdir(path)**os.fchdir(fd)****os.getcwd()**

These functions are described in *Files and Directories*.

os.ctermid()

Return the filename corresponding to the controlling terminal of the process.

Availability: Unix.

os.getegid()

Return the effective group id of the current process. This corresponds to the 《set id》 bit on the file being executed in the current process.

Availability: Unix.

os.geteuid()

Return the current process's effective user id.

Availability: Unix.

os.getgid()

Return the real group id of the current process.

Availability: Unix.

os.getgroups()

Return list of supplemental group ids associated with the current process.

Availability: Unix.

참고: On Mac OS X, `getgroups()` behavior differs somewhat from other Unix platforms. If the Python interpreter was built with a deployment target of 10.5 or earlier, `getgroups()` returns the list of effective group ids associated with the current user process; this list is limited to a system-defined number of entries, typically 16, and may be modified by calls to `setgroups()` if suitably privileged. If built with a deployment target greater than 10.5, `getgroups()` returns the current group access list for the user associated with the effective user id of the process; the group access list may change over the lifetime of the process, it is not affected by calls to `setgroups()`, and its length is not limited to 16. The deployment target value, `MACOSX_DEPLOYMENT_TARGET`, can be obtained with `sysconfig.get_config_var()`.

os.initgroups(username, gid)

Call the system `initgroups()` to initialize the group access list with all of the groups of which the specified username is a member, plus the specified group id.

Availability: Unix.

버전 2.7에 추가.

os.getlogin()

Return the name of the user logged in on the controlling terminal of the process. For most purposes, it is more useful to use the environment variable `LOGNAME` to find out who the user is, or `pwd.getpwuid(os.getuid())[0]` to get the login name of the process's real user id.

Availability: Unix.

os.getpgid(pid)

Return the process group id of the process with process id *pid*. If *pid* is 0, the process group id of the current process is returned.

Availability: Unix.

버전 2.3에 추가.

os.getpgrp()

Return the id of the current process group.

Availability: Unix.

os.getpid()

Return the current process id.

Availability: Unix, Windows.

os.getppid()

Return the parent's process id.

Availability: Unix.

`os.getresuid()`

Return a tuple (ruid, euid, suid) denoting the current process's real, effective, and saved user ids.

Availability: Unix.

버전 2.7에 추가.

`os.getresgid()`

Return a tuple (rgid, egid, sgid) denoting the current process's real, effective, and saved group ids.

Availability: Unix.

버전 2.7에 추가.

`os.getuid()`

Return the current process's real user id.

Availability: Unix.

`os.getenv(varname[, value])`

Return the value of the environment variable *varname* if it exists, or *value* if it doesn't. *value* defaults to None.

Availability: most flavors of Unix, Windows.

`os.putenv(varname, value)`

Set the environment variable named *varname* to the string *value*. Such changes to the environment affect subprocesses started with `os.system()`, `popen()` or `fork()` and `execv()`.

Availability: most flavors of Unix, Windows.

참고: On some platforms, including FreeBSD and Mac OS X, setting `environ` may cause memory leaks. Refer to the system documentation for `putenv`.

When `putenv()` is supported, assignments to items in `os.environ` are automatically translated into corresponding calls to `putenv()`; however, calls to `putenv()` don't update `os.environ`, so it is actually preferable to assign to items of `os.environ`.

`os.setegid(egid)`

Set the current process's effective group id.

Availability: Unix.

`os.seteuid(euid)`

Set the current process's effective user id.

Availability: Unix.

`os.setgid(gid)`

Set the current process's group id.

Availability: Unix.

`os.setgroups(groups)`

Set the list of supplemental group ids associated with the current process to *groups*. *groups* must be a sequence, and each element must be an integer identifying a group. This operation is typically available only to the superuser.

Availability: Unix.

버전 2.2에 추가.

참고: On Mac OS X, the length of *groups* may not exceed the system-defined maximum number of effective group ids, typically 16. See the documentation for `getgroups()` for cases where it may not return the same

group list set by calling `setgroups()`.

os.setpgrp()

Call the system call `setpgrp()` or `setpgrp(0, 0)` depending on which version is implemented (if any). See the Unix manual for the semantics.

Availability: Unix.

os.setpgid(pid, grp)

Call the system call `setpgid()` to set the process group id of the process with id *pid* to the process group with id *grp*. See the Unix manual for the semantics.

Availability: Unix.

os.setregid(rgid, egid)

Set the current process's real and effective group ids.

Availability: Unix.

os.setresgid(rgid, egid, sgid)

Set the current process's real, effective, and saved group ids.

Availability: Unix.

버전 2.7에 추가.

os.setresuid(ruid, euid, suid)

Set the current process's real, effective, and saved user ids.

Availability: Unix.

버전 2.7에 추가.

os.setreuid(ruid, euid)

Set the current process's real and effective user ids.

Availability: Unix.

os.getsid(pid)

Call the system call `getsid()`. See the Unix manual for the semantics.

Availability: Unix.

버전 2.4에 추가.

os.setsid()

Call the system call `setsid()`. See the Unix manual for the semantics.

Availability: Unix.

os.setuid(uid)

Set the current process's user id.

Availability: Unix.

os.strerror(code)

Return the error message corresponding to the error code in *code*. On platforms where `strerror()` returns `NULL` when given an unknown error number, `ValueError` is raised.

Availability: Unix, Windows.

os.umask(mask)

Set the current numeric umask and return the previous umask.

Availability: Unix, Windows.

os.uname()

Return a 5-tuple containing information identifying the current operating system. The tuple contains 5 strings: (sysname, nodename, release, version, machine). Some systems truncate the nodename to 8 characters or to the leading component; a better way to get the hostname is `socket.gethostname()` or even `socket.gethostbyaddr(socket.gethostname())`.

Availability: recent flavors of Unix.

os.unsetenv(varname)

Unset (delete) the environment variable named *varname*. Such changes to the environment affect subprocesses started with `os.system()`, `popen()` or `fork()` and `execv()`.

When `unsetenv()` is supported, deletion of items in `os.environ` is automatically translated into a corresponding call to `unsetenv()`; however, calls to `unsetenv()` don't update `os.environ`, so it is actually preferable to delete items of `os.environ`.

Availability: most flavors of Unix, Windows.

15.1.2 File Object Creation

These functions create new file objects. (See also `open()`.)

os.fdopen(fd[, mode[, bufsize]])

Return an open file object connected to the file descriptor *fd*. The *mode* and *bufsize* arguments have the same meaning as the corresponding arguments to the built-in `open()` function. If `fdopen()` raises an exception, it leaves *fd* untouched (unclosed).

Availability: Unix, Windows.

버전 2.3에서 변경: When specified, the *mode* argument must now start with one of the letters 'r', 'w', or 'a', otherwise a `ValueError` is raised.

버전 2.5에서 변경: On Unix, when the *mode* argument starts with 'a', the `O_APPEND` flag is set on the file descriptor (which the `fdopen()` implementation already does on most platforms).

os.popen(command[, mode[, bufsize]])

Open a pipe to or from *command*. The return value is an open file object connected to the pipe, which can be read or written depending on whether *mode* is 'r' (default) or 'w'. The *bufsize* argument has the same meaning as the corresponding argument to the built-in `open()` function. The exit status of the command (encoded in the format specified for `wait()`) is available as the return value of the `close()` method of the file object, except that when the exit status is zero (termination without errors), `None` is returned.

Availability: Unix, Windows.

버전 2.6부터 폐지: This function is obsolete. Use the `subprocess` module. Check especially the *Replacing Older Functions with the subprocess Module* section.

버전 2.0에서 변경: This function worked unreliably under Windows in earlier versions of Python. This was due to the use of the `_popen()` function from the libraries provided with Windows. Newer versions of Python do not use the broken implementation from the Windows libraries.

os.tmpfile()

Return a new file object opened in update mode (`w+b`). The file has no directory entries associated with it and will be automatically deleted once there are no file descriptors for the file.

Availability: Unix, Windows.

There are a number of different `popen*` functions that provide slightly different ways to create subprocesses.

버전 2.6부터 폐지: All of the `popen*` functions are obsolete. Use the `subprocess` module.

For each of the `popen*()` variants, if `bufsize` is specified, it specifies the buffer size for the I/O pipes. `mode`, if provided, should be the string `'b'` or `'t'`; on Windows this is needed to determine whether the file objects should be opened in binary or text mode. The default value for `mode` is `'t'`.

Also, for each of these variants, on Unix, `cmd` may be a sequence, in which case arguments will be passed directly to the program without shell intervention (as with `os.spawnv()`). If `cmd` is a string it will be passed to the shell (as with `os.system()`).

These methods do not make it possible to retrieve the exit status from the child processes. The only way to control the input and output streams and also retrieve the return codes is to use the `subprocess` module; these are only available on Unix.

For a discussion of possible deadlock conditions related to the use of these functions, see [Flow Control Issues](#).

`os.popen2(cmd[, mode[, bufsize]])`

Execute `cmd` as a sub-process and return the file objects (`child_stdin`, `child_stdout`).

버전 2.6부터 폐지: This function is obsolete. Use the `subprocess` module. Check especially the [Replacing Older Functions with the subprocess Module](#) section.

Availability: Unix, Windows.

버전 2.0에 추가.

`os.popen3(cmd[, mode[, bufsize]])`

Execute `cmd` as a sub-process and return the file objects (`child_stdin`, `child_stdout`, `child_stderr`).

버전 2.6부터 폐지: This function is obsolete. Use the `subprocess` module. Check especially the [Replacing Older Functions with the subprocess Module](#) section.

Availability: Unix, Windows.

버전 2.0에 추가.

`os.popen4(cmd[, mode[, bufsize]])`

Execute `cmd` as a sub-process and return the file objects (`child_stdin`, `child_stdout_and_stderr`).

버전 2.6부터 폐지: This function is obsolete. Use the `subprocess` module. Check especially the [Replacing Older Functions with the subprocess Module](#) section.

Availability: Unix, Windows.

버전 2.0에 추가.

(Note that `child_stdin`, `child_stdout`, and `child_stderr` are named from the point of view of the child process, so `child_stdin` is the child's standard input.)

This functionality is also available in the `popen2` module using functions of the same names, but the return values of those functions have a different order.

15.1.3 File Descriptor Operations

These functions operate on I/O streams referenced using file descriptors.

File descriptors are small integers corresponding to a file that has been opened by the current process. For example, standard input is usually file descriptor 0, standard output is 1, and standard error is 2. Further files opened by a process will then be assigned 3, 4, 5, and so forth. The name “file descriptor” is slightly deceptive; on Unix platforms, sockets and pipes are also referenced by file descriptors.

The `fileno()` method can be used to obtain the file descriptor associated with a file object when required. Note that using the file descriptor directly will bypass the file object methods, ignoring aspects such as internal buffering of data.

`os.close(fd)`

Close file descriptor *fd*.

Availability: Unix, Windows.

참고: This function is intended for low-level I/O and must be applied to a file descriptor as returned by `os.open()` or `pipe()`. To close a 《file object》 returned by the built-in function `open()` or by `popen()` or `fdopen()`, use its `close()` method.

`os.closerange(fd_low, fd_high)`

Close all file descriptors from *fd_low* (inclusive) to *fd_high* (exclusive), ignoring errors. Equivalent to:

```
for fd in xrange(fd_low, fd_high):
    try:
        os.close(fd)
    except OSError:
        pass
```

Availability: Unix, Windows.

버전 2.6에 추가.

`os.dup(fd)`

Return a duplicate of file descriptor *fd*.

Availability: Unix, Windows.

`os.dup2(fd, fd2)`

Duplicate file descriptor *fd* to *fd2*, closing the latter first if necessary.

Availability: Unix, Windows.

`os.fchmod(fd, mode)`

Change the mode of the file given by *fd* to the numeric *mode*. See the docs for `chmod()` for possible values of *mode*.

Availability: Unix.

버전 2.6에 추가.

`os.fchown(fd, uid, gid)`

Change the owner and group id of the file given by *fd* to the numeric *uid* and *gid*. To leave one of the ids unchanged, set it to -1.

Availability: Unix.

버전 2.6에 추가.

`os.fdatasync(fd)`

Force write of file with filedescriptor *fd* to disk. Does not force update of metadata.

Availability: Unix.

참고: This function is not available on MacOS.

`os.fpathconf(fd, name)`

Return system configuration information relevant to an open file. *name* specifies the configuration value to retrieve; it may be a string which is the name of a defined system value; these names are specified in a number of standards (POSIX.1, Unix 95, Unix 98, and others). Some platforms define additional names as well. The names known to

the host operating system are given in the `pathconf_names` dictionary. For configuration variables not included in that mapping, passing an integer for *name* is also accepted.

If *name* is a string and is not known, `ValueError` is raised. If a specific value for *name* is not supported by the host system, even if it is included in `pathconf_names`, an `OSError` is raised with `errno.EINVAL` for the error number.

Availability: Unix.

`os.fstat(fd)`

Return status for file descriptor *fd*, like `stat()`.

Availability: Unix, Windows.

`os.fstatvfs(fd)`

Return information about the filesystem containing the file associated with file descriptor *fd*, like `statvfs()`.

Availability: Unix.

`os.fsync(fd)`

Force write of file with file descriptor *fd* to disk. On Unix, this calls the native `fsync()` function; on Windows, the `MS_commit()` function.

If you're starting with a Python file object *f*, first do `f.flush()`, and then do `os.fsync(f.fileno())`, to ensure that all internal buffers associated with *f* are written to disk.

Availability: Unix, and Windows starting in 2.2.3.

`os.ftruncate(fd, length)`

Truncate the file corresponding to file descriptor *fd*, so that it is at most *length* bytes in size.

Availability: Unix.

`os.isatty(fd)`

Return `True` if the file descriptor *fd* is open and connected to a tty(-like) device, else `False`.

`os.lseek(fd, pos, how)`

Set the current position of file descriptor *fd* to position *pos*, modified by *how*: `SEEK_SET` or 0 to set the position relative to the beginning of the file; `SEEK_CUR` or 1 to set it relative to the current position; `SEEK_END` or 2 to set it relative to the end of the file. Return the new cursor position in bytes, starting from the beginning.

Availability: Unix, Windows.

`os.SEEK_SET`

`os.SEEK_CUR`

`os.SEEK_END`

Parameters to the `lseek()` function. Their values are 0, 1, and 2, respectively.

Availability: Windows, Unix.

버전 2.5에 추가.

`os.open(file, flags[, mode])`

Open the file *file* and set various flags according to *flags* and possibly its mode according to *mode*. The default *mode* is 0777 (octal), and the current umask value is first masked out. Return the file descriptor for the newly opened file.

For a description of the flag and mode values, see the C run-time documentation; flag constants (like `O_RDONLY` and `O_WRONLY`) are defined in this module too (see `open() flag constants`). In particular, on Windows adding `O_BINARY` is needed to open files in binary mode.

Availability: Unix, Windows.

참고: This function is intended for low-level I/O. For normal usage, use the built-in function `open()`, which returns a 《file object》 with `read()` and `write()` methods (and many more). To wrap a file descriptor in a 《file object》, use `fdopen()`.

os.openpty()

Open a new pseudo-terminal pair. Return a pair of file descriptors (`master`, `slave`) for the pty and the tty, respectively. For a (slightly) more portable approach, use the `pty` module.

Availability: some flavors of Unix.

os.pipe()

Create a pipe. Return a pair of file descriptors (`r`, `w`) usable for reading and writing, respectively.

Availability: Unix, Windows.

os.read(*fd*, *n*)

Read at most *n* bytes from file descriptor *fd*. Return a string containing the bytes read. If the end of the file referred to by *fd* has been reached, an empty string is returned.

Availability: Unix, Windows.

참고: This function is intended for low-level I/O and must be applied to a file descriptor as returned by `os.open()` or `pipe()`. To read a 《file object》 returned by the built-in function `open()` or by `popen()` or `fdopen()`, or `sys.stdin`, use its `read()` or `readline()` methods.

os.tcgetpgrp(*fd*)

Return the process group associated with the terminal given by *fd* (an open file descriptor as returned by `os.open()`).

Availability: Unix.

os.tcsetpgrp(*fd*, *pg*)

Set the process group associated with the terminal given by *fd* (an open file descriptor as returned by `os.open()`) to *pg*.

Availability: Unix.

os.ttyname(*fd*)

Return a string which specifies the terminal device associated with file descriptor *fd*. If *fd* is not associated with a terminal device, an exception is raised.

Availability: Unix.

os.write(*fd*, *str*)

Write the string *str* to file descriptor *fd*. Return the number of bytes actually written.

Availability: Unix, Windows.

참고: This function is intended for low-level I/O and must be applied to a file descriptor as returned by `os.open()` or `pipe()`. To write a 《file object》 returned by the built-in function `open()` or by `popen()` or `fdopen()`, or `sys.stdout` or `sys.stderr`, use its `write()` method.

`open()` flag constants

The following constants are options for the *flags* parameter to the `open()` function. They can be combined using the bitwise OR operator `|`. Some of them are not available on all platforms. For descriptions of their availability and use, consult the `open(2)` manual page on Unix or the MSDN on Windows.

```
os.O_RDONLY
os.O_WRONLY
os.O_RDWR
os.O_APPEND
os.O_CREAT
os.O_EXCL
os.O_TRUNC
```

The above constants are available on Unix and Windows.

```
os.O_DSYNC
os.O_RSYNC
os.O_SYNC
os.O_NDELAY
os.O_NONBLOCK
os.O_NOCTTY
```

The above constants are only available on Unix.

```
os.O_BINARY
os.O_NOINHERIT
os.O_SHORT_LIVED
os.O_TEMPORARY
os.O_RANDOM
os.O_SEQUENTIAL
os.O_TEXT
```

The above constants are only available on Windows.

```
os.O_ASYNC
os.O_DIRECT
os.O_DIRECTORY
os.O_NOFOLLOW
os.O_NOATIME
os.O_SHLOCK
os.O_EXLOCK
```

The above constants are extensions and not present if they are not defined by the C library.

15.1.4 Files and Directories

`os.access(path, mode)`

Use the real uid/gid to test for access to *path*. Note that most operations will use the effective uid/gid, therefore this routine can be used in a suid/sgid environment to test if the invoking user has the specified access to *path*. *mode* should be `F_OK` to test the existence of *path*, or it can be the inclusive OR of one or more of `R_OK`, `W_OK`, and `X_OK` to test permissions. Return `True` if access is allowed, `False` if not. See the Unix man page `access(2)` for more information.

Availability: Unix, Windows.

참고: Using `access()` to check if a user is authorized to e.g. open a file before actually doing so using `open()` creates a security hole, because the user might exploit the short time interval between checking and opening the file to manipulate it. It's preferable to use *EAFP* techniques. For example:

```
if os.access("myfile", os.R_OK):
    with open("myfile") as fp:
        return fp.read()
return "some default data"
```

is better written as:

```
try:
    fp = open("myfile")
except IOError as e:
    if e.errno == errno.EACCES:
        return "some default data"
    # Not a permission error.
    raise
else:
    with fp:
        return fp.read()
```

참고: I/O operations may fail even when `access()` indicates that they would succeed, particularly for operations on network filesystems which may have permissions semantics beyond the usual POSIX permission-bit model.

os.F_OK

Value to pass as the *mode* parameter of `access()` to test the existence of *path*.

os.R_OK

Value to include in the *mode* parameter of `access()` to test the readability of *path*.

os.W_OK

Value to include in the *mode* parameter of `access()` to test the writability of *path*.

os.X_OK

Value to include in the *mode* parameter of `access()` to determine if *path* can be executed.

os.chdir(path)

Change the current working directory to *path*.

Availability: Unix, Windows.

os.fchdir(fd)

Change the current working directory to the directory represented by the file descriptor *fd*. The descriptor must refer to an opened directory, not an open file.

Availability: Unix.

버전 2.3에 추가.

os.getcwd()

Return a string representing the current working directory.

Availability: Unix, Windows.

os.getcwdu()

Return a Unicode object representing the current working directory.

Availability: Unix, Windows.

버전 2.3에 추가.

os.chflags (*path*, *flags*)

Set the flags of *path* to the numeric *flags*. *flags* may take a combination (bitwise OR) of the following values (as defined in the *stat* module):

- *stat.UF_NODUMP*
- *stat.UF_IMMUTABLE*
- *stat.UF_APPEND*
- *stat.UF_OPAQUE*
- *stat.UF_NOUNLINK*
- *stat.UF_COMPRESSED*
- *stat.UF_HIDDEN*
- *stat.SF_ARCHIVED*
- *stat.SF_IMMUTABLE*
- *stat.SF_APPEND*
- *stat.SF_NOUNLINK*
- *stat.SF_SNAPSHOT*

Availability: Unix.

버전 2.6에 추가.

os.chroot (*path*)

Change the root directory of the current process to *path*. Availability: Unix.

버전 2.2에 추가.

os.chmod (*path*, *mode*)

Change the mode of *path* to the numeric *mode*. *mode* may take one of the following values (as defined in the *stat* module) or bitwise ORed combinations of them:

- *stat.S_ISUID*
- *stat.S_ISGID*
- *stat.S_ENFMT*
- *stat.S_ISVTX*
- *stat.S_IREAD*
- *stat.S_IWRITE*
- *stat.S_IEXEC*
- *stat.S_IRWXU*
- *stat.S_IRUSR*
- *stat.S_IWUSR*
- *stat.S_IXUSR*
- *stat.S_IRWXG*
- *stat.S_IRGRP*
- *stat.S_IWGRP*
- *stat.S_IXGRP*

- `stat.S_IRWXO`
- `stat.S_IROTH`
- `stat.S_IWOTH`
- `stat.S_IXOTH`

Availability: Unix, Windows.

참고: Although Windows supports `chmod()`, you can only set the file's read-only flag with it (via the `stat.S_IWRITE` and `stat.S_IREAD` constants or a corresponding integer value). All other bits are ignored.

os.**chown** (*path*, *uid*, *gid*)

Change the owner and group id of *path* to the numeric *uid* and *gid*. To leave one of the ids unchanged, set it to -1.

Availability: Unix.

os.**lchflags** (*path*, *flags*)

Set the flags of *path* to the numeric *flags*, like `chflags()`, but do not follow symbolic links.

Availability: Unix.

버전 2.6에 추가.

os.**lchmod** (*path*, *mode*)

Change the mode of *path* to the numeric *mode*. If *path* is a symlink, this affects the symlink rather than the target. See the docs for `chmod()` for possible values of *mode*.

Availability: Unix.

버전 2.6에 추가.

os.**lchown** (*path*, *uid*, *gid*)

Change the owner and group id of *path* to the numeric *uid* and *gid*. This function will not follow symbolic links.

Availability: Unix.

버전 2.3에 추가.

os.**link** (*source*, *link_name*)

Create a hard link pointing to *source* named *link_name*.

Availability: Unix.

os.**listdir** (*path*)

Return a list containing the names of the entries in the directory given by *path*. The list is in arbitrary order. It does not include the special entries `'.'` and `'..'` even if they are present in the directory.

Availability: Unix, Windows.

버전 2.3에서 변경: On Windows NT/2k/XP and Unix, if *path* is a Unicode object, the result will be a list of Unicode objects. Undecodable filenames will still be returned as string objects.

os.**lstat** (*path*)

Perform the equivalent of an `lstat()` system call on the given path. Similar to `stat()`, but does not follow symbolic links. On platforms that do not support symbolic links, this is an alias for `stat()`.

os.**mkfifo** (*path*[, *mode*])

Create a FIFO (a named pipe) named *path* with numeric mode *mode*. The default *mode* is 0666 (octal). The current umask value is first masked out from the mode.

Availability: Unix.

FIFOs are pipes that can be accessed like regular files. FIFOs exist until they are deleted (for example with `os.unlink()`). Generally, FIFOs are used as rendezvous between 《client》 and 《server》 type processes: the server opens the FIFO for reading, and the client opens it for writing. Note that `mkfifo()` doesn't open the FIFO — it just creates the rendezvous point.

`os.mknod(filename[, mode=0600[, device=0]])`

Create a filesystem node (file, device special file or named pipe) named *filename*. *mode* specifies both the permissions to use and the type of node to be created, being combined (bitwise OR) with one of `stat.S_IFREG`, `stat.S_IFCHR`, `stat.S_IFBLK`, and `stat.S_IFIFO` (those constants are available in `stat`). For `stat.S_IFCHR` and `stat.S_IFBLK`, *device* defines the newly created device special file (probably using `os.makedev()`), otherwise it is ignored.

버전 2.3에 추가.

`os.major(device)`

Extract the device major number from a raw device number (usually the `st_dev` or `st_rdev` field from `stat`).

버전 2.3에 추가.

`os.minor(device)`

Extract the device minor number from a raw device number (usually the `st_dev` or `st_rdev` field from `stat`).

버전 2.3에 추가.

`os.makedev(major, minor)`

Compose a raw device number from the major and minor device numbers.

버전 2.3에 추가.

`os.mkdir(path[, mode])`

Create a directory named *path* with numeric mode *mode*. The default *mode* is 0777 (octal). If the directory already exists, `OSError` is raised.

On some systems, *mode* is ignored. Where it is used, the current umask value is first masked out. If bits other than the last 9 (i.e. the last 3 digits of the octal representation of the *mode*) are set, their meaning is platform-dependent. On some platforms, they are ignored and you should call `chmod()` explicitly to set them.

It is also possible to create temporary directories; see the `tempfile` module's `tempfile.mkdtemp()` function.

Availability: Unix, Windows.

`os.makedirs(path[, mode])`

Recursive directory creation function. Like `mkdir()`, but makes all intermediate-level directories needed to contain the leaf directory. Raises an `error` exception if the leaf directory already exists or cannot be created. The default *mode* is 0777 (octal).

The *mode* parameter is passed to `mkdir()`; see *the mkdir() description* for how it is interpreted.

참고: `makedirs()` will become confused if the path elements to create include `os.pardir`.

버전 1.5.2에 추가.

버전 2.3에서 변경: This function now handles UNC paths correctly.

`os.pathconf(path, name)`

Return system configuration information relevant to a named file. *name* specifies the configuration value to retrieve; it may be a string which is the name of a defined system value; these names are specified in a number of standards (POSIX.1, Unix 95, Unix 98, and others). Some platforms define additional names as well. The names known to the host operating system are given in the `pathconf_names` dictionary. For configuration variables not included in that mapping, passing an integer for *name* is also accepted.

If *name* is a string and is not known, `ValueError` is raised. If a specific value for *name* is not supported by the host system, even if it is included in `pathconf_names`, an `OSError` is raised with `errno.EINVAL` for the error number.

Availability: Unix.

os.pathconf_names

Dictionary mapping names accepted by `pathconf()` and `fpathconf()` to the integer values defined for those names by the host operating system. This can be used to determine the set of names known to the system. Availability: Unix.

os.readlink(path)

Return a string representing the path to which the symbolic link points. The result may be either an absolute or relative pathname; if it is relative, it may be converted to an absolute pathname using `os.path.join(os.path.dirname(path), result)`.

버전 2.6에서 변경: If the *path* is a Unicode object the result will also be a Unicode object.

Availability: Unix.

os.remove(path)

Remove (delete) the file *path*. If *path* is a directory, `OSError` is raised; see `rmdir()` below to remove a directory. This is identical to the `unlink()` function documented below. On Windows, attempting to remove a file that is in use causes an exception to be raised; on Unix, the directory entry is removed but the storage allocated to the file is not made available until the original file is no longer in use.

Availability: Unix, Windows.

os.removedirs(path)

Remove directories recursively. Works like `rmdir()` except that, if the leaf directory is successfully removed, `removedirs()` tries to successively remove every parent directory mentioned in *path* until an error is raised (which is ignored, because it generally means that a parent directory is not empty). For example, `os.removedirs('foo/bar/baz')` will first remove the directory 'foo/bar/baz', and then remove 'foo/bar' and 'foo' if they are empty. Raises `OSError` if the leaf directory could not be successfully removed.

버전 1.5.2에 추가.

os.rename(src, dst)

Rename the file or directory *src* to *dst*. If *dst* is a directory, `OSError` will be raised. On Unix, if *dst* exists and is a file, it will be replaced silently if the user has permission. The operation may fail on some Unix flavors if *src* and *dst* are on different filesystems. If successful, the renaming will be an atomic operation (this is a POSIX requirement). On Windows, if *dst* already exists, `OSError` will be raised even if it is a file; there may be no way to implement an atomic rename when *dst* names an existing file.

Availability: Unix, Windows.

os.renames(old, new)

Recursive directory or file renaming function. Works like `rename()`, except creation of any intermediate directories needed to make the new pathname good is attempted first. After the rename, directories corresponding to rightmost path segments of the old name will be pruned away using `removedirs()`.

버전 1.5.2에 추가.

참고: This function can fail with the new directory structure made if you lack permissions needed to remove the leaf directory or file.

os.rmdir(path)

Remove (delete) the directory *path*. Only works when the directory is empty, otherwise, `OSError` is raised. In order to remove whole directory trees, `shutil.rmtree()` can be used.

Availability: Unix, Windows.

`os.stat(path)`

Perform the equivalent of a `stat()` system call on the given path. (This function follows symlinks; to stat a symlink use `lstat()`.)

The return value is an object whose attributes correspond to the members of the `stat` structure, namely:

- `st_mode` - protection bits,
- `st_ino` - inode number,
- `st_dev` - device,
- `st_nlink` - number of hard links,
- `st_uid` - user id of owner,
- `st_gid` - group id of owner,
- `st_size` - size of file, in bytes,
- `st_atime` - time of most recent access,
- `st_mtime` - time of most recent content modification,
- `st_ctime` - platform dependent; time of most recent metadata change on Unix, or the time of creation on Windows)

버전 2.3에서 변경: If `stat_float_times()` returns `True`, the time values are floats, measuring seconds. Fractions of a second may be reported if the system supports that. See `stat_float_times()` for further discussion.

On some Unix systems (such as Linux), the following attributes may also be available:

- `st_blocks` - number of 512-byte blocks allocated for file
- `st_blksize` - filesystem blocksize for efficient file system I/O
- `st_rdev` - type of device if an inode device
- `st_flags` - user defined flags for file

On other Unix systems (such as FreeBSD), the following attributes may be available (but may be only filled out if root tries to use them):

- `st_gen` - file generation number
- `st_birthtime` - time of file creation

On RISCOS systems, the following attributes are also available:

- `st_ftype` (file type)
- `st_attrs` (attributes)
- `st_obtype` (object type).

참고: The exact meaning and resolution of the `st_atime`, `st_mtime`, and `st_ctime` attributes depend on the operating system and the file system. For example, on Windows systems using the FAT or FAT32 file systems, `st_mtime` has 2-second resolution, and `st_atime` has only 1-day resolution. See your operating system documentation for details.

For backward compatibility, the return value of `stat()` is also accessible as a tuple of at least 10 integers giving the most important (and portable) members of the `stat` structure, in the order `st_mode`, `st_ino`, `st_dev`,

`st_nlink`, `st_uid`, `st_gid`, `st_size`, `st_atime`, `st_mtime`, `st_ctime`. More items may be added at the end by some implementations.

The standard module `stat` defines functions and constants that are useful for extracting information from a `stat` structure. (On Windows, some items are filled with dummy values.)

Example:

```
>>> import os
>>> statinfo = os.stat('somefile.txt')
>>> statinfo
(33188, 422511, 769, 1, 1032, 100, 926, 1105022698, 1105022732, 1105022732)
>>> statinfo.st_size
926
```

Availability: Unix, Windows.

버전 2.2에서 변경: Added access to values as attributes of the returned object.

버전 2.5에서 변경: Added `st_gen` and `st_birthtime`.

`os.stat_float_times([newvalue])`

Determine whether `stat_result` represents time stamps as float objects. If `newvalue` is `True`, future calls to `stat()` return floats, if it is `False`, future calls return ints. If `newvalue` is omitted, return the current setting.

For compatibility with older Python versions, accessing `stat_result` as a tuple always returns integers.

버전 2.5에서 변경: Python now returns float values by default. Applications which do not work correctly with floating point time stamps can use this function to restore the old behaviour.

The resolution of the timestamps (that is the smallest possible fraction) depends on the system. Some systems only support second resolution; on these systems, the fraction will always be zero.

It is recommended that this setting is only changed at program startup time in the `__main__` module; libraries should never change this setting. If an application uses a library that works incorrectly if floating point time stamps are processed, this application should turn the feature off until the library has been corrected.

`os.statvfs(path)`

Perform a `statvfs()` system call on the given path. The return value is an object whose attributes describe the filesystem on the given path, and correspond to the members of the `statvfs` structure, namely: `f_bsize`, `f_frsize`, `f_blocks`, `f_bfree`, `f_bavail`, `f_files`, `f_ffree`, `f_favail`, `f_flag`, `f_namemax`.

For backward compatibility, the return value is also accessible as a tuple whose values correspond to the attributes, in the order given above. The standard module `statvfs` defines constants that are useful for extracting information from a `statvfs` structure when accessing it as a sequence; this remains useful when writing code that needs to work with versions of Python that don't support accessing the fields as attributes.

Availability: Unix.

버전 2.2에서 변경: Added access to values as attributes of the returned object.

`os.symlink(source, link_name)`

Create a symbolic link pointing to `source` named `link_name`.

Availability: Unix.

`os.tempnam([dir[, prefix]])`

Return a unique path name that is reasonable for creating a temporary file. This will be an absolute path that names a potential directory entry in the directory `dir` or a common location for temporary files if `dir` is omitted or `None`. If given and not `None`, `prefix` is used to provide a short prefix to the filename. Applications are responsible for properly creating and managing files created using paths returned by `tempnam()`; no automatic cleanup is provided. On

Unix, the environment variable `TMPDIR` overrides *dir*, while on Windows `TMP` is used. The specific behavior of this function depends on the C library implementation; some aspects are underspecified in system documentation.

경고: Use of `tempnam()` is vulnerable to symlink attacks; consider using `tmpfile()` (section [File Object Creation](#)) instead.

Availability: Unix, Windows.

os.tmpnam()

Return a unique path name that is reasonable for creating a temporary file. This will be an absolute path that names a potential directory entry in a common location for temporary files. Applications are responsible for properly creating and managing files created using paths returned by `tmpnam()`; no automatic cleanup is provided.

경고: Use of `tmpnam()` is vulnerable to symlink attacks; consider using `tmpfile()` (section [File Object Creation](#)) instead.

Availability: Unix, Windows. This function probably shouldn't be used on Windows, though: Microsoft's implementation of `tmpnam()` always creates a name in the root directory of the current drive, and that's generally a poor location for a temp file (depending on privileges, you may not even be able to open a file using this name).

os.TMP_MAX

The maximum number of unique names that `tmpnam()` will generate before reusing names.

os.unlink(path)

Remove (delete) the file *path*. This is the same function as `remove()`; the `unlink()` name is its traditional Unix name.

Availability: Unix, Windows.

os.utime(path, times)

Set the access and modified times of the file specified by *path*. If *times* is `None`, then the file's access and modified times are set to the current time. (The effect is similar to running the Unix program `touch` on the path.) Otherwise, *times* must be a 2-tuple of numbers, of the form (`atime`, `mtime`) which is used to set the access and modified times, respectively. Whether a directory can be given for *path* depends on whether the operating system implements directories as files (for example, Windows does not). Note that the exact times you set here may not be returned by a subsequent `stat()` call, depending on the resolution with which your operating system records access and modification times; see `stat()`.

버전 2.0에서 변경: Added support for `None` for *times*.

Availability: Unix, Windows.

os.walk(top, topdown=True, onerror=None, followlinks=False)

Generate the file names in a directory tree by walking the tree either top-down or bottom-up. For each directory in the tree rooted at directory *top* (including *top* itself), it yields a 3-tuple (*dirpath*, *dirnames*, *filenames*).

dirpath is a string, the path to the directory. *dirnames* is a list of the names of the subdirectories in *dirpath* (excluding `'.'` and `'..'`). *filenames* is a list of the names of the non-directory files in *dirpath*. Note that the names in the lists contain no path components. To get a full path (which begins with *top*) to a file or directory in *dirpath*, do `os.path.join(dirpath, name)`.

If optional argument *topdown* is `True` or not specified, the triple for a directory is generated before the triples for any of its subdirectories (directories are generated top-down). If *topdown* is `False`, the triple for a directory is generated after the triples for all of its subdirectories (directories are generated bottom-up). No matter the value of *topdown*, the list of subdirectories is retrieved before the tuples for the directory and its subdirectories are generated.

When *topdown* is `True`, the caller can modify the *dirnames* list in-place (perhaps using `del` or slice assignment), and *walk()* will only recurse into the subdirectories whose names remain in *dirnames*; this can be used to prune the search, impose a specific order of visiting, or even to inform *walk()* about directories the caller creates or renames before it resumes *walk()* again. Modifying *dirnames* when *topdown* is `False` has no effect on the behavior of the walk, because in bottom-up mode the directories in *dirnames* are generated before *dirpath* itself is generated.

By default, errors from the *listdir()* call are ignored. If optional argument *onerror* is specified, it should be a function; it will be called with one argument, an *OSError* instance. It can report the error to continue with the walk, or raise the exception to abort the walk. Note that the filename is available as the *filename* attribute of the exception object.

By default, *walk()* will not walk down into symbolic links that resolve to directories. Set *followlinks* to `True` to visit directories pointed to by symlinks, on systems that support them.

버전 2.6에 추가: The *followlinks* parameter.

참고: Be aware that setting *followlinks* to `True` can lead to infinite recursion if a link points to a parent directory of itself. *walk()* does not keep track of the directories it visited already.

참고: If you pass a relative pathname, don't change the current working directory between resumptions of *walk()*. *walk()* never changes the current directory, and assumes that its caller doesn't either.

This example displays the number of bytes taken by non-directory files in each directory under the starting directory, except that it doesn't look under any CVS subdirectory:

```
import os
from os.path import join, getsize
for root, dirs, files in os.walk('python/Lib/email'):
    print root, "consumes",
    print sum(getsize(join(root, name)) for name in files),
    print "bytes in", len(files), "non-directory files"
    if 'CVS' in dirs:
        dirs.remove('CVS') # don't visit CVS directories
```

In the next example, walking the tree bottom-up is essential: *rmdir()* doesn't allow deleting a directory before the directory is empty:

```
# Delete everything reachable from the directory named in "top",
# assuming there are no symbolic links.
# CAUTION: This is dangerous! For example, if top == '/', it
# could delete all your disk files.
import os
for root, dirs, files in os.walk(top, topdown=False):
    for name in files:
        os.remove(os.path.join(root, name))
    for name in dirs:
        os.rmdir(os.path.join(root, name))
```

버전 2.3에 추가.

15.1.5 Process Management

These functions may be used to create and manage processes.

The various *exec** functions take a list of arguments for the new program loaded into the process. In each case, the first of these arguments is passed to the new program as its own name rather than as an argument a user may have typed on a command line. For the C programmer, this is the `argv[0]` passed to a program's `main()`. For example, `os.execl('/bin/echo', ['foo', 'bar'])` will only print `bar` on standard output; `foo` will seem to be ignored.

`os.abort()`

Generate a SIGABRT signal to the current process. On Unix, the default behavior is to produce a core dump; on Windows, the process immediately returns an exit code of 3. Be aware that calling this function will not call the Python signal handler registered for SIGABRT with `signal.signal()`.

Availability: Unix, Windows.

`os.execl(path, arg0, arg1, ...)`

`os.execle(path, arg0, arg1, ..., env)`

`os.execlp(file, arg0, arg1, ...)`

`os.execlpe(file, arg0, arg1, ..., env)`

`os.execv(path, args)`

`os.execve(path, args, env)`

`os.execvp(file, args)`

`os.execvpe(file, args, env)`

These functions all execute a new program, replacing the current process; they do not return. On Unix, the new executable is loaded into the current process, and will have the same process id as the caller. Errors will be reported as *OSError* exceptions.

The current process is replaced immediately. Open file objects and descriptors are not flushed, so if there may be data buffered on these open files, you should flush them using `sys.stdout.flush()` or `os.fsync()` before calling an *exec** function.

The `<l>` and `<v>` variants of the *exec** functions differ in how command-line arguments are passed. The `<l>` variants are perhaps the easiest to work with if the number of parameters is fixed when the code is written; the individual parameters simply become additional parameters to the *execl**() functions. The `<v>` variants are good when the number of parameters is variable, with the arguments being passed in a list or tuple as the *args* parameter. In either case, the arguments to the child process should start with the name of the command being run, but this is not enforced.

The variants which include a `<p>` near the end (*execlp()*, *execlpe()*, *execvp()*, and *execvpe()*) will use the `PATH` environment variable to locate the program *file*. When the environment is being replaced (using one of the *exec*e* variants, discussed in the next paragraph), the new environment is used as the source of the `PATH` variable. The other variants, *execl()*, *execle()*, *execv()*, and *execve()*, will not use the `PATH` variable to locate the executable; *path* must contain an appropriate absolute or relative path.

For *execle()*, *execlpe()*, *execve()*, and *execvpe()* (note that these all end in `<e>`), the *env* parameter must be a mapping which is used to define the environment variables for the new process (these are used instead of the current process' environment); the functions *execl()*, *execlp()*, *execv()*, and *execvp()* all cause the new process to inherit the environment of the current process.

Availability: Unix, Windows.

`os._exit(n)`

Exit the process with status *n*, without calling cleanup handlers, flushing stdio buffers, etc.

Availability: Unix, Windows.

참고: The standard way to exit is `sys.exit(n)`. `_exit()` should normally only be used in the child process after a `fork()`.

The following exit codes are defined and can be used with `_exit()`, although they are not required. These are typically used for system programs written in Python, such as a mail server's external command delivery program.

참고: Some of these may not be available on all Unix platforms, since there is some variation. These constants are defined where they are defined by the underlying platform.

os.EX_OK

Exit code that means no error occurred.

Availability: Unix.

버전 2.3에 추가.

os.EX_USAGE

Exit code that means the command was used incorrectly, such as when the wrong number of arguments are given.

Availability: Unix.

버전 2.3에 추가.

os.EX_DATAERR

Exit code that means the input data was incorrect.

Availability: Unix.

버전 2.3에 추가.

os.EX_NOINPUT

Exit code that means an input file did not exist or was not readable.

Availability: Unix.

버전 2.3에 추가.

os.EX_NOUSER

Exit code that means a specified user did not exist.

Availability: Unix.

버전 2.3에 추가.

os.EX_NOHOST

Exit code that means a specified host did not exist.

Availability: Unix.

버전 2.3에 추가.

os.EX_UNAVAILABLE

Exit code that means that a required service is unavailable.

Availability: Unix.

버전 2.3에 추가.

os.EX_SOFTWARE

Exit code that means an internal software error was detected.

Availability: Unix.

버전 2.3에 추가.

os.EX_OSERR

Exit code that means an operating system error was detected, such as the inability to fork or create a pipe.

Availability: Unix.

버전 2.3에 추가.

os.EX_OSFILE

Exit code that means some system file did not exist, could not be opened, or had some other kind of error.

Availability: Unix.

버전 2.3에 추가.

os.EX_CANTCREAT

Exit code that means a user specified output file could not be created.

Availability: Unix.

버전 2.3에 추가.

os.EX_IOERR

Exit code that means that an error occurred while doing I/O on some file.

Availability: Unix.

버전 2.3에 추가.

os.EX_TEMPFAIL

Exit code that means a temporary failure occurred. This indicates something that may not really be an error, such as a network connection that couldn't be made during a retryable operation.

Availability: Unix.

버전 2.3에 추가.

os.EX_PROTOCOL

Exit code that means that a protocol exchange was illegal, invalid, or not understood.

Availability: Unix.

버전 2.3에 추가.

os.EX_NOPERM

Exit code that means that there were insufficient permissions to perform the operation (but not intended for file system problems).

Availability: Unix.

버전 2.3에 추가.

os.EX_CONFIG

Exit code that means that some kind of configuration error occurred.

Availability: Unix.

버전 2.3에 추가.

os.EX_NOTFOUND

Exit code that means something like 《an entry was not found》.

Availability: Unix.

버전 2.3에 추가.

os.fork()

Fork a child process. Return 0 in the child and the child's process id in the parent. If an error occurs *OSError* is raised.

Note that some platforms including FreeBSD <= 6.3, Cygwin and OS/2 EMX have known issues when using `fork()` from a thread.

경고: See [ssl](#) for applications that use the SSL module with `fork()`.

Availability: Unix.

os.forkpty()

Fork a child process, using a new pseudo-terminal as the child's controlling terminal. Return a pair of (*pid*, *fd*), where *pid* is 0 in the child, the new child's process id in the parent, and *fd* is the file descriptor of the master end of the pseudo-terminal. For a more portable approach, use the *pty* module. If an error occurs *OSError* is raised.

Availability: some flavors of Unix.

os.kill(pid, sig)

Send signal *sig* to the process *pid*. Constants for the specific signals available on the host platform are defined in the *signal* module.

Windows: The *signal.CTRL_C_EVENT* and *signal.CTRL_BREAK_EVENT* signals are special signals which can only be sent to console processes which share a common console window, e.g., some subprocesses. Any other value for *sig* will cause the process to be unconditionally killed by the `TerminateProcess` API, and the exit code will be set to *sig*. The Windows version of *kill()* additionally takes process handles to be killed.

버전 2.7에 추가: Windows support

os.killpg(pgid, sig)

Send the signal *sig* to the process group *pgid*.

Availability: Unix.

버전 2.3에 추가.

os.nice(increment)

Add *increment* to the process's «niceness». Return the new niceness.

Availability: Unix.

os.plock(op)

Lock program segments into memory. The value of *op* (defined in `<sys/lock.h>`) determines which segments are locked.

Availability: Unix.

os.popen(...)**os.popen2(...)****os.popen3(...)****os.popen4(...)**

Run child processes, returning opened pipes for communications. These functions are described in section [File Object Creation](#).

os.spawnl(mode, path, ...)**os.spawnle(mode, path, ..., env)****os.spawnlp(mode, file, ...)****os.spawnlpe(mode, file, ..., env)****os.spawnv(mode, path, args)**

`os.spawnve(mode, path, args, env)`
`os.spawnvp(mode, file, args)`
`os.spawnvpe(mode, file, args, env)`

Execute the program *path* in a new process.

(Note that the *subprocess* module provides more powerful facilities for spawning new processes and retrieving their results; using that module is preferable to using these functions. Check especially the *Replacing Older Functions with the subprocess Module* section.)

If *mode* is *P_NOWAIT*, this function returns the process id of the new process; if *mode* is *P_WAIT*, returns the process's exit code if it exits normally, or *-signal*, where *signal* is the signal that killed the process. On Windows, the process id will actually be the process handle, so can be used with the *waitpid()* function.

The `<1>` and `<v>` variants of the *spawn** functions differ in how command-line arguments are passed. The `<1>` variants are perhaps the easiest to work with if the number of parameters is fixed when the code is written; the individual parameters simply become additional parameters to the *spawnl*()* functions. The `<v>` variants are good when the number of parameters is variable, with the arguments being passed in a list or tuple as the *args* parameter. In either case, the arguments to the child process must start with the name of the command being run.

The variants which include a second `<p>` near the end (*spawnlp()*, *spawnlpe()*, *spawnvp()*, and *spawnvpe()*) will use the *PATH* environment variable to locate the program *file*. When the environment is being replaced (using one of the *spawn*e* variants, discussed in the next paragraph), the new environment is used as the source of the *PATH* variable. The other variants, *spawnl()*, *spawnle()*, *spawnv()*, and *spawnve()*, will not use the *PATH* variable to locate the executable; *path* must contain an appropriate absolute or relative path.

For *spawnle()*, *spawnlpe()*, *spawnve()*, and *spawnvpe()* (note that these all end in `<e>`), the *env* parameter must be a mapping which is used to define the environment variables for the new process (they are used instead of the current process's environment); the functions *spawnl()*, *spawnlp()*, *spawnv()*, and *spawnvp()* all cause the new process to inherit the environment of the current process. Note that keys and values in the *env* dictionary must be strings; invalid keys or values will cause the function to fail, with a return value of 127.

As an example, the following calls to *spawnlp()* and *spawnvpe()* are equivalent:

```
import os
os.spawnlp(os.P_WAIT, 'cp', 'cp', 'index.html', '/dev/null')

L = ['cp', 'index.html', '/dev/null']
os.spawnvpe(os.P_WAIT, 'cp', L, os.environ)
```

Availability: Unix, Windows. *spawnlp()*, *spawnlpe()*, *spawnvp()* and *spawnvpe()* are not available on Windows. *spawnle()* and *spawnve()* are not thread-safe on Windows; we advise you to use the *subprocess* module instead.

버전 1.6에 추가.

`os.P_NOWAIT`
`os.P_NOWAITO`

Possible values for the *mode* parameter to the *spawn** family of functions. If either of these values is given, the *spawn*()* functions will return as soon as the new process has been created, with the process id as the return value.

Availability: Unix, Windows.

버전 1.6에 추가.

`os.P_WAIT`

Possible value for the *mode* parameter to the *spawn** family of functions. If this is given as *mode*, the *spawn*()* functions will not return until the new process has run to completion and will return the exit code of the process the run is successful, or *-signal* if a signal kills the process.

Availability: Unix, Windows.

버전 1.6에 추가.

`os.P_DETACH`

`os.P_OVERLAY`

Possible values for the *mode* parameter to the *spawn** family of functions. These are less portable than those listed above. *P_DETACH* is similar to *P_NOWAIT*, but the new process is detached from the console of the calling process. If *P_OVERLAY* is used, the current process will be replaced; the *spawn*()* function will not return.

Availability: Windows.

버전 1.6에 추가.

`os.startfile(path[, operation])`

Start a file with its associated application.

When *operation* is not specified or 'open', this acts like double-clicking the file in Windows Explorer, or giving the file name as an argument to the **start** command from the interactive command shell: the file is opened with whatever application (if any) its extension is associated.

When another *operation* is given, it must be a *command verb* that specifies what should be done with the file. Common verbs documented by Microsoft are 'print' and 'edit' (to be used on files) as well as 'explore' and 'find' (to be used on directories).

startfile() returns as soon as the associated application is launched. There is no option to wait for the application to close, and no way to retrieve the application's exit status. The *path* parameter is relative to the current directory. If you want to use an absolute path, make sure the first character is not a slash ('/'); the underlying Win32 *ShellExecute()* function doesn't work if it is. Use the *os.path.normpath()* function to ensure that the path is properly encoded for Win32.

Availability: Windows.

버전 2.0에 추가.

버전 2.5에 추가: The *operation* parameter.

`os.system(command)`

Execute the command (a string) in a subshell. This is implemented by calling the Standard C function *system()*, and has the same limitations. Changes to *sys.stdin*, etc. are not reflected in the environment of the executed command.

On Unix, the return value is the exit status of the process encoded in the format specified for *wait()*. Note that POSIX does not specify the meaning of the return value of the C *system()* function, so the return value of the Python function is system-dependent.

On Windows, the return value is that returned by the system shell after running *command*, given by the Windows environment variable *COMSPEC*: on **command.com** systems (Windows 95, 98 and ME) this is always 0; on **cmd.exe** systems (Windows NT, 2000 and XP) this is the exit status of the command run; on systems using a non-native shell, consult your shell documentation.

The *subprocess* module provides more powerful facilities for spawning new processes and retrieving their results; using that module is preferable to using this function. See the *Replacing Older Functions with the subprocess Module* section in the *subprocess* documentation for some helpful recipes.

Availability: Unix, Windows.

`os.times()`

Return a 5-tuple of floating point numbers indicating accumulated (processor or other) times, in seconds. The items are: user time, system time, children's user time, children's system time, and elapsed real time since a fixed point in the past, in that order. See the Unix manual page *times(2)* or the corresponding Windows Platform API documentation. On Windows, only the first two items are filled, the others are zero.

Availability: Unix, Windows

os.wait()

Wait for completion of a child process, and return a tuple containing its pid and exit status indication: a 16-bit number, whose low byte is the signal number that killed the process, and whose high byte is the exit status (if the signal number is zero); the high bit of the low byte is set if a core file was produced.

Availability: Unix.

os.waitpid(pid, options)

The details of this function differ on Unix and Windows.

On Unix: Wait for completion of a child process given by process id *pid*, and return a tuple containing its process id and exit status indication (encoded as for `wait()`). The semantics of the call are affected by the value of the integer *options*, which should be 0 for normal operation.

If *pid* is greater than 0, `waitpid()` requests status information for that specific process. If *pid* is 0, the request is for the status of any child in the process group of the current process. If *pid* is -1, the request pertains to any child of the current process. If *pid* is less than -1, status is requested for any process in the process group -*pid* (the absolute value of *pid*).

An `OSError` is raised with the value of `errno` when the syscall returns -1.

On Windows: Wait for completion of a process given by process handle *pid*, and return a tuple containing *pid*, and its exit status shifted left by 8 bits (shifting makes cross-platform use of the function easier). A *pid* less than or equal to 0 has no special meaning on Windows, and raises an exception. The value of integer *options* has no effect. *pid* can refer to any process whose id is known, not necessarily a child process. The `spawn*` functions called with `P_NOWAIT` return suitable process handles.

os.wait3(options)

Similar to `waitpid()`, except no process id argument is given and a 3-element tuple containing the child's process id, exit status indication, and resource usage information is returned. Refer to `resource.getrusage()` for details on resource usage information. The option argument is the same as that provided to `waitpid()` and `wait4()`.

Availability: Unix.

버전 2.5에 추가.

os.wait4(pid, options)

Similar to `waitpid()`, except a 3-element tuple, containing the child's process id, exit status indication, and resource usage information is returned. Refer to `resource.getrusage()` for details on resource usage information. The arguments to `wait4()` are the same as those provided to `waitpid()`.

Availability: Unix.

버전 2.5에 추가.

os.WNOHANG

The option for `waitpid()` to return immediately if no child process status is available immediately. The function returns (0, 0) in this case.

Availability: Unix.

os.WCONTINUED

This option causes child processes to be reported if they have been continued from a job control stop since their status was last reported.

Availability: Some Unix systems.

버전 2.3에 추가.

os.WUNTRACED

This option causes child processes to be reported if they have been stopped but their current state has not been reported since they were stopped.

Availability: Unix.

버전 2.3에 추가.

The following functions take a process status code as returned by `system()`, `wait()`, or `waitpid()` as a parameter. They may be used to determine the disposition of a process.

os.WCOREDUMP (*status*)

Return `True` if a core dump was generated for the process, otherwise return `False`.

Availability: Unix.

버전 2.3에 추가.

os.WIFCONTINUED (*status*)

Return `True` if the process has been continued from a job control stop, otherwise return `False`.

Availability: Unix.

버전 2.3에 추가.

os.WIFSTOPPED (*status*)

Return `True` if the process has been stopped, otherwise return `False`.

Availability: Unix.

os.WIFSIGNALED (*status*)

Return `True` if the process exited due to a signal, otherwise return `False`.

Availability: Unix.

os.WIFEXITED (*status*)

Return `True` if the process exited using the `exit(2)` system call, otherwise return `False`.

Availability: Unix.

os.WEXITSTATUS (*status*)

If `WIFEXITED(status)` is true, return the integer parameter to the `exit(2)` system call. Otherwise, the return value is meaningless.

Availability: Unix.

os.WSTOPSIG (*status*)

Return the signal which caused the process to stop.

Availability: Unix.

os.WTERMSIG (*status*)

Return the signal which caused the process to exit.

Availability: Unix.

15.1.6 Miscellaneous System Information

`os.confstr(name)`

Return string-valued system configuration values. *name* specifies the configuration value to retrieve; it may be a string which is the name of a defined system value; these names are specified in a number of standards (POSIX, Unix 95, Unix 98, and others). Some platforms define additional names as well. The names known to the host operating system are given as the keys of the `confstr_names` dictionary. For configuration variables not included in that mapping, passing an integer for *name* is also accepted.

If the configuration value specified by *name* isn't defined, `None` is returned.

If *name* is a string and is not known, `ValueError` is raised. If a specific value for *name* is not supported by the host system, even if it is included in `confstr_names`, an `OSError` is raised with `errno.EINVAL` for the error number.

Availability: Unix

`os.confstr_names`

Dictionary mapping names accepted by `confstr()` to the integer values defined for those names by the host operating system. This can be used to determine the set of names known to the system.

Availability: Unix.

`os.getloadavg()`

Return the number of processes in the system run queue averaged over the last 1, 5, and 15 minutes or raises `OSError` if the load average was unobtainable.

Availability: Unix.

버전 2.3에 추가.

`os.sysconf(name)`

Return integer-valued system configuration values. If the configuration value specified by *name* isn't defined, `-1` is returned. The comments regarding the *name* parameter for `confstr()` apply here as well; the dictionary that provides information on the known names is given by `sysconf_names`.

Availability: Unix.

`os.sysconf_names`

Dictionary mapping names accepted by `sysconf()` to the integer values defined for those names by the host operating system. This can be used to determine the set of names known to the system.

Availability: Unix.

The following data values are used to support path manipulation operations. These are defined for all platforms.

Higher-level operations on pathnames are defined in the `os.path` module.

`os.curdir`

The constant string used by the operating system to refer to the current directory. This is `'.'` for Windows and POSIX. Also available via `os.path`.

`os.pardir`

The constant string used by the operating system to refer to the parent directory. This is `'..'` for Windows and POSIX. Also available via `os.path`.

`os.sep`

The character used by the operating system to separate pathname components. This is `'/'` for POSIX and `'\'` for Windows. Note that knowing this is not sufficient to be able to parse or concatenate pathnames — use `os.path.split()` and `os.path.join()` — but it is occasionally useful. Also available via `os.path`.

`os.altsep`

An alternative character used by the operating system to separate pathname components, or `None` if only one

separator character exists. This is set to `'/'` on Windows systems where `sep` is a backslash. Also available via `os.path`.

`os.extsep`

The character which separates the base filename from the extension; for example, the `'.'` in `os.py`. Also available via `os.path`.

버전 2.2에 추가.

`os.pathsep`

The character conventionally used by the operating system to separate search path components (as in `PATH`), such as `':'` for POSIX or `';'` for Windows. Also available via `os.path`.

`os.defpath`

The default search path used by `exec*p*` and `spawn*p*` if the environment doesn't have a `'PATH'` key. Also available via `os.path`.

`os.linesep`

The string used to separate (or, rather, terminate) lines on the current platform. This may be a single character, such as `'\n'` for POSIX, or multiple characters, for example, `'\r\n'` for Windows. Do not use `os.linesep` as a line terminator when writing files opened in text mode (the default); use a single `'\n'` instead, on all platforms.

`os.devnull`

The file path of the null device. For example: `'/dev/null '` for POSIX, `'nul '` for Windows. Also available via `os.path`.

버전 2.4에 추가.

15.1.7 Miscellaneous Functions

`os.urandom(n)`

Return a string of *n* random bytes suitable for cryptographic use.

This function returns random bytes from an OS-specific randomness source. The returned data should be unpredictable enough for cryptographic applications, though its exact quality depends on the OS implementation. On a UNIX-like system this will query `/dev/urandom`, and on Windows it will use `CryptGenRandom()`. If a randomness source is not found, `NotImplementedError` will be raised.

For an easy-to-use interface to the random number generator provided by your platform, please see `random.SystemRandom`.

버전 2.4에 추가.

15.2 `io` — Core tools for working with streams

버전 2.6에 추가.

The `io` module provides the Python interfaces to stream handling. Under Python 2.x, this is proposed as an alternative to the built-in `file` object, but in Python 3.x it is the default interface to access files and streams.

참고: Since this module has been designed primarily for Python 3.x, you have to be aware that all uses of `《bytes》` in this document refer to the `str` type (of which `bytes` is an alias), and all uses of `《text》` refer to the `unicode` type. Furthermore, those two types are not interchangeable in the `io` APIs.

At the top of the I/O hierarchy is the abstract base class `IOBase`. It defines the basic interface to a stream. Note, however, that there is no separation between reading and writing to streams; implementations are allowed to raise an `IOError` if they do not support a given operation.

Extending `IOBase` is `RawIOBase` which deals simply with the reading and writing of raw bytes to a stream. `FileIO` subclasses `RawIOBase` to provide an interface to files in the machine's file system.

`BufferedIOBase` deals with buffering on a raw byte stream (`RawIOBase`). Its subclasses, `BufferedWriter`, `BufferedReader`, and `BufferedRWPair` buffer streams that are readable, writable, and both readable and writable. `BufferedRandom` provides a buffered interface to random access streams. `BytesIO` is a simple stream of in-memory bytes.

Another `IOBase` subclass, `TextIOBase`, deals with streams whose bytes represent text, and handles encoding and decoding from and to `unicode` strings. `TextIOWrapper`, which extends it, is a buffered text interface to a buffered raw stream (`BufferedIOBase`). Finally, `StringIO` is an in-memory stream for unicode text.

Argument names are not part of the specification, and only the arguments of `open()` are intended to be used as keyword arguments.

15.2.1 Module Interface

`io.DEFAULT_BUFFER_SIZE`

An int containing the default buffer size used by the module's buffered I/O classes. `open()` uses the file's `blksize` (as obtained by `os.stat()`) if possible.

`io.open(file, mode='r', buffering=-1, encoding=None, errors=None, newline=None, closefd=True)`
Open `file` and return a corresponding stream. If the file cannot be opened, an `IOError` is raised.

`file` is either a string giving the pathname (absolute or relative to the current working directory) of the file to be opened or an integer file descriptor of the file to be wrapped. (If a file descriptor is given, it is closed when the returned I/O object is closed, unless `closefd` is set to `False`.)

`mode` is an optional string that specifies the mode in which the file is opened. It defaults to `'r'` which means open for reading in text mode. Other common values are `'w'` for writing (truncating the file if it already exists), and `'a'` for appending (which on *some* Unix systems, means that *all* writes append to the end of the file regardless of the current seek position). In text mode, if `encoding` is not specified the encoding used is platform dependent. (For reading and writing raw bytes use binary mode and leave `encoding` unspecified.) The available modes are:

Character	Meaning
<code>'r'</code>	open for reading (default)
<code>'w'</code>	open for writing, truncating the file first
<code>'a'</code>	open for writing, appending to the end of the file if it exists
<code>'b'</code>	binary mode
<code>'t'</code>	text mode (default)
<code>'+'</code>	open a disk file for updating (reading and writing)
<code>'U'</code>	universal newlines mode (for backwards compatibility; should not be used in new code)

The default mode is `'rt'` (open for reading text). For binary random access, the mode `'w+b'` opens and truncates the file to 0 bytes, while `'r+b'` opens the file without truncation.

Python distinguishes between files opened in binary and text modes, even when the underlying operating system doesn't. Files opened in binary mode (including `'b'` in the `mode` argument) return contents as `bytes` objects without any decoding. In text mode (the default, or when `'t'` is included in the `mode` argument), the contents of the file are returned as `unicode` strings, the bytes having been first decoded using a platform-dependent encoding or using the specified `encoding` if given.

buffering is an optional integer used to set the buffering policy. Pass 0 to switch buffering off (only allowed in binary mode), 1 to select line buffering (only usable in text mode), and an integer > 1 to indicate the size of a fixed-size chunk buffer. When no *buffering* argument is given, the default buffering policy works as follows:

- Binary files are buffered in fixed-size chunks; the size of the buffer is chosen using a heuristic trying to determine the underlying device's «block size» and falling back on `DEFAULT_BUFFER_SIZE`. On many systems, the buffer will typically be 4096 or 8192 bytes long.
- «Interactive» text files (files for which `isatty()` returns True) use line buffering. Other text files use the policy described above for binary files.

encoding is the name of the encoding used to decode or encode the file. This should only be used in text mode. The default encoding is platform dependent (whatever `locale.getpreferredencoding()` returns), but any encoding supported by Python can be used. See the `codecs` module for the list of supported encodings.

errors is an optional string that specifies how encoding and decoding errors are to be handled—this cannot be used in binary mode. Pass 'strict' to raise a `ValueError` exception if there is an encoding error (the default of None has the same effect), or pass 'ignore' to ignore errors. (Note that ignoring encoding errors can lead to data loss.) 'replace' causes a replacement marker (such as '?') to be inserted where there is malformed data. When writing, 'xmlcharrefreplace' (replace with the appropriate XML character reference) or 'backslashreplace' (replace with backslashed escape sequences) can be used. Any other error handling name that has been registered with `codecs.register_error()` is also valid.

newline controls how *universal newlines* works (it only applies to text mode). It can be None, '', '\n', '\r', and '\r\n'. It works as follows:

- On input, if *newline* is None, universal newlines mode is enabled. Lines in the input can end in '\n', '\r', or '\r\n', and these are translated into '\n' before being returned to the caller. If it is '', universal newlines mode is enabled, but line endings are returned to the caller untranslated. If it has any of the other legal values, input lines are only terminated by the given string, and the line ending is returned to the caller untranslated.
- On output, if *newline* is None, any '\n' characters written are translated to the system default line separator, `os.linesep`. If *newline* is '', no translation takes place. If *newline* is any of the other legal values, any '\n' characters written are translated to the given string.

If *closefd* is False and a file descriptor rather than a filename was given, the underlying file descriptor will be kept open when the file is closed. If a filename is given *closefd* has no effect and must be True (the default).

The type of file object returned by the `open()` function depends on the mode. When `open()` is used to open a file in a text mode ('w', 'r', 'wt', 'rt', etc.), it returns a subclass of `TextIOBase` (specifically `TextIOWrapper`). When used to open a file in a binary mode with buffering, the returned class is a subclass of `BufferedIOBase`. The exact class varies: in read binary mode, it returns a `BufferedReader`; in write binary and append binary modes, it returns a `BufferedWriter`, and in read/write mode, it returns a `BufferedRandom`. When buffering is disabled, the raw stream, a subclass of `RawIOBase`, `FileIO`, is returned.

It is also possible to use an *unicode* or *bytes* string as a file for both reading and writing. For *unicode* strings `StringIO` can be used like a file opened in text mode, and for *bytes* a `BytesIO` can be used like a file opened in a binary mode.

exception `io.BlockingIOError`

Error raised when blocking would occur on a non-blocking stream. It inherits `IOError`.

In addition to those of `IOError`, `BlockingIOError` has one attribute:

`characters_written`

An integer containing the number of characters written to the stream before it blocked.

exception `io.UnsupportedOperation`

An exception inheriting `IOError` and `ValueError` that is raised when an unsupported operation is called on a stream.

15.2.2 I/O Base Classes

class `io.IOBase`

The abstract base class for all I/O classes, acting on streams of bytes. There is no public constructor.

This class provides empty abstract implementations for many methods that derived classes can override selectively; the default implementations represent a file that cannot be read, written or seeked.

Even though `IOBase` does not declare `read()`, `readinto()`, or `write()` because their signatures will vary, implementations and clients should consider those methods part of the interface. Also, implementations may raise an `IOError` when operations they do not support are called.

The basic type used for binary data read from or written to a file is `bytes` (also known as `str`). Method arguments may also be `bytearray` or `memoryview` of arrays of bytes. In some cases, such as `readinto()`, a writable object such as `bytearray` is required. Text I/O classes work with `unicode` data.

버전 2.7에서 변경: Implementations should support `memoryview` arguments.

Note that calling any method (even inquiries) on a closed stream is undefined. Implementations may raise `IOError` in this case.

`IOBase` (and its subclasses) support the iterator protocol, meaning that an `IOBase` object can be iterated over yielding the lines in a stream. Lines are defined slightly differently depending on whether the stream is a binary stream (yielding `bytes`), or a text stream (yielding `unicode` strings). See `readline()` below.

`IOBase` is also a context manager and therefore supports the `with` statement. In this example, `file` is closed after the `with` statement's suite is finished—even if an exception occurs:

```
with io.open('spam.txt', 'w') as file:
    file.write(u'Spam and eggs!')
```

`IOBase` provides these data attributes and methods:

close()

Flush and close this stream. This method has no effect if the file is already closed. Once the file is closed, any operation on the file (e.g. reading or writing) will raise a `ValueError`.

As a convenience, it is allowed to call this method more than once; only the first call, however, will have an effect.

closed

True if the stream is closed.

fileno()

Return the underlying file descriptor (an integer) of the stream if it exists. An `IOError` is raised if the IO object does not use a file descriptor.

flush()

Flush the write buffers of the stream if applicable. This does nothing for read-only and non-blocking streams.

isatty()

Return True if the stream is interactive (i.e., connected to a terminal/tty device).

readable()

Return True if the stream can be read from. If False, `read()` will raise `IOError`.

readline (*limit=-1*)

Read and return one line from the stream. If *limit* is specified, at most *limit* bytes will be read.

The line terminator is always `b'\n'` for binary files; for text files, the *newline* argument to `open()` can be used to select the line terminator(s) recognized.

readlines (*hint=-1*)

Read and return a list of lines from the stream. *hint* can be specified to control the number of lines read: no more lines will be read if the total size (in bytes/characters) of all lines so far exceeds *hint*.

Note that it's already possible to iterate on file objects using `for line in file: ...` without calling `file.readlines()`.

seek (*offset, whence=SEEK_SET*)

Change the stream position to the given byte *offset*. *offset* is interpreted relative to the position indicated by *whence*. The default value for *whence* is `SEEK_SET`. Values for *whence* are:

- `SEEK_SET` or 0 – start of the stream (the default); *offset* should be zero or positive
- `SEEK_CUR` or 1 – current stream position; *offset* may be negative
- `SEEK_END` or 2 – end of the stream; *offset* is usually negative

Return the new absolute position.

버전 2.7에 추가: The `SEEK_*` constants

seekable ()

Return `True` if the stream supports random access. If `False`, `seek()`, `tell()` and `truncate()` will raise `IOError`.

tell ()

Return the current stream position.

truncate (*size=None*)

Resize the stream to the given *size* in bytes (or the current position if *size* is not specified). The current stream position isn't changed. This resizing can extend or reduce the current file size. In case of extension, the contents of the new file area depend on the platform (on most systems, additional bytes are zero-filled, on Windows they're undetermined). The new file size is returned.

writable ()

Return `True` if the stream supports writing. If `False`, `write()` and `truncate()` will raise `IOError`.

writelines (*lines*)

Write a list of lines to the stream. Line separators are not added, so it is usual for each of the lines provided to have a line separator at the end.

__del__ ()

Prepare for object destruction. `IOBase` provides a default implementation of this method that calls the instance's `close()` method.

class io.RawIOBase

Base class for raw binary I/O. It inherits `IOBase`. There is no public constructor.

Raw binary I/O typically provides low-level access to an underlying OS device or API, and does not try to encapsulate it in high-level primitives (this is left to Buffered I/O and Text I/O, described later in this page).

In addition to the attributes and methods from `IOBase`, `RawIOBase` provides the following methods:

read (*n=-1*)

Read up to *n* bytes from the object and return them. As a convenience, if *n* is unspecified or -1, `readall()` is called. Otherwise, only one system call is ever made. Fewer than *n* bytes may be returned if the operating system call returns fewer than *n* bytes.

If 0 bytes are returned, and *n* was not 0, this indicates end of file. If the object is in non-blocking mode and no bytes are available, *None* is returned.

readall()

Read and return all the bytes from the stream until EOF, using multiple calls to the stream if necessary.

readinto(*b*)

Read up to `len(b)` bytes into *b*, and return the number of bytes read. The object *b* should be a pre-allocated, writable array of bytes, either *bytearray* or *memoryview*. If the object is in non-blocking mode and no bytes are available, *None* is returned.

write(*b*)

Write *b* to the underlying raw stream, and return the number of bytes written. The object *b* should be an array of bytes, either *bytes*, *bytearray*, or *memoryview*. The return value can be less than `len(b)`, depending on specifics of the underlying raw stream, and especially if it is in non-blocking mode. *None* is returned if the raw stream is set not to block and no single byte could be readily written to it. The caller may release or mutate *b* after this method returns, so the implementation should only access *b* during the method call.

class io.BufferedIOBase

Base class for binary streams that support some kind of buffering. It inherits *IOBase*. There is no public constructor.

The main difference with *RawIOBase* is that methods *read()*, *readinto()* and *write()* will try (respectively) to read as much input as requested or to consume all given output, at the expense of making perhaps more than one system call.

In addition, those methods can raise *BlockingIOError* if the underlying raw stream is in non-blocking mode and cannot take or give enough data; unlike their *RawIOBase* counterparts, they will never return *None*.

Besides, the *read()* method does not have a default implementation that defers to *readinto()*.

A typical *BufferedIOBase* implementation should not inherit from a *RawIOBase* implementation, but wrap one, like *BufferedWriter* and *BufferedReader* do.

BufferedIOBase provides or overrides these methods and attribute in addition to those from *IOBase*:

raw

The underlying raw stream (a *RawIOBase* instance) that *BufferedIOBase* deals with. This is not part of the *BufferedIOBase* API and may not exist on some implementations.

detach()

Separate the underlying raw stream from the buffer and return it.

After the raw stream has been detached, the buffer is in an unusable state.

Some buffers, like *BytesIO*, do not have the concept of a single raw stream to return from this method. They raise *UnsupportedOperation*.

버전 2.7에 추가.

read(*n=-1*)

Read and return up to *n* bytes. If the argument is omitted, *None*, or negative, data is read and returned until EOF is reached. An empty bytes object is returned if the stream is already at EOF.

If the argument is positive, and the underlying raw stream is not interactive, multiple raw reads may be issued to satisfy the byte count (unless EOF is reached first). But for interactive raw streams, at most one raw read will be issued, and a short result does not imply that EOF is imminent.

A *BlockingIOError* is raised if the underlying raw stream is in non blocking-mode, and has no data available at the moment.

read1 (*n=-1*)

Read and return up to *n* bytes, with at most one call to the underlying raw stream's `read()` method. This can be useful if you are implementing your own buffering on top of a `BufferedIOBase` object.

readinto (*b*)

Read up to `len(b)` bytes into *b*, and return the number of bytes read. The object *b* should be a pre-allocated, writable array of bytes, either `bytearray` or `memoryview`.

Like `read()`, multiple reads may be issued to the underlying raw stream, unless the latter is `<interactive>`.

A `BlockingIOError` is raised if the underlying raw stream is in non blocking-mode, and has no data available at the moment.

write (*b*)

Write *b*, and return the number of bytes written (always equal to `len(b)`, since if the write fails an `IOError` will be raised). The object *b* should be an array of bytes, either `bytes`, `bytearray`, or `memoryview`. Depending on the actual implementation, these bytes may be readily written to the underlying stream, or held in a buffer for performance and latency reasons.

When in non-blocking mode, a `BlockingIOError` is raised if the data needed to be written to the raw stream but it couldn't accept all the data without blocking.

The caller may release or mutate *b* after this method returns, so the implementation should only access *b* during the method call.

15.2.3 Raw File I/O

class `io.FileIO` (*name, mode='r', closefd=True*)

`FileIO` represents an OS-level file containing bytes data. It implements the `RawIOBase` interface (and therefore the `IOBase` interface, too).

The *name* can be one of two things:

- a string representing the path to the file which will be opened;
- an integer representing the number of an existing OS-level file descriptor to which the resulting `FileIO` object will give access.

The *mode* can be `'r'`, `'w'` or `'a'` for reading (default), writing, or appending. The file will be created if it doesn't exist when opened for writing or appending; it will be truncated when opened for writing. Add a `'+'` to the mode to allow simultaneous reading and writing.

The `read()` (when called with a positive argument), `readinto()` and `write()` methods on this class will only make one system call.

In addition to the attributes and methods from `IOBase` and `RawIOBase`, `FileIO` provides the following data attributes and methods:

mode

The mode as given in the constructor.

name

The file name. This is the file descriptor of the file when no name is given in the constructor.

15.2.4 Buffered Streams

Buffered I/O streams provide a higher-level interface to an I/O device than raw I/O does.

class `io.BytesIO([initial_bytes])`

A stream implementation using an in-memory bytes buffer. It inherits *BufferedIOBase*.

The optional argument *initial_bytes* is a `bytes` object that contains initial data.

BytesIO provides or overrides these methods in addition to those from *BufferedIOBase* and *IOBase*:

getvalue()

Return `bytes` containing the entire contents of the buffer.

read1()

In *BytesIO*, this is the same as `read()`.

class `io.BufferedReader(raw, buffer_size=DEFAULT_BUFFER_SIZE)`

A buffer providing higher-level access to a readable, sequential *RawIOBase* object. It inherits *BufferedIOBase*. When reading data from this object, a larger amount of data may be requested from the underlying raw stream, and kept in an internal buffer. The buffered data can then be returned directly on subsequent reads.

The constructor creates a *BufferedReader* for the given readable *raw* stream and *buffer_size*. If *buffer_size* is omitted, *DEFAULT_BUFFER_SIZE* is used.

BufferedReader provides or overrides these methods in addition to those from *BufferedIOBase* and *IOBase*:

peek([n])

Return bytes from the stream without advancing the position. At most one single read on the raw stream is done to satisfy the call. The number of bytes returned may be less or more than requested.

read([n])

Read and return *n* bytes, or if *n* is not given or negative, until EOF or if the read call would block in non-blocking mode.

read1(n)

Read and return up to *n* bytes with only one call on the raw stream. If at least one byte is buffered, only buffered bytes are returned. Otherwise, one raw stream read call is made.

class `io.BufferedWriter(raw, buffer_size=DEFAULT_BUFFER_SIZE)`

A buffer providing higher-level access to a writeable, sequential *RawIOBase* object. It inherits *BufferedIOBase*. When writing to this object, data is normally held into an internal buffer. The buffer will be written out to the underlying *RawIOBase* object under various conditions, including:

- when the buffer gets too small for all pending data;
- when *flush()* is called;
- when a *seek()* is requested (for *BufferedRandom* objects);
- when the *BufferedWriter* object is closed or destroyed.

The constructor creates a *BufferedWriter* for the given writeable *raw* stream. If the *buffer_size* is not given, it defaults to *DEFAULT_BUFFER_SIZE*.

A third argument, *max_buffer_size*, is supported, but unused and deprecated.

BufferedWriter provides or overrides these methods in addition to those from *BufferedIOBase* and *IOBase*:

flush()

Force bytes held in the buffer into the raw stream. A *BlockingIOError* should be raised if the raw stream blocks.

write(b)

Write *b*, and return the number of bytes written. The object *b* should be an array of bytes, either *bytes*, *bytearray*, or *memoryview*. When in non-blocking mode, a *BlockingIOError* is raised if the buffer needs to be written out but the raw stream blocks.

class io.BufferedRandom(raw, buffer_size=DEFAULT_BUFFER_SIZE)

A buffered interface to random access streams. It inherits *BufferedReader* and *BufferedWriter*, and further supports *seek()* and *tell()* functionality.

The constructor creates a reader and writer for a seekable raw stream, given in the first argument. If the *buffer_size* is omitted it defaults to *DEFAULT_BUFFER_SIZE*.

A third argument, *max_buffer_size*, is supported, but unused and deprecated.

BufferedRandom is capable of anything *BufferedReader* or *BufferedWriter* can do.

class io.BufferedRWPair(reader, writer, buffer_size=DEFAULT_BUFFER_SIZE)

A buffered I/O object combining two unidirectional *RawIOBase* objects – one readable, the other writeable – into a single bidirectional endpoint. It inherits *BufferedIOBase*.

reader and *writer* are *RawIOBase* objects that are readable and writeable respectively. If the *buffer_size* is omitted it defaults to *DEFAULT_BUFFER_SIZE*.

A fourth argument, *max_buffer_size*, is supported, but unused and deprecated.

BufferedRWPair implements all of *BufferedIOBase*'s methods except for *detach()*, which raises *UnsupportedOperation*.

경고: *BufferedRWPair* does not attempt to synchronize accesses to its underlying raw streams. You should not pass it the same object as reader and writer; use *BufferedRandom* instead.

15.2.5 Text I/O

class io.TextIOBase

Base class for text streams. This class provides a unicode character and line based interface to stream I/O. There is no *readinto()* method because Python's *unicode* strings are immutable. It inherits *IOBase*. There is no public constructor.

TextIOBase provides or overrides these data attributes and methods in addition to those from *IOBase*:

encoding

The name of the encoding used to decode the stream's bytes into strings, and to encode strings into bytes.

errors

The error setting of the decoder or encoder.

newlines

A string, a tuple of strings, or *None*, indicating the newlines translated so far. Depending on the implementation and the initial constructor flags, this may not be available.

buffer

The underlying binary buffer (a *BufferedIOBase* instance) that *TextIOBase* deals with. This is not part of the *TextIOBase* API and may not exist on some implementations.

detach()

Separate the underlying binary buffer from the `TextIOBase` and return it.

After the underlying buffer has been detached, the `TextIOBase` is in an unusable state.

Some `TextIOBase` implementations, like `StringIO`, may not have the concept of an underlying buffer and calling this method will raise `UnsupportedOperation`.

버전 2.7에 추가.

read(n=-1)

Read and return at most *n* characters from the stream as a single `unicode`. If *n* is negative or `None`, reads until EOF.

readline(limit=-1)

Read until newline or EOF and return a single `unicode`. If the stream is already at EOF, an empty string is returned.

If *limit* is specified, at most *limit* characters will be read.

seek(offset, whence=SEEK_SET)

Change the stream position to the given *offset*. Behaviour depends on the *whence* parameter. The default value for *whence* is `SEEK_SET`.

- `SEEK_SET` or 0: seek from the start of the stream (the default); *offset* must either be a number returned by `TextIOBase.tell()`, or zero. Any other *offset* value produces undefined behaviour.
- `SEEK_CUR` or 1: 《seek》 to the current position; *offset* must be zero, which is a no-operation (all other values are unsupported).
- `SEEK_END` or 2: seek to the end of the stream; *offset* must be zero (all other values are unsupported).

Return the new absolute position as an opaque number.

버전 2.7에 추가: The `SEEK_*` constants.

tell()

Return the current stream position as an opaque number. The number does not usually represent a number of bytes in the underlying binary storage.

write(s)

Write the `unicode` string *s* to the stream and return the number of characters written.

class io.TextIOWrapper(buffer, encoding=None, errors=None, newline=None, line_buffering=False)

A buffered text stream over a `BufferedIOBase` binary stream. It inherits `TextIOBase`.

encoding gives the name of the encoding that the stream will be decoded or encoded with. It defaults to `locale.getpreferredencoding()`.

errors is an optional string that specifies how encoding and decoding errors are to be handled. Pass `'strict'` to raise a `ValueError` exception if there is an encoding error (the default of `None` has the same effect), or pass `'ignore'` to ignore errors. (Note that ignoring encoding errors can lead to data loss.) `'replace'` causes a replacement marker (such as `'?'`) to be inserted where there is malformed data. When writing, `'xmlcharrefreplace'` (replace with the appropriate XML character reference) or `'backslashreplace'` (replace with backslashed escape sequences) can be used. Any other error handling name that has been registered with `codecs.register_error()` is also valid.

newline controls how line endings are handled. It can be `None`, `''`, `'\n'`, `'\r'`, and `'\r\n'`. It works as follows:

- On input, if *newline* is `None`, *universal newlines* mode is enabled. Lines in the input can end in `'\n'`, `'\r'`, or `'\r\n'`, and these are translated into `'\n'` before being returned to the caller. If it is `''`, universal newlines mode is enabled, but line endings are returned to the caller untranslated. If it has any of the other

legal values, input lines are only terminated by the given string, and the line ending is returned to the caller untranslated.

- On output, if *newline* is `None`, any `'\n'` characters written are translated to the system default line separator, `os.linesep`. If *newline* is `' '`, no translation takes place. If *newline* is any of the other legal values, any `'\n'` characters written are translated to the given string.

If *line_buffering* is `True`, `flush()` is implied when a call to write contains a newline character or a carriage return.

`TextIOWrapper` provides one attribute in addition to those of `TextIOBase` and its parents:

line_buffering

Whether line buffering is enabled.

class `io.StringIO` (*initial_value*=`u''`, *newline*=`u'\n'`)

An in-memory stream for unicode text. It inherits `TextIOWrapper`.

The initial value of the buffer can be set by providing *initial_value*. If newline translation is enabled, newlines will be encoded as if by `write()`. The stream is positioned at the start of the buffer.

The *newline* argument works like that of `TextIOWrapper`. The default is to consider only `\n` characters as ends of lines and to do no newline translation. If *newline* is set to `None`, newlines are written as `\n` on all platforms, but universal newline decoding is still performed when reading.

`StringIO` provides this method in addition to those from `TextIOWrapper` and its parents:

getvalue()

Return a unicode containing the entire contents of the buffer at any time before the `StringIO` object's `close()` method is called. Newlines are decoded as if by `read()`, although the stream position is not changed.

Example usage:

```
import io

output = io.StringIO()
output.write(u'First line.\n')
output.write(u'Second line.\n')

# Retrieve file contents -- this will be
# u'First line.\nSecond line.\n'
contents = output.getvalue()

# Close object and discard memory buffer --
# .getvalue() will now raise an exception.
output.close()
```

class `io.IncrementalNewlineDecoder`

A helper codec that decodes newlines for *universal newlines* mode. It inherits `codecs.IncrementalDecoder`.

15.2.6 Advanced topics

Here we will discuss several advanced topics pertaining to the concrete I/O implementations described above.

Performance

Binary I/O

By reading and writing only large chunks of data even when the user asks for a single byte, buffered I/O is designed to hide any inefficiency in calling and executing the operating system's unbuffered I/O routines. The gain will vary very much depending on the OS and the kind of I/O which is performed (for example, on some contemporary OSes such as Linux, unbuffered disk I/O can be as fast as buffered I/O). The bottom line, however, is that buffered I/O will offer you predictable performance regardless of the platform and the backing device. Therefore, it is most always preferable to use buffered I/O rather than unbuffered I/O.

Text I/O

Text I/O over a binary storage (such as a file) is significantly slower than binary I/O over the same storage, because it implies conversions from unicode to binary data using a character codec. This can become noticeable if you handle huge amounts of text data (for example very large log files). Also, `TextIOWrapper.tell()` and `TextIOWrapper.seek()` are both quite slow due to the reconstruction algorithm used.

StringIO, however, is a native in-memory unicode container and will exhibit similar speed to *BytesIO*.

Multi-threading

FileIO objects are thread-safe to the extent that the operating system calls (such as `read(2)` under Unix) they are wrapping are thread-safe too.

Binary buffered objects (instances of *BufferedReader*, *BufferedWriter*, *BufferedRandom* and *BufferedRWPair*) protect their internal structures using a lock; it is therefore safe to call them from multiple threads at once.

TextIOWrapper objects are not thread-safe.

Reentrancy

Binary buffered objects (instances of *BufferedReader*, *BufferedWriter*, *BufferedRandom* and *BufferedRWPair*) are not reentrant. While reentrant calls will not happen in normal situations, they can arise if you are doing I/O in a *signal* handler. If it is attempted to enter a buffered object again while already being accessed *from the same thread*, then a *RuntimeError* is raised.

The above implicitly extends to text files, since the `open()` function will wrap a buffered object inside a *TextIOWrapper*. This includes standard streams and therefore affects the built-in function `print()` as well.

15.3 `time` — Time access and conversions

This module provides various time-related functions. For related functionality, see also the `datetime` and `calendar` modules.

Although this module is always available, not all functions are available on all platforms. Most of the functions defined in this module call platform C library functions with the same name. It may sometimes be helpful to consult the platform documentation, because the semantics of these functions varies among platforms.

An explanation of some terminology and conventions is in order.

- The *epoch* is the point where the time starts. On January 1st of that year, at 0 hours, the «time since the epoch» is zero. For Unix, the epoch is 1970. To find out what the epoch is, look at `gmtime(0)`.
- The functions in this module do not handle dates and times before the epoch or far in the future. The cut-off point in the future is determined by the C library; for Unix, it is typically in 2038.
- **Year 2000 (Y2K) issues:** Python depends on the platform's C library, which generally doesn't have year 2000 issues, since all dates and times are represented internally as seconds since the epoch. Functions accepting a `struct_time` (see below) generally require a 4-digit year. For backward compatibility, 2-digit years are supported if the module variable `accept2dyear` is a non-zero integer; this variable is initialized to 1 unless the environment variable `PYTHONY2K` is set to a non-empty string, in which case it is initialized to 0. Thus, you can set `PYTHONY2K` to a non-empty string in the environment to require 4-digit years for all year input. When 2-digit years are accepted, they are converted according to the POSIX or X/Open standard: values 69-99 are mapped to 1969-1999, and values 0-68 are mapped to 2000-2068. Values 100-1899 are always illegal.
- UTC is Coordinated Universal Time (formerly known as Greenwich Mean Time, or GMT). The acronym UTC is not a mistake but a compromise between English and French.
- DST is Daylight Saving Time, an adjustment of the timezone by (usually) one hour during part of the year. DST rules are magic (determined by local law) and can change from year to year. The C library has a table containing the local rules (often it is read from a system file for flexibility) and is the only source of True Wisdom in this respect.
- The precision of the various real-time functions may be less than suggested by the units in which their value or argument is expressed. E.g. on most Unix systems, the clock «ticks» only 50 or 100 times a second.
- On the other hand, the precision of `time()` and `sleep()` is better than their Unix equivalents: times are expressed as floating point numbers, `time()` returns the most accurate time available (using `gettimeofday()` where available), and `sleep()` will accept a time with a nonzero fraction (Unix `select()` is used to implement this, where available).
- The time value as returned by `gmtime()`, `localtime()`, and `strptime()`, and accepted by `asctime()`, `mktime()` and `strftime()`, may be considered as a sequence of 9 integers. The return values of `gmtime()`, `localtime()`, and `strptime()` also offer attribute names for individual fields.

See `struct_time` for a description of these objects.

버전 2.2에서 변경: The time value sequence was changed from a tuple to a `struct_time`, with the addition of attribute names for the fields.

- Use the following functions to convert between time representations:

From	To	Use
seconds since the epoch	<code>struct_time</code> in UTC	<code>gmtime()</code>
seconds since the epoch	<code>struct_time</code> in local time	<code>localtime()</code>
<code>struct_time</code> in UTC	seconds since the epoch	<code>calendar.timegm()</code>
<code>struct_time</code> in local time	seconds since the epoch	<code>mktime()</code>

The module defines the following functions and data items:

time.accept2dayear

Boolean value indicating whether two-digit year values will be accepted. This is true by default, but will be set to false if the environment variable `PYTHONY2K` has been set to a non-empty string. It may also be modified at run time.

time.altzone

The offset of the local DST timezone, in seconds west of UTC, if one is defined. This is negative if the local DST timezone is east of UTC (as in Western Europe, including the UK). Only use this if `daylight` is nonzero.

time.asctime([t])

Convert a tuple or *struct_time* representing a time as returned by *gmtime()* or *localtime()* to a 24-character string of the following form: 'Sun Jun 20 23:21:05 1993'. If *t* is not provided, the current time as returned by *localtime()* is used. Locale information is not used by *asctime()*.

참고: Unlike the C function of the same name, there is no trailing newline.

버전 2.1에서 변경: Allowed *t* to be omitted.

time.clock()

On Unix, return the current processor time as a floating point number expressed in seconds. The precision, and in fact the very definition of the meaning of ‘processor time’, depends on that of the C function of the same name, but in any case, this is the function to use for benchmarking Python or timing algorithms.

On Windows, this function returns wall-clock seconds elapsed since the first call to this function, as a floating point number, based on the Win32 function `QueryPerformanceCounter()`. The resolution is typically better than one microsecond.

time.ctime([secs])

Convert a time expressed in seconds since the epoch to a string representing local time. If *secs* is not provided or *None*, the current time as returned by *time()* is used. *ctime(secs)* is equivalent to *asctime(localtime(secs))*. Locale information is not used by *ctime()*.

버전 2.1에서 변경: Allowed *secs* to be omitted.

버전 2.4에서 변경: If *secs* is *None*, the current time is used.

time.daylight

Nonzero if a DST timezone is defined.

time.gmtime([secs])

Convert a time expressed in seconds since the epoch to a *struct_time* in UTC in which the dst flag is always zero. If *secs* is not provided or *None*, the current time as returned by *time()* is used. Fractions of a second are ignored. See above for a description of the *struct_time* object. See *calendar.timegm()* for the inverse of this function.

버전 2.1에서 변경: Allowed *secs* to be omitted.

버전 2.4에서 변경: If *secs* is *None*, the current time is used.

time.localtime([secs])

Like *gmtime()* but converts to local time. If *secs* is not provided or *None*, the current time as returned by *time()* is used. The dst flag is set to 1 when DST applies to the given time.

버전 2.1에서 변경: Allowed *secs* to be omitted.

버전 2.4에서 변경: If *secs* is *None*, the current time is used.

time.mktime(t)

This is the inverse function of *localtime()*. Its argument is the *struct_time* or full 9-tuple (since the dst

flag is needed; use `-1` as the dst flag if it is unknown) which expresses the time in *local* time, not UTC. It returns a floating point number, for compatibility with `time()`. If the input value cannot be represented as a valid time, either `OverflowError` or `ValueError` will be raised (which depends on whether the invalid value is caught by Python or the underlying C libraries). The earliest date for which it can generate a time is platform-dependent.

`time.sleep(secs)`

Suspend execution of the current thread for the given number of seconds. The argument may be a floating point number to indicate a more precise sleep time. The actual suspension time may be less than that requested because any caught signal will terminate the `sleep()` following execution of that signal's catching routine. Also, the suspension time may be longer than requested by an arbitrary amount because of the scheduling of other activity in the system.

`time.strftime(format[, t])`

Convert a tuple or `struct_time` representing a time as returned by `gmtime()` or `localtime()` to a string as specified by the `format` argument. If `t` is not provided, the current time as returned by `localtime()` is used. `format` must be a string. `ValueError` is raised if any field in `t` is outside of the allowed range. `strftime()` returns a locale dependent byte string; the result may be converted to unicode by doing `strftime(<myformat>).decode(locale.getlocale()[1])`.

버전 2.1에서 변경: Allowed `t` to be omitted.

버전 2.4에서 변경: `ValueError` raised if a field in `t` is out of range.

버전 2.5에서 변경: 0 is now a legal argument for any position in the time tuple; if it is normally illegal the value is forced to a correct one.

The following directives can be embedded in the `format` string. They are shown without the optional field width and precision specification, and are replaced by the indicated characters in the `strftime()` result:

Directive	Meaning	Notes
%a	Locale's abbreviated weekday name.	
%A	Locale's full weekday name.	
%b	Locale's abbreviated month name.	
%B	Locale's full month name.	
%c	Locale's appropriate date and time representation.	
%d	Day of the month as a decimal number [01,31].	
%H	Hour (24-hour clock) as a decimal number [00,23].	
%I	Hour (12-hour clock) as a decimal number [01,12].	
%j	Day of the year as a decimal number [001,366].	
%m	Month as a decimal number [01,12].	
%M	Minute as a decimal number [00,59].	
%p	Locale's equivalent of either AM or PM.	(1)
%S	Second as a decimal number [00,61].	(2)
%U	Week number of the year (Sunday as the first day of the week) as a decimal number [00,53]. All days in a new year preceding the first Sunday are considered to be in week 0.	(3)
%w	Weekday as a decimal number [0(Sunday),6].	
%W	Week number of the year (Monday as the first day of the week) as a decimal number [00,53]. All days in a new year preceding the first Monday are considered to be in week 0.	(3)
%x	Locale's appropriate date representation.	
%X	Locale's appropriate time representation.	
%y	Year without century as a decimal number [00,99].	
%Y	Year with century as a decimal number.	
%Z	Time zone name (no characters if no time zone exists).	
%%	A literal '%' character.	

Notes:

- (1) When used with the `strptime()` function, the `%p` directive only affects the output hour field if the `%I` directive is used to parse the hour.
- (2) The range really is 0 to 61; this accounts for leap seconds and the (very rare) double leap seconds.
- (3) When used with the `strptime()` function, `%U` and `%W` are only used in calculations when the day of the week and the year are specified.

Here is an example, a format for dates compatible with that specified in the [RFC 2822](#) Internet email standard.¹

```
>>> from time import gmtime, strftime
>>> strftime("%a, %d %b %Y %H:%M:%S +0000", gmtime())
'Thu, 28 Jun 2001 14:17:15 +0000'
```

Additional directives may be supported on certain platforms, but only the ones listed here have a meaning standardized by ANSI C. To see the full set of format codes supported on your platform, consult the `strftime(3)` documentation.

On some platforms, an optional field width and precision specification can immediately follow the initial `'%'` of a directive in the following order; this is also not portable. The field width is normally 2 except for `%j` where it is 3.

`time.strptime(string[, format])`

Parse a string representing a time according to a format. The return value is a `struct_time` as returned by `gmtime()` or `localtime()`.

The `format` parameter uses the same directives as those used by `strftime()`; it defaults to `"%a %b %d %H:%M:%S %Y"` which matches the formatting returned by `ctime()`. If `string` cannot be parsed according to `format`, or if it has excess data after parsing, `ValueError` is raised. The default values used to fill in any missing data when more accurate values cannot be inferred are `(1900, 1, 1, 0, 0, 0, 0, 1, -1)`.

For example:

```
>>> import time
>>> time.strptime("30 Nov 00", "%d %b %y")
time.struct_time(tm_year=2000, tm_mon=11, tm_mday=30, tm_hour=0, tm_min=0,
                  tm_sec=0, tm_wday=3, tm_yday=335, tm_isdst=-1)
```

Support for the `%Z` directive is based on the values contained in `tzname` and whether `daylight` is true. Because of this, it is platform-specific except for recognizing UTC and GMT which are always known (and are considered to be non-daylight savings timezones).

Only the directives specified in the documentation are supported. Because `strftime()` is implemented per platform it can sometimes offer more directives than those listed. But `strptime()` is independent of any platform and thus does not necessarily support all directives available that are not documented as supported.

class `time.struct_time`

The type of the time value sequence returned by `gmtime()`, `localtime()`, and `strptime()`. It is an object with a *named tuple* interface: values can be accessed by index and by attribute name. The following values are present:

¹ The use of `%Z` is now deprecated, but the `%z` escape that expands to the preferred hour/minute offset is not supported by all ANSI C libraries. Also, a strict reading of the original 1982 [RFC 822](#) standard calls for a two-digit year (`%y` rather than `%Y`), but practice moved to 4-digit years long before the year 2000. After that, [RFC 822](#) became obsolete and the 4-digit year has been first recommended by [RFC 1123](#) and then mandated by [RFC 2822](#).

Index	Attribute	Values
0	tm_year	(for example, 1993)
1	tm_mon	range [1, 12]
2	tm_mday	range [1, 31]
3	tm_hour	range [0, 23]
4	tm_min	range [0, 59]
5	tm_sec	range [0, 61]; see (2) in <code>strptime()</code> description
6	tm_wday	range [0, 6], Monday is 0
7	tm_yday	range [1, 366]
8	tm_isdst	0, 1 or -1; see below

버전 2.2에 추가.

Note that unlike the C structure, the month value is a range of [1, 12], not [0, 11]. A year value will be handled as described under *Year 2000 (Y2K) issues* above.

In calls to `mktime()`, `tm_isdst` may be set to 1 when daylight savings time is in effect, and 0 when it is not. A value of -1 indicates that this is not known, and will usually result in the correct state being filled in.

When a tuple with an incorrect length is passed to a function expecting a `struct_time`, or having elements of the wrong type, a `TypeError` is raised.

`time.time()`

Return the time in seconds since the epoch as a floating point number. Note that even though the time is always returned as a floating point number, not all systems provide time with a better precision than 1 second. While this function normally returns non-decreasing values, it can return a lower value than a previous call if the system clock has been set back between the two calls.

`time.timezone`

The offset of the local (non-DST) timezone, in seconds west of UTC (negative in most of Western Europe, positive in the US, zero in the UK).

`time.tzname`

A tuple of two strings: the first is the name of the local non-DST timezone, the second is the name of the local DST timezone. If no DST timezone is defined, the second string should not be used.

`time.tzset()`

Reset the time conversion rules used by the library routines. The environment variable `TZ` specifies how this is done. It will also set the variables `tzname` (from the `TZ` environment variable), `timezone` (non-DST seconds West of UTC), `altzone` (DST seconds west of UTC) and `daylight` (to 0 if this timezone does not have any daylight saving time rules, or to nonzero if there is a time, past, present or future when daylight saving time applies).

버전 2.3에 추가.

Availability: Unix.

참고: Although in many cases, changing the `TZ` environment variable may affect the output of functions like `localtime()` without calling `tzset()`, this behavior should not be relied on.

The `TZ` environment variable should contain no whitespace.

The standard format of the `TZ` environment variable is (whitespace added for clarity):

```
std offset [dst [offset [,start[/time], end[/time]]]]
```

Where the components are:

std and dst Three or more alphanumerics giving the timezone abbreviations. These will be propagated into `time.tzname`

offset The offset has the form: $\pm hh[:mm[:ss]]$. This indicates the value added the local time to arrive at UTC. If preceded by a $\langle - \rangle$, the timezone is east of the Prime Meridian; otherwise, it is west. If no offset follows **dst**, summer time is assumed to be one hour ahead of standard time.

start[/time], end[/time] Indicates when to change to and back from DST. The format of the start and end dates are one of the following:

Jn The Julian day n ($1 \leq n \leq 365$). Leap days are not counted, so in all years February 28 is day 59 and March 1 is day 60.

n The zero-based Julian day ($0 \leq n \leq 365$). Leap days are counted, and it is possible to refer to February 29.

Mm.n.d The d 'th day ($0 \leq d \leq 6$) or week n of month m of the year ($1 \leq n \leq 5$, $1 \leq m \leq 12$, where week 5 means «the last d day in month m » which may occur in either the fourth or the fifth week). Week 1 is the first week in which the d 'th day occurs. Day zero is Sunday.

`time` has the same format as `offset` except that no leading sign ($\langle - \rangle$ or $\langle + \rangle$) is allowed. The default, if `time` is not given, is 02:00:00.

```
>>> os.environ['TZ'] = 'EST+05EDT,M4.1.0,M10.5.0'
>>> time.tzset()
>>> time.strftime('%X %x %Z')
'02:07:36 05/08/03 EDT'
>>> os.environ['TZ'] = 'AEST-10AEDT-11,M10.5.0,M3.5.0'
>>> time.tzset()
>>> time.strftime('%X %x %Z')
'16:08:12 05/08/03 AEST'
```

On many Unix systems (including *BSD, Linux, Solaris, and Darwin), it is more convenient to use the system's `zoneinfo` (`tzfile(5)`) database to specify the timezone rules. To do this, set the `TZ` environment variable to the path of the required timezone datafile, relative to the root of the systems `zoneinfo` timezone database, usually located at `/usr/share/zoneinfo`. For example, `'US/Eastern'`, `'Australia/Melbourne'`, `'Egypt'` or `'Europe/Amsterdam'`.

```
>>> os.environ['TZ'] = 'US/Eastern'
>>> time.tzset()
>>> time.tzname
('EST', 'EDT')
>>> os.environ['TZ'] = 'Egypt'
>>> time.tzset()
>>> time.tzname
('EET', 'EEST')
```

더 보기:

Module `datetime` More object-oriented interface to dates and times.

Module `locale` Internationalization services. The locale setting affects the interpretation of many format specifiers in `strftime()` and `strptime()`.

Module `calendar` General calendar-related functions. `timegm()` is the inverse of `gmtime()` from this module.

15.4 argparse — Parser for command-line options, arguments and sub-commands

버전 2.7에 추가.

Source code: [Lib/argparse.py](#)

Tutorial

This page contains the API reference information. For a more gentle introduction to Python command-line parsing, have a look at the [argparse tutorial](#).

The `argparse` module makes it easy to write user-friendly command-line interfaces. The program defines what arguments it requires, and `argparse` will figure out how to parse those out of `sys.argv`. The `argparse` module also automatically generates help and usage messages and issues errors when users give the program invalid arguments.

15.4.1 Example

The following code is a Python program that takes a list of integers and produces either the sum or the max:

```
import argparse

parser = argparse.ArgumentParser(description='Process some integers.')
parser.add_argument('integers', metavar='N', type=int, nargs='+',
                    help='an integer for the accumulator')
parser.add_argument('--sum', dest='accumulate', action='store_const',
                    const=sum, default=max,
                    help='sum the integers (default: find the max)')

args = parser.parse_args()
print args.accumulate(args.integers)
```

Assuming the Python code above is saved into a file called `prog.py`, it can be run at the command line and provides useful help messages:

```
$ python prog.py -h
usage: prog.py [-h] [--sum] N [N ...]

Process some integers.

positional arguments:
  N                an integer for the accumulator

optional arguments:
  -h, --help      show this help message and exit
  --sum           sum the integers (default: find the max)
```

When run with the appropriate arguments, it prints either the sum or the max of the command-line integers:

```
$ python prog.py 1 2 3 4
4
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
$ python prog.py 1 2 3 4 --sum
10
```

If invalid arguments are passed in, it will issue an error:

```
$ python prog.py a b c
usage: prog.py [-h] [--sum] N [N ...]
prog.py: error: argument N: invalid int value: 'a'
```

The following sections walk you through this example.

Creating a parser

The first step in using the *argparse* is creating an *ArgumentParser* object:

```
>>> parser = argparse.ArgumentParser(description='Process some integers.')
```

The *ArgumentParser* object will hold all the information necessary to parse the command line into Python data types.

Adding arguments

Filling an *ArgumentParser* with information about program arguments is done by making calls to the *add_argument()* method. Generally, these calls tell the *ArgumentParser* how to take the strings on the command line and turn them into objects. This information is stored and used when *parse_args()* is called. For example:

```
>>> parser.add_argument('integers', metavar='N', type=int, nargs='+',
...                     help='an integer for the accumulator')
>>> parser.add_argument('--sum', dest='accumulate', action='store_const',
...                     const=sum, default=max,
...                     help='sum the integers (default: find the max)')
```

Later, calling *parse_args()* will return an object with two attributes, *integers* and *accumulate*. The *integers* attribute will be a list of one or more ints, and the *accumulate* attribute will be either the *sum()* function, if *--sum* was specified at the command line, or the *max()* function if it was not.

Parsing arguments

ArgumentParser parses arguments through the *parse_args()* method. This will inspect the command line, convert each argument to the appropriate type and then invoke the appropriate action. In most cases, this means a simple *Namespace* object will be built up from attributes parsed out of the command line:

```
>>> parser.parse_args(['--sum', '7', '-1', '42'])
Namespace(accumulate=<built-in function sum>, integers=[7, -1, 42])
```

In a script, *parse_args()* will typically be called with no arguments, and the *ArgumentParser* will automatically determine the command-line arguments from *sys.argv*.

15.4.2 ArgumentParser objects

class `argparse.ArgumentParser` (*prog=None, usage=None, description=None, epilog=None, parents=[], formatter_class=argparse.HelpFormatter, prefix_chars='-', fromfile_prefix_chars=None, argument_default=None, conflict_handler='error', add_help=True*)

Create a new *ArgumentParser* object. All parameters should be passed as keyword arguments. Each parameter has its own more detailed description below, but in short they are:

- *prog* - The name of the program (default: `sys.argv[0]`)
- *usage* - The string describing the program usage (default: generated from arguments added to parser)
- *description* - Text to display before the argument help (default: none)
- *epilog* - Text to display after the argument help (default: none)
- *parents* - A list of *ArgumentParser* objects whose arguments should also be included
- *formatter_class* - A class for customizing the help output
- *prefix_chars* - The set of characters that prefix optional arguments (default: `<->`)
- *fromfile_prefix_chars* - The set of characters that prefix files from which additional arguments should be read (default: None)
- *argument_default* - The global default value for arguments (default: None)
- *conflict_handler* - The strategy for resolving conflicting optionals (usually unnecessary)
- *add_help* - Add a `-h/--help` option to the parser (default: True)

The following sections describe how each of these are used.

prog

By default, *ArgumentParser* objects use `sys.argv[0]` to determine how to display the name of the program in help messages. This default is almost always desirable because it will make the help messages match how the program was invoked on the command line. For example, consider a file named `myprogram.py` with the following code:

```
import argparse
parser = argparse.ArgumentParser()
parser.add_argument('--foo', help='foo help')
args = parser.parse_args()
```

The help for this program will display `myprogram.py` as the program name (regardless of where the program was invoked from):

```
$ python myprogram.py --help
usage: myprogram.py [-h] [--foo FOO]

optional arguments:
  -h, --help  show this help message and exit
  --foo FOO   foo help
$ cd ..
$ python subdir/myprogram.py --help
usage: myprogram.py [-h] [--foo FOO]

optional arguments:
  -h, --help  show this help message and exit
  --foo FOO   foo help
```

To change this default behavior, another value can be supplied using the `prog=` argument to *ArgumentParser*:

```
>>> parser = argparse.ArgumentParser(prog='myprogram')
>>> parser.print_help()
usage: myprogram [-h]

optional arguments:
  -h, --help  show this help message and exit
```

Note that the program name, whether determined from `sys.argv[0]` or from the `prog=` argument, is available to help messages using the `%(prog)s` format specifier.

```
>>> parser = argparse.ArgumentParser(prog='myprogram')
>>> parser.add_argument('--foo', help='foo of the %(prog)s program')
>>> parser.print_help()
usage: myprogram [-h] [--foo FOO]

optional arguments:
  -h, --help  show this help message and exit
  --foo FOO   foo of the myprogram program
```

usage

By default, *ArgumentParser* calculates the usage message from the arguments it contains:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('--foo', nargs='?', help='foo help')
>>> parser.add_argument('bar', nargs='+', help='bar help')
>>> parser.print_help()
usage: PROG [-h] [--foo [FOO]] bar [bar ...]

positional arguments:
  bar                bar help

optional arguments:
  -h, --help  show this help message and exit
  --foo [FOO] foo help
```

The default message can be overridden with the `usage=` keyword argument:

```
>>> parser = argparse.ArgumentParser(prog='PROG', usage='%(prog)s [options]')
>>> parser.add_argument('--foo', nargs='?', help='foo help')
>>> parser.add_argument('bar', nargs='+', help='bar help')
>>> parser.print_help()
usage: PROG [options]

positional arguments:
  bar                bar help

optional arguments:
  -h, --help  show this help message and exit
  --foo [FOO] foo help
```

The `%(prog)s` format specifier is available to fill in the program name in your usage messages.

description

Most calls to the `ArgumentParser` constructor will use the `description=` keyword argument. This argument gives a brief description of what the program does and how it works. In help messages, the description is displayed between the command-line usage string and the help messages for the various arguments:

```
>>> parser = argparse.ArgumentParser(description='A foo that bars')
>>> parser.print_help()
usage: argparse.py [-h]

A foo that bars

optional arguments:
  -h, --help  show this help message and exit
```

By default, the description will be line-wrapped so that it fits within the given space. To change this behavior, see the `formatter_class` argument.

epilog

Some programs like to display additional description of the program after the description of the arguments. Such text can be specified using the `epilog=` argument to `ArgumentParser`:

```
>>> parser = argparse.ArgumentParser(
...     description='A foo that bars',
...     epilog="And that's how you'd foo a bar")
>>> parser.print_help()
usage: argparse.py [-h]

A foo that bars

optional arguments:
  -h, --help  show this help message and exit

And that's how you'd foo a bar
```

As with the `description` argument, the `epilog=` text is by default line-wrapped, but this behavior can be adjusted with the `formatter_class` argument to `ArgumentParser`.

parents

Sometimes, several parsers share a common set of arguments. Rather than repeating the definitions of these arguments, a single parser with all the shared arguments and passed to `parents=` argument to `ArgumentParser` can be used. The `parents=` argument takes a list of `ArgumentParser` objects, collects all the positional and optional actions from them, and adds these actions to the `ArgumentParser` object being constructed:

```
>>> parent_parser = argparse.ArgumentParser(add_help=False)
>>> parent_parser.add_argument('--parent', type=int)

>>> foo_parser = argparse.ArgumentParser(parents=[parent_parser])
>>> foo_parser.add_argument('foo')
>>> foo_parser.parse_args(['--parent', '2', 'XXX'])
Namespace(foo='XXX', parent=2)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> bar_parser = argparse.ArgumentParser(parents=[parent_parser])
>>> bar_parser.add_argument('--bar')
>>> bar_parser.parse_args(['--bar', 'YYY'])
Namespace(bar='YYY', parent=None)
```

Note that most parent parsers will specify `add_help=False`. Otherwise, the *ArgumentParser* will see two `-h/--help` options (one in the parent and one in the child) and raise an error.

참고: You must fully initialize the parsers before passing them via `parents=`. If you change the parent parsers after the child parser, those changes will not be reflected in the child.

formatter_class

ArgumentParser objects allow the help formatting to be customized by specifying an alternate formatting class. Currently, there are three such classes:

```
class argparse.RawDescriptionHelpFormatter
class argparse.RawTextHelpFormatter
class argparse.ArgumentDefaultsHelpFormatter
```

The first two allow more control over how textual descriptions are displayed, while the last automatically adds information about argument default values.

By default, *ArgumentParser* objects line-wrap the *description* and *epilog* texts in command-line help messages:

```
>>> parser = argparse.ArgumentParser(
...     prog='PROG',
...     description='''this description
...         was indented weird
...         but that is okay''',
...     epilog='''
...         likewise for this epilog whose whitespace will
...         be cleaned up and whose words will be wrapped
...         across a couple lines''')
>>> parser.print_help()
usage: PROG [-h]

this description was indented weird but that is okay

optional arguments:
  -h, --help  show this help message and exit

likewise for this epilog whose whitespace will be cleaned up and whose words
will be wrapped across a couple lines
```

Passing *RawDescriptionHelpFormatter* as `formatter_class=` indicates that *description* and *epilog* are already correctly formatted and should not be line-wrapped:

```
>>> parser = argparse.ArgumentParser(
...     prog='PROG',
...     formatter_class=argparse.RawDescriptionHelpFormatter,
...     description=textwrap.dedent('''\
...         Please do not mess up this text!
...         -----
...     '''))
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

...         I have indented it
...         exactly the way
...         I want it
...     '''))
>>> parser.print_help()
usage: PROG [-h]

Please do not mess up this text!
-----
    I have indented it
    exactly the way
    I want it

optional arguments:
  -h, --help  show this help message and exit

```

RawTextHelpFormatter maintains whitespace for all sorts of help text, including argument descriptions. However, multiple new lines are replaced with one. If you wish to preserve multiple blank lines, add spaces between the newlines.

The other formatter class available, *ArgumentDefaultsHelpFormatter*, will add information about the default value of each of the arguments:

```

>>> parser = argparse.ArgumentParser(
...     prog='PROG',
...     formatter_class=argparse.ArgumentDefaultsHelpFormatter)
>>> parser.add_argument('--foo', type=int, default=42, help='FOO!')
>>> parser.add_argument('bar', nargs='*', default=[1, 2, 3], help='BAR!')
>>> parser.print_help()
usage: PROG [-h] [--foo FOO] [bar [bar ...]]

positional arguments:
  bar          BAR! (default: [1, 2, 3])

optional arguments:
  -h, --help  show this help message and exit
  --foo FOO   FOO! (default: 42)

```

prefix_chars

Most command-line options will use `-` as the prefix, e.g. `-f/--foo`. Parsers that need to support different or additional prefix characters, e.g. for options like `+f` or `/foo`, may specify them using the `prefix_chars=` argument to the `ArgumentParser` constructor:

```

>>> parser = argparse.ArgumentParser(prog='PROG', prefix_chars='+-')
>>> parser.add_argument('+f')
>>> parser.add_argument('++bar')
>>> parser.parse_args('+f X ++bar Y'.split())
Namespace(bar='Y', f='X')

```

The `prefix_chars=` argument defaults to `'-'`. Supplying a set of characters that does not include `-` will cause `-f/--foo` options to be disallowed.

fromfile_prefix_chars

Sometimes, for example when dealing with a particularly long argument lists, it may make sense to keep the list of arguments in a file rather than typing it out at the command line. If the `fromfile_prefix_chars=` argument is given to the `ArgumentParser` constructor, then arguments that start with any of the specified characters will be treated as files, and will be replaced by the arguments they contain. For example:

```
>>> with open('args.txt', 'w') as fp:
...     fp.write('-f\nbar')
>>> parser = argparse.ArgumentParser(fromfile_prefix_chars='@')
>>> parser.add_argument('-f')
>>> parser.parse_args(['-f', 'foo', '@args.txt'])
Namespace(f='bar')
```

Arguments read from a file must by default be one per line (but see also `convert_arg_line_to_args()`) and are treated as if they were in the same place as the original file referencing argument on the command line. So in the example above, the expression `['-f', 'foo', '@args.txt']` is considered equivalent to the expression `['-f', 'foo', '-f', 'bar']`.

The `fromfile_prefix_chars=` argument defaults to `None`, meaning that arguments will never be treated as file references.

argument_default

Generally, argument defaults are specified either by passing a default to `add_argument()` or by calling the `set_defaults()` methods with a specific set of name-value pairs. Sometimes however, it may be useful to specify a single parser-wide default for arguments. This can be accomplished by passing the `argument_default=` keyword argument to `ArgumentParser`. For example, to globally suppress attribute creation on `parse_args()` calls, we supply `argument_default=SUPPRESS`:

```
>>> parser = argparse.ArgumentParser(argument_default=argparse.SUPPRESS)
>>> parser.add_argument('--foo')
>>> parser.add_argument('bar', nargs='?')
>>> parser.parse_args(['--foo', '1', 'BAR'])
Namespace(bar='BAR', foo='1')
>>> parser.parse_args([])
Namespace()
```

conflict_handler

`ArgumentParser` objects do not allow two actions with the same option string. By default, `ArgumentParser` objects raise an exception if an attempt is made to create an argument with an option string that is already in use:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('-f', '--foo', help='old foo help')
>>> parser.add_argument('--foo', help='new foo help')
Traceback (most recent call last):
...
ArgumentError: argument --foo: conflicting option string(s): --foo
```

Sometimes (e.g. when using `parents`) it may be useful to simply override any older arguments with the same option string. To get this behavior, the value `'resolve'` can be supplied to the `conflict_handler=` argument of `ArgumentParser`:

```
>>> parser = argparse.ArgumentParser(prog='PROG', conflict_handler='resolve')
>>> parser.add_argument('-f', '--foo', help='old foo help')
>>> parser.add_argument('--foo', help='new foo help')
>>> parser.print_help()
usage: PROG [-h] [-f FOO] [--foo FOO]

optional arguments:
  -h, --help  show this help message and exit
  -f FOO      old foo help
  --foo FOO   new foo help
```

Note that `ArgumentParser` objects only remove an action if all of its option strings are overridden. So, in the example above, the old `-f/--foo` action is retained as the `-f` action, because only the `--foo` option string was overridden.

add_help

By default, `ArgumentParser` objects add an option which simply displays the parser's help message. For example, consider a file named `myprogram.py` containing the following code:

```
import argparse
parser = argparse.ArgumentParser()
parser.add_argument('--foo', help='foo help')
args = parser.parse_args()
```

If `-h` or `--help` is supplied at the command line, the `ArgumentParser` help will be printed:

```
$ python myprogram.py --help
usage: myprogram.py [-h] [--foo FOO]

optional arguments:
  -h, --help  show this help message and exit
  --foo FOO   foo help
```

Occasionally, it may be useful to disable the addition of this help option. This can be achieved by passing `False` as the `add_help=` argument to `ArgumentParser`:

```
>>> parser = argparse.ArgumentParser(prog='PROG', add_help=False)
>>> parser.add_argument('--foo', help='foo help')
>>> parser.print_help()
usage: PROG [--foo FOO]

optional arguments:
  --foo FOO   foo help
```

The help option is typically `-h/--help`. The exception to this is if the `prefix_chars=` is specified and does not include `-`, in which case `-h` and `--help` are not valid options. In this case, the first character in `prefix_chars` is used to prefix the help options:

```
>>> parser = argparse.ArgumentParser(prog='PROG', prefix_chars='+/')
>>> parser.print_help()
usage: PROG [+h]

optional arguments:
  +h, ++help  show this help message and exit
```

15.4.3 The `add_argument()` method

`ArgumentParser.add_argument` (*name or flags...* [, *action*] [, *nargs*] [, *const*] [, *default*] [, *type*] [, *choices*] [, *required*] [, *help*] [, *metavar*] [, *dest*])

Define how a single command-line argument should be parsed. Each parameter has its own more detailed description below, but in short they are:

- *name or flags* - Either a name or a list of option strings, e.g. `foo` or `-f`, `--foo`.
- *action* - The basic type of action to be taken when this argument is encountered at the command line.
- *nargs* - The number of command-line arguments that should be consumed.
- *const* - A constant value required by some *action* and *nargs* selections.
- *default* - The value produced if the argument is absent from the command line.
- *type* - The type to which the command-line argument should be converted.
- *choices* - A container of the allowable values for the argument.
- *required* - Whether or not the command-line option may be omitted (optionals only).
- *help* - A brief description of what the argument does.
- *metavar* - A name for the argument in usage messages.
- *dest* - The name of the attribute to be added to the object returned by `parse_args()`.

The following sections describe how each of these are used.

name or flags

The `add_argument()` method must know whether an optional argument, like `-f` or `--foo`, or a positional argument, like a list of filenames, is expected. The first arguments passed to `add_argument()` must therefore be either a series of flags, or a simple argument name. For example, an optional argument could be created like:

```
>>> parser.add_argument('-f', '--foo')
```

while a positional argument could be created like:

```
>>> parser.add_argument('bar')
```

When `parse_args()` is called, optional arguments will be identified by the `-` prefix, and the remaining arguments will be assumed to be positional:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('-f', '--foo')
>>> parser.add_argument('bar')
>>> parser.parse_args(['BAR'])
Namespace(bar='BAR', foo=None)
>>> parser.parse_args(['BAR', '--foo', 'FOO'])
Namespace(bar='BAR', foo='FOO')
>>> parser.parse_args(['--foo', 'FOO'])
usage: PROG [-h] [-f FOO] bar
PROG: error: too few arguments
```

action

ArgumentParser objects associate command-line arguments with actions. These actions can do just about anything with the command-line arguments associated with them, though most actions simply add an attribute to the object returned by *parse_args()*. The *action* keyword argument specifies how the command-line arguments should be handled. The supplied actions are:

- 'store' - This just stores the argument's value. This is the default action. For example:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo')
>>> parser.parse_args('--foo 1'.split())
Namespace(foo='1')
```

- 'store_const' - This stores the value specified by the *const* keyword argument. The 'store_const' action is most commonly used with optional arguments that specify some sort of flag. For example:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', action='store_const', const=42)
>>> parser.parse_args(['--foo'])
Namespace(foo=42)
```

- 'store_true' and 'store_false' - These are special cases of 'store_const' using for storing the values True and False respectively. In addition, they create default values of False and True respectively. For example:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', action='store_true')
>>> parser.add_argument('--bar', action='store_false')
>>> parser.add_argument('--baz', action='store_false')
>>> parser.parse_args('--foo --bar'.split())
Namespace(bar=False, baz=True, foo=True)
```

- 'append' - This stores a list, and appends each argument value to the list. This is useful to allow an option to be specified multiple times. Example usage:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', action='append')
>>> parser.parse_args('--foo 1 --foo 2'.split())
Namespace(foo=['1', '2'])
```

- 'append_const' - This stores a list, and appends the value specified by the *const* keyword argument to the list. (Note that the *const* keyword argument defaults to None.) The 'append_const' action is typically useful when multiple arguments need to store constants to the same list. For example:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--str', dest='types', action='append_const', const=str)
>>> parser.add_argument('--int', dest='types', action='append_const', const=int)
>>> parser.parse_args('--str --int'.split())
Namespace(types=[<type 'str'>, <type 'int'>])
```

- 'count' - This counts the number of times a keyword argument occurs. For example, this is useful for increasing verbosity levels:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--verbose', '-v', action='count')
>>> parser.parse_args(['-vvv'])
Namespace(verbose=3)
```

- 'help' - This prints a complete help message for all the options in the current parser and then exits. By default a help action is automatically added to the parser. See [ArgumentParser](#) for details of how the output is created.
- 'version' - This expects a version= keyword argument in the `add_argument()` call, and prints version information and exits when invoked:

```
>>> import argparse
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('--version', action='version', version='%(prog)s 2.0')
>>> parser.parse_args(['--version'])
PROG 2.0
```

You may also specify an arbitrary action by passing an Action subclass or other object that implements the same interface. The recommended way to do this is to extend [Action](#), overriding the `__call__` method and optionally the `__init__` method.

An example of a custom action:

```
>>> class FooAction(argparse.Action):
...     def __init__(self, option_strings, dest, nargs=None, **kwargs):
...         if nargs is not None:
...             raise ValueError("nargs not allowed")
...         super(FooAction, self).__init__(option_strings, dest, **kwargs)
...     def __call__(self, parser, namespace, values, option_string=None):
...         print '%r %r %r' % (namespace, values, option_string)
...         setattr(namespace, self.dest, values)
...
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', action=FooAction)
>>> parser.add_argument('bar', action=FooAction)
>>> args = parser.parse_args('1 --foo 2'.split())
Namespace(bar=None, foo=None) '1' None
Namespace(bar='1', foo=None) '2' '--foo'
>>> args
Namespace(bar='1', foo='2')
```

For more details, see [Action](#).

nargs

`ArgumentParser` objects usually associate a single command-line argument with a single action to be taken. The `nargs` keyword argument associates a different number of command-line arguments with a single action. The supported values are:

- N (an integer). N arguments from the command line will be gathered together into a list. For example:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', nargs=2)
>>> parser.add_argument('bar', nargs=1)
>>> parser.parse_args('c --foo a b'.split())
Namespace(bar=['c'], foo=['a', 'b'])
```

Note that `nargs=1` produces a list of one item. This is different from the default, in which the item is produced by itself.

- '?'. One argument will be consumed from the command line if possible, and produced as a single item. If no command-line argument is present, the value from [default](#) will be produced. Note that for optional arguments,

there is an additional case - the option string is present but not followed by a command-line argument. In this case the value from `const` will be produced. Some examples to illustrate this:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', nargs='?', const='c', default='d')
>>> parser.add_argument('bar', nargs='?', default='d')
>>> parser.parse_args(['XX', '--foo', 'YY'])
Namespace(bar='XX', foo='YY')
>>> parser.parse_args(['XX', '--foo'])
Namespace(bar='XX', foo='c')
>>> parser.parse_args([])
Namespace(bar='d', foo='d')
```

One of the more common uses of `nargs='?'` is to allow optional input and output files:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('infile', nargs='?', type=argparse.FileType('r'),
...                     default=sys.stdin)
>>> parser.add_argument('outfile', nargs='?', type=argparse.FileType('w'),
...                     default=sys.stdout)
>>> parser.parse_args(['input.txt', 'output.txt'])
Namespace(infile=<open file 'input.txt', mode 'r' at 0x...>,
          outfile=<open file 'output.txt', mode 'w' at 0x...>)
>>> parser.parse_args([])
Namespace(infile=<open file '<stdin>', mode 'r' at 0x...>,
          outfile=<open file '<stdout>', mode 'w' at 0x...>)
```

- `'*'`. All command-line arguments present are gathered into a list. Note that it generally doesn't make much sense to have more than one positional argument with `nargs='*'`, but multiple optional arguments with `nargs='*'` is possible. For example:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', nargs='*')
>>> parser.add_argument('--bar', nargs='*')
>>> parser.add_argument('baz', nargs='*')
>>> parser.parse_args('a b --foo x y --bar 1 2'.split())
Namespace(bar=['1', '2'], baz=['a', 'b'], foo=['x', 'y'])
```

- `'+'`. Just like `'*'`, all command-line args present are gathered into a list. Additionally, an error message will be generated if there wasn't at least one command-line argument present. For example:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('foo', nargs='+')
>>> parser.parse_args(['a', 'b'])
Namespace(foo=['a', 'b'])
>>> parser.parse_args([])
usage: PROG [-h] foo [foo ...]
PROG: error: too few arguments
```

- `argparse.REMAINDER`. All the remaining command-line arguments are gathered into a list. This is commonly useful for command line utilities that dispatch to other command line utilities:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('--foo')
>>> parser.add_argument('command')
>>> parser.add_argument('args', nargs=argparse.REMAINDER)
>>> print parser.parse_args('--foo B cmd --arg1 XX ZZ'.split())
Namespace(args=['--arg1', 'XX', 'ZZ'], command='cmd', foo='B')
```


If the `nargs` keyword argument is not provided, the number of arguments consumed is determined by the *action*. Generally this means a single command-line argument will be consumed and a single item (not a list) will be produced.

const

The `const` argument of `add_argument()` is used to hold constant values that are not read from the command line but are required for the various *ArgumentParser* actions. The two most common uses of it are:

- When `add_argument()` is called with `action='store_const'` or `action='append_const'`. These actions add the `const` value to one of the attributes of the object returned by `parse_args()`. See the *action* description for examples.
- When `add_argument()` is called with option strings (like `-f` or `--foo`) and `nargs='?'`. This creates an optional argument that can be followed by zero or one command-line arguments. When parsing the command line, if the option string is encountered with no command-line argument following it, the value of `const` will be assumed instead. See the *nargs* description for examples.

With the `'store_const'` and `'append_const'` actions, the `const` keyword argument must be given. For other actions, it defaults to `None`.

default

All optional arguments and some positional arguments may be omitted at the command line. The `default` keyword argument of `add_argument()`, whose value defaults to `None`, specifies what value should be used if the command-line argument is not present. For optional arguments, the `default` value is used when the option string was not present at the command line:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', default=42)
>>> parser.parse_args(['--foo', '2'])
Namespace(foo='2')
>>> parser.parse_args([])
Namespace(foo=42)
```

If the `default` value is a string, the parser parses the value as if it were a command-line argument. In particular, the parser applies any *type* conversion argument, if provided, before setting the attribute on the *Namespace* return value. Otherwise, the parser uses the value as is:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--length', default='10', type=int)
>>> parser.add_argument('--width', default=10.5, type=int)
>>> parser.parse_args()
Namespace(length=10, width=10.5)
```

For positional arguments with *nargs* equal to `?` or `*`, the `default` value is used when no command-line argument was present:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('foo', nargs='?', default=42)
>>> parser.parse_args(['a'])
Namespace(foo='a')
>>> parser.parse_args([])
Namespace(foo=42)
```

Providing `default=argparse.SUPPRESS` causes no attribute to be added if the command-line argument was not present.:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', default=argparse.SUPPRESS)
>>> parser.parse_args([])
Namespace()
>>> parser.parse_args(['--foo', '1'])
Namespace(foo='1')
```

type

By default, *ArgumentParser* objects read command-line arguments in as simple strings. However, quite often the command-line string should instead be interpreted as another type, like a *float* or *int*. The *type* keyword argument of *add_argument()* allows any necessary type-checking and type conversions to be performed. Common built-in types and functions can be used directly as the value of the *type* argument:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('foo', type=int)
>>> parser.add_argument('bar', type=file)
>>> parser.parse_args('2 temp.txt'.split())
Namespace(bar=<open file 'temp.txt', mode 'r' at 0x...>, foo=2)
```

See the section on the *default* keyword argument for information on when the *type* argument is applied to default arguments.

To ease the use of various types of files, the *argparse* module provides the factory *FileType* which takes the *mode=* and *bufsize=* arguments of the file object. For example, *FileType('w')* can be used to create a writable file:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('bar', type=argparse.FileType('w'))
>>> parser.parse_args(['out.txt'])
Namespace(bar=<open file 'out.txt', mode 'w' at 0x...>)
```

type= can take any callable that takes a single string argument and returns the converted value:

```
>>> def perfect_square(string):
...     value = int(string)
...     sqrt = math.sqrt(value)
...     if sqrt != int(sqrt):
...         msg = "%r is not a perfect square" % string
...         raise argparse.ArgumentTypeError(msg)
...     return value
...
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('foo', type=perfect_square)
>>> parser.parse_args(['9'])
Namespace(foo=9)
>>> parser.parse_args(['7'])
usage: PROG [-h] foo
PROG: error: argument foo: '7' is not a perfect square
```

The *choices* keyword argument may be more convenient for type checkers that simply check against a range of values:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('foo', type=int, choices=xrange(5, 10))
>>> parser.parse_args(['7'])
Namespace(foo=7)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> parser.parse_args(['11'])
usage: PROG [-h] {5,6,7,8,9}
PROG: error: argument foo: invalid choice: 11 (choose from 5, 6, 7, 8, 9)
```

See the [choices](#) section for more details.

choices

Some command-line arguments should be selected from a restricted set of values. These can be handled by passing a container object as the *choices* keyword argument to [add_argument\(\)](#). When the command line is parsed, argument values will be checked, and an error message will be displayed if the argument was not one of the acceptable values:

```
>>> parser = argparse.ArgumentParser(prog='game.py')
>>> parser.add_argument('move', choices=['rock', 'paper', 'scissors'])
>>> parser.parse_args(['rock'])
Namespace(move='rock')
>>> parser.parse_args(['fire'])
usage: game.py [-h] {rock,paper,scissors}
game.py: error: argument move: invalid choice: 'fire' (choose from 'rock',
'paper', 'scissors')
```

Note that inclusion in the *choices* container is checked after any *type* conversions have been performed, so the type of the objects in the *choices* container should match the *type* specified:

```
>>> parser = argparse.ArgumentParser(prog='doors.py')
>>> parser.add_argument('door', type=int, choices=range(1, 4))
>>> print(parser.parse_args(['3']))
Namespace(door=3)
>>> parser.parse_args(['4'])
usage: doors.py [-h] {1,2,3}
doors.py: error: argument door: invalid choice: 4 (choose from 1, 2, 3)
```

Any object that supports the *in* operator can be passed as the *choices* value, so *dict* objects, *set* objects, custom containers, etc. are all supported.

required

In general, the *argparse* module assumes that flags like *-f* and *--bar* indicate *optional* arguments, which can always be omitted at the command line. To make an option *required*, *True* can be specified for the *required=* keyword argument to [add_argument\(\)](#):

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', required=True)
>>> parser.parse_args(['--foo', 'BAR'])
Namespace(foo='BAR')
>>> parser.parse_args([])
usage: argparse.py [-h] [--foo FOO]
argparse.py: error: option --foo is required
```

As the example shows, if an option is marked as *required*, [parse_args\(\)](#) will report an error if that option is not present at the command line.

참고: Required options are generally considered bad form because users expect *options* to be *optional*, and thus they should be avoided when possible.

help

The help value is a string containing a brief description of the argument. When a user requests help (usually by using `-h` or `--help` at the command line), these help descriptions will be displayed with each argument:

```
>>> parser = argparse.ArgumentParser(prog='frobble')
>>> parser.add_argument('--foo', action='store_true',
...                     help='foo the bars before frobbling')
>>> parser.add_argument('bar', nargs='+',
...                     help='one of the bars to be frobbled')
>>> parser.parse_args(['-h'])
usage: frobble [-h] [--foo] bar [bar ...]

positional arguments:
  bar                one of the bars to be frobbled

optional arguments:
  -h, --help        show this help message and exit
  --foo            foo the bars before frobbling
```

The help strings can include various format specifiers to avoid repetition of things like the program name or the argument *default*. The available specifiers include the program name, `%(prog)s` and most keyword arguments to `add_argument()`, e.g. `%(default)s`, `%(type)s`, etc.:

```
>>> parser = argparse.ArgumentParser(prog='frobble')
>>> parser.add_argument('bar', nargs='?', type=int, default=42,
...                     help='the bar to %(prog)s (default: %(default)s)')
>>> parser.print_help()
usage: frobble [-h] [bar]

positional arguments:
  bar                the bar to frobble (default: 42)

optional arguments:
  -h, --help        show this help message and exit
```

`argparse` supports silencing the help entry for certain options, by setting the help value to `argparse.SUPPRESS`:

```
>>> parser = argparse.ArgumentParser(prog='frobble')
>>> parser.add_argument('--foo', help=argparse.SUPPRESS)
>>> parser.print_help()
usage: frobble [-h]

optional arguments:
  -h, --help        show this help message and exit
```

metavar

When `ArgumentParser` generates help messages, it needs some way to refer to each expected argument. By default, `ArgumentParser` objects use the `dest` value as the «name» of each object. By default, for positional argument actions, the `dest` value is used directly, and for optional argument actions, the `dest` value is uppercased. So, a single positional argument with `dest='bar'` will be referred to as `bar`. A single optional argument `--foo` that should be followed by a single command-line argument will be referred to as `FOO`. An example:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo')
>>> parser.add_argument('bar')
>>> parser.parse_args('X --foo Y'.split())
Namespace(bar='X', foo='Y')
>>> parser.print_help()
usage: [-h] [--foo FOO] bar

positional arguments:
  bar

optional arguments:
  -h, --help  show this help message and exit
  --foo FOO
```

An alternative name can be specified with `metavar`:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', metavar='YYY')
>>> parser.add_argument('bar', metavar='XXX')
>>> parser.parse_args('X --foo Y'.split())
Namespace(bar='X', foo='Y')
>>> parser.print_help()
usage: [-h] [--foo YYY] XXX

positional arguments:
  XXX

optional arguments:
  -h, --help  show this help message and exit
  --foo YYY
```

Note that `metavar` only changes the *displayed* name - the name of the attribute on the `parse_args()` object is still determined by the `dest` value.

Different values of `nargs` may cause the `metavar` to be used multiple times. Providing a tuple to `metavar` specifies a different display for each of the arguments:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('-x', nargs=2)
>>> parser.add_argument('--foo', nargs=2, metavar=('bar', 'baz'))
>>> parser.print_help()
usage: PROG [-h] [-x X X] [--foo bar baz]

optional arguments:
  -h, --help  show this help message and exit
  -x X X
  --foo bar baz
```

dest

Most *ArgumentParser* actions add some value as an attribute of the object returned by *parse_args()*. The name of this attribute is determined by the *dest* keyword argument of *add_argument()*. For positional argument actions, *dest* is normally supplied as the first argument to *add_argument()*:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('bar')
>>> parser.parse_args(['XXX'])
Namespace(bar='XXX')
```

For optional argument actions, the value of *dest* is normally inferred from the option strings. *ArgumentParser* generates the value of *dest* by taking the first long option string and stripping away the initial `--` string. If no long option strings were supplied, *dest* will be derived from the first short option string by stripping the initial `-` character. Any internal `-` characters will be converted to `_` characters to make sure the string is a valid attribute name. The examples below illustrate this behavior:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('-f', '--foo-bar', '--foo')
>>> parser.add_argument('-x', '-y')
>>> parser.parse_args('-f 1 -x 2'.split())
Namespace(foo_bar='1', x='2')
>>> parser.parse_args('--foo 1 -y 2'.split())
Namespace(foo_bar='1', x='2')
```

dest allows a custom attribute name to be provided:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', dest='bar')
>>> parser.parse_args('--foo XXX'.split())
Namespace(bar='XXX')
```

Action classes

Action classes implement the Action API, a callable which returns a callable which processes arguments from the command-line. Any object which follows this API may be passed as the *action* parameter to *add_argument()*.

class *argparse.Action*(*option_strings*, *dest*, *nargs=None*, *const=None*, *default=None*, *type=None*, *choices=None*, *required=False*, *help=None*, *metavar=None*)

Action objects are used by an *ArgumentParser* to represent the information needed to parse a single argument from one or more strings from the command line. The Action class must accept the two positional arguments plus any keyword arguments passed to *ArgumentParser.add_argument()* except for the *action* itself.

Instances of *Action* (or return value of any callable to the *action* parameter) should have attributes `dest`, `option_strings`, `default`, `type`, `required`, `help`, etc. defined. The easiest way to ensure these attributes are defined is to call *Action.__init__*.

Action instances should be callable, so subclasses must override the `__call__` method, which should accept four parameters:

- *parser* - The *ArgumentParser* object which contains this action.
- *namespace* - The *Namespace* object that will be returned by *parse_args()*. Most actions add an attribute to this object using *setattr()*.
- *values* - The associated command-line arguments, with any type conversions applied. Type conversions are specified with the *type* keyword argument to *add_argument()*.

- `option_string` - The option string that was used to invoke this action. The `option_string` argument is optional, and will be absent if the action is associated with a positional argument.

The `__call__` method may perform arbitrary actions, but will typically set attributes on the `namespace` based on `dest` and `values`.

15.4.4 The `parse_args()` method

`ArgumentParser.parse_args(args=None, namespace=None)`

Convert argument strings to objects and assign them as attributes of the namespace. Return the populated namespace.

Previous calls to `add_argument()` determine exactly what objects are created and how they are assigned. See the documentation for `add_argument()` for details.

- `args` - List of strings to parse. The default is taken from `sys.argv`.
- `namespace` - An object to take the attributes. The default is a new empty `Namespace` object.

Option value syntax

The `parse_args()` method supports several ways of specifying the value of an option (if it takes one). In the simplest case, the option and its value are passed as two separate arguments:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('-x')
>>> parser.add_argument('--foo')
>>> parser.parse_args(['-x', 'X'])
Namespace(foo=None, x='X')
>>> parser.parse_args(['--foo', 'FOO'])
Namespace(foo='FOO', x=None)
```

For long options (options with names longer than a single character), the option and value can also be passed as a single command-line argument, using `=` to separate them:

```
>>> parser.parse_args(['--foo=FOO'])
Namespace(foo='FOO', x=None)
```

For short options (options only one character long), the option and its value can be concatenated:

```
>>> parser.parse_args(['-xX'])
Namespace(foo=None, x='X')
```

Several short options can be joined together, using only a single `-` prefix, as long as only the last option (or none of them) requires a value:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('-x', action='store_true')
>>> parser.add_argument('-y', action='store_true')
>>> parser.add_argument('-z')
>>> parser.parse_args(['-xyzZ'])
Namespace(x=True, y=True, z='Z')
```

Invalid arguments

While parsing the command line, `parse_args()` checks for a variety of errors, including ambiguous options, invalid types, invalid options, wrong number of positional arguments, etc. When it encounters such an error, it exits and prints the error along with a usage message:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('--foo', type=int)
>>> parser.add_argument('bar', nargs='?')

>>> # invalid type
>>> parser.parse_args(['--foo', 'spam'])
usage: PROG [-h] [--foo FOO] [bar]
PROG: error: argument --foo: invalid int value: 'spam'

>>> # invalid option
>>> parser.parse_args(['--bar'])
usage: PROG [-h] [--foo FOO] [bar]
PROG: error: no such option: --bar

>>> # wrong number of arguments
>>> parser.parse_args(['spam', 'badger'])
usage: PROG [-h] [--foo FOO] [bar]
PROG: error: extra arguments found: badger
```

Arguments containing -

The `parse_args()` method attempts to give errors whenever the user has clearly made a mistake, but some situations are inherently ambiguous. For example, the command-line argument `-1` could either be an attempt to specify an option or an attempt to provide a positional argument. The `parse_args()` method is cautious here: positional arguments may only begin with `-` if they look like negative numbers and there are no options in the parser that look like negative numbers:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('-x')
>>> parser.add_argument('foo', nargs='?')

>>> # no negative number options, so -1 is a positional argument
>>> parser.parse_args(['-x', '-1'])
Namespace(foo=None, x='-1')

>>> # no negative number options, so -1 and -5 are positional arguments
>>> parser.parse_args(['-x', '-1', '-5'])
Namespace(foo='-5', x='-1')

>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('-1', dest='one')
>>> parser.add_argument('foo', nargs='?')

>>> # negative number options present, so -1 is an option
>>> parser.parse_args(['-1', 'X'])
Namespace(foo=None, one='X')

>>> # negative number options present, so -2 is an option
>>> parser.parse_args(['-2'])
usage: PROG [-h] [-1 ONE] [foo]
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

PROG: error: no such option: -2

>>> # negative number options present, so both -1s are options
>>> parser.parse_args(['-1', '-1'])
usage: PROG [-h] [-1 ONE] [foo]
PROG: error: argument -1: expected one argument

```

If you have positional arguments that must begin with `-` and don't look like negative numbers, you can insert the pseudo-argument `--` which tells `parse_args()` that everything after that is a positional argument:

```

>>> parser.parse_args(['--', '-f'])
Namespace(foo='-f', one=None)

```

Argument abbreviations (prefix matching)

The `parse_args()` method allows long options to be abbreviated to a prefix, if the abbreviation is unambiguous (the prefix matches a unique option):

```

>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('-bacon')
>>> parser.add_argument('-badger')
>>> parser.parse_args(['-bac MMM'].split())
Namespace(bacon='MMM', badger=None)
>>> parser.parse_args(['-bad WOOD'].split())
Namespace(bacon=None, badger='WOOD')
>>> parser.parse_args(['-ba BA'].split())
usage: PROG [-h] [-bacon BACON] [-badger BADGER]
PROG: error: ambiguous option: -ba could match -badger, -bacon

```

An error is produced for arguments that could produce more than one options.

Beyond `sys.argv`

Sometimes it may be useful to have an `ArgumentParser` parse arguments other than those of `sys.argv`. This can be accomplished by passing a list of strings to `parse_args()`. This is useful for testing at the interactive prompt:

```

>>> parser = argparse.ArgumentParser()
>>> parser.add_argument(
...     'integers', metavar='int', type=int, choices=xrange(10),
...     nargs='+', help='an integer in the range 0..9')
>>> parser.add_argument(
...     '--sum', dest='accumulate', action='store_const', const=sum,
...     default=max, help='sum the integers (default: find the max)')
>>> parser.parse_args(['1', '2', '3', '4'])
Namespace(accumulate=<built-in function max>, integers=[1, 2, 3, 4])
>>> parser.parse_args(['1', '2', '3', '4', '--sum'])
Namespace(accumulate=<built-in function sum>, integers=[1, 2, 3, 4])

```

The Namespace object

`class argparse.Namespace`

Simple class used by default by `parse_args()` to create an object holding attributes and return it.

This class is deliberately simple, just an *object* subclass with a readable string representation. If you prefer to have dict-like view of the attributes, you can use the standard Python idiom, `vars()`:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo')
>>> args = parser.parse_args(['--foo', 'BAR'])
>>> vars(args)
{'foo': 'BAR'}
```

It may also be useful to have an *ArgumentParser* assign attributes to an already existing object, rather than a new *Namespace* object. This can be achieved by specifying the `namespace=` keyword argument:

```
>>> class C(object):
...     pass
...
>>> c = C()
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo')
>>> parser.parse_args(args=['--foo', 'BAR'], namespace=c)
>>> c.foo
'BAR'
```

15.4.5 Other utilities

Sub-commands

`ArgumentParser.add_subparsers([title][, description][, prog][, parser_class][, action][, option_string][, dest][, help][, metavar])`

Many programs split up their functionality into a number of sub-commands, for example, the `svn` program can invoke sub-commands like `svn checkout`, `svn update`, and `svn commit`. Splitting up functionality this way can be a particularly good idea when a program performs several different functions which require different kinds of command-line arguments. *ArgumentParser* supports the creation of such sub-commands with the `add_subparsers()` method. The `add_subparsers()` method is normally called with no arguments and returns a special action object. This object has a single method, `add_parser()`, which takes a command name and any *ArgumentParser* constructor arguments, and returns an *ArgumentParser* object that can be modified as usual.

Description of parameters:

- `title` - title for the sub-parser group in help output; by default 《subcommands》 if description is provided, otherwise uses title for positional arguments
- `description` - description for the sub-parser group in help output, by default `None`
- `prog` - usage information that will be displayed with sub-command help, by default the name of the program and any positional arguments before the subparser argument
- `parser_class` - class which will be used to create sub-parser instances, by default the class of the current parser (e.g. *ArgumentParser*)
- `action` - the basic type of action to be taken when this argument is encountered at the command line

- *dest* - name of the attribute under which sub-command name will be stored; by default `None` and no value is stored
- *help* - help for sub-parser group in help output, by default `None`
- *metavar* - string presenting available sub-commands in help; by default it is `None` and presents sub-commands in form `{cmd1, cmd2, ..}`

Some example usage:

```
>>> # create the top-level parser
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> parser.add_argument('--foo', action='store_true', help='foo help')
>>> subparsers = parser.add_subparsers(help='sub-command help')
>>>
>>> # create the parser for the "a" command
>>> parser_a = subparsers.add_parser('a', help='a help')
>>> parser_a.add_argument('bar', type=int, help='bar help')
>>>
>>> # create the parser for the "b" command
>>> parser_b = subparsers.add_parser('b', help='b help')
>>> parser_b.add_argument('--baz', choices='XYZ', help='baz help')
>>>
>>> # parse some argument lists
>>> parser.parse_args(['a', '12'])
Namespace(bar=12, foo=False)
>>> parser.parse_args(['--foo', 'b', '--baz', 'Z'])
Namespace(baz='Z', foo=True)
```

Note that the object returned by `parse_args()` will only contain attributes for the main parser and the subparser that was selected by the command line (and not any other subparsers). So in the example above, when the `a` command is specified, only the `foo` and `bar` attributes are present, and when the `b` command is specified, only the `foo` and `baz` attributes are present.

Similarly, when a help message is requested from a subparser, only the help for that particular parser will be printed. The help message will not include parent parser or sibling parser messages. (A help message for each subparser command, however, can be given by supplying the `help=` argument to `add_parser()` as above.)

```
>>> parser.parse_args(['--help'])
usage: PROG [-h] [--foo] {a,b} ...

positional arguments:
  {a,b}  sub-command help
  a      a help
  b      b help

optional arguments:
  -h, --help  show this help message and exit
  --foo       foo help

>>> parser.parse_args(['a', '--help'])
usage: PROG a [-h] bar

positional arguments:
  bar      bar help

optional arguments:
  -h, --help  show this help message and exit
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> parser.parse_args(['b', '--help'])
usage: PROG b [-h] [--baz {X,Y,Z}]

optional arguments:
  -h, --help      show this help message and exit
  --baz {X,Y,Z}   baz help
```

The `add_subparsers()` method also supports `title` and `description` keyword arguments. When either is present, the subparser's commands will appear in their own group in the help output. For example:

```
>>> parser = argparse.ArgumentParser()
>>> subparsers = parser.add_subparsers(title='subcommands',
...                                   description='valid subcommands',
...                                   help='additional help')
>>> subparsers.add_parser('foo')
>>> subparsers.add_parser('bar')
>>> parser.parse_args(['-h'])
usage: [-h] {foo,bar} ...

optional arguments:
  -h, --help  show this help message and exit

subcommands:
  valid subcommands

  {foo,bar}   additional help
```

One particularly effective way of handling sub-commands is to combine the use of the `add_subparsers()` method with calls to `set_defaults()` so that each subparser knows which Python function it should execute. For example:

```
>>> # sub-command functions
>>> def foo(args):
...     print args.x * args.y
...
>>> def bar(args):
...     print '(%s)' % args.z
...
>>> # create the top-level parser
>>> parser = argparse.ArgumentParser()
>>> subparsers = parser.add_subparsers()
>>>
>>> # create the parser for the "foo" command
>>> parser_foo = subparsers.add_parser('foo')
>>> parser_foo.add_argument('-x', type=int, default=1)
>>> parser_foo.add_argument('y', type=float)
>>> parser_foo.set_defaults(func=foo)
>>>
>>> # create the parser for the "bar" command
>>> parser_bar = subparsers.add_parser('bar')
>>> parser_bar.add_argument('z')
>>> parser_bar.set_defaults(func=bar)
>>>
>>> # parse the args and call whatever function was selected
>>> args = parser.parse_args('foo 1 -x 2'.split())
>>> args.func(args)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

2.0
>>>
>>> # parse the args and call whatever function was selected
>>> args = parser.parse_args('bar XYZYX'.split())
>>> args.func(args)
((XYZYX))

```

This way, you can let `parse_args()` do the job of calling the appropriate function after argument parsing is complete. Associating functions with actions like this is typically the easiest way to handle the different actions for each of your subparsers. However, if it is necessary to check the name of the subparser that was invoked, the `dest` keyword argument to the `add_subparsers()` call will work:

```

>>> parser = argparse.ArgumentParser()
>>> subparsers = parser.add_subparsers(dest='subparser_name')
>>> subparser1 = subparsers.add_parser('1')
>>> subparser1.add_argument('-x')
>>> subparser2 = subparsers.add_parser('2')
>>> subparser2.add_argument('y')
>>> parser.parse_args(['2', 'frobble'])
Namespace(subparser_name='2', y='frobble')

```

FileType objects

class `argparse.FileType` (*mode='r', bufsize=None*)

The `FileType` factory creates objects that can be passed to the `type` argument of `ArgumentParser.add_argument()`. Arguments that have `FileType` objects as their type will open command-line arguments as files with the requested modes and buffer sizes:

```

>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--output', type=argparse.FileType('wb', 0))
>>> parser.parse_args(['--output', 'out'])
Namespace(output=<open file 'out', mode 'wb' at 0x...>)

```

`FileType` objects understand the pseudo-argument `'-'` and automatically convert this into `sys.stdin` for readable `FileType` objects and `sys.stdout` for writable `FileType` objects:

```

>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('infile', type=argparse.FileType('r'))
>>> parser.parse_args(['-'])
Namespace(infile=<open file '<stdin>', mode 'r' at 0x...>)

```

Argument groups

`ArgumentParser.add_argument_group` (*title=None, description=None*)

By default, `ArgumentParser` groups command-line arguments into 《positional arguments》 and 《optional arguments》 when displaying help messages. When there is a better conceptual grouping of arguments than this default one, appropriate groups can be created using the `add_argument_group()` method:

```

>>> parser = argparse.ArgumentParser(prog='PROG', add_help=False)
>>> group = parser.add_argument_group('group')
>>> group.add_argument('--foo', help='foo help')
>>> group.add_argument('bar', help='bar help')

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> parser.print_help()
usage: PROG [--foo FOO] bar

group:
  bar      bar help
  --foo FOO  foo help
```

The `add_argument_group()` method returns an argument group object which has an `add_argument()` method just like a regular `ArgumentParser`. When an argument is added to the group, the parser treats it just like a normal argument, but displays the argument in a separate group for help messages. The `add_argument_group()` method accepts *title* and *description* arguments which can be used to customize this display:

```
>>> parser = argparse.ArgumentParser(prog='PROG', add_help=False)
>>> group1 = parser.add_argument_group('group1', 'group1 description')
>>> group1.add_argument('foo', help='foo help')
>>> group2 = parser.add_argument_group('group2', 'group2 description')
>>> group2.add_argument('--bar', help='bar help')
>>> parser.print_help()
usage: PROG [--bar BAR] foo

group1:
  group1 description

  foo      foo help

group2:
  group2 description

  --bar BAR  bar help
```

Note that any arguments not in your user-defined groups will end up back in the usual 《positional arguments》 and 《optional arguments》 sections.

Mutual exclusion

`ArgumentParser.add_mutually_exclusive_group(required=False)`

Create a mutually exclusive group. *argparse* will make sure that only one of the arguments in the mutually exclusive group was present on the command line:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> group = parser.add_mutually_exclusive_group()
>>> group.add_argument('--foo', action='store_true')
>>> group.add_argument('--bar', action='store_false')
>>> parser.parse_args(['--foo'])
Namespace(bar=True, foo=True)
>>> parser.parse_args(['--bar'])
Namespace(bar=False, foo=False)
>>> parser.parse_args(['--foo', '--bar'])
usage: PROG [-h] [--foo | --bar]
PROG: error: argument --bar: not allowed with argument --foo
```

The `add_mutually_exclusive_group()` method also accepts a *required* argument, to indicate that at least one of the mutually exclusive arguments is required:

```
>>> parser = argparse.ArgumentParser(prog='PROG')
>>> group = parser.add_mutually_exclusive_group(required=True)
>>> group.add_argument('--foo', action='store_true')
>>> group.add_argument('--bar', action='store_false')
>>> parser.parse_args([])
usage: PROG [-h] (--foo | --bar)
PROG: error: one of the arguments --foo --bar is required
```

Note that currently mutually exclusive argument groups do not support the *title* and *description* arguments of `add_argument_group()`.

Parser defaults

`ArgumentParser.set_defaults(**kwargs)`

Most of the time, the attributes of the object returned by `parse_args()` will be fully determined by inspecting the command-line arguments and the argument actions. `set_defaults()` allows some additional attributes that are determined without any inspection of the command line to be added:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('foo', type=int)
>>> parser.set_defaults(bar=42, baz='badger')
>>> parser.parse_args(['736'])
Namespace(bar=42, baz='badger', foo=736)
```

Note that parser-level defaults always override argument-level defaults:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', default='bar')
>>> parser.set_defaults(foo='spam')
>>> parser.parse_args([])
Namespace(foo='spam')
```

Parser-level defaults can be particularly useful when working with multiple parsers. See the `add_subparsers()` method for an example of this type.

`ArgumentParser.get_default(dest)`

Get the default value for a namespace attribute, as set by either `add_argument()` or by `set_defaults()`:

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', default='badger')
>>> parser.get_default('foo')
'badger'
```

Printing help

In most typical applications, `parse_args()` will take care of formatting and printing any usage or error messages. However, several formatting methods are available:

`ArgumentParser.print_usage(file=None)`

Print a brief description of how the *ArgumentParser* should be invoked on the command line. If *file* is *None*, `sys.stdout` is assumed.

`ArgumentParser.print_help(file=None)`

Print a help message, including the program usage and information about the arguments registered with the *ArgumentParser*. If *file* is *None*, `sys.stdout` is assumed.

There are also variants of these methods that simply return a string instead of printing it:

`ArgumentParser.format_usage()`

Return a string containing a brief description of how the *ArgumentParser* should be invoked on the command line.

`ArgumentParser.format_help()`

Return a string containing a help message, including the program usage and information about the arguments registered with the *ArgumentParser*.

Partial parsing

`ArgumentParser.parse_known_args(args=None, namespace=None)`

Sometimes a script may only parse a few of the command-line arguments, passing the remaining arguments on to another script or program. In these cases, the *parse_known_args()* method can be useful. It works much like *parse_args()* except that it does not produce an error when extra arguments are present. Instead, it returns a two item tuple containing the populated namespace and the list of remaining argument strings.

```
>>> parser = argparse.ArgumentParser()
>>> parser.add_argument('--foo', action='store_true')
>>> parser.add_argument('bar')
>>> parser.parse_known_args(['--foo', '--badger', 'BAR', 'spam'])
(Namespace(bar='BAR', foo=True), ['--badger', 'spam'])
```

경고: *Prefix matching* rules apply to *parse_known_args()*. The parser may consume an option even if it's just a prefix of one of its known options, instead of leaving it in the remaining arguments list.

Customizing file parsing

`ArgumentParser.convert_arg_line_to_args(arg_line)`

Arguments that are read from a file (see the *fromfile_prefix_chars* keyword argument to the *ArgumentParser* constructor) are read one argument per line. *convert_arg_line_to_args()* can be overridden for fancier reading.

This method takes a single argument *arg_line* which is a string read from the argument file. It returns a list of arguments parsed from this string. The method is called once per line read from the argument file, in order.

A useful override of this method is one that treats each space-separated word as an argument:

```
def convert_arg_line_to_args(self, arg_line):
    return arg_line.split()
```

Exiting methods

`ArgumentParser.exit(status=0, message=None)`

This method terminates the program, exiting with the specified *status* and, if given, it prints a *message* before that.

`ArgumentParser.error(message)`

This method prints a usage message including the *message* to the standard error and terminates the program with a status code of 2.

15.4.6 Upgrading optparse code

Originally, the `argparse` module had attempted to maintain compatibility with `optparse`. However, `optparse` was difficult to extend transparently, particularly with the changes required to support the new `nargs=` specifiers and better usage messages. When most everything in `optparse` had either been copy-pasted over or monkey-patched, it no longer seemed practical to try to maintain the backwards compatibility.

The `argparse` module improves on the standard library `optparse` module in a number of ways including:

- Handling positional arguments.
- Supporting sub-commands.
- Allowing alternative option prefixes like `+` and `/`.
- Handling zero-or-more and one-or-more style arguments.
- Producing more informative usage messages.
- Providing a much simpler interface for custom type and action.

A partial upgrade path from `optparse` to `argparse`:

- Replace all `optparse.OptionParser.add_option()` calls with `ArgumentParser.add_argument()` calls.
- Replace `(options, args) = parser.parse_args()` with `args = parser.parse_args()` and add additional `ArgumentParser.add_argument()` calls for the positional arguments. Keep in mind that what was previously called `options`, now in the `argparse` context is called `args`.
- Replace `optparse.OptionParser.disable_interspersed_args()` by setting `nargs` of a positional argument to `argparse.REMAINDER`, or use `parse_known_args()` to collect unparsed argument strings in a separate list.
- Replace callback actions and the `callback_*` keyword arguments with `type` or `action` arguments.
- Replace string names for `type` keyword arguments with the corresponding type objects (e.g. `int`, `float`, `complex`, etc).
- Replace `optparse.Values` with `Namespace` and `optparse.OptionError` and `optparse.OptionValueError` with `ArgumentError`.
- Replace strings with implicit arguments such as `%default` or `%prog` with the standard Python syntax to use dictionaries to format strings, that is, `%(default)s` and `%(prog)s`.
- Replace the `OptionParser` constructor version argument with a call to `parser.add_argument('--version', action='version', version='<the version>')`.

15.5 optparse — Parser for command line options

버전 2.3에 추가.

버전 2.7부터 폐지: The `optparse` module is deprecated and will not be developed further; development will continue with the `argparse` module.

Source code: `Lib/optparse.py`

`optparse` is a more convenient, flexible, and powerful library for parsing command-line options than the old `getopt` module. `optparse` uses a more declarative style of command-line parsing: you create an instance of `OptionParser`,

populate it with options, and parse the command line. *optparse* allows users to specify options in the conventional GNU/POSIX syntax, and additionally generates usage and help messages for you.

Here's an example of using *optparse* in a simple script:

```
from optparse import OptionParser
...
parser = OptionParser()
parser.add_option("-f", "--file", dest="filename",
                  help="write report to FILE", metavar="FILE")
parser.add_option("-q", "--quiet",
                  action="store_false", dest="verbose", default=True,
                  help="don't print status messages to stdout")

(options, args) = parser.parse_args()
```

With these few lines of code, users of your script can now do the 《usual thing》 on the command-line, for example:

```
<yourscript> --file=outfile -q
```

As it parses the command line, *optparse* sets attributes of the options object returned by `parse_args()` based on user-supplied command-line values. When `parse_args()` returns from parsing this command line, `options.filename` will be "outfile" and `options.verbose` will be `False`. *optparse* supports both long and short options, allows short options to be merged together, and allows options to be associated with their arguments in a variety of ways. Thus, the following command lines are all equivalent to the above example:

```
<yourscript> -f outfile --quiet
<yourscript> --quiet --file outfile
<yourscript> -q -foutfile
<yourscript> -qfoutfile
```

Additionally, users can run one of

```
<yourscript> -h
<yourscript> --help
```

and *optparse* will print out a brief summary of your script's options:

```
Usage: <yourscript> [options]

Options:
  -h, --help            show this help message and exit
  -f FILE, --file=FILE  write report to FILE
  -q, --quiet           don't print status messages to stdout
```

where the value of *yourscript* is determined at runtime (normally from `sys.argv[0]`).

15.5.1 Background

`optparse` was explicitly designed to encourage the creation of programs with straightforward, conventional command-line interfaces. To that end, it supports only the most common command-line syntax and semantics conventionally used under Unix. If you are unfamiliar with these conventions, read this section to acquaint yourself with them.

Terminology

argument a string entered on the command-line, and passed by the shell to `exec1()` or `execv()`. In Python, arguments are elements of `sys.argv[1:]` (`sys.argv[0]` is the name of the program being executed). Unix shells also use the term *«word»*.

It is occasionally desirable to substitute an argument list other than `sys.argv[1:]`, so you should read *«argument»* as *«an element of `sys.argv[1:]`, or of some other list provided as a substitute for `sys.argv[1:]`»*.

option an argument used to supply extra information to guide or customize the execution of a program. There are many different syntaxes for options; the traditional Unix syntax is a hyphen (*«-»*) followed by a single letter, e.g. `-x` or `-F`. Also, traditional Unix syntax allows multiple options to be merged into a single argument, e.g. `-x -F` is equivalent to `-xF`. The GNU project introduced `--` followed by a series of hyphen-separated words, e.g. `--file` or `--dry-run`. These are the only two option syntaxes provided by `optparse`.

Some other option syntaxes that the world has seen include:

- a hyphen followed by a few letters, e.g. `-pf` (this is *not* the same as multiple options merged into a single argument)
- a hyphen followed by a whole word, e.g. `-file` (this is technically equivalent to the previous syntax, but they aren't usually seen in the same program)
- a plus sign followed by a single letter, or a few letters, or a word, e.g. `+f`, `+rgb`
- a slash followed by a letter, or a few letters, or a word, e.g. `/f`, `/file`

These option syntaxes are not supported by `optparse`, and they never will be. This is deliberate: the first three are non-standard on any environment, and the last only makes sense if you're exclusively targeting VMS, MS-DOS, and/or Windows.

option argument an argument that follows an option, is closely associated with that option, and is consumed from the argument list when that option is. With `optparse`, option arguments may either be in a separate argument from their option:

```
-f foo
--file foo
```

or included in the same argument:

```
-ffoo
--file=foo
```

Typically, a given option either takes an argument or it doesn't. Lots of people want an *«optional option arguments»* feature, meaning that some options will take an argument if they see it, and won't if they don't. This is somewhat controversial, because it makes parsing ambiguous: if `-a` takes an optional argument and `-b` is another option entirely, how do we interpret `-ab`? Because of this ambiguity, `optparse` does not support this feature.

positional argument something leftover in the argument list after options have been parsed, i.e. after options and their arguments have been parsed and removed from the argument list.

required option an option that must be supplied on the command-line; note that the phrase 《required option》 is self-contradictory in English. `optparse` doesn't prevent you from implementing required options, but doesn't give you much help at it either.

For example, consider this hypothetical command-line:

```
prog -v --report report.txt foo bar
```

`-v` and `--report` are both options. Assuming that `--report` takes one argument, `report.txt` is an option argument. `foo` and `bar` are positional arguments.

What are options for?

Options are used to provide extra information to tune or customize the execution of a program. In case it wasn't clear, options are usually *optional*. A program should be able to run just fine with no options whatsoever. (Pick a random program from the Unix or GNU toolsets. Can it run without any options at all and still make sense? The main exceptions are `find`, `tar`, and `dd`—all of which are mutant oddballs that have been rightly criticized for their non-standard syntax and confusing interfaces.)

Lots of people want their programs to have 《required options》. Think about it. If it's required, then it's *not optional*! If there is a piece of information that your program absolutely requires in order to run successfully, that's what positional arguments are for.

As an example of good command-line interface design, consider the humble `cp` utility, for copying files. It doesn't make much sense to try to copy files without supplying a destination and at least one source. Hence, `cp` fails if you run it with no arguments. However, it has a flexible, useful syntax that does not require any options at all:

```
cp SOURCE DEST
cp SOURCE ... DEST-DIR
```

You can get pretty far with just that. Most `cp` implementations provide a bunch of options to tweak exactly how the files are copied: you can preserve mode and modification time, avoid following symlinks, ask before clobbering existing files, etc. But none of this distracts from the core mission of `cp`, which is to copy either one file to another, or several files to another directory.

What are positional arguments for?

Positional arguments are for those pieces of information that your program absolutely, positively requires to run.

A good user interface should have as few absolute requirements as possible. If your program requires 17 distinct pieces of information in order to run successfully, it doesn't much matter *how* you get that information from the user—most people will give up and walk away before they successfully run the program. This applies whether the user interface is a command-line, a configuration file, or a GUI: if you make that many demands on your users, most of them will simply give up.

In short, try to minimize the amount of information that users are absolutely required to supply—use sensible defaults whenever possible. Of course, you also want to make your programs reasonably flexible. That's what options are for. Again, it doesn't matter if they are entries in a config file, widgets in the 《Preferences》 dialog of a GUI, or command-line options—the more options you implement, the more flexible your program is, and the more complicated its implementation becomes. Too much flexibility has drawbacks as well, of course; too many options can overwhelm users and make your code much harder to maintain.

15.5.2 Tutorial

While *optparse* is quite flexible and powerful, it's also straightforward to use in most cases. This section covers the code patterns that are common to any *optparse*-based program.

First, you need to import the `OptionParser` class; then, early in the main program, create an `OptionParser` instance:

```
from optparse import OptionParser
...
parser = OptionParser()
```

Then you can start defining options. The basic syntax is:

```
parser.add_option(opt_str, ...,
                  attr=value, ...)
```

Each option has one or more option strings, such as `-f` or `--file`, and several option attributes that tell *optparse* what to expect and what to do when it encounters that option on the command line.

Typically, each option will have one short option string and one long option string, e.g.:

```
parser.add_option("-f", "--file", ...)
```

You're free to define as many short option strings and as many long option strings as you like (including zero), as long as there is at least one option string overall.

The option strings passed to `OptionParser.add_option()` are effectively labels for the option defined by that call. For brevity, we will frequently refer to *encountering an option* on the command line; in reality, *optparse* encounters *option strings* and looks up options from them.

Once all of your options are defined, instruct *optparse* to parse your program's command line:

```
(options, args) = parser.parse_args()
```

(If you like, you can pass a custom argument list to `parse_args()`, but that's rarely necessary: by default it uses `sys.argv[1:]`.)

`parse_args()` returns two values:

- `options`, an object containing values for all of your options—e.g. if `--file` takes a single string argument, then `options.file` will be the filename supplied by the user, or `None` if the user did not supply that option
- `args`, the list of positional arguments leftover after parsing options

This tutorial section only covers the four most important option attributes: *action*, *type*, *dest* (destination), and *help*. Of these, *action* is the most fundamental.

Understanding option actions

Actions tell *optparse* what to do when it encounters an option on the command line. There is a fixed set of actions hard-coded into *optparse*; adding new actions is an advanced topic covered in section *Extending optparse*. Most actions tell *optparse* to store a value in some variable—for example, take a string from the command line and store it in an attribute of `options`.

If you don't specify an option action, *optparse* defaults to `store`.

The store action

The most common option action is `store`, which tells *optparse* to take the next argument (or the remainder of the current argument), ensure that it is of the correct type, and store it to your chosen destination.

For example:

```
parser.add_option("-f", "--file",
                  action="store", type="string", dest="filename")
```

Now let's make up a fake command line and ask *optparse* to parse it:

```
args = ["-f", "foo.txt"]
(options, args) = parser.parse_args(args)
```

When *optparse* sees the option string `-f`, it consumes the next argument, `foo.txt`, and stores it in `options.filename`. So, after this call to `parse_args()`, `options.filename` is `"foo.txt"`.

Some other option types supported by *optparse* are `int` and `float`. Here's an option that expects an integer argument:

```
parser.add_option("-n", type="int", dest="num")
```

Note that this option has no long option string, which is perfectly acceptable. Also, there's no explicit action, since the default is `store`.

Let's parse another fake command-line. This time, we'll jam the option argument right up against the option: since `-n42` (one argument) is equivalent to `-n 42` (two arguments), the code

```
(options, args) = parser.parse_args(["-n42"])
print options.num
```

will print 42.

If you don't specify a type, *optparse* assumes `string`. Combined with the fact that the default action is `store`, that means our first example can be a lot shorter:

```
parser.add_option("-f", "--file", dest="filename")
```

If you don't supply a destination, *optparse* figures out a sensible default from the option strings: if the first long option string is `--foo-bar`, then the default destination is `foo_bar`. If there are no long option strings, *optparse* looks at the first short option string: the default destination for `-f` is `f`.

optparse also includes built-in long and complex types. Adding types is covered in section [Extending optparse](#).

Handling boolean (flag) options

Flag options—set a variable to true or false when a particular option is seen—are quite common. *optparse* supports them with two separate actions, `store_true` and `store_false`. For example, you might have a `verbose` flag that is turned on with `-v` and off with `-q`:

```
parser.add_option("-v", action="store_true", dest="verbose")
parser.add_option("-q", action="store_false", dest="verbose")
```

Here we have two different options with the same destination, which is perfectly OK. (It just means you have to be a bit careful when setting default values—see below.)

When *optparse* encounters `-v` on the command line, it sets `options.verbose` to `True`; when it encounters `-q`, `options.verbose` is set to `False`.

Other actions

Some other actions supported by *optparse* are:

"**store_const**" store a constant value

"**append**" append this option's argument to a list

"**count**" increment a counter by one

"**callback**" call a specified function

These are covered in section *Reference Guide*, Reference Guide and section *Option Callbacks*.

Default values

All of the above examples involve setting some variable (the «destination») when certain command-line options are seen. What happens if those options are never seen? Since we didn't supply any defaults, they are all set to `None`. This is usually fine, but sometimes you want more control. *optparse* lets you supply a default value for each destination, which is assigned before the command line is parsed.

First, consider the verbose/quiet example. If we want *optparse* to set `verbose` to `True` unless `-q` is seen, then we can do this:

```
parser.add_option("-v", action="store_true", dest="verbose", default=True)
parser.add_option("-q", action="store_false", dest="verbose")
```

Since default values apply to the *destination* rather than to any particular option, and these two options happen to have the same destination, this is exactly equivalent:

```
parser.add_option("-v", action="store_true", dest="verbose")
parser.add_option("-q", action="store_false", dest="verbose", default=True)
```

Consider this:

```
parser.add_option("-v", action="store_true", dest="verbose", default=False)
parser.add_option("-q", action="store_false", dest="verbose", default=True)
```

Again, the default value for `verbose` will be `True`: the last default value supplied for any particular destination is the one that counts.

A clearer way to specify default values is the `set_defaults()` method of `OptionParser`, which you can call at any time before calling `parse_args()`:

```
parser.set_defaults(verbose=True)
parser.add_option(...)
(options, args) = parser.parse_args()
```

As before, the last value specified for a given option destination is the one that counts. For clarity, try to use one method or the other of setting default values, not both.

Generating help

optparse's ability to generate help and usage text automatically is useful for creating user-friendly command-line interfaces. All you have to do is supply a *help* value for each option, and optionally a short usage message for your whole program. Here's an *OptionParser* populated with user-friendly (documented) options:

```
usage = "usage: %prog [options] arg1 arg2"
parser = OptionParser(usage=usage)
parser.add_option("-v", "--verbose",
                  action="store_true", dest="verbose", default=True,
                  help="make lots of noise [default]")
parser.add_option("-q", "--quiet",
                  action="store_false", dest="verbose",
                  help="be vewwy quiet (I'm hunting wabbits)")
parser.add_option("-f", "--filename",
                  metavar="FILE", help="write output to FILE")
parser.add_option("-m", "--mode",
                  default="intermediate",
                  help="interaction mode: novice, intermediate, "
                        "or expert [default: %default]")
```

If *optparse* encounters either `-h` or `--help` on the command-line, or if you just call `parser.print_help()`, it prints the following to standard output:

```
Usage: <yourscrip> [options] arg1 arg2

Options:
  -h, --help            show this help message and exit
  -v, --verbose          make lots of noise [default]
  -q, --quiet           be vewwy quiet (I'm hunting wabbits)
  -f FILE, --filename=FILE
                        write output to FILE
  -m MODE, --mode=MODE  interaction mode: novice, intermediate, or
                        expert [default: intermediate]
```

(If the help output is triggered by a help option, *optparse* exits after printing the help text.)

There's a lot going on here to help *optparse* generate the best possible help message:

- the script defines its own usage message:

```
usage = "usage: %prog [options] arg1 arg2"
```

optparse expands `%prog` in the usage string to the name of the current program, i.e. `os.path.basename(sys.argv[0])`. The expanded string is then printed before the detailed option help.

If you don't supply a usage string, *optparse* uses a bland but sensible default: `"Usage: %prog [options]"`, which is fine if your script doesn't take any positional arguments.

- every option defines a help string, and doesn't worry about line-wrapping— *optparse* takes care of wrapping lines and making the help output look good.
- options that take a value indicate this fact in their automatically-generated help message, e.g. for the `《mode》` option:

```
-m MODE, --mode=MODE
```

Here, `《MODE》` is called the meta-variable: it stands for the argument that the user is expected to supply to `-m/--mode`. By default, *optparse* converts the destination variable name to uppercase and uses that for

the meta-variable. Sometimes, that's not what you want—for example, the `--filename` option explicitly sets `metavar="FILE"`, resulting in this automatically-generated option description:

```
-f FILE, --filename=FILE
```

This is important for more than just saving space, though: the manually written help text uses the meta-variable `FILE` to clue the user in that there's a connection between the semi-formal syntax `-f FILE` and the informal semantic description «write output to `FILE`». This is a simple but effective way to make your help text a lot clearer and more useful for end users.

버전 2.4에 추가: Options that have a default value can include `%default` in the help string—`optparse` will replace it with `str()` of the option's default value. If an option has no default value (or the default value is `None`), `%default` expands to `none`.

Grouping Options

When dealing with many options, it is convenient to group these options for better help output. An `OptionParser` can contain several option groups, each of which can contain several options.

An option group is obtained using the class `OptionGroup`:

class `optparse.OptionGroup` (*parser, title, description=None*)
where

- `parser` is the `OptionParser` instance the group will be insterted in to
- `title` is the group title
- `description`, optional, is a long description of the group

`OptionGroup` inherits from `OptionContainer` (like `OptionParser`) and so the `add_option()` method can be used to add an option to the group.

Once all the options are declared, using the `OptionParser` method `add_option_group()` the group is added to the previously defined parser.

Continuing with the parser defined in the previous section, adding an `OptionGroup` to a parser is easy:

```
group = OptionGroup(parser, "Dangerous Options",
                    "Caution: use these options at your own risk.  "
                    "It is believed that some of them bite.")
group.add_option("-g", action="store_true", help="Group option.")
parser.add_option_group(group)
```

This would result in the following help output:

```
Usage: <yourscript> [options] arg1 arg2

Options:
  -h, --help            show this help message and exit
  -v, --verbose          make lots of noise [default]
  -q, --quiet           be vewwy quiet (I'm hunting wabbits)
  -f FILE, --filename=FILE
                        write output to FILE
  -m MODE, --mode=MODE  interaction mode: novice, intermediate, or
                        expert [default: intermediate]

Dangerous Options:
  Caution: use these options at your own risk.  It is believed that some
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

of them bite.

-g Group option.

A bit more complete example might involve using more than one group: still extending the previous example:

```
group = OptionGroup(parser, "Dangerous Options",
                    "Caution: use these options at your own risk. "
                    "It is believed that some of them bite.")
group.add_option("-g", action="store_true", help="Group option.")
parser.add_option_group(group)

group = OptionGroup(parser, "Debug Options")
group.add_option("-d", "--debug", action="store_true",
                help="Print debug information")
group.add_option("-s", "--sql", action="store_true",
                help="Print all SQL statements executed")
group.add_option("-e", action="store_true", help="Print every action done")
parser.add_option_group(group)
```

that results in the following output:

```
Usage: <yourscript> [options] arg1 arg2

Options:
  -h, --help            show this help message and exit
  -v, --verbose         make lots of noise [default]
  -q, --quiet           be vewwy quiet (I'm hunting wabbits)
  -f FILE, --filename=FILE
                        write output to FILE
  -m MODE, --mode=MODE  interaction mode: novice, intermediate, or expert
                        [default: intermediate]

Dangerous Options:
  Caution: use these options at your own risk.  It is believed that some
  of them bite.

  -g                    Group option.

Debug Options:
  -d, --debug          Print debug information
  -s, --sql            Print all SQL statements executed
  -e                  Print every action done
```

Another interesting method, in particular when working programmatically with option groups is:

`OptionParser.get_option_group(opt_str)`

Return the *OptionGroup* to which the short or long option string *opt_str* (e.g. '-o' or '--option') belongs. If there's no such *OptionGroup*, return None.

Printing a version string

Similar to the brief usage string, `optparse` can also print a version string for your program. You have to supply the string as the `version` argument to `OptionParser`:

```
parser = OptionParser(usage="%prog [-f] [-q]", version="%prog 1.0")
```

`%prog` is expanded just like it is in usage. Apart from that, `version` can contain anything you like. When you supply it, `optparse` automatically adds a `--version` option to your parser. If it encounters this option on the command line, it expands your `version` string (by replacing `%prog`), prints it to stdout, and exits.

For example, if your script is called `/usr/bin/foo`:

```
$ /usr/bin/foo --version
foo 1.0
```

The following two methods can be used to print and get the `version` string:

`OptionParser.print_version(file=None)`

Print the version message for the current program (`self.version`) to `file` (default stdout). As with `print_usage()`, any occurrence of `%prog` in `self.version` is replaced with the name of the current program. Does nothing if `self.version` is empty or undefined.

`OptionParser.get_version()`

Same as `print_version()` but returns the version string instead of printing it.

How `optparse` handles errors

There are two broad classes of errors that `optparse` has to worry about: programmer errors and user errors. Programmer errors are usually erroneous calls to `OptionParser.add_option()`, e.g. invalid option strings, unknown option attributes, missing option attributes, etc. These are dealt with in the usual way: raise an exception (either `optparse.OptionError` or `TypeError`) and let the program crash.

Handling user errors is much more important, since they are guaranteed to happen no matter how stable your code is. `optparse` can automatically detect some user errors, such as bad option arguments (passing `-n 4x` where `-n` takes an integer argument), missing arguments (`-n` at the end of the command line, where `-n` takes an argument of any type). Also, you can call `OptionParser.error()` to signal an application-defined error condition:

```
(options, args) = parser.parse_args()
...
if options.a and options.b:
    parser.error("options -a and -b are mutually exclusive")
```

In either case, `optparse` handles the error the same way: it prints the program's usage message and an error message to standard error and exits with error status 2.

Consider the first example above, where the user passes `4x` to an option that takes an integer:

```
$ /usr/bin/foo -n 4x
Usage: foo [options]

foo: error: option -n: invalid integer value: '4x'
```

Or, where the user fails to pass a value at all:

```
$ /usr/bin/foo -n
Usage: foo [options]

foo: error: -n option requires an argument
```

optparse-generated error messages take care always to mention the option involved in the error; be sure to do the same when calling `OptionParser.error()` from your application code.

If *optparse*'s default error-handling behaviour does not suit your needs, you'll need to subclass `OptionParser` and override its `exit()` and/or `error()` methods.

Putting it all together

Here's what *optparse*-based scripts usually look like:

```
from optparse import OptionParser
...
def main():
    usage = "usage: %prog [options] arg"
    parser = OptionParser(usage)
    parser.add_option("-f", "--file", dest="filename",
                      help="read data from FILENAME")
    parser.add_option("-v", "--verbose",
                      action="store_true", dest="verbose")
    parser.add_option("-q", "--quiet",
                      action="store_false", dest="verbose")
    ...
    (options, args) = parser.parse_args()
    if len(args) != 1:
        parser.error("incorrect number of arguments")
    if options.verbose:
        print "reading %s..." % options.filename
    ...

if __name__ == "__main__":
    main()
```

15.5.3 Reference Guide

Creating the parser

The first step in using *optparse* is to create an `OptionParser` instance.

class `optparse.OptionParser(...)`

The `OptionParser` constructor has no required arguments, but a number of optional keyword arguments. You should always pass them as keyword arguments, i.e. do not rely on the order in which the arguments are declared.

usage (default: `"%prog [options]"`) The usage summary to print when your program is run incorrectly or with a help option. When *optparse* prints the usage string, it expands `%prog` to `os.path.basename(sys.argv[0])` (or to `prog` if you passed that keyword argument). To suppress a usage message, pass the special value `optparse.SUPPRESS_USAGE`.

option_list (default: `[]`) A list of `Option` objects to populate the parser with. The options in `option_list` are added after any options in `standard_option_list` (a class attribute that may be

set by `OptionParser` subclasses), but before any version or help options. Deprecated; use `add_option()` after creating the parser instead.

option_class (default: `optparse.Option`) Class to use when adding options to the parser in `add_option()`.

version (default: `None`) A version string to print when the user supplies a version option. If you supply a true value for `version`, `optparse` automatically adds a version option with the single option string `--version`. The substring `%prog` is expanded the same as for `usage`.

conflict_handler (default: `"error"`) Specifies what to do when options with conflicting option strings are added to the parser; see section *Conflicts between options*.

description (default: `None`) A paragraph of text giving a brief overview of your program. `optparse` reformats this paragraph to fit the current terminal width and prints it when the user requests help (after `usage`, but before the list of options).

formatter (default: a new `IndentedHelpFormatter`) An instance of `optparse.HelpFormatter` that will be used for printing help text. `optparse` provides two concrete classes for this purpose: `IndentedHelpFormatter` and `TitledHelpFormatter`.

add_help_option (default: `True`) If true, `optparse` will add a help option (with option strings `-h` and `--help`) to the parser.

prog The string to use when expanding `%prog` in `usage` and `version` instead of `os.path.basename(sys.argv[0])`.

epilog (default: `None`) A paragraph of help text to print after the option help.

Populating the parser

There are several ways to populate the parser with options. The preferred way is by using `OptionParser.add_option()`, as shown in section *Tutorial*. `add_option()` can be called in one of two ways:

- pass it an `Option` instance (as returned by `make_option()`)
- pass it any combination of positional and keyword arguments that are acceptable to `make_option()` (i.e., to the `Option` constructor), and it will create the `Option` instance for you

The other alternative is to pass a list of pre-constructed `Option` instances to the `OptionParser` constructor, as in:

```
option_list = [
    make_option("-f", "--filename",
                action="store", type="string", dest="filename"),
    make_option("-q", "--quiet",
                action="store_false", dest="verbose"),
]
parser = OptionParser(option_list=option_list)
```

(`make_option()` is a factory function for creating `Option` instances; currently it is an alias for the `Option` constructor. A future version of `optparse` may split `Option` into several classes, and `make_option()` will pick the right class to instantiate. Do not instantiate `Option` directly.)

Defining options

Each `Option` instance represents a set of synonymous command-line option strings, e.g. `-f` and `--file`. You can specify any number of short or long option strings, but you must specify at least one overall option string.

The canonical way to create an `Option` instance is with the `add_option()` method of `OptionParser`.

```
OptionParser.add_option(option)
OptionParser.add_option(*opt_str, attr=value, ...)
```

To define an option with only a short option string:

```
parser.add_option("-f", attr=value, ...)
```

And to define an option with only a long option string:

```
parser.add_option("--foo", attr=value, ...)
```

The keyword arguments define attributes of the new `Option` object. The most important option attribute is *action*, and it largely determines which other attributes are relevant or required. If you pass irrelevant option attributes, or fail to pass required ones, *optparse* raises an `OptionError` exception explaining your mistake.

An option's *action* determines what *optparse* does when it encounters this option on the command-line. The standard option actions hard-coded into *optparse* are:

"store" store this option's argument (default)

"store_const" store a constant value

"store_true" store a true value

"store_false" store a false value

"append" append this option's argument to a list

"append_const" append a constant value to a list

"count" increment a counter by one

"callback" call a specified function

"help" print a usage message including all options and the documentation for them

(If you don't supply an action, the default is `"store"`. For this action, you may also supply *type* and *dest* option attributes; see *Standard option actions*.)

As you can see, most actions involve storing or updating a value somewhere. *optparse* always creates a special object for this, conventionally called `options` (it happens to be an instance of `optparse.Values`). Option arguments (and various other values) are stored as attributes of this object, according to the *dest* (destination) option attribute.

For example, when you call

```
parser.parse_args()
```

one of the first things *optparse* does is create the `options` object:

```
options = Values()
```

If one of the options in this parser is defined with

```
parser.add_option("-f", "--file", action="store", type="string", dest="filename")
```

and the command-line being parsed includes any of the following:

```
-ffoo
-f foo
--file=foo
--file foo
```

then `optparse`, on seeing this option, will do the equivalent of

```
options.filename = "foo"
```

The `type` and `dest` option attributes are almost as important as `action`, but `action` is the only one that makes sense for *all* options.

Option attributes

The following option attributes may be passed as keyword arguments to `OptionParser.add_option()`. If you pass an option attribute that is not relevant to a particular option, or fail to pass a required option attribute, `optparse` raises `OptionError`.

Option.action
(default: "store")

Determines `optparse`'s behaviour when this option is seen on the command line; the available options are documented [here](#).

Option.type
(default: "string")

The argument type expected by this option (e.g., "string" or "int"); the available option types are documented [here](#).

Option.dest
(default: derived from option strings)

If the option's action implies writing or modifying a value somewhere, this tells `optparse` where to write it: `dest` names an attribute of the options object that `optparse` builds as it parses the command line.

Option.default
The value to use for this option's destination if the option is not seen on the command line. See also `OptionParser.set_defaults()`.

Option.nargs
(default: 1)

How many arguments of type `type` should be consumed when this option is seen. If > 1 , `optparse` will store a tuple of values to `dest`.

Option.const
For actions that store a constant value, the constant value to store.

Option.choices
For options of type "choice", the list of strings the user may choose from.

Option.callback
For options with action "callback", the callable to call when this option is seen. See section [Option Callbacks](#) for detail on the arguments passed to the callable.

Option.callback_args

Option.callback_kwargs

Additional positional and keyword arguments to pass to `callback` after the four standard callback arguments.

Option.help

Help text to print for this option when listing all available options after the user supplies a *help* option (such as `--help`). If no help text is supplied, the option will be listed without help text. To hide this option, use the special value `optparse.SUPPRESS_HELP`.

Option.metavar

(default: derived from option strings)

Stand-in for the option argument(s) to use when printing help text. See section *Tutorial* for an example.

Standard option actions

The various option actions all have slightly different requirements and effects. Most actions have several relevant option attributes which you may specify to guide *optparse*'s behaviour; a few have required attributes, which you must specify for any option using that action.

- "store" [relevant: *type*, *dest*, *nargs*, *choices*]

The option must be followed by an argument, which is converted to a value according to *type* and stored in *dest*. If *nargs* > 1, multiple arguments will be consumed from the command line; all will be converted according to *type* and stored to *dest* as a tuple. See the *Standard option types* section.

If *choices* is supplied (a list or tuple of strings), the type defaults to "choice".

If *type* is not supplied, it defaults to "string".

If *dest* is not supplied, *optparse* derives a destination from the first long option string (e.g., `--foo-bar` implies `foo_bar`). If there are no long option strings, *optparse* derives a destination from the first short option string (e.g., `-f` implies `f`).

Example:

```
parser.add_option("-f")
parser.add_option("-p", type="float", nargs=3, dest="point")
```

As it parses the command line

```
-f foo.txt -p 1 -3.5 4 -fbar.txt
```

optparse will set

```
options.f = "foo.txt"
options.point = (1.0, -3.5, 4.0)
options.f = "bar.txt"
```

- "store_const" [required: *const*; relevant: *dest*]

The value *const* is stored in *dest*.

Example:

```
parser.add_option("-q", "--quiet",
                  action="store_const", const=0, dest="verbose")
parser.add_option("-v", "--verbose",
                  action="store_const", const=1, dest="verbose")
parser.add_option("--noisy",
                  action="store_const", const=2, dest="verbose")
```

If `--noisy` is seen, *optparse* will set


```
options.verbose = 2
```

- "store_true" [relevant: *dest*]

A special case of "store_const" that stores a true value to *dest*.

- "store_false" [relevant: *dest*]

Like "store_true", but stores a false value.

Example:

```
parser.add_option("--clobber", action="store_true", dest="clobber")
parser.add_option("--no-clobber", action="store_false", dest="clobber")
```

- "append" [relevant: *type*, *dest*, *nargs*, *choices*]

The option must be followed by an argument, which is appended to the list in *dest*. If no default value for *dest* is supplied, an empty list is automatically created when *optparse* first encounters this option on the command-line. If *nargs* > 1, multiple arguments are consumed, and a tuple of length *nargs* is appended to *dest*.

The defaults for *type* and *dest* are the same as for the "store" action.

Example:

```
parser.add_option("-t", "--tracks", action="append", type="int")
```

If `-t3` is seen on the command-line, *optparse* does the equivalent of:

```
options.tracks = []
options.tracks.append(int("3"))
```

If, a little later on, `--tracks=4` is seen, it does:

```
options.tracks.append(int("4"))
```

The append action calls the append method on the current value of the option. This means that any default value specified must have an append method. It also means that if the default value is non-empty, the default elements will be present in the parsed value for the option, with any values from the command line appended after those default values:

```
>>> parser.add_option("--files", action="append", default=['~/mypkg/defaults'])
>>> opts, args = parser.parse_args(['--files', 'overrides.mypkg'])
>>> opts.files
['~/mypkg/defaults', 'overrides.mypkg']
```

- "append_const" [required: *const*; relevant: *dest*]

Like "store_const", but the value *const* is appended to *dest*; as with "append", *dest* defaults to None, and an empty list is automatically created the first time the option is encountered.

- "count" [relevant: *dest*]

Increment the integer stored at *dest*. If no default value is supplied, *dest* is set to zero before being incremented the first time.

Example:

```
parser.add_option("-v", action="count", dest="verbosity")
```

The first time `-v` is seen on the command line, *optparse* does the equivalent of:

```
options.verbosity = 0
options.verbosity += 1
```

Every subsequent occurrence of `-v` results in

```
options.verbosity += 1
```

- "callback" [required: *callback*; relevant: *type*, *nargs*, *callback_args*, *callback_kwargs*]

Call the function specified by *callback*, which is called as

```
func(option, opt_str, value, parser, *args, **kwargs)
```

See section *Option Callbacks* for more detail.

- "help"

Prints a complete help message for all the options in the current option parser. The help message is constructed from the usage string passed to `OptionParser`'s constructor and the *help* string passed to every option.

If no *help* string is supplied for an option, it will still be listed in the help message. To omit an option entirely, use the special value `optparse.SUPPRESS_HELP`.

optparse automatically adds a *help* option to all `OptionParsers`, so you do not normally need to create one.

Example:

```
from optparse import OptionParser, SUPPRESS_HELP

# usually, a help option is added automatically, but that can
# be suppressed using the add_help_option argument
parser = OptionParser(add_help_option=False)

parser.add_option("-h", "--help", action="help")
parser.add_option("-v", action="store_true", dest="verbose",
                  help="Be moderately verbose")
parser.add_option("--file", dest="filename",
                  help="Input file to read data from")
parser.add_option("--secret", help=SUPPRESS_HELP)
```

If *optparse* sees either `-h` or `--help` on the command line, it will print something like the following help message to stdout (assuming `sys.argv[0]` is `"foo.py"`):

```
Usage: foo.py [options]

Options:
  -h, --help            Show this help message and exit
  -v                    Be moderately verbose
  --file=FILENAME       Input file to read data from
```

After printing the help message, *optparse* terminates your process with `sys.exit(0)`.

- "version"

Prints the version number supplied to the `OptionParser` to stdout and exits. The version number is actually formatted and printed by the `print_version()` method of `OptionParser`. Generally only relevant if the *version* argument is supplied to the `OptionParser` constructor. As with *help* options, you will rarely create *version* options, since *optparse* automatically adds them when needed.

Standard option types

`optparse` has six built-in option types: "string", "int", "long", "choice", "float" and "complex". If you need to add new option types, see section [Extending `optparse`](#).

Arguments to string options are not checked or converted in any way: the text on the command line is stored in the destination (or passed to the callback) as-is.

Integer arguments (type "int" or "long") are parsed as follows:

- if the number starts with 0x, it is parsed as a hexadecimal number
- if the number starts with 0, it is parsed as an octal number
- if the number starts with 0b, it is parsed as a binary number
- otherwise, the number is parsed as a decimal number

The conversion is done by calling either `int()` or `long()` with the appropriate base (2, 8, 10, or 16). If this fails, so will `optparse`, although with a more useful error message.

"float" and "complex" option arguments are converted directly with `float()` and `complex()`, with similar error-handling.

"choice" options are a subtype of "string" options. The `choices` option attribute (a sequence of strings) defines the set of allowed option arguments. `optparse.check_choice()` compares user-supplied option arguments against this master list and raises `OptionValueError` if an invalid string is given.

Parsing arguments

The whole point of creating and populating an `OptionParser` is to call its `parse_args()` method:

```
(options, args) = parser.parse_args(args=None, values=None)
```

where the input parameters are

args the list of arguments to process (default: `sys.argv[1:]`)

values an `optparse.Values` object to store option arguments in (default: a new instance of `Values`) – if you give an existing object, the option defaults will not be initialized on it

and the return values are

options the same object that was passed in as `values`, or the `optparse.Values` instance created by `optparse`

args the leftover positional arguments after all options have been processed

The most common usage is to supply neither keyword argument. If you supply `values`, it will be modified with repeated `setattr()` calls (roughly one for every option argument stored to an option destination) and returned by `parse_args()`.

If `parse_args()` encounters any errors in the argument list, it calls the `OptionParser`'s `error()` method with an appropriate end-user error message. This ultimately terminates your process with an exit status of 2 (the traditional Unix exit status for command-line errors).

Querying and manipulating your option parser

The default behavior of the option parser can be customized slightly, and you can also poke around your option parser and see what's there. `OptionParser` provides several methods to help you out:

`OptionParser.disable_interspersed_args()`

Set parsing to stop on the first non-option. For example, if `-a` and `-b` are both simple options that take no arguments, `optparse` normally accepts this syntax:

```
prog -a arg1 -b arg2
```

and treats it as equivalent to

```
prog -a -b arg1 arg2
```

To disable this feature, call `disable_interspersed_args()`. This restores traditional Unix syntax, where option parsing stops with the first non-option argument.

Use this if you have a command processor which runs another command which has options of its own and you want to make sure these options don't get confused. For example, each command might have a different set of options.

`OptionParser.enable_interspersed_args()`

Set parsing to not stop on the first non-option, allowing interspersing switches with command arguments. This is the default behavior.

`OptionParser.get_option(opt_str)`

Returns the `Option` instance with the option string `opt_str`, or `None` if no options have that option string.

`OptionParser.has_option(opt_str)`

Return true if the `OptionParser` has an option with option string `opt_str` (e.g., `-q` or `--verbose`).

`OptionParser.remove_option(opt_str)`

If the `OptionParser` has an option corresponding to `opt_str`, that option is removed. If that option provided any other option strings, all of those option strings become invalid. If `opt_str` does not occur in any option belonging to this `OptionParser`, raises `ValueError`.

Conflicts between options

If you're not careful, it's easy to define options with conflicting option strings:

```
parser.add_option("-n", "--dry-run", ...)
...
parser.add_option("-n", "--noisy", ...)
```

(This is particularly true if you've defined your own `OptionParser` subclass with some standard options.)

Every time you add an option, `optparse` checks for conflicts with existing options. If it finds any, it invokes the current conflict-handling mechanism. You can set the conflict-handling mechanism either in the constructor:

```
parser = OptionParser(..., conflict_handler=handler)
```

or with a separate call:

```
parser.set_conflict_handler(handler)
```

The available conflict handlers are:

"error" (default) assume option conflicts are a programming error and raise `OptionConflictError`

"resolve" resolve option conflicts intelligently (see below)

As an example, let's define an `OptionParser` that resolves conflicts intelligently and add conflicting options to it:

```
parser = OptionParser(conflict_handler="resolve")
parser.add_option("-n", "--dry-run", ..., help="do no harm")
parser.add_option("-n", "--noisy", ..., help="be noisy")
```

At this point, `optparse` detects that a previously-added option is already using the `-n` option string. Since `conflict_handler` is "resolve", it resolves the situation by removing `-n` from the earlier option's list of option strings. Now `--dry-run` is the only way for the user to activate that option. If the user asks for help, the help message will reflect that:

```
Options:
  --dry-run      do no harm
  ...
  -n, --noisy    be noisy
```

It's possible to whittle away the option strings for a previously-added option until there are none left, and the user has no way of invoking that option from the command-line. In that case, `optparse` removes that option completely, so it doesn't show up in help text or anywhere else. Carrying on with our existing `OptionParser`:

```
parser.add_option("--dry-run", ..., help="new dry-run option")
```

At this point, the original `-n/--dry-run` option is no longer accessible, so `optparse` removes it, leaving this help text:

```
Options:
  ...
  -n, --noisy    be noisy
  --dry-run      new dry-run option
```

Cleanup

`OptionParser` instances have several cyclic references. This should not be a problem for Python's garbage collector, but you may wish to break the cyclic references explicitly by calling `destroy()` on your `OptionParser` once you are done with it. This is particularly useful in long-running applications where large object graphs are reachable from your `OptionParser`.

Other methods

`OptionParser` supports several other public methods:

`OptionParser.set_usage(usage)`

Set the usage string according to the rules described above for the `usage` constructor keyword argument. Passing `None` sets the default usage string; use `optparse.SUPPRESS_USAGE` to suppress a usage message.

`OptionParser.print_usage(file=None)`

Print the usage message for the current program (`self.usage`) to `file` (default `stdout`). Any occurrence of the string `%prog` in `self.usage` is replaced with the name of the current program. Does nothing if `self.usage` is empty or not defined.

`OptionParser.get_usage()`

Same as `print_usage()` but returns the usage string instead of printing it.

`OptionParser.set_defaults(dest=value, ...)`

Set default values for several option destinations at once. Using `set_defaults()` is the preferred way to set default values for options, since multiple options can share the same destination. For example, if several 《mode》 options all set the same destination, any one of them can set the default, and the last one wins:

```
parser.add_option("--advanced", action="store_const",
                  dest="mode", const="advanced",
                  default="novice")    # overridden below
parser.add_option("--novice", action="store_const",
                  dest="mode", const="novice",
                  default="advanced")  # overrides above setting
```

To avoid this confusion, use `set_defaults()`:

```
parser.set_defaults(mode="advanced")
parser.add_option("--advanced", action="store_const",
                  dest="mode", const="advanced")
parser.add_option("--novice", action="store_const",
                  dest="mode", const="novice")
```

15.5.4 Option Callbacks

When `optparse`'s built-in actions and types aren't quite enough for your needs, you have two choices: extend `optparse` or define a callback option. Extending `optparse` is more general, but overkill for a lot of simple cases. Quite often a simple callback is all you need.

There are two steps to defining a callback option:

- define the option itself using the "callback" action
- write the callback; this is a function (or method) that takes at least four arguments, as described below

Defining a callback option

As always, the easiest way to define a callback option is by using the `OptionParser.add_option()` method. Apart from `action`, the only option attribute you must specify is `callback`, the function to call:

```
parser.add_option("-c", action="callback", callback=my_callback)
```

`callback` is a function (or other callable object), so you must have already defined `my_callback()` when you create this callback option. In this simple case, `optparse` doesn't even know if `-c` takes any arguments, which usually means that the option takes no arguments—the mere presence of `-c` on the command-line is all it needs to know. In some circumstances, though, you might want your callback to consume an arbitrary number of command-line arguments. This is where writing callbacks gets tricky; it's covered later in this section.

`optparse` always passes four particular arguments to your callback, and it will only pass additional arguments if you specify them via `callback_args` and `callback_kwargs`. Thus, the minimal callback function signature is:

```
def my_callback(option, opt, value, parser):
```

The four arguments to a callback are described below.

There are several other option attributes that you can supply when you define a callback option:

type has its usual meaning: as with the "store" or "append" actions, it instructs `optparse` to consume one argument and convert it to `type`. Rather than storing the converted value(s) anywhere, though, `optparse` passes it to your callback function.

nargs also has its usual meaning: if it is supplied and > 1 , *optparse* will consume *nargs* arguments, each of which must be convertible to *type*. It then passes a tuple of converted values to your callback.

callback_args a tuple of extra positional arguments to pass to the callback

callback_kwargs a dictionary of extra keyword arguments to pass to the callback

How callbacks are called

All callbacks are called as follows:

```
func(option, opt_str, value, parser, *args, **kwargs)
```

where

option is the Option instance that's calling the callback

opt_str is the option string seen on the command-line that's triggering the callback. (If an abbreviated long option was used, *opt_str* will be the full, canonical option string—e.g. if the user puts `--foo` on the command-line as an abbreviation for `--foobar`, then *opt_str* will be `"--foobar"`.)

value is the argument to this option seen on the command-line. *optparse* will only expect an argument if *type* is set; the type of *value* will be the type implied by the option's type. If *type* for this option is `None` (no argument expected), then *value* will be `None`. If *nargs* > 1 , *value* will be a tuple of values of the appropriate type.

parser is the OptionParser instance driving the whole thing, mainly useful because you can access some other interesting data through its instance attributes:

parser.largs the current list of leftover arguments, ie. arguments that have been consumed but are neither options nor option arguments. Feel free to modify *parser.largs*, e.g. by adding more arguments to it. (This list will become *args*, the second return value of *parse_args()*.)

parser.rargs the current list of remaining arguments, ie. with *opt_str* and *value* (if applicable) removed, and only the arguments following them still there. Feel free to modify *parser.rargs*, e.g. by consuming more arguments.

parser.values the object where option values are by default stored (an instance of *optparse.OptionValues*). This lets callbacks use the same mechanism as the rest of *optparse* for storing option values; you don't need to mess around with globals or closures. You can also access or modify the value(s) of any options already encountered on the command-line.

args is a tuple of arbitrary positional arguments supplied via the *callback_args* option attribute.

kwargs is a dictionary of arbitrary keyword arguments supplied via *callback_kwargs*.

Raising errors in a callback

The callback function should raise *OptionValueError* if there are any problems with the option or its argument(s). *optparse* catches this and terminates the program, printing the error message you supply to *stderr*. Your message should be clear, concise, accurate, and mention the option at fault. Otherwise, the user will have a hard time figuring out what they did wrong.

Callback example 1: trivial callback

Here's an example of a callback option that takes no arguments, and simply records that the option was seen:

```
def record_foo_seen(option, opt_str, value, parser):
    parser.values.saw_foo = True

parser.add_option("--foo", action="callback", callback=record_foo_seen)
```

Of course, you could do that with the "store_true" action.

Callback example 2: check option order

Here's a slightly more interesting example: record the fact that -a is seen, but blow up if it comes after -b in the command-line.

```
def check_order(option, opt_str, value, parser):
    if parser.values.b:
        raise OptionValueError("can't use -a after -b")
    parser.values.a = 1
...
parser.add_option("-a", action="callback", callback=check_order)
parser.add_option("-b", action="store_true", dest="b")
```

Callback example 3: check option order (generalized)

If you want to re-use this callback for several similar options (set a flag, but blow up if -b has already been seen), it needs a bit of work: the error message and the flag that it sets must be generalized.

```
def check_order(option, opt_str, value, parser):
    if parser.values.b:
        raise OptionValueError("can't use %s after -b" % opt_str)
    setattr(parser.values, option.dest, 1)
...
parser.add_option("-a", action="callback", callback=check_order, dest='a')
parser.add_option("-b", action="store_true", dest="b")
parser.add_option("-c", action="callback", callback=check_order, dest='c')
```

Callback example 4: check arbitrary condition

Of course, you could put any condition in there—you're not limited to checking the values of already-defined options. For example, if you have options that should not be called when the moon is full, all you have to do is this:

```
def check_moon(option, opt_str, value, parser):
    if is_moon_full():
        raise OptionValueError("%s option invalid when moon is full"
                                % opt_str)
    setattr(parser.values, option.dest, 1)
...
parser.add_option("--foo",
                  action="callback", callback=check_moon, dest="foo")
```

(The definition of `is_moon_full()` is left as an exercise for the reader.)

Callback example 5: fixed arguments

Things get slightly more interesting when you define callback options that take a fixed number of arguments. Specifying that a callback option takes arguments is similar to defining a "store" or "append" option: if you define `type`, then the option takes one argument that must be convertible to that type; if you further define `nargs`, then the option takes `nargs` arguments.

Here's an example that just emulates the standard "store" action:

```
def store_value(option, opt_str, value, parser):
    setattr(parser.values, option.dest, value)
...
parser.add_option("--foo",
                  action="callback", callback=store_value,
                  type="int", nargs=3, dest="foo")
```

Note that `optparse` takes care of consuming 3 arguments and converting them to integers for you; all you have to do is store them. (Or whatever; obviously you don't need a callback for this example.)

Callback example 6: variable arguments

Things get hairy when you want an option to take a variable number of arguments. For this case, you must write a callback, as `optparse` doesn't provide any built-in capabilities for it. And you have to deal with certain intricacies of conventional Unix command-line parsing that `optparse` normally handles for you. In particular, callbacks should implement the conventional rules for bare `--` and `-` arguments:

- either `--` or `-` can be option arguments
- bare `--` (if not the argument to some option): halt command-line processing and discard the `--`
- bare `-` (if not the argument to some option): halt command-line processing but keep the `-` (append it to `parser.largs`)

If you want an option that takes a variable number of arguments, there are several subtle, tricky issues to worry about. The exact implementation you choose will be based on which trade-offs you're willing to make for your application (which is why `optparse` doesn't support this sort of thing directly).

Nevertheless, here's a stab at a callback for an option with variable arguments:

```
def vararg_callback(option, opt_str, value, parser):
    assert value is None
    value = []

    def floatable(str):
        try:
            float(str)
            return True
        except ValueError:
            return False

    for arg in parser.rargs:
        # stop on --foo like options
        if arg[:2] == "--" and len(arg) > 2:
            break
        # stop on -a, but not on -3 or -3.0
        if arg[:1] == "-" and len(arg) > 1 and not floatable(arg):
            break
        value.append(arg)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

del parser.rargs[:len(value)]
setattr(parser.values, option.dest, value)

...
parser.add_option("-c", "--callback", dest="vararg_attr",
                  action="callback", callback=vararg_callback)

```

15.5.5 Extending `optparse`

Since the two major controlling factors in how `optparse` interprets command-line options are the action and type of each option, the most likely direction of extension is to add new actions and new types.

Adding new types

To add new types, you need to define your own subclass of `optparse`'s `Option` class. This class has a couple of attributes that define `optparse`'s types: `TYPES` and `TYPE_CHECKER`.

`Option.TYPES`

A tuple of type names; in your subclass, simply define a new tuple `TYPES` that builds on the standard one.

`Option.TYPE_CHECKER`

A dictionary mapping type names to type-checking functions. A type-checking function has the following signature:

```
def check_mytype(option, opt, value)
```

where `option` is an `Option` instance, `opt` is an option string (e.g., `-f`), and `value` is the string from the command line that must be checked and converted to your desired type. `check_mytype()` should return an object of the hypothetical type `mytype`. The value returned by a type-checking function will wind up in the `OptionValues` instance returned by `OptionParser.parse_args()`, or be passed to a callback as the `value` parameter.

Your type-checking function should raise `OptionValueError` if it encounters any problems. `OptionValueError` takes a single string argument, which is passed as-is to `OptionParser`'s `error()` method, which in turn prepends the program name and the string `"error:"` and prints everything to `stderr` before terminating the process.

Here's a silly example that demonstrates adding a `"complex"` option type to parse Python-style complex numbers on the command line. (This is even sillier than it used to be, because `optparse` 1.3 added built-in support for complex numbers, but never mind.)

First, the necessary imports:

```

from copy import copy
from optparse import Option, OptionValueError

```

You need to define your type-checker first, since it's referred to later (in the `TYPE_CHECKER` class attribute of your `Option` subclass):

```

def check_complex(option, opt, value):
    try:
        return complex(value)
    except ValueError:
        raise OptionValueError(
            "option %s: invalid complex value: %r" % (opt, value))

```

Finally, the Option subclass:

```
class MyOption (Option):
    TYPES = Option.TYPES + ("complex",)
    TYPE_CHECKER = copy(Option.TYPE_CHECKER)
    TYPE_CHECKER["complex"] = check_complex
```

(If we didn't make a `copy()` of `Option.TYPE_CHECKER`, we would end up modifying the `TYPE_CHECKER` attribute of `optparse`'s Option class. This being Python, nothing stops you from doing that except good manners and common sense.)

That's it! Now you can write a script that uses the new option type just like any other `optparse`-based script, except you have to instruct your OptionParser to use MyOption instead of Option:

```
parser = OptionParser(option_class=MyOption)
parser.add_option("-c", type="complex")
```

Alternately, you can build your own option list and pass it to OptionParser; if you don't use `add_option()` in the above way, you don't need to tell OptionParser which option class to use:

```
option_list = [MyOption("-c", action="store", type="complex", dest="c")]
parser = OptionParser(option_list=option_list)
```

Adding new actions

Adding new actions is a bit trickier, because you have to understand that `optparse` has a couple of classifications for actions:

《store》actions actions that result in `optparse` storing a value to an attribute of the current OptionValues instance; these options require a `dest` attribute to be supplied to the Option constructor.

《typed》actions actions that take a value from the command line and expect it to be of a certain type; or rather, a string that can be converted to a certain type. These options require a `type` attribute to the Option constructor.

These are overlapping sets: some default 《store》actions are "store", "store_const", "append", and "count", while the default 《typed》actions are "store", "append", and "callback".

When you add an action, you need to categorize it by listing it in at least one of the following class attributes of Option (all are lists of strings):

`Option.ACTIONS`

All actions must be listed in ACTIONS.

`Option.STORE_ACTIONS`

《store》actions are additionally listed here.

`Option.TYPED_ACTIONS`

《typed》actions are additionally listed here.

`Option.ALWAYS_TYPED_ACTIONS`

Actions that always take a type (i.e. whose options always take a value) are additionally listed here. The only effect of this is that `optparse` assigns the default type, "string", to options with no explicit type whose action is listed in `ALWAYS_TYPED_ACTIONS`.

In order to actually implement your new action, you must override Option's `take_action()` method and add a case that recognizes your action.

For example, let's add an "extend" action. This is similar to the standard "append" action, but instead of taking a single value from the command-line and appending it to an existing list, "extend" will take multiple values in a single

comma-delimited string, and extend an existing list with them. That is, if `--names` is an "extend" option of type "string", the command line

```
--names=foo,bar --names blah --names ding,dong
```

would result in a list

```
["foo", "bar", "blah", "ding", "dong"]
```

Again we define a subclass of `Option`:

```
class MyOption(Option):

    ACTIONS = Option.ACTIONS + ("extend",)
    STORE_ACTIONS = Option.STORE_ACTIONS + ("extend",)
    TYPED_ACTIONS = Option.TYPED_ACTIONS + ("extend",)
    ALWAYS_TYPED_ACTIONS = Option.ALWAYS_TYPED_ACTIONS + ("extend",)

    def take_action(self, action, dest, opt, value, values, parser):
        if action == "extend":
            lvalue = value.split(",")
            values.ensure_value(dest, []).extend(lvalue)
        else:
            Option.take_action(
                self, action, dest, opt, value, values, parser)
```

Features of note:

- "extend" both expects a value on the command-line and stores that value somewhere, so it goes in both `STORE_ACTIONS` and `TYPED_ACTIONS`.
- to ensure that `optparse` assigns the default type of "string" to "extend" actions, we put the "extend" action in `ALWAYS_TYPED_ACTIONS` as well.
- `MyOption.take_action()` implements just this one new action, and passes control back to `Option.take_action()` for the standard `optparse` actions.
- `values` is an instance of the `optparse_parser.Values` class, which provides the very useful `ensure_value()` method. `ensure_value()` is essentially `getattr()` with a safety valve; it is called as

```
values.ensure_value(attr, value)
```

If the `attr` attribute of `values` doesn't exist or is `None`, then `ensure_value()` first sets it to `value`, and then returns `<value>`. This is very handy for actions like "extend", "append", and "count", all of which accumulate data in a variable and expect that variable to be of a certain type (a list for the first two, an integer for the latter). Using `ensure_value()` means that scripts using your action don't have to worry about setting a default value for the option destinations in question; they can just leave the default as `None` and `ensure_value()` will take care of getting it right when it's needed.

15.6 getopt — C-style parser for command line options

Source code: [Lib/getopt.py](#)

참고: The `getopt` module is a parser for command line options whose API is designed to be familiar to users of the `C getopt()` function. Users who are unfamiliar with the `C getopt()` function or who would like to write less code and get better help and error messages should consider using the `argparse` module instead.

This module helps scripts to parse the command line arguments in `sys.argv`. It supports the same conventions as the Unix `getopt()` function (including the special meanings of arguments of the form `<-<` and `<--<`). Long options similar to those supported by GNU software may be used as well via an optional third argument.

This module provides two functions and an exception:

`getopt.getopt(args, options[, long_options])`

Parses command line options and parameter list. *args* is the argument list to be parsed, without the leading reference to the running program. Typically, this means `sys.argv[1:]`. *options* is the string of option letters that the script wants to recognize, with options that require an argument followed by a colon (':'); i.e., the same format that Unix `getopt()` uses).

참고: Unlike GNU `getopt()`, after a non-option argument, all further arguments are considered also non-options. This is similar to the way non-GNU Unix systems work.

long_options, if specified, must be a list of strings with the names of the long options which should be supported. The leading `--` characters should not be included in the option name. Long options which require an argument should be followed by an equal sign ('='). Optional arguments are not supported. To accept only long options, *options* should be an empty string. Long options on the command line can be recognized so long as they provide a prefix of the option name that matches exactly one of the accepted options. For example, if *long_options* is `['foo', 'frob']`, the option `--fo` will match as `--foo`, but `--f` will not match uniquely, so `GetoptError` will be raised.

The return value consists of two elements: the first is a list of (option, value) pairs; the second is the list of program arguments left after the option list was stripped (this is a trailing slice of *args*). Each option-and-value pair returned has the option as its first element, prefixed with a hyphen for short options (e.g., `-x`) or two hyphens for long options (e.g., `--long-option`), and the option argument as its second element, or an empty string if the option has no argument. The options occur in the list in the same order in which they were found, thus allowing multiple occurrences. Long and short options may be mixed.

`getopt.gnu_getopt(args, options[, long_options])`

This function works like `getopt()`, except that GNU style scanning mode is used by default. This means that option and non-option arguments may be intermixed. The `getopt()` function stops processing options as soon as a non-option argument is encountered.

If the first character of the option string is '+', or if the environment variable `POSIXLY_CORRECT` is set, then option processing stops as soon as a non-option argument is encountered.

버전 2.3에 추가.

exception `getopt.GetoptError`

This is raised when an unrecognized option is found in the argument list or when an option requiring an argument is given none. The argument to the exception is a string indicating the cause of the error. For long options, an argument given to an option which does not require one will also cause this exception to be raised. The attributes `msg` and `opt` give the error message and related option; if there is no specific option to which the exception relates, `opt` is an empty string.

버전 1.6에서 변경: Introduced `GetoptError` as a synonym for `error`.

exception `getopt.error`

Alias for `GetoptError`; for backward compatibility.

An example using only Unix style options:

```
>>> import getopt
>>> args = '-a -b -cfoo -d bar a1 a2'.split()
>>> args
['-a', '-b', '-cfoo', '-d', 'bar', 'a1', 'a2']
>>> optlist, args = getopt.getopt(args, 'abc:d:')
>>> optlist
[('-a', ''), ('-b', ''), ('-c', 'foo'), ('-d', 'bar')]
>>> args
['a1', 'a2']
```

Using long option names is equally easy:

```
>>> s = '--condition=foo --testing --output-file abc.def -x a1 a2'
>>> args = s.split()
>>> args
['--condition=foo', '--testing', '--output-file', 'abc.def', '-x', 'a1', 'a2']
>>> optlist, args = getopt.getopt(args, 'x', [
...     'condition=', 'output-file=', 'testing'])
>>> optlist
[('--condition', 'foo'), ('--testing', ''), ('--output-file', 'abc.def'), ('-x', '')]
>>> args
['a1', 'a2']
```

In a script, typical usage is something like this:

```
import getopt, sys

def main():
    try:
        opts, args = getopt.getopt(sys.argv[1:], "ho:v", ["help", "output="])
    except getopt.GetoptError as err:
        # print help information and exit:
        print str(err) # will print something like "option -a not recognized"
        usage()
        sys.exit(2)
    output = None
    verbose = False
    for o, a in opts:
        if o == "-v":
            verbose = True
        elif o in ("-h", "--help"):
            usage()
            sys.exit()
        elif o in ("-o", "--output"):
            output = a
        else:
            assert False, "unhandled option"
    # ...

if __name__ == "__main__":
    main()
```

Note that an equivalent command line interface could be produced with less code and more informative help and error messages by using the `argparse` module:

```
import argparse

if __name__ == '__main__':
    parser = argparse.ArgumentParser()
    parser.add_argument('-o', '--output')
    parser.add_argument('-v', dest='verbose', action='store_true')
    args = parser.parse_args()
    # ... do something with args.output ...
    # ... do something with args.verbose ..
```

더 보기:

Module `argparse` Alternative command line option and argument parsing library.

15.7 logging — Logging facility for Python

Important

This page contains the API reference information. For tutorial information and discussion of more advanced topics, see

- Basic Tutorial
- Advanced Tutorial
- Logging Cookbook

Source code: `Lib/logging/__init__.py`

버전 2.3에 추가.

This module defines functions and classes which implement a flexible event logging system for applications and libraries.

The key benefit of having the logging API provided by a standard library module is that all Python modules can participate in logging, so your application log can include your own messages integrated with messages from third-party modules.

The module provides a lot of functionality and flexibility. If you are unfamiliar with logging, the best way to get to grips with it is to see the tutorials (see the links on the right).

The basic classes defined by the module, together with their functions, are listed below.

- Loggers expose the interface that application code directly uses.
- Handlers send the log records (created by loggers) to the appropriate destination.
- Filters provide a finer grained facility for determining which log records to output.
- Formatters specify the layout of log records in the final output.

15.7.1 Logger Objects

Loggers have the following attributes and methods. Note that Loggers are never instantiated directly, but always through the module-level function `logging.getLogger(name)`. Multiple calls to `getLogger()` with the same name will always return a reference to the same Logger object.

The name is potentially a period-separated hierarchical value, like `foo.bar.baz` (though it could also be just plain `foo`, for example). Loggers that are further down in the hierarchical list are children of loggers higher up in the list. For example, given a logger with a name of `foo`, loggers with names of `foo.bar`, `foo.bar.baz`, and `foo.bam` are all descendants of `foo`. The logger name hierarchy is analogous to the Python package hierarchy, and identical to it if you organise your loggers on a per-module basis using the recommended construction `logging.getLogger(__name__)`. That's because in a module, `__name__` is the module's name in the Python package namespace.

class `logging.Logger`

`Logger.propagate`

If this evaluates to true, events logged to this logger will be passed to the handlers of higher level (ancestor) loggers, in addition to any handlers attached to this logger. Messages are passed directly to the ancestor loggers' handlers - neither the level nor filters of the ancestor loggers in question are considered.

If this evaluates to false, logging messages are not passed to the handlers of ancestor loggers.

The constructor sets this attribute to `True`.

참고: If you attach a handler to a logger *and* one or more of its ancestors, it may emit the same record multiple times. In general, you should not need to attach a handler to more than one logger - if you just attach it to the appropriate logger which is highest in the logger hierarchy, then it will see all events logged by all descendant loggers, provided that their propagate setting is left set to `True`. A common scenario is to attach handlers only to the root logger, and to let propagation take care of the rest.

`Logger.setLevel(level)`

Sets the threshold for this logger to *level*. Logging messages which are less severe than *level* will be ignored. When a logger is created, the level is set to `NOTSET` (which causes all messages to be processed when the logger is the root logger, or delegation to the parent when the logger is a non-root logger). Note that the root logger is created with level `WARNING`.

The term <delegation to the parent> means that if a logger has a level of `NOTSET`, its chain of ancestor loggers is traversed until either an ancestor with a level other than `NOTSET` is found, or the root is reached.

If an ancestor is found with a level other than `NOTSET`, then that ancestor's level is treated as the effective level of the logger where the ancestor search began, and is used to determine how a logging event is handled.

If the root is reached, and it has a level of `NOTSET`, then all messages will be processed. Otherwise, the root's level will be used as the effective level.

See [Logging Levels](#) for a list of levels.

`Logger.isEnabledFor(lvl)`

Indicates if a message of severity *lvl* would be processed by this logger. This method checks first the module-level level set by `logging.disable(lvl)` and then the logger's effective level as determined by `getEffectiveLevel()`.

`Logger.getEffectiveLevel()`

Indicates the effective level for this logger. If a value other than `NOTSET` has been set using `setLevel()`, it is returned. Otherwise, the hierarchy is traversed towards the root until a value other than `NOTSET` is found, and that value is returned. The value returned is an integer, typically one of `logging.DEBUG`, `logging.INFO` etc.

`Logger.getChild(suffix)`

Returns a logger which is a descendant to this logger, as determined by the suffix. Thus, `logging.getLogger('abc').getChild('def.ghi')` would return the same logger as would be returned by `logging.getLogger('abc.def.ghi')`. This is a convenience method, useful when the parent logger is named using e.g. `__name__` rather than a literal string.

버전 2.7에 추가.

`Logger.debug(msg, *args, **kwargs)`

Logs a message with level `DEBUG` on this logger. The *msg* is the message format string, and the *args* are the arguments which are merged into *msg* using the string formatting operator. (Note that this means that you can use keywords in the format string, together with a single dictionary argument.)

There are two keyword arguments in *kwargs* which are inspected: *exc_info* which, if it does not evaluate as false, causes exception information to be added to the logging message. If an exception tuple (in the format returned by `sys.exc_info()`) is provided, it is used; otherwise, `sys.exc_info()` is called to get the exception information.

The second keyword argument is *extra* which can be used to pass a dictionary which is used to populate the `__dict__` of the `LogRecord` created for the logging event with user-defined attributes. These custom attributes can then be used as you like. For example, they could be incorporated into logged messages. For example:

```
FORMAT = '%(asctime)-15s %(clientip)s %(user)-8s %(message)s'
logging.basicConfig(format=FORMAT)
d = {'clientip': '192.168.0.1', 'user': 'fbloggs'}
logger = logging.getLogger('tcpserver')
logger.warning('Protocol problem: %s', 'connection reset', extra=d)
```

would print something like

```
2006-02-08 22:20:02,165 192.168.0.1 fbloggs Protocol problem: connection reset
```

The keys in the dictionary passed in *extra* should not clash with the keys used by the logging system. (See the *Formatter* documentation for more information on which keys are used by the logging system.)

If you choose to use these attributes in logged messages, you need to exercise some care. In the above example, for instance, the *Formatter* has been set up with a format string which expects `<clientip>` and `<user>` in the attribute dictionary of the `LogRecord`. If these are missing, the message will not be logged because a string formatting exception will occur. So in this case, you always need to pass the *extra* dictionary with these keys.

While this might be annoying, this feature is intended for use in specialized circumstances, such as multi-threaded servers where the same code executes in many contexts, and interesting conditions which arise are dependent on this context (such as remote client IP address and authenticated user name, in the above example). In such circumstances, it is likely that specialized *Formatters* would be used with particular *Handlers*.

`Logger.info(msg, *args, **kwargs)`

Logs a message with level `INFO` on this logger. The arguments are interpreted as for `debug()`.

`Logger.warning(msg, *args, **kwargs)`

Logs a message with level `WARNING` on this logger. The arguments are interpreted as for `debug()`.

`Logger.error(msg, *args, **kwargs)`

Logs a message with level `ERROR` on this logger. The arguments are interpreted as for `debug()`.

`Logger.critical(msg, *args, **kwargs)`

Logs a message with level `CRITICAL` on this logger. The arguments are interpreted as for `debug()`.

`Logger.log(lvl, msg, *args, **kwargs)`

Logs a message with integer level *lvl* on this logger. The other arguments are interpreted as for `debug()`.

`Logger.exception(msg, *args, **kwargs)`

Logs a message with level `ERROR` on this logger. The arguments are interpreted as for `debug()`, except that any passed `exc_info` is not inspected. Exception info is always added to the logging message. This method should only be called from an exception handler.

`Logger.addFilter(filter)`

Adds the specified filter *filter* to this logger.

`Logger.removeFilter(filter)`

Removes the specified filter *filter* from this logger.

`Logger.filter(record)`

Applies this logger's filters to the record and returns a true value if the record is to be processed. The filters are consulted in turn, until one of them returns a false value. If none of them return a false value, the record will be processed (passed to handlers). If one returns a false value, no further processing of the record occurs.

`Logger.addHandler(hdlr)`

Adds the specified handler *hdlr* to this logger.

`Logger.removeHandler(hdlr)`

Removes the specified handler *hdlr* from this logger.

`Logger.findCaller()`

Finds the caller's source filename and line number. Returns the filename, line number and function name as a 3-element tuple.

버전 2.4에서 변경: The function name was added. In earlier versions, the filename and line number were returned as a 2-element tuple.

`Logger.handle(record)`

Handles a record by passing it to all handlers associated with this logger and its ancestors (until a false value of *propagate* is found). This method is used for unpickled records received from a socket, as well as those created locally. Logger-level filtering is applied using `filter()`.

`Logger.makeRecord(name, lvl, fn, lno, msg, args, exc_info, func=None, extra=None)`

This is a factory method which can be overridden in subclasses to create specialized `LogRecord` instances.

버전 2.5에서 변경: *func* and *extra* were added.

15.7.2 Logging Levels

The numeric values of logging levels are given in the following table. These are primarily of interest if you want to define your own levels, and need them to have specific values relative to the predefined levels. If you define a level with the same numeric value, it overwrites the predefined value; the predefined name is lost.

Level	Numeric value
CRITICAL	50
ERROR	40
WARNING	30
INFO	20
DEBUG	10
NOTSET	0

15.7.3 Handler Objects

Handlers have the following attributes and methods. Note that `Handler` is never instantiated directly; this class acts as a base for more useful subclasses. However, the `__init__()` method in subclasses needs to call `Handler.__init__()`.

`Handler.__init__(level=NOTSET)`

Initializes the `Handler` instance by setting its level, setting the list of filters to the empty list and creating a lock (using `createLock()`) for serializing access to an I/O mechanism.

`Handler.createLock()`

Initializes a thread lock which can be used to serialize access to underlying I/O functionality which may not be threadsafe.

`Handler.acquire()`

Acquires the thread lock created with `createLock()`.

`Handler.release()`

Releases the thread lock acquired with `acquire()`.

`Handler.setLevel(level)`

Sets the threshold for this handler to *level*. Logging messages which are less severe than *level* will be ignored. When a handler is created, the level is set to `NOTSET` (which causes all messages to be processed).

See [Logging Levels](#) for a list of levels.

`Handler.setFormatter(fmt)`

Sets the *Formatter* for this handler to *fmt*.

`Handler.addFilter(filter)`

Adds the specified filter *filter* to this handler.

`Handler.removeFilter(filter)`

Removes the specified filter *filter* from this handler.

`Handler.filter(record)`

Applies this handler's filters to the record and returns a true value if the record is to be processed. The filters are consulted in turn, until one of them returns a false value. If none of them return a false value, the record will be emitted. If one returns a false value, the handler will not emit the record.

`Handler.flush()`

Ensure all logging output has been flushed. This version does nothing and is intended to be implemented by subclasses.

`Handler.close()`

Tidy up any resources used by the handler. This version does no output but removes the handler from an internal list of handlers which is closed when `shutdown()` is called. Subclasses should ensure that this gets called from overridden `close()` methods.

`Handler.handle(record)`

Conditionally emits the specified logging record, depending on filters which may have been added to the handler. Wraps the actual emission of the record with acquisition/release of the I/O thread lock.

`Handler.handleError(record)`

This method should be called from handlers when an exception is encountered during an `emit()` call. If the module-level attribute `raiseExceptions` is `False`, exceptions get silently ignored. This is what is mostly wanted for a logging system - most users will not care about errors in the logging system, they are more interested in application errors. You could, however, replace this with a custom handler if you wish. The specified record is the one which was being processed when the exception occurred. (The default value of `raiseExceptions` is `True`, as that is more useful during development).

`Handler.format(record)`

Do formatting for a record - if a formatter is set, use it. Otherwise, use the default formatter for the module.

`Handler.emit(record)`

Do whatever it takes to actually log the specified logging record. This version is intended to be implemented by subclasses and so raises a `NotImplementedError`.

For a list of handlers included as standard, see `logging.handlers`.

15.7.4 Formatter Objects

`Formatter` objects have the following attributes and methods. They are responsible for converting a `LogRecord` to (usually) a string which can be interpreted by either a human or an external system. The base `Formatter` allows a formatting string to be specified. If none is supplied, the default value of `'%(message)s'` is used, which just includes the message in the logging call. To have additional items of information in the formatted output (such as a timestamp), keep reading.

A Formatter can be initialized with a format string which makes use of knowledge of the `LogRecord` attributes - such as the default value mentioned above making use of the fact that the user's message and arguments are pre-formatted into a `LogRecord`'s `message` attribute. This format string contains standard Python %-style mapping keys. See section *String Formatting Operations* for more information on string formatting.

The useful mapping keys in a `LogRecord` are given in the section on *LogRecord attributes*.

class `logging.Formatter` (*fmt=None, datefmt=None*)

Returns a new instance of the `Formatter` class. The instance is initialized with a format string for the message as a whole, as well as a format string for the date/time portion of a message. If no *fmt* is specified, `'%(message)s'` is used. If no *datefmt* is specified, the ISO8601 date format is used.

format (*record*)

The record's attribute dictionary is used as the operand to a string formatting operation. Returns the resulting string. Before formatting the dictionary, a couple of preparatory steps are carried out. The `message` attribute of the record is computed using `msg % args`. If the formatting string contains `'(asctime)'`, `formatTime()` is called to format the event time. If there is exception information, it is formatted using `formatException()` and appended to the message. Note that the formatted exception information is cached in attribute `exc_text`. This is useful because the exception information can be pickled and sent across the wire, but you should be careful if you have more than one `Formatter` subclass which customizes the formatting of exception information. In this case, you will have to clear the cached value after a formatter has done its formatting, so that the next formatter to handle the event doesn't use the cached value but recalculates it afresh.

formatTime (*record, datefmt=None*)

This method should be called from `format()` by a formatter which wants to make use of a formatted time. This method can be overridden in formatters to provide for any specific requirement, but the basic behavior is as follows: if *datefmt* (a string) is specified, it is used with `time.strftime()` to format the creation time of the record. Otherwise, the ISO8601 format is used. The resulting string is returned.

This function uses a user-configurable function to convert the creation time to a tuple. By default, `time.localtime()` is used; to change this for a particular formatter instance, set the `converter` attribute to a function with the same signature as `time.localtime()` or `time.gmtime()`. To change it for all formatters, for example if you want all logging times to be shown in GMT, set the `converter` attribute in the `Formatter` class.

formatException (*exc_info*)

Formats the specified exception information (a standard exception tuple as returned by `sys.exc_info()`) as a string. This default implementation just uses `traceback.print_exception()`. The resulting string is returned.

15.7.5 Filter Objects

Filters can be used by Handlers and Loggers for more sophisticated filtering than is provided by levels. The base filter class only allows events which are below a certain point in the logger hierarchy. For example, a filter initialized with `<A.B>` will allow events logged by loggers `<A.B>`, `<A.B.C>`, `<A.B.C.D>`, `<A.B.D>` etc. but not `<A.BB>`, `<B.A.B>` etc. If initialized with the empty string, all events are passed.

class `logging.Filter` (*name=""*)

Returns an instance of the `Filter` class. If *name* is specified, it names a logger which, together with its children, will have its events allowed through the filter. If *name* is the empty string, allows every event.

filter (*record*)

Is the specified record to be logged? Returns zero for no, nonzero for yes. If deemed appropriate, the record may be modified in-place by this method.

Note that filters attached to handlers are consulted before an event is emitted by the handler, whereas filters attached to loggers are consulted whenever an event is logged (using `debug()`, `info()`, etc.), before sending an event to handlers. This means that events which have been generated by descendant loggers will not be filtered by a logger's filter setting, unless the filter has also been applied to those descendant loggers.

You don't actually need to subclass `Filter`: you can pass any instance which has a `filter` method with the same semantics.

Although filters are used primarily to filter records based on more sophisticated criteria than levels, they get to see every record which is processed by the handler or logger they're attached to: this can be useful if you want to do things like counting how many records were processed by a particular logger or handler, or adding, changing or removing attributes in the `LogRecord` being processed. Obviously changing the `LogRecord` needs to be done with some care, but it does allow the injection of contextual information into logs (see `filters-contextual`).

15.7.6 LogRecord Objects

`LogRecord` instances are created automatically by the `Logger` every time something is logged, and can be created manually via `makeLogRecord()` (for example, from a pickled event received over the wire).

class `logging.LogRecord` (*name, level, pathname, lineno, msg, args, exc_info, func=None*)

Contains all the information pertinent to the event being logged.

The primary information is passed in *msg* and *args*, which are combined using `msg % args` to create the message field of the record.

매개변수

- **name** – The name of the logger used to log the event represented by this `LogRecord`. Note that this name will always have this value, even though it may be emitted by a handler attached to a different (ancestor) logger.
- **level** – The numeric level of the logging event (one of `DEBUG`, `INFO` etc.) Note that this is converted to *two* attributes of the `LogRecord`: `lineno` for the numeric value and `levelname` for the corresponding level name.
- **pathname** – The full pathname of the source file where the logging call was made.
- **lineno** – The line number in the source file where the logging call was made.
- **msg** – The event description message, possibly a format string with placeholders for variable data.
- **args** – Variable data to merge into the *msg* argument to obtain the event description.

- **exc_info** – An exception tuple with the current exception information, or `None` if no exception information is available.
- **func** – The name of the function or method from which the logging call was invoked.

버전 2.5에서 변경: *func* was added.

getMessage()

Returns the message for this *LogRecord* instance after merging any user-supplied arguments with the message. If the user-supplied message argument to the logging call is not a string, *str()* is called on it to convert it to a string. This allows use of user-defined classes as messages, whose `__str__` method can return the actual format string to be used.

15.7.7 LogRecord attributes

The *LogRecord* has a number of attributes, most of which are derived from the parameters to the constructor. (Note that the names do not always correspond exactly between the *LogRecord* constructor parameters and the *LogRecord* attributes.) These attributes can be used to merge data from the record into the format string. The following table lists (in alphabetical order) the attribute names, their meanings and the corresponding placeholder in a %-style format string.

Attribute name	Format	Description
args	You shouldn't need to format this yourself.	The tuple of arguments merged into <code>msg</code> to produce <code>message</code> , or a dict whose values are used for the merge (when there is only one argument, and it is a dictionary).
asctime	<code>%(asctime)s</code>	Human-readable time when the <i>LogRecord</i> was created. By default this is of the form <code><2003-07-08 16:49:45,896></code> (the numbers after the comma are millisecond portion of the time).
created	<code>%(created)f</code>	Time when the <i>LogRecord</i> was created (as returned by <code>time.time()</code>).
exc_info	You shouldn't need to format this yourself.	Exception tuple (à la <code>sys.exc_info</code>) or, if no exception has occurred, <code>None</code> .
filename	<code>%(filename)s</code>	Filename portion of <code>pathname</code> .
funcName	<code>%(funcName)s</code>	Name of function containing the logging call.
levelname	<code>%(levelname)s</code>	Text logging level for the message ('DEBUG', 'INFO', 'WARNING', 'ERROR', 'CRITICAL').
levelno	<code>%(levelno)s</code>	Numeric logging level for the message (DEBUG, INFO, WARNING, ERROR, CRITICAL).
lineno	<code>%(lineno)d</code>	Source line number where the logging call was issued (if available).
module	<code>%(module)s</code>	Module (name portion of <code>filename</code>).
msecs	<code>%(msecs)d</code>	Millisecond portion of the time when the <i>LogRecord</i> was created.
message	<code>%(message)s</code>	The logged message, computed as <code>msg % args</code> . This is set when <i>Formatter.format()</i> is invoked.
msg	You shouldn't need to format this yourself.	The format string passed in the original logging call. Merged with <code>args</code> to produce <code>message</code> , or an arbitrary object (see arbitrary-object-messages).
name	<code>%(name)s</code>	Name of the logger used to log the call.
pathname	<code>%(pathname)s</code>	Full pathname of the source file where the logging call was issued (if available).
process	<code>%(process)d</code>	Process ID (if available).
processName	<code>%(processName)s</code>	Process name (if available).
relativeCreated	<code>%(relativeCreated)d</code>	Time in milliseconds when the <i>LogRecord</i> was created, relative to the time the logging module was loaded.
thread	<code>%(thread)d</code>	Thread ID (if available).
threadName	<code>%(threadName)s</code>	Thread name (if available).

버전 2.5에서 변경: *funcName* was added.

버전 2.6에서 변경: *processName* was added.

15.7.8 LoggerAdapter Objects

LoggerAdapter instances are used to conveniently pass contextual information into logging calls. For a usage example, see the section on adding contextual information to your logging output.

버전 2.6에 추가.

class logging.LoggerAdapter(*logger, extra*)

Returns an instance of *LoggerAdapter* initialized with an underlying *Logger* instance and a dict-like object.

process (*msg, kwargs*)

Modifies the message and/or keyword arguments passed to a logging call in order to insert contextual information. This implementation takes the object passed as *extra* to the constructor and adds it to *kwargs* using key `<extra>`. The return value is a (*msg, kwargs*) tuple which has the (possibly modified) versions of the arguments passed in.

In addition to the above, *LoggerAdapter* supports the following methods of *Logger*: *debug()*, *info()*, *warning()*, *error()*, *exception()*, *critical()*, *log()* and *isEnabledFor()*. These methods have the same signatures as their counterparts in *Logger*, so you can use the two types of instances interchangeably for these calls.

버전 2.7에서 변경: The *isEnabledFor()* method was added to *LoggerAdapter*. This method delegates to the underlying logger.

15.7.9 Thread Safety

The logging module is intended to be thread-safe without any special work needing to be done by its clients. It achieves this though using threading locks; there is one lock to serialize access to the module's shared data, and each handler also creates a lock to serialize access to its underlying I/O.

If you are implementing asynchronous signal handlers using the *signal* module, you may not be able to use logging from within such handlers. This is because lock implementations in the *threading* module are not always re-entrant, and so cannot be invoked from such signal handlers.

15.7.10 Module-Level Functions

In addition to the classes described above, there are a number of module-level functions.

logging.getLogger(*[name]*)

Return a logger with the specified name or, if no name is specified, return a logger which is the root logger of the hierarchy. If specified, the name is typically a dot-separated hierarchical name like `<a>`, `<a.b>` or `<a.b.c.d>`. Choice of these names is entirely up to the developer who is using logging.

All calls to this function with a given name return the same logger instance. This means that logger instances never need to be passed between different parts of an application.

logging.getLoggerClass()

Return either the standard *Logger* class, or the last class passed to *setLoggerClass()*. This function may be called from within a new class definition, to ensure that installing a customized *Logger* class will not undo customizations already applied by other code. For example:

```
class MyLogger(logging.getLoggerClass()):
    # ... override behaviour here
```

logging.debug(*msg[, *args[, **kwargs]]*)

Logs a message with level `DEBUG` on the root logger. The *msg* is the message format string, and the *args* are the

arguments which are merged into *msg* using the string formatting operator. (Note that this means that you can use keywords in the format string, together with a single dictionary argument.)

There are two keyword arguments in *kwargs* which are inspected: *exc_info* which, if it does not evaluate as false, causes exception information to be added to the logging message. If an exception tuple (in the format returned by `sys.exc_info()`) is provided, it is used; otherwise, `sys.exc_info()` is called to get the exception information.

The other optional keyword argument is *extra* which can be used to pass a dictionary which is used to populate the `__dict__` of the LogRecord created for the logging event with user-defined attributes. These custom attributes can then be used as you like. For example, they could be incorporated into logged messages. For example:

```
FORMAT = "%(asctime)-15s %(clientip)s %(user)-8s %(message)s"
logging.basicConfig(format=FORMAT)
d = {'clientip': '192.168.0.1', 'user': 'fbloggs'}
logging.warning("Protocol problem: %s", "connection reset", extra=d)
```

would print something like:

```
2006-02-08 22:20:02,165 192.168.0.1 fbloggs Protocol problem: connection reset
```

The keys in the dictionary passed in *extra* should not clash with the keys used by the logging system. (See the *Formatter* documentation for more information on which keys are used by the logging system.)

If you choose to use these attributes in logged messages, you need to exercise some care. In the above example, for instance, the *Formatter* has been set up with a format string which expects `<clientip>` and `<user>` in the attribute dictionary of the LogRecord. If these are missing, the message will not be logged because a string formatting exception will occur. So in this case, you always need to pass the *extra* dictionary with these keys.

While this might be annoying, this feature is intended for use in specialized circumstances, such as multi-threaded servers where the same code executes in many contexts, and interesting conditions which arise are dependent on this context (such as remote client IP address and authenticated user name, in the above example). In such circumstances, it is likely that specialized *Formatters* would be used with particular *Handlers*.

버전 2.5에서 변경: *extra* was added.

`logging.info(msg[, *args[, **kwargs]])`

Logs a message with level INFO on the root logger. The arguments are interpreted as for `debug()`.

`logging.warning(msg[, *args[, **kwargs]])`

Logs a message with level WARNING on the root logger. The arguments are interpreted as for `debug()`.

`logging.error(msg[, *args[, **kwargs]])`

Logs a message with level ERROR on the root logger. The arguments are interpreted as for `debug()`.

`logging.critical(msg[, *args[, **kwargs]])`

Logs a message with level CRITICAL on the root logger. The arguments are interpreted as for `debug()`.

`logging.exception(msg[, *args[, **kwargs]])`

Logs a message with level ERROR on the root logger. The arguments are interpreted as for `debug()`, except that any passed *exc_info* is not inspected. Exception info is always added to the logging message. This function should only be called from an exception handler.

`logging.log(level, msg[, *args[, **kwargs]])`

Logs a message with level *level* on the root logger. The other arguments are interpreted as for `debug()`.

참고: The above module-level convenience functions, which delegate to the root logger, call `basicConfig()` to ensure that at least one handler is available. Because of this, they should *not* be used in threads, in versions of Python earlier than 2.7.1 and 3.2, unless at least one handler has been added to the root logger *before* the threads are started. In earlier versions of Python, due to a thread safety shortcoming in `basicConfig()`, this can (under

rare circumstances) lead to handlers being added multiple times to the root logger, which can in turn lead to multiple messages for the same event.

`logging.disable(lvl)`

Provides an overriding level *lvl* for all loggers which takes precedence over the logger's own level. When the need arises to temporarily throttle logging output down across the whole application, this function can be useful. Its effect is to disable all logging calls of severity *lvl* and below, so that if you call it with a value of INFO, then all INFO and DEBUG events would be discarded, whereas those of severity WARNING and above would be processed according to the logger's effective level. If `logging.disable(logging.NOTSET)` is called, it effectively removes this overriding level, so that logging output again depends on the effective levels of individual loggers.

`logging.addLevelName(lvl, levelName)`

Associates level *lvl* with text *levelName* in an internal dictionary, which is used to map numeric levels to a textual representation, for example when a *Formatter* formats a message. This function can also be used to define your own levels. The only constraints are that all levels used must be registered using this function, levels should be positive integers and they should increase in increasing order of severity.

참고: If you are thinking of defining your own levels, please see the section on custom-levels.

`logging.getLevelName(lvl)`

Returns the textual representation of logging level *lvl*. If the level is one of the predefined levels CRITICAL, ERROR, WARNING, INFO or DEBUG then you get the corresponding string. If you have associated levels with names using `addLevelName()` then the name you have associated with *lvl* is returned. If a numeric value corresponding to one of the defined levels is passed in, the corresponding string representation is returned. Otherwise, the string `<Level %s> % lvl` is returned.

참고: Integer levels should be used when e.g. setting levels on instances of *Logger* and handlers. This function is used to convert between an integer level and the level name displayed in the formatted log output by means of the `%(levelname)s` format specifier (see *LogRecord attributes*).

`logging.makeLogRecord(attrdict)`

Creates and returns a new *LogRecord* instance whose attributes are defined by *attrdict*. This function is useful for taking a pickled *LogRecord* attribute dictionary, sent over a socket, and reconstituting it as a *LogRecord* instance at the receiving end.

`logging.basicConfig([**kwargs])`

Does basic configuration for the logging system by creating a *StreamHandler* with a default *Formatter* and adding it to the root logger. The functions `debug()`, `info()`, `warning()`, `error()` and `critical()` will call `basicConfig()` automatically if no handlers are defined for the root logger.

This function does nothing if the root logger already has handlers configured for it.

버전 2.4에서 변경: Formerly, `basicConfig()` did not take any keyword arguments.

참고: This function should be called from the main thread before other threads are started. In versions of Python prior to 2.7.1 and 3.2, if this function is called from multiple threads, it is possible (in rare circumstances) that a handler will be added to the root logger more than once, leading to unexpected results such as messages being duplicated in the log.

The following keyword arguments are supported.

Format	Description
<i>filename</i>	Specifies that a <code>FileHandler</code> be created, using the specified filename, rather than a <code>StreamHandler</code> .
<i>filemode</i>	If <i>filename</i> is specified, open the file in this mode. Defaults to 'a'.
<i>format</i>	Use the specified format string for the handler.
<i>datefmt</i>	Use the specified date/time format, as accepted by <code>time.strftime()</code> .
<i>level</i>	Set the root logger level to the specified <i>level</i> .
<i>stream</i>	Use the specified stream to initialize the <code>StreamHandler</code> . Note that this argument is incompatible with <i>filename</i> - if both are present, <i>stream</i> is ignored.

`logging.shutdown()`

Informs the logging system to perform an orderly shutdown by flushing and closing all handlers. This should be called at application exit and no further use of the logging system should be made after this call.

`logging.setLoggerClass(klass)`

Tells the logging system to use the class *klass* when instantiating a logger. The class should define `__init__()` such that only a name argument is required, and the `__init__()` should call `Logger.__init__()`. This function is typically called before any loggers are instantiated by applications which need to use custom logger behavior.

15.7.11 Integration with the warnings module

The `captureWarnings()` function can be used to integrate `logging` with the `warnings` module.

`logging.captureWarnings(capture)`

This function is used to turn the capture of warnings by logging on and off.

If *capture* is `True`, warnings issued by the `warnings` module will be redirected to the logging system. Specifically, a warning will be formatted using `warnings.formatwarning()` and the resulting string logged to a logger named 'py.warnings' with a severity of `WARNING`.

If *capture* is `False`, the redirection of warnings to the logging system will stop, and warnings will be redirected to their original destinations (i.e. those in effect before `captureWarnings(True)` was called).

더 보기:

Module `logging.config` Configuration API for the logging module.

Module `logging.handlers` Useful handlers included with the logging module.

PEP 282 - A Logging System The proposal which described this feature for inclusion in the Python standard library.

Original Python logging package This is the original source for the `logging` package. The version of the package available from this site is suitable for use with Python 1.5.2, 2.1.x and 2.2.x, which do not include the `logging` package in the standard library.

15.8 logging.config — Logging configuration

Important

This page contains only reference information. For tutorials, please see

- Basic Tutorial
- Advanced Tutorial

Source code: [Lib/logging/config.py](#)

This section describes the API for configuring the logging module.

15.8.1 Configuration functions

The following functions configure the logging module. They are located in the `logging.config` module. Their use is optional — you can configure the logging module using these functions or by making calls to the main API (defined in `logging` itself) and defining handlers which are declared either in `logging` or `logging.handlers`.

`logging.config.dictConfig(config)`

Takes the logging configuration from a dictionary. The contents of this dictionary are described in *Configuration dictionary schema* below.

If an error is encountered during configuration, this function will raise a `ValueError`, `TypeError`, `AttributeError` or `ImportError` with a suitably descriptive message. The following is a (possibly incomplete) list of conditions which will raise an error:

- A `level` which is not a string or which is a string not corresponding to an actual logging level.
- A `propagate` value which is not a boolean.
- An `id` which does not have a corresponding destination.
- A non-existent handler `id` found during an incremental call.
- An invalid logger name.
- Inability to resolve to an internal or external object.

Parsing is performed by the `DictConfigurator` class, whose constructor is passed the dictionary used for configuration, and has a `configure()` method. The `logging.config` module has a callable attribute `dictConfigClass` which is initially set to `DictConfigurator`. You can replace the value of `dictConfigClass` with a suitable implementation of your own.

`dictConfig()` calls `dictConfigClass` passing the specified dictionary, and then calls the `configure()` method on the returned object to put the configuration into effect:

```
def dictConfig(config):
    dictConfigClass(config).configure()
```

For example, a subclass of `DictConfigurator` could call `DictConfigurator.__init__()` in its own `__init__()`, then set up custom prefixes which would be usable in the subsequent `configure()` call. `dictConfigClass` would be bound to this new subclass, and then `dictConfig()` could be called exactly as in the default, uncustomized state.

버전 2.7에 추가.

`logging.config.fileConfig(fname, defaults=None, disable_existing_loggers=True)`

Reads the logging configuration from a `configparser`-format file named `fname`. The format of the file should be as described in *Configuration file format*. This function can be called several times from an application, allowing an end user to select from various pre-canned configurations (if the developer provides a mechanism to present the choices and load the chosen configuration).

매개변수

- **defaults** – Defaults to be passed to the ConfigParser can be specified in this argument.
- **disable_existing_loggers** – If specified as `False`, loggers which exist when this call is made are left enabled. The default is `True` because this enables old behaviour in a backward-compatible way. This behaviour is to disable any existing loggers unless they or their ancestors are explicitly named in the logging configuration.

버전 2.6에서 변경: The `disable_existing_loggers` keyword argument was added. Previously, existing loggers were *always* disabled.

`logging.config.listen(port=DEFAULT_LOGGING_CONFIG_PORT)`

Starts up a socket server on the specified port, and listens for new configurations. If no port is specified, the module's default `DEFAULT_LOGGING_CONFIG_PORT` is used. Logging configurations will be sent as a file suitable for processing by `fileConfig()`. Returns a `Thread` instance on which you can call `start()` to start the server, and which you can `join()` when appropriate. To stop the server, call `stopListening()`.

To send a configuration to the socket, read in the configuration file and send it to the socket as a string of bytes preceded by a four-byte length string packed in binary using `struct.pack('>L', n)`.

참고: Because portions of the configuration are passed through `eval()`, use of this function may open its users to a security risk. While the function only binds to a socket on `localhost`, and so does not accept connections from remote machines, there are scenarios where untrusted code could be run under the account of the process which calls `listen()`. Specifically, if the process calling `listen()` runs on a multi-user machine where users cannot trust each other, then a malicious user could arrange to run essentially arbitrary code in a victim user's process, simply by connecting to the victim's `listen()` socket and sending a configuration which runs whatever code the attacker wants to have executed in the victim's process. This is especially easy to do if the default port is used, but not hard even if a different port is used).

`logging.config.stopListening()`

Stops the listening server which was created with a call to `listen()`. This is typically called before calling `join()` on the return value from `listen()`.

15.8.2 Configuration dictionary schema

Describing a logging configuration requires listing the various objects to create and the connections between them; for example, you may create a handler named `<console>` and then say that the logger named `<startup>` will send its messages to the `<console>` handler. These objects aren't limited to those provided by the `logging` module because you might write your own formatter or handler class. The parameters to these classes may also need to include external objects such as `sys.stderr`. The syntax for describing these objects and connections is defined in *Object connections* below.

Dictionary Schema Details

The dictionary passed to `dictConfig()` must contain the following keys:

- *version* - to be set to an integer value representing the schema version. The only valid value at present is 1, but having this key allows the schema to evolve while still preserving backwards compatibility.

All other keys are optional, but if present they will be interpreted as described below. In all cases below where a `<configuring dict>` is mentioned, it will be checked for the special `'()'` key to see if a custom instantiation is required. If so, the mechanism described in *User-defined objects* below is used to create an instance; otherwise, the context is used to determine what to instantiate.

- *formatters* - the corresponding value will be a dict in which each key is a formatter id and each value is a dict describing how to configure the corresponding `Formatter` instance.

The configuring dict is searched for keys `format` and `datefmt` (with defaults of `None`) and these are used to construct a `Formatter` instance.

- *filters* - the corresponding value will be a dict in which each key is a filter id and each value is a dict describing how to configure the corresponding Filter instance.

The configuring dict is searched for the key `name` (defaulting to the empty string) and this is used to construct a `logging.Filter` instance.

- *handlers* - the corresponding value will be a dict in which each key is a handler id and each value is a dict describing how to configure the corresponding Handler instance.

The configuring dict is searched for the following keys:

- `class` (mandatory). This is the fully qualified name of the handler class.
- `level` (optional). The level of the handler.
- `formatter` (optional). The id of the formatter for this handler.
- `filters` (optional). A list of ids of the filters for this handler.

All *other* keys are passed through as keyword arguments to the handler's constructor. For example, given the snippet:

```
handlers:
  console:
    class : logging.StreamHandler
    formatter: brief
    level  : INFO
    filters: [allow_foo]
    stream : ext://sys.stdout
  file:
    class : logging.handlers.RotatingFileHandler
    formatter: precise
    filename: logconfig.log
    maxBytes: 1024
    backupCount: 3
```

the handler with id `console` is instantiated as a `logging.StreamHandler`, using `sys.stdout` as the underlying stream. The handler with id `file` is instantiated as a `logging.handlers.RotatingFileHandler` with the keyword arguments `filename='logconfig.log'`, `maxBytes=1024`, `backupCount=3`.

- *loggers* - the corresponding value will be a dict in which each key is a logger name and each value is a dict describing how to configure the corresponding Logger instance.

The configuring dict is searched for the following keys:

- `level` (optional). The level of the logger.
- `propagate` (optional). The propagation setting of the logger.
- `filters` (optional). A list of ids of the filters for this logger.
- `handlers` (optional). A list of ids of the handlers for this logger.

The specified loggers will be configured according to the level, propagation, filters and handlers specified.

- *root* - this will be the configuration for the root logger. Processing of the configuration will be as for any logger, except that the `propagate` setting will not be applicable.

- *incremental* - whether the configuration is to be interpreted as incremental to the existing configuration. This value defaults to `False`, which means that the specified configuration replaces the existing configuration with the same semantics as used by the existing `fileConfig()` API.

If the specified value is `True`, the configuration is processed as described in the section on *Incremental Configuration*.

- *disable_existing_loggers* - whether any existing loggers are to be disabled. This setting mirrors the parameter of the same name in `fileConfig()`. If absent, this parameter defaults to `True`. This value is ignored if *incremental* is `True`.

Incremental Configuration

It is difficult to provide complete flexibility for incremental configuration. For example, because objects such as filters and formatters are anonymous, once a configuration is set up, it is not possible to refer to such anonymous objects when augmenting a configuration.

Furthermore, there is not a compelling case for arbitrarily altering the object graph of loggers, handlers, filters, formatters at run-time, once a configuration is set up; the verbosity of loggers and handlers can be controlled just by setting levels (and, in the case of loggers, propagation flags). Changing the object graph arbitrarily in a safe way is problematic in a multi-threaded environment; while not impossible, the benefits are not worth the complexity it adds to the implementation.

Thus, when the `incremental` key of a configuration dict is present and is `True`, the system will completely ignore any `formatters` and `filters` entries, and process only the `level` settings in the `handlers` entries, and the `level` and `propagate` settings in the `loggers` and `root` entries.

Using a value in the configuration dict lets configurations to be sent over the wire as pickled dicts to a socket listener. Thus, the logging verbosity of a long-running application can be altered over time with no need to stop and restart the application.

Object connections

The schema describes a set of logging objects - loggers, handlers, formatters, filters - which are connected to each other in an object graph. Thus, the schema needs to represent connections between the objects. For example, say that, once configured, a particular logger has attached to it a particular handler. For the purposes of this discussion, we can say that the logger represents the source, and the handler the destination, of a connection between the two. Of course in the configured objects this is represented by the logger holding a reference to the handler. In the configuration dict, this is done by giving each destination object an id which identifies it unambiguously, and then using the id in the source object's configuration to indicate that a connection exists between the source and the destination object with that id.

So, for example, consider the following YAML snippet:

```
formatters:
  brief:
    # configuration for formatter with id 'brief' goes here
  precise:
    # configuration for formatter with id 'precise' goes here
handlers:
  h1: #This is an id
    # configuration of handler with id 'h1' goes here
    formatter: brief
  h2: #This is another id
    # configuration of handler with id 'h2' goes here
    formatter: precise
loggers:
  foo.bar.baz:
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
# other configuration for logger 'foo.bar.baz'
handlers: [h1, h2]
```

(Note: YAML used here because it's a little more readable than the equivalent Python source form for the dictionary.)

The ids for loggers are the logger names which would be used programmatically to obtain a reference to those loggers, e.g. `foo.bar.baz`. The ids for Formatters and Filters can be any string value (such as `brief`, `precise` above) and they are transient, in that they are only meaningful for processing the configuration dictionary and used to determine connections between objects, and are not persisted anywhere when the configuration call is complete.

The above snippet indicates that logger named `foo.bar.baz` should have two handlers attached to it, which are described by the handler ids `h1` and `h2`. The formatter for `h1` is that described by id `brief`, and the formatter for `h2` is that described by id `precise`.

User-defined objects

The schema supports user-defined objects for handlers, filters and formatters. (Loggers do not need to have different types for different instances, so there is no support in this configuration schema for user-defined logger classes.)

Objects to be configured are described by dictionaries which detail their configuration. In some places, the logging system will be able to infer from the context how an object is to be instantiated, but when a user-defined object is to be instantiated, the system will not know how to do this. In order to provide complete flexibility for user-defined object instantiation, the user needs to provide a *factory* - a callable which is called with a configuration dictionary and which returns the instantiated object. This is signalled by an absolute import path to the factory being made available under the special key `()`. Here's a concrete example:

```
formatters:
  brief:
    format: '%(message)s'
  default:
    format: '%(asctime)s %(levelname)-8s %(name)-15s %(message)s'
    datefmt: '%Y-%m-%d %H:%M:%S'
  custom:
    (): my.package.customFormatterFactory
    bar: baz
    spam: 99.9
    answer: 42
```

The above YAML snippet defines three formatters. The first, with id `brief`, is a standard `logging.Formatter` instance with the specified format string. The second, with id `default`, has a longer format and also defines the time format explicitly, and will result in a `logging.Formatter` initialized with those two format strings. Shown in Python source form, the `brief` and `default` formatters have configuration sub-dictionaries:

```
{
  'format' : '%(message)s'
}
```

and:

```
{
  'format' : '%(asctime)s %(levelname)-8s %(name)-15s %(message)s',
  'datefmt' : '%Y-%m-%d %H:%M:%S'
}
```


respectively, and as these dictionaries do not contain the special key '()' , the instantiation is inferred from the context: as a result, standard `logging.Formatter` instances are created. The configuration sub-dictionary for the third formatter, with id `custom`, is:

```
{
    '()' : 'my.package.customFormatterFactory',
    'bar' : 'baz',
    'spam' : 99.9,
    'answer' : 42
}
```

and this contains the special key '()' , which means that user-defined instantiation is wanted. In this case, the specified factory callable will be used. If it is an actual callable it will be used directly - otherwise, if you specify a string (as in the example) the actual callable will be located using normal import mechanisms. The callable will be called with the **remaining** items in the configuration sub-dictionary as keyword arguments. In the above example, the formatter with id `custom` will be assumed to be returned by the call:

```
my.package.customFormatterFactory(bar='baz', spam=99.9, answer=42)
```

The key '()' has been used as the special key because it is not a valid keyword parameter name, and so will not clash with the names of the keyword arguments used in the call. The '()' also serves as a mnemonic that the corresponding value is a callable.

Access to external objects

There are times where a configuration needs to refer to objects external to the configuration, for example `sys.stderr`. If the configuration dict is constructed using Python code, this is straightforward, but a problem arises when the configuration is provided via a text file (e.g. JSON, YAML). In a text file, there is no standard way to distinguish `sys.stderr` from the literal string `'sys.stderr'`. To facilitate this distinction, the configuration system looks for certain special prefixes in string values and treat them specially. For example, if the literal string `'ext://sys.stderr'` is provided as a value in the configuration, then the `ext://` will be stripped off and the remainder of the value processed using normal import mechanisms.

The handling of such prefixes is done in a way analogous to protocol handling: there is a generic mechanism to look for prefixes which match the regular expression `^(?P<prefix>[a-z]+) :// (?P<suffix>.*)$` whereby, if the `prefix` is recognised, the `suffix` is processed in a prefix-dependent manner and the result of the processing replaces the string value. If the prefix is not recognised, then the string value will be left as-is.

Access to internal objects

As well as external objects, there is sometimes also a need to refer to objects in the configuration. This will be done implicitly by the configuration system for things that it knows about. For example, the string value `'DEBUG'` for a level in a logger or handler will automatically be converted to the value `logging.DEBUG`, and the `handlers`, `filters` and `formatter` entries will take an object id and resolve to the appropriate destination object.

However, a more generic mechanism is needed for user-defined objects which are not known to the `logging` module. For example, consider `logging.handlers.MemoryHandler`, which takes a `target` argument which is another handler to delegate to. Since the system already knows about this class, then in the configuration, the given `target` just needs to be the object id of the relevant target handler, and the system will resolve to the handler from the id. If, however, a user defines a `my.package.MyHandler` which has an `alternate` handler, the configuration system would not know that the `alternate` referred to a handler. To cater for this, a generic resolution system allows the user to specify:

```
handlers:
    file:
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
# configuration of file handler goes here

custom:
    (): my.package.MyHandler
    alternate: cfg://handlers.file
```

The literal string `'cfg://handlers.file'` will be resolved in an analogous way to strings with the `ext://` prefix, but looking in the configuration itself rather than the import namespace. The mechanism allows access by dot or by index, in a similar way to that provided by `str.format`. Thus, given the following snippet:

```
handlers:
    email:
        class: logging.handlers.SMTPHandler
        mailhost: localhost
        fromaddr: my_app@domain.tld
        toaddrs:
            - support_team@domain.tld
            - dev_team@domain.tld
        subject: Houston, we have a problem.
```

in the configuration, the string `'cfg://handlers'` would resolve to the dict with key `handlers`, the string `'cfg://handlers.email'` would resolve to the dict with key `email` in the `handlers` dict, and so on. The string `'cfg://handlers.email.toaddrs[1]'` would resolve to `'dev_team.domain.tld'` and the string `'cfg://handlers.email.toaddrs[0]'` would resolve to the value `'support_team@domain.tld'`. The subject value could be accessed using either `'cfg://handlers.email.subject'` or, equivalently, `'cfg://handlers.email[subject]'`. The latter form only needs to be used if the key contains spaces or non-alphanumeric characters. If an index value consists only of decimal digits, access will be attempted using the corresponding integer value, falling back to the string value if needed.

Given a string `cfg://handlers.myhandler.mykey.123`, this will resolve to `config_dict['handlers']['myhandler']['mykey']['123']`. If the string is specified as `cfg://handlers.myhandler.mykey[123]`, the system will attempt to retrieve the value from `config_dict['handlers']['myhandler']['mykey'][123]`, and fall back to `config_dict['handlers']['myhandler']['mykey']['123']` if that fails.

Import resolution and custom importers

Import resolution, by default, uses the builtin `__import__()` function to do its importing. You may want to replace this with your own importing mechanism: if so, you can replace the `importer` attribute of the `DictConfigurator` or its superclass, the `BaseConfigurator` class. However, you need to be careful because of the way functions are accessed from classes via descriptors. If you are using a Python callable to do your imports, and you want to define it at class level rather than instance level, you need to wrap it with `staticmethod()`. For example:

```
from importlib import import_module
from logging.config import BaseConfigurator

BaseConfigurator.importer = staticmethod(import_module)
```

You don't need to wrap with `staticmethod()` if you're setting the import callable on a configurator *instance*.

15.8.3 Configuration file format

The configuration file format understood by `fileConfig()` is based on `configparser` functionality. The file must contain sections called `[loggers]`, `[handlers]` and `[formatters]` which identify by name the entities of each type which are defined in the file. For each such entity, there is a separate section which identifies how that entity is configured. Thus, for a logger named `log01` in the `[loggers]` section, the relevant configuration details are held in a section `[logger_log01]`. Similarly, a handler called `hand01` in the `[handlers]` section will have its configuration held in a section called `[handler_hand01]`, while a formatter called `form01` in the `[formatters]` section will have its configuration specified in a section called `[formatter_form01]`. The root logger configuration must be specified in a section called `[logger_root]`.

참고: The `fileConfig()` API is older than the `dictConfig()` API and does not provide functionality to cover certain aspects of logging. For example, you cannot configure `Filter` objects, which provide for filtering of messages beyond simple integer levels, using `fileConfig()`. If you need to have instances of `Filter` in your logging configuration, you will need to use `dictConfig()`. Note that future enhancements to configuration functionality will be added to `dictConfig()`, so it's worth considering transitioning to this newer API when it's convenient to do so.

Examples of these sections in the file are given below.

```
[loggers]
keys=root,log02,log03,log04,log05,log06,log07

[handlers]
keys=hand01,hand02,hand03,hand04,hand05,hand06,hand07,hand08,hand09

[formatters]
keys=form01,form02,form03,form04,form05,form06,form07,form08,form09
```

The root logger must specify a level and a list of handlers. An example of a root logger section is given below.

```
[logger_root]
level=NOTSET
handlers=hand01
```

The `level` entry can be one of `DEBUG`, `INFO`, `WARNING`, `ERROR`, `CRITICAL` or `NOTSET`. For the root logger only, `NOTSET` means that all messages will be logged. Level values are `eval()`uated in the context of the logging package's namespace.

The `handlers` entry is a comma-separated list of handler names, which must appear in the `[handlers]` section. These names must appear in the `[handlers]` section and have corresponding sections in the configuration file.

For loggers other than the root logger, some additional information is required. This is illustrated by the following example.

```
[logger_parser]
level=DEBUG
handlers=hand01
propagate=1
qualname=compiler.parser
```

The `level` and `handlers` entries are interpreted as for the root logger, except that if a non-root logger's level is specified as `NOTSET`, the system consults loggers higher up the hierarchy to determine the effective level of the logger. The `propagate` entry is set to 1 to indicate that messages must propagate to handlers higher up the logger hierarchy from this logger, or 0 to indicate that messages are **not** propagated to handlers up the hierarchy. The `qualname` entry is the hierarchical channel name of the logger, that is to say the name used by the application to get the logger.

Sections which specify handler configuration are exemplified by the following.

```
[handler_hand01]
class=StreamHandler
level=NOTSET
formatter=form01
args=(sys.stdout,)
```

The `class` entry indicates the handler's class (as determined by `eval()` in the `logging` package's namespace). The `level` is interpreted as for loggers, and `NOTSET` is taken to mean <log everything>.

버전 2.6에서 변경: Added support for resolving the handler's class as a dotted module and class name.

The `formatter` entry indicates the key name of the formatter for this handler. If blank, a default formatter (`logging._defaultFormatter`) is used. If a name is specified, it must appear in the `[formatters]` section and have a corresponding section in the configuration file.

The `args` entry, when `eval()` uated in the context of the `logging` package's namespace, is the list of arguments to the constructor for the handler class. Refer to the constructors for the relevant handlers, or to the examples below, to see how typical entries are constructed.

```
[handler_hand02]
class=FileHandler
level=DEBUG
formatter=form02
args=('python.log', 'w')

[handler_hand03]
class=handlers.SocketHandler
level=INFO
formatter=form03
args=('localhost', handlers.DEFAULT_TCP_LOGGING_PORT)

[handler_hand04]
class=handlers.DatagramHandler
level=WARN
formatter=form04
args=('localhost', handlers.DEFAULT_UDP_LOGGING_PORT)

[handler_hand05]
class=handlers.SysLogHandler
level=ERROR
formatter=form05
args= (('localhost', handlers.SYSLOG_UDP_PORT), handlers.SysLogHandler.LOG_USER)

[handler_hand06]
class=handlers.NTEventLogHandler
level=CRITICAL
formatter=form06
args=('Python Application', '', 'Application')

[handler_hand07]
class=handlers.SMTPHandler
level=WARN
formatter=form07
args=('localhost', 'from@abc', ['user1@abc', 'user2@xyz'], 'Logger Subject')

[handler_hand08]
class=handlers.MemoryHandler
level=NOTSET
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

formatter=form08
target=
args=(10, ERROR)

[handler_hand09]
class=handlers.HTTPHandler
level=NOTSET
formatter=form09
args=('localhost:9022', '/log', 'GET')

```

Sections which specify formatter configuration are typified by the following.

```

[formatter_form01]
format=F1 %(asctime)s %(levelname)s %(message)s
datefmt=
class=logging.Formatter

```

The `format` entry is the overall format string, and the `datefmt` entry is the `strftime()`-compatible date/time format string. If empty, the package substitutes ISO8601 format date/times, which is almost equivalent to specifying the date format string `'%Y-%m-%d %H:%M:%S'`. The ISO8601 format also specifies milliseconds, which are appended to the result of using the above format string, with a comma separator. An example time in ISO8601 format is `2003-01-23 00:29:50,411`.

The `class` entry is optional. It indicates the name of the formatter's class (as a dotted module and class name.) This option is useful for instantiating a *Formatter* subclass. Subclasses of *Formatter* can present exception tracebacks in an expanded or condensed format.

참고: Due to the use of `eval()` as described above, there are potential security risks which result from using the `listen()` to send and receive configurations via sockets. The risks are limited to where multiple users with no mutual trust run code on the same machine; see the `listen()` documentation for more information.

더 보기:

Module `logging` API reference for the logging module.

Module `logging.handlers` Useful handlers included with the logging module.

15.9 logging.handlers — Logging handlers

Important

This page contains only reference information. For tutorials, please see

- Basic Tutorial
- Advanced Tutorial
- Logging Cookbook

Source code: [Lib/logging/handlers.py](#)

The following useful handlers are provided in the package. Note that three of the handlers (*StreamHandler*, *FileHandler* and *NullHandler*) are actually defined in the *logging* module itself, but have been documented here along with the other handlers.

15.9.1 StreamHandler

The *StreamHandler* class, located in the core *logging* package, sends logging output to streams such as *sys.stdout*, *sys.stderr* or any file-like object (or, more precisely, any object which supports *write()* and *flush()* methods).

class *logging.StreamHandler* (*stream=None*)

Returns a new instance of the *StreamHandler* class. If *stream* is specified, the instance will use it for logging output; otherwise, *sys.stderr* will be used.

emit (*record*)

If a formatter is specified, it is used to format the record. The record is then written to the stream with a newline terminator. If exception information is present, it is formatted using *traceback.print_exception()* and appended to the stream.

flush ()

Flushes the stream by calling its *flush()* method. Note that the *close()* method is inherited from *Handler* and so does no output, so an explicit *flush()* call may be needed at times.

15.9.2 FileHandler

The *FileHandler* class, located in the core *logging* package, sends logging output to a disk file. It inherits the output functionality from *StreamHandler*.

class *logging.FileHandler* (*filename, mode='a', encoding=None, delay=False*)

Returns a new instance of the *FileHandler* class. The specified file is opened and used as the stream for logging. If *mode* is not specified, 'a' is used. If *encoding* is not *None*, it is used to open the file with that encoding. If *delay* is true, then file opening is deferred until the first call to *emit()*. By default, the file grows indefinitely.

버전 2.6에서 변경: *delay* was added.

close ()

Closes the file.

emit (*record*)

Outputs the record to the file.

15.9.3 NullHandler

버전 2.7에 추가.

The *NullHandler* class, located in the core *logging* package, does not do any formatting or output. It is essentially a <no-op> handler for use by library developers.

class *logging.NullHandler*

Returns a new instance of the *NullHandler* class.

emit (*record*)

This method does nothing.

handle (*record*)

This method does nothing.

createLock()

This method returns `None` for the lock, since there is no underlying I/O to which access needs to be serialized.

See `library-config` for more information on how to use `NullHandler`.

15.9.4 WatchedFileHandler

버전 2.6에 추가.

The `WatchedFileHandler` class, located in the `logging.handlers` module, is a `FileHandler` which watches the file it is logging to. If the file changes, it is closed and reopened using the file name.

A file change can happen because of usage of programs such as `newsyslog` and `logrotate` which perform log file rotation. This handler, intended for use under Unix/Linux, watches the file to see if it has changed since the last emit. (A file is deemed to have changed if its device or inode have changed.) If the file has changed, the old file stream is closed, and the file opened to get a new stream.

This handler is not appropriate for use under Windows, because under Windows open log files cannot be moved or renamed - logging opens the files with exclusive locks - and so there is no need for such a handler. Furthermore, `ST_INO` is not supported under Windows; `stat()` always returns zero for this value.

class `logging.handlers.WatchedFileHandler` (`filename`[, `mode`[, `encoding`[, `delay`]]])

Returns a new instance of the `WatchedFileHandler` class. The specified file is opened and used as the stream for logging. If `mode` is not specified, 'a' is used. If `encoding` is not `None`, it is used to open the file with that encoding. If `delay` is true, then file opening is deferred until the first call to `emit()`. By default, the file grows indefinitely.

emit(record)

Outputs the record to the file, but first checks to see if the file has changed. If it has, the existing stream is flushed and closed and the file opened again, before outputting the record to the file.

15.9.5 RotatingFileHandler

The `RotatingFileHandler` class, located in the `logging.handlers` module, supports rotation of disk log files.

class `logging.handlers.RotatingFileHandler` (`filename`, `mode`='a', `maxBytes`=0, `backupCount`=0, `encoding`=None, `delay`=0)

Returns a new instance of the `RotatingFileHandler` class. The specified file is opened and used as the stream for logging. If `mode` is not specified, 'a' is used. If `encoding` is not `None`, it is used to open the file with that encoding. If `delay` is true, then file opening is deferred until the first call to `emit()`. By default, the file grows indefinitely.

You can use the `maxBytes` and `backupCount` values to allow the file to *rollover* at a predetermined size. When the size is about to be exceeded, the file is closed and a new file is silently opened for output. Rollover occurs whenever the current log file is nearly `maxBytes` in length; if either of `maxBytes` or `backupCount` is zero, rollover never occurs. If `backupCount` is non-zero, the system will save old log files by appending the extensions <.1>, <.2> etc., to the filename. For example, with a `backupCount` of 5 and a base file name of `app.log`, you would get `app.log`, `app.log.1`, `app.log.2`, up to `app.log.5`. The file being written to is always `app.log`. When this file is filled, it is closed and renamed to `app.log.1`, and if files `app.log.1`, `app.log.2`, etc. exist, then they are renamed to `app.log.2`, `app.log.3` etc. respectively.

버전 2.6에서 변경: `delay` was added.

doRollover()

Does a rollover, as described above.

emit (*record*)

Outputs the record to the file, catering for rollover as described previously.

15.9.6 TimedRotatingFileHandler

The *TimedRotatingFileHandler* class, located in the *logging.handlers* module, supports rotation of disk log files at certain timed intervals.

class logging.handlers.**TimedRotatingFileHandler** (*filename*, *when='h'*, *interval=1*, *backupCount=0*, *encoding=None*, *delay=False*, *utc=False*)

Returns a new instance of the *TimedRotatingFileHandler* class. The specified file is opened and used as the stream for logging. On rotating it also sets the filename suffix. Rotating happens based on the product of *when* and *interval*.

You can use the *when* to specify the type of *interval*. The list of possible values is below. Note that they are not case sensitive.

Value	Type of interval
'S'	Seconds
'M'	Minutes
'H'	Hours
'D'	Days
'W0'-'W6'	Weekday (0=Monday)
'midnight'	Roll over at midnight

When using weekday-based rotation, specify <W0> for Monday, <W1> for Tuesday, and so on up to <W6> for Sunday. In this case, the value passed for *interval* isn't used.

The system will save old log files by appending extensions to the filename. The extensions are date-and-time based, using the strftime format `%Y-%m-%d_%H-%M-%S` or a leading portion thereof, depending on the rollover interval.

When computing the next rollover time for the first time (when the handler is created), the last modification time of an existing log file, or else the current time, is used to compute when the next rotation will occur.

If the *utc* argument is true, times in UTC will be used; otherwise local time is used.

If *backupCount* is nonzero, at most *backupCount* files will be kept, and if more would be created when rollover occurs, the oldest one is deleted. The deletion logic uses the interval to determine which files to delete, so changing the interval may leave old files lying around.

If *delay* is true, then file opening is deferred until the first call to *emit()*.

버전 2.6에서 변경: *delay* and *utc* were added.

doRollover ()

Does a rollover, as described above.

emit (*record*)

Outputs the record to the file, catering for rollover as described above.

15.9.7 SocketHandler

The *SocketHandler* class, located in the *logging.handlers* module, sends logging output to a network socket. The base class uses a TCP socket.

class *logging.handlers.SocketHandler* (*host*, *port*)

Returns a new instance of the *SocketHandler* class intended to communicate with a remote machine whose address is given by *host* and *port*.

close ()

Closes the socket.

emit ()

Pickles the record's attribute dictionary and writes it to the socket in binary format. If there is an error with the socket, silently drops the packet. If the connection was previously lost, re-establishes the connection. To unpickle the record at the receiving end into a *LogRecord*, use the *makeLogRecord* () function.

handleError ()

Handles an error which has occurred during *emit* (). The most likely cause is a lost connection. Closes the socket so that we can retry on the next event.

makeSocket ()

This is a factory method which allows subclasses to define the precise type of socket they want. The default implementation creates a TCP socket (*socket.SOCK_STREAM*).

makePickle (*record*)

Pickles the record's attribute dictionary in binary format with a length prefix, and returns it ready for transmission across the socket.

Note that pickles aren't completely secure. If you are concerned about security, you may want to override this method to implement a more secure mechanism. For example, you can sign pickles using HMAC and then verify them on the receiving end, or alternatively you can disable unpickling of global objects on the receiving end.

send (*packet*)

Send a pickled string *packet* to the socket. This function allows for partial sends which can happen when the network is busy.

createSocket ()

Tries to create a socket; on failure, uses an exponential back-off algorithm. On initial failure, the handler will drop the message it was trying to send. When subsequent messages are handled by the same instance, it will not try connecting until some time has passed. The default parameters are such that the initial delay is one second, and if after that delay the connection still can't be made, the handler will double the delay each time up to a maximum of 30 seconds.

This behaviour is controlled by the following handler attributes:

- *retryStart* (initial delay, defaulting to 1.0 seconds).
- *retryFactor* (multiplier, defaulting to 2.0).
- *retryMax* (maximum delay, defaulting to 30.0 seconds).

This means that if the remote listener starts up *after* the handler has been used, you could lose messages (since the handler won't even attempt a connection until the delay has elapsed, but just silently drop messages during the delay period).

15.9.8 DatagramHandler

The *DatagramHandler* class, located in the *logging.handlers* module, inherits from *SocketHandler* to support sending logging messages over UDP sockets.

class logging.handlers.**DatagramHandler** (*host*, *port*)
Returns a new instance of the *DatagramHandler* class intended to communicate with a remote machine whose address is given by *host* and *port*.

emit ()
Pickles the record's attribute dictionary and writes it to the socket in binary format. If there is an error with the socket, silently drops the packet. To unpickle the record at the receiving end into a *LogRecord*, use the *makeLogRecord()* function.

makeSocket ()
The factory method of *SocketHandler* is here overridden to create a UDP socket (*socket.SOCK_DGRAM*).

send (*s*)
Send a pickled string to a socket.

15.9.9 SysLogHandler

The *SysLogHandler* class, located in the *logging.handlers* module, supports sending logging messages to a remote or local Unix syslog.

class logging.handlers.**SysLogHandler** (*address*=(*'localhost'*, *SYSLOG_UDP_PORT*), *facility*=*LOG_USER*, *sockettype*=*socket.SOCK_DGRAM*)
Returns a new instance of the *SysLogHandler* class intended to communicate with a remote Unix machine whose address is given by *address* in the form of a (*host*, *port*) tuple. If *address* is not specified, (*'localhost'*, 514) is used. The address is used to open a socket. An alternative to providing a (*host*, *port*) tuple is providing an address as a string, for example *</dev/log>*. In this case, a Unix domain socket is used to send the message to the syslog. If *facility* is not specified, *LOG_USER* is used. The type of socket opened depends on the *sockettype* argument, which defaults to *socket.SOCK_DGRAM* and thus opens a UDP socket. To open a TCP socket (for use with the newer syslog daemons such as rsyslog), specify a value of *socket.SOCK_STREAM*.

Note that if your server is not listening on UDP port 514, *SysLogHandler* may appear not to work. In that case, check what address you should be using for a domain socket - it's system dependent. For example, on Linux it's usually *</dev/log>* but on OS/X it's *</var/run/syslog>*. You'll need to check your platform and use the appropriate address (you may need to do this check at runtime if your application needs to run on several platforms). On Windows, you pretty much have to use the UDP option.

버전 2.7에서 변경: *sockettype* was added.

close ()
Closes the socket to the remote host.

emit (*record*)
The record is formatted, and then sent to the syslog server. If exception information is present, it is *not* sent to the server.

encodePriority (*facility*, *priority*)
Encodes the facility and priority into an integer. You can pass in strings or integers - if strings are passed, internal mapping dictionaries are used to convert them to integers.

The symbolic *LOG_* values are defined in *SysLogHandler* and mirror the values defined in the *sys/syslog.h* header file.

Priorities

Name (string)	Symbolic value
alert	LOG_ALERT
crit or critical	LOG_CRIT
debug	LOG_DEBUG
emerg or panic	LOG_EMERG
err or error	LOG_ERR
info	LOG_INFO
notice	LOG_NOTICE
warn or warning	LOG_WARNING

Facilities

Name (string)	Symbolic value
auth	LOG_AUTH
authpriv	LOG_AUTHPRIV
cron	LOG_CRON
daemon	LOG_DAEMON
ftp	LOG_FTP
kern	LOG_KERN
lpr	LOG_LPR
mail	LOG_MAIL
news	LOG_NEWS
syslog	LOG_SYSLOG
user	LOG_USER
uucp	LOG_UUCP
local0	LOG_LOCAL0
local1	LOG_LOCAL1
local2	LOG_LOCAL2
local3	LOG_LOCAL3
local4	LOG_LOCAL4
local5	LOG_LOCAL5
local6	LOG_LOCAL6
local7	LOG_LOCAL7

mapPriority (*levelname*)

Maps a logging level name to a syslog priority name. You may need to override this if you are using custom levels, or if the default algorithm is not suitable for your needs. The default algorithm maps `DEBUG`, `INFO`, `WARNING`, `ERROR` and `CRITICAL` to the equivalent syslog names, and all other level names to `<warning>`.

15.9.10 NTEventLogHandler

The `NTEventLogHandler` class, located in the `logging.handlers` module, supports sending logging messages to a local Windows NT, Windows 2000 or Windows XP event log. Before you can use it, you need Mark Hammond's Win32 extensions for Python installed.

class `logging.handlers.NTEventLogHandler` (*appname*, *dllname=None*, *logtype='Application'*)

Returns a new instance of the `NTEventLogHandler` class. The *appname* is used to define the application name as it appears in the event log. An appropriate registry entry is created using this name. The *dllname* should give the fully qualified pathname of a .dll or .exe which contains message definitions to hold in the log (if not specified, 'win32service.pyd' is used - this is installed with the Win32 extensions and contains some basic placeholder message definitions. Note that use of these placeholders will make your event logs big, as the entire message source

is held in the log. If you want slimmer logs, you have to pass in the name of your own .dll or .exe which contains the message definitions you want to use in the event log). The *logtype* is one of 'Application', 'System' or 'Security', and defaults to 'Application'.

close()

At this point, you can remove the application name from the registry as a source of event log entries. However, if you do this, you will not be able to see the events as you intended in the Event Log Viewer - it needs to be able to access the registry to get the .dll name. The current version does not do this.

emit(record)

Determines the message ID, event category and event type, and then logs the message in the NT event log.

getEventCategory(record)

Returns the event category for the record. Override this if you want to specify your own categories. This version returns 0.

getEventType(record)

Returns the event type for the record. Override this if you want to specify your own types. This version does a mapping using the handler's *typemap* attribute, which is set up in `__init__()` to a dictionary which contains mappings for `DEBUG`, `INFO`, `WARNING`, `ERROR` and `CRITICAL`. If you are using your own levels, you will either need to override this method or place a suitable dictionary in the handler's *typemap* attribute.

getMessageID(record)

Returns the message ID for the record. If you are using your own messages, you could do this by having the *msg* passed to the logger being an ID rather than a format string. Then, in here, you could use a dictionary lookup to get the message ID. This version returns 1, which is the base message ID in `win32service.pyd`.

15.9.11 SMTPHandler

The *SMTPHandler* class, located in the `logging.handlers` module, supports sending logging messages to an email address via SMTP.

class `logging.handlers.SMTPHandler` (*mailhost*, *fromaddr*, *toaddrs*, *subject*, *credentials=None*, *secure=None*)

Returns a new instance of the *SMTPHandler* class. The instance is initialized with the from and to addresses and subject line of the email. The *toaddrs* should be a list of strings. To specify a non-standard SMTP port, use the (host, port) tuple format for the *mailhost* argument. If you use a string, the standard SMTP port is used. If your SMTP server requires authentication, you can specify a (username, password) tuple for the *credentials* argument.

To specify the use of a secure protocol (TLS), pass in a tuple to the *secure* argument. This will only be used when authentication credentials are supplied. The tuple should be either an empty tuple, or a single-value tuple with the name of a keyfile, or a 2-value tuple with the names of the keyfile and certificate file. (This tuple is passed to the `smtplib.SMTP.starttls()` method.)

버전 2.6에서 변경: *credentials* was added.

버전 2.7에서 변경: *secure* was added.

emit(record)

Formats the record and sends it to the specified addressees.

getSubject(record)

If you want to specify a subject line which is record-dependent, override this method.

15.9.12 MemoryHandler

The *MemoryHandler* class, located in the *logging.handlers* module, supports buffering of logging records in memory, periodically flushing them to a *target* handler. Flushing occurs whenever the buffer is full, or when an event of a certain severity or greater is seen.

MemoryHandler is a subclass of the more general *BufferingHandler*, which is an abstract class. This buffers logging records in memory. Whenever each record is added to the buffer, a check is made by calling *shouldFlush()* to see if the buffer should be flushed. If it should, then *flush()* is expected to do the flushing.

class *logging.handlers.BufferingHandler* (*capacity*)

Initializes the handler with a buffer of the specified capacity.

emit (*record*)

Appends the record to the buffer. If *shouldFlush()* returns true, calls *flush()* to process the buffer.

flush ()

You can override this to implement custom flushing behavior. This version just zaps the buffer to empty.

shouldFlush (*record*)

Returns true if the buffer is up to capacity. This method can be overridden to implement custom flushing strategies.

class *logging.handlers.MemoryHandler* (*capacity*, *flushLevel=ERROR*, *target=None*)

Returns a new instance of the *MemoryHandler* class. The instance is initialized with a buffer size of *capacity*. If *flushLevel* is not specified, *ERROR* is used. If no *target* is specified, the target will need to be set using *setTarget()* before this handler does anything useful.

close ()

Calls *flush()*, sets the target to *None* and clears the buffer.

flush ()

For a *MemoryHandler*, flushing means just sending the buffered records to the target, if there is one. The buffer is also cleared when this happens. Override if you want different behavior.

setTarget (*target*)

Sets the target handler for this handler.

shouldFlush (*record*)

Checks for buffer full or a record at the *flushLevel* or higher.

15.9.13 HTTPHandler

The *HTTPHandler* class, located in the *logging.handlers* module, supports sending logging messages to a Web server, using either GET or POST semantics.

class *logging.handlers.HTTPHandler* (*host*, *url*, *method='GET'*)

Returns a new instance of the *HTTPHandler* class. The *host* can be of the form *host:port*, should you need to use a specific port number.

mapLogRecord (*record*)

Provides a dictionary, based on *record*, which is to be URL-encoded and sent to the web server. The default implementation just returns *record.__dict__*. This method can be overridden if e.g. only a subset of *LogRecord* is to be sent to the web server, or if more specific customization of what's sent to the server is required.

emit (*record*)

Sends the record to the Web server as a URL-encoded dictionary. The *mapLogRecord()* method is used to convert the record to the dictionary to be sent.

참고: Since preparing a record for sending it to a Web server is not the same as a generic formatting operation, using `setFormatter()` to specify a `Formatter` for a `HTTPHandler` has no effect. Instead of calling `format()`, this handler calls `mapLogRecord()` and then `urllib.urlencode()` to encode the dictionary in a form suitable for sending to a Web server.

더 보기:

Module `logging` API reference for the logging module.

Module `logging.config` Configuration API for the logging module.

15.10 `getpass` — Portable password input

The `getpass` module provides two functions:

`getpass.getpass([prompt[, stream]])`

Prompt the user for a password without echoing. The user is prompted using the string `prompt`, which defaults to 'Password: '. On Unix, the prompt is written to the file-like object `stream`. `stream` defaults to the controlling terminal (`/dev/tty`) or if that is unavailable to `sys.stderr` (this argument is ignored on Windows).

If echo free input is unavailable `getpass()` falls back to printing a warning message to `stream` and reading from `sys.stdin` and issuing a `GetPassWarning`.

버전 2.5에서 변경: The `stream` parameter was added.

버전 2.6에서 변경: On Unix it defaults to using `/dev/tty` before falling back to `sys.stdin` and `sys.stderr`.

참고: If you call `getpass` from within IDLE, the input may be done in the terminal you launched IDLE from rather than the idle window itself.

exception `getpass.GetPassWarning`

A `UserWarning` subclass issued when password input may be echoed.

`getpass.getuser()`

Return the `<login name>` of the user.

This function checks the environment variables `LOGNAME`, `USER`, `LNAME` and `USERNAME`, in order, and returns the value of the first one which is set to a non-empty string. If none are set, the login name from the password database is returned on systems which support the `pwd` module, otherwise, an exception is raised.

15.11 `curses` — Terminal handling for character-cell displays

버전 1.6에서 변경: Added support for the `ncurses` library and converted to a package.

The `curses` module provides an interface to the `curses` library, the de-facto standard for portable advanced terminal handling.

While `curses` is most widely used in the Unix environment, versions are available for DOS, OS/2, and possibly other systems as well. This extension module is designed to match the API of `ncurses`, an open-source `curses` library hosted on Linux and the BSD variants of Unix.

참고: Since version 5.4, the `ncurses` library decides how to interpret non-ASCII data using the `nl_langinfo` function. That means that you have to call `locale.setlocale()` in the application and encode Unicode strings using one of the system's available encodings. This example uses the system's default encoding:

```
import locale
locale.setlocale(locale.LC_ALL, '')
code = locale.getpreferredencoding()
```

Then use `code` as the encoding for `str.encode()` calls.

더 보기:

Module `curses.ascii` Utilities for working with ASCII characters, regardless of your locale settings.

Module `curses.panel` A panel stack extension that adds depth to `curses` windows.

Module `curses.textpad` Editable text widget for `curses` supporting **Emacs**-like bindings.

`curses-howto` Tutorial material on using `curses` with Python, by Andrew Kuchling and Eric Raymond.

The `Demo/curses/` directory in the Python source distribution contains some example programs using the `curses` bindings provided by this module.

15.11.1 Functions

The module `curses` defines the following exception:

exception `curses.error`

Exception raised when a `curses` library function returns an error.

참고: Whenever `x` or `y` arguments to a function or a method are optional, they default to the current cursor location. Whenever `attr` is optional, it defaults to `A_NORMAL`.

The module `curses` defines the following functions:

`curses.baudrate()`

Return the output speed of the terminal in bits per second. On software terminal emulators it will have a fixed high value. Included for historical reasons; in former times, it was used to write output loops for time delays and occasionally to change interfaces depending on the line speed.

`curses.beep()`

Emit a short attention sound.

`curses.can_change_color()`

Return `True` or `False`, depending on whether the programmer can change the colors displayed by the terminal.

`curses.cbreak()`

Enter `cbreak` mode. In `cbreak` mode (sometimes called «rare» mode) normal tty line buffering is turned off and characters are available to be read one by one. However, unlike raw mode, special characters (interrupt, quit, suspend, and flow control) retain their effects on the tty driver and calling program. Calling first `raw()` then `cbreak()` leaves the terminal in `cbreak` mode.

`curses.color_content(color_number)`

Return the intensity of the red, green, and blue (RGB) components in the color `color_number`, which must be between 0 and `COLORS`. A 3-tuple is returned, containing the R,G,B values for the given color, which will be between 0 (no component) and 1000 (maximum amount of component).

`curses.color_pair(color_number)`

Return the attribute value for displaying text in the specified color. This attribute value can be combined with `A_STANDOUT`, `A_REVERSE`, and the other `A_*` attributes. `pair_number()` is the counterpart to this function.

`curses.curs_set(visibility)`

Set the cursor state. *visibility* can be set to 0, 1, or 2, for invisible, normal, or very visible. If the terminal supports the visibility requested, the previous cursor state is returned; otherwise, an exception is raised. On many terminals, the «visible» mode is an underline cursor and the «very visible» mode is a block cursor.

`curses.def_prog_mode()`

Save the current terminal mode as the «program» mode, the mode when the running program is using curses. (Its counterpart is the «shell» mode, for when the program is not in curses.) Subsequent calls to `reset_prog_mode()` will restore this mode.

`curses.def_shell_mode()`

Save the current terminal mode as the «shell» mode, the mode when the running program is not using curses. (Its counterpart is the «program» mode, when the program is using curses capabilities.) Subsequent calls to `reset_shell_mode()` will restore this mode.

`curses.delay_output(ms)`

Insert an *ms* millisecond pause in output.

`curses.doupdate()`

Update the physical screen. The curses library keeps two data structures, one representing the current physical screen contents and a virtual screen representing the desired next state. The `doupdate()` ground updates the physical screen to match the virtual screen.

The virtual screen may be updated by a `noutrefresh()` call after write operations such as `addstr()` have been performed on a window. The normal `refresh()` call is simply `noutrefresh()` followed by `doupdate()`; if you have to update multiple windows, you can speed performance and perhaps reduce screen flicker by issuing `noutrefresh()` calls on all windows, followed by a single `doupdate()`.

`curses.echo()`

Enter echo mode. In echo mode, each character input is echoed to the screen as it is entered.

`curses.endwin()`

De-initialize the library, and return terminal to normal status.

`curses.erasechar()`

Return the user's current erase character. Under Unix operating systems this is a property of the controlling tty of the curses program, and is not set by the curses library itself.

`curses.filter()`

The `filter()` routine, if used, must be called before `initscr()` is called. The effect is that, during those calls, `LINES` is set to 1; the capabilities `clear`, `cup`, `cud`, `cud1`, `cuu1`, `cuu`, `vpa` are disabled; and the home string is set to the value of `cr`. The effect is that the cursor is confined to the current line, and so are screen updates. This may be used for enabling character-at-a-time line editing without touching the rest of the screen.

`curses.flash()`

Flash the screen. That is, change it to reverse-video and then change it back in a short interval. Some people prefer such as «visible bell» to the audible attention signal produced by `beep()`.

`curses.flushinp()`

Flush all input buffers. This throws away any typeahead that has been typed by the user and has not yet been processed by the program.

`curses.getmouse()`

After `getch()` returns `KEY_MOUSE` to signal a mouse event, this method should be call to retrieve the queued mouse event, represented as a 5-tuple (*id*, *x*, *y*, *z*, *bstate*). *id* is an ID value used to distinguish multiple devices, and *x*, *y*, *z* are the event's coordinates. (*z* is currently unused.) *bstate* is an integer value

whose bits will be set to indicate the type of event, and will be the bitwise OR of one or more of the following constants, where *n* is the button number from 1 to 4: `BUTTONn_PRESSED`, `BUTTONn_RELEASED`, `BUTTONn_CLICKED`, `BUTTONn_DOUBLE_CLICKED`, `BUTTONn_TRIPLE_CLICKED`, `BUTTON_SHIFT`, `BUTTON_CTRL`, `BUTTON_ALT`.

`curses.getsyx()`

Return the current coordinates of the virtual screen cursor in *y* and *x*. If `leaveok` is currently true, then `-1,-1` is returned.

`curses.getwin(file)`

Read window related data stored in the file by an earlier `putwin()` call. The routine then creates and initializes a new window using that data, returning the new window object.

`curses.has_colors()`

Return True if the terminal can display colors; otherwise, return False.

`curses.has_ic()`

Return True if the terminal has insert- and delete-character capabilities. This function is included for historical reasons only, as all modern software terminal emulators have such capabilities.

`curses.has_il()`

Return True if the terminal has insert- and delete-line capabilities, or can simulate them using scrolling regions. This function is included for historical reasons only, as all modern software terminal emulators have such capabilities.

`curses.has_key(ch)`

Take a key value *ch*, and return True if the current terminal type recognizes a key with that value.

`curses.halfdelay(tenths)`

Used for half-delay mode, which is similar to `cbreak` mode in that characters typed by the user are immediately available to the program. However, after blocking for *tenths* tenths of seconds, an exception is raised if nothing has been typed. The value of *tenths* must be a number between 1 and 255. Use `nocbreak()` to leave half-delay mode.

`curses.init_color(color_number, r, g, b)`

Change the definition of a color, taking the number of the color to be changed followed by three RGB values (for the amounts of red, green, and blue components). The value of *color_number* must be between 0 and `COLORS`. Each of *r*, *g*, *b*, must be a value between 0 and 1000. When `init_color()` is used, all occurrences of that color on the screen immediately change to the new definition. This function is a no-op on most terminals; it is active only if `can_change_color()` returns 1.

`curses.init_pair(pair_number, fg, bg)`

Change the definition of a color-pair. It takes three arguments: the number of the color-pair to be changed, the foreground color number, and the background color number. The value of *pair_number* must be between 1 and `COLOR_PAIRS - 1` (the 0 color pair is wired to white on black and cannot be changed). The value of *fg* and *bg* arguments must be between 0 and `COLORS`. If the color-pair was previously initialized, the screen is refreshed and all occurrences of that color-pair are changed to the new definition.

`curses.initscr()`

Initialize the library. Return a `WindowObject` which represents the whole screen.

참고: If there is an error opening the terminal, the underlying curses library may cause the interpreter to exit.

`curses.is_term_resized(nlines, ncols)`

Return True if `resize_term()` would modify the window structure, False otherwise.

`curses.isendwin()`

Return True if `endwin()` has been called (that is, the curses library has been deinitialized).

`curses.keyname(k)`

Return the name of the key numbered *k*. The name of a key generating printable ASCII character is the key's character. The name of a control-key combination is a two-character string consisting of a caret followed by the corresponding printable ASCII character. The name of an alt-key combination (128–255) is a string consisting of the prefix <M-< followed by the name of the corresponding ASCII character.

`curses.killchar()`

Return the user's current line kill character. Under Unix operating systems this is a property of the controlling tty of the curses program, and is not set by the curses library itself.

`curses.longname()`

Return a string containing the terminfo long name field describing the current terminal. The maximum length of a verbose description is 128 characters. It is defined only after the call to `initscr()`.

`curses.meta(yes)`

If *yes* is 1, allow 8-bit characters to be input. If *yes* is 0, allow only 7-bit chars.

`curses.mouseinterval(interval)`

Set the maximum time in milliseconds that can elapse between press and release events in order for them to be recognized as a click, and return the previous interval value. The default value is 200 msec, or one fifth of a second.

`curses.mousemask(mousemask)`

Set the mouse events to be reported, and return a tuple (*availmask*, *oldmask*). *availmask* indicates which of the specified mouse events can be reported; on complete failure it returns 0. *oldmask* is the previous value of the given window's mouse event mask. If this function is never called, no mouse events are ever reported.

`curses.napms(ms)`

Sleep for *ms* milliseconds.

`curses.newpad(nlines, ncols)`

Create and return a pointer to a new pad data structure with the given number of lines and columns. A pad is returned as a window object.

A pad is like a window, except that it is not restricted by the screen size, and is not necessarily associated with a particular part of the screen. Pads can be used when a large window is needed, and only a part of the window will be on the screen at one time. Automatic refreshes of pads (such as from scrolling or echoing of input) do not occur. The `refresh()` and `noutrefresh()` methods of a pad require 6 arguments to specify the part of the pad to be displayed and the location on the screen to be used for the display. The arguments are *pminrow*, *pmincol*, *sminrow*, *smincol*, *smaxrow*, *smaxcol*; the *p* arguments refer to the upper left corner of the pad region to be displayed and the *s* arguments define a clipping box on the screen within which the pad region is to be displayed.

`curses.newwin(nlines, ncols)`

`curses.newwin(nlines, ncols, begin_y, begin_x)`

Return a new window, whose left-upper corner is at (*begin_y*, *begin_x*), and whose height/width is *nlines/ncols*.

By default, the window will extend from the specified position to the lower right corner of the screen.

`curses.nl()`

Enter newline mode. This mode translates the return key into newline on input, and translates newline into return and line-feed on output. Newline mode is initially on.

`curses.nocbreak()`

Leave cbreak mode. Return to normal 《cooked》 mode with line buffering.

`curses.noecho()`

Leave echo mode. Echoing of input characters is turned off.

`curses.nonl()`

Leave newline mode. Disable translation of return into newline on input, and disable low-level translation of newline into newline/return on output (but this does not change the behavior of `addch('\n')`, which always does the

equivalent of return and line feed on the virtual screen). With translation off, curses can sometimes speed up vertical motion a little; also, it will be able to detect the return key on input.

`curses.noqiflush()`

When the `noqiflush()` routine is used, normal flush of input and output queues associated with the INTR, QUIT and SUSP characters will not be done. You may want to call `noqiflush()` in a signal handler if you want output to continue as though the interrupt had not occurred, after the handler exits.

`curses.noraw()`

Leave raw mode. Return to normal 《cooked》 mode with line buffering.

`curses.pair_content(pair_number)`

Return a tuple (fg, bg) containing the colors for the requested color pair. The value of *pair_number* must be between 1 and `COLOR_PAIRS - 1`.

`curses.pair_number(attr)`

Return the number of the color-pair set by the attribute value *attr*. `color_pair()` is the counterpart to this function.

`curses.putp(string)`

Equivalent to `tputs(str, 1, putchar)`; emit the value of a specified terminfo capability for the current terminal. Note that the output of `putp()` always goes to standard output.

`curses.qiflush([flag])`

If *flag* is False, the effect is the same as calling `noqiflush()`. If *flag* is True, or no argument is provided, the queues will be flushed when these control characters are read.

`curses.raw()`

Enter raw mode. In raw mode, normal line buffering and processing of interrupt, quit, suspend, and flow control keys are turned off; characters are presented to curses input functions one by one.

`curses.reset_prog_mode()`

Restore the terminal to 《program》 mode, as previously saved by `def_prog_mode()`.

`curses.reset_shell_mode()`

Restore the terminal to 《shell》 mode, as previously saved by `def_shell_mode()`.

`curses.resetty()`

Restore the state of the terminal modes to what it was at the last call to `savetty()`.

`curses.resize_term(nlines, ncols)`

Backend function used by `resizeterm()`, performing most of the work; when resizing the windows, `resize_term()` blank-fills the areas that are extended. The calling application should fill in these areas with appropriate data. The `resize_term()` function attempts to resize all windows. However, due to the calling convention of pads, it is not possible to resize these without additional interaction with the application.

`curses.resizeterm(nlines, ncols)`

Resize the standard and current windows to the specified dimensions, and adjusts other bookkeeping data used by the curses library that record the window dimensions (in particular the SIGWINCH handler).

`curses.savetty()`

Save the current state of the terminal modes in a buffer, usable by `resetty()`.

`curses.setsyx(y, x)`

Set the virtual screen cursor to y, x. If y and x are both -1, then leaveok is set.

`curses.setupterm([termstr, fd])`

Initialize the terminal. *termstr* is a string giving the terminal name; if omitted, the value of the `TERM` environment variable will be used. *fd* is the file descriptor to which any initialization sequences will be sent; if not supplied, the file descriptor for `sys.stdout` will be used.

`curses.start_color()`

Must be called if the programmer wants to use colors, and before any other color manipulation routine is called. It is good practice to call this routine right after `initscr()`.

`start_color()` initializes eight basic colors (black, red, green, yellow, blue, magenta, cyan, and white), and two global variables in the `curses` module, `COLORS` and `COLOR_PAIRS`, containing the maximum number of colors and color-pairs the terminal can support. It also restores the colors on the terminal to the values they had when the terminal was just turned on.

`curses.termattrs()`

Return a logical OR of all video attributes supported by the terminal. This information is useful when a curses program needs complete control over the appearance of the screen.

`curses.termname()`

Return the value of the environment variable `TERM`, truncated to 14 characters.

`curses.tigetflag(capname)`

Return the value of the Boolean capability corresponding to the terminfo capability name *capname*. The value `-1` is returned if *capname* is not a Boolean capability, or `0` if it is canceled or absent from the terminal description.

`curses.tigetnum(capname)`

Return the value of the numeric capability corresponding to the terminfo capability name *capname*. The value `-2` is returned if *capname* is not a numeric capability, or `-1` if it is canceled or absent from the terminal description.

`curses.tigetstr(capname)`

Return the value of the string capability corresponding to the terminfo capability name *capname*. `None` is returned if *capname* is not a string capability, or is canceled or absent from the terminal description.

`curses.tparm(str[, ...])`

Instantiate the string *str* with the supplied parameters, where *str* should be a parameterized string obtained from the terminfo database. E.g. `tparm(tigetstr("cup"), 5, 3)` could result in `'\033[6;4H'`, the exact result depending on terminal type.

`curses.typeahead(fd)`

Specify that the file descriptor *fd* be used for typeahead checking. If *fd* is `-1`, then no typeahead checking is done.

The curses library does 《line-breakout optimization》 by looking for typeahead periodically while updating the screen. If input is found, and it is coming from a tty, the current update is postponed until `refresh` or `doupdate` is called again, allowing faster response to commands typed in advance. This function allows specifying a different file descriptor for typeahead checking.

`curses.unctrl(ch)`

Return a string which is a printable representation of the character *ch*. Control characters are displayed as a caret followed by the character, for example as `^C`. Printing characters are left as they are.

`curses.ungetch(ch)`

Push *ch* so the next `getch()` will return it.

참고: Only one *ch* can be pushed before `getch()` is called.

`curses.ungetmouse(id, x, y, z, bstate)`

Push a `KEY_MOUSE` event onto the input queue, associating the given state data with it.

`curses.use_env(flag)`

If used, this function should be called before `initscr()` or `newterm` are called. When *flag* is `False`, the values of lines and columns specified in the terminfo database will be used, even if environment variables `LINES` and `COLUMNS` (used by default) are set, or if curses is running in a window (in which case default behavior would be to use the window size if `LINES` and `COLUMNS` are not set).

`curses.use_default_colors()`

Allow use of default values for colors on terminals supporting this feature. Use this to support transparency in your application. The default color is assigned to the color number -1. After calling this function, `init_pair(x, curses.COLOR_RED, -1)` initializes, for instance, color pair *x* to a red foreground color on the default background.

`curses.wrapper(func, ...)`

Initialize curses and call another callable object, *func*, which should be the rest of your curses-using application. If the application raises an exception, this function will restore the terminal to a sane state before re-raising the exception and generating a traceback. The callable object *func* is then passed the main window `<stdscr>` as its first argument, followed by any other arguments passed to `wrapper()`. Before calling *func*, `wrapper()` turns on cbreak mode, turns off echo, enables the terminal keypad, and initializes colors if the terminal has color support. On exit (whether normally or by exception) it restores cooked mode, turns on echo, and disables the terminal keypad.

15.11.2 Window Objects

Window objects, as returned by `initscr()` and `newwin()` above, have the following methods:

`window.addch(ch[, attr])`
`window.addch(y, x, ch[, attr])`

참고: A *character* means a C character (an ASCII code), rather than a Python character (a string of length 1). (This note is true whenever the documentation mentions a character.) The built-in `ord()` is handy for conveying strings to codes.

Paint character *ch* at (*y*, *x*) with attributes *attr*, overwriting any character previously painter at that location. By default, the character position and attributes are the current settings for the window object.

참고: Writing outside the window, subwindow, or pad raises a `curses.error`. Attempting to write to the lower right corner of a window, subwindow, or pad will cause an exception to be raised after the character is printed.

`window.addnstr(str, n[, attr])`
`window.addnstr(y, x, str, n[, attr])`

Paint at most *n* characters of the string *str* at (*y*, *x*) with attributes *attr*, overwriting anything previously on the display.

`window.addstr(str[, attr])`
`window.addstr(y, x, str[, attr])`

Paint the string *str* at (*y*, *x*) with attributes *attr*, overwriting anything previously on the display.

참고: Writing outside the window, subwindow, or pad raises `curses.error`. Attempting to write to the lower right corner of a window, subwindow, or pad will cause an exception to be raised after the string is printed.

`window.attroff(attr)`

Remove attribute *attr* from the `《background》` set applied to all writes to the current window.

`window.atttron(attr)`

Add attribute *attr* from the `《background》` set applied to all writes to the current window.

`window.attrset(attr)`

Set the `《background》` set of attributes to *attr*. This set is initially 0 (no attributes).

`window.bkgd(ch[, attr])`

Set the background property of the window to the character *ch*, with attributes *attr*. The change is then applied to every character position in that window:

- The attribute of every character in the window is changed to the new background attribute.
- Wherever the former background character appears, it is changed to the new background character.

`window.bkgdset(ch[, attr])`

Set the window's background. A window's background consists of a character and any combination of attributes. The attribute part of the background is combined (OR'ed) with all non-blank characters that are written into the window. Both the character and attribute parts of the background are combined with the blank characters. The background becomes a property of the character and moves with the character through any scrolling and insert/delete line/character operations.

`window.border([ls[, rs[, ts[, bs[, tl[, tr[, bl[, br]]]]]])`

Draw a border around the edges of the window. Each parameter specifies the character to use for a specific part of the border; see the table below for more details. The characters can be specified as integers or as one-character strings.

참고: A 0 value for any parameter will cause the default character to be used for that parameter. Keyword parameters can *not* be used. The defaults are listed in this table:

Parameter	Description	Default value
<i>ls</i>	Left side	ACS_VLINE
<i>rs</i>	Right side	ACS_VLINE
<i>ts</i>	Top	ACS_HLINE
<i>bs</i>	Bottom	ACS_HLINE
<i>tl</i>	Upper-left corner	ACS_ULCORNER
<i>tr</i>	Upper-right corner	ACS_URCORNER
<i>bl</i>	Bottom-left corner	ACS_LLCORNER
<i>br</i>	Bottom-right corner	ACS_LRCORNER

`window.box([vertch, horch])`

Similar to `border()`, but both *ls* and *rs* are *vertch* and both *ts* and *bs* are *horch*. The default corner characters are always used by this function.

`window.chgat(attr)`

`window.chgat(num, attr)`

`window.chgat(y, x, attr)`

`window.chgat(y, x, num, attr)`

Set the attributes of *num* characters at the current cursor position, or at position (*y*, *x*) if supplied. If *num* is not given or is -1, the attribute will be set on all the characters to the end of the line. This function moves cursor to position (*y*, *x*) if supplied. The changed line will be touched using the `touchline()` method so that the contents will be redisplayed by the next window refresh.

`window.clear()`

Like `erase()`, but also cause the whole window to be repainted upon next call to `refresh()`.

`window.clearok(yes)`

If *yes* is 1, the next call to `refresh()` will clear the window completely.

`window.clrtobot()`

Erase from cursor to the end of the window: all lines below the cursor are deleted, and then the equivalent of `clrtoeol()` is performed.

`window.clrtoeol()`
Erase from cursor to the end of the line.

`window.cursyncup()`
Update the current cursor position of all the ancestors of the window to reflect the current cursor position of the window.

`window.delch([y, x])`
Delete any character at (y, x) .

`window.deleteln()`
Delete the line under the cursor. All following lines are moved up by one line.

`window.derwin(begin_y, begin_x)`
`window.derwin(nlines, ncols, begin_y, begin_x)`
An abbreviation for 《derive window》, `derwin()` is the same as calling `subwin()`, except that `begin_y` and `begin_x` are relative to the origin of the window, rather than relative to the entire screen. Return a window object for the derived window.

`window.echochar(ch[, attr])`
Add character `ch` with attribute `attr`, and immediately call `refresh()` on the window.

`window.enclose(y, x)`
Test whether the given pair of screen-relative character-cell coordinates are enclosed by the given window, returning True or False. It is useful for determining what subset of the screen windows enclose the location of a mouse event.

`window.erase()`
Clear the window.

`window.getbegyx()`
Return a tuple (y, x) of co-ordinates of upper-left corner.

`window.getbkgd()`
Return the given window's current background character/attribute pair.

`window.getch([y, x])`
Get a character. Note that the integer returned does *not* have to be in ASCII range: function keys, keypad keys and so on return numbers higher than 256. In no-delay mode, -1 is returned if there is no input, else `getch()` waits until a key is pressed.

`window.getkey([y, x])`
Get a character, returning a string instead of an integer, as `getch()` does. Function keys, keypad keys and so on return a multibyte string containing the key name. In no-delay mode, an exception is raised if there is no input.

`window.getmaxyx()`
Return a tuple (y, x) of the height and width of the window.

`window.getparyx()`
Return the beginning coordinates of this window relative to its parent window into two integer variables `y` and `x`. Return -1, -1 if this window has no parent.

`window.getstr([y, x])`
Read a string from the user, with primitive line editing capacity.

`window.getyx()`
Return a tuple (y, x) of current cursor position relative to the window's upper-left corner.

`window.hline(ch, n)`
`window.hline(y, x, ch, n)`
Display a horizontal line starting at (y, x) with length `n` consisting of the character `ch`.

`window.idcok(flag)`

If *flag* is `False`, `curses` no longer considers using the hardware insert/delete character feature of the terminal; if *flag* is `True`, use of character insertion and deletion is enabled. When `curses` is first initialized, use of character insert/delete is enabled by default.

`window.idlok(yes)`

If called with *yes* equal to 1, `curses` will try and use hardware line editing facilities. Otherwise, line insertion/deletion are disabled.

`window.immedok(flag)`

If *flag* is `True`, any change in the window image automatically causes the window to be refreshed; you no longer have to call `refresh()` yourself. However, it may degrade performance considerably, due to repeated calls to `wrefresh`. This option is disabled by default.

`window.inch([y, x])`

Return the character at the given position in the window. The bottom 8 bits are the character proper, and upper bits are the attributes.

`window.insch(ch[, attr])`

`window.insch(y, x, ch[, attr])`

Paint character *ch* at (*y*, *x*) with attributes *attr*, moving the line from position *x* right by one character.

`window.insdelln(nlines)`

Insert *nlines* lines into the specified window above the current line. The *nlines* bottom lines are lost. For negative *nlines*, delete *nlines* lines starting with the one under the cursor, and move the remaining lines up. The bottom *nlines* lines are cleared. The current cursor position remains the same.

`window.insertln()`

Insert a blank line under the cursor. All following lines are moved down by one line.

`window.insnstr(str, n[, attr])`

`window.insnstr(y, x, str, n[, attr])`

Insert a character string (as many characters as will fit on the line) before the character under the cursor, up to *n* characters. If *n* is zero or negative, the entire string is inserted. All characters to the right of the cursor are shifted right, with the rightmost characters on the line being lost. The cursor position does not change (after moving to *y*, *x*, if specified).

`window.insstr(str[, attr])`

`window.insstr(y, x, str[, attr])`

Insert a character string (as many characters as will fit on the line) before the character under the cursor. All characters to the right of the cursor are shifted right, with the rightmost characters on the line being lost. The cursor position does not change (after moving to *y*, *x*, if specified).

`window.instr([n])`

`window.instr(y, x[, n])`

Return a string of characters, extracted from the window starting at the current cursor position, or at *y*, *x* if specified. Attributes are stripped from the characters. If *n* is specified, `instr()` returns a string at most *n* characters long (exclusive of the trailing NUL).

`window.is_linetouched(line)`

Return `True` if the specified line was modified since the last call to `refresh()`; otherwise return `False`. Raise a `curses.error` exception if *line* is not valid for the given window.

`window.is_wintouched()`

Return `True` if the specified window was modified since the last call to `refresh()`; otherwise return `False`.

`window.keypad(yes)`

If *yes* is 1, escape sequences generated by some keys (keypad, function keys) will be interpreted by `curses`. If *yes* is 0, escape sequences will be left as is in the input stream.

`window.leaveok (yes)`

If *yes* is 1, cursor is left where it is on update, instead of being at `⟨cursor position⟩`. This reduces cursor movement where possible. If possible the cursor will be made invisible.

If *yes* is 0, cursor will always be at `⟨cursor position⟩` after an update.

`window.move (new_y, new_x)`

Move cursor to `(new_y, new_x)`.

`window.mvderwin (y, x)`

Move the window inside its parent window. The screen-relative parameters of the window are not changed. This routine is used to display different parts of the parent window at the same physical position on the screen.

`window.mvwin (new_y, new_x)`

Move the window so its upper-left corner is at `(new_y, new_x)`.

`window.nodelay (yes)`

If *yes* is 1, `getch()` will be non-blocking.

`window.notimeout (yes)`

If *yes* is 1, escape sequences will not be timed out.

If *yes* is 0, after a few milliseconds, an escape sequence will not be interpreted, and will be left in the input stream as is.

`window.noutrefresh ()`

Mark for refresh but wait. This function updates the data structure representing the desired state of the window, but does not force an update of the physical screen. To accomplish that, call `doupdate()`.

`window.overlay (destwin[, sminrow, smincol, dminrow, dmincol, dmaxrow, dmaxcol])`

Overlay the window on top of *destwin*. The windows need not be the same size, only the overlapping region is copied. This copy is non-destructive, which means that the current background character does not overwrite the old contents of *destwin*.

To get fine-grained control over the copied region, the second form of `overlay()` can be used. *sminrow* and *smincol* are the upper-left coordinates of the source window, and the other variables mark a rectangle in the destination window.

`window.overwrite (destwin[, sminrow, smincol, dminrow, dmincol, dmaxrow, dmaxcol])`

Overwrite the window on top of *destwin*. The windows need not be the same size, in which case only the overlapping region is copied. This copy is destructive, which means that the current background character overwrites the old contents of *destwin*.

To get fine-grained control over the copied region, the second form of `overwrite()` can be used. *sminrow* and *smincol* are the upper-left coordinates of the source window, the other variables mark a rectangle in the destination window.

`window.putwin (file)`

Write all data associated with the window into the provided file object. This information can be later retrieved using the `getwin()` function.

`window.redrawln (beg, num)`

Indicate that the *num* screen lines, starting at line *beg*, are corrupted and should be completely redrawn on the next `refresh()` call.

`window.redrawwin ()`

Touch the entire window, causing it to be completely redrawn on the next `refresh()` call.

`window.refresh ([pminrow, pmincol, sminrow, smincol, smaxrow, smaxcol])`

Update the display immediately (sync actual screen with previous drawing/deleting methods).

The 6 optional arguments can only be specified when the window is a pad created with `newpad()`. The additional parameters are needed to indicate what part of the pad and screen are involved. `pminrow` and `pmincol` specify the upper left-hand corner of the rectangle to be displayed in the pad. `sminrow`, `smincol`, `smaxrow`, and `smaxcol` specify the edges of the rectangle to be displayed on the screen. The lower right-hand corner of the rectangle to be displayed in the pad is calculated from the screen coordinates, since the rectangles must be the same size. Both rectangles must be entirely contained within their respective structures. Negative values of `pminrow`, `pmincol`, `sminrow`, or `smincol` are treated as if they were zero.

`window.resize(nlines, ncols)`

Reallocate storage for a curses window to adjust its dimensions to the specified values. If either dimension is larger than the current values, the window's data is filled with blanks that have the current background rendition (as set by `bkgdset()`) merged into them.

`window.scroll([lines=1])`

Scroll the screen or scrolling region upward by *lines* lines.

`window.scrollok(flag)`

Control what happens when the cursor of a window is moved off the edge of the window or scrolling region, either as a result of a newline action on the bottom line, or typing the last character of the last line. If *flag* is false, the cursor is left on the bottom line. If *flag* is true, the window is scrolled up one line. Note that in order to get the physical scrolling effect on the terminal, it is also necessary to call `idlok()`.

`window.setscrreg(top, bottom)`

Set the scrolling region from line *top* to line *bottom*. All scrolling actions will take place in this region.

`window.standend()`

Turn off the standout attribute. On some terminals this has the side effect of turning off all attributes.

`window.standout()`

Turn on attribute `A_STANDOUT`.

`window.subpad(begin_y, begin_x)`

`window.subpad(nlines, ncols, begin_y, begin_x)`

Return a sub-window, whose upper-left corner is at (*begin_y*, *begin_x*), and whose width/height is *ncols/nlines*.

`window.subwin(begin_y, begin_x)`

`window.subwin(nlines, ncols, begin_y, begin_x)`

Return a sub-window, whose upper-left corner is at (*begin_y*, *begin_x*), and whose width/height is *ncols/nlines*.

By default, the sub-window will extend from the specified position to the lower right corner of the window.

`window.syncdown()`

Touch each location in the window that has been touched in any of its ancestor windows. This routine is called by `refresh()`, so it should almost never be necessary to call it manually.

`window.syncok(flag)`

If called with *flag* set to True, then `syncup()` is called automatically whenever there is a change in the window.

`window.syncup()`

Touch all locations in ancestors of the window that have been changed in the window.

`window.timeout(delay)`

Set blocking or non-blocking read behavior for the window. If *delay* is negative, blocking read is used (which will wait indefinitely for input). If *delay* is zero, then non-blocking read is used, and -1 will be returned by `getch()` if no input is waiting. If *delay* is positive, then `getch()` will block for *delay* milliseconds, and return -1 if there is still no input at the end of that time.

`window.touchline (start, count[, changed])`

Pretend *count* lines have been changed, starting with line *start*. If *changed* is supplied, it specifies whether the affected lines are marked as having been changed (*changed*=1) or unchanged (*changed*=0).

`window.touchwin ()`

Pretend the whole window has been changed, for purposes of drawing optimizations.

`window.untouchwin ()`

Mark all lines in the window as unchanged since the last call to `refresh()`.

`window.vline (ch, n)`

`window.vline (y, x, ch, n)`

Display a vertical line starting at (*y*, *x*) with length *n* consisting of the character *ch*.

15.11.3 Constants

The `curses` module defines the following data members:

`curses.ERR`

Some curses routines that return an integer, such as `getch()`, return `ERR` upon failure.

`curses.OK`

Some curses routines that return an integer, such as `napms()`, return `OK` upon success.

`curses.version`

A string representing the current version of the module. Also available as `__version__`.

Some constants are available to specify character cell attributes. The exact constants available are system dependent.

Attribute	Meaning
<code>A_ALTCHARSET</code>	Alternate character set mode
<code>A_BLINK</code>	Blink mode
<code>A_BOLD</code>	Bold mode
<code>A_DIM</code>	Dim mode
<code>A_INVIS</code>	Invisible or blank mode
<code>A_NORMAL</code>	Normal attribute
<code>A_PROTECT</code>	Protected mode
<code>A_REVERSE</code>	Reverse background and foreground colors
<code>A_STANDOUT</code>	Standout mode
<code>A_UNDERLINE</code>	Underline mode
<code>A_HORIZONTAL</code>	Horizontal highlight
<code>A_LEFT</code>	Left highlight
<code>A_LOW</code>	Low highlight
<code>A_RIGHT</code>	Right highlight
<code>A_TOP</code>	Top highlight
<code>A_VERTICAL</code>	Vertical highlight
<code>A_CHARTEXT</code>	Bit-mask to extract a character

Several constants are available to extract corresponding attributes returned by some methods.

Bit-mask	Meaning
<code>A_ATTRIBUTES</code>	Bit-mask to extract attributes
<code>A_CHARTEXT</code>	Bit-mask to extract a character
<code>A_COLOR</code>	Bit-mask to extract color-pair field information

Keys are referred to by integer constants with names starting with `KEY_`. The exact keycaps available are system dependent.

Key constant	Key
<code>KEY_MIN</code>	Minimum key value
<code>KEY_BREAK</code>	Break key (unreliable)
<code>KEY_DOWN</code>	Down-arrow
<code>KEY_UP</code>	Up-arrow
<code>KEY_LEFT</code>	Left-arrow
<code>KEY_RIGHT</code>	Right-arrow
<code>KEY_HOME</code>	Home key (upward+left arrow)
<code>KEY_BACKSPACE</code>	Backspace (unreliable)
<code>KEY_F0</code>	Function keys. Up to 64 function keys are supported.
<code>KEY_Fn</code>	Value of function key <i>n</i>
<code>KEY_DL</code>	Delete line
<code>KEY_IL</code>	Insert line
<code>KEY_DC</code>	Delete character
<code>KEY_IC</code>	Insert char or enter insert mode
<code>KEY_EIC</code>	Exit insert char mode
<code>KEY_CLEAR</code>	Clear screen
<code>KEY_EOS</code>	Clear to end of screen
<code>KEY_EOL</code>	Clear to end of line
<code>KEY_SF</code>	Scroll 1 line forward
<code>KEY_SR</code>	Scroll 1 line backward (reverse)
<code>KEY_NPAGE</code>	Next page
<code>KEY_PPAGE</code>	Previous page
<code>KEY_STAB</code>	Set tab
<code>KEY_CTAB</code>	Clear tab
<code>KEY_CATAB</code>	Clear all tabs
<code>KEY_ENTER</code>	Enter or send (unreliable)
<code>KEY_SRESET</code>	Soft (partial) reset (unreliable)
<code>KEY_RESET</code>	Reset or hard reset (unreliable)
<code>KEY_PRINT</code>	Print
<code>KEY_LL</code>	Home down or bottom (lower left)
<code>KEY_A1</code>	Upper left of keypad
<code>KEY_A3</code>	Upper right of keypad
<code>KEY_B2</code>	Center of keypad
<code>KEY_C1</code>	Lower left of keypad
<code>KEY_C3</code>	Lower right of keypad
<code>KEY_BTAB</code>	Back tab
<code>KEY_BEG</code>	Beg (beginning)
<code>KEY_CANCEL</code>	Cancel
<code>KEY_CLOSE</code>	Close
<code>KEY_COMMAND</code>	Cmd (command)
<code>KEY_COPY</code>	Copy
<code>KEY_CREATE</code>	Create
<code>KEY_END</code>	End
<code>KEY_EXIT</code>	Exit
<code>KEY_FIND</code>	Find
<code>KEY_HELP</code>	Help
<code>KEY_MARK</code>	Mark

다음 페이지에 계속

표 1 - 이전 페이지에서 계속

Key constant	Key
KEY_MESSAGE	Message
KEY_MOVE	Move
KEY_NEXT	Next
KEY_OPEN	Open
KEY_OPTIONS	Options
KEY_PREVIOUS	Prev (previous)
KEY_REDO	Redo
KEY_REFERENCE	Ref (reference)
KEY_REFRESH	Refresh
KEY_REPLACE	Replace
KEY_RESTART	Restart
KEY_RESUME	Resume
KEY_SAVE	Save
KEY_SBEG	Shifted Beg (beginning)
KEY_SCANCEL	Shifted Cancel
KEY_SCOMMAND	Shifted Command
KEY_SCOPY	Shifted Copy
KEY_SCREATE	Shifted Create
KEY_SDC	Shifted Delete char
KEY_SDL	Shifted Delete line
KEY_SELECT	Select
KEY_SEND	Shifted End
KEY_SEOL	Shifted Clear line
KEY_SEXIT	Shifted Exit
KEY_SFIND	Shifted Find
KEY_SHELP	Shifted Help
KEY_SHOME	Shifted Home
KEY_SIC	Shifted Input
KEY_SLEFT	Shifted Left arrow
KEY_SMESSAGE	Shifted Message
KEY_SMOVE	Shifted Move
KEY_SNEXT	Shifted Next
KEY_SOPTIONS	Shifted Options
KEY_SPREVIOUS	Shifted Prev
KEY_SPRINT	Shifted Print
KEY_SREDO	Shifted Redo
KEY_SREPLACE	Shifted Replace
KEY_SRIGHT	Shifted Right arrow
KEY_SRSUME	Shifted Resume
KEY_SSAVE	Shifted Save
KEY_SSUSPEND	Shifted Suspend
KEY_SUNDO	Shifted Undo
KEY_SUSPEND	Suspend
KEY_UNDO	Undo
KEY_MOUSE	Mouse event has occurred
KEY_RESIZE	Terminal resize event
KEY_MAX	Maximum key value

On VT100s and their software emulations, such as X terminal emulators, there are normally at least four function keys (KEY_F1, KEY_F2, KEY_F3, KEY_F4) available, and the arrow keys mapped to KEY_UP, KEY_DOWN, KEY_LEFT

and `KEY_RIGHT` in the obvious way. If your machine has a PC keyboard, it is safe to expect arrow keys and twelve function keys (older PC keyboards may have only ten function keys); also, the following keypad mappings are standard:

Keycap	Constant
Insert	<code>KEY_IC</code>
Delete	<code>KEY_DC</code>
Home	<code>KEY_HOME</code>
End	<code>KEY_END</code>
Page Up	<code>KEY_PPAGE</code>
Page Down	<code>KEY_NPAGE</code>

The following table lists characters from the alternate character set. These are inherited from the VT100 terminal, and will generally be available on software emulations such as X terminals. When there is no graphic available, curses falls back on a crude printable ASCII approximation.

참고: These are available only after `initscr()` has been called.

ACS code	Meaning
<code>ACS_BBSS</code>	alternate name for upper right corner
<code>ACS_BLOCK</code>	solid square block
<code>ACS_BOARD</code>	board of squares
<code>ACS_BSBS</code>	alternate name for horizontal line
<code>ACS_BSSB</code>	alternate name for upper left corner
<code>ACS_BSSS</code>	alternate name for top tee
<code>ACS_BTEE</code>	bottom tee
<code>ACS_BULLET</code>	bullet
<code>ACS_CKBOARD</code>	checker board (stipple)
<code>ACS_DARROW</code>	arrow pointing down
<code>ACS_DEGREE</code>	degree symbol
<code>ACS_DIAMOND</code>	diamond
<code>ACS_GEQUAL</code>	greater-than-or-equal-to
<code>ACS_HLINE</code>	horizontal line
<code>ACS_LANTERN</code>	lantern symbol
<code>ACS_LARROW</code>	left arrow
<code>ACS_LEQUAL</code>	less-than-or-equal-to
<code>ACS_LLCORNER</code>	lower left-hand corner
<code>ACS_LRCORNER</code>	lower right-hand corner
<code>ACS_LTEE</code>	left tee
<code>ACS_NEQUAL</code>	not-equal sign
<code>ACS_PI</code>	letter pi
<code>ACS_PLMINUS</code>	plus-or-minus sign
<code>ACS_PLUS</code>	big plus sign
<code>ACS_RARROW</code>	right arrow
<code>ACS_RTEE</code>	right tee
<code>ACS_S1</code>	scan line 1
<code>ACS_S3</code>	scan line 3
<code>ACS_S7</code>	scan line 7
<code>ACS_S9</code>	scan line 9
<code>ACS_SBBS</code>	alternate name for lower right corner

다음 페이지에 계속

표 2 - 이전 페이지에서 계속

ACS code	Meaning
ACS_SBSB	alternate name for vertical line
ACS_SBSS	alternate name for right tee
ACS_SSBB	alternate name for lower left corner
ACS_SSBS	alternate name for bottom tee
ACS_SSSB	alternate name for left tee
ACS_SSSS	alternate name for crossover or big plus
ACS_STERLING	pound sterling
ACS_TTEE	top tee
ACS_UARROW	up arrow
ACS_ULCORNER	upper left corner
ACS_URCORNER	upper right corner
ACS_VLINE	vertical line

The following table lists the predefined colors:

Constant	Color
COLOR_BLACK	Black
COLOR_BLUE	Blue
COLOR_CYAN	Cyan (light greenish blue)
COLOR_GREEN	Green
COLOR_MAGENTA	Magenta (purplish red)
COLOR_RED	Red
COLOR_WHITE	White
COLOR_YELLOW	Yellow

15.12 `curses.textpad` — Text input widget for curses programs

버전 1.6에 추가.

The `curses.textpad` module provides a `Textbox` class that handles elementary text editing in a curses window, supporting a set of keybindings resembling those of Emacs (thus, also of Netscape Navigator, BBedit 6.x, FrameMaker, and many other programs). The module also provides a rectangle-drawing function useful for framing text boxes or for other purposes.

The module `curses.textpad` defines the following function:

`curses.textpad.rectangle` (*win, uly, ulx, lry, lrx*)

Draw a rectangle. The first argument must be a window object; the remaining arguments are coordinates relative to that window. The second and third arguments are the y and x coordinates of the upper left hand corner of the rectangle to be drawn; the fourth and fifth arguments are the y and x coordinates of the lower right hand corner. The rectangle will be drawn using VT100/IBM PC forms characters on terminals that make this possible (including xterm and most other software terminal emulators). Otherwise it will be drawn with ASCII dashes, vertical bars, and plus signs.

15.12.1 Textbox objects

You can instantiate a *Textbox* object as follows:

class `curses.textpad.Textbox` (*win*)

Return a textbox widget object. The *win* argument should be a `curses.WindowObject` in which the textbox is to be contained. The edit cursor of the textbox is initially located at the upper left hand corner of the containing window, with coordinates (0, 0). The instance's *stripspaces* flag is initially on.

Textbox objects have the following methods:

edit ([*validator*])

This is the entry point you will normally use. It accepts editing keystrokes until one of the termination keystrokes is entered. If *validator* is supplied, it must be a function. It will be called for each keystroke entered with the keystroke as a parameter; command dispatch is done on the result. This method returns the window contents as a string; whether blanks in the window are included is affected by the *stripspaces* attribute.

do_command (*ch*)

Process a single command keystroke. Here are the supported special keystrokes:

Keystroke	Action
Control-A	Go to left edge of window.
Control-B	Cursor left, wrapping to previous line if appropriate.
Control-D	Delete character under cursor.
Control-E	Go to right edge (stripspaces off) or end of line (stripspaces on).
Control-F	Cursor right, wrapping to next line when appropriate.
Control-G	Terminate, returning the window contents.
Control-H	Delete character backward.
Control-J	Terminate if the window is 1 line, otherwise insert newline.
Control-K	If line is blank, delete it, otherwise clear to end of line.
Control-L	Refresh screen.
Control-N	Cursor down; move down one line.
Control-O	Insert a blank line at cursor location.
Control-P	Cursor up; move up one line.

Move operations do nothing if the cursor is at an edge where the movement is not possible. The following synonyms are supported where possible:

Constant	Keystroke
KEY_LEFT	Control-B
KEY_RIGHT	Control-F
KEY_UP	Control-P
KEY_DOWN	Control-N
KEY_BACKSPACE	Control-h

All other keystrokes are treated as a command to insert the given character and move right (with line wrapping).

gather ()

Return the window contents as a string; whether blanks in the window are included is affected by the *stripspaces* member.

stripspaces

This attribute is a flag which controls the interpretation of blanks in the window. When it is on, trailing blanks

on each line are ignored; any cursor motion that would land the cursor on a trailing blank goes to the end of that line instead, and trailing blanks are stripped when the window contents are gathered.

15.13 `curses.ascii` — Utilities for ASCII characters

버전 1.6에 추가.

The `curses.ascii` module supplies name constants for ASCII characters and functions to test membership in various ASCII character classes. The constants supplied are names for control characters as follows:

Name	Meaning
NUL	
SOH	Start of heading, console interrupt
STX	Start of text
ETX	End of text
EOT	End of transmission
ENQ	Enquiry, goes with ACK flow control
ACK	Acknowledgement
BEL	Bell
BS	Backspace
TAB	Tab
HT	Alias for TAB: 《Horizontal tab》
LF	Line feed
NL	Alias for LF: 《New line》
VT	Vertical tab
FF	Form feed
CR	Carriage return
SO	Shift-out, begin alternate character set
SI	Shift-in, resume default character set
DLE	Data-link escape
DC1	XON, for flow control
DC2	Device control 2, block-mode flow control
DC3	XOFF, for flow control
DC4	Device control 4
NAK	Negative acknowledgement
SYN	Synchronous idle
ETB	End transmission block
CAN	Cancel
EM	End of medium
SUB	Substitute
ESC	Escape
FS	File separator
GS	Group separator
RS	Record separator, block-mode terminator
US	Unit separator
SP	Space
DEL	Delete

Note that many of these have little practical significance in modern usage. The mnemonics derive from teleprinter conventions that predate digital computers.

The module supplies the following functions, patterned on those in the standard C library:

`curses.ascii.isalnum(c)`

Checks for an ASCII alphanumeric character; it is equivalent to `isalpha(c)` or `isdigit(c)`.

`curses.ascii.isalpha(c)`

Checks for an ASCII alphabetic character; it is equivalent to `isupper(c)` or `islower(c)`.

`curses.ascii.isascii(c)`

Checks for a character value that fits in the 7-bit ASCII set.

`curses.ascii.isblank(c)`

Checks for an ASCII whitespace character; space or horizontal tab.

`curses.ascii.iscntrl(c)`

Checks for an ASCII control character (in the range 0x00 to 0x1f or 0x7f).

`curses.ascii.isdigit(c)`

Checks for an ASCII decimal digit, '0' through '9'. This is equivalent to `c in string.digits`.

`curses.ascii.isgraph(c)`

Checks for ASCII any printable character except space.

`curses.ascii.islower(c)`

Checks for an ASCII lower-case character.

`curses.ascii.isprint(c)`

Checks for any ASCII printable character including space.

`curses.ascii.ispunct(c)`

Checks for any printable ASCII character which is not a space or an alphanumeric character.

`curses.ascii.isspace(c)`

Checks for ASCII white-space characters; space, line feed, carriage return, form feed, horizontal tab, vertical tab.

`curses.ascii.isupper(c)`

Checks for an ASCII uppercase letter.

`curses.ascii.isxdigit(c)`

Checks for an ASCII hexadecimal digit. This is equivalent to `c in string.hexdigits`.

`curses.ascii.isctrl(c)`

Checks for an ASCII control character (ordinal values 0 to 31).

`curses.ascii.ismeta(c)`

Checks for a non-ASCII character (ordinal values 0x80 and above).

These functions accept either integers or strings; when the argument is a string, it is first converted using the built-in function `ord()`.

Note that all these functions check ordinal bit values derived from the first character of the string you pass in; they do not actually know anything about the host machine's character encoding. For functions that know about the character encoding (and handle internationalization properly) see the [string](#) module.

The following two functions take either a single-character string or integer byte value; they return a value of the same type.

`curses.ascii.ascii(c)`

Return the ASCII value corresponding to the low 7 bits of `c`.

`curses.ascii.ctrl(c)`

Return the control character corresponding to the given character (the character bit value is bitwise-anded with 0x1f).

`curses.ascii.alt(c)`

Return the 8-bit character corresponding to the given ASCII character (the character bit value is bitwise-ored with 0x80).

The following function takes either a single-character string or integer value; it returns a string.

`curses.ascii.unctrl(c)`

Return a string representation of the ASCII character *c*. If *c* is printable, this string is the character itself. If the character is a control character (0x00–0x1f) the string consists of a caret ('^') followed by the corresponding uppercase letter. If the character is an ASCII delete (0x7f) the string is '^?'. If the character has its meta bit (0x80) set, the meta bit is stripped, the preceding rules applied, and '!' prepended to the result.

`curses.ascii.controlnames`

A 33-element string array that contains the ASCII mnemonics for the thirty-two ASCII control characters from 0 (NUL) to 0x1f (US), in order, plus the mnemonic *SP* for the space character.

15.14 `curses.panel` — A panel stack extension for curses

Panels are windows with the added feature of depth, so they can be stacked on top of each other, and only the visible portions of each window will be displayed. Panels can be added, moved up or down in the stack, and removed.

15.14.1 Functions

The module `curses.panel` defines the following functions:

`curses.panel.bottom_panel()`

Returns the bottom panel in the panel stack.

`curses.panel.new_panel(win)`

Returns a panel object, associating it with the given window *win*. Be aware that you need to keep the returned panel object referenced explicitly. If you don't, the panel object is garbage collected and removed from the panel stack.

`curses.panel.top_panel()`

Returns the top panel in the panel stack.

`curses.panel.update_panels()`

Updates the virtual screen after changes in the panel stack. This does not call `curses.doupdate()`, so you'll have to do this yourself.

15.14.2 Panel Objects

Panel objects, as returned by `new_panel()` above, are windows with a stacking order. There's always a window associated with a panel which determines the content, while the panel methods are responsible for the window's depth in the panel stack.

Panel objects have the following methods:

`Panel.above()`

Returns the panel above the current panel.

`Panel.below()`

Returns the panel below the current panel.

`Panel.bottom()`

Push the panel to the bottom of the stack.

`Panel.hidden()`

Returns true if the panel is hidden (not visible), false otherwise.

`Panel.hide()`

Hide the panel. This does not delete the object, it just makes the window on screen invisible.

`Panel.move(y, x)`

Move the panel to the screen coordinates `(y, x)`.

`Panel.replace(win)`

Change the window associated with the panel to the window `win`.

`Panel.set_userptr(obj)`

Set the panel's user pointer to `obj`. This is used to associate an arbitrary piece of data with the panel, and can be any Python object.

`Panel.show()`

Display the panel (which might have been hidden).

`Panel.top()`

Push panel to the top of the stack.

`Panel.userptr()`

Returns the user pointer for the panel. This might be any Python object.

`Panel.window()`

Returns the window object associated with the panel.

15.15 platform — Access to underlying platform's identifying data

버전 2.3에 추가.

Source code: [Lib/platform.py](#)

참고: Specific platforms listed alphabetically, with Linux included in the Unix section.

15.15.1 Cross Platform

`platform.architecture(executable=sys.executable, bits="", linkage="")`

Queries the given executable (defaults to the Python interpreter binary) for various architecture information.

Returns a tuple `(bits, linkage)` which contain information about the bit architecture and the linkage format used for the executable. Both values are returned as strings.

Values that cannot be determined are returned as given by the parameter presets. If `bits` is given as `' '`, the `sizeof(pointer)` (or `sizeof(long)` on Python version < 1.5.2) is used as indicator for the supported pointer size.

The function relies on the system's `file` command to do the actual work. This is available on most if not all Unix platforms and some non-Unix platforms and then only if the executable points to the Python interpreter. Reasonable defaults are used when the above needs are not met.

참고: On Mac OS X (and perhaps other platforms), executable files may be universal files containing multiple architectures.

To get at the «64-bitness» of the current interpreter, it is more reliable to query the `sys.maxsize` attribute:

```
is_64bits = sys.maxsize > 2**32
```

`platform.machine()`

Returns the machine type, e.g. 'i386'. An empty string is returned if the value cannot be determined.

`platform.node()`

Returns the computer's network name (may not be fully qualified!). An empty string is returned if the value cannot be determined.

`platform.platform(aliased=0, terse=0)`

Returns a single string identifying the underlying platform with as much useful information as possible.

The output is intended to be *human readable* rather than machine parseable. It may look different on different platforms and this is intended.

If *aliased* is true, the function will use aliases for various platforms that report system names which differ from their common names, for example SunOS will be reported as Solaris. The `system_alias()` function is used to implement this.

Setting *terse* to true causes the function to return only the absolute minimum information needed to identify the platform.

`platform.processor()`

Returns the (real) processor name, e.g. 'amd64'.

An empty string is returned if the value cannot be determined. Note that many platforms do not provide this information or simply return the same value as for `machine()`. NetBSD does this.

`platform.python_build()`

Returns a tuple (buildno, builddate) stating the Python build number and date as strings.

`platform.python_compiler()`

Returns a string identifying the compiler used for compiling Python.

`platform.python_branch()`

Returns a string identifying the Python implementation SCM branch.

버전 2.6에 추가.

`platform.python_implementation()`

Returns a string identifying the Python implementation. Possible return values are: <CPython>, <IronPython>, <Jython>, <PyPy>.

버전 2.6에 추가.

`platform.python_revision()`

Returns a string identifying the Python implementation SCM revision.

버전 2.6에 추가.

`platform.python_version()`

Returns the Python version as string 'major.minor.patchlevel'.

Note that unlike the Python `sys.version`, the returned value will always include the patchlevel (it defaults to 0).

`platform.python_version_tuple()`

Returns the Python version as tuple (major, minor, patchlevel) of strings.

Note that unlike the Python `sys.version`, the returned value will always include the patchlevel (it defaults to '0').

`platform.release()`

Returns the system's release, e.g. '2.2.0' or 'NT'. An empty string is returned if the value cannot be determined.

`platform.system()`

Returns the system/OS name, e.g. 'Linux', 'Windows', or 'Java'. An empty string is returned if the value cannot be determined.

`platform.system_alias(system, release, version)`

Returns (system, release, version) aliased to common marketing names used for some systems. It also does some reordering of the information in some cases where it would otherwise cause confusion.

`platform.version()`

Returns the system's release version, e.g. '#3 on degas'. An empty string is returned if the value cannot be determined.

`platform.uname()`

Fairly portable uname interface. Returns a tuple of strings (system, node, release, version, machine, processor) identifying the underlying platform.

Note that unlike the `os.uname()` function this also returns possible processor information as additional tuple entry.

Entries which cannot be determined are set to ''.

15.15.2 Java Platform

`platform.java_ver(release="", vendor="", vminfo=("", ""), osinfo=("", ""))`

Version interface for Jython.

Returns a tuple (release, vendor, vminfo, osinfo) with *vminfo* being a tuple (vm_name, vm_release, vm_vendor) and *osinfo* being a tuple (os_name, os_version, os_arch). Values which cannot be determined are set to the defaults given as parameters (which all default to '').

15.15.3 Windows Platform

`platform.win32_ver(release="", version="", csd="", ptype="")`

Get additional version information from the Windows Registry and return a tuple (release, version, csd, ptype) referring to OS release, version number, CSD level (service pack) and OS type (multi/single processor).

As a hint: *ptype* is 'Uniprocessor Free' on single processor NT machines and 'Multiprocessor Free' on multi processor machines. The *Free* refers to the OS version being free of debugging code. It could also state *Checked* which means the OS version uses debugging code, i.e. code that checks arguments, ranges, etc.

참고: This function works best with Mark Hammond's `win32all` package installed, but also on Python 2.3 and later (support for this was added in Python 2.6). It obviously only runs on Win32 compatible platforms.

Win95/98 specific

`platform.popen (cmd, mode='r', bufsize=None)`

Portable `popen()` interface. Find a working `popen` implementation preferring `win32pipe.popen()`. On Windows NT, `win32pipe.popen()` should work; on Windows 9x it hangs due to bugs in the MS C library.

15.15.4 Mac OS Platform

`platform.mac_ver (release="", versioninfo=("", "", " "), machine="")`

Get Mac OS version information and return it as tuple `(release, versioninfo, machine)` with `versioninfo` being a tuple `(version, dev_stage, non_release_version)`.

Entries which cannot be determined are set to `' '`. All tuple entries are strings.

15.15.5 Unix Platforms

`platform.dist (distname="", version="", id="", supported_dists=('SuSE', 'debian', 'redhat', 'mandrake', ...))`

This is an old version of the functionality now provided by `linux_distribution()`. For new code, please use the `linux_distribution()`.

The only difference between the two is that `dist()` always returns the short name of the distribution taken from the `supported_dists` parameter.

버전 2.6부터 폐지.

`platform.linux_distribution (distname="", version="", id="", supported_dists=('SuSE', 'debian', 'redhat', 'mandrake', ...), full_distribution_name=1)`

Tries to determine the name of the Linux OS distribution name.

`supported_dists` may be given to define the set of Linux distributions to look for. It defaults to a list of currently supported Linux distributions identified by their release file name.

If `full_distribution_name` is true (default), the full distribution read from the OS is returned. Otherwise the short name taken from `supported_dists` is used.

Returns a tuple `(distname, version, id)` which defaults to the args given as parameters. `id` is the item in parentheses after the version number. It is usually the version codename.

참고: This function is deprecated since Python 3.5 and removed in Python 3.8. See alternative like the `distro` package.

버전 2.6에 추가.

`platform.libc_ver (executable=sys.executable, lib="", version="", chunksize=2048)`

Tries to determine the libc version against which the file `executable` (defaults to the Python interpreter) is linked. Returns a tuple of strings `(lib, version)` which default to the given parameters in case the lookup fails.

Note that this function has intimate knowledge of how different libc versions add symbols to the executable is probably only usable for executables compiled using `gcc`.

The file is read and scanned in chunks of `chunksize` bytes.

15.16 `errno` — Standard `errno` system symbols

This module makes available standard `errno` system symbols. The value of each symbol is the corresponding integer value. The names and descriptions are borrowed from `linux/include/errno.h`, which should be pretty all-inclusive.

`errno.errorcode`

Dictionary providing a mapping from the `errno` value to the string name in the underlying system. For instance, `errno.errorcode[errno.EPERM]` maps to `'EPERM'`.

To translate a numeric error code to an error message, use `os.strerror()`.

Of the following list, symbols that are not used on the current platform are not defined by the module. The specific list of defined symbols is available as `errno.errorcode.keys()`. Symbols available can include:

`errno.EPERM`

Operation not permitted

`errno.ENOENT`

No such file or directory

`errno.ESRCH`

No such process

`errno.EINTR`

Interrupted system call

`errno.EIO`

I/O error

`errno.ENXIO`

No such device or address

`errno.E2BIG`

Arg list too long

`errno.ENOEXEC`

Exec format error

`errno.EBADF`

Bad file number

`errno.ECHILD`

No child processes

`errno.EAGAIN`

Try again

`errno.ENOMEM`

Out of memory

`errno.EACCES`

Permission denied

`errno.EFAULT`

Bad address

`errno.ENOTBLK`

Block device required

`errno.EBUSY`

Device or resource busy

`errno.EEXIST`
File exists

`errno.EXDEV`
Cross-device link

`errno.ENODEV`
No such device

`errno.ENOTDIR`
Not a directory

`errno.EISDIR`
Is a directory

`errno.EINVAL`
Invalid argument

`errno.ENFILE`
File table overflow

`errno.EMFILE`
Too many open files

`errno.ENOTTY`
Not a typewriter

`errno.ETXTBSY`
Text file busy

`errno.EFBIG`
File too large

`errno.ENOSPC`
No space left on device

`errno.ESPIPE`
Illegal seek

`errno.EROFS`
Read-only file system

`errno.EMLINK`
Too many links

`errno.EPIPE`
Broken pipe

`errno.EDOM`
Math argument out of domain of func

`errno.ERANGE`
Math result not representable

`errno.EDEADLK`
Resource deadlock would occur

`errno.ENAMETOOLONG`
File name too long

`errno.ENOLCK`
No record locks available

`errno.ENOSYS`
Function not implemented

`errno.ENOTEMPTY`
Directory not empty

`errno.ELOOP`
Too many symbolic links encountered

`errno.EWOULDBLOCK`
Operation would block

`errno.ENOMSG`
No message of desired type

`errno.EIDRM`
Identifier removed

`errno.ECHRNG`
Channel number out of range

`errno.EL2NSYNC`
Level 2 not synchronized

`errno.EL3HLT`
Level 3 halted

`errno.EL3RST`
Level 3 reset

`errno.ELNRNG`
Link number out of range

`errno.EUNATCH`
Protocol driver not attached

`errno.ENOCSI`
No CSI structure available

`errno.EL2HLT`
Level 2 halted

`errno.EBADE`
Invalid exchange

`errno.EBADR`
Invalid request descriptor

`errno.EXFULL`
Exchange full

`errno.ENOANO`
No anode

`errno.EBADRQC`
Invalid request code

`errno.EBADSLT`
Invalid slot

`errno.EDEADLOCK`
File locking deadlock error

`errno.EBFONT`
Bad font file format

`errno.ENOSTR`
Device not a stream

`errno.ENODATA`
No data available

`errno.ETIME`
Timer expired

`errno.ENOSR`
Out of streams resources

`errno.ENONET`
Machine is not on the network

`errno.ENOPKG`
Package not installed

`errno.EREMOTE`
Object is remote

`errno.ENOLINK`
Link has been severed

`errno.EADV`
Advertise error

`errno.ESRMNT`
Srmount error

`errno.ECOMM`
Communication error on send

`errno.EPROTO`
Protocol error

`errno.EMULTIHOP`
Multihop attempted

`errno.EDOTDOT`
RFS specific error

`errno.EBADMSG`
Not a data message

`errno.EOVERFLOW`
Value too large for defined data type

`errno.ENOTUNIQ`
Name not unique on network

`errno.EBADFD`
File descriptor in bad state

`errno.EREMCHG`
Remote address changed

`errno.ELIBACC`
Can not access a needed shared library

`errno.ELIBBAD`
Accessing a corrupted shared library

`errno.ELIBSCN`
.lib section in a.out corrupted

`errno.ELIBMAX`
Attempting to link in too many shared libraries

`errno.ELIBEXEC`
Cannot exec a shared library directly

`errno.EILSEQ`
Illegal byte sequence

`errno.ERESTART`
Interrupted system call should be restarted

`errno.ESTRPIPE`
Streams pipe error

`errno.EUSERS`
Too many users

`errno.ENOTSOCK`
Socket operation on non-socket

`errno.EDESTADDRREQ`
Destination address required

`errno.EMSGSIZE`
Message too long

`errno.EPROTOTYPE`
Protocol wrong type for socket

`errno.ENOPROTOOPT`
Protocol not available

`errno.EPROTONOSUPPORT`
Protocol not supported

`errno.ESOCKTNOSUPPORT`
Socket type not supported

`errno.EOPNOTSUPP`
Operation not supported on transport endpoint

`errno.EPFNOSUPPORT`
Protocol family not supported

`errno.EAFNOSUPPORT`
Address family not supported by protocol

`errno.EADDRINUSE`
Address already in use

`errno.EADDRNOTAVAIL`
Cannot assign requested address

`errno.ENETDOWN`
Network is down

`errno.ENETUNREACH`
Network is unreachable

`errno.ENETRESET`
Network dropped connection because of reset

`errno.ECONNABORTED`
Software caused connection abort

`errno.ECONNRESET`
Connection reset by peer

`errno.ENOBUFS`
No buffer space available

`errno.EISCONN`
Transport endpoint is already connected

`errno.ENOTCONN`
Transport endpoint is not connected

`errno.ESHUTDOWN`
Cannot send after transport endpoint shutdown

`errno.ETOOMANYREFS`
Too many references: cannot splice

`errno.ETIMEDOUT`
Connection timed out

`errno.ECONNREFUSED`
Connection refused

`errno.EHOSTDOWN`
Host is down

`errno.EHOSTUNREACH`
No route to host

`errno.EALREADY`
Operation already in progress

`errno.EINPROGRESS`
Operation now in progress

`errno.ESTALE`
Stale NFS file handle

`errno.EUCLEAN`
Structure needs cleaning

`errno.ENOTNAM`
Not a XENIX named type file

`errno.ENAVAIL`
No XENIX semaphores available

`errno.EISNAM`
Is a named type file

`errno.EREMOTEIO`
Remote I/O error

```
errno.EDQUOT
Quota exceeded
```

15.17 ctypes — A foreign function library for Python

버전 2.5에 추가.

ctypes is a foreign function library for Python. It provides C compatible data types, and allows calling functions in DLLs or shared libraries. It can be used to wrap these libraries in pure Python.

15.17.1 ctypes tutorial

Note: The code samples in this tutorial use *doctest* to make sure that they actually work. Since some code samples behave differently under Linux, Windows, or Mac OS X, they contain doctest directives in comments.

Note: Some code samples reference the ctypes *c_int* type. This type is an alias for the *c_long* type on 32-bit systems. So, you should not be confused if *c_long* is printed if you would expect *c_int* — they are actually the same type.

Loading dynamic link libraries

ctypes exports the *cdll*, and on Windows *windll* and *oledll* objects, for loading dynamic link libraries.

You load libraries by accessing them as attributes of these objects. *cdll* loads libraries which export functions using the standard *cdecl* calling convention, while *windll* libraries call functions using the *stdcall* calling convention. *oledll* also uses the *stdcall* calling convention, and assumes the functions return a Windows *HRESULT* error code. The error code is used to automatically raise a *WindowsError* exception when the function call fails.

Here are some examples for Windows. Note that *msvcrt* is the MS standard C library containing most standard C functions, and uses the *cdecl* calling convention:

```
>>> from ctypes import *
>>> print windll.kernel32
<WinDLL 'kernel32', handle ... at ...>
>>> print cdll.msvcrt
<CDLL 'msvcrt', handle ... at ...>
>>> libc = cdll.msvcrt
>>>
```

Windows appends the usual *.dll* file suffix automatically.

On Linux, it is required to specify the filename *including* the extension to load a library, so attribute access can not be used to load libraries. Either the *LoadLibrary()* method of the dll loaders should be used, or you should load the library by creating an instance of *CDLL* by calling the constructor:

```
>>> cdll.LoadLibrary("libc.so.6")
<CDLL 'libc.so.6', handle ... at ...>
>>> libc = CDLL("libc.so.6")
>>> libc
<CDLL 'libc.so.6', handle ... at ...>
>>>
```

Accessing functions from loaded dlls

Functions are accessed as attributes of dll objects:

```
>>> from ctypes import *
>>> libc.printf
<_FuncPtr object at 0x...>
>>> print windll.kernel32.GetModuleHandleA
<_FuncPtr object at 0x...>
>>> print windll.kernel32.MyOwnFunction
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
  File "ctypes.py", line 239, in __getattr__
    func = _StdcallFuncPtr(name, self)
AttributeError: function 'MyOwnFunction' not found
>>>
```

Note that win32 system dlls like `kernel32` and `user32` often export ANSI as well as UNICODE versions of a function. The UNICODE version is exported with an `W` appended to the name, while the ANSI version is exported with an `A` appended to the name. The win32 `GetModuleHandle` function, which returns a *module handle* for a given module name, has the following C prototype, and a macro is used to expose one of them as `GetModuleHandle` depending on whether UNICODE is defined or not:

```
/* ANSI version */
HMODULE GetModuleHandleA(LPCSTR lpModuleName);
/* UNICODE version */
HMODULE GetModuleHandleW(LPCWSTR lpModuleName);
```

`windll` does not try to select one of them by magic, you must access the version you need by specifying `GetModuleHandleA` or `GetModuleHandleW` explicitly, and then call it with strings or unicode strings respectively.

Sometimes, dlls export functions with names which aren't valid Python identifiers, like `"??2@YAPAXI@Z"`. In this case you have to use `getattr()` to retrieve the function:

```
>>> getattr(cdll.msvcrt, "??2@YAPAXI@Z")
<_FuncPtr object at 0x...>
>>>
```

On Windows, some dlls export functions not by name but by ordinal. These functions can be accessed by indexing the dll object with the ordinal number:

```
>>> cdll.kernel32[1]
<_FuncPtr object at 0x...>
>>> cdll.kernel32[0]
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
  File "ctypes.py", line 310, in __getitem__
    func = _StdcallFuncPtr(name, self)
AttributeError: function ordinal 0 not found
>>>
```

Calling functions

You can call these functions like any other Python callable. This example uses the `time()` function, which returns system time in seconds since the Unix epoch, and the `GetModuleHandleA()` function, which returns a win32 module handle.

This example calls both functions with a NULL pointer (`None` should be used as the NULL pointer):

```
>>> print libc.time(None)
1150640792
>>> print hex(windll.kernel32.GetModuleHandleA(None))
0x1d000000
>>>
```

`ctypes` tries to protect you from calling functions with the wrong number of arguments or the wrong calling convention. Unfortunately this only works on Windows. It does this by examining the stack after the function returns, so although an error is raised the function *has* been called:

```
>>> windll.kernel32.GetModuleHandleA()
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ValueError: Procedure probably called with not enough arguments (4 bytes missing)
>>> windll.kernel32.GetModuleHandleA(0, 0)
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ValueError: Procedure probably called with too many arguments (4 bytes in excess)
>>>
```

The same exception is raised when you call an `stdcall` function with the `cdecl` calling convention, or vice versa:

```
>>> cdll.kernel32.GetModuleHandleA(None)
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ValueError: Procedure probably called with not enough arguments (4 bytes missing)
>>>

>>> windll.msvcrt.printf("spam")
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ValueError: Procedure probably called with too many arguments (4 bytes in excess)
>>>
```

To find out the correct calling convention you have to look into the C header file or the documentation for the function you want to call.

On Windows, `ctypes` uses win32 structured exception handling to prevent crashes from general protection faults when functions are called with invalid argument values:

```
>>> windll.kernel32.GetModuleHandleA(32)
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
WindowsError: exception: access violation reading 0x00000020
>>>
```

There are, however, enough ways to crash Python with `ctypes`, so you should be careful anyway.

`None`, integers, longs, byte strings and unicode strings are the only native Python objects that can directly be used as parameters in these function calls. `None` is passed as a C `NULL` pointer, byte strings and unicode strings are passed as pointer to the memory block that contains their data (`char *` or `wchar_t *`). Python integers and Python longs are passed as the platforms default C `int` type, their value is masked to fit into the C type.

Before we move on calling functions with other parameter types, we have to learn more about *ctypes* data types.

Fundamental data types

ctypes defines a number of primitive C compatible data types:

ctypes type	C type	Python type
<code>c_bool</code>	<code>_Bool</code>	bool (1)
<code>c_char</code>	<code>char</code>	1-character string
<code>c_wchar</code>	<code>wchar_t</code>	1-character unicode string
<code>c_byte</code>	<code>char</code>	int/long
<code>c_ubyte</code>	unsigned char	int/long
<code>c_short</code>	<code>short</code>	int/long
<code>c_ushort</code>	unsigned short	int/long
<code>c_int</code>	<code>int</code>	int/long
<code>c_uint</code>	unsigned int	int/long
<code>c_long</code>	<code>long</code>	int/long
<code>c_ulong</code>	unsigned long	int/long
<code>c_longlong</code>	<code>__int64</code> or long long	int/long
<code>c_ulonglong</code>	unsigned <code>__int64</code> or unsigned long long	int/long
<code>c_float</code>	<code>float</code>	float
<code>c_double</code>	<code>double</code>	float
<code>c_longdouble</code>	long double	float
<code>c_char_p</code>	<code>char *</code> (NUL terminated)	string or None
<code>c_wchar_p</code>	<code>wchar_t *</code> (NUL terminated)	unicode or None
<code>c_void_p</code>	<code>void *</code>	int/long or None

(1) The constructor accepts any object with a truth value.

All these types can be created by calling them with an optional initializer of the correct type and value:

```
>>> c_int()
c_long(0)
>>> c_char_p("Hello, World")
c_char_p('Hello, World')
>>> c_ushort(-3)
c_ushort(65533)
>>>
```

Since these types are mutable, their value can also be changed afterwards:

```
>>> i = c_int(42)
>>> print i
c_long(42)
>>> print i.value
42
>>> i.value = -99
>>> print i.value
-99
>>>
```

Assigning a new value to instances of the pointer types `c_char_p`, `c_wchar_p`, and `c_void_p` changes the *memory location* they point to, *not the contents* of the memory block (of course not, because Python strings are immutable):

```

>>> s = "Hello, World"
>>> c_s = c_char_p(s)
>>> print c_s
c_char_p('Hello, World')
>>> c_s.value = "Hi, there"
>>> print c_s
c_char_p('Hi, there')
>>> print s
Hello, World
>>>

```

first string is unchanged

You should be careful, however, not to pass them to functions expecting pointers to mutable memory. If you need mutable memory blocks, ctypes has a `create_string_buffer()` function which creates these in various ways. The current memory block contents can be accessed (or changed) with the `raw` property; if you want to access it as NUL terminated string, use the `value` property:

```

>>> from ctypes import *
>>> p = create_string_buffer(3)      # create a 3 byte buffer, initialized to NUL
↳ bytes
>>> print sizeof(p), repr(p.raw)
3 '\x00\x00\x00'
>>> p = create_string_buffer("Hello") # create a buffer containing a NUL
↳ terminated string
>>> print sizeof(p), repr(p.raw)
6 'Hello\x00'
>>> print repr(p.value)
'Hello'
>>> p = create_string_buffer("Hello", 10) # create a 10 byte buffer
>>> print sizeof(p), repr(p.raw)
10 'Hello\x00\x00\x00\x00\x00\x00'
>>> p.value = "Hi"
>>> print sizeof(p), repr(p.raw)
10 'Hi\x00lo\x00\x00\x00\x00\x00'
>>>

```

The `create_string_buffer()` function replaces the `c_buffer()` function (which is still available as an alias), as well as the `c_string()` function from earlier ctypes releases. To create a mutable memory block containing unicode characters of the C type `wchar_t` use the `create_unicode_buffer()` function.

Calling functions, continued

Note that `printf` prints to the real standard output channel, *not* to `sys.stdout`, so these examples will only work at the console prompt, not from within *IDLE* or *Python Win*:

```

>>> printf = libc.printf
>>> printf("Hello, %s\n", "World!")
Hello, World!
14
>>> printf("Hello, %S\n", u"World!")
Hello, World!
14
>>> printf("%d bottles of beer\n", 42)
42 bottles of beer
19
>>> printf("%f bottles of beer\n", 42.5)

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ArgumentError: argument 2: exceptions.TypeError: Don't know how to convert parameter 2
>>>
```

As has been mentioned before, all Python types except integers, strings, and unicode strings have to be wrapped in their corresponding *ctypes* type, so that they can be converted to the required C data type:

```
>>> printf("An int %d, a double %f\n", 1234, c_double(3.14))
An int 1234, a double 3.140000
31
>>>
```

Calling functions with your own custom data types

You can also customize *ctypes* argument conversion to allow instances of your own classes be used as function arguments. *ctypes* looks for an `_as_parameter_` attribute and uses this as the function argument. Of course, it must be one of integer, string, or unicode:

```
>>> class Bottles(object):
...     def __init__(self, number):
...         self._as_parameter_ = number
...
>>> bottles = Bottles(42)
>>> printf("%d bottles of beer\n", bottles)
42 bottles of beer
19
>>>
```

If you don't want to store the instance's data in the `_as_parameter_` instance variable, you could define a *property()* which makes the data available.

Specifying the required argument types (function prototypes)

It is possible to specify the required argument types of functions exported from DLLs by setting the `argtypes` attribute.

`argtypes` must be a sequence of C data types (the `printf` function is probably not a good example here, because it takes a variable number and different types of parameters depending on the format string, on the other hand this is quite handy to experiment with this feature):

```
>>> printf.argtypes = [c_char_p, c_char_p, c_int, c_double]
>>> printf("String '%s', Int %d, Double %f\n", "Hi", 10, 2.2)
String 'Hi', Int 10, Double 2.200000
37
>>>
```

Specifying a format protects against incompatible argument types (just as a prototype for a C function), and tries to convert the arguments to valid types:

```
>>> printf("%d %d %d", 1, 2, 3)
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ArgumentError: argument 2: exceptions.TypeError: wrong type
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> printf("%s %d %f\n", "x", 2, 3)
x 2 3.000000
13
>>>
```

If you have defined your own classes which you pass to function calls, you have to implement a `from_param()` class method for them to be able to use them in the `argtypes` sequence. The `from_param()` class method receives the Python object passed to the function call, it should do a typecheck or whatever is needed to make sure this object is acceptable, and then return the object itself, its `_as_parameter_` attribute, or whatever you want to pass as the C function argument in this case. Again, the result should be an integer, string, unicode, a `ctypes` instance, or an object with an `_as_parameter_` attribute.

Return types

By default functions are assumed to return the C `int` type. Other return types can be specified by setting the `restype` attribute of the function object.

Here is a more advanced example, it uses the `strchr` function, which expects a string pointer and a char, and returns a pointer to a string:

```
>>> strchr = libc.strchr
>>> strchr("abcdef", ord("d"))
8059983
>>> strchr.restype = c_char_p    # c_char_p is a pointer to a string
>>> strchr("abcdef", ord("d"))
'def'
>>> print strchr("abcdef", ord("x"))
None
>>>
```

If you want to avoid the `ord("x")` calls above, you can set the `argtypes` attribute, and the second argument will be converted from a single character Python string into a C char:

```
>>> strchr.restype = c_char_p
>>> strchr.argtypes = [c_char_p, c_char]
>>> strchr("abcdef", "d")
'def'
>>> strchr("abcdef", "def")
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ArgumentError: argument 2: exceptions.TypeError: one character string expected
>>> print strchr("abcdef", "x")
None
>>> strchr("abcdef", "d")
'def'
>>>
```

You can also use a callable Python object (a function or a class for example) as the `restype` attribute, if the foreign function returns an integer. The callable will be called with the *integer* the C function returns, and the result of this call will be used as the result of your function call. This is useful to check for error return values and automatically raise an exception:

```
>>> GetModuleHandle = windll.kernel32.GetModuleHandleA
>>> def ValidHandle(value):
...     if value == 0:
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

...         raise WinError()
...     return value
...
>>>
>>> GetModuleHandle.restype = ValidHandle
>>> GetModuleHandle(None)
486539264
>>> GetModuleHandle("something silly")
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
  File "<stdin>", line 3, in ValidHandle
WindowsError: [Errno 126] The specified module could not be found.
>>>

```

`WinError` is a function which will call `Windows FormatMessage()` api to get the string representation of an error code, and *returns* an exception. `WinError` takes an optional error code parameter, if no one is used, it calls `GetLastError()` to retrieve it.

Please note that a much more powerful error checking mechanism is available through the `errcheck` attribute; see the reference manual for details.

Passing pointers (or: passing parameters by reference)

Sometimes a C api function expects a *pointer* to a data type as parameter, probably to write into the corresponding location, or if the data is too large to be passed by value. This is also known as *passing parameters by reference*.

`ctypes` exports the `byref()` function which is used to pass parameters by reference. The same effect can be achieved with the `pointer()` function, although `pointer()` does a lot more work since it constructs a real pointer object, so it is faster to use `byref()` if you don't need the pointer object in Python itself:

```

>>> i = c_int()
>>> f = c_float()
>>> s = create_string_buffer('\000' * 32)
>>> print i.value, f.value, repr(s.value)
0 0.0 ''
>>> libc.sscanf("1 3.14 Hello", "%d %f %s",
...             byref(i), byref(f), s)
3
>>> print i.value, f.value, repr(s.value)
1 3.1400001049 'Hello'
>>>

```

Structures and unions

Structures and unions must derive from the `Structure` and `Union` base classes which are defined in the `ctypes` module. Each subclass must define a `_fields_` attribute. `_fields_` must be a list of *2-tuples*, containing a *field name* and a *field type*.

The field type must be a `ctypes` type like `c_int`, or any other derived `ctypes` type: structure, union, array, pointer.

Here is a simple example of a POINT structure, which contains two integers named *x* and *y*, and also shows how to initialize a structure in the constructor:

```

>>> from ctypes import *
>>> class POINT(Structure):
...     _fields_ = [("x", c_int),
...                 ("y", c_int)]
...
>>> point = POINT(10, 20)
>>> print point.x, point.y
10 20
>>> point = POINT(y=5)
>>> print point.x, point.y
0 5
>>> POINT(1, 2, 3)
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
TypeError: too many initializers
>>>

```

You can, however, build much more complicated structures. A structure can itself contain other structures by using a structure as a field type.

Here is a RECT structure which contains two POINTs named *upperleft* and *lowerright*:

```

>>> class RECT(Structure):
...     _fields_ = [("upperleft", POINT),
...                 ("lowerright", POINT)]
...
>>> rc = RECT(point)
>>> print rc.upperleft.x, rc.upperleft.y
0 5
>>> print rc.lowerright.x, rc.lowerright.y
0 0
>>>

```

Nested structures can also be initialized in the constructor in several ways:

```

>>> r = RECT(POINT(1, 2), POINT(3, 4))
>>> r = RECT((1, 2), (3, 4))

```

Field *descriptors* can be retrieved from the *class*, they are useful for debugging because they can provide useful information:

```

>>> print POINT.x
<Field type=c_long, ofs=0, size=4>
>>> print POINT.y
<Field type=c_long, ofs=4, size=4>
>>>

```

경고: `ctypes` does not support passing unions or structures with bit-fields to functions by value. While this may work on 32-bit x86, it's not guaranteed by the library to work in the general case. Unions and structures with bit-fields should always be passed to functions by pointer.

Structure/union alignment and byte order

By default, Structure and Union fields are aligned in the same way the C compiler does it. It is possible to override this behavior by specifying a `_pack_` class attribute in the subclass definition. This must be set to a positive integer and specifies the maximum alignment for the fields. This is what `#pragma pack(n)` also does in MSVC.

`ctypes` uses the native byte order for Structures and Unions. To build structures with non-native byte order, you can use one of the `BigEndianStructure`, `LittleEndianStructure`, `BigEndianUnion`, and `LittleEndianUnion` base classes. These classes cannot contain pointer fields.

Bit fields in structures and unions

It is possible to create structures and unions containing bit fields. Bit fields are only possible for integer fields, the bit width is specified as the third item in the `_fields_` tuples:

```
>>> class Int(Structure):
...     _fields_ = [("first_16", c_int, 16),
...                 ("second_16", c_int, 16)]
...
>>> print Int.first_16
<Field type=c_long, ofs=0:0, bits=16>
>>> print Int.second_16
<Field type=c_long, ofs=0:16, bits=16>
>>>
```

Arrays

Arrays are sequences, containing a fixed number of instances of the same type.

The recommended way to create array types is by multiplying a data type with a positive integer:

```
TenPointsArrayType = POINT * 10
```

Here is an example of a somewhat artificial data type, a structure containing 4 POINTs among other stuff:

```
>>> from ctypes import *
>>> class POINT(Structure):
...     _fields_ = ("x", c_int), ("y", c_int)
...
>>> class MyStruct(Structure):
...     _fields_ = [("a", c_int),
...                 ("b", c_float),
...                 ("point_array", POINT * 4)]
>>>
>>> print len(MyStruct().point_array)
4
>>>
```

Instances are created in the usual way, by calling the class:

```
arr = TenPointsArrayType()
for pt in arr:
    print pt.x, pt.y
```

The above code prints a series of 0 0 lines, because the array contents is initialized to zeros.

Initializers of the correct type can also be specified:

```
>>> from ctypes import *
>>> TenIntegers = c_int * 10
>>> ii = TenIntegers(1, 2, 3, 4, 5, 6, 7, 8, 9, 10)
>>> print ii
<c_long_Array_10 object at 0x...>
>>> for i in ii: print i,
...
1 2 3 4 5 6 7 8 9 10
>>>
```

Pointers

Pointer instances are created by calling the `pointer()` function on a `ctypes` type:

```
>>> from ctypes import *
>>> i = c_int(42)
>>> pi = pointer(i)
>>>
```

Pointer instances have a `contents` attribute which returns the object to which the pointer points, the `i` object above:

```
>>> pi.contents
c_long(42)
>>>
```

Note that `ctypes` does not have OOR (original object return), it constructs a new, equivalent object each time you retrieve an attribute:

```
>>> pi.contents is i
False
>>> pi.contents is pi.contents
False
>>>
```

Assigning another `c_int` instance to the pointer's `contents` attribute would cause the pointer to point to the memory location where this is stored:

```
>>> i = c_int(99)
>>> pi.contents = i
>>> pi.contents
c_long(99)
>>>
```

Pointer instances can also be indexed with integers:

```
>>> pi[0]
99
>>>
```

Assigning to an integer index changes the pointed to value:

```
>>> print i
c_long(99)
>>> pi[0] = 22
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> print i
c_long(22)
>>>
```

It is also possible to use indexes different from 0, but you must know what you're doing, just as in C: You can access or change arbitrary memory locations. Generally you only use this feature if you receive a pointer from a C function, and you *know* that the pointer actually points to an array instead of a single item.

Behind the scenes, the `pointer()` function does more than simply create pointer instances, it has to create pointer *types* first. This is done with the `POINTER()` function, which accepts any *ctypes* type, and returns a new type:

```
>>> PI = POINTER(c_int)
>>> PI
<class 'ctypes.LP_c_int'>
>>> PI(42)
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
TypeError: expected c_int instead of int
>>> PI(c_int(42))
<ctypes.LP_c_int object at 0x...>
>>>
```

Calling the pointer type without an argument creates a NULL pointer. NULL pointers have a `False` boolean value:

```
>>> null_ptr = POINTER(c_int)()
>>> print bool(null_ptr)
False
>>>
```

ctypes checks for NULL when dereferencing pointers (but dereferencing invalid non-NULL pointers would crash Python):

```
>>> null_ptr[0]
Traceback (most recent call last):
  ....
ValueError: NULL pointer access
>>>

>>> null_ptr[0] = 1234
Traceback (most recent call last):
  ....
ValueError: NULL pointer access
>>>
```

Type conversions

Usually, *ctypes* does strict type checking. This means, if you have `POINTER(c_int)` in the `argtypes` list of a function or as the type of a member field in a structure definition, only instances of exactly the same type are accepted. There are some exceptions to this rule, where *ctypes* accepts other objects. For example, you can pass compatible array instances instead of pointer types. So, for `POINTER(c_int)`, *ctypes* accepts an array of `c_int`:

```
>>> class Bar(Structure):
...     _fields_ = [("count", c_int), ("values", POINTER(c_int))]
... 
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

>>> bar = Bar()
>>> bar.values = (c_int * 3)(1, 2, 3)
>>> bar.count = 3
>>> for i in range(bar.count):
...     print bar.values[i]
...
1
2
3
>>>

```

In addition, if a function argument is explicitly declared to be a pointer type (such as `POINTER(c_int)`) in `argtypes`, an object of the pointed type (`c_int` in this case) can be passed to the function. `ctypes` will apply the required *byref()* conversion in this case automatically.

To set a `POINTER` type field to `NULL`, you can assign `None`:

```

>>> bar.values = None
>>>

```

Sometimes you have instances of incompatible types. In C, you can cast one type into another type. `ctypes` provides a `cast()` function which can be used in the same way. The `Bar` structure defined above accepts `POINTER(c_int)` pointers or `c_int` arrays for its `values` field, but not instances of other types:

```

>>> bar.values = (c_byte * 4)()
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
TypeError: incompatible types, c_byte_Array_4 instance instead of LP_c_long instance
>>>

```

For these cases, the `cast()` function is handy.

The `cast()` function can be used to cast a `ctypes` instance into a pointer to a different `ctypes` data type. `cast()` takes two parameters, a `ctypes` object that is or can be converted to a pointer of some kind, and a `ctypes` pointer type. It returns an instance of the second argument, which references the same memory block as the first argument:

```

>>> a = (c_byte * 4)()
>>> cast(a, POINTER(c_int))
<ctypes.LP_c_long object at ...>
>>>

```

So, `cast()` can be used to assign to the `values` field of `Bar` the structure:

```

>>> bar = Bar()
>>> bar.values = cast((c_byte * 4)(), POINTER(c_int))
>>> print bar.values[0]
0
>>>

```

Incomplete Types

Incomplete Types are structures, unions or arrays whose members are not yet specified. In C, they are specified by forward declarations, which are defined later:

```
struct cell; /* forward declaration */

struct cell {
    char *name;
    struct cell *next;
};
```

The straightforward translation into ctypes code would be this, but it does not work:

```
>>> class cell(Structure):
...     _fields_ = [("name", c_char_p),
...                 ("next", POINTER(cell))]
...
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
  File "<stdin>", line 2, in cell
NameError: name 'cell' is not defined
>>>
```

because the new class `cell` is not available in the class statement itself. In *ctypes*, we can define the `cell` class and set the `_fields_` attribute later, after the class statement:

```
>>> from ctypes import *
>>> class cell(Structure):
...     pass
...
>>> cell._fields_ = [("name", c_char_p),
...                  ("next", POINTER(cell))]
>>>
```

Lets try it. We create two instances of `cell`, and let them point to each other, and finally follow the pointer chain a few times:

```
>>> c1 = cell()
>>> c1.name = "foo"
>>> c2 = cell()
>>> c2.name = "bar"
>>> c1.next = pointer(c2)
>>> c2.next = pointer(c1)
>>> p = c1
>>> for i in range(8):
...     print p.name,
...     p = p.next[0]
...
foo bar foo bar foo bar foo bar
>>>
```

Callback functions

`ctypes` allows creating C callable function pointers from Python callables. These are sometimes called *callback functions*.

First, you must create a class for the callback function, the class knows the calling convention, the return type, and the number and types of arguments this function will receive.

The `CFUNCTYPE` factory function creates types for callback functions using the normal `cdecl` calling convention, and, on Windows, the `WINFUNCTYPE` factory function creates types for callback functions using the `stdcall` calling convention.

Both of these factory functions are called with the result type as first argument, and the callback functions expected argument types as the remaining arguments.

I will present an example here which uses the standard C library's `qsort()` function, this is used to sort items with the help of a callback function. `qsort()` will be used to sort an array of integers:

```
>>> IntArray5 = c_int * 5
>>> ia = IntArray5(5, 1, 7, 33, 99)
>>> qsort = libc.qsort
>>> qsort.restype = None
>>>
```

`qsort()` must be called with a pointer to the data to sort, the number of items in the data array, the size of one item, and a pointer to the comparison function, the callback. The callback will then be called with two pointers to items, and it must return a negative integer if the first item is smaller than the second, a zero if they are equal, and a positive integer else.

So our callback function receives pointers to integers, and must return an integer. First we create the type for the callback function:

```
>>> CMPFUNC = CFUNCTYPE(c_int, POINTER(c_int), POINTER(c_int))
>>>
```

For the first implementation of the callback function, we simply print the arguments we get, and return 0 (incremental development ;-):

```
>>> def py_cmp_func(a, b):
...     print "py_cmp_func", a, b
...     return 0
...
>>>
```

Create the C callable callback:

```
>>> cmp_func = CMPFUNC(py_cmp_func)
>>>
```

And we're ready to go:

```
>>> qsort(ia, len(ia), sizeof(c_int), cmp_func)
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
>>>

```

We know how to access the contents of a pointer, so let's redefine our callback:

```

>>> def py_cmp_func(a, b):
...     print "py_cmp_func", a[0], b[0]
...     return 0
...
>>> cmp_func = CMPFUNC(py_cmp_func)
>>>

```

Here is what we get on Windows:

```

>>> qsort(ia, len(ia), sizeof(c_int), cmp_func)
py_cmp_func 7 1
py_cmp_func 33 1
py_cmp_func 99 1
py_cmp_func 5 1
py_cmp_func 7 5
py_cmp_func 33 5
py_cmp_func 99 5
py_cmp_func 7 99
py_cmp_func 33 99
py_cmp_func 7 33
>>>

```

It is funny to see that on linux the sort function seems to work much more efficiently, it is doing less comparisons:

```

>>> qsort(ia, len(ia), sizeof(c_int), cmp_func)
py_cmp_func 5 1
py_cmp_func 33 99
py_cmp_func 7 33
py_cmp_func 5 7
py_cmp_func 1 7
>>>

```

Ah, we're nearly done! The last step is to actually compare the two items and return a useful result:

```

>>> def py_cmp_func(a, b):
...     print "py_cmp_func", a[0], b[0]
...     return a[0] - b[0]
...
>>>

```

Final run on Windows:

```

>>> qsort(ia, len(ia), sizeof(c_int), CMPFUNC(py_cmp_func))
py_cmp_func 33 7
py_cmp_func 99 33
py_cmp_func 5 99
py_cmp_func 1 99
py_cmp_func 33 7
py_cmp_func 1 33

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
py_cmp_func 5 33
py_cmp_func 5 7
py_cmp_func 1 7
py_cmp_func 5 1
>>>
```

and on Linux:

```
>>> qsort(ia, len(ia), sizeof(c_int), CMPFUNC(py_cmp_func))
py_cmp_func 5 1
py_cmp_func 33 99
py_cmp_func 7 33
py_cmp_func 1 7
py_cmp_func 5 7
>>>
```

It is quite interesting to see that the Windows `qsort()` function needs more comparisons than the linux version!

As we can easily check, our array is sorted now:

```
>>> for i in ia: print i,
...
1 5 7 33 99
>>>
```

참고: Make sure you keep references to `CFUNCTYPE()` objects as long as they are used from C code. `ctypes` doesn't, and if you don't, they may be garbage collected, crashing your program when a callback is made.

Also, note that if the callback function is called in a thread created outside of Python's control (e.g. by the foreign code that calls the callback), `ctypes` creates a new dummy Python thread on every invocation. This behavior is correct for most purposes, but it means that values stored with `threading.local` will *not* survive across different callbacks, even when those calls are made from the same C thread.

Accessing values exported from dlls

Some shared libraries not only export functions, they also export variables. An example in the Python library itself is the `Py_OptimizeFlag`, an integer set to 0, 1, or 2, depending on the `-O` or `-OO` flag given on startup.

`ctypes` can access values like this with the `in_dll()` class methods of the type. `pythonapi` is a predefined symbol giving access to the Python C api:

```
>>> opt_flag = c_int.in_dll(pythonapi, "Py_OptimizeFlag")
>>> print opt_flag
c_long(0)
>>>
```

If the interpreter would have been started with `-O`, the sample would have printed `c_long(1)`, or `c_long(2)` if `-OO` would have been specified.

An extended example which also demonstrates the use of pointers accesses the `PyImport_FrozenModules` pointer exported by Python.

Quoting the Python docs: *This pointer is initialized to point to an array of `struct _frozen` records, terminated by one whose members are all NULL or zero. When a frozen module is imported, it is searched in this table. Third-party code could play tricks with this to provide a dynamically created collection of frozen modules.*

So manipulating this pointer could even prove useful. To restrict the example size, we show only how this table can be read with `ctypes`:

```
>>> from ctypes import *
>>>
>>> class struct_frozen(Structure):
...     _fields_ = [("name", c_char_p),
...                 ("code", POINTER(c_ubyte)),
...                 ("size", c_int)]
...
>>>
```

We have defined the struct `_frozen` data type, so we can get the pointer to the table:

```
>>> FrozenTable = POINTER(struct_frozen)
>>> table = FrozenTable.in_dll(pythonapi, "PyImport_FrozenModules")
>>>
```

Since `table` is a pointer to the array of `struct_frozen` records, we can iterate over it, but we just have to make sure that our loop terminates, because pointers have no size. Sooner or later it would probably crash with an access violation or whatever, so it's better to break out of the loop when we hit the NULL entry:

```
>>> for item in table:
...     print item.name, item.size
...     if item.name is None:
...         break
...
__hello__ 104
__phello__ -104
__phello__.spam 104
None 0
>>>
```

The fact that standard Python has a frozen module and a frozen package (indicated by the negative size member) is not well known, it is only used for testing. Try it out with `import __hello__` for example.

Surprises

There are some edge cases in `ctypes` where you might expect something other than what actually happens.

Consider the following example:

```
>>> from ctypes import *
>>> class POINT(Structure):
...     _fields_ = ("x", c_int), ("y", c_int)
...
>>> class RECT(Structure):
...     _fields_ = ("a", POINT), ("b", POINT)
...
>>> p1 = POINT(1, 2)
>>> p2 = POINT(3, 4)
>>> rc = RECT(p1, p2)
>>> print rc.a.x, rc.a.y, rc.b.x, rc.b.y
1 2 3 4
>>> # now swap the two points
>>> rc.a, rc.b = rc.b, rc.a
>>> print rc.a.x, rc.a.y, rc.b.x, rc.b.y
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
3 4 3 4
>>>
```

Hm. We certainly expected the last statement to print 3 4 1 2. What happened? Here are the steps of the `rc.a`, `rc.b = rc.b`, `rc.a` line above:

```
>>> temp0, temp1 = rc.b, rc.a
>>> rc.a = temp0
>>> rc.b = temp1
>>>
```

Note that `temp0` and `temp1` are objects still using the internal buffer of the `rc` object above. So executing `rc.a = temp0` copies the buffer contents of `temp0` into `rc`'s buffer. This, in turn, changes the contents of `temp1`. So, the last assignment `rc.b = temp1`, doesn't have the expected effect.

Keep in mind that retrieving sub-objects from Structure, Unions, and Arrays doesn't *copy* the sub-object, instead it retrieves a wrapper object accessing the root-object's underlying buffer.

Another example that may behave different from what one would expect is this:

```
>>> s = c_char_p()
>>> s.value = "abc def ghi"
>>> s.value
'abc def ghi'
>>> s.value is s.value
False
>>>
```

Why is it printing `False`? `ctypes` instances are objects containing a memory block plus some *descriptors* accessing the contents of the memory. Storing a Python object in the memory block does not store the object itself, instead the contents of the object is stored. Accessing the contents again constructs a new Python object each time!

Variable-sized data types

`ctypes` provides some support for variable-sized arrays and structures.

The `resize()` function can be used to resize the memory buffer of an existing `ctypes` object. The function takes the object as first argument, and the requested size in bytes as the second argument. The memory block cannot be made smaller than the natural memory block specified by the objects type, a `ValueError` is raised if this is tried:

```
>>> short_array = (c_short * 4)()
>>> print sizeof(short_array)
8
>>> resize(short_array, 4)
Traceback (most recent call last):
...
ValueError: minimum size is 8
>>> resize(short_array, 32)
>>> sizeof(short_array)
32
>>> sizeof(type(short_array))
8
>>>
```

This is nice and fine, but how would one access the additional elements contained in this array? Since the type still only knows about 4 elements, we get errors accessing other elements:


```
>>> short_array[:]
[0, 0, 0, 0]
>>> short_array[7]
Traceback (most recent call last):
...
IndexError: invalid index
>>>
```

Another way to use variable-sized data types with *ctypes* is to use the dynamic nature of Python, and (re-)define the data type after the required size is already known, on a case by case basis.

15.17.2 ctypes reference

Finding shared libraries

When programming in a compiled language, shared libraries are accessed when compiling/linking a program, and when the program is run.

The purpose of the `find_library()` function is to locate a library in a way similar to what the compiler does (on platforms with several versions of a shared library the most recent should be loaded), while the *ctypes* library loaders act like when a program is run, and call the runtime loader directly.

The `ctypes.util` module provides a function which can help to determine the library to load.

`ctypes.util.find_library(name)`

Try to find a library and return a pathname. *name* is the library name without any prefix like *lib*, suffix like *.so*, *.dylib* or version number (this is the form used for the *posix* linker option *-l*). If no library can be found, returns *None*.

The exact functionality is system dependent.

On Linux, `find_library()` tries to run external programs (*/sbin/ldconfig*, *gcc*, and *objdump*) to find the library file. It returns the filename of the library file. Here are some examples:

```
>>> from ctypes.util import find_library
>>> find_library("m")
'libm.so.6'
>>> find_library("c")
'libc.so.6'
>>> find_library("bz2")
'libbz2.so.1.0'
>>>
```

On OS X, `find_library()` tries several predefined naming schemes and paths to locate the library, and returns a full pathname if successful:

```
>>> from ctypes.util import find_library
>>> find_library("c")
'/usr/lib/libc.dylib'
>>> find_library("m")
'/usr/lib/libm.dylib'
>>> find_library("bz2")
'/usr/lib/libbz2.dylib'
>>> find_library("AGL")
'/System/Library/Frameworks/AGL.framework/AGL'
>>>
```

On Windows, `find_library()` searches along the system search path, and returns the full pathname, but since there is no predefined naming scheme a call like `find_library("c")` will fail and return `None`.

If wrapping a shared library with `ctypes`, it *may* be better to determine the shared library name at development time, and hardcode that into the wrapper module instead of using `find_library()` to locate the library at runtime.

Loading shared libraries

There are several ways to load shared libraries into the Python process. One way is to instantiate one of the following classes:

class `ctypes.CDLL`(*name*, *mode*=`DEFAULT_MODE`, *handle*=`None`, *use_errno*=`False`,
 use_last_error=`False`)
Instances of this class represent loaded shared libraries. Functions in these libraries use the standard C calling convention, and are assumed to return `int`.

class `ctypes.OleDLL`(*name*, *mode*=`DEFAULT_MODE`, *handle*=`None`, *use_errno*=`False`,
 use_last_error=`False`)
Windows only: Instances of this class represent loaded shared libraries, functions in these libraries use the `stdcall` calling convention, and are assumed to return the windows specific `HRESULT` code. `HRESULT` values contain information specifying whether the function call failed or succeeded, together with additional error code. If the return value signals a failure, an `WindowsError` is automatically raised.

class `ctypes.WinDLL`(*name*, *mode*=`DEFAULT_MODE`, *handle*=`None`, *use_errno*=`False`,
 use_last_error=`False`)
Windows only: Instances of this class represent loaded shared libraries, functions in these libraries use the `stdcall` calling convention, and are assumed to return `int` by default.

On Windows CE only the standard calling convention is used, for convenience the `WinDLL` and `OleDLL` use the standard calling convention on this platform.

The Python *global interpreter lock* is released before calling any function exported by these libraries, and reacquired afterwards.

class `ctypes.PyDLL`(*name*, *mode*=`DEFAULT_MODE`, *handle*=`None`)
Instances of this class behave like `CDLL` instances, except that the Python GIL is *not* released during the function call, and after the function execution the Python error flag is checked. If the error flag is set, a Python exception is raised.

Thus, this is only useful to call Python C api functions directly.

All these classes can be instantiated by calling them with at least one argument, the pathname of the shared library. If you have an existing handle to an already loaded shared library, it can be passed as the `handle` named parameter, otherwise the underlying platforms `dlopen` or `LoadLibrary` function is used to load the library into the process, and to get a handle to it.

The *mode* parameter can be used to specify how the library is loaded. For details, consult the `dlopen(3)` manpage. On Windows, *mode* is ignored. On posix systems, `RTLD_NOW` is always added, and is not configurable.

The *use_errno* parameter, when set to true, enables a ctypes mechanism that allows accessing the system `errno` error number in a safe way. `ctypes` maintains a thread-local copy of the systems `errno` variable; if you call foreign functions created with `use_errno=True` then the `errno` value before the function call is swapped with the ctypes private copy, the same happens immediately after the function call.

The function `ctypes.get_errno()` returns the value of the ctypes private copy, and the function `ctypes.set_errno()` changes the ctypes private copy to a new value and returns the former value.

The *use_last_error* parameter, when set to true, enables the same mechanism for the Windows error code which is managed by the `GetLastError()` and `SetLastError()` Windows API functions; `ctypes.get_last_error()` and `ctypes.set_last_error()` are used to request and change the ctypes private copy of the windows error code.

버전 2.6에 추가: The *use_last_error* and *use_errno* optional parameters were added.

`ctypes.RTLD_GLOBAL`

Flag to use as *mode* parameter. On platforms where this flag is not available, it is defined as the integer zero.

`ctypes.RTLD_LOCAL`

Flag to use as *mode* parameter. On platforms where this is not available, it is the same as *RTLD_GLOBAL*.

`ctypes.DEFAULT_MODE`

The default mode which is used to load shared libraries. On OSX 10.3, this is *RTLD_GLOBAL*, otherwise it is the same as *RTLD_LOCAL*.

Instances of these classes have no public methods. Functions exported by the shared library can be accessed as attributes or by index. Please note that accessing the function through an attribute caches the result and therefore accessing it repeatedly returns the same object each time. On the other hand, accessing it through an index returns a new object each time:

```
>>> libc.time == libc.time
True
>>> libc['time'] == libc['time']
False
```

The following public attributes are available, their name starts with an underscore to not clash with exported function names:

`PyDLL._handle`

The system handle used to access the library.

`PyDLL._name`

The name of the library passed in the constructor.

Shared libraries can also be loaded by using one of the prefabricated objects, which are instances of the *LibraryLoader* class, either by calling the `LoadLibrary()` method, or by retrieving the library as attribute of the loader instance.

class `ctypes.LibraryLoader` (*dlltype*)

Class which loads shared libraries. *dlltype* should be one of the *CDLL*, *PyDLL*, *WinDLL*, or *OleDLL* types.

`__getattr__()` has special behavior: It allows loading a shared library by accessing it as attribute of a library loader instance. The result is cached, so repeated attribute accesses return the same library each time.

LoadLibrary (*name*)

Load a shared library into the process and return it. This method always returns a new instance of the library.

These prefabricated library loaders are available:

`ctypes.cdll`

Creates *CDLL* instances.

`ctypes.windll`

Windows only: Creates *WinDLL* instances.

`ctypes.oledll`

Windows only: Creates *OleDLL* instances.

`ctypes.pydll`

Creates *PyDLL* instances.

For accessing the C Python api directly, a ready-to-use Python shared library object is available:

`ctypes.pythonapi`

An instance of *PyDLL* that exposes Python C API functions as attributes. Note that all these functions are assumed

to return `C int`, which is of course not always the truth, so you have to assign the correct `restype` attribute to use these functions.

Foreign functions

As explained in the previous section, foreign functions can be accessed as attributes of loaded shared libraries. The function objects created in this way by default accept any number of arguments, accept any ctypes data instances as arguments, and return the default result type specified by the library loader. They are instances of a private class:

class `ctypes._FuncPtr`

Base class for C callable foreign functions.

Instances of foreign functions are also C compatible data types; they represent C function pointers.

This behavior can be customized by assigning to special attributes of the foreign function object.

restype

Assign a ctypes type to specify the result type of the foreign function. Use `None` for `void`, a function not returning anything.

It is possible to assign a callable Python object that is not a ctypes type, in this case the function is assumed to return a `C int`, and the callable will be called with this integer, allowing further processing or error checking. Using this is deprecated, for more flexible post processing or error checking use a ctypes data type as `restype` and assign a callable to the `errcheck` attribute.

argtypes

Assign a tuple of ctypes types to specify the argument types that the function accepts. Functions using the `stdcall` calling convention can only be called with the same number of arguments as the length of this tuple; functions using the C calling convention accept additional, unspecified arguments as well.

When a foreign function is called, each actual argument is passed to the `from_param()` class method of the items in the `argtypes` tuple, this method allows adapting the actual argument to an object that the foreign function accepts. For example, a `c_char_p` item in the `argtypes` tuple will convert a unicode string passed as argument into a byte string using ctypes conversion rules.

New: It is now possible to put items in `argtypes` which are not ctypes types, but each item must have a `from_param()` method which returns a value usable as argument (integer, string, ctypes instance). This allows defining adapters that can adapt custom objects as function parameters.

errcheck

Assign a Python function or another callable to this attribute. The callable will be called with three or more arguments:

callable (*result, func, arguments*)

result is what the foreign function returns, as specified by the `restype` attribute.

func is the foreign function object itself, this allows reusing the same callable object to check or post process the results of several functions.

arguments is a tuple containing the parameters originally passed to the function call, this allows specializing the behavior on the arguments used.

The object that this function returns will be returned from the foreign function call, but it can also check the result value and raise an exception if the foreign function call failed.

exception `ctypes.ArgumentError`

This exception is raised when a foreign function call cannot convert one of the passed arguments.

Function prototypes

Foreign functions can also be created by instantiating function prototypes. Function prototypes are similar to function prototypes in C; they describe a function (return type, argument types, calling convention) without defining an implementation. The factory functions must be called with the desired result type and the argument types of the function.

`ctypes.CFUNCTYPE` (*restype*, **argtypes*, *use_errno*=False, *use_last_error*=False)

The returned function prototype creates functions that use the standard C calling convention. The function will release the GIL during the call. If *use_errno* is set to true, the ctypes private copy of the system `errno` variable is exchanged with the real `errno` value before and after the call; *use_last_error* does the same for the Windows error code.

버전 2.6에서 변경: The optional *use_errno* and *use_last_error* parameters were added.

`ctypes.WINFUNCTYPE` (*restype*, **argtypes*, *use_errno*=False, *use_last_error*=False)

Windows only: The returned function prototype creates functions that use the `stdcall` calling convention, except on Windows CE where `WINFUNCTYPE()` is the same as `CFUNCTYPE()`. The function will release the GIL during the call. *use_errno* and *use_last_error* have the same meaning as above.

`ctypes.PYFUNCTYPE` (*restype*, **argtypes*)

The returned function prototype creates functions that use the Python calling convention. The function will *not* release the GIL during the call.

Function prototypes created by these factory functions can be instantiated in different ways, depending on the type and number of the parameters in the call:

prototype (*address*)

Returns a foreign function at the specified address which must be an integer.

prototype (*callable*)

Create a C callable function (a callback function) from a Python *callable*.

prototype (*func_spec*[, *paramflags*])

Returns a foreign function exported by a shared library. *func_spec* must be a 2-tuple (*name_or_ordinal*, *library*). The first item is the name of the exported function as string, or the ordinal of the exported function as small integer. The second item is the shared library instance.

prototype (*vtbl_index*, *name*[, *paramflags*[, *iid*]])

Returns a foreign function that will call a COM method. *vtbl_index* is the index into the virtual function table, a small non-negative integer. *name* is name of the COM method. *iid* is an optional pointer to the interface identifier which is used in extended error reporting.

COM methods use a special calling convention: They require a pointer to the COM interface as first argument, in addition to those parameters that are specified in the *argtypes* tuple.

The optional *paramflags* parameter creates foreign function wrappers with much more functionality than the features described above.

paramflags must be a tuple of the same length as *argtypes*.

Each item in this tuple contains further information about a parameter, it must be a tuple containing one, two, or three items.

The first item is an integer containing a combination of direction flags for the parameter:

- 1 Specifies an input parameter to the function.
- 2 Output parameter. The foreign function fills in a value.
- 4 Input parameter which defaults to the integer zero.

The optional second item is the parameter name as string. If this is specified, the foreign function can be called with named parameters.

The optional third item is the default value for this parameter.

This example demonstrates how to wrap the Windows `MessageBoxA` function so that it supports default parameters and named arguments. The C declaration from the windows header file is this:

```
WINUSERAPI int WINAPI
MessageBoxA(
    HWND hWnd,
    LPCSTR lpText,
    LPCSTR lpCaption,
    UINT uType);
```

Here is the wrapping with `ctypes`:

```
>>> from ctypes import c_int, WINFUNCTYPE, windll
>>> from ctypes.wintypes import HWND, LPCSTR, UINT
>>> prototype = WINFUNCTYPE(c_int, HWND, LPCSTR, LPCSTR, UINT)
>>> paramflags = (1, "hwnd", 0), (1, "text", "Hi"), (1, "caption", None), (1, "flags",
↳ 0)
>>> MessageBox = prototype(("MessageBoxA", windll.user32), paramflags)
>>>
```

The `MessageBox` foreign function can now be called in these ways:

```
>>> MessageBox()
>>> MessageBox(text="Spam, spam, spam")
>>> MessageBox(flags=2, text="foo bar")
>>>
```

A second example demonstrates output parameters. The win32 `GetWindowRect` function retrieves the dimensions of a specified window by copying them into `RECT` structure that the caller has to supply. Here is the C declaration:

```
WINUSERAPI BOOL WINAPI
GetWindowRect(
    HWND hWnd,
    LPRECT lpRect);
```

Here is the wrapping with `ctypes`:

```
>>> from ctypes import POINTER, WINFUNCTYPE, windll, WinError
>>> from ctypes.wintypes import BOOL, HWND, RECT
>>> prototype = WINFUNCTYPE(BOOL, HWND, POINTER(RECT))
>>> paramflags = (1, "hwnd"), (2, "lprect")
>>> GetWindowRect = prototype(("GetWindowRect", windll.user32), paramflags)
>>>
```

Functions with output parameters will automatically return the output parameter value if there is a single one, or a tuple containing the output parameter values when there are more than one, so the `GetWindowRect` function now returns a `RECT` instance, when called.

Output parameters can be combined with the `errcheck` protocol to do further output processing and error checking. The win32 `GetWindowRect` api function returns a `BOOL` to signal success or failure, so this function could do the error checking, and raises an exception when the api call failed:

```
>>> def errcheck(result, func, args):
...     if not result:
...         raise WinError()
...     return args
...
>>> GetWindowRect.errcheck = errcheck
>>>
```

If the `errcheck` function returns the argument tuple it receives unchanged, `ctypes` continues the normal processing it does on the output parameters. If you want to return a tuple of window coordinates instead of a `RECT` instance, you can retrieve the fields in the function and return them instead, the normal processing will no longer take place:

```
>>> def errcheck(result, func, args):
...     if not result:
...         raise WinError()
...     rc = args[1]
...     return rc.left, rc.top, rc.bottom, rc.right
...
>>> GetWindowRect.errcheck = errcheck
>>>
```

Utility functions

`ctypes.addressof(obj)`

Returns the address of the memory buffer as integer. *obj* must be an instance of a `ctypes` type.

`ctypes.alignment(obj_or_type)`

Returns the alignment requirements of a `ctypes` type. *obj_or_type* must be a `ctypes` type or instance.

`ctypes.byref(obj[, offset])`

Returns a light-weight pointer to *obj*, which must be an instance of a `ctypes` type. *offset* defaults to zero, and must be an integer that will be added to the internal pointer value.

`byref(obj, offset)` corresponds to this C code:

```
((char *)&obj) + offset)
```

The returned object can only be used as a foreign function call parameter. It behaves similar to `pointer(obj)`, but the construction is a lot faster.

버전 2.6에 추가: The *offset* optional argument was added.

`ctypes.cast(obj, type)`

This function is similar to the cast operator in C. It returns a new instance of *type* which points to the same memory block as *obj*. *type* must be a pointer type, and *obj* must be an object that can be interpreted as a pointer.

`ctypes.create_string_buffer(init_or_size[, size])`

This function creates a mutable character buffer. The returned object is a `ctypes` array of `c_char`.

init_or_size must be an integer which specifies the size of the array, or a string which will be used to initialize the array items.

If a string is specified as first argument, the buffer is made one item larger than the length of the string so that the last element in the array is a NUL termination character. An integer can be passed as second argument which allows specifying the size of the array if the length of the string should not be used.

If the first parameter is a unicode string, it is converted into an 8-bit string according to `ctypes` conversion rules.

`ctypes.create_unicode_buffer (init_or_size[, size])`

This function creates a mutable unicode character buffer. The returned object is a ctypes array of `c_wchar`.

`init_or_size` must be an integer which specifies the size of the array, or a unicode string which will be used to initialize the array items.

If a unicode string is specified as first argument, the buffer is made one item larger than the length of the string so that the last element in the array is a NUL termination character. An integer can be passed as second argument which allows specifying the size of the array if the length of the string should not be used.

If the first parameter is an 8-bit string, it is converted into a unicode string according to ctypes conversion rules.

`ctypes.DllCanUnloadNow ()`

Windows only: This function is a hook which allows implementing in-process COM servers with ctypes. It is called from the `DllCanUnloadNow` function that the `_ctypes` extension dll exports.

`ctypes.DllGetClassObject ()`

Windows only: This function is a hook which allows implementing in-process COM servers with ctypes. It is called from the `DllGetClassObject` function that the `_ctypes` extension dll exports.

`ctypes.util.find_library (name)`

Try to find a library and return a pathname. `name` is the library name without any prefix like `lib`, suffix like `.so`, `.dylib` or version number (this is the form used for the posix linker option `-l`). If no library can be found, returns `None`.

The exact functionality is system dependent.

버전 2.6에서 변경: Windows only: `find_library ("m")` or `find_library ("c")` return the result of a call to `find_msvcr()`.

`ctypes.util.find_msvcr ()`

Windows only: return the filename of the VC runtime library used by Python, and by the extension modules. If the name of the library cannot be determined, `None` is returned.

If you need to free memory, for example, allocated by an extension module with a call to the `free(void *)`, it is important that you use the function in the same library that allocated the memory.

버전 2.6에 추가.

`ctypes.FormatError ([code])`

Windows only: Returns a textual description of the error code `code`. If no error code is specified, the last error code is used by calling the Windows api function `GetLastError`.

`ctypes.GetLastError ()`

Windows only: Returns the last error code set by Windows in the calling thread. This function calls the Windows `GetLastError()` function directly, it does not return the ctypes-private copy of the error code.

`ctypes.get_errno ()`

Returns the current value of the ctypes-private copy of the system `errno` variable in the calling thread.

버전 2.6에 추가.

`ctypes.get_last_error ()`

Windows only: returns the current value of the ctypes-private copy of the system `LastError` variable in the calling thread.

버전 2.6에 추가.

`ctypes.memmove (dst, src, count)`

Same as the standard C `memmove` library function: copies `count` bytes from `src` to `dst`. `dst` and `src` must be integers or ctypes instances that can be converted to pointers.

`ctypes.memset(dst, c, count)`

Same as the standard C `memset` library function: fills the memory block at address *dst* with *count* bytes of value *c*. *dst* must be an integer specifying an address, or a `ctypes` instance.

`ctypes.POINTER(type)`

This factory function creates and returns a new `ctypes` pointer type. Pointer types are cached and reused internally, so calling this function repeatedly is cheap. *type* must be a `ctypes` type.

`ctypes.pointer(obj)`

This function creates a new pointer instance, pointing to *obj*. The returned object is of the type `POINTER(type(obj))`.

Note: If you just want to pass a pointer to an object to a foreign function call, you should use `byref(obj)` which is much faster.

`ctypes.resize(obj, size)`

This function resizes the internal memory buffer of *obj*, which must be an instance of a `ctypes` type. It is not possible to make the buffer smaller than the native size of the objects type, as given by `sizeof(type(obj))`, but it is possible to enlarge the buffer.

`ctypes.set_conversion_mode(encoding, errors)`

This function sets the rules that `ctypes` objects use when converting between 8-bit strings and unicode strings. *encoding* must be a string specifying an encoding, like `'utf-8'` or `'mbcs'`, *errors* must be a string specifying the error handling on encoding/decoding errors. Examples of possible values are `"strict"`, `"replace"`, or `"ignore"`.

`set_conversion_mode()` returns a 2-tuple containing the previous conversion rules. On windows, the initial conversion rules are `('mbcs', 'ignore')`, on other systems `('ascii', 'strict')`.

`ctypes.set_errno(value)`

Set the current value of the `ctypes`-private copy of the system `errno` variable in the calling thread to *value* and return the previous value.

버전 2.6에 추가.

`ctypes.set_last_error(value)`

Windows only: set the current value of the `ctypes`-private copy of the system `LastError` variable in the calling thread to *value* and return the previous value.

버전 2.6에 추가.

`ctypes.sizeof(obj_or_type)`

Returns the size in bytes of a `ctypes` type or instance memory buffer. Does the same as the C `sizeof` operator.

`ctypes.string_at(address[, size])`

This function returns the string starting at memory address *address*. If *size* is specified, it is used as size, otherwise the string is assumed to be zero-terminated.

`ctypes.WinError(code=None, descr=None)`

Windows only: this function is probably the worst-named thing in `ctypes`. It creates an instance of `WindowsError`. If *code* is not specified, `GetLastError` is called to determine the error code. If *descr* is not specified, `FormatError()` is called to get a textual description of the error.

`ctypes.wstring_at(address[, size])`

This function returns the wide character string starting at memory address *address* as unicode string. If *size* is specified, it is used as the number of characters of the string, otherwise the string is assumed to be zero-terminated.

Data types

`class ctypes._CData`

This non-public class is the common base class of all ctypes data types. Among other things, all ctypes type instances contain a memory block that hold C compatible data; the address of the memory block is returned by the `addressof()` helper function. Another instance variable is exposed as `_objects`; this contains other Python objects that need to be kept alive in case the memory block contains pointers.

Common methods of ctypes data types, these are all class methods (to be exact, they are methods of the *metaclass*):

`from_buffer(source[, offset])`

This method returns a ctypes instance that shares the buffer of the *source* object. The *source* object must support the writeable buffer interface. The optional *offset* parameter specifies an offset into the source buffer in bytes; the default is zero. If the source buffer is not large enough a *ValueError* is raised.

버전 2.6에 추가.

`from_buffer_copy(source[, offset])`

This method creates a ctypes instance, copying the buffer from the *source* object buffer which must be readable. The optional *offset* parameter specifies an offset into the source buffer in bytes; the default is zero. If the source buffer is not large enough a *ValueError* is raised.

버전 2.6에 추가.

`from_address(address)`

This method returns a ctypes type instance using the memory specified by *address* which must be an integer.

`from_param(obj)`

This method adapts *obj* to a ctypes type. It is called with the actual object used in a foreign function call when the type is present in the foreign function's *argtypes* tuple; it must return an object that can be used as a function call parameter.

All ctypes data types have a default implementation of this classmethod that normally returns *obj* if that is an instance of the type. Some types accept other objects as well.

`in_dll(library, name)`

This method returns a ctypes type instance exported by a shared library. *name* is the name of the symbol that exports the data, *library* is the loaded shared library.

Common instance variables of ctypes data types:

`_b_base_`

Sometimes ctypes data instances do not own the memory block they contain, instead they share part of the memory block of a base object. The `_b_base_` read-only member is the root ctypes object that owns the memory block.

`_b_needsfree_`

This read-only variable is true when the ctypes data instance has allocated the memory block itself, false otherwise.

`_objects`

This member is either `None` or a dictionary containing Python objects that need to be kept alive so that the memory block contents is kept valid. This object is only exposed for debugging; never modify the contents of this dictionary.

Fundamental data types

class `ctypes._SimpleCData`

This non-public class is the base class of all fundamental ctypes data types. It is mentioned here because it contains the common attributes of the fundamental ctypes data types. `_SimpleCData` is a subclass of `_CData`, so it inherits their methods and attributes.

버전 2.6에서 변경: ctypes data types that are not and do not contain pointers can now be pickled.

Instances have a single attribute:

value

This attribute contains the actual value of the instance. For integer and pointer types, it is an integer, for character types, it is a single character string, for character pointer types it is a Python string or unicode string.

When the `value` attribute is retrieved from a ctypes instance, usually a new object is returned each time. `ctypes` does *not* implement original object return, always a new object is constructed. The same is true for all other ctypes object instances.

Fundamental data types, when returned as foreign function call results, or, for example, by retrieving structure field members or array items, are transparently converted to native Python types. In other words, if a foreign function has a `restype` of `c_char_p`, you will always receive a Python string, *not* a `c_char_p` instance.

Subclasses of fundamental data types do *not* inherit this behavior. So, if a foreign functions `restype` is a subclass of `c_void_p`, you will receive an instance of this subclass from the function call. Of course, you can get the value of the pointer by accessing the `value` attribute.

These are the fundamental ctypes data types:

class `ctypes.c_byte`

Represents the C `signed char` datatype, and interprets the value as small integer. The constructor accepts an optional integer initializer; no overflow checking is done.

class `ctypes.c_char`

Represents the C `char` datatype, and interprets the value as a single character. The constructor accepts an optional string initializer, the length of the string must be exactly one character.

class `ctypes.c_char_p`

Represents the C `char *` datatype when it points to a zero-terminated string. For a general character pointer that may also point to binary data, `POINTER(c_char)` must be used. The constructor accepts an integer address, or a string.

class `ctypes.c_double`

Represents the C `double` datatype. The constructor accepts an optional float initializer.

class `ctypes.c_longdouble`

Represents the C `long double` datatype. The constructor accepts an optional float initializer. On platforms where `sizeof(long double) == sizeof(double)` it is an alias to `c_double`.

버전 2.6에 추가.

class `ctypes.c_float`

Represents the C `float` datatype. The constructor accepts an optional float initializer.

class `ctypes.c_int`

Represents the C `signed int` datatype. The constructor accepts an optional integer initializer; no overflow checking is done. On platforms where `sizeof(int) == sizeof(long)` it is an alias to `c_long`.

class `ctypes.c_int8`

Represents the C 8-bit signed `int` datatype. Usually an alias for `c_byte`.

class `ctypes.c_int16`
Represents the C 16-bit signed `int` datatype. Usually an alias for `c_short`.

class `ctypes.c_int32`
Represents the C 32-bit signed `int` datatype. Usually an alias for `c_int`.

class `ctypes.c_int64`
Represents the C 64-bit signed `int` datatype. Usually an alias for `c_longlong`.

class `ctypes.c_long`
Represents the C signed `long` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `ctypes.c_longlong`
Represents the C signed `long long` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `ctypes.c_short`
Represents the C signed `short` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `ctypes.c_size_t`
Represents the C `size_t` datatype.

class `ctypes.c_ssize_t`
Represents the C `ssize_t` datatype.
버전 2.7에 추가.

class `ctypes.c_ubyte`
Represents the C unsigned `char` datatype, it interprets the value as small integer. The constructor accepts an optional integer initializer; no overflow checking is done.

class `ctypes.c_uint`
Represents the C unsigned `int` datatype. The constructor accepts an optional integer initializer; no overflow checking is done. On platforms where `sizeof(int) == sizeof(long)` it is an alias for `c_ulong`.

class `ctypes.c_uint8`
Represents the C 8-bit unsigned `int` datatype. Usually an alias for `c_ubyte`.

class `ctypes.c_uint16`
Represents the C 16-bit unsigned `int` datatype. Usually an alias for `c_ushort`.

class `ctypes.c_uint32`
Represents the C 32-bit unsigned `int` datatype. Usually an alias for `c_uint`.

class `ctypes.c_uint64`
Represents the C 64-bit unsigned `int` datatype. Usually an alias for `c_ulonglong`.

class `ctypes.c_ulong`
Represents the C unsigned `long` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `ctypes.c_ulonglong`
Represents the C unsigned `long long` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `ctypes.c_ushort`
Represents the C unsigned `short` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `ctypes.c_void_p`

Represents the C `void *` type. The value is represented as integer. The constructor accepts an optional integer initializer.

class `ctypes.c_wchar`

Represents the C `wchar_t` datatype, and interprets the value as a single character unicode string. The constructor accepts an optional string initializer, the length of the string must be exactly one character.

class `ctypes.c_wchar_p`

Represents the C `wchar_t *` datatype, which must be a pointer to a zero-terminated wide character string. The constructor accepts an integer address, or a string.

class `ctypes.c_bool`

Represent the C `bool` datatype (more accurately, `_Bool` from C99). Its value can be `True` or `False`, and the constructor accepts any object that has a truth value.

버전 2.6에 추가.

class `ctypes.HRESULT`

Windows only: Represents a `HRESULT` value, which contains success or error information for a function or method call.

class `ctypes.py_object`

Represents the C `PyObject *` datatype. Calling this without an argument creates a `NULL PyObject *` pointer.

The `ctypes.wintypes` module provides quite some other Windows specific data types, for example `HWND`, `WPARAM`, or `DWORD`. Some useful structures like `MSG` or `RECT` are also defined.

Structured data types

class `ctypes.Union(*args, **kw)`

Abstract base class for unions in native byte order.

class `ctypes.BigEndianStructure(*args, **kw)`

Abstract base class for structures in *big endian* byte order.

class `ctypes.LittleEndianStructure(*args, **kw)`

Abstract base class for structures in *little endian* byte order.

Structures with non-native byte order cannot contain pointer type fields, or any other data types containing pointer type fields.

class `ctypes.Structure(*args, **kw)`

Abstract base class for structures in *native* byte order.

Concrete structure and union types must be created by subclassing one of these types, and at least define a `_fields_` class variable. `ctypes` will create *descriptors* which allow reading and writing the fields by direct attribute accesses. These are the

`_fields_`

A sequence defining the structure fields. The items must be 2-tuples or 3-tuples. The first item is the name of the field, the second item specifies the type of the field; it can be any `ctypes` data type.

For integer type fields like `c_int`, a third optional item can be given. It must be a small positive integer defining the bit width of the field.

Field names must be unique within one structure or union. This is not checked, only one field can be accessed when names are repeated.

It is possible to define the `__fields__` class variable *after* the class statement that defines the Structure subclass, this allows creating data types that directly or indirectly reference themselves:

```
class List(Structure):
    pass
List.__fields__ = [("pNext", POINTER(List)),
                  ...
                  ]
```

The `__fields__` class variable must, however, be defined before the type is first used (an instance is created, `sizeof()` is called on it, and so on). Later assignments to the `__fields__` class variable will raise an `AttributeError`.

It is possible to defined sub-subclasses of structure types, they inherit the fields of the base class plus the `__fields__` defined in the sub-subclass, if any.

`__pack__`

An optional small integer that allows overriding the alignment of structure fields in the instance. `__pack__` must already be defined when `__fields__` is assigned, otherwise it will have no effect.

`__anonymous__`

An optional sequence that lists the names of unnamed (anonymous) fields. `__anonymous__` must be already defined when `__fields__` is assigned, otherwise it will have no effect.

The fields listed in this variable must be structure or union type fields. `ctypes` will create descriptors in the structure type that allow accessing the nested fields directly, without the need to create the structure or union field.

Here is an example type (Windows):

```
class _U(Union):
    __fields__ = [("lptdesc", POINTER(TYPEDESC)),
                  ("lpadesc", POINTER(ARRAYDESC)),
                  ("hreftype", HREFTYPE)]

class TYPEDESC(Structure):
    __anonymous__ = ("u",)
    __fields__ = [("u", _U),
                  ("vt", VARTYPE)]
```

The `TYPEDESC` structure describes a COM data type, the `vt` field specifies which one of the union fields is valid. Since the `u` field is defined as anonymous field, it is now possible to access the members directly off the `TYPEDESC` instance. `td.lptdesc` and `td.u.lptdesc` are equivalent, but the former is faster since it does not need to create a temporary union instance:

```
td = TYPEDESC()
td.vt = VT_PTR
td.lptdesc = POINTER(some_type)
td.u.lptdesc = POINTER(some_type)
```

It is possible to defined sub-subclasses of structures, they inherit the fields of the base class. If the subclass definition has a separate `__fields__` variable, the fields specified in this are appended to the fields of the base class.

Structure and union constructors accept both positional and keyword arguments. Positional arguments are used to initialize member fields in the same order as they are appear in `__fields__`. Keyword arguments in the constructor are interpreted as attribute assignments, so they will initialize `__fields__` with the same name, or create new attributes for names not present in `__fields__`.

Arrays and pointers

class `ctypes.Array(*args)`

Abstract base class for arrays.

The recommended way to create concrete array types is by multiplying any `ctypes` data type with a positive integer. Alternatively, you can subclass this type and define `_length_` and `_type_` class variables. Array elements can be read and written using standard subscript and slice accesses; for slice reads, the resulting object is *not* itself an `Array`.

`_length_`

A positive integer specifying the number of elements in the array. Out-of-range subscripts result in an `IndexError`. Will be returned by `len()`.

`_type_`

Specifies the type of each element in the array.

Array subclass constructors accept positional arguments, used to initialize the elements in order.

class `ctypes._Pointer`

Private, abstract base class for pointers.

Concrete pointer types are created by calling `POINTER()` with the type that will be pointed to; this is done automatically by `pointer()`.

If a pointer points to an array, its elements can be read and written using standard subscript and slice accesses. Pointer objects have no size, so `len()` will raise `TypeError`. Negative subscripts will read from the memory *before* the pointer (as in C), and out-of-range subscripts will probably crash with an access violation (if you're lucky).

`_type_`

Specifies the type pointed to.

`contents`

Returns the object to which the pointer points. Assigning to this attribute changes the pointer to point to the assigned object.

Optional Operating System Services

The modules described in this chapter provide interfaces to operating system features that are available on selected operating systems only. The interfaces are generally modeled after the Unix or C interfaces but they are available on some other systems as well (e.g. Windows or NT). Here's an overview:

16.1 `select` — Waiting for I/O completion

This module provides access to the `select()` and `poll()` functions available in most operating systems, `epoll()` available on Linux 2.5+ and `kqueue()` available on most BSD. Note that on Windows, it only works for sockets; on other operating systems, it also works for other file types (in particular, on Unix, it works on pipes). It cannot be used on regular files to determine whether a file has grown since it was last read.

The module defines the following:

exception `select.error`

The exception raised when an error occurs. The accompanying value is a pair containing the numeric error code from `errno` and the corresponding string, as would be printed by the C function `perror()`.

`select.epoll([sizehint=-1])`

(Only supported on Linux 2.5.44 and newer.) Returns an edge polling object, which can be used as Edge or Level Triggered interface for I/O events; see section *Edge and Level Trigger Polling (epoll) Objects* below for the methods supported by epolling objects.

버전 2.6에 추가.

`select.poll()`

(Not supported by all operating systems.) Returns a polling object, which supports registering and unregistering file descriptors, and then polling them for I/O events; see section *Polling Objects* below for the methods supported by polling objects.

`select.kqueue()`

(Only supported on BSD.) Returns a kernel queue object; see section *Kqueue Objects* below for the methods supported by kqueue objects.

버전 2.6에 추가.

`select.kevent` (*ident*, *filter*=`KQ_FILTER_READ`, *flags*=`KQ_EV_ADD`, *f*flags=0, *data*=0, *udata*=0)
(Only supported on BSD.) Returns a kernel event object; see section *Kevent Objects* below for the methods supported by kevent objects.

버전 2.6에 추가.

`select.select` (*rlist*, *wlist*, *xlist*[, *timeout*])

This is a straightforward interface to the Unix `select()` system call. The first three arguments are sequences of <waitable objects>: either integers representing file descriptors or objects with a parameterless method named `fileno()` returning such an integer:

- *rlist*: wait until ready for reading
- *wlist*: wait until ready for writing
- *xlist*: wait for an <exceptional condition> (see the manual page for what your system considers such a condition)

Empty sequences are allowed, but acceptance of three empty sequences is platform-dependent. (It is known to work on Unix but not on Windows.) The optional *timeout* argument specifies a time-out as a floating point number in seconds. When the *timeout* argument is omitted the function blocks until at least one file descriptor is ready. A time-out value of zero specifies a poll and never blocks.

The return value is a triple of lists of objects that are ready: subsets of the first three arguments. When the time-out is reached without a file descriptor becoming ready, three empty lists are returned.

Among the acceptable object types in the sequences are Python file objects (e.g. `sys.stdin`, or objects returned by `open()` or `os.popen()`), socket objects returned by `socket.socket()`. You may also define a *wrapper* class yourself, as long as it has an appropriate `fileno()` method (that really returns a file descriptor, not just a random integer).

참고: File objects on Windows are not acceptable, but sockets are. On Windows, the underlying `select()` function is provided by the WinSock library, and does not handle file descriptors that don't originate from WinSock.

`select.PIPE_BUF`

Files reported as ready for writing by `select()`, `poll()` or similar interfaces in this module are guaranteed to not block on a write of up to `PIPE_BUF` bytes. This value is guaranteed by POSIX to be at least 512. Availability: Unix.

버전 2.7에 추가.

16.1.1 Edge and Level Trigger Polling (epoll) Objects

<http://linux.die.net/man/4/epoll>

eventmask

Constant	Meaning
EPOLLIN	Available for read
EPOLLOUT	Available for write
EPOLLPRI	Urgent data for read
EPOLLERR	Error condition happened on the assoc. fd
EPOLLHUP	Hang up happened on the assoc. fd
EPOLLET	Set Edge Trigger behavior, the default is Level Trigger behavior
EPOLLONESHOT	Set one-shot behavior. After one event is pulled out, the fd is internally disabled
EPOLLRDNORM	Equivalent to EPOLLIN
EPOLLRDBAND	Priority data band can be read.
EPOLLWRNORM	Equivalent to EPOLLOUT
EPOLLWRBAND	Priority data may be written.
EPOLLMSG	Ignored.

`epoll.close()`
Close the control file descriptor of the epoll object.

`epoll.fileno()`
Return the file descriptor number of the control fd.

`epoll.fromfd(fd)`
Create an epoll object from a given file descriptor.

`epoll.register(fd[, eventmask])`
Register a fd descriptor with the epoll object.

참고: Registering a file descriptor that's already registered raises an `IOError` – contrary to *Polling Objects*'s register.

`epoll.modify(fd, eventmask)`
Modify a register file descriptor.

`epoll.unregister(fd)`
Remove a registered file descriptor from the epoll object.

`epoll.poll([timeout=-1[, maxevents=-1]])`
Wait for events. timeout in seconds (float)

16.1.2 Polling Objects

The `poll()` system call, supported on most Unix systems, provides better scalability for network servers that service many, many clients at the same time. `poll()` scales better because the system call only requires listing the file descriptors of interest, while `select()` builds a bitmap, turns on bits for the fds of interest, and then afterward the whole bitmap has to be linearly scanned again. `select()` is $O(\text{highest file descriptor})$, while `poll()` is $O(\text{number of file descriptors})$.

`poll.register(fd[, eventmask])`

Register a file descriptor with the polling object. Future calls to the `poll()` method will then check whether the file descriptor has any pending I/O events. `fd` can be either an integer, or an object with a `fileno()` method that returns an integer. File objects implement `fileno()`, so they can also be used as the argument.

`eventmask` is an optional bitmask describing the type of events you want to check for, and can be a combination of the constants `POLLIN`, `POLLPRI`, and `POLLOUT`, described in the table below. If not specified, the default value used will check for all 3 types of events.

Constant	Meaning
POLLIN	There is data to read
POLLPRI	There is urgent data to read
POLLOUT	Ready for output: writing will not block
POLLERR	Error condition of some sort
POLLHUP	Hung up
POLLNVAL	Invalid request: descriptor not open

Registering a file descriptor that's already registered is not an error, and has the same effect as registering the descriptor exactly once.

`poll.modify(fd, eventmask)`

Modifies an already registered `fd`. This has the same effect as `register(fd, eventmask)`. Attempting to modify a file descriptor that was never registered causes an `IOError` exception with `errno EWOULDBLOCK` to be raised.

버전 2.6에 추가.

`poll.unregister(fd)`

Remove a file descriptor being tracked by a polling object. Just like the `register()` method, `fd` can be an integer or an object with a `fileno()` method that returns an integer.

Attempting to remove a file descriptor that was never registered causes a `KeyError` exception to be raised.

`poll.poll([timeout])`

Polls the set of registered file descriptors, and returns a possibly-empty list containing `(fd, event)` 2-tuples for the descriptors that have events or errors to report. `fd` is the file descriptor, and `event` is a bitmask with bits set for the reported events for that descriptor — `POLLIN` for waiting input, `POLLOUT` to indicate that the descriptor can be written to, and so forth. An empty list indicates that the call timed out and no file descriptors had any events to report. If `timeout` is given, it specifies the length of time in milliseconds which the system will wait for events before returning. If `timeout` is omitted, negative, or `None`, the call will block until there is an event for this poll object.

16.1.3 Kqueue Objects

`kqueue.close()`

Close the control file descriptor of the kqueue object.

`kqueue.fileno()`

Return the file descriptor number of the control fd.

`kqueue.fromfd(fd)`

Create a kqueue object from a given file descriptor.

`kqueue.control(changelist, max_events[, timeout])` → eventlist

Low level interface to kevent

- `changelist` must be an iterable of kevent objects or `None`
- `max_events` must be 0 or a positive integer
- `timeout` in seconds (floats possible); the default is `None`, to wait forever

16.1.4 Kevent Objects

<https://www.freebsd.org/cgi/man.cgi?query=kqueue&sektion=2>

`kevent.ident`

Value used to identify the event. The interpretation depends on the filter but it's usually the file descriptor. In the constructor `ident` can either be an int or an object with a `fileno()` function. `kevent` stores the integer internally.

`kevent.filter`

Name of the kernel filter.

Constant	Meaning
<code>KQ_FILTER_READ</code>	Takes a descriptor and returns whenever there is data available to read
<code>KQ_FILTER_WRITE</code>	Takes a descriptor and returns whenever there is data available to write
<code>KQ_FILTER_AIO</code>	AIO requests
<code>KQ_FILTER_VNODE</code>	Returns when one or more of the requested events watched in <i>fflag</i> occurs
<code>KQ_FILTER_PROC</code>	Watch for events on a process id
<code>KQ_FILTER_NETDEV</code>	Watch for events on a network device [not available on Mac OS X]
<code>KQ_FILTER_SIGNAL</code>	Returns whenever the watched signal is delivered to the process
<code>KQ_FILTER_TIMER</code>	Establishes an arbitrary timer

`kevent.flags`

Filter action.

Constant	Meaning
<code>KQ_EV_ADD</code>	Adds or modifies an event
<code>KQ_EV_DELETE</code>	Removes an event from the queue
<code>KQ_EV_ENABLE</code>	Permits <code>control()</code> to return the event
<code>KQ_EV_DISABLE</code>	Disable event
<code>KQ_EV_ONESHOT</code>	Removes event after first occurrence
<code>KQ_EV_CLEAR</code>	Reset the state after an event is retrieved
<code>KQ_EV_SYSFLAGS</code>	internal event
<code>KQ_EV_FLAG1</code>	internal event
<code>KQ_EV_EOF</code>	Filter specific EOF condition
<code>KQ_EV_ERROR</code>	See return values

`kevent.fflags`

Filter specific flags.

`KQ_FILTER_READ` and `KQ_FILTER_WRITE` filter flags:

Constant	Meaning
<code>KQ_NOTE_LOWAT</code>	low water mark of a socket buffer

`KQ_FILTER_VNODE` filter flags:

Constant	Meaning
KQ_NOTE_DELETE	<i>unlink()</i> was called
KQ_NOTE_WRITE	a write occurred
KQ_NOTE_EXTEND	the file was extended
KQ_NOTE_ATTRIB	an attribute was changed
KQ_NOTE_LINK	the link count has changed
KQ_NOTE_RENAME	the file was renamed
KQ_NOTE_REVOKE	access to the file was revoked

KQ_FILTER_PROC filter flags:

Constant	Meaning
KQ_NOTE_EXIT	the process has exited
KQ_NOTE_FORK	the process has called <i>fork()</i>
KQ_NOTE_EXEC	the process has executed a new process
KQ_NOTE_PCTRLMASK	internal filter flag
KQ_NOTE_PDATAMASK	internal filter flag
KQ_NOTE_TRACK	follow a process across <i>fork()</i>
KQ_NOTE_CHILD	returned on the child process for <i>NOTE_TRACK</i>
KQ_NOTE_TRACKERR	unable to attach to a child

KQ_FILTER_NETDEV filter flags (not available on Mac OS X):

Constant	Meaning
KQ_NOTE_LINKUP	link is up
KQ_NOTE_LINKDOWN	link is down
KQ_NOTE_LINKINV	link state is invalid

`kevent.data`
Filter specific data.

`kevent.udata`
User defined value.

16.2 threading — Higher-level threading interface

Source code: [Lib/threading.py](#)

This module constructs higher-level threading interfaces on top of the lower level *thread* module. See also the *mutex* and *Queue* modules.

The *dummy_threading* module is provided for situations where *threading* cannot be used because *thread* is missing.

참고: Starting with Python 2.6, this module provides **PEP 8** compliant aliases and properties to replace the `camelCase` names that were inspired by Java's threading API. This updated API is compatible with that of the *multiprocessing* module. However, no schedule has been set for the deprecation of the `camelCase` names and they remain fully supported in both Python 2.x and 3.x.

참고: Starting with Python 2.5, several Thread methods raise `RuntimeError` instead of `AssertionError` if called erroneously.

CPython implementation detail: In CPython, due to the *Global Interpreter Lock*, only one thread can execute Python code at once (even though certain performance-oriented libraries might overcome this limitation). If you want your application to make better use of the computational resources of multi-core machines, you are advised to use *multiprocessing*. However, threading is still an appropriate model if you want to run multiple I/O-bound tasks simultaneously.

This module defines the following functions and objects:

`threading.active_count()`

`threading.activeCount()`

Return the number of *Thread* objects currently alive. The returned count is equal to the length of the list returned by `enumerate()`.

버전 2.6에서 변경: Added `active_count()` spelling.

`threading.Condition()`

A factory function that returns a new condition variable object. A condition variable allows one or more threads to wait until they are notified by another thread.

See *Condition Objects*.

`threading.current_thread()`

`threading.currentThread()`

Return the current *Thread* object, corresponding to the caller's thread of control. If the caller's thread of control was not created through the *threading* module, a dummy thread object with limited functionality is returned.

버전 2.6에서 변경: Added `current_thread()` spelling.

`threading.enumerate()`

Return a list of all *Thread* objects currently alive. The list includes daemonic threads, dummy thread objects created by `current_thread()`, and the main thread. It excludes terminated threads and threads that have not yet been started.

`threading.Event()`

A factory function that returns a new event object. An event manages a flag that can be set to true with the `set()` method and reset to false with the `clear()` method. The `wait()` method blocks until the flag is true.

See *Event Objects*.

class `threading.local`

A class that represents thread-local data. Thread-local data are data whose values are thread specific. To manage thread-local data, just create an instance of *local* (or a subclass) and store attributes on it:

```
mydata = threading.local()
mydata.x = 1
```

The instance's values will be different for separate threads.

For more details and extensive examples, see the documentation string of the `_threading_local` module.

버전 2.4에 추가.

`threading.Lock()`

A factory function that returns a new primitive lock object. Once a thread has acquired it, subsequent attempts to acquire it block, until it is released; any thread may release it.

See *Lock Objects*.

`threading.RLock()`

A factory function that returns a new reentrant lock object. A reentrant lock must be released by the thread that acquired it. Once a thread has acquired a reentrant lock, the same thread may acquire it again without blocking; the thread must release it once for each time it has acquired it.

See *RLock Objects*.

`threading.Semaphore([value])`

A factory function that returns a new semaphore object. A semaphore manages a counter representing the number of `release()` calls minus the number of `acquire()` calls, plus an initial value. The `acquire()` method blocks if necessary until it can return without making the counter negative. If not given, *value* defaults to 1.

See *Semaphore Objects*.

`threading.BoundedSemaphore([value])`

A factory function that returns a new bounded semaphore object. A bounded semaphore checks to make sure its current value doesn't exceed its initial value. If it does, *ValueError* is raised. In most situations semaphores are used to guard resources with limited capacity. If the semaphore is released too many times it's a sign of a bug. If not given, *value* defaults to 1.

class `threading.Thread`

A class that represents a thread of control. This class can be safely subclassed in a limited fashion.

See *Thread Objects*.

class `threading.Timer`

A thread that executes a function after a specified interval has passed.

See *Timer Objects*.

`threading.settrace(func)`

Set a trace function for all threads started from the *threading* module. The *func* will be passed to *sys.settrace()* for each thread, before its *run()* method is called.

버전 2.3에 추가.

`threading.setprofile(func)`

Set a profile function for all threads started from the *threading* module. The *func* will be passed to *sys.setprofile()* for each thread, before its *run()* method is called.

버전 2.3에 추가.

`threading.stack_size([size])`

Return the thread stack size used when creating new threads. The optional *size* argument specifies the stack size to be used for subsequently created threads, and must be 0 (use platform or configured default) or a positive integer value of at least 32,768 (32 KiB). If *size* is not specified, 0 is used. If changing the thread stack size is unsupported, a *ThreadError* is raised. If the specified stack size is invalid, a *ValueError* is raised and the stack size is unmodified. 32kB is currently the minimum supported stack size value to guarantee sufficient stack space for the interpreter itself. Note that some platforms may have particular restrictions on values for the stack size, such as requiring a minimum stack size > 32kB or requiring allocation in multiples of the system memory page size - platform documentation should be referred to for more information (4kB pages are common; using multiples of 4096 for the stack size is the suggested approach in the absence of more specific information). Availability: Windows, systems with POSIX threads.

버전 2.5에 추가.

exception `threading.ThreadError`

Raised for various threading-related errors as described below. Note that many interfaces use *RuntimeError* instead of *ThreadError*.

Detailed interfaces for the objects are documented below.

The design of this module is loosely based on Java's threading model. However, where Java makes locks and condition variables basic behavior of every object, they are separate objects in Python. Python's `Thread` class supports a subset of the behavior of Java's `Thread` class; currently, there are no priorities, no thread groups, and threads cannot be destroyed, stopped, suspended, resumed, or interrupted. The static methods of Java's `Thread` class, when implemented, are mapped to module-level functions.

All of the methods described below are executed atomically.

16.2.1 Thread Objects

This class represents an activity that is run in a separate thread of control. There are two ways to specify the activity: by passing a callable object to the constructor, or by overriding the `run()` method in a subclass. No other methods (except for the constructor) should be overridden in a subclass. In other words, *only* override the `__init__()` and `run()` methods of this class.

Once a thread object is created, its activity must be started by calling the thread's `start()` method. This invokes the `run()` method in a separate thread of control.

Once the thread's activity is started, the thread is considered *alive*. It stops being alive when its `run()` method terminates – either normally, or by raising an unhandled exception. The `is_alive()` method tests whether the thread is alive.

Other threads can call a thread's `join()` method. This blocks the calling thread until the thread whose `join()` method is called is terminated.

A thread has a name. The name can be passed to the constructor, and read or changed through the `name` attribute.

A thread can be flagged as a *daemon thread*. The significance of this flag is that the entire Python program exits when only daemon threads are left. The initial value is inherited from the creating thread. The flag can be set through the `daemon` property.

참고: Daemon threads are abruptly stopped at shutdown. Their resources (such as open files, database transactions, etc.) may not be released properly. If you want your threads to stop gracefully, make them non-daemonic and use a suitable signalling mechanism such as an *Event*.

There is a *main thread* object; this corresponds to the initial thread of control in the Python program. It is not a daemon thread.

There is the possibility that *dummy thread objects* are created. These are thread objects corresponding to *alien threads*, which are threads of control started outside the threading module, such as directly from C code. Dummy thread objects have limited functionality; they are always considered alive and daemonic, and cannot be `joined`. They are never deleted, since it is impossible to detect the termination of alien threads.

class `threading.Thread` (*group=None, target=None, name=None, args=(), kwargs={}*)

This constructor should always be called with keyword arguments. Arguments are:

group should be `None`; reserved for future extension when a `ThreadGroup` class is implemented.

target is the callable object to be invoked by the `run()` method. Defaults to `None`, meaning nothing is called.

name is the thread name. By default, a unique name is constructed of the form *Thread-N* where *N* is a small decimal number.

args is the argument tuple for the target invocation. Defaults to `()`.

kwargs is a dictionary of keyword arguments for the target invocation. Defaults to `{}`.

If the subclass overrides the constructor, it must make sure to invoke the base class constructor (`Thread.__init__()`) before doing anything else to the thread.

start ()

Start the thread's activity.

It must be called at most once per thread object. It arranges for the object's `run ()` method to be invoked in a separate thread of control.

This method will raise a `RuntimeError` if called more than once on the same thread object.

run ()

Method representing the thread's activity.

You may override this method in a subclass. The standard `run ()` method invokes the callable object passed to the object's constructor as the *target* argument, if any, with sequential and keyword arguments taken from the *args* and *kwargs* arguments, respectively.

join ([timeout])

Wait until the thread terminates. This blocks the calling thread until the thread whose `join ()` method is called terminates – either normally or through an unhandled exception – or until the optional timeout occurs.

When the *timeout* argument is present and not `None`, it should be a floating point number specifying a timeout for the operation in seconds (or fractions thereof). As `join ()` always returns `None`, you must call `isAlive ()` after `join ()` to decide whether a timeout happened – if the thread is still alive, the `join ()` call timed out.

When the *timeout* argument is not present or `None`, the operation will block until the thread terminates.

A thread can be `join ()`ed many times.

`join ()` raises a `RuntimeError` if an attempt is made to join the current thread as that would cause a deadlock. It is also an error to `join ()` a thread before it has been started and attempts to do so raises the same exception.

name

A string used for identification purposes only. It has no semantics. Multiple threads may be given the same name. The initial name is set by the constructor.

버전 2.6에 추가.

getName ()**setName ()**

Pre-2.6 API for *name*.

ident

The <thread identifier> of this thread or `None` if the thread has not been started. This is a nonzero integer. See the `thread.get_ident ()` function. Thread identifiers may be recycled when a thread exits and another thread is created. The identifier is available even after the thread has exited.

버전 2.6에 추가.

is_alive ()**isAlive ()**

Return whether the thread is alive.

This method returns `True` just before the `run ()` method starts until just after the `run ()` method terminates. The module function `enumerate ()` returns a list of all alive threads.

버전 2.6에서 변경: Added `is_alive ()` spelling.

daemon

A boolean value indicating whether this thread is a daemon thread (`True`) or not (`False`). This must be set before `start ()` is called, otherwise `RuntimeError` is raised. Its initial value is inherited from the creating thread; the main thread is not a daemon thread and therefore all threads created in the main thread default to `daemon = False`.

The entire Python program exits when no alive non-daemon threads are left.

버전 2.6에 추가.

isDaemon()

setDaemon()

Pre-2.6 API for *daemon*.

16.2.2 Lock Objects

A primitive lock is a synchronization primitive that is not owned by a particular thread when locked. In Python, it is currently the lowest level synchronization primitive available, implemented directly by the *thread* extension module.

A primitive lock is in one of two states, 《locked》 or 《unlocked》. It is created in the unlocked state. It has two basic methods, *acquire()* and *release()*. When the state is unlocked, *acquire()* changes the state to locked and returns immediately. When the state is locked, *acquire()* blocks until a call to *release()* in another thread changes it to unlocked, then the *acquire()* call resets it to locked and returns. The *release()* method should only be called in the locked state; it changes the state to unlocked and returns immediately. If an attempt is made to release an unlocked lock, a *ThreadError* will be raised.

When more than one thread is blocked in *acquire()* waiting for the state to turn to unlocked, only one thread proceeds when a *release()* call resets the state to unlocked; which one of the waiting threads proceeds is not defined, and may vary across implementations.

All methods are executed atomically.

Lock.acquire([blocking])

Acquire a lock, blocking or non-blocking.

When invoked with the *blocking* argument set to *True* (the default), block until the lock is unlocked, then set it to locked and return *True*.

When invoked with the *blocking* argument set to *False*, do not block. If a call with *blocking* set to *True* would block, return *False* immediately; otherwise, set the lock to locked and return *True*.

Lock.release()

Release a lock.

When the lock is locked, reset it to unlocked, and return. If any other threads are blocked waiting for the lock to become unlocked, allow exactly one of them to proceed.

When invoked on an unlocked lock, a *ThreadError* is raised.

There is no return value.

locked()

Return true if the lock is acquired.

16.2.3 RLock Objects

A reentrant lock is a synchronization primitive that may be acquired multiple times by the same thread. Internally, it uses the concepts of 《owning thread》 and 《recursion level》 in addition to the locked/unlocked state used by primitive locks. In the locked state, some thread owns the lock; in the unlocked state, no thread owns it.

To lock the lock, a thread calls its *acquire()* method; this returns once the thread owns the lock. To unlock the lock, a thread calls its *release()* method. *acquire()/release()* call pairs may be nested; only the final *release()* (the *release()* of the outermost pair) resets the lock to unlocked and allows another thread blocked in *acquire()* to proceed.

`RLock.acquire([blocking=1])`

Acquire a lock, blocking or non-blocking.

When invoked without arguments: if this thread already owns the lock, increment the recursion level by one, and return immediately. Otherwise, if another thread owns the lock, block until the lock is unlocked. Once the lock is unlocked (not owned by any thread), then grab ownership, set the recursion level to one, and return. If more than one thread is blocked waiting until the lock is unlocked, only one at a time will be able to grab ownership of the lock. There is no return value in this case.

When invoked with the *blocking* argument set to true, do the same thing as when called without arguments, and return true.

When invoked with the *blocking* argument set to false, do not block. If a call without an argument would block, return false immediately; otherwise, do the same thing as when called without arguments, and return true.

`RLock.release()`

Release a lock, decrementing the recursion level. If after the decrement it is zero, reset the lock to unlocked (not owned by any thread), and if any other threads are blocked waiting for the lock to become unlocked, allow exactly one of them to proceed. If after the decrement the recursion level is still nonzero, the lock remains locked and owned by the calling thread.

Only call this method when the calling thread owns the lock. A *RuntimeError* is raised if this method is called when the lock is unlocked.

There is no return value.

16.2.4 Condition Objects

A condition variable is always associated with some kind of lock; this can be passed in or one will be created by default. (Passing one in is useful when several condition variables must share the same lock.)

A condition variable has `acquire()` and `release()` methods that call the corresponding methods of the associated lock. It also has a `wait()` method, and `notify()` and `notifyAll()` methods. These three must only be called when the calling thread has acquired the lock, otherwise a *RuntimeError* is raised.

The `wait()` method releases the lock, and then blocks until it is awakened by a `notify()` or `notifyAll()` call for the same condition variable in another thread. Once awakened, it re-acquires the lock and returns. It is also possible to specify a timeout.

The `notify()` method wakes up one of the threads waiting for the condition variable, if any are waiting. The `notifyAll()` method wakes up all threads waiting for the condition variable.

Note: the `notify()` and `notifyAll()` methods don't release the lock; this means that the thread or threads awakened will not return from their `wait()` call immediately, but only when the thread that called `notify()` or `notifyAll()` finally relinquishes ownership of the lock.

Tip: the typical programming style using condition variables uses the lock to synchronize access to some shared state; threads that are interested in a particular change of state call `wait()` repeatedly until they see the desired state, while threads that modify the state call `notify()` or `notifyAll()` when they change the state in such a way that it could possibly be a desired state for one of the waiters. For example, the following code is a generic producer-consumer situation with unlimited buffer capacity:

```
# Consume one item
cv.acquire()
while not an_item_is_available():
    cv.wait()
get_an_available_item()
cv.release()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
# Produce one item
cv.acquire()
make_an_item_available()
cv.notify()
cv.release()
```

To choose between `notify()` and `notifyAll()`, consider whether one state change can be interesting for only one or several waiting threads. E.g. in a typical producer-consumer situation, adding one item to the buffer only needs to wake up one consumer thread.

class `threading.Condition([lock])`

If the `lock` argument is given and not `None`, it must be a `Lock` or `RLock` object, and it is used as the underlying lock. Otherwise, a new `RLock` object is created and used as the underlying lock.

acquire (*args)

Acquire the underlying lock. This method calls the corresponding method on the underlying lock; the return value is whatever that method returns.

release ()

Release the underlying lock. This method calls the corresponding method on the underlying lock; there is no return value.

wait ([timeout])

Wait until notified or until a timeout occurs. If the calling thread has not acquired the lock when this method is called, a `RuntimeError` is raised.

This method releases the underlying lock, and then blocks until it is awakened by a `notify()` or `notifyAll()` call for the same condition variable in another thread, or until the optional timeout occurs. Once awakened or timed out, it re-acquires the lock and returns.

When the `timeout` argument is present and not `None`, it should be a floating point number specifying a timeout for the operation in seconds (or fractions thereof).

When the underlying lock is an `RLock`, it is not released using its `release()` method, since this may not actually unlock the lock when it was acquired multiple times recursively. Instead, an internal interface of the `RLock` class is used, which really unlocks it even when it has been recursively acquired several times. Another internal interface is then used to restore the recursion level when the lock is reacquired.

notify (n=1)

By default, wake up one thread waiting on this condition, if any. If the calling thread has not acquired the lock when this method is called, a `RuntimeError` is raised.

This method wakes up at most `n` of the threads waiting for the condition variable; it is a no-op if no threads are waiting.

The current implementation wakes up exactly `n` threads, if at least `n` threads are waiting. However, it's not safe to rely on this behavior. A future, optimized implementation may occasionally wake up more than `n` threads.

Note: an awakened thread does not actually return from its `wait()` call until it can reacquire the lock. Since `notify()` does not release the lock, its caller should.

notify_all ()

notifyAll ()

Wake up all threads waiting on this condition. This method acts like `notify()`, but wakes up all waiting threads instead of one. If the calling thread has not acquired the lock when this method is called, a `RuntimeError` is raised.

버전 2.6에서 변경: Added `notify_all()` spelling.

16.2.5 Semaphore Objects

This is one of the oldest synchronization primitives in the history of computer science, invented by the early Dutch computer scientist Edsger W. Dijkstra (he used `P()` and `V()` instead of `acquire()` and `release()`).

A semaphore manages an internal counter which is decremented by each `acquire()` call and incremented by each `release()` call. The counter can never go below zero; when `acquire()` finds that it is zero, it blocks, waiting until some other thread calls `release()`.

class `threading.Semaphore([value])`

The optional argument gives the initial *value* for the internal counter; it defaults to 1. If the *value* given is less than 0, `ValueError` is raised.

acquire (`[blocking]`)

Acquire a semaphore.

When invoked without arguments: if the internal counter is larger than zero on entry, decrement it by one and return immediately. If it is zero on entry, block, waiting until some other thread has called `release()` to make it larger than zero. This is done with proper interlocking so that if multiple `acquire()` calls are blocked, `release()` will wake exactly one of them up. The implementation may pick one at random, so the order in which blocked threads are awakened should not be relied on. There is no return value in this case.

When invoked with *blocking* set to true, do the same thing as when called without arguments, and return true.

When invoked with *blocking* set to false, do not block. If a call without an argument would block, return false immediately; otherwise, do the same thing as when called without arguments, and return true.

release ()

Release a semaphore, incrementing the internal counter by one. When it was zero on entry and another thread is waiting for it to become larger than zero again, wake up that thread.

Semaphore Example

Semaphores are often used to guard resources with limited capacity, for example, a database server. In any situation where the size of the resource is fixed, you should use a bounded semaphore. Before spawning any worker threads, your main thread would initialize the semaphore:

```
maxconnections = 5
...
pool_sema = BoundedSemaphore(value=maxconnections)
```

Once spawned, worker threads call the semaphore's `acquire` and `release` methods when they need to connect to the server:

```
pool_sema.acquire()
conn = connectdb()
... use connection ...
conn.close()
pool_sema.release()
```

The use of a bounded semaphore reduces the chance that a programming error which causes the semaphore to be released more than it's acquired will go undetected.

16.2.6 Event Objects

This is one of the simplest mechanisms for communication between threads: one thread signals an event and other threads wait for it.

An event object manages an internal flag that can be set to true with the `set()` method and reset to false with the `clear()` method. The `wait()` method blocks until the flag is true.

class `threading.Event`

The internal flag is initially false.

`is_set()`

`isSet()`

Return true if and only if the internal flag is true.

버전 2.6에서 변경: Added `is_set()` spelling.

`set()`

Set the internal flag to true. All threads waiting for it to become true are awakened. Threads that call `wait()` once the flag is true will not block at all.

`clear()`

Reset the internal flag to false. Subsequently, threads calling `wait()` will block until `set()` is called to set the internal flag to true again.

`wait([timeout])`

Block until the internal flag is true. If the internal flag is true on entry, return immediately. Otherwise, block until another thread calls `set()` to set the flag to true, or until the optional timeout occurs.

When the timeout argument is present and not `None`, it should be a floating point number specifying a timeout for the operation in seconds (or fractions thereof).

This method returns the internal flag on exit, so it will always return `True` except if a timeout is given and the operation times out.

버전 2.7에서 변경: Previously, the method always returned `None`.

16.2.7 Timer Objects

This class represents an action that should be run only after a certain amount of time has passed — a timer. `Timer` is a subclass of `Thread` and as such also functions as an example of creating custom threads.

Timers are started, as with threads, by calling their `start()` method. The timer can be stopped (before its action has begun) by calling the `cancel()` method. The interval the timer will wait before executing its action may not be exactly the same as the interval specified by the user.

For example:

```
def hello():
    print "hello, world"

t = Timer(30.0, hello)
t.start()  # after 30 seconds, "hello, world" will be printed
```

class `threading.Timer(interval, function, args=[], kwargs={})`

Create a timer that will run `function` with arguments `args` and keyword arguments `kwargs`, after `interval` seconds have passed.

`cancel()`

Stop the timer, and cancel the execution of the timer's action. This will only work if the timer is still in its waiting stage.

16.2.8 Using locks, conditions, and semaphores in the `with` statement

All of the objects provided by this module that have `acquire()` and `release()` methods can be used as context managers for a `with` statement. The `acquire()` method will be called when the block is entered, and `release()` will be called when the block is exited.

Currently, `Lock`, `RLock`, `Condition`, `Semaphore`, and `BoundedSemaphore` objects may be used as `with` statement context managers. For example:

```
import threading

some_rlock = threading.RLock()

with some_rlock:
    print "some_rlock is locked while this executes"
```

16.2.9 Importing in threaded code

While the import machinery is thread-safe, there are two key restrictions on threaded imports due to inherent limitations in the way that thread-safety is provided:

- Firstly, other than in the main module, an import should not have the side effect of spawning a new thread and then waiting for that thread in any way. Failing to abide by this restriction can lead to a deadlock if the spawned thread directly or indirectly attempts to import a module.
- Secondly, all import attempts must be completed before the interpreter starts shutting itself down. This can be most easily achieved by only performing imports from non-daemon threads created through the `threading` module. Daemon threads and threads created directly with the `thread` module will require some other form of synchronization to ensure they do not attempt imports after system shutdown has commenced. Failure to abide by this restriction will lead to intermittent exceptions and crashes during interpreter shutdown (as the late imports attempt to access machinery which is no longer in a valid state).

16.3 `thread` — Multiple threads of control

참고: The `thread` module has been renamed to `_thread` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3; however, you should consider using the high-level `threading` module instead.

This module provides low-level primitives for working with multiple threads (also called *light-weight processes* or *tasks*) — multiple threads of control sharing their global data space. For synchronization, simple locks (also called *mutexes* or *binary semaphores*) are provided. The `threading` module provides an easier to use and higher-level threading API built on top of this module.

The module is optional. It is supported on Windows, Linux, SGI IRIX, Solaris 2.x, as well as on systems that have a POSIX thread (a.k.a. 《pthread》) implementation. For systems lacking the `thread` module, the `dummy_thread` module is available. It duplicates this module's interface and can be used as a drop-in replacement.

It defines the following constant and functions:

exception `thread.error`

Raised on thread-specific errors.

thread.LockType

This is the type of lock objects.

thread.start_new_thread (*function*, *args*[, *kwargs*])

Start a new thread and return its identifier. The thread executes the function *function* with the argument list *args* (which must be a tuple). The optional *kwargs* argument specifies a dictionary of keyword arguments. When the function returns, the thread silently exits. When the function terminates with an unhandled exception, a stack trace is printed and then the thread exits (but other threads continue to run).

thread.interrupt_main ()

Raise a `KeyboardInterrupt` exception in the main thread. A subthread can use this function to interrupt the main thread.

버전 2.3에 추가.

thread.exit ()

Raise the `SystemExit` exception. When not caught, this will cause the thread to exit silently.

thread.allocate_lock ()

Return a new lock object. Methods of locks are described below. The lock is initially unlocked.

thread.get_ident ()

Return the <thread identifier> of the current thread. This is a nonzero integer. Its value has no direct meaning; it is intended as a magic cookie to be used e.g. to index a dictionary of thread-specific data. Thread identifiers may be recycled when a thread exits and another thread is created.

thread.stack_size ([*size*])

Return the thread stack size used when creating new threads. The optional *size* argument specifies the stack size to be used for subsequently created threads, and must be 0 (use platform or configured default) or a positive integer value of at least 32,768 (32kB). If *size* is not specified, 0 is used. If changing the thread stack size is unsupported, the `error` exception is raised. If the specified stack size is invalid, a `ValueError` is raised and the stack size is unmodified. 32kB is currently the minimum supported stack size value to guarantee sufficient stack space for the interpreter itself. Note that some platforms may have particular restrictions on values for the stack size, such as requiring a minimum stack size > 32kB or requiring allocation in multiples of the system memory page size - platform documentation should be referred to for more information (4kB pages are common; using multiples of 4096 for the stack size is the suggested approach in the absence of more specific information). Availability: Windows, systems with POSIX threads.

버전 2.5에 추가.

Lock objects have the following methods:

lock.acquire ([*waitflag*])

Without the optional argument, this method acquires the lock unconditionally, if necessary waiting until it is released by another thread (only one thread at a time can acquire a lock — that's their reason for existence). If the integer *waitflag* argument is present, the action depends on its value: if it is zero, the lock is only acquired if it can be acquired immediately without waiting, while if it is nonzero, the lock is acquired unconditionally as before. The return value is `True` if the lock is acquired successfully, `False` if not.

lock.release ()

Releases the lock. The lock must have been acquired earlier, but not necessarily by the same thread.

lock.locked ()

Return the status of the lock: `True` if it has been acquired by some thread, `False` if not.

In addition to these methods, lock objects can also be used via the `with` statement, e.g.:

```
import thread

a_lock = thread.allocate_lock()

with a_lock:
    print "a_lock is locked while this executes"
```

Caveats:

- Threads interact strangely with interrupts: the *KeyboardInterrupt* exception will be received by an arbitrary thread. (When the *signal* module is available, interrupts always go to the main thread.)
- Calling *sys.exit()* or raising the *SystemExit* exception is equivalent to calling *thread.exit()*.
- It is not possible to interrupt the *acquire()* method on a lock — the *KeyboardInterrupt* exception will happen after the lock has been acquired.
- When the main thread exits, it is system defined whether the other threads survive. On SGI IRIX using the native thread implementation, they survive. On most other systems, they are killed without executing *try ... finally* clauses or executing object destructors.
- When the main thread exits, it does not do any of its usual cleanup (except that *try ... finally* clauses are honored), and the standard I/O files are not flushed.

16.4 dummy_threading — Drop-in replacement for the threading module

Source code: *Lib/dummy_threading.py*

This module provides a duplicate interface to the *threading* module. It is meant to be imported when the *thread* module is not provided on a platform.

Suggested usage is:

```
try:
    import threading as _threading
except ImportError:
    import dummy_threading as _threading
```

Be careful to not use this module where deadlock might occur from a thread being created that blocks waiting for another thread to be created. This often occurs with blocking I/O.

16.5 dummy_thread — Drop-in replacement for the thread module

참고: The *dummy_thread* module has been renamed to *_dummy_thread* in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3; however, you should consider using the high-level *dummy_threading* module instead.

Source code: *Lib/dummy_thread.py*

This module provides a duplicate interface to the `thread` module. It is meant to be imported when the `thread` module is not provided on a platform.

Suggested usage is:

```
try:
    import thread as _thread
except ImportError:
    import dummy_thread as _thread
```

Be careful to not use this module where deadlock might occur from a thread being created that blocks waiting for another thread to be created. This often occurs with blocking I/O.

16.6 multiprocessing — Process-based 《threading》 interface

버전 2.6에 추가.

16.6.1 Introduction

`multiprocessing` is a package that supports spawning processes using an API similar to the `threading` module. The `multiprocessing` package offers both local and remote concurrency, effectively side-stepping the *Global Interpreter Lock* by using subprocesses instead of threads. Due to this, the `multiprocessing` module allows the programmer to fully leverage multiple processors on a given machine. It runs on both Unix and Windows.

The `multiprocessing` module also introduces APIs which do not have analogs in the `threading` module. A prime example of this is the `Pool` object which offers a convenient means of parallelizing the execution of a function across multiple input values, distributing the input data across processes (data parallelism). The following example demonstrates the common practice of defining such functions in a module so that child processes can successfully import that module. This basic example of data parallelism using `Pool`,

```
from multiprocessing import Pool

def f(x):
    return x*x

if __name__ == '__main__':
    p = Pool(5)
    print(p.map(f, [1, 2, 3]))
```

will print to standard output

```
[1, 4, 9]
```

The `Process` class

In *multiprocessing*, processes are spawned by creating a *Process* object and then calling its *start()* method. *Process* follows the API of *threading.Thread*. A trivial example of a multiprocess program is

```
from multiprocessing import Process

def f(name):
    print 'hello', name

if __name__ == '__main__':
    p = Process(target=f, args=('bob',))
    p.start()
    p.join()
```

To show the individual process IDs involved, here is an expanded example:

```
from multiprocessing import Process
import os

def info(title):
    print title
    print 'module name:', __name__
    if hasattr(os, 'getppid'): # only available on Unix
        print 'parent process:', os.getppid()
    print 'process id:', os.getpid()

def f(name):
    info('function f')
    print 'hello', name

if __name__ == '__main__':
    info('main line')
    p = Process(target=f, args=('bob',))
    p.start()
    p.join()
```

For an explanation of why (on Windows) the `if __name__ == '__main__':` part is necessary, see *Programming guidelines*.

Exchanging objects between processes

multiprocessing supports two types of communication channel between processes:

Queues

The *Queue* class is a near clone of *Queue.Queue*. For example:

```
from multiprocessing import Process, Queue

def f(q):
    q.put([42, None, 'hello'])

if __name__ == '__main__':
    q = Queue()
    p = Process(target=f, args=(q,))
    p.start()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
print q.get()      # prints "[42, None, 'hello']"
p.join()
```

Queues are thread and process safe.

Pipes

The *Pipe()* function returns a pair of connection objects connected by a pipe which by default is duplex (two-way). For example:

```
from multiprocessing import Process, Pipe

def f(conn):
    conn.send([42, None, 'hello'])
    conn.close()

if __name__ == '__main__':
    parent_conn, child_conn = Pipe()
    p = Process(target=f, args=(child_conn,))
    p.start()
    print parent_conn.recv()      # prints "[42, None, 'hello']"
    p.join()
```

The two connection objects returned by *Pipe()* represent the two ends of the pipe. Each connection object has *send()* and *recv()* methods (among others). Note that data in a pipe may become corrupted if two processes (or threads) try to read from or write to the *same* end of the pipe at the same time. Of course there is no risk of corruption from processes using different ends of the pipe at the same time.

Synchronization between processes

multiprocessing contains equivalents of all the synchronization primitives from *threading*. For instance one can use a lock to ensure that only one process prints to standard output at a time:

```
from multiprocessing import Process, Lock

def f(l, i):
    l.acquire()
    print 'hello world', i
    l.release()

if __name__ == '__main__':
    lock = Lock()

    for num in range(10):
        Process(target=f, args=(lock, num)).start()
```

Without using the lock output from the different processes is liable to get all mixed up.

Sharing state between processes

As mentioned above, when doing concurrent programming it is usually best to avoid using shared state as far as possible. This is particularly true when using multiple processes.

However, if you really do need to use some shared data then *multiprocessing* provides a couple of ways of doing so.

Shared memory

Data can be stored in a shared memory map using *Value* or *Array*. For example, the following code

```
from multiprocessing import Process, Value, Array

def f(n, a):
    n.value = 3.1415927
    for i in range(len(a)):
        a[i] = -a[i]

if __name__ == '__main__':
    num = Value('d', 0.0)
    arr = Array('i', range(10))

    p = Process(target=f, args=(num, arr))
    p.start()
    p.join()

    print num.value
    print arr[:]
```

will print

```
3.1415927
[0, -1, -2, -3, -4, -5, -6, -7, -8, -9]
```

The 'd' and 'i' arguments used when creating *num* and *arr* are typecodes of the kind used by the *array* module: 'd' indicates a double precision float and 'i' indicates a signed integer. These shared objects will be process and thread-safe.

For more flexibility in using shared memory one can use the *multiprocessing.sharedctypes* module which supports the creation of arbitrary ctypes objects allocated from shared memory.

Server process

A manager object returned by *Manager()* controls a server process which holds Python objects and allows other processes to manipulate them using proxies.

A manager returned by *Manager()* will support types *list*, *dict*, *Namespace*, *Lock*, *RLock*, *Semaphore*, *BoundedSemaphore*, *Condition*, *Event*, *Queue*, *Value* and *Array*. For example,

```
from multiprocessing import Process, Manager

def f(d, l):
    d[1] = '1'
    d['2'] = 2
    d[0.25] = None
    l.reverse()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

if __name__ == '__main__':
    manager = Manager()

    d = manager.dict()
    l = manager.list(range(10))

    p = Process(target=f, args=(d, l))
    p.start()
    p.join()

    print d
    print l

```

will print

```

{0.25: None, 1: '1', '2': 2}
[9, 8, 7, 6, 5, 4, 3, 2, 1, 0]

```

Server process managers are more flexible than using shared memory objects because they can be made to support arbitrary object types. Also, a single manager can be shared by processes on different computers over a network. They are, however, slower than using shared memory.

Using a pool of workers

The `Pool` class represents a pool of worker processes. It has methods which allows tasks to be offloaded to the worker processes in a few different ways.

For example:

```

from multiprocessing import Pool, TimeoutError
import time
import os

def f(x):
    return x*x

if __name__ == '__main__':
    pool = Pool(processes=4)           # start 4 worker processes

    # print "[0, 1, 4, ..., 81]"
    print pool.map(f, range(10))

    # print same numbers in arbitrary order
    for i in pool.imap_unordered(f, range(10)):
        print i

    # evaluate "f(20)" asynchronously
    res = pool.apply_async(f, (20,))   # runs in *only* one process
    print res.get(timeout=1)           # prints "400"

    # evaluate "os.getpid()" asynchronously
    res = pool.apply_async(os.getpid, ()) # runs in *only* one process
    print res.get(timeout=1)           # prints the PID of that process

    # launching multiple evaluations asynchronously *may* use more processes

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
multiple_results = [pool.apply_async(os.getpid, ()) for i in range(4)]
print [res.get(timeout=1) for res in multiple_results]

# make a single worker sleep for 10 secs
res = pool.apply_async(time.sleep, (10,))
try:
    print res.get(timeout=1)
except TimeoutError:
    print "We lacked patience and got a multiprocessing.TimeoutError"
```

Note that the methods of a pool should only ever be used by the process which created it.

참고: Functionality within this package requires that the `__main__` module be importable by the children. This is covered in *Programming guidelines* however it is worth pointing out here. This means that some examples, such as the Pool examples will not work in the interactive interpreter. For example:

```
>>> from multiprocessing import Pool
>>> p = Pool(5)
>>> def f(x):
...     return x*x
...
>>> p.map(f, [1,2,3])
Process PoolWorker-1:
Process PoolWorker-2:
Process PoolWorker-3:
Traceback (most recent call last):
AttributeError: 'module' object has no attribute 'f'
AttributeError: 'module' object has no attribute 'f'
AttributeError: 'module' object has no attribute 'f'
```

(If you try this it will actually output three full tracebacks interleaved in a semi-random fashion, and then you may have to stop the master process somehow.)

16.6.2 Reference

The *multiprocessing* package mostly replicates the API of the *threading* module.

Process and exceptions

class `multiprocessing.Process` (*group=None, target=None, name=None, args=(), kwargs={}*)

Process objects represent activity that is run in a separate process. The *Process* class has equivalents of all the methods of *threading.Thread*.

The constructor should always be called with keyword arguments. *group* should always be `None`; it exists solely for compatibility with *threading.Thread*. *target* is the callable object to be invoked by the *run()* method. It defaults to `None`, meaning nothing is called. *name* is the process name. By default, a unique name is constructed of the form `<Process-N1:N2:...:Nk>` where *N₁, N₂, ..., N_k* is a sequence of integers whose length is determined by the *generation* of the process. *args* is the argument tuple for the target invocation. *kwargs* is a dictionary of keyword arguments for the target invocation. By default, no arguments are passed to *target*.

If a subclass overrides the constructor, it must make sure it invokes the base class constructor (`Process.__init__()`) before doing anything else to the process.

run()

Method representing the process's activity.

You may override this method in a subclass. The standard `run()` method invokes the callable object passed to the object's constructor as the target argument, if any, with sequential and keyword arguments taken from the `args` and `kwargs` arguments, respectively.

start()

Start the process's activity.

This must be called at most once per process object. It arranges for the object's `run()` method to be invoked in a separate process.

join([timeout])

Block the calling thread until the process whose `join()` method is called terminates or until the optional timeout occurs.

If `timeout` is `None` then there is no timeout.

A process can be joined many times.

A process cannot join itself because this would cause a deadlock. It is an error to attempt to join a process before it has been started.

name

The process's name.

The name is a string used for identification purposes only. It has no semantics. Multiple processes may be given the same name. The initial name is set by the constructor.

is_alive()

Return whether the process is alive.

Roughly, a process object is alive from the moment the `start()` method returns until the child process terminates.

daemon

The process's daemon flag, a Boolean value. This must be set before `start()` is called.

The initial value is inherited from the creating process.

When a process exits, it attempts to terminate all of its daemon child processes.

Note that a daemon process is not allowed to create child processes. Otherwise a daemon process would leave its children orphaned if it gets terminated when its parent process exits. Additionally, these are **not** Unix daemons or services, they are normal processes that will be terminated (and not joined) if non-daemon processes have exited.

In addition to the `threading.Thread` API, `Process` objects also support the following attributes and methods:

pid

Return the process ID. Before the process is spawned, this will be `None`.

exitcode

The child's exit code. This will be `None` if the process has not yet terminated. A negative value `-N` indicates that the child was terminated by signal `N`.

authkey

The process's authentication key (a byte string).

When `multiprocessing` is initialized the main process is assigned a random string using `os.urandom()`.

When a *Process* object is created, it will inherit the authentication key of its parent process, although this may be changed by setting *authkey* to another byte string.

See *Authentication keys*.

terminate()

Terminate the process. On Unix this is done using the SIGTERM signal; on Windows *TerminateProcess()* is used. Note that exit handlers and finally clauses, etc., will not be executed.

Note that descendant processes of the process will *not* be terminated – they will simply become orphaned.

경고: If this method is used when the associated process is using a pipe or queue then the pipe or queue is liable to become corrupted and may become unusable by other process. Similarly, if the process has acquired a lock or semaphore etc. then terminating it is liable to cause other processes to deadlock.

Note that the *start()*, *join()*, *is_alive()*, *terminate()* and *exitcode* methods should only be called by the process that created the process object.

Example usage of some of the methods of *Process*:

```
>>> import multiprocessing, time, signal
>>> p = multiprocessing.Process(target=time.sleep, args=(1000,))
>>> print p, p.is_alive()
<Process(Process-1, initial)> False
>>> p.start()
>>> print p, p.is_alive()
<Process(Process-1, started)> True
>>> p.terminate()
>>> time.sleep(0.1)
>>> print p, p.is_alive()
<Process(Process-1, stopped[SIGTERM])> False
>>> p.exitcode == -signal.SIGTERM
True
```

exception multiprocessing.BufferTooShort

Exception raised by *Connection.recv_bytes_into()* when the supplied buffer object is too small for the message read.

If *e* is an instance of *BufferTooShort* then *e.args[0]* will give the message as a byte string.

Pipes and Queues

When using multiple processes, one generally uses message passing for communication between processes and avoids having to use any synchronization primitives like locks.

For passing messages one can use *Pipe()* (for a connection between two processes) or a queue (which allows multiple producers and consumers).

The *Queue*, *multiprocessing.queues.SimpleQueue* and *JoinableQueue* types are multi-producer, multi-consumer FIFO queues modelled on the *Queue.Queue* class in the standard library. They differ in that *Queue* lacks the *task_done()* and *join()* methods introduced into Python 2.5's *Queue.Queue* class.

If you use *JoinableQueue* then you **must** call *JoinableQueue.task_done()* for each task removed from the queue or else the semaphore used to count the number of unfinished tasks may eventually overflow, raising an exception.

Note that one can also create a shared queue by using a manager object – see *Managers*.

참고: `multiprocessing` uses the usual `Queue.Empty` and `Queue.Full` exceptions to signal a timeout. They are not available in the `multiprocessing` namespace so you need to import them from `Queue`.

참고: When an object is put on a queue, the object is pickled and a background thread later flushes the pickled data to an underlying pipe. This has some consequences which are a little surprising, but should not cause any practical difficulties – if they really bother you then you can instead use a queue created with a *manager*.

- (1) After putting an object on an empty queue there may be an infinitesimal delay before the queue's `empty()` method returns `False` and `get_nowait()` can return without raising `Queue.Empty`.
- (2) If multiple processes are enqueueing objects, it is possible for the objects to be received at the other end out-of-order. However, objects enqueued by the same process will always be in the expected order with respect to each other.

경고: If a process is killed using `Process.terminate()` or `os.kill()` while it is trying to use a `Queue`, then the data in the queue is likely to become corrupted. This may cause any other process to get an exception when it tries to use the queue later on.

경고: As mentioned above, if a child process has put items on a queue (and it has not used `JoinableQueue.cancel_join_thread`), then that process will not terminate until all buffered items have been flushed to the pipe.

This means that if you try joining that process you may get a deadlock unless you are sure that all items which have been put on the queue have been consumed. Similarly, if the child process is non-daemonic then the parent process may hang on exit when it tries to join all its non-daemonic children.

Note that a queue created using a manager does not have this issue. See *Programming guidelines*.

For an example of the usage of queues for interprocess communication see *Examples*.

`multiprocessing.Pipe([duplex])`

Returns a pair (`conn1`, `conn2`) of `Connection` objects representing the ends of a pipe.

If `duplex` is `True` (the default) then the pipe is bidirectional. If `duplex` is `False` then the pipe is unidirectional: `conn1` can only be used for receiving messages and `conn2` can only be used for sending messages.

class `multiprocessing.Queue([maxsize])`

Returns a process shared queue implemented using a pipe and a few locks/semaphores. When a process first puts an item on the queue a feeder thread is started which transfers objects from a buffer into the pipe.

The usual `Queue.Empty` and `Queue.Full` exceptions from the standard library's `Queue` module are raised to signal timeouts.

`Queue` implements all the methods of `Queue.Queue` except for `task_done()` and `join()`.

qsize()

Return the approximate size of the queue. Because of multithreading/multiprocessing semantics, this number is not reliable.

Note that this may raise `NotImplementedError` on Unix platforms like Mac OS X where `sem_getvalue()` is not implemented.

empty()

Return `True` if the queue is empty, `False` otherwise. Because of multithreading/multiprocessing semantics,

this is not reliable.

full()

Return `True` if the queue is full, `False` otherwise. Because of multithreading/multiprocessing semantics, this is not reliable.

put(obj[, block[, timeout]])

Put `obj` into the queue. If the optional argument `block` is `True` (the default) and `timeout` is `None` (the default), block if necessary until a free slot is available. If `timeout` is a positive number, it blocks at most `timeout` seconds and raises the `Queue.Full` exception if no free slot was available within that time. Otherwise (`block` is `False`), put an item on the queue if a free slot is immediately available, else raise the `Queue.Full` exception (`timeout` is ignored in that case).

put_nowait(obj)

Equivalent to `put(obj, False)`.

get([block[, timeout]])

Remove and return an item from the queue. If optional args `block` is `True` (the default) and `timeout` is `None` (the default), block if necessary until an item is available. If `timeout` is a positive number, it blocks at most `timeout` seconds and raises the `Queue.Empty` exception if no item was available within that time. Otherwise (`block` is `False`), return an item if one is immediately available, else raise the `Queue.Empty` exception (`timeout` is ignored in that case).

get_nowait()

Equivalent to `get(False)`.

`Queue` has a few additional methods not found in `Queue.Queue`. These methods are usually unnecessary for most code:

close()

Indicate that no more data will be put on this queue by the current process. The background thread will quit once it has flushed all buffered data to the pipe. This is called automatically when the queue is garbage collected.

join_thread()

Join the background thread. This can only be used after `close()` has been called. It blocks until the background thread exits, ensuring that all data in the buffer has been flushed to the pipe.

By default if a process is not the creator of the queue then on exit it will attempt to join the queue's background thread. The process can call `cancel_join_thread()` to make `join_thread()` do nothing.

cancel_join_thread()

Prevent `join_thread()` from blocking. In particular, this prevents the background thread from being joined automatically when the process exits – see `join_thread()`.

A better name for this method might be `allow_exit_without_flush()`. It is likely to cause enqueued data to be lost, and you almost certainly will not need to use it. It is really only there if you need the current process to exit immediately without waiting to flush enqueued data to the underlying pipe, and you don't care about lost data.

참고: This class's functionality requires a functioning shared semaphore implementation on the host operating system. Without one, the functionality in this class will be disabled, and attempts to instantiate a `Queue` will result in an `ImportError`. See [bpo-3770](#) for additional information. The same holds true for any of the specialized queue types listed below.

class multiprocessing.queues.SimpleQueue

It is a simplified `Queue` type, very close to a locked `Pipe`.

empty()
Return True if the queue is empty, False otherwise.

get()
Remove and return an item from the queue.

put(item)
Put *item* into the queue.

class multiprocessing.JoinableQueue([maxsize])
JoinableQueue, a *Queue* subclass, is a queue which additionally has *task_done()* and *join()* methods.

task_done()
Indicate that a formerly enqueued task is complete. Used by queue consumer threads. For each *get()* used to fetch a task, a subsequent call to *task_done()* tells the queue that the processing on the task is complete.

If a *join()* is currently blocking, it will resume when all items have been processed (meaning that a *task_done()* call was received for every item that had been *put()* into the queue).

Raises a *ValueError* if called more times than there were items placed in the queue.

join()
Block until all items in the queue have been gotten and processed.

The count of unfinished tasks goes up whenever an item is added to the queue. The count goes down whenever a consumer thread calls *task_done()* to indicate that the item was retrieved and all work on it is complete. When the count of unfinished tasks drops to zero, *join()* unblocks.

Miscellaneous

multiprocessing.active_children()
Return list of all live children of the current process.

Calling this has the side effect of «joining» any processes which have already finished.

multiprocessing.cpu_count()
Return the number of CPUs in the system. May raise *NotImplementedError*.

multiprocessing.current_process()
Return the *Process* object corresponding to the current process.

An analogue of *threading.current_thread()*.

multiprocessing.freeze_support()
Add support for when a program which uses *multiprocessing* has been frozen to produce a Windows executable. (Has been tested with **py2exe**, **PyInstaller** and **cx_Freeze**.)

One needs to call this function straight after the `if __name__ == '__main__':` line of the main module. For example:

```
from multiprocessing import Process, freeze_support

def f():
    print 'hello world!'

if __name__ == '__main__':
    freeze_support()
    Process(target=f).start()
```

If the `freeze_support()` line is omitted then trying to run the frozen executable will raise `RuntimeError`.

Calling `freeze_support()` has no effect when invoked on any operating system other than Windows. In addition, if the module is being run normally by the Python interpreter on Windows (the program has not been frozen), then `freeze_support()` has no effect.

`multiprocessing.set_executable()`

Sets the path of the Python interpreter to use when starting a child process. (By default `sys.executable` is used). Embedders will probably need to do some thing like

```
set_executable(os.path.join(sys.exec_prefix, 'pythonw.exe'))
```

before they can create child processes. (Windows only)

참고: `multiprocessing` contains no analogues of `threading.active_count()`, `threading.enumerate()`, `threading.settrace()`, `threading.setprofile()`, `threading.Timer`, or `threading.local`.

Connection Objects

Connection objects allow the sending and receiving of picklable objects or strings. They can be thought of as message oriented connected sockets.

Connection objects are usually created using *Pipe* – see also *Listeners and Clients*.

class Connection

send(obj)

Send an object to the other end of the connection which should be read using `recv()`.

The object must be picklable. Very large pickles (approximately 32 MB+, though it depends on the OS) may raise a `ValueError` exception.

recv()

Return an object sent from the other end of the connection using `send()`. Blocks until there is something to receive. Raises `EOFError` if there is nothing left to receive and the other end was closed.

fileno()

Return the file descriptor or handle used by the connection.

close()

Close the connection.

This is called automatically when the connection is garbage collected.

poll([timeout])

Return whether there is any data available to be read.

If `timeout` is not specified then it will return immediately. If `timeout` is a number then this specifies the maximum time in seconds to block. If `timeout` is `None` then an infinite timeout is used.

send_bytes(buffer[, offset[, size]])

Send byte data from an object supporting the buffer interface as a complete message.

If `offset` is given then data is read from that position in `buffer`. If `size` is given then that many bytes will be read from buffer. Very large buffers (approximately 32 MB+, though it depends on the OS) may raise a `ValueError` exception

recv_bytes (*maxlength*)

Return a complete message of byte data sent from the other end of the connection as a string. Blocks until there is something to receive. Raises *EOFError* if there is nothing left to receive and the other end has closed.

If *maxlength* is specified and the message is longer than *maxlength* then *IOError* is raised and the connection will no longer be readable.

recv_bytes_into (*buffer* [, *offset*])

Read into *buffer* a complete message of byte data sent from the other end of the connection and return the number of bytes in the message. Blocks until there is something to receive. Raises *EOFError* if there is nothing left to receive and the other end was closed.

buffer must be an object satisfying the writable buffer interface. If *offset* is given then the message will be written into the buffer from that position. Offset must be a non-negative integer less than the length of *buffer* (in bytes).

If the buffer is too short then a *BufferTooShort* exception is raised and the complete message is available as *e.args[0]* where *e* is the exception instance.

For example:

```
>>> from multiprocessing import Pipe
>>> a, b = Pipe()
>>> a.send([1, 'hello', None])
>>> b.recv()
[1, 'hello', None]
>>> b.send_bytes('thank you')
>>> a.recv_bytes()
'thank you'
>>> import array
>>> arr1 = array.array('i', range(5))
>>> arr2 = array.array('i', [0] * 10)
>>> a.send_bytes(arr1)
>>> count = b.recv_bytes_into(arr2)
>>> assert count == len(arr1) * arr1.itemsize
>>> arr2
array('i', [0, 1, 2, 3, 4, 0, 0, 0, 0, 0])
```

경고: The *Connection.recv()* method automatically unpickles the data it receives, which can be a security risk unless you can trust the process which sent the message.

Therefore, unless the connection object was produced using *Pipe()* you should only use the *recv()* and *send()* methods after performing some sort of authentication. See *Authentication keys*.

경고: If a process is killed while it is trying to read or write to a pipe then the data in the pipe is likely to become corrupted, because it may become impossible to be sure where the message boundaries lie.

Synchronization primitives

Generally synchronization primitives are not as necessary in a multiprocess program as they are in a multithreaded program. See the documentation for *threading* module.

Note that one can also create synchronization primitives by using a manager object – see *Managers*.

class multiprocessing.BoundedSemaphore ([value])

A bounded semaphore object: a close analog of *threading.BoundedSemaphore*.

A solitary difference from its close analog exists: its *acquire* method's first argument is named *block* and it supports an optional second argument *timeout*, as is consistent with *Lock.acquire()*.

참고: On Mac OS X, this is indistinguishable from *Semaphore* because *sem_getvalue()* is not implemented on that platform.

class multiprocessing.Condition ([lock])

A condition variable: a clone of *threading.Condition*.

If *lock* is specified then it should be a *Lock* or *RLock* object from *multiprocessing*.

class multiprocessing.Event

A clone of *threading.Event*. This method returns the state of the internal semaphore on exit, so it will always return *True* except if a timeout is given and the operation times out.

버전 2.7에서 변경: Previously, the method always returned *None*.

class multiprocessing.Lock

A non-recursive lock object: a close analog of *threading.Lock*. Once a process or thread has acquired a lock, subsequent attempts to acquire it from any process or thread will block until it is released; any process or thread may release it. The concepts and behaviors of *threading.Lock* as it applies to threads are replicated here in *multiprocessing.Lock* as it applies to either processes or threads, except as noted.

Note that *Lock* is actually a factory function which returns an instance of *multiprocessing.synchronize.Lock* initialized with a default context.

Lock supports the *context manager* protocol and thus may be used in *with* statements.

acquire (block=True, timeout=None)

Acquire a lock, blocking or non-blocking.

With the *block* argument set to *True* (the default), the method call will block until the lock is in an unlocked state, then set it to locked and return *True*. Note that the name of this first argument differs from that in *threading.Lock.acquire()*.

With the *block* argument set to *False*, the method call does not block. If the lock is currently in a locked state, return *False*; otherwise set the lock to a locked state and return *True*.

When invoked with a positive, floating-point value for *timeout*, block for at most the number of seconds specified by *timeout* as long as the lock can not be acquired. Invocations with a negative value for *timeout* are equivalent to a *timeout* of zero. Invocations with a *timeout* value of *None* (the default) set the timeout period to infinite. The *timeout* argument has no practical implications if the *block* argument is set to *False* and is thus ignored. Returns *True* if the lock has been acquired or *False* if the timeout period has elapsed. Note that the *timeout* argument does not exist in this method's analog, *threading.Lock.acquire()*.

release ()

Release a lock. This can be called from any process or thread, not only the process or thread which originally acquired the lock.

Behavior is the same as in `threading.Lock.release()` except that when invoked on an unlocked lock, a `ValueError` is raised.

class multiprocessing.RLock

A recursive lock object: a close analog of `threading.RLock`. A recursive lock must be released by the process or thread that acquired it. Once a process or thread has acquired a recursive lock, the same process or thread may acquire it again without blocking; that process or thread must release it once for each time it has been acquired.

Note that `RLock` is actually a factory function which returns an instance of `multiprocessing.synchronize.RLock` initialized with a default context.

`RLock` supports the *context manager* protocol and thus may be used in `with` statements.

acquire (*block=True, timeout=None*)

Acquire a lock, blocking or non-blocking.

When invoked with the *block* argument set to `True`, block until the lock is in an unlocked state (not owned by any process or thread) unless the lock is already owned by the current process or thread. The current process or thread then takes ownership of the lock (if it does not already have ownership) and the recursion level inside the lock increments by one, resulting in a return value of `True`. Note that there are several differences in this first argument's behavior compared to the implementation of `threading.RLock.acquire()`, starting with the name of the argument itself.

When invoked with the *block* argument set to `False`, do not block. If the lock has already been acquired (and thus is owned) by another process or thread, the current process or thread does not take ownership and the recursion level within the lock is not changed, resulting in a return value of `False`. If the lock is in an unlocked state, the current process or thread takes ownership and the recursion level is incremented, resulting in a return value of `True`.

Use and behaviors of the *timeout* argument are the same as in `Lock.acquire()`. Note that the *timeout* argument does not exist in this method's analog, `threading.RLock.acquire()`.

release ()

Release a lock, decrementing the recursion level. If after the decrement the recursion level is zero, reset the lock to unlocked (not owned by any process or thread) and if any other processes or threads are blocked waiting for the lock to become unlocked, allow exactly one of them to proceed. If after the decrement the recursion level is still nonzero, the lock remains locked and owned by the calling process or thread.

Only call this method when the calling process or thread owns the lock. An `AssertionError` is raised if this method is called by a process or thread other than the owner or if the lock is in an unlocked (un-owned) state. Note that the type of exception raised in this situation differs from the implemented behavior in `threading.RLock.release()`.

class multiprocessing.Semaphore ([*value*])

A semaphore object: a close analog of `threading.Semaphore`.

A solitary difference from its close analog exists: its `acquire` method's first argument is named *block* and it supports an optional second argument *timeout*, as is consistent with `Lock.acquire()`.

참고: The `acquire()` method of `BoundedSemaphore`, `Lock`, `RLock` and `Semaphore` has a *timeout* parameter not supported by the equivalents in `threading`. The signature is `acquire(block=True, timeout=None)` with keyword parameters being acceptable. If *block* is `True` and *timeout* is not `None` then it specifies a timeout in seconds. If *block* is `False` then *timeout* is ignored.

On Mac OS X, `sem_timedwait` is unsupported, so calling `acquire()` with a *timeout* will emulate that function's behavior using a sleeping loop.

참고: If the SIGINT signal generated by Ctrl-C arrives while the main thread is blocked by a call to

`BoundedSemaphore.acquire()`, `Lock.acquire()`, `RLock.acquire()`, `Semaphore.acquire()`, `Condition.acquire()` or `Condition.wait()` then the call will be immediately interrupted and `KeyboardInterrupt` will be raised.

This differs from the behaviour of `threading` where `SIGINT` will be ignored while the equivalent blocking calls are in progress.

참고: Some of this package's functionality requires a functioning shared semaphore implementation on the host operating system. Without one, the `multiprocessing.synchronize` module will be disabled, and attempts to import it will result in an `ImportError`. See [bpo-3770](#) for additional information.

Shared ctypes Objects

It is possible to create shared objects using shared memory which can be inherited by child processes.

`multiprocessing.Value` (*typecode_or_type*, **args*[, *lock*])

Return a `ctypes` object allocated from shared memory. By default the return value is actually a synchronized wrapper for the object.

typecode_or_type determines the type of the returned object: it is either a `ctypes` type or a one character typecode of the kind used by the `array` module. **args* is passed on to the constructor for the type.

If *lock* is `True` (the default) then a new recursive lock object is created to synchronize access to the value. If *lock* is a `Lock` or `RLock` object then that will be used to synchronize access to the value. If *lock* is `False` then access to the returned object will not be automatically protected by a lock, so it will not necessarily be «process-safe».

Operations like `+=` which involve a read and write are not atomic. So if, for instance, you want to atomically increment a shared value it is insufficient to just do

```
counter.value += 1
```

Assuming the associated lock is recursive (which it is by default) you can instead do

```
with counter.get_lock():
    counter.value += 1
```

Note that *lock* is a keyword-only argument.

`multiprocessing.Array` (*typecode_or_type*, *size_or_initializer*, *, *lock=True*)

Return a `ctypes` array allocated from shared memory. By default the return value is actually a synchronized wrapper for the array.

typecode_or_type determines the type of the elements of the returned array: it is either a `ctypes` type or a one character typecode of the kind used by the `array` module. If *size_or_initializer* is an integer, then it determines the length of the array, and the array will be initially zeroed. Otherwise, *size_or_initializer* is a sequence which is used to initialize the array and whose length determines the length of the array.

If *lock* is `True` (the default) then a new lock object is created to synchronize access to the value. If *lock* is a `Lock` or `RLock` object then that will be used to synchronize access to the value. If *lock* is `False` then access to the returned object will not be automatically protected by a lock, so it will not necessarily be «process-safe».

Note that *lock* is a keyword only argument.

Note that an array of `ctypes.c_char` has *value* and *raw* attributes which allow one to use it to store and retrieve strings.

The multiprocessing.sharedctypes module

The `multiprocessing.sharedctypes` module provides functions for allocating `ctypes` objects from shared memory which can be inherited by child processes.

참고: Although it is possible to store a pointer in shared memory remember that this will refer to a location in the address space of a specific process. However, the pointer is quite likely to be invalid in the context of a second process and trying to dereference the pointer from the second process may cause a crash.

`multiprocessing.sharedctypes.RawArray` (*typecode_or_type*, *size_or_initializer*)

Return a ctypes array allocated from shared memory.

typecode_or_type determines the type of the elements of the returned array: it is either a ctypes type or a one character typecode of the kind used by the `array` module. If *size_or_initializer* is an integer then it determines the length of the array, and the array will be initially zeroed. Otherwise *size_or_initializer* is a sequence which is used to initialize the array and whose length determines the length of the array.

Note that setting and getting an element is potentially non-atomic – use `Array()` instead to make sure that access is automatically synchronized using a lock.

`multiprocessing.sharedctypes.RawValue` (*typecode_or_type*, **args*)

Return a ctypes object allocated from shared memory.

typecode_or_type determines the type of the returned object: it is either a ctypes type or a one character typecode of the kind used by the `array` module. **args* is passed on to the constructor for the type.

Note that setting and getting the value is potentially non-atomic – use `Value()` instead to make sure that access is automatically synchronized using a lock.

Note that an array of `ctypes.c_char` has `value` and `raw` attributes which allow one to use it to store and retrieve strings – see documentation for `ctypes`.

`multiprocessing.sharedctypes.Array` (*typecode_or_type*, *size_or_initializer*, **args*[, *lock*])

The same as `RawArray()` except that depending on the value of *lock* a process-safe synchronization wrapper may be returned instead of a raw ctypes array.

If *lock* is `True` (the default) then a new lock object is created to synchronize access to the value. If *lock* is a `Lock` or `RLock` object then that will be used to synchronize access to the value. If *lock* is `False` then access to the returned object will not be automatically protected by a lock, so it will not necessarily be ‘process-safe’.

Note that *lock* is a keyword-only argument.

`multiprocessing.sharedctypes.Value` (*typecode_or_type*, **args*[, *lock*])

The same as `RawValue()` except that depending on the value of *lock* a process-safe synchronization wrapper may be returned instead of a raw ctypes object.

If *lock* is `True` (the default) then a new lock object is created to synchronize access to the value. If *lock* is a `Lock` or `RLock` object then that will be used to synchronize access to the value. If *lock* is `False` then access to the returned object will not be automatically protected by a lock, so it will not necessarily be ‘process-safe’.

Note that *lock* is a keyword-only argument.

`multiprocessing.sharedctypes.copy` (*obj*)

Return a ctypes object allocated from shared memory which is a copy of the ctypes object *obj*.

`multiprocessing.sharedctypes.synchronized` (*obj*[, *lock*])

Return a process-safe wrapper object for a ctypes object which uses *lock* to synchronize access. If *lock* is `None` (the default) then a `multiprocessing.RLock` object is created automatically.

A synchronized wrapper will have two methods in addition to those of the object it wraps: `get_obj()` returns the wrapped object and `get_lock()` returns the lock object used for synchronization.

Note that accessing the ctypes object through the wrapper can be a lot slower than accessing the raw ctypes object.

The table below compares the syntax for creating shared ctypes objects from shared memory with the normal ctypes syntax. (In the table `MyStruct` is some subclass of `ctypes.Structure`.)

ctypes	sharedctypes using type	sharedctypes using typecode
<code>c_double(2.4)</code>	<code>RawValue(c_double, 2.4)</code>	<code>RawValue(<d>, 2.4)</code>
<code>MyStruct(4, 6)</code>	<code>RawValue(MyStruct, 4, 6)</code>	
<code>(c_short * 7)()</code>	<code>RawArray(c_short, 7)</code>	<code>RawArray(<h>, 7)</code>
<code>(c_int * 3)(9, 2, 8)</code>	<code>RawArray(c_int, (9, 2, 8))</code>	<code>RawArray(<i>, (9, 2, 8))</code>

Below is an example where a number of ctypes objects are modified by a child process:

```
from multiprocessing import Process, Lock
from multiprocessing.sharedctypes import Value, Array
from ctypes import Structure, c_double

class Point(Structure):
    _fields_ = [('x', c_double), ('y', c_double)]

def modify(n, x, s, A):
    n.value *= 2
    x.value *= 2
    s.value = s.value.upper()
    for a in A:
        a.x *= 2
        a.y *= 2

if __name__ == '__main__':
    lock = Lock()

    n = Value('i', 7)
    x = Value(c_double, 1.0/3.0, lock=False)
    s = Array('c', 'hello world', lock=lock)
    A = Array(Point, [(1.875, -6.25), (-5.75, 2.0), (2.375, 9.5)], lock=lock)

    p = Process(target=modify, args=(n, x, s, A))
    p.start()
    p.join()

    print n.value
    print x.value
    print s.value
    print [(a.x, a.y) for a in A]
```

The results printed are

```
49
0.1111111111111111
HELLO WORLD
[(3.515625, 39.0625), (33.0625, 4.0), (5.640625, 90.25)]
```

Managers

Managers provide a way to create data which can be shared between different processes. A manager object controls a server process which manages *shared objects*. Other processes can access the shared objects by using proxies.

`multiprocessing.Manager()`

Returns a started *SyncManager* object which can be used for sharing objects between processes. The returned manager object corresponds to a spawned child process and has methods which will create shared objects and return corresponding proxies.

Manager processes will be shutdown as soon as they are garbage collected or their parent process exits. The manager classes are defined in the `multiprocessing.managers` module:

class `multiprocessing.managers.BaseManager([address[, authkey]])`

Create a BaseManager object.

Once created one should call `start()` or `get_server().serve_forever()` to ensure that the manager object refers to a started manager process.

address is the address on which the manager process listens for new connections. If *address* is `None` then an arbitrary one is chosen.

authkey is the authentication key which will be used to check the validity of incoming connections to the server process. If *authkey* is `None` then `current_process().authkey`. Otherwise *authkey* is used and it must be a string.

start (`[initializer[, initargs]]`)

Start a subprocess to start the manager. If *initializer* is not `None` then the subprocess will call `initializer(*initargs)` when it starts.

get_server ()

Returns a *Server* object which represents the actual server under the control of the Manager. The *Server* object supports the `serve_forever()` method:

```
>>> from multiprocessing.managers import BaseManager
>>> manager = BaseManager(address=(' ', 50000), authkey='abc')
>>> server = manager.get_server()
>>> server.serve_forever()
```

Server additionally has an *address* attribute.

connect ()

Connect a local manager object to a remote manager process:

```
>>> from multiprocessing.managers import BaseManager
>>> m = BaseManager(address=('127.0.0.1', 5000), authkey='abc')
>>> m.connect()
```

shutdown ()

Stop the process used by the manager. This is only available if `start()` has been used to start the server process.

This can be called multiple times.

register (`(typeid[, callable[, proxytype[, exposed[, method_to_typeid[, create_method]]]])`)

A classmethod which can be used for registering a type or callable with the manager class.

typeid is a «type identifier» which is used to identify a particular type of shared object. This must be a string.

callable is a callable used for creating objects for this type identifier. If a manager instance will be created using the `from_address()` classmethod or if the *create_method* argument is `False` then this can be left

as None.

proxytype is a subclass of *BaseProxy* which is used to create proxies for shared objects with this *typeid*. If None then a proxy class is created automatically.

exposed is used to specify a sequence of method names which proxies for this *typeid* should be allowed to access using *BaseProxy._callmethod()*. (If *exposed* is None then *proxytype._exposed_* is used instead if it exists.) In the case where no exposed list is specified, all «public methods» of the shared object will be accessible. (Here a «public method» means any attribute which has a *__call__()* method and whose name does not begin with *'_'*.)

method_to_typeid is a mapping used to specify the return type of those exposed methods which should return a proxy. It maps method names to typeid strings. (If *method_to_typeid* is None then *proxytype._method_to_typeid_* is used instead if it exists.) If a method's name is not a key of this mapping or if the mapping is None then the object returned by the method will be copied by value.

create_method determines whether a method should be created with name *typeid* which can be used to tell the server process to create a new shared object and return a proxy for it. By default it is True.

BaseManager instances also have one read-only property:

address

The address used by the manager.

class multiprocessing.managers.SyncManager

A subclass of *BaseManager* which can be used for the synchronization of processes. Objects of this type are returned by *multiprocessing.Manager()*.

It also supports creation of shared lists and dictionaries.

BoundedSemaphore ([*value*])

Create a shared *threading.BoundedSemaphore* object and return a proxy for it.

Condition ([*lock*])

Create a shared *threading.Condition* object and return a proxy for it.

If *lock* is supplied then it should be a proxy for a *threading.Lock* or *threading.RLock* object.

Event ()

Create a shared *threading.Event* object and return a proxy for it.

Lock ()

Create a shared *threading.Lock* object and return a proxy for it.

Namespace ()

Create a shared *Namespace* object and return a proxy for it.

Queue ([*maxsize*])

Create a shared *Queue.Queue* object and return a proxy for it.

RLock ()

Create a shared *threading.RLock* object and return a proxy for it.

Semaphore ([*value*])

Create a shared *threading.Semaphore* object and return a proxy for it.

Array (*typecode*, *sequence*)

Create an array and return a proxy for it.

Value (*typecode*, *value*)

Create an object with a writable *value* attribute and return a proxy for it.

dict ()

dict (*mapping*)

dict (*sequence*)
 Create a shared dict object and return a proxy for it.

list ()
list (*sequence*)
 Create a shared list object and return a proxy for it.

참고: Modifications to mutable values or items in dict and list proxies will not be propagated through the manager, because the proxy has no way of knowing when its values or items are modified. To modify such an item, you can re-assign the modified object to the container proxy:

```
# create a list proxy and append a mutable object (a dictionary)
lproxy = manager.list()
lproxy.append({})
# now mutate the dictionary
d = lproxy[0]
d['a'] = 1
d['b'] = 2
# at this point, the changes to d are not yet synced, but by
# reassigning the dictionary, the proxy is notified of the change
lproxy[0] = d
```

class multiprocessing.managers.Namespace

A type that can register with *SyncManager*.

A namespace object has no public methods, but does have writable attributes. Its representation shows the values of its attributes.

However, when using a proxy for a namespace object, an attribute beginning with '_' will be an attribute of the proxy and not an attribute of the referent:

```
>>> manager = multiprocessing.Manager()
>>> Global = manager.Namespace()
>>> Global.x = 10
>>> Global.y = 'hello'
>>> Global._z = 12.3      # this is an attribute of the proxy
>>> print Global
Namespace(x=10, y='hello')
```

Customized managers

To create one's own manager, one creates a subclass of *BaseManager* and uses the *register()* classmethod to register new types or callables with the manager class. For example:

```
from multiprocessing.managers import BaseManager

class MathsClass(object):
    def add(self, x, y):
        return x + y
    def mul(self, x, y):
        return x * y

class MyManager(BaseManager):
    pass
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
MyManager.register('Maths', MathsClass)

if __name__ == '__main__':
    manager = MyManager()
    manager.start()
    maths = manager.Maths()
    print maths.add(4, 3)          # prints 7
    print maths.mul(7, 8)         # prints 56
```

Using a remote manager

It is possible to run a manager server on one machine and have clients use it from other machines (assuming that the firewalls involved allow it).

Running the following commands creates a server for a single shared queue which remote clients can access:

```
>>> from multiprocessing.managers import BaseManager
>>> import Queue
>>> queue = Queue.Queue()
>>> class QueueManager(BaseManager): pass
>>> QueueManager.register('get_queue', callable=lambda:queue)
>>> m = QueueManager(address=('', 50000), authkey='abracadabra')
>>> s = m.get_server()
>>> s.serve_forever()
```

One client can access the server as follows:

```
>>> from multiprocessing.managers import BaseManager
>>> class QueueManager(BaseManager): pass
>>> QueueManager.register('get_queue')
>>> m = QueueManager(address=('foo.bar.org', 50000), authkey='abracadabra')
>>> m.connect()
>>> queue = m.get_queue()
>>> queue.put('hello')
```

Another client can also use it:

```
>>> from multiprocessing.managers import BaseManager
>>> class QueueManager(BaseManager): pass
>>> QueueManager.register('get_queue')
>>> m = QueueManager(address=('foo.bar.org', 50000), authkey='abracadabra')
>>> m.connect()
>>> queue = m.get_queue()
>>> queue.get()
'hello'
```

Local processes can also access that queue, using the code from above on the client to access it remotely:

```
>>> from multiprocessing import Process, Queue
>>> from multiprocessing.managers import BaseManager
>>> class Worker(Process):
...     def __init__(self, q):
...         self.q = q
...         super(Worker, self).__init__()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

...     def run(self):
...         self.q.put('local hello')
...
>>> queue = Queue()
>>> w = Worker(queue)
>>> w.start()
>>> class QueueManager(BaseManager): pass
...
>>> QueueManager.register('get_queue', callable=lambda: queue)
>>> m = QueueManager(address=('', 50000), authkey='abracadabra')
>>> s = m.get_server()
>>> s.serve_forever()

```

Proxy Objects

A proxy is an object which *refers* to a shared object which lives (presumably) in a different process. The shared object is said to be the *referent* of the proxy. Multiple proxy objects may have the same referent.

A proxy object has methods which invoke corresponding methods of its referent (although not every method of the referent will necessarily be available through the proxy). A proxy can usually be used in most of the same ways that its referent can:

```

>>> from multiprocessing import Manager
>>> manager = Manager()
>>> l = manager.list([i*i for i in range(10)])
>>> print l
[0, 1, 4, 9, 16, 25, 36, 49, 64, 81]
>>> print repr(l)
<ListProxy object, typeid 'list' at 0x...>
>>> l[4]
16
>>> l[2:5]
[4, 9, 16]

```

Notice that applying `str()` to a proxy will return the representation of the referent, whereas applying `repr()` will return the representation of the proxy.

An important feature of proxy objects is that they are picklable so they can be passed between processes. Note, however, that if a proxy is sent to the corresponding manager's process then unpickling it will produce the referent itself. This means, for example, that one shared object can contain a second:

```

>>> a = manager.list()
>>> b = manager.list()
>>> a.append(b)           # referent of a now contains referent of b
>>> print a, b
[[]] []
>>> b.append('hello')
>>> print a, b
[['hello']] ['hello']

```

참고: The proxy types in `multiprocessing` do nothing to support comparisons by value. So, for instance, we have:

```

>>> manager.list([1,2,3]) == [1,2,3]
False

```

One should just use a copy of the referent instead when making comparisons.

class multiprocessing.managers.**BaseProxy**

Proxy objects are instances of subclasses of *BaseProxy*.

_callmethod (*methodname* [, *args* [, *kws*]])

Call and return the result of a method of the proxy's referent.

If proxy is a proxy whose referent is obj then the expression

```
proxy._callmethod(methodname, args, kws)
```

will evaluate the expression

```
getattr(obj, methodname) (*args, **kws)
```

in the manager's process.

The returned value will be a copy of the result of the call or a proxy to a new shared object – see documentation for the *method_to_typeid* argument of *BaseManager.register()*.

If an exception is raised by the call, then is re-raised by *_callmethod()*. If some other exception is raised in the manager's process then this is converted into a *RemoteError* exception and is raised by *_callmethod()*.

Note in particular that an exception will be raised if *methodname* has not been *exposed*.

An example of the usage of *_callmethod()*:

```
>>> l = manager.list(range(10))
>>> l._callmethod('__len__')
10
>>> l._callmethod('__getslice__', (2, 7))    # equiv to `l[2:7]`
[2, 3, 4, 5, 6]
>>> l._callmethod('__getitem__', (20,))      # equiv to `l[20]`
Traceback (most recent call last):
...
IndexError: list index out of range
```

_getvalue ()

Return a copy of the referent.

If the referent is unpicklable then this will raise an exception.

__repr__ ()

Return a representation of the proxy object.

__str__ ()

Return the representation of the referent.

Cleanup

A proxy object uses a weakref callback so that when it gets garbage collected it deregisters itself from the manager which owns its referent.

A shared object gets deleted from the manager process when there are no longer any proxies referring to it.

Process Pools

One can create a pool of processes which will carry out tasks submitted to it with the `Pool` class.

class `multiprocessing.Pool` (`[processes[, initializer[, initargs[, maxtasksperchild]]]`)

A process pool object which controls a pool of worker processes to which jobs can be submitted. It supports asynchronous results with timeouts and callbacks and has a parallel map implementation.

processes is the number of worker processes to use. If *processes* is `None` then the number returned by `cpu_count()` is used. If *initializer* is not `None` then each worker process will call `initializer(*initargs)` when it starts.

Note that the methods of the pool object should only be called by the process which created the pool.

버전 2.7에 추가: *maxtasksperchild* is the number of tasks a worker process can complete before it will exit and be replaced with a fresh worker process, to enable unused resources to be freed. The default *maxtasksperchild* is `None`, which means worker processes will live as long as the pool.

참고: Worker processes within a `Pool` typically live for the complete duration of the `Pool`'s work queue. A frequent pattern found in other systems (such as Apache, `mod_wsgi`, etc) to free resources held by workers is to allow a worker within a pool to complete only a set amount of work before being exiting, being cleaned up and a new process spawned to replace the old one. The *maxtasksperchild* argument to the `Pool` exposes this ability to the end user.

apply (`func[, args[, kwds]]`)

Equivalent of the `apply()` built-in function. It blocks until the result is ready, so `apply_async()` is better suited for performing work in parallel. Additionally, *func* is only executed in one of the workers of the pool.

apply_async (`func[, args[, kwds[, callback]]]`)

A variant of the `apply()` method which returns a result object.

If *callback* is specified then it should be a callable which accepts a single argument. When the result becomes ready *callback* is applied to it (unless the call failed). *callback* should complete immediately since otherwise the thread which handles the results will get blocked.

map (`func, iterable[, chunksize]`)

A parallel equivalent of the `map()` built-in function (it supports only one *iterable* argument though). It blocks until the result is ready.

This method chops the iterable into a number of chunks which it submits to the process pool as separate tasks. The (approximate) size of these chunks can be specified by setting *chunksize* to a positive integer.

map_async (`func, iterable[, chunksize[, callback]]`)

A variant of the `map()` method which returns a result object.

If *callback* is specified then it should be a callable which accepts a single argument. When the result becomes ready *callback* is applied to it (unless the call failed). *callback* should complete immediately since otherwise the thread which handles the results will get blocked.

imap (*func*, *iterable*[, *chunksize*])

An equivalent of `itertools.imap()`.

The *chunksize* argument is the same as the one used by the `map()` method. For very long iterables using a large value for *chunksize* can make the job complete **much** faster than using the default value of 1.

Also if *chunksize* is 1 then the `next()` method of the iterator returned by the `imap()` method has an optional *timeout* parameter: `next(timeout)` will raise `multiprocessing.TimeoutError` if the result cannot be returned within *timeout* seconds.

imap_unordered (*func*, *iterable*[, *chunksize*])

The same as `imap()` except that the ordering of the results from the returned iterator should be considered arbitrary. (Only when there is only one worker process is the order guaranteed to be «correct».)

close ()

Prevents any more tasks from being submitted to the pool. Once all the tasks have been completed the worker processes will exit.

terminate ()

Stops the worker processes immediately without completing outstanding work. When the pool object is garbage collected `terminate()` will be called immediately.

join ()

Wait for the worker processes to exit. One must call `close()` or `terminate()` before using `join()`.

class `multiprocessing.pool.AsyncResult`

The class of the result returned by `Pool.apply_async()` and `Pool.map_async()`.

get ([*timeout*])

Return the result when it arrives. If *timeout* is not None and the result does not arrive within *timeout* seconds then `multiprocessing.TimeoutError` is raised. If the remote call raised an exception then that exception will be reraised by `get()`.

wait ([*timeout*])

Wait until the result is available or until *timeout* seconds pass.

ready ()

Return whether the call has completed.

successful ()

Return whether the call completed without raising an exception. Will raise `AssertionError` if the result is not ready.

The following example demonstrates the use of a pool:

```
from multiprocessing import Pool
import time

def f(x):
    return x*x

if __name__ == '__main__':
    pool = Pool(processes=4)           # start 4 worker processes

    result = pool.apply_async(f, (10,)) # evaluate "f(10)" asynchronously in a
    ↪ single process
    print result.get(timeout=1)         # prints "100" unless your computer is
    ↪ *very* slow

    print pool.map(f, range(10))       # prints "[0, 1, 4, ..., 81]"
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

it = pool.imap(f, range(10))
print it.next()           # prints "0"
print it.next()           # prints "1"
print it.next(timeout=1)  # prints "4" unless your computer is *very*
↳slow                     ↳

result = pool.apply_async(time.sleep, (10,))
print result.get(timeout=1) # raises multiprocessing.TimeoutError

```

Listeners and Clients

Usually message passing between processes is done using queues or by using *Connection* objects returned by *Pipe()*.

However, the *multiprocessing.connection* module allows some extra flexibility. It basically gives a high level message oriented API for dealing with sockets or Windows named pipes, and also has support for *digest authentication* using the *hmac* module.

multiprocessing.connection.deliver_challenge (*connection*, *authkey*)

Send a randomly generated message to the other end of the connection and wait for a reply.

If the reply matches the digest of the message using *authkey* as the key then a welcome message is sent to the other end of the connection. Otherwise *AuthenticationError* is raised.

multiprocessing.connection.answer_challenge (*connection*, *authkey*)

Receive a message, calculate the digest of the message using *authkey* as the key, and then send the digest back.

If a welcome message is not received, then *AuthenticationError* is raised.

multiprocessing.connection.Client (*address*[, *family*[, *authenticate*[, *authkey*]]])

Attempt to set up a connection to the listener which is using address *address*, returning a *Connection*.

The type of the connection is determined by *family* argument, but this can generally be omitted since it can usually be inferred from the format of *address*. (See *Address Formats*)

If *authenticate* is True or *authkey* is a string then digest authentication is used. The key used for authentication will be either *authkey* or *current_process().authkey* if *authkey* is None. If authentication fails then *AuthenticationError* is raised. See *Authentication keys*.

class *multiprocessing.connection.Listener* ([*address*[, *family*[, *backlog*[, *authenticate*[, *authkey*]]]]])

A wrapper for a bound socket or Windows named pipe which is <listening> for connections.

address is the address to be used by the bound socket or named pipe of the listener object.

참고: If an address of <0.0.0.0> is used, the address will not be a connectable end point on Windows. If you require a connectable end-point, you should use <127.0.0.1>.

family is the type of socket (or named pipe) to use. This can be one of the strings 'AF_INET' (for a TCP socket), 'AF_UNIX' (for a Unix domain socket) or 'AF_PIPE' (for a Windows named pipe). Of these only the first is guaranteed to be available. If *family* is None then the family is inferred from the format of *address*. If *address* is also None then a default is chosen. This default is the family which is assumed to be the fastest available. See *Address Formats*. Note that if *family* is 'AF_UNIX' and *address* is None then the socket will be created in a private temporary directory created using *tempfile.mkstemp()*.

If the listener object uses a socket then *backlog* (1 by default) is passed to the *listen()* method of the socket once it has been bound.

If *authenticate* is `True` (False by default) or *authkey* is not `None` then digest authentication is used.

If *authkey* is a string then it will be used as the authentication key; otherwise it must be `None`.

If *authkey* is `None` and *authenticate* is `True` then `current_process().authkey` is used as the authentication key. If *authkey* is `None` and *authenticate* is `False` then no authentication is done. If authentication fails then *AuthenticationError* is raised. See *Authentication keys*.

accept()

Accept a connection on the bound socket or named pipe of the listener object and return a *Connection* object. If authentication is attempted and fails, then *AuthenticationError* is raised.

close()

Close the bound socket or named pipe of the listener object. This is called automatically when the listener is garbage collected. However it is advisable to call it explicitly.

Listener objects have the following read-only properties:

address

The address which is being used by the Listener object.

last_accepted

The address from which the last accepted connection came. If this is unavailable then it is `None`.

The module defines the following exceptions:

exception multiprocessing.connection.ProcessError

The base class of all *multiprocessing* exceptions.

exception multiprocessing.connection.BufferTooShort

Exception raised by *Connection.recv_bytes_into()* when the supplied buffer object is too small for the message read.

exception multiprocessing.connection.AuthenticationError

Raised when there is an authentication error.

exception multiprocessing.connection.TimeoutError

Raised by methods with a timeout when the timeout expires.

Examples

The following server code creates a listener which uses 'secret password' as an authentication key. It then waits for a connection and sends some data to the client:

```
from multiprocessing.connection import Listener
from array import array

address = ('localhost', 6000)      # family is deduced to be 'AF_INET'
listener = Listener(address, authkey='secret password')

conn = listener.accept()
print 'connection accepted from', listener.last_accepted

conn.send([2.25, None, 'junk', float])

conn.send_bytes('hello')

conn.send_bytes(array('i', [42, 1729]))

conn.close()
listener.close()
```

The following code connects to the server and receives some data from the server:

```

from multiprocessing.connection import Client
from array import array

address = ('localhost', 6000)
conn = Client(address, authkey='secret password')

print conn.recv()                # => [2.25, None, 'junk', float]

print conn.recv_bytes()          # => 'hello'

arr = array('i', [0, 0, 0, 0, 0])
print conn.recv_bytes_into(arr)  # => 8
print arr                       # => array('i', [42, 1729, 0, 0, 0])

conn.close()

```

Address Formats

- An 'AF_INET' address is a tuple of the form (hostname, port) where *hostname* is a string and *port* is an integer.
- An 'AF_UNIX' address is a string representing a filename on the filesystem.
- An 'AF_PIPE' address is a string of the form r'\.\pipe{PipeName}'. To use `Client()` to connect to a named pipe on a remote computer called *ServerName* one should use an address of the form r'\ServerName\pipe{PipeName}' instead.

Note that any string beginning with two backslashes is assumed by default to be an 'AF_PIPE' address rather than an 'AF_UNIX' address.

Authentication keys

When one uses `Connection.recv()`, the data received is automatically unpickled. Unfortunately unpickling data from an untrusted source is a security risk. Therefore `Listener` and `Client()` use the `hmac` module to provide digest authentication.

An authentication key is a string which can be thought of as a password: once a connection is established both ends will demand proof that the other knows the authentication key. (Demonstrating that both ends are using the same key does **not** involve sending the key over the connection.)

If authentication is requested but no authentication key is specified then the return value of `current_process().authkey` is used (see `Process`). This value will be automatically inherited by any `Process` object that the current process creates. This means that (by default) all processes of a multi-process program will share a single authentication key which can be used when setting up connections between themselves.

Suitable authentication keys can also be generated by using `os.urandom()`.

Logging

Some support for logging is available. Note, however, that the `logging` package does not use process shared locks so it is possible (depending on the handler type) for messages from different processes to get mixed up.

`multiprocessing.get_logger()`

Returns the logger used by `multiprocessing`. If necessary, a new one will be created.

When first created the logger has level `logging.NOTSET` and no default handler. Messages sent to this logger will not by default propagate to the root logger.

Note that on Windows child processes will only inherit the level of the parent process's logger – any other customization of the logger will not be inherited.

`multiprocessing.log_to_stderr()`

This function performs a call to `get_logger()` but in addition to returning the logger created by `get_logger`, it adds a handler which sends output to `sys.stderr` using format `'[(levelname)s/ (processName)s] (message)s'`.

Below is an example session with logging turned on:

```
>>> import multiprocessing, logging
>>> logger = multiprocessing.log_to_stderr()
>>> logger.setLevel(logging.INFO)
>>> logger.warning('doomed')
[WARNING/MainProcess] doomed
>>> m = multiprocessing.Manager()
[INFO/SyncManager-...] child process calling self.run()
[INFO/SyncManager-...] created temp directory /.../pypm-...
[INFO/SyncManager-...] manager serving at '/.../listener-...'
>>> del m
[INFO/MainProcess] sending shutdown message to manager
[INFO/SyncManager-...] manager exiting with exitcode 0
```

In addition to having these two logging functions, the `multiprocessing` also exposes two additional logging level attributes. These are `SUBWARNING` and `SUBDEBUG`. The table below illustrates where these fit in the normal level hierarchy.

Level	Numeric value
<code>SUBWARNING</code>	25
<code>SUBDEBUG</code>	5

For a full table of logging levels, see the `logging` module.

These additional logging levels are used primarily for certain debug messages within the `multiprocessing` module. Below is the same example as above, except with `SUBDEBUG` enabled:

```
>>> import multiprocessing, logging
>>> logger = multiprocessing.log_to_stderr()
>>> logger.setLevel(multiprocessing.SUBDEBUG)
>>> logger.warning('doomed')
[WARNING/MainProcess] doomed
>>> m = multiprocessing.Manager()
[INFO/SyncManager-...] child process calling self.run()
[INFO/SyncManager-...] created temp directory /.../pypm-...
[INFO/SyncManager-...] manager serving at '/.../pypm-djGBXN/listener-...'
>>> del m
[SUBDEBUG/MainProcess] finalizer calling ...
[INFO/MainProcess] sending shutdown message to manager
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
[DEBUG/SyncManager-...] manager received shutdown message
[SUBDEBUG/SyncManager-...] calling <Finalize object, callback=unlink, ...
[SUBDEBUG/SyncManager-...] finalizer calling <built-in function unlink> ...
[SUBDEBUG/SyncManager-...] calling <Finalize object, dead>
[SUBDEBUG/SyncManager-...] finalizer calling <function rmtree at 0x5aa730> ...
[INFO/SyncManager-...] manager exiting with exitcode 0
```

The `multiprocessing.dummy` module

`multiprocessing.dummy` replicates the API of `multiprocessing` but is no more than a wrapper around the `threading` module.

16.6.3 Programming guidelines

There are certain guidelines and idioms which should be adhered to when using `multiprocessing`.

All platforms

Avoid shared state

As far as possible one should try to avoid shifting large amounts of data between processes.

It is probably best to stick to using queues or pipes for communication between processes rather than using the lower level synchronization primitives from the `threading` module.

Picklability

Ensure that the arguments to the methods of proxies are picklable.

Thread safety of proxies

Do not use a proxy object from more than one thread unless you protect it with a lock.

(There is never a problem with different processes using the *same* proxy.)

Joining zombie processes

On Unix when a process finishes but has not been joined it becomes a zombie. There should never be very many because each time a new process starts (or `active_children()` is called) all completed processes which have not yet been joined will be joined. Also calling a finished process's `Process.is_alive` will join the process. Even so it is probably good practice to explicitly join all the processes that you start.

Better to inherit than pickle/unpickle

On Windows many types from `multiprocessing` need to be picklable so that child processes can use them. However, one should generally avoid sending shared objects to other processes using pipes or queues. Instead you should arrange the program so that a process which needs access to a shared resource created elsewhere can inherit it from an ancestor process.

Avoid terminating processes

Using the `Process.terminate` method to stop a process is liable to cause any shared resources (such as locks, semaphores, pipes and queues) currently being used by the process to become broken or unavailable to other processes.

Therefore it is probably best to only consider using `Process.terminate` on processes which never use any shared resources.

Joining processes that use queues

Bear in mind that a process that has put items in a queue will wait before terminating until all the buffered items are fed by the 《feeder》 thread to the underlying pipe. (The child process can call the `cancel_join_thread()` method of the queue to avoid this behaviour.)

This means that whenever you use a queue you need to make sure that all items which have been put on the queue will eventually be removed before the process is joined. Otherwise you cannot be sure that processes which have put items on the queue will terminate. Remember also that non-daemonic processes will be joined automatically.

An example which will deadlock is the following:

```
from multiprocessing import Process, Queue

def f(q):
    q.put('X' * 1000000)

if __name__ == '__main__':
    queue = Queue()
    p = Process(target=f, args=(queue,))
    p.start()
    p.join()                # this deadlocks
    obj = queue.get()
```

A fix here would be to swap the last two lines (or simply remove the `p.join()` line).

Explicitly pass resources to child processes

On Unix a child process can make use of a shared resource created in a parent process using a global resource. However, it is better to pass the object as an argument to the constructor for the child process.

Apart from making the code (potentially) compatible with Windows this also ensures that as long as the child process is still alive the object will not be garbage collected in the parent process. This might be important if some resource is freed when the object is garbage collected in the parent process.

So for instance

```
from multiprocessing import Process, Lock

def f():
    ... do something using "lock" ...

if __name__ == '__main__':
    lock = Lock()
    for i in range(10):
        Process(target=f).start()
```

should be rewritten as

```
from multiprocessing import Process, Lock

def f(l):
    ... do something using "l" ...

if __name__ == '__main__':
    lock = Lock()
    for i in range(10):
        Process(target=f, args=(lock,)).start()
```

Beware of replacing `sys.stdin` with a 《file like object》

`multiprocessing` originally unconditionally called:

```
os.close(sys.stdin.fileno())
```

in the `multiprocessing.Process._bootstrap()` method — this resulted in issues with processes-in-processes. This has been changed to:

```
sys.stdin.close()
sys.stdin = open(os.devnull)
```

Which solves the fundamental issue of processes colliding with each other resulting in a bad file descriptor error, but introduces a potential danger to applications which replace `sys.stdin()` with a «file-like object» with output buffering. This danger is that if multiple processes call `close()` on this file-like object, it could result in the same data being flushed to the object multiple times, resulting in corruption.

If you write a file-like object and implement your own caching, you can make it fork-safe by storing the pid whenever you append to the cache, and discarding the cache when the pid changes. For example:

```
@property
def cache(self):
    pid = os.getpid()
    if pid != self._pid:
        self._pid = pid
        self._cache = []
    return self._cache
```

For more information, see [bpo-5155](#), [bpo-5313](#) and [bpo-5331](#)

Windows

Since Windows lacks `os.fork()` it has a few extra restrictions:

More picklability

Ensure that all arguments to `Process.__init__()` are picklable. This means, in particular, that bound or unbound methods cannot be used directly as the `target` argument on Windows — just define a function and use that instead.

Also, if you subclass `Process` then make sure that instances will be picklable when the `Process.start` method is called.

Global variables

Bear in mind that if code run in a child process tries to access a global variable, then the value it sees (if any) may not be the same as the value in the parent process at the time that `Process.start` was called.

However, global variables which are just module level constants cause no problems.

Safe importing of main module

Make sure that the main module can be safely imported by a new Python interpreter without causing unintended side effects (such as starting a new process).

For example, under Windows running the following module would fail with a `RuntimeError`:

```
from multiprocessing import Process

def foo():
    print 'hello'
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
p = Process(target=foo)
p.start()
```

Instead one should protect the 《entry point》 of the program by using `if __name__ == '__main__':` as follows:

```
from multiprocessing import Process, freeze_support

def foo():
    print 'hello'

if __name__ == '__main__':
    freeze_support()
    p = Process(target=foo)
    p.start()
```

(The `freeze_support()` line can be omitted if the program will be run normally instead of frozen.)

This allows the newly spawned Python interpreter to safely import the module and then run the module's `foo()` function.

Similar restrictions apply if a pool or manager is created in the main module.

16.6.4 Examples

Demonstration of how to create and use customized managers and proxies:

```
#
# This module shows how to use arbitrary callables with a subclass of
# `BaseManager`.
#
# Copyright (c) 2006-2008, R Oudkerk
# All rights reserved.
#

from multiprocessing import freeze_support
from multiprocessing.managers import BaseManager, BaseProxy
import operator

##

class Foo(object):
    def f(self):
        print 'you called Foo.f()'
    def g(self):
        print 'you called Foo.g()'
    def _h(self):
        print 'you called Foo._h()'

# A simple generator function
def baz():
    for i in xrange(10):
        yield i*i

# Proxy type for generator objects
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

class GeneratorProxy(BaseProxy):
    _exposed_ = ('next', '__next__')
    def __iter__(self):
        return self
    def next(self):
        return self._callmethod('next')
    def __next__(self):
        return self._callmethod('__next__')

# Function to return the operator module
def get_operator_module():
    return operator

##

class MyManager(BaseManager):
    pass

# register the Foo class; make `f()` and `g()` accessible via proxy
MyManager.register('Foo1', Foo)

# register the Foo class; make `g()` and `_h()` accessible via proxy
MyManager.register('Foo2', Foo, exposed=('g', '_h'))

# register the generator function baz; use `GeneratorProxy` to make proxies
MyManager.register('baz', baz, proxytype=GeneratorProxy)

# register get_operator_module(); make public functions accessible via proxy
MyManager.register('operator', get_operator_module)

##

def test():
    manager = MyManager()
    manager.start()

    print '-' * 20

    f1 = manager.Foo1()
    f1.f()
    f1.g()
    assert not hasattr(f1, '_h')
    assert sorted(f1._exposed_) == sorted(['f', 'g'])

    print '-' * 20

    f2 = manager.Foo2()
    f2.g()
    f2._h()
    assert not hasattr(f2, 'f')
    assert sorted(f2._exposed_) == sorted(['g', '_h'])

    print '-' * 20

    it = manager.baz()
    for i in it:

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    print '<%d>' % i,
    print

    print '-' * 20

    op = manager.operator()
    print 'op.add(23, 45) =', op.add(23, 45)
    print 'op.pow(2, 94) =', op.pow(2, 94)
    print 'op.getslice(range(10), 2, 6) =', op.getslice(range(10), 2, 6)
    print 'op.repeat(range(5), 3) =', op.repeat(range(5), 3)
    print 'op._exposed_ =', op._exposed_

##

if __name__ == '__main__':
    freeze_support()
    test()

```

Using Pool:

```

#
# A test of `multiprocessing.Pool` class
#
# Copyright (c) 2006-2008, R Oudkerk
# All rights reserved.
#

import multiprocessing
import time
import random
import sys

#
# Functions used by test code
#

def calculate(func, args):
    result = func(*args)
    return '%s says that %s%s = %s' % (
        multiprocessing.current_process().name,
        func.__name__, args, result
    )

def calculatestar(args):
    return calculate(*args)

def mul(a, b):
    time.sleep(0.5*random.random())
    return a * b

def plus(a, b):
    time.sleep(0.5*random.random())
    return a + b

def f(x):
    return 1.0 / (x-5.0)

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

def pow3(x):
    return x**3

def noop(x):
    pass

#
# Test code
#

def test():
    print 'cpu_count() = %d\n' % multiprocessing.cpu_count()

    #
    # Create pool
    #

    PROCESSES = 4
    print 'Creating pool with %d processes\n' % PROCESSES
    pool = multiprocessing.Pool(PROCESSES)
    print 'pool = %s' % pool
    print

    #
    # Tests
    #

    TASKS = [(mul, (i, 7)) for i in range(10)] + \
            [(plus, (i, 8)) for i in range(10)]

    results = [pool.apply_async(calculate, t) for t in TASKS]
    imap_it = pool.imap(calculatestar, TASKS)
    imap_unordered_it = pool.imap_unordered(calculatestar, TASKS)

    print 'Ordered results using pool.apply_async():'
    for r in results:
        print '\t', r.get()
    print

    print 'Ordered results using pool.imap():'
    for x in imap_it:
        print '\t', x
    print

    print 'Unordered results using pool.imap_unordered():'
    for x in imap_unordered_it:
        print '\t', x
    print

    print 'Ordered results using pool.map() --- will block till complete:'
    for x in pool.map(calculatestar, TASKS):
        print '\t', x
    print

    #

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

# Simple benchmarks
#

N = 100000
print 'def pow3(x): return x**3'

t = time.time()
A = map(pow3, xrange(N))
print '\tmap(pow3, xrange(%d)):\n\t\t%s seconds' % \
      (N, time.time() - t)

t = time.time()
B = pool.map(pow3, xrange(N))
print '\tpool.map(pow3, xrange(%d)):\n\t\t%s seconds' % \
      (N, time.time() - t)

t = time.time()
C = list(pool.imap(pow3, xrange(N), chunksize=N//8))
print '\tlist(pool.imap(pow3, xrange(%d), chunksize=%d)):\n\t\t%s' \
      ' seconds' % (N, N//8, time.time() - t)

assert A == B == C, (len(A), len(B), len(C))
print

L = [None] * 1000000
print 'def noop(x): pass'
print 'L = [None] * 1000000'

t = time.time()
A = map(noop, L)
print '\tmap(noop, L):\n\t\t%s seconds' % \
      (time.time() - t)

t = time.time()
B = pool.map(noop, L)
print '\tpool.map(noop, L):\n\t\t%s seconds' % \
      (time.time() - t)

t = time.time()
C = list(pool.imap(noop, L, chunksize=len(L)//8))
print '\tlist(pool.imap(noop, L, chunksize=%d)):\n\t\t%s seconds' % \
      (len(L)//8, time.time() - t)

assert A == B == C, (len(A), len(B), len(C))
print

del A, B, C, L

#
# Test error handling
#

print 'Testing error handling:'

try:
    print pool.apply(f, (5,))

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

except ZeroDivisionError:
    print '\tGot ZeroDivisionError as expected from pool.apply()'
else:
    raise AssertionError('expected ZeroDivisionError')

try:
    print pool.map(f, range(10))
except ZeroDivisionError:
    print '\tGot ZeroDivisionError as expected from pool.map()'
else:
    raise AssertionError('expected ZeroDivisionError')

try:
    print list(pool.imap(f, range(10)))
except ZeroDivisionError:
    print '\tGot ZeroDivisionError as expected from list(pool.imap())'
else:
    raise AssertionError('expected ZeroDivisionError')

it = pool.imap(f, range(10))
for i in range(10):
    try:
        x = it.next()
    except ZeroDivisionError:
        if i == 5:
            pass
        except StopIteration:
            break
    else:
        if i == 5:
            raise AssertionError('expected ZeroDivisionError')

assert i == 9
print '\tGot ZeroDivisionError as expected from IMapIterator.next()'
print

#
# Testing timeouts
#

print 'Testing ApplyResult.get() with timeout:',
res = pool.apply_async(calculate, TASKS[0])
while 1:
    sys.stdout.flush()
    try:
        sys.stdout.write('\n\t%s' % res.get(0.02))
        break
    except multiprocessing.TimeoutError:
        sys.stdout.write('.')
print
print

print 'Testing IMapIterator.next() with timeout:',
it = pool.imap(calculatestar, TASKS)
while 1:
    sys.stdout.flush()

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    try:
        sys.stdout.write('\n\t%s' % it.next(0.02))
    except StopIteration:
        break
    except multiprocessing.TimeoutError:
        sys.stdout.write('.')

print
print

#
# Testing callback
#

print 'Testing callback:'

A = []
B = [56, 0, 1, 8, 27, 64, 125, 216, 343, 512, 729]

r = pool.apply_async(mul, (7, 8), callback=A.append)
r.wait()

r = pool.map_async(pow3, range(10), callback=A.extend)
r.wait()

if A == B:
    print '\tcallbacks succeeded\n'
else:
    print '\t*** callbacks failed\n\t\t%s != %s\n' % (A, B)

#
# Check there are no outstanding tasks
#

assert not pool._cache, 'cache = %r' % pool._cache

#
# Check close() methods
#

print 'Testing close():'

for worker in pool._pool:
    assert worker.is_alive()

result = pool.apply_async(time.sleep, [0.5])
pool.close()
pool.join()

assert result.get() is None

for worker in pool._pool:
    assert not worker.is_alive()

print '\tclose() succeeded\n'

#

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

# Check terminate() method
#

print 'Testing terminate():'

pool = multiprocessing.Pool(2)
DELTA = 0.1
ignore = pool.apply(pow3, [2])
results = [pool.apply_async(time.sleep, [DELTA]) for i in range(100)]
pool.terminate()
pool.join()

for worker in pool._pool:
    assert not worker.is_alive()

print '\tterminate() succeeded\n'

#
# Check garbage collection
#

print 'Testing garbage collection:'

pool = multiprocessing.Pool(2)
DELTA = 0.1
processes = pool._pool
ignore = pool.apply(pow3, [2])
results = [pool.apply_async(time.sleep, [DELTA]) for i in range(100)]

results = pool = None

time.sleep(DELTA * 2)

for worker in processes:
    assert not worker.is_alive()

print '\tgarbage collection succeeded\n'

if __name__ == '__main__':
    multiprocessing.freeze_support()

    assert len(sys.argv) in (1, 2)

    if len(sys.argv) == 1 or sys.argv[1] == 'processes':
        print ' Using processes '.center(79, '-')
    elif sys.argv[1] == 'threads':
        print ' Using threads '.center(79, '-')
        import multiprocessing.dummy as multiprocessing
    else:
        print 'Usage:\n\t%s [processes | threads]' % sys.argv[0]
        raise SystemExit(2)

test()

```

Synchronization types like locks, conditions and queues:

```
#
# A test file for the `multiprocessing` package
#
# Copyright (c) 2006-2008, R Oudkerk
# All rights reserved.
#

import time, sys, random
from Queue import Empty

import multiprocessing          # may get overwritten

#### TEST_VALUE

def value_func(running, mutex):
    random.seed()
    time.sleep(random.random()*4)

    mutex.acquire()
    print '\n\t\t\t' + str(multiprocessing.current_process()) + ' has finished'
    running.value -= 1
    mutex.release()

def test_value():
    TASKS = 10
    running = multiprocessing.Value('i', TASKS)
    mutex = multiprocessing.Lock()

    for i in range(TASKS):
        p = multiprocessing.Process(target=value_func, args=(running, mutex))
        p.start()

    while running.value > 0:
        time.sleep(0.08)
        mutex.acquire()
        print running.value,
        sys.stdout.flush()
        mutex.release()

    print
    print 'No more running processes'

#### TEST_QUEUE

def queue_func(queue):
    for i in range(30):
        time.sleep(0.5 * random.random())
        queue.put(i*i)
        queue.put('STOP')

def test_queue():
    q = multiprocessing.Queue()

    p = multiprocessing.Process(target=queue_func, args=(q,))
    p.start()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

o = None
while o != 'STOP':
    try:
        o = q.get(timeout=0.3)
        print o,
        sys.stdout.flush()
    except Empty:
        print 'TIMEOUT'

print

#### TEST_CONDITION

def condition_func(cond):
    cond.acquire()
    print '\t' + str(cond)
    time.sleep(2)
    print '\tchild is notifying'
    print '\t' + str(cond)
    cond.notify()
    cond.release()

def test_condition():
    cond = multiprocessing.Condition()

    p = multiprocessing.Process(target=condition_func, args=(cond,))
    print cond

    cond.acquire()
    print cond
    cond.acquire()
    print cond

    p.start()

    print 'main is waiting'
    cond.wait()
    print 'main has woken up'

    print cond
    cond.release()
    print cond
    cond.release()

    p.join()
    print cond

#### TEST_SEMAPHORE

def semaphore_func(sema, mutex, running):
    sema.acquire()

    mutex.acquire()

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    running.value += 1
    print running.value, 'tasks are running'
    mutex.release()

    random.seed()
    time.sleep(random.random()*2)

    mutex.acquire()
    running.value -= 1
    print '%s has finished' % multiprocessing.current_process()
    mutex.release()

    sema.release()

def test_semaphore():
    sema = multiprocessing.Semaphore(3)
    mutex = multiprocessing.RLock()
    running = multiprocessing.Value('i', 0)

    processes = [
        multiprocessing.Process(target=semaphore_func,
                                args=(sema, mutex, running))
        for i in range(10)
    ]

    for p in processes:
        p.start()

    for p in processes:
        p.join()

#### TEST_JOIN_TIMEOUT

def join_timeout_func():
    print '\tchild sleeping'
    time.sleep(5.5)
    print '\n\tchild terminating'

def test_join_timeout():
    p = multiprocessing.Process(target=join_timeout_func)
    p.start()

    print 'waiting for process to finish'

    while 1:
        p.join(timeout=1)
        if not p.is_alive():
            break
        print '.',
        sys.stdout.flush()

#### TEST_EVENT

def event_func(event):

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

print '\t%r is waiting' % multiprocessing.current_process()
event.wait()
print '\t%r has woken up' % multiprocessing.current_process()

def test_event():
    event = multiprocessing.Event()

    processes = [multiprocessing.Process(target=event_func, args=(event,))
                  for i in range(5)]

    for p in processes:
        p.start()

    print 'main is sleeping'
    time.sleep(2)

    print 'main is setting event'
    event.set()

    for p in processes:
        p.join()

#### TEST_SHAREDVALUES

def sharedvalues_func(values, arrays, shared_values, shared_arrays):
    for i in range(len(values)):
        v = values[i][1]
        sv = shared_values[i].value
        assert v == sv

    for i in range(len(values)):
        a = arrays[i][1]
        sa = list(shared_arrays[i][:])
        assert a == sa

    print 'Tests passed'

def test_sharedvalues():
    values = [
        ('i', 10),
        ('h', -2),
        ('d', 1.25)
    ]
    arrays = [
        ('i', range(100)),
        ('d', [0.25 * i for i in range(100)]),
        ('H', range(1000))
    ]

    shared_values = [multiprocessing.Value(id, v) for id, v in values]
    shared_arrays = [multiprocessing.Array(id, a) for id, a in arrays]

    p = multiprocessing.Process(
        target=sharedvalues_func,
        args=(values, arrays, shared_values, shared_arrays)

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    )
    p.start()
    p.join()

    assert p.exitcode == 0

####

def test(namespace=multiprocessing):
    global multiprocessing

    multiprocessing = namespace

    for func in [ test_value, test_queue, test_condition,
                  test_semaphore, test_join_timeout, test_event,
                  test_sharedvalues ]:

        print '\n\t##### %s\n' % func.__name__
        func()

    ignore = multiprocessing.active_children()          # cleanup any old processes
    if hasattr(multiprocessing, '_debug_info'):
        info = multiprocessing._debug_info()
        if info:
            print info
            raise ValueError('there should be no positive refcounts left')

if __name__ == '__main__':
    multiprocessing.freeze_support()

    assert len(sys.argv) in (1, 2)

    if len(sys.argv) == 1 or sys.argv[1] == 'processes':
        print 'Using processes '.center(79, '-')
        namespace = multiprocessing
    elif sys.argv[1] == 'manager':
        print 'Using processes and a manager '.center(79, '-')
        namespace = multiprocessing.Manager()
        namespace.Process = multiprocessing.Process
        namespace.current_process = multiprocessing.current_process
        namespace.active_children = multiprocessing.active_children
    elif sys.argv[1] == 'threads':
        print 'Using threads '.center(79, '-')
        import multiprocessing.dummy as namespace
    else:
        print 'Usage:\n\t%s [processes | manager | threads]' % sys.argv[0]
        raise SystemExit(2)

    test(namespace)

```

An example showing how to use queues to feed tasks to a collection of worker processes and collect the results:

```

#
# Simple example which uses a pool of workers to carry out some tasks.

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

#
# Notice that the results will probably not come out of the output
# queue in the same in the same order as the corresponding tasks were
# put on the input queue.  If it is important to get the results back
# in the original order then consider using `Pool.map()` or
# `Pool.imap()` (which will save on the amount of code needed anyway).
#
# Copyright (c) 2006-2008, R Oudkerk
# All rights reserved.
#

import time
import random

from multiprocessing import Process, Queue, current_process, freeze_support

#
# Function run by worker processes
#

def worker(input, output):
    for func, args in iter(input.get, 'STOP'):
        result = calculate(func, args)
        output.put(result)

#
# Function used to calculate result
#

def calculate(func, args):
    result = func(*args)
    return '%s says that %s%s = %s' % \
        (current_process().name, func.__name__, args, result)

#
# Functions referenced by tasks
#

def mul(a, b):
    time.sleep(0.5*random.random())
    return a * b

def plus(a, b):
    time.sleep(0.5*random.random())
    return a + b

#
#
#

def test():
    NUMBER_OF_PROCESSES = 4
    TASKS1 = [(mul, (i, 7)) for i in range(20)]
    TASKS2 = [(plus, (i, 8)) for i in range(10)]

    # Create queues

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

task_queue = Queue()
done_queue = Queue()

# Submit tasks
for task in TASKS1:
    task_queue.put(task)

# Start worker processes
for i in range(NUMBER_OF_PROCESSES):
    Process(target=worker, args=(task_queue, done_queue)).start()

# Get and print results
print 'Unordered results:'
for i in range(len(TASKS1)):
    print '\t', done_queue.get()

# Add more tasks using `put()`
for task in TASKS2:
    task_queue.put(task)

# Get and print some more results
for i in range(len(TASKS2)):
    print '\t', done_queue.get()

# Tell child processes to stop
for i in range(NUMBER_OF_PROCESSES):
    task_queue.put('STOP')

if __name__ == '__main__':
    freeze_support()
    test()

```

An example of how a pool of worker processes can each run a `SimpleHTTPServer.HTTPServer` instance while sharing a single listening socket.

```

#
# Example where a pool of http servers share a single listening socket
#
# On Windows this module depends on the ability to pickle a socket
# object so that the worker processes can inherit a copy of the server
# object. (We import `multiprocessing.reduction` to enable this pickling.)
#
# Not sure if we should synchronize access to `socket.accept()` method by
# using a process-shared lock -- does not seem to be necessary.
#
# Copyright (c) 2006-2008, R Oudkerk
# All rights reserved.
#

import os
import sys

from multiprocessing import Process, current_process, freeze_support
from BaseHTTPServer import HTTPServer
from SimpleHTTPServer import SimpleHTTPRequestHandler

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

if sys.platform == 'win32':
    import multiprocessing.reduction    # make sockets pickable/inheritable

def note(format, *args):
    sys.stderr.write('[%s]\t%s\n' % (current_process().name, format%args))

class RequestHandler(SimpleHTTPRequestHandler):
    # we override log_message() to show which process is handling the request
    def log_message(self, format, *args):
        note(format, *args)

def serve_forever(server):
    note('starting server')
    try:
        server.serve_forever()
    except KeyboardInterrupt:
        pass

def runpool(address, number_of_processes):
    # create a single server object -- children will each inherit a copy
    server = HTTPServer(address, RequestHandler)

    # create child processes to act as workers
    for i in range(number_of_processes-1):
        Process(target=serve_forever, args=(server,)).start()

    # main process also acts as a worker
    serve_forever(server)

def test():
    DIR = os.path.join(os.path.dirname(__file__), '..')
    ADDRESS = ('localhost', 8000)
    NUMBER_OF_PROCESSES = 4

    print 'Serving at http://%s:%d using %d worker processes' % \
        (ADDRESS[0], ADDRESS[1], NUMBER_OF_PROCESSES)
    print 'To exit press Ctrl-' + ['C', 'Break'][sys.platform=='win32']

    os.chdir(DIR)
    runpool(ADDRESS, NUMBER_OF_PROCESSES)

if __name__ == '__main__':
    freeze_support()
    test()

```

Some simple benchmarks comparing *multiprocessing* with *threading*:

```

#
# Simple benchmarks for the multiprocessing package
#

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

# Copyright (c) 2006-2008, R Oudkerk
# All rights reserved.
#

import time, sys, multiprocessing, threading, Queue, gc

if sys.platform == 'win32':
    _timer = time.clock
else:
    _timer = time.time

delta = 1

#### TEST_QUEUESPEED

def queuespeed_func(q, c, iterations):
    a = '0' * 256
    c.acquire()
    c.notify()
    c.release()

    for i in xrange(iterations):
        q.put(a)

    q.put('STOP')

def test_queuespeed(Process, q, c):
    elapsed = 0
    iterations = 1

    while elapsed < delta:
        iterations *= 2

        p = Process(target=queuespeed_func, args=(q, c, iterations))
        c.acquire()
        p.start()
        c.wait()
        c.release()

        result = None
        t = _timer()

        while result != 'STOP':
            result = q.get()

        elapsed = _timer() - t

        p.join()

    print iterations, 'objects passed through the queue in', elapsed, 'seconds'
    print 'average number/sec:', iterations/elapsed

#### TEST_PIPESPEED

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

def pipe_func(c, cond, iterations):
    a = '0' * 256
    cond.acquire()
    cond.notify()
    cond.release()

    for i in xrange(iterations):
        c.send(a)

    c.send('STOP')

def test_pipespeed():
    c, d = multiprocessing.Pipe()
    cond = multiprocessing.Condition()
    elapsed = 0
    iterations = 1

    while elapsed < delta:
        iterations *= 2

        p = multiprocessing.Process(target=pipe_func,
                                    args=(d, cond, iterations))

        cond.acquire()
        p.start()
        cond.wait()
        cond.release()

        result = None
        t = _timer()

        while result != 'STOP':
            result = c.recv()

        elapsed = _timer() - t
        p.join()

    print iterations, 'objects passed through connection in', elapsed, 'seconds'
    print 'average number/sec:', iterations/elapsed

#### TEST_SEQSPEED

def test_seqspeek(seq):
    elapsed = 0
    iterations = 1

    while elapsed < delta:
        iterations *= 2

        t = _timer()

        for i in xrange(iterations):
            a = seq[5]

        elapsed = _timer() - t

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

print iterations, 'iterations in', elapsed, 'seconds'
print 'average number/sec:', iterations/elapsed

#### TEST_LOCK

def test_lockspeed(l):
    elapsed = 0
    iterations = 1

    while elapsed < delta:
        iterations *= 2

        t = _timer()

        for i in xrange(iterations):
            l.acquire()
            l.release()

        elapsed = _timer()-t

    print iterations, 'iterations in', elapsed, 'seconds'
    print 'average number/sec:', iterations/elapsed

#### TEST_CONDITION

def conditionspeed_func(c, N):
    c.acquire()
    c.notify()

    for i in xrange(N):
        c.wait()
        c.notify()

    c.release()

def test_conditionspeed(Process, c):
    elapsed = 0
    iterations = 1

    while elapsed < delta:
        iterations *= 2

        c.acquire()
        p = Process(target=conditionspeed_func, args=(c, iterations))
        p.start()

        c.wait()

        t = _timer()

        for i in xrange(iterations):
            c.notify()
            c.wait()

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

        elapsed = _timer()-t

        c.release()
        p.join()

    print iterations * 2, 'waits in', elapsed, 'seconds'
    print 'average number/sec:', iterations * 2 / elapsed

####

def test():
    manager = multiprocessing.Manager()

    gc.disable()

    print '\n\t##### testing Queue.Queue\n'
    test_queuespeed(threading.Thread, Queue.Queue(),
                    threading.Condition())
    print '\n\t##### testing multiprocessing.Queue\n'
    test_queuespeed(multiprocessing.Process, multiprocessing.Queue(),
                    multiprocessing.Condition())
    print '\n\t##### testing Queue managed by server process\n'
    test_queuespeed(multiprocessing.Process, manager.Queue(),
                    manager.Condition())
    print '\n\t##### testing multiprocessing.Pipe\n'
    test_pipespeed()

    print

    print '\n\t##### testing list\n'
    test_seqspeak(range(10))
    print '\n\t##### testing list managed by server process\n'
    test_seqspeak(manager.list(range(10)))
    print '\n\t##### testing Array("i", ..., lock=False)\n'
    test_seqspeak(multiprocessing.Array('i', range(10), lock=False))
    print '\n\t##### testing Array("i", ..., lock=True)\n'
    test_seqspeak(multiprocessing.Array('i', range(10), lock=True))

    print

    print '\n\t##### testing threading.Lock\n'
    test_lockspeed(threading.Lock())
    print '\n\t##### testing threading.RLock\n'
    test_lockspeed(threading.RLock())
    print '\n\t##### testing multiprocessing.Lock\n'
    test_lockspeed(multiprocessing.Lock())
    print '\n\t##### testing multiprocessing.RLock\n'
    test_lockspeed(multiprocessing.RLock())
    print '\n\t##### testing lock managed by server process\n'
    test_lockspeed(manager.Lock())
    print '\n\t##### testing rlock managed by server process\n'
    test_lockspeed(manager.RLock())

    print

    print '\n\t##### testing threading.Condition\n'

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

test_conditionspeed(threading.Thread, threading.Condition())
print '\n\t##### testing multiprocessing.Condition\n'
test_conditionspeed(multiprocessing.Process, multiprocessing.Condition())
print '\n\t##### testing condition managed by a server process\n'
test_conditionspeed(multiprocessing.Process, manager.Condition())

gc.enable()

if __name__ == '__main__':
    multiprocessing.freeze_support()
    test()

```

16.7 mmap — Memory-mapped file support

Memory-mapped file objects behave like both strings and like file objects. Unlike normal string objects, however, these are mutable. You can use mmap objects in most places where strings are expected; for example, you can use the *re* module to search through a memory-mapped file. Since they're mutable, you can change a single character by doing `obj[index] = 'a'`, or change a substring by assigning to a slice: `obj[i1:i2] = '...'`. You can also read and write data starting at the current file position, and `seek()` through the file to different positions.

A memory-mapped file is created by the *mmap* constructor, which is different on Unix and on Windows. In either case you must provide a file descriptor for a file opened for update. If you wish to map an existing Python file object, use its `fileno()` method to obtain the correct value for the *fileno* parameter. Otherwise, you can open the file using the *os.open()* function, which returns a file descriptor directly (the file still needs to be closed when done).

참고: If you want to create a memory-mapping for a writable, buffered file, you should *flush()* the file first. This is necessary to ensure that local modifications to the buffers are actually available to the mapping.

For both the Unix and Windows versions of the constructor, *access* may be specified as an optional keyword parameter. *access* accepts one of three values: `ACCESS_READ`, `ACCESS_WRITE`, or `ACCESS_COPY` to specify read-only, write-through or copy-on-write memory respectively. *access* can be used on both Unix and Windows. If *access* is not specified, Windows mmap returns a write-through mapping. The initial memory values for all three access types are taken from the specified file. Assignment to an `ACCESS_READ` memory map raises a *TypeError* exception. Assignment to an `ACCESS_WRITE` memory map affects both memory and the underlying file. Assignment to an `ACCESS_COPY` memory map affects memory but does not update the underlying file.

버전 2.5에서 변경: To map anonymous memory, -1 should be passed as the *fileno* along with the length.

버전 2.6에서 변경: `mmap.mmap` has formerly been a factory function creating mmap objects. Now `mmap.mmap` is the class itself.

class `mmap.mmap` (*fileno*, *length*[, *tagname*[, *access*[, *offset*]]])

(Windows version) Maps *length* bytes from the file specified by the file handle *fileno*, and creates a mmap object. If *length* is larger than the current size of the file, the file is extended to contain *length* bytes. If *length* is 0, the maximum length of the map is the current size of the file, except that if the file is empty Windows raises an exception (you cannot create an empty mapping on Windows).

tagname, if specified and not `None`, is a string giving a tag name for the mapping. Windows allows you to have many different mappings against the same file. If you specify the name of an existing tag, that tag is opened, otherwise a new tag of this name is created. If this parameter is omitted or `None`, the mapping is created without a name. Avoiding the use of the tag parameter will assist in keeping your code portable between Unix and Windows.

offset may be specified as a non-negative integer offset. *mmap* references will be relative to the offset from the beginning of the file. *offset* defaults to 0. *offset* must be a multiple of the `ALLOCATIONGRANULARITY`.

class `mmap.mmap` (*fileno*, *length*[, *flags*[, *prot*[, *access*[, *offset*]]]])

(Unix version) Maps *length* bytes from the file specified by the file descriptor *fileno*, and returns a *mmap* object. If *length* is 0, the maximum length of the map will be the current size of the file when *mmap* is called.

flags specifies the nature of the mapping. `MAP_PRIVATE` creates a private copy-on-write mapping, so changes to the contents of the *mmap* object will be private to this process, and `MAP_SHARED` creates a mapping that's shared with all other processes mapping the same areas of the file. The default value is `MAP_SHARED`.

prot, if specified, gives the desired memory protection; the two most useful values are `PROT_READ` and `PROT_WRITE`, to specify that the pages may be read or written. *prot* defaults to `PROT_READ | PROT_WRITE`.

access may be specified in lieu of *flags* and *prot* as an optional keyword parameter. It is an error to specify both *flags*, *prot* and *access*. See the description of *access* above for information on how to use this parameter.

offset may be specified as a non-negative integer offset. *mmap* references will be relative to the offset from the beginning of the file. *offset* defaults to 0. *offset* must be a multiple of `ALLOCATIONGRANULARITY` which is equal to `PAGESIZE` on Unix systems.

To ensure validity of the created memory mapping the file specified by the descriptor *fileno* is internally automatically synchronized with physical backing store on Mac OS X and OpenVMS.

This example shows a simple way of using *mmap*:

```
import mmap

# write a simple example file
with open("hello.txt", "wb") as f:
    f.write("Hello Python!\n")

with open("hello.txt", "r+b") as f:
    # memory-map the file, size 0 means whole file
    mm = mmap.mmap(f.fileno(), 0)
    # read content via standard file methods
    print mm.readline() # prints "Hello Python!"
    # read content via slice notation
    print mm[:5] # prints "Hello"
    # update content using slice notation;
    # note that new content must have same size
    mm[6:] = " world!\n"
    # ... and read again using standard file methods
    mm.seek(0)
    print mm.readline() # prints "Hello world!"
    # close the map
    mm.close()
```

The next example demonstrates how to create an anonymous map and exchange data between the parent and child processes:

```
import mmap
import os

mm = mmap.mmap(-1, 13)
mm.write("Hello world!")

pid = os.fork()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

if pid == 0: # In a child process
    mm.seek(0)
    print mm.readline()

    mm.close()

```

Memory-mapped file objects support the following methods:

close()

Closes the mmap. Subsequent calls to other methods of the object will result in a `ValueError` exception being raised. This will not close the open file.

find(*string*[, *start*[, *end*]])

Returns the lowest index in the object where the substring *string* is found, such that *string* is contained in the range [*start*, *end*]. Optional arguments *start* and *end* are interpreted as in slice notation. Returns `-1` on failure.

flush([*offset*, *size*])

Flushes changes made to the in-memory copy of a file back to disk. Without use of this call there is no guarantee that changes are written back before the object is destroyed. If *offset* and *size* are specified, only changes to the given range of bytes will be flushed to disk; otherwise, the whole extent of the mapping is flushed. *offset* must be a multiple of the `PAGESIZE` or `ALLOCATIONGRANULARITY`.

(Windows version) A nonzero value returned indicates success; zero indicates failure.

(Unix version) A zero value is returned to indicate success. An exception is raised when the call failed.

move(*dest*, *src*, *count*)

Copy the *count* bytes starting at offset *src* to the destination index *dest*. If the mmap was created with `ACCESS_READ`, then calls to move will raise a `TypeError` exception.

read(*num*)

Return a string containing up to *num* bytes starting from the current file position; the file position is updated to point after the bytes that were returned.

read_byte()

Returns a string of length 1 containing the character at the current file position, and advances the file position by 1.

readline()

Returns a single line, starting at the current file position and up to the next newline.

resize(*newsize*)

Resizes the map and the underlying file, if any. If the mmap was created with `ACCESS_READ` or `ACCESS_COPY`, resizing the map will raise a `TypeError` exception.

rfind(*string*[, *start*[, *end*]])

Returns the highest index in the object where the substring *string* is found, such that *string* is contained in the range [*start*, *end*]. Optional arguments *start* and *end* are interpreted as in slice notation. Returns `-1` on failure.

seek(*pos*[, *whence*])

Set the file's current position. *whence* argument is optional and defaults to `os.SEEK_SET` or 0 (absolute file positioning); other values are `os.SEEK_CUR` or 1 (seek relative to the current position) and `os.SEEK_END` or 2 (seek relative to the file's end).

size()

Return the length of the file, which can be larger than the size of the memory-mapped area.

tell()

Returns the current position of the file pointer.

write (*string*)

Write the bytes in *string* into memory at the current position of the file pointer; the file position is updated to point after the bytes that were written. If the mmap was created with `ACCESS_READ`, then writing to it will raise a `TypeError` exception.

write_byte (*byte*)

Write the single-character string *byte* into memory at the current position of the file pointer; the file position is advanced by 1. If the mmap was created with `ACCESS_READ`, then writing to it will raise a `TypeError` exception.

16.8 readline — GNU readline interface

The `readline` module defines a number of functions to facilitate completion and reading/writing of history files from the Python interpreter. This module can be used directly, or via the `rlcompleter` module, which supports completion of Python identifiers at the interactive prompt. Settings made using this module affect the behaviour of both the interpreter's interactive prompt and the prompts offered by the `raw_input()` and `input()` built-in functions.

참고: The underlying Readline library API may be implemented by the `libedit` library instead of GNU readline. On MacOS X the `readline` module detects which library is being used at run time.

The configuration file for `libedit` is different from that of GNU readline. If you programmatically load configuration strings you can check for the text `libedit` in `readline.__doc__` to differentiate between GNU readline and `libedit`.

Readline keybindings may be configured via an initialization file, typically `.inputrc` in your home directory. See [Readline Init File](#) in the GNU Readline manual for information about the format and allowable constructs of that file, and the capabilities of the Readline library in general.

16.8.1 Init file

The following functions relate to the init file and user configuration:

readline.parse_and_bind (*string*)

Execute the init line provided in the *string* argument. This calls `rl_parse_and_bind()` in the underlying library.

readline.read_init_file (*[filename]*)

Execute a readline initialization file. The default filename is the last filename used. This calls `rl_read_init_file()` in the underlying library.

16.8.2 Line buffer

The following functions operate on the line buffer:

readline.get_line_buffer ()

Return the current contents of the line buffer (`rl_line_buffer` in the underlying library).

readline.insert_text (*string*)

Insert text into the line buffer at the cursor position. This calls `rl_insert_text()` in the underlying library, but ignores the return value.

readline.redisplay ()

Change what's displayed on the screen to reflect the current contents of the line buffer. This calls `rl_redisplay()` in the underlying library.

16.8.3 History file

The following functions operate on a history file:

`readline.read_history_file([filename])`

Load a readline history file, and append it to the history list. The default filename is `~/.history`. This calls `read_history()` in the underlying library.

`readline.write_history_file([filename])`

Save the history list to a readline history file, overwriting any existing file. The default filename is `~/.history`. This calls `write_history()` in the underlying library.

`readline.get_history_length()`

`readline.set_history_length(length)`

Set or return the desired number of lines to save in the history file. The `write_history_file()` function uses this value to truncate the history file, by calling `history_truncate_file()` in the underlying library. Negative values imply unlimited history file size.

16.8.4 History list

The following functions operate on a global history list:

`readline.clear_history()`

Clear the current history. This calls `clear_history()` in the underlying library. The Python function only exists if Python was compiled for a version of the library that supports it.

버전 2.4에 추가.

`readline.get_current_history_length()`

Return the number of items currently in the history. (This is different from `get_history_length()`, which returns the maximum number of lines that will be written to a history file.)

버전 2.3에 추가.

`readline.get_history_item(index)`

Return the current contents of history item at `index`. The item index is one-based. This calls `history_get()` in the underlying library.

버전 2.3에 추가.

`readline.remove_history_item(pos)`

Remove history item specified by its position from the history. The position is zero-based. This calls `remove_history()` in the underlying library.

버전 2.4에 추가.

`readline.replace_history_item(pos, line)`

Replace history item specified by its position with `line`. The position is zero-based. This calls `replace_history_entry()` in the underlying library.

버전 2.4에 추가.

`readline.add_history(line)`

Append `line` to the history buffer, as if it was the last line typed. This calls `add_history()` in the underlying library.

16.8.5 Startup hooks

버전 2.3에 추가.

`readline.set_startup_hook([function])`

Set or remove the function invoked by the `rl_startup_hook` callback of the underlying library. If *function* is specified, it will be used as the new hook function; if omitted or `None`, any function already installed is removed. The hook is called with no arguments just before `readline` prints the first prompt.

`readline.set_pre_input_hook([function])`

Set or remove the function invoked by the `rl_pre_input_hook` callback of the underlying library. If *function* is specified, it will be used as the new hook function; if omitted or `None`, any function already installed is removed. The hook is called with no arguments after the first prompt has been printed and just before `readline` starts reading input characters. This function only exists if Python was compiled for a version of the library that supports it.

16.8.6 Completion

The following functions relate to implementing a custom word completion function. This is typically operated by the Tab key, and can suggest and automatically complete a word being typed. By default, `Readline` is set up to be used by `rlcompleter` to complete Python identifiers for the interactive interpreter. If the `readline` module is to be used with a custom completer, a different set of word delimiters should be set.

`readline.set_completer([function])`

Set or remove the completer function. If *function* is specified, it will be used as the new completer function; if omitted or `None`, any completer function already installed is removed. The completer function is called as `function(text, state)`, for *state* in 0, 1, 2, ..., until it returns a non-string value. It should return the next possible completion starting with *text*.

The installed completer function is invoked by the `entry_func` callback passed to `rl_completion_matches()` in the underlying library. The *text* string comes from the first parameter to the `rl_attempted_completion_function` callback of the underlying library.

`readline.get_completer()`

Get the completer function, or `None` if no completer function has been set.

버전 2.3에 추가.

`readline.get_completion_type()`

Get the type of completion being attempted. This returns the `rl_completion_type` variable in the underlying library as an integer.

버전 2.6에 추가.

`readline.get_begidx()`

`readline.get_endidx()`

Get the beginning or ending index of the completion scope. These indexes are the *start* and *end* arguments passed to the `rl_attempted_completion_function` callback of the underlying library.

`readline.set_completer_delims(string)`

`readline.get_completer_delims()`

Set or get the word delimiters for completion. These determine the start of the word to be considered for completion (the completion scope). These functions access the `rl_completer_word_break_characters` variable in the underlying library.

`readline.set_completion_display_matches_hook([function])`

Set or remove the completion display function. If *function* is specified, it will be used as the new completion display function; if omitted or `None`, any completion display function already installed is removed. This sets or clears the `rl_completion_display_matches_hook` callback in the underlying library. The completion

display function is called as `function(substitution, [matches], longest_match_length)` once each time matches need to be displayed.

버전 2.6에 추가.

16.8.7 Example

The following example demonstrates how to use the `readline` module's history reading and writing functions to automatically load and save a history file named `.pyhist` from the user's home directory. The code below would normally be executed automatically during interactive sessions from the user's `PYTHONSTARTUP` file.

```
import os
import readline
histfile = os.path.join(os.path.expanduser("~"), ".pyhist")
try:
    readline.read_history_file(histfile)
    # default history len is -1 (infinite), which may grow unruly
    readline.set_history_length(1000)
except IOError:
    pass
import atexit
atexit.register(readline.write_history_file, histfile)
del os, histfile
```

The following example extends the `code.InteractiveConsole` class to support history save/restore.

```
import code
import readline
import atexit
import os

class HistoryConsole(code.InteractiveConsole):
    def __init__(self, locals=None, filename="<console>",
                 histfile=os.path.expanduser("~/console-history")):
        code.InteractiveConsole.__init__(self, locals, filename)
        self.init_history(histfile)

    def init_history(self, histfile):
        readline.parse_and_bind("tab: complete")
        if hasattr(readline, "read_history_file"):
            try:
                readline.read_history_file(histfile)
            except IOError:
                pass
        atexit.register(self.save_history, histfile)

    def save_history(self, histfile):
        readline.set_history_length(1000)
        readline.write_history_file(histfile)
```

16.9 rlcompleter — Completion function for GNU readline

Source code: [Lib/rlcompleter.py](#)

The `rlcompleter` module defines a completion function suitable for the `readline` module by completing valid Python identifiers and keywords.

When this module is imported on a Unix platform with the `readline` module available, an instance of the `Completer` class is automatically created and its `complete()` method is set as the `readline` completer.

Example:

```
>>> import rlcompleter
>>> import readline
>>> readline.parse_and_bind("tab: complete")
>>> readline. <TAB PRESSED>
readline.__doc__          readline.get_line_buffer(  readline.read_init_file(
readline.__file__         readline.insert_text(      readline.set_completer(
readline.__name__         readline.parse_and_bind(
>>> readline.
```

The `rlcompleter` module is designed for use with Python's interactive mode. A user can add the following lines to his or her initialization file (identified by the `PYTHONSTARTUP` environment variable) to get automatic Tab completion:

```
try:
    import readline
except ImportError:
    print "Module readline not available."
else:
    import rlcompleter
    readline.parse_and_bind("tab: complete")
```

On platforms without `readline`, the `Completer` class defined by this module can still be used for custom purposes.

16.9.1 Completer Objects

Completer objects have the following method:

`Completer.complete(text, state)`

Return the *state*th completion for *text*.

If called for *text* that doesn't include a period character ('.'), it will complete from names currently defined in `__main__`, `__builtin__` and keywords (as defined by the `keyword` module).

If called for a dotted name, it will try to evaluate anything without obvious side-effects (functions will not be evaluated, but it can generate calls to `__getattr__()`) up to the last part, and find matches for the rest via the `dir()` function. Any exception raised during the evaluation of the expression is caught, silenced and `None` is returned.

Interprocess Communication and Networking

The modules described in this chapter provide mechanisms for different processes to communicate.

Some modules only work for two processes that are on the same machine, e.g. [signal](#) and [subprocess](#). Other modules support networking protocols that two or more processes can use to communicate across machines.

The list of modules described in this chapter is:

17.1 [subprocess](#) — Subprocess management

버전 2.4에 추가.

The [subprocess](#) module allows you to spawn new processes, connect to their input/output/error pipes, and obtain their return codes. This module intends to replace several older modules and functions:

```
os.system
os.spawn*
os.popen*
popen2.*
commands.*
```

Information about how this module can be used to replace the older functions can be found in the [subprocess-replacements](#) section.

더 보기:

POSIX users (Linux, BSD, etc.) are strongly encouraged to install and use the much more recent [subprocess32](#) module instead of the version included with python 2.7. It is a drop in replacement with better behavior in many situations.

PEP 324 – PEP proposing the subprocess module

17.1.1 Using the `subprocess` Module

The recommended way to launch subprocesses is to use the following convenience functions. For more advanced use cases when these do not meet your needs, use the underlying *Popen* interface.

`subprocess.call` (*args*, *, *stdin=None*, *stdout=None*, *stderr=None*, *shell=False*)

Run the command described by *args*. Wait for command to complete, then return the `returncode` attribute.

The arguments shown above are merely the most common ones, described below in *Frequently Used Arguments* (hence the slightly odd notation in the abbreviated signature). The full function signature is the same as that of the *Popen* constructor - this functions passes all supplied arguments directly through to that interface.

Examples:

```
>>> subprocess.call(["ls", "-l"])
0

>>> subprocess.call("exit 1", shell=True)
1
```

경고: Using `shell=True` can be a security hazard. See the warning under *Frequently Used Arguments* for details.

참고: Do not use `stdout=PIPE` or `stderr=PIPE` with this function as that can deadlock based on the child process output volume. Use *Popen* with the `communicate()` method when you need pipes.

`subprocess.check_call` (*args*, *, *stdin=None*, *stdout=None*, *stderr=None*, *shell=False*)

Run command with arguments. Wait for command to complete. If the return code was zero then return, otherwise raise *CalledProcessError*. The *CalledProcessError* object will have the return code in the `returncode` attribute.

The arguments shown above are merely the most common ones, described below in *Frequently Used Arguments* (hence the slightly odd notation in the abbreviated signature). The full function signature is the same as that of the *Popen* constructor - this functions passes all supplied arguments directly through to that interface.

Examples:

```
>>> subprocess.check_call(["ls", "-l"])
0

>>> subprocess.check_call("exit 1", shell=True)
Traceback (most recent call last):
...
subprocess.CalledProcessError: Command 'exit 1' returned non-zero exit status 1
```

버전 2.5에 추가.

경고: Using `shell=True` can be a security hazard. See the warning under *Frequently Used Arguments* for details.

참고: Do not use `stdout=PIPE` or `stderr=PIPE` with this function as that can deadlock based on the child

process output volume. Use *Popen* with the `communicate()` method when you need pipes.

`subprocess.check_output(args, *, stdin=None, stderr=None, shell=False, universal_newlines=False)`

Run command with arguments and return its output as a byte string.

If the return code was non-zero it raises a *CalledProcessError*. The *CalledProcessError* object will have the return code in the *returncode* attribute and any output in the *output* attribute.

The arguments shown above are merely the most common ones, described below in *Frequently Used Arguments* (hence the slightly odd notation in the abbreviated signature). The full function signature is largely the same as that of the *Popen* constructor, except that *stdout* is not permitted as it is used internally. All other supplied arguments are passed directly through to the *Popen* constructor.

Examples:

```
>>> subprocess.check_output(["echo", "Hello World!"])
'Hello World!\n'

>>> subprocess.check_output("exit 1", shell=True)
Traceback (most recent call last):
...
subprocess.CalledProcessError: Command 'exit 1' returned non-zero exit status 1
```

To also capture standard error in the result, use `stderr=subprocess.STDOUT`:

```
>>> subprocess.check_output(
...     "ls non_existent_file; exit 0",
...     stderr=subprocess.STDOUT,
...     shell=True)
'ls: non_existent_file: No such file or directory\n'
```

버전 2.7에 추가.

경고: Using `shell=True` can be a security hazard. See the warning under *Frequently Used Arguments* for details.

참고: Do not use `stderr=PIPE` with this function as that can deadlock based on the child process error volume. Use *Popen* with the `communicate()` method when you need a `stderr` pipe.

`subprocess.PIPE`

Special value that can be used as the *stdin*, *stdout* or *stderr* argument to *Popen* and indicates that a pipe to the standard stream should be opened.

`subprocess.STDOUT`

Special value that can be used as the *stderr* argument to *Popen* and indicates that standard error should go into the same handle as standard output.

exception `subprocess.CalledProcessError`

Exception raised when a process run by *check_call()* or *check_output()* returns a non-zero exit status.

returncode

Exit status of the child process.

cmd

Command that was used to spawn the child process.

output

Output of the child process if this exception is raised by `check_output()`. Otherwise, `None`.

Frequently Used Arguments

To support a wide variety of use cases, the `Popen` constructor (and the convenience functions) accept a large number of optional arguments. For most typical use cases, many of these arguments can be safely left at their default values. The arguments that are most commonly needed are:

`args` is required for all calls and should be a string, or a sequence of program arguments. Providing a sequence of arguments is generally preferred, as it allows the module to take care of any required escaping and quoting of arguments (e.g. to permit spaces in file names). If passing a single string, either `shell` must be `True` (see below) or else the string must simply name the program to be executed without specifying any arguments.

`stdin`, `stdout` and `stderr` specify the executed program's standard input, standard output and standard error file handles, respectively. Valid values are `PIPE`, an existing file descriptor (a positive integer), an existing file object, and `None`. `PIPE` indicates that a new pipe to the child should be created. With the default settings of `None`, no redirection will occur; the child's file handles will be inherited from the parent. Additionally, `stderr` can be `STDOUT`, which indicates that the `stderr` data from the child process should be captured into the same file handle as for `stdout`.

When `stdout` or `stderr` are pipes and `universal_newlines` is `True` then all line endings will be converted to `'\n'` as described for the `universal newlines 'U'` mode argument to `open()`.

If `shell` is `True`, the specified command will be executed through the shell. This can be useful if you are using Python primarily for the enhanced control flow it offers over most system shells and still want convenient access to other shell features such as shell pipes, filename wildcards, environment variable expansion, and expansion of `~` to a user's home directory. However, note that Python itself offers implementations of many shell-like features (in particular, `glob`, `fnmatch`, `os.walk()`, `os.path.expandvars()`, `os.path.expanduser()`, and `shutil`).

경고: Executing shell commands that incorporate unsanitized input from an untrusted source makes a program vulnerable to [shell injection](#), a serious security flaw which can result in arbitrary command execution. For this reason, the use of `shell=True` is **strongly discouraged** in cases where the command string is constructed from external input:

```
>>> from subprocess import call
>>> filename = input("What file would you like to display?\n")
What file would you like to display?
non_existent; rm -rf / #
>>> call("cat " + filename, shell=True) # Uh-oh. This will end badly...
```

`shell=False` disables all shell based features, but does not suffer from this vulnerability; see the Note in the `Popen` constructor documentation for helpful hints in getting `shell=False` to work.

When using `shell=True`, `pipes.quote()` can be used to properly escape whitespace and shell metacharacters in strings that are going to be used to construct shell commands.

These options, along with all of the other options, are described in more detail in the `Popen` constructor documentation.

Popen Constructor

The underlying process creation and management in this module is handled by the [Popen](#) class. It offers a lot of flexibility so that developers are able to handle the less common cases not covered by the convenience functions.

```
class subprocess.Popen(args, bufsize=0, executable=None, stdin=None, stdout=None, stderr=None,
                        preexec_fn=None, close_fds=False, shell=False, cwd=None, env=None, uni-
                        versal_newlines=False, startupinfo=None, creationflags=0)
```

Execute a child program in a new process. On Unix, the class uses [os.execvp\(\)](#)-like behavior to execute the child program. On Windows, the class uses the Windows `CreateProcess()` function. The arguments to [Popen](#) are as follows.

args should be a sequence of program arguments or else a single string. By default, the program to execute is the first item in *args* if *args* is a sequence. If *args* is a string, the interpretation is platform-dependent and described below. See the *shell* and *executable* arguments for additional differences from the default behavior. Unless otherwise stated, it is recommended to pass *args* as a sequence.

On Unix, if *args* is a string, the string is interpreted as the name or path of the program to execute. However, this can only be done if not passing arguments to the program.

참고: [shlex.split\(\)](#) can be useful when determining the correct tokenization for *args*, especially in complex cases:

```
>>> import shlex, subprocess
>>> command_line = raw_input()
/bin/vikings -input eggs.txt -output "spam spam.txt" -cmd "echo '$MONEY'"
>>> args = shlex.split(command_line)
>>> print args
['/bin/vikings', '-input', 'eggs.txt', '-output', 'spam spam.txt', '-cmd', "echo '
↪$MONEY'"]
>>> p = subprocess.Popen(args) # Success!
```

Note in particular that options (such as *-input*) and arguments (such as *eggs.txt*) that are separated by whitespace in the shell go in separate list elements, while arguments that need quoting or backslash escaping when used in the shell (such as filenames containing spaces or the *echo* command shown above) are single list elements.

On Windows, if *args* is a sequence, it will be converted to a string in a manner described in [Converting an argument sequence to a string on Windows](#). This is because the underlying `CreateProcess()` operates on strings.

The *shell* argument (which defaults to `False`) specifies whether to use the shell as the program to execute. If *shell* is `True`, it is recommended to pass *args* as a string rather than as a sequence.

On Unix with *shell*=`True`, the shell defaults to `/bin/sh`. If *args* is a string, the string specifies the command to execute through the shell. This means that the string must be formatted exactly as it would be when typed at the shell prompt. This includes, for example, quoting or backslash escaping filenames with spaces in them. If *args* is a sequence, the first item specifies the command string, and any additional items will be treated as additional arguments to the shell itself. That is to say, [Popen](#) does the equivalent of:

```
Popen(['/bin/sh', '-c', args[0], args[1], ...])
```

On Windows with *shell*=`True`, the COMSPEC environment variable specifies the default shell. The only time you need to specify *shell*=`True` on Windows is when the command you wish to execute is built into the shell (e.g. `dir` or `copy`). You do not need *shell*=`True` to run a batch file or console-based executable.

경고: Passing `shell=True` can be a security hazard if combined with untrusted input. See the warning under *Frequently Used Arguments* for details.

bufsize, if given, has the same meaning as the corresponding argument to the built-in `open()` function: 0 means unbuffered, 1 means line buffered, any other positive value means use a buffer of (approximately) that size. A negative *bufsize* means to use the system default, which usually means fully buffered. The default value for *bufsize* is 0 (unbuffered).

참고: If you experience performance issues, it is recommended that you try to enable buffering by setting *bufsize* to either -1 or a large enough positive value (such as 4096).

The *executable* argument specifies a replacement program to execute. It is very seldom needed. When `shell=False`, *executable* replaces the program to execute specified by *args*. However, the original *args* is still passed to the program. Most programs treat the program specified by *args* as the command name, which can then be different from the program actually executed. On Unix, the *args* name becomes the display name for the executable in utilities such as **ps**. If `shell=True`, on Unix the *executable* argument specifies a replacement shell for the default `/bin/sh`.

stdin, *stdout* and *stderr* specify the executed program's standard input, standard output and standard error file handles, respectively. Valid values are *PIPE*, an existing file descriptor (a positive integer), an existing file object, and `None`. *PIPE* indicates that a new pipe to the child should be created. With the default settings of `None`, no redirection will occur; the child's file handles will be inherited from the parent. Additionally, *stderr* can be *STDOUT*, which indicates that the *stderr* data from the child process should be captured into the same file handle as for *stdout*.

If *preexec_fn* is set to a callable object, this object will be called in the child process just before the child is executed. (Unix only)

If *close_fds* is true, all file descriptors except 0, 1 and 2 will be closed before the child process is executed. (Unix only). Or, on Windows, if *close_fds* is true then no handles will be inherited by the child process. Note that on Windows, you cannot set *close_fds* to true and also redirect the standard handles by setting *stdin*, *stdout* or *stderr*.

If *cwd* is not `None`, the child's current directory will be changed to *cwd* before it is executed. Note that this directory is not considered when searching the executable, so you can't specify the program's path relative to *cwd*.

If *env* is not `None`, it must be a mapping that defines the environment variables for the new process; these are used instead of inheriting the current process's environment, which is the default behavior.

참고: If specified, *env* must provide any variables required for the program to execute. On Windows, in order to run a *side-by-side assembly* the specified *env* **must** include a valid `SystemRoot`.

If *universal_newlines* is `True`, the file objects *stdout* and *stderr* are opened as text files in *universal newlines* mode. Lines may be terminated by any of `'\n'`, the Unix end-of-line convention, `'\r'`, the old Macintosh convention or `'\r\n'`, the Windows convention. All of these external representations are seen as `'\n'` by the Python program.

참고: This feature is only available if Python is built with universal newline support (the default). Also, the *newlines* attribute of the file objects *stdout*, *stdin* and *stderr* are not updated by the `communicate()` method.

If given, *startupinfo* will be a *STARTUPINFO* object, which is passed to the underlying `CreateProcess` function. *creationflags*, if given, can be *CREATE_NEW_CONSOLE* or *CREATE_NEW_PROCESS_GROUP*. (Windows only)

Exceptions

Exceptions raised in the child process, before the new program has started to execute, will be re-raised in the parent. Additionally, the exception object will have one extra attribute called `child_traceback`, which is a string containing traceback information from the child's point of view.

The most common exception raised is `OSError`. This occurs, for example, when trying to execute a non-existent file. Applications should prepare for `OSError` exceptions.

A `ValueError` will be raised if `Popen` is called with invalid arguments.

`check_call()` and `check_output()` will raise `CalledProcessError` if the called process returns a non-zero return code.

Security

Unlike some other `popen` functions, this implementation will never call a system shell implicitly. This means that all characters, including shell metacharacters, can safely be passed to child processes. Obviously, if the shell is invoked explicitly, then it is the application's responsibility to ensure that all whitespace and metacharacters are quoted appropriately.

17.1.2 Popen Objects

Instances of the `Popen` class have the following methods:

`Popen.poll()`

Check if child process has terminated. Set and return `returncode` attribute.

`Popen.wait()`

Wait for child process to terminate. Set and return `returncode` attribute.

경고: This will deadlock when using `stdout=PIPE` and/or `stderr=PIPE` and the child process generates enough output to a pipe such that it blocks waiting for the OS pipe buffer to accept more data. Use `communicate()` to avoid that.

`Popen.communicate(input=None)`

Interact with process: Send data to stdin. Read data from stdout and stderr, until end-of-file is reached. Wait for process to terminate. The optional `input` argument should be a string to be sent to the child process, or `None`, if no data should be sent to the child.

`communicate()` returns a tuple (`stdoutdata`, `stderrdata`).

Note that if you want to send data to the process's stdin, you need to create the `Popen` object with `stdin=PIPE`. Similarly, to get anything other than `None` in the result tuple, you need to give `stdout=PIPE` and/or `stderr=PIPE` too.

참고: The data read is buffered in memory, so do not use this method if the data size is large or unlimited.

`Popen.send_signal(signal)`

Sends the signal `signal` to the child.

참고: On Windows, `SIGTERM` is an alias for `terminate()`. `CTRL_C_EVENT` and `CTRL_BREAK_EVENT` can be sent to processes started with a `creationflags` parameter which includes

CREATE_NEW_PROCESS_GROUP.

버전 2.6에 추가.

`Popen.terminate()`

Stop the child. On Posix OSs the method sends `SIGTERM` to the child. On Windows the Win32 API function `TerminateProcess()` is called to stop the child.

버전 2.6에 추가.

`Popen.kill()`

Kills the child. On Posix OSs the function sends `SIGKILL` to the child. On Windows `kill()` is an alias for `terminate()`.

버전 2.6에 추가.

The following attributes are also available:

경고: Use `communicate()` rather than `.stdin.write`, `.stdout.read` or `.stderr.read` to avoid deadlocks due to any of the other OS pipe buffers filling up and blocking the child process.

`Popen.stdin`

If the `stdin` argument was `PIPE`, this attribute is a file object that provides input to the child process. Otherwise, it is `None`.

`Popen.stdout`

If the `stdout` argument was `PIPE`, this attribute is a file object that provides output from the child process. Otherwise, it is `None`.

`Popen.stderr`

If the `stderr` argument was `PIPE`, this attribute is a file object that provides error output from the child process. Otherwise, it is `None`.

`Popen.pid`

The process ID of the child process.

Note that if you set the `shell` argument to `True`, this is the process ID of the spawned shell.

`Popen.returncode`

The child return code, set by `poll()` and `wait()` (and indirectly by `communicate()`). A `None` value indicates that the process hasn't terminated yet.

A negative value `-N` indicates that the child was terminated by signal `N` (Unix only).

17.1.3 Windows Popen Helpers

The `STARTUPINFO` class and following constants are only available on Windows.

class `subprocess.STARTUPINFO`

Partial support of the Windows `STARTUPINFO` structure is used for `Popen` creation.

dwFlags

A bit field that determines whether certain `STARTUPINFO` attributes are used when the process creates a window.

```
si = subprocess.STARTUPINFO()
si.dwFlags = subprocess.STARTF_USESTDHANDLES | subprocess.STARTF_USESHOWWINDOW
```


hStdInput

If *dwFlags* specifies *STARTF_USESTDHANDLES*, this attribute is the standard input handle for the process. If *STARTF_USESTDHANDLES* is not specified, the default for standard input is the keyboard buffer.

hStdOutput

If *dwFlags* specifies *STARTF_USESTDHANDLES*, this attribute is the standard output handle for the process. Otherwise, this attribute is ignored and the default for standard output is the console window's buffer.

hStdError

If *dwFlags* specifies *STARTF_USESTDHANDLES*, this attribute is the standard error handle for the process. Otherwise, this attribute is ignored and the default for standard error is the console window's buffer.

wShowWindow

If *dwFlags* specifies *STARTF_USESHOWWINDOW*, this attribute can be any of the values that can be specified in the *nCmdShow* parameter for the *ShowWindow* function, except for *SW_SHOWDEFAULT*. Otherwise, this attribute is ignored.

SW_HIDE is provided for this attribute. It is used when *Popen* is called with *shell=True*.

Constants

The *subprocess* module exposes the following constants.

subprocess.STD_INPUT_HANDLE

The standard input device. Initially, this is the console input buffer, *CONIN\$*.

subprocess.STD_OUTPUT_HANDLE

The standard output device. Initially, this is the active console screen buffer, *CONOUT\$*.

subprocess.STD_ERROR_HANDLE

The standard error device. Initially, this is the active console screen buffer, *CONOUT\$*.

subprocess.SW_HIDE

Hides the window. Another window will be activated.

subprocess.STARTF_USESTDHANDLES

Specifies that the *STARTUPINFO.hStdInput*, *STARTUPINFO.hStdOutput*, and *STARTUPINFO.hStdError* attributes contain additional information.

subprocess.STARTF_USESHOWWINDOW

Specifies that the *STARTUPINFO.wShowWindow* attribute contains additional information.

subprocess.CREATE_NEW_CONSOLE

The new process has a new console, instead of inheriting its parent's console (the default).

This flag is always set when *Popen* is created with *shell=True*.

subprocess.CREATE_NEW_PROCESS_GROUP

A *Popen* *creationflags* parameter to specify that a new process group will be created. This flag is necessary for using *os.kill()* on the subprocess.

This flag is ignored if *CREATE_NEW_CONSOLE* is specified.

17.1.4 Replacing Older Functions with the `subprocess` Module

In this section, «a becomes b» means that b can be used as a replacement for a.

참고: All «a» functions in this section fail (more or less) silently if the executed program cannot be found; the «b» replacements raise `OSError` instead.

In addition, the replacements using `check_output()` will fail with a `CalledProcessError` if the requested operation produces a non-zero return code. The output is still available as the `output` attribute of the raised exception.

In the following examples, we assume that the relevant functions have already been imported from the `subprocess` module.

Replacing `/bin/sh` shell backquote

```
output=`mycmd myarg`
```

becomes:

```
output = check_output(["mycmd", "myarg"])
```

Replacing shell pipeline

```
output=`dmesg | grep hda`
```

becomes:

```
p1 = Popen(["dmesg"], stdout=PIPE)
p2 = Popen(["grep", "hda"], stdin=p1.stdout, stdout=PIPE)
p1.stdout.close() # Allow p1 to receive a SIGPIPE if p2 exits.
output = p2.communicate()[0]
```

The `p1.stdout.close()` call after starting the `p2` is important in order for `p1` to receive a `SIGPIPE` if `p2` exits before `p1`.

Alternatively, for trusted input, the shell's own pipeline support may still be used directly:

```
output=`dmesg | grep hda`
```

becomes:

```
output=check_output("dmesg | grep hda", shell=True)
```

Replacing `os.system()`

```
status = os.system("mycmd" + " myarg")
# becomes
status = subprocess.call("mycmd" + " myarg", shell=True)
```

Notes:

- Calling the program through the shell is usually not required.

A more realistic example would look like this:

```
try:
    retcode = call("mycmd" + " myarg", shell=True)
    if retcode < 0:
        print >>sys.stderr, "Child was terminated by signal", -retcode
    else:
        print >>sys.stderr, "Child returned", retcode
except OSError as e:
    print >>sys.stderr, "Execution failed:", e
```

Replacing the `os.spawn` family

`P_NOWAIT` example:

```
pid = os.spawnlp(os.P_NOWAIT, "/bin/mycmd", "mycmd", "myarg")
==>
pid = Popen(["/bin/mycmd", "myarg"]).pid
```

`P_WAIT` example:

```
retcode = os.spawnlp(os.P_WAIT, "/bin/mycmd", "mycmd", "myarg")
==>
retcode = call(["/bin/mycmd", "myarg"])
```

Vector example:

```
os.spawnvp(os.P_NOWAIT, path, args)
==>
Popen([path] + args[1:])
```

Environment example:

```
os.spawnlpe(os.P_NOWAIT, "/bin/mycmd", "mycmd", "myarg", env)
==>
Popen(["/bin/mycmd", "myarg"], env={"PATH": "/usr/bin"})
```

Replacing `os.popen()`, `os.popen2()`, `os.popen3()`

```
pipe = os.popen("cmd", 'r', bufsize)
==>
pipe = Popen("cmd", shell=True, bufsize=bufsize, stdout=PIPE).stdout
```

```
pipe = os.popen("cmd", 'w', bufsize)
==>
pipe = Popen("cmd", shell=True, bufsize=bufsize, stdin=PIPE).stdin
```

```
(child_stdin, child_stdout) = os.popen2("cmd", mode, bufsize)
==>
p = Popen("cmd", shell=True, bufsize=bufsize,
         stdin=PIPE, stdout=PIPE, close_fds=True)
(child_stdin, child_stdout) = (p.stdin, p.stdout)
```

```
(child_stdin,
 child_stdout,
 child_stderr) = os.popen3("cmd", mode, bufsize)
==>
p = Popen("cmd", shell=True, bufsize=bufsize,
          stdin=PIPE, stdout=PIPE, stderr=PIPE, close_fds=True)
(child_stdin,
 child_stdout,
 child_stderr) = (p.stdin, p.stdout, p.stderr)
```

```
(child_stdin, child_stdout_and_stderr) = os.popen4("cmd", mode,
                                                    bufsize)
==>
p = Popen("cmd", shell=True, bufsize=bufsize,
          stdin=PIPE, stdout=PIPE, stderr=STDOUT, close_fds=True)
(child_stdin, child_stdout_and_stderr) = (p.stdin, p.stdout)
```

On Unix, `os.popen2`, `os.popen3` and `os.popen4` also accept a sequence as the command to execute, in which case arguments will be passed directly to the program without shell intervention. This usage can be replaced as follows:

```
(child_stdin, child_stdout) = os.popen2(["/bin/ls", "-l"], mode,
                                         bufsize)
==>
p = Popen(["/bin/ls", "-l"], bufsize=bufsize, stdin=PIPE, stdout=PIPE)
(child_stdin, child_stdout) = (p.stdin, p.stdout)
```

Return code handling translates as follows:

```
pipe = os.popen("cmd", 'w')
...
rc = pipe.close()
if rc is not None and rc >> 8:
    print "There were some errors"
==>
process = Popen("cmd", shell=True, stdin=PIPE)
...
process.stdin.close()
if process.wait() != 0:
    print "There were some errors"
```

Replacing functions from the `popen2` module

```
(child_stdout, child_stdin) = popen2.popen2("somestring", bufsize, mode)
==>
p = Popen("somestring", shell=True, bufsize=bufsize,
          stdin=PIPE, stdout=PIPE, close_fds=True)
(child_stdout, child_stdin) = (p.stdout, p.stdin)
```

On Unix, `popen2` also accepts a sequence as the command to execute, in which case arguments will be passed directly to the program without shell intervention. This usage can be replaced as follows:

```
(child_stdout, child_stdin) = popen2.popen2(["mycmd", "myarg"], bufsize,
                                             mode)
==>
p = Popen(["mycmd", "myarg"], bufsize=bufsize,
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
stdin=PIPE, stdout=PIPE, close_fds=True)
(child_stdout, child_stdin) = (p.stdout, p.stdin)
```

`popen2.Popen3` and `popen2.Popen4` basically work as `subprocess.Popen`, except that:

- `Popen` raises an exception if the execution fails.
- the `capturestderr` argument is replaced with the `stderr` argument.
- `stdin=PIPE` and `stdout=PIPE` must be specified.
- `popen2` closes all file descriptors by default, but you have to specify `close_fds=True` with `Popen`.

17.1.5 Notes

Converting an argument sequence to a string on Windows

On Windows, an *args* sequence is converted to a string that can be parsed using the following rules (which correspond to the rules used by the MS C runtime):

1. Arguments are delimited by white space, which is either a space or a tab.
2. A string surrounded by double quotation marks is interpreted as a single argument, regardless of white space contained within. A quoted string can be embedded in an argument.
3. A double quotation mark preceded by a backslash is interpreted as a literal double quotation mark.
4. Backslashes are interpreted literally, unless they immediately precede a double quotation mark.
5. If backslashes immediately precede a double quotation mark, every pair of backslashes is interpreted as a literal backslash. If the number of backslashes is odd, the last backslash escapes the next double quotation mark as described in rule 3.

17.2 socket — Low-level networking interface

This module provides access to the BSD *socket* interface. It is available on all modern Unix systems, Windows, Mac OS X, BeOS, OS/2, and probably additional platforms.

참고: Some behavior may be platform dependent, since calls are made to the operating system socket APIs.

For an introduction to socket programming (in C), see the following papers: An Introductory 4.3BSD Interprocess Communication Tutorial, by Stuart Sechrest and An Advanced 4.3BSD Interprocess Communication Tutorial, by Samuel J. Leffler et al, both in the UNIX Programmer's Manual, Supplementary Documents 1 (sections PS1:7 and PS1:8). The platform-specific reference material for the various socket-related system calls are also a valuable source of information on the details of socket semantics. For Unix, refer to the manual pages; for Windows, see the WinSock (or Winsock 2) specification. For IPv6-ready APIs, readers may want to refer to [RFC 3493](#) titled Basic Socket Interface Extensions for IPv6.

The Python interface is a straightforward transliteration of the Unix system call and library interface for sockets to Python's object-oriented style: the `socket()` function returns a *socket object* whose methods implement the various socket system calls. Parameter types are somewhat higher-level than in the C interface: as with `read()` and `write()` operations on Python files, buffer allocation on receive operations is automatic, and buffer length is implicit on send operations.

Socket addresses are represented as follows: A single string is used for the `AF_UNIX` address family. A pair (`host`, `port`) is used for the `AF_INET` address family, where `host` is a string representing either a hostname in Internet domain notation like `'daring.cwi.nl'` or an IPv4 address like `'100.50.200.5'`, and `port` is an integer. For `AF_INET6` address family, a four-tuple (`host`, `port`, `flowinfo`, `scopeid`) is used, where `flowinfo` and `scopeid` represents `sin6_flowinfo` and `sin6_scope_id` member in `struct sockaddr_in6` in C. For `socket` module methods, `flowinfo` and `scopeid` can be omitted just for backward compatibility. Note, however, omission of `scopeid` can cause problems in manipulating scoped IPv6 addresses. Other address families are currently not supported. The address format required by a particular socket object is automatically selected based on the address family specified when the socket object was created.

For IPv4 addresses, two special forms are accepted instead of a host address: the empty string represents `INADDR_ANY`, and the string `'<broadcast>'` represents `INADDR_BROADCAST`. The behavior is not available for IPv6 for backward compatibility, therefore, you may want to avoid these if you intend to support IPv6 with your Python programs.

If you use a hostname in the `host` portion of IPv4/v6 socket address, the program may show a nondeterministic behavior, as Python uses the first address returned from the DNS resolution. The socket address will be resolved differently into an actual IPv4/v6 address, depending on the results from DNS resolution and/or the host configuration. For deterministic behavior use a numeric address in `host` portion.

버전 2.5에 추가: `AF_NETLINK` sockets are represented as pairs `pid`, `groups`.

버전 2.6에 추가: Linux-only support for TIPC is also available using the `AF_TIPC` address family. TIPC is an open, non-IP based networked protocol designed for use in clustered computer environments. Addresses are represented by a tuple, and the fields depend on the address type. The general tuple form is (`addr_type`, `v1`, `v2`, `v3` [, `scope`]), where:

- `addr_type` is one of `TIPC_ADDR_NAMESEQ`, `TIPC_ADDR_NAME`, or `TIPC_ADDR_ID`.
- `scope` is one of `TIPC_ZONE_SCOPE`, `TIPC_CLUSTER_SCOPE`, and `TIPC_NODE_SCOPE`.
- If `addr_type` is `TIPC_ADDR_NAME`, then `v1` is the server type, `v2` is the port identifier, and `v3` should be 0.

If `addr_type` is `TIPC_ADDR_NAMESEQ`, then `v1` is the server type, `v2` is the lower port number, and `v3` is the upper port number.

If `addr_type` is `TIPC_ADDR_ID`, then `v1` is the node, `v2` is the reference, and `v3` should be set to 0.

All errors raise exceptions. The normal exceptions for invalid argument types and out-of-memory conditions can be raised; errors related to socket or address semantics raise the error `socket.error`.

Non-blocking mode is supported through `setblocking()`. A generalization of this based on timeouts is supported through `settimeout()`.

The module `socket` exports the following constants and functions:

exception `socket.error`

This exception is raised for socket-related errors. The accompanying value is either a string telling what went wrong or a pair (`errno`, `string`) representing an error returned by a system call, similar to the value accompanying `os.error`. See the module `errno`, which contains names for the error codes defined by the underlying operating system.

버전 2.6에서 변경: `socket.error` is now a child class of `IOError`.

exception `socket.herror`

This exception is raised for address-related errors, i.e. for functions that use `h_errno` in the C API, including `gethostbyname_ex()` and `gethostbyaddr()`.

The accompanying value is a pair (`h_errno`, `string`) representing an error returned by a library call. `string` represents the description of `h_errno`, as returned by the `hstrerror()` C function.

exception `socket.gaierror`

This exception is raised for address-related errors, for `getaddrinfo()` and `getnameinfo()`. The accom-

panying value is a pair (*error*, *string*) representing an error returned by a library call. *string* represents the description of *error*, as returned by the `gai_strerror()` C function. The *error* value will match one of the `EAI_*` constants defined in this module.

exception `socket.timeout`

This exception is raised when a timeout occurs on a socket which has had timeouts enabled via a prior call to `settimeout()`. The accompanying value is a string whose value is currently always `«timed out»`.

버전 2.3에 추가.

`socket.AF_UNIX`

`socket.AF_INET`

`socket.AF_INET6`

These constants represent the address (and protocol) families, used for the first argument to `socket()`. If the `AF_UNIX` constant is not defined then this protocol is unsupported.

`socket.SOCK_STREAM`

`socket.SOCK_DGRAM`

`socket.SOCK_RAW`

`socket.SOCK_RDM`

`socket.SOCK_SEQPACKET`

These constants represent the socket types, used for the second argument to `socket()`. (Only `SOCK_STREAM` and `SOCK_DGRAM` appear to be generally useful.)

`SO_*`

`socket.SOMAXCONN`

`MSG_*`

`SOL_*`

`IPPROTO_*`

`IPPORT_*`

`INADDR_*`

`IP_*`

`IPV6_*`

`EAI_*`

`AI_*`

`NI_*`

`TCP_*`

Many constants of these forms, documented in the Unix documentation on sockets and/or the IP protocol, are also defined in the `socket` module. They are generally used in arguments to the `setsockopt()` and `getsockopt()` methods of socket objects. In most cases, only those symbols that are defined in the Unix header files are defined; for a few symbols, default values are provided.

`SIO_*`

`RCVALL_*`

Constants for Windows' `WSAIoctl()`. The constants are used as arguments to the `ioctl()` method of socket objects.

버전 2.6에 추가.

`TIPC_*`

TIPC related constants, matching the ones exported by the C socket API. See the TIPC documentation for more information.

버전 2.6에 추가.

`socket.has_ipv6`

This constant contains a boolean value which indicates if IPv6 is supported on this platform.

버전 2.3에 추가.

`socket.create_connection(address[, timeout[, source_address]])`

Connect to a TCP service listening on the Internet *address* (a 2-tuple (host, port)), and return the socket object. This is a higher-level function than `socket.connect()`: if *host* is a non-numeric hostname, it will try to resolve it for both `AF_INET` and `AF_INET6`, and then try to connect to all possible addresses in turn until a connection succeeds. This makes it easy to write clients that are compatible to both IPv4 and IPv6.

Passing the optional *timeout* parameter will set the timeout on the socket instance before attempting to connect. If no *timeout* is supplied, the global default timeout setting returned by `getdefaulttimeout()` is used.

If supplied, *source_address* must be a 2-tuple (host, port) for the socket to bind to as its source address before connecting. If host or port are `<>` or 0 respectively the OS default behavior will be used.

버전 2.6에 추가.

버전 2.7에서 변경: *source_address* was added.

`socket.getaddrinfo(host, port[, family[, socktype[, proto[, flags]]]])`

Translate the *host/port* argument into a sequence of 5-tuples that contain all the necessary arguments for creating a socket connected to that service. *host* is a domain name, a string representation of an IPv4/v6 address or None. *port* is a string service name such as 'http', a numeric port number or None. By passing None as the value of *host* and *port*, you can pass NULL to the underlying C API.

The *family*, *socktype* and *proto* arguments can be optionally specified in order to narrow the list of addresses returned. By default, their value is 0, meaning that the full range of results is selected. The *flags* argument can be one or several of the `AI_*` constants, and will influence how results are computed and returned. Its default value is 0. For example, `AI_NUMERICHOST` will disable domain name resolution and will raise an error if *host* is a domain name.

The function returns a list of 5-tuples with the following structure:

```
(family, socktype, proto, canonname, sockaddr)
```

In these tuples, *family*, *socktype*, *proto* are all integers and are meant to be passed to the `socket()` function. *canonname* will be a string representing the canonical name of the *host* if `AI_CANONNAME` is part of the *flags* argument; else *canonname* will be empty. *sockaddr* is a tuple describing a socket address, whose format depends on the returned *family* (a (address, port) 2-tuple for `AF_INET`, a (address, port, flow info, scope id) 4-tuple for `AF_INET6`), and is meant to be passed to the `socket.connect()` method.

The following example fetches address information for a hypothetical TCP connection to `example.org` on port 80 (results may differ on your system if IPv6 isn't enabled):

```
>>> socket.getaddrinfo("example.org", 80, 0, 0, socket.IPPROTO_TCP)
[(10, 1, 6, '', ('2606:2800:220:1:248:1893:25c8:1946', 80, 0, 0)),
 (2, 1, 6, '', ('93.184.216.34', 80))]
```

버전 2.2에 추가.

`socket.getfqdn([name])`

Return a fully qualified domain name for *name*. If *name* is omitted or empty, it is interpreted as the local host. To find the fully qualified name, the hostname returned by `gethostbyaddr()` is checked, followed by aliases for the host, if available. The first name which includes a period is selected. In case no fully qualified domain name is available, the hostname as returned by `gethostname()` is returned.

버전 2.0에 추가.

`socket.gethostbyname(hostname)`

Translate a host name to IPv4 address format. The IPv4 address is returned as a string, such as '100.50.200.5'. If the host name is an IPv4 address itself it is returned unchanged. See `gethostbyname_ex()` for a more complete interface. `gethostbyname()` does not support IPv6 name resolution, and `getaddrinfo()` should be used instead for IPv4/v6 dual stack support.

`socket.gethostbyname_ex(hostname)`

Translate a host name to IPv4 address format, extended interface. Return a triple (*hostname*, *aliaslist*, *ipaddrlist*) where *hostname* is the primary host name responding to the given *ip_address*, *aliaslist* is a (possibly empty) list of alternative host names for the same address, and *ipaddrlist* is a list of IPv4 addresses for the same interface on the same host (often but not always a single address). `gethostbyname_ex()` does not support IPv6 name resolution, and `getaddrinfo()` should be used instead for IPv4/v6 dual stack support.

`socket.gethostname()`

Return a string containing the hostname of the machine where the Python interpreter is currently executing.

If you want to know the current machine's IP address, you may want to use `gethostbyname(gethostname())`. This operation assumes that there is a valid address-to-host mapping for the host, and the assumption does not always hold.

Note: `gethostname()` doesn't always return the fully qualified domain name; use `getfqdn()` (see above).

`socket.gethostbyaddr(ip_address)`

Return a triple (*hostname*, *aliaslist*, *ipaddrlist*) where *hostname* is the primary host name responding to the given *ip_address*, *aliaslist* is a (possibly empty) list of alternative host names for the same address, and *ipaddrlist* is a list of IPv4/v6 addresses for the same interface on the same host (most likely containing only a single address). To find the fully qualified domain name, use the function `getfqdn()`. `gethostbyaddr()` supports both IPv4 and IPv6.

`socket.getnameinfo(sockaddr, flags)`

Translate a socket address *sockaddr* into a 2-tuple (*host*, *port*). Depending on the settings of *flags*, the result can contain a fully-qualified domain name or numeric address representation in *host*. Similarly, *port* can contain a string port name or a numeric port number.

버전 2.2에 추가.

`socket.getprotobyname(protocolname)`

Translate an Internet protocol name (for example, 'icmp') to a constant suitable for passing as the (optional) third argument to the `socket()` function. This is usually only needed for sockets opened in `raw` mode (`SOCK_RAW`); for the normal socket modes, the correct protocol is chosen automatically if the protocol is omitted or zero.

`socket.getservbyname(servicename[, protocolname])`

Translate an Internet service name and protocol name to a port number for that service. The optional protocol name, if given, should be 'tcp' or 'udp', otherwise any protocol will match.

`socket.getservbyport(port[, protocolname])`

Translate an Internet port number and protocol name to a service name for that service. The optional protocol name, if given, should be 'tcp' or 'udp', otherwise any protocol will match.

`socket.socket([family[, type[, proto]]])`

Create a new socket using the given address family, socket type and protocol number. The address family should be `AF_INET` (the default), `AF_INET6` or `AF_UNIX`. The socket type should be `SOCK_STREAM` (the default), `SOCK_DGRAM` or perhaps one of the other `SOCK_` constants. The protocol number is usually zero and may be omitted in that case.

`socket.socketpair([family[, type[, proto]]])`

Build a pair of connected socket objects using the given address family, socket type, and protocol number. Address family, socket type, and protocol number are as for the `socket()` function above. The default family is `AF_UNIX` if defined on the platform; otherwise, the default is `AF_INET`. Availability: Unix.

버전 2.4에 추가.

`socket.fromfd(fd, family, type[, proto])`

Duplicate the file descriptor *fd* (an integer as returned by a file object's `fileno()` method) and build a socket object from the result. Address family, socket type and protocol number are as for the `socket()` function above.

The file descriptor should refer to a socket, but this is not checked — subsequent operations on the object may fail if the file descriptor is invalid. This function is rarely needed, but can be used to get or set socket options on a socket passed to a program as standard input or output (such as a server started by the Unix `inet` daemon). The socket is assumed to be in blocking mode. Availability: Unix.

`socket.ntohl(x)`

Convert 32-bit positive integers from network to host byte order. On machines where the host byte order is the same as network byte order, this is a no-op; otherwise, it performs a 4-byte swap operation.

`socket.ntohs(x)`

Convert 16-bit positive integers from network to host byte order. On machines where the host byte order is the same as network byte order, this is a no-op; otherwise, it performs a 2-byte swap operation.

`socket.htonl(x)`

Convert 32-bit positive integers from host to network byte order. On machines where the host byte order is the same as network byte order, this is a no-op; otherwise, it performs a 4-byte swap operation.

`socket.htons(x)`

Convert 16-bit positive integers from host to network byte order. On machines where the host byte order is the same as network byte order, this is a no-op; otherwise, it performs a 2-byte swap operation.

`socket.inet_aton(ip_string)`

Convert an IPv4 address from dotted-quad string format (for example, `<123.45.67.89>`) to 32-bit packed binary format, as a string four characters in length. This is useful when conversing with a program that uses the standard C library and needs objects of type `struct in_addr`, which is the C type for the 32-bit packed binary this function returns.

`inet_aton()` also accepts strings with less than three dots; see the Unix manual page `inet(3)` for details.

If the IPv4 address string passed to this function is invalid, `socket.error` will be raised. Note that exactly what is valid depends on the underlying C implementation of `inet_aton()`.

`inet_aton()` does not support IPv6, and `inet_pton()` should be used instead for IPv4/v6 dual stack support.

`socket.inet_ntoa(packed_ip)`

Convert a 32-bit packed IPv4 address (a string four characters in length) to its standard dotted-quad string representation (for example, `<123.45.67.89>`). This is useful when conversing with a program that uses the standard C library and needs objects of type `struct in_addr`, which is the C type for the 32-bit packed binary data this function takes as an argument.

If the string passed to this function is not exactly 4 bytes in length, `socket.error` will be raised. `inet_ntoa()` does not support IPv6, and `inet_ntop()` should be used instead for IPv4/v6 dual stack support.

`socket.inet_pton(address_family, ip_string)`

Convert an IP address from its family-specific string format to a packed, binary format. `inet_pton()` is useful when a library or network protocol calls for an object of type `struct in_addr` (similar to `inet_aton()`) or `struct in6_addr`.

Supported values for `address_family` are currently `AF_INET` and `AF_INET6`. If the IP address string `ip_string` is invalid, `socket.error` will be raised. Note that exactly what is valid depends on both the value of `address_family` and the underlying implementation of `inet_pton()`.

Availability: Unix (maybe not all platforms).

버전 2.3에 추가.

`socket.inet_ntop(address_family, packed_ip)`

Convert a packed IP address (a string of some number of characters) to its standard, family-specific string representation (for example, `'7.10.0.5'` or `'5aef:2b::8'`) `inet_ntop()` is useful when a library or network protocol returns an object of type `struct in_addr` (similar to `inet_ntoa()`) or `struct in6_addr`.

Supported values for *address_family* are currently *AF_INET* and *AF_INET6*. If the string *packed_ip* is not the correct length for the specified address family, *ValueError* will be raised. A *socket.error* is raised for errors from the call to *inet_ntop()*.

Availability: Unix (maybe not all platforms).

버전 2.3에 추가.

`socket.getdefaulttimeout()`

Return the default timeout in seconds (float) for new socket objects. A value of *None* indicates that new socket objects have no timeout. When the socket module is first imported, the default is *None*.

버전 2.3에 추가.

`socket.setdefaulttimeout(timeout)`

Set the default timeout in seconds (float) for new socket objects. A value of *None* indicates that new socket objects have no timeout. When the socket module is first imported, the default is *None*.

버전 2.3에 추가.

`socket.SocketType`

This is a Python type object that represents the socket object type. It is the same as `type(socket(...))`.

더 보기:

Module *SocketServer* Classes that simplify writing network servers.

Module *ssl* A TLS/SSL wrapper for socket objects.

17.2.1 Socket Objects

Socket objects have the following methods. Except for `makefile()` these correspond to Unix system calls applicable to sockets.

`socket.accept()`

Accept a connection. The socket must be bound to an address and listening for connections. The return value is a pair (*conn*, *address*) where *conn* is a new socket object usable to send and receive data on the connection, and *address* is the address bound to the socket on the other end of the connection.

`socket.bind(address)`

Bind the socket to *address*. The socket must not already be bound. (The format of *address* depends on the address family — see above.)

참고: This method has historically accepted a pair of parameters for *AF_INET* addresses instead of only a tuple. This was never intentional and is no longer available in Python 2.0 and later.

`socket.close()`

Close the socket. All future operations on the socket object will fail. The remote end will receive no more data (after queued data is flushed). Sockets are automatically closed when they are garbage-collected.

참고: `close()` releases the resource associated with a connection but does not necessarily close the connection immediately. If you want to close the connection in a timely fashion, call `shutdown()` before `close()`.

`socket.connect(address)`

Connect to a remote socket at *address*. (The format of *address* depends on the address family — see above.)

참고: This method has historically accepted a pair of parameters for `AF_INET` addresses instead of only a tuple. This was never intentional and is no longer available in Python 2.0 and later.

`socket.connect_ex(address)`

Like `connect(address)`, but return an error indicator instead of raising an exception for errors returned by the C-level `connect()` call (other problems, such as “host not found,” can still raise exceptions). The error indicator is 0 if the operation succeeded, otherwise the value of the `errno` variable. This is useful to support, for example, asynchronous connects.

참고: This method has historically accepted a pair of parameters for `AF_INET` addresses instead of only a tuple. This was never intentional and is no longer available in Python 2.0 and later.

`socket.fileno()`

Return the socket’s file descriptor (a small integer). This is useful with `select.select()`.

Under Windows the small integer returned by this method cannot be used where a file descriptor can be used (such as `os.fdopen()`). Unix does not have this limitation.

`socket.getpeername()`

Return the remote address to which the socket is connected. This is useful to find out the port number of a remote IPv4/v6 socket, for instance. (The format of the address returned depends on the address family — see above.) On some systems this function is not supported.

`socket.getsockname()`

Return the socket’s own address. This is useful to find out the port number of an IPv4/v6 socket, for instance. (The format of the address returned depends on the address family — see above.)

`socket.getsockopt(level, optname[, buflen])`

Return the value of the given socket option (see the Unix man page `getsockopt(2)`). The needed symbolic constants (`SO_*` etc.) are defined in this module. If `buflen` is absent, an integer option is assumed and its integer value is returned by the function. If `buflen` is present, it specifies the maximum length of the buffer used to receive the option in, and this buffer is returned as a string. It is up to the caller to decode the contents of the buffer (see the optional built-in module `struct` for a way to decode C structures encoded as strings).

`socket.ioctl(control, option)`

Platform Windows

The `ioctl()` method is a limited interface to the `WSAIoctl` system interface. Please refer to the [Win32 documentation](#) for more information.

On other platforms, the generic `fcntl.fcntl()` and `fcntl.ioctl()` functions may be used; they accept a socket object as their first argument.

버전 2.6에 추가.

`socket.listen(backlog)`

Listen for connections made to the socket. The `backlog` argument specifies the maximum number of queued connections and should be at least 0; the maximum value is system-dependent (usually 5), the minimum value is forced to 0.

`socket.makefile([mode[, bufsize]])`

Return a *file object* associated with the socket. (File objects are described in [File Objects](#).) The file object does not close the socket explicitly when its `close()` method is called, but only removes its reference to the socket object, so that the socket will be closed if it is not referenced from anywhere else.

The socket must be in blocking mode (it can not have a timeout). The optional *mode* and *bufsize* arguments are interpreted the same way as by the built-in `file()` function.

참고: On Windows, the file-like object created by `makefile()` cannot be used where a file object with a file descriptor is expected, such as the stream arguments of `subprocess.Popen()`.

`socket.recv(bufsize[, flags])`

Receive data from the socket. The return value is a string representing the data received. The maximum amount of data to be received at once is specified by *bufsize*. See the Unix manual page `recv(2)` for the meaning of the optional argument *flags*; it defaults to zero.

참고: For best match with hardware and network realities, the value of *bufsize* should be a relatively small power of 2, for example, 4096.

`socket.recvfrom(bufsize[, flags])`

Receive data from the socket. The return value is a pair (*string*, *address*) where *string* is a string representing the data received and *address* is the address of the socket sending the data. See the Unix manual page `recv(2)` for the meaning of the optional argument *flags*; it defaults to zero. (The format of *address* depends on the address family — see above.)

`socket.recvfrom_into(buffer[, nbytes[, flags]])`

Receive data from the socket, writing it into *buffer* instead of creating a new string. The return value is a pair (*nbytes*, *address*) where *nbytes* is the number of bytes received and *address* is the address of the socket sending the data. See the Unix manual page `recv(2)` for the meaning of the optional argument *flags*; it defaults to zero. (The format of *address* depends on the address family — see above.)

버전 2.5에 추가.

`socket.recv_into(buffer[, nbytes[, flags]])`

Receive up to *nbytes* bytes from the socket, storing the data into a buffer rather than creating a new string. If *nbytes* is not specified (or 0), receive up to the size available in the given buffer. Returns the number of bytes received. See the Unix manual page `recv(2)` for the meaning of the optional argument *flags*; it defaults to zero.

버전 2.5에 추가.

`socket.send(string[, flags])`

Send data to the socket. The socket must be connected to a remote socket. The optional *flags* argument has the same meaning as for `recv()` above. Returns the number of bytes sent. Applications are responsible for checking that all data has been sent; if only some of the data was transmitted, the application needs to attempt delivery of the remaining data. For further information on this concept, consult the socket-howto.

`socket.sendall(string[, flags])`

Send data to the socket. The socket must be connected to a remote socket. The optional *flags* argument has the same meaning as for `recv()` above. Unlike `send()`, this method continues to send data from *string* until either all data has been sent or an error occurs. `None` is returned on success. On error, an exception is raised, and there is no way to determine how much data, if any, was successfully sent.

`socket.sendto(string, address)`

`socket.sendto(string, flags, address)`

Send data to the socket. The socket should not be connected to a remote socket, since the destination socket is specified by *address*. The optional *flags* argument has the same meaning as for `recv()` above. Return the number of bytes sent. (The format of *address* depends on the address family — see above.)

`socket.setblocking(flag)`

Set blocking or non-blocking mode of the socket: if *flag* is 0, the socket is set to non-blocking, else to blocking mode. Initially all sockets are in blocking mode. In non-blocking mode, if a `recv()` call doesn't find any data,

or if a `send()` call can't immediately dispose of the data, an `error` exception is raised; in blocking mode, the calls block until they can proceed. `s.setblocking(0)` is equivalent to `s.settimeout(0.0)`; `s.setblocking(1)` is equivalent to `s.settimeout(None)`.

`socket.settimeout(value)`

Set a timeout on blocking socket operations. The *value* argument can be a nonnegative float expressing seconds, or `None`. If a float is given, subsequent socket operations will raise a `timeout` exception if the timeout period *value* has elapsed before the operation has completed. Setting a timeout of `None` disables timeouts on socket operations. `s.settimeout(0.0)` is equivalent to `s.setblocking(0)`; `s.settimeout(None)` is equivalent to `s.setblocking(1)`.

버전 2.3에 추가.

`socket.gettimeout()`

Return the timeout in seconds (float) associated with socket operations, or `None` if no timeout is set. This reflects the last call to `setblocking()` or `settimeout()`.

버전 2.3에 추가.

Some notes on socket blocking and timeouts: A socket object can be in one of three modes: blocking, non-blocking, or timeout. Sockets are always created in blocking mode. In blocking mode, operations block until complete or the system returns an error (such as connection timed out). In non-blocking mode, operations fail (with an error that is unfortunately system-dependent) if they cannot be completed immediately. In timeout mode, operations fail if they cannot be completed within the timeout specified for the socket or if the system returns an error. The `setblocking()` method is simply a shorthand for certain `settimeout()` calls.

Timeout mode internally sets the socket in non-blocking mode. The blocking and timeout modes are shared between file descriptors and socket objects that refer to the same network endpoint. A consequence of this is that file objects returned by the `makefile()` method must only be used when the socket is in blocking mode; in timeout or non-blocking mode file operations that cannot be completed immediately will fail.

Note that the `connect()` operation is subject to the timeout setting, and in general it is recommended to call `settimeout()` before calling `connect()` or pass a timeout parameter to `create_connection()`. The system network stack may return a connection timeout error of its own regardless of any Python socket timeout setting.

`socket.setsockopt(level, optname, value)`

Set the value of the given socket option (see the Unix manual page `setsockopt(2)`). The needed symbolic constants are defined in the `socket` module (`SO_*` etc.). The value can be an integer or a string representing a buffer. In the latter case it is up to the caller to ensure that the string contains the proper bits (see the optional built-in module `struct` for a way to encode C structures as strings).

`socket.shutdown(how)`

Shut down one or both halves of the connection. If *how* is `SHUT_RD`, further receives are disallowed. If *how* is `SHUT_WR`, further sends are disallowed. If *how* is `SHUT_RDWR`, further sends and receives are disallowed. Depending on the platform, shutting down one half of the connection can also close the opposite half (e.g. on Mac OS X, `shutdown(SHUT_WR)` does not allow further reads on the other end of the connection).

Note that there are no methods `read()` or `write()`; use `recv()` and `send()` without *flags* argument instead.

Socket objects also have these (read-only) attributes that correspond to the values given to the `socket` constructor.

`socket.family`

The socket family.

버전 2.5에 추가.

`socket.type`

The socket type.

버전 2.5에 추가.

`socket.proto`

The socket protocol.

버전 2.5에 추가.

17.2.2 Example

Here are four minimal example programs using the TCP/IP protocol: a server that echoes all data that it receives back (servicing only one client), and a client using it. Note that a server must perform the sequence `socket()`, `bind()`, `listen()`, `accept()` (possibly repeating the `accept()` to service more than one client), while a client only needs the sequence `socket()`, `connect()`. Also note that the server does not `sendall()/recv()` on the socket it is listening on but on the new socket returned by `accept()`.

The first two examples support IPv4 only.

```
# Echo server program
import socket

HOST = ''                    # Symbolic name meaning all available interfaces
PORT = 50007                # Arbitrary non-privileged port
s = socket.socket(socket.AF_INET, socket.SOCK_STREAM)
s.bind((HOST, PORT))
s.listen(1)
conn, addr = s.accept()
print 'Connected by', addr
while 1:
    data = conn.recv(1024)
    if not data: break
    conn.sendall(data)
conn.close()
```

```
# Echo client program
import socket

HOST = 'daring.cwi.nl'      # The remote host
PORT = 50007                # The same port as used by the server
s = socket.socket(socket.AF_INET, socket.SOCK_STREAM)
s.connect((HOST, PORT))
s.sendall('Hello, world')
data = s.recv(1024)
s.close()
print 'Received', repr(data)
```

The next two examples are identical to the above two, but support both IPv4 and IPv6. The server side will listen to the first address family available (it should listen to both instead). On most of IPv6-ready systems, IPv6 will take precedence and the server may not accept IPv4 traffic. The client side will try to connect to the all addresses returned as a result of the name resolution, and sends traffic to the first one connected successfully.

```
# Echo server program
import socket
import sys

HOST = None                 # Symbolic name meaning all available interfaces
PORT = 50007                # Arbitrary non-privileged port
s = None
for res in socket.getaddrinfo(HOST, PORT, socket.AF_UNSPEC,
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

                                socket.SOCK_STREAM, 0, socket.AI_PASSIVE):
af, socktype, proto, canonname, sa = res
try:
    s = socket.socket(af, socktype, proto)
except socket.error as msg:
    s = None
    continue
try:
    s.bind(sa)
    s.listen(1)
except socket.error as msg:
    s.close()
    s = None
    continue
break
if s is None:
    print 'could not open socket'
    sys.exit(1)
conn, addr = s.accept()
print 'Connected by', addr
while 1:
    data = conn.recv(1024)
    if not data: break
    conn.send(data)
conn.close()

```

```

# Echo client program
import socket
import sys

HOST = 'daring.cwi.nl'      # The remote host
PORT = 50007                # The same port as used by the server
s = None
for res in socket.getaddrinfo(HOST, PORT, socket.AF_UNSPEC, socket.SOCK_STREAM):
    af, socktype, proto, canonname, sa = res
    try:
        s = socket.socket(af, socktype, proto)
    except socket.error as msg:
        s = None
        continue
    try:
        s.connect(sa)
    except socket.error as msg:
        s.close()
        s = None
        continue
    break
if s is None:
    print 'could not open socket'
    sys.exit(1)
s.sendall('Hello, world')
data = s.recv(1024)
s.close()
print 'Received', repr(data)

```

The last example shows how to write a very simple network sniffer with raw sockets on Windows. The example requires administrator privileges to modify the interface:


```
import socket

# the public network interface
HOST = socket.gethostbyname(socket.gethostname())

# create a raw socket and bind it to the public interface
s = socket.socket(socket.AF_INET, socket.SOCK_RAW, socket.IPPROTO_IP)
s.bind((HOST, 0))

# Include IP headers
s.setsockopt(socket.IPPROTO_IP, socket.IP_HDRINCL, 1)

# receive all packages
s.ioctl(socket.SIO_RCVALL, socket.RCVALL_ON)

# receive a package
print s.recvfrom(65565)

# disabled promiscuous mode
s.ioctl(socket.SIO_RCVALL, socket.RCVALL_OFF)
```

Running an example several times with too small delay between executions, could lead to this error:

```
socket.error: [Errno 98] Address already in use
```

This is because the previous execution has left the socket in a `TIME_WAIT` state, and can't be immediately reused.

There is a `socket` flag to set, in order to prevent this, `socket.SO_REUSEADDR`:

```
s = socket.socket(socket.AF_INET, socket.SOCK_STREAM)
s.setsockopt(socket.SOL_SOCKET, socket.SO_REUSEADDR, 1)
s.bind((HOST, PORT))
```

the `SO_REUSEADDR` flag tells the kernel to reuse a local socket in `TIME_WAIT` state, without waiting for its natural timeout to expire.

17.3 `ssl` — TLS/SSL wrapper for socket objects

버전 2.6에 추가.

Source code: [Lib/ssl.py](#)

This module provides access to Transport Layer Security (often known as 《Secure Sockets Layer》) encryption and peer authentication facilities for network sockets, both client-side and server-side. This module uses the OpenSSL library. It is available on all modern Unix systems, Windows, Mac OS X, and probably additional platforms, as long as OpenSSL is installed on that platform.

버전 2.7.13에서 변경: Updated to support linking with OpenSSL 1.1.0

참고: Some behavior may be platform dependent, since calls are made to the operating system socket APIs. The installed version of OpenSSL may also cause variations in behavior. For example, TLSv1.1 and TLSv1.2 come with openssl version 1.0.1.

경고: Don't use this module without reading the *Security considerations*. Doing so may lead to a false sense of security, as the default settings of the `ssl` module are not necessarily appropriate for your application.

This section documents the objects and functions in the `ssl` module; for more general information about TLS, SSL, and certificates, the reader is referred to the documents in the *《See Also》* section at the bottom.

This module provides a class, `ssl.SSLSocket`, which is derived from the `socket.socket` type, and provides a socket-like wrapper that also encrypts and decrypts the data going over the socket with SSL. It supports additional methods such as `getpeercert()`, which retrieves the certificate of the other side of the connection, and `cipher()`, which retrieves the cipher being used for the secure connection.

For more sophisticated applications, the `ssl.SSLContext` class helps manage settings and certificates, which can then be inherited by SSL sockets created through the `SSLContext.wrap_socket()` method.

17.3.1 Functions, Constants, and Exceptions

exception `ssl.SSLError`

Raised to signal an error from the underlying SSL implementation (currently provided by the OpenSSL library). This signifies some problem in the higher-level encryption and authentication layer that's superimposed on the underlying network connection. This error is a subtype of `socket.error`, which in turn is a subtype of `IOError`. The error code and message of `SSLError` instances are provided by the OpenSSL library.

library

A string mnemonic designating the OpenSSL submodule in which the error occurred, such as `SSL`, `PEM` or `X509`. The range of possible values depends on the OpenSSL version.

버전 2.7.9에 추가.

reason

A string mnemonic designating the reason this error occurred, for example `CERTIFICATE_VERIFY_FAILED`. The range of possible values depends on the OpenSSL version.

버전 2.7.9에 추가.

exception `ssl.SSLZeroReturnError`

A subclass of `SSLError` raised when trying to read or write and the SSL connection has been closed cleanly. Note that this doesn't mean that the underlying transport (read TCP) has been closed.

버전 2.7.9에 추가.

exception `ssl.SSLWantReadError`

A subclass of `SSLError` raised by a *non-blocking SSL socket* when trying to read or write data, but more data needs to be received on the underlying TCP transport before the request can be fulfilled.

버전 2.7.9에 추가.

exception `ssl.SSLWantWriteError`

A subclass of `SSLError` raised by a *non-blocking SSL socket* when trying to read or write data, but more data needs to be sent on the underlying TCP transport before the request can be fulfilled.

버전 2.7.9에 추가.

exception `ssl.SSLSyscallError`

A subclass of `SSLError` raised when a system error was encountered while trying to fulfill an operation on a SSL socket. Unfortunately, there is no easy way to inspect the original `errno` number.

버전 2.7.9에 추가.

exception `ssl.SSLEOFError`

A subclass of `SSL_ERROR` raised when the SSL connection has been terminated abruptly. Generally, you shouldn't try to reuse the underlying transport when this error is encountered.

버전 2.7.9에 추가.

exception `ssl.CertificateError`

Raised to signal an error with a certificate (such as mismatching hostname). Certificate errors detected by OpenSSL, though, raise an `SSL_ERROR`.

Socket creation

The following function allows for standalone socket creation. Starting from Python 2.7.9, it can be more flexible to use `SSLContext.wrap_socket()` instead.

`ssl.wrap_socket(sock, keyfile=None, certfile=None, server_side=False, cert_reqs=CERT_NONE, ssl_version={see docs}, ca_certs=None, do_handshake_on_connect=True, suppress_ragged_eofs=True, ciphers=None)`

Takes an instance `sock` of `socket.socket`, and returns an instance of `ssl.SSLSocket`, a subtype of `socket.socket`, which wraps the underlying socket in an SSL context. `sock` must be a `SOCK_STREAM` socket; other socket types are unsupported.

For client-side sockets, the context construction is lazy; if the underlying socket isn't connected yet, the context construction will be performed after `connect()` is called on the socket. For server-side sockets, if the socket has no remote peer, it is assumed to be a listening socket, and the server-side SSL wrapping is automatically performed on client connections accepted via the `accept()` method. `wrap_socket()` may raise `SSL_ERROR`.

The `keyfile` and `certfile` parameters specify optional files which contain a certificate to be used to identify the local side of the connection. See the discussion of [Certificates](#) for more information on how the certificate is stored in the `certfile`.

The parameter `server_side` is a boolean which identifies whether server-side or client-side behavior is desired from this socket.

The parameter `cert_reqs` specifies whether a certificate is required from the other side of the connection, and whether it will be validated if provided. It must be one of the three values `CERT_NONE` (certificates ignored), `CERT_OPTIONAL` (not required, but validated if provided), or `CERT_REQUIRED` (required and validated). If the value of this parameter is not `CERT_NONE`, then the `ca_certs` parameter must point to a file of CA certificates.

The `ca_certs` file contains a set of concatenated 《certification authority》 certificates, which are used to validate certificates passed from the other end of the connection. See the discussion of [Certificates](#) for more information about how to arrange the certificates in this file.

The parameter `ssl_version` specifies which version of the SSL protocol to use. Typically, the server chooses a particular protocol version, and the client must adapt to the server's choice. Most of the versions are not interoperable with the other versions. If not specified, the default is `PROTOCOL_SSLv23`; it provides the most compatibility with other versions.

Here's a table showing which versions in a client (down the side) can connect to which versions in a server (along the top):

<i>client / server</i>	SSLv2	SSLv3	SSLv23	TLSv1	TLSv1.1	TLSv1.2
SSLv2	yes	no	yes	no	no	no
SSLv3	no	yes	yes	no	no	no
SSLv23 ¹	no	yes	yes	yes	yes	yes
TLSv1	no	no	yes	yes	no	no
TLSv1.1	no	no	yes	no	yes	no
TLSv1.2	no	no	yes	no	no	yes

참고: Which connections succeed will vary depending on the version of OpenSSL. For example, before OpenSSL 1.0.0, an SSLv23 client would always attempt SSLv2 connections.

The *ciphers* parameter sets the available ciphers for this SSL object. It should be a string in the [OpenSSL cipher list format](#).

The parameter *do_handshake_on_connect* specifies whether to do the SSL handshake automatically after doing a `socket.connect()`, or whether the application program will call it explicitly, by invoking the `SSLSocket.do_handshake()` method. Calling `SSLSocket.do_handshake()` explicitly gives the program control over the blocking behavior of the socket I/O involved in the handshake.

The parameter *suppress_ragged_eofs* specifies how the `SSLSocket.read()` method should signal unexpected EOF from the other end of the connection. If specified as *True* (the default), it returns a normal EOF (an empty bytes object) in response to unexpected EOF errors raised from the underlying socket; if *False*, it will raise the exceptions back to the caller.

버전 2.7에서 변경: New optional argument *ciphers*.

Context creation

A convenience function helps create *SSLContext* objects for common purposes.

`ssl.create_default_context(purpose=Purpose.SERVER_AUTH, cafile=None, capath=None, cadata=None)`

Return a new *SSLContext* object with default settings for the given *purpose*. The settings are chosen by the *ssl* module, and usually represent a higher security level than when calling the *SSLContext* constructor directly.

cafile, *capath*, *cadata* represent optional CA certificates to trust for certificate verification, as in *SSLContext.load_verify_locations()*. If all three are *None*, this function can choose to trust the system's default CA certificates instead.

The settings are: *PROTOCOL_SSLv23*, *OP_NO_SSLv2*, and *OP_NO_SSLv3* with high encryption cipher suites without RC4 and without unauthenticated cipher suites. Passing *SERVER_AUTH* as *purpose* sets *verify_mode* to *CERT_REQUIRED* and either loads CA certificates (when at least one of *cafile*, *capath* or *cadata* is given) or uses *SSLContext.load_default_certs()* to load default CA certificates.

참고: The protocol, options, cipher and other settings may change to more restrictive values anytime without prior deprecation. The values represent a fair balance between compatibility and security.

If your application needs specific settings, you should create a *SSLContext* and apply the settings yourself.

참고: If you find that when certain older clients or servers attempt to connect with a *SSLContext* created by this function that they get an error stating 《Protocol or cipher suite mismatch》, it may be that they only support SSL3.0 which this function excludes using the *OP_NO_SSLv3*. SSL3.0 is widely considered to be [completely broken](#). If you still wish to continue to use this function but still allow SSL 3.0 connections you can re-enable them using:

```
ctx = ssl.create_default_context(Purpose.CLIENT_AUTH)
ctx.options |= ~ssl.OP_NO_SSLv3
```

¹ TLS 1.3 protocol will be available with *PROTOCOL_SSLv23* in OpenSSL >= 1.1.1. There is no dedicated *PROTOCOL* constant for just TLS 1.3.

버전 2.7.9에 추가.

버전 2.7.10에서 변경: RC4 was dropped from the default cipher string.

버전 2.7.13에서 변경: ChaCha20/Poly1305 was added to the default cipher string.

3DES was dropped from the default cipher string.

`ssl._https_verify_certificates(enable=True)`

Specifies whether or not server certificates are verified when creating client HTTPS connections without specifying a particular SSL context.

Starting with Python 2.7.9, `httpplib` and modules which use it, such as `urllib2` and `xmllib`, default to verifying remote server certificates received when establishing client HTTPS connections. This default verification checks that the certificate is signed by a Certificate Authority in the system trust store and that the Common Name (or Subject Alternate Name) on the presented certificate matches the requested host.

Setting `enable` to `True` ensures this default behaviour is in effect.

Setting `enable` to `False` reverts the default HTTPS certificate handling to that of Python 2.7.8 and earlier, allowing connections to servers using self-signed certificates, servers using certificates signed by a Certificate Authority not present in the system trust store, and servers where the hostname does not match the presented server certificate.

The leading underscore on this function denotes that it intentionally does not exist in any implementation of Python 3 and may not be present in all Python 2.7 implementations. The portable approach to bypassing certificate checks or the system trust store when necessary is for tools to enable that on a case-by-case basis by explicitly passing in a suitably configured SSL context, rather than reverting the default behaviour of the standard library client modules.

버전 2.7.12에 추가.

더 보기:

- [CVE-2014-9365](#) – HTTPS man-in-the-middle attack against Python clients using default settings
- [PEP 476](#) – Enabling certificate verification by default for HTTPS
- [PEP 493](#) – HTTPS verification migration tools for Python 2.7

Random generation

버전 2.7.13 부터 폐지: OpenSSL has deprecated `ssl.RAND_pseudo_bytes()`, use `ssl.RAND_bytes()` instead.

`ssl.RAND_status()`

Return `True` if the SSL pseudo-random number generator has been seeded with <enough> randomness, and `False` otherwise. You can use `ssl.RAND_egd()` and `ssl.RAND_add()` to increase the randomness of the pseudo-random number generator.

`ssl.RAND_egd(path)`

If you are running an entropy-gathering daemon (EGD) somewhere, and `path` is the pathname of a socket connection open to it, this will read 256 bytes of randomness from the socket, and add it to the SSL pseudo-random number generator to increase the security of generated secret keys. This is typically only necessary on systems without better sources of randomness.

See <http://egd.sourceforge.net/> or <http://prngd.sourceforge.net/> for sources of entropy-gathering daemons.

Availability: not available with LibreSSL and OpenSSL > 1.1.0

`ssl.RAND_add (bytes, entropy)`

Mix the given *bytes* into the SSL pseudo-random number generator. The parameter *entropy* (a float) is a lower bound on the entropy contained in string (so you can always use 0.0). See [RFC 1750](#) for more information on sources of entropy.

Certificate handling

`ssl.match_hostname (cert, hostname)`

Verify that *cert* (in decoded format as returned by `SSLSocket.getpeercert()`) matches the given *hostname*. The rules applied are those for checking the identity of HTTPS servers as outlined in [RFC 2818](#) and [RFC 6125](#), except that IP addresses are not currently supported. In addition to HTTPS, this function should be suitable for checking the identity of servers in various SSL-based protocols such as FTPS, IMAPS, POPS and others.

`CertificateError` is raised on failure. On success, the function returns nothing:

```
>>> cert = {'subject': (('commonName', 'example.com'),),)}
>>> ssl.match_hostname(cert, "example.com")
>>> ssl.match_hostname(cert, "example.org")
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
  File "/home/py3k/Lib/ssl.py", line 130, in match_hostname
ssl.CertificateError: hostname 'example.org' doesn't match 'example.com'
```

버전 2.7.9에 추가.

`ssl.cert_time_to_seconds (cert_time)`

Return the time in seconds since the Epoch, given the *cert_time* string representing the `<notBefore>` or `<notAfter>` date from a certificate in "`%b %d %H:%M:%S %Y %Z`" strptime format (C locale).

Here's an example:

```
>>> import ssl
>>> timestamp = ssl.cert_time_to_seconds("Jan  5 09:34:43 2018 GMT")
>>> timestamp
1515144883
>>> from datetime import datetime
>>> print(datetime.utcfromtimestamp(timestamp))
2018-01-05 09:34:43
```

`<notBefore>` or `<notAfter>` dates must use GMT ([RFC 5280](#)).

버전 2.7.9에서 변경: Interpret the input time as a time in UTC as specified by `<GMT>` timezone in the input string. Local timezone was used previously. Return an integer (no fractions of a second in the input format)

`ssl.get_server_certificate (addr, ssl_version=PROTOCOL_SSLv23, ca_certs=None)`

Given the address *addr* of an SSL-protected server, as a (*hostname*, *port-number*) pair, fetches the server's certificate, and returns it as a PEM-encoded string. If *ssl_version* is specified, uses that version of the SSL protocol to attempt to connect to the server. If *ca_certs* is specified, it should be a file containing a list of root certificates, the same format as used for the same parameter in `wrap_socket()`. The call will attempt to validate the server certificate against that set of root certificates, and will fail if the validation attempt fails.

버전 2.7.9에서 변경: This function is now IPv6-compatible, and the default *ssl_version* is changed from `PROTOCOL_SSLv3` to `PROTOCOL_SSLv23` for maximum compatibility with modern servers.

`ssl.DER_cert_to_PEM_cert (DER_cert_bytes)`

Given a certificate as a DER-encoded blob of bytes, returns a PEM-encoded string version of the same certificate.

`ssl.PEM_cert_to_DER_cert (PEM_cert_string)`

Given a certificate as an ASCII PEM string, returns a DER-encoded sequence of bytes for that same certificate.

ssl.get_default_verify_paths()

Returns a named tuple with paths to OpenSSL's default cafile and capath. The paths are the same as used by `SSLContext.set_default_verify_paths()`. The return value is a *named tuple* `DefaultVerifyPaths`:

- `cafile` - resolved path to cafile or `None` if the file doesn't exist,
- `capath` - resolved path to capath or `None` if the directory doesn't exist,
- `openssl_cafile_env` - OpenSSL's environment key that points to a cafile,
- `openssl_cafile` - hard coded path to a cafile,
- `openssl_capath_env` - OpenSSL's environment key that points to a capath,
- `openssl_capath` - hard coded path to a capath directory

Availability: LibreSSL ignores the environment vars `openssl_cafile_env` and `openssl_capath_env` 버전 2.7.9에 추가.

ssl.enum_certificates(store_name)

Retrieve certificates from Windows' system cert store. `store_name` may be one of `CA`, `ROOT` or `MY`. Windows may provide additional cert stores, too.

The function returns a list of (cert_bytes, encoding_type, trust) tuples. The `encoding_type` specifies the encoding of `cert_bytes`. It is either `x509_asn` for X.509 ASN.1 data or `pkcs_7_asn` for PKCS#7 ASN.1 data. Trust specifies the purpose of the certificate as a set of OIDS or exactly `True` if the certificate is trustworthy for all purposes.

Example:

```
>>> ssl.enum_certificates("CA")
[(b'data...', 'x509_asn', {'1.3.6.1.5.5.7.3.1', '1.3.6.1.5.5.7.3.2'}),
 (b'data...', 'x509_asn', True)]
```

Availability: Windows.

버전 2.7.9에 추가.

ssl.enum_crls(store_name)

Retrieve CRLs from Windows' system cert store. `store_name` may be one of `CA`, `ROOT` or `MY`. Windows may provide additional cert stores, too.

The function returns a list of (cert_bytes, encoding_type, trust) tuples. The `encoding_type` specifies the encoding of `cert_bytes`. It is either `x509_asn` for X.509 ASN.1 data or `pkcs_7_asn` for PKCS#7 ASN.1 data.

Availability: Windows.

버전 2.7.9에 추가.

Constants

ssl.CERT_NONE

Possible value for `SSLContext.verify_mode`, or the `cert_reqs` parameter to `wrap_socket()`. In this mode (the default), no certificates will be required from the other side of the socket connection. If a certificate is received from the other end, no attempt to validate it is made.

See the discussion of *Security considerations* below.

ssl.CERT_OPTIONAL

Possible value for `SSLContext.verify_mode`, or the `cert_reqs` parameter to `wrap_socket()`. In

this mode no certificates will be required from the other side of the socket connection; but if they are provided, validation will be attempted and an *SSL**Error* will be raised on failure.

Use of this setting requires a valid set of CA certificates to be passed, either to *SSLContext.load_verify_locations()* or as a value of the *ca_certs* parameter to *wrap_socket()*.

ssl.CERT_REQUIRED

Possible value for *SSLContext.verify_mode*, or the *cert_reqs* parameter to *wrap_socket()*. In this mode, certificates are required from the other side of the socket connection; an *SSL**Error* will be raised if no certificate is provided, or if its validation fails.

Use of this setting requires a valid set of CA certificates to be passed, either to *SSLContext.load_verify_locations()* or as a value of the *ca_certs* parameter to *wrap_socket()*.

ssl.VERIFY_DEFAULT

Possible value for *SSLContext.verify_flags*. In this mode, certificate revocation lists (CRLs) are not checked. By default OpenSSL does neither require nor verify CRLs.

버전 2.7.9에 추가.

ssl.VERIFY_CRL_CHECK_LEAF

Possible value for *SSLContext.verify_flags*. In this mode, only the peer cert is check but non of the intermediate CA certificates. The mode requires a valid CRL that is signed by the peer cert's issuer (its direct ancestor CA). If no proper has been loaded *SSLContext.load_verify_locations*, validation will fail.

버전 2.7.9에 추가.

ssl.VERIFY_CRL_CHECK_CHAIN

Possible value for *SSLContext.verify_flags*. In this mode, CRLs of all certificates in the peer cert chain are checked.

버전 2.7.9에 추가.

ssl.VERIFY_X509_STRICT

Possible value for *SSLContext.verify_flags* to disable workarounds for broken X.509 certificates.

버전 2.7.9에 추가.

ssl.VERIFY_X509_TRUSTED_FIRST

Possible value for *SSLContext.verify_flags*. It instructs OpenSSL to prefer trusted certificates when building the trust chain to validate a certificate. This flag is enabled by default.

버전 2.7.10에 추가.

ssl.PROTOCOL_TLS

Selects the highest protocol version that both the client and server support. Despite the name, this option can select <TLS> protocols as well as <SSL>.

버전 2.7.13에 추가.

ssl.PROTOCOL_SSLv23

Alias for *PROTOCOL_TLS*.

버전 2.7.13부터 폐지: Use *PROTOCOL_TLS* instead.

ssl.PROTOCOL_SSLv2

Selects SSL version 2 as the channel encryption protocol.

This protocol is not available if OpenSSL is compiled with the *OPENSSL_NO_SSL2* flag.

경고: SSL version 2 is insecure. Its use is highly discouraged.

버전 2.7.13부터 폐지: OpenSSL has removed support for SSLv2.

`ssl.PROTOCOL_SSLv3`

Selects SSL version 3 as the channel encryption protocol.

This protocol is not be available if OpenSSL is compiled with the `OPENSSL_NO_SSLv3` flag.

경고: SSL version 3 is insecure. Its use is highly discouraged.

버전 2.7.13부터 폐지: OpenSSL has deprecated all version specific protocols. Use the default protocol with flags like `OP_NO_SSLv3` instead.

`ssl.PROTOCOL_TLSv1`

Selects TLS version 1.0 as the channel encryption protocol.

버전 2.7.13부터 폐지: OpenSSL has deprecated all version specific protocols. Use the default protocol with flags like `OP_NO_SSLv3` instead.

`ssl.PROTOCOL_TLSv1_1`

Selects TLS version 1.1 as the channel encryption protocol. Available only with openssl version 1.0.1+.

버전 2.7.9에 추가.

버전 2.7.13부터 폐지: OpenSSL has deprecated all version specific protocols. Use the default protocol with flags like `OP_NO_SSLv3` instead.

`ssl.PROTOCOL_TLSv1_2`

Selects TLS version 1.2 as the channel encryption protocol. This is the most modern version, and probably the best choice for maximum protection, if both sides can speak it. Available only with openssl version 1.0.1+.

버전 2.7.9에 추가.

버전 2.7.13부터 폐지: OpenSSL has deprecated all version specific protocols. Use the default protocol with flags like `OP_NO_SSLv3` instead.

`ssl.OP_ALL`

Enables workarounds for various bugs present in other SSL implementations. This option is set by default. It does not necessarily set the same flags as OpenSSL's `SSL_OP_ALL` constant.

버전 2.7.9에 추가.

`ssl.OP_NO_SSLv2`

Prevents an SSLv2 connection. This option is only applicable in conjunction with `PROTOCOL_SSLv23`. It prevents the peers from choosing SSLv2 as the protocol version.

버전 2.7.9에 추가.

`ssl.OP_NO_SSLv3`

Prevents an SSLv3 connection. This option is only applicable in conjunction with `PROTOCOL_SSLv23`. It prevents the peers from choosing SSLv3 as the protocol version.

버전 2.7.9에 추가.

`ssl.OP_NO_TLSv1`

Prevents a TLSv1 connection. This option is only applicable in conjunction with `PROTOCOL_SSLv23`. It prevents the peers from choosing TLSv1 as the protocol version.

버전 2.7.9에 추가.

`ssl.OP_NO_TLSv1_1`

Prevents a TLSv1.1 connection. This option is only applicable in conjunction with `PROTOCOL_SSLv23`. It prevents the peers from choosing TLSv1.1 as the protocol version. Available only with openssl version 1.0.1+.

버전 2.7.9에 추가.

ssl.OP_NO_TLSv1_2

Prevents a TLSv1.2 connection. This option is only applicable in conjunction with [PROTOCOL_SSLv23](#). It prevents the peers from choosing TLSv1.2 as the protocol version. Available only with openssl version 1.0.1+.

버전 2.7.9에 추가.

ssl.OP_NO_TLSv1_3

Prevents a TLSv1.3 connection. This option is only applicable in conjunction with [PROTOCOL_TLS](#). It prevents the peers from choosing TLSv1.3 as the protocol version. TLS 1.3 is available with OpenSSL 1.1.1 or later. When Python has been compiled against an older version of OpenSSL, the flag defaults to 0.

버전 2.7.15에 추가.

ssl.OP_CIPHER_SERVER_PREFERENCE

Use the server's cipher ordering preference, rather than the client's. This option has no effect on client sockets and SSLv2 server sockets.

버전 2.7.9에 추가.

ssl.OP_SINGLE_DH_USE

Prevents re-use of the same DH key for distinct SSL sessions. This improves forward secrecy but requires more computational resources. This option only applies to server sockets.

버전 2.7.9에 추가.

ssl.OP_SINGLE_ECDH_USE

Prevents re-use of the same ECDH key for distinct SSL sessions. This improves forward secrecy but requires more computational resources. This option only applies to server sockets.

버전 2.7.9에 추가.

ssl.OP_ENABLE_MIDDLEBOX_COMPAT

Send dummy Change Cipher Spec (CCS) messages in TLS 1.3 handshake to make a TLS 1.3 connection look more like a TLS 1.2 connection.

This option is only available with OpenSSL 1.1.1 and later.

버전 2.7.16에 추가.

ssl.OP_NO_COMPRESSION

Disable compression on the SSL channel. This is useful if the application protocol supports its own compression scheme.

This option is only available with OpenSSL 1.0.0 and later.

버전 2.7.9에 추가.

ssl.HAS_ALPN

Whether the OpenSSL library has built-in support for the *Application-Layer Protocol Negotiation* TLS extension as described in [RFC 7301](#).

버전 2.7.10에 추가.

ssl.HAS_ECDH

Whether the OpenSSL library has built-in support for Elliptic Curve-based Diffie-Hellman key exchange. This should be true unless the feature was explicitly disabled by the distributor.

버전 2.7.9에 추가.

ssl.HAS_SNI

Whether the OpenSSL library has built-in support for the *Server Name Indication* extension (as defined in [RFC 4366](#)).

버전 2.7.9에 추가.

`ssl.HAS_NPN`

Whether the OpenSSL library has built-in support for *Next Protocol Negotiation* as described in the [NPN draft specification](#). When true, you can use the `SSLContext.set_npn_protocols()` method to advertise which protocols you want to support.

버전 2.7.9에 추가.

`ssl.HAS_TLSv1_3`

Whether the OpenSSL library has built-in support for the TLS 1.3 protocol.

버전 2.7.15에 추가.

`ssl.CHANNEL_BINDING_TYPES`

List of supported TLS channel binding types. Strings in this list can be used as arguments to `SSLSocket.get_channel_binding()`.

버전 2.7.9에 추가.

`ssl.OPENSSSL_VERSION`

The version string of the OpenSSL library loaded by the interpreter:

```
>>> ssl.OPENSSSL_VERSION
'OpenSSL 0.9.8k 25 Mar 2009'
```

버전 2.7에 추가.

`ssl.OPENSSSL_VERSION_INFO`

A tuple of five integers representing version information about the OpenSSL library:

```
>>> ssl.OPENSSSL_VERSION_INFO
(0, 9, 8, 11, 15)
```

버전 2.7에 추가.

`ssl.OPENSSSL_VERSION_NUMBER`

The raw version number of the OpenSSL library, as a single integer:

```
>>> ssl.OPENSSSL_VERSION_NUMBER
9470143L
>>> hex(ssl.OPENSSSL_VERSION_NUMBER)
'0x9080bfL'
```

버전 2.7에 추가.

`ssl.ALERT_DESCRIPTION_HANDSHAKE_FAILURE`

`ssl.ALERT_DESCRIPTION_INTERNAL_ERROR`

`ALERT_DESCRIPTION_*`

Alert Descriptions from [RFC 5246](#) and others. The [IANA TLS Alert Registry](#) contains this list and references to the RFCs where their meaning is defined.

Used as the return value of the callback function in `SSLContext.set_servername_callback()`.

버전 2.7.9에 추가.

`Purpose.SERVER_AUTH`

Option for `create_default_context()` and `SSLContext.load_default_certs()`. This value indicates that the context may be used to authenticate Web servers (therefore, it will be used to create client-side sockets).

버전 2.7.9에 추가.

Purpose.CLIENT_AUTH

Option for `create_default_context()` and `SSLContext.load_default_certs()`. This value indicates that the context may be used to authenticate Web clients (therefore, it will be used to create server-side sockets).

버전 2.7.9에 추가.

17.3.2 SSL Sockets

SSL sockets provide the following methods of *Socket Objects*:

- `accept()`
- `bind()`
- `close()`
- `connect()`
- `fileno()`
- `getpeername()`, `getsockname()`
- `getsockopt()`, `setsockopt()`
- `gettimeout()`, `settimeout()`, `setblocking()`
- `listen()`
- `makefile()`
- `recv()`, `recv_into()` (but passing a non-zero flags argument is not allowed)
- `send()`, `sendall()` (with the same limitation)
- `shutdown()`

However, since the SSL (and TLS) protocol has its own framing atop of TCP, the SSL sockets abstraction can, in certain respects, diverge from the specification of normal, OS-level sockets. See especially the *notes on non-blocking sockets*.

SSL sockets also have the following additional methods and attributes:

SSLSocket.do_handshake()

Perform the SSL setup handshake.

버전 2.7.9에서 변경: The handshake method also performs `match_hostname()` when the `check_hostname` attribute of the socket's `context` is true.

SSLSocket.getpeercert(binary_form=False)

If there is no certificate for the peer on the other end of the connection, return `None`. If the SSL handshake hasn't been done yet, raise `ValueError`.

If the `binary_form` parameter is `False`, and a certificate was received from the peer, this method returns a `dict` instance. If the certificate was not validated, the dict is empty. If the certificate was validated, it returns a dict with several keys, amongst them `subject` (the principal for which the certificate was issued) and `issuer` (the principal issuing the certificate). If a certificate contains an instance of the *Subject Alternative Name* extension (see **RFC 3280**), there will also be a `subjectAltName` key in the dictionary.

The `subject` and `issuer` fields are tuples containing the sequence of relative distinguished names (RDNs) given in the certificate's data structure for the respective fields, and each RDN is a sequence of name-value pairs. Here is a real-world example:

```
{'issuer': (((('countryName', 'IL'),),
              (('organizationName', 'StartCom Ltd.'),),
              (('organizationalUnitName',
               'Secure Digital Certificate Signing'),),
              (('commonName',
               'StartCom Class 2 Primary Intermediate Server CA'),)),
 'notAfter': 'Nov 22 08:15:19 2013 GMT',
 'notBefore': 'Nov 21 03:09:52 2011 GMT',
 'serialNumber': '95F0',
 'subject': (((('description', '571208-SLe257oHY9fVQ07Z'),),
                (('countryName', 'US'),),
                (('stateOrProvinceName', 'California'),),
                (('localityName', 'San Francisco'),),
                (('organizationName', 'Electronic Frontier Foundation, Inc.'),),
                (('commonName', '*.eff.org'),),
                (('emailAddress', 'hostmaster@eff.org'),)),
 'subjectAltName': (('DNS', '*.eff.org'), ('DNS', 'eff.org')),
 'version': 3}
```

참고: To validate a certificate for a particular service, you can use the `match_hostname()` function.

If the `binary_form` parameter is `True`, and a certificate was provided, this method returns the DER-encoded form of the entire certificate as a sequence of bytes, or `None` if the peer did not provide a certificate. Whether the peer provides a certificate depends on the SSL socket's role:

- for a client SSL socket, the server will always provide a certificate, regardless of whether validation was required;
- for a server SSL socket, the client will only provide a certificate when requested by the server; therefore `getpeercert()` will return `None` if you used `CERT_NONE` (rather than `CERT_OPTIONAL` or `CERT_REQUIRED`).

버전 2.7.9에서 변경: The returned dictionary includes additional items such as `issuer` and `notBefore`. Additionally `ValueError` is raised when the handshake isn't done. The returned dictionary includes additional X509v3 extension items such as `crlDistributionPoints`, `caIssuers` and OCSP URIs.

`SSLSocket.cipher()`

Returns a three-value tuple containing the name of the cipher being used, the version of the SSL protocol that defines its use, and the number of secret bits being used. If no connection has been established, returns `None`.

`SSLSocket.compression()`

Return the compression algorithm being used as a string, or `None` if the connection isn't compressed.

If the higher-level protocol supports its own compression mechanism, you can use `OP_NO_COMPRESSION` to disable SSL-level compression.

버전 2.7.9에 추가.

`SSLSocket.get_channel_binding(cb_type="tls-unique")`

Get channel binding data for current connection, as a bytes object. Returns `None` if not connected or the handshake has not been completed.

The `cb_type` parameter allow selection of the desired channel binding type. Valid channel binding types are listed in the `CHANNEL_BINDING_TYPES` list. Currently only the `<tls-unique>` channel binding, defined by [RFC 5929](#), is supported. `ValueError` will be raised if an unsupported channel binding type is requested.

버전 2.7.9에 추가.

`SSLSocket.selected_alpn_protocol()`

Return the protocol that was selected during the TLS handshake. If `SSLContext.set_alpn_protocols()` was not called, if the other party does not support ALPN, if this socket does not support any of the client's proposed protocols, or if the handshake has not happened yet, `None` is returned.

버전 2.7.10에 추가.

`SSLSocket.selected_npn_protocol()`

Return the higher-level protocol that was selected during the TLS/SSL handshake. If `SSLContext.set_npn_protocols()` was not called, or if the other party does not support NPN, or if the handshake has not yet happened, this will return `None`.

버전 2.7.9에 추가.

`SSLSocket.unwrap()`

Performs the SSL shutdown handshake, which removes the TLS layer from the underlying socket, and returns the underlying socket object. This can be used to go from encrypted operation over a connection to unencrypted. The returned socket should always be used for further communication with the other side of the connection, rather than the original socket.

`SSLSocket.version()`

Return the actual SSL protocol version negotiated by the connection as a string, or `None` if no secure connection is established. As of this writing, possible return values include "SSLv2", "SSLv3", "TLSv1", "TLSv1.1" and "TLSv1.2". Recent OpenSSL versions may define more return values.

버전 2.7.9에 추가.

`SSLSocket.context`

The `SSLContext` object this SSL socket is tied to. If the SSL socket was created using the top-level `wrap_socket()` function (rather than `SSLContext.wrap_socket()`), this is a custom context object created for this SSL socket.

버전 2.7.9에 추가.

17.3.3 SSL Contexts

버전 2.7.9에 추가.

An SSL context holds various data longer-lived than single SSL connections, such as SSL configuration options, certificate(s) and private key(s). It also manages a cache of SSL sessions for server-side sockets, in order to speed up repeated connections from the same clients.

class `ssl.SSLContext` (*protocol*)

Create a new SSL context. You must pass *protocol* which must be one of the `PROTOCOL_*` constants defined in this module. `PROTOCOL_SSLv23` is currently recommended for maximum interoperability.

더 보기:

`create_default_context()` lets the `ssl` module choose security settings for a given purpose.

버전 2.7.16에서 변경: The context is created with secure default values. The options `OP_NO_COMPRESSION`, `OP_CIPHER_SERVER_PREFERENCE`, `OP_SINGLE_DH_USE`, `OP_SINGLE_ECDH_USE`, `OP_NO_SSLv2` (except for `PROTOCOL_SSLv2`), and `OP_NO_SSLv3` (except for `PROTOCOL_SSLv3`) are set by default. The initial cipher suite list contains only HIGH ciphers, no NULL ciphers and no MD5 ciphers (except for `PROTOCOL_SSLv2`).

`SSLContext` objects have the following methods and attributes:

`SSLContext.cert_store_stats()`

Get statistics about quantities of loaded X.509 certificates, count of X.509 certificates flagged as CA certificates and certificate revocation lists as dictionary.

Example for a context with one CA cert and one other cert:

```
>>> context.cert_store_stats()
{'crl': 0, 'x509_ca': 1, 'x509': 2}
```

`SSLContext.load_cert_chain(certfile, keyfile=None, password=None)`

Load a private key and the corresponding certificate. The *certfile* string must be the path to a single file in PEM format containing the certificate as well as any number of CA certificates needed to establish the certificate's authenticity. The *keyfile* string, if present, must point to a file containing the private key in. Otherwise the private key will be taken from *certfile* as well. See the discussion of [Certificates](#) for more information on how the certificate is stored in the *certfile*.

The *password* argument may be a function to call to get the password for decrypting the private key. It will only be called if the private key is encrypted and a password is necessary. It will be called with no arguments, and it should return a string, bytes, or bytearray. If the return value is a string it will be encoded as UTF-8 before using it to decrypt the key. Alternatively a string, bytes, or bytearray value may be supplied directly as the *password* argument. It will be ignored if the private key is not encrypted and no password is needed.

If the *password* argument is not specified and a password is required, OpenSSL's built-in password prompting mechanism will be used to interactively prompt the user for a password.

An [SSLError](#) is raised if the private key doesn't match with the certificate.

`SSLContext.load_default_certs(purpose=Purpose.SERVER_AUTH)`

Load a set of default «certification authority» (CA) certificates from default locations. On Windows it loads CA certs from the CA and ROOT system stores. On other systems it calls `SSLContext.set_default_verify_paths()`. In the future the method may load CA certificates from other locations, too.

The *purpose* flag specifies what kind of CA certificates are loaded. The default settings `Purpose.SERVER_AUTH` loads certificates, that are flagged and trusted for TLS web server authentication (client side sockets). `Purpose.CLIENT_AUTH` loads CA certificates for client certificate verification on the server side.

`SSLContext.load_verify_locations(cafile=None, capath=None, cadata=None)`

Load a set of «certification authority» (CA) certificates used to validate other peers' certificates when *verify_mode* is other than `CERT_NONE`. At least one of *cafile* or *capath* must be specified.

This method can also load certification revocation lists (CRLs) in PEM or DER format. In order to make use of CRLs, `SSLContext.verify_flags` must be configured properly.

The *cafile* string, if present, is the path to a file of concatenated CA certificates in PEM format. See the discussion of [Certificates](#) for more information about how to arrange the certificates in this file.

The *capath* string, if present, is the path to a directory containing several CA certificates in PEM format, following an [OpenSSL specific layout](#).

The *cadata* object, if present, is either an ASCII string of one or more PEM-encoded certificates or a bytes-like object of DER-encoded certificates. Like with *capath* extra lines around PEM-encoded certificates are ignored but at least one certificate must be present.

`SSLContext.get_ca_certs(binary_form=False)`

Get a list of loaded «certification authority» (CA) certificates. If the *binary_form* parameter is `False` each list entry is a dict like the output of `SSLSocket.getpeercert()`. Otherwise the method returns a list of DER-encoded certificates. The returned list does not contain certificates from *capath* unless a certificate was requested and loaded by a SSL connection.

참고: Certificates in a `capath` directory aren't loaded unless they have been used at least once.

`SSLContext.set_default_verify_paths()`

Load a set of default 《certification authority》(CA) certificates from a filesystem path defined when building the OpenSSL library. Unfortunately, there's no easy way to know whether this method succeeds: no error is returned if no certificates are to be found. When the OpenSSL library is provided as part of the operating system, though, it is likely to be configured properly.

`SSLContext.set_ciphers(ciphers)`

Set the available ciphers for sockets created with this context. It should be a string in the [OpenSSL cipher list format](#). If no cipher can be selected (because compile-time options or other configuration forbids use of all the specified ciphers), an `SSL_ERROR` will be raised.

참고: when connected, the `SSLSocket.cipher()` method of SSL sockets will give the currently selected cipher.

OpenSSL 1.1.1 has TLS 1.3 cipher suites enabled by default. The suites cannot be disabled with `set_ciphers()`.

`SSLContext.set_alpn_protocols(protocols)`

Specify which protocols the socket should advertise during the SSL/TLS handshake. It should be a list of ASCII strings, like `['http/1.1', 'spdy/2']`, ordered by preference. The selection of a protocol will happen during the handshake, and will play out according to [RFC 7301](#). After a successful handshake, the `SSLSocket.selected_alpn_protocol()` method will return the agreed-upon protocol.

This method will raise `NotImplementedError` if `HAS_ALPN` is False.

OpenSSL 1.1.0 to 1.1.0e will abort the handshake and raise `SSL_ERROR` when both sides support ALPN but cannot agree on a protocol. 1.1.0f+ behaves like 1.0.2, `SSLSocket.selected_alpn_protocol()` returns None.

버전 2.7.10에 추가.

`SSLContext.set_npn_protocols(protocols)`

Specify which protocols the socket should advertise during the SSL/TLS handshake. It should be a list of strings, like `['http/1.1', 'spdy/2']`, ordered by preference. The selection of a protocol will happen during the handshake, and will play out according to the [NPN draft specification](#). After a successful handshake, the `SSLSocket.selected_npn_protocol()` method will return the agreed-upon protocol.

This method will raise `NotImplementedError` if `HAS_NPN` is False.

`SSLContext.set_servername_callback(server_name_callback)`

Register a callback function that will be called after the TLS Client Hello handshake message has been received by the SSL/TLS server when the TLS client specifies a server name indication. The server name indication mechanism is specified in [RFC 6066](#) section 3 - Server Name Indication.

Only one callback can be set per `SSLContext`. If `server_name_callback` is None then the callback is disabled. Calling this function a subsequent time will disable the previously registered callback.

The callback function, `server_name_callback`, will be called with three arguments; the first being the `ssl.SSLSocket`, the second is a string that represents the server name that the client is intending to communicate (or None if the TLS Client Hello does not contain a server name) and the third argument is the original `SSLContext`. The server name argument is the IDNA decoded server name.

A typical use of this callback is to change the `ssl.SSLSocket`'s `SSLSocket.context` attribute to a new object of type `SSLContext` representing a certificate chain that matches the server name.

Due to the early negotiation phase of the TLS connection, only limited methods and attributes are usable like `SSLSocket.selected_alpn_protocol()` and `SSLSocket.context`. `SSLSocket.getpeercert()`, `SSLSocket.getpeercert()`, `SSLSocket.cipher()` and `SSLSocket.compress()` methods require that the TLS connection has progressed beyond the TLS Client Hello and therefore will not contain return meaningful values nor can they be called safely.

The `server_name_callback` function must return `None` to allow the TLS negotiation to continue. If a TLS failure is required, a constant `ALERT_DESCRIPTION_*` can be returned. Other return values will result in a TLS fatal error with `ALERT_DESCRIPTION_INTERNAL_ERROR`.

If there is an IDNA decoding error on the server name, the TLS connection will terminate with an `ALERT_DESCRIPTION_INTERNAL_ERROR` fatal TLS alert message to the client.

If an exception is raised from the `server_name_callback` function the TLS connection will terminate with a fatal TLS alert message `ALERT_DESCRIPTION_HANDSHAKE_FAILURE`.

This method will raise `NotImplementedError` if the OpenSSL library had `OPENSSL_NO_TLSEXT` defined when it was built.

`SSLContext.load_dh_params(dhfile)`

Load the key generation parameters for Diffie-Helman (DH) key exchange. Using DH key exchange improves forward secrecy at the expense of computational resources (both on the server and on the client). The `dhfile` parameter should be the path to a file containing DH parameters in PEM format.

This setting doesn't apply to client sockets. You can also use the `OP_SINGLE_DH_USE` option to further improve security.

`SSLContext.set_ecdh_curve(curve_name)`

Set the curve name for Elliptic Curve-based Diffie-Hellman (ECDH) key exchange. ECDH is significantly faster than regular DH while arguably as secure. The `curve_name` parameter should be a string describing a well-known elliptic curve, for example `prime256v1` for a widely supported curve.

This setting doesn't apply to client sockets. You can also use the `OP_SINGLE_ECDH_USE` option to further improve security.

This method is not available if `HAS_ECDH` is `False`.

더 보기:

SSL/TLS & Perfect Forward Secrecy Vincent Bernat.

`SSLContext.wrap_socket(sock, server_side=False, do_handshake_on_connect=True, suppress_ragged_eofs=True, server_hostname=None)`

Wrap an existing Python socket `sock` and return an `SSLSocket` object. `sock` must be a `SOCK_STREAM` socket; other socket types are unsupported.

The returned SSL socket is tied to the context, its settings and certificates. The parameters `server_side`, `do_handshake_on_connect` and `suppress_ragged_eofs` have the same meaning as in the top-level `wrap_socket()` function.

On client connections, the optional parameter `server_hostname` specifies the hostname of the service which we are connecting to. This allows a single server to host multiple SSL-based services with distinct certificates, quite similarly to HTTP virtual hosts. Specifying `server_hostname` will raise a `ValueError` if `server_side` is true.

버전 2.7.9에서 변경: Always allow a `server_hostname` to be passed, even if OpenSSL does not have SNI.

`SSLContext.session_stats()`

Get statistics about the SSL sessions created or managed by this context. A dictionary is returned which maps the names of each `piece of information` to their numeric values. For example, here is the total number of hits and misses in the session cache since the context was created:

```
>>> stats = context.session_stats()
>>> stats['hits'], stats['misses']
(0, 0)
```

SSLContext.check_hostname

Whether to match the peer cert's hostname with `match_hostname()` in `SSLSocket.do_handshake()`. The context's `verify_mode` must be set to `CERT_OPTIONAL` or `CERT_REQUIRED`, and you must pass `server_hostname` to `wrap_socket()` in order to match the hostname.

Example:

```
import socket, ssl

context = ssl.SSLContext(ssl.PROTOCOL_TLS)
context.verify_mode = ssl.CERT_REQUIRED
context.check_hostname = True
context.load_default_certs()

s = socket.socket(socket.AF_INET, socket.SOCK_STREAM)
ssl_sock = context.wrap_socket(s, server_hostname='www.verisign.com')
ssl_sock.connect(('www.verisign.com', 443))
```

참고: This features requires OpenSSL 0.9.8f or newer.

SSLContext.options

An integer representing the set of SSL options enabled on this context. The default value is `OP_ALL`, but you can specify other options such as `OP_NO_SSLv2` by ORing them together.

참고: With versions of OpenSSL older than 0.9.8m, it is only possible to set options, not to clear them. Attempting to clear an option (by resetting the corresponding bits) will raise a `ValueError`.

SSLContext.protocol

The protocol version chosen when constructing the context. This attribute is read-only.

SSLContext.verify_flags

The flags for certificate verification operations. You can set flags like `VERIFY_CRL_CHECK_LEAF` by ORing them together. By default OpenSSL does neither require nor verify certificate revocation lists (CRLs). Available only with openssl version 0.9.8+.

SSLContext.verify_mode

Whether to try to verify other peers' certificates and how to behave if verification fails. This attribute must be one of `CERT_NONE`, `CERT_OPTIONAL` or `CERT_REQUIRED`.

17.3.4 Certificates

Certificates in general are part of a public-key / private-key system. In this system, each *principal*, (which may be a machine, or a person, or an organization) is assigned a unique two-part encryption key. One part of the key is public, and is called the *public key*; the other part is kept secret, and is called the *private key*. The two parts are related, in that if you encrypt a message with one of the parts, you can decrypt it with the other part, and **only** with the other part.

A certificate contains information about two principals. It contains the name of a *subject*, and the subject's public key. It also contains a statement by a second principal, the *issuer*, that the subject is who they claim to be, and that this is indeed the subject's public key. The issuer's statement is signed with the issuer's private key, which only the issuer knows.

However, anyone can verify the issuer's statement by finding the issuer's public key, decrypting the statement with it, and comparing it to the other information in the certificate. The certificate also contains information about the time period over which it is valid. This is expressed as two fields, called `notBefore` and `notAfter`.

In the Python use of certificates, a client or server can use a certificate to prove who they are. The other side of a network connection can also be required to produce a certificate, and that certificate can be validated to the satisfaction of the client or server that requires such validation. The connection attempt can be set to raise an exception if the validation fails. Validation is done automatically, by the underlying OpenSSL framework; the application need not concern itself with its mechanics. But the application does usually need to provide sets of certificates to allow this process to take place.

Python uses files to contain certificates. They should be formatted as `PEM` (see [RFC 1422](#)), which is a base-64 encoded form wrapped with a header line and a footer line:

```
-----BEGIN CERTIFICATE-----
... (certificate in base64 PEM encoding) ...
-----END CERTIFICATE-----
```

Certificate chains

The Python files which contain certificates can contain a sequence of certificates, sometimes called a *certificate chain*. This chain should start with the specific certificate for the principal who `is` the client or server, and then the certificate for the issuer of that certificate, and then the certificate for the issuer of *that* certificate, and so on up the chain till you get to a certificate which is *self-signed*, that is, a certificate which has the same subject and issuer, sometimes called a *root certificate*. The certificates should just be concatenated together in the certificate file. For example, suppose we had a three certificate chain, from our server certificate to the certificate of the certification authority that signed our server certificate, to the root certificate of the agency which issued the certification authority's certificate:

```
-----BEGIN CERTIFICATE-----
... (certificate for your server)...
-----END CERTIFICATE-----
-----BEGIN CERTIFICATE-----
... (the certificate for the CA)...
-----END CERTIFICATE-----
-----BEGIN CERTIFICATE-----
... (the root certificate for the CA's issuer)...
-----END CERTIFICATE-----
```

CA certificates

If you are going to require validation of the other side of the connection's certificate, you need to provide a 《CA certs》 file, filled with the certificate chains for each issuer you are willing to trust. Again, this file just contains these chains concatenated together. For validation, Python will use the first chain it finds in the file which matches. The platform's certificates file can be used by calling `SSLContext.load_default_certs()`, this is done automatically with `create_default_context()`.

Combined key and certificate

Often the private key is stored in the same file as the certificate; in this case, only the `certfile` parameter to `SSLContext.load_cert_chain()` and `wrap_socket()` needs to be passed. If the private key is stored with the certificate, it should come before the first certificate in the certificate chain:

```
-----BEGIN RSA PRIVATE KEY-----
... (private key in base64 encoding) ...
-----END RSA PRIVATE KEY-----
-----BEGIN CERTIFICATE-----
... (certificate in base64 PEM encoding) ...
-----END CERTIFICATE-----
```

Self-signed certificates

If you are going to create a server that provides SSL-encrypted connection services, you will need to acquire a certificate for that service. There are many ways of acquiring appropriate certificates, such as buying one from a certification authority. Another common practice is to generate a self-signed certificate. The simplest way to do this is with the OpenSSL package, using something like the following:

```
% openssl req -new -x509 -days 365 -nodes -out cert.pem -keyout cert.pem
Generating a 1024 bit RSA private key
.....++++++
.....++++++
writing new private key to 'cert.pem'
-----
You are about to be asked to enter information that will be incorporated
into your certificate request.
What you are about to enter is what is called a Distinguished Name or a DN.
There are quite a few fields but you can leave some blank
For some fields there will be a default value,
If you enter '.', the field will be left blank.
-----
Country Name (2 letter code) [AU]:US
State or Province Name (full name) [Some-State]:MyState
Locality Name (eg, city) []:Some City
Organization Name (eg, company) [Internet Widgits Pty Ltd]:My Organization, Inc.
Organizational Unit Name (eg, section) []:My Group
Common Name (eg, YOUR name) []:myserver.mygroup.myorganization.com
Email Address []:ops@myserver.mygroup.myorganization.com
%
```

The disadvantage of a self-signed certificate is that it is its own root certificate, and no one else will have it in their cache of known (and trusted) root certificates.

17.3.5 Examples

Testing for SSL support

To test for the presence of SSL support in a Python installation, user code should use the following idiom:

```
try:
    import ssl
except ImportError:
    pass
else:
    ... # do something that requires SSL support
```

Client-side operation

This example creates a SSL context with the recommended security settings for client sockets, including automatic certificate verification:

```
>>> context = ssl.create_default_context()
```

If you prefer to tune security settings yourself, you might create a context from scratch (but beware that you might not get the settings right):

```
>>> context = ssl.SSLContext(ssl.PROTOCOL_TLS)
>>> context.verify_mode = ssl.CERT_REQUIRED
>>> context.check_hostname = True
>>> context.load_verify_locations("/etc/ssl/certs/ca-bundle.crt")
```

(this snippet assumes your operating system places a bundle of all CA certificates in `/etc/ssl/certs/ca-bundle.crt`; if not, you'll get an error and have to adjust the location)

When you use the context to connect to a server, `CERT_REQUIRED` validates the server certificate: it ensures that the server certificate was signed with one of the CA certificates, and checks the signature for correctness:

```
>>> conn = context.wrap_socket(socket.socket(socket.AF_INET),
...                             server_hostname="www.python.org")
>>> conn.connect(("www.python.org", 443))
```

You may then fetch the certificate:

```
>>> cert = conn.getpeercert()
```

Visual inspection shows that the certificate does identify the desired service (that is, the HTTPS host `www.python.org`):

```
>>> pprint.pprint(cert)
{'OCSP': ('http://ocsp.digicert.com',),
 'caIssuers': ('http://cacerts.digicert.com/DigiCertSHA2ExtendedValidationServerCA.crt',),
 'crlDistributionPoints': ('http://crl3.digicert.com/sha2-ev-server-g1.crl',
                           'http://crl4.digicert.com/sha2-ev-server-g1.crl'),
 'issuer': (((('countryName', 'US'),),
               (('organizationName', 'DigiCert Inc'),),
               (('organizationalUnitName', 'www.digicert.com'),),
               (('commonName', 'DigiCert SHA2 Extended Validation Server CA'),)),
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
'notAfter': 'Sep  9 12:00:00 2016 GMT',
'notBefore': 'Sep  5 00:00:00 2014 GMT',
'serialNumber': '01BB6F00122B177F36CAB49CEA8B6B26',
'subject': (((('businessCategory', 'Private Organization'),),
              (('1.3.6.1.4.1.311.60.2.1.3', 'US'),),
              (('1.3.6.1.4.1.311.60.2.1.2', 'Delaware'),),
              (('serialNumber', '3359300'),),
              (('streetAddress', '16 Allen Rd'),),
              (('postalCode', '03894-4801'),),
              (('countryName', 'US'),),
              (('stateOrProvinceName', 'NH'),),
              (('localityName', 'Wolfeboro,'),),
              (('organizationName', 'Python Software Foundation'),),
              (('commonName', 'www.python.org'),)),
'subjectAltName': (('DNS', 'www.python.org'),
                  ('DNS', 'python.org'),
                  ('DNS', 'pypi.org'),
                  ('DNS', 'docs.python.org'),
                  ('DNS', 'testpypi.python.org'),
                  ('DNS', 'bugs.python.org'),
                  ('DNS', 'wiki.python.org'),
                  ('DNS', 'hg.python.org'),
                  ('DNS', 'mail.python.org'),
                  ('DNS', 'packaging.python.org'),
                  ('DNS', 'pythonhosted.org'),
                  ('DNS', 'www.pythonhosted.org'),
                  ('DNS', 'test.pythonhosted.org'),
                  ('DNS', 'us.pycon.org'),
                  ('DNS', 'id.python.org')),
'version': 3}
```

Now the SSL channel is established and the certificate verified, you can proceed to talk with the server:

```
>>> conn.sendall(b"HEAD / HTTP/1.0\r\nHost: linuxfr.org\r\n\r\n")
>>> pprint.pprint(conn.recv(1024).split(b"\r\n"))
[b'HTTP/1.1 200 OK',
 b'Date: Sat, 18 Oct 2014 18:27:20 GMT',
 b'Server: nginx',
 b'Content-Type: text/html; charset=utf-8',
 b'X-Frame-Options: SAMEORIGIN',
 b'Content-Length: 45679',
 b'Accept-Ranges: bytes',
 b'Via: 1.1 varnish',
 b'Age: 2188',
 b'X-Served-By: cache-lcy1134-LCY',
 b'X-Cache: HIT',
 b'X-Cache-Hits: 11',
 b'Vary: Cookie',
 b'Strict-Transport-Security: max-age=63072000; includeSubDomains',
 b'Connection: close',
 b'',
 b'']
```

See the discussion of *Security considerations* below.

Server-side operation

For server operation, typically you'll need to have a server certificate, and private key, each in a file. You'll first create a context holding the key and the certificate, so that clients can check your authenticity. Then you'll open a socket, bind it to a port, call `listen()` on it, and start waiting for clients to connect:

```
import socket, ssl

context = ssl.create_default_context(ssl.Purpose.CLIENT_AUTH)
context.load_cert_chain(certfile="mycertfile", keyfile="mykeyfile")

bindsocket = socket.socket()
bindsocket.bind(('myaddr.mydomain.com', 10023))
bindsocket.listen(5)
```

When a client connects, you'll call `accept()` on the socket to get the new socket from the other end, and use the context's `SSLContext.wrap_socket()` method to create a server-side SSL socket for the connection:

```
while True:
    newsocket, fromaddr = bindsocket.accept()
    connstream = context.wrap_socket(newsocket, server_side=True)
    try:
        deal_with_client(connstream)
    finally:
        connstream.shutdown(socket.SHUT_RDWR)
        connstream.close()
```

Then you'll read data from the `connstream` and do something with it till you are finished with the client (or the client is finished with you):

```
def deal_with_client(connstream):
    data = connstream.read()
    # null data means the client is finished with us
    while data:
        if not do_something(connstream, data):
            # we'll assume do_something returns False
            # when we're finished with client
            break
        data = connstream.read()
    # finished with client
```

And go back to listening for new client connections (of course, a real server would probably handle each client connection in a separate thread, or put the sockets in non-blocking mode and use an event loop).

17.3.6 Notes on non-blocking sockets

When working with non-blocking sockets, there are several things you need to be aware of:

- Calling `select()` tells you that the OS-level socket can be read from (or written to), but it does not imply that there is sufficient data at the upper SSL layer. For example, only part of an SSL frame might have arrived. Therefore, you must be ready to handle `SSLSocket.recv()` and `SSLSocket.send()` failures, and retry after another call to `select()`.
- Conversely, since the SSL layer has its own framing, a SSL socket may still have data available for reading without `select()` being aware of it. Therefore, you should first call `SSLSocket.recv()` to drain any potentially available data, and then only block on a `select()` call if still necessary.

(of course, similar provisions apply when using other primitives such as `poll()`, or those in the `selectors` module)

- The SSL handshake itself will be non-blocking: the `SSLSocket.do_handshake()` method has to be retried until it returns successfully. Here is a synopsis using `select()` to wait for the socket's readiness:

```
while True:
    try:
        sock.do_handshake()
        break
    except ssl.SSLWantReadError:
        select.select([sock], [], [])
    except ssl.SSLWantWriteError:
        select.select([], [sock], [])
```

17.3.7 Security considerations

Best defaults

For **client use**, if you don't have any special requirements for your security policy, it is highly recommended that you use the `create_default_context()` function to create your SSL context. It will load the system's trusted CA certificates, enable certificate validation and hostname checking, and try to choose reasonably secure protocol and cipher settings.

If a client certificate is needed for the connection, it can be added with `SSLContext.load_cert_chain()`.

By contrast, if you create the SSL context by calling the `SSLContext` constructor yourself, it will not have certificate validation nor hostname checking enabled by default. If you do so, please read the paragraphs below to achieve a good security level.

Manual settings

Verifying certificates

When calling the `SSLContext` constructor directly, `CERT_NONE` is the default. Since it does not authenticate the other peer, it can be insecure, especially in client mode where most of time you would like to ensure the authenticity of the server you're talking to. Therefore, when in client mode, it is highly recommended to use `CERT_REQUIRED`. However, it is in itself not sufficient; you also have to check that the server certificate, which can be obtained by calling `SSLSocket.getpeercert()`, matches the desired service. For many protocols and applications, the service can be identified by the hostname; in this case, the `match_hostname()` function can be used. This common check is automatically performed when `SSLContext.check_hostname` is enabled.

In server mode, if you want to authenticate your clients using the SSL layer (rather than using a higher-level authentication mechanism), you'll also have to specify `CERT_REQUIRED` and similarly check the client certificate.

참고: In client mode, `CERT_OPTIONAL` and `CERT_REQUIRED` are equivalent unless anonymous ciphers are enabled (they are disabled by default).

Protocol versions

SSL versions 2 and 3 are considered insecure and are therefore dangerous to use. If you want maximum compatibility between clients and servers, it is recommended to use `PROTOCOL_SSLv23` as the protocol version and then disable SSLv2 and SSLv3 explicitly using the `SSLContext.options` attribute:

```
context = ssl.SSLContext(ssl.PROTOCOL_SSLv23)
context.options |= ssl.OP_NO_SSLv2
context.options |= ssl.OP_NO_SSLv3
```

The SSL context created above will only allow TLSv1 and later (if supported by your system) connections.

Cipher selection

If you have advanced security requirements, fine-tuning of the ciphers enabled when negotiating a SSL session is possible through the `SSLContext.set_ciphers()` method. Starting from Python 2.7.9, the `ssl` module disables certain weak ciphers by default, but you may want to further restrict the cipher choice. Be sure to read OpenSSL's documentation about the [cipher list format](#). If you want to check which ciphers are enabled by a given cipher list, use the `openssl ciphers` command on your system.

Multi-processing

If using this module as part of a multi-processed application (using, for example the `multiprocessing` or `concurrent.futures` modules), be aware that OpenSSL's internal random number generator does not properly handle forked processes. Applications must change the PRNG state of the parent process if they use any SSL feature with `os.fork()`. Any successful call of `RAND_add()`, `RAND_bytes()` or `RAND_pseudo_bytes()` is sufficient.

17.3.8 LibreSSL support

LibreSSL is a fork of OpenSSL 1.0.1. The `ssl` module has limited support for LibreSSL. Some features are not available when the `ssl` module is compiled with LibreSSL.

- LibreSSL >= 2.6.1 no longer supports NPN. The methods `SSLContext.set_npn_protocols()` and `SSLSocket.selected_npn_protocol()` are not available.
- `SSLContext.set_default_verify_paths()` ignores the env vars `SSL_CERT_FILE` and `SSL_CERT_PATH` although `get_default_verify_paths()` still reports them.

더 보기:

Class `socket.socket` Documentation of underlying `socket` class

SSL/TLS Strong Encryption: An Introduction Intro from the Apache webserver documentation

RFC 1422: Privacy Enhancement for Internet Electronic Mail: Part II: Certificate-Based Key Management
Steve Kent

RFC 1750: Randomness Recommendations for Security D. Eastlake et. al.

RFC 3280: Internet X.509 Public Key Infrastructure Certificate and CRL Profile Housley et. al.

RFC 4366: Transport Layer Security (TLS) Extensions Blake-Wilson et. al.

RFC 5246: The Transport Layer Security (TLS) Protocol Version 1.2 T. Dierks et. al.

RFC 6066: Transport Layer Security (TLS) Extensions D. Eastlake

IANA TLS: Transport Layer Security (TLS) Parameters IANA

RFC 7525: Recommendations for Secure Use of Transport Layer Security (TLS) and Datagram Transport Layer Security (DTLS) IETF

Mozilla's Server Side TLS recommendations Mozilla

17.4 `signal` — Set handlers for asynchronous events

This module provides mechanisms to use signal handlers in Python. Some general rules for working with signals and their handlers:

- A handler for a particular signal, once set, remains installed until it is explicitly reset (Python emulates the BSD style interface regardless of the underlying implementation), with the exception of the handler for `SIGCHLD`, which follows the underlying implementation.
- There is no way to «block» signals temporarily from critical sections (since this is not supported by all Unix flavors).
- Although Python signal handlers are called asynchronously as far as the Python user is concerned, they can only occur between the «atomic» instructions of the Python interpreter. This means that signals arriving during long calculations implemented purely in C (such as regular expression matches on large bodies of text) may be delayed for an arbitrary amount of time.
- When a signal arrives during an I/O operation, it is possible that the I/O operation raises an exception after the signal handler returns. This is dependent on the underlying Unix system's semantics regarding interrupted system calls.
- Because the C signal handler always returns, it makes little sense to catch synchronous errors like `SIGFPE` or `SIGSEGV`.
- Python installs a small number of signal handlers by default: `SIGPIPE` is ignored (so write errors on pipes and sockets can be reported as ordinary Python exceptions) and `SIGINT` is translated into a `KeyboardInterrupt` exception. All of these can be overridden.
- Some care must be taken if both signals and threads are used in the same program. The fundamental thing to remember in using signals and threads simultaneously is: always perform `signal()` operations in the main thread of execution. Any thread can perform an `alarm()`, `getsignal()`, `pause()`, `setitimer()` or `getitimer()`; only the main thread can set a new signal handler, and the main thread will be the only one to receive signals (this is enforced by the Python `signal` module, even if the underlying thread implementation supports sending signals to individual threads). This means that signals can't be used as a means of inter-thread communication. Use locks instead.

The variables defined in the `signal` module are:

`signal.SIG_DFL`

This is one of two standard signal handling options; it will simply perform the default function for the signal. For example, on most systems the default action for `SIGQUIT` is to dump core and exit, while the default action for `SIGCHLD` is to simply ignore it.

`signal.SIG_IGN`

This is another standard signal handler, which will simply ignore the given signal.

SIG*

All the signal numbers are defined symbolically. For example, the hangup signal is defined as `signal.SIGHUP`; the variable names are identical to the names used in C programs, as found in `<signal.h>`. The Unix man page for `<signal()>` lists the existing signals (on some systems this is `signal(2)`, on others the list is in `signal(7)`). Note that not all systems define the same set of signal names; only those names defined by the system are defined by this module.

signal.CTRL_C_EVENT

The signal corresponding to the Ctrl+C keystroke event. This signal can only be used with `os.kill()`.

Availability: Windows.

버전 2.7에 추가.

signal.CTRL_BREAK_EVENT

The signal corresponding to the Ctrl+Break keystroke event. This signal can only be used with `os.kill()`.

Availability: Windows.

버전 2.7에 추가.

signal.NSIG

One more than the number of the highest signal number.

signal.ITIMER_REAL

Decrements interval timer in real time, and delivers SIGALRM upon expiration.

signal.ITIMER_VIRTUAL

Decrements interval timer only when the process is executing, and delivers SIGVTALRM upon expiration.

signal.ITIMER_PROF

Decrements interval timer both when the process executes and when the system is executing on behalf of the process. Coupled with ITIMER_VIRTUAL, this timer is usually used to profile the time spent by the application in user and kernel space. SIGPROF is delivered upon expiration.

The `signal` module defines one exception:

exception signal.ItimerError

Raised to signal an error from the underlying `setitimer()` or `getitimer()` implementation. Expect this error if an invalid interval timer or a negative time is passed to `setitimer()`. This error is a subtype of `IOError`.

The `signal` module defines the following functions:

signal.alarm(*time*)

If *time* is non-zero, this function requests that a SIGALRM signal be sent to the process in *time* seconds. Any previously scheduled alarm is canceled (only one alarm can be scheduled at any time). The returned value is then the number of seconds before any previously set alarm was to have been delivered. If *time* is zero, no alarm is scheduled, and any scheduled alarm is canceled. If the return value is zero, no alarm is currently scheduled. (See the Unix man page `alarm(2)`.) Availability: Unix.

signal.getsignal(*signalnum*)

Return the current signal handler for the signal *signalnum*. The returned value may be a callable Python object, or one of the special values `signal.SIG_IGN`, `signal.SIG_DFL` or `None`. Here, `signal.SIG_IGN` means that the signal was previously ignored, `signal.SIG_DFL` means that the default way of handling the signal was previously in use, and `None` means that the previous signal handler was not installed from Python.

signal.pause()

Cause the process to sleep until a signal is received; the appropriate handler will then be called. Returns nothing. Not on Windows. (See the Unix man page `signal(2)`.)

signal.setitimer(*which*, *seconds*[, *interval*])

Sets given interval timer (one of `signal.ITIMER_REAL`, `signal.ITIMER_VIRTUAL` or `signal.ITIMER_PROF`) specified by *which* to fire after *seconds* (float is accepted, different from `alarm()`) and after that every *interval* seconds. The interval timer specified by *which* can be cleared by setting *seconds* to zero.

When an interval timer fires, a signal is sent to the process. The signal sent is dependent on the timer being used; `signal.ITIMER_REAL` will deliver SIGALRM, `signal.ITIMER_VIRTUAL` sends SIGVTALRM, and `signal.ITIMER_PROF` will deliver SIGPROF.

The old values are returned as a tuple: (delay, interval).

Attempting to pass an invalid interval timer will cause an `ItimerError`. Availability: Unix.

버전 2.6에 추가.

`signal.getitimer` (*which*)

Returns current value of a given interval timer specified by *which*. Availability: Unix.

버전 2.6에 추가.

`signal.set_wakeup_fd` (*fd*)

Set the wakeup fd to *fd*. When a signal is received, a `'\0'` byte is written to the fd. This can be used by a library to wakeup a poll or select call, allowing the signal to be fully processed.

The old wakeup fd is returned (or -1 if file descriptor wakeup was not enabled). If *fd* is -1, file descriptor wakeup is disabled. If not -1, *fd* must be non-blocking. It is up to the library to remove any bytes from *fd* before calling poll or select again.

When threads are enabled, this function can only be called from the main thread; attempting to call it from other threads will cause a `ValueError` exception to be raised.

버전 2.6에 추가.

`signal.siginterrupt` (*signalnum*, *flag*)

Change system call restart behaviour: if *flag* is `False`, system calls will be restarted when interrupted by signal *signalnum*, otherwise system calls will be interrupted. Returns nothing. Availability: Unix (see the man page `siginterrupt(3)` for further information).

Note that installing a signal handler with `signal()` will reset the restart behaviour to interruptible by implicitly calling `siginterrupt()` with a true *flag* value for the given signal.

버전 2.6에 추가.

`signal.signal` (*signalnum*, *handler*)

Set the handler for signal *signalnum* to the function *handler*. *handler* can be a callable Python object taking two arguments (see below), or one of the special values `signal.SIG_IGN` or `signal.SIG_DFL`. The previous signal handler will be returned (see the description of `getsignal()` above). (See the Unix man page `signal(2)`.)

When threads are enabled, this function can only be called from the main thread; attempting to call it from other threads will cause a `ValueError` exception to be raised.

The *handler* is called with two arguments: the signal number and the current stack frame (`None` or a frame object; for a description of frame objects, see the description in the type hierarchy or see the attribute descriptions in the `inspect` module).

On Windows, `signal()` can only be called with `SIGABRT`, `SIGFPE`, `SIGILL`, `SIGINT`, `SIGSEGV`, or `SIGTERM`. A `ValueError` will be raised in any other case.

17.4.1 Example

Here is a minimal example program. It uses the `alarm()` function to limit the time spent waiting to open a file; this is useful if the file is for a serial device that may not be turned on, which would normally cause the `os.open()` to hang indefinitely. The solution is to set a 5-second alarm before opening the file; if the operation takes too long, the alarm signal will be sent, and the handler raises an exception.

```
import signal, os

def handler(signum, frame):
    print 'Signal handler called with signal', signum
    raise IOError("Couldn't open device!")
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
# Set the signal handler and a 5-second alarm
signal.signal(signal.SIGALRM, handler)
signal.alarm(5)

# This open() may hang indefinitely
fd = os.open('/dev/ttyS0', os.O_RDWR)

signal.alarm(0)          # Disable the alarm
```

17.5 popen2 — Subprocesses with accessible I/O streams

버전 2.6부터 폐지: This module is obsolete. Use the *subprocess* module. Check especially the *Replacing Older Functions with the subprocess Module* section.

This module allows you to spawn processes and connect to their input/output/error pipes and obtain their return codes under Unix and Windows.

The *subprocess* module provides more powerful facilities for spawning new processes and retrieving their results. Using the *subprocess* module is preferable to using the *popen2* module.

The primary interface offered by this module is a trio of factory functions. For each of these, if *bufsize* is specified, it specifies the buffer size for the I/O pipes. *mode*, if provided, should be the string 'b' or 't'; on Windows this is needed to determine whether the file objects should be opened in binary or text mode. The default value for *mode* is 't'.

On Unix, *cmd* may be a sequence, in which case arguments will be passed directly to the program without shell intervention (as with *os.spawnv()*). If *cmd* is a string it will be passed to the shell (as with *os.system()*).

The only way to retrieve the return codes for the child processes is by using the *poll()* or *wait()* methods on the *Popen3* and *Popen4* classes; these are only available on Unix. This information is not available when using the *popen2()*, *popen3()*, and *popen4()* functions, or the equivalent functions in the *os* module. (Note that the tuples returned by the *os* module's functions are in a different order from the ones returned by the *popen2* module.)

`popen2.popen2(cmd[, bufsize[, mode]])`

Executes *cmd* as a sub-process. Returns the file objects (*child_stdout*, *child_stdin*).

`popen2.popen3(cmd[, bufsize[, mode]])`

Executes *cmd* as a sub-process. Returns the file objects (*child_stdout*, *child_stdin*, *child_stderr*).

`popen2.popen4(cmd[, bufsize[, mode]])`

Executes *cmd* as a sub-process. Returns the file objects (*child_stdout_and_stderr*, *child_stdin*).

버전 2.0에 추가.

On Unix, a class defining the objects returned by the factory functions is also available. These are not used for the Windows implementation, and are not available on that platform.

`class popen2.Popen3(cmd[, capturestderr[, bufsize]])`

This class represents a child process. Normally, *Popen3* instances are created using the *popen2()* and *popen3()* factory functions described above.

If not using one of the helper functions to create *Popen3* objects, the parameter *cmd* is the shell command to execute in a sub-process. The *capturestderr* flag, if true, specifies that the object should capture standard error output of the child process. The default is false. If the *bufsize* parameter is specified, it specifies the size of the I/O buffers to/from the child process.

class `popen2.Popen4` (*cmd* [, *bufsize*])

Similar to `Popen3`, but always captures standard error into the same file object as standard output. These are typically created using `popen4()`.

버전 2.0에 추가.

17.5.1 Popen3 and Popen4 Objects

Instances of the `Popen3` and `Popen4` classes have the following methods:

`Popen3.poll()`

Returns `-1` if child process hasn't completed yet, or its status code (see `wait()`) otherwise.

`Popen3.wait()`

Waits for and returns the status code of the child process. The status code encodes both the return code of the process and information about whether it exited using the `exit()` system call or died due to a signal. Functions to help interpret the status code are defined in the `os` module; see section *Process Management* for the `W*` () family of functions.

The following attributes are also available:

`Popen3.fromchild`

A file object that provides output from the child process. For `Popen4` instances, this will provide both the standard output and standard error streams.

`Popen3.tochild`

A file object that provides input to the child process.

`Popen3.childerr`

A file object that provides error output from the child process, if `capturestderr` was true for the constructor, otherwise `None`. This will always be `None` for `Popen4` instances.

`Popen3.pid`

The process ID of the child process.

17.5.2 Flow Control Issues

Any time you are working with any form of inter-process communication, control flow needs to be carefully thought out. This remains the case with the file objects provided by this module (or the `os` module equivalents).

When reading output from a child process that writes a lot of data to standard error while the parent is reading from the child's standard output, a deadlock can occur. A similar situation can occur with other combinations of reads and writes. The essential factors are that more than `_PC_PIPE_BUF` bytes are being written by one process in a blocking fashion, while the other process is reading from the first process, also in a blocking fashion.

There are several ways to deal with this situation.

The simplest application change, in many cases, will be to follow this model in the parent process:

```
import popen2

r, w, e = popen2.Popen3('python slave.py')
e.readlines()
r.readlines()
r.close()
e.close()
w.close()
```

with code like this in the child:

```
import os
import sys

# note that each of these print statements
# writes a single long string

print >>sys.stderr, 400 * 'this is a test\n'
os.close(sys.stderr.fileno())
print >>sys.stdout, 400 * 'this is another test\n'
```

In particular, note that `sys.stderr` must be closed after writing all data, or `readlines()` won't return. Also note that `os.close()` must be used, as `sys.stderr.close()` won't close `stderr` (otherwise assigning to `sys.stderr` will silently close it, so no further errors can be printed).

Applications which need to support a more general approach should integrate I/O over pipes with their `select()` loops, or use separate threads to read each of the individual files provided by whichever `popen*()` function or `Popen*` class was used.

더 보기:

Module `subprocess` Module for spawning and managing subprocesses.

17.6 `asyncore` — Asynchronous socket handler

Source code: [Lib/asyncore.py](#)

This module provides the basic infrastructure for writing asynchronous socket service clients and servers.

There are only two ways to have a program on a single processor do 《more than one thing at a time.》 Multi-threaded programming is the simplest and most popular way to do it, but there is another very different technique, that lets you have nearly all the advantages of multi-threading, without actually using multiple threads. It's really only practical if your program is largely I/O bound. If your program is processor bound, then pre-emptive scheduled threads are probably what you really need. Network servers are rarely processor bound, however.

If your operating system supports the `select()` system call in its I/O library (and nearly all do), then you can use it to juggle multiple communication channels at once; doing other work while your I/O is taking place in the 《background.》 Although this strategy can seem strange and complex, especially at first, it is in many ways easier to understand and control than multi-threaded programming. The `asyncore` module solves many of the difficult problems for you, making the task of building sophisticated high-performance network servers and clients a snap. For 《conversational》 applications and protocols the companion `asynchat` module is invaluable.

The basic idea behind both modules is to create one or more network *channels*, instances of class `asyncore.dispatcher` and `asynchat.async_chat`. Creating the channels adds them to a global map, used by the `loop()` function if you do not provide it with your own *map*.

Once the initial channel(s) is(are) created, calling the `loop()` function activates channel service, which continues until the last channel (including any that have been added to the map during asynchronous service) is closed.

`asyncore.loop([timeout[, use_poll[, map[, count]]]])`

Enter a polling loop that terminates after *count* passes or all open channels have been closed. All arguments are optional. The *count* parameter defaults to `None`, resulting in the loop terminating only when all channels have been closed. The *timeout* argument sets the timeout parameter for the appropriate `select()` or `poll()` call, measured in seconds; the default is 30 seconds. The *use_poll* parameter, if true, indicates that `poll()` should be used in preference to `select()` (the default is `False`).

The *map* parameter is a dictionary whose items are the channels to watch. As channels are closed they are deleted from their map. If *map* is omitted, a global map is used. Channels (instances of `asyncore.dispatcher`, `asyncchat.async_chat` and subclasses thereof) can freely be mixed in the map.

class `asyncore.dispatcher`

The *dispatcher* class is a thin wrapper around a low-level socket object. To make it more useful, it has a few methods for event-handling which are called from the asynchronous loop. Otherwise, it can be treated as a normal non-blocking socket object.

The firing of low-level events at certain times or in certain connection states tells the asynchronous loop that certain higher-level events have taken place. For example, if we have asked for a socket to connect to another host, we know that the connection has been made when the socket becomes writable for the first time (at this point you know that you may write to it with the expectation of success). The implied higher-level events are:

Event	Description
<code>handle_connect()</code>	Implied by the first read or write event
<code>handle_close()</code>	Implied by a read event with no data available
<code>handle_accept()</code>	Implied by a read event on a listening socket

During asynchronous processing, each mapped channel's *readable()* and *writable()* methods are used to determine whether the channel's socket should be added to the list of channels *select()*ed or *poll()*ed for read and write events.

Thus, the set of channel events is larger than the basic socket events. The full set of methods that can be overridden in your subclass follows:

handle_read()

Called when the asynchronous loop detects that a *read()* call on the channel's socket will succeed.

handle_write()

Called when the asynchronous loop detects that a writable socket can be written. Often this method will implement the necessary buffering for performance. For example:

```
def handle_write(self):
    sent = self.send(self.buffer)
    self.buffer = self.buffer[sent:]
```

handle_expt()

Called when there is out of band (OOB) data for a socket connection. This will almost never happen, as OOB is tenuously supported and rarely used.

handle_connect()

Called when the active opener's socket actually makes a connection. Might send a «welcome» banner, or initiate a protocol negotiation with the remote endpoint, for example.

handle_close()

Called when the socket is closed.

handle_error()

Called when an exception is raised and not otherwise handled. The default version prints a condensed traceback.

handle_accept()

Called on listening channels (passive openers) when a connection can be established with a new remote endpoint that has issued a *connect()* call for the local endpoint.

readable()

Called each time around the asynchronous loop to determine whether a channel's socket should be added to

the list on which read events can occur. The default method simply returns `True`, indicating that by default, all channels will be interested in read events.

writable()

Called each time around the asynchronous loop to determine whether a channel's socket should be added to the list on which write events can occur. The default method simply returns `True`, indicating that by default, all channels will be interested in write events.

In addition, each channel delegates or extends many of the socket methods. Most of these are nearly identical to their socket partners.

create_socket(family, type)

This is identical to the creation of a normal socket, and will use the same options for creation. Refer to the [socket](#) documentation for information on creating sockets.

connect(address)

As with the normal socket object, *address* is a tuple with the first element the host to connect to, and the second the port number.

send(data)

Send *data* to the remote end-point of the socket.

recv(buffer_size)

Read at most *buffer_size* bytes from the socket's remote end-point. An empty string implies that the channel has been closed from the other end.

Note that *recv()* may raise *socket.error* with *EAGAIN* or *EWouldBlock*, even though *select.select()* or *select.poll()* has reported the socket ready for reading.

listen(backlog)

Listen for connections made to the socket. The *backlog* argument specifies the maximum number of queued connections and should be at least 1; the maximum value is system-dependent (usually 5).

bind(address)

Bind the socket to *address*. The socket must not already be bound. (The format of *address* depends on the address family — refer to the [socket](#) documentation for more information.) To mark the socket as re-usable (setting the `SO_REUSEADDR` option), call the *dispatcher* object's *set_reuse_addr()* method.

accept()

Accept a connection. The socket must be bound to an address and listening for connections. The return value can be either `None` or a pair (*conn*, *address*) where *conn* is a *new* socket object usable to send and receive data on the connection, and *address* is the address bound to the socket on the other end of the connection. When `None` is returned it means the connection didn't take place, in which case the server should just ignore this event and keep listening for further incoming connections.

close()

Close the socket. All future operations on the socket object will fail. The remote end-point will receive no more data (after queued data is flushed). Sockets are automatically closed when they are garbage-collected.

class asyncio.dispatcher_with_send

A *dispatcher* subclass which adds simple buffered output capability, useful for simple clients. For more sophisticated usage use *asyncchat.async_chat*.

class asyncio.file_dispatcher

A *file_dispatcher* takes a file descriptor or file object along with an optional *map* argument and wraps it for use with the *poll()* or *loop()* functions. If provided a file object or anything with a *fileno()* method, that method will be called and passed to the *file_wrapper* constructor. Availability: UNIX.

class asyncio.file_wrapper

A *file_wrapper* takes an integer file descriptor and calls *os.dup()* to duplicate the handle so that the original

handle may be closed independently of the file_wrapper. This class implements sufficient methods to emulate a socket for use by the *file_dispatcher* class. Availability: UNIX.

17.6.1 *asyncore* Example basic HTTP client

Here is a very basic HTTP client that uses the *dispatcher* class to implement its socket handling:

```
import asyncore, socket

class HTTPClient(asyncore.dispatcher):

    def __init__(self, host, path):
        asyncore.dispatcher.__init__(self)
        self.create_socket(socket.AF_INET, socket.SOCK_STREAM)
        self.connect((host, 80))
        self.buffer = 'GET %s HTTP/1.0\r\n\r\n' % path

    def handle_connect(self):
        pass

    def handle_close(self):
        self.close()

    def handle_read(self):
        print self.recv(8192)

    def writable(self):
        return (len(self.buffer) > 0)

    def handle_write(self):
        sent = self.send(self.buffer)
        self.buffer = self.buffer[sent:]

client = HTTPClient('www.python.org', '/')
asyncore.loop()
```

17.6.2 *asyncore* Example basic echo server

Here is a basic echo server that uses the *dispatcher* class to accept connections and dispatches the incoming connections to a handler:

```
import asyncore
import socket

class EchoHandler(asyncore.dispatcher_with_send):

    def handle_read(self):
        data = self.recv(8192)
        if data:
            self.send(data)

class EchoServer(asyncore.dispatcher):

    def __init__(self, host, port):
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

asyncore.dispatcher.__init__(self)
self.create_socket(socket.AF_INET, socket.SOCK_STREAM)
self.set_reuse_addr()
self.bind((host, port))
self.listen(5)

def handle_accept(self):
    pair = self.accept()
    if pair is not None:
        sock, addr = pair
        print 'Incoming connection from %s' % repr(addr)
        handler = EchoHandler(sock)

server = EchoServer('localhost', 8080)
asyncore.loop()

```

17.7 `asyncchat` — Asynchronous socket command/response handler

Source code: [Lib/asyncchat.py](#)

This module builds on the `asyncore` infrastructure, simplifying asynchronous clients and servers and making it easier to handle protocols whose elements are terminated by arbitrary strings, or are of variable length. `asyncchat` defines the abstract class `async_chat` that you subclass, providing implementations of the `collect_incoming_data()` and `found_terminator()` methods. It uses the same asynchronous loop as `asyncore`, and the two types of channel, `asyncore.dispatcher` and `async_chat.async_chat`, can freely be mixed in the channel map. Typically an `asyncore.dispatcher` server channel generates new `async_chat.async_chat` channel objects as it receives incoming connection requests.

`class async_chat.async_chat`

This class is an abstract subclass of `asyncore.dispatcher`. To make practical use of the code you must subclass `async_chat`, providing meaningful `collect_incoming_data()` and `found_terminator()` methods. The `asyncore.dispatcher` methods can be used, although not all make sense in a message/response context.

Like `asyncore.dispatcher`, `async_chat` defines a set of events that are generated by an analysis of socket conditions after a `select()` call. Once the polling loop has been started the `async_chat` object's methods are called by the event-processing framework with no action on the part of the programmer.

Two class attributes can be modified, to improve performance, or possibly even to conserve memory.

`ac_in_buffer_size`

The asynchronous input buffer size (default 4096).

`ac_out_buffer_size`

The asynchronous output buffer size (default 4096).

Unlike `asyncore.dispatcher`, `async_chat` allows you to define a first-in-first-out queue (fifo) of *producers*. A producer need have only one method, `more()`, which should return data to be transmitted on the channel. The producer indicates exhaustion (*i.e.* that it contains no more data) by having its `more()` method return the empty string. At this point the `async_chat` object removes the producer from the fifo and starts using the next producer, if any. When the producer fifo is empty the `handle_write()` method does nothing. You use the channel object's `set_terminator()` method to describe how to recognize the end of, or an important breakpoint in, an incoming transmission from the remote endpoint.

To build a functioning `async_chat` subclass your input methods `collect_incoming_data()` and `found_terminator()` must handle the data that the channel receives asynchronously. The methods are described below.

`async_chat.close_when_done()`

Pushes a `None` on to the producer fifo. When this producer is popped off the fifo it causes the channel to be closed.

`async_chat.collect_incoming_data(data)`

Called with `data` holding an arbitrary amount of received data. The default method, which must be overridden, raises a `NotImplementedError` exception.

`async_chat.discard_buffers()`

In emergencies this method will discard any data held in the input and/or output buffers and the producer fifo.

`async_chat.found_terminator()`

Called when the incoming data stream matches the termination condition set by `set_terminator()`. The default method, which must be overridden, raises a `NotImplementedError` exception. The buffered input data should be available via an instance attribute.

`async_chat.get_terminator()`

Returns the current terminator for the channel.

`async_chat.push(data)`

Pushes data on to the channel's fifo to ensure its transmission. This is all you need to do to have the channel write the data out to the network, although it is possible to use your own producers in more complex schemes to implement encryption and chunking, for example.

`async_chat.push_with_producer(producer)`

Takes a producer object and adds it to the producer fifo associated with the channel. When all currently-pushed producers have been exhausted the channel will consume this producer's data by calling its `more()` method and send the data to the remote endpoint.

`async_chat.set_terminator(term)`

Sets the terminating condition to be recognized on the channel. `term` may be any of three types of value, corresponding to three different ways to handle incoming protocol data.

term	Description
<i>string</i>	Will call <code>found_terminator()</code> when the string is found in the input stream
<i>integer</i>	Will call <code>found_terminator()</code> when the indicated number of characters have been received
<code>None</code>	The channel continues to collect data forever

Note that any data following the terminator will be available for reading by the channel after `found_terminator()` is called.

17.7.1 asynchat - Auxiliary Classes

class `asynchat.fifo([list=None])`

A *fifo* holding data which has been pushed by the application but not yet popped for writing to the channel. A *fifo* is a list used to hold data and/or producers until they are required. If the *list* argument is provided then it should contain producers or data items to be written to the channel.

is_empty()

Returns `True` if and only if the fifo is empty.

first()

Returns the least-recently *push()*ed item from the fifo.

push(data)

Adds the given data (which may be a string or a producer object) to the producer fifo.

pop()

If the fifo is not empty, returns `True`, `first()`, deleting the popped item. Returns `False`, `None` for an empty fifo.

17.7.2 asynchat Example

The following partial example shows how HTTP requests can be read with `asynchat`. A web server might create an `http_request_handler` object for each incoming client connection. Notice that initially the channel terminator is set to match the blank line at the end of the HTTP headers, and a flag indicates that the headers are being read.

Once the headers have been read, if the request is of type POST (indicating that further data are present in the input stream) then the `Content-Length`: header is used to set a numeric terminator to read the right amount of data from the channel.

The `handle_request()` method is called once all relevant input has been marshalled, after setting the channel terminator to `None` to ensure that any extraneous data sent by the web client are ignored.

```
class http_request_handler(asynchat.async_chat):

    def __init__(self, sock, addr, sessions, log):
        asynchat.async_chat.__init__(self, sock=sock)
        self.addr = addr
        self.sessions = sessions
        self.ibuffer = []
        self.obuffer = ""
        self.set_terminator("\r\n\r\n")
        self.reading_headers = True
        self.handling = False
        self.cgi_data = None
        self.log = log

    def collect_incoming_data(self, data):
        """Buffer the data"""
        self.ibuffer.append(data)

    def found_terminator(self):
        if self.reading_headers:
            self.reading_headers = False
            self.parse_headers("".join(self.ibuffer))
            self.ibuffer = []
            if self.op.upper() == "POST":
                clen = self.headers.getheader("content-length")
                self.set_terminator(int(clen))
            else:
                self.handling = True
                self.set_terminator(None)
                self.handle_request()
        elif not self.handling:
            self.set_terminator(None) # browsers sometimes over-send
            self.cgi_data = parse(self.headers, "".join(self.ibuffer))
            self.handling = True
            self.ibuffer = []
            self.handle_request()
```


This chapter describes modules which support handling data formats commonly used on the Internet.

18.1 `email` — An email and MIME handling package

버전 2.2에 추가.

The `email` package is a library for managing email messages, including MIME and other **RFC 2822**-based message documents. It subsumes most of the functionality in several older standard modules such as `rfc822`, `mimetools`, `multifile`, and other non-standard packages such as `mimecntl`. It is specifically *not* designed to do any sending of email messages to SMTP (**RFC 2821**), NNTP, or other servers; those are functions of modules such as `smtplib` and `nntplib`. The `email` package attempts to be as RFC-compliant as possible, supporting in addition to **RFC 2822**, such MIME-related RFCs as **RFC 2045**, **RFC 2046**, **RFC 2047**, and **RFC 2231**.

The primary distinguishing feature of the `email` package is that it splits the parsing and generating of email messages from the internal *object model* representation of email. Applications using the `email` package deal primarily with objects; you can add sub-objects to messages, remove sub-objects from messages, completely re-arrange the contents, etc. There is a separate parser and a separate generator which handles the transformation from flat text to the object model, and then back to flat text again. There are also handy subclasses for some common MIME object types, and a few miscellaneous utilities that help with such common tasks as extracting and parsing message field values, creating RFC-compliant dates, etc.

The following sections describe the functionality of the `email` package. The ordering follows a progression that should be common in applications: an email message is read as flat text from a file or other source, the text is parsed to produce the object structure of the email message, this structure is manipulated, and finally, the object tree is rendered back into flat text.

It is perfectly feasible to create the object structure out of whole cloth — i.e. completely from scratch. From there, a similar progression can be taken as above.

Also included are detailed specifications of all the classes and modules that the `email` package provides, the exception classes you might encounter while using the `email` package, some auxiliary utilities, and a few examples. For users of the older `mimelib` package, or previous versions of the `email` package, a section on differences and porting is provided.

Contents of the *email* package documentation:

18.1.1 `email.message`: Representing an email message

The central class in the *email* package is the *Message* class, imported from the *email.message* module. It is the base class for the *email* object model. *Message* provides the core functionality for setting and querying header fields, and for accessing message bodies.

Conceptually, a *Message* object consists of *headers* and *payloads*. Headers are **RFC 2822** style field names and values where the field name and value are separated by a colon. The colon is not part of either the field name or the field value.

Headers are stored and returned in case-preserving form but are matched case-insensitively. There may also be a single envelope header, also known as the *Unix-From* header or the `From_` header. The payload is either a string in the case of simple message objects or a list of *Message* objects for MIME container documents (e.g. *multipart/** and *message/rfc822*).

Message objects provide a mapping style interface for accessing the message headers, and an explicit interface for accessing both the headers and the payload. It provides convenience methods for generating a flat text representation of the message object tree, for accessing commonly used header parameters, and for recursively walking over the object tree.

Here are the methods of the *Message* class:

class `email.message.Message`

The constructor takes no arguments.

as_string (`[unixfrom]`)

Return the entire message flattened as a string. When optional *unixfrom* is `True`, the envelope header is included in the returned string. *unixfrom* defaults to `False`. Flattening the message may trigger changes to the *Message* if defaults need to be filled in to complete the transformation to a string (for example, MIME boundaries may be generated or modified).

Note that this method is provided as a convenience and may not always format the message the way you want. For example, by default it mangles lines that begin with `From`. For more flexibility, instantiate a *Generator* instance and use its *flatten()* method directly. For example:

```
from cStringIO import StringIO
from email.generator import Generator
fp = StringIO()
g = Generator(fp, mangle_from_=False, maxheaderlen=60)
g.flatten(msg)
text = fp.getvalue()
```

__str__ ()

Equivalent to `as_string(unixfrom=True)`.

is_multipart ()

Return `True` if the message's payload is a list of sub-*Message* objects, otherwise return `False`. When *is_multipart()* returns `False`, the payload should be a string object.

set_unixfrom (*unixfrom*)

Set the message's envelope header to *unixfrom*, which should be a string.

get_unixfrom ()

Return the message's envelope header. Defaults to `None` if the envelope header was never set.

attach (*payload*)

Add the given *payload* to the current payload, which must be `None` or a list of *Message* objects before the call. After the call, the payload will always be a list of *Message* objects. If you want to set the payload to a scalar object (e.g. a string), use *set_payload()* instead.

get_payload (*i* [, *decode*])

Return the current payload, which will be a list of *Message* objects when *is_multipart()* is True, or a string when *is_multipart()* is False. If the payload is a list and you mutate the list object, you modify the message's payload in place.

With optional argument *i*, *get_payload()* will return the *i*-th element of the payload, counting from zero, if *is_multipart()* is True. An *IndexError* will be raised if *i* is less than 0 or greater than or equal to the number of items in the payload. If the payload is a string (i.e. *is_multipart()* is False) and *i* is given, a *TypeError* is raised.

Optional *decode* is a flag indicating whether the payload should be decoded or not, according to the *Content-Transfer-Encoding* header. When True and the message is not a multipart, the payload will be decoded if this header's value is quoted-printable or base64. If some other encoding is used, or *Content-Transfer-Encoding* header is missing, or if the payload has bogus base64 data, the payload is returned as-is (undecoded). If the message is a multipart and the *decode* flag is True, then None is returned. The default for *decode* is False.

set_payload (*payload* [, *charset*])

Set the entire message object's payload to *payload*. It is the client's responsibility to ensure the payload invariants. Optional *charset* sets the message's default character set; see *set_charset()* for details.

버전 2.2.2에서 변경: *charset* argument added.

set_charset (*charset*)

Set the character set of the payload to *charset*, which can either be a *Charset* instance (see *email.charset*), a string naming a character set, or None. If it is a string, it will be converted to a *Charset* instance. If *charset* is None, the *charset* parameter will be removed from the *Content-Type* header (the message will not be otherwise modified). Anything else will generate a *TypeError*.

If there is no existing *MIME-Version* header one will be added. If there is no existing *Content-Type* header, one will be added with a value of *text/plain*. Whether the *Content-Type* header already exists or not, its *charset* parameter will be set to *charset.output_charset*. If *charset.input_charset* and *charset.output_charset* differ, the payload will be re-encoded to the *output_charset*. If there is no existing *Content-Transfer-Encoding* header, then the payload will be transfer-encoded, if needed, using the specified *Charset*, and a header with the appropriate value will be added. If a *Content-Transfer-Encoding* header already exists, the payload is assumed to already be correctly encoded using that *Content-Transfer-Encoding* and is not modified.

The message will be assumed to be of type *text/**, with the payload either in unicode or encoded with *charset.input_charset*. It will be encoded or converted to *charset.output_charset* and transfer encoded properly, if needed, when generating the plain text representation of the message. MIME headers (*MIME-Version*, *Content-Type*, *Content-Transfer-Encoding*) will be added as needed.

버전 2.2.2에 추가.

get_charset ()

Return the *Charset* instance associated with the message's payload.

버전 2.2.2에 추가.

The following methods implement a mapping-like interface for accessing the message's **RFC 2822** headers. Note that there are some semantic differences between these methods and a normal mapping (i.e. dictionary) interface. For example, in a dictionary there are no duplicate keys, but here there may be duplicate message headers. Also, in dictionaries there is no guaranteed order to the keys returned by *keys()*, but in a *Message* object, headers are always returned in the order they appeared in the original message, or were added to the message later. Any header deleted and then re-added are always appended to the end of the header list.

These semantic differences are intentional and are biased toward maximal convenience.

Note that in all cases, any envelope header present in the message is not included in the mapping interface.

__len__()

Return the total number of headers, including duplicates.

__contains__(name)

Return true if the message object has a field named *name*. Matching is done case-insensitively and *name* should not include the trailing colon. Used for the `in` operator, e.g.:

```
if 'message-id' in myMessage:
    print 'Message-ID:', myMessage['message-id']
```

__getitem__(name)

Return the value of the named header field. *name* should not include the colon field separator. If the header is missing, `None` is returned; a `KeyError` is never raised.

Note that if the named field appears more than once in the message's headers, exactly which of those field values will be returned is undefined. Use the `get_all()` method to get the values of all the extant named headers.

__setitem__(name, val)

Add a header to the message with field name *name* and value *val*. The field is appended to the end of the message's existing fields.

Note that this does *not* overwrite or delete any existing header with the same name. If you want to ensure that the new header is the only one present in the message with field name *name*, delete the field first, e.g.:

```
del msg['subject']
msg['subject'] = 'Python roolz!'
```

__delitem__(name)

Delete all occurrences of the field with name *name* from the message's headers. No exception is raised if the named field isn't present in the headers.

has_key(name)

Return true if the message contains a header field named *name*, otherwise return false.

keys()

Return a list of all the message's header field names.

values()

Return a list of all the message's field values.

items()

Return a list of 2-tuples containing all the message's field headers and values.

get(name[, failobj])

Return the value of the named header field. This is identical to `__getitem__()` except that optional *failobj* is returned if the named header is missing (defaults to `None`).

Here are some additional useful methods:

get_all(name[, failobj])

Return a list of all the values for the field named *name*. If there are no such named headers in the message, *failobj* is returned (defaults to `None`).

add_header(_name, _value, **_params)

Extended header setting. This method is similar to `__setitem__()` except that additional header parameters can be provided as keyword arguments. *_name* is the header field to add and *_value* is the *primary* value for the header.

For each item in the keyword argument dictionary *_params*, the key is taken as the parameter name, with underscores converted to dashes (since dashes are illegal in Python identifiers). Normally, the parameter will

be added as `key="value"` unless the value is `None`, in which case only the key will be added. If the value contains non-ASCII characters, it must be specified as a three tuple in the format (`CHARSET`, `LANGUAGE`, `VALUE`), where `CHARSET` is a string naming the charset to be used to encode the value, `LANGUAGE` can usually be set to `None` or the empty string (see [RFC 2231](#) for other possibilities), and `VALUE` is the string value containing non-ASCII code points.

Here's an example:

```
msg.add_header('Content-Disposition', 'attachment', filename='bud.gif')
```

This will add a header that looks like

```
Content-Disposition: attachment; filename="bud.gif"
```

An example with non-ASCII characters:

```
msg.add_header('Content-Disposition', 'attachment',
               filename=('iso-8859-1', '', 'Fußballer.ppt'))
```

Which produces

```
Content-Disposition: attachment; filename*="iso-8859-1'Fu%DFballer.ppt"
```

replace_header (*_name*, *_value*)

Replace a header. Replace the first header found in the message that matches *_name*, retaining header order and field name case. If no matching header was found, a *KeyError* is raised.

버전 2.2.2에 추가.

get_content_type ()

Return the message's content type. The returned string is coerced to lower case of the form *maintype/subtype*. If there was no *Content-Type* header in the message the default type as given by *get_default_type* () will be returned. Since according to [RFC 2045](#), messages always have a default type, *get_content_type* () will always return a value.

[RFC 2045](#) defines a message's default type to be *text/plain* unless it appears inside a *multipart/digest* container, in which case it would be *message/rfc822*. If the *Content-Type* header has an invalid type specification, [RFC 2045](#) mandates that the default type be *text/plain*.

버전 2.2.2에 추가.

get_content_maintype ()

Return the message's main content type. This is the *maintype* part of the string returned by *get_content_type* ().

버전 2.2.2에 추가.

get_content_subtype ()

Return the message's sub-content type. This is the *subtype* part of the string returned by *get_content_type* ().

버전 2.2.2에 추가.

get_default_type ()

Return the default content type. Most messages have a default content type of *text/plain*, except for messages that are subparts of *multipart/digest* containers. Such subparts have a default content type of *message/rfc822*.

버전 2.2.2에 추가.

set_default_type (*ctype*)

Set the default content type. *ctype* should either be *text/plain* or *message/rfc822*, although this is not enforced. The default content type is not stored in the *Content-Type* header.

버전 2.2.2에 추가.

get_params ([*failobj* [, *header* [, *unquote*]]])

Return the message's *Content-Type* parameters, as a list. The elements of the returned list are 2-tuples of key/value pairs, as split on the '=' sign. The left hand side of the '=' is the key, while the right hand side is the value. If there is no '=' sign in the parameter the value is the empty string, otherwise the value is as described in *get_param()* and is unquoted if optional *unquote* is *True* (the default).

Optional *failobj* is the object to return if there is no *Content-Type* header. Optional *header* is the header to search instead of *Content-Type*.

버전 2.2.2에서 변경: *unquote* argument added.

get_param (*param* [, *failobj* [, *header* [, *unquote*]]])

Return the value of the *Content-Type* header's parameter *param* as a string. If the message has no *Content-Type* header or if there is no such parameter, then *failobj* is returned (defaults to *None*).

Optional *header* if given, specifies the message header to use instead of *Content-Type*.

Parameter keys are always compared case insensitively. The return value can either be a string, or a 3-tuple if the parameter was **RFC 2231** encoded. When it's a 3-tuple, the elements of the value are of the form (CHARSET, LANGUAGE, VALUE). Note that both CHARSET and LANGUAGE can be *None*, in which case you should consider VALUE to be encoded in the *us-ascii* charset. You can usually ignore LANGUAGE.

If your application doesn't care whether the parameter was encoded as in **RFC 2231**, you can collapse the parameter value by calling *email.utils.collapse_rfc2231_value()*, passing in the return value from *get_param()*. This will return a suitably decoded Unicode string when the value is a tuple, or the original string unquoted if it isn't. For example:

```
rawparam = msg.get_param('foo')
param = email.utils.collapse_rfc2231_value(rawparam)
```

In any case, the parameter value (either the returned string, or the VALUE item in the 3-tuple) is always unquoted, unless *unquote* is set to *False*.

버전 2.2.2에서 변경: *unquote* argument added, and 3-tuple return value possible.

set_param (*param*, *value* [, *header* [, *quote* [, *charset* [, *language*]]]])

Set a parameter in the *Content-Type* header. If the parameter already exists in the header, its value will be replaced with *value*. If the *Content-Type* header has not yet been defined for this message, it will be set to *text/plain* and the new parameter value will be appended as per **RFC 2045**.

Optional *header* specifies an alternative header to *Content-Type*, and all parameters will be quoted as necessary unless optional *quote* is *False* (the default is *True*).

If optional *charset* is specified, the parameter will be encoded according to **RFC 2231**. Optional *language* specifies the RFC 2231 language, defaulting to the empty string. Both *charset* and *language* should be strings.

버전 2.2.2에 추가.

del_param (*param* [, *header* [, *quote*]])

Remove the given parameter completely from the *Content-Type* header. The header will be re-written in place without the parameter or its value. All values will be quoted as necessary unless *quote* is *False* (the default is *True*). Optional *header* specifies an alternative to *Content-Type*.

버전 2.2.2에 추가.

set_type (*type*[, *header*][, *reqquote*])

Set the main type and subtype for the *Content-Type* header. *type* must be a string in the form *maintype/subtype*, otherwise a *ValueError* is raised.

This method replaces the *Content-Type* header, keeping all the parameters in place. If *reqquote* is *False*, this leaves the existing header's quoting as is, otherwise the parameters will be quoted (the default).

An alternative header can be specified in the *header* argument. When the *Content-Type* header is set a *MIME-Version* header is also added.

버전 2.2.2에 추가.

get_filename ([*failobj*])

Return the value of the *filename* parameter of the *Content-Disposition* header of the message. If the header does not have a *filename* parameter, this method falls back to looking for the *name* parameter on the *Content-Type* header. If neither is found, or the header is missing, then *failobj* is returned. The returned string will always be unquoted as per *email.utils.unquote()*.

get_boundary ([*failobj*])

Return the value of the *boundary* parameter of the *Content-Type* header of the message, or *failobj* if either the header is missing, or has no *boundary* parameter. The returned string will always be unquoted as per *email.utils.unquote()*.

set_boundary (*boundary*)

Set the *boundary* parameter of the *Content-Type* header to *boundary*. *set_boundary()* will always quote *boundary* if necessary. A *HeaderParseError* is raised if the message object has no *Content-Type* header.

Note that using this method is subtly different than deleting the old *Content-Type* header and adding a new one with the new *boundary* via *add_header()*, because *set_boundary()* preserves the order of the *Content-Type* header in the list of headers. However, it does *not* preserve any continuation lines which may have been present in the original *Content-Type* header.

get_content_charset ([*failobj*])

Return the *charset* parameter of the *Content-Type* header, coerced to lower case. If there is no *Content-Type* header, or if that header has no *charset* parameter, *failobj* is returned.

Note that this method differs from *get_charset()* which returns the *Charset* instance for the default encoding of the message body.

버전 2.2.2에 추가.

get_charsets ([*failobj*])

Return a list containing the character set names in the message. If the message is a *multipart*, then the list will contain one element for each subpart in the payload, otherwise, it will be a list of length 1.

Each item in the list will be a string which is the value of the *charset* parameter in the *Content-Type* header for the represented subpart. However, if the subpart has no *Content-Type* header, no *charset* parameter, or is not of the *text* main MIME type, then that item in the returned list will be *failobj*.

walk ()

The *walk()* method is an all-purpose generator which can be used to iterate over all the parts and subparts of a message object tree, in depth-first traversal order. You will typically use *walk()* as the iterator in a *for* loop; each iteration returns the next subpart.

Here's an example that prints the MIME type of every part of a multipart message structure:

```
>>> for part in msg.walk():
...     print part.get_content_type()
multipart/report
text/plain
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
message/delivery-status
text/plain
text/plain
message/rfc822
```

버전 2.5에서 변경: The previously deprecated methods `get_type()`, `get_main_type()`, and `get_subtype()` were removed.

Message objects can also optionally contain two instance attributes, which can be used when generating the plain text of a MIME message.

preamble

The format of a MIME document allows for some text between the blank line following the headers, and the first multipart boundary string. Normally, this text is never visible in a MIME-aware mail reader because it falls outside the standard MIME armor. However, when viewing the raw text of the message, or when viewing the message in a non-MIME aware reader, this text can become visible.

The *preamble* attribute contains this leading extra-armor text for MIME documents. When the *Parser* discovers some text after the headers but before the first boundary string, it assigns this text to the message's *preamble* attribute. When the *Generator* is writing out the plain text representation of a MIME message, and it finds the message has a *preamble* attribute, it will write this text in the area between the headers and the first boundary. See *email.parser* and *email.generator* for details.

Note that if the message object has no preamble, the *preamble* attribute will be `None`.

epilogue

The *epilogue* attribute acts the same way as the *preamble* attribute, except that it contains text that appears between the last boundary and the end of the message.

버전 2.5에서 변경: You do not need to set the epilogue to the empty string in order for the *Generator* to print a newline at the end of the file.

defects

The *defects* attribute contains a list of all the problems found when parsing this message. See *email.errors* for a detailed description of the possible parsing defects.

버전 2.4에 추가.

18.1.2 email.parser: Parsing email messages

Message object structures can be created in one of two ways: they can be created from whole cloth by instantiating *Message* objects and stringing them together via *attach()* and *set_payload()* calls, or they can be created by parsing a flat text representation of the email message.

The *email* package provides a standard parser that understands most email document structures, including MIME documents. You can pass the parser a string or a file object, and the parser will return to you the root *Message* instance of the object structure. For simple, non-MIME messages the payload of this root object will likely be a string containing the text of the message. For MIME messages, the root object will return `True` from its *is_multipart()* method, and the subparts can be accessed via the *get_payload()* and *walk()* methods.

There are actually two parser interfaces available for use, the classic *Parser* API and the incremental *FeedParser* API. The classic *Parser* API is fine if you have the entire text of the message in memory as a string, or if the entire message lives in a file on the file system. *FeedParser* is more appropriate for when you're reading the message from a stream which might block waiting for more input (e.g. reading an email message from a socket). The *FeedParser* can consume and parse the message incrementally, and only returns the root object when you close the parser¹.

¹ As of email package version 3.0, introduced in Python 2.4, the classic *Parser* was re-implemented in terms of the *FeedParser*, so the semantics and results are identical between the two parsers.

Note that the parser can be extended in limited ways, and of course you can implement your own parser completely from scratch. There is no magical connection between the `email` package's bundled parser and the `Message` class, so your custom parser can create message object trees any way it finds necessary.

FeedParser API

버전 2.4에 추가.

The `FeedParser`, imported from the `email.feedparser` module, provides an API that is conducive to incremental parsing of email messages, such as would be necessary when reading the text of an email message from a source that can block (e.g. a socket). The `FeedParser` can of course be used to parse an email message fully contained in a string or a file, but the classic `Parser` API may be more convenient for such use cases. The semantics and results of the two parser APIs are identical.

The `FeedParser`'s API is simple; you create an instance, feed it a bunch of text until there's no more to feed it, then close the parser to retrieve the root message object. The `FeedParser` is extremely accurate when parsing standards-compliant messages, and it does a very good job of parsing non-compliant messages, providing information about how a message was deemed broken. It will populate a message object's `defects` attribute with a list of any problems it found in a message. See the `email.errors` module for the list of defects that it can find.

Here is the API for the `FeedParser`:

class `email.parser.FeedParser` (`[_factory]`)

Create a `FeedParser` instance. Optional `_factory` is a no-argument callable that will be called whenever a new message object is needed. It defaults to the `email.message.Message` class.

feed (`data`)

Feed the `FeedParser` some more data. `data` should be a string containing one or more lines. The lines can be partial and the `FeedParser` will stitch such partial lines together properly. The lines in the string can have any of the common three line endings, carriage return, newline, or carriage return and newline (they can even be mixed).

close ()

Closing a `FeedParser` completes the parsing of all previously fed data, and returns the root message object. It is undefined what happens if you feed more data to a closed `FeedParser`.

Parser class API

The `Parser` class, imported from the `email.parser` module, provides an API that can be used to parse a message when the complete contents of the message are available in a string or file. The `email.parser` module also provides a second class, called `HeaderParser` which can be used if you're only interested in the headers of the message. `HeaderParser` can be much faster in these situations, since it does not attempt to parse the message body, instead setting the payload to the raw body as a string. `HeaderParser` has the same API as the `Parser` class.

class `email.parser.Parser` (`[_class]`)

The constructor for the `Parser` class takes an optional argument `_class`. This must be a callable factory (such as a function or a class), and it is used whenever a sub-message object needs to be created. It defaults to `Message` (see `email.message`). The factory will be called without arguments.

The optional `strict` flag is ignored.

버전 2.4부터 폐지: Because the `Parser` class is a backward compatible API wrapper around the new-in-Python 2.4 `FeedParser`, all parsing is effectively non-strict. You should simply stop passing a `strict` flag to the `Parser` constructor.

버전 2.2.2에서 변경: The `strict` flag was added.

버전 2.4에서 변경: The `strict` flag was deprecated.

The other public *Parser* methods are:

parse (*fp*[, *headersonly*])

Read all the data from the file-like object *fp*, parse the resulting text, and return the root message object. *fp* must support both the *readline()* and the *read()* methods on file-like objects.

The text contained in *fp* must be formatted as a block of **RFC 2822** style headers and header continuation lines, optionally preceded by an envelope header. The header block is terminated either by the end of the data or by a blank line. Following the header block is the body of the message (which may contain MIME-encoded subparts).

Optional *headersonly* is a flag specifying whether to stop parsing after reading the headers or not. The default is `False`, meaning it parses the entire contents of the file.

버전 2.2.2에서 변경 : The *headersonly* flag was added.

parsestr (*text*[, *headersonly*])

Similar to the *parse()* method, except it takes a string object instead of a file-like object. Calling this method on a string is exactly equivalent to wrapping *text* in a *StringIO* instance first and calling *parse()*.

Optional *headersonly* is as with the *parse()* method.

버전 2.2.2에서 변경 : The *headersonly* flag was added.

Since creating a message object structure from a string or a file object is such a common task, two functions are provided as a convenience. They are available in the top-level *email* package namespace.

email.message_from_string (*s*[, *_class*[, *strict*]])

Return a message object structure from a string. This is exactly equivalent to *Parser().parsestr(s)*. Optional *_class* and *strict* are interpreted as with the *Parser* class constructor.

버전 2.2.2에서 변경 : The *strict* flag was added.

email.message_from_file (*fp*[, *_class*[, *strict*]])

Return a message object structure tree from an open file object. This is exactly equivalent to *Parser().parse(fp)*. Optional *_class* and *strict* are interpreted as with the *Parser* class constructor.

버전 2.2.2에서 변경 : The *strict* flag was added.

Here's an example of how you might use this at an interactive Python prompt:

```
>>> import email
>>> msg = email.message_from_string(myString)
```

Additional notes

Here are some notes on the parsing semantics:

- Most non-*multipart* type messages are parsed as a single message object with a string payload. These objects will return `False` for *is_multipart()*. Their *get_payload()* method will return a string object.
- All *multipart* type messages will be parsed as a container message object with a list of sub-message objects for their payload. The outer container message will return `True` for *is_multipart()* and their *get_payload()* method will return the list of *Message* subparts.
- Most messages with a content type of *message/** (e.g. *message/delivery-status* and *message/rfc822*) will also be parsed as container object containing a list payload of length 1. Their *is_multipart()* method will return `True`. The single element in the list payload will be a sub-message object.
- Some non-standards compliant messages may not be internally consistent about their *multipart*-edness. Such messages may have a *Content-Type* header of type *multipart*, but their *is_multipart()* method

may return `False`. If such messages were parsed with the `FeedParser`, they will have an instance of the `MultipartInvariantViolationDefect` class in their `defects` attribute list. See `email.errors` for details.

18.1.3 `email.generator`: Generating MIME documents

One of the most common tasks is to generate the flat text of the email message represented by a message object structure. You will need to do this if you want to send your message via the `smtplib` module or the `nntplib` module, or print the message on the console. Taking a message object structure and producing a flat text document is the job of the `Generator` class.

Again, as with the `email.parser` module, you aren't limited to the functionality of the bundled generator; you could write one from scratch yourself. However the bundled generator knows how to generate most email in a standards-compliant way, should handle MIME and non-MIME email messages just fine, and is designed so that the transformation from flat text, to a message structure via the `Parser` class, and back to flat text, is idempotent (the input is identical to the output)¹. On the other hand, using the `Generator` on a `Message` constructed by program may result in changes to the `Message` object as defaults are filled in.

Here are the public methods of the `Generator` class, imported from the `email.generator` module:

class `email.generator.Generator` (`outfp`[, `mangle_from_`[, `maxheaderlen`]])

The constructor for the `Generator` class takes a file-like object called `outfp` for an argument. `outfp` must support the `write()` method and be usable as the output file in a Python extended print statement.

Optional `mangle_from_` is a flag that, when `True`, puts a `>` character in front of any line in the body that starts exactly as `From`, i.e. `From` followed by a space at the beginning of the line. This is the only guaranteed portable way to avoid having such lines be mistaken for a Unix mailbox format envelope header separator (see [WHY THE CONTENT-LENGTH FORMAT IS BAD](#) for details). `mangle_from_` defaults to `True`, but you might want to set this to `False` if you are not writing Unix mailbox format files.

Optional `maxheaderlen` specifies the longest length for a non-continued header. When a header line is longer than `maxheaderlen` (in characters, with tabs expanded to 8 spaces), the header will be split as defined in the `Header` class. Set to zero to disable header wrapping. The default is 78, as recommended (but not required) by [RFC 2822](#).

The other public `Generator` methods are:

flatten (`msg`[, `unixfrom`])

Print the textual representation of the message object structure rooted at `msg` to the output file specified when the `Generator` instance was created. Subparts are visited depth-first and the resulting text will be properly MIME encoded.

Optional `unixfrom` is a flag that forces the printing of the envelope header delimiter before the first [RFC 2822](#) header of the root message object. If the root object has no envelope header, a standard one is crafted. By default, this is set to `False` to inhibit the printing of the envelope delimiter.

Note that for subparts, no envelope header is ever printed.

버전 2.2.2에 추가.

clone (`fp`)

Return an independent clone of this `Generator` instance with the exact same options.

버전 2.2.2에 추가.

write (`s`)

Write the string `s` to the underlying file object, i.e. `outfp` passed to `Generator`'s constructor. This provides just enough file-like API for `Generator` instances to be used in extended print statements.

¹ This statement assumes that you use the appropriate setting for the `unixfrom` argument, and that you set `maxheaderlen=0` (which will preserve whatever the input line lengths were). It is also not strictly true, since in many cases runs of whitespace in headers are collapsed into single blanks. The latter is a bug that will eventually be fixed.

As a convenience, see the methods `Message.as_string()` and `str(aMessage)`, a.k.a. `Message.__str__()`, which simplify the generation of a formatted string representation of a message object. For more detail, see [email.message](#).

The [email.generator](#) module also provides a derived class, called [DecodedGenerator](#) which is like the [Generator](#) base class, except that non-*text* parts are substituted with a format string representing the part.

class `email.generator.DecodedGenerator` (`outfp`_{[, `mangle_from_`_{[, `maxheaderlen`_[, `fmt`]]])}}

This class, derived from [Generator](#) walks through all the subparts of a message. If the subpart is of main type *text*, then it prints the decoded payload of the subpart. Optional `_mangle_from_` and `maxheaderlen` are as with the [Generator](#) base class.

If the subpart is not of main type *text*, optional `fmt` is a format string that is used instead of the message payload. `fmt` is expanded with the following keywords, `%(keyword)s` format:

- `type` – Full MIME type of the non-*text* part
- `maintype` – Main MIME type of the non-*text* part
- `subtype` – Sub-MIME type of the non-*text* part
- `filename` – Filename of the non-*text* part
- `description` – Description associated with the non-*text* part
- `encoding` – Content transfer encoding of the non-*text* part

The default value for `fmt` is `None`, meaning

```
[Non-text %(type)s part of message omitted, filename %(filename)s]
```

버전 2.2.2에 추가.

버전 2.5에서 변경: The previously deprecated method `__call__()` was removed.

18.1.4 email.mime: Creating email and MIME objects from scratch

Ordinarily, you get a message object structure by passing a file or some text to a parser, which parses the text and returns the root message object. However you can also build a complete message structure from scratch, or even individual [Message](#) objects by hand. In fact, you can also take an existing structure and add new [Message](#) objects, move them around, etc. This makes a very convenient interface for slicing-and-dicing MIME messages.

You can create a new object structure by creating [Message](#) instances, adding attachments and all the appropriate headers manually. For MIME messages though, the [email](#) package provides some convenient subclasses to make things easier.

Here are the classes:

class `email.mime.base.MIMEBase` (`_maintype`, `_subtype`, `**_params`)

Module: `email.mime.base`

This is the base class for all the MIME-specific subclasses of [Message](#). Ordinarily you won't create instances specifically of [MIMEBase](#), although you could. [MIMEBase](#) is provided primarily as a convenient base class for more specific MIME-aware subclasses.

`_maintype` is the *Content-Type* major type (e.g. *text* or *image*), and `_subtype` is the *Content-Type* minor type (e.g. *plain* or *gif*). `_params` is a parameter key/value dictionary and is passed directly to [Message.add_header](#).

The [MIMEBase](#) class always adds a *Content-Type* header (based on `_maintype`, `_subtype`, and `_params`), and a *MIME-Version* header (always set to 1.0).

```
class email.mime.nonmultipart.MIMENonMultipart
```

Module: email.mime.nonmultipart

A subclass of *MIMEBase*, this is an intermediate base class for MIME messages that are not *multipart*. The primary purpose of this class is to prevent the use of the *attach()* method, which only makes sense for *multipart* messages. If *attach()* is called, a *MultipartConversionError* exception is raised.

버전 2.2.2에 추가.

```
class email.mime.multipart.MIMEMultipart([_subtype[, boundary[, _subparts[, _params]]])
```

Module: email.mime.multipart

A subclass of *MIMEBase*, this is an intermediate base class for MIME messages that are *multipart*. Optional *_subtype* defaults to *mixed*, but can be used to specify the subtype of the message. A *Content-Type* header of *multipart/_subtype* will be added to the message object. A *MIME-Version* header will also be added.

Optional *boundary* is the multipart boundary string. When *None* (the default), the boundary is calculated when needed (for example, when the message is serialized).

_subparts is a sequence of initial subparts for the payload. It must be possible to convert this sequence to a list. You can always attach new subparts to the message by using the *Message.attach* method.

Additional parameters for the *Content-Type* header are taken from the keyword arguments, or passed into the *_params* argument, which is a keyword dictionary.

버전 2.2.2에 추가.

```
class email.mime.application.MIMEApplication([_data[, _subtype[, _encoder[, **_params]]])
```

Module: email.mime.application

A subclass of *MIMENonMultipart*, the *MIMEApplication* class is used to represent MIME message objects of major type *application*. *_data* is a string containing the raw byte data. Optional *_subtype* specifies the MIME subtype and defaults to *octet-stream*.

Optional *_encoder* is a callable (i.e. function) which will perform the actual encoding of the data for transport. This callable takes one argument, which is the *MIMEApplication* instance. It should use *get_payload()* and *set_payload()* to change the payload to encoded form. It should also add any *Content-Transfer-Encoding* or other headers to the message object as necessary. The default encoding is base64. See the *email.encoders* module for a list of the built-in encoders.

_params are passed straight through to the base class constructor.

버전 2.5에 추가.

```
class email.mime.audio.MIMEAudio([_audiodata[, _subtype[, _encoder[, **_params]]])
```

Module: email.mime.audio

A subclass of *MIMENonMultipart*, the *MIMEAudio* class is used to create MIME message objects of major type *audio*. *_audiodata* is a string containing the raw audio data. If this data can be decoded by the standard Python module *sndhdr*, then the subtype will be automatically included in the *Content-Type* header. Otherwise you can explicitly specify the audio subtype via the *_subtype* parameter. If the minor type could not be guessed and *_subtype* was not given, then *TypeError* is raised.

Optional *_encoder* is a callable (i.e. function) which will perform the actual encoding of the audio data for transport. This callable takes one argument, which is the *MIMEAudio* instance. It should use *get_payload()* and *set_payload()* to change the payload to encoded form. It should also add any *Content-Transfer-Encoding* or other headers to the message object as necessary. The default encoding is base64. See the *email.encoders* module for a list of the built-in encoders.

_params are passed straight through to the base class constructor.

```
class email.mime.image.MIMEImage(_imagedata[, _subtype[, _encoder[, **_params]]])
Module: email.mime.image
```

A subclass of *MIMENonMultipart*, the *MIMEImage* class is used to create MIME message objects of major type *image*. *_imagedata* is a string containing the raw image data. If this data can be decoded by the standard Python module *imghdr*, then the subtype will be automatically included in the *Content-Type* header. Otherwise you can explicitly specify the image subtype via the *_subtype* parameter. If the minor type could not be guessed and *_subtype* was not given, then *TypeError* is raised.

Optional *_encoder* is a callable (i.e. function) which will perform the actual encoding of the image data for transport. This callable takes one argument, which is the *MIMEImage* instance. It should use *get_payload()* and *set_payload()* to change the payload to encoded form. It should also add any *Content-Transfer-Encoding* or other headers to the message object as necessary. The default encoding is base64. See the *email.encoders* module for a list of the built-in encoders.

_params are passed straight through to the *MIMEBase* constructor.

```
class email.mime.message.MIMEMessage(_msg[, _subtype])
Module: email.mime.message
```

A subclass of *MIMENonMultipart*, the *MIMEMessage* class is used to create MIME objects of main type *message*. *_msg* is used as the payload, and must be an instance of class *Message* (or a subclass thereof), otherwise a *TypeError* is raised.

Optional *_subtype* sets the subtype of the message; it defaults to *rfc822*.

```
class email.mime.text.MIMEText(_text[, _subtype[, _charset]])
Module: email.mime.text
```

A subclass of *MIMENonMultipart*, the *MIMEText* class is used to create MIME objects of major type *text*. *_text* is the string for the payload. *_subtype* is the minor type and defaults to *plain*. *_charset* is the character set of the text and is passed as a parameter to the *MIMENonMultipart* constructor; it defaults to *us-ascii*. If *_text* is unicode, it is encoded using the *output_charset* of *_charset*, otherwise it is used as-is.

버전 2.4에서 변경: The previously deprecated *_encoding* argument has been removed. Content Transfer Encoding now happens implicitly based on the *_charset* argument.

Unless the *_charset* parameter is explicitly set to *None*, the *MIMEText* object created will have both a *Content-Type* header with a *charset* parameter, and a *Content-Transfer-Encoding* header. This means that a subsequent *set_payload* call will not result in an encoded payload, even if a charset is passed in the *set_payload* command. You can 《reset》 this behavior by deleting the *Content-Transfer-Encoding* header, after which a *set_payload* call will automatically encode the new payload (and add a new *Content-Transfer-Encoding* header).

18.1.5 email.header: Internationalized headers

RFC 2822 is the base standard that describes the format of email messages. It derives from the older **RFC 822** standard which came into widespread use at a time when most email was composed of ASCII characters only. **RFC 2822** is a specification written assuming email contains only 7-bit ASCII characters.

Of course, as email has been deployed worldwide, it has become internationalized, such that language specific character sets can now be used in email messages. The base standard still requires email messages to be transferred using only 7-bit ASCII characters, so a slew of RFCs have been written describing how to encode email containing non-ASCII characters into **RFC 2822**-compliant format. These RFCs include **RFC 2045**, **RFC 2046**, **RFC 2047**, and **RFC 2231**. The *email* package supports these standards in its *email.header* and *email.charset* modules.

If you want to include non-ASCII characters in your email headers, say in the *Subject* or *To* fields, you should use the *Header* class and assign the field in the *Message* object to an instance of *Header* instead of using a string for the header value. Import the *Header* class from the *email.header* module. For example:

```
>>> from email.message import Message
>>> from email.header import Header
>>> msg = Message()
>>> h = Header('p\xf6stal', 'iso-8859-1')
>>> msg['Subject'] = h
>>> print msg.as_string()
Subject: =?iso-8859-1?q?p=F6stal?=
```

Notice here how we wanted the *Subject* field to contain a non-ASCII character? We did this by creating a *Header* instance and passing in the character set that the byte string was encoded in. When the subsequent *Message* instance was flattened, the *Subject* field was properly **RFC 2047** encoded. MIME-aware mail readers would show this header using the embedded ISO-8859-1 character.

버전 2.2.2에 추가.

Here is the *Header* class description:

```
class email.header.Header ([s[, charset[, maxlinelen[, header_name[, continuation_ws[, errors]]]]])
```

Create a MIME-compliant header that can contain strings in different character sets.

Optional *s* is the initial header value. If *None* (the default), the initial header value is not set. You can later append to the header with *append()* method calls. *s* may be a byte string or a Unicode string, but see the *append()* documentation for semantics.

Optional *charset* serves two purposes: it has the same meaning as the *charset* argument to the *append()* method. It also sets the default character set for all subsequent *append()* calls that omit the *charset* argument. If *charset* is not provided in the constructor (the default), the *us-ascii* character set is used both as *s*'s initial charset and as the default for subsequent *append()* calls.

The maximum line length can be specified explicitly via *maxlinelen*. For splitting the first line to a shorter value (to account for the field header which isn't included in *s*, e.g. *Subject*) pass in the name of the field in *header_name*. The default *maxlinelen* is 76, and the default value for *header_name* is *None*, meaning it is not taken into account for the first line of a long, split header.

Optional *continuation_ws* must be **RFC 2822**-compliant folding whitespace, and is usually either a space or a hard tab character. This character will be prepended to continuation lines. *continuation_ws* defaults to a single space character (⟨ ⟩).

Optional *errors* is passed straight through to the *append()* method.

```
append (s[, charset[, errors]])
```

Append the string *s* to the MIME header.

Optional *charset*, if given, should be a *Charset* instance (see *email.charset*) or the name of a character set, which will be converted to a *Charset* instance. A value of *None* (the default) means that the *charset* given in the constructor is used.

s may be a byte string or a Unicode string. If it is a byte string (i.e. *isinstance(s, str)* is true), then *charset* is the encoding of that byte string, and a *UnicodeError* will be raised if the string cannot be decoded with that character set.

If *s* is a Unicode string, then *charset* is a hint specifying the character set of the characters in the string. In this case, when producing an **RFC 2822**-compliant header using **RFC 2047** rules, the Unicode string will be encoded using the following charsets in order: *us-ascii*, the *charset* hint, *utf-8*. The first character set to not provoke a *UnicodeError* is used.

Optional *errors* is passed through to any *unicode()* or *unicode.encode()* call, and defaults to ⟨strict⟩.

encode ([*splitchars*])

Encode a message header into an RFC-compliant format, possibly wrapping long lines and encapsulating non-ASCII parts in base64 or quoted-printable encodings. Optional *splitchars* is a string containing characters to split long ASCII lines on, in rough support of **RFC 2822**'s *highest level syntactic breaks*. This doesn't affect **RFC 2047** encoded lines.

The *Header* class also provides a number of methods to support standard operators and built-in functions.

__str__ ()

A synonym for *Header.encode()*. Useful for `str(aHeader)`.

__unicode__ ()

A helper for the built-in *unicode()* function. Returns the header as a Unicode string.

__eq__ (*other*)

This method allows you to compare two *Header* instances for equality.

__ne__ (*other*)

This method allows you to compare two *Header* instances for inequality.

The *email.header* module also provides the following convenient functions.

email.header.decode_header (*header*)

Decode a message header value without converting the character set. The header value is in *header*.

This function returns a list of (*decoded_string*, *charset*) pairs containing each of the decoded parts of the header. *charset* is `None` for non-encoded parts of the header, otherwise a lower case string containing the name of the character set specified in the encoded string.

Here's an example:

```
>>> from email.header import decode_header
>>> decode_header('=?iso-8859-1?q?F6stal?=')
[('p\xf6stal', 'iso-8859-1')]
```

email.header.make_header (*decoded_seq*[, *maxlinelen*[, *header_name*[, *continuation_ws*]]])

Create a *Header* instance from a sequence of pairs as returned by *decode_header()*.

decode_header() takes a header value string and returns a sequence of pairs of the format (*decoded_string*, *charset*) where *charset* is the name of the character set.

This function takes one of those sequence of pairs and returns a *Header* instance. Optional *maxlinelen*, *header_name*, and *continuation_ws* are as in the *Header* constructor.

18.1.6 email.charset: Representing character sets

This module provides a class *Charset* for representing character sets and character set conversions in email messages, as well as a character set registry and several convenience methods for manipulating this registry. Instances of *Charset* are used in several other modules within the *email* package.

Import this class from the *email.charset* module.

버전 2.2.2에 추가.

class *email.charset.Charset* ([*input_charset*])

Map character sets to their email properties.

This class provides information about the requirements imposed on email for a specific character set. It also provides convenience routines for converting between character sets, given the availability of the applicable codecs. Given a character set, it will do its best to provide information on how to use that character set in an email message in an RFC-compliant way.

Certain character sets must be encoded with quoted-printable or base64 when used in email headers or bodies. Certain character sets must be converted outright, and are not allowed in email.

Optional *input_charset* is as described below; it is always coerced to lower case. After being alias normalized it is also used as a lookup into the registry of character sets to find out the header encoding, body encoding, and output conversion codec to be used for the character set. For example, if *input_charset* is `iso-8859-1`, then headers and bodies will be encoded using quoted-printable and no output conversion codec is necessary. If *input_charset* is `eur-jp`, then headers will be encoded with base64, bodies will not be encoded, but output text will be converted from the `eur-jp` character set to the `iso-2022-jp` character set.

Charset instances have the following data attributes:

input_charset

The initial character set specified. Common aliases are converted to their *official* email names (e.g. `latin_1` is converted to `iso-8859-1`). Defaults to 7-bit `us-ascii`.

header_encoding

If the character set must be encoded before it can be used in an email header, this attribute will be set to `Charset.QP` (for quoted-printable), `Charset.BASE64` (for base64 encoding), or `Charset.SHORTEST` for the shortest of QP or BASE64 encoding. Otherwise, it will be `None`.

body_encoding

Same as *header_encoding*, but describes the encoding for the mail message's body, which indeed may be different than the header encoding. `Charset.SHORTEST` is not allowed for *body_encoding*.

output_charset

Some character sets must be converted before they can be used in email headers or bodies. If the *input_charset* is one of them, this attribute will contain the name of the character set output will be converted to. Otherwise, it will be `None`.

input_codec

The name of the Python codec used to convert the *input_charset* to Unicode. If no conversion codec is necessary, this attribute will be `None`.

output_codec

The name of the Python codec used to convert Unicode to the *output_charset*. If no conversion codec is necessary, this attribute will have the same value as the *input_codec*.

Charset instances also have the following methods:

get_body_encoding()

Return the content transfer encoding used for body encoding.

This is either the string `quoted-printable` or `base64` depending on the encoding used, or it is a function, in which case you should call the function with a single argument, the Message object being encoded. The function should then set the *Content-Transfer-Encoding* header itself to whatever is appropriate.

Returns the string `quoted-printable` if *body_encoding* is `QP`, returns the string `base64` if *body_encoding* is `BASE64`, and returns the string `7bit` otherwise.

convert(s)

Convert the string *s* from the *input_codec* to the *output_codec*.

to_splittable(s)

Convert a possibly multibyte string to a safely splittable format. *s* is the string to split.

Uses the *input_codec* to try and convert the string to Unicode, so it can be safely split on character boundaries (even for multibyte characters).

Returns the string as-is if it isn't known how to convert *s* to Unicode with the *input_charset*.

Characters that could not be converted to Unicode will be replaced with the Unicode replacement character 'U+FFFD'.

from_splittable (*ustr* [, *to_output*])

Convert a splittable string back into an encoded string. *ustr* is a Unicode string to 《unsplit》.

This method uses the proper codec to try and convert the string from Unicode back into an encoded format. Return the string as-is if it is not Unicode, or if it could not be converted from Unicode.

Characters that could not be converted from Unicode will be replaced with an appropriate character (usually '?').

If *to_output* is `True` (the default), uses *output_codec* to convert to an encoded format. If *to_output* is `False`, it uses *input_codec*.

get_output_charset ()

Return the output character set.

This is the *output_charset* attribute if that is not `None`, otherwise it is *input_charset*.

encoded_header_len ()

Return the length of the encoded header string, properly calculating for quoted-printable or base64 encoding.

header_encode (*s* [, *convert*])

Header-encode the string *s*.

If *convert* is `True`, the string will be converted from the input charset to the output charset automatically. This is not useful for multibyte character sets, which have line length issues (multibyte characters must be split on a character, not a byte boundary); use the higher-level [Header](#) class to deal with these issues (see [email.header](#)). *convert* defaults to `False`.

The type of encoding (base64 or quoted-printable) will be based on the *header_encoding* attribute.

body_encode (*s* [, *convert*])

Body-encode the string *s*.

If *convert* is `True` (the default), the string will be converted from the input charset to output charset automatically. Unlike [header_encode\(\)](#), there are no issues with byte boundaries and multibyte charsets in email bodies, so this is usually pretty safe.

The type of encoding (base64 or quoted-printable) will be based on the *body_encoding* attribute.

The [Charset](#) class also provides a number of methods to support standard operations and built-in functions.

__str__ ()

Returns *input_charset* as a string coerced to lower case. **__repr__** () is an alias for **__str__** () .

__eq__ (*other*)

This method allows you to compare two [Charset](#) instances for equality.

__ne__ (*other*)

This method allows you to compare two [Charset](#) instances for inequality.

The [email.charset](#) module also provides the following functions for adding new entries to the global character set, alias, and codec registries:

`email.charset.add_charset` (*charset* [, *header_enc* [, *body_enc* [, *output_charset*]]])

Add character properties to the global registry.

charset is the input character set, and must be the canonical name of a character set.

Optional *header_enc* and *body_enc* is either `Charset.QP` for quoted-printable, `Charset.BASE64` for base64 encoding, `Charset.SHORTEST` for the shortest of quoted-printable or base64 encoding, or `None` for no encoding. `SHORTEST` is only valid for *header_enc*. The default is `None` for no encoding.

Optional *output_charset* is the character set that the output should be in. Conversions will proceed from input charset, to Unicode, to the output charset when the method `Charset.convert()` is called. The default is to output in the same character set as the input.

Both *input_charset* and *output_charset* must have Unicode codec entries in the module's character set-to-codec mapping; use `add_codec()` to add codecs the module does not know about. See the `codecs` module's documentation for more information.

The global character set registry is kept in the module global dictionary `CHARSETS`.

`email.charset.add_alias(alias, canonical)`

Add a character set alias. *alias* is the alias name, e.g. `latin-1`. *canonical* is the character set's canonical name, e.g. `iso-8859-1`.

The global charset alias registry is kept in the module global dictionary `ALIASES`.

`email.charset.add_codec(charset, codecname)`

Add a codec that map characters in the given character set to and from Unicode.

charset is the canonical name of a character set. *codecname* is the name of a Python codec, as appropriate for the second argument to the `unicode()` built-in, or to the `encode()` method of a Unicode string.

18.1.7 email.encoders: Encoders

When creating *Message* objects from scratch, you often need to encode the payloads for transport through compliant mail servers. This is especially true for *image/** and *text/** type messages containing binary data.

The *email* package provides some convenient encodings in its `encoders` module. These encoders are actually used by the *MIMEAudio* and *MIMEImage* class constructors to provide default encodings. All encoder functions take exactly one argument, the message object to encode. They usually extract the payload, encode it, and reset the payload to this newly encoded value. They should also set the *Content-Transfer-Encoding* header as appropriate.

Note that these functions are not meaningful for a multipart message. They must be applied to individual subparts instead, and will raise a *TypeError* if passed a message whose type is multipart.

Here are the encoding functions provided:

`email.encoders.encode_quopri(msg)`

Encodes the payload into quoted-printable form and sets the *Content-Transfer-Encoding* header to quoted-printable¹. This is a good encoding to use when most of your payload is normal printable data, but contains a few unprintable characters.

`email.encoders.encode_base64(msg)`

Encodes the payload into base64 form and sets the *Content-Transfer-Encoding* header to base64. This is a good encoding to use when most of your payload is unprintable data since it is a more compact form than quoted-printable. The drawback of base64 encoding is that it renders the text non-human readable.

`email.encoders.encode_7or8bit(msg)`

This doesn't actually modify the message's payload, but it does set the *Content-Transfer-Encoding* header to either 7bit or 8bit as appropriate, based on the payload data.

`email.encoders.encode_noop(msg)`

This does nothing; it doesn't even set the *Content-Transfer-Encoding* header.

¹ Note that encoding with `encode_quopri()` also encodes all tabs and space characters in the data.

18.1.8 `email.errors`: Exception and Defect classes

The following exception classes are defined in the `email.errors` module:

exception `email.errors.MessageError`

This is the base class for all exceptions that the `email` package can raise. It is derived from the standard `Exception` class and defines no additional methods.

exception `email.errors.MessageParseError`

This is the base class for exceptions raised by the `Parser` class. It is derived from `MessageError`.

exception `email.errors.HeaderParseError`

Raised under some error conditions when parsing the **RFC 2822** headers of a message, this class is derived from `MessageParseError`. It can be raised from the `Parser.parse` or `Parser.parsestr` methods.

Situations where it can be raised include finding an envelope header after the first **RFC 2822** header of the message, finding a continuation line before the first **RFC 2822** header is found, or finding a line in the headers which is neither a header or a continuation line.

exception `email.errors.BoundaryError`

Raised under some error conditions when parsing the **RFC 2822** headers of a message, this class is derived from `MessageParseError`. It can be raised from the `Parser.parse` or `Parser.parsestr` methods.

Situations where it can be raised include not being able to find the starting or terminating boundary in a `multipart/*` message when strict parsing is used.

exception `email.errors.MultipartConversionError`

Raised when a payload is added to a `Message` object using `add_payload()`, but the payload is already a scalar and the message's `Content-Type` main type is not either `multipart` or missing. `MultipartConversionError` multiply inherits from `MessageError` and the built-in `TypeError`.

Since `Message.add_payload()` is deprecated, this exception is rarely raised in practice. However the exception may also be raised if the `attach()` method is called on an instance of a class derived from `MIMENonMultipart` (e.g. `MIMEImage`).

Here's the list of the defects that the `FeedParser` can find while parsing messages. Note that the defects are added to the message where the problem was found, so for example, if a message nested inside a `multipart/alternative` had a malformed header, that nested message object would have a defect, but the containing messages would not.

All defect classes are subclassed from `email.errors.MessageDefect`, but this class is *not* an exception!

버전 2.4에 추가: All the defect classes were added.

- `NoBoundaryInMultipartDefect` – A message claimed to be a multipart, but had no *boundary* parameter.
- `StartBoundaryNotFoundDefect` – The start boundary claimed in the *Content-Type* header was never found.
- `FirstHeaderLineIsContinuationDefect` – The message had a continuation line as its first header line.
- `MisplacedEnvelopeHeaderDefect` – A `«Unix From»` header was found in the middle of a header block.
- `MalformedHeaderDefect` – A header was found that was missing a colon, or was otherwise malformed.
- `MultipartInvariantViolationDefect` – A message claimed to be a *multipart*, but no subparts were found. Note that when a message has this defect, its `is_multipart()` method may return false even though its content type claims to be *multipart*.

18.1.9 email.utils: Miscellaneous utilities

There are several useful utilities provided in the `email.utils` module:

`email.utils.quote(str)`

Return a new string with backslashes in *str* replaced by two backslashes, and double quotes replaced by backslash-double quote.

`email.utils.unquote(str)`

Return a new string which is an *unquoted* version of *str*. If *str* ends and begins with double quotes, they are stripped off. Likewise if *str* ends and begins with angle brackets, they are stripped off.

`email.utils.parseaddr(address)`

Parse address – which should be the value of some address-containing field such as *To* or *Cc* – into its constituent *realname* and *email address* parts. Returns a tuple of that information, unless the parse fails, in which case a 2-tuple of ('', '') is returned.

`email.utils.formataddr(pair)`

The inverse of `parseaddr()`, this takes a 2-tuple of the form (realname, email_address) and returns the string value suitable for a *To* or *Cc* header. If the first element of *pair* is false, then the second element is returned unmodified.

`email.utils.getaddresses(fieldvalues)`

This method returns a list of 2-tuples of the form returned by `parseaddr()`. *fieldvalues* is a sequence of header field values as might be returned by `Message.get_all()`. Here's a simple example that gets all the recipients of a message:

```
from email.utils import getaddresses

tos = msg.get_all('to', [])
ccs = msg.get_all('cc', [])
resent_tos = msg.get_all('resent-to', [])
resent_ccs = msg.get_all('resent-cc', [])
all_recipients = getaddresses(tos + ccs + resent_tos + resent_ccs)
```

`email.utils.parsedate(date)`

Attempts to parse a date according to the rules in **RFC 2822**. However, some mailers don't follow that format as specified, so `parsedate()` tries to guess correctly in such cases. *date* is a string containing an **RFC 2822** date, such as "Mon, 20 Nov 1995 19:12:08 -0500". If it succeeds in parsing the date, `parsedate()` returns a 9-tuple that can be passed directly to `time.mktime()`; otherwise None will be returned. Note that indexes 6, 7, and 8 of the result tuple are not usable.

`email.utils.parsedate_tz(date)`

Performs the same function as `parsedate()`, but returns either None or a 10-tuple; the first 9 elements make up a tuple that can be passed directly to `time.mktime()`, and the tenth is the offset of the date's timezone from UTC (which is the official term for Greenwich Mean Time)¹. If the input string has no timezone, the last element of the tuple returned is None. Note that indexes 6, 7, and 8 of the result tuple are not usable.

`email.utils.mktime_tz(tuple)`

Turn a 10-tuple as returned by `parsedate_tz()` into a UTC timestamp (seconds since the Epoch). If the timezone item in the tuple is None, assume local time.

`email.utils.formatdate([timeval[, localtime][, usegmt]])`

Returns a date string as per **RFC 2822**, e.g.:

¹ Note that the sign of the timezone offset is the opposite of the sign of the `time.timezone` variable for the same timezone; the latter variable follows the POSIX standard while this module follows **RFC 2822**.

Fri, 09 Nov 2001 01:08:47 -0000

Optional *timeval* if given is a floating point time value as accepted by `time.gmtime()` and `time.localtime()`, otherwise the current time is used.

Optional *localtime* is a flag that when `True`, interprets *timeval*, and returns a date relative to the local timezone instead of UTC, properly taking daylight savings time into account. The default is `False` meaning UTC is used.

Optional *usegmt* is a flag that when `True`, outputs a date string with the timezone as an ascii string GMT, rather than a numeric -0000. This is needed for some protocols (such as HTTP). This only applies when *localtime* is `False`. The default is `False`.

버전 2.4에 추가.

`email.utils.make_msgid([idstring])`

Returns a string suitable for an **RFC 2822**-compliant *Message-ID* header. Optional *idstring* if given, is a string used to strengthen the uniqueness of the message id.

`email.utils.decode_rfc2231(s)`

Decode the string *s* according to **RFC 2231**.

`email.utils.encode_rfc2231(s[, charset[, language]])`

Encode the string *s* according to **RFC 2231**. Optional *charset* and *language*, if given is the character set name and language name to use. If neither is given, *s* is returned as-is. If *charset* is given but *language* is not, the string is encoded using the empty string for *language*.

`email.utils.collapse_rfc2231_value(value[, errors[, fallback_charset]])`

When a header parameter is encoded in **RFC 2231** format, *Message.get_param* may return a 3-tuple containing the character set, language, and value. *collapse_rfc2231_value()* turns this into a unicode string. Optional *errors* is passed to the *errors* argument of the built-in *unicode()* function; it defaults to `replace`. Optional *fallback_charset* specifies the character set to use if the one in the **RFC 2231** header is not known by Python; it defaults to `us-ascii`.

For convenience, if the *value* passed to *collapse_rfc2231_value()* is not a tuple, it should be a string and it is returned unquoted.

`email.utils.decode_params(params)`

Decode parameters list according to **RFC 2231**. *params* is a sequence of 2-tuples containing elements of the form (content-type, string-value).

버전 2.4에서 변경: The *dump_address_pair()* function has been removed; use *formataddr()* instead.

버전 2.4에서 변경: The *decode()* function has been removed; use the *Header.decode_header* method instead.

버전 2.4에서 변경: The *encode()* function has been removed; use the *Header.encode* method instead.

18.1.10 email.iterators: Iterators

Iterating over a message object tree is fairly easy with the *Message.walk* method. The *email.iterators* module provides some useful higher level iterations over message object trees.

`email.iterators.body_line_iterator(msg[, decode])`

This iterates over all the payloads in all the subparts of *msg*, returning the string payloads line-by-line. It skips over all the subpart headers, and it skips over any subpart with a payload that isn't a Python string. This is somewhat equivalent to reading the flat text representation of the message from a file using *readline()*, skipping over all the intervening headers.

Optional *decode* is passed through to *Message.get_payload*.

`email.iterators.typed_subpart_iterator(msg[, maintype[, subtype]])`

This iterates over all the subparts of *msg*, returning only those subparts that match the MIME type specified by *maintype* and *subtype*.

Note that *subtype* is optional; if omitted, then subpart MIME type matching is done only with the main type. *maintype* is optional too; it defaults to *text*.

Thus, by default `typed_subpart_iterator()` returns each subpart that has a MIME type of *text/**.

The following function has been added as a useful debugging tool. It should *not* be considered part of the supported public interface for the package.

`email.iterators._structure(msg[, fp[, level]])`

Prints an indented representation of the content types of the message object structure. For example:

```
>>> msg = email.message_from_file(somefile)
>>> _structure(msg)
multipart/mixed
  text/plain
  text/plain
  multipart/digest
    message/rfc822
      text/plain
    message/rfc822
      text/plain
    message/rfc822
      text/plain
    message/rfc822
      text/plain
    message/rfc822
      text/plain
    message/rfc822
      text/plain
  text/plain
text/plain
```

Optional *fp* is a file-like object to print the output to. It must be suitable for Python's extended print statement. *level* is used internally.

18.1.11 email: Examples

Here are a few examples of how to use the *email* package to read, write, and send simple email messages, as well as more complex MIME messages.

First, let's see how to create and send a simple text message:

```
# Import smtplib for the actual sending function
import smtplib

# Import the email modules we'll need
from email.mime.text import MIMEText

# Open a plain text file for reading. For this example, assume that
# the text file contains only ASCII characters.
fp = open(textfile, 'rb')
# Create a text/plain message
msg = MIMEText(fp.read())
fp.close()

# me == the sender's email address
# you == the recipient's email address
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

msg['Subject'] = 'The contents of %s' % textfile
msg['From'] = me
msg['To'] = you

# Send the message via our own SMTP server, but don't include the
# envelope header.
s = smtplib.SMTP('localhost')
s.sendmail(me, [you], msg.as_string())
s.quit()

```

And parsing RFC822 headers can easily be done by the `parse(filename)` or `parsestr(message_as_string)` methods of the `Parser()` class:

```

# Import the email modules we'll need
from email.parser import Parser

# If the e-mail headers are in a file, uncomment this line:
#headers = Parser().parse(open(messagefile, 'r'))

# Or for parsing headers in a string, use:
headers = Parser().parsestr('From: <user@example.com>\n'
                             'To: <someone_else@example.com>\n'
                             'Subject: Test message\n'
                             '\n'
                             'Body would go here\n')

# Now the header items can be accessed as a dictionary:
print 'To: %s' % headers['to']
print 'From: %s' % headers['from']
print 'Subject: %s' % headers['subject']

```

Here's an example of how to send a MIME message containing a bunch of family pictures that may be residing in a directory:

```

# Import smtplib for the actual sending function
import smtplib

# Here are the email package modules we'll need
from email.mime.image import MIMEImage
from email.mime.multipart import MIMEMultipart

COMMASPACE = ', '

# Create the container (outer) email message.
msg = MIMEMultipart()
msg['Subject'] = 'Our family reunion'
# me == the sender's email address
# family = the list of all recipients' email addresses
msg['From'] = me
msg['To'] = COMMASPACE.join(family)
msg.preamble = 'Our family reunion'

# Assume we know that the image files are all in PNG format
for file in pngfiles:
    # Open the files in binary mode. Let the MIMEImage class automatically
    # guess the specific image type.

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

fp = open(file, 'rb')
img = MIMEImage(fp.read())
fp.close()
msg.attach(img)

# Send the email via our own SMTP server.
s = smtplib.SMTP('localhost')
s.sendmail(me, family, msg.as_string())
s.quit()

```

Here's an example of how to send the entire contents of a directory as an email message:¹

```

#!/usr/bin/env python

"""Send the contents of a directory as a MIME message."""

import os
import sys
import smtplib
# For guessing MIME type based on file name extension
import mimetypes

from optparse import OptionParser

from email import encoders
from email.message import Message
from email.mime.audio import MIMEAudio
from email.mime.base import MIMEBase
from email.mime.image import MIMEImage
from email.mime.multipart import MIMEMultipart
from email.mime.text import MIMEText

COMMASPACE = ', '

def main():
    parser = OptionParser(usage="""\
Send the contents of a directory as a MIME message.

Usage: %prog [options]

Unless the -o option is given, the email is sent by forwarding to your local
SMTP server, which then does the normal delivery process.  Your local machine
must be running an SMTP server.
""")
    parser.add_option('-d', '--directory',
                      type='string', action='store',
                      help="""Mail the contents of the specified directory,
otherwise use the current directory.  Only the regular
files in the directory are sent, and we don't recurse to
subdirectories.""")
    parser.add_option('-o', '--output',
                      type='string', action='store', metavar='FILE',
                      help="""Print the composed message to FILE instead of
sending the message to the SMTP server.""")

```

(다음 페이지에 계속)

¹ Thanks to Matthew Dixon Cowles for the original inspiration and examples.

(이전 페이지에서 계속)

```

parser.add_option('-s', '--sender',
                  type='string', action='store', metavar='SENDER',
                  help='The value of the From: header (required)')
parser.add_option('-r', '--recipient',
                  type='string', action='append', metavar='RECIPIENT',
                  default=[], dest='recipients',
                  help='A To: header value (at least one required)')

opts, args = parser.parse_args()
if not opts.sender or not opts.recipients:
    parser.print_help()
    sys.exit(1)

directory = opts.directory
if not directory:
    directory = '.'
# Create the enclosing (outer) message
outer = MIMEMultipart()
outer['Subject'] = 'Contents of directory %s' % os.path.abspath(directory)
outer['To'] = COMMASPACE.join(opts.recipients)
outer['From'] = opts.sender
outer.preamble = 'You will not see this in a MIME-aware mail reader.\n'

for filename in os.listdir(directory):
    path = os.path.join(directory, filename)
    if not os.path.isfile(path):
        continue
    # Guess the content type based on the file's extension. Encoding
    # will be ignored, although we should check for simple things like
    # gzip'd or compressed files.
    ctype, encoding = mimetypes.guess_type(path)
    if ctype is None or encoding is not None:
        # No guess could be made, or the file is encoded (compressed), so
        # use a generic bag-of-bits type.
        ctype = 'application/octet-stream'
    maintype, subtype = ctype.split('/', 1)
    if maintype == 'text':
        fp = open(path)
        # Note: we should handle calculating the charset
        msg = MIMEText(fp.read(), _subtype=subtype)
        fp.close()
    elif maintype == 'image':
        fp = open(path, 'rb')
        msg = MIMEImage(fp.read(), _subtype=subtype)
        fp.close()
    elif maintype == 'audio':
        fp = open(path, 'rb')
        msg = MIMEAudio(fp.read(), _subtype=subtype)
        fp.close()
    else:
        fp = open(path, 'rb')
        msg = MIMEBase(maintype, subtype)
        msg.set_payload(fp.read())
        fp.close()
        # Encode the payload using Base64
        encoders.encode_base64(msg)
    # Set the filename parameter
    msg.add_header('Content-Disposition', 'attachment', filename=filename)

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

        outer.attach(msg)
    # Now send or store the message
    composed = outer.as_string()
    if opts.output:
        fp = open(opts.output, 'w')
        fp.write(composed)
        fp.close()
    else:
        s = smtplib.SMTP('localhost')
        s.sendmail(opts.sender, opts.recipients, composed)
        s.quit()

if __name__ == '__main__':
    main()

```

Here's an example of how to unpack a MIME message like the one above, into a directory of files:

```

#!/usr/bin/env python

"""Unpack a MIME message into a directory of files."""

import os
import sys
import email
import errno
import mimetypes

from optparse import OptionParser

def main():
    parser = OptionParser(usage="""\
Unpack a MIME message into a directory of files.

Usage: %prog [options] msgfile
""")
    parser.add_option('-d', '--directory',
                      type='string', action='store',
                      help="""Unpack the MIME message into the named
                      directory, which will be created if it doesn't already
                      exist.""")
    opts, args = parser.parse_args()
    if not opts.directory:
        parser.print_help()
        sys.exit(1)

    try:
        msgfile = args[0]
    except IndexError:
        parser.print_help()
        sys.exit(1)

    try:
        os.mkdir(opts.directory)
    except OSError as e:

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    # Ignore directory exists error
    if e.errno != errno.EEXIST:
        raise

fp = open(msgfile)
msg = email.message_from_file(fp)
fp.close()

counter = 1
for part in msg.walk():
    # multipart/* are just containers
    if part.get_content_maintype() == 'multipart':
        continue
    # Applications should really sanitize the given filename so that an
    # email message can't be used to overwrite important files
    filename = part.get_filename()
    if not filename:
        ext = mimetypes.guess_extension(part.get_content_type())
        if not ext:
            # Use a generic bag-of-bits extension
            ext = '.bin'
        filename = 'part-%03d%s' % (counter, ext)
        counter += 1
    fp = open(os.path.join(opts.directory, filename), 'wb')
    fp.write(part.get_payload(decode=True))
    fp.close()

if __name__ == '__main__':
    main()

```

Here's an example of how to create an HTML message with an alternative plain text version:²

```

#!/usr/bin/env python

import smtplib

from email.mime.multipart import MIMEMultipart
from email.mime.text import MIMEText

# me == my email address
# you == recipient's email address
me = "my@email.com"
you = "your@email.com"

# Create message container - the correct MIME type is multipart/alternative.
msg = MIMEMultipart('alternative')
msg['Subject'] = "Link"
msg['From'] = me
msg['To'] = you

# Create the body of the message (a plain-text and an HTML version).
text = "Hi!\nHow are you?\nHere is the link you wanted:\nhttps://www.python.org"
html = ""\
<html>

```

(다음 페이지에 계속)

² Contributed by Martin Matejek.

(이전 페이지에서 계속)

```

<head></head>
<body>
  <p>Hi!<br>
    How are you?<br>
    Here is the <a href="https://www.python.org">link</a> you wanted.
  </p>
</body>
</html>
"""

# Record the MIME types of both parts - text/plain and text/html.
part1 = MIMEText(text, 'plain')
part2 = MIMEText(html, 'html')

# Attach parts into message container.
# According to RFC 2046, the last part of a multipart message, in this case
# the HTML message, is best and preferred.
msg.attach(part1)
msg.attach(part2)

# Send the message via local SMTP server.
s = smtplib.SMTP('localhost')
# sendmail function takes 3 arguments: sender's address, recipient's address
# and message to send - here it is sent as one string.
s.sendmail(me, you, msg.as_string())
s.quit()

```

더 보기:**Module `smtplib`** SMTP protocol client**Module `nntplib`** NNTP protocol client

18.1.12 Package History

This table describes the release history of the email package, corresponding to the version of Python that the package was released with. For purposes of this document, when you see a note about change or added versions, these refer to the Python version the change was made in, *not* the email package version. This table also describes the Python compatibility of each version of the package.

email version	distributed with	compatible with
1.x	Python 2.2.0 to Python 2.2.1	<i>no longer supported</i>
2.5	Python 2.2.2+ and Python 2.3	Python 2.1 to 2.5
3.0	Python 2.4	Python 2.3 to 2.5
4.0	Python 2.5	Python 2.3 to 2.5

Here are the major differences between `email` version 4 and version 3:

- All modules have been renamed according to **PEP 8** standards. For example, the version 3 module `email.Message` was renamed to `email.message` in version 4.
- A new subpackage `email.mime` was added and all the version 3 `email.MIME*` modules were renamed and situated into the `email.mime` subpackage. For example, the version 3 module `email.MIMEText` was renamed to `email.mime.text`.

Note that the version 3 names will continue to work until Python 2.6.

- The `email.mime.application` module was added, which contains the `MIMEApplication` class.
- Methods that were deprecated in version 3 have been removed. These include `Generator.__call__()`, `Message.get_type()`, `Message.get_main_type()`, `Message.get_subtype()`.
- Fixes have been added for **RFC 2231** support which can change some of the return types for `Message.get_param` and friends. Under some circumstances, values which used to return a 3-tuple now return simple strings (specifically, if all extended parameter segments were unencoded, there is no language and charset designation expected, so the return type is now a simple string). Also, %-decoding used to be done for both encoded and unencoded segments; this decoding is now done only for encoded segments.

Here are the major differences between `email` version 3 and version 2:

- The `FeedParser` class was introduced, and the `Parser` class was implemented in terms of the `FeedParser`. All parsing therefore is non-strict, and parsing will make a best effort never to raise an exception. Problems found while parsing messages are stored in the message's `defect` attribute.
- All aspects of the API which raised `DeprecationWarnings` in version 2 have been removed. These include the `_encoder` argument to the `MIMEText` constructor, the `Message.add_payload()` method, the `Utils.dump_address_pair()` function, and the functions `Utils.decode()` and `Utils.encode()`.
- New `DeprecationWarnings` have been added to: `Generator.__call__()`, `Message.get_type()`, `Message.get_main_type()`, `Message.get_subtype()`, and the `strict` argument to the `Parser` class. These are expected to be removed in future versions.
- Support for Pythons earlier than 2.3 has been removed.

Here are the differences between `email` version 2 and version 1:

- The `email.Header` and `email.Charset` modules have been added.
- The pickle format for `Message` instances has changed. Since this was never (and still isn't) formally defined, this isn't considered a backward incompatibility. However if your application pickles and unpickles `Message` instances, be aware that in `email` version 2, `Message` instances now have private variables `_charset` and `_default_type`.
- Several methods in the `Message` class have been deprecated, or their signatures changed. Also, many new methods have been added. See the documentation for the `Message` class for details. The changes should be completely backward compatible.
- The object structure has changed in the face of `message/rfc822` content types. In `email` version 1, such a type would be represented by a scalar payload, i.e. the container message's `is_multipart()` returned false, `get_payload()` was not a list object, but a single `Message` instance.

This structure was inconsistent with the rest of the package, so the object representation for `message/rfc822` content types was changed. In `email` version 2, the container *does* return True from `is_multipart()`, and `get_payload()` returns a list containing a single `Message` item.

Note that this is one place that backward compatibility could not be completely maintained. However, if you're already testing the return type of `get_payload()`, you should be fine. You just need to make sure your code doesn't do a `set_payload()` with a `Message` instance on a container with a content type of `message/rfc822`.

- The `Parser` constructor's `strict` argument was added, and its `parse()` and `parsestr()` methods grew a *header-only* argument. The `strict` flag was also added to functions `email.message_from_file()` and `email.message_from_string()`.
- `Generator.__call__()` is deprecated; use `Generator.flatten` instead. The `Generator` class has also grown the `clone()` method.
- The `DecodedGenerator` class in the `email.generator` module was added.

- The intermediate base classes `MIMENonMultipart` and `MIMEMultipart` have been added, and interposed in the class hierarchy for most of the other MIME-related derived classes.
- The `_encoder` argument to the `MIMEText` constructor has been deprecated. Encoding now happens implicitly based on the `_charset` argument.
- The following functions in the `email.Utils` module have been deprecated: `dump_address_pairs()`, `decode()`, and `encode()`. The following functions have been added to the module: `make_msgid()`, `decode_rfc2231()`, `encode_rfc2231()`, and `decode_params()`.
- The non-public function `email.Iterators._structure()` was added.

18.1.13 Differences from `mimelib`

The `email` package was originally prototyped as a separate library called `mimelib`. Changes have been made so that method names are more consistent, and some methods or modules have either been added or removed. The semantics of some of the methods have also changed. For the most part, any functionality available in `mimelib` is still available in the `email` package, albeit often in a different way. Backward compatibility between the `mimelib` package and the `email` package was not a priority.

Here is a brief description of the differences between the `mimelib` and the `email` packages, along with hints on how to port your applications.

Of course, the most visible difference between the two packages is that the package name has been changed to `email`. In addition, the top-level package has the following differences:

- `messageFromString()` has been renamed to `message_from_string()`.
- `messageFromFile()` has been renamed to `message_from_file()`.

The `Message` class has the following differences:

- The method `asString()` was renamed to `as_string()`.
- The method `ismultipart()` was renamed to `is_multipart()`.
- The `get_payload()` method has grown a `decode` optional argument.
- The method `getall()` was renamed to `get_all()`.
- The method `addheader()` was renamed to `add_header()`.
- The method `gettype()` was renamed to `get_type()`.
- The method `getmaintype()` was renamed to `get_main_type()`.
- The method `getsubtype()` was renamed to `get_subtype()`.
- The method `getparams()` was renamed to `get_params()`. Also, whereas `getparams()` returned a list of strings, `get_params()` returns a list of 2-tuples, effectively the key/value pairs of the parameters, split on the '=' sign.
- The method `getparam()` was renamed to `get_param()`.
- The method `getcharsets()` was renamed to `get_charsets()`.
- The method `getfilename()` was renamed to `get_filename()`.
- The method `getboundary()` was renamed to `get_boundary()`.
- The method `setboundary()` was renamed to `set_boundary()`.
- The method `getdecodedpayload()` was removed. To get similar functionality, pass the value 1 to the `decode` flag of the `get_payload()` method.

- The method `getpayloadastext()` was removed. Similar functionality is supported by the `DecodedGenerator` class in the `email.generator` module.
- The method `getbodyastext()` was removed. You can get similar functionality by creating an iterator with `typed_subpart_iterator()` in the `email.iterators` module.

The `Parser` class has no differences in its public interface. It does have some additional smarts to recognize `message/delivery-status` type messages, which it represents as a `Message` instance containing separate `Message` subparts for each header block in the delivery status notification¹.

The `Generator` class has no differences in its public interface. There is a new class in the `email.generator` module though, called `DecodedGenerator` which provides most of the functionality previously available in the `Message`. `getpayloadastext()` method.

The following modules and classes have been changed:

- The `MIMEBase` class constructor arguments `_major` and `_minor` have changed to `_maintype` and `_subtype` respectively.
- The `Image` class/module has been renamed to `MIMEImage`. The `_minor` argument has been renamed to `_subtype`.
- The `Text` class/module has been renamed to `MIMEText`. The `_minor` argument has been renamed to `_subtype`.
- The `MessageRFC822` class/module has been renamed to `MIMEMessage`. Note that an earlier version of `mimelib` called this class/module `RFC822`, but that clashed with the Python standard library module `rfc822` on some case-insensitive file systems.

Also, the `MIMEMessage` class now represents any kind of MIME message with main type `message`. It takes an optional argument `_subtype` which is used to set the MIME subtype. `_subtype` defaults to `rfc822`.

`mimelib` provided some utility functions in its `address` and `date` modules. All of these functions have been moved to the `email.utils` module.

The `MsgReader` class/module has been removed. Its functionality is most closely supported in the `body_line_iterator()` function in the `email.iterators` module.

18.2 json — JSON encoder and decoder

버전 2.6에 추가.

JSON (JavaScript Object Notation), specified by **RFC 7159** (which obsoletes **RFC 4627**) and by **ECMA-404**, is a lightweight data interchange format inspired by JavaScript object literal syntax (although it is not a strict subset of JavaScript¹).

`json` exposes an API familiar to users of the standard library `marshal` and `pickle` modules.

Encoding basic Python object hierarchies:

```
>>> import json
>>> json.dumps(['foo', {'bar': ('baz', None, 1.0, 2)}])
'["foo", {"bar": ["baz", null, 1.0, 2]}]'
>>> print json.dumps("\"foo\\bar\"")
\"foo\\bar\"
>>> print json.dumps(u'\\u1234')
\"\\u1234\"
>>> print json.dumps('\\')
'\\'
```

(다음 페이지에 계속)

¹ Delivery Status Notifications (DSN) are defined in **RFC 1894**.

¹ As noted in the errata for **RFC 7159**, JSON permits literal U+2028 (LINE SEPARATOR) and U+2029 (PARAGRAPH SEPARATOR) characters in strings, whereas JavaScript (as of ECMAScript Edition 5.1) does not.

(이전 페이지에서 계속)

```

"\\"
>>> print json.dumps({"c": 0, "b": 0, "a": 0}, sort_keys=True)
{"a": 0, "b": 0, "c": 0}
>>> from StringIO import StringIO
>>> io = StringIO()
>>> json.dump(['streaming API'], io)
>>> io.getvalue()
'["streaming API"]'

```

Compact encoding:

```

>>> import json
>>> json.dumps([1,2,3,{ '4': 5, '6': 7}], separators=(',', ':'))
'[1,2,3,{"4":5,"6":7}]'

```

Pretty printing:

```

>>> import json
>>> print json.dumps({'4': 5, '6': 7}, sort_keys=True,
...                  indent=4, separators=(',', ' '))
{
    "4": 5,
    "6": 7
}

```

Decoding JSON:

```

>>> import json
>>> json.loads('["foo", {"bar":["baz", null, 1.0, 2]}]')
[u'foo', {u'bar': [u'baz', None, 1.0, 2]}]
>>> json.loads('"\"foo\\bar\"')
u'foo\x08ar'
>>> from StringIO import StringIO
>>> io = StringIO('["streaming API"]')
>>> json.load(io)
[u'streaming API']

```

Specializing JSON object decoding:

```

>>> import json
>>> def as_complex(dct):
...     if '__complex__' in dct:
...         return complex(dct['real'], dct['imag'])
...     return dct
...
>>> json.loads('{"__complex__": true, "real": 1, "imag": 2}',
...            object_hook=as_complex)
(1+2j)
>>> import decimal
>>> json.loads('1.1', parse_float=decimal.Decimal)
Decimal('1.1')

```

Extending *JSONEncoder*:

```

>>> import json
>>> class ComplexEncoder(json.JSONEncoder):

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

...     def default(self, obj):
...         if isinstance(obj, complex):
...             return [obj.real, obj.imag]
...         # Let the base class default method raise the TypeError
...         return json.JSONEncoder.default(self, obj)
...
>>> json.dumps(2 + 1j, cls=ComplexEncoder)
'[2.0, 1.0]'
>>> ComplexEncoder().encode(2 + 1j)
'[2.0, 1.0]'
>>> list(ComplexEncoder().iterencode(2 + 1j))
['[', '2.0', ',', '1.0', ']']

```

Using `json.tool` from the shell to validate and pretty-print:

```

$ echo '{"json":"obj"}' | python -m json.tool
{
    "json": "obj"
}
$ echo '{1.2:3.4}' | python -m json.tool
Expecting property name enclosed in double quotes: line 1 column 2 (char 1)

```

참고: JSON is a subset of [YAML 1.2](#). The JSON produced by this module's default settings (in particular, the default *separators* value) is also a subset of [YAML 1.0](#) and [1.1](#). This module can thus also be used as a [YAML](#) serializer.

18.2.1 Basic Usage

`json.dump(obj, fp, skipkeys=False, ensure_ascii=True, check_circular=True, allow_nan=True, cls=None, indent=None, separators=None, encoding="utf-8", default=None, sort_keys=False, **kw)`
 Serialize *obj* as a JSON formatted stream to *fp* (a `.write()`-supporting *file-like object*) using this *conversion table*.

If *skipkeys* is true (default: False), then dict keys that are not of a basic type (*str*, *unicode*, *int*, *long*, *float*, *bool*, None) will be skipped instead of raising a *TypeError*.

If *ensure_ascii* is true (the default), all non-ASCII characters in the output are escaped with `\uXXXX` sequences, and the result is a *str* instance consisting of ASCII characters only. If *ensure_ascii* is false, some chunks written to *fp* may be *unicode* instances. This usually happens because the input contains unicode strings or the *encoding* parameter is used. Unless *fp.write()* explicitly understands *unicode* (as in `codecs.getwriter()`) this is likely to cause an error.

If *check_circular* is false (default: True), then the circular reference check for container types will be skipped and a circular reference will result in an *OverflowError* (or worse).

If *allow_nan* is false (default: True), then it will be a *ValueError* to serialize out of range *float* values (nan, inf, -inf) in strict compliance of the JSON specification. If *allow_nan* is true, their JavaScript equivalents (NaN, Infinity, -Infinity) will be used.

If *indent* is a non-negative integer, then JSON array elements and object members will be pretty-printed with that indent level. An indent level of 0, or negative, will only insert newlines. None (the default) selects the most compact representation.

참고: Since the default item separator is `,` , the output might include trailing whitespace when *indent* is

specified. You can use `separators=(', ', ': ')` to avoid this.

If specified, *separators* should be an (*item_separator*, *key_separator*) tuple. By default, `(' ', ': ')` are used. To get the most compact JSON representation, you should specify `(' ', ': ')` to eliminate whitespace.

encoding is the character encoding for str instances, default is UTF-8.

If specified, *default* should be a function that gets called for objects that can't otherwise be serialized. It should return a JSON encodable version of the object or raise a `TypeError`. If not specified, `TypeError` is raised.

If *sort_keys* is true (default: `False`), then the output of dictionaries will be sorted by key.

To use a custom `JSONEncoder` subclass (e.g. one that overrides the `default()` method to serialize additional types), specify it with the *cls* kwarg; otherwise `JSONEncoder` is used.

참고: Unlike `pickle` and `marshal`, JSON is not a framed protocol so trying to serialize more objects with repeated calls to `dump()` and the same *fp* will result in an invalid JSON file.

`json.dumps(obj, skipkeys=False, ensure_ascii=True, check_circular=True, allow_nan=True, cls=None, indent=None, separators=None, encoding="utf-8", default=None, sort_keys=False, **kw)`

Serialize *obj* to a JSON formatted *str* using this [conversion table](#). If *ensure_ascii* is false, the result may contain non-ASCII characters and the return value may be a `unicode` instance.

The arguments have the same meaning as in `dump()`.

참고: Keys in key/value pairs of JSON are always of the type `str`. When a dictionary is converted into JSON, all the keys of the dictionary are coerced to strings. As a result of this, if a dictionary is converted into JSON and then back into a dictionary, the dictionary may not equal the original one. That is, `loads(dumps(x)) != x` if *x* has non-string keys.

`json.load(fp[, encoding[, cls[, object_hook[, parse_float[, parse_int[, parse_constant[, object_pairs_hook[, **kw]]]]]]])`

Deserialize *fp* (a `.read()`-supporting *file-like object* containing a JSON document) to a Python object using this [conversion table](#).

If the contents of *fp* are encoded with an ASCII based encoding other than UTF-8 (e.g. latin-1), then an appropriate *encoding* name must be specified. Encodings that are not ASCII based (such as UCS-2) are not allowed, and should be wrapped with `codecs.getreader(encoding)(fp)`, or simply decoded to a `unicode` object and passed to `loads()`.

object_hook is an optional function that will be called with the result of any object literal decoded (a `dict`). The return value of *object_hook* will be used instead of the `dict`. This feature can be used to implement custom decoders (e.g. `JSON-RPC` class hinting).

object_pairs_hook is an optional function that will be called with the result of any object literal decoded with an ordered list of pairs. The return value of *object_pairs_hook* will be used instead of the `dict`. This feature can be used to implement custom decoders that rely on the order that the key and value pairs are decoded (for example, `collections.OrderedDict()` will remember the order of insertion). If *object_hook* is also defined, the *object_pairs_hook* takes priority.

버전 2.7에서 변경: Added support for *object_pairs_hook*.

parse_float, if specified, will be called with the string of every JSON float to be decoded. By default, this is equivalent to `float(num_str)`. This can be used to use another datatype or parser for JSON floats (e.g. `decimal.Decimal`).

parse_int, if specified, will be called with the string of every JSON int to be decoded. By default, this is equivalent to `int(num_str)`. This can be used to use another datatype or parser for JSON integers (e.g. *float*).

parse_constant, if specified, will be called with one of the following strings: `'-Infinity'`, `'Infinity'`, `'NaN'`. This can be used to raise an exception if invalid JSON numbers are encountered.

버전 2.7에서 변경: *parse_constant* doesn't get called on `<null>`, `<true>`, `<false>` anymore.

To use a custom *JSONDecoder* subclass, specify it with the `cls` kwarg; otherwise *JSONDecoder* is used. Additional keyword arguments will be passed to the constructor of the class.

```
json.loads(s[, encoding[, cls[, object_hook[, parse_float[, parse_int[, parse_constant[, object_pairs_hook[,
                **kw]]]]]]]])
```

Deserialize *s* (a *str* or *unicode* instance containing a JSON document) to a Python object using this *conversion table*.

If *s* is a *str* instance and is encoded with an ASCII based encoding other than UTF-8 (e.g. latin-1), then an appropriate *encoding* name must be specified. Encodings that are not ASCII based (such as UCS-2) are not allowed and should be decoded to *unicode* first.

The other arguments have the same meaning as in *load()*.

18.2.2 Encoders and Decoders

```
class json.JSONDecoder([encoding[, object_hook[, parse_float[, parse_int[, parse_constant[, strict[,
                        object_pairs_hook]]]]]])
```

Simple JSON decoder.

Performs the following translations in decoding by default:

JSON	Python
object	dict
array	list
string	unicode
number (int)	int, long
number (real)	float
true	True
false	False
null	None

It also understands NaN, Infinity, and -Infinity as their corresponding *float* values, which is outside the JSON spec.

encoding determines the encoding used to interpret any *str* objects decoded by this instance (UTF-8 by default). It has no effect when decoding *unicode* objects.

Note that currently only encodings that are a superset of ASCII work, strings of other encodings should be passed in as *unicode*.

object_hook, if specified, will be called with the result of every JSON object decoded and its return value will be used in place of the given *dict*. This can be used to provide custom deserializations (e.g. to support JSON-RPC class hinting).

object_pairs_hook, if specified will be called with the result of every JSON object decoded with an ordered list of pairs. The return value of *object_pairs_hook* will be used instead of the *dict*. This feature can be used to implement custom decoders that rely on the order that the key and value pairs are decoded (for example, *collections.OrderedDict()* will remember the order of insertion). If *object_hook* is also defined, the *object_pairs_hook* takes priority.

버전 2.7에서 변경: Added support for *object_pairs_hook*.

parse_float, if specified, will be called with the string of every JSON float to be decoded. By default, this is equivalent to `float(num_str)`. This can be used to use another datatype or parser for JSON floats (e.g. *decimal.Decimal*).

parse_int, if specified, will be called with the string of every JSON int to be decoded. By default, this is equivalent to `int(num_str)`. This can be used to use another datatype or parser for JSON integers (e.g. *float*).

parse_constant, if specified, will be called with one of the following strings: `'-Infinity'`, `'Infinity'`, `'NaN'`. This can be used to raise an exception if invalid JSON numbers are encountered.

If *strict* is false (`True` is the default), then control characters will be allowed inside strings. Control characters in this context are those with character codes in the 0–31 range, including `'\t'` (tab), `'\n'`, `'\r'` and `'\0'`.

If the data being deserialized is not a valid JSON document, a *ValueError* will be raised.

decode (*s*)

Return the Python representation of *s* (a *str* or *unicode* instance containing a JSON document).

raw_decode (*s*)

Decode a JSON document from *s* (a *str* or *unicode* beginning with a JSON document) and return a 2-tuple of the Python representation and the index in *s* where the document ended.

This can be used to decode a JSON document from a string that may have extraneous data at the end.

```
class json.JSONEncoder([skipkeys[, ensure_ascii[, check_circular[, allow_nan[, sort_keys[, indent[,
                        separators[, encoding[, default]]]]]]]])
```

Extensible JSON encoder for Python data structures.

Supports the following objects and types by default:

Python	JSON
dict	object
list, tuple	array
str, unicode	string
int, long, float	number
True	true
False	false
None	null

To extend this to recognize other objects, subclass and implement a *default()* method with another method that returns a serializable object for *o* if possible, otherwise it should call the superclass implementation (to raise *TypeError*).

If *skipkeys* is false (the default), then it is a *TypeError* to attempt encoding of keys that are not *str*, *int*, *long*, *float* or *None*. If *skipkeys* is true, such items are simply skipped.

If *ensure_ascii* is true (the default), all non-ASCII characters in the output are escaped with `\uXXXX` sequences, and the results are *str* instances consisting of ASCII characters only. If *ensure_ascii* is false, a result may be a *unicode* instance. This usually happens if the input contains unicode strings or the *encoding* parameter is used.

If *check_circular* is true (the default), then lists, dicts, and custom encoded objects will be checked for circular references during encoding to prevent an infinite recursion (which would cause an *OverflowError*). Otherwise, no such check takes place.

If *allow_nan* is true (the default), then `NaN`, `Infinity`, and `-Infinity` will be encoded as such. This behavior is not JSON specification compliant, but is consistent with most JavaScript based encoders and decoders. Otherwise, it will be a *ValueError* to encode such floats.

If *sort_keys* is true (default: `False`), then the output of dictionaries will be sorted by key; this is useful for regression tests to ensure that JSON serializations can be compared on a day-to-day basis.

If *indent* is a non-negative integer (it is `None` by default), then JSON array elements and object members will be pretty-printed with that indent level. An indent level of 0 will only insert newlines. `None` is the most compact representation.

참고: Since the default item separator is `' , '`, the output might include trailing whitespace when *indent* is specified. You can use `separators=(' ', ': ')` to avoid this.

If specified, *separators* should be an (*item_separator*, *key_separator*) tuple. By default, `(' ', ': ')` are used. To get the most compact JSON representation, you should specify `(' ', ': ')` to eliminate whitespace.

If specified, *default* should be a function that gets called for objects that can't otherwise be serialized. It should return a JSON encodable version of the object or raise a `TypeError`. If not specified, `TypeError` is raised.

If *encoding* is not `None`, then all input strings will be transformed into unicode using that encoding prior to JSON-encoding. The default is UTF-8.

default (*o*)

Implement this method in a subclass such that it returns a serializable object for *o*, or calls the base implementation (to raise a `TypeError`).

For example, to support arbitrary iterators, you could implement *default* like this:

```
def default(self, o):
    try:
        iterable = iter(o)
    except TypeError:
        pass
    else:
        return list(iterable)
    # Let the base class default method raise the TypeError
    return JSONEncoder.default(self, o)
```

encode (*o*)

Return a JSON string representation of a Python data structure, *o*. For example:

```
>>> JSONEncoder().encode({"foo": ["bar", "baz"]})
'{"foo": ["bar", "baz"]}'
```

iterencode (*o*)

Encode the given object, *o*, and yield each string representation as available. For example:

```
for chunk in JSONEncoder().iterencode(bigobject):
    mysocket.write(chunk)
```

18.2.3 Standard Compliance and Interoperability

The JSON format is specified by [RFC 7159](#) and by [ECMA-404](#). This section details this module's level of compliance with the RFC. For simplicity, *JSONEncoder* and *JSONDecoder* subclasses, and parameters other than those explicitly mentioned, are not considered.

This module does not comply with the RFC in a strict fashion, implementing some extensions that are valid JavaScript but not valid JSON. In particular:

- Infinite and NaN number values are accepted and output;
- Repeated names within an object are accepted, and only the value of the last name-value pair is used.

Since the RFC permits RFC-compliant parsers to accept input texts that are not RFC-compliant, this module's deserializer is technically RFC-compliant under default settings.

Character Encodings

The RFC requires that JSON be represented using either UTF-8, UTF-16, or UTF-32, with UTF-8 being the recommended default for maximum interoperability. Accordingly, this module uses UTF-8 as the default for its *encoding* parameter.

This module's deserializer only directly works with ASCII-compatible encodings; UTF-16, UTF-32, and other ASCII-incompatible encodings require the use of workarounds described in the documentation for the deserializer's *encoding* parameter.

As permitted, though not required, by the RFC, this module's serializer sets *ensure_ascii=True* by default, thus escaping the output so that the resulting strings only contain ASCII characters.

The RFC prohibits adding a byte order mark (BOM) to the start of a JSON text, and this module's serializer does not add a BOM to its output. The RFC permits, but does not require, JSON deserializers to ignore an initial BOM in their input. This module's deserializer raises a *ValueError* when an initial BOM is present.

The RFC does not explicitly forbid JSON strings which contain byte sequences that don't correspond to valid Unicode characters (e.g. unpaired UTF-16 surrogates), but it does note that they may cause interoperability problems. By default, this module accepts and outputs (when present in the original *str*) code points for such sequences.

Infinite and NaN Number Values

The RFC does not permit the representation of infinite or NaN number values. Despite that, by default, this module accepts and outputs *Infinity*, *-Infinity*, and *NaN* as if they were valid JSON number literal values:

```
>>> # Neither of these calls raises an exception, but the results are not valid JSON
>>> json.dumps(float('-inf'))
'-Infinity'
>>> json.dumps(float('nan'))
'NaN'
>>> # Same when deserializing
>>> json.loads('-Infinity')
-inf
>>> json.loads('NaN')
nan
```

In the serializer, the *allow_nan* parameter can be used to alter this behavior. In the deserializer, the *parse_constant* parameter can be used to alter this behavior.

Repeated Names Within an Object

The RFC specifies that the names within a JSON object should be unique, but does not mandate how repeated names in JSON objects should be handled. By default, this module does not raise an exception; instead, it ignores all but the last name-value pair for a given name:

```
>>> weird_json = '{"x": 1, "x": 2, "x": 3}'
>>> json.loads(weird_json)
{'u'x': 3}
```

The *object_pairs_hook* parameter can be used to alter this behavior.

Top-level Non-Object, Non-Array Values

The old version of JSON specified by the obsolete [RFC 4627](#) required that the top-level value of a JSON text must be either a JSON object or array (Python *dict* or *list*), and could not be a JSON null, boolean, number, or string value. [RFC 7159](#) removed that restriction, and this module does not and has never implemented that restriction in either its serializer or its deserializer.

Regardless, for maximum interoperability, you may wish to voluntarily adhere to the restriction yourself.

Implementation Limitations

Some JSON deserializer implementations may set limits on:

- the size of accepted JSON texts
- the maximum level of nesting of JSON objects and arrays
- the range and precision of JSON numbers
- the content and maximum length of JSON strings

This module does not impose any such limits beyond those of the relevant Python datatypes themselves or the Python interpreter itself.

When serializing to JSON, beware any such limitations in applications that may consume your JSON. In particular, it is common for JSON numbers to be deserialized into IEEE 754 double precision numbers and thus subject to that representation's range and precision limitations. This is especially relevant when serializing Python *int* values of extremely large magnitude, or when serializing instances of «exotic» numerical types such as *decimal.Decimal*.

18.3 mailcap — Mailcap file handling

Source code: [Lib/mailcap.py](#)

Mailcap files are used to configure how MIME-aware applications such as mail readers and Web browsers react to files with different MIME types. (The name «mailcap» is derived from the phrase «mail capability».) For example, a mailcap file might contain a line like `video/mpeg; xmpeg %s`. Then, if the user encounters an email message or Web document with the MIME type `video/mpeg`, `%s` will be replaced by a filename (usually one belonging to a temporary file) and the `xmpeg` program can be automatically started to view the file.

The mailcap format is documented in [RFC 1524](#), «A User Agent Configuration Mechanism For Multimedia Mail Format Information, » but is not an Internet standard. However, mailcap files are supported on most Unix systems.

`mailcap.findmatch(caps, MIMEtype[, key[, filename[, plist]]])`

Return a 2-tuple; the first element is a string containing the command line to be executed (which can be passed to `os.system()`), and the second element is the mailcap entry for a given MIME type. If no matching MIME type can be found, `(None, None)` is returned.

key is the name of the field desired, which represents the type of activity to be performed; the default value is `<view>`, since in the most common case you simply want to view the body of the MIME-typed data. Other possible values might be `<compose>` and `<edit>`, if you wanted to create a new body of the given MIME type or alter the existing body data. See [RFC 1524](#) for a complete list of these fields.

filename is the filename to be substituted for `%s` in the command line; the default value is `'/dev/null'` which is almost certainly not what you want, so usually you'll override it by specifying a filename.

plist can be a list containing named parameters; the default value is simply an empty list. Each entry in the list must be a string containing the parameter name, an equals sign (`'='`), and the parameter's value. Mailcap entries can contain named parameters like `%{foo}`, which will be replaced by the value of the parameter named `<foo>`. For example, if the command line `showpartial %{id} %{number} %{total}` was in a mailcap file, and *plist* was set to `['id=1', 'number=2', 'total=3']`, the resulting command line would be `'showpartial 1 2 3'`.

In a mailcap file, the `<test>` field can optionally be specified to test some external condition (such as the machine architecture, or the window system in use) to determine whether or not the mailcap line applies. `findmatch()` will automatically check such conditions and skip the entry if the check fails.

`mailcap.getcaps()`

Returns a dictionary mapping MIME types to a list of mailcap file entries. This dictionary must be passed to the `findmatch()` function. An entry is stored as a list of dictionaries, but it shouldn't be necessary to know the details of this representation.

The information is derived from all of the mailcap files found on the system. Settings in the user's mailcap file `$HOME/.mailcap` will override settings in the system mailcap files `/etc/mailcap`, `/usr/etc/mailcap`, and `/usr/local/etc/mailcap`.

An example usage:

```
>>> import mailcap
>>> d = mailcap.getcaps()
>>> mailcap.findmatch(d, 'video/mpeg', filename='tmp1223')
('xmpeg tmp1223', {'view': 'xmpeg %s'})
```

18.4 mailbox — Manipulate mailboxes in various formats

This module defines two classes, *Mailbox* and *Message*, for accessing and manipulating on-disk mailboxes and the messages they contain. *Mailbox* offers a dictionary-like mapping from keys to messages. *Message* extends the *email.message* module's *Message* class with format-specific state and behavior. Supported mailbox formats are Maildir, mbox, MH, Babyl, and MMDF.

더 보기:

Module *email* Represent and manipulate messages.

18.4.1 Mailbox objects

class mailbox.Mailbox

A mailbox, which may be inspected and modified.

The *Mailbox* class defines an interface and is not intended to be instantiated. Instead, format-specific subclasses should inherit from *Mailbox* and your code should instantiate a particular subclass.

The *Mailbox* interface is dictionary-like, with small keys corresponding to messages. Keys are issued by the *Mailbox* instance with which they will be used and are only meaningful to that *Mailbox* instance. A key continues to identify a message even if the corresponding message is modified, such as by replacing it with another message.

Messages may be added to a *Mailbox* instance using the set-like method *add()* and removed using a *del* statement or the set-like methods *remove()* and *discard()*.

Mailbox interface semantics differ from dictionary semantics in some noteworthy ways. Each time a message is requested, a new representation (typically a *Message* instance) is generated based upon the current state of the mailbox. Similarly, when a message is added to a *Mailbox* instance, the provided message representation's contents are copied. In neither case is a reference to the message representation kept by the *Mailbox* instance.

The default *Mailbox* iterator iterates over message representations, not keys as the default dictionary iterator does. Moreover, modification of a mailbox during iteration is safe and well-defined. Messages added to the mailbox after an iterator is created will not be seen by the iterator. Messages removed from the mailbox before the iterator yields them will be silently skipped, though using a key from an iterator may result in a *KeyError* exception if the corresponding message is subsequently removed.

경고: Be very cautious when modifying mailboxes that might be simultaneously changed by some other process. The safest mailbox format to use for such tasks is Maildir; try to avoid using single-file formats such as mbox for concurrent writing. If you're modifying a mailbox, you *must* lock it by calling the *lock()* and *unlock()* methods *before* reading any messages in the file or making any changes by adding or deleting a message. Failing to lock the mailbox runs the risk of losing messages or corrupting the entire mailbox.

Mailbox instances have the following methods:

add (*message*)

Add *message* to the mailbox and return the key that has been assigned to it.

Parameter *message* may be a *Message* instance, an *email.message.Message* instance, a string, or a file-like object (which should be open in text mode). If *message* is an instance of the appropriate format-specific *Message* subclass (e.g., if it's an *mboxMessage* instance and this is an *mbox* instance), its format-specific information is used. Otherwise, reasonable defaults for format-specific information are used.

remove (*key*)

__delitem__ (*key*)

discard (*key*)

Delete the message corresponding to *key* from the mailbox.

If no such message exists, a *KeyError* exception is raised if the method was called as *remove()* or *__delitem__()* but no exception is raised if the method was called as *discard()*. The behavior of *discard()* may be preferred if the underlying mailbox format supports concurrent modification by other processes.

__setitem__ (*key*, *message*)

Replace the message corresponding to *key* with *message*. Raise a *KeyError* exception if no message already corresponds to *key*.

As with `add()`, parameter *message* may be a *Message* instance, an *email.message.Message* instance, a string, or a file-like object (which should be open in text mode). If *message* is an instance of the appropriate format-specific *Message* subclass (e.g., if it's an *mbboxMessage* instance and this is an *mbbox* instance), its format-specific information is used. Otherwise, the format-specific information of the message that currently corresponds to *key* is left unchanged.

iterkeys()

keys()

Return an iterator over all keys if called as *iterkeys()* or return a list of keys if called as *keys()*.

intervalues()

__iter__()

values()

Return an iterator over representations of all messages if called as *intervalues()* or *__iter__()* or return a list of such representations if called as *values()*. The messages are represented as instances of the appropriate format-specific *Message* subclass unless a custom message factory was specified when the *Mailbox* instance was initialized.

참고: The behavior of *__iter__()* is unlike that of dictionaries, which iterate over keys.

iteritems()

items()

Return an iterator over (*key*, *message*) pairs, where *key* is a key and *message* is a message representation, if called as *iteritems()* or return a list of such pairs if called as *items()*. The messages are represented as instances of the appropriate format-specific *Message* subclass unless a custom message factory was specified when the *Mailbox* instance was initialized.

get(key, default=None)

__getitem__(key)

Return a representation of the message corresponding to *key*. If no such message exists, *default* is returned if the method was called as *get()* and a *KeyError* exception is raised if the method was called as *__getitem__()*. The message is represented as an instance of the appropriate format-specific *Message* subclass unless a custom message factory was specified when the *Mailbox* instance was initialized.

get_message(key)

Return a representation of the message corresponding to *key* as an instance of the appropriate format-specific *Message* subclass, or raise a *KeyError* exception if no such message exists.

get_string(key)

Return a string representation of the message corresponding to *key*, or raise a *KeyError* exception if no such message exists.

get_file(key)

Return a file-like representation of the message corresponding to *key*, or raise a *KeyError* exception if no such message exists. The file-like object behaves as if open in binary mode. This file should be closed once it is no longer needed.

참고: Unlike other representations of messages, file-like representations are not necessarily independent of the *Mailbox* instance that created them or of the underlying mailbox. More specific documentation is provided by each subclass.

has_key(key)

__contains__(key)

Return True if *key* corresponds to a message, False otherwise.

__len__()

Return a count of messages in the mailbox.

clear()

Delete all messages from the mailbox.

pop(*key*[, *default*])

Return a representation of the message corresponding to *key* and delete the message. If no such message exists, return *default* if it was supplied or else raise a `KeyError` exception. The message is represented as an instance of the appropriate format-specific `Message` subclass unless a custom message factory was specified when the `Mailbox` instance was initialized.

popitem()

Return an arbitrary (*key*, *message*) pair, where *key* is a key and *message* is a message representation, and delete the corresponding message. If the mailbox is empty, raise a `KeyError` exception. The message is represented as an instance of the appropriate format-specific `Message` subclass unless a custom message factory was specified when the `Mailbox` instance was initialized.

update(*arg*)

Parameter *arg* should be a *key*-to-*message* mapping or an iterable of (*key*, *message*) pairs. Updates the mailbox so that, for each given *key* and *message*, the message corresponding to *key* is set to *message* as if by using `__setitem__()`. As with `__setitem__()`, each *key* must already correspond to a message in the mailbox or else a `KeyError` exception will be raised, so in general it is incorrect for *arg* to be a `Mailbox` instance.

참고: Unlike with dictionaries, keyword arguments are not supported.

flush()

Write any pending changes to the filesystem. For some `Mailbox` subclasses, changes are always written immediately and `flush()` does nothing, but you should still make a habit of calling this method.

lock()

Acquire an exclusive advisory lock on the mailbox so that other processes know not to modify it. An `ExternalClashError` is raised if the lock is not available. The particular locking mechanisms used depend upon the mailbox format. You should *always* lock the mailbox before making any modifications to its contents.

unlock()

Release the lock on the mailbox, if any.

close()

Flush the mailbox, unlock it if necessary, and close any open files. For some `Mailbox` subclasses, this method does nothing.

Maildir

class mailbox.**Maildir**(*dirname*, *factory*=rfc822.Message, *create*=True)

A subclass of `Mailbox` for mailboxes in Maildir format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is None, `MaildirMessage` is used as the default message representation. If *create* is True, the mailbox is created if it does not exist.

It is for historical reasons that *factory* defaults to `rfc822.Message` and that *dirname* is named as such rather than *path*. For a `Maildir` instance that behaves like instances of other `Mailbox` subclasses, set *factory* to None.

Maildir is a directory-based mailbox format invented for the qmail mail transfer agent and now widely supported by other programs. Messages in a Maildir mailbox are stored in separate files within a common directory structure.

This design allows Maildir mailboxes to be accessed and modified by multiple unrelated programs without data corruption, so file locking is unnecessary.

Maildir mailboxes contain three subdirectories, namely: `tmp`, `new`, and `cur`. Messages are created momentarily in the `tmp` subdirectory and then moved to the `new` subdirectory to finalize delivery. A mail user agent may subsequently move the message to the `cur` subdirectory and store information about the state of the message in a special `«info»` section appended to its file name.

Folders of the style introduced by the Courier mail transfer agent are also supported. Any subdirectory of the main mailbox is considered a folder if `'.'` is the first character in its name. Folder names are represented by *Maildir* without the leading `'.'`. Each folder is itself a Maildir mailbox but should not contain other folders. Instead, a logical nesting is indicated using `'.'` to delimit levels, e.g., `«Archived.2005.07»`.

참고: The Maildir specification requires the use of a colon (`:`) in certain message file names. However, some operating systems do not permit this character in file names. If you wish to use a Maildir-like format on such an operating system, you should specify another character to use instead. The exclamation point (`!`) is a popular choice. For example:

```
import mailbox
mailbox.Maildir.colon = '!'
```

The `colon` attribute may also be set on a per-instance basis.

Maildir instances have all of the methods of *Mailbox* in addition to the following:

list_folders()

Return a list of the names of all folders.

get_folder(folder)

Return a *Maildir* instance representing the folder whose name is *folder*. A *NoSuchMailboxError* exception is raised if the folder does not exist.

add_folder(folder)

Create a folder whose name is *folder* and return a *Maildir* instance representing it.

remove_folder(folder)

Delete the folder whose name is *folder*. If the folder contains any messages, a *NotEmptyError* exception will be raised and the folder will not be deleted.

clean()

Delete temporary files from the mailbox that have not been accessed in the last 36 hours. The Maildir specification says that mail-reading programs should do this occasionally.

Some *Mailbox* methods implemented by *Maildir* deserve special remarks:

add(message)

__setitem__(key, message)

update(arg)

경고: These methods generate unique file names based upon the current process ID. When using multiple threads, undetected name clashes may occur and cause corruption of the mailbox unless threads are coordinated to avoid using these methods to manipulate the same mailbox simultaneously.

flush()

All changes to Maildir mailboxes are immediately applied, so this method does nothing.

`lock()`

`unlock()`

Maildir mailboxes do not support (or require) locking, so these methods do nothing.

`close()`

Maildir instances do not keep any open files and the underlying mailboxes do not support locking, so this method does nothing.

`get_file(key)`

Depending upon the host platform, it may not be possible to modify or remove the underlying message while the returned file remains open.

더 보기:

maildir man page from qmail The original specification of the format.

Using maildir format Notes on Maildir by its inventor. Includes an updated name-creation scheme and details on *⟨info⟩* semantics.

maildir man page from Courier Another specification of the format. Describes a common extension for supporting folders.

mbx

class `mailbox.mbx` (*path*, *factory=None*, *create=True*)

A subclass of *Mailbox* for mailboxes in mbx format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is *None*, *mbxMessage* is used as the default message representation. If *create* is *True*, the mailbox is created if it does not exist.

The mbx format is the classic format for storing mail on Unix systems. All messages in an mbx mailbox are stored in a single file with the beginning of each message indicated by a line whose first five characters are *⟨From* *⟨*.

Several variations of the mbx format exist to address perceived shortcomings in the original. In the interest of compatibility, *mbx* implements the original format, which is sometimes referred to as *mbxo*. This means that the *Content-Length* header, if present, is ignored and that any occurrences of *⟨From* *⟩* at the beginning of a line in a message body are transformed to *⟨>From* *⟩* when storing the message, although occurrences of *⟨>From* *⟩* are not transformed to *⟨From* *⟩* when reading the message.

Some *Mailbox* methods implemented by *mbx* deserve special remarks:

`get_file(key)`

Using the file after calling `flush()` or `close()` on the *mbx* instance may yield unpredictable results or raise an exception.

`lock()`

`unlock()`

Three locking mechanisms are used—dot locking and, if available, the `flock()` and `lockf()` system calls.

더 보기:

mbx man page from qmail A specification of the format and its variations.

mbx man page from tin Another specification of the format, with details on locking.

Configuring Netscape Mail on Unix: Why The Content-Length Format is Bad An argument for using the original mbx format rather than a variation.

⟨mbx⟩ is a family of several mutually incompatible mailbox formats A history of mbx variations.

MH

class mailbox.**MH** (*path*, *factory*=None, *create*=True)

A subclass of *Mailbox* for mailboxes in MH format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is None, *MHMessage* is used as the default message representation. If *create* is True, the mailbox is created if it does not exist.

MH is a directory-based mailbox format invented for the MH Message Handling System, a mail user agent. Each message in an MH mailbox resides in its own file. An MH mailbox may contain other MH mailboxes (called *folders*) in addition to messages. Folders may be nested indefinitely. MH mailboxes also support *sequences*, which are named lists used to logically group messages without moving them to sub-folders. Sequences are defined in a file called *.mh_sequences* in each folder.

The *MH* class manipulates MH mailboxes, but it does not attempt to emulate all of *mh*'s behaviors. In particular, it does not modify and is not affected by the *context* or *.mh_profile* files that are used by *mh* to store its state and configuration.

MH instances have all of the methods of *Mailbox* in addition to the following:

list_folders ()

Return a list of the names of all folders.

get_folder (*folder*)

Return an *MH* instance representing the folder whose name is *folder*. A *NoSuchMailboxError* exception is raised if the folder does not exist.

add_folder (*folder*)

Create a folder whose name is *folder* and return an *MH* instance representing it.

remove_folder (*folder*)

Delete the folder whose name is *folder*. If the folder contains any messages, a *NotEmptyError* exception will be raised and the folder will not be deleted.

get_sequences ()

Return a dictionary of sequence names mapped to key lists. If there are no sequences, the empty dictionary is returned.

set_sequences (*sequences*)

Re-define the sequences that exist in the mailbox based upon *sequences*, a dictionary of names mapped to key lists, like returned by *get_sequences* ().

pack ()

Rename messages in the mailbox as necessary to eliminate gaps in numbering. Entries in the sequences list are updated correspondingly.

참고: Already-issued keys are invalidated by this operation and should not be subsequently used.

Some *Mailbox* methods implemented by *MH* deserve special remarks:

remove (*key*)

__delitem__ (*key*)

discard (*key*)

These methods immediately delete the message. The MH convention of marking a message for deletion by prepending a comma to its name is not used.

lock ()

unlock ()

Three locking mechanisms are used—dot locking and, if available, the *flock* () and *lockf* () system

calls. For MH mailboxes, locking the mailbox means locking the `.mh_sequences` file and, only for the duration of any operations that affect them, locking individual message files.

get_file (*key*)

Depending upon the host platform, it may not be possible to remove the underlying message while the returned file remains open.

flush ()

All changes to MH mailboxes are immediately applied, so this method does nothing.

close ()

MH instances do not keep any open files, so this method is equivalent to `unlock()`.

더 보기:

nmh - Message Handling System Home page of **nmh**, an updated version of the original **mh**.

MH & nmh: Email for Users & Programmers A GPL-licensed book on **mh** and **nmh**, with some information on the mailbox format.

Babyl

class mailbox.**Babyl** (*path*, *factory*=None, *create*=True)

A subclass of *Mailbox* for mailboxes in Babyl format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is None, *BabylMessage* is used as the default message representation. If *create* is True, the mailbox is created if it does not exist.

Babyl is a single-file mailbox format used by the Rmail mail user agent included with Emacs. The beginning of a message is indicated by a line containing the two characters Control-Underscore ('`\037`') and Control-L ('`\014`'). The end of a message is indicated by the start of the next message or, in the case of the last message, a line containing a Control-Underscore ('`\037`') character.

Messages in a Babyl mailbox have two sets of headers, original headers and so-called visible headers. Visible headers are typically a subset of the original headers that have been reformatted or abridged to be more attractive. Each message in a Babyl mailbox also has an accompanying list of *labels*, or short strings that record extra information about the message, and a list of all user-defined labels found in the mailbox is kept in the Babyl options section.

Babyl instances have all of the methods of *Mailbox* in addition to the following:

get_labels ()

Return a list of the names of all user-defined labels used in the mailbox.

참고: The actual messages are inspected to determine which labels exist in the mailbox rather than consulting the list of labels in the Babyl options section, but the Babyl section is updated whenever the mailbox is modified.

Some *Mailbox* methods implemented by *Babyl* deserve special remarks:

get_file (*key*)

In Babyl mailboxes, the headers of a message are not stored contiguously with the body of the message. To generate a file-like representation, the headers and body are copied together into a *StringIO* instance (from the *StringIO* module), which has an API identical to that of a file. As a result, the file-like object is truly independent of the underlying mailbox but does not save memory compared to a string representation.

lock ()

unlock()

Three locking mechanisms are used—dot locking and, if available, the `flock()` and `lockf()` system calls.

더 보기:

Format of Version 5 Babyl Files A specification of the Babyl format.

Reading Mail with Rmail The Rmail manual, with some information on Babyl semantics.

MMDF

class `mailbox.MMDF` (*path*, *factory=None*, *create=True*)

A subclass of `Mailbox` for mailboxes in MMDF format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is `None`, `MMDFMessage` is used as the default message representation. If *create* is `True`, the mailbox is created if it does not exist.

MMDF is a single-file mailbox format invented for the Multichannel Memorandum Distribution Facility, a mail transfer agent. Each message is in the same form as an mbox message but is bracketed before and after by lines containing four Control-A (`'\001'`) characters. As with the mbox format, the beginning of each message is indicated by a line whose first five characters are `<<From <`, but additional occurrences of `<<From >` are not transformed to `<>From >` when storing messages because the extra message separator lines prevent mistaking such occurrences for the starts of subsequent messages.

Some `Mailbox` methods implemented by `MMDF` deserve special remarks:

get_file (*key*)

Using the file after calling `flush()` or `close()` on the `MMDF` instance may yield unpredictable results or raise an exception.

lock()

unlock()

Three locking mechanisms are used—dot locking and, if available, the `flock()` and `lockf()` system calls.

더 보기:

mmdf man page from tin A specification of MMDF format from the documentation of tin, a newsreader.

MMDF A Wikipedia article describing the Multichannel Memorandum Distribution Facility.

18.4.2 Message objects

class `mailbox.Message` (*[message]*)

A subclass of the `email.message` module's `Message`. Subclasses of `mailbox.Message` add mailbox-format-specific state and behavior.

If *message* is omitted, the new instance is created in a default, empty state. If *message* is an `email.message.Message` instance, its contents are copied; furthermore, any format-specific information is converted insofar as possible if *message* is a `Message` instance. If *message* is a string or a file, it should contain an **RFC 2822**-compliant message, which is read and parsed.

The format-specific state and behaviors offered by subclasses vary, but in general it is only the properties that are not specific to a particular mailbox that are supported (although presumably the properties are specific to a particular mailbox format). For example, file offsets for single-file mailbox formats and file names for directory-based mailbox formats are not retained, because they are only applicable to the original mailbox. But state such as

whether a message has been read by the user or marked as important is retained, because it applies to the message itself.

There is no requirement that *Message* instances be used to represent messages retrieved using *Mailbox* instances. In some situations, the time and memory required to generate *Message* representations might not be acceptable. For such situations, *Mailbox* instances also offer string and file-like representations, and a custom message factory may be specified when a *Mailbox* instance is initialized.

MaildirMessage

class mailbox.**MaildirMessage** (*[message]*)

A message with Maildir-specific behaviors. Parameter *message* has the same meaning as with the *Message* constructor.

Typically, a mail user agent application moves all of the messages in the *new* subdirectory to the *cur* subdirectory after the first time the user opens and closes the mailbox, recording that the messages are old whether or not they've actually been read. Each message in *cur* has an *«info»* section added to its file name to store information about its state. (Some mail readers may also add an *«info»* section to messages in *new*.) The *«info»* section may take one of two forms: it may contain *«2,»* followed by a list of standardized flags (e.g., *«2,FR»*) or it may contain *«1,»* followed by so-called experimental information. Standard flags for Maildir messages are as follows:

Flag	Meaning	Explanation
D	Draft	Under composition
F	Flagged	Marked as important
P	Passed	Forwarded, resent, or bounced
R	Replied	Replied to
S	Seen	Read
T	Trashed	Marked for subsequent deletion

MaildirMessage instances offer the following methods:

get_subdir ()

Return either *«new»* (if the message should be stored in the *new* subdirectory) or *«cur»* (if the message should be stored in the *cur* subdirectory).

참고: A message is typically moved from *new* to *cur* after its mailbox has been accessed, whether or not the message is has been read. A message *msg* has been read if *"S"* in *msg.get_flags()* is True.

set_subdir (*subdir*)

Set the subdirectory the message should be stored in. Parameter *subdir* must be either *«new»* or *«cur»*.

get_flags ()

Return a string specifying the flags that are currently set. If the message complies with the standard Maildir format, the result is the concatenation in alphabetical order of zero or one occurrence of each of *'D'*, *'F'*, *'P'*, *'R'*, *'S'*, and *'T'*. The empty string is returned if no flags are set or if *«info»* contains experimental semantics.

set_flags (*flags*)

Set the flags specified by *flags* and unset all others.

add_flag (*flag*)

Set the flag(s) specified by *flag* without changing other flags. To add more than one flag at a time, *flag* may be a string of more than one character. The current *«info»* is overwritten whether or not it contains experimental information rather than flags.

remove_flag (*flag*)

Unset the flag(s) specified by *flag* without changing other flags. To remove more than one flag at a time, *flag* maybe a string of more than one character. If `⟨info⟩` contains experimental information rather than flags, the current `⟨info⟩` is not modified.

get_date ()

Return the delivery date of the message as a floating-point number representing seconds since the epoch.

set_date (*date*)

Set the delivery date of the message to *date*, a floating-point number representing seconds since the epoch.

get_info ()

Return a string containing the `⟨info⟩` for a message. This is useful for accessing and modifying `⟨info⟩` that is experimental (i.e., not a list of flags).

set_info (*info*)

Set `⟨info⟩` to *info*, which should be a string.

When a *MaildirMessage* instance is created based upon an *mbxMessage* or *MMDFMessage* instance, the *Status* and *X-Status* headers are omitted and the following conversions take place:

Resulting state	<i>mbxMessage</i> or <i>MMDFMessage</i> state
<code>⟨cur⟩</code> subdirectory	O flag
F flag	F flag
R flag	A flag
S flag	R flag
T flag	D flag

When a *MaildirMessage* instance is created based upon an *MHMessage* instance, the following conversions take place:

Resulting state	<i>MHMessage</i> state
<code>⟨cur⟩</code> subdirectory	<code>⟨unseen⟩</code> sequence
<code>⟨cur⟩</code> subdirectory and S flag	no <code>⟨unseen⟩</code> sequence
F flag	<code>⟨flagged⟩</code> sequence
R flag	<code>⟨replied⟩</code> sequence

When a *MaildirMessage* instance is created based upon a *BabylMessage* instance, the following conversions take place:

Resulting state	<i>BabylMessage</i> state
<code>⟨cur⟩</code> subdirectory	<code>⟨unseen⟩</code> label
<code>⟨cur⟩</code> subdirectory and S flag	no <code>⟨unseen⟩</code> label
P flag	<code>⟨forwarded⟩</code> or <code>⟨resent⟩</code> label
R flag	<code>⟨answered⟩</code> label
T flag	<code>⟨deleted⟩</code> label

mboxMessage**class** mailbox.mboxMessage ([*message*])

A message with mbox-specific behaviors. Parameter *message* has the same meaning as with the *Message* constructor.

Messages in an mbox mailbox are stored together in a single file. The sender's envelope address and the time of delivery are typically stored in a line beginning with `<From >` that is used to indicate the start of a message, though there is considerable variation in the exact format of this data among mbox implementations. Flags that indicate the state of the message, such as whether it has been read or marked as important, are typically stored in *Status* and *X-Status* headers.

Conventional flags for mbox messages are as follows:

Flag	Meaning	Explanation
R	Read	Read
O	Old	Previously detected by MUA
D	Deleted	Marked for subsequent deletion
F	Flagged	Marked as important
A	Answered	Replied to

The `<R>` and `<O>` flags are stored in the *Status* header, and the `<D>`, `<F>`, and `<A>` flags are stored in the *X-Status* header. The flags and headers typically appear in the order mentioned.

mboxMessage instances offer the following methods:

get_from()

Return a string representing the `<From >` line that marks the start of the message in an mbox mailbox. The leading `<From >` and the trailing newline are excluded.

set_from (*from_*, *time_=None*)

Set the `<From >` line to *from_*, which should be specified without a leading `<From >` or trailing newline. For convenience, *time_* may be specified and will be formatted appropriately and appended to *from_*. If *time_* is specified, it should be a *time.struct_time* instance, a tuple suitable for passing to *time.strftime()*, or True (to use *time.gmtime()*).

get_flags()

Return a string specifying the flags that are currently set. If the message complies with the conventional format, the result is the concatenation in the following order of zero or one occurrence of each of 'R', 'O', 'D', 'F', and 'A'.

set_flags (*flags*)

Set the flags specified by *flags* and unset all others. Parameter *flags* should be the concatenation in any order of zero or more occurrences of each of 'R', 'O', 'D', 'F', and 'A'.

add_flag (*flag*)

Set the flag(s) specified by *flag* without changing other flags. To add more than one flag at a time, *flag* may be a string of more than one character.

remove_flag (*flag*)

Unset the flag(s) specified by *flag* without changing other flags. To remove more than one flag at a time, *flag* maybe a string of more than one character.

When an *mboxMessage* instance is created based upon a *MaiIdirMessage* instance, a `<From >` line is generated based upon the *MaiIdirMessage* instance's delivery date, and the following conversions take place:

Resulting state	<i>MaiDirMessage</i> state
R flag	S flag
O flag	《cur》 subdirectory
D flag	T flag
F flag	F flag
A flag	R flag

When an *mbxMessage* instance is created based upon an *MHMessage* instance, the following conversions take place:

Resulting state	<i>MHMessage</i> state
R flag and O flag	no 《unseen》 sequence
O flag	《unseen》 sequence
F flag	《flagged》 sequence
A flag	《replied》 sequence

When an *mbxMessage* instance is created based upon a *BabylMessage* instance, the following conversions take place:

Resulting state	<i>BabylMessage</i> state
R flag and O flag	no 《unseen》 label
O flag	《unseen》 label
D flag	《deleted》 label
A flag	《answered》 label

When a *Message* instance is created based upon an *MMDFMessage* instance, the 《From》 line is copied and all flags directly correspond:

Resulting state	<i>MMDFMessage</i> state
R flag	R flag
O flag	O flag
D flag	D flag
F flag	F flag
A flag	A flag

MHMessage

class mailbox.**MHMessage**(*[message]*)

A message with MH-specific behaviors. Parameter *message* has the same meaning as with the *Message* constructor.

MH messages do not support marks or flags in the traditional sense, but they do support sequences, which are logical groupings of arbitrary messages. Some mail reading programs (although not the standard **mh** and **nmh**) use sequences in much the same way flags are used with other formats, as follows:

Sequence	Explanation
unseen	Not read, but previously detected by MUA
replied	Replied to
flagged	Marked as important

MHMessage instances offer the following methods:

get_sequences ()

Return a list of the names of sequences that include this message.

set_sequences (*sequences*)

Set the list of sequences that include this message.

add_sequence (*sequence*)

Add *sequence* to the list of sequences that include this message.

remove_sequence (*sequence*)

Remove *sequence* from the list of sequences that include this message.

When an *MHMessage* instance is created based upon a *MaildirMessage* instance, the following conversions take place:

Resulting state	<i>MaildirMessage</i> state
《unseen》 sequence	no S flag
《replied》 sequence	R flag
《flagged》 sequence	F flag

When an *MHMessage* instance is created based upon an *mboxMessage* or *MMDFMessage* instance, the *Status* and *X-Status* headers are omitted and the following conversions take place:

Resulting state	<i>mboxMessage</i> or <i>MMDFMessage</i> state
《unseen》 sequence	no R flag
《replied》 sequence	A flag
《flagged》 sequence	F flag

When an *MHMessage* instance is created based upon a *BabylMessage* instance, the following conversions take place:

Resulting state	<i>BabylMessage</i> state
《unseen》 sequence	《unseen》 label
《replied》 sequence	《answered》 label

BabylMessage

class mailbox.**BabylMessage** ([*message*])

A message with Babyl-specific behaviors. Parameter *message* has the same meaning as with the *Message* constructor.

Certain message labels, called *attributes*, are defined by convention to have special meanings. The attributes are as follows:

Label	Explanation
unseen	Not read, but previously detected by MUA
deleted	Marked for subsequent deletion
filed	Copied to another file or mailbox
answered	Replied to
forwarded	Forwarded
edited	Modified by the user
resent	Resent

By default, Rmail displays only visible headers. The *Baby1Message* class, though, uses the original headers because they are more complete. Visible headers may be accessed explicitly if desired.

Baby1Message instances offer the following methods:

get_labels()

Return a list of labels on the message.

set_labels(labels)

Set the list of labels on the message to *labels*.

add_label(label)

Add *label* to the list of labels on the message.

remove_label(label)

Remove *label* from the list of labels on the message.

get_visible()

Return an *Message* instance whose headers are the message's visible headers and whose body is empty.

set_visible(visible)

Set the message's visible headers to be the same as the headers in *message*. Parameter *visible* should be a *Message* instance, an *email.message.Message* instance, a string, or a file-like object (which should be open in text mode).

update_visible()

When a *Baby1Message* instance's original headers are modified, the visible headers are not automatically modified to correspond. This method updates the visible headers as follows: each visible header with a corresponding original header is set to the value of the original header, each visible header without a corresponding original header is removed, and any of *Date*, *From*, *Reply-To*, *To*, *CC*, and *Subject* that are present in the original headers but not the visible headers are added to the visible headers.

When a *Baby1Message* instance is created based upon a *Mai1dirMessage* instance, the following conversions take place:

Resulting state	<i>Mai1dirMessage</i> state
《unseen》label	no S flag
《deleted》label	T flag
《answered》label	R flag
《forwarded》label	P flag

When a *Baby1Message* instance is created based upon an *mboxMessage* or *MMDFMMessage* instance, the *Status* and *X-Status* headers are omitted and the following conversions take place:

Resulting state	<i>mboxMessage</i> or <i>MMDFMMessage</i> state
《unseen》label	no R flag
《deleted》label	D flag
《answered》label	A flag

When a *Baby1Message* instance is created based upon an *MHMessage* instance, the following conversions take place:

Resulting state	<i>MHMessage</i> state
《unseen》label	《unseen》sequence
《answered》label	《replied》sequence

MMDFMessage**class** mailbox.**MMDFMessage** ([*message*])

A message with MMDF-specific behaviors. Parameter *message* has the same meaning as with the *Message* constructor.

As with message in an mbox mailbox, MMDF messages are stored with the sender's address and the delivery date in an initial line beginning with `From`. Likewise, flags that indicate the state of the message are typically stored in *Status* and *X-Status* headers.

Conventional flags for MMDF messages are identical to those of mbox message and are as follows:

Flag	Meaning	Explanation
R	Read	Read
O	Old	Previously detected by MUA
D	Deleted	Marked for subsequent deletion
F	Flagged	Marked as important
A	Answered	Replied to

The `R` and `O` flags are stored in the *Status* header, and the `D`, `F`, and `A` flags are stored in the *X-Status* header. The flags and headers typically appear in the order mentioned.

MMDFMessage instances offer the following methods, which are identical to those offered by *mboxMessage*:

get_from ()

Return a string representing the `From` line that marks the start of the message in an mbox mailbox. The leading `From` and the trailing newline are excluded.

set_from (*from_*, *time_*=None)

Set the `From` line to *from_*, which should be specified without a leading `From` or trailing newline. For convenience, *time_* may be specified and will be formatted appropriately and appended to *from_*. If *time_* is specified, it should be a *time.struct_time* instance, a tuple suitable for passing to *time.strftime* (), or True (to use *time.gmtime* ()).

get_flags ()

Return a string specifying the flags that are currently set. If the message complies with the conventional format, the result is the concatenation in the following order of zero or one occurrence of each of `'R'`, `'O'`, `'D'`, `'F'`, and `'A'`.

set_flags (*flags*)

Set the flags specified by *flags* and unset all others. Parameter *flags* should be the concatenation in any order of zero or more occurrences of each of `'R'`, `'O'`, `'D'`, `'F'`, and `'A'`.

add_flag (*flag*)

Set the flag(s) specified by *flag* without changing other flags. To add more than one flag at a time, *flag* may be a string of more than one character.

remove_flag (*flag*)

Unset the flag(s) specified by *flag* without changing other flags. To remove more than one flag at a time, *flag* may be a string of more than one character.

When an *MMDFMessage* instance is created based upon a *MaildirMessage* instance, a `From` line is generated based upon the *MaildirMessage* instance's delivery date, and the following conversions take place:

Resulting state	<i>MaiMdirMessage</i> state
R flag	S flag
O flag	《cur》 subdirectory
D flag	T flag
F flag	F flag
A flag	R flag

When an *MMDFMessage* instance is created based upon an *MHMessage* instance, the following conversions take place:

Resulting state	<i>MHMessage</i> state
R flag and O flag	no 《unseen》 sequence
O flag	《unseen》 sequence
F flag	《flagged》 sequence
A flag	《replied》 sequence

When an *MMDFMessage* instance is created based upon a *BabylMessage* instance, the following conversions take place:

Resulting state	<i>BabylMessage</i> state
R flag and O flag	no 《unseen》 label
O flag	《unseen》 label
D flag	《deleted》 label
A flag	《answered》 label

When an *MMDFMessage* instance is created based upon an *mbxMessage* instance, the 《From 》 line is copied and all flags directly correspond:

Resulting state	<i>mbxMessage</i> state
R flag	R flag
O flag	O flag
D flag	D flag
F flag	F flag
A flag	A flag

18.4.3 Exceptions

The following exception classes are defined in the *mailbox* module:

exception `mailbox.Error`

The based class for all other module-specific exceptions.

exception `mailbox.NoSuchMailboxError`

Raised when a mailbox is expected but is not found, such as when instantiating a *Mailbox* subclass with a path that does not exist (and with the *create* parameter set to `False`), or when opening a folder that does not exist.

exception `mailbox.NotEmptyError`

Raised when a mailbox is not empty but is expected to be, such as when deleting a folder that contains messages.

exception `mailbox.ExternalClashError`

Raised when some mailbox-related condition beyond the control of the program causes it to be unable to proceed, such as when failing to acquire a lock that another program already holds a lock, or when a uniquely-generated file name already exists.

exception mailbox.FormatError

Raised when the data in a file cannot be parsed, such as when an *MH* instance attempts to read a corrupted .mh_sequences file.

18.4.4 Deprecated classes and methods

버전 2.6부터 폐지.

Older versions of the *mailbox* module do not support modification of mailboxes, such as adding or removing message, and do not provide classes to represent format-specific message properties. For backward compatibility, the older mailbox classes are still available, but the newer classes should be used in preference to them. The old classes have been removed in Python 3.

Older mailbox objects support only iteration and provide a single public method:

`oldmailbox.next()`

Return the next message in the mailbox, created with the optional *factory* argument passed into the mailbox object's constructor. By default this is an *rfc822.Message* object (see the *rfc822* module). Depending on the mailbox implementation the *fp* attribute of this object may be a true file object or a class instance simulating a file object, taking care of things like message boundaries if multiple mail messages are contained in a single file, etc. If no more messages are available, this method returns *None*.

Most of the older mailbox classes have names that differ from the current mailbox class names, except for *Maildir*. For this reason, the new *Maildir* class defines a `next()` method and its constructor differs slightly from those of the other new mailbox classes.

The older mailbox classes whose names are not the same as their newer counterparts are as follows:

class mailbox.UnixMailbox (*fp*[, *factory*])

Access to a classic Unix-style mailbox, where all messages are contained in a single file and separated by *From* (a.k.a. *From_*) lines. The file object *fp* points to the mailbox file. The optional *factory* parameter is a callable that should create new message objects. *factory* is called with one argument, *fp* by the `next()` method of the mailbox object. The default is the *rfc822.Message* class (see the *rfc822* module – and the note below).

참고: For reasons of this module's internal implementation, you will probably want to open the *fp* object in binary mode. This is especially important on Windows.

For maximum portability, messages in a Unix-style mailbox are separated by any line that begins exactly with the string 'From ' (note the trailing space) if preceded by exactly two newlines. Because of the wide-range of variations in practice, nothing else on the *From_* line should be considered. However, the current implementation doesn't check for the leading two newlines. This is usually fine for most applications.

The *UnixMailbox* class implements a more strict version of *From_* line checking, using a regular expression that usually correctly matched *From_* delimiters. It considers delimiter line to be separated by *From* name time lines. For maximum portability, use the *PortableUnixMailbox* class instead. This class is identical to *UnixMailbox* except that individual messages are separated by only *From* lines.

class mailbox.PortableUnixMailbox (*fp*[, *factory*])

A less-strict version of *UnixMailbox*, which considers only the *From* at the beginning of the line separating messages. The «*name time*» portion of the *From* line is ignored, to protect against some variations that are observed in practice. This works since lines in the message which begin with 'From ' are quoted by mail handling software at delivery-time.

class mailbox.MmdfMailbox (*fp*[, *factory*])

Access an MMDF-style mailbox, where all messages are contained in a single file and separated by lines con-

sisting of 4 control-A characters. The file object *fp* points to the mailbox file. Optional *factory* is as with the *UnixMailbox* class.

class mailbox.**MHMailbox**(*dirname*[, *factory*])

Access an MH mailbox, a directory with each message in a separate file with a numeric name. The name of the mailbox directory is passed in *dirname*. *factory* is as with the *UnixMailbox* class.

class mailbox.**BabylMailbox**(*fp*[, *factory*])

Access a Babyl mailbox, which is similar to an MMDF mailbox. In Babyl format, each message has two sets of headers, the *original* headers and the *visible* headers. The original headers appear before a line containing only '*** EOOH ***' (End-Of-Original-Headers) and the visible headers appear after the EOOH line. Babyl-compliant mail readers will show you only the visible headers, and *BabylMailbox* objects will return messages containing only the visible headers. You'll have to do your own parsing of the mailbox file to get at the original headers. Mail messages start with the EOOH line and end with a line containing only '\037\014'. *factory* is as with the *UnixMailbox* class.

If you wish to use the older mailbox classes with the *email* module rather than the deprecated *rfc822* module, you can do so as follows:

```
import email
import email.Errors
import mailbox

def msgfactory(fp):
    try:
        return email.message_from_file(fp)
    except email.Errors.MessageParseError:
        # Don't return None since that will
        # stop the mailbox iterator
        return ''

mbox = mailbox.UnixMailbox(fp, msgfactory)
```

Alternatively, if you know your mailbox contains only well-formed MIME messages, you can simplify this to:

```
import email
import mailbox

mbox = mailbox.UnixMailbox(fp, email.message_from_file)
```

18.4.5 Examples

A simple example of printing the subjects of all messages in a mailbox that seem interesting:

```
import mailbox
for message in mailbox.mbox('~/.mbox'):
    subject = message['subject'] # Could possibly be None.
    if subject and 'python' in subject.lower():
        print subject
```

To copy all mail from a Babyl mailbox to an MH mailbox, converting all of the format-specific information that can be converted:

```
import mailbox
destination = mailbox.MH('~/.Mail')
destination.lock()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
for message in mailbox.Babyl('~/.RMAIL'):  
    destination.add(mailbox.MHMessage(message))  
destination.flush()  
destination.unlock()
```

This example sorts mail from several mailing lists into different mailboxes, being careful to avoid mail corruption due to concurrent modification by other programs, mail loss due to interruption of the program, or premature termination due to malformed messages in the mailbox:

```
import mailbox  
import email.errors  
  
list_names = ('python-list', 'python-dev', 'python-bugs')  
  
boxes = dict((name, mailbox.mbox('~/.email/%s' % name)) for name in list_names)  
inbox = mailbox.Maildir('~/.Maildir', factory=None)  
  
for key in inbox.iterkeys():  
    try:  
        message = inbox[key]  
    except email.errors.MessageParseError:  
        continue # The message is malformed. Just leave it.  
  
    for name in list_names:  
        list_id = message['list-id']  
        if list_id and name in list_id:  
            # Get mailbox to use  
            box = boxes[name]  
  
            # Write copy to disk before removing original.  
            # If there's a crash, you might duplicate a message, but  
            # that's better than losing a message completely.  
            box.lock()  
            box.add(message)  
            box.flush()  
            box.unlock()  
  
            # Remove original message  
            inbox.lock()  
            inbox.discard(key)  
            inbox.flush()  
            inbox.unlock()  
            break # Found destination, so stop looking.  
  
for box in boxes.itervalues():  
    box.close()
```

18.5 `mhlib` — Access to MH mailboxes

버전 2.6부터 폐지: The `mhlib` module has been removed in Python 3. Use the `mailbox` instead.

The `mhlib` module provides a Python interface to MH folders and their contents.

The module contains three basic classes, `MH`, which represents a particular collection of folders, `Folder`, which represents a single folder, and `Message`, which represents a single message.

class `mhlib.MH`(`[path[, profile]]`)

`MH` represents a collection of MH folders.

class `mhlib.Folder`(`mh, name`)

The `Folder` class represents a single folder and its messages.

class `mhlib.Message`(`folder, number[, name]`)

`Message` objects represent individual messages in a folder. The `Message` class is derived from `mimetools.Message`.

18.5.1 MH Objects

`MH` instances have the following methods:

`MH.error`(`format[, ...]`)

Print an error message – can be overridden.

`MH.getprofile`(`key`)

Return a profile entry (None if not set).

`MH.getpath`()

Return the mailbox pathname.

`MH.getcontext`()

Return the current folder name.

`MH.setcontext`(`name`)

Set the current folder name.

`MH.listfolders`()

Return a list of top-level folders.

`MH.listallfolders`()

Return a list of all folders.

`MH.listsubfolders`(`name`)

Return a list of direct subfolders of the given folder.

`MH.listallsubfolders`(`name`)

Return a list of all subfolders of the given folder.

`MH.makefolder`(`name`)

Create a new folder.

`MH.deletefolder`(`name`)

Delete a folder – must have no subfolders.

`MH.openfolder`(`name`)

Return a new open folder object.

18.5.2 Folder Objects

Folder instances represent open folders and have the following methods:

`Folder.error (format[, ...])`

Print an error message – can be overridden.

`Folder.getfullname ()`

Return the folder's full pathname.

`Folder.getsequencesfilename ()`

Return the full pathname of the folder's sequences file.

`Folder.getmessagefilename (n)`

Return the full pathname of message *n* of the folder.

`Folder.listmessages ()`

Return a list of messages in the folder (as numbers).

`Folder.getcurrent ()`

Return the current message number.

`Folder.setcurrent (n)`

Set the current message number to *n*.

`Folder.parsesequence (seq)`

Parse msgs syntax into list of messages.

`Folder.getlast ()`

Get last message, or 0 if no messages are in the folder.

`Folder.setlast (n)`

Set last message (internal use only).

`Folder.getsequences ()`

Return dictionary of sequences in folder. The sequence names are used as keys, and the values are the lists of message numbers in the sequences.

`Folder.putsequences (dict)`

Return dictionary of sequences in folder name: list.

`Folder.removemessages (list)`

Remove messages in list from folder.

`Folder.refilemessages (list, tofolder)`

Move messages in list to other folder.

`Folder.movemessage (n, tofolder, ton)`

Move one message to a given destination in another folder.

`Folder.copymessage (n, tofolder, ton)`

Copy one message to a given destination in another folder.

18.5.3 Message Objects

The *Message* class adds one method to those of *mimertools.Message*:

`Message.openmessage(n)`

Return a new open message object (costs a file descriptor).

18.6 *mimertools* — Tools for parsing MIME messages

버전 2.3부터 폐지: The *email* package should be used in preference to the *mimertools* module. This module is present only to maintain backward compatibility, and it has been removed in 3.x.

This module defines a subclass of the *rfc822* module's *Message* class and a number of utility functions that are useful for the manipulation for MIME multipart or encoded message.

It defines the following items:

class *mimertools.Message* (*fp*[, *seekable*])

Return a new instance of the *Message* class. This is a subclass of the *rfc822.Message* class, with some additional methods (see below). The *seekable* argument has the same meaning as for *rfc822.Message*.

mimertools.choose_boundary ()

Return a unique string that has a high likelihood of being usable as a part boundary. The string has the form 'hostipaddr.uid.pid.timestamp.random'.

mimertools.decode (*input*, *output*, *encoding*)

Read data encoded using the allowed MIME *encoding* from open file object *input* and write the decoded data to open file object *output*. Valid values for *encoding* include 'base64', 'quoted-printable', 'uuencode', 'x-uuencode', 'uue', 'x-uue', '7bit', and '8bit'. Decoding messages encoded in '7bit' or '8bit' has no effect. The input is simply copied to the output.

mimertools.encode (*input*, *output*, *encoding*)

Read data from open file object *input* and write it encoded using the allowed MIME *encoding* to open file object *output*. Valid values for *encoding* are the same as for *decode* ().

mimertools.copyliteral (*input*, *output*)

Read lines from open file *input* until EOF and write them to open file *output*.

mimertools.copybinary (*input*, *output*)

Read blocks until EOF from open file *input* and write them to open file *output*. The block size is currently fixed at 8192.

더 보기:

Module *email* Comprehensive email handling package; supersedes the *mimertools* module.

Module *rfc822* Provides the base class for *mimertools.Message*.

Module *multifile* Support for reading files which contain distinct parts, such as MIME data.

<http://faqs.cs.uu.nl/na-dir/mail/mime-faq/.html> The MIME Frequently Asked Questions document. For an overview of MIME, see the answer to question 1.1 in Part 1 of this document.

18.6.1 Additional Methods of Message Objects

The `Message` class defines the following methods in addition to the `rfc822.Message` methods:

`Message.getplist()`

Return the parameter list of the *Content-Type* header. This is a list of strings. For parameters of the form *key=value*, *key* is converted to lower case but *value* is not. For example, if the message contains the header *Content-type: text/html; spam=1; Spam=2; Spam* then `getplist()` will return the Python list `['spam=1', 'spam=2', 'Spam']`.

`Message.getparam(name)`

Return the *value* of the first parameter (as returned by `getplist()`) of the form *name=value* for the given *name*. If *value* is surrounded by quotes of the form `<...>` or `"..."`, these are removed.

`Message.getencoding()`

Return the encoding specified in the *Content-Transfer-Encoding* message header. If no such header exists, return `'7bit'`. The encoding is converted to lower case.

`Message.gettype()`

Return the message type (of the form *type/subtype*) as specified in the *Content-Type* header. If no such header exists, return `'text/plain'`. The type is converted to lower case.

`Message.getmaintype()`

Return the main type as specified in the *Content-Type* header. If no such header exists, return `'text'`. The main type is converted to lower case.

`Message.getsubtype()`

Return the subtype as specified in the *Content-Type* header. If no such header exists, return `'plain'`. The subtype is converted to lower case.

18.7 mimetypes — Map filenames to MIME types

Source code: [Lib/mimetypes.py](#)

The `mimetypes` module converts between a filename or URL and the MIME type associated with the filename extension. Conversions are provided from filename to MIME type and from MIME type to filename extension; encodings are not supported for the latter conversion.

The module provides one class and a number of convenience functions. The functions are the normal interface to this module, but some applications may be interested in the class as well.

The functions described below provide the primary interface for this module. If the module has not been initialized, they will call `init()` if they rely on the information `init()` sets up.

`mimetypes.guess_type(url, strict=True)`

Guess the type of a file based on its filename or URL, given by *url*. The return value is a tuple (*type*, *encoding*) where *type* is None if the type can't be guessed (missing or unknown suffix) or a string of the form *'type/subtype'*, usable for a MIME *content-type* header.

encoding is None for no encoding or the name of the program used to encode (e.g. **compress** or **gzip**). The encoding is suitable for use as a *Content-Encoding* header, **not** as a *Content-Transfer-Encoding* header. The mappings are table driven. Encoding suffixes are case sensitive; type suffixes are first tried case sensitively, then case insensitively.

The optional *strict* argument is a flag specifying whether the list of known MIME types is limited to only the official types [registered with IANA](#). When *strict* is `True` (the default), only the IANA types are supported; when *strict* is `False`, some additional non-standard but commonly used MIME types are also recognized.

`mimetypes.guess_all_extensions (type, strict=True)`

Guess the extensions for a file based on its MIME type, given by *type*. The return value is a list of strings giving all possible filename extensions, including the leading dot ('.'). The extensions are not guaranteed to have been associated with any particular data stream, but would be mapped to the MIME type *type* by `guess_type()`.

The optional *strict* argument has the same meaning as with the `guess_type()` function.

`mimetypes.guess_extension (type, strict=True)`

Guess the extension for a file based on its MIME type, given by *type*. The return value is a string giving a filename extension, including the leading dot ('.'). The extension is not guaranteed to have been associated with any particular data stream, but would be mapped to the MIME type *type* by `guess_type()`. If no extension can be guessed for *type*, `None` is returned.

The optional *strict* argument has the same meaning as with the `guess_type()` function.

Some additional functions and data items are available for controlling the behavior of the module.

`mimetypes.init (files=None)`

Initialize the internal data structures. If given, *files* must be a sequence of file names which should be used to augment the default type map. If omitted, the file names to use are taken from `knownfiles`; on Windows, the current registry settings are loaded. Each file named in *files* or `knownfiles` takes precedence over those named before it. Calling `init()` repeatedly is allowed.

Specifying an empty list for *files* will prevent the system defaults from being applied: only the well-known values will be present from a built-in list.

버전 2.7에서 변경: Previously, Windows registry settings were ignored.

`mimetypes.read_mime_types (filename)`

Load the type map given in the file *filename*, if it exists. The type map is returned as a dictionary mapping filename extensions, including the leading dot ('. '), to strings of the form 'type/subtype'. If the file *filename* does not exist or cannot be read, `None` is returned.

`mimetypes.add_type (type, ext, strict=True)`

Add a mapping from the MIME type *type* to the extension *ext*. When the extension is already known, the new type will replace the old one. When the type is already known the extension will be added to the list of known extensions.

When *strict* is `True` (the default), the mapping will be added to the official MIME types, otherwise to the non-standard ones.

`mimetypes.inited`

Flag indicating whether or not the global data structures have been initialized. This is set to `True` by `init()`.

`mimetypes.knownfiles`

List of type map file names commonly installed. These files are typically named `mime.types` and are installed in different locations by different packages.

`mimetypes.suffix_map`

Dictionary mapping suffixes to suffixes. This is used to allow recognition of encoded files for which the encoding and the type are indicated by the same extension. For example, the `.tgz` extension is mapped to `.tar.gz` to allow the encoding and type to be recognized separately.

`mimetypes.encodings_map`

Dictionary mapping filename extensions to encoding types.

`mimetypes.types_map`

Dictionary mapping filename extensions to MIME types.

`mimetypes.common_types`

Dictionary mapping filename extensions to non-standard, but commonly found MIME types.

An example usage of the module:

```
>>> import mimetypes
>>> mimetypes.init()
>>> mimetypes.knownfiles
['/etc/mime.types', '/etc/httpd/mime.types', ... ]
>>> mimetypes.suffix_map['.tgz']
'.tar.gz'
>>> mimetypes.encodings_map['.gz']
'gzip'
>>> mimetypes.types_map['.tgz']
'application/x-tar-gz'
```

18.7.1 MimeTypes Objects

The *MimeTypes* class may be useful for applications which may want more than one MIME-type database; it provides an interface similar to the one of the *mimetypes* module.

class *mimetypes.MimeTypes* (*filenames=()*, *strict=True*)

This class represents a MIME-types database. By default, it provides access to the same database as the rest of this module. The initial database is a copy of that provided by the module, and may be extended by loading additional *mime.types*-style files into the database using the *read()* or *readfp()* methods. The mapping dictionaries may also be cleared before loading additional data if the default data is not desired.

The optional *filenames* parameter can be used to cause additional files to be loaded 《on top》 of the default database.

suffix_map

Dictionary mapping suffixes to suffixes. This is used to allow recognition of encoded files for which the encoding and the type are indicated by the same extension. For example, the *.tgz* extension is mapped to *.tar.gz* to allow the encoding and type to be recognized separately. This is initially a copy of the global *suffix_map* defined in the module.

encodings_map

Dictionary mapping filename extensions to encoding types. This is initially a copy of the global *encodings_map* defined in the module.

types_map

Tuple containing two dictionaries, mapping filename extensions to MIME types: the first dictionary is for the non-standards types and the second one is for the standard types. They are initialized by *common_types* and *types_map*.

types_map_inv

Tuple containing two dictionaries, mapping MIME types to a list of filename extensions: the first dictionary is for the non-standards types and the second one is for the standard types. They are initialized by *common_types* and *types_map*.

guess_extension (*type*, *strict=True*)

Similar to the *guess_extension()* function, using the tables stored as part of the object.

guess_type (*url*, *strict=True*)

Similar to the *guess_type()* function, using the tables stored as part of the object.

guess_all_extensions (*type*, *strict=True*)

Similar to the *guess_all_extensions()* function, using the tables stored as part of the object.

read (*filename*, *strict=True*)

Load MIME information from a file named *filename*. This uses *readfp()* to parse the file.

If *strict* is `True`, information will be added to list of standard types, else to the list of non-standard types.

readfp (*fp*, *strict=True*)

Load MIME type information from an open file *fp*. The file must have the format of the standard `mimetypes` files.

If *strict* is `True`, information will be added to the list of standard types, else to the list of non-standard types.

read_windows_registry (*strict=True*)

Load MIME type information from the Windows registry. Availability: Windows.

If *strict* is `True`, information will be added to the list of standard types, else to the list of non-standard types.

버전 2.7에 추가.

18.8 MimeWriter — Generic MIME file writer

버전 2.3부터 폐지: The `email` package should be used in preference to the `MimeWriter` module. This module is present only to maintain backward compatibility.

This module defines the class `MimeWriter`. The `MimeWriter` class implements a basic formatter for creating MIME multi-part files. It doesn't seek around the output file nor does it use large amounts of buffer space. You must write the parts out in the order that they should occur in the final file. `MimeWriter` does buffer the headers you add, allowing you to rearrange their order.

class `MimeWriter.MimeWriter` (*fp*)

Return a new instance of the `MimeWriter` class. The only argument passed, *fp*, is a file object to be used for writing. Note that a `StringIO` object could also be used.

18.8.1 MimeWriter Objects

`MimeWriter` instances have the following methods:

`MimeWriter.addheader` (*key*, *value* [, *prefix*])

Add a header line to the MIME message. The *key* is the name of the header, where the *value* obviously provides the value of the header. The optional argument *prefix* determines where the header is inserted; 0 means append at the end, 1 is insert at the start. The default is to append.

`MimeWriter.flushheaders` ()

Causes all headers accumulated so far to be written out (and forgotten). This is useful if you don't need a body part at all, e.g. for a subpart of type `message/rfc822` that's (mis)used to store some header-like information.

`MimeWriter.startbody` (*ctype* [, *plist* [, *prefix*]])

Returns a file-like object which can be used to write to the body of the message. The content-type is set to the provided *ctype*, and the optional parameter *plist* provides additional parameters for the content-type declaration. *prefix* functions as in `addheader` () except that the default is to insert at the start.

`MimeWriter.startmultipartbody` (*subtype* [, *boundary* [, *plist* [, *prefix*]]])

Returns a file-like object which can be used to write to the body of the message. Additionally, this method initializes the multi-part code, where *subtype* provides the multipart subtype, *boundary* may provide a user-defined boundary specification, and *plist* provides optional parameters for the subtype. *prefix* functions as in `startbody` (). Subparts should be created using `nextpart` ().

`MimeWriter.nextpart` ()

Returns a new instance of `MimeWriter` which represents an individual part in a multipart message. This may be used to write the part as well as used for creating recursively complex multipart messages. The message must first be initialized with `startmultipartbody` () before using `nextpart` ().

`MimeWriter.lastpart()`

This is used to designate the last part of a multipart message, and should *always* be used when writing multipart messages.

18.9 `mimify` — MIME processing of mail messages

버전 2.3부터 폐지: The `email` package should be used in preference to the `mimify` module. This module is present only to maintain backward compatibility.

The `mimify` module defines two functions to convert mail messages to and from MIME format. The mail message can be either a simple message or a so-called multipart message. Each part is treated separately. Mimifying (a part of) a message entails encoding the message as quoted-printable if it contains any characters that cannot be represented using 7-bit ASCII. Unmimifying (a part of) a message entails undoing the quoted-printable encoding. Mimify and unmimify are especially useful when a message has to be edited before being sent. Typical use would be:

```
unmimify message
edit message
mimify message
send message
```

The module defines the following user-callable functions and user-settable variables:

`mimify.mimify(infile, outfile)`

Copy the message in *infile* to *outfile*, converting parts to quoted-printable and adding MIME mail headers when necessary. *infile* and *outfile* can be file objects (actually, any object that has a `readline()` method (for *infile*) or a `write()` method (for *outfile*)) or strings naming the files. If *infile* and *outfile* are both strings, they may have the same value.

`mimify.unmimify(infile, outfile[, decode_base64])`

Copy the message in *infile* to *outfile*, decoding all quoted-printable parts. *infile* and *outfile* can be file objects (actually, any object that has a `readline()` method (for *infile*) or a `write()` method (for *outfile*)) or strings naming the files. If *infile* and *outfile* are both strings, they may have the same value. If the `decode_base64` argument is provided and tests true, any parts that are coded in the base64 encoding are decoded as well.

`mimify.mime_decode_header(line)`

Return a decoded version of the encoded header line in *line*. This only supports the ISO 8859-1 charset (Latin-1).

`mimify.mime_encode_header(line)`

Return a MIME-encoded version of the header line in *line*.

`mimify.MAXLEN`

By default, a part will be encoded as quoted-printable when it contains any non-ASCII characters (characters with the 8th bit set), or if there are any lines longer than `MAXLEN` characters (default value 200).

`mimify.CHARSET`

When not specified in the mail headers, a character set must be filled in. The string used is stored in `CHARSET`, and the default value is ISO-8859-1 (also known as Latin1 (latin-one)).

This module can also be used from the command line. Usage is as follows:

```
mimify.py -e [-l length] [infile [outfile]]
mimify.py -d [-b] [infile [outfile]]
```

to encode (mimify) and decode (unmimify) respectively. *infile* defaults to standard input, *outfile* defaults to standard output. The same file can be specified for input and output.

If the `-l` option is given when encoding, if there are any lines longer than the specified *length*, the containing part will be encoded.

If the **-b** option is given when decoding, any base64 parts will be decoded as well.

더 보기:

Module *quopri* Encode and decode MIME quoted-printable files.

18.10 *multifile* — Support for files containing distinct parts

버전 2.5부터 폐지: The *email* package should be used in preference to the *multifile* module. This module is present only to maintain backward compatibility.

The *MultiFile* object enables you to treat sections of a text file as file-like input objects, with `' '` being returned by *readline()* when a given delimiter pattern is encountered. The defaults of this class are designed to make it useful for parsing MIME multipart messages, but by subclassing it and overriding methods it can be easily adapted for more general use.

class *multifile.MultiFile* (*fp*[, *seekable*])

Create a multi-file. You must instantiate this class with an input object argument for the *MultiFile* instance to get lines from, such as a file object returned by *open()*.

MultiFile only ever looks at the input object's *readline()*, *seek()* and *tell()* methods, and the latter two are only needed if you want random access to the individual MIME parts. To use *MultiFile* on a non-seekable stream object, set the optional *seekable* argument to false; this will prevent using the input object's *seek()* and *tell()* methods.

It will be useful to know that in *MultiFile*'s view of the world, text is composed of three kinds of lines: data, section-dividers, and end-markers. *MultiFile* is designed to support parsing of messages that may have multiple nested message parts, each with its own pattern for section-divider and end-marker lines.

더 보기:

Module *email* Comprehensive email handling package; supersedes the *multifile* module.

18.10.1 MultiFile Objects

A *MultiFile* instance has the following methods:

MultiFile.**readline** (*str*)

Read a line. If the line is data (not a section-divider or end-marker or real EOF) return it. If the line matches the most-recently-stacked boundary, return `' '` and set *self.last* to 1 or 0 according as the match is or is not an end-marker. If the line matches any other stacked boundary, raise an error. On encountering end-of-file on the underlying stream object, the method raises *Error* unless all boundaries have been popped.

MultiFile.**readlines** (*str*)

Return all lines remaining in this part as a list of strings.

MultiFile.**read** ()

Read all lines, up to the next section. Return them as a single (multiline) string. Note that this doesn't take a size argument!

MultiFile.**seek** (*pos*[, *whence*])

Seek. Seek indices are relative to the start of the current section. The *pos* and *whence* arguments are interpreted as for a file seek.

MultiFile.**tell** ()

Return the file position relative to the start of the current section.

`MultiFile.next()`

Skip lines to the next section (that is, read lines until a section-divider or end-marker has been consumed). Return true if there is such a section, false if an end-marker is seen. Re-enable the most-recently-pushed boundary.

`MultiFile.is_data(str)`

Return true if *str* is data and false if it might be a section boundary. As written, it tests for a prefix other than ' -- ' at start of line (which all MIME boundaries have) but it is declared so it can be overridden in derived classes.

Note that this test is used intended as a fast guard for the real boundary tests; if it always returns false it will merely slow processing, not cause it to fail.

`MultiFile.push(str)`

Push a boundary string. When a decorated version of this boundary is found as an input line, it will be interpreted as a section-divider or end-marker (depending on the decoration, see [RFC 2045](#)). All subsequent reads will return the empty string to indicate end-of-file, until a call to `pop()` removes the boundary or `next()` call reenables it.

It is possible to push more than one boundary. Encountering the most-recently-pushed boundary will return EOF; encountering any other boundary will raise an error.

`MultiFile.pop()`

Pop a section boundary. This boundary will no longer be interpreted as EOF.

`MultiFile.section_divider(str)`

Turn a boundary into a section-divider line. By default, this method prepends ' -- ' (which MIME section boundaries have) but it is declared so it can be overridden in derived classes. This method need not append LF or CR-LF, as comparison with the result ignores trailing whitespace.

`MultiFile.end_marker(str)`

Turn a boundary string into an end-marker line. By default, this method prepends ' -- ' and appends ' -- ' (like a MIME-multipart end-of-message marker) but it is declared so it can be overridden in derived classes. This method need not append LF or CR-LF, as comparison with the result ignores trailing whitespace.

Finally, *MultiFile* instances have two public instance variables:

`MultiFile.level`

Nesting depth of the current part.

`MultiFile.last`

True if the last end-of-file was for an end-of-message marker.

18.10.2 MultiFile Example

```
import mimetools
import multifile
import StringIO

def extract_mime_part_matching(stream, mimetype):
    """Return the first element in a multipart MIME message on stream
    matching mimetype."""

    msg = mimetools.Message(stream)
    msgtype = msg.gettype()
    params = msg.getplist()

    data = StringIO.StringIO()
    if msgtype[:10] == "multipart/":
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

file = multifile.MultiFile(stream)
file.push(msg.getparam("boundary"))
while file.next():
    submsg = mimetools.Message(file)
    try:
        data = StringIO.StringIO()
        mimetools.decode(file, data, submsg.getencoding())
    except ValueError:
        continue
    if submsg.gettype() == mimetype:
        break
file.pop()
return data.getvalue()

```

18.11 rfc822 — Parse RFC 2822 mail headers

버전 2.3부터 폐지: The *email* package should be used in preference to the *rfc822* module. This module is present only to maintain backward compatibility, and has been removed in Python 3.

This module defines a class, *Message*, which represents an «email message» as defined by the Internet standard **RFC 2822**.¹ Such messages consist of a collection of message headers, and a message body. This module also defines a helper class *AddressList* for parsing **RFC 2822** addresses. Please refer to the RFC for information on the specific syntax of **RFC 2822** messages.

The *mailbox* module provides classes to read mailboxes produced by various end-user mail programs.

class *rfc822.Message* (*file*[, *seekable*])

A *Message* instance is instantiated with an input object as parameter. *Message* relies only on the input object having a *readline()* method; in particular, ordinary file objects qualify. Instantiation reads headers from the input object up to a delimiter line (normally a blank line) and stores them in the instance. The message body, following the headers, is not consumed.

This class can work with any input object that supports a *readline()* method. If the input object has seek and tell capability, the *rewindbody()* method will work; also, illegal lines will be pushed back onto the input stream. If the input object lacks seek but has an *unread()* method that can push back a line of input, *Message* will use that to push back illegal lines. Thus this class can be used to parse messages coming from a buffered stream.

The optional *seekable* argument is provided as a workaround for certain stdio libraries in which *tell()* discards buffered data before discovering that the *lseek()* system call doesn't work. For maximum portability, you should set the *seekable* argument to zero to prevent that initial *tell()* when passing in an unseekable object such as a file object created from a socket object.

Input lines as read from the file may either be terminated by CR-LF or by a single linefeed; a terminating CR-LF is replaced by a single linefeed before the line is stored.

All header matching is done independent of upper or lower case; e.g. *m['From']*, *m['from']* and *m['FROM']* all yield the same result.

class *rfc822.AddressList* (*field*)

You may instantiate the *AddressList* helper class using a single string parameter, a comma-separated list of **RFC 2822** addresses to be parsed. (The parameter *None* yields an empty list.)

¹ This module originally conformed to **RFC 822**, hence the name. Since then, **RFC 2822** has been released as an update to **RFC 822**. This module should be considered **RFC 2822**-conformant, especially in cases where the syntax or semantics have changed since **RFC 822**.

`rfc822.quote(str)`

Return a new string with backslashes in *str* replaced by two backslashes and double quotes replaced by backslash-double quote.

`rfc822.unquote(str)`

Return a new string which is an *unquoted* version of *str*. If *str* ends and begins with double quotes, they are stripped off. Likewise if *str* ends and begins with angle brackets, they are stripped off.

`rfc822.parseaddr(address)`

Parse *address*, which should be the value of some address-containing field such as *To* or *Cc*, into its constituent *realname* and *email address* parts. Returns a tuple of that information, unless the parse fails, in which case a 2-tuple (*None*, *None*) is returned.

`rfc822.dump_address_pair(pair)`

The inverse of *parseaddr()*, this takes a 2-tuple of the form (*realname*, *email_address*) and returns the string value suitable for a *To* or *Cc* header. If the first element of *pair* is false, then the second element is returned unmodified.

`rfc822.parsedate(date)`

Attempts to parse a date according to the rules in **RFC 2822**. However, some mailers don't follow that format as specified, so *parsedate()* tries to guess correctly in such cases. *date* is a string containing an **RFC 2822** date, such as 'Mon, 20 Nov 1995 19:12:08 -0500'. If it succeeds in parsing the date, *parsedate()* returns a 9-tuple that can be passed directly to *time.mktime()*; otherwise *None* will be returned. Note that indexes 6, 7, and 8 of the result tuple are not usable.

`rfc822.parsedate_tz(date)`

Performs the same function as *parsedate()*, but returns either *None* or a 10-tuple; the first 9 elements make up a tuple that can be passed directly to *time.mktime()*, and the tenth is the offset of the date's timezone from UTC (which is the official term for Greenwich Mean Time). (Note that the sign of the timezone offset is the opposite of the sign of the *time.timezone* variable for the same timezone; the latter variable follows the POSIX standard while this module follows **RFC 2822**.) If the input string has no timezone, the last element of the tuple returned is *None*. Note that indexes 6, 7, and 8 of the result tuple are not usable.

`rfc822.mktime_tz(tuple)`

Turn a 10-tuple as returned by *parsedate_tz()* into a UTC timestamp. If the timezone item in the tuple is *None*, assume local time. Minor deficiency: this first interprets the first 8 elements as a local time and then compensates for the timezone difference; this may yield a slight error around daylight savings time switch dates. Not enough to worry about for common use.

더 보기:

Module *email* Comprehensive email handling package; supersedes the *rfc822* module.

Module *mailbox* Classes to read various mailbox formats produced by end-user mail programs.

Module *mimetools* Subclass of *rfc822.Message* that handles MIME encoded messages.

18.11.1 Message Objects

A *Message* instance has the following methods:

`Message.rewindbody()`

Seek to the start of the message body. This only works if the file object is seekable.

`Message.isheader(line)`

Returns a line's canonicalized fieldname (the dictionary key that will be used to index it) if the line is a legal **RFC 2822** header; otherwise returns *None* (implying that parsing should stop here and the line be pushed back on the input stream). It is sometimes useful to override this method in a subclass.

`Message.islast (line)`

Return true if the given line is a delimiter on which Message should stop. The delimiter line is consumed, and the file object's read location positioned immediately after it. By default this method just checks that the line is blank, but you can override it in a subclass.

`Message.iscomment (line)`

Return True if the given line should be ignored entirely, just skipped. By default this is a stub that always returns False, but you can override it in a subclass.

`Message.getallmatchingheaders (name)`

Return a list of lines consisting of all headers matching *name*, if any. Each physical line, whether it is a continuation line or not, is a separate list item. Return the empty list if no header matches *name*.

`Message.getfirstmatchingheader (name)`

Return a list of lines comprising the first header matching *name*, and its continuation line(s), if any. Return None if there is no header matching *name*.

`Message.getrawheader (name)`

Return a single string consisting of the text after the colon in the first header matching *name*. This includes leading whitespace, the trailing linefeed, and internal linefeeds and whitespace if there any continuation line(s) were present. Return None if there is no header matching *name*.

`Message.getheader (name[, default])`

Return a single string consisting of the last header matching *name*, but strip leading and trailing whitespace. Internal whitespace is not stripped. The optional *default* argument can be used to specify a different default to be returned when there is no header matching *name*; it defaults to None. This is the preferred way to get parsed headers.

`Message.get (name[, default])`

An alias for `getheader()`, to make the interface more compatible with regular dictionaries.

`Message.getaddr (name)`

Return a pair (full name, email address) parsed from the string returned by `getheader(name)`. If no header matching *name* exists, return (None, None); otherwise both the full name and the address are (possibly empty) strings.

Example: If *m*'s first *From* header contains the string 'jack@cwil.nl (Jack Jansen)', then `m.getaddr('From')` will yield the pair ('Jack Jansen', 'jack@cwil.nl'). If the header contained 'Jack Jansen <jack@cwil.nl>' instead, it would yield the exact same result.

`Message.getaddrlist (name)`

This is similar to `getaddr(list)`, but parses a header containing a list of email addresses (e.g. a *To* header) and returns a list of (full name, email address) pairs (even if there was only one address in the header). If there is no header matching *name*, return an empty list.

If multiple headers exist that match the named header (e.g. if there are several *Cc* headers), all are parsed for addresses. Any continuation lines the named headers contain are also parsed.

`Message.getdate (name)`

Retrieve a header using `getheader()` and parse it into a 9-tuple compatible with `time.mktime()`; note that fields 6, 7, and 8 are not usable. If there is no header matching *name*, or it is unparseable, return None.

Date parsing appears to be a black art, and not all mailers adhere to the standard. While it has been tested and found correct on a large collection of email from many sources, it is still possible that this function may occasionally yield an incorrect result.

`Message.getdate_tz (name)`

Retrieve a header using `getheader()` and parse it into a 10-tuple; the first 9 elements will make a tuple compatible with `time.mktime()`, and the 10th is a number giving the offset of the date's timezone from UTC. Note that fields 6, 7, and 8 are not usable. Similarly to `getdate()`, if there is no header matching *name*, or it is unparseable, return None.

Message instances also support a limited mapping interface. In particular: `m[name]` is like `m.getheader(name)` but raises *KeyError* if there is no matching header; and `len(m)`, `m.get(name[, default])`, `name in m`, `m.keys()`, `m.values()`, `m.items()`, and `m.setdefault(name[, default])` act as expected, with the one difference that `setdefault()` uses an empty string as the default value. *Message* instances also support the mapping writable interface `m[name] = value` and `del m[name]`. *Message* objects do not support the `clear()`, `copy()`, `popitem()`, or `update()` methods of the mapping interface. (Support for `get()` and `setdefault()` was only added in Python 2.2.)

Finally, *Message* instances have some public instance variables:

`Message.headers`

A list containing the entire set of header lines, in the order in which they were read (except that `setitem` calls may disturb this order). Each line contains a trailing newline. The blank line terminating the headers is not contained in the list.

`Message.fp`

The file or file-like object passed at instantiation time. This can be used to read the message content.

`Message.unixfrom`

The Unix From line, if the message had one, or an empty string. This is needed to regenerate the message in some contexts, such as an mbox-style mailbox file.

18.11.2 AddressList Objects

An *AddressList* instance has the following methods:

`AddressList.__len__()`

Return the number of addresses in the address list.

`AddressList.__str__()`

Return a canonicalized string representation of the address list. Addresses are rendered in `<name><host@domain>` form, comma-separated.

`AddressList.__add__(alist)`

Return a new *AddressList* instance that contains all addresses in both *AddressList* operands, with duplicates removed (set union).

`AddressList.__iadd__(alist)`

In-place version of `__add__()`; turns this *AddressList* instance into the union of itself and the right-hand instance, *alist*.

`AddressList.__sub__(alist)`

Return a new *AddressList* instance that contains every address in the left-hand *AddressList* operand that is not present in the right-hand address operand (set difference).

`AddressList.__isub__(alist)`

In-place version of `__sub__()`, removing addresses in this list which are also in *alist*.

Finally, *AddressList* instances have one public instance variable:

`AddressList.addresslist`

A list of tuple string pairs, one per address. In each member, the first is the canonicalized name part, the second is the actual route-address ('@'-separated username-host.domain pair).

18.12 base64 — RFC 3548: Base16, Base32, Base64 Data Encodings

This module provides data encoding and decoding as specified in [RFC 3548](#). This standard defines the Base16, Base32, and Base64 algorithms for encoding and decoding arbitrary binary strings into text strings that can be safely sent by email, used as parts of URLs, or included as part of an HTTP POST request. The encoding algorithm is not the same as the `uuencode` program.

There are two interfaces provided by this module. The modern interface supports encoding and decoding string objects using both base-64 alphabets defined in [RFC 3548](#) (normal, and URL- and filesystem-safe). The legacy interface provides for encoding and decoding to and from file-like objects as well as strings, but only using the Base64 standard alphabet.

The modern interface, which was introduced in Python 2.4, provides:

`base64.b64encode(s[, altchars])`

Encode a string using Base64.

s is the string to encode. Optional *altchars* must be a string of at least length 2 (additional characters are ignored) which specifies an alternative alphabet for the + and / characters. This allows an application to e.g. generate URL or filesystem safe Base64 strings. The default is `None`, for which the standard Base64 alphabet is used.

The encoded string is returned.

`base64.b64decode(s[, altchars])`

Decode a Base64 encoded string.

s is the string to decode. Optional *altchars* must be a string of at least length 2 (additional characters are ignored) which specifies the alternative alphabet used instead of the + and / characters.

The decoded string is returned. A `TypeError` is raised if *s* is incorrectly padded. Characters that are neither in the normal base-64 alphabet nor the alternative alphabet are discarded prior to the padding check.

`base64.standard_b64encode(s)`

Encode string *s* using the standard Base64 alphabet.

`base64.standard_b64decode(s)`

Decode string *s* using the standard Base64 alphabet.

`base64.urlsafe_b64encode(s)`

Encode string *s* using the URL- and filesystem-safe alphabet, which substitutes - instead of + and _ instead of / in the standard Base64 alphabet. The result can still contain =.

`base64.urlsafe_b64decode(s)`

Decode string *s* using the URL- and filesystem-safe alphabet, which substitutes - instead of + and _ instead of / in the standard Base64 alphabet.

`base64.b32encode(s)`

Encode a string using Base32. *s* is the string to encode. The encoded string is returned.

`base64.b32decode(s[, casefold[, map01]])`

Decode a Base32 encoded string.

s is the string to decode. Optional *casefold* is a flag specifying whether a lowercase alphabet is acceptable as input. For security purposes, the default is `False`.

[RFC 3548](#) allows for optional mapping of the digit 0 (zero) to the letter O (oh), and for optional mapping of the digit 1 (one) to either the letter I (eye) or letter L (el). The optional argument *map01* when not `None`, specifies which letter the digit 1 should be mapped to (when *map01* is not `None`, the digit 0 is always mapped to the letter O). For security purposes the default is `None`, so that 0 and 1 are not allowed in the input.

The decoded string is returned. A `TypeError` is raised if *s* is incorrectly padded or if there are non-alphabet characters present in the string.

`base64.b16encode(s)`

Encode a string using Base16.

s is the string to encode. The encoded string is returned.

`base64.b16decode(s[, casefold])`

Decode a Base16 encoded string.

s is the string to decode. Optional *casefold* is a flag specifying whether a lowercase alphabet is acceptable as input. For security purposes, the default is `False`.

The decoded string is returned. A `TypeError` is raised if *s* were incorrectly padded or if there are non-alphabet characters present in the string.

The legacy interface:

`base64.decode(input, output)`

Decode the contents of the *input* file and write the resulting binary data to the *output* file. *input* and *output* must either be file objects or objects that mimic the file object interface. *input* will be read until `input.read()` returns an empty string.

`base64.decodestring(s)`

Decode the string *s*, which must contain one or more lines of base64 encoded data, and return a string containing the resulting binary data.

`base64.encode(input, output)`

Encode the contents of the *input* file and write the resulting base64 encoded data to the *output* file. *input* and *output* must either be file objects or objects that mimic the file object interface. *input* will be read until `input.read()` returns an empty string. `encode()` returns the encoded data plus a trailing newline character (`'\n'`).

`base64.encodestring(s)`

Encode the string *s*, which can contain arbitrary binary data, and return a string containing one or more lines of base64-encoded data. `encodestring()` returns a string containing one or more lines of base64-encoded data always including an extra trailing newline (`'\n'`).

An example usage of the module:

```
>>> import base64
>>> encoded = base64.b64encode('data to be encoded')
>>> encoded
'ZGF0YSB0byBiZSB1bmNvZGVk'
>>> data = base64.b64decode(encoded)
>>> data
'data to be encoded'
```

더 보기:

Module `binascii` Support module containing ASCII-to-binary and binary-to-ASCII conversions.

RFC 1521 - MIME (Multipurpose Internet Mail Extensions) Part One: Mechanisms for Specifying and Describing the Format of

Section 5.2, 《Base64 Content-Transfer-Encoding,》 provides the definition of the base64 encoding.

18.13 binhex — Encode and decode binhex4 files

This module encodes and decodes files in binhex4 format, a format allowing representation of Macintosh files in ASCII. On the Macintosh, both forks of a file and the finder information are encoded (or decoded), on other platforms only the data fork is handled.

참고: In Python 3.x, special Macintosh support has been removed.

The *binhex* module defines the following functions:

`binhex.binhex(input, output)`

Convert a binary file with filename *input* to binhex file *output*. The *output* parameter can either be a filename or a file-like object (any object supporting a `write()` and `close()` method).

`binhex.hexbin(input[, output])`

Decode a binhex file *input*. *input* may be a filename or a file-like object supporting `read()` and `close()` methods. The resulting file is written to a file named *output*, unless the argument is omitted in which case the output filename is read from the binhex file.

The following exception is also defined:

exception `binhex.Error`

Exception raised when something can't be encoded using the binhex format (for example, a filename is too long to fit in the filename field), or when input is not properly encoded binhex data.

더 보기:

Module *binascii* Support module containing ASCII-to-binary and binary-to-ASCII conversions.

18.13.1 Notes

There is an alternative, more powerful interface to the coder and decoder, see the source for details.

If you code or decode textfiles on non-Macintosh platforms they will still use the old Macintosh newline convention (carriage-return as end of line).

As of this writing, *hexbin()* appears to not work in all cases.

18.14 binascii — Convert between binary and ASCII

The *binascii* module contains a number of methods to convert between binary and various ASCII-encoded binary representations. Normally, you will not use these functions directly but use wrapper modules like *uu*, *base64*, or *binhex* instead. The *binascii* module contains low-level functions written in C for greater speed that are used by the higher-level modules.

The *binascii* module defines the following functions:

`binascii.a2b_uu(string)`

Convert a single line of uuencoded data back to binary and return the binary data. Lines normally contain 45 (binary) bytes, except for the last line. Line data may be followed by whitespace.

`binascii.b2a_uu(data)`

Convert binary data to a line of ASCII characters, the return value is the converted line, including a newline char. The length of *data* should be at most 45.

`binascii.a2b_base64` (*string*)

Convert a block of base64 data back to binary and return the binary data. More than one line may be passed at a time.

`binascii.b2a_base64` (*data*)

Convert binary data to a line of ASCII characters in base64 coding. The return value is the converted line, including a newline char. The newline is added because the original use case for this function was to feed it a series of 57 byte input lines to get output lines that conform to the MIME-base64 standard. Otherwise the output conforms to [RFC 3548](#).

`binascii.a2b_qp` (*string*[, *header*])

Convert a block of quoted-printable data back to binary and return the binary data. More than one line may be passed at a time. If the optional argument *header* is present and true, underscores will be decoded as spaces.

`binascii.b2a_qp` (*data*[, *quotetabs*, *istext*, *header*])

Convert binary data to a line(s) of ASCII characters in quoted-printable encoding. The return value is the converted line(s). If the optional argument *quotetabs* is present and true, all tabs and spaces will be encoded. If the optional argument *istext* is present and true, newlines are not encoded but trailing whitespace will be encoded. If the optional argument *header* is present and true, spaces will be encoded as underscores per RFC1522. If the optional argument *header* is present and false, newline characters will be encoded as well; otherwise linefeed conversion might corrupt the binary data stream.

`binascii.a2b_hqx` (*string*)

Convert binhex4 formatted ASCII data to binary, without doing RLE-decompression. The string should contain a complete number of binary bytes, or (in case of the last portion of the binhex4 data) have the remaining bits zero.

`binascii.rledecode_hqx` (*data*)

Perform RLE-decompression on the data, as per the binhex4 standard. The algorithm uses 0x90 after a byte as a repeat indicator, followed by a count. A count of 0 specifies a byte value of 0x90. The routine returns the decompressed data, unless data input data ends in an orphaned repeat indicator, in which case the *Incomplete* exception is raised.

`binascii.rlecode_hqx` (*data*)

Perform binhex4 style RLE-compression on *data* and return the result.

`binascii.b2a_hqx` (*data*)

Perform hexbin4 binary-to-ASCII translation and return the resulting string. The argument should already be RLE-coded, and have a length divisible by 3 (except possibly the last fragment).

`binascii.crc_hqx` (*data*, *crc*)

Compute a 16-bit CRC value of *data*, starting with an initial *crc* and returning the result. This uses the CRC-CCITT polynomial $x^{16} + x^{12} + x^5 + 1$, often represented as 0x1021. This CRC is used in the binhex4 format.

`binascii.crc32` (*data*[, *crc*])

Compute CRC-32, the 32-bit checksum of data, starting with an initial *crc*. This is consistent with the ZIP file checksum. Since the algorithm is designed for use as a checksum algorithm, it is not suitable for use as a general hash algorithm. Use as follows:

```
print binascii.crc32("hello world")
# Or, in two pieces:
crc = binascii.crc32("hello")
crc = binascii.crc32(" world", crc) & 0xffffffff
print 'crc32 = 0x%08x' % crc
```

참고: To generate the same numeric value across all Python versions and platforms use `crc32(data) & 0xffffffff`. If you are only using the checksum in packed binary format this is not necessary as the return value is the correct 32bit binary representation regardless of sign.

버전 2.6에서 변경: The return value is in the range $[-2^{31}, 2^{31}-1]$ regardless of platform. In the past the value would be signed on some platforms and unsigned on others. Use `& 0xffffffff` on the value if you want it to match Python 3 behavior.

버전 3.0에서 변경: The return value is unsigned and in the range $[0, 2^{32}-1]$ regardless of platform.

`binascii.b2a_hex(data)`

`binascii.hexlify(data)`

Return the hexadecimal representation of the binary *data*. Every byte of *data* is converted into the corresponding 2-digit hex representation. The resulting string is therefore twice as long as the length of *data*.

`binascii.a2b_hex(hexstr)`

`binascii.unhexlify(hexstr)`

Return the binary data represented by the hexadecimal string *hexstr*. This function is the inverse of `b2a_hex()`. *hexstr* must contain an even number of hexadecimal digits (which can be upper or lower case), otherwise a `TypeError` is raised.

exception `binascii.Error`

Exception raised on errors. These are usually programming errors.

exception `binascii.Incomplete`

Exception raised on incomplete data. These are usually not programming errors, but may be handled by reading a little more data and trying again.

더 보기:

Module `base64` Support for RFC compliant base64-style encoding in base 16, 32, and 64.

Module `binhex` Support for the binhex format used on the Macintosh.

Module `uu` Support for UU encoding used on Unix.

Module `quopri` Support for quoted-printable encoding used in MIME email messages.

18.15 quopri — Encode and decode MIME quoted-printable data

Source code: [Lib/quopri.py](#)

This module performs quoted-printable transport encoding and decoding, as defined in [RFC 1521](#): 《MIME (Multipurpose Internet Mail Extensions) Part One: Mechanisms for Specifying and Describing the Format of Internet Message Bodies》. The quoted-printable encoding is designed for data where there are relatively few nonprintable characters; the base64 encoding scheme available via the `base64` module is more compact if there are many such characters, as when sending a graphics file.

`quopri.decode(input, output[, header])`

Decode the contents of the *input* file and write the resulting decoded binary data to the *output* file. *input* and *output* must either be file objects or objects that mimic the file object interface. *input* will be read until `input.readline()` returns an empty string. If the optional argument *header* is present and true, underscore will be decoded as space. This is used to decode 《Q》-encoded headers as described in [RFC 1522](#): 《MIME (Multipurpose Internet Mail Extensions) Part Two: Message Header Extensions for Non-ASCII Text》.

`quopri.encode(input, output, quotetabs)`

Encode the contents of the *input* file and write the resulting quoted-printable data to the *output* file. *input* and *output* must either be file objects or objects that mimic the file object interface. *input* will be read until `input.readline()` returns an empty string. *quotetabs* is a flag which controls whether to encode embedded spaces and tabs; when true it encodes such embedded whitespace, and when false it leaves them unencoded. Note that spaces and tabs appearing at the end of lines are always encoded, as per [RFC 1521](#).

`quopri.decodestring(s[, header])`

Like `decode()`, except that it accepts a source string and returns the corresponding decoded string.

`quopri.encodestring(s[, quotetabs])`

Like `encode()`, except that it accepts a source string and returns the corresponding encoded string. `quotetabs` is optional (defaulting to 0), and is passed straight through to `encode()`.

더 보기:

Module `mimify` General utilities for processing of MIME messages.

Module `base64` Encode and decode MIME base64 data

18.16 uu — Encode and decode uuencode files

Source code: [Lib/uu.py](#)

This module encodes and decodes files in uuencode format, allowing arbitrary binary data to be transferred over ASCII-only connections. Wherever a file argument is expected, the methods accept a file-like object. For backwards compatibility, a string containing a pathname is also accepted, and the corresponding file will be opened for reading and writing; the pathname `'-'` is understood to mean the standard input or output. However, this interface is deprecated; it's better for the caller to open the file itself, and be sure that, when required, the mode is `'rb'` or `'wb'` on Windows.

This code was contributed by Lance Ellinghouse, and modified by Jack Jansen.

The `uu` module defines the following functions:

`uu.encode(in_file, out_file[, name[, mode]])`

Uuencode file `in_file` into file `out_file`. The uuencoded file will have the header specifying `name` and `mode` as the defaults for the results of decoding the file. The default defaults are taken from `in_file`, or `'-'` and `0666` respectively.

`uu.decode(in_file[, out_file[, mode[, quiet]]])`

This call decodes uuencoded file `in_file` placing the result on file `out_file`. If `out_file` is a pathname, `mode` is used to set the permission bits if the file must be created. Defaults for `out_file` and `mode` are taken from the uuencode header. However, if the file specified in the header already exists, a `uu.Error` is raised.

`decode()` may print a warning to standard error if the input was produced by an incorrect uuencoder and Python could recover from that error. Setting `quiet` to a true value silences this warning.

exception `uu.Error`

Subclass of `Exception`, this can be raised by `uu.decode()` under various situations, such as described above, but also including a badly formatted header, or truncated input file.

더 보기:

Module `binascii` Support module containing ASCII-to-binary and binary-to-ASCII conversions.

Structured Markup Processing Tools

Python supports a variety of modules to work with various forms of structured data markup. This includes modules to work with the Standard Generalized Markup Language (SGML) and the Hypertext Markup Language (HTML), and several interfaces for working with the Extensible Markup Language (XML).

It is important to note that modules in the `xml` package require that there be at least one SAX-compliant XML parser available. Starting with Python 2.3, the Expat parser is included with Python, so the `xml.parsers.expat` module will always be available. You may still want to be aware of the [PyXML add-on package](#); that package provides an extended set of XML libraries for Python.

The documentation for the `xml.dom` and `xml.sax` packages are the definition of the Python bindings for the DOM and SAX interfaces.

19.1 HTMLParser — Simple HTML and XHTML parser

참고: The `HTMLParser` module has been renamed to `html.parser` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

버전 2.2에 추가.

Source code: [Lib/HTMLParser.py](#)

This module defines a class `HTMLParser` which serves as the basis for parsing text files formatted in HTML (HyperText Mark-up Language) and XHTML. Unlike the parser in `htmllib`, this parser is not based on the SGML parser in `sgmlib`.

class `HTMLParser.HTMLParser`

An `HTMLParser` instance is fed HTML data and calls handler methods when start tags, end tags, text, comments, and other markup elements are encountered. The user should subclass `HTMLParser` and override its methods to implement the desired behavior.

The `HTMLParser` class is instantiated without arguments.

Unlike the parser in `htmllib`, this parser does not check that end tags match start tags or call the end-tag handler for elements which are closed implicitly by closing an outer element.

An exception is defined as well:

exception `HTMLParser.HTMLParseError`

`HTMLParser` is able to handle broken markup, but in some cases it might raise this exception when it encounters an error while parsing. This exception provides three attributes: `msg` is a brief message explaining the error, `lineno` is the number of the line on which the broken construct was detected, and `offset` is the number of characters into the line at which the construct starts.

19.1.1 Example HTML Parser Application

As a basic example, below is a simple HTML parser that uses the `HTMLParser` class to print out start tags, end tags and data as they are encountered:

```
from HTMLParser import HTMLParser

# create a subclass and override the handler methods
class MyHTMLParser(HTMLParser):
    def handle_starttag(self, tag, attrs):
        print "Encountered a start tag:", tag

    def handle_endtag(self, tag):
        print "Encountered an end tag :", tag

    def handle_data(self, data):
        print "Encountered some data :", data

# instantiate the parser and fed it some HTML
parser = MyHTMLParser()
parser.feed('<html><head><title>Test</title></head>'
          '<body><h1>Parse me!</h1></body></html>')
```

The output will then be:

```
Encountered a start tag: html
Encountered a start tag: head
Encountered a start tag: title
Encountered some data : Test
Encountered an end tag : title
Encountered an end tag : head
Encountered a start tag: body
Encountered a start tag: h1
Encountered some data : Parse me!
Encountered an end tag : h1
Encountered an end tag : body
Encountered an end tag : html
```


19.1.2 HTMLParser Methods

HTMLParser instances have the following methods:

HTMLParser.feed(*data*)

Feed some text to the parser. It is processed insofar as it consists of complete elements; incomplete data is buffered until more data is fed or *close()* is called. *data* can be either *unicode* or *str*, but passing *unicode* is advised.

HTMLParser.close()

Force processing of all buffered data as if it were followed by an end-of-file mark. This method may be redefined by a derived class to define additional processing at the end of the input, but the redefined version should always call the *HTMLParser* base class method *close()*.

HTMLParser.reset()

Reset the instance. Loses all unprocessed data. This is called implicitly at instantiation time.

HTMLParser.getpos()

Return current line number and offset.

HTMLParser.get_starttag_text()

Return the text of the most recently opened start tag. This should not normally be needed for structured processing, but may be useful in dealing with HTML 《as deployed》 or for re-generating input with minimal changes (whitespace between attributes can be preserved, etc.).

The following methods are called when data or markup elements are encountered and they are meant to be overridden in a subclass. The base class implementations do nothing (except for *handle_startendtag()*):

HTMLParser.handle_starttag(*tag*, *attrs*)

This method is called to handle the start of a tag (e.g. `<div id="main">`).

The *tag* argument is the name of the tag converted to lower case. The *attrs* argument is a list of (*name*, *value*) pairs containing the attributes found inside the tag's `<>` brackets. The *name* will be translated to lower case, and quotes in the *value* have been removed, and character and entity references have been replaced.

For instance, for the tag ``, this method would be called as `handle_starttag('a', [('href', 'https://www.cwi.nl/')])`.

버전 2.6에서 변경: All entity references from *htmlentitydefs* are now replaced in the attribute values.

HTMLParser.handle_endtag(*tag*)

This method is called to handle the end tag of an element (e.g. `</div>`).

The *tag* argument is the name of the tag converted to lower case.

HTMLParser.handle_startendtag(*tag*, *attrs*)

Similar to *handle_starttag()*, but called when the parser encounters an XHTML-style empty tag (``). This method may be overridden by subclasses which require this particular lexical information; the default implementation simply calls *handle_starttag()* and *handle_endtag()*.

HTMLParser.handle_data(*data*)

This method is called to process arbitrary data (e.g. text nodes and the content of `<script>...</script>` and `<style>...</style>`).

HTMLParser.handle_entityref(*name*)

This method is called to process a named character reference of the form `&name;` (e.g. `>`), where *name* is a general entity reference (e.g. `'gt'`).

HTMLParser.handle_charref(*name*)

This method is called to process decimal and hexadecimal numeric character references of the form `&#NNN;` and `&#xNNN;`. For example, the decimal equivalent for `>` is `>`, whereas the hexadecimal is `>`; in this case the method will receive `'62'` or `'x3E'`.

`HTMLParser.handle_comment` (*data*)

This method is called when a comment is encountered (e.g. `<!--comment-->`).

For example, the comment `<!-- comment -->` will cause this method to be called with the argument `'comment '`.

The content of Internet Explorer conditional comments (condcoms) will also be sent to this method, so, for `<!--[if IE 9]>IE9-specific content<![endif]-->`, this method will receive `'[if IE 9]>IE9-specific content<![endif] '`.

`HTMLParser.handle_decl` (*decl*)

This method is called to handle an HTML doctype declaration (e.g. `<!DOCTYPE html>`).

The *decl* parameter will be the entire contents of the declaration inside the `<![...]>` markup (e.g. `'DOCTYPE html'`).

`HTMLParser.handle_pi` (*data*)

This method is called when a processing instruction is encountered. The *data* parameter will contain the entire processing instruction. For example, for the processing instruction `<?proc color='red'>`, this method would be called as `handle_pi("proc color='red'")`.

참고: The `HTMLParser` class uses the SGML syntactic rules for processing instructions. An XHTML processing instruction using the trailing `'?'` will cause the `'?'` to be included in *data*.

`HTMLParser.unknown_decl` (*data*)

This method is called when an unrecognized declaration is read by the parser.

The *data* parameter will be the entire contents of the declaration inside the `<![...]>` markup. It is sometimes useful to be overridden by a derived class.

19.1.3 Examples

The following class implements a parser that will be used to illustrate more examples:

```
from HTMLParser import HTMLParser
from htmlentitydefs import name2codepoint

class MyHTMLParser(HTMLParser):
    def handle_starttag(self, tag, attrs):
        print "Start tag:", tag
        for attr in attrs:
            print "    attr:", attr

    def handle_endtag(self, tag):
        print "End tag  :", tag

    def handle_data(self, data):
        print "Data      :", data

    def handle_comment(self, data):
        print "Comment  :", data

    def handle_entityref(self, name):
        c = unichr(name2codepoint[name])
        print "Named ent:", c
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

def handle_charref(self, name):
    if name.startswith('x'):
        c = unichr(int(name[1:], 16))
    else:
        c = unichr(int(name))
    print "Num ent  :", c

def handle_decl(self, data):
    print "Decl     :", data

parser = MyHTMLParser()

```

Parsing a doctype:

```

>>> parser.feed('<!DOCTYPE HTML PUBLIC "-//W3C//DTD HTML 4.01//EN" '
...           '"http://www.w3.org/TR/html4/strict.dtd">')
Decl      : DOCTYPE HTML PUBLIC "-//W3C//DTD HTML 4.01//EN" "http://www.w3.org/TR/
->html4/strict.dtd"

```

Parsing an element with a few attributes and a title:

```

>>> parser.feed('')
Start tag: img
      attr: ('src', 'python-logo.png')
      attr: ('alt', 'The Python logo')
>>>
>>> parser.feed('<h1>Python</h1>')
Start tag: h1
Data      : Python
End tag   : h1

```

The content of script and style elements is returned as is, without further parsing:

```

>>> parser.feed('<style type="text/css">#python { color: green }</style>')
Start tag: style
      attr: ('type', 'text/css')
Data      : #python { color: green }
End tag   : style

>>> parser.feed('<script type="text/javascript">'
...           'alert("<strong>hello!</strong>");</script>')
Start tag: script
      attr: ('type', 'text/javascript')
Data      : alert("<strong>hello!</strong>");
End tag   : script

```

Parsing comments:

```

>>> parser.feed('<!-- a comment -->'
...           '<!--[if IE 9]>IE-specific content<![endif]-->')
Comment   : a comment
Comment   : [if IE 9]>IE-specific content<![endif]

```

Parsing named and numeric character references and converting them to the correct char (note: these 3 references are all equivalent to '>'):

```
>>> parser.feed('&gt;&#62;&#x3E;')
Named ent: >
Num ent   : >
Num ent   : >
```

Feeding incomplete chunks to `feed()` works, but `handle_data()` might be called more than once:

```
>>> for chunk in ['<sp', 'an>buff', 'ered ', 'text</s', 'pan>']:
...     parser.feed(chunk)
...
Start tag: span
Data      : buff
Data      : ered
Data      : text
End tag   : span
```

Parsing invalid HTML (e.g. unquoted attributes) also works:

```
>>> parser.feed('<p><a class=link href=#main>tag soup</p ></a>')
Start tag: p
Start tag: a
      attr: ('class', 'link')
      attr: ('href', '#main')
Data      : tag soup
End tag   : p
End tag   : a
```

19.2 sgmllib — Simple SGML parser

버전 2.6부터 폐지: The `sgmlib` module has been removed in Python 3.

This module defines a class `SGMLParser` which serves as the basis for parsing text files formatted in SGML (Standard Generalized Mark-up Language). In fact, it does not provide a full SGML parser — it only parses SGML insofar as it is used by HTML, and the module only exists as a base for the `htmlib` module. Another HTML parser which supports XHTML and offers a somewhat different interface is available in the `HTMLParser` module.

class sgmlib.SGMLParser

The `SGMLParser` class is instantiated without arguments. The parser is hardcoded to recognize the following constructs:

- Opening and closing tags of the form `<tag attr="value" ...>` and `</tag>`, respectively.
- Numeric character references of the form `&#name;`.
- Entity references of the form `&name;`.
- SGML comments of the form `<!--text-->`. Note that spaces, tabs, and newlines are allowed between the trailing `>` and the immediately preceding `--`.

A single exception is defined as well:

exception sgmlib.SGMLParseError

Exception raised by the `SGMLParser` class when it encounters an error while parsing.

버전 2.1에 추가.

`SGMLParser` instances have the following methods:

`SGMLParser.reset()`

Reset the instance. Loses all unprocessed data. This is called implicitly at instantiation time.

`SGMLParser.setnomoretags()`

Stop processing tags. Treat all following input as literal input (CDATA). (This is only provided so the HTML tag `<PLAINTEXT>` can be implemented.)

`SGMLParser.setliteral()`

Enter literal mode (CDATA mode).

`SGMLParser.feed(data)`

Feed some text to the parser. It is processed insofar as it consists of complete elements; incomplete data is buffered until more data is fed or `close()` is called.

`SGMLParser.close()`

Force processing of all buffered data as if it were followed by an end-of-file mark. This method may be redefined by a derived class to define additional processing at the end of the input, but the redefined version should always call `close()`.

`SGMLParser.get_starttag_text()`

Return the text of the most recently opened start tag. This should not normally be needed for structured processing, but may be useful in dealing with HTML *as deployed* or for re-generating input with minimal changes (whitespace between attributes can be preserved, etc.).

`SGMLParser.handle_starttag(tag, method, attributes)`

This method is called to handle start tags for which either a `start_tag()` or `do_tag()` method has been defined. The *tag* argument is the name of the tag converted to lower case, and the *method* argument is the bound method which should be used to support semantic interpretation of the start tag. The *attributes* argument is a list of (*name*, *value*) pairs containing the attributes found inside the tag's `<>` brackets.

The *name* has been translated to lower case. Double quotes and backslashes in the *value* have been interpreted, as well as known character references and known entity references terminated by a semicolon (normally, entity references can be terminated by any non-alphanumeric character, but this would break the very common case of `` when *eggs* is a valid entity name).

For instance, for the tag ``, this method would be called as `unknown_starttag('a', [('href', 'http://www.cwi.nl/')])`. The base implementation simply calls *method* with *attributes* as the only argument.

버전 2.5에 추가: Handling of entity and character references within attribute values.

`SGMLParser.handle_endtag(tag, method)`

This method is called to handle endtags for which an `end_tag()` method has been defined. The *tag* argument is the name of the tag converted to lower case, and the *method* argument is the bound method which should be used to support semantic interpretation of the end tag. If no `end_tag()` method is defined for the closing element, this handler is not called. The base implementation simply calls *method*.

`SGMLParser.handle_data(data)`

This method is called to process arbitrary data. It is intended to be overridden by a derived class; the base class implementation does nothing.

`SGMLParser.handle_charref(ref)`

This method is called to process a character reference of the form `&#ref;`. The base implementation uses `convert_charref()` to convert the reference to a string. If that method returns a string, it is passed to `handle_data()`, otherwise `unknown_charref(ref)` is called to handle the error.

버전 2.5에서 변경: Use `convert_charref()` instead of hard-coding the conversion.

`SGMLParser.convert_charref(ref)`

Convert a character reference to a string, or None. *ref* is the reference passed in as a string. In the base implementation, *ref* must be a decimal number in the range 0–255. It converts the code point found using the

`convert_codepoint()` method. If *ref* is invalid or out of range, this method returns `None`. This method is called by the default `handle_charref()` implementation and by the attribute value parser.

버전 2.5에 추가.

`SGMLParser.convert_codepoint(codepoint)`

Convert a code point to a `str` value. Encodings can be handled here if appropriate, though the rest of `sgmllib` is oblivious on this matter.

버전 2.5에 추가.

`SGMLParser.handle_entityref(ref)`

This method is called to process a general entity reference of the form `&ref;` where *ref* is a general entity reference. It converts *ref* by passing it to `convert_entityref()`. If a translation is returned, it calls the method `handle_data()` with the translation; otherwise, it calls the method `unknown_entityref(ref)`. The default `entitydefs` defines translations for `&`, `'`, `>`, `<`, and `"`.

버전 2.5에서 변경: Use `convert_entityref()` instead of hard-coding the conversion.

`SGMLParser.convert_entityref(ref)`

Convert a named entity reference to a `str` value, or `None`. The resulting value will not be parsed. *ref* will be only the name of the entity. The default implementation looks for *ref* in the instance (or class) variable `entitydefs` which should be a mapping from entity names to corresponding translations. If no translation is available for *ref*, this method returns `None`. This method is called by the default `handle_entityref()` implementation and by the attribute value parser.

버전 2.5에 추가.

`SGMLParser.handle_comment(comment)`

This method is called when a comment is encountered. The *comment* argument is a string containing the text between the `<!--` and `-->` delimiters, but not the delimiters themselves. For example, the comment `<!--text-->` will cause this method to be called with the argument `'text'`. The default method does nothing.

`SGMLParser.handle_decl(data)`

Method called when an SGML declaration is read by the parser. In practice, the `DOCTYPE` declaration is the only thing observed in HTML, but the parser does not discriminate among different (or broken) declarations. Internal subsets in a `DOCTYPE` declaration are not supported. The *data* parameter will be the entire contents of the declaration inside the `<! ... >` markup. The default implementation does nothing.

`SGMLParser.report_unbalanced(tag)`

This method is called when an end tag is found which does not correspond to any open element.

`SGMLParser.unknown_starttag(tag, attributes)`

This method is called to process an unknown start tag. It is intended to be overridden by a derived class; the base class implementation does nothing.

`SGMLParser.unknown_endtag(tag)`

This method is called to process an unknown end tag. It is intended to be overridden by a derived class; the base class implementation does nothing.

`SGMLParser.unknown_charref(ref)`

This method is called to process unresolvable numeric character references. Refer to `handle_charref()` to determine what is handled by default. It is intended to be overridden by a derived class; the base class implementation does nothing.

`SGMLParser.unknown_entityref(ref)`

This method is called to process an unknown entity reference. It is intended to be overridden by a derived class; the base class implementation does nothing.

Apart from overriding or extending the methods listed above, derived classes may also define methods of the following form to define processing of specific tags. Tag names in the input stream are case independent; the *tag* occurring in

method names must be in lower case:

`SGMLParser.start_tag(attributes)`

This method is called to process an opening tag *tag*. It has preference over `do_tag()`. The *attributes* argument has the same meaning as described for `handle_starttag()` above.

`SGMLParser.do_tag(attributes)`

This method is called to process an opening tag *tag* for which no `start_tag()` method is defined. The *attributes* argument has the same meaning as described for `handle_starttag()` above.

`SGMLParser.end_tag()`

This method is called to process a closing tag *tag*.

Note that the parser maintains a stack of open elements for which no end tag has been found yet. Only tags processed by `start_tag()` are pushed on this stack. Definition of an `end_tag()` method is optional for these tags. For tags processed by `do_tag()` or by `unknown_tag()`, no `end_tag()` method must be defined; if defined, it will not be used. If both `start_tag()` and `do_tag()` methods exist for a tag, the `start_tag()` method takes precedence.

19.3 htmllib — A parser for HTML documents

버전 2.6부터 폐지: The `htmllib` module has been removed in Python 3. Use `HTMLParser` instead in Python 2, and the equivalent, `html.parser`, in Python 3.

This module defines a class which can serve as a base for parsing text files formatted in the HyperText Mark-up Language (HTML). The class is not directly concerned with I/O — it must be provided with input in string form via a method, and makes calls to methods of a *formatter* object in order to produce output. The `HTMLParser` class is designed to be used as a base class for other classes in order to add functionality, and allows most of its methods to be extended or overridden. In turn, this class is derived from and extends the `SGMLParser` class defined in module `sgmlib`. The `HTMLParser` implementation supports the HTML 2.0 language as described in [RFC 1866](#). Two implementations of formatter objects are provided in the `formatter` module; refer to the documentation for that module for information on the formatter interface.

The following is a summary of the interface defined by `sgmlib.SGMLParser`:

- The interface to feed data to an instance is through the `feed()` method, which takes a string argument. This can be called with as little or as much text at a time as desired; `p.feed(a)`; `p.feed(b)` has the same effect as `p.feed(a+b)`. When the data contains complete HTML markup constructs, these are processed immediately; incomplete constructs are saved in a buffer. To force processing of all unprocessed data, call the `close()` method.

For example, to parse the entire contents of a file, use:

```
parser.feed(open('myfile.html').read())
parser.close()
```

- The interface to define semantics for HTML tags is very simple: derive a class and define methods called `start_tag()`, `end_tag()`, or `do_tag()`. The parser will call these at appropriate moments: `start_tag()` or `do_tag()` is called when an opening tag of the form `<tag ...>` is encountered; `end_tag()` is called when a closing tag of the form `</tag>` is encountered. If an opening tag requires a corresponding closing tag, like `<H1> ... </H1>`, the class should define the `start_tag()` method; if a tag requires no closing tag, like `<P>`, the class should define the `do_tag()` method.

The module defines a parser class and an exception:

class `htmllib.HTMLParser(formatter)`

This is the basic HTML parser class. It supports all entity names required by the XHTML 1.0 Recommendation (<https://www.w3.org/TR/xhtml1>). It also defines handlers for all HTML 2.0 and many HTML 3.0 and 3.2 elements.

exception `htmllib.HTMLParseError`

Exception raised by the `HTMLParser` class when it encounters an error while parsing.

버전 2.4에 추가.

더 보기:

Module `formatter` Interface definition for transforming an abstract flow of formatting events into specific output events on writer objects.

Module `HTMLParser` Alternate HTML parser that offers a slightly lower-level view of the input, but is designed to work with XHTML, and does not implement some of the SGML syntax not used in 《HTML as deployed》 and which isn't legal for XHTML.

Module `htmlentitydefs` Definition of replacement text for XHTML 1.0 entities.

Module `sgmlib` Base class for `HTMLParser`.

19.3.1 HTMLParser Objects

In addition to tag methods, the `HTMLParser` class provides some additional methods and instance variables for use within tag methods.

`HTMLParser.formatter`

This is the formatter instance associated with the parser.

`HTMLParser.nofill`

Boolean flag which should be true when whitespace should not be collapsed, or false when it should be. In general, this should only be true when character data is to be treated as 《preformatted》 text, as within a `<PRE>` element. The default value is false. This affects the operation of `handle_data()` and `save_end()`.

`HTMLParser.anchor_bgn(href, name, type)`

This method is called at the start of an anchor region. The arguments correspond to the attributes of the `<A>` tag with the same names. The default implementation maintains a list of hyperlinks (defined by the `HREF` attribute for `<A>` tags) within the document. The list of hyperlinks is available as the data attribute `anchorlist`.

`HTMLParser.anchor_end()`

This method is called at the end of an anchor region. The default implementation adds a textual footnote marker using an index into the list of hyperlinks created by `anchor_bgn()`.

`HTMLParser.handle_image(source, alt[, ismap[, align[, width[, height]]]])`

This method is called to handle images. The default implementation simply passes the `alt` value to the `handle_data()` method.

`HTMLParser.save_bgn()`

Begins saving character data in a buffer instead of sending it to the formatter object. Retrieve the stored data via `save_end()`. Use of the `save_bgn()` / `save_end()` pair may not be nested.

`HTMLParser.save_end()`

Ends buffering character data and returns all data saved since the preceding call to `save_bgn()`. If the `nofill` flag is false, whitespace is collapsed to single spaces. A call to this method without a preceding call to `save_bgn()` will raise a `TypeError` exception.

19.4 `htmlentitydefs` — Definitions of HTML general entities

참고: The `htmlentitydefs` module has been renamed to `html.entities` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

Source code: [Lib/htmlentitydefs.py](#)

This module defines three dictionaries, `name2codepoint`, `codepoint2name`, and `entitydefs`. `entitydefs` is used by the `html` module to provide the `entitydefs` attribute of the `HTMLParser` class. The definition provided here contains all the entities defined by XHTML 1.0 that can be handled using simple textual substitution in the Latin-1 character set (ISO-8859-1).

`htmlentitydefs.entitydefs`

A dictionary mapping XHTML 1.0 entity definitions to their replacement text in ISO Latin-1.

`htmlentitydefs.name2codepoint`

A dictionary that maps HTML entity names to the Unicode code points.

버전 2.3에 추가.

`htmlentitydefs.codepoint2name`

A dictionary that maps Unicode code points to HTML entity names.

버전 2.3에 추가.

19.5 XML Processing Modules

Python's interfaces for processing XML are grouped in the `xml` package.

경고: The XML modules are not secure against erroneous or maliciously constructed data. If you need to parse untrusted or unauthenticated data see *XML vulnerabilities*.

It is important to note that modules in the `xml` package require that there be at least one SAX-compliant XML parser available. The Expat parser is included with Python, so the `xml.parsers.expat` module will always be available.

The documentation for the `xml.dom` and `xml.sax` packages are the definition of the Python bindings for the DOM and SAX interfaces.

The XML handling submodules are:

- `xml.etree.ElementTree`: the ElementTree API, a simple and lightweight XML processor
- `xml.dom`: the DOM API definition
- `xml.dom.minidom`: a minimal DOM implementation
- `xml.dom.pulldom`: support for building partial DOM trees
- `xml.sax`: SAX2 base classes and convenience functions
- `xml.parsers.expat`: the Expat parser binding

19.6 XML vulnerabilities

The XML processing modules are not secure against maliciously constructed data. An attacker can abuse vulnerabilities for e.g. denial of service attacks, to access local files, to generate network connections to other machines, or to or circumvent firewalls. The attacks on XML abuse unfamiliar features like inline [DTD](#) (document type definition) with entities.

The following table gives an overview of the known attacks and if the various modules are vulnerable to them.

kind	sax	etree	minidom	pullDOM	xmlrpc
billion laughs	Vulnerable	Vulnerable	Vulnerable	Vulnerable	Vulnerable
quadratic blowup	Vulnerable	Vulnerable	Vulnerable	Vulnerable	Vulnerable
external entity expansion	Vulnerable	Safe (1)	Safe (2)	Vulnerable	Safe (3)
DTD retrieval	Vulnerable	Safe	Safe	Vulnerable	Safe
decompression bomb	Safe	Safe	Safe	Safe	Vulnerable

1. `xml.etree.ElementTree` doesn't expand external entities and raises a `ParserError` when an entity occurs.
2. `xml.dom.minidom` doesn't expand external entities and simply returns the unexpanded entity verbatim.
3. `xmlrpclib` doesn't expand external entities and omits them.

billion laughs / exponential entity expansion The [Billion Laughs](#) attack – also known as exponential entity expansion – uses multiple levels of nested entities. Each entity refers to another entity several times, the final entity definition contains a small string. Eventually the small string is expanded to several gigabytes. The exponential expansion consumes lots of CPU time, too.

quadratic blowup entity expansion A quadratic blowup attack is similar to a [Billion Laughs](#) attack; it abuses entity expansion, too. Instead of nested entities it repeats one large entity with a couple of thousand chars over and over again. The attack isn't as efficient as the exponential case but it avoids triggering countermeasures of parsers against heavily nested entities.

external entity expansion Entity declarations can contain more than just text for replacement. They can also point to external resources by public identifiers or system identifiers. System identifiers are standard URIs or can refer to local files. The XML parser retrieves the resource with e.g. HTTP or FTP requests and embeds the content into the XML document.

DTD retrieval Some XML libraries like Python's `xml.dom.pullDOM` retrieve document type definitions from remote or local locations. The feature has similar implications as the external entity expansion issue.

decompression bomb The issue of decompression bombs (aka [ZIP bomb](#)) apply to all XML libraries that can parse compressed XML stream like gzipped HTTP streams or LZMA-ed files. For an attacker it can reduce the amount of transmitted data by three magnitudes or more.

The documentation of [defusedxml](#) on PyPI has further information about all known attack vectors with examples and references.

19.6.1 defused packages

These external packages are recommended for any code that parses untrusted XML data.

[defusedxml](#) is a pure Python package with modified subclasses of all stdlib XML parsers that prevent any potentially malicious operation. The package also ships with example exploits and extended documentation on more XML exploits like xpath injection.

[defusedexpat](#) provides a modified libexpat and patched replacement `pyexpat` extension module with countermeasures against entity expansion DoS attacks. Defusedexpat still allows a sane and configurable amount of entity expansions. The modifications will be merged into future releases of Python.

The workarounds and modifications are not included in patch releases as they break backward compatibility. After all inline DTD and entity expansion are well-defined XML features.

19.7 `xml.etree.ElementTree` — The ElementTree XML API

버전 2.5에 추가.

Source code: [Lib/xml/etree/ElementTree.py](#)

The *Element* type is a flexible container object, designed to store hierarchical data structures in memory. The type can be described as a cross between a list and a dictionary.

경고: The `xml.etree.ElementTree` module is not secure against maliciously constructed data. If you need to parse untrusted or unauthenticated data see [XML vulnerabilities](#).

Each element has a number of properties associated with it:

- a tag which is a string identifying what kind of data this element represents (the element type, in other words).
- a number of attributes, stored in a Python dictionary.
- a text string.
- an optional tail string.
- a number of child elements, stored in a Python sequence

To create an element instance, use the *Element* constructor or the *SubElement()* factory function.

The *ElementTree* class can be used to wrap an element structure, and convert it from and to XML.

A C implementation of this API is available as `xml.etree.cElementTree`.

See <http://effbot.org/zone/element-index.htm> for tutorials and links to other docs. Fredrik Lundh's page is also the location of the development version of the `xml.etree.ElementTree`.

버전 2.7에서 변경: The ElementTree API is updated to 1.3. For more information, see [Introducing ElementTree 1.3](#).

19.7.1 Tutorial

This is a short tutorial for using `xml.etree.ElementTree` (ET in short). The goal is to demonstrate some of the building blocks and basic concepts of the module.

XML tree and elements

XML is an inherently hierarchical data format, and the most natural way to represent it is with a tree. ET has two classes for this purpose - *ElementTree* represents the whole XML document as a tree, and *Element* represents a single node in this tree. Interactions with the whole document (reading and writing to/from files) are usually done on the *ElementTree* level. Interactions with a single XML element and its sub-elements are done on the *Element* level.

Parsing XML

We'll be using the following XML document as the sample data for this section:

```
<?xml version="1.0"?>
<data>
  <country name="Liechtenstein">
    <rank>1</rank>
    <year>2008</year>
    <gdppc>141100</gdppc>
    <neighbor name="Austria" direction="E"/>
    <neighbor name="Switzerland" direction="W"/>
  </country>
  <country name="Singapore">
    <rank>4</rank>
    <year>2011</year>
    <gdppc>59900</gdppc>
    <neighbor name="Malaysia" direction="N"/>
  </country>
  <country name="Panama">
    <rank>68</rank>
    <year>2011</year>
    <gdppc>13600</gdppc>
    <neighbor name="Costa Rica" direction="W"/>
    <neighbor name="Colombia" direction="E"/>
  </country>
</data>
```

We have a number of ways to import the data. Reading the file from disk:

```
import xml.etree.ElementTree as ET
tree = ET.parse('country_data.xml')
root = tree.getroot()
```

Reading the data from a string:

```
root = ET.fromstring(country_data_as_string)
```

fromstring() parses XML from a string directly into an *Element*, which is the root element of the parsed tree. Other parsing functions may create an *ElementTree*. Check the documentation to be sure.

As an *Element*, *root* has a tag and a dictionary of attributes:

```
>>> root.tag
'data'
>>> root.attrib
{}
```

It also has children nodes over which we can iterate:

```
>>> for child in root:
...     print child.tag, child.attrib
...
country {'name': 'Liechtenstein'}
country {'name': 'Singapore'}
country {'name': 'Panama'}
```

Children are nested, and we can access specific child nodes by index:

```
>>> root[0][1].text
'2008'
```

Finding interesting elements

Element has some useful methods that help iterate recursively over all the sub-tree below it (its children, their children, and so on). For example, *Element.iter()*:

```
>>> for neighbor in root.iter('neighbor'):
...     print neighbor.attrib
...
{'name': 'Austria', 'direction': 'E'}
{'name': 'Switzerland', 'direction': 'W'}
{'name': 'Malaysia', 'direction': 'N'}
{'name': 'Costa Rica', 'direction': 'W'}
{'name': 'Colombia', 'direction': 'E'}
```

Element.findall() finds only elements with a tag which are direct children of the current element. *Element.find()* finds the *first* child with a particular tag, and *Element.text* accesses the element's text content. *Element.get()* accesses the element's attributes:

```
>>> for country in root.findall('country'):
...     rank = country.find('rank').text
...     name = country.get('name')
...     print name, rank
...
Liechtenstein 1
Singapore 4
Panama 68
```

More sophisticated specification of which elements to look for is possible by using *XPath*.

Modifying an XML File

ElementTree provides a simple way to build XML documents and write them to files. The *ElementTree.write()* method serves this purpose.

Once created, an *Element* object may be manipulated by directly changing its fields (such as *Element.text*), adding and modifying attributes (*Element.set()* method), as well as adding new children (for example with *Element.append()*).

Let's say we want to add one to each country's rank, and add an *updated* attribute to the rank element:

```
>>> for rank in root.iter('rank'):
...     new_rank = int(rank.text) + 1
...     rank.text = str(new_rank)
...     rank.set('updated', 'yes')
...
>>> tree.write('output.xml')
```

Our XML now looks like this:

```
<?xml version="1.0"?>
<data>
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

<country name="Liechtenstein">
  <rank updated="yes">2</rank>
  <year>2008</year>
  <gdppc>141100</gdppc>
  <neighbor name="Austria" direction="E"/>
  <neighbor name="Switzerland" direction="W"/>
</country>
<country name="Singapore">
  <rank updated="yes">5</rank>
  <year>2011</year>
  <gdppc>59900</gdppc>
  <neighbor name="Malaysia" direction="N"/>
</country>
<country name="Panama">
  <rank updated="yes">69</rank>
  <year>2011</year>
  <gdppc>13600</gdppc>
  <neighbor name="Costa Rica" direction="W"/>
  <neighbor name="Colombia" direction="E"/>
</country>
</data>

```

We can remove elements using `Element.remove()`. Let's say we want to remove all countries with a rank higher than 50:

```

>>> for country in root.findall('country'):
...     rank = int(country.find('rank').text)
...     if rank > 50:
...         root.remove(country)
...
>>> tree.write('output.xml')

```

Our XML now looks like this:

```

<?xml version="1.0"?>
<data>
  <country name="Liechtenstein">
    <rank updated="yes">2</rank>
    <year>2008</year>
    <gdppc>141100</gdppc>
    <neighbor name="Austria" direction="E"/>
    <neighbor name="Switzerland" direction="W"/>
  </country>
  <country name="Singapore">
    <rank updated="yes">5</rank>
    <year>2011</year>
    <gdppc>59900</gdppc>
    <neighbor name="Malaysia" direction="N"/>
  </country>
</data>

```

Building XML documents

The `SubElement()` function also provides a convenient way to create new sub-elements for a given element:

```
>>> a = ET.Element('a')
>>> b = ET.SubElement(a, 'b')
>>> c = ET.SubElement(a, 'c')
>>> d = ET.SubElement(c, 'd')
>>> ET.dump(a)
<a><b /><c><d /></c></a>
```

Parsing XML with Namespaces

If the XML input has [namespaces](#), tags and attributes with prefixes in the form `prefix:sometag` get expanded to `{uri}sometag` where the *prefix* is replaced by the full *URI*. Also, if there is a [default namespace](#), that full URI gets prepended to all of the non-prefixed tags.

Here is an XML example that incorporates two namespaces, one with the prefix `fictional` and the other serving as the default namespace:

```
<?xml version="1.0"?>
<actors xmlns:fictional="http://characters.example.com"
        xmlns="http://people.example.com">
  <actor>
    <name>John Cleese</name>
    <fictional:character>Lancelot</fictional:character>
    <fictional:character>Archie Leach</fictional:character>
  </actor>
  <actor>
    <name>Eric Idle</name>
    <fictional:character>Sir Robin</fictional:character>
    <fictional:character>Gunther</fictional:character>
    <fictional:character>Commander Clement</fictional:character>
  </actor>
</actors>
```

One way to search and explore this XML example is to manually add the URI to every tag or attribute in the `xpath` of a `find()` or `findall()`:

```
root = fromstring(xml_text)
for actor in root.findall('{http://people.example.com}actor'):
    name = actor.find('{http://people.example.com}name')
    print name.text
    for char in actor.findall('{http://characters.example.com}character'):
        print ' |-->', char.text
```

A better way to search the namespaced XML example is to create a dictionary with your own prefixes and use those in the search functions:

```
ns = {'real_person': 'http://people.example.com',
      'role': 'http://characters.example.com'}

for actor in root.findall('real_person:actor', ns):
    name = actor.find('real_person:name', ns)
    print name.text
    for char in actor.findall('role:character', ns):
        print ' |-->', char.text
```

These two approaches both output:

```
John Cleese
|--> Lancelot
|--> Archie Leach
Eric Idle
|--> Sir Robin
|--> Gunther
|--> Commander Clement
```

Additional resources

See <http://effbot.org/zone/element-index.htm> for tutorials and links to other docs.

19.7.2 XPath support

This module provides limited support for [XPath expressions](#) for locating elements in a tree. The goal is to support a small subset of the abbreviated syntax; a full XPath engine is outside the scope of the module.

Example

Here's an example that demonstrates some of the XPath capabilities of the module. We'll be using the `countrydata` XML document from the *Parsing XML* section:

```
import xml.etree.ElementTree as ET

root = ET.fromstring(countrydata)

# Top-level elements
root.findall(".")

# All 'neighbor' grand-children of 'country' children of the top-level
# elements
root.findall("./country/neighbor")

# Nodes with name='Singapore' that have a 'year' child
root.findall("./year/..[@name='Singapore']")

# 'year' nodes that are children of nodes with name='Singapore'
root.findall("./*[@name='Singapore']/year")

# All 'neighbor' nodes that are the second child of their parent
root.findall("./neighbor[2]")
```


Supported XPath syntax

Syntax	Meaning
<code>tag</code>	Selects all child elements with the given tag. For example, <code>spam</code> selects all child elements named <code>spam</code> , and <code>spam/egg</code> selects all grandchildren named <code>egg</code> in all children named <code>spam</code> .
<code>*</code>	Selects all child elements. For example, <code>*/egg</code> selects all grandchildren named <code>egg</code> .
<code>.</code>	Selects the current node. This is mostly useful at the beginning of the path, to indicate that it's a relative path.
<code>//</code>	Selects all subelements, on all levels beneath the current element. For example, <code>./egg</code> selects all <code>egg</code> elements in the entire tree.
<code>..</code>	Selects the parent element.
<code>[@attrib]</code>	Selects all elements that have the given attribute.
<code>[@attrib='value']</code>	Selects all elements for which the given attribute has the given value. The value cannot contain quotes.
<code>[tag]</code>	Selects all elements that have a child named <code>tag</code> . Only immediate children are supported.
<code>[tag='text']</code>	Selects all elements that have a child named <code>tag</code> whose complete text content, including descendants, equals the given <code>text</code> .
<code>[position]</code>	Selects all elements that are located at the given position. The position can be either an integer (1 is the first position), the expression <code>last()</code> (for the last position), or a position relative to the last position (e.g. <code>last()-1</code>).

Predicates (expressions within square brackets) must be preceded by a tag name, an asterisk, or another predicate. `position` predicates must be preceded by a tag name.

19.7.3 Reference

Functions

`xml.etree.ElementTree.Comment` (*text=None*)

Comment element factory. This factory function creates a special element that will be serialized as an XML comment by the standard serializer. The comment string can be either a bytestring or a Unicode string. *text* is a string containing the comment string. Returns an element instance representing a comment.

`xml.etree.ElementTree.dump` (*elem*)

Writes an element tree or element structure to `sys.stdout`. This function should be used for debugging only.

The exact output format is implementation dependent. In this version, it's written as an ordinary XML file.

elem is an element tree or an individual element.

`xml.etree.ElementTree.fromstring` (*text*)

Parses an XML section from a string constant. Same as `XML()`. *text* is a string containing XML data. Returns an *Element* instance.

`xml.etree.ElementTree.fromstringlist` (*sequence, parser=None*)

Parses an XML document from a sequence of string fragments. *sequence* is a list or other sequence containing XML data fragments. *parser* is an optional parser instance. If not given, the standard *XMLParser* parser is used. Returns an *Element* instance.

버전 2.7에 추가.

`xml.etree.ElementTree.iselement (element)`

Checks if an object appears to be a valid element object. *element* is an element instance. Returns a true value if this is an element object.

`xml.etree.ElementTree.iterparse (source, events=None, parser=None)`

Parses an XML section into an element tree incrementally, and reports what's going on to the user. *source* is a filename or file object containing XML data. *events* is a list of events to report back. If omitted, only `<<end>>` events are reported. *parser* is an optional parser instance. If not given, the standard `XMLParser` parser is used. *parser* is not supported by `cElementTree`. Returns an *iterator* providing (event, elem) pairs.

참고: `iterparse()` only guarantees that it has seen the `<>` character of a starting tag when it emits a `<start>` event, so the attributes are defined, but the contents of the text and tail attributes are undefined at that point. The same applies to the element children; they may or may not be present.

If you need a fully populated element, look for `<end>` events instead.

`xml.etree.ElementTree.parse (source, parser=None)`

Parses an XML section into an element tree. *source* is a filename or file object containing XML data. *parser* is an optional parser instance. If not given, the standard `XMLParser` parser is used. Returns an `ElementTree` instance.

`xml.etree.ElementTree.ProcessingInstruction (target, text=None)`

PI element factory. This factory function creates a special element that will be serialized as an XML processing instruction. *target* is a string containing the PI target. *text* is a string containing the PI contents, if given. Returns an element instance, representing a processing instruction.

`xml.etree.ElementTree.register_namespace (prefix, uri)`

Registers a namespace prefix. The registry is global, and any existing mapping for either the given prefix or the namespace URI will be removed. *prefix* is a namespace prefix. *uri* is a namespace uri. Tags and attributes in this namespace will be serialized with the given prefix, if at all possible.

버전 2.7에 추가.

`xml.etree.ElementTree.SubElement (parent, tag, attrib={}, **extra)`

Subelement factory. This function creates an element instance, and appends it to an existing element.

The element name, attribute names, and attribute values can be either bytestrings or Unicode strings. *parent* is the parent element. *tag* is the subelement name. *attrib* is an optional dictionary, containing element attributes. *extra* contains additional attributes, given as keyword arguments. Returns an element instance.

`xml.etree.ElementTree.tostring (element, encoding="us-ascii", method="xml")`

Generates a string representation of an XML element, including all subelements. *element* is an `Element` instance. *encoding*¹ is the output encoding (default is US-ASCII). *method* is either `"xml"`, `"html"` or `"text"` (default is `"xml"`). Returns an encoded string containing the XML data.

`xml.etree.ElementTree.tostringlist (element, encoding="us-ascii", method="xml")`

Generates a string representation of an XML element, including all subelements. *element* is an `Element` instance. *encoding*¹ is the output encoding (default is US-ASCII). *method* is either `"xml"`, `"html"` or `"text"` (default is `"xml"`). Returns a list of encoded strings containing the XML data. It does not guarantee any specific sequence, except that `"".join(tostringlist(element)) == tostring(element)`.

버전 2.7에 추가.

`xml.etree.ElementTree.XML (text, parser=None)`

Parses an XML section from a string constant. This function can be used to embed `<XML literals>` in Python code.

¹ The encoding string included in XML output should conform to the appropriate standards. For example, `<UTF-8>` is valid, but `<UTF8>` is not. See <https://www.w3.org/TR/2006/REC-xml11-20060816/#NT-EncodingDecl> and <https://www.iana.org/assignments/character-sets/character-sets.xhtml>.

text is a string containing XML data. *parser* is an optional parser instance. If not given, the standard *XMLParser* parser is used. Returns an *Element* instance.

`xml.etree.ElementTree.XMLID (text, parser=None)`

Parses an XML section from a string constant, and also returns a dictionary which maps from element id:s to elements. *text* is a string containing XML data. *parser* is an optional parser instance. If not given, the standard *XMLParser* parser is used. Returns a tuple containing an *Element* instance and a dictionary.

Element Objects

class `xml.etree.ElementTree.Element (tag, attrib={}, **extra)`

Element class. This class defines the Element interface, and provides a reference implementation of this interface.

The element name, attribute names, and attribute values can be either bytestrings or Unicode strings. *tag* is the element name. *attrib* is an optional dictionary, containing element attributes. *extra* contains additional attributes, given as keyword arguments.

tag

A string identifying what kind of data this element represents (the element type, in other words).

text

tail

These attributes can be used to hold additional data associated with the element. Their values are usually strings but may be any application-specific object. If the element is created from an XML file, the *text* attribute holds either the text between the element's start tag and its first child or end tag, or `None`, and the *tail* attribute holds either the text between the element's end tag and the next tag, or `None`. For the XML data

```
<a><b>1<c>2<d/>3</c></b>4</a>
```

the *a* element has `None` for both *text* and *tail* attributes, the *b* element has *text* "1" and *tail* "4", the *c* element has *text* "2" and *tail* `None`, and the *d* element has *text* `None` and *tail* "3".

To collect the inner text of an element, see *itertext()*, for example `"".join(element.itertext())`.

Applications may store arbitrary objects in these attributes.

attrib

A dictionary containing the element's attributes. Note that while the *attrib* value is always a real mutable Python dictionary, an *ElementTree* implementation may choose to use another internal representation, and create the dictionary only if someone asks for it. To take advantage of such implementations, use the dictionary methods below whenever possible.

The following dictionary-like methods work on the element attributes.

clear ()

Resets an element. This function removes all subelements, clears all attributes, and sets the text and tail attributes to `None`.

get (key, default=None)

Gets the element attribute named *key*.

Returns the attribute value, or *default* if the attribute was not found.

items ()

Returns the element attributes as a sequence of (name, value) pairs. The attributes are returned in an arbitrary order.

keys ()

Returns the elements attribute names as a list. The names are returned in an arbitrary order.

set (*key*, *value*)

Set the attribute *key* on the element to *value*.

The following methods work on the element's children (subelements).

append (*subelement*)

Adds the element *subelement* to the end of this element's internal list of subelements.

extend (*subelements*)

Appends *subelements* from a sequence object with zero or more elements. Raises `AssertionError` if a subelement is not a valid object.

버전 2.7에 추가.

find (*match*)

Finds the first subelement matching *match*. *match* may be a tag name or path. Returns an element instance or `None`.

findall (*match*)

Finds all matching subelements, by tag name or path. Returns a list containing all matching elements in document order.

findtext (*match*, *default=None*)

Finds text for the first subelement matching *match*. *match* may be a tag name or path. Returns the text content of the first matching element, or *default* if no element was found. Note that if the matching element has no text content an empty string is returned.

getchildren ()

버전 2.7부터 폐지: Use `list(elem)` or iteration.

getiterator (*tag=None*)

버전 2.7부터 폐지: Use method `Element.iter()` instead.

insert (*index*, *element*)

Inserts a subelement at the given position in this element.

iter (*tag=None*)

Creates a tree *iterator* with the current element as the root. The iterator iterates over this element and all elements below it, in document (depth first) order. If *tag* is not `None` or `'*'`, only elements whose tag equals *tag* are returned from the iterator. If the tree structure is modified during iteration, the result is undefined.

버전 2.7에 추가.

iterfind (*match*)

Finds all matching subelements, by tag name or path. Returns an iterable yielding all matching elements in document order.

버전 2.7에 추가.

itertext ()

Creates a text iterator. The iterator loops over this element and all subelements, in document order, and returns all inner text.

버전 2.7에 추가.

makeelement (*tag*, *attrib*)

Creates a new element object of the same type as this element. Do not call this method, use the `SubElement()` factory function instead.

remove (*subelement*)

Removes *subelement* from the element. Unlike the `find*` methods this method compares elements based on the instance identity, not on tag value or contents.

Element objects also support the following sequence type methods for working with subelements: `__delitem__()`, `__getitem__()`, `__setitem__()`, `__len__()`.

Caution: Elements with no subelements will test as `False`. This behavior will change in future versions. Use specific `len(elem)` or `elem is None` test instead.

```
element = root.find('foo')

if not element: # careful!
    print "element not found, or element has no subelements"

if element is None:
    print "element not found"
```

ElementTree Objects

class `xml.etree.ElementTree.ElementTree` (*element=None, file=None*)

ElementTree wrapper class. This class represents an entire element hierarchy, and adds some extra support for serialization to and from standard XML.

element is the root element. The tree is initialized with the contents of the XML *file* if given.

_setroot (*element*)

Replaces the root element for this tree. This discards the current contents of the tree, and replaces it with the given element. Use with care. *element* is an element instance.

find (*match*)

Same as `Element.find()`, starting at the root of the tree.

findall (*match*)

Same as `Element.findall()`, starting at the root of the tree.

findtext (*match, default=None*)

Same as `Element.findtext()`, starting at the root of the tree.

getiterator (*tag=None*)

버전 2.7부터 폐지: Use method `ElementTree.iter()` instead.

getroot ()

Returns the root element for this tree.

iter (*tag=None*)

Creates and returns a tree iterator for the root element. The iterator loops over all elements in this tree, in section order. *tag* is the tag to look for (default is to return all elements).

iterfind (*match*)

Finds all matching subelements, by tag name or path. Same as `getroot().iterfind(match)`. Returns an iterable yielding all matching elements in document order.

버전 2.7에 추가.

parse (*source, parser=None*)

Loads an external XML section into this element tree. *source* is a file name or file object. *parser* is an optional parser instance. If not given, the standard XMLParser parser is used. Returns the section root element.

write (*file, encoding="us-ascii", xml_declaration=None, default_namespace=None, method="xml"*)

Writes the element tree to a file, as XML. *file* is a file name, or a file object opened for writing. *encoding*¹ is the output encoding (default is US-ASCII). *xml_declaration* controls if an XML declaration should be added to the file. Use `False` for never, `True` for always, `None` for only if not US-ASCII or UTF-8 (default

is None). *default_namespace* sets the default XML namespace (for `<xmlns>`). *method* is either "xml", "html" or "text" (default is "xml"). Returns an encoded string.

This is the XML file that is going to be manipulated:

```
<html>
  <head>
    <title>Example page</title>
  </head>
  <body>
    <p>Moved to <a href="http://example.org/">example.org</a>
    or <a href="http://example.com/">example.com</a>.</p>
  </body>
</html>
```

Example of changing the attribute `<target>` of every link in first paragraph:

```
>>> from xml.etree.ElementTree import ElementTree
>>> tree = ElementTree()
>>> tree.parse("index.xhtml")
<Element 'html' at 0xb77e6fac>
>>> p = tree.find("body/p")      # Finds first occurrence of tag p in body
>>> p
<Element 'p' at 0xb77ec26c>
>>> links = list(p.iter("a"))    # Returns list of all links
>>> links
[<Element 'a' at 0xb77ec2ac>, <Element 'a' at 0xb77ec1cc>]
>>> for i in links:              # Iterates through all found links
...     i.attrib["target"] = "blank"
...
>>> tree.write("output.xhtml")
```

QName Objects

class `xml.etree.ElementTree.QName` (*text_or_uri*, *tag=None*)

QName wrapper. This can be used to wrap a QName attribute value, in order to get proper namespace handling on output. *text_or_uri* is a string containing the QName value, in the form {uri}local, or, if the tag argument is given, the URI part of a QName. If *tag* is given, the first argument is interpreted as a URI, and this argument is interpreted as a local name. *QName* instances are opaque.

TreeBuilder Objects

class `xml.etree.ElementTree.TreeBuilder` (*element_factory=None*)

Generic element structure builder. This builder converts a sequence of start, data, and end method calls to a well-formed element structure. You can use this class to build an element structure using a custom XML parser, or a parser for some other XML-like format. The *element_factory* is called to create new *Element* instances when given.

close()

Flushes the builder buffers, and returns the toplevel document element. Returns an *Element* instance.

data (*data*)

Adds text to the current element. *data* is a string. This should be either a bytestring, or a Unicode string.

end (*tag*)

Closes the current element. *tag* is the element name. Returns the closed element.

start (*tag, attrs*)

Opens a new element. *tag* is the element name. *attrs* is a dictionary containing element attributes. Returns the opened element.

In addition, a custom *TreeBuilder* object can provide the following method:

doctype (*name, pubid, system*)

Handles a doctype declaration. *name* is the doctype name. *pubid* is the public identifier. *system* is the system identifier. This method does not exist on the default *TreeBuilder* class.

버전 2.7에 추가.

XMLParser Objects

class `xml.etree.ElementTree.XMLParser` (*html=0, target=None, encoding=None*)

Element structure builder for XML source data, based on the expat parser. *html* are predefined HTML entities. This flag is not supported by the current implementation. *target* is the target object. If omitted, the builder uses an instance of the standard *TreeBuilder* class. *encoding*¹ is optional. If given, the value overrides the encoding specified in the XML file.

close ()

Finishes feeding data to the parser. Returns an element structure.

doctype (*name, pubid, system*)

버전 2.7부터 폐지: Define the *TreeBuilder.doctype()* method on a custom *TreeBuilder* target.

feed (*data*)

Feeds data to the parser. *data* is encoded data.

XMLParser.feed() calls *target*'s *start()* method for each opening tag, its *end()* method for each closing tag, and data is processed by method *data()*. *XMLParser.close()* calls *target*'s method *close()*. *XMLParser* can be used not only for building a tree structure. This is an example of counting the maximum depth of an XML file:

```
>>> from xml.etree.ElementTree import XMLParser
>>> class MaxDepth:                                # The target object of the parser
...     maxDepth = 0
...     depth = 0
...     def start(self, tag, attrib):                # Called for each opening tag.
...         self.depth += 1
...         if self.depth > self.maxDepth:
...             self.maxDepth = self.depth
...     def end(self, tag):                            # Called for each closing tag.
...         self.depth -= 1
...     def data(self, data):
...         pass                                     # We do not need to do anything with data.
...     def close(self):                             # Called when all data has been parsed.
...         return self.maxDepth
...
>>> target = MaxDepth()
>>> parser = XMLParser(target=target)
>>> exampleXml = """
... <a>
...     <b>
...     </b>
...     <b>
...     <c>
...     <d>
...     </d>
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

...     </c>
...     </b>
... </a>"""
>>> parser.feed(exampleXml)
>>> parser.close()
4

```

19.8 `xml.dom` — The Document Object Model API

버전 2.0에 추가.

The Document Object Model, or 《DOM, 》 is a cross-language API from the World Wide Web Consortium (W3C) for accessing and modifying XML documents. A DOM implementation presents an XML document as a tree structure, or allows client code to build such a structure from scratch. It then gives access to the structure through a set of objects which provided well-known interfaces.

The DOM is extremely useful for random-access applications. SAX only allows you a view of one bit of the document at a time. If you are looking at one SAX element, you have no access to another. If you are looking at a text node, you have no access to a containing element. When you write a SAX application, you need to keep track of your program's position in the document somewhere in your own code. SAX does not do it for you. Also, if you need to look ahead in the XML document, you are just out of luck.

Some applications are simply impossible in an event driven model with no access to a tree. Of course you could build some sort of tree yourself in SAX events, but the DOM allows you to avoid writing that code. The DOM is a standard tree representation for XML data.

The Document Object Model is being defined by the W3C in stages, or 《levels 》 in their terminology. The Python mapping of the API is substantially based on the DOM Level 2 recommendation.

DOM applications typically start by parsing some XML into a DOM. How this is accomplished is not covered at all by DOM Level 1, and Level 2 provides only limited improvements: There is a `DOMImplementation` object class which provides access to `Document` creation methods, but no way to access an XML reader/parser/Document builder in an implementation-independent way. There is also no well-defined way to access these methods without an existing `Document` object. In Python, each DOM implementation will provide a function `getDOMImplementation()`. DOM Level 3 adds a Load/Store specification, which defines an interface to the reader, but this is not yet available in the Python standard library.

Once you have a DOM document object, you can access the parts of your XML document through its properties and methods. These properties are defined in the DOM specification; this portion of the reference manual describes the interpretation of the specification in Python.

The specification provided by the W3C defines the DOM API for Java, ECMAScript, and OMG IDL. The Python mapping defined here is based in large part on the IDL version of the specification, but strict compliance is not required (though implementations are free to support the strict mapping from IDL). See section [Conformance](#) for a detailed discussion of mapping requirements.

더 보기:

Document Object Model (DOM) Level 2 Specification The W3C recommendation upon which the Python DOM API is based.

Document Object Model (DOM) Level 1 Specification The W3C recommendation for the DOM supported by `xml.dom.minidom`.

Python Language Mapping Specification This specifies the mapping from OMG IDL to Python.

19.8.1 Module Contents

The `xml.dom` contains the following functions:

`xml.dom.registerDOMImplementation(name, factory)`

Register the *factory* function with the name *name*. The factory function should return an object which implements the `DOMImplementation` interface. The factory function can return the same object every time, or a new one for each call, as appropriate for the specific implementation (e.g. if that implementation supports some customization).

`xml.dom.getDOMImplementation([name[, features]])`

Return a suitable DOM implementation. The *name* is either well-known, the module name of a DOM implementation, or `None`. If it is not `None`, imports the corresponding module and returns a `DOMImplementation` object if the import succeeds. If no name is given, and if the environment variable `PYTHON_DOM` is set, this variable is used to find the implementation.

If name is not given, this examines the available implementations to find one with the required feature set. If no implementation can be found, raise an `ImportError`. The features list must be a sequence of (*feature*, *version*) pairs which are passed to the `hasFeature()` method on available `DOMImplementation` objects.

Some convenience constants are also provided:

`xml.dom.EMPTY_NAMESPACE`

The value used to indicate that no namespace is associated with a node in the DOM. This is typically found as the `namespaceURI` of a node, or used as the *namespaceURI* parameter to a namespaces-specific method.

버전 2.2에 추가.

`xml.dom.XML_NAMESPACE`

The namespace URI associated with the reserved prefix `xml`, as defined by [Namespaces in XML](#) (section 4).

버전 2.2에 추가.

`xml.dom.XMLNS_NAMESPACE`

The namespace URI for namespace declarations, as defined by [Document Object Model \(DOM\) Level 2 Core Specification](#) (section 1.1.8).

버전 2.2에 추가.

`xml.dom.XHTML_NAMESPACE`

The URI of the XHTML namespace as defined by [XHTML 1.0: The Extensible HyperText Markup Language](#) (section 3.1.1).

버전 2.2에 추가.

In addition, `xml.dom` contains a base `Node` class and the DOM exception classes. The `Node` class provided by this module does not implement any of the methods or attributes defined by the DOM specification; concrete DOM implementations must provide those. The `Node` class provided as part of this module does provide the constants used for the `nodeType` attribute on concrete `Node` objects; they are located within the class rather than at the module level to conform with the DOM specifications.

19.8.2 Objects in the DOM

The definitive documentation for the DOM is the DOM specification from the W3C.

Note that DOM attributes may also be manipulated as nodes instead of as simple strings. It is fairly rare that you must do this, however, so this usage is not yet documented.

Interface	Section	Purpose
<code>DOMImplementation</code>	<i>DOMImplementation Objects</i>	Interface to the underlying implementation.
<code>Node</code>	<i>Node Objects</i>	Base interface for most objects in a document.
<code>NodeList</code>	<i>NodeList Objects</i>	Interface for a sequence of nodes.
<code>DocumentType</code>	<i>DocumentType Objects</i>	Information about the declarations needed to process a document.
<code>Document</code>	<i>Document Objects</i>	Object which represents an entire document.
<code>Element</code>	<i>Element Objects</i>	Element nodes in the document hierarchy.
<code>Attr</code>	<i>Attr Objects</i>	Attribute value nodes on element nodes.
<code>Comment</code>	<i>Comment Objects</i>	Representation of comments in the source document.
<code>Text</code>	<i>Text and CDATASection Objects</i>	Nodes containing textual content from the document.
<code>ProcessingInstruction</code>	<i>ProcessingInstruction Objects</i>	Processing instruction representation.

An additional section describes the exceptions defined for working with the DOM in Python.

DOMImplementation Objects

The `DOMImplementation` interface provides a way for applications to determine the availability of particular features in the DOM they are using. DOM Level 2 added the ability to create new `Document` and `DocumentType` objects using the `DOMImplementation` as well.

`DOMImplementation.hasFeature` (*feature*, *version*)

Return true if the feature identified by the pair of strings *feature* and *version* is implemented.

`DOMImplementation.createDocument` (*namespaceUri*, *qualifiedName*, *doctype*)

Return a new `Document` object (the root of the DOM), with a child `Element` object having the given *namespaceUri* and *qualifiedName*. The *doctype* must be a `DocumentType` object created by `createDocumentType()`, or `None`. In the Python DOM API, the first two arguments can also be `None` in order to indicate that no `Element` child is to be created.

`DOMImplementation.createDocumentType` (*qualifiedName*, *publicId*, *systemId*)

Return a new `DocumentType` object that encapsulates the given *qualifiedName*, *publicId*, and *systemId* strings, representing the information contained in an XML document type declaration.

Node Objects

All of the components of an XML document are subclasses of `Node`.

`Node.nodeType`

An integer representing the node type. Symbolic constants for the types are on the `Node` object: `ELEMENT_NODE`, `ATTRIBUTE_NODE`, `TEXT_NODE`, `CDATA_SECTION_NODE`, `ENTITY_NODE`, `PROCESSING_INSTRUCTION_NODE`, `COMMENT_NODE`, `DOCUMENT_NODE`, `DOCUMENT_TYPE_NODE`, `NOTATION_NODE`. This is a read-only attribute.

`Node.parentNode`

The parent of the current node, or `None` for the document node. The value is always a `Node` object or `None`. For `Element` nodes, this will be the parent element, except for the root element, in which case it will be the `Document` object. For `Attr` nodes, this is always `None`. This is a read-only attribute.

`Node.attributes`

A `NamedNodeMap` of attribute objects. Only elements have actual values for this; others provide `None` for this attribute. This is a read-only attribute.

`Node.previousSibling`

The node that immediately precedes this one with the same parent. For instance the element with an end-tag that comes just before the *self* element's start-tag. Of course, XML documents are made up of more than just elements so the previous sibling could be text, a comment, or something else. If this node is the first child of the parent, this attribute will be `None`. This is a read-only attribute.

`Node.nextSibling`

The node that immediately follows this one with the same parent. See also [previousSibling](#). If this is the last child of the parent, this attribute will be `None`. This is a read-only attribute.

`Node.childNodes`

A list of nodes contained within this node. This is a read-only attribute.

`Node.firstChild`

The first child of the node, if there are any, or `None`. This is a read-only attribute.

`Node.lastChild`

The last child of the node, if there are any, or `None`. This is a read-only attribute.

`Node.localName`

The part of the `tagName` following the colon if there is one, else the entire `tagName`. The value is a string.

`Node.prefix`

The part of the `tagName` preceding the colon if there is one, else the empty string. The value is a string, or `None`.

`Node.namespaceURI`

The namespace associated with the element name. This will be a string or `None`. This is a read-only attribute.

`Node.nodeName`

This has a different meaning for each node type; see the DOM specification for details. You can always get the information you would get here from another property such as the `tagName` property for elements or the `name` property for attributes. For all node types, the value of this attribute will be either a string or `None`. This is a read-only attribute.

`Node.nodeValue`

This has a different meaning for each node type; see the DOM specification for details. The situation is similar to that with [nodeName](#). The value is a string or `None`.

`Node.hasAttributes()`

Returns true if the node has any attributes.

`Node.hasChildNodes()`

Returns true if the node has any child nodes.

`Node.isSameNode(other)`

Returns true if *other* refers to the same node as this node. This is especially useful for DOM implementations which use any sort of proxy architecture (because more than one object can refer to the same node).

참고: This is based on a proposed DOM Level 3 API which is still in the 《working draft》 stage, but this particular interface appears uncontroversial. Changes from the W3C will not necessarily affect this method in the Python DOM interface (though any new W3C API for this would also be supported).

`Node.appendChild(newChild)`

Add a new child node to this node at the end of the list of children, returning *newChild*. If the node was already in the tree, it is removed first.

`Node.insertBefore(newChild, refChild)`

Insert a new child node before an existing child. It must be the case that *refChild* is a child of this node; if not, `ValueError` is raised. *newChild* is returned. If *refChild* is `None`, it inserts *newChild* at the end of the children's list.

`Node.removeChild(oldChild)`

Remove a child node. *oldChild* must be a child of this node; if not, `ValueError` is raised. *oldChild* is returned on success. If *oldChild* will not be used further, its `unlink()` method should be called.

`Node.replaceChild(newChild, oldChild)`

Replace an existing node with a new node. It must be the case that *oldChild* is a child of this node; if not, `ValueError` is raised.

`Node.normalize()`

Join adjacent text nodes so that all stretches of text are stored as single `Text` instances. This simplifies processing text from a DOM tree for many applications.

버전 2.1에 추가.

`Node.cloneNode(deep)`

Clone this node. Setting *deep* means to clone all child nodes as well. This returns the clone.

NodeList Objects

A `NodeList` represents a sequence of nodes. These objects are used in two ways in the DOM Core recommendation: an `Element` object provides one as its list of child nodes, and the `getElementsByTagName()` and `getElementsByTagNameNS()` methods of `Node` return objects with this interface to represent query results.

The DOM Level 2 recommendation defines one method and one attribute for these objects:

`NodeList.item(i)`

Return the *i*'th item from the sequence, if there is one, or `None`. The index *i* is not allowed to be less than zero or greater than or equal to the length of the sequence.

`NodeList.length`

The number of nodes in the sequence.

In addition, the Python DOM interface requires that some additional support is provided to allow `NodeList` objects to be used as Python sequences. All `NodeList` implementations must include support for `__len__()` and `__getitem__()`; this allows iteration over the `NodeList` in `for` statements and proper support for the `len()` built-in function.

If a DOM implementation supports modification of the document, the `NodeList` implementation must also support the `__setitem__()` and `__delitem__()` methods.

DocumentType Objects

Information about the notations and entities declared by a document (including the external subset if the parser uses it and can provide the information) is available from a `DocumentType` object. The `DocumentType` for a document is available from the `Document` object's `doctype` attribute; if there is no `DOCTYPE` declaration for the document, the document's `doctype` attribute will be set to `None` instead of an instance of this interface.

`DocumentType` is a specialization of `Node`, and adds the following attributes:

`DocumentType.publicId`

The public identifier for the external subset of the document type definition. This will be a string or `None`.

`DocumentType.systemId`

The system identifier for the external subset of the document type definition. This will be a URI as a string, or `None`.

`DocumentType.internalSubset`

A string giving the complete internal subset from the document. This does not include the brackets which enclose the subset. If the document has no internal subset, this should be `None`.

`DocumentType.name`

The name of the root element as given in the `DOCTYPE` declaration, if present.

`DocumentType.entities`

This is a `NamedNodeMap` giving the definitions of external entities. For entity names defined more than once, only the first definition is provided (others are ignored as required by the XML recommendation). This may be `None` if the information is not provided by the parser, or if no entities are defined.

`DocumentType.notations`

This is a `NamedNodeMap` giving the definitions of notations. For notation names defined more than once, only the first definition is provided (others are ignored as required by the XML recommendation). This may be `None` if the information is not provided by the parser, or if no notations are defined.

Document Objects

A `Document` represents an entire XML document, including its constituent elements, attributes, processing instructions, comments etc. Remember that it inherits properties from `Node`.

`Document.documentElement`

The one and only root element of the document.

`Document.createElement(tagName)`

Create and return a new element node. The element is not inserted into the document when it is created. You need to explicitly insert it with one of the other methods such as `insertBefore()` or `appendChild()`.

`Document.createElementNS(namespaceURI, tagName)`

Create and return a new element with a namespace. The `tagName` may have a prefix. The element is not inserted into the document when it is created. You need to explicitly insert it with one of the other methods such as `insertBefore()` or `appendChild()`.

`Document.createTextNode(data)`

Create and return a text node containing the data passed as a parameter. As with the other creation methods, this one does not insert the node into the tree.

`Document.createComment (data)`

Create and return a comment node containing the data passed as a parameter. As with the other creation methods, this one does not insert the node into the tree.

`Document.createProcessingInstruction (target, data)`

Create and return a processing instruction node containing the *target* and *data* passed as parameters. As with the other creation methods, this one does not insert the node into the tree.

`Document.createAttribute (name)`

Create and return an attribute node. This method does not associate the attribute node with any particular element. You must use `setAttributeNode()` on the appropriate `Element` object to use the newly created attribute instance.

`Document.createAttributeNS (namespaceURI, qualifiedName)`

Create and return an attribute node with a namespace. The *tagName* may have a prefix. This method does not associate the attribute node with any particular element. You must use `setAttributeNode()` on the appropriate `Element` object to use the newly created attribute instance.

`Document.getElementsByTagName (tagName)`

Search for all descendants (direct children, children's children, etc.) with a particular element type name.

`Document.getElementsByTagNameNS (namespaceURI, localName)`

Search for all descendants (direct children, children's children, etc.) with a particular namespace URI and localname. The localname is the part of the namespace after the prefix.

Element Objects

`Element` is a subclass of `Node`, so inherits all the attributes of that class.

`Element.tagName`

The element type name. In a namespace-using document it may have colons in it. The value is a string.

`Element.getElementsByTagName (tagName)`

Same as equivalent method in the `Document` class.

`Element.getElementsByTagNameNS (namespaceURI, localName)`

Same as equivalent method in the `Document` class.

`Element.hasAttribute (name)`

Returns true if the element has an attribute named by *name*.

`Element.hasAttributeNS (namespaceURI, localName)`

Returns true if the element has an attribute named by *namespaceURI* and *localName*.

`Element.getAttribute (name)`

Return the value of the attribute named by *name* as a string. If no such attribute exists, an empty string is returned, as if the attribute had no value.

`Element.getAttributeNode (attrname)`

Return the `Attr` node for the attribute named by *attrname*.

`Element.getAttributeNS (namespaceURI, localName)`

Return the value of the attribute named by *namespaceURI* and *localName* as a string. If no such attribute exists, an empty string is returned, as if the attribute had no value.

`Element.getAttributeNodeNS (namespaceURI, localName)`

Return an attribute value as a node, given a *namespaceURI* and *localName*.

`Element.removeAttribute (name)`

Remove an attribute by name. If there is no matching attribute, a `NotFoundErr` is raised.

`Element.removeAttributeNode (oldAttr)`

Remove and return *oldAttr* from the attribute list, if present. If *oldAttr* is not present, *NotFoundErr* is raised.

`Element.removeAttributeNS (namespaceURI, localName)`

Remove an attribute by name. Note that it uses a *localName*, not a *qname*. No exception is raised if there is no matching attribute.

`Element.setAttribute (name, value)`

Set an attribute value from a string.

`Element.setAttributeNode (newAttr)`

Add a new attribute node to the element, replacing an existing attribute if necessary if the *name* attribute matches. If a replacement occurs, the old attribute node will be returned. If *newAttr* is already in use, *InuseAttributeErr* will be raised.

`Element.setAttributeNodeNS (newAttr)`

Add a new attribute node to the element, replacing an existing attribute if necessary if the *namespaceURI* and *localName* attributes match. If a replacement occurs, the old attribute node will be returned. If *newAttr* is already in use, *InuseAttributeErr* will be raised.

`Element.setAttributeNS (namespaceURI, qname, value)`

Set an attribute value from a string, given a *namespaceURI* and a *qname*. Note that a *qname* is the whole attribute name. This is different than above.

Attr Objects

Attr inherits from *Node*, so inherits all its attributes.

`Attr.name`

The attribute name. In a namespace-using document it may include a colon.

`Attr.localName`

The part of the name following the colon if there is one, else the entire name. This is a read-only attribute.

`Attr.prefix`

The part of the name preceding the colon if there is one, else the empty string.

`Attr.value`

The text value of the attribute. This is a synonym for the *nodeValue* attribute.

NamedNodeMap Objects

NamedNodeMap does *not* inherit from *Node*.

`NamedNodeMap.length`

The length of the attribute list.

`NamedNodeMap.item (index)`

Return an attribute with a particular index. The order you get the attributes in is arbitrary but will be consistent for the life of a DOM. Each item is an attribute node. Get its value with the *value* attribute.

There are also experimental methods that give this class more mapping behavior. You can use them or you can use the standardized *getAttribute*()* family of methods on the *Element* objects.

Comment Objects

`Comment` represents a comment in the XML document. It is a subclass of `Node`, but cannot have child nodes.

`Comment.data`

The content of the comment as a string. The attribute contains all characters between the leading `<!--` and trailing `-->`, but does not include them.

Text and CDATASection Objects

The `Text` interface represents text in the XML document. If the parser and DOM implementation support the DOM's XML extension, portions of the text enclosed in CDATA marked sections are stored in `CDATASection` objects. These two interfaces are identical, but provide different values for the `nodeType` attribute.

These interfaces extend the `Node` interface. They cannot have child nodes.

`Text.data`

The content of the text node as a string.

참고: The use of a `CDATASection` node does not indicate that the node represents a complete CDATA marked section, only that the content of the node was part of a CDATA section. A single CDATA section may be represented by more than one node in the document tree. There is no way to determine whether two adjacent `CDATASection` nodes represent different CDATA marked sections.

ProcessingInstruction Objects

Represents a processing instruction in the XML document; this inherits from the `Node` interface and cannot have child nodes.

`ProcessingInstruction.target`

The content of the processing instruction up to the first whitespace character. This is a read-only attribute.

`ProcessingInstruction.data`

The content of the processing instruction following the first whitespace character.

Exceptions

버전 2.1에 추가.

The DOM Level 2 recommendation defines a single exception, *DOMException*, and a number of constants that allow applications to determine what sort of error occurred. *DOMException* instances carry a *code* attribute that provides the appropriate value for the specific exception.

The Python DOM interface provides the constants, but also expands the set of exceptions so that a specific exception exists for each of the exception codes defined by the DOM. The implementations must raise the appropriate specific exception, each of which carries the appropriate value for the *code* attribute.

exception `xml.dom.DOMException`

Base exception class used for all specific DOM exceptions. This exception class cannot be directly instantiated.

exception `xml.dom.DomstringSizeErr`

Raised when a specified range of text does not fit into a string. This is not known to be used in the Python DOM implementations, but may be received from DOM implementations not written in Python.

exception `xml.dom.HierarchyRequestErr`

Raised when an attempt is made to insert a node where the node type is not allowed.

exception `xml.dom.IndexSizeErr`

Raised when an index or size parameter to a method is negative or exceeds the allowed values.

exception `xml.dom.InuseAttributeErr`

Raised when an attempt is made to insert an `Attr` node that is already present elsewhere in the document.

exception `xml.dom.InvalidAccessErr`

Raised if a parameter or an operation is not supported on the underlying object.

exception `xml.dom.InvalidCharacterErr`

This exception is raised when a string parameter contains a character that is not permitted in the context it's being used in by the XML 1.0 recommendation. For example, attempting to create an `Element` node with a space in the element type name will cause this error to be raised.

exception `xml.dom.InvalidModificationErr`

Raised when an attempt is made to modify the type of a node.

exception `xml.dom.InvalidStateErr`

Raised when an attempt is made to use an object that is not defined or is no longer usable.

exception `xml.dom.NamespaceErr`

If an attempt is made to change any object in a way that is not permitted with regard to the [Namespaces in XML](#) recommendation, this exception is raised.

exception `xml.dom.NotFoundErr`

Exception when a node does not exist in the referenced context. For example, `NamedNodeMap.removeNamedItem()` will raise this if the node passed in does not exist in the map.

exception `xml.dom.NotSupportedErr`

Raised when the implementation does not support the requested type of object or operation.

exception `xml.dom.NoDataAllowedErr`

This is raised if data is specified for a node which does not support data.

exception `xml.dom.NoModificationAllowedErr`

Raised on attempts to modify an object where modifications are not allowed (such as for read-only nodes).

exception `xml.dom.SyntaxErr`

Raised when an invalid or illegal string is specified.

exception `xml.dom.WrongDocumentErr`

Raised when a node is inserted in a different document than it currently belongs to, and the implementation does not support migrating the node from one document to the other.

The exception codes defined in the DOM recommendation map to the exceptions described above according to this table:

Constant	Exception
DOMSTRING_SIZE_ERR	<i>DomstringSizeErr</i>
HIERARCHY_REQUEST_ERR	<i>HierarchyRequestErr</i>
INDEX_SIZE_ERR	<i>IndexSizeErr</i>
INUSE_ATTRIBUTE_ERR	<i>InuseAttributeErr</i>
INVALID_ACCESS_ERR	<i>InvalidAccessErr</i>
INVALID_CHARACTER_ERR	<i>InvalidCharacterErr</i>
INVALID_MODIFICATION_ERR	<i>InvalidModificationErr</i>
INVALID_STATE_ERR	<i>InvalidStateErr</i>
NAMESPACE_ERR	<i>NamespaceErr</i>
NOT_FOUND_ERR	<i>NotFoundErr</i>
NOT_SUPPORTED_ERR	<i>NotSupportedErr</i>
NO_DATA_ALLOWED_ERR	<i>NoDataAllowedErr</i>
NO_MODIFICATION_ALLOWED_ERR	<i>NoModificationAllowedErr</i>
SYNTAX_ERR	<i>SyntaxErr</i>
WRONG_DOCUMENT_ERR	<i>WrongDocumentErr</i>

19.8.3 Conformance

This section describes the conformance requirements and relationships between the Python DOM API, the W3C DOM recommendations, and the OMG IDL mapping for Python.

Type Mapping

The primitive IDL types used in the DOM specification are mapped to Python types according to the following table.

IDL Type	Python Type
boolean	IntegerType (with a value of 0 or 1)
int	IntegerType
long int	IntegerType
unsigned int	IntegerType

Additionally, the `DOMString` defined in the recommendation is mapped to a Python string or Unicode string. Applications should be able to handle Unicode whenever a string is returned from the DOM.

The IDL `null` value is mapped to `None`, which may be accepted or provided by the implementation whenever `null` is allowed by the API.

Accessor Methods

The mapping from OMG IDL to Python defines accessor functions for IDL `attribute` declarations in much the way the Java mapping does. Mapping the IDL declarations

```
readonly attribute string someValue;  
    attribute string anotherValue;
```

yields three accessor functions: a `«get»` method for `someValue` (`_get_someValue()`), and `«get»` and `«set»` methods for `anotherValue` (`_get_anotherValue()` and `_set_anotherValue()`). The mapping, in particular, does not require that the IDL attributes are accessible as normal Python attributes: `object.someValue` is *not* required to work, and may raise an *AttributeError*.

The Python DOM API, however, *does* require that normal attribute access work. This means that the typical surrogates generated by Python IDL compilers are not likely to work, and wrapper objects may be needed on the client if the DOM objects are accessed via CORBA. While this does require some additional consideration for CORBA DOM clients, the implementers with experience using DOM over CORBA from Python do not consider this a problem. Attributes that are declared `readonly` may not restrict write access in all DOM implementations.

In the Python DOM API, accessor functions are not required. If provided, they should take the form defined by the Python IDL mapping, but these methods are considered unnecessary since the attributes are accessible directly from Python. `«Set»` accessors should never be provided for `readonly` attributes.

The IDL definitions do not fully embody the requirements of the W3C DOM API, such as the notion of certain objects, such as the return value of `getElementsByTagName()`, being `«live»`. The Python DOM API does not require implementations to enforce such requirements.

19.9 `xml.dom.minidom` — Minimal DOM implementation

버전 2.0에 추가.

Source code: `Lib/xml/dom/minidom.py`

`xml.dom.minidom` is a minimal implementation of the Document Object Model interface, with an API similar to that in other languages. It is intended to be simpler than the full DOM and also significantly smaller. Users who are not already proficient with the DOM should consider using the `xml.etree.ElementTree` module for their XML processing instead.

경고: The `xml.dom.minidom` module is not secure against maliciously constructed data. If you need to parse untrusted or unauthenticated data see *XML vulnerabilities*.

DOM applications typically start by parsing some XML into a DOM. With `xml.dom.minidom`, this is done through the parse functions:

```
from xml.dom.minidom import parse, parseString

dom1 = parse('c:\\temp\\mydata.xml') # parse an XML file by name

datasource = open('c:\\temp\\mydata.xml')
dom2 = parse(datasource) # parse an open file

dom3 = parseString('<myxml>Some data<empty/> some more data</myxml>')
```

The `parse()` function can take either a filename or an open file object.

`xml.dom.minidom.parse(filename_or_file[, parser[, bufsize]])`

Return a Document from the given input. `filename_or_file` may be either a file name, or a file-like object. `parser`, if given, must be a SAX2 parser object. This function will change the document handler of the parser and activate namespace support; other parser configuration (like setting an entity resolver) must have been done in advance.

If you have XML in a string, you can use the `parseString()` function instead:

`xml.dom.minidom.parseString(string[, parser])`

Return a Document that represents the `string`. This method creates a `StringIO` object for the string and passes that on to `parse()`.

Both functions return a `Document` object representing the content of the document.

What the `parse()` and `parseString()` functions do is connect an XML parser with a «DOM builder» that can accept parse events from any SAX parser and convert them into a DOM tree. The name of the functions are perhaps misleading, but are easy to grasp when learning the interfaces. The parsing of the document will be completed before these functions return; it's simply that these functions do not provide a parser implementation themselves.

You can also create a `Document` by calling a method on a «DOM Implementation» object. You can get this object either by calling the `getDOMImplementation()` function in the `xml.dom` package or the `xml.dom.minidom` module. Using the implementation from the `xml.dom.minidom` module will always return a `Document` instance from the minidom implementation, while the version from `xml.dom` may provide an alternate implementation (this is likely if you have the `PyXML` package installed). Once you have a `Document`, you can add child nodes to it to populate the DOM:

```
from xml.dom.minidom import getDOMImplementation

impl = getDOMImplementation()

newdoc = impl.createDocument(None, "some_tag", None)
top_element = newdoc.documentElement
text = newdoc.createTextNode('Some textual content.')
top_element.appendChild(text)
```

Once you have a DOM document object, you can access the parts of your XML document through its properties and methods. These properties are defined in the DOM specification. The main property of the document object is the `documentElement` property. It gives you the main element in the XML document: the one that holds all others. Here is an example program:

```
dom3 = parseString("<myxml>Some data</myxml>")
assert dom3.documentElement.tagName == "myxml"
```

When you are finished with a DOM tree, you may optionally call the `unlink()` method to encourage early cleanup of the now-unneeded objects. `unlink()` is an `xml.dom.minidom`-specific extension to the DOM API that renders the node and its descendants are essentially useless. Otherwise, Python's garbage collector will eventually take care of the objects in the tree.

더 보기:

Document Object Model (DOM) Level 1 Specification The W3C recommendation for the DOM supported by `xml.dom.minidom`.

19.9.1 DOM Objects

The definition of the DOM API for Python is given as part of the `xml.dom` module documentation. This section lists the differences between the API and `xml.dom.minidom`.

`Node.unlink()`

Break internal references within the DOM so that it will be garbage collected on versions of Python without cyclic GC. Even when cyclic GC is available, using this can make large amounts of memory available sooner, so calling this on DOM objects as soon as they are no longer needed is good practice. This only needs to be called on the `Document` object, but may be called on child nodes to discard children of that node.

`Node.writexml(writer, indent="", addindent="", newl="")`

Write XML to the writer object. The writer should have a `write()` method which matches that of the file object interface. The `indent` parameter is the indentation of the current node. The `addindent` parameter is the incremental indentation to use for subnodes of the current one. The `newl` parameter specifies the string to use to terminate newlines.

For the `Document` node, an additional keyword argument *encoding* can be used to specify the encoding field of the XML header.

버전 2.1에서 변경: The optional keyword parameters *indent*, *addindent*, and *newl* were added to support pretty output.

버전 2.3에서 변경: For the `Document` node, an additional keyword argument *encoding* can be used to specify the encoding field of the XML header.

Node **`.toxml`** (*[encoding]*)

Return the XML that the DOM represents as a string.

With no argument, the XML header does not specify an encoding, and the result is Unicode string if the default encoding cannot represent all characters in the document. Encoding this string in an encoding other than UTF-8 is likely incorrect, since UTF-8 is the default encoding of XML.

With an explicit *encoding*¹ argument, the result is a byte string in the specified encoding. It is recommended that this argument is always specified. To avoid `UnicodeError` exceptions in case of unrepresentable text data, the encoding argument should be specified as `«utf-8»`.

버전 2.3에서 변경: the *encoding* argument was introduced; see `writexml()`.

Node **`.toprettyxml`** (*indent="t", newl="n", encoding=None*)

Return a pretty-printed version of the document. *indent* specifies the indentation string and defaults to a tabulator; *newl* specifies the string emitted at the end of each line and defaults to `\n`.

버전 2.1에 추가.

버전 2.3에서 변경: the *encoding* argument was introduced; see `writexml()`.

The following standard DOM methods have special considerations with `xml.dom.minidom`:

Node **`.cloneNode`** (*deep*)

Although this method was present in the version of `xml.dom.minidom` packaged with Python 2.0, it was seriously broken. This has been corrected for subsequent releases.

19.9.2 DOM Example

This example program is a fairly realistic example of a simple program. In this particular case, we do not take much advantage of the flexibility of the DOM.

```
import xml.dom.minidom

document = """\
<slideshow>
<title>Demo slideshow</title>
<slide><title>Slide title</title>
<point>This is a demo</point>
<point>Of a program for processing slides</point>
</slide>

<slide><title>Another demo slide</title>
<point>It is important</point>
<point>To have more than</point>
<point>one slide</point>
</slide>
```

(다음 페이지에 계속)

¹ The encoding string included in XML output should conform to the appropriate standards. For example, `«UTF-8»` is valid, but `«UTF8»` is not. See <https://www.w3.org/TR/2006/REC-xml11-20060816/#NT-EncodingDecl> and <https://www.iana.org/assignments/character-sets/character-sets.xhtml>.

(이전 페이지에서 계속)

```

</slideshow>
"""

dom = xml.dom.minidom.parseString(document)

def getText(nodelist):
    rc = []
    for node in nodelist:
        if node.nodeType == node.TEXT_NODE:
            rc.append(node.data)
    return ''.join(rc)

def handleSlideshow(slideshow):
    print "<html>"
    handleSlideshowTitle(slideshow.getElementsByTagName("title")[0])
    slides = slideshow.getElementsByTagName("slide")
    handleToc(slides)
    handleSlides(slides)
    print "</html>"

def handleSlides(slides):
    for slide in slides:
        handleSlide(slide)

def handleSlide(slide):
    handleSlideTitle(slide.getElementsByTagName("title")[0])
    handlePoints(slide.getElementsByTagName("point"))

def handleSlideshowTitle(title):
    print "<title>%s</title>" % getText(title.childNodes)

def handleSlideTitle(title):
    print "<h2>%s</h2>" % getText(title.childNodes)

def handlePoints(points):
    print "<ul>"
    for point in points:
        handlePoint(point)
    print "</ul>"

def handlePoint(point):
    print "<li>%s</li>" % getText(point.childNodes)

def handleToc(slides):
    for slide in slides:
        title = slide.getElementsByTagName("title")[0]
        print "<p>%s</p>" % getText(title.childNodes)

handleSlideshow(dom)

```

19.9.3 minidom and the DOM standard

The `xml.dom.minidom` module is essentially a DOM 1.0-compatible DOM with some DOM 2 features (primarily namespace features).

Usage of the DOM interface in Python is straight-forward. The following mapping rules apply:

- Interfaces are accessed through instance objects. Applications should not instantiate the classes themselves; they should use the creator functions available on the `Document` object. Derived interfaces support all operations (and attributes) from the base interfaces, plus any new operations.
- Operations are used as methods. Since the DOM uses only `in` parameters, the arguments are passed in normal order (from left to right). There are no optional arguments. `void` operations return `None`.
- IDL attributes map to instance attributes. For compatibility with the OMG IDL language mapping for Python, an attribute `foo` can also be accessed through accessor methods `_get_foo()` and `_set_foo()`. `readonly` attributes must not be changed; this is not enforced at runtime.
- The types `short` `int`, `unsigned int`, `unsigned long` `long`, and `boolean` all map to Python integer objects.
- The type `DOMString` maps to Python strings. `xml.dom.minidom` supports either byte or Unicode strings, but will normally produce Unicode strings. Values of type `DOMString` may also be `None` where allowed to have the IDL `null` value by the DOM specification from the W3C.
- `const` declarations map to variables in their respective scope (e.g. `xml.dom.minidom.Node.PROCESSING_INSTRUCTION_NODE`); they must not be changed.
- `DOMException` is currently not supported in `xml.dom.minidom`. Instead, `xml.dom.minidom` uses standard Python exceptions such as `TypeError` and `AttributeError`.
- `NodeList` objects are implemented using Python's built-in list type. Starting with Python 2.2, these objects provide the interface defined in the DOM specification, but with earlier versions of Python they do not support the official API. They are, however, much more «Pythonic» than the interface defined in the W3C recommendations.

The following interfaces have no implementation in `xml.dom.minidom`:

- `DOMTimeStamp`
- `DocumentType` (added in Python 2.1)
- `DOMImplementation` (added in Python 2.1)
- `CharacterData`
- `CDATASection`
- `Notation`
- `Entity`
- `EntityReference`
- `DocumentFragment`

Most of these reflect information in the XML document that is not of general utility to most DOM users.

19.10 `xml.dom.pulldom` — Support for building partial DOM trees

버전 2.0에 추가.

Source code: `Lib/xml/dom/pulldom.py`

`xml.dom.pulldom` allows building only selected portions of a Document Object Model representation of a document from SAX events.

경고: The `xml.dom.pulldom` module is not secure against maliciously constructed data. If you need to parse untrusted or unauthenticated data see [XML vulnerabilities](#).

```
class xml.dom.pulldom.PullDOM ([documentFactory])
    xml.sax.handler.ContentHandler implementation that ...

class xml.dom.pulldom.DOMEventStream (stream, parser, bufsize)
    ...

class xml.dom.pulldom.SAX2DOM ([documentFactory])
    xml.sax.handler.ContentHandler implementation that ...

xml.dom.pulldom.parse (stream_or_string[, parser[, bufsize]])
    ...

xml.dom.pulldom.parseString (string[, parser])
    ...

xml.dom.pulldom.default_bufsize
    Default value for the bufsize parameter to parse().
```

버전 2.1에서 변경: The value of this variable can be changed before calling `parse()` and the new value will take effect.

19.10.1 DOMEventStream Objects

```
DOMEventStream.getEvent ()
    ...

DOMEventStream.expandNode (node)
    ...

DOMEventStream.reset ()
    ...
```

19.11 `xml.sax` — Support for SAX2 parsers

버전 2.0에 추가.

The `xml.sax` package provides a number of modules which implement the Simple API for XML (SAX) interface for Python. The package itself provides the SAX exceptions and the convenience functions which will be most used by users of the SAX API.

경고: The `xml.sax` module is not secure against maliciously constructed data. If you need to parse untrusted or unauthenticated data see [XML vulnerabilities](#).

The convenience functions are:

`xml.sax.make_parser([parser_list])`

Create and return a SAX `XMLReader` object. The first parser found will be used. If `parser_list` is provided, it must be a list of strings which name modules that have a function named `create_parser()`. Modules listed in `parser_list` will be used before modules in the default list of parsers.

`xml.sax.parse(filename_or_stream, handler[, error_handler])`

Create a SAX parser and use it to parse a document. The document, passed in as `filename_or_stream`, can be a filename or a file object. The `handler` parameter needs to be a SAX `ContentHandler` instance. If `error_handler` is given, it must be a SAX `ErrorHandler` instance; if omitted, `SAXParseException` will be raised on all errors. There is no return value; all work must be done by the `handler` passed in.

`xml.sax.parseString(string, handler[, error_handler])`

Similar to `parse()`, but parses from a buffer `string` received as a parameter.

A typical SAX application uses three kinds of objects: readers, handlers and input sources. «Reader» in this context is another term for parser, i.e. some piece of code that reads the bytes or characters from the input source, and produces a sequence of events. The events then get distributed to the handler objects, i.e. the reader invokes a method on the handler. A SAX application must therefore obtain a reader object, create or open the input sources, create the handlers, and connect these objects all together. As the final step of preparation, the reader is called to parse the input. During parsing, methods on the handler objects are called based on structural and syntactic events from the input data.

For these objects, only the interfaces are relevant; they are normally not instantiated by the application itself. Since Python does not have an explicit notion of interface, they are formally introduced as classes, but applications may use implementations which do not inherit from the provided classes. The `InputSource`, `Locator`, `Attributes`, `AttributesNS`, and `XMLReader` interfaces are defined in the module `xml.sax.xmlreader`. The handler interfaces are defined in `xml.sax.handler`. For convenience, `InputSource` (which is often instantiated directly) and the handler classes are also available from `xml.sax`. These interfaces are described below.

In addition to these classes, `xml.sax` provides the following exception classes.

exception `xml.sax.SAXException(msg[, exception])`

Encapsulate an XML error or warning. This class can contain basic error or warning information from either the XML parser or the application: it can be subclassed to provide additional functionality or to add localization. Note that although the handlers defined in the `ErrorHandler` interface receive instances of this exception, it is not required to actually raise the exception — it is also useful as a container for information.

When instantiated, `msg` should be a human-readable description of the error. The optional `exception` parameter, if given, should be `None` or an exception that was caught by the parsing code and is being passed along as information.

This is the base class for the other SAX exception classes.

exception `xml.sax.SAXParseException(msg, exception, locator)`

Subclass of `SAXException` raised on parse errors. Instances of this class are passed to the methods of the SAX `ErrorHandler` interface to provide information about the parse error. This class supports the SAX `Locator` interface as well as the `SAXException` interface.

exception `xml.sax.SAXNotRecognizedException(msg[, exception])`

Subclass of `SAXException` raised when a SAX `XMLReader` is confronted with an unrecognized feature or property. SAX applications and extensions may use this class for similar purposes.

exception `xml.sax.SAXNotSupportedException(msg[, exception])`

Subclass of `SAXException` raised when a SAX `XMLReader` is asked to enable a feature that is not supported, or to set a property to a value that the implementation does not support. SAX applications and extensions may use this class for similar purposes.

더 보기:

SAX: The Simple API for XML This site is the focal point for the definition of the SAX API. It provides a Java implementation and online documentation. Links to implementations and historical information are also available.

Module `xml.sax.handler` Definitions of the interfaces for application-provided objects.

Module `xml.sax.saxutils` Convenience functions for use in SAX applications.

Module `xml.sax.xmlreader` Definitions of the interfaces for parser-provided objects.

19.11.1 SAXException Objects

The `SAXException` exception class supports the following methods:

`SAXException.getMessage()`
Return a human-readable message describing the error condition.

`SAXException.getException()`
Return an encapsulated exception object, or `None`.

19.12 `xml.sax.handler` — Base classes for SAX handlers

버전 2.0에 추가.

The SAX API defines four kinds of handlers: content handlers, DTD handlers, error handlers, and entity resolvers. Applications normally only need to implement those interfaces whose events they are interested in; they can implement the interfaces in a single object or in multiple objects. Handler implementations should inherit from the base classes provided in the module `xml.sax.handler`, so that all methods get default implementations.

class `xml.sax.handler.ContentHandler`

This is the main callback interface in SAX, and the one most important to applications. The order of events in this interface mirrors the order of the information in the document.

class `xml.sax.handler.DTDHandler`

Handle DTD events.

This interface specifies only those DTD events required for basic parsing (unparsed entities and attributes).

class `xml.sax.handler.EntityResolver`

Basic interface for resolving entities. If you create an object implementing this interface, then register the object with your Parser, the parser will call the method in your object to resolve all external entities.

class `xml.sax.handler.ErrorHandler`

Interface used by the parser to present error and warning messages to the application. The methods of this object control whether errors are immediately converted to exceptions or are handled in some other way.

In addition to these classes, `xml.sax.handler` provides symbolic constants for the feature and property names.

`xml.sax.handler.feature_namespaces`

value: "http://xml.org/sax/features/namespaces"

true: Perform Namespace processing.

false: Optionally do not perform Namespace processing (implies namespace-prefixes; default).

access: (parsing) read-only; (not parsing) read/write

`xml.sax.handler.feature_namespace_prefixes`

value: "http://xml.org/sax/features/namespace-prefixes"
 true: Report the original prefixed names and attributes used for Namespace declarations.
 false: Do not report attributes used for Namespace declarations, and optionally do not report original prefixed names (default).
 access: (parsing) read-only; (not parsing) read/write

`xml.sax.handler.feature_string_interning`

value: "http://xml.org/sax/features/string-interning"
 true: All element names, prefixes, attribute names, Namespace URIs, and local names are interned using the built-in intern function.
 false: Names are not necessarily interned, although they may be (default).
 access: (parsing) read-only; (not parsing) read/write

`xml.sax.handler.feature_validation`

value: "http://xml.org/sax/features/validation"
 true: Report all validation errors (implies external-general-entities and external-parameter-entities).
 false: Do not report validation errors.
 access: (parsing) read-only; (not parsing) read/write

`xml.sax.handler.feature_external_ges`

value: "http://xml.org/sax/features/external-general-entities"
 true: Include all external general (text) entities.
 false: Do not include external general entities.
 access: (parsing) read-only; (not parsing) read/write

`xml.sax.handler.feature_external_pes`

value: "http://xml.org/sax/features/external-parameter-entities"
 true: Include all external parameter entities, including the external DTD subset.
 false: Do not include any external parameter entities, even the external DTD subset.
 access: (parsing) read-only; (not parsing) read/write

`xml.sax.handler.all_features`

List of all features.

`xml.sax.handler.property_lexical_handler`

value: "http://xml.org/sax/properties/lexical-handler"
 data type: `xml.sax.sax2lib.LexicalHandler` (not supported in Python 2)
 description: An optional extension handler for lexical events like comments.
 access: read/write

`xml.sax.handler.property_declaration_handler`

value: "http://xml.org/sax/properties/declaration-handler"
 data type: `xml.sax.sax2lib.DeclHandler` (not supported in Python 2)
 description: An optional extension handler for DTD-related events other than notations and unparsed entities.
 access: read/write

`xml.sax.handler.property_dom_node`

value: "http://xml.org/sax/properties/dom-node"

data type: `org.w3c.dom.Node` (not supported in Python 2)

description: When parsing, the current DOM node being visited if this is a DOM iterator; when not parsing, the root DOM node for iteration.

access: (parsing) read-only; (not parsing) read/write

`xml.sax.handler.property_xml_string`

value: "http://xml.org/sax/properties/xml-string"

data type: `String`

description: The literal string of characters that was the source for the current event.

access: read-only

`xml.sax.handler.all_properties`

List of all known property names.

19.12.1 ContentHandler Objects

Users are expected to subclass `ContentHandler` to support their application. The following methods are called by the parser on the appropriate events in the input document:

`ContentHandler.setDocumentLocator(locator)`

Called by the parser to give the application a locator for locating the origin of document events.

SAX parsers are strongly encouraged (though not absolutely required) to supply a locator: if it does so, it must supply the locator to the application by invoking this method before invoking any of the other methods in the `DocumentHandler` interface.

The locator allows the application to determine the end position of any document-related event, even if the parser is not reporting an error. Typically, the application will use this information for reporting its own errors (such as character content that does not match an application's business rules). The information returned by the locator is probably not sufficient for use with a search engine.

Note that the locator will return correct information only during the invocation of the events in this interface. The application should not attempt to use it at any other time.

`ContentHandler.startDocument()`

Receive notification of the beginning of a document.

The SAX parser will invoke this method only once, before any other methods in this interface or in `DTDHandler` (except for `setDocumentLocator()`).

`ContentHandler.endDocument()`

Receive notification of the end of a document.

The SAX parser will invoke this method only once, and it will be the last method invoked during the parse. The parser shall not invoke this method until it has either abandoned parsing (because of an unrecoverable error) or reached the end of input.

`ContentHandler.startPrefixMapping(prefix, uri)`

Begin the scope of a prefix-URI Namespace mapping.

The information from this event is not necessary for normal Namespace processing: the SAX XML reader will automatically replace prefixes for element and attribute names when the `feature_namespaces` feature is enabled (the default).

There are cases, however, when applications need to use prefixes in character data or in attribute values, where they cannot safely be expanded automatically; the `startPrefixMapping()` and `endPrefixMapping()` events supply the information to the application to expand prefixes in those contexts itself, if necessary.

Note that `startPrefixMapping()` and `endPrefixMapping()` events are not guaranteed to be properly nested relative to each-other: all `startPrefixMapping()` events will occur before the corresponding `startElement()` event, and all `endPrefixMapping()` events will occur after the corresponding `endElement()` event, but their order is not guaranteed.

`ContentHandler.endPrefixMapping(prefix)`
End the scope of a prefix-URI mapping.

See `startPrefixMapping()` for details. This event will always occur after the corresponding `endElement()` event, but the order of `endPrefixMapping()` events is not otherwise guaranteed.

`ContentHandler.startElement(name, attrs)`
Signals the start of an element in non-namespace mode.

The `name` parameter contains the raw XML 1.0 name of the element type as a string and the `attrs` parameter holds an object of the `Attributes` interface (see [The Attributes Interface](#)) containing the attributes of the element. The object passed as `attrs` may be re-used by the parser; holding on to a reference to it is not a reliable way to keep a copy of the attributes. To keep a copy of the attributes, use the `copy()` method of the `attrs` object.

`ContentHandler.endElement(name)`
Signals the end of an element in non-namespace mode.

The `name` parameter contains the name of the element type, just as with the `startElement()` event.

`ContentHandler.startElementNS(name, qname, attrs)`
Signals the start of an element in namespace mode.

The `name` parameter contains the name of the element type as a `(uri, localname)` tuple, the `qname` parameter contains the raw XML 1.0 name used in the source document, and the `attrs` parameter holds an instance of the `AttributesNS` interface (see [The AttributesNS Interface](#)) containing the attributes of the element. If no namespace is associated with the element, the `uri` component of `name` will be `None`. The object passed as `attrs` may be re-used by the parser; holding on to a reference to it is not a reliable way to keep a copy of the attributes. To keep a copy of the attributes, use the `copy()` method of the `attrs` object.

Parsers may set the `qname` parameter to `None`, unless the `feature_namespace_prefixes` feature is activated.

`ContentHandler.endElementNS(name, qname)`
Signals the end of an element in namespace mode.

The `name` parameter contains the name of the element type, just as with the `startElementNS()` method, likewise the `qname` parameter.

`ContentHandler.characters(content)`
Receive notification of character data.

The Parser will call this method to report each chunk of character data. SAX parsers may return all contiguous character data in a single chunk, or they may split it into several chunks; however, all of the characters in any single event must come from the same external entity so that the Locator provides useful information.

`content` may be a Unicode string or a byte string; the `expat` reader module produces always Unicode strings.

참고: The earlier SAX 1 interface provided by the Python XML Special Interest Group used a more Java-like interface for this method. Since most parsers used from Python did not take advantage of the older interface, the simpler signature was chosen to replace it. To convert old code to the new interface, use `content` instead of slicing `content` with the old `offset` and `length` parameters.

`ContentHandler.ignorableWhitespace` (*whitespace*)

Receive notification of ignorable whitespace in element content.

Validating Parsers must use this method to report each chunk of ignorable whitespace (see the W3C XML 1.0 recommendation, section 2.10): non-validating parsers may also use this method if they are capable of parsing and using content models.

SAX parsers may return all contiguous whitespace in a single chunk, or they may split it into several chunks; however, all of the characters in any single event must come from the same external entity, so that the Locator provides useful information.

`ContentHandler.processingInstruction` (*target, data*)

Receive notification of a processing instruction.

The Parser will invoke this method once for each processing instruction found: note that processing instructions may occur before or after the main document element.

A SAX parser should never report an XML declaration (XML 1.0, section 2.8) or a text declaration (XML 1.0, section 4.3.1) using this method.

`ContentHandler.skippedEntity` (*name*)

Receive notification of a skipped entity.

The Parser will invoke this method once for each entity skipped. Non-validating processors may skip entities if they have not seen the declarations (because, for example, the entity was declared in an external DTD subset). All processors may skip external entities, depending on the values of the `feature_external_ges` and the `feature_external_pes` properties.

19.12.2 DTDHandler Objects

DTDHandler instances provide the following methods:

`DTDHandler.notationDecl` (*name, publicId, systemId*)

Handle a notation declaration event.

`DTDHandler.unparsedEntityDecl` (*name, publicId, systemId, ndata*)

Handle an unparsed entity declaration event.

19.12.3 EntityResolver Objects

`EntityResolver.resolveEntity` (*publicId, systemId*)

Resolve the system identifier of an entity and return either the system identifier to read from as a string, or an `InputSource` to read from. The default implementation returns *systemId*.

19.12.4 ErrorHandler Objects

Objects with this interface are used to receive error and warning information from the *XMLReader*. If you create an object that implements this interface, then register the object with your *XMLReader*, the parser will call the methods in your object to report all warnings and errors. There are three levels of errors available: warnings, (possibly) recoverable errors, and unrecoverable errors. All methods take a `SAXParseException` as the only parameter. Errors and warnings may be converted to an exception by raising the passed-in exception object.

`ErrorHandler.error` (*exception*)

Called when the parser encounters a recoverable error. If this method does not raise an exception, parsing may continue, but further document information should not be expected by the application. Allowing the parser to continue may allow additional errors to be discovered in the input document.

`ErrorHandler.fatalError` (*exception*)

Called when the parser encounters an error it cannot recover from; parsing is expected to terminate when this method returns.

`ErrorHandler.warning` (*exception*)

Called when the parser presents minor warning information to the application. Parsing is expected to continue when this method returns, and document information will continue to be passed to the application. Raising an exception in this method will cause parsing to end.

19.13 `xml.sax.saxutils` — SAX Utilities

버전 2.0에 추가.

The module `xml.sax.saxutils` contains a number of classes and functions that are commonly useful when creating SAX applications, either in direct use, or as base classes.

`xml.sax.saxutils.escape` (*data*[, *entities*])

Escape '&', '<', and '>' in a string of data.

You can escape other strings of data by passing a dictionary as the optional *entities* parameter. The keys and values must all be strings; each key will be replaced with its corresponding value. The characters '&', '<' and '>' are always escaped, even if *entities* is provided.

`xml.sax.saxutils.unescape` (*data*[, *entities*])

Unescape '&'; '<'; and '>'; in a string of data.

You can unescape other strings of data by passing a dictionary as the optional *entities* parameter. The keys and values must all be strings; each key will be replaced with its corresponding value. '&', '<'; and '>'; are always unescaped, even if *entities* is provided.

버전 2.3에 추가.

`xml.sax.saxutils.quoteattr` (*data*[, *entities*])

Similar to `escape()`, but also prepares *data* to be used as an attribute value. The return value is a quoted version of *data* with any additional required replacements. `quoteattr()` will select a quote character based on the content of *data*, attempting to avoid encoding any quote characters in the string. If both single- and double-quote characters are already in *data*, the double-quote characters will be encoded and *data* will be wrapped in double-quotes. The resulting string can be used directly as an attribute value:

```
>>> print "<element attr=%s>" % quoteattr("ab ' cd \" ef")
<element attr="ab ' cd &quot; ef">
```

This function is useful when generating attribute values for HTML or any SGML using the reference concrete syntax.

버전 2.2에 추가.

class `xml.sax.saxutils.XMLGenerator` ([*out*[, *encoding*]])

This class implements the `ContentHandler` interface by writing SAX events back into an XML document. In other words, using an `XMLGenerator` as the content handler will reproduce the original document being parsed. *out* should be a file-like object which will default to `sys.stdout`. *encoding* is the encoding of the output stream which defaults to 'iso-8859-1'.

class `xml.sax.saxutils.XMLFilterBase` (*base*)

This class is designed to sit between an `XMLReader` and the client application's event handlers. By default, it does nothing but pass requests up to the reader and events on to the handlers unmodified, but subclasses can override specific methods to modify the event stream or the configuration requests as they pass through.

`xml.sax.saxutils.prepare_input_source(source[, base])`

This function takes an input source and an optional base URL and returns a fully resolved *InputSource* object ready for reading. The input source can be given as a string, a file-like object, or an *InputSource* object; parsers will use this function to implement the polymorphic *source* argument to their `parse()` method.

19.14 `xml.sax.xmlreader` — Interface for XML parsers

버전 2.0에 추가.

SAX parsers implement the *XMLReader* interface. They are implemented in a Python module, which must provide a function `create_parser()`. This function is invoked by `xml.sax.make_parser()` with no arguments to create a new parser object.

class `xml.sax.xmlreader.XMLReader`

Base class which can be inherited by SAX parsers.

class `xml.sax.xmlreader.IncrementalParser`

In some cases, it is desirable not to parse an input source at once, but to feed chunks of the document as they get available. Note that the reader will normally not read the entire file, but read it in chunks as well; still `parse()` won't return until the entire document is processed. So these interfaces should be used if the blocking behaviour of `parse()` is not desirable.

When the parser is instantiated it is ready to begin accepting data from the feed method immediately. After parsing has been finished with a call to `close` the `reset` method must be called to make the parser ready to accept new data, either from `feed` or using the `parse` method.

Note that these methods must *not* be called during parsing, that is, after `parse` has been called and before it returns.

By default, the class also implements the `parse` method of the *XMLReader* interface using the `feed`, `close` and `reset` methods of the *IncrementalParser* interface as a convenience to SAX 2.0 driver writers.

class `xml.sax.xmlreader.Locator`

Interface for associating a SAX event with a document location. A locator object will return valid results only during calls to `DocumentHandler` methods; at any other time, the results are unpredictable. If information is not available, methods may return `None`.

class `xml.sax.xmlreader.InputSource([systemId])`

Encapsulation of the information needed by the *XMLReader* to read entities.

This class may include information about the public identifier, system identifier, byte stream (possibly with character encoding information) and/or the character stream of an entity.

Applications will create objects of this class for use in the `XMLReader.parse()` method and for returning from `EntityResolver.resolveEntity`.

An *InputSource* belongs to the application, the *XMLReader* is not allowed to modify *InputSource* objects passed to it from the application, although it may make copies and modify those.

class `xml.sax.xmlreader.AttributesImpl(attrs)`

This is an implementation of the *Attributes* interface (see section *The Attributes Interface*). This is a dictionary-like object which represents the element attributes in a `startElement()` call. In addition to the most useful dictionary operations, it supports a number of other methods as described by the interface. Objects of this class should be instantiated by readers; *attrs* must be a dictionary-like object containing a mapping from attribute names to attribute values.

class `xml.sax.xmlreader.AttributesNSImpl(attrs, qnames)`

Namespace-aware variant of *AttributesImpl*, which will be passed to `startElementNS()`. It is derived from *AttributesImpl*, but understands attribute names as two-tuples of *namespaceURI* and *localname*. In

addition, it provides a number of methods expecting qualified names as they appear in the original document. This class implements the `AttributesNS` interface (see section [The AttributesNS Interface](#)).

19.14.1 XMLReader Objects

The `XMLReader` interface supports the following methods:

`XMLReader.parse(source)`

Process an input source, producing SAX events. The *source* object can be a system identifier (a string identifying the input source – typically a file name or a URL), a file-like object, or an `InputSource` object. When `parse()` returns, the input is completely processed, and the parser object can be discarded or reset. As a limitation, the current implementation only accepts byte streams; processing of character streams is for further study.

`XMLReader.getContentHandler()`

Return the current `ContentHandler`.

`XMLReader.setContentHandler(handler)`

Set the current `ContentHandler`. If no `ContentHandler` is set, content events will be discarded.

`XMLReader.getDTDHandler()`

Return the current `DTDHandler`.

`XMLReader.setDTDHandler(handler)`

Set the current `DTDHandler`. If no `DTDHandler` is set, DTD events will be discarded.

`XMLReader.getEntityResolver()`

Return the current `EntityResolver`.

`XMLReader.setEntityResolver(handler)`

Set the current `EntityResolver`. If no `EntityResolver` is set, attempts to resolve an external entity will result in opening the system identifier for the entity, and fail if it is not available.

`XMLReader.getErrorHandler()`

Return the current `ErrorHandler`.

`XMLReader.setErrorHandler(handler)`

Set the current error handler. If no `ErrorHandler` is set, errors will be raised as exceptions, and warnings will be printed.

`XMLReader.setLocale(locale)`

Allow an application to set the locale for errors and warnings.

SAX parsers are not required to provide localization for errors and warnings; if they cannot support the requested locale, however, they must raise a SAX exception. Applications may request a locale change in the middle of a parse.

`XMLReader.getFeature(featurename)`

Return the current setting for feature *featurename*. If the feature is not recognized, `SAXNotRecognizedException` is raised. The well-known featurenames are listed in the module `xml.sax.handler`.

`XMLReader.setFeature(featurename, value)`

Set the *featurename* to *value*. If the feature is not recognized, `SAXNotRecognizedException` is raised. If the feature or its setting is not supported by the parser, `SAXNotSupportedException` is raised.

`XMLReader.getProperty(propertyname)`

Return the current setting for property *propertyname*. If the property is not recognized, a `SAXNotRecognizedException` is raised. The well-known propertynames are listed in the module `xml.sax.handler`.

`XMLReader.setProperty(propertyname, value)`

Set the *propertyname* to *value*. If the property is not recognized, `SAXNotRecognizedException` is raised. If the property or its setting is not supported by the parser, `SAXNotSupportedException` is raised.

19.14.2 IncrementalParser Objects

Instances of *IncrementalParser* offer the following additional methods:

`IncrementalParser.feed(data)`

Process a chunk of *data*.

`IncrementalParser.close()`

Assume the end of the document. That will check well-formedness conditions that can be checked only at the end, invoke handlers, and may clean up resources allocated during parsing.

`IncrementalParser.reset()`

This method is called after `close` has been called to reset the parser so that it is ready to parse new documents. The results of calling `parse` or `feed` after `close` without calling `reset` are undefined.

19.14.3 Locator Objects

Instances of *Locator* provide these methods:

`Locator.getColumnNumber()`

Return the column number where the current event begins.

`Locator.getLineNumber()`

Return the line number where the current event begins.

`Locator.getPublicId()`

Return the public identifier for the current event.

`Locator.getSystemId()`

Return the system identifier for the current event.

19.14.4 InputSource Objects

`InputSource.setPublicId(id)`

Sets the public identifier of this *InputSource*.

`InputSource.getPublicId()`

Returns the public identifier of this *InputSource*.

`InputSource.setSystemId(id)`

Sets the system identifier of this *InputSource*.

`InputSource.getSystemId()`

Returns the system identifier of this *InputSource*.

`InputSource.setEncoding(encoding)`

Sets the character encoding of this *InputSource*.

The encoding must be a string acceptable for an XML encoding declaration (see section 4.3.3 of the XML recommendation).

The encoding attribute of the *InputSource* is ignored if the *InputSource* also contains a character stream.

`InputSource.getEncoding()`

Get the character encoding of this `InputSource`.

`InputSource.setByteStream(bytefile)`

Set the byte stream (a Python file-like object which does not perform byte-to-character conversion) for this input source.

The SAX parser will ignore this if there is also a character stream specified, but it will use a byte stream in preference to opening a URI connection itself.

If the application knows the character encoding of the byte stream, it should set it with the `setEncoding` method.

`InputSource.getByteStream()`

Get the byte stream for this input source.

The `getEncoding` method will return the character encoding for this byte stream, or `None` if unknown.

`InputSource.setCharacterStream(charfile)`

Set the character stream for this input source. (The stream must be a Python 1.6 Unicode-wrapped file-like that performs conversion to Unicode strings.)

If there is a character stream specified, the SAX parser will ignore any byte stream and will not attempt to open a URI connection to the system identifier.

`InputSource.getCharacterStream()`

Get the character stream for this input source.

19.14.5 The `Attributes` Interface

`Attributes` objects implement a portion of the mapping protocol, including the methods `copy()`, `get()`, `has_key()`, `items()`, `keys()`, and `values()`. The following methods are also provided:

`Attributes.getLength()`

Return the number of attributes.

`Attributes.getNames()`

Return the names of the attributes.

`Attributes.getType(name)`

Returns the type of the attribute *name*, which is normally `'CDATA'`.

`Attributes.getValue(name)`

Return the value of attribute *name*.

19.14.6 The `AttributesNS` Interface

This interface is a subtype of the `Attributes` interface (see section [The `Attributes` Interface](#)). All methods supported by that interface are also available on `AttributesNS` objects.

The following methods are also available:

`AttributesNS.getValueByQName(name)`

Return the value for a qualified name.

`AttributesNS.getNameByQName(name)`

Return the (namespace, localname) pair for a qualified *name*.

`AttributesNS.getQNameByName(name)`

Return the qualified name for a (namespace, localname) pair.

`AttributesNS.getQNames()`

Return the qualified names of all attributes.

19.15 `xml.parsers.expat` — Fast XML parsing using Expat

경고: The `pyexpat` module is not secure against maliciously constructed data. If you need to parse untrusted or unauthenticated data see [XML vulnerabilities](#).

버전 2.0에 추가.

The `xml.parsers.expat` module is a Python interface to the Expat non-validating XML parser. The module provides a single extension type, `xmlparser`, that represents the current state of an XML parser. After an `xmlparser` object has been created, various attributes of the object can be set to handler functions. When an XML document is then fed to the parser, the handler functions are called for the character data and markup in the XML document.

This module uses the `pyexpat` module to provide access to the Expat parser. Direct use of the `pyexpat` module is deprecated.

This module provides one exception and one type object:

exception `xml.parsers.expat.ExpatError`

The exception raised when Expat reports an error. See section [ExpatError Exceptions](#) for more information on interpreting Expat errors.

exception `xml.parsers.expat.error`

Alias for [ExpatError](#).

`xml.parsers.expat.XMLParserType`

The type of the return values from the [ParserCreate\(\)](#) function.

The `xml.parsers.expat` module contains two functions:

`xml.parsers.expat.ErrorString(errno)`

Returns an explanatory string for a given error number *errno*.

`xml.parsers.expat.ParserCreate([encoding[, namespace_separator]])`

Creates and returns a new `xmlparser` object. *encoding*, if specified, must be a string naming the encoding used by the XML data. Expat doesn't support as many encodings as Python does, and its repertoire of encodings can't be extended; it supports UTF-8, UTF-16, ISO-8859-1 (Latin1), and ASCII. If *encoding*¹ is given it will override the implicit or explicit encoding of the document.

Expat can optionally do XML namespace processing for you, enabled by providing a value for *namespace_separator*. The value must be a one-character string; a [ValueError](#) will be raised if the string has an illegal length (None is considered the same as omission). When namespace processing is enabled, element type names and attribute names that belong to a namespace will be expanded. The element name passed to the element handlers `StartElementHandler` and `EndElementHandler` will be the concatenation of the namespace URI, the namespace separator character, and the local part of the name. If the namespace separator is a zero byte (`chr(0)`) then the namespace URI and the local part will be concatenated without any separator.

For example, if *namespace_separator* is set to a space character (' ') and the following document is parsed:

¹ The encoding string included in XML output should conform to the appropriate standards. For example, `<UTF-8>` is valid, but `<UTF8>` is not. See <https://www.w3.org/TR/2006/REC-xml11-20060816/#NT-EncodingDecl> and <https://www.iana.org/assignments/character-sets/character-sets.xhtml>.

```
<?xml version="1.0"?>
<root xmlns = "http://default-namespace.org/"
      xmlns:py = "http://www.python.org/ns/">
  <py:elem1 />
  <elem2 xmlns="" />
</root>
```

StartElementHandler will receive the following strings for each element:

```
http://default-namespace.org/ root
http://www.python.org/ns/ elem1
elem2
```

Due to limitations in the Expat library used by pyexpat, the `xmlparser` instance returned can only be used to parse a single XML document. Call `ParserCreate` for each document to provide unique parser instances.

더 보기:

[The Expat XML Parser](#) Home page of the Expat project.

19.15.1 XMLParser Objects

`xmlparser` objects have the following methods:

`xmlparser.Parse(data[, isfinal])`

Parses the contents of the string *data*, calling the appropriate handler functions to process the parsed data. *isfinal* must be true on the final call to this method; it allows the parsing of a single file in fragments, not the submission of multiple files. *data* can be the empty string at any time.

`xmlparser.ParseFile(file)`

Parse XML data reading from the object *file*. *file* only needs to provide the `read(nbytes)` method, returning the empty string when there's no more data.

`xmlparser.SetBase(base)`

Sets the base to be used for resolving relative URIs in system identifiers in declarations. Resolving relative identifiers is left to the application: this value will be passed through as the *base* argument to the `ExternalEntityRefHandler()`, `NotationDeclHandler()`, and `UnparsedEntityDeclHandler()` functions.

`xmlparser.GetBase()`

Returns a string containing the base set by a previous call to `SetBase()`, or None if `SetBase()` hasn't been called.

`xmlparser.GetInputContext()`

Returns the input data that generated the current event as a string. The data is in the encoding of the entity which contains the text. When called while an event handler is not active, the return value is None.

버전 2.1에 추가.

`xmlparser.ExternalEntityParserCreate(context[, encoding])`

Create a «child» parser which can be used to parse an external parsed entity referred to by content parsed by the parent parser. The *context* parameter should be the string passed to the `ExternalEntityRefHandler()` handler function, described below. The child parser is created with the `ordered_attributes`, `returns_unicode` and `specified_attributes` set to the values of this parser.

`xmlparser.SetParamEntityParsing(flag)`

Control parsing of parameter entities (including the external DTD subset). Possible *flag* values are

`XML_PARAM_ENTITY_PARSING_NEVER`, `XML_PARAM_ENTITY_PARSING_UNLESS_STANDALONE` and `XML_PARAM_ENTITY_PARSING_ALWAYS`. Return true if setting the flag was successful.

`xmlparser.UseForeignDTD([flag])`

Calling this with a true value for *flag* (the default) will cause Expat to call the *ExternalEntityRefHandler* with *None* for all arguments to allow an alternate DTD to be loaded. If the document does not contain a document type declaration, the *ExternalEntityRefHandler* will still be called, but the *StartDoctypeDeclHandler* and *EndDoctypeDeclHandler* will not be called.

Passing a false value for *flag* will cancel a previous call that passed a true value, but otherwise has no effect.

This method can only be called before the *Parse()* or *ParseFile()* methods are called; calling it after either of those have been called causes *ExpatriError* to be raised with the *code* attribute set to *errors.XML_ERROR_CANT_CHANGE_FEATURE_ONCE_PARSING*.

버전 2.3에 추가.

`xmlparser` objects have the following attributes:

`xmlparser.buffer_size`

The size of the buffer used when *buffer_text* is true. A new buffer size can be set by assigning a new integer value to this attribute. When the size is changed, the buffer will be flushed.

버전 2.3에 추가.

버전 2.6에서 변경: The buffer size can now be changed.

`xmlparser.buffer_text`

Setting this to true causes the `xmlparser` object to buffer textual content returned by Expat to avoid multiple calls to the *CharacterDataHandler()* callback whenever possible. This can improve performance substantially since Expat normally breaks character data into chunks at every line ending. This attribute is false by default, and may be changed at any time.

버전 2.3에 추가.

`xmlparser.buffer_used`

If *buffer_text* is enabled, the number of bytes stored in the buffer. These bytes represent UTF-8 encoded text. This attribute has no meaningful interpretation when *buffer_text* is false.

버전 2.3에 추가.

`xmlparser.ordered_attributes`

Setting this attribute to a non-zero integer causes the attributes to be reported as a list rather than a dictionary. The attributes are presented in the order found in the document text. For each attribute, two list entries are presented: the attribute name and the attribute value. (Older versions of this module also used this format.) By default, this attribute is false; it may be changed at any time.

버전 2.1에 추가.

`xmlparser.returns_unicode`

If this attribute is set to a non-zero integer, the handler functions will be passed Unicode strings. If *returns_unicode* is *False*, 8-bit strings containing UTF-8 encoded data will be passed to the handlers. This is *True* by default when Python is built with Unicode support.

버전 1.6에서 변경: Can be changed at any time to affect the result type.

`xmlparser.specified_attributes`

If set to a non-zero integer, the parser will report only those attributes which were specified in the document instance and not those which were derived from attribute declarations. Applications which set this need to be especially careful to use what additional information is available from the declarations as needed to comply with the standards for the behavior of XML processors. By default, this attribute is false; it may be changed at any time.

버전 2.1에 추가.

The following attributes contain values relating to the most recent error encountered by an `xmlparser` object, and will only have correct values once a call to `Parse()` or `ParseFile()` has raised an `xml.parsers.expat.ExpatError` exception.

`xmlparser.ErrorCode`

Byte index at which an error occurred.

`xmlparser.ErrorCode`

Numeric code specifying the problem. This value can be passed to the `ErrorString()` function, or compared to one of the constants defined in the `errors` object.

`xmlparser.ErrorColumnNumber`

Column number at which an error occurred.

`xmlparser.ErrorLineNumber`

Line number at which an error occurred.

The following attributes contain values relating to the current parse location in an `xmlparser` object. During a callback reporting a parse event they indicate the location of the first of the sequence of characters that generated the event. When called outside of a callback, the position indicated will be just past the last parse event (regardless of whether there was an associated callback).

버전 2.4에 추가.

`xmlparser.CurrentByteIndex`

Current byte index in the parser input.

`xmlparser.CurrentColumnNumber`

Current column number in the parser input.

`xmlparser.CurrentLineNumber`

Current line number in the parser input.

Here is the list of handlers that can be set. To set a handler on an `xmlparser` object *o*, use `o.handlername = func`. *handlername* must be taken from the following list, and *func* must be a callable object accepting the correct number of arguments. The arguments are all strings, unless otherwise stated.

`xmlparser.XmlDeclHandler` (*version, encoding, standalone*)

Called when the XML declaration is parsed. The XML declaration is the (optional) declaration of the applicable version of the XML recommendation, the encoding of the document text, and an optional «standalone» declaration. *version* and *encoding* will be strings of the type dictated by the `returns_unicode` attribute, and *standalone* will be 1 if the document is declared standalone, 0 if it is declared not to be standalone, or -1 if the standalone clause was omitted. This is only available with Expat version 1.95.0 or newer.

버전 2.1에 추가.

`xmlparser.StartDoctypeDeclHandler` (*doctypeName, systemId, publicId, has_internal_subset*)

Called when Expat begins parsing the document type declaration (`<!DOCTYPE ...`). The *doctypeName* is provided exactly as presented. The *systemId* and *publicId* parameters give the system and public identifiers if specified, or None if omitted. *has_internal_subset* will be true if the document contains an internal document declaration subset. This requires Expat version 1.2 or newer.

`xmlparser.EndDoctypeDeclHandler` ()

Called when Expat is done parsing the document type declaration. This requires Expat version 1.2 or newer.

`xmlparser.ElementDeclHandler` (*name, model*)

Called once for each element type declaration. *name* is the name of the element type, and *model* is a representation of the content model.

`xmlparser.AttestDeclHandler` (*elname, attname, type, default, required*)

Called for each declared attribute for an element type. If an attribute list declaration declares three attributes, this handler is called three times, once for each attribute. *elname* is the name of the element to which the declaration

applies and *attname* is the name of the attribute declared. The attribute type is a string passed as *type*; the possible values are 'CDATA', 'ID', 'IDREF', ... *default* gives the default value for the attribute used when the attribute is not specified by the document instance, or *None* if there is no default value (#IMPLIED values). If the attribute is required to be given in the document instance, *required* will be true. This requires Expat version 1.95.0 or newer.

`xmlparser.StartElementHandler` (*name*, *attributes*)

Called for the start of every element. *name* is a string containing the element name, and *attributes* is a dictionary mapping attribute names to their values.

`xmlparser.EndElementHandler` (*name*)

Called for the end of every element.

`xmlparser.ProcessingInstructionHandler` (*target*, *data*)

Called for every processing instruction.

`xmlparser.CharacterDataHandler` (*data*)

Called for character data. This will be called for normal character data, CDATA marked content, and ignorable whitespace. Applications which must distinguish these cases can use the [StartCdataSectionHandler](#), [EndCdataSectionHandler](#), and [ElementDeclHandler](#) callbacks to collect the required information.

`xmlparser.UnparsedEntityDeclHandler` (*entityName*, *base*, *systemId*, *publicId*, *notationName*)

Called for unparsed (NDATA) entity declarations. This is only present for version 1.2 of the Expat library; for more recent versions, use [EntityDeclHandler](#) instead. (The underlying function in the Expat library has been declared obsolete.)

`xmlparser.EntityDeclHandler` (*entityName*, *is_parameter_entity*, *value*, *base*, *systemId*, *publicId*, *notationName*)

Called for all entity declarations. For parameter and internal entities, *value* will be a string giving the declared contents of the entity; this will be *None* for external entities. The *notationName* parameter will be *None* for parsed entities, and the name of the notation for unparsed entities. *is_parameter_entity* will be true if the entity is a parameter entity or false for general entities (most applications only need to be concerned with general entities). This is only available starting with version 1.95.0 of the Expat library.

버전 2.1에 추가.

`xmlparser.NotationDeclHandler` (*notationName*, *base*, *systemId*, *publicId*)

Called for notation declarations. *notationName*, *base*, and *systemId*, and *publicId* are strings if given. If the public identifier is omitted, *publicId* will be *None*.

`xmlparser.StartNamespaceDeclHandler` (*prefix*, *uri*)

Called when an element contains a namespace declaration. Namespace declarations are processed before the [StartElementHandler](#) is called for the element on which declarations are placed.

`xmlparser.EndNamespaceDeclHandler` (*prefix*)

Called when the closing tag is reached for an element that contained a namespace declaration. This is called once for each namespace declaration on the element in the reverse of the order for which the [StartNamespaceDeclHandler](#) was called to indicate the start of each namespace declaration's scope. Calls to this handler are made after the corresponding [EndElementHandler](#) for the end of the element.

`xmlparser.CommentHandler` (*data*)

Called for comments. *data* is the text of the comment, excluding the leading '`<!--`' and trailing '`-->`'.

`xmlparser.StartCdataSectionHandler` ()

Called at the start of a CDATA section. This and [EndCdataSectionHandler](#) are needed to be able to identify the syntactical start and end for CDATA sections.

`xmlparser.EndCdataSectionHandler` ()

Called at the end of a CDATA section.

`xmlparser.DefaultHandler` (*data*)

Called for any characters in the XML document for which no applicable handler has been specified. This means

characters that are part of a construct which could be reported, but for which no handler has been supplied.

`xmlparser.DefaultHandlerExpand(data)`

This is the same as the `DefaultHandler()`, but doesn't inhibit expansion of internal entities. The entity reference will not be passed to the default handler.

`xmlparser.NotStandaloneHandler()`

Called if the XML document hasn't been declared as being a standalone document. This happens when there is an external subset or a reference to a parameter entity, but the XML declaration does not set `standalone` to `yes` in an XML declaration. If this handler returns 0, then the parser will raise an `XML_ERROR_NOT_STANDALONE` error. If this handler is not set, no exception is raised by the parser for this condition.

`xmlparser.ExternalEntityRefHandler(context, base, systemId, publicId)`

Called for references to external entities. `base` is the current base, as set by a previous call to `SetBase()`. The public and system identifiers, `systemId` and `publicId`, are strings if given; if the public identifier is not given, `publicId` will be `None`. The `context` value is opaque and should only be used as described below.

For external entities to be parsed, this handler must be implemented. It is responsible for creating the sub-parser using `ExternalEntityParserCreate(context)`, initializing it with the appropriate callbacks, and parsing the entity. This handler should return an integer; if it returns 0, the parser will raise an `XML_ERROR_EXTERNAL_ENTITY_HANDLING` error, otherwise parsing will continue.

If this handler is not provided, external entities are reported by the `DefaultHandler` callback, if provided.

19.15.2 ExpatError Exceptions

`ExpatError` exceptions have a number of interesting attributes:

`ExpatError.code`

Expat's internal error number for the specific error. This will match one of the constants defined in the `errors` object from this module.

버전 2.1에 추가.

`ExpatError.lineno`

Line number on which the error was detected. The first line is numbered 1.

버전 2.1에 추가.

`ExpatError.offset`

Character offset into the line where the error occurred. The first column is numbered 0.

버전 2.1에 추가.

19.15.3 Example

The following program defines three handlers that just print out their arguments.

```
import xml.parsers.expat

# 3 handler functions
def start_element(name, attrs):
    print 'Start element:', name, attrs
def end_element(name):
    print 'End element:', name
def char_data(data):
    print 'Character data:', repr(data)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
p = xml.parsers.expat.ParserCreate()

p.StartElementHandler = start_element
p.EndElementHandler = end_element
p.CharacterDataHandler = char_data

p.Parse("""<?xml version="1.0"?>
<parent id="top"><child1 name="paul">Text goes here</child1>
<child2 name="fred">More text</child2>
</parent>""", 1)
```

The output from this program is:

```
Start element: parent {'id': 'top'}
Start element: child1 {'name': 'paul'}
Character data: 'Text goes here'
End element: child1
Character data: '\n'
Start element: child2 {'name': 'fred'}
Character data: 'More text'
End element: child2
Character data: '\n'
End element: parent
```

19.15.4 Content Model Descriptions

Content models are described using nested tuples. Each tuple contains four values: the type, the quantifier, the name, and a tuple of children. Children are simply additional content model descriptions.

The values of the first two fields are constants defined in the `model` object of the `xml.parsers.expat` module. These constants can be collected in two groups: the model type group and the quantifier group.

The constants in the model type group are:

`xml.parsers.expat.XML_CTYPE_ANY`

The element named by the model name was declared to have a content model of ANY.

`xml.parsers.expat.XML_CTYPE_CHOICE`

The named element allows a choice from a number of options; this is used for content models such as (A | B | C).

`xml.parsers.expat.XML_CTYPE_EMPTY`

Elements which are declared to be EMPTY have this model type.

`xml.parsers.expat.XML_CTYPE_MIXED`

`xml.parsers.expat.XML_CTYPE_NAME`

`xml.parsers.expat.XML_CTYPE_SEQ`

Models which represent a series of models which follow one after the other are indicated with this model type. This is used for models such as (A, B, C).

The constants in the quantifier group are:

`xml.parsers.expat.XML_CQUANT_NONE`

No modifier is given, so it can appear exactly once, as for A.

`xml.parsers.expat.XML_CQUANT_OPT`

The model is optional: it can appear once or not at all, as for A?.

`xml.parsers.expat.XML_CQUANT_PLUS`
The model must occur one or more times (like A+).

`xml.parsers.expat.XML_CQUANT_REP`
The model must occur zero or more times, as for A*.

19.15.5 Expat error constants

The following constants are provided in the `errors` object of the `xml.parsers.expat` module. These constants are useful in interpreting some of the attributes of the `ExpatriError` exception objects raised when an error has occurred.

The `errors` object has the following attributes:

`xml.parsers.expat.XML_ERROR_ASYNC_ENTITY`

`xml.parsers.expat.XML_ERROR_ATTRIBUTE_EXTERNAL_ENTITY_REF`
An entity reference in an attribute value referred to an external entity instead of an internal entity.

`xml.parsers.expat.XML_ERROR_BAD_CHAR_REF`
A character reference referred to a character which is illegal in XML (for example, character 0, or `<�>`).

`xml.parsers.expat.XML_ERROR_BINARY_ENTITY_REF`
An entity reference referred to an entity which was declared with a notation, so cannot be parsed.

`xml.parsers.expat.XML_ERROR_DUPLICATE_ATTRIBUTE`
An attribute was used more than once in a start tag.

`xml.parsers.expat.XML_ERROR_INCORRECT_ENCODING`

`xml.parsers.expat.XML_ERROR_INVALID_TOKEN`
Raised when an input byte could not properly be assigned to a character; for example, a NUL byte (value 0) in a UTF-8 input stream.

`xml.parsers.expat.XML_ERROR_JUNK_AFTER_DOC_ELEMENT`
Something other than whitespace occurred after the document element.

`xml.parsers.expat.XML_ERROR_MISPLACED_XML_PI`
An XML declaration was found somewhere other than the start of the input data.

`xml.parsers.expat.XML_ERROR_NO_ELEMENTS`
The document contains no elements (XML requires all documents to contain exactly one top-level element)..

`xml.parsers.expat.XML_ERROR_NO_MEMORY`
Expat was not able to allocate memory internally.

`xml.parsers.expat.XML_ERROR_PARAM_ENTITY_REF`
A parameter entity reference was found where it was not allowed.

`xml.parsers.expat.XML_ERROR_PARTIAL_CHAR`
An incomplete character was found in the input.

`xml.parsers.expat.XML_ERROR_RECURSIVE_ENTITY_REF`
An entity reference contained another reference to the same entity; possibly via a different name, and possibly indirectly.

`xml.parsers.expat.XML_ERROR_SYNTAX`
Some unspecified syntax error was encountered.

`xml.parsers.expat.XML_ERROR_TAG_MISMATCH`
An end tag did not match the innermost open start tag.

`xml.parsers.expat.XML_ERROR_UNCLOSED_TOKEN`
Some token (such as a start tag) was not closed before the end of the stream or the next token was encountered.

`xml.parsers.expat.XML_ERROR_UNDEFINED_ENTITY`
A reference was made to an entity which was not defined.

`xml.parsers.expat.XML_ERROR_UNKNOWN_ENCODING`
The document encoding is not supported by Expat.

`xml.parsers.expat.XML_ERROR_UNCLOSED_CDATA_SECTION`
A CDATA marked section was not closed.

`xml.parsers.expat.XML_ERROR_EXTERNAL_ENTITY_HANDLING`

`xml.parsers.expat.XML_ERROR_NOT_STANDALONE`
The parser determined that the document was not 《standalone》 though it declared itself to be in the XML declaration, and the `NotStandaloneHandler` was set and returned 0.

`xml.parsers.expat.XML_ERROR_UNEXPECTED_STATE`

`xml.parsers.expat.XML_ERROR_ENTITY_DECLARED_IN_PE`

`xml.parsers.expat.XML_ERROR_FEATURE_REQUIRES_XML_DTD`
An operation was requested that requires DTD support to be compiled in, but Expat was configured without DTD support. This should never be reported by a standard build of the `xml.parsers.expat` module.

`xml.parsers.expat.XML_ERROR_CANT_CHANGE_FEATURE_ONCE_PARSING`
A behavioral change was requested after parsing started that can only be changed before parsing has started. This is (currently) only raised by `UseForeignDTD()`.

`xml.parsers.expat.XML_ERROR_UNBOUND_PREFIX`
An undeclared prefix was found when namespace processing was enabled.

`xml.parsers.expat.XML_ERROR_UNDECLARING_PREFIX`
The document attempted to remove the namespace declaration associated with a prefix.

`xml.parsers.expat.XML_ERROR_INCOMPLETE_PE`
A parameter entity contained incomplete markup.

`xml.parsers.expat.XML_ERROR_XML_DECL`
The document contained no document element at all.

`xml.parsers.expat.XML_ERROR_TEXT_DECL`
There was an error parsing a text declaration in an external entity.

`xml.parsers.expat.XML_ERROR_PUBLICID`
Characters were found in the public id that are not allowed.

`xml.parsers.expat.XML_ERROR_SUSPENDED`
The requested operation was made on a suspended parser, but isn't allowed. This includes attempts to provide additional input or to stop the parser.

`xml.parsers.expat.XML_ERROR_NOT_SUSPENDED`
An attempt to resume the parser was made when the parser had not been suspended.

`xml.parsers.expat.XML_ERROR_ABORTED`
This should not be reported to Python applications.

`xml.parsers.expat.XML_ERROR_FINISHED`
The requested operation was made on a parser which was finished parsing input, but isn't allowed. This includes attempts to provide additional input or to stop the parser.

`xml.parsers.expat.XML_ERROR_SUSPEND_PE`

The modules described in this chapter implement Internet protocols and support for related technology. They are all implemented in Python. Most of these modules require the presence of the system-dependent module `socket`, which is currently supported on most popular platforms. Here is an overview:

20.1 `webbrowser` — Convenient Web-browser controller

Source code: [Lib/webbrowser.py](#)

The `webbrowser` module provides a high-level interface to allow displaying Web-based documents to users. Under most circumstances, simply calling the `open()` function from this module will do the right thing.

Under Unix, graphical browsers are preferred under X11, but text-mode browsers will be used if graphical browsers are not available or an X11 display isn't available. If text-mode browsers are used, the calling process will block until the user exits the browser.

If the environment variable `BROWSER` exists, it is interpreted to override the platform default list of browsers, as an `os.pathsep`-separated list of browsers to try in order. When the value of a list part contains the string `%s`, then it is interpreted as a literal browser command line to be used with the argument URL substituted for `%s`; if the part does not contain `%s`, it is simply interpreted as the name of the browser to launch.¹

For non-Unix platforms, or when a remote browser is available on Unix, the controlling process will not wait for the user to finish with the browser, but allow the remote browser to maintain its own windows on the display. If remote browsers are not available on Unix, the controlling process will launch a new browser and wait.

The script `webbrowser` can be used as a command-line interface for the module. It accepts a URL as the argument. It accepts the following optional parameters: `-n` opens the URL in a new browser window, if possible; `-t` opens the URL in a new browser page (⟨tab⟩). The options are, naturally, mutually exclusive. Usage example:

```
python -m webbrowser -t "http://www.python.org"
```

¹ Executables named here without a full path will be searched in the directories given in the `PATH` environment variable.

The following exception is defined:

exception `webbrowser.Error`

Exception raised when a browser control error occurs.

The following functions are defined:

`webbrowser.open(url, new=0, autoraise=True)`

Display *url* using the default browser. If *new* is 0, the *url* is opened in the same browser window if possible. If *new* is 1, a new browser window is opened if possible. If *new* is 2, a new browser page (《tab》) is opened if possible. If *autoraise* is `True`, the window is raised if possible (note that under many window managers this will occur regardless of the setting of this variable).

Note that on some platforms, trying to open a filename using this function, may work and start the operating system's associated program. However, this is neither supported nor portable.

버전 2.5에서 변경: *new* can now be 2.

`webbrowser.open_new(url)`

Open *url* in a new window of the default browser, if possible, otherwise, open *url* in the only browser window.

`webbrowser.open_new_tab(url)`

Open *url* in a new page (《tab》) of the default browser, if possible, otherwise equivalent to `open_new()`.

버전 2.5에 추가.

`webbrowser.get([name])`

Return a controller object for the browser type *name*. If *name* is empty, return a controller for a default browser appropriate to the caller's environment.

`webbrowser.register(name, constructor[, instance])`

Register the browser type *name*. Once a browser type is registered, the `get()` function can return a controller for that browser type. If *instance* is not provided, or is `None`, *constructor* will be called without parameters to create an instance when needed. If *instance* is provided, *constructor* will never be called, and may be `None`.

This entry point is only useful if you plan to either set the `BROWSER` variable or call `get()` with a nonempty argument matching the name of a handler you declare.

A number of browser types are predefined. This table gives the type names that may be passed to the `get()` function and the corresponding instantiations for the controller classes, all defined in this module.

Type Name	Class Name	Notes
'mozilla'	Mozilla('mozilla')	
'firefox'	Mozilla('mozilla')	
'netscape'	Mozilla('netscape')	
'galeon'	Galeon('galeon')	
'epiphany'	Galeon('epiphany')	
'skipstone'	BackgroundBrowser('skipstone')	
'kfmclient'	Konqueror()	(1)
'konqueror'	Konqueror()	(1)
'kfm'	Konqueror()	(1)
'mosaic'	BackgroundBrowser('mosaic')	
'opera'	Opera()	
'grail'	Grail()	
'links'	GenericBrowser('links')	
'elinks'	Elinks('elinks')	
'lynx'	GenericBrowser('lynx')	
'w3m'	GenericBrowser('w3m')	
'windows-default'	WindowsDefault	(2)
'macosx'	MacOSX('default')	(3)
'safari'	MacOSX('safari')	(3)
'google-chrome'	Chrome('google-chrome')	(4)
'chrome'	Chrome('chrome')	(4)
'chromium'	Chromium('chromium')	(4)
'chromium-browser'	Chromium('chromium-browser')	(4)

Notes:

- (1) 《Konqueror》 is the file manager for the KDE desktop environment for Unix, and only makes sense to use if KDE is running. Some way of reliably detecting KDE would be nice; the `KDEDIR` variable is not sufficient. Note also that the name 《kfm》 is used even when using the **konqueror** command with KDE 2 — the implementation selects the best strategy for running Konqueror.
- (2) Only on Windows platforms.
- (3) Only on Mac OS X platform.
- (4) Support for Chrome/Chromium has been added in version 2.7.5.

Here are some simple examples:

```
url = 'http://www.python.org/'

# Open URL in a new tab, if a browser window is already open.
webbrowser.open_new_tab(url + 'doc/')

# Open URL in new window, raising the window if possible.
webbrowser.open_new(url)
```

20.1.1 Browser Controller Objects

Browser controllers provide these methods which parallel three of the module-level convenience functions:

`controller.open(url, new=0, autoraise=True)`

Display *url* using the browser handled by this controller. If *new* is 1, a new browser window is opened if possible. If *new* is 2, a new browser page (《tab》) is opened if possible.

`controller.open_new(url)`

Open *url* in a new window of the browser handled by this controller, if possible, otherwise, open *url* in the only browser window. Alias `open_new()`.

`controller.open_new_tab(url)`

Open *url* in a new page (《tab》) of the browser handled by this controller, if possible, otherwise equivalent to `open_new()`.

버전 2.5에 추가.

20.2 cgi — Common Gateway Interface support

Source code: [Lib/cgi.py](#)

Support module for Common Gateway Interface (CGI) scripts.

This module defines a number of utilities for use by CGI scripts written in Python.

20.2.1 Introduction

A CGI script is invoked by an HTTP server, usually to process user input submitted through an HTML `<FORM>` or `<ISINDEX>` element.

Most often, CGI scripts live in the server's special `cgi-bin` directory. The HTTP server places all sorts of information about the request (such as the client's hostname, the requested URL, the query string, and lots of other goodies) in the script's shell environment, executes the script, and sends the script's output back to the client.

The script's input is connected to the client too, and sometimes the form data is read this way; at other times the form data is passed via the 《query string》 part of the URL. This module is intended to take care of the different cases and provide a simpler interface to the Python script. It also provides a number of utilities that help in debugging scripts, and the latest addition is support for file uploads from a form (if your browser supports it).

The output of a CGI script should consist of two sections, separated by a blank line. The first section contains a number of headers, telling the client what kind of data is following. Python code to generate a minimal header section looks like this:

```
print "Content-Type: text/html"      # HTML is following
print                               # blank line, end of headers
```

The second section is usually HTML, which allows the client software to display nicely formatted text with header, in-line images, etc. Here's Python code that prints a simple piece of HTML:

```
print "<TITLE>CGI script output</TITLE>"
print "<H1>This is my first CGI script</H1>"
print "Hello, world!"
```


20.2.2 Using the cgi module

Begin by writing `import cgi`. Do not use `from cgi import *` — the module defines all sorts of names for its own use or for backward compatibility that you don't want in your namespace.

When you write a new script, consider adding these lines:

```
import cgitb
cgitb.enable()
```

This activates a special exception handler that will display detailed reports in the Web browser if any errors occur. If you'd rather not show the guts of your program to users of your script, you can have the reports saved to files instead, with code like this:

```
import cgitb
cgitb.enable(display=0, logdir="/path/to/logdir")
```

It's very helpful to use this feature during script development. The reports produced by `cgitb` provide information that can save you a lot of time in tracking down bugs. You can always remove the `cgitb` line later when you have tested your script and are confident that it works correctly.

To get at submitted form data, it's best to use the `FieldStorage` class. The other classes defined in this module are provided mostly for backward compatibility. Instantiate it exactly once, without arguments. This reads the form contents from standard input or the environment (depending on the value of various environment variables set according to the CGI standard). Since it may consume standard input, it should be instantiated only once.

The `FieldStorage` instance can be indexed like a Python dictionary. It allows membership testing with the `in` operator, and also supports the standard dictionary method `keys()` and the built-in function `len()`. Form fields containing empty strings are ignored and do not appear in the dictionary; to keep such values, provide a true value for the optional `keep_blank_values` keyword parameter when creating the `FieldStorage` instance.

For instance, the following code (which assumes that the `Content-Type` header and blank line have already been printed) checks that the fields `name` and `addr` are both set to a non-empty string:

```
form = cgi.FieldStorage()
if "name" not in form or "addr" not in form:
    print "<H1>Error</H1>"
    print "Please fill in the name and addr fields."
    return
print "<p>name:", form["name"].value
print "<p>addr:", form["addr"].value
...further form processing here...
```

Here the fields, accessed through `form[key]`, are themselves instances of `FieldStorage` (or `MiniFieldStorage`, depending on the form encoding). The `value` attribute of the instance yields the string value of the field. The `getvalue()` method returns this string value directly; it also accepts an optional second argument as a default to return if the requested key is not present.

If the submitted form data contains more than one field with the same name, the object retrieved by `form[key]` is not a `FieldStorage` or `MiniFieldStorage` instance but a list of such instances. Similarly, in this situation, `form.getvalue(key)` would return a list of strings. If you expect this possibility (when your HTML form contains multiple fields with the same name), use the `getlist()` method, which always returns a list of values (so that you do not need to special-case the single item case). For example, this code concatenates any number of username fields, separated by commas:

```
value = form.getlist("username")
usernames = ",".join(value)
```

If a field represents an uploaded file, accessing the value via the `value` attribute or the `getvalue()` method reads the entire file in memory as a string. This may not be what you want. You can test for an uploaded file by testing either the `filename` attribute or the `file` attribute. You can then read the data at leisure from the `file` attribute:

```
fileitem = form["userfile"]
if fileitem.file:
    # It's an uploaded file; count lines
    linecount = 0
    while 1:
        line = fileitem.file.readline()
        if not line: break
        linecount = linecount + 1
```

If an error is encountered when obtaining the contents of an uploaded file (for example, when the user interrupts the form submission by clicking on a Back or Cancel button) the `done` attribute of the object for the field will be set to the value `-1`.

The file upload draft standard entertains the possibility of uploading multiple files from one field (using a recursive *multipart/** encoding). When this occurs, the item will be a dictionary-like `FieldStorage` item. This can be determined by testing its `type` attribute, which should be *multipart/form-data* (or perhaps another MIME type matching *multipart/**). In this case, it can be iterated over recursively just like the top-level form object.

When a form is submitted in the «old» format (as the query string or as a single data part of type *application/x-www-form-urlencoded*), the items will actually be instances of the class `MiniFieldStorage`. In this case, the `list`, `file`, and `filename` attributes are always `None`.

A form submitted via POST that also has a query string will contain both `FieldStorage` and `MiniFieldStorage` items.

20.2.3 Higher Level Interface

버전 2.2에 추가.

The previous section explains how to read CGI form data using the `FieldStorage` class. This section describes a higher level interface which was added to this class to allow one to do it in a more readable and intuitive way. The interface doesn't make the techniques described in previous sections obsolete — they are still useful to process file uploads efficiently, for example.

The interface consists of two simple methods. Using the methods you can process form data in a generic way, without the need to worry whether only one or more values were posted under one name.

In the previous section, you learned to write following code anytime you expected a user to post more than one value under one name:

```
item = form.getvalue("item")
if isinstance(item, list):
    # The user is requesting more than one item.
else:
    # The user is requesting only one item.
```

This situation is common for example when a form contains a group of multiple checkboxes with the same name:

```
<input type="checkbox" name="item" value="1" />
<input type="checkbox" name="item" value="2" />
```

In most situations, however, there's only one form control with a particular name in a form and then you expect and need only one value associated with this name. So you write a script containing for example this code:

```
user = form.getvalue("user").upper()
```

The problem with the code is that you should never expect that a client will provide valid input to your scripts. For example, if a curious user appends another `user=foo` pair to the query string, then the script would crash, because in this situation the `getvalue("user")` method call returns a list instead of a string. Calling the `upper()` method on a list is not valid (since lists do not have a method of this name) and results in an `AttributeError` exception.

Therefore, the appropriate way to read form data values was to always use the code which checks whether the obtained value is a single value or a list of values. That's annoying and leads to less readable scripts.

A more convenient approach is to use the methods `getfirst()` and `getlist()` provided by this higher level interface.

`FieldStorage.getfirst(name[, default])`

This method always returns only one value associated with form field *name*. The method returns only the first value in case that more values were posted under such name. Please note that the order in which the values are received may vary from browser to browser and should not be counted on.¹ If no such form field or value exists then the method returns the value specified by the optional parameter *default*. This parameter defaults to `None` if not specified.

`FieldStorage.getlist(name)`

This method always returns a list of values associated with form field *name*. The method returns an empty list if no such form field or value exists for *name*. It returns a list consisting of one item if only one such value exists.

Using these methods you can write nice compact code:

```
import cgi
form = cgi.FieldStorage()
user = form.getfirst("user", "").upper()    # This way it's safe.
for item in form.getlist("item"):
    do_something(item)
```

20.2.4 Old classes

버전 2.6부터 폐지: These classes, present in earlier versions of the `cgi` module, are still supported for backward compatibility. New applications should use the `FieldStorage` class.

`SvFormContentDict` stores single value form content as dictionary; it assumes each field name occurs in the form only once.

`FormContentDict` stores multiple value form content as a dictionary (the form items are lists of values). Useful if your form contains multiple fields with the same name.

Other classes (`FormContent`, `InterpFormContentDict`) are present for backwards compatibility with really old applications only.

¹ Note that some recent versions of the HTML specification do state what order the field values should be supplied in, but knowing whether a request was received from a conforming browser, or even from a browser at all, is tedious and error-prone.

20.2.5 Functions

These are useful if you want more control, or if you want to employ some of the algorithms implemented in this module in other circumstances.

`cgi.parse(fp[, environ[, keep_blank_values[, strict_parsing]]])`

Parse a query in the environment or from a file (the file defaults to `sys.stdin` and environment defaults to `os.environ`). The `keep_blank_values` and `strict_parsing` parameters are passed to `urlparse.parse_qs()` unchanged.

`cgi.parse_qs(qs[, keep_blank_values[, strict_parsing[, max_num_fields]]])`

This function is deprecated in this module. Use `urlparse.parse_qs()` instead. It is maintained here only for backward compatibility.

`cgi.parse_qs1(qs[, keep_blank_values[, strict_parsing[, max_num_fields]]])`

This function is deprecated in this module. Use `urlparse.parse_qs1()` instead. It is maintained here only for backward compatibility.

`cgi.parse_multipart(fp, pdict)`

Parse input of type *multipart/form-data* (for file uploads). Arguments are *fp* for the input file and *pdict* for a dictionary containing other parameters in the *Content-Type* header.

Returns a dictionary just like `urlparse.parse_qs()` keys are the field names, each value is a list of values for that field. This is easy to use but not much good if you are expecting megabytes to be uploaded — in that case, use the `FieldStorage` class instead which is much more flexible.

Note that this does not parse nested multipart parts — use `FieldStorage` for that.

`cgi.parse_header(string)`

Parse a MIME header (such as *Content-Type*) into a main value and a dictionary of parameters.

`cgi.test()`

Robust test CGI script, usable as main program. Writes minimal HTTP headers and formats all information provided to the script in HTML form.

`cgi.print_environ()`

Format the shell environment in HTML.

`cgi.print_form(form)`

Format a form in HTML.

`cgi.print_directory()`

Format the current directory in HTML.

`cgi.print_environ_usage()`

Print a list of useful (used by CGI) environment variables in HTML.

`cgi.escape(s[, quote])`

Convert the characters '&', '<' and '>' in string *s* to HTML-safe sequences. Use this if you need to display text that might contain such characters in HTML. If the optional flag *quote* is true, the quotation mark character (") is also translated; this helps for inclusion in an HTML attribute value delimited by double quotes, as in ``. Note that single quotes are never translated.

If the value to be quoted might include single- or double-quote characters, or both, consider using the `quoteattr()` function in the `xml.sax.saxutils` module instead.

20.2.6 Caring about security

There's one important rule: if you invoke an external program (via the `os.system()` or `os.popen()` functions, or others with similar functionality), make very sure you don't pass arbitrary strings received from the client to the shell. This is a well-known security hole whereby clever hackers anywhere on the Web can exploit a gullible CGI script to invoke arbitrary shell commands. Even parts of the URL or field names cannot be trusted, since the request doesn't have to come from your form!

To be on the safe side, if you must pass a string gotten from a form to a shell command, you should make sure the string contains only alphanumeric characters, dashes, underscores, and periods.

20.2.7 Installing your CGI script on a Unix system

Read the documentation for your HTTP server and check with your local system administrator to find the directory where CGI scripts should be installed; usually this is in a directory `cgi-bin` in the server tree.

Make sure that your script is readable and executable by `«others»`; the Unix file mode should be `0755` octal (use `chmod 0755 filename`). Make sure that the first line of the script contains `#!` starting in column 1 followed by the pathname of the Python interpreter, for instance:

```
#!/usr/local/bin/python
```

Make sure the Python interpreter exists and is executable by `«others»`.

Make sure that any files your script needs to read or write are readable or writable, respectively, by `«others»` — their mode should be `0644` for readable and `0666` for writable. This is because, for security reasons, the HTTP server executes your script as user `«nobody»`, without any special privileges. It can only read (write, execute) files that everybody can read (write, execute). The current directory at execution time is also different (it is usually the server's `cgi-bin` directory) and the set of environment variables is also different from what you get when you log in. In particular, don't count on the shell's search path for executables (`PATH`) or the Python module search path (`PYTHONPATH`) to be set to anything interesting.

If you need to load modules from a directory which is not on Python's default module search path, you can change the path in your script, before importing other modules. For example:

```
import sys
sys.path.insert(0, "/usr/home/joe/lib/python")
sys.path.insert(0, "/usr/local/lib/python")
```

(This way, the directory inserted last will be searched first!)

Instructions for non-Unix systems will vary; check your HTTP server's documentation (it will usually have a section on CGI scripts).

20.2.8 Testing your CGI script

Unfortunately, a CGI script will generally not run when you try it from the command line, and a script that works perfectly from the command line may fail mysteriously when run from the server. There's one reason why you should still test your script from the command line: if it contains a syntax error, the Python interpreter won't execute it at all, and the HTTP server will most likely send a cryptic error to the client.

Assuming your script has no syntax errors, yet it does not work, you have no choice but to read the next section.

20.2.9 Debugging CGI scripts

First of all, check for trivial installation errors — reading the section above on installing your CGI script carefully can save you a lot of time. If you wonder whether you have understood the installation procedure correctly, try installing a copy of this module file (`cgi.py`) as a CGI script. When invoked as a script, the file will dump its environment and the contents of the form in HTML form. Give it the right mode etc, and send it a request. If it's installed in the standard `cgi-bin` directory, it should be possible to send it a request by entering a URL into your browser of the form:

```
http://yourhostname/cgi-bin/cgi.py?name=Joe+Blow&addr=At+Home
```

If this gives an error of type 404, the server cannot find the script — perhaps you need to install it in a different directory. If it gives another error, there's an installation problem that you should fix before trying to go any further. If you get a nicely formatted listing of the environment and form content (in this example, the fields should be listed as `<addr>` with value `<At Home>` and `<name>` with value `<Joe Blow>`), the `cgi.py` script has been installed correctly. If you follow the same procedure for your own script, you should now be able to debug it.

The next step could be to call the `cgi` module's `test()` function from your script: replace its main code with the single statement

```
cgi.test()
```

This should produce the same results as those gotten from installing the `cgi.py` file itself.

When an ordinary Python script raises an unhandled exception (for whatever reason: of a typo in a module name, a file that can't be opened, etc.), the Python interpreter prints a nice traceback and exits. While the Python interpreter will still do this when your CGI script raises an exception, most likely the traceback will end up in one of the HTTP server's log files, or be discarded altogether.

Fortunately, once you have managed to get your script to execute *some* code, you can easily send tracebacks to the Web browser using the `cgitb` module. If you haven't done so already, just add the lines:

```
import cgitb
cgitb.enable()
```

to the top of your script. Then try running it again; when a problem occurs, you should see a detailed report that will likely make apparent the cause of the crash.

If you suspect that there may be a problem in importing the `cgitb` module, you can use an even more robust approach (which only uses built-in modules):

```
import sys
sys.stderr = sys.stdout
print "Content-Type: text/plain"
print
...your code here...
```

This relies on the Python interpreter to print the traceback. The content type of the output is set to plain text, which disables all HTML processing. If your script works, the raw HTML will be displayed by your client. If it raises an exception, most likely after the first two lines have been printed, a traceback will be displayed. Because no HTML interpretation is going on, the traceback will be readable.

20.2.10 Common problems and solutions

- Most HTTP servers buffer the output from CGI scripts until the script is completed. This means that it is not possible to display a progress report on the client's display while the script is running.
- Check the installation instructions above.
- Check the HTTP server's log files. (`tail -f logfile` in a separate window may be useful!)
- Always check a script for syntax errors first, by doing something like `python script.py`.
- If your script does not have any syntax errors, try adding `import cgitb; cgitb.enable()` to the top of the script.
- When invoking external programs, make sure they can be found. Usually, this means using absolute path names — `PATH` is usually not set to a very useful value in a CGI script.
- When reading or writing external files, make sure they can be read or written by the `userid` under which your CGI script will be running: this is typically the `userid` under which the web server is running, or some explicitly specified `userid` for a web server's `suexec` feature.
- Don't try to give a CGI script a `set-uid` mode. This doesn't work on most systems, and is a security liability as well.

20.3 cgitb — Traceback manager for CGI scripts

버전 2.2에 추가.

The `cgitb` module provides a special exception handler for Python scripts. (Its name is a bit misleading. It was originally designed to display extensive traceback information in HTML for CGI scripts. It was later generalized to also display this information in plain text.) After this module is activated, if an uncaught exception occurs, a detailed, formatted report will be displayed. The report includes a traceback showing excerpts of the source code for each level, as well as the values of the arguments and local variables to currently running functions, to help you debug the problem. Optionally, you can save this information to a file instead of sending it to the browser.

To enable this feature, simply add this to the top of your CGI script:

```
import cgitb
cgitb.enable()
```

The options to the `enable()` function control whether the report is displayed in the browser and whether the report is logged to a file for later analysis.

```
cgitb.enable([display[, logdir[, context[, format]]]])
```

This function causes the `cgitb` module to take over the interpreter's default handling for exceptions by setting the value of `sys.excepthook`.

The optional argument `display` defaults to 1 and can be set to 0 to suppress sending the traceback to the browser. If the argument `logdir` is present, the traceback reports are written to files. The value of `logdir` should be a directory where these files will be placed. The optional argument `context` is the number of lines of context to display around the current line of source code in the traceback; this defaults to 5. If the optional argument `format` is "html", the output is formatted as HTML. Any other value forces plain text output. The default value is "html".

```
cgitb.handler([info])
```

This function handles an exception using the default settings (that is, show a report in the browser, but don't log to a file). This can be used when you've caught an exception and want to report it using `cgitb`. The optional `info` argument should be a 3-tuple containing an exception type, exception value, and traceback object, exactly like the tuple returned by `sys.exc_info()`. If the `info` argument is not supplied, the current exception is obtained from `sys.exc_info()`.

20.4 wsgiref — WSGI Utilities and Reference Implementation

버전 2.5에 추가.

The Web Server Gateway Interface (WSGI) is a standard interface between web server software and web applications written in Python. Having a standard interface makes it easy to use an application that supports WSGI with a number of different web servers.

Only authors of web servers and programming frameworks need to know every detail and corner case of the WSGI design. You don't need to understand every detail of WSGI just to install a WSGI application or to write a web application using an existing framework.

`wsgiref` is a reference implementation of the WSGI specification that can be used to add WSGI support to a web server or framework. It provides utilities for manipulating WSGI environment variables and response headers, base classes for implementing WSGI servers, a demo HTTP server that serves WSGI applications, and a validation tool that checks WSGI servers and applications for conformance to the WSGI specification ([PEP 333](#)).

See <https://wsgi.readthedocs.org/> for more information about WSGI, and links to tutorials and other resources.

20.4.1 wsgiref.util — WSGI environment utilities

This module provides a variety of utility functions for working with WSGI environments. A WSGI environment is a dictionary containing HTTP request variables as described in [PEP 333](#). All of the functions taking an *environ* parameter expect a WSGI-compliant dictionary to be supplied; please see [PEP 333](#) for a detailed specification.

`wsgiref.util.guess_scheme(environ)`

Return a guess for whether `wsgi.url_scheme` should be `http` or `https`, by checking for a `HTTPS` environment variable in the *environ* dictionary. The return value is a string.

This function is useful when creating a gateway that wraps CGI or a CGI-like protocol such as FastCGI. Typically, servers providing such protocols will include a `HTTPS` variable with a value of `1`, `yes`, or `on` when a request is received via SSL. So, this function returns `https` if such a value is found, and `http` otherwise.

`wsgiref.util.request_uri(environ, include_query=1)`

Return the full request URI, optionally including the query string, using the algorithm found in the `URL Reconstruction` section of [PEP 333](#). If *include_query* is false, the query string is not included in the resulting URI.

`wsgiref.util.application_uri(environ)`

Similar to `request_uri()`, except that the `PATH_INFO` and `QUERY_STRING` variables are ignored. The result is the base URI of the application object addressed by the request.

`wsgiref.util.shift_path_info(environ)`

Shift a single name from `PATH_INFO` to `SCRIPT_NAME` and return the name. The *environ* dictionary is *modified* in-place; use a copy if you need to keep the original `PATH_INFO` or `SCRIPT_NAME` intact.

If there are no remaining path segments in `PATH_INFO`, `None` is returned.

Typically, this routine is used to process each portion of a request URI path, for example to treat the path as a series of dictionary keys. This routine modifies the passed-in environment to make it suitable for invoking another WSGI application that is located at the target URI. For example, if there is a WSGI application at `/foo`, and the request URI path is `/foo/bar/baz`, and the WSGI application at `/foo` calls `shift_path_info()`, it will receive the string `bar`, and the environment will be updated to be suitable for passing to a WSGI application at `/foo/bar`. That is, `SCRIPT_NAME` will change from `/foo` to `/foo/bar`, and `PATH_INFO` will change from `/bar/baz` to `/baz`.

When `PATH_INFO` is just a `/`, this routine returns an empty string and appends a trailing slash to `SCRIPT_NAME`, even though empty path segments are normally ignored, and `SCRIPT_NAME` doesn't normally

end in a slash. This is intentional behavior, to ensure that an application can tell the difference between URIs ending in `/x` from ones ending in `/x/` when using this routine to do object traversal.

`wsgiref.util.setup_testing_defaults(environ)`

Update *environ* with trivial defaults for testing purposes.

This routine adds various parameters required for WSGI, including `HTTP_HOST`, `SERVER_NAME`, `SERVER_PORT`, `REQUEST_METHOD`, `SCRIPT_NAME`, `PATH_INFO`, and all of the [PEP 333](#)-defined `wsgi.*` variables. It only supplies default values, and does not replace any existing settings for these variables.

This routine is intended to make it easier for unit tests of WSGI servers and applications to set up dummy environments. It should NOT be used by actual WSGI servers or applications, since the data is fake!

Example usage:

```
from wsgiref.util import setup_testing_defaults
from wsgiref.simple_server import make_server

# A relatively simple WSGI application. It's going to print out the
# environment dictionary after being updated by setup_testing_defaults
def simple_app(environ, start_response):
    setup_testing_defaults(environ)

    status = '200 OK'
    headers = [('Content-type', 'text/plain')]

    start_response(status, headers)

    ret = ["%s: %s\n" % (key, value)
           for key, value in environ.iteritems()]
    return ret

httpd = make_server('', 8000, simple_app)
print "Serving on port 8000..."
httpd.serve_forever()
```

In addition to the environment functions above, the `wsgiref.util` module also provides these miscellaneous utilities:

`wsgiref.util.is_hop_by_hop(header_name)`

Return true if `<header_name>` is an HTTP/1.1 «Hop-by-Hop» header, as defined by [RFC 2616](#).

class `wsgiref.util.FileWrapper(filelike, blksize=8192)`

A wrapper to convert a file-like object to an *iterator*. The resulting objects support both `__getitem__()` and `__iter__()` iteration styles, for compatibility with Python 2.1 and Jython. As the object is iterated over, the optional *blksize* parameter will be repeatedly passed to the *filelike* object's `read()` method to obtain strings to yield. When `read()` returns an empty string, iteration is ended and is not resumable.

If *filelike* has a `close()` method, the returned object will also have a `close()` method, and it will invoke the *filelike* object's `close()` method when called.

Example usage:

```
from StringIO import StringIO
from wsgiref.util import FileWrapper

# We're using a StringIO-buffer for as the file-like object
filelike = StringIO("This is an example file-like object"*10)
wrapper = FileWrapper(filelike, blksize=5)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
for chunk in wrapper:
    print chunk
```

20.4.2 wsgiref.headers – WSGI response header tools

This module provides a single class, *Headers*, for convenient manipulation of WSGI response headers using a mapping-like interface.

class wsgiref.headers.*Headers* (*headers*)

Create a mapping-like object wrapping *headers*, which must be a list of header name/value tuples as described in [PEP 333](#). Any changes made to the new *Headers* object will directly update the *headers* list it was created with.

Headers objects support typical mapping operations including `__getitem__()`, `get()`, `__setitem__()`, `setdefault()`, `__delitem__()`, `__contains__()` and `has_key()`. For each of these methods, the key is the header name (treated case-insensitively), and the value is the first value associated with that header name. Setting a header deletes any existing values for that header, then adds a new value at the end of the wrapped header list. *Headers* existing order is generally maintained, with new headers added to the end of the wrapped list.

Unlike a dictionary, *Headers* objects do not raise an error when you try to get or delete a key that isn't in the wrapped header list. Getting a nonexistent header just returns `None`, and deleting a nonexistent header does nothing.

Headers objects also support `keys()`, `values()`, and `items()` methods. The lists returned by `keys()` and `items()` can include the same key more than once if there is a multi-valued header. The `len()` of a *Headers* object is the same as the length of its `items()`, which is the same as the length of the wrapped header list. In fact, the `items()` method just returns a copy of the wrapped header list.

Calling `str()` on a *Headers* object returns a formatted string suitable for transmission as HTTP response headers. Each header is placed on a line with its value, separated by a colon and a space. Each line is terminated by a carriage return and line feed, and the string is terminated with a blank line.

In addition to their mapping interface and formatting features, *Headers* objects also have the following methods for querying and adding multi-valued headers, and for adding headers with MIME parameters:

get_all (*name*)

Return a list of all the values for the named header.

The returned list will be sorted in the order they appeared in the original header list or were added to this instance, and may contain duplicates. Any fields deleted and re-inserted are always appended to the header list. If no fields exist with the given name, returns an empty list.

add_header (*name*, *value*, ***_params*)

Add a (possibly multi-valued) header, with optional MIME parameters specified via keyword arguments.

name is the header field to add. Keyword arguments can be used to set MIME parameters for the header field. Each parameter must be a string or `None`. Underscores in parameter names are converted to dashes, since dashes are illegal in Python identifiers, but many MIME parameter names include dashes. If the parameter value is a string, it is added to the header value parameters in the form `name="value"`. If it is `None`, only the parameter name is added. (This is used for MIME parameters without a value.) Example usage:

```
h.add_header('content-disposition', 'attachment', filename='bud.gif')
```

The above will add a header that looks like this:

```
Content-Disposition: attachment; filename="bud.gif"
```

20.4.3 wsgiref.simple_server – a simple WSGI HTTP server

This module implements a simple HTTP server (based on `BaseHTTPServer`) that serves WSGI applications. Each server instance serves a single WSGI application on a given host and port. If you want to serve multiple applications on a single host and port, you should create a WSGI application that parses `PATH_INFO` to select which application to invoke for each request. (E.g., using the `shift_path_info()` function from `wsgiref.util`.)

`wsgiref.simple_server.make_server(host, port, app, server_class=WSGIServer, handler_class=WSGIRequestHandler)`

Create a new WSGI server listening on *host* and *port*, accepting connections for *app*. The return value is an instance of the supplied *server_class*, and will process requests using the specified *handler_class*. *app* must be a WSGI application object, as defined by [PEP 333](#).

Example usage:

```
from wsgiref.simple_server import make_server, demo_app

httpd = make_server('', 8000, demo_app)
print "Serving HTTP on port 8000..."

# Respond to requests until process is killed
httpd.serve_forever()

# Alternative: serve one request, then exit
httpd.handle_request()
```

`wsgiref.simple_server.demo_app(envIRON, start_response)`

This function is a small but complete WSGI application that returns a text page containing the message «Hello world! » and a list of the key/value pairs provided in the *environ* parameter. It's useful for verifying that a WSGI server (such as `wsgiref.simple_server`) is able to run a simple WSGI application correctly.

class `wsgiref.simple_server.WSGIServer(server_address, RequestHandlerClass)`

Create a `WSGIServer` instance. *server_address* should be a (host, port) tuple, and *RequestHandlerClass* should be the subclass of `BaseHTTPServer.BaseHTTPRequestHandler` that will be used to process requests.

You do not normally need to call this constructor, as the `make_server()` function can handle all the details for you.

`WSGIServer` is a subclass of `BaseHTTPServer.HTTPServer`, so all of its methods (such as `serve_forever()` and `handle_request()`) are available. `WSGIServer` also provides these WSGI-specific methods:

set_app(application)

Sets the callable *application* as the WSGI application that will receive requests.

get_app()

Returns the currently-set application callable.

Normally, however, you do not need to use these additional methods, as `set_app()` is normally called by `make_server()`, and the `get_app()` exists mainly for the benefit of request handler instances.

class `wsgiref.simple_server.WSGIRequestHandler(request, client_address, server)`

Create an HTTP handler for the given *request* (i.e. a socket), *client_address* (a (host, port) tuple), and *server* (`WSGIServer` instance).

You do not need to create instances of this class directly; they are automatically created as needed by `WSGIServer` objects. You can, however, subclass this class and supply it as a *handler_class* to the `make_server()` function. Some possibly relevant methods for overriding in subclasses:

get_environ()

Returns a dictionary containing the WSGI environment for a request. The default implementation copies the contents of the `WSGIServer` object's `base_environ` dictionary attribute and then adds various headers derived from the HTTP request. Each call to this method should return a new dictionary containing all of the relevant CGI environment variables as specified in [PEP 333](#).

get_stderr()

Return the object that should be used as the `wsgi.errors` stream. The default implementation just returns `sys.stderr`.

handle()

Process the HTTP request. The default implementation creates a handler instance using a `wsgiref.handlers` class to implement the actual WSGI application interface.

20.4.4 `wsgiref.validate` — WSGI conformance checker

When creating new WSGI application objects, frameworks, servers, or middleware, it can be useful to validate the new code's conformance using `wsgiref.validate`. This module provides a function that creates WSGI application objects that validate communications between a WSGI server or gateway and a WSGI application object, to check both sides for protocol conformance.

Note that this utility does not guarantee complete [PEP 333](#) compliance; an absence of errors from this module does not necessarily mean that errors do not exist. However, if this module does produce an error, then it is virtually certain that either the server or application is not 100% compliant.

This module is based on the `paste.lint` module from Ian Bicking's *《Python Paste》* library.

`wsgiref.validate.validator(application)`

Wrap *application* and return a new WSGI application object. The returned application will forward all requests to the original *application*, and will check that both the *application* and the server invoking it are conforming to the WSGI specification and to RFC 2616.

Any detected nonconformance results in an `AssertionError` being raised; note, however, that how these errors are handled is server-dependent. For example, `wsgiref.simple_server` and other servers based on `wsgiref.handlers` (that don't override the error handling methods to do something else) will simply output a message that an error has occurred, and dump the traceback to `sys.stderr` or some other error stream.

This wrapper may also generate output using the `warnings` module to indicate behaviors that are questionable but which may not actually be prohibited by [PEP 333](#). Unless they are suppressed using Python command-line options or the `warnings` API, any such warnings will be written to `sys.stderr` (not `wsgi.errors`, unless they happen to be the same object).

Example usage:

```
from wsgiref.validate import validator
from wsgiref.simple_server import make_server

# Our callable object which is intentionally not compliant to the
# standard, so the validator is going to break
def simple_app(environ, start_response):
    status = '200 OK' # HTTP Status
    headers = [('Content-type', 'text/plain')] # HTTP Headers
    start_response(status, headers)

    # This is going to break because we need to return a list, and
    # the validator is going to inform us
    return "Hello World"
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
# This is the application wrapped in a validator
validator_app = validator(simple_app)

httpd = make_server(' ', 8000, validator_app)
print "Listening on port 8000...."
httpd.serve_forever()
```

20.4.5 wsgiref.handlers – server/gateway base classes

This module provides base handler classes for implementing WSGI servers and gateways. These base classes handle most of the work of communicating with a WSGI application, as long as they are given a CGI-like environment, along with input, output, and error streams.

class wsgiref.handlers.CGIHandler

CGI-based invocation via `sys.stdin`, `sys.stdout`, `sys.stderr` and `os.environ`. This is useful when you have a WSGI application and want to run it as a CGI script. Simply invoke `CGIHandler().run(app)`, where `app` is the WSGI application object you wish to invoke.

This class is a subclass of `BaseCGIHandler` that sets `wsgi.run_once` to true, `wsgi.multithread` to false, and `wsgi.multiprocess` to true, and always uses `sys` and `os` to obtain the necessary CGI streams and environment.

class wsgiref.handlers.BaseCGIHandler(*stdin, stdout, stderr, environ, multithread=True, multiprocess=False*)

Similar to `CGIHandler`, but instead of using the `sys` and `os` modules, the CGI environment and I/O streams are specified explicitly. The `multithread` and `multiprocess` values are used to set the `wsgi.multithread` and `wsgi.multiprocess` flags for any applications run by the handler instance.

This class is a subclass of `SimpleHandler` intended for use with software other than HTTP 《origin servers》. If you are writing a gateway protocol implementation (such as CGI, FastCGI, SCGI, etc.) that uses a `Status:` header to send an HTTP status, you probably want to subclass this instead of `SimpleHandler`.

class wsgiref.handlers.SimpleHandler(*stdin, stdout, stderr, environ, multithread=True, multiprocess=False*)

Similar to `BaseCGIHandler`, but designed for use with HTTP origin servers. If you are writing an HTTP server implementation, you will probably want to subclass this instead of `BaseCGIHandler`.

This class is a subclass of `BaseHandler`. It overrides the `__init__()`, `get_stdin()`, `get_stderr()`, `add_cgi_vars()`, `_write()`, and `_flush()` methods to support explicitly setting the environment and streams via the constructor. The supplied environment and streams are stored in the `stdin`, `stdout`, `stderr`, and `environ` attributes.

class wsgiref.handlers.BaseHandler

This is an abstract base class for running WSGI applications. Each instance will handle a single HTTP request, although in principle you could create a subclass that was reusable for multiple requests.

`BaseHandler` instances have only one method intended for external use:

run (*app*)

Run the specified WSGI application, *app*.

All of the other `BaseHandler` methods are invoked by this method in the process of running the application, and thus exist primarily to allow customizing the process.

The following methods MUST be overridden in a subclass:

`_write(data)`

Buffer the string `data` for transmission to the client. It's okay if this method actually transmits the data; `BaseHandler` just separates write and flush operations for greater efficiency when the underlying system actually has such a distinction.

`_flush()`

Force buffered data to be transmitted to the client. It's okay if this method is a no-op (i.e., if `_write()` actually sends the data).

`get_stdin()`

Return an input stream object suitable for use as the `wsgi.input` of the request currently being processed.

`get_stderr()`

Return an output stream object suitable for use as the `wsgi.errors` of the request currently being processed.

`add_cgi_vars()`

Insert CGI variables for the current request into the `environ` attribute.

Here are some other methods and attributes you may wish to override. This list is only a summary, however, and does not include every method that can be overridden. You should consult the docstrings and source code for additional information before attempting to create a customized `BaseHandler` subclass.

Attributes and methods for customizing the WSGI environment:

`wsgi_multithread`

The value to be used for the `wsgi.multithread` environment variable. It defaults to true in `BaseHandler`, but may have a different default (or be set by the constructor) in the other subclasses.

`wsgi_multiprocess`

The value to be used for the `wsgi.multiprocess` environment variable. It defaults to true in `BaseHandler`, but may have a different default (or be set by the constructor) in the other subclasses.

`wsgi_run_once`

The value to be used for the `wsgi.run_once` environment variable. It defaults to false in `BaseHandler`, but `CGIHandler` sets it to true by default.

`os_environ`

The default environment variables to be included in every request's WSGI environment. By default, this is a copy of `os.environ` at the time that `wsgiref.handlers` was imported, but subclasses can either create their own at the class or instance level. Note that the dictionary should be considered read-only, since the default value is shared between multiple classes and instances.

`server_software`

If the `origin_server` attribute is set, this attribute's value is used to set the default `SERVER_SOFTWARE` WSGI environment variable, and also to set a default `Server:` header in HTTP responses. It is ignored for handlers (such as `BaseCGIHandler` and `CGIHandler`) that are not HTTP origin servers.

`get_scheme()`

Return the URL scheme being used for the current request. The default implementation uses the `guess_scheme()` function from `wsgiref.util` to guess whether the scheme should be `http` or `https`, based on the current request's `environ` variables.

`setup_environ()`

Set the `environ` attribute to a fully-populated WSGI environment. The default implementation uses all of the above methods and attributes, plus the `get_stdin()`, `get_stderr()`, and `add_cgi_vars()` methods and the `wsgi_file_wrapper` attribute. It also inserts a `SERVER_SOFTWARE` key if not present, as long as the `origin_server` attribute is a true value and the `server_software` attribute is set.

Methods and attributes for customizing exception handling:

log_exception (*exc_info*)

Log the *exc_info* tuple in the server log. *exc_info* is a (type, value, traceback) tuple. The default implementation simply writes the traceback to the request's `wsgi.errors` stream and flushes it. Subclasses can override this method to change the format or retarget the output, mail the traceback to an administrator, or whatever other action may be deemed suitable.

traceback_limit

The maximum number of frames to include in tracebacks output by the default `log_exception()` method. If `None`, all frames are included.

error_output (*environ*, *start_response*)

This method is a WSGI application to generate an error page for the user. It is only invoked if an error occurs before headers are sent to the client.

This method can access the current error information using `sys.exc_info()`, and should pass that information to *start_response* when calling it (as described in the «Error Handling» section of [PEP 333](#)).

The default implementation just uses the `error_status`, `error_headers`, and `error_body` attributes to generate an output page. Subclasses can override this to produce more dynamic error output.

Note, however, that it's not recommended from a security perspective to spit out diagnostics to any old user; ideally, you should have to do something special to enable diagnostic output, which is why the default implementation doesn't include any.

error_status

The HTTP status used for error responses. This should be a status string as defined in [PEP 333](#); it defaults to a 500 code and message.

error_headers

The HTTP headers used for error responses. This should be a list of WSGI response headers ((name, value) tuples), as described in [PEP 333](#). The default list just sets the content type to `text/plain`.

error_body

The error response body. This should be an HTTP response body string. It defaults to the plain text, «A server error occurred. Please contact the administrator.»

Methods and attributes for [PEP 333](#)'s «Optional Platform-Specific File Handling» feature:

wsgi_file_wrapper

A `wsgi.file_wrapper` factory, or `None`. The default value of this attribute is the `FileWrapper` class from `wsgiref.util`.

sendfile ()

Override to implement platform-specific file transmission. This method is called only if the application's return value is an instance of the class specified by the `wsgi_file_wrapper` attribute. It should return a true value if it was able to successfully transmit the file, so that the default transmission code will not be executed. The default implementation of this method just returns a false value.

Miscellaneous methods and attributes:

origin_server

This attribute should be set to a true value if the handler's `_write()` and `_flush()` are being used to communicate directly to the client, rather than via a CGI-like gateway protocol that wants the HTTP status in a special `Status:` header.

This attribute's default value is true in `BaseHandler`, but false in `BaseCGIHandler` and `CGIHandler`.

http_version

If `origin_server` is true, this string attribute is used to set the HTTP version of the response set to the client. It defaults to `"1.0"`.

20.4.6 Examples

This is a working 《Hello World》WSGI application:

```
from wsgiref.simple_server import make_server

# Every WSGI application must have an application object - a callable
# object that accepts two arguments. For that purpose, we're going to
# use a function (note that you're not limited to a function, you can
# use a class for example). The first argument passed to the function
# is a dictionary containing CGI-style environment variables and the
# second variable is the callable object (see PEP 333).
def hello_world_app(environ, start_response):
    status = '200 OK' # HTTP Status
    headers = [('Content-type', 'text/plain')] # HTTP Headers
    start_response(status, headers)

    # The returned object is going to be printed
    return ["Hello World"]

httpd = make_server('', 8000, hello_world_app)
print "Serving on port 8000..."

# Serve until process is killed
httpd.serve_forever()
```

20.5 urllib — Open arbitrary resources by URL

참고: The `urllib` module has been split into parts and renamed in Python 3 to `urllib.request`, `urllib.parse`, and `urllib.error`. The *2to3* tool will automatically adapt imports when converting your sources to Python 3. Also note that the `urllib.request.urlopen()` function in Python 3 is equivalent to `urllib2.urlopen()` and that `urllib.urlopen()` has been removed.

This module provides a high-level interface for fetching data across the World Wide Web. In particular, the `urlopen()` function is similar to the built-in function `open()`, but accepts Universal Resource Locators (URLs) instead of filenames. Some restrictions apply — it can only open URLs for reading, and no seek operations are available.

더 보기:

The [Requests package](#) is recommended for a higher-level HTTP client interface.

버전 2.7.9에서 변경: For HTTPS URIs, `urllib` performs all the necessary certificate and hostname checks by default.

경고: For Python versions earlier than 2.7.9, `urllib` does not attempt to validate the server certificates of HTTPS URIs. Use at your own risk!

20.5.1 High-level interface

`urllib.urlopen(url[, data[, proxies[, context]]])`

Open a network object denoted by a URL for reading. If the URL does not have a scheme identifier, or if it has `file:` as its scheme identifier, this opens a local file (without *universal newlines*); otherwise it opens a socket to a server somewhere on the network. If the connection cannot be made the `IOError` exception is raised. If all went well, a file-like object is returned. This supports the following methods: `read()`, `readline()`, `readlines()`, `fileno()`, `close()`, `info()`, `getcode()` and `geturl()`. It also has proper support for the *iterator* protocol. One caveat: the `read()` method, if the size argument is omitted or negative, may not read until the end of the data stream; there is no good way to determine that the entire stream from a socket has been read in the general case.

Except for the `info()`, `getcode()` and `geturl()` methods, these methods have the same interface as for file objects — see section *File Objects* in this manual. (It is not a built-in file object, however, so it can't be used at those few places where a true built-in file object is required.)

The `info()` method returns an instance of the class `mimertools.Message` containing meta-information associated with the URL. When the method is HTTP, these headers are those returned by the server at the head of the retrieved HTML page (including Content-Length and Content-Type). When the method is FTP, a Content-Length header will be present if (as is now usual) the server passed back a file length in response to the FTP retrieval request. A Content-Type header will be present if the MIME type can be guessed. When the method is local-file, returned headers will include a Date representing the file's last-modified time, a Content-Length giving file size, and a Content-Type containing a guess at the file's type. See also the description of the `mimertools` module.

The `geturl()` method returns the real URL of the page. In some cases, the HTTP server redirects a client to another URL. The `urlopen()` function handles this transparently, but in some cases the caller needs to know which URL the client was redirected to. The `geturl()` method can be used to get at this redirected URL.

The `getcode()` method returns the HTTP status code that was sent with the response, or `None` if the URL is no HTTP URL.

If the `url` uses the `http:` scheme identifier, the optional `data` argument may be given to specify a POST request (normally the request type is GET). The `data` argument must be in standard `application/x-www-form-urlencoded` format; see the `urlencode()` function below.

The `urlopen()` function works transparently with proxies which do not require authentication. In a Unix or Windows environment, set the `http_proxy`, or `ftp_proxy` environment variables to a URL that identifies the proxy server before starting the Python interpreter. For example (the `'%'` is the command prompt):

```
% http_proxy="http://www.someproxy.com:3128"
% export http_proxy
% python
...
```

The `no_proxy` environment variable can be used to specify hosts which shouldn't be reached via proxy; if set, it should be a comma-separated list of hostname suffixes, optionally with `:port` appended, for example `cern.ch,nasa.uiuc.edu,some.host:8080`.

In a Windows environment, if no proxy environment variables are set, proxy settings are obtained from the registry's Internet Settings section.

In a Mac OS X environment, `urlopen()` will retrieve proxy information from the OS X System Configuration Framework, which can be managed with Network System Preferences panel.

Alternatively, the optional `proxies` argument may be used to explicitly specify proxies. It must be a dictionary mapping scheme names to proxy URLs, where an empty dictionary causes no proxies to be used, and `None` (the default value) causes environmental proxy settings to be used as discussed above. For example:

```
# Use http://www.someproxy.com:3128 for HTTP proxying
proxies = {'http': 'http://www.someproxy.com:3128'}
filehandle = urllib.urlopen(some_url, proxies=proxies)
# Don't use any proxies
filehandle = urllib.urlopen(some_url, proxies={})
# Use proxies from environment - both versions are equivalent
filehandle = urllib.urlopen(some_url, proxies=None)
filehandle = urllib.urlopen(some_url)
```

Proxies which require authentication for use are not currently supported; this is considered an implementation limitation.

The *context* parameter may be set to a `ssl.SSLContext` instance to configure the SSL settings that are used if `urlopen()` makes a HTTPS connection.

버전 2.3에서 변경: Added the *proxies* support.

버전 2.6에서 변경: Added `getcode()` to returned object and support for the `no_proxy` environment variable.

버전 2.7.9에서 변경: The *context* parameter was added. All the necessary certificate and hostname checks are done by default.

버전 2.6부터 폐지: The `urlopen()` function has been removed in Python 3 in favor of `urllib2.urlopen()`.

`urllib.urlretrieve(url[, filename[, reporthook[, data[, context]]]])`

Copy a network object denoted by a URL to a local file, if necessary. If the URL points to a local file, or a valid cached copy of the object exists, the object is not copied. Return a tuple (*filename*, *headers*) where *filename* is the local file name under which the object can be found, and *headers* is whatever the `info()` method of the object returned by `urlopen()` returned (for a remote object, possibly cached). Exceptions are the same as for `urlopen()`.

The second argument, if present, specifies the file location to copy to (if absent, the location will be a tempfile with a generated name). The third argument, if present, is a callable that will be called once on establishment of the network connection and once after each block read thereafter. The callable will be passed three arguments; a count of blocks transferred so far, a block size in bytes, and the total size of the file. The third argument may be `-1` on older FTP servers which do not return a file size in response to a retrieval request.

If the *url* uses the `http:` scheme identifier, the optional *data* argument may be given to specify a POST request (normally the request type is GET). The *data* argument must in standard `application/x-www-form-urlencoded` format; see the `urlencode()` function below.

The *context* parameter may be set to a `ssl.SSLContext` instance to configure the SSL settings that are used if `urlretrieve()` makes a HTTPS connection.

버전 2.5에서 변경: `urlretrieve()` will raise `ContentTooShortError` when it detects that the amount of data available was less than the expected amount (which is the size reported by a *Content-Length* header). This can occur, for example, when the download is interrupted.

The *Content-Length* is treated as a lower bound: if there's more data to read, `urlretrieve()` reads more data, but if less data is available, it raises the exception.

You can still retrieve the downloaded data in this case, it is stored in the `content` attribute of the exception instance.

If no *Content-Length* header was supplied, `urlretrieve()` can not check the size of the data it has downloaded, and just returns it. In this case you just have to assume that the download was successful.

버전 2.7.9에서 변경: The *context* parameter was added. All the necessary certificate and hostname checks are done by default.

urllib._urlopener

The public functions `urlopen()` and `urlretrieve()` create an instance of the `FancyURLOpener` class and use it to perform their requested actions. To override this functionality, programmers can create a subclass of `URLOpener` or `FancyURLOpener`, then assign an instance of that class to the `urllib._urlopener` variable before calling the desired function. For example, applications may want to specify a different *User-Agent* header than `URLOpener` defines. This can be accomplished with the following code:

```
import urllib

class AppURLOpener(urllib.FancyURLOpener):
    version = "App/1.7"

urllib._urlopener = AppURLOpener()
```

urllib.urlcleanup()

Clear the cache that may have been built up by previous calls to `urlretrieve()`.

20.5.2 Utility functions

urllib.quote(*string* [, *safe*])

Replace special characters in *string* using the `%xx` escape. Letters, digits, and the characters `'_.-'` are never quoted. By default, this function is intended for quoting the path section of the URL. The optional *safe* parameter specifies additional characters that should not be quoted — its default value is `'/'`.

Example: `quote('/~connolly/')` yields `'/%7Econnolly/'`.

urllib.quote_plus(*string* [, *safe*])

Like `quote()`, but also replaces spaces by plus signs, as required for quoting HTML form values when building up a query string to go into a URL. Plus signs in the original string are escaped unless they are included in *safe*. It also does not have *safe* default to `'/'`.

urllib.unquote(*string*)

Replace `%xx` escapes by their single-character equivalent.

Example: `unquote('/%7Econnolly/')` yields `'/~connolly/'`.

urllib.unquote_plus(*string*)

Like `unquote()`, but also replaces plus signs by spaces, as required for unquoting HTML form values.

urllib.urlencode(*query* [, *doseq*])

Convert a mapping object or a sequence of two-element tuples to a «percent-encoded» string, suitable to pass to `urlopen()` above as the optional *data* argument. This is useful to pass a dictionary of form fields to a POST request. The resulting string is a series of *key=value* pairs separated by `'&'` characters, where both *key* and *value* are quoted using `quote_plus()` above. When a sequence of two-element tuples is used as the *query* argument, the first element of each tuple is a key and the second is a value. The value element in itself can be a sequence and in that case, if the optional parameter *doseq* is evaluates to `True`, individual *key=value* pairs separated by `'&'` are generated for each element of the value sequence for the key. The order of parameters in the encoded string will match the order of parameter tuples in the sequence. The `urlparse` module provides the functions `parse_qs()` and `parse_qsl()` which are used to parse query strings into Python data structures.

urllib.pathname2url(*path*)

Convert the pathname *path* from the local syntax for a path to the form used in the path component of a URL. This does not produce a complete URL. The return value will already be quoted using the `quote()` function.

urllib.url2pathname(*path*)

Convert the path component *path* from a percent-encoded URL to the local syntax for a path. This does not accept a complete URL. This function uses `unquote()` to decode *path*.

`urllib.getproxies()`

This helper function returns a dictionary of scheme to proxy server URL mappings. It scans the environment for variables named `<scheme>_proxy`, in case insensitive way, for all operating systems first, and when it cannot find it, looks for proxy information from Mac OSX System Configuration for Mac OS X and Windows Systems Registry for Windows. If both lowercase and uppercase environment variables exist (and disagree), lowercase is preferred.

참고: If the environment variable `REQUEST_METHOD` is set, which usually indicates your script is running in a CGI environment, the environment variable `HTTP_PROXY` (uppercase `_PROXY`) will be ignored. This is because that variable can be injected by a client using the `Proxy:` HTTP header. If you need to use an HTTP proxy in a CGI environment, either use `ProxyHandler` explicitly, or make sure the variable name is in lowercase (or at least the `_proxy` suffix).

참고: `urllib` also exposes certain utility functions like `splitttype`, `splthost` and others parsing URL into various components. But it is recommended to use `urlparse` for parsing URLs rather than using these functions directly. Python 3 does not expose these helper functions from `urllib.parse` module.

20.5.3 URL Opener objects

class `urllib.URLOpener` (`[proxies[, context[, **x509]]]`)

Base class for opening and reading URLs. Unless you need to support opening objects using schemes other than `http:`, `ftp:`, or `file:`, you probably want to use `FancyURLOpener`.

By default, the `URLOpener` class sends a *User-Agent* header of `urllib/VVV`, where `VVV` is the `urllib` version number. Applications can define their own *User-Agent* header by subclassing `URLOpener` or `FancyURLOpener` and setting the class attribute `version` to an appropriate string value in the subclass definition.

The optional `proxies` parameter should be a dictionary mapping scheme names to proxy URLs, where an empty dictionary turns proxies off completely. Its default value is `None`, in which case environmental proxy settings will be used if present, as discussed in the definition of `urlopen()`, above.

The `context` parameter may be a `ssl.SSLContext` instance. If given, it defines the SSL settings the opener uses to make HTTPS connections.

Additional keyword parameters, collected in `x509`, may be used for authentication of the client when using the `https:` scheme. The keywords `key_file` and `cert_file` are supported to provide an SSL key and certificate; both are needed to support client authentication.

`URLOpener` objects will raise an `IOError` exception if the server returns an error code.

버전 2.7.9에서 변경: The `context` parameter was added. All the necessary certificate and hostname checks are done by default.

open (`fullurl[, data]`)

Open `fullurl` using the appropriate protocol. This method sets up cache and proxy information, then calls the appropriate open method with its input arguments. If the scheme is not recognized, `open_unknown()` is called. The `data` argument has the same meaning as the `data` argument of `urlopen()`.

open_unknown (`fullurl[, data]`)

Overridable interface to open unknown URL types.

retrieve (`url[, filename[, reporthook[, data]]]`)

Retrieves the contents of `url` and places it in `filename`. The return value is a tuple consisting of a local filename

and either a *mimetools.Message* object containing the response headers (for remote URLs) or *None* (for local URLs). The caller must then open and read the contents of *filename*. If *filename* is not given and the URL refers to a local file, the input filename is returned. If the URL is non-local and *filename* is not given, the filename is the output of *tempfile.mktemp()* with a suffix that matches the suffix of the last path component of the input URL. If *reporthook* is given, it must be a function accepting three numeric parameters. It will be called after each chunk of data is read from the network. *reporthook* is ignored for local URLs.

If the *url* uses the *http:* scheme identifier, the optional *data* argument may be given to specify a POST request (normally the request type is GET). The *data* argument must in standard *application/x-www-form-urlencoded* format; see the *urlencode()* function below.

version

Variable that specifies the user agent of the opener object. To get *urllib* to tell servers that it is a particular user agent, set this in a subclass as a class variable or in the constructor before calling the base constructor.

class *urllib.FancyURLopener* (...)

FancyURLopener subclasses *URLopener* providing default handling for the following HTTP response codes: 301, 302, 303, 307 and 401. For the 30x response codes listed above, the *Location* header is used to fetch the actual URL. For 401 response codes (authentication required), basic HTTP authentication is performed. For the 30x response codes, recursion is bounded by the value of the *maxtries* attribute, which defaults to 10.

For all other response codes, the method *http_error_default()* is called which you can override in subclasses to handle the error appropriately.

참고: According to the letter of **RFC 2616**, 301 and 302 responses to POST requests must not be automatically redirected without confirmation by the user. In reality, browsers do allow automatic redirection of these responses, changing the POST to a GET, and *urllib* reproduces this behaviour.

The parameters to the constructor are the same as those for *URLopener*.

참고: When performing basic authentication, a *FancyURLopener* instance calls its *prompt_user_passwd()* method. The default implementation asks the users for the required information on the controlling terminal. A subclass may override this method to support more appropriate behavior if needed.

The *FancyURLopener* class offers one additional method that should be overloaded to provide the appropriate behavior:

prompt_user_passwd (*host*, *realm*)

Return information needed to authenticate the user at the given host in the specified security realm. The return value should be a tuple, (*user*, *password*), which can be used for basic authentication.

The implementation prompts for this information on the terminal; an application should override this method to use an appropriate interaction model in the local environment.

exception *urllib.ContentTooShortError* (*msg*[, *content*])

This exception is raised when the *urlretrieve()* function detects that the amount of the downloaded data is less than the expected amount (given by the *Content-Length* header). The *content* attribute stores the downloaded (and supposedly truncated) data.

버전 2.5에 추가.

20.5.4 urllib Restrictions

- Currently, only the following protocols are supported: HTTP, (versions 0.9 and 1.0), FTP, and local files.
- The caching feature of `urlretrieve()` has been disabled until I find the time to hack proper processing of Expiration time headers.
- There should be a function to query whether a particular URL is in the cache.
- For backward compatibility, if a URL appears to point to a local file but the file can't be opened, the URL is re-interpreted using the FTP protocol. This can sometimes cause confusing error messages.
- The `urlopen()` and `urlretrieve()` functions can cause arbitrarily long delays while waiting for a network connection to be set up. This means that it is difficult to build an interactive Web client using these functions without using threads.
- The data returned by `urlopen()` or `urlretrieve()` is the raw data returned by the server. This may be binary data (such as an image), plain text or (for example) HTML. The HTTP protocol provides type information in the reply header, which can be inspected by looking at the `Content-Type` header. If the returned data is HTML, you can use the module `htmllib` to parse it.
- The code handling the FTP protocol cannot differentiate between a file and a directory. This can lead to unexpected behavior when attempting to read a URL that points to a file that is not accessible. If the URL ends in a `/`, it is assumed to refer to a directory and will be handled accordingly. But if an attempt to read a file leads to a 550 error (meaning the URL cannot be found or is not accessible, often for permission reasons), then the path is treated as a directory in order to handle the case when a directory is specified by a URL but the trailing `/` has been left off. This can cause misleading results when you try to fetch a file whose read permissions make it inaccessible; the FTP code will try to read it, fail with a 550 error, and then perform a directory listing for the unreadable file. If fine-grained control is needed, consider using the `ftplib` module, subclassing `FancyURLopener`, or changing `_urloper` to meet your needs.
- This module does not support the use of proxies which require authentication. This may be implemented in the future.
- Although the `urllib` module contains (undocumented) routines to parse and unparse URL strings, the recommended interface for URL manipulation is in module `urlparse`.

20.5.5 Examples

Here is an example session that uses the GET method to retrieve a URL containing parameters:

```
>>> import urllib
>>> params = urllib.urlencode({'spam': 1, 'eggs': 2, 'bacon': 0})
>>> f = urllib.urlopen("http://www.musi-cal.com/cgi-bin/query?%s" % params)
>>> print f.read()
```

The following example uses the POST method instead:

```
>>> import urllib
>>> params = urllib.urlencode({'spam': 1, 'eggs': 2, 'bacon': 0})
>>> f = urllib.urlopen("http://www.musi-cal.com/cgi-bin/query", params)
>>> print f.read()
```

The following example uses an explicitly specified HTTP proxy, overriding environment settings:


```
>>> import urllib
>>> proxies = {'http': 'http://proxy.example.com:8080/'}
>>> opener = urllib.FancyURLopener(proxies)
>>> f = opener.open("http://www.python.org")
>>> f.read()
```

The following example uses no proxies at all, overriding environment settings:

```
>>> import urllib
>>> opener = urllib.FancyURLopener({})
>>> f = opener.open("http://www.python.org/")
>>> f.read()
```

20.6 urllib2 — extensible library for opening URLs

참고: The *urllib2* module has been split across several modules in Python 3 named `urllib.request` and `urllib.error`. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

The *urllib2* module defines functions and classes which help in opening URLs (mostly HTTP) in a complex world — basic and digest authentication, redirections, cookies and more.

더 보기:

The *Requests* package is recommended for a higher-level HTTP client interface.

The *urllib2* module defines the following functions:

`urllib2.urlopen(url[, data[, timeout[, cafile[, capath[, cadefault[, context]]]])`

Open the URL *url*, which can be either a string or a *Request* object.

data may be a string specifying additional data to send to the server, or `None` if no such data is needed. Currently HTTP requests are the only ones that use *data*; the HTTP request will be a POST instead of a GET when the *data* parameter is provided. *data* should be a buffer in the standard *application/x-www-form-urlencoded* format. The `urllib.urlencode()` function takes a mapping or sequence of 2-tuples and returns a string in this format. *urllib2* module sends HTTP/1.1 requests with `Connection:close` header included.

The optional *timeout* parameter specifies a timeout in seconds for blocking operations like the connection attempt (if not specified, the global default timeout setting will be used). This actually only works for HTTP, HTTPS and FTP connections.

If *context* is specified, it must be a `ssl.SSLContext` instance describing the various SSL options. See *HTTPConnection* for more details.

The optional *cafile* and *capath* parameters specify a set of trusted CA certificates for HTTPS requests. *cafile* should point to a single file containing a bundle of CA certificates, whereas *capath* should point to a directory of hashed certificate files. More information can be found in `ssl.SSLContext.load_verify_locations()`.

The *cadefault* parameter is ignored.

This function returns a file-like object with three additional methods:

- `geturl()` — return the URL of the resource retrieved, commonly used to determine if a redirect was followed
- `info()` — return the meta-information of the page, such as headers, in the form of an *mimertools.Message* instance (see *Quick Reference to HTTP Headers*)

- `getcode()` — return the HTTP status code of the response.

Raises `URLError` on errors.

Note that `None` may be returned if no handler handles the request (though the default installed global `OpenerDirector` uses `UnknownHandler` to ensure this never happens).

In addition, if proxy settings are detected (for example, when a `*_proxy` environment variable like `http_proxy` is set), `ProxyHandler` is default installed and makes sure the requests are handled through the proxy.

버전 2.6에서 변경: `timeout` was added.

버전 2.7.9에서 변경: `cafile`, `capath`, `cadefault`, and `context` were added.

`urllib2.install_opener(opener)`

Install an `OpenerDirector` instance as the default global opener. Installing an opener is only necessary if you want `urlopen` to use that opener; otherwise, simply call `OpenerDirector.open()` instead of `urlopen()`. The code does not check for a real `OpenerDirector`, and any class with the appropriate interface will work.

`urllib2.build_opener([handler, ...])`

Return an `OpenerDirector` instance, which chains the handlers in the order given. *handlers* can be either instances of `BaseHandler`, or subclasses of `BaseHandler` (in which case it must be possible to call the constructor without any parameters). Instances of the following classes will be in front of the *handlers*, unless the *handlers* contain them, instances of them or subclasses of them: `ProxyHandler` (if proxy settings are detected), `UnknownHandler`, `HTTPHandler`, `HTTPDefaultErrorHandler`, `HTTPRedirectHandler`, `FTPHandler`, `FileHandler`, `HTTPErrorProcessor`.

If the Python installation has SSL support (i.e., if the `ssl` module can be imported), `HTTPSHandler` will also be added.

Beginning in Python 2.3, a `BaseHandler` subclass may also change its `handler_order` attribute to modify its position in the handlers list.

The following exceptions are raised as appropriate:

exception `urllib2.URLError`

The handlers raise this exception (or derived exceptions) when they run into a problem. It is a subclass of `IOError`.

reason

The reason for this error. It can be a message string or another exception instance (`socket.error` for remote URLs, `OSError` for local URLs).

exception `urllib2.HTTPError`

Though being an exception (a subclass of `URLError`), an `HTTPError` can also function as a non-exceptional file-like return value (the same thing that `urlopen()` returns). This is useful when handling exotic HTTP errors, such as requests for authentication.

code

An HTTP status code as defined in RFC 2616. This numeric value corresponds to a value found in the dictionary of codes as found in `BaseHTTPServer.BaseHTTPRequestHandler.responses`.

reason

The reason for this error. It can be a message string or another exception instance.

The following classes are provided:

class `urllib2.Request(url[, data][, headers][, origin_req_host][, unverifiable])`

This class is an abstraction of a URL request.

url should be a string containing a valid URL.

data may be a string specifying additional data to send to the server, or `None` if no such data is needed. Currently HTTP requests are the only ones that use *data*; the HTTP request will be a POST instead of a GET when the *data* parameter is provided. *data* should be a buffer in the standard *application/x-www-form-urlencoded* format. The `urllib.urlencode()` function takes a mapping or sequence of 2-tuples and returns a string in this format.

headers should be a dictionary, and will be treated as if `add_header()` was called with each key and value as arguments. This is often used to «spoof» the User-Agent header value, which is used by a browser to identify itself – some HTTP servers only allow requests coming from common browsers as opposed to scripts. For example, Mozilla Firefox may identify itself as "Mozilla/5.0 (X11; U; Linux i686) Gecko/20071127 Firefox/2.0.0.11", while `urllib2`'s default user agent string is "Python-urllib/2.6" (on Python 2.6).

The final two arguments are only of interest for correct handling of third-party HTTP cookies:

origin_req_host should be the request-host of the origin transaction, as defined by [RFC 2965](#). It defaults to `cookielib.request_host(self)`. This is the host name or IP address of the original request that was initiated by the user. For example, if the request is for an image in an HTML document, this should be the request-host of the request for the page containing the image.

unverifiable should indicate whether the request is unverifiable, as defined by RFC 2965. It defaults to `False`. An unverifiable request is one whose URL the user did not have the option to approve. For example, if the request is for an image in an HTML document, and the user had no option to approve the automatic fetching of the image, this should be true.

class `urllib2.OpenerDirector`

The `OpenerDirector` class opens URLs via `BaseHandlers` chained together. It manages the chaining of handlers, and recovery from errors.

class `urllib2.BaseHandler`

This is the base class for all registered handlers — and handles only the simple mechanics of registration.

class `urllib2.HTTPDefaultErrorHandler`

A class which defines a default handler for HTTP error responses; all responses are turned into `HTTPError` exceptions.

class `urllib2.HTTPRedirectHandler`

A class to handle redirections.

class `urllib2.HTTPCookieProcessor` (`[cookiejar]`)

A class to handle HTTP Cookies.

class `urllib2.ProxyHandler` (`[proxies]`)

Cause requests to go through a proxy. If *proxies* is given, it must be a dictionary mapping protocol names to URLs of proxies. The default is to read the list of proxies from the environment variables `<protocol>_proxy`. If no proxy environment variables are set, then in a Windows environment proxy settings are obtained from the registry's Internet Settings section, and in a Mac OS X environment proxy information is retrieved from the OS X System Configuration Framework.

To disable autodetected proxy pass an empty dictionary.

참고: `HTTP_PROXY` will be ignored if a variable `REQUEST_METHOD` is set; see the documentation on `getproxies()`.

class `urllib2.HTTPPasswordMgr`

Keep a database of (realm, uri) -> (user, password) mappings.

class urllib2.HTTPPasswordMgrWithDefaultRealm

Keep a database of (realm, uri) -> (user, password) mappings. A realm of None is considered a catch-all realm, which is searched if no other realm fits.

class urllib2.AbstractBasicAuthHandler ([password_mgr])

This is a mixin class that helps with HTTP authentication, both to the remote host and to a proxy. *password_mgr*, if given, should be something that is compatible with [HTTPPasswordMgr](#); refer to section [HTTPPasswordMgr Objects](#) for information on the interface that must be supported.

class urllib2.HTTPBasicAuthHandler ([password_mgr])

Handle authentication with the remote host. *password_mgr*, if given, should be something that is compatible with [HTTPPasswordMgr](#); refer to section [HTTPPasswordMgr Objects](#) for information on the interface that must be supported.

class urllib2.ProxyBasicAuthHandler ([password_mgr])

Handle authentication with the proxy. *password_mgr*, if given, should be something that is compatible with [HTTPPasswordMgr](#); refer to section [HTTPPasswordMgr Objects](#) for information on the interface that must be supported.

class urllib2.AbstractDigestAuthHandler ([password_mgr])

This is a mixin class that helps with HTTP authentication, both to the remote host and to a proxy. *password_mgr*, if given, should be something that is compatible with [HTTPPasswordMgr](#); refer to section [HTTPPasswordMgr Objects](#) for information on the interface that must be supported.

class urllib2.HTTPDigestAuthHandler ([password_mgr])

Handle authentication with the remote host. *password_mgr*, if given, should be something that is compatible with [HTTPPasswordMgr](#); refer to section [HTTPPasswordMgr Objects](#) for information on the interface that must be supported.

class urllib2.ProxyDigestAuthHandler ([password_mgr])

Handle authentication with the proxy. *password_mgr*, if given, should be something that is compatible with [HTTPPasswordMgr](#); refer to section [HTTPPasswordMgr Objects](#) for information on the interface that must be supported.

class urllib2.HTTPHandler

A class to handle opening of HTTP URLs.

class urllib2.HTTPSHandler ([debuglevel[, context]])

A class to handle opening of HTTPS URLs. *context* has the same meaning as for [httplib.HTTPSConnection](#).

버전 2.7.9에서 변경: *context* added.

class urllib2.FileHandler

Open local files.

class urllib2.FTPHandler

Open FTP URLs.

class urllib2.CacheFTPHandler

Open FTP URLs, keeping a cache of open FTP connections to minimize delays.

class urllib2.UnknownHandler

A catch-all class to handle unknown URLs.

class urllib2.HTTPErrorProcessor

Process HTTP error responses.

20.6.1 Request Objects

The following methods describe all of *Request*'s public interface, and so all must be overridden in subclasses.

`Request.add_data(data)`

Set the *Request* data to *data*. This is ignored by all handlers except HTTP handlers — and there it should be a byte string, and will change the request to be POST rather than GET.

`Request.get_method()`

Return a string indicating the HTTP request method. This is only meaningful for HTTP requests, and currently always returns 'GET' or 'POST'.

`Request.has_data()`

Return whether the instance has a non-None data.

`Request.get_data()`

Return the instance's data.

`Request.add_header(key, val)`

Add another header to the request. Headers are currently ignored by all handlers except HTTP handlers, where they are added to the list of headers sent to the server. Note that there cannot be more than one header with the same name, and later calls will overwrite previous calls in case the *key* collides. Currently, this is no loss of HTTP functionality, since all headers which have meaning when used more than once have a (header-specific) way of gaining the same functionality using only one header.

`Request.add_unredirected_header(key, header)`

Add a header that will not be added to a redirected request.

버전 2.4에 추가.

`Request.has_header(header)`

Return whether the instance has the named header (checks both regular and unredirected).

버전 2.4에 추가.

`Request.get_full_url()`

Return the URL given in the constructor.

`Request.get_type()`

Return the type of the URL — also known as the scheme.

`Request.get_host()`

Return the host to which a connection will be made.

`Request.get_selector()`

Return the selector — the part of the URL that is sent to the server.

`Request.get_header(header_name, default=None)`

Return the value of the given header. If the header is not present, return the default value.

`Request.header_items()`

Return a list of tuples (header_name, header_value) of the Request headers.

`Request.set_proxy(host, type)`

Prepare the request by connecting to a proxy server. The *host* and *type* will replace those of the instance, and the instance's selector will be the original URL given in the constructor.

`Request.get_origin_req_host()`

Return the request-host of the origin transaction, as defined by [RFC 2965](#). See the documentation for the *Request* constructor.

`Request.is_unverifiable()`

Return whether the request is unverifiable, as defined by RFC 2965. See the documentation for the *Request* constructor.

20.6.2 OpenerDirector Objects

OpenerDirector instances have the following methods:

`OpenerDirector.add_handler(handler)`

handler should be an instance of *BaseHandler*. The following methods are searched, and added to the possible chains (note that HTTP errors are a special case).

- *protocol_open* — signal that the handler knows how to open *protocol* URLs.
- *http_error_type* — signal that the handler knows how to handle HTTP errors with HTTP error code *type*.
- *protocol_error* — signal that the handler knows how to handle errors from (non-http) *protocol*.
- *protocol_request* — signal that the handler knows how to pre-process *protocol* requests.
- *protocol_response* — signal that the handler knows how to post-process *protocol* responses.

`OpenerDirector.open(url[, data][, timeout])`

Open the given *url* (which can be a request object or a string), optionally passing the given *data*. Arguments, return values and exceptions raised are the same as those of *urlopen()* (which simply calls the *open()* method on the currently installed global *OpenerDirector*). The optional *timeout* parameter specifies a timeout in seconds for blocking operations like the connection attempt (if not specified, the global default timeout setting will be used). The timeout feature actually works only for HTTP, HTTPS and FTP connections).

버전 2.6에서 변경: *timeout* was added.

`OpenerDirector.error(proto[, arg[, ...]])`

Handle an error of the given protocol. This will call the registered error handlers for the given protocol with the given arguments (which are protocol specific). The HTTP protocol is a special case which uses the HTTP response code to determine the specific error handler; refer to the *http_error_*()* methods of the handler classes.

Return values and exceptions raised are the same as those of *urlopen()*.

OpenerDirector objects open URLs in three stages:

The order in which these methods are called within each stage is determined by sorting the handler instances.

1. Every handler with a method named like *protocol_request* has that method called to pre-process the request.
2. Handlers with a method named like *protocol_open* are called to handle the request. This stage ends when a handler either returns a non-*None* value (ie. a response), or raises an exception (usually *URLError*). Exceptions are allowed to propagate.

In fact, the above algorithm is first tried for methods named *default_open()*. If all such methods return *None*, the algorithm is repeated for methods named like *protocol_open*. If all such methods return *None*, the algorithm is repeated for methods named *unknown_open()*.

Note that the implementation of these methods may involve calls of the parent *OpenerDirector* instance's *open()* and *error()* methods.

3. Every handler with a method named like *protocol_response* has that method called to post-process the response.

20.6.3 BaseHandler Objects

BaseHandler objects provide a couple of methods that are directly useful, and others that are meant to be used by derived classes. These are intended for direct use:

`BaseHandler.add_parent (director)`

Add a director as parent.

`BaseHandler.close ()`

Remove any parents.

The following attributes and methods should only be used by classes derived from *BaseHandler*.

참고 : The convention has been adopted that subclasses defining `protocol_request ()` or `protocol_response ()` methods are named **Processor*; all others are named **Handler*.

`BaseHandler.parent`

A valid *OpenerDirector*, which can be used to open using a different protocol, or handle errors.

`BaseHandler.default_open (req)`

This method is *not* defined in *BaseHandler*, but subclasses should define it if they want to catch all URLs.

This method, if implemented, will be called by the parent *OpenerDirector*. It should return a file-like object as described in the return value of the `open ()` of *OpenerDirector*, or *None*. It should raise *URLError*, unless a truly exceptional thing happens (for example, *MemoryError* should not be mapped to *URLError*).

This method will be called before any protocol-specific open method.

`BaseHandler.protocol_open (req)`

(`protocol` is to be replaced by the protocol name.)

This method is *not* defined in *BaseHandler*, but subclasses should define it if they want to handle URLs with the given *protocol*.

This method, if defined, will be called by the parent *OpenerDirector*. Return values should be the same as for `default_open ()`.

`BaseHandler.unknown_open (req)`

This method is *not* defined in *BaseHandler*, but subclasses should define it if they want to catch all URLs with no specific registered handler to open it.

This method, if implemented, will be called by the parent *OpenerDirector*. Return values should be the same as for `default_open ()`.

`BaseHandler.http_error_default (req, fp, code, msg, hdrs)`

This method is *not* defined in *BaseHandler*, but subclasses should override it if they intend to provide a catch-all for otherwise unhandled HTTP errors. It will be called automatically by the *OpenerDirector* getting the error, and should not normally be called in other circumstances.

req will be a *Request* object, *fp* will be a file-like object with the HTTP error body, *code* will be the three-digit code of the error, *msg* will be the user-visible explanation of the code and *hdrs* will be a mapping object with the headers of the error.

Return values and exceptions raised should be the same as those of `urlopen ()`.

`BaseHandler.http_error_nnn (req, fp, code, msg, hdrs)`

nnn should be a three-digit HTTP error code. This method is also not defined in *BaseHandler*, but will be called, if it exists, on an instance of a subclass, when an HTTP error with code *nnn* occurs.

Subclasses should override this method to handle specific HTTP errors.

Arguments, return values and exceptions raised should be the same as for `http_error_default()`.

`BaseHandler.protocol_request(req)`

(`protocol` is to be replaced by the protocol name.)

This method is *not* defined in `BaseHandler`, but subclasses should define it if they want to pre-process requests of the given *protocol*.

This method, if defined, will be called by the parent `OpenerDirector`. *req* will be a `Request` object. The return value should be a `Request` object.

`BaseHandler.protocol_response(req, response)`

(`protocol` is to be replaced by the protocol name.)

This method is *not* defined in `BaseHandler`, but subclasses should define it if they want to post-process responses of the given *protocol*.

This method, if defined, will be called by the parent `OpenerDirector`. *req* will be a `Request` object. *response* will be an object implementing the same interface as the return value of `urlopen()`. The return value should implement the same interface as the return value of `urlopen()`.

20.6.4 HTTPRedirectHandler Objects

참고: Some HTTP redirections require action from this module's client code. If this is the case, `HTTPError` is raised. See [RFC 2616](#) for details of the precise meanings of the various redirection codes.

`HTTPRedirectHandler.redirect_request(req, fp, code, msg, hdrs, newurl)`

Return a `Request` or `None` in response to a redirect. This is called by the default implementations of the `http_error_30*`() methods when a redirection is received from the server. If a redirection should take place, return a new `Request` to allow `http_error_30*`() to perform the redirect to *newurl*. Otherwise, raise `HTTPError` if no other handler should try to handle this URL, or return `None` if you can't but another handler might.

참고: The default implementation of this method does not strictly follow [RFC 2616](#), which says that 301 and 302 responses to POST requests must not be automatically redirected without confirmation by the user. In reality, browsers do allow automatic redirection of these responses, changing the POST to a GET, and the default implementation reproduces this behavior.

`HTTPRedirectHandler.http_error_301(req, fp, code, msg, hdrs)`

Redirect to the `Location:` or `URI:` URL. This method is called by the parent `OpenerDirector` when getting an HTTP `<moved permanently>` response.

`HTTPRedirectHandler.http_error_302(req, fp, code, msg, hdrs)`

The same as `http_error_301()`, but called for the `<found>` response.

`HTTPRedirectHandler.http_error_303(req, fp, code, msg, hdrs)`

The same as `http_error_301()`, but called for the `<see other>` response.

`HTTPRedirectHandler.http_error_307(req, fp, code, msg, hdrs)`

The same as `http_error_301()`, but called for the `<temporary redirect>` response.

20.6.5 HTTPCookieProcessor Objects

버전 2.4에 추가.

HTTPCookieProcessor instances have one attribute:

`HTTPCookieProcessor.cookiejar`

The *cookielib.CookieJar* in which cookies are stored.

20.6.6 ProxyHandler Objects

`ProxyHandler.protocol_open(request)`

(`protocol` is to be replaced by the protocol name.)

The *ProxyHandler* will have a method *protocol_open* for every *protocol* which has a proxy in the *proxies* dictionary given in the constructor. The method will modify requests to go through the proxy, by calling `request.set_proxy()`, and call the next handler in the chain to actually execute the protocol.

20.6.7 HTTPPasswordMgr Objects

These methods are available on *HTTPPasswordMgr* and *HTTPPasswordMgrWithDefaultRealm* objects.

`HTTPPasswordMgr.add_password(realm, uri, user, passwd)`

uri can be either a single URI, or a sequence of URIs. *realm*, *user* and *passwd* must be strings. This causes (*user*, *passwd*) to be used as authentication tokens when authentication for *realm* and a super-URI of any of the given URIs is given.

`HTTPPasswordMgr.find_user_password(realm, authuri)`

Get user/password for given realm and URI, if any. This method will return (*None*, *None*) if there is no matching user/password.

For *HTTPPasswordMgrWithDefaultRealm* objects, the realm *None* will be searched if the given *realm* has no matching user/password.

20.6.8 AbstractBasicAuthHandler Objects

`AbstractBasicAuthHandler.http_error_auth_reqd(authreq, host, req, headers)`

Handle an authentication request by getting a user/password pair, and re-trying the request. *authreq* should be the name of the header where the information about the realm is included in the request, *host* specifies the URL and path to authenticate for, *req* should be the (failed) *Request* object, and *headers* should be the error headers.

host is either an authority (e.g. "python.org") or a URL containing an authority component (e.g. "http://python.org/"). In either case, the authority must not contain a userinfo component (so, "python.org" and "python.org:80" are fine, "joe:password@python.org" is not).

20.6.9 HTTPBasicAuthHandler Objects

`HTTPBasicAuthHandler.http_error_401` (*req, fp, code, msg, hdrs*)
Retry the request with authentication information, if available.

20.6.10 ProxyBasicAuthHandler Objects

`ProxyBasicAuthHandler.http_error_407` (*req, fp, code, msg, hdrs*)
Retry the request with authentication information, if available.

20.6.11 AbstractDigestAuthHandler Objects

`AbstractDigestAuthHandler.http_error_auth_reged` (*authreq, host, req, headers*)
authreq should be the name of the header where the information about the realm is included in the request, *host* should be the host to authenticate to, *req* should be the (failed) *Request* object, and *headers* should be the error headers.

20.6.12 HTTPDigestAuthHandler Objects

`HTTPDigestAuthHandler.http_error_401` (*req, fp, code, msg, hdrs*)
Retry the request with authentication information, if available.

20.6.13 ProxyDigestAuthHandler Objects

`ProxyDigestAuthHandler.http_error_407` (*req, fp, code, msg, hdrs*)
Retry the request with authentication information, if available.

20.6.14 HTTPHandler Objects

`HTTPHandler.http_open` (*req*)
Send an HTTP request, which can be either GET or POST, depending on `req.has_data()`.

20.6.15 HTTPSHandler Objects

`HTTPSHandler.https_open` (*req*)
Send an HTTPS request, which can be either GET or POST, depending on `req.has_data()`.

20.6.16 FileHandler Objects

`FileHandler.file_open` (*req*)
Open the file locally, if there is no host name, or the host name is 'localhost'. Change the protocol to ftp otherwise, and retry opening it using `parent`.

20.6.17 FTPHandler Objects

`FTPHandler.ftp_open(req)`

Open the FTP file indicated by *req*. The login is always done with empty username and password.

20.6.18 CacheFTPHandler Objects

CacheFTPHandler objects are *FTPHandler* objects with the following additional methods:

`CacheFTPHandler.setTimeout(t)`

Set timeout of connections to *t* seconds.

`CacheFTPHandler.setMaxConns(m)`

Set maximum number of cached connections to *m*.

20.6.19 UnknownHandler Objects

`UnknownHandler.unknown_open()`

Raise a *URLError* exception.

20.6.20 HTTPErrorProcessor Objects

버전 2.4에 추가.

`HTTPErrorProcessor.http_response()`

Process HTTP error responses.

For 200 error codes, the response object is returned immediately.

For non-200 error codes, this simply passes the job on to the *protocol_error_code* handler methods, via *OpenerDirector.error()*. Eventually, *urllib2.HTTPDefaultErrorHandler* will raise an *HTTPError* if no other handler handles the error.

`HTTPErrorProcessor.https_response()`

Process HTTPS error responses.

The behavior is same as *http_response()*.

20.6.21 Examples

In addition to the examples below, more examples are given in *urllib-howto*.

This example gets the python.org main page and displays the first 100 bytes of it:

```
>>> import urllib2
>>> f = urllib2.urlopen('http://www.python.org/')
>>> print f.read(100)
<!DOCTYPE html PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
<?xml-stylesheet href="./css/ht2html
```

Here we are sending a data-stream to the stdin of a CGI and reading the data it returns to us. Note that this example will only work when the Python installation supports SSL.

```
>>> import urllib2
>>> req = urllib2.Request(url='https://localhost/cgi-bin/test.cgi',
...                        data='This data is passed to stdin of the CGI')
>>> f = urllib2.urlopen(req)
>>> print f.read()
Got Data: "This data is passed to stdin of the CGI"
```

The code for the sample CGI used in the above example is:

```
#!/usr/bin/env python
import sys
data = sys.stdin.read()
print 'Content-type: text-plain\n\nGot Data: "%s"' % data
```

Use of Basic HTTP Authentication:

```
import urllib2
# Create an OpenerDirector with support for Basic HTTP Authentication...
auth_handler = urllib2.HTTPBasicAuthHandler()
auth_handler.add_password(realm='PDQ Application',
                          uri='https://mahler:8092/site-updates.py',
                          user='klem',
                          passwd='kadidd!ehopper')
opener = urllib2.build_opener(auth_handler)
# ...and install it globally so it can be used with urlopen.
urllib2.install_opener(opener)
urllib2.urlopen('http://www.example.com/login.html')
```

build_opener() provides many handlers by default, including a *ProxyHandler*. By default, *ProxyHandler* uses the environment variables named *<scheme>_proxy*, where *<scheme>* is the URL scheme involved. For example, the *http_proxy* environment variable is read to obtain the HTTP proxy's URL.

This example replaces the default *ProxyHandler* with one that uses programmatically-supplied proxy URLs, and adds proxy authorization support with *ProxyBasicAuthHandler*.

```
proxy_handler = urllib2.ProxyHandler({'http': 'http://www.example.com:3128/'})
proxy_auth_handler = urllib2.ProxyBasicAuthHandler()
proxy_auth_handler.add_password('realm', 'host', 'username', 'password')

opener = urllib2.build_opener(proxy_handler, proxy_auth_handler)
# This time, rather than install the OpenerDirector, we use it directly:
opener.open('http://www.example.com/login.html')
```

Adding HTTP headers:

Use the *headers* argument to the *Request* constructor, or:

```
import urllib2
req = urllib2.Request('http://www.example.com/')
req.add_header('Referer', 'http://www.python.org/')
# Customize the default User-Agent header value:
req.add_header('User-Agent', 'urllib-example/0.1 (Contact: . . .)')
r = urllib2.urlopen(req)
```

OpenerDirector automatically adds a *User-Agent* header to every *Request*. To change this:

```
import urllib2
opener = urllib2.build_opener()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
opener.addheaders = [('User-agent', 'Mozilla/5.0')]
opener.open('http://www.example.com/')
```

Also, remember that a few standard headers (*Content-Length*, *Content-Type* and *Host*) are added when the *Request* is passed to *urlopen()* (or *OpenerDirector.open()*).

20.7 httplib — HTTP protocol client

참고: The *httplib* module has been renamed to *http.client* in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

Source code: [Lib/httplib.py](#)

This module defines classes which implement the client side of the HTTP and HTTPS protocols. It is normally not used directly — the module *urllib* uses it to handle URLs that use HTTP and HTTPS.

더 보기:

The [Requests package](#) is recommended for a higher-level HTTP client interface.

참고: HTTPS support is only available if the *socket* module was compiled with SSL support.

참고: The public interface for this module changed substantially in Python 2.0. The *HTTP* class is retained only for backward compatibility with 1.5.2. It should not be used in new code. Refer to the online docstrings for usage.

The module provides the following classes:

class `httplib.HTTPConnection`(*host*[, *port*[, *strict*[, *timeout*[, *source_address*]]]])

An *HTTPConnection* instance represents one transaction with an HTTP server. It should be instantiated passing it a host and optional port number. If no port number is passed, the port is extracted from the host string if it has the form *host:port*, else the default HTTP port (80) is used. When true, the optional parameter *strict* (which defaults to a false value) causes *BadStatusLine* to be raised if the status line can't be parsed as a valid HTTP/1.0 or 1.1 status line. If the optional *timeout* parameter is given, blocking operations (like connection attempts) will timeout after that many seconds (if it is not given, the global default timeout setting is used). The optional *source_address* parameter may be a tuple of a (host, port) to use as the source address the HTTP connection is made from.

For example, the following calls all create instances that connect to the server at the same host and port:

```
>>> h1 = httplib.HTTPConnection('www.cwi.nl')
>>> h2 = httplib.HTTPConnection('www.cwi.nl:80')
>>> h3 = httplib.HTTPConnection('www.cwi.nl', 80)
>>> h3 = httplib.HTTPConnection('www.cwi.nl', 80, timeout=10)
```

버전 2.0에 추가.

버전 2.6에서 변경: *timeout* was added.

버전 2.7에서 변경: *source_address* was added.

class `httplib.HTTPSConnection` (`host`[, `port`[, `key_file`[, `cert_file`[, `strict`[, `timeout`[, `source_address`[, `context`]]]]]])

A subclass of `HTTPConnection` that uses SSL for communication with secure servers. Default port is 443. If `context` is specified, it must be a `ssl.SSLContext` instance describing the various SSL options.

`key_file` and `cert_file` are deprecated, please use `ssl.SSLContext.load_cert_chain()` instead, or let `ssl.create_default_context()` select the system's trusted CA certificates for you.

Please read *Security considerations* for more information on best practices.

버전 2.0에 추가.

버전 2.6에서 변경: `timeout` was added.

버전 2.7에서 변경: `source_address` was added.

버전 2.7.9에서 변경: `context` was added.

This class now performs all the necessary certificate and hostname checks by default. To revert to the previous, unverified, behavior `ssl._create_unverified_context()` can be passed to the `context` parameter.

class `httplib.HTTPResponse` (`sock`, `debuglevel=0`, `strict=0`)

Class whose instances are returned upon successful connection. Not instantiated directly by user.

버전 2.0에 추가.

class `httplib.HTTPMessage`

An `HTTPMessage` instance is used to hold the headers from an HTTP response. It is implemented using the `mimetypes.Message` class and provides utility functions to deal with HTTP Headers. It is not directly instantiated by the users.

The following exceptions are raised as appropriate:

exception `httplib.HTTPException`

The base class of the other exceptions in this module. It is a subclass of `Exception`.

버전 2.0에 추가.

exception `httplib.NotConnected`

A subclass of `HTTPException`.

버전 2.0에 추가.

exception `httplib.InvalidURL`

A subclass of `HTTPException`, raised if a port is given and is either non-numeric or empty.

버전 2.3에 추가.

exception `httplib.UnknownProtocol`

A subclass of `HTTPException`.

버전 2.0에 추가.

exception `httplib.UnknownTransferEncoding`

A subclass of `HTTPException`.

버전 2.0에 추가.

exception `httplib.UnimplementedFileMode`

A subclass of `HTTPException`.

버전 2.0에 추가.

exception `httplib.IncompleteRead`

A subclass of `HTTPException`.

버전 2.0에 추가.

exception `httplib.ImproperConnectionState`

A subclass of `HTTPException`.

버전 2.0에 추가.

exception `httplib.CannotSendRequest`

A subclass of `ImproperConnectionState`.

버전 2.0에 추가.

exception `httplib.CannotSendHeader`

A subclass of `ImproperConnectionState`.

버전 2.0에 추가.

exception `httplib.ResponseNotReady`

A subclass of `ImproperConnectionState`.

버전 2.0에 추가.

exception `httplib.BadStatusLine`

A subclass of `HTTPException`. Raised if a server responds with a HTTP status code that we don't understand.

버전 2.0에 추가.

The constants defined in this module are:

`httplib.HTTP_PORT`

The default port for the HTTP protocol (always 80).

`httplib.HTTPS_PORT`

The default port for the HTTPS protocol (always 443).

and also the following constants for integer status codes:

Constant	Value	Definition
CONTINUE	100	HTTP/1.1, RFC 2616, Section 10.1.1
SWITCHING_PROTOCOLS	101	HTTP/1.1, RFC 2616, Section 10.1.2
PROCESSING	102	WEBDAV, RFC 2518, Section 10.1
OK	200	HTTP/1.1, RFC 2616, Section 10.2.1
CREATED	201	HTTP/1.1, RFC 2616, Section 10.2.2
ACCEPTED	202	HTTP/1.1, RFC 2616, Section 10.2.3
NON_AUTHORITATIVE_INFORMATION	203	HTTP/1.1, RFC 2616, Section 10.2.4
NO_CONTENT	204	HTTP/1.1, RFC 2616, Section 10.2.5
RESET_CONTENT	205	HTTP/1.1, RFC 2616, Section 10.2.6
PARTIAL_CONTENT	206	HTTP/1.1, RFC 2616, Section 10.2.7
MULTI_STATUS	207	WEBDAV RFC 2518, Section 10.2
IM_USED	226	Delta encoding in HTTP, RFC 3229, Section 10.4.1
MULTIPLE_CHOICES	300	HTTP/1.1, RFC 2616, Section 10.3.1
MOVED_PERMANENTLY	301	HTTP/1.1, RFC 2616, Section 10.3.2
FOUND	302	HTTP/1.1, RFC 2616, Section 10.3.3
SEE_OTHER	303	HTTP/1.1, RFC 2616, Section 10.3.4
NOT_MODIFIED	304	HTTP/1.1, RFC 2616, Section 10.3.5
USE_PROXY	305	HTTP/1.1, RFC 2616, Section 10.3.6
TEMPORARY_REDIRECT	307	HTTP/1.1, RFC 2616, Section 10.3.8
BAD_REQUEST	400	HTTP/1.1, RFC 2616, Section 10.4.1
UNAUTHORIZED	401	HTTP/1.1, RFC 2616, Section 10.4.2
PAYMENT_REQUIRED	402	HTTP/1.1, RFC 2616, Section 10.4.3

다음 페이지에 계속

표 1 – 이전 페이지에서 계속

Constant	Value	Definition
FORBIDDEN	403	HTTP/1.1, RFC 2616, Section 10.4.4
NOT_FOUND	404	HTTP/1.1, RFC 2616, Section 10.4.5
METHOD_NOT_ALLOWED	405	HTTP/1.1, RFC 2616, Section 10.4.6
NOT_ACCEPTABLE	406	HTTP/1.1, RFC 2616, Section 10.4.7
PROXY_AUTHENTICATION_REQUIRED	407	HTTP/1.1, RFC 2616, Section 10.4.8
REQUEST_TIMEOUT	408	HTTP/1.1, RFC 2616, Section 10.4.9
CONFLICT	409	HTTP/1.1, RFC 2616, Section 10.4.10
GONE	410	HTTP/1.1, RFC 2616, Section 10.4.11
LENGTH_REQUIRED	411	HTTP/1.1, RFC 2616, Section 10.4.12
PRECONDITION_FAILED	412	HTTP/1.1, RFC 2616, Section 10.4.13
REQUEST_ENTITY_TOO_LARGE	413	HTTP/1.1, RFC 2616, Section 10.4.14
REQUEST_URI_TOO_LONG	414	HTTP/1.1, RFC 2616, Section 10.4.15
UNSUPPORTED_MEDIA_TYPE	415	HTTP/1.1, RFC 2616, Section 10.4.16
REQUESTED_RANGE_NOT_SATISFIABLE	416	HTTP/1.1, RFC 2616, Section 10.4.17
EXPECTATION_FAILED	417	HTTP/1.1, RFC 2616, Section 10.4.18
UNPROCESSABLE_ENTITY	422	WEBDAV, RFC 2518, Section 10.3
LOCKED	423	WEBDAV RFC 2518, Section 10.4
FAILED_DEPENDENCY	424	WEBDAV, RFC 2518, Section 10.5
UPGRADE_REQUIRED	426	HTTP Upgrade to TLS, RFC 2817 , Section 6
INTERNAL_SERVER_ERROR	500	HTTP/1.1, RFC 2616, Section 10.5.1
NOT_IMPLEMENTED	501	HTTP/1.1, RFC 2616, Section 10.5.2
BAD_GATEWAY	502	HTTP/1.1 RFC 2616, Section 10.5.3
SERVICE_UNAVAILABLE	503	HTTP/1.1, RFC 2616, Section 10.5.4
GATEWAY_TIMEOUT	504	HTTP/1.1 RFC 2616, Section 10.5.5
HTTP_VERSION_NOT_SUPPORTED	505	HTTP/1.1, RFC 2616, Section 10.5.6
INSUFFICIENT_STORAGE	507	WEBDAV, RFC 2518, Section 10.6
NOT_EXTENDED	510	An HTTP Extension Framework, RFC 2774 , Section 7

httplib.responses

This dictionary maps the HTTP 1.1 status codes to the W3C names.

Example: `httplib.responses[httplib.NOT_FOUND]` is 'Not Found'.

버전 2.5에 추가.

20.7.1 HTTPConnection Objects

HTTPConnection instances have the following methods:

HTTPConnection.request (*method*, *url* [, *body* [, *headers*]])

This will send a request to the server using the HTTP request method *method* and the selector *url*. If the *body* argument is present, it should be a string of data to send after the headers are finished. Alternatively, it may be an open file object, in which case the contents of the file is sent; this file object should support `fileno()` and `read()` methods. The *headers* argument should be a mapping of extra HTTP headers to send with the request.

If one is not provided in *headers*, a `Content-Length` header is added automatically for all methods if the length of the body can be determined, either from the length of the `str` representation, or from the reported size of the file on disk. If *body* is `None` the header is not set except for methods that expect a body (`PUT`, `POST`, and `PATCH`) in which case it is set to 0.

버전 2.6에서 변경: *body* can be a file object.

`HTTPConnection.getresponse()`

Should be called after a request is sent to get the response from the server. Returns an *HTTPResponse* instance.

참고: Note that you must have read the whole response before you can send a new request to the server.

`HTTPConnection.set_debuglevel(level)`

Set the debugging level (the amount of debugging output printed). The default debug level is 0, meaning no debugging output is printed.

`HTTPConnection.set_tunnel(host, port=None, headers=None)`

Set the host and the port for HTTP Connect Tunnelling. Normally used when it is required to do HTTPS Connection through a proxy server.

The headers argument should be a mapping of extra HTTP headers to send with the CONNECT request.

버전 2.7에 추가.

`HTTPConnection.connect()`

Connect to the server specified when the object was created.

`HTTPConnection.close()`

Close the connection to the server.

As an alternative to using the `request()` method described above, you can also send your request step by step, by using the four functions below.

`HTTPConnection.putrequest(request, selector[, skip_host[, skip_accept_encoding]])`

This should be the first call after the connection to the server has been made. It sends a line to the server consisting of the *request* string, the *selector* string, and the HTTP version (HTTP/1.1). To disable automatic sending of Host: or Accept-Encoding: headers (for example to accept additional content encodings), specify *skip_host* or *skip_accept_encoding* with non-False values.

버전 2.4에서 변경: *skip_accept_encoding* argument added.

`HTTPConnection.putheader(header, argument[, ...])`

Send an RFC 822-style header to the server. It sends a line to the server consisting of the header, a colon and a space, and the first argument. If more arguments are given, continuation lines are sent, each consisting of a tab and an argument.

`HTTPConnection.endheaders(message_body=None)`

Send a blank line to the server, signalling the end of the headers. The optional *message_body* argument can be used to pass a message body associated with the request. The message body will be sent in the same packet as the message headers if it is string, otherwise it is sent in a separate packet.

버전 2.7에서 변경: *message_body* was added.

`HTTPConnection.send(data)`

Send data to the server. This should be used directly only after the *endheaders()* method has been called and before *getresponse()* is called.

20.7.2 HTTPResponse Objects

HTTPResponse instances have the following methods and attributes:

`HTTPResponse.read([amt])`

Reads and returns the response body, or up to the next *amt* bytes.

`HTTPResponse.getheader(name[, default])`

Get the contents of the header *name*, or *default* if there is no matching header.

`HTTPResponse.getheaders()`

Return a list of (header, value) tuples.

버전 2.4에 추가.

`HTTPResponse.fileno()`

Returns the *fileno* of the underlying socket.

`HTTPResponse.msg`

A *mimetools.Message* instance containing the response headers.

`HTTPResponse.version`

HTTP protocol version used by server. 10 for HTTP/1.0, 11 for HTTP/1.1.

`HTTPResponse.status`

Status code returned by server.

`HTTPResponse.reason`

Reason phrase returned by server.

20.7.3 Examples

Here is an example session that uses the GET method:

```
>>> import httplib
>>> conn = httplib.HTTPSConnection("www.python.org")
>>> conn.request("GET", "/")
>>> r1 = conn.getresponse()
>>> print r1.status, r1.reason
200 OK
>>> data1 = r1.read()
>>> conn.request("GET", "/")
>>> r2 = conn.getresponse()
>>> print r2.status, r2.reason
404 Not Found
>>> data2 = r2.read()
>>> conn.close()
```

Here is an example session that uses the HEAD method. Note that the HEAD method never returns any data.

```
>>> import httplib
>>> conn = httplib.HTTPSConnection("www.python.org")
>>> conn.request("HEAD", "/")
>>> res = conn.getresponse()
>>> print res.status, res.reason
200 OK
>>> data = res.read()
>>> print len(data)
0
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> data == ''
True
```

Here is an example session that shows how to POST requests:

```
>>> import urllib, urllib
>>> params = urllib.urlencode({'@number': 12524, '@type': 'issue', '@action': 'show'})
>>> headers = {"Content-type": "application/x-www-form-urlencoded",
...           "Accept": "text/plain"}
>>> conn = urllib.HTTPConnection("bugs.python.org")
>>> conn.request("POST", "", params, headers)
>>> response = conn.getresponse()
>>> print response.status, response.reason
302 Found
>>> data = response.read()
>>> data
'Redirecting to <a href="http://bugs.python.org/issue12524">http://bugs.python.org/
↪issue12524</a>'
>>> conn.close()
```

Client side HTTP PUT requests are very similar to POST requests. The difference lies only the server side where HTTP server will allow resources to be created via PUT request. Here is an example session that shows how to do PUT request using urllib:

```
>>> # This creates an HTTP message
>>> # with the content of BODY as the enclosed representation
>>> # for the resource http://localhost:8080/foobar
...
>>> import urllib
>>> BODY = "***filecontents***"
>>> conn = urllib.HTTPConnection("localhost", 8080)
>>> conn.request("PUT", "/file", BODY)
>>> response = conn.getresponse()
>>> print response.status, response.reason
200, OK
```

20.8 ftplib — FTP protocol client

Source code: [Lib/ftplib.py](#)

This module defines the class *FTP* and a few related items. The *FTP* class implements the client side of the FTP protocol. You can use this to write Python programs that perform a variety of automated FTP jobs, such as mirroring other FTP servers. It is also used by the module *urllib* to handle URLs that use FTP. For more information on FTP (File Transfer Protocol), see Internet [RFC 959](#).

Here's a sample session using the *ftplib* module:

```
>>> from ftplib import FTP
>>> ftp = FTP('ftp.debian.org')      # connect to host, default port
>>> ftp.login()                      # user anonymous, passwd anonymous@
'230 Login successful.'
>>> ftp.cwd('debian')                # change into "debian" directory
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

>>> ftp.retrlines('LIST')           # list directory contents
-rw-rw-r-- 1 1176 1176 1063 Jun 15 10:18 README
...
drwxr-sr-x 5 1176 1176 4096 Dec 19 2000 pool
drwxr-sr-x 4 1176 1176 4096 Nov 17 2008 project
drwxr-xr-x 3 1176 1176 4096 Oct 10 2012 tools
'226 Directory send OK.'
>>> ftp.retrbinary('RETR README', open('README', 'wb').write)
'226 Transfer complete.'
>>> ftp.quit()

```

The module defines the following items:

class `ftplib.FTP([host[, user[, passwd[, acct[, timeout]]]])`

Return a new instance of the `FTP` class. When `host` is given, the method call `connect(host)` is made. When `user` is given, additionally the method call `login(user, passwd, acct)` is made (where `passwd` and `acct` default to the empty string when not given). The optional `timeout` parameter specifies a timeout in seconds for blocking operations like the connection attempt (if is not specified, the global default timeout setting will be used).

버전 2.6에서 변경: `timeout` was added.

class `ftplib.FTP_TLS([host[, user[, passwd[, acct[, keyfile[, certfile[, context[, timeout]]]]]])`

A `FTP` subclass which adds TLS support to FTP as described in [RFC 4217](#). Connect as usual to port 21 implicitly securing the FTP control connection before authenticating. Securing the data connection requires the user to explicitly ask for it by calling the `prot_p()` method. `context` is a `ssl.SSLContext` object which allows bundling SSL configuration options, certificates and private keys into a single (potentially long-lived) structure. Please read [Security considerations](#) for best practices.

`keyfile` and `certfile` are a legacy alternative to `context` – they can point to PEM-formatted private key and certificate chain files (respectively) for the SSL connection.

버전 2.7에 추가.

버전 2.7.10에서 변경: The `context` parameter was added.

Here's a sample session using the `FTP_TLS` class:

```

>>> from ftplib import FTP_TLS
>>> ftps = FTP_TLS('ftp.python.org')
>>> ftps.login()           # login anonymously before securing control channel
>>> ftps.prot_p()         # switch to secure data connection
>>> ftps.retrlines('LIST') # list directory content securely
total 9
drwxr-xr-x 8 root wheel 1024 Jan 3 1994 .
drwxr-xr-x 8 root wheel 1024 Jan 3 1994 ..
drwxr-xr-x 2 root wheel 1024 Jan 3 1994 bin
drwxr-xr-x 2 root wheel 1024 Jan 3 1994 etc
d-wxrwxr-x 2 ftp wheel 1024 Sep 5 13:43 incoming
drwxr-xr-x 2 root wheel 1024 Nov 17 1993 lib
drwxr-xr-x 6 1094 wheel 1024 Sep 13 19:07 pub
drwxr-xr-x 3 root wheel 1024 Jan 3 1994 usr
-rw-r--r-- 1 root root 312 Aug 1 1994 welcome.msg
'226 Transfer complete.'
>>> ftps.quit()
>>>

```

exception `ftplib.error_reply`

Exception raised when an unexpected reply is received from the server.

exception `ftplib.error_temp`

Exception raised when an error code signifying a temporary error (response codes in the range 400–499) is received.

exception `ftplib.error_perm`

Exception raised when an error code signifying a permanent error (response codes in the range 500–599) is received.

exception `ftplib.error_proto`

Exception raised when a reply is received from the server that does not fit the response specifications of the File Transfer Protocol, i.e. begin with a digit in the range 1–5.

ftplib.all_errors

The set of all exceptions (as a tuple) that methods of `FTP` instances may raise as a result of problems with the FTP connection (as opposed to programming errors made by the caller). This set includes the four exceptions listed above as well as `socket.error` and `IOError`.

더 보기:

Module `netrc` Parser for the `.netrc` file format. The file `.netrc` is typically used by FTP clients to load user authentication information before prompting the user.

The file `Tools/scripts/ftpmirror.py` in the Python source distribution is a script that can mirror FTP sites, or portions thereof, using the `ftplib` module. It can be used as an extended example that applies this module.

20.8.1 FTP Objects

Several methods are available in two flavors: one for handling text files and another for binary files. These are named for the command which is used followed by `lines` for the text version or `binary` for the binary version.

`FTP` instances have the following methods:

FTP.set_debuglevel (*level*)

Set the instance's debugging level. This controls the amount of debugging output printed. The default, 0, produces no debugging output. A value of 1 produces a moderate amount of debugging output, generally a single line per request. A value of 2 or higher produces the maximum amount of debugging output, logging each line sent and received on the control connection.

FTP.connect (*host* [, *port* [, *timeout*]])

Connect to the given host and port. The default port number is 21, as specified by the FTP protocol specification. It is rarely needed to specify a different port number. This function should be called only once for each instance; it should not be called at all if a host was given when the instance was created. All other methods can only be used after a connection has been made.

The optional *timeout* parameter specifies a timeout in seconds for the connection attempt. If no *timeout* is passed, the global default timeout setting will be used.

버전 2.6에서 변경: *timeout* was added.

FTP.getwelcome ()

Return the welcome message sent by the server in reply to the initial connection. (This message sometimes contains disclaimers or help information that may be relevant to the user.)

FTP.login ([*user* [, *passwd* [, *acct*]]])

Log in as the given *user*. The *passwd* and *acct* parameters are optional and default to the empty string. If no *user* is specified, it defaults to 'anonymous'. If *user* is 'anonymous', the default *passwd* is 'anonymous@'. This function should be called only once for each instance, after a connection has been established; it should not be called at all if a host and user were given when the instance was created. Most FTP commands are only allowed after the client has logged in. The *acct* parameter supplies 《accounting information》; few systems implement this.

FTP.abort ()

Abort a file transfer that is in progress. Using this does not always work, but it's worth a try.

FTP.**sendcmd** (*command*)

Send a simple command string to the server and return the response string.

FTP.**voidcmd** (*command*)

Send a simple command string to the server and handle the response. Return nothing if a response code corresponding to success (codes in the range 200–299) is received. Raise *error_reply* otherwise.

FTP.**retrbinary** (*command*, *callback*[, *maxblocksize*[, *rest*]])

Retrieve a file in binary transfer mode. *command* should be an appropriate RETR command: 'RETR *filename*'. The *callback* function is called for each block of data received, with a single string argument giving the data block. The optional *maxblocksize* argument specifies the maximum chunk size to read on the low-level socket object created to do the actual transfer (which will also be the largest size of the data blocks passed to *callback*). A reasonable default is chosen. *rest* means the same thing as in the *transfercmd()* method.

FTP.**retrlines** (*command*[, *callback*])

Retrieve a file or directory listing in ASCII transfer mode. *command* should be an appropriate RETR command (see *retrbinary()*) or a command such as LIST, NLST or MLSD (usually just the string 'LIST'). LIST retrieves a list of files and information about those files. NLST retrieves a list of file names. On some servers, MLSD retrieves a machine readable list of files and information about those files. The *callback* function is called for each line with a string argument containing the line with the trailing CRLF stripped. The default *callback* prints the line to *sys.stdout*.

FTP.**set_pasv** (*val*)

Enable «passive» mode if *val* is true, otherwise disable passive mode. (In Python 2.0 and before, passive mode was off by default; in Python 2.1 and later, it is on by default.)

FTP.**storbinary** (*command*, *fp*[, *blocksize*, *callback*, *rest*])

Store a file in binary transfer mode. *command* should be an appropriate STOR command: "STOR *filename*". *fp* is an open file object which is read until EOF using its *read()* method in blocks of size *blocksize* to provide the data to be stored. The *blocksize* argument defaults to 8192. *callback* is an optional single parameter callable that is called on each block of data after it is sent. *rest* means the same thing as in the *transfercmd()* method.

버전 2.1에서 변경: default for *blocksize* added.

버전 2.6에서 변경: *callback* parameter added.

버전 2.7에서 변경: *rest* parameter added.

FTP.**storlines** (*command*, *fp*[, *callback*])

Store a file in ASCII transfer mode. *command* should be an appropriate STOR command (see *storbinary()*). Lines are read until EOF from the open file object *fp* using its *readline()* method to provide the data to be stored. *callback* is an optional single parameter callable that is called on each line after it is sent.

버전 2.6에서 변경: *callback* parameter added.

FTP.**transfercmd** (*cmd*[, *rest*])

Initiate a transfer over the data connection. If the transfer is active, send an EPRT or PORT command and the transfer command specified by *cmd*, and accept the connection. If the server is passive, send an EPSV or PASV command, connect to it, and start the transfer command. Either way, return the socket for the connection.

If optional *rest* is given, a REST command is sent to the server, passing *rest* as an argument. *rest* is usually a byte offset into the requested file, telling the server to restart sending the file's bytes at the requested offset, skipping over the initial bytes. Note however that RFC 959 requires only that *rest* be a string containing characters in the printable range from ASCII code 33 to ASCII code 126. The *transfercmd()* method, therefore, converts *rest* to a string, but no check is performed on the string's contents. If the server does not recognize the REST command, an *error_reply* exception will be raised. If this happens, simply call *transfercmd()* without a *rest* argument.

FTP.**nttransfercmd** (*cmd*[, *rest*])

Like *transfercmd()*, but returns a tuple of the data connection and the expected size of the data. If the

expected size could not be computed, `None` will be returned as the expected size. `cmd` and `rest` means the same thing as in `transfercmd()`.

`FTP.nlst(argument[, ...])`

Return a list of file names as returned by the NLST command. The optional *argument* is a directory to list (default is the current server directory). Multiple arguments can be used to pass non-standard options to the NLST command.

`FTP.dir(argument[, ...])`

Produce a directory listing as returned by the LIST command, printing it to standard output. The optional *argument* is a directory to list (default is the current server directory). Multiple arguments can be used to pass non-standard options to the LIST command. If the last argument is a function, it is used as a *callback* function as for `retrlines()`; the default prints to `sys.stdout`. This method returns `None`.

`FTP.rename(fromname, toname)`

Rename file *fromname* on the server to *toname*.

`FTP.delete(filename)`

Remove the file named *filename* from the server. If successful, returns the text of the response, otherwise raises `error_perm` on permission errors or `error_reply` on other errors.

`FTP.cwd(pathname)`

Set the current directory on the server.

`FTP.mkd(pathname)`

Create a new directory on the server.

`FTP.pwd()`

Return the pathname of the current directory on the server.

`FTP.rmd(dirname)`

Remove the directory named *dirname* on the server.

`FTP.size(filename)`

Request the size of the file named *filename* on the server. On success, the size of the file is returned as an integer, otherwise `None` is returned. Note that the SIZE command is not standardized, but is supported by many common server implementations.

`FTP.quit()`

Send a QUIT command to the server and close the connection. This is the «polite» way to close a connection, but it may raise an exception if the server responds with an error to the QUIT command. This implies a call to the `close()` method which renders the `FTP` instance useless for subsequent calls (see below).

`FTP.close()`

Close the connection unilaterally. This should not be applied to an already closed connection such as after a successful call to `quit()`. After this call the `FTP` instance should not be used any more (after a call to `close()` or `quit()` you cannot reopen the connection by issuing another `login()` method).

20.8.2 FTP_TLS Objects

`FTP_TLS` class inherits from `FTP`, defining these additional objects:

`FTP_TLS.ssl_version`

The SSL version to use (defaults to `ssl.PROTOCOL_SSLv23`).

`FTP_TLS.auth()`

Set up secure control connection by using TLS or SSL, depending on what specified in `ssl_version()` attribute.

`FTP_TLS.prot_p()`

Set up secure data connection.

`FTP_TLS.prot_c()`
Set up clear text data connection.

20.9 poplib — POP3 protocol client

Source code: [Lib/poplib.py](#)

This module defines a class, `POP3`, which encapsulates a connection to a POP3 server and implements the protocol as defined in [RFC 1725](#). The `POP3` class supports both the minimal and optional command sets. Additionally, this module provides a class `POP3_SSL`, which provides support for connecting to POP3 servers that use SSL as an underlying protocol layer.

Note that POP3, though widely supported, is obsolescent. The implementation quality of POP3 servers varies widely, and too many are quite poor. If your mailserver supports IMAP, you would be better off using the `imaplib.IMAP4` class, as IMAP servers tend to be better implemented.

The `poplib` module provides two classes:

class `poplib.POP3` (`host`[, `port`[, `timeout`]])

This class implements the actual POP3 protocol. The connection is created when the instance is initialized. If `port` is omitted, the standard POP3 port (110) is used. The optional `timeout` parameter specifies a timeout in seconds for the connection attempt (if not specified, the global default timeout setting will be used).

버전 2.6에서 변경: `timeout` was added.

class `poplib.POP3_SSL` (`host`[, `port`[, `keyfile`[, `certfile`]]])

This is a subclass of `POP3` that connects to the server over an SSL encrypted socket. If `port` is not specified, 995, the standard POP3-over-SSL port is used. `keyfile` and `certfile` are also optional - they can contain a PEM formatted private key and certificate chain file for the SSL connection.

버전 2.4에 추가.

One exception is defined as an attribute of the `poplib` module:

exception `poplib.error_proto`

Exception raised on any errors from this module (errors from `socket` module are not caught). The reason for the exception is passed to the constructor as a string.

더 보기:

Module `imaplib` The standard Python IMAP module.

Frequently Asked Questions About Fetchmail The FAQ for the `fetchmail` POP/IMAP client collects information on POP3 server variations and RFC noncompliance that may be useful if you need to write an application based on the POP protocol.

20.9.1 POP3 Objects

All POP3 commands are represented by methods of the same name, in lower-case; most return the response text sent by the server.

An `POP3` instance has the following methods:

`POP3.set_debuglevel` (`level`)

Set the instance's debugging level. This controls the amount of debugging output printed. The default, 0, produces no debugging output. A value of 1 produces a moderate amount of debugging output, generally a single line per

request. A value of 2 or higher produces the maximum amount of debugging output, logging each line sent and received on the control connection.

POP3.**getwelcome**()

Returns the greeting string sent by the POP3 server.

POP3.**user**(*username*)

Send user command, response should indicate that a password is required.

POP3.**pass_**(*password*)

Send password, response includes message count and mailbox size. Note: the mailbox on the server is locked until `quit()` is called.

POP3.**apop**(*user*, *secret*)

Use the more secure APOP authentication to log into the POP3 server.

POP3.**rpop**(*user*)

Use RPOP authentication (similar to UNIX r-commands) to log into POP3 server.

POP3.**stat**()

Get mailbox status. The result is a tuple of 2 integers: (message count, mailbox size).

POP3.**list**(*[which]*)

Request message list, result is in the form (response, ['mesg_num octets', ...], octets). If *which* is set, it is the message to list.

POP3.**retr**(*which*)

Retrieve whole message number *which*, and set its seen flag. Result is in form (response, ['line', ...], octets).

POP3.**dele**(*which*)

Flag message number *which* for deletion. On most servers deletions are not actually performed until QUIT (the major exception is Eudora QPOP, which deliberately violates the RFCs by doing pending deletes on any disconnect).

POP3.**rset**()

Remove any deletion marks for the mailbox.

POP3.**noop**()

Do nothing. Might be used as a keep-alive.

POP3.**quit**()

Signoff: commit changes, unlock mailbox, drop connection.

POP3.**top**(*which*, *howmuch*)

Retrieves the message header plus *howmuch* lines of the message after the header of message number *which*. Result is in form (response, ['line', ...], octets).

The POP3 TOP command this method uses, unlike the RETR command, doesn't set the message's seen flag; unfortunately, TOP is poorly specified in the RFCs and is frequently broken in off-brand servers. Test this method by hand against the POP3 servers you will use before trusting it.

POP3.**uidl**(*[which]*)

Return message digest (unique id) list. If *which* is specified, result contains the unique id for that message in the form 'response mesgnum uid, otherwise result is list (response, ['mesgnum uid', ...], octets).

Instances of `POP3_SSL` have no additional methods. The interface of this subclass is identical to its parent.

20.9.2 POP3 Example

Here is a minimal example (without error checking) that opens a mailbox and retrieves and prints all messages:

```
import getpass, poplib

M = poplib.POP3('localhost')
M.user(getpass.getuser())
M.pass_(getpass.getpass())
numMessages = len(M.list()[1])
for i in range(numMessages):
    for j in M.retr(i+1)[1]:
        print j
```

At the end of the module, there is a test section that contains a more extensive example of usage.

20.10 imaplib — IMAP4 protocol client

Source code: [Lib/imaplib.py](#)

This module defines three classes, *IMAP4*, *IMAP4_SSL* and *IMAP4_stream*, which encapsulate a connection to an IMAP4 server and implement a large subset of the IMAP4rev1 client protocol as defined in [RFC 2060](#). It is backward compatible with IMAP4 ([RFC 1730](#)) servers, but note that the STATUS command is not supported in IMAP4.

Three classes are provided by the *imaplib* module, *IMAP4* is the base class:

class *imaplib.IMAP4*([*host*[, *port*]])

This class implements the actual IMAP4 protocol. The connection is created and protocol version (IMAP4 or IMAP4rev1) is determined when the instance is initialized. If *host* is not specified, '' (the local host) is used. If *port* is omitted, the standard IMAP4 port (143) is used.

Three exceptions are defined as attributes of the *IMAP4* class:

exception *IMAP4.error*

Exception raised on any errors. The reason for the exception is passed to the constructor as a string.

exception *IMAP4.abort*

IMAP4 server errors cause this exception to be raised. This is a sub-class of *IMAP4.error*. Note that closing the instance and instantiating a new one will usually allow recovery from this exception.

exception *IMAP4.readonly*

This exception is raised when a writable mailbox has its status changed by the server. This is a sub-class of *IMAP4.error*. Some other client now has write permission, and the mailbox will need to be re-opened to re-obtain write permission.

There's also a subclass for secure connections:

class *imaplib.IMAP4_SSL*([*host*[, *port*[, *keyfile*[, *certfile*]]]])

This is a subclass derived from *IMAP4* that connects over an SSL encrypted socket (to use this class you need a socket module that was compiled with SSL support). If *host* is not specified, '' (the local host) is used. If *port* is omitted, the standard IMAP4-over-SSL port (993) is used. *keyfile* and *certfile* are also optional - they can contain a PEM formatted private key and certificate chain file for the SSL connection.

The second subclass allows for connections created by a child process:

class `imaplib.IMAP4_stream` (*command*)

This is a subclass derived from `IMAP4` that connects to the `stdin/stdout` file descriptors created by passing *command* to `os.popen2()`.

버전 2.3에 추가.

The following utility functions are defined:

`imaplib.Internaldate2tuple` (*datestr*)

Parse an IMAP4 INTERNALDATE string and return corresponding local time. The return value is a `time.struct_time` instance or `None` if the string has wrong format.

`imaplib.Int2AP` (*num*)

Converts an integer into a string representation using characters from the set [A .. P].

`imaplib.ParseFlags` (*flagstr*)

Converts an IMAP4 FLAGS response to a tuple of individual flags.

`imaplib.Time2Internaldate` (*date_time*)

Convert *date_time* to an IMAP4 INTERNALDATE representation. The return value is a string in the form: "DD-Mmm-YYYY HH:MM:SS +HHMM" (including double-quotes). The *date_time* argument can be a number (int or float) representing seconds since epoch (as returned by `time.time()`), a 9-tuple representing local time (as returned by `time.localtime()`), or a double-quoted string. In the last case, it is assumed to already be in the correct format.

Note that IMAP4 message numbers change as the mailbox changes; in particular, after an EXPUNGE command performs deletions the remaining messages are renumbered. So it is highly advisable to use UIDs instead, with the UID command.

At the end of the module, there is a test section that contains a more extensive example of usage.

더 보기:

Documents describing the protocol, and sources and binaries for servers implementing it, can all be found at the University of Washington's *IMAP Information Center* (<https://www.washington.edu/imap/>).

20.10.1 IMAP4 Objects

All IMAP4rev1 commands are represented by methods of the same name, either upper-case or lower-case.

All arguments to commands are converted to strings, except for `AUTHENTICATE`, and the last argument to `APPEND` which is passed as an IMAP4 literal. If necessary (the string contains IMAP4 protocol-sensitive characters and isn't enclosed with either parentheses or double quotes) each string is quoted. However, the *password* argument to the `LOGIN` command is always quoted. If you want to avoid having an argument string quoted (eg: the *flags* argument to `STORE`) then enclose the string in parentheses (eg: `r'(\Deleted)'`).

Each command returns a tuple: (*type*, [*data*, ...]) where *type* is usually 'OK' or 'NO', and *data* is either the text from the command response, or mandated results from the command. Each *data* is either a string, or a tuple. If a tuple, then the first part is the header of the response, and the second part contains the data (ie: `<literal>` value).

The *message_set* options to commands below is a string specifying one or more messages to be acted upon. It may be a simple message number ('1'), a range of message numbers ('2:4'), or a group of non-contiguous ranges separated by commas ('1:3, 6:9'). A range can contain an asterisk to indicate an infinite upper bound ('3:*').

An `IMAP4` instance has the following methods:

`IMAP4.append` (*mailbox*, *flags*, *date_time*, *message*)

Append *message* to named mailbox.

`IMAP4.authenticate` (*mechanism*, *authobject*)

Authenticate command — requires response processing.

mechanism specifies which authentication mechanism is to be used - it should appear in the instance variable *capabilities* in the form `AUTH=mechanism`.

authobject must be a callable object:

```
data = authobject(response)
```

It will be called to process server continuation responses. It should return *data* that will be encoded and sent to server. It should return `None` if the client abort response * should be sent instead.

`IMAP4.check()`

Checkpoint mailbox on server.

`IMAP4.close()`

Close currently selected mailbox. Deleted messages are removed from writable mailbox. This is the recommended command before `LOGOUT`.

`IMAP4.copy(message_set, new_mailbox)`

Copy *message_set* messages onto end of *new_mailbox*.

`IMAP4.create(mailbox)`

Create new mailbox named *mailbox*.

`IMAP4.delete(mailbox)`

Delete old mailbox named *mailbox*.

`IMAP4.deleteacl(mailbox, who)`

Delete the ACLs (remove any rights) set for *who* on mailbox.

버전 2.4에 추가.

`IMAP4.expunge()`

Permanently remove deleted items from selected mailbox. Generates an `EXPUNGE` response for each deleted message. Returned data contains a list of `EXPUNGE` message numbers in order received.

`IMAP4.fetch(message_set, message_parts)`

Fetch (parts of) messages. *message_parts* should be a string of message part names enclosed within parentheses, eg: " (UID BODY[TEXT]) ". Returned data are tuples of message part envelope and data.

`IMAP4.getacl(mailbox)`

Get the ACLs for *mailbox*. The method is non-standard, but is supported by the `Cyrus` server.

`IMAP4.getannotation(mailbox, entry, attribute)`

Retrieve the specified `ANNOTATIONS` for *mailbox*. The method is non-standard, but is supported by the `Cyrus` server.

버전 2.5에 추가.

`IMAP4.getquota(root)`

Get the quota *root*'s resource usage and limits. This method is part of the `IMAP4 QUOTA` extension defined in `rfc2087`.

버전 2.3에 추가.

`IMAP4.getquotaroot(mailbox)`

Get the list of quota roots for the named *mailbox*. This method is part of the `IMAP4 QUOTA` extension defined in `rfc2087`.

버전 2.3에 추가.

`IMAP4.list([directory[, pattern]])`

List mailbox names in *directory* matching *pattern*. *directory* defaults to the top-level mail folder, and *pattern* defaults to match anything. Returned data contains a list of `LIST` responses.

`IMAP4.login(user, password)`

Identify the client using a plaintext password. The *password* will be quoted.

`IMAP4.login_cram_md5(user, password)`

Force use of CRAM-MD5 authentication when identifying the client to protect the password. Will only work if the server CAPABILITY response includes the phrase AUTH=CRAM-MD5.

버전 2.3에 추가.

`IMAP4.logout()`

Shutdown connection to server. Returns server BYE response.

`IMAP4.lsub([directory[, pattern]])`

List subscribed mailbox names in directory matching pattern. *directory* defaults to the top level directory and *pattern* defaults to match any mailbox. Returned data are tuples of message part envelope and data.

`IMAP4.myrights(mailbox)`

Show my ACLs for a mailbox (i.e. the rights that I have on mailbox).

버전 2.4에 추가.

`IMAP4.namespace()`

Returns IMAP namespaces as defined in RFC2342.

버전 2.3에 추가.

`IMAP4.noop()`

Send NOOP to server.

`IMAP4.open(host, port)`

Opens socket to *port* at *host*. This method is implicitly called by the *IMAP4* constructor. The connection objects established by this method will be used in the *IMAP4.read()*, *IMAP4.readline()*, *IMAP4.send()*, and *IMAP4.shutdown()* methods. You may override this method.

`IMAP4.partial(message_num, message_part, start, length)`

Fetch truncated part of a message. Returned data is a tuple of message part envelope and data.

`IMAP4.proxyauth(user)`

Assume authentication as *user*. Allows an authorised administrator to proxy into any user's mailbox.

버전 2.3에 추가.

`IMAP4.read(size)`

Reads *size* bytes from the remote server. You may override this method.

`IMAP4.readline()`

Reads one line from the remote server. You may override this method.

`IMAP4.recent()`

Prompt server for an update. Returned data is `None` if no new messages, else value of RECENT response.

`IMAP4.rename(oldmailbox, newmailbox)`

Rename mailbox named *oldmailbox* to *newmailbox*.

`IMAP4.response(code)`

Return data for response *code* if received, or `None`. Returns the given code, instead of the usual type.

`IMAP4.search(charset, criterion[, ...])`

Search mailbox for matching messages. *charset* may be `None`, in which case no CHARSET will be specified in the request to the server. The IMAP protocol requires that at least one criterion be specified; an exception will be raised when the server returns an error.

Example:

```
# M is a connected IMAP4 instance...
typ, msgnums = M.search(None, 'FROM', '"LDJ"')

# or:
typ, msgnums = M.search(None, '(FROM "LDJ")')
```

IMAP4.select ([*mailbox* [, *readonly*]])

Select a mailbox. Returned data is the count of messages in *mailbox* (EXISTS response). The default *mailbox* is 'INBOX'. If the *readonly* flag is set, modifications to the mailbox are not allowed.

IMAP4.send (*data*)

Sends data to the remote server. You may override this method.

IMAP4.setacl (*mailbox*, *who*, *what*)

Set an ACL for *mailbox*. The method is non-standard, but is supported by the Cyrus server.

IMAP4.setannotation (*mailbox*, *entry*, *attribute* [, ...])

Set ANNOTATIONS for *mailbox*. The method is non-standard, but is supported by the Cyrus server.

버전 2.5에 추가.

IMAP4.setquota (*root*, *limits*)

Set the quota *root*'s resource *limits*. This method is part of the IMAP4 QUOTA extension defined in rfc2087.

버전 2.3에 추가.

IMAP4.shutdown ()

Close connection established in *open*. This method is implicitly called by *IMAP4.logout* (). You may override this method.

IMAP4.socket ()

Returns socket instance used to connect to server.

IMAP4.sort (*sort_criteria*, *charset*, *search_criterion* [, ...])

The *sort* command is a variant of *search* with sorting semantics for the results. Returned data contains a space separated list of matching message numbers.

Sort has two arguments before the *search_criterion* argument(s); a parenthesized list of *sort_criteria*, and the searching *charset*. Note that unlike *search*, the searching *charset* argument is mandatory. There is also a *uid sort* command which corresponds to *sort* the way that *uid search* corresponds to *search*. The *sort* command first searches the mailbox for messages that match the given searching criteria using the *charset* argument for the interpretation of strings in the searching criteria. It then returns the numbers of matching messages.

This is an IMAP4rev1 extension command.

IMAP4.status (*mailbox*, *names*)

Request named status conditions for *mailbox*.

IMAP4.store (*message_set*, *command*, *flag_list*)

Alters flag dispositions for messages in mailbox. *command* is specified by section 6.4.6 of **RFC 2060** as being one of «FLAGS», «+FLAGS», or «-FLAGS», optionally with a suffix of «.SILENT».

For example, to set the delete flag on all messages:

```
typ, data = M.search(None, 'ALL')
for num in data[0].split():
    M.store(num, '+FLAGS', '\\Deleted')
M.expunge()
```

IMAP4.subscribe (*mailbox*)

Subscribe to new mailbox.

`IMAP4.thread` (*threading_algorithm*, *charset*, *search_criterion*[, ...])

The `thread` command is a variant of `search` with threading semantics for the results. Returned data contains a space separated list of thread members.

Thread members consist of zero or more messages numbers, delimited by spaces, indicating successive parent and child.

Thread has two arguments before the *search_criterion* argument(s); a *threading_algorithm*, and the searching *charset*. Note that unlike `search`, the searching *charset* argument is mandatory. There is also a `uid thread` command which corresponds to `thread` the way that `uid search` corresponds to `search`. The `thread` command first searches the mailbox for messages that match the given searching criteria using the *charset* argument for the interpretation of strings in the searching criteria. It then returns the matching messages threaded according to the specified threading algorithm.

This is an IMAP4rev1 extension command.

버전 2.4에 추가.

`IMAP4.uid` (*command*, *arg*[, ...])

Execute command args with messages identified by UID, rather than message number. Returns response appropriate to command. At least one argument must be supplied; if none are provided, the server will return an error and an exception will be raised.

`IMAP4.unsubscribe` (*mailbox*)

Unsubscribe from old mailbox.

`IMAP4.xatom` (*name*[, *arg*[, ...]])

Allow simple extension commands notified by server in CAPABILITY response.

Instances of `IMAP4_SSL` have just one additional method:

`IMAP4_SSL.ssl` ()

Returns `SSLObject` instance used for the secure connection with the server.

The following attributes are defined on instances of `IMAP4`:

`IMAP4.PROTOCOL_VERSION`

The most recent supported protocol in the CAPABILITY response from the server.

`IMAP4.debug`

Integer value to control debugging output. The initialize value is taken from the module variable `Debug`. Values greater than three trace each command.

20.10.2 IMAP4 Example

Here is a minimal example (without error checking) that opens a mailbox and retrieves and prints all messages:

```
import getpass, imaplib

M = imaplib.IMAP4()
M.login(getpass.getuser(), getpass.getpass())
M.select()
typ, data = M.search(None, 'ALL')
for num in data[0].split():
    typ, data = M.fetch(num, '(RFC822)')
    print 'Message %s\n%s\n' % (num, data[0][1])
M.close()
M.logout()
```

20.11 nntplib — NNTP protocol client

Source code: [Lib/nntplib.py](#)

This module defines the class `NNTP` which implements the client side of the NNTP protocol. It can be used to implement a news reader or poster, or automated news processors. For more information on NNTP (Network News Transfer Protocol), see Internet [RFC 977](#).

Here are two small examples of how it can be used. To list some statistics about a newsgroup and print the subjects of the last 10 articles:

```
>>> s = NNTP('news.gmane.org')
>>> resp, count, first, last, name = s.group('gmane.comp.python.committers')
>>> print 'Group', name, 'has', count, 'articles, range', first, 'to', last
Group gmane.comp.python.committers has 1071 articles, range 1 to 1071
>>> resp, subs = s.xhdr('subject', first + '-' + last)
>>> for id, sub in subs[-10:]: print id, sub
...
1062 Re: Mercurial Status?
1063 Re: [python-committers] (Windows) buildbots on 3.x
1064 Re: Mercurial Status?
1065 Re: Mercurial Status?
1066 Python 2.6.6 status
1067 Commit Privileges for Ask Solem
1068 Re: Commit Privileges for Ask Solem
1069 Re: Commit Privileges for Ask Solem
1070 Re: Commit Privileges for Ask Solem
1071 2.6.6 rc 2
>>> s.quit()
'205 Bye!'
```

To post an article from a file (this assumes that the article has valid headers, and that you have right to post on the particular newsgroup):

```
>>> s = NNTP('news.gmane.org')
>>> f = open('articlefile')
>>> s.post(f)
'240 Article posted successfully.'
>>> s.quit()
'205 Bye!'
```

The module itself defines the following items:

class `nntplib>NNTP` (*host* [, *port* [, *user* [, *password* [, *readermode*] [, *usenetr*]]]])

Return a new instance of the `NNTP` class, representing a connection to the NNTP server running on host *host*, listening at port *port*. The default *port* is 119. If the optional *user* and *password* are provided, or if suitable credentials are present in `/.netrc` and the optional flag *usenetr* is true (the default), the `AUTHINFO USER` and `AUTHINFO PASS` commands are used to identify and authenticate the user to the server. If the optional flag *readermode* is true, then a `mode reader` command is sent before authentication is performed. Reader mode is sometimes necessary if you are connecting to an NNTP server on the local machine and intend to call reader-specific commands, such as `group`. If you get unexpected `NNTPPermanentErrors`, you might need to set *readermode*. *readermode* defaults to `None`. *usenetr* defaults to `True`.

버전 2.4에서 변경: *usenetr* argument added.

exception nntplib.NNTPError

Derived from the standard exception *Exception*, this is the base class for all exceptions raised by the *nntplib* module.

exception nntplib.NNTPReplyError

Exception raised when an unexpected reply is received from the server. For backwards compatibility, the exception *error_reply* is equivalent to this class.

exception nntplib.NNTPTemporaryError

Exception raised when an error code in the range 400–499 is received. For backwards compatibility, the exception *error_temp* is equivalent to this class.

exception nntplib.NNTPPermanentError

Exception raised when an error code in the range 500–599 is received. For backwards compatibility, the exception *error_perm* is equivalent to this class.

exception nntplib.NNTPProtocolError

Exception raised when a reply is received from the server that does not begin with a digit in the range 1–5. For backwards compatibility, the exception *error_proto* is equivalent to this class.

exception nntplib.NNTPDataError

Exception raised when there is some error in the response data. For backwards compatibility, the exception *error_data* is equivalent to this class.

20.11.1 NNTP Objects

NNTP instances have the following methods. The *response* that is returned as the first item in the return tuple of almost all methods is the server's response: a string beginning with a three-digit code. If the server's response indicates an error, the method raises one of the above exceptions.

NNTP.getwelcome()

Return the welcome message sent by the server in reply to the initial connection. (This message sometimes contains disclaimers or help information that may be relevant to the user.)

NNTP.set_debuglevel(*level*)

Set the instance's debugging level. This controls the amount of debugging output printed. The default, 0, produces no debugging output. A value of 1 produces a moderate amount of debugging output, generally a single line per request or response. A value of 2 or higher produces the maximum amount of debugging output, logging each line sent and received on the connection (including message text).

NNTP.newgroups(*date*, *time*[, *file*])

Send a NEWGROUPS command. The *date* argument should be a string of the form 'yyymmdd' indicating the date, and *time* should be a string of the form 'hhmmss' indicating the time. Return a pair (*response*, *groups*) where *groups* is a list of group names that are new since the given date and time. If the *file* parameter is supplied, then the output of the NEWGROUPS command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling *write()* on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

NNTP.newnews(*group*, *date*, *time*[, *file*])

Send a NEWNEWS command. Here, *group* is a group name or '*', and *date* and *time* have the same meaning as for *newgroups()*. Return a pair (*response*, *articles*) where *articles* is a list of message ids. If the *file* parameter is supplied, then the output of the NEWNEWS command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling *write()* on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

NNTP.list([*file*])

Send a LIST command. Return a pair (*response*, *list*) where *list* is a list of tuples. Each tuple has the form (*group*, *last*, *first*, *flag*), where *group* is a group name, *last* and *first* are the last and first article

numbers (as strings), and *flag* is 'y' if posting is allowed, 'n' if not, and 'm' if the newsgroup is moderated. (Note the ordering: *last*, *first*.) If the *file* parameter is supplied, then the output of the `LIST` command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

NNTP.descriptions (*grouppattern*)

Send a `LIST NEWSGROUPS` command, where *grouppattern* is a wildmat string as specified in RFC2980 (it's essentially the same as DOS or UNIX shell wildcard strings). Return a pair (*response*, *list*), where *list* is a list of tuples containing (*name*, *title*).

버전 2.4에 추가.

NNTP.description (*group*)

Get a description for a single group *group*. If more than one group matches (if *group* is a real wildmat string), return the first match. If no group matches, return an empty string.

This elides the response code from the server. If the response code is needed, use `descriptions()`.

버전 2.4에 추가.

NNTP.group (*name*)

Send a `GROUP` command, where *name* is the group name. Return a tuple (*response*, *count*, *first*, *last*, *name*) where *count* is the (estimated) number of articles in the group, *first* is the first article number in the group, *last* is the last article number in the group, and *name* is the group name. The numbers are returned as strings.

NNTP.help ([*file*])

Send a `HELP` command. Return a pair (*response*, *list*) where *list* is a list of help strings. If the *file* parameter is supplied, then the output of the `HELP` command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

NNTP.stat (*id*)

Send a `STAT` command, where *id* is the message id (enclosed in '<' and '>') or an article number (as a string). Return a triple (*response*, *number*, *id*) where *number* is the article number (as a string) and *id* is the message id (enclosed in '<' and '>').

NNTP.next ()

Send a `NEXT` command. Return as for `stat()`.

NNTP.last ()

Send a `LAST` command. Return as for `stat()`.

NNTP.head (*id*)

Send a `HEAD` command, where *id* has the same meaning as for `stat()`. Return a tuple (*response*, *number*, *id*, *list*) where the first three are the same as for `stat()`, and *list* is a list of the article's headers (an uninterpreted list of lines, without trailing newlines).

NNTP.body (*id*, [*file*])

Send a `BODY` command, where *id* has the same meaning as for `stat()`. If the *file* parameter is supplied, then the body is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the body. Return as for `head()`. If *file* is supplied, then the returned *list* is an empty list.

NNTP.article (*id*)

Send an `ARTICLE` command, where *id* has the same meaning as for `stat()`. Return as for `head()`.

NNTP.slave ()

Send a `SLAVE` command. Return the server's *response*.

NNTP.**xhdr** (*header*, *string*[, *file*])

Send an XHDR command. This command is not defined in the RFC but is a common extension. The *header* argument is a header keyword, e.g. 'subject'. The *string* argument should have the form 'first-last' where *first* and *last* are the first and last article numbers to search. Return a pair (*response*, *list*), where *list* is a list of pairs (*id*, *text*), where *id* is an article number (as a string) and *text* is the text of the requested header for that article. If the *file* parameter is supplied, then the output of the XHDR command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

NNTP.**post** (*file*)

Post an article using the POST command. The *file* argument is an open file object which is read until EOF using its `readline()` method. It should be a well-formed news article, including the required headers. The `post()` method automatically escapes lines beginning with ..

NNTP.**ihave** (*id*, *file*)

Send an IHAVE command. *id* is a message id (enclosed in '<' and '>'). If the response is not an error, treat *file* exactly as for the `post()` method.

NNTP.**date** ()

Return a triple (*response*, *date*, *time*), containing the current date and time in a form suitable for the `newnews()` and `newgroups()` methods. This is an optional NNTP extension, and may not be supported by all servers.

NNTP.**xgtitle** (*name*[, *file*])

Process an XGTITLE command, returning a pair (*response*, *list*), where *list* is a list of tuples containing (*name*, *title*). If the *file* parameter is supplied, then the output of the XGTITLE command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list. This is an optional NNTP extension, and may not be supported by all servers.

RFC2980 says «It is suggested that this extension be deprecated». Use `descriptions()` or `description()` instead.

NNTP.**xover** (*start*, *end*[, *file*])

Return a pair (*resp*, *list*). *list* is a list of tuples, one for each article in the range delimited by the *start* and *end* article numbers. Each tuple is of the form (*article number*, *subject*, *poster*, *date*, *id*, *references*, *size*, *lines*). If the *file* parameter is supplied, then the output of the XOVER command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list. This is an optional NNTP extension, and may not be supported by all servers.

NNTP.**xpath** (*id*)

Return a pair (*resp*, *path*), where *path* is the directory path to the article with message ID *id*. This is an optional NNTP extension, and may not be supported by all servers.

NNTP.**quit** ()

Send a QUIT command and close the connection. Once this method has been called, no other methods of the NNTP object should be called.

20.12 smtplib — SMTP protocol client

Source code: [Lib/smtplib.py](#)

The `smtplib` module defines an SMTP client session object that can be used to send mail to any Internet machine with an SMTP or ESMTP listener daemon. For details of SMTP and ESMTP operation, consult [RFC 821](#) (Simple Mail Transfer Protocol) and [RFC 1869](#) (SMTP Service Extensions).

class `smtplib.SMTP` (`[host[, port[, local_hostname[, timeout]]]]`)

An `SMTP` instance encapsulates an SMTP connection. It has methods that support a full repertoire of SMTP and ESMTP operations. If the optional host and port parameters are given, the `SMTP.connect()` method is called with those parameters during initialization. If specified, `local_hostname` is used as the FQDN of the local host in the HELO/EHLO command. Otherwise, the local hostname is found using `socket.getfqdn()`. If the `connect()` call returns anything other than a success code, an `SMTPConnectError` is raised. The optional `timeout` parameter specifies a timeout in seconds for blocking operations like the connection attempt (if not specified, the global default timeout setting will be used). If the timeout expires, `socket.timeout` is raised.

For normal use, you should only require the initialization/connect, `sendmail()`, and `SMTP.quit()` methods. An example is included below.

버전 2.6에서 변경: `timeout` was added.

class `smtplib.SMTP_SSL` (`[host[, port[, local_hostname[, keyfile[, certfile[, timeout]]]]]]`)

An `SMTP_SSL` instance behaves exactly the same as instances of `SMTP`. `SMTP_SSL` should be used for situations where SSL is required from the beginning of the connection and using `starttls()` is not appropriate. If `host` is not specified, the local host is used. If `port` is omitted, the standard SMTP-over-SSL port (465) is used. `local_hostname` has the same meaning as it does for the `SMTP` class. `keyfile` and `certfile` are also optional, and can contain a PEM formatted private key and certificate chain file for the SSL connection. The optional `timeout` parameter specifies a timeout in seconds for blocking operations like the connection attempt (if not specified, the global default timeout setting will be used). If the timeout expires, `socket.timeout` is raised.

버전 2.6에 추가.

class `smtplib.LMTP` (`[host[, port[, local_hostname]]]`)

The LMTP protocol, which is very similar to ESMTP, is heavily based on the standard SMTP client. It's common to use Unix sockets for LMTP, so our `connect()` method must support that as well as a regular host:port server. `local_hostname` has the same meaning as it does for the `SMTP` class. To specify a Unix socket, you must use an absolute path for `host`, starting with a `/`.

Authentication is supported, using the regular SMTP mechanism. When using a Unix socket, LMTP generally don't support or require any authentication, but your mileage might vary.

버전 2.6에 추가.

A nice selection of exceptions is defined as well:

exception `smtplib.SMTPException`

The base exception class for all the other exceptions provided by this module.

exception `smtplib.SMTPServerDisconnected`

This exception is raised when the server unexpectedly disconnects, or when an attempt is made to use the `SMTP` instance before connecting it to a server.

exception `smtplib.SMTPResponseException`

Base class for all exceptions that include an SMTP error code. These exceptions are generated in some instances when the SMTP server returns an error code. The error code is stored in the `smtplib_code` attribute of the error, and the `smtplib_error` attribute is set to the error message.

exception `smtplib.SMTPSenderRefused`

Sender address refused. In addition to the attributes set by on all *SMTPResponseException* exceptions, this sets `<sender>` to the string that the SMTP server refused.

exception `smtplib.SMTPRecipientsRefused`

All recipient addresses refused. The errors for each recipient are accessible through the attribute `recipients`, which is a dictionary of exactly the same sort as *SMTP.sendmail()* returns.

exception `smtplib.SMTPDataError`

The SMTP server refused to accept the message data.

exception `smtplib.SMTPConnectError`

Error occurred during establishment of a connection with the server.

exception `smtplib.SMTPHeloError`

The server refused our HELO message.

exception `smtplib.SMTPAuthenticationError`

SMTP authentication went wrong. Most probably the server didn't accept the username/password combination provided.

더 보기:

RFC 821 - Simple Mail Transfer Protocol Protocol definition for SMTP. This document covers the model, operating procedure, and protocol details for SMTP.

RFC 1869 - SMTP Service Extensions Definition of the ESMTP extensions for SMTP. This describes a framework for extending SMTP with new commands, supporting dynamic discovery of the commands provided by the server, and defines a few additional commands.

20.12.1 SMTP Objects

An *SMTP* instance has the following methods:

`SMTP.set_debuglevel (level)`

Set the debug output level. A true value for *level* results in debug messages for connection and for all messages sent to and received from the server.

`SMTP.docmd (cmd[, argstring])`

Send a command *cmd* to the server. The optional argument *argstring* is simply concatenated to the command, separated by a space.

This returns a 2-tuple composed of a numeric response code and the actual response line (multiline responses are joined into one long line.)

In normal operation it should not be necessary to call this method explicitly. It is used to implement other methods and may be useful for testing private extensions.

If the connection to the server is lost while waiting for the reply, *SMTPServerDisconnected* will be raised.

`SMTP.connect ([host[, port]])`

Connect to a host on a given port. The defaults are to connect to the local host at the standard SMTP port (25). If the hostname ends with a colon (':') followed by a number, that suffix will be stripped off and the number interpreted as the port number to use. This method is automatically invoked by the constructor if a host is specified during instantiation. Returns a 2-tuple of the response code and message sent by the server in its connection response.

`SMTP.helo ([hostname])`

Identify yourself to the SMTP server using HELO. The hostname argument defaults to the fully qualified domain name of the local host. The message returned by the server is stored as the `helo_resp` attribute of the object.

In normal operation it should not be necessary to call this method explicitly. It will be implicitly called by the `sendmail()` when necessary.

SMTP.**ehlo** (`[hostname]`)

Identify yourself to an ESMTP server using EHLO. The `hostname` argument defaults to the fully qualified domain name of the local host. Examine the response for ESMTP option and store them for use by `has_extn()`. Also sets several informational attributes: the message returned by the server is stored as the `ehlo_resp` attribute, `does_esmtp` is set to true or false depending on whether the server supports ESMTP, and `esmtp_features` will be a dictionary containing the names of the SMTP service extensions this server supports, and their parameters (if any).

Unless you wish to use `has_extn()` before sending mail, it should not be necessary to call this method explicitly. It will be implicitly called by `sendmail()` when necessary.

SMTP.**ehlo_or_helo_if_needed** ()

This method call `ehlo()` and or `helo()` if there has been no previous EHLO or HELO command this session. It tries ESMTP EHLO first.

SMTPHeloError The server didn't reply properly to the HELO greeting.

버전 2.6에 추가.

SMTP.**has_extn** (`name`)

Return `True` if `name` is in the set of SMTP service extensions returned by the server, `False` otherwise. Case is ignored.

SMTP.**verify** (`address`)

Check the validity of an address on this server using SMTP VRFY. Returns a tuple consisting of code 250 and a full **RFC 822** address (including human name) if the user address is valid. Otherwise returns an SMTP error code of 400 or greater and an error string.

참고: Many sites disable SMTP VRFY in order to foil spammers.

SMTP.**login** (`user, password`)

Log in on an SMTP server that requires authentication. The arguments are the username and the password to authenticate with. If there has been no previous EHLO or HELO command this session, this method tries ESMTP EHLO first. This method will return normally if the authentication was successful, or may raise the following exceptions:

SMTPHeloError The server didn't reply properly to the HELO greeting.

SMTPAuthenticationError The server didn't accept the username/password combination.

SMTPException No suitable authentication method was found.

SMTP.**starttls** (`[keyfile[, certfile]]`)

Put the SMTP connection in TLS (Transport Layer Security) mode. All SMTP commands that follow will be encrypted. You should then call `ehlo()` again.

If `keyfile` and `certfile` are provided, these are passed to the `socket` module's `ssl()` function.

If there has been no previous EHLO or HELO command this session, this method tries ESMTP EHLO first.

버전 2.6에서 변경.

SMTPHeloError The server didn't reply properly to the HELO greeting.

SMTPException The server does not support the STARTTLS extension.

버전 2.6에서 변경.

RuntimeError SSL/TLS support is not available to your Python interpreter.

`SMTP.sendmail (from_addr, to_addrs, msg[, mail_options, rcpt_options])`

Send mail. The required arguments are an **RFC 822** from-address string, a list of **RFC 822** to-address strings (a bare string will be treated as a list with 1 address), and a message string. The caller may pass a list of ESMTP options (such as `8bitmime`) to be used in `MAIL FROM` commands as *mail_options*. ESMTP options (such as DSN commands) that should be used with all `RCPT` commands can be passed as *rcpt_options*. (If you need to use different ESMTP options to different recipients you have to use the low-level methods such as `mail()`, `rcpt()` and `data()` to send the message.)

참고: The *from_addr* and *to_addrs* parameters are used to construct the message envelope used by the transport agents. The *SMTP* does not modify the message headers in any way.

If there has been no previous `EHLO` or `HELO` command this session, this method tries ESMTP `EHLO` first. If the server does ESMTP, message size and each of the specified options will be passed to it (if the option is in the feature set the server advertises). If `EHLO` fails, `HELO` will be tried and ESMTP options suppressed.

This method will return normally if the mail is accepted for at least one recipient. Otherwise it will raise an exception. That is, if this method does not raise an exception, then someone should get your mail. If this method does not raise an exception, it returns a dictionary, with one entry for each recipient that was refused. Each entry contains a tuple of the SMTP error code and the accompanying error message sent by the server.

This method may raise the following exceptions:

SMTPRecipientsRefused All recipients were refused. Nobody got the mail. The *recipients* attribute of the exception object is a dictionary with information about the refused recipients (like the one returned when at least one recipient was accepted).

SMTPHeloError The server didn't reply properly to the `HELO` greeting.

SMTPSenderRefused The server didn't accept the *from_addr*.

SMTPDataError The server replied with an unexpected error code (other than a refusal of a recipient).

Unless otherwise noted, the connection will be open even after an exception is raised.

`SMTP.quit ()`

Terminate the SMTP session and close the connection. Return the result of the SMTP `QUIT` command.

버전 2.6에서 변경: Return a value.

Low-level methods corresponding to the standard SMTP/ESMTP commands `HELP`, `RSET`, `NOOP`, `MAIL`, `RCPT`, and `DATA` are also supported. Normally these do not need to be called directly, so they are not documented here. For details, consult the module code.

20.12.2 SMTP Example

This example prompts the user for addresses needed in the message envelope (`<To>` and `<From>` addresses), and the message to be delivered. Note that the headers to be included with the message must be included in the message as entered; this example doesn't do any processing of the **RFC 822** headers. In particular, the `<To>` and `<From>` addresses must be included in the message headers explicitly.

```
import smtplib

def prompt(prompt):
    return raw_input(prompt).strip()

fromaddr = prompt("From: ")
toaddrs = prompt("To: ").split()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
print "Enter message, end with ^D (Unix) or ^Z (Windows):"

# Add the From: and To: headers at the start!
msg = ("From: %s\r\nTo: %s\r\n\r\n"
       % (fromaddr, ", ".join(toaddrs)))
while 1:
    try:
        line = raw_input()
    except EOFError:
        break
    if not line:
        break
    msg = msg + line

print "Message length is " + repr(len(msg))

server = smtplib.SMTP('localhost')
server.set_debuglevel(1)
server.sendmail(fromaddr, toaddrs, msg)
server.quit()
```

참고: In general, you will want to use the *email* package's features to construct an email message, which you can then convert to a string and send via `sendmail()`; see *email: Examples*.

20.13 smtpd — SMTP Server

Source code: [Lib/smtpd.py](#)

This module offers several classes to implement SMTP servers. One is a generic do-nothing implementation, which can be overridden, while the other two offer specific mail-sending strategies.

20.13.1 SMTPServer Objects

class `smtpd.SMTPServer` (*localaddr*, *remoteaddr*)

Create a new *SMTPServer* object, which binds to local address *localaddr*. It will treat *remoteaddr* as an upstream SMTP relayer. Both *localaddr* and *remoteaddr* should be a (*host*, *port*) tuple. The object inherits from *asyncore.dispatcher*, and so will insert itself into *asyncore*'s event loop on instantiation.

process_message (*peer*, *mailfrom*, *rcpttos*, *data*)

Raise *NotImplementedError* exception. Override this in subclasses to do something useful with this message. Whatever was passed in the constructor as *remoteaddr* will be available as the *_remoteaddr* attribute. *peer* is the remote host's address, *mailfrom* is the envelope originator, *rcpttos* are the envelope recipients and *data* is a string containing the contents of the e-mail (which should be in **RFC 2822** format).

20.13.2 DebuggingServer Objects

class `smtpd.DebuggingServer` (*localaddr*, *remoteaddr*)

Create a new debugging server. Arguments are as per *SMTPServer*. Messages will be discarded, and printed on stdout.

20.13.3 PureProxy Objects

class `smtpd.PureProxy` (*localaddr*, *remoteaddr*)

Create a new pure proxy server. Arguments are as per *SMTPServer*. Everything will be relayed to *remoteaddr*. Note that running this has a good chance to make you into an open relay, so please be careful.

20.13.4 MailmanProxy Objects

class `smtpd.MailmanProxy` (*localaddr*, *remoteaddr*)

Create a new pure proxy server. Arguments are as per *SMTPServer*. Everything will be relayed to *remoteaddr*, unless local mailman configurations knows about an address, in which case it will be handled via mailman. Note that running this has a good chance to make you into an open relay, so please be careful.

20.14 telnetlib — Telnet client

Source code: [Lib/telnetlib.py](#)

The *telnetlib* module provides a *Telnet* class that implements the Telnet protocol. See [RFC 854](#) for details about the protocol. In addition, it provides symbolic constants for the protocol characters (see below), and for the telnet options. The symbolic names of the telnet options follow the definitions in `arpa/telnet.h`, with the leading `TELOPT_` removed. For symbolic names of options which are traditionally not included in `arpa/telnet.h`, see the module source itself.

The symbolic constants for the telnet commands are: IAC, DONT, DO, WONT, WILL, SE (Subnegotiation End), NOP (No Operation), DM (Data Mark), BRK (Break), IP (Interrupt process), AO (Abort output), AYT (Are You There), EC (Erase Character), EL (Erase Line), GA (Go Ahead), SB (Subnegotiation Begin).

class `telnetlib.Telnet` (*[host[, port[, timeout]]]*)

Telnet represents a connection to a Telnet server. The instance is initially not connected by default; the *open()* method must be used to establish a connection. Alternatively, the host name and optional port number can be passed to the constructor, to, in which case the connection to the server will be established before the constructor returns. The optional *timeout* parameter specifies a timeout in seconds for blocking operations like the connection attempt (if not specified, the global default timeout setting will be used).

Do not reopen an already connected instance.

This class has many *read_*()* methods. Note that some of them raise *EOFError* when the end of the connection is read, because they can return an empty string for other reasons. See the individual descriptions below.

버전 2.6에서 변경: *timeout* was added.

더 보기:

RFC 854 - Telnet Protocol Specification Definition of the Telnet protocol.

20.14.1 Telnet Objects

Telnet instances have the following methods:

`Telnet.read_until(expected[, timeout])`

Read until a given string, *expected*, is encountered or until *timeout* seconds have passed.

When no match is found, return whatever is available instead, possibly the empty string. Raise *EOFError* if the connection is closed and no cooked data is available.

`Telnet.read_all()`

Read all data until EOF; block until connection closed.

`Telnet.read_some()`

Read at least one byte of cooked data unless EOF is hit. Return '' if EOF is hit. Block if no data is immediately available.

`Telnet.read_very_eager()`

Read everything that can be without blocking in I/O (eager).

Raise *EOFError* if connection closed and no cooked data available. Return '' if no cooked data available otherwise. Do not block unless in the midst of an IAC sequence.

`Telnet.read_eager()`

Read readily available data.

Raise *EOFError* if connection closed and no cooked data available. Return '' if no cooked data available otherwise. Do not block unless in the midst of an IAC sequence.

`Telnet.read_lazy()`

Process and return data already in the queues (lazy).

Raise *EOFError* if connection closed and no data available. Return '' if no cooked data available otherwise. Do not block unless in the midst of an IAC sequence.

`Telnet.read_very_lazy()`

Return any data available in the cooked queue (very lazy).

Raise *EOFError* if connection closed and no data available. Return '' if no cooked data available otherwise. This method never blocks.

`Telnet.read_sb_data()`

Return the data collected between a SB/SE pair (suboption begin/end). The callback should access these data when it was invoked with a SE command. This method never blocks.

버전 2.3에 추가.

`Telnet.open(host[, port[, timeout]])`

Connect to a host. The optional second argument is the port number, which defaults to the standard Telnet port (23). The optional *timeout* parameter specifies a timeout in seconds for blocking operations like the connection attempt (if not specified, the global default timeout setting will be used).

Do not try to reopen an already connected instance.

버전 2.6에서 변경: *timeout* was added.

`Telnet.msg(msg[, *args])`

Print a debug message when the debug level is > 0. If extra arguments are present, they are substituted in the message using the standard string formatting operator.

`Telnet.set_debuglevel(debuglevel)`

Set the debug level. The higher the value of *debuglevel*, the more debug output you get (on `sys.stdout`).

`Telnet.close()`
Close the connection.

`Telnet.get_socket()`
Return the socket object used internally.

`Telnet.fileno()`
Return the file descriptor of the socket object used internally.

`Telnet.write(buffer)`
Write a string to the socket, doubling any IAC characters. This can block if the connection is blocked. May raise `socket.error` if the connection is closed.

`Telnet.interact()`
Interaction function, emulates a very dumb Telnet client.

`Telnet.mt_interact()`
Multithreaded version of `interact()`.

`Telnet.expect(list[, timeout])`
Read until one from a list of a regular expressions matches.

The first argument is a list of regular expressions, either compiled (`regex objects`) or uncompiled (strings). The optional second argument is a timeout, in seconds; the default is to block indefinitely.

Return a tuple of three items: the index in the list of the first regular expression that matches; the match object returned; and the text read up till and including the match.

If end of file is found and no text was read, raise `EOFError`. Otherwise, when nothing matches, return `(-1, None, text)` where `text` is the text received so far (may be the empty string if a timeout happened).

If a regular expression ends with a greedy match (such as `.*`) or if more than one expression can match the same input, the results are non-deterministic, and may depend on the I/O timing.

`Telnet.set_option_negotiation_callback(callback)`
Each time a telnet option is read on the input flow, this `callback` (if set) is called with the following parameters: `callback(telnet socket, command (DO/DONT/WILL/WONT), option)`. No other action is done afterwards by `telnetlib`.

20.14.2 Telnet Example

A simple example illustrating typical use:

```
import getpass
import sys
import telnetlib

HOST = "localhost"
user = raw_input("Enter your remote account: ")
password = getpass.getpass()

tn = telnetlib.Telnet(HOST)

tn.read_until("login: ")
tn.write(user + "\n")
if password:
    tn.read_until("Password: ")
    tn.write(password + "\n")
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
tn.write("ls\n")
tn.write("exit\n")

print tn.read_all()
```

20.15 uuid — UUID objects according to RFC 4122

버전 2.5에 추가.

This module provides immutable *UUID* objects (the *UUID* class) and the functions *uuid1()*, *uuid3()*, *uuid4()*, *uuid5()* for generating version 1, 3, 4, and 5 UUIDs as specified in **RFC 4122**.

If all you want is a unique ID, you should probably call *uuid1()* or *uuid4()*. Note that *uuid1()* may compromise privacy since it creates a UUID containing the computer's network address. *uuid4()* creates a random UUID.

class *uuid.UUID* (*[hex[, bytes[, bytes_le[, fields[, int[, version]]]]]*)

Create a UUID from either a string of 32 hexadecimal digits, a string of 16 bytes in big-endian order as the *bytes* argument, a string of 16 bytes in little-endian order as the *bytes_le* argument, a tuple of six integers (32-bit *time_low*, 16-bit *time_mid*, 16-bit *time_hi_version*, 8-bit *clock_seq_hi_variant*, 8-bit *clock_seq_low*, 48-bit *node*) as the *fields* argument, or a single 128-bit integer as the *int* argument. When a string of hex digits is given, curly braces, hyphens, and a URN prefix are all optional. For example, these expressions all yield the same UUID:

```
UUID('{12345678-1234-5678-1234-567812345678}')
UUID('12345678123456781234567812345678')
UUID('urn:uuid:12345678-1234-5678-1234-567812345678')
UUID(bytes='\x12\x34\x56\x78'*4)
UUID(bytes_le='\x78\x56\x34\x12\x34\x12\x78\x56' +
              '\x12\x34\x56\x78\x12\x34\x56\x78')
UUID(fields=(0x12345678, 0x1234, 0x5678, 0x12, 0x34, 0x567812345678))
UUID(int=0x12345678123456781234567812345678)
```

Exactly one of *hex*, *bytes*, *bytes_le*, *fields*, or *int* must be given. The *version* argument is optional; if given, the resulting UUID will have its variant and version number set according to RFC 4122, overriding bits in the given *hex*, *bytes*, *bytes_le*, *fields*, or *int*.

UUID instances have these read-only attributes:

UUID.**bytes**

The UUID as a 16-byte string (containing the six integer fields in big-endian byte order).

UUID.**bytes_le**

The UUID as a 16-byte string (with *time_low*, *time_mid*, and *time_hi_version* in little-endian byte order).

UUID.**fields**

A tuple of the six integer fields of the UUID, which are also available as six individual attributes and two derived attributes:

Field	Meaning
<code>time_low</code>	the first 32 bits of the UUID
<code>time_mid</code>	the next 16 bits of the UUID
<code>time_hi_version</code>	the next 16 bits of the UUID
<code>clock_seq_hi_variant</code>	the next 8 bits of the UUID
<code>clock_seq_low</code>	the next 8 bits of the UUID
<code>node</code>	the last 48 bits of the UUID
<i>time</i>	the 60-bit timestamp
<code>clock_seq</code>	the 14-bit sequence number

`UUID.hex`

The UUID as a 32-character hexadecimal string.

`UUID.int`

The UUID as a 128-bit integer.

`UUID.urn`

The UUID as a URN as specified in RFC 4122.

`UUID.variant`

The UUID variant, which determines the internal layout of the UUID. This will be one of the constants `RESERVED_NCS`, `RFC_4122`, `RESERVED_MICROSOFT`, or `RESERVED_FUTURE`.

`UUID.version`

The UUID version number (1 through 5, meaningful only when the variant is `RFC_4122`).

The `uuid` module defines the following functions:

`uuid.getnode()`

Get the hardware address as a 48-bit positive integer. The first time this runs, it may launch a separate program, which could be quite slow. If all attempts to obtain the hardware address fail, we choose a random 48-bit number with its eighth bit set to 1 as recommended in RFC 4122. 《Hardware address》 means the MAC address of a network interface, and on a machine with multiple network interfaces the MAC address of any one of them may be returned.

`uuid.uuid1([node[, clock_seq]])`

Generate a UUID from a host ID, sequence number, and the current time. If `node` is not given, `getnode()` is used to obtain the hardware address. If `clock_seq` is given, it is used as the sequence number; otherwise a random 14-bit sequence number is chosen.

`uuid.uuid3(namespace, name)`

Generate a UUID based on the MD5 hash of a namespace identifier (which is a UUID) and a name (which is a string).

`uuid.uuid4()`

Generate a random UUID.

`uuid.uuid5(namespace, name)`

Generate a UUID based on the SHA-1 hash of a namespace identifier (which is a UUID) and a name (which is a string).

The `uuid` module defines the following namespace identifiers for use with `uuid3()` or `uuid5()`.

`uuid.NAMESPACE_DNS`

When this namespace is specified, the `name` string is a fully-qualified domain name.

`uuid.NAMESPACE_URL`

When this namespace is specified, the `name` string is a URL.

`uuid.NAMESPACE_OID`

When this namespace is specified, the *name* string is an ISO OID.

`uuid.NAMESPACE_X500`

When this namespace is specified, the *name* string is an X.500 DN in DER or a text output format.

The `uuid` module defines the following constants for the possible values of the `variant` attribute:

`uuid.RESERVED_NCS`

Reserved for NCS compatibility.

`uuid.RFC_4122`

Specifies the UUID layout given in [RFC 4122](#).

`uuid.RESERVED_MICROSOFT`

Reserved for Microsoft compatibility.

`uuid.RESERVED_FUTURE`

Reserved for future definition.

더 보기:

RFC 4122 - A Universally Unique Identifier (UUID) URN Namespace This specification defines a Uniform Resource Name namespace for UUIDs, the internal format of UUIDs, and methods of generating UUIDs.

20.15.1 Example

Here are some examples of typical usage of the `uuid` module:

```
>>> import uuid

>>> # make a UUID based on the host ID and current time
>>> uuid.uuid1()
UUID('a8098c1a-f86e-11da-bd1a-00112444be1e')

>>> # make a UUID using an MD5 hash of a namespace UUID and a name
>>> uuid.uuid3(uuid.NAMESPACE_DNS, 'python.org')
UUID('6fa459ea-ee8a-3ca4-894e-db77e160355e')

>>> # make a random UUID
>>> uuid.uuid4()
UUID('16fd2706-8baf-433b-82eb-8c7fada847da')

>>> # make a UUID using a SHA-1 hash of a namespace UUID and a name
>>> uuid.uuid5(uuid.NAMESPACE_DNS, 'python.org')
UUID('886313e1-3b8a-5372-9b90-0c9aee199e5d')

>>> # make a UUID from a string of hex digits (braces and hyphens ignored)
>>> x = uuid.UUID('{00010203-0405-0607-0809-0a0b0c0d0e0f}')

>>> # convert a UUID to a string of hex digits in standard form
>>> str(x)
'00010203-0405-0607-0809-0a0b0c0d0e0f'

>>> # get the raw 16 bytes of the UUID
>>> x.bytes
'\x00\x01\x02\x03\x04\x05\x06\x07\x08\t\n\x0b\x0c\r\x0e\x0f'

>>> # make a UUID from a 16-byte string
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> uuid.UUID(bytes=x.bytes)
UUID('00010203-0405-0607-0809-0a0b0c0d0e0f')
```

20.16 urlparse — Parse URLs into components

참고: The `urlparse` module is renamed to `urllib.parse` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

Source code: [Lib/urlparse.py](#)

This module defines a standard interface to break Uniform Resource Locator (URL) strings up in components (addressing scheme, network location, path etc.), to combine the components back into a URL string, and to convert a «relative URL» to an absolute URL given a «base URL.»

The module has been designed to match the Internet RFC on Relative Uniform Resource Locators. It supports the following URL schemes: file, ftp, gopher, hdl, http, https, imap, mailto, mms, news, nntp, prospero, rsync, rtsp, rtspu, sftp, shhttp, sip, sips, snews, svn, svn+ssh, telnet, wais.

버전 2.5에 추가: Support for the sftp and sips schemes.

The `urlparse` module defines the following functions:

`urlparse.urlparse(urlstring[, scheme[, allow_fragments]])`

Parse a URL into six components, returning a 6-tuple. This corresponds to the general structure of a URL: `scheme://netloc/path;parameters?query#fragment`. Each tuple item is a string, possibly empty. The components are not broken up in smaller parts (for example, the network location is a single string), and % escapes are not expanded. The delimiters as shown above are not part of the result, except for a leading slash in the `path` component, which is retained if present. For example:

```
>>> from urlparse import urlparse
>>> o = urlparse('http://www.cwi.nl:80/%7Eguido/Python.html')
>>> o
ParseResult(scheme='http', netloc='www.cwi.nl:80', path='/%7Eguido/Python.html',
            params='', query='', fragment='')
>>> o.scheme
'http'
>>> o.port
80
>>> o.geturl()
'http://www.cwi.nl:80/%7Eguido/Python.html'
```

Following the syntax specifications in [RFC 1808](#), `urlparse` recognizes a netloc only if it is properly introduced by `<//>`. Otherwise the input is presumed to be a relative URL and thus to start with a path component.

```
>>> from urlparse import urlparse
>>> urlparse('//www.cwi.nl:80/%7Eguido/Python.html')
ParseResult(scheme='', netloc='www.cwi.nl:80', path='/%7Eguido/Python.html',
            params='', query='', fragment='')
>>> urlparse('www.cwi.nl/%7Eguido/Python.html')
ParseResult(scheme='', netloc='', path='www.cwi.nl/%7Eguido/Python.html',
            params='', query='', fragment='')
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> urlparse('help/Python.html')
ParseResult(scheme='', netloc='', path='help/Python.html', params='',
            query='', fragment='')
```

If the *scheme* argument is specified, it gives the default addressing scheme, to be used only if the URL does not specify one. The default value for this argument is the empty string.

If the *allow_fragments* argument is false, fragment identifiers are not recognized and parsed as part of the preceding component, even if the URL's addressing scheme normally does support them. The default value for this argument is *True*.

The return value is actually an instance of a subclass of *tuple*. This class has the following additional read-only convenience attributes:

Attribute	Index	Value	Value if not present
<i>scheme</i>	0	URL scheme specifier	<i>scheme</i> parameter
<i>netloc</i>	1	Network location part	empty string
<i>path</i>	2	Hierarchical path	empty string
<i>params</i>	3	Parameters for last path element	empty string
<i>query</i>	4	Query component	empty string
<i>fragment</i>	5	Fragment identifier	empty string
<i>username</i>		User name	<i>None</i>
<i>password</i>		Password	<i>None</i>
<i>hostname</i>		Host name (lower case)	<i>None</i>
<i>port</i>		Port number as integer, if present	<i>None</i>

See section *Results of urlparse() and urlsplit()* for more information on the result object.

Characters in the *netloc* attribute that decompose under NFKC normalization (as used by the IDNA encoding) into any of /, ?, #, @, or : will raise a *ValueError*. If the URL is decomposed before parsing, or is not a Unicode string, no error will be raised.

버전 2.5에서 변경: Added attributes to return value.

버전 2.7에서 변경: Added IPv6 URL parsing capabilities.

버전 2.7.17에서 변경: Characters that affect netloc parsing under NFKC normalization will now raise *ValueError*.

`urlparse.parse_qs(qs[, keep_blank_values[, strict_parsing[, max_num_fields]])`

Parse a query string given as a string argument (data of type *application/x-www-form-urlencoded*). Data are returned as a dictionary. The dictionary keys are the unique query variable names and the values are lists of values for each name.

The optional argument *keep_blank_values* is a flag indicating whether blank values in percent-encoded queries should be treated as blank strings. A true value indicates that blanks should be retained as blank strings. The default false value indicates that blank values are to be ignored and treated as if they were not included.

The optional argument *strict_parsing* is a flag indicating what to do with parsing errors. If false (the default), errors are silently ignored. If true, errors raise a *ValueError* exception.

The optional argument *max_num_fields* is the maximum number of fields to read. If set, then throws a *ValueError* if there are more than *max_num_fields* fields read.

Use the `urllib.urlencode()` function to convert such dictionaries into query strings.

버전 2.6에 추가: Copied from the *cgi* module.

버전 2.7.16에서 변경: Added *max_num_fields* parameter.

`urlparse.parse_qs(qs[, keep_blank_values[, strict_parsing[, max_num_fields]])]`

Parse a query string given as a string argument (data of type *application/x-www-form-urlencoded*). Data are returned as a list of name, value pairs.

The optional argument *keep_blank_values* is a flag indicating whether blank values in percent-encoded queries should be treated as blank strings. A true value indicates that blanks should be retained as blank strings. The default false value indicates that blank values are to be ignored and treated as if they were not included.

The optional argument *strict_parsing* is a flag indicating what to do with parsing errors. If false (the default), errors are silently ignored. If true, errors raise a *ValueError* exception.

The optional argument *max_num_fields* is the maximum number of fields to read. If set, then throws a *ValueError* if there are more than *max_num_fields* fields read.

Use the *urllib.urlencode()* function to convert such lists of pairs into query strings.

버전 2.6에 추가: Copied from the *cgi* module.

버전 2.7.16에서 변경: Added *max_num_fields* parameter.

`urlparse.urlunparse(parts)`

Construct a URL from a tuple as returned by *urlparse()*. The *parts* argument can be any six-item iterable. This may result in a slightly different, but equivalent URL, if the URL that was parsed originally had unnecessary delimiters (for example, a ? with an empty query; the RFC states that these are equivalent).

`urlparse.urlsplit(urlstring[, scheme[, allow_fragments]])]`

This is similar to *urlparse()*, but does not split the params from the URL. This should generally be used instead of *urlparse()* if the more recent URL syntax allowing parameters to be applied to each segment of the *path* portion of the URL (see [RFC 2396](#)) is wanted. A separate function is needed to separate the path segments and parameters. This function returns a 5-tuple: (addressing scheme, network location, path, query, fragment identifier).

The return value is actually an instance of a subclass of *tuple*. This class has the following additional read-only convenience attributes:

Attribute	Index	Value	Value if not present
<i>scheme</i>	0	URL scheme specifier	<i>scheme</i> parameter
<i>netloc</i>	1	Network location part	empty string
<i>path</i>	2	Hierarchical path	empty string
<i>query</i>	3	Query component	empty string
<i>fragment</i>	4	Fragment identifier	empty string
<i>username</i>		User name	<i>None</i>
<i>password</i>		Password	<i>None</i>
<i>hostname</i>		Host name (lower case)	<i>None</i>
<i>port</i>		Port number as integer, if present	<i>None</i>

See section *Results of urlparse() and urlsplit()* for more information on the result object.

Characters in the *netloc* attribute that decompose under NFKC normalization (as used by the IDNA encoding) into any of /, ?, #, @, or : will raise a *ValueError*. If the URL is decomposed before parsing, or is not a Unicode string, no error will be raised.

버전 2.2에 추가.

버전 2.5에서 변경: Added attributes to return value.

버전 2.7.17에서 변경: Characters that affect *netloc* parsing under NFKC normalization will now raise *ValueError*.

`urlparse.urlunsplit (parts)`

Combine the elements of a tuple as returned by `urlsplit ()` into a complete URL as a string. The *parts* argument can be any five-item iterable. This may result in a slightly different, but equivalent URL, if the URL that was parsed originally had unnecessary delimiters (for example, a `?` with an empty query; the RFC states that these are equivalent).

버전 2.2에 추가.

`urlparse.urljoin (base, url[, allow_fragments])`

Construct a full (《absolute》) URL by combining a 《base URL》 (*base*) with another URL (*url*). Informally, this uses components of the base URL, in particular the addressing scheme, the network location and (part of) the path, to provide missing components in the relative URL. For example:

```
>>> from urlparse import urljoin
>>> urljoin('http://www.cwi.nl/%7Eguido/Python.html', 'FAQ.html')
'http://www.cwi.nl/%7Eguido/FAQ.html'
```

The *allow_fragments* argument has the same meaning and default as for `urlparse ()`.

참고: If *url* is an absolute URL (that is, starting with `//` or `scheme://`), the *url*'s host name and/or scheme will be present in the result. For example:

```
>>> urljoin('http://www.cwi.nl/%7Eguido/Python.html',
...         '//www.python.org/%7Eguido')
'http://www.python.org/%7Eguido'
```

If you do not want that behavior, preprocess the *url* with `urlsplit ()` and `urlunsplit ()`, removing possible *scheme* and *netloc* parts.

`urlparse.urldefrag (url)`

If *url* contains a fragment identifier, returns a modified version of *url* with no fragment identifier, and the fragment identifier as a separate string. If there is no fragment identifier in *url*, returns *url* unmodified and an empty string.

더 보기:

RFC 3986 - Uniform Resource Identifiers This is the current standard (STD66). Any changes to `urlparse` module should conform to this. Certain deviations could be observed, which are mostly for backward compatibility purposes and for certain de-facto parsing requirements as commonly observed in major browsers.

RFC 2732 - Format for Literal IPv6 Addresses in URL's. This specifies the parsing requirements of IPv6 URLs.

RFC 2396 - Uniform Resource Identifiers (URI): Generic Syntax Document describing the generic syntactic requirements for both Uniform Resource Names (URNs) and Uniform Resource Locators (URLs).

RFC 2368 - The mailto URL scheme. Parsing requirements for mailto URL schemes.

RFC 1808 - Relative Uniform Resource Locators This Request For Comments includes the rules for joining an absolute and a relative URL, including a fair number of 《Abnormal Examples》 which govern the treatment of border cases.

RFC 1738 - Uniform Resource Locators (URL) This specifies the formal syntax and semantics of absolute URLs.

20.16.1 Results of `urlparse()` and `urlsplit()`

The result objects from the `urlparse()` and `urlsplit()` functions are subclasses of the `tuple` type. These subclasses add the attributes described in those functions, as well as provide an additional method:

`ParseResult.geturl()`

Return the re-combined version of the original URL as a string. This may differ from the original URL in that the scheme will always be normalized to lower case and empty components may be dropped. Specifically, empty parameters, queries, and fragment identifiers will be removed.

The result of this method is a fixpoint if passed back through the original parsing function:

```
>>> import urlparse
>>> url = 'HTTP://www.Python.org/doc/#'
```

```
>>> r1 = urlparse.urlsplit(url)
>>> r1.geturl()
'http://www.Python.org/doc/'
```

```
>>> r2 = urlparse.urlsplit(r1.geturl())
>>> r2.geturl()
'http://www.Python.org/doc/'
```

버전 2.5에 추가.

The following classes provide the implementations of the parse results:

class `urlparse.ParseResult` (*scheme, netloc, path, params, query, fragment*)
Concrete class for `urlparse()` results.

class `urlparse.SplitResult` (*scheme, netloc, path, query, fragment*)
Concrete class for `urlsplit()` results.

20.17 SocketServer — A framework for network servers

참고: The `SocketServer` module has been renamed to `socketserver` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

Source code: [Lib/SocketServer.py](#)

The `SocketServer` module simplifies the task of writing network servers.

There are four basic concrete server classes:

class `SocketServer.TCPServer` (*server_address, RequestHandlerClass, bind_and_activate=True*)
This uses the Internet TCP protocol, which provides for continuous streams of data between the client and server. If *bind_and_activate* is true, the constructor automatically attempts to invoke `server_bind()` and `server_activate()`. The other parameters are passed to the `BaseServer` base class.

class `SocketServer.UDPServer` (*server_address, RequestHandlerClass, bind_and_activate=True*)
This uses datagrams, which are discrete packets of information that may arrive out of order or be lost while in transit. The parameters are the same as for `TCPServer`.

class `SocketServer.UnixStreamServer` (*server_address, RequestHandlerClass, bind_and_activate=True*)

```
class SocketServer.UnixDatagramServer(server_address, RequestHandlerClass,
                                     bind_and_activate=True)
```

These more infrequently used classes are similar to the TCP and UDP classes, but use Unix domain sockets; they're not available on non-Unix platforms. The parameters are the same as for *TCPServer*.

These four classes process requests *synchronously*; each request must be completed before the next request can be started. This isn't suitable if each request takes a long time to complete, because it requires a lot of computation, or because it returns a lot of data which the client is slow to process. The solution is to create a separate process or thread to handle each request; the *ForkingMixIn* and *ThreadingMixIn* mix-in classes can be used to support asynchronous behaviour.


Creating a server requires several steps. First, you must create a request handler class by subclassing the *BaseRequestHandler* class and overriding its *handle()* method; this method will process incoming requests. Second, you must instantiate one of the server classes, passing it the server's address and the request handler class. Then call the *handle_request()* or *serve_forever()* method of the server object to process one or many requests. Finally, call *server_close()* to close the socket.

When inheriting from *ThreadingMixIn* for threaded connection behavior, you should explicitly declare how you want your threads to behave on an abrupt shutdown. The *ThreadingMixIn* class defines an attribute *daemon_threads*, which indicates whether or not the server should wait for thread termination. You should set the flag explicitly if you would like threads to behave autonomously; the default is *False*, meaning that Python will not exit until all threads created by *ThreadingMixIn* have exited.

Server classes have the same external methods and attributes, no matter what network protocol they use.

20.17.1 Server Creation Notes

There are five classes in an inheritance diagram, four of which represent synchronous servers of four types:



Note that *UnixDatagramServer* derives from *UDPServer*, not from *UnixStreamServer* — the only difference between an IP and a Unix stream server is the address family, which is simply repeated in both Unix server classes.

```
class SocketServer.ForkingMixIn
```

```
class SocketServer.ThreadingMixIn
```

Forking and threading versions of each type of server can be created using these mix-in classes. For instance, *ThreadingUDPServer* is created as follows:

```
class ThreadingUDPServer(ThreadingMixIn, UDPServer):
    pass
```

The mix-in class comes first, since it overrides a method defined in *UDPServer*. Setting the various attributes also changes the behavior of the underlying server mechanism.

ForkingMixIn and the Forking classes mentioned below are only available on POSIX platforms that support *fork()*.

```
class SocketServer.ForkingTCPServer
class SocketServer.ForkingUDPServer
class SocketServer.ThreadingTCPServer
class SocketServer.ThreadingUDPServer
```

These classes are pre-defined using the mix-in classes.

To implement a service, you must derive a class from *BaseRequestHandler* and redefine its *handle()* method. You can then run various versions of the service by combining one of the server classes with your request handler class. The request handler class must be different for datagram or stream services. This can be hidden by using the handler subclasses *StreamRequestHandler* or *DatagramRequestHandler*.

Of course, you still have to use your head! For instance, it makes no sense to use a forking server if the service contains state in memory that can be modified by different requests, since the modifications in the child process would never reach the initial state kept in the parent process and passed to each child. In this case, you can use a threading server, but you will probably have to use locks to protect the integrity of the shared data.

On the other hand, if you are building an HTTP server where all data is stored externally (for instance, in the file system), a synchronous class will essentially render the service 《deaf》 while one request is being handled – which may be for a very long time if a client is slow to receive all the data it has requested. Here a threading or forking server is appropriate.

In some cases, it may be appropriate to process part of a request synchronously, but to finish processing in a forked child depending on the request data. This can be implemented by using a synchronous server and doing an explicit fork in the request handler class *handle()* method.

Another approach to handling multiple simultaneous requests in an environment that supports neither threads nor *fork()* (or where these are too expensive or inappropriate for the service) is to maintain an explicit table of partially finished requests and to use *select()* to decide which request to work on next (or whether to handle a new incoming request). This is particularly important for stream services where each client can potentially be connected for a long time (if threads or subprocesses cannot be used). See *asyncore* for another way to manage this.

20.17.2 Server Objects

```
class SocketServer.BaseServer (server_address, RequestHandlerClass)
```

This is the superclass of all Server objects in the module. It defines the interface, given below, but does not implement most of the methods, which is done in subclasses. The two parameters are stored in the respective *server_address* and *RequestHandlerClass* attributes.

```
fileno ()
```

Return an integer file descriptor for the socket on which the server is listening. This function is most commonly passed to *select.select()*, to allow monitoring multiple servers in the same process.

```
handle_request ()
```

Process a single request. This function calls the following methods in order: *get_request()*, *verify_request()*, and *process_request()*. If the user-provided *handle()* method of the handler class raises an exception, the server's *handle_error()* method will be called. If no request is received within *timeout* seconds, *handle_timeout()* will be called and *handle_request()* will return.

```
serve_forever (poll_interval=0.5)
```

Handle requests until an explicit *shutdown()* request. Poll for shutdown every *poll_interval* seconds. Ignores the *timeout* attribute. If you need to do periodic tasks, do them in another thread.

```
shutdown ()
```

Tell the *serve_forever()* loop to stop and wait until it does.

버전 2.6에 추가.

server_close()

Clean up the server. May be overridden.

버전 2.6에 추가.

address_family

The family of protocols to which the server's socket belongs. Common examples are `socket.AF_INET` and `socket.AF_UNIX`.

RequestHandlerClass

The user-provided request handler class; an instance of this class is created for each request.

server_address

The address on which the server is listening. The format of addresses varies depending on the protocol family; see the documentation for the `socket` module for details. For Internet protocols, this is a tuple containing a string giving the address, and an integer port number: `('127.0.0.1', 80)`, for example.

socket

The socket object on which the server will listen for incoming requests.

The server classes support the following class variables:

allow_reuse_address

Whether the server will allow the reuse of an address. This defaults to `False`, and can be set in subclasses to change the policy.

request_queue_size

The size of the request queue. If it takes a long time to process a single request, any requests that arrive while the server is busy are placed into a queue, up to `request_queue_size` requests. Once the queue is full, further requests from clients will get a 《Connection denied》 error. The default value is usually 5, but this can be overridden by subclasses.

socket_type

The type of socket used by the server; `socket.SOCK_STREAM` and `socket.SOCK_DGRAM` are two common values.

timeout

Timeout duration, measured in seconds, or `None` if no timeout is desired. If `handle_request()` receives no incoming requests within the timeout period, the `handle_timeout()` method is called.

There are various server methods that can be overridden by subclasses of base server classes like `TCPServer`; these methods aren't useful to external users of the server object.

finish_request(request, client_address)

Actually processes the request by instantiating `RequestHandlerClass` and calling its `handle()` method.

get_request()

Must accept a request from the socket, and return a 2-tuple containing the *new* socket object to be used to communicate with the client, and the client's address.

handle_error(request, client_address)

This function is called if the `handle()` method of a `RequestHandlerClass` instance raises an exception. The default action is to print the traceback to standard output and continue handling further requests.

handle_timeout()

This function is called when the `timeout` attribute has been set to a value other than `None` and the timeout period has passed with no requests being received. The default action for forking servers is to collect the status of any child processes that have exited, while in threading servers this method does nothing.

process_request (*request*, *client_address*)

Calls *finish_request()* to create an instance of the *RequestHandlerClass*. If desired, this function can create a new process or thread to handle the request; the *ForkingMixIn* and *ThreadingMixIn* classes do this.

server_activate ()

Called by the server's constructor to activate the server. The default behavior for a TCP server just invokes *listen()* on the server's socket. May be overridden.

server_bind ()

Called by the server's constructor to bind the socket to the desired address. May be overridden.

verify_request (*request*, *client_address*)

Must return a Boolean value; if the value is *True*, the request will be processed, and if it's *False*, the request will be denied. This function can be overridden to implement access controls for a server. The default implementation always returns *True*.

20.17.3 Request Handler Objects

class `SocketServer.BaseRequestHandler`

This is the superclass of all request handler objects. It defines the interface, given below. A concrete request handler subclass must define a new *handle()* method, and can override any of the other methods. A new instance of the subclass is created for each request.

setup ()

Called before the *handle()* method to perform any initialization actions required. The default implementation does nothing.

handle ()

This function must do all the work required to service a request. The default implementation does nothing. Several instance attributes are available to it; the request is available as *self.request*; the client address as *self.client_address*; and the server instance as *self.server*, in case it needs access to per-server information.

The type of *self.request* is different for datagram or stream services. For stream services, *self.request* is a socket object; for datagram services, *self.request* is a pair of string and socket.

finish ()

Called after the *handle()* method to perform any clean-up actions required. The default implementation does nothing. If *setup()* raises an exception, this function will not be called.

class `SocketServer.StreamRequestHandler`

class `SocketServer.DatagramRequestHandler`

These *BaseRequestHandler* subclasses override the *setup()* and *finish()* methods, and provide *self.rfile* and *self.wfile* attributes. The *self.rfile* and *self.wfile* attributes can be read or written, respectively, to get the request data or return data to the client.

20.17.4 Examples

SocketServer.TCPServer Example

This is the server side:

```
import SocketServer

class MyTCPHandler(SocketServer.BaseRequestHandler):
    """
    The request handler class for our server.

    It is instantiated once per connection to the server, and must
    override the handle() method to implement communication to the
    client.
    """

    def handle(self):
        # self.request is the TCP socket connected to the client
        self.data = self.request.recv(1024).strip()
        print "{} wrote:".format(self.client_address[0])
        print self.data
        # just send back the same data, but upper-cased
        self.request.sendall(self.data.upper())

if __name__ == "__main__":
    HOST, PORT = "localhost", 9999

    # Create the server, binding to localhost on port 9999
    server = SocketServer.TCPServer((HOST, PORT), MyTCPHandler)

    # Activate the server; this will keep running until you
    # interrupt the program with Ctrl-C
    server.serve_forever()
```

An alternative request handler class that makes use of streams (file-like objects that simplify communication by providing the standard file interface):

```
class MyTCPHandler(SocketServer.StreamRequestHandler):

    def handle(self):
        # self.rfile is a file-like object created by the handler;
        # we can now use e.g. readline() instead of raw recv() calls
        self.data = self.rfile.readline().strip()
        print "{} wrote:".format(self.client_address[0])
        print self.data
        # Likewise, self.wfile is a file-like object used to write back
        # to the client
        self.wfile.write(self.data.upper())
```

The difference is that the `readline()` call in the second handler will call `recv()` multiple times until it encounters a newline character, while the single `recv()` call in the first handler will just return what has been sent from the client in one `sendall()` call.

This is the client side:

```

import socket
import sys

HOST, PORT = "localhost", 9999
data = " ".join(sys.argv[1:])

# Create a socket (SOCK_STREAM means a TCP socket)
sock = socket.socket(socket.AF_INET, socket.SOCK_STREAM)

try:
    # Connect to server and send data
    sock.connect((HOST, PORT))
    sock.sendall(data + "\n")

    # Receive data from the server and shut down
    received = sock.recv(1024)
finally:
    sock.close()

print "Sent: {}".format(data)
print "Received: {}".format(received)

```

The output of the example should look something like this:

Server:

```

$ python TCPServer.py
127.0.0.1 wrote:
hello world with TCP
127.0.0.1 wrote:
python is nice

```

Client:

```

$ python TCPClient.py hello world with TCP
Sent:      hello world with TCP
Received:  HELLO WORLD WITH TCP
$ python TCPClient.py python is nice
Sent:      python is nice
Received:  PYTHON IS NICE

```

SocketServer.UDPServer Example

This is the server side:

```

import SocketServer

class MyUDPHandler(SocketServer.BaseRequestHandler):
    """
    This class works similar to the TCP handler class, except that
    self.request consists of a pair of data and client socket, and since
    there is no connection the client address must be given explicitly
    when sending data back via sendto().
    """

    def handle(self):

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

        data = self.request[0].strip()
        socket = self.request[1]
        print "{} wrote:".format(self.client_address[0])
        print data
        socket.sendto(data.upper(), self.client_address)

if __name__ == "__main__":
    HOST, PORT = "localhost", 9999
    server = SocketServer.UDPServer((HOST, PORT), MyUDPHandler)
    server.serve_forever()

```

This is the client side:

```

import socket
import sys

HOST, PORT = "localhost", 9999
data = " ".join(sys.argv[1:])

# SOCK_DGRAM is the socket type to use for UDP sockets
sock = socket.socket(socket.AF_INET, socket.SOCK_DGRAM)

# As you can see, there is no connect() call; UDP has no connections.
# Instead, data is directly sent to the recipient via sendto().
sock.sendto(data + "\n", (HOST, PORT))
received = sock.recv(1024)

print "Sent:      {}".format(data)
print "Received: {}".format(received)

```

The output of the example should look exactly like for the TCP server example.

Asynchronous Mixins

To build asynchronous handlers, use the *ThreadingMixin* and *ForkingMixin* classes.

An example for the *ThreadingMixin* class:

```

import socket
import threading
import SocketServer

class ThreadedTCPRequestHandler(SocketServer.BaseRequestHandler):

    def handle(self):
        data = self.request.recv(1024)
        cur_thread = threading.current_thread()
        response = "{}: {}".format(cur_thread.name, data)
        self.request.sendall(response)

class ThreadedTCPServer(SocketServer.ThreadingMixin, SocketServer.TCPServer):
    pass

def client(ip, port, message):
    sock = socket.socket(socket.AF_INET, socket.SOCK_STREAM)
    sock.connect((ip, port))

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

try:
    sock.sendall(message)
    response = sock.recv(1024)
    print "Received: {}".format(response)
finally:
    sock.close()

if __name__ == "__main__":
    # Port 0 means to select an arbitrary unused port
    HOST, PORT = "localhost", 0

    server = ThreadedTCPServer((HOST, PORT), ThreadedTCPRequestHandler)
    ip, port = server.server_address

    # Start a thread with the server -- that thread will then start one
    # more thread for each request
    server_thread = threading.Thread(target=server.serve_forever)
    # Exit the server thread when the main thread terminates
    server_thread.daemon = True
    server_thread.start()
    print "Server loop running in thread:", server_thread.name

    client(ip, port, "Hello World 1")
    client(ip, port, "Hello World 2")
    client(ip, port, "Hello World 3")

    server.shutdown()
    server.server_close()

```

The output of the example should look something like this:

```

$ python ThreadedTCPServer.py
Server loop running in thread: Thread-1
Received: Thread-2: Hello World 1
Received: Thread-3: Hello World 2
Received: Thread-4: Hello World 3

```

The *ForkingMixIn* class is used in the same way, except that the server will spawn a new process for each request. Available only on POSIX platforms that support *fork()*.

20.18 BaseHTTPServer — Basic HTTP server

참고: The *BaseHTTPServer* module has been merged into `http.server` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

Source code: [Lib/BaseHTTPServer.py](#)

This module defines two classes for implementing HTTP servers (Web servers). Usually, this module isn't used directly, but is used as a basis for building functioning Web servers. See the *SimpleHTTPServer* and *CGIHTTPServer* modules.

The first class, `HTTPServer`, is a `SocketServer.TCPServer` subclass, and therefore implements the `SocketServer.BaseServer` interface. It creates and listens at the HTTP socket, dispatching the requests to a handler. Code to create and run the server looks like this:

```
def run(server_class=BaseHTTPServer.HTTPServer,
        handler_class=BaseHTTPServer.BaseHTTPRequestHandler):
    server_address = ('', 8000)
    httpd = server_class(server_address, handler_class)
    httpd.serve_forever()
```

class `BaseHTTPServer.HTTPServer` (*server_address, RequestHandlerClass*)

This class builds on the `TCPServer` class by storing the server address as instance variables named `server_name` and `server_port`. The server is accessible by the handler, typically through the handler's `server` instance variable.

class `BaseHTTPServer.BaseHTTPRequestHandler` (*request, client_address, server*)

This class is used to handle the HTTP requests that arrive at the server. By itself, it cannot respond to any actual HTTP requests; it must be subclassed to handle each request method (e.g. `GET` or `POST`). `BaseHTTPRequestHandler` provides a number of class and instance variables, and methods for use by subclasses.

The handler will parse the request and the headers, then call a method specific to the request type. The method name is constructed from the request. For example, for the request method `SPAM`, the `do_SPAM()` method will be called with no arguments. All of the relevant information is stored in instance variables of the handler. Subclasses should not need to override or extend the `__init__()` method.

`BaseHTTPRequestHandler` has the following instance variables:

client_address

Contains a tuple of the form (`host`, `port`) referring to the client's address.

server

Contains the server instance.

command

Contains the command (request type). For example, `'GET'`.

path

Contains the request path.

request_version

Contains the version string from the request. For example, `'HTTP/1.0'`.

headers

Holds an instance of the class specified by the `MessageClass` class variable. This instance parses and manages the headers in the HTTP request.

rfile

Contains an input stream, positioned at the start of the optional input data.

wfile

Contains the output stream for writing a response back to the client. Proper adherence to the HTTP protocol must be used when writing to this stream.

`BaseHTTPRequestHandler` has the following class variables:

server_version

Specifies the server software version. You may want to override this. The format is multiple whitespace-separated strings, where each string is of the form `name[/version]`. For example, `'BaseHTTP/0.2'`.

sys_version

Contains the Python system version, in a form usable by the `version_string` method and the `server_version` class variable. For example, 'Python/1.4'.

error_message_format

Specifies a format string for building an error response to the client. It uses parenthesized, keyed format specifiers, so the format operand must be a dictionary. The `code` key should be an integer, specifying the numeric HTTP error code value. `message` should be a string containing a (detailed) error message of what occurred, and `explain` should be an explanation of the error code number. Default `message` and `explain` values can found in the `responses` class variable.

error_content_type

Specifies the Content-Type HTTP header of error responses sent to the client. The default value is 'text/html'.

버전 2.6에 추가: Previously, the content type was always 'text/html'.

protocol_version

This specifies the HTTP protocol version used in responses. If set to 'HTTP/1.1', the server will permit HTTP persistent connections; however, your server *must* then include an accurate Content-Length header (using `send_header()`) in all of its responses to clients. For backwards compatibility, the setting defaults to 'HTTP/1.0'.

MessageClass

Specifies a `rfc822.Message`-like class to parse HTTP headers. Typically, this is not overridden, and it defaults to `mimetools.Message`.

responses

This variable contains a mapping of error code integers to two-element tuples containing a short and long message. For example, {code: (shortmessage, longmessage)}. The `shortmessage` is usually used as the `message` key in an error response, and `longmessage` as the `explain` key (see the `error_message_format` class variable).

A `BaseHTTPRequestHandler` instance has the following methods:

handle()

Calls `handle_one_request()` once (or, if persistent connections are enabled, multiple times) to handle incoming HTTP requests. You should never need to override it; instead, implement appropriate `do_*()` methods.

handle_one_request()

This method will parse and dispatch the request to the appropriate `do_*()` method. You should never need to override it.

send_error(code[, message])

Sends and logs a complete error reply to the client. The numeric `code` specifies the HTTP error code, with `message` as optional, more specific text. A complete set of headers is sent, followed by text composed using the `error_message_format` class variable. The body will be empty if the method is HEAD or the response code is one of the following: 1xx, 204 No Content, 205 Reset Content, 304 Not Modified.

send_response(code[, message])

Sends a response header and logs the accepted request. The HTTP response line is sent, followed by `Server` and `Date` headers. The values for these two headers are picked up from the `version_string()` and `date_time_string()` methods, respectively.

send_header(keyword, value)

Writes a specific HTTP header to the output stream. `keyword` should specify the header keyword, with `value` specifying its value.

end_headers()

Sends a blank line, indicating the end of the HTTP headers in the response.

log_request([code[, size]])

Logs an accepted (successful) request. *code* should specify the numeric HTTP code associated with the response. If a size of the response is available, then it should be passed as the *size* parameter.

log_error(...)

Logs an error when a request cannot be fulfilled. By default, it passes the message to *log_message()*, so it takes the same arguments (*format* and additional values).

log_message(format, ...)

Logs an arbitrary message to `sys.stderr`. This is typically overridden to create custom error logging mechanisms. The *format* argument is a standard printf-style format string, where the additional arguments to *log_message()* are applied as inputs to the formatting. The client ip address and current date and time are prefixed to every message logged.

version_string()

Returns the server software's version string. This is a combination of the *server_version* and *sys_version* class variables.

date_time_string([timestamp])

Returns the date and time given by *timestamp* (which must be in the format returned by *time.time()*), formatted for a message header. If *timestamp* is omitted, it uses the current date and time.

The result looks like 'Sun, 06 Nov 1994 08:49:37 GMT'.

버전 2.5에 추가: The *timestamp* parameter.

log_date_time_string()

Returns the current date and time, formatted for logging.

address_string()

Returns the client address, formatted for logging. A name lookup is performed on the client's IP address.

20.18.1 More examples

To create a server that doesn't run forever, but until some condition is fulfilled:

```
def run_while_true(server_class=BaseHTTPServer.HTTPServer,
                   handler_class=BaseHTTPServer.BaseHTTPRequestHandler):
    """
    This assumes that keep_running() is a function of no arguments which
    is tested initially and after each request. If its return value
    is true, the server continues.
    """
    server_address = ('', 8000)
    httpd = server_class(server_address, handler_class)
    while keep_running():
        httpd.handle_request()
```

더 보기:

Module *CGIHTTPServer* Extended request handler that supports CGI scripts.

Module *SimpleHTTPServer* Basic request handler that limits response to files actually under the document root.

20.19 SimpleHTTPServer — Simple HTTP request handler

참고: The *SimpleHTTPServer* module has been merged into `http.server` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

경고: *SimpleHTTPServer* is not recommended for production. It only implements basic security checks.

The *SimpleHTTPServer* module defines a single class, *SimpleHTTPRequestHandler*, which is interface-compatible with *BaseHTTPServer.BaseHTTPRequestHandler*.

The *SimpleHTTPServer* module defines the following class:

class `SimpleHTTPServer.SimpleHTTPRequestHandler` (*request, client_address, server*)

This class serves files from the current directory and below, directly mapping the directory structure to HTTP requests.

A lot of the work, such as parsing the request, is done by the base class *BaseHTTPServer.BaseHTTPRequestHandler*. This class implements the `do_GET()` and `do_HEAD()` functions.

The following are defined as class-level attributes of *SimpleHTTPRequestHandler*:

server_version

This will be "SimpleHTTP/" + `__version__`, where `__version__` is defined at the module level.

extensions_map

A dictionary mapping suffixes into MIME types. The default is signified by an empty string, and is considered to be `application/octet-stream`. The mapping is used case-insensitively, and so should contain only lower-cased keys.

The *SimpleHTTPRequestHandler* class defines the following methods:

do_HEAD()

This method serves the 'HEAD' request type: it sends the headers it would send for the equivalent GET request. See the `do_GET()` method for a more complete explanation of the possible headers.

do_GET()

The request is mapped to a local file by interpreting the request as a path relative to the current working directory.

If the request was mapped to a directory, the directory is checked for a file named `index.html` or `index.htm` (in that order). If found, the file's contents are returned; otherwise a directory listing is generated by calling the `list_directory()` method. This method uses `os.listdir()` to scan the directory, and returns a 404 error response if the `listdir()` fails.

If the request was mapped to a file, it is opened and the contents are returned. Any *IOError* exception in opening the requested file is mapped to a 404, 'File not found' error. Otherwise, the content type is guessed by calling the `guess_type()` method, which in turn uses the `extensions_map` variable.

A 'Content-type:' header with the guessed content type is output, followed by a 'Content-Length:' header with the file's size and a 'Last-Modified:' header with the file's modification time.

Then follows a blank line signifying the end of the headers, and then the contents of the file are output. If the file's MIME type starts with `text/` the file is opened in text mode; otherwise binary mode is used.

The `test()` function in the `SimpleHTTPServer` module is an example which creates a server using the `SimpleHTTPRequestHandler` as the Handler.

버전 2.5에 추가: The 'Last-Modified' header.

The `SimpleHTTPServer` module can be used in the following manner in order to set up a very basic web server serving files relative to the current directory.

```
import SimpleHTTPServer
import SocketServer

PORT = 8000

Handler = SimpleHTTPServer.SimpleHTTPRequestHandler

httpd = SocketServer.TCPServer(("", PORT), Handler)

print "serving at port", PORT
httpd.serve_forever()
```

The `SimpleHTTPServer` module can also be invoked directly using the `-m` switch of the interpreter with a port number argument. Similar to the previous example, this serves the files relative to the current directory.

```
python -m SimpleHTTPServer 8000
```

더 보기:

Module `BaseHTTPServer` Base class implementation for Web server and request handler.

20.20 CGIHTTPServer — CGI-capable HTTP request handler

참고: The `CGIHTTPServer` module has been merged into `http.server` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

The `CGIHTTPServer` module defines a request-handler class, interface compatible with `BaseHTTPServer.BaseHTTPRequestHandler` and inherits behavior from `SimpleHTTPServer.SimpleHTTPRequestHandler` but can also run CGI scripts.

참고: This module can run CGI scripts on Unix and Windows systems.

참고: CGI scripts run by the `CGIHTTPRequestHandler` class cannot execute redirects (HTTP code 302), because code 200 (script output follows) is sent prior to execution of the CGI script. This pre-empts the status code.

The `CGIHTTPServer` module defines the following class:

class `CGIHTTPServer.CGIHTTPRequestHandler` (*request, client_address, server*)

This class is used to serve either files or output of CGI scripts from the current directory and below. Note that mapping HTTP hierarchic structure to local directory structure is exactly as in `SimpleHTTPServer.SimpleHTTPRequestHandler`.

The class will however, run the CGI script, instead of serving it as a file, if it guesses it to be a CGI script. Only directory-based CGI are used — the other common server configuration is to treat special extensions as denoting

CGI scripts.

The `do_GET()` and `do_HEAD()` functions are modified to run CGI scripts and serve the output, instead of serving files, if the request leads to somewhere below the `cgi_directories` path.

The `CGIHTTPRequestHandler` defines the following data member:

`cgi_directories`

This defaults to `['/cgi-bin', '/htbin']` and describes directories to treat as containing CGI scripts.

The `CGIHTTPRequestHandler` defines the following methods:

`do_POST()`

This method serves the `'POST'` request type, only allowed for CGI scripts. Error 501, 《Can only POST to CGI scripts》, is output when trying to POST to a non-CGI url.

Note that CGI scripts will be run with UID of user nobody, for security reasons. Problems with the CGI script will be translated to error 403.

For example usage, see the implementation of the `test()` function.

더 보기:

Module `BaseHTTPServer` Base class implementation for Web server and request handler.

20.21 `cookielib` — Cookie handling for HTTP clients

참고: The `cookielib` module has been renamed to `http.cookiejar` in Python 3. The [2to3](#) tool will automatically adapt imports when converting your sources to Python 3.

버전 2.4에 추가.

Source code: [Lib/cookiejar.py](#)

The `cookielib` module defines classes for automatic handling of HTTP cookies. It is useful for accessing web sites that require small pieces of data – *cookies* – to be set on the client machine by an HTTP response from a web server, and then returned to the server in later HTTP requests.

Both the regular Netscape cookie protocol and the protocol defined by [RFC 2965](#) are handled. RFC 2965 handling is switched off by default. [RFC 2109](#) cookies are parsed as Netscape cookies and subsequently treated either as Netscape or RFC 2965 cookies according to the `<policy>` in effect. Note that the great majority of cookies on the Internet are Netscape cookies. `cookielib` attempts to follow the de-facto Netscape cookie protocol (which differs substantially from that set out in the original Netscape specification), including taking note of the `max-age` and `port` cookie-attributes introduced with RFC 2965.

참고: The various named parameters found in `Set-Cookie` and `Set-Cookie2` headers (eg. `domain` and `expires`) are conventionally referred to as *attributes*. To distinguish them from Python attributes, the documentation for this module uses the term *cookie-attribute* instead.

The module defines the following exception:

exception `cookielib.LoadError`

Instances of `FileCookieJar` raise this exception on failure to load cookies from a file.

참고: For backwards-compatibility with Python 2.4 (which raised an *IOError*), *LoadError* is a subclass of *IOError*.

The following classes are provided:

class `cookielib.CookieJar` (*policy=None*)
policy is an object implementing the *CookiePolicy* interface.

The *CookieJar* class stores HTTP cookies. It extracts cookies from HTTP requests, and returns them in HTTP responses. *CookieJar* instances automatically expire contained cookies when necessary. Subclasses are also responsible for storing and retrieving cookies from a file or database.

class `cookielib.FileCookieJar` (*filename, delayload=None, policy=None*)
policy is an object implementing the *CookiePolicy* interface. For the other arguments, see the documentation for the corresponding attributes.

A *CookieJar* which can load cookies from, and perhaps save cookies to, a file on disk. Cookies are **NOT** loaded from the named file until either the *load()* or *revert()* method is called. Subclasses of this class are documented in section *FileCookieJar subclasses and co-operation with web browsers*.

class `cookielib.CookiePolicy`
This class is responsible for deciding whether each cookie should be accepted from / returned to the server.

class `cookielib.DefaultCookiePolicy` (*blocked_domains=None, allowed_domains=None, netscape=True, rfc2965=False, rfc2109_as_netscape=None, hide_cookie2=False, strict_domain=False, strict_rfc2965_unverifiable=True, strict_ns_unverifiable=False, strict_ns_domain=DefaultCookiePolicy.DomainLiberal, strict_ns_set_initial_dollar=False, strict_ns_set_path=False*)

Constructor arguments should be passed as keyword arguments only. *blocked_domains* is a sequence of domain names that we never accept cookies from, nor return cookies to. *allowed_domains* if not *None*, this is a sequence of the only domains for which we accept and return cookies. For all other arguments, see the documentation for *CookiePolicy* and *DefaultCookiePolicy* objects.

DefaultCookiePolicy implements the standard accept / reject rules for Netscape and RFC 2965 cookies. By default, RFC 2109 cookies (ie. cookies received in a *Set-Cookie* header with a version cookie-attribute of 1) are treated according to the RFC 2965 rules. However, if RFC 2965 handling is turned off or *rfc2109_as_netscape* is *True*, RFC 2109 cookies are <downgraded> by the *CookieJar* instance to Netscape cookies, by setting the *version* attribute of the *Cookie* instance to 0. *DefaultCookiePolicy* also provides some parameters to allow some fine-tuning of policy.

class `cookielib.Cookie`
This class represents Netscape, RFC 2109 and RFC 2965 cookies. It is not expected that users of *cookielib* construct their own *Cookie* instances. Instead, if necessary, call *make_cookies()* on a *CookieJar* instance.

더 보기:

Module *urllib2* URL opening with automatic cookie handling.

Module *Cookie* HTTP cookie classes, principally useful for server-side code. The *cookielib* and *Cookie* modules do not depend on each other.

https://curl.haxx.se/rfc/cookie_spec.html The specification of the original Netscape cookie protocol. Though this is still the dominant protocol, the <Netscape cookie protocol> implemented by all the major browsers (and *cookielib*) only bears a passing resemblance to the one sketched out in *cookie_spec.html*.

RFC 2109 - HTTP State Management Mechanism Obsoleted by RFC 2965. Uses *Set-Cookie* with version=1.

RFC 2965 - HTTP State Management Mechanism The Netscape protocol with the bugs fixed. Uses *Set-Cookie2* in place of *Set-Cookie*. Not widely used.

<http://kristol.org/cookie/errata.html> Unfinished errata to RFC 2965.

RFC 2964 - Use of HTTP State Management

20.21.1 CookieJar and FileCookieJar Objects

CookieJar objects support the *iterator* protocol for iterating over contained *Cookie* objects.

CookieJar has the following methods:

`CookieJar.add_cookie_header(request)`

Add correct *Cookie* header to *request*.

If policy allows (ie. the `rfc2965` and `hide_cookie2` attributes of the *CookieJar*'s *CookiePolicy* instance are true and false respectively), the *Cookie2* header is also added when appropriate.

The *request* object (usually a *urllib2.Request* instance) must support the methods `get_full_url()`, `get_host()`, `get_type()`, `unverifiable()`, `get_origin_req_host()`, `has_header()`, `get_header()`, `header_items()`, and `add_unredirected_header()`, as documented by *urllib2*.

`CookieJar.extract_cookies(response, request)`

Extract cookies from HTTP *response* and store them in the *CookieJar*, where allowed by policy.

The *CookieJar* will look for allowable *Set-Cookie* and *Set-Cookie2* headers in the *response* argument, and store cookies as appropriate (subject to the *CookiePolicy.set_ok()* method's approval).

The *response* object (usually the result of a call to *urllib2.urlopen()*, or similar) should support an `info()` method, which returns an object with a `getallmatchingheaders()` method (usually a *mimetypes.Message* instance).

The *request* object (usually a *urllib2.Request* instance) must support the methods `get_full_url()`, `get_host()`, `unverifiable()`, and `get_origin_req_host()`, as documented by *urllib2*. The request is used to set default values for cookie-attributes as well as for checking that the cookie is allowed to be set.

`CookieJar.set_policy(policy)`

Set the *CookiePolicy* instance to be used.

`CookieJar.make_cookies(response, request)`

Return sequence of *Cookie* objects extracted from *response* object.

See the documentation for `extract_cookies()` for the interfaces required of the *response* and *request* arguments.

`CookieJar.set_cookie_if_ok(cookie, request)`

Set a *Cookie* if policy says it's OK to do so.

`CookieJar.set_cookie(cookie)`

Set a *Cookie*, without checking with policy to see whether or not it should be set.

`CookieJar.clear([domain[, path[, name]])`

Clear some cookies.

If invoked without arguments, clear all cookies. If given a single argument, only cookies belonging to that *domain* will be removed. If given two arguments, cookies belonging to the specified *domain* and URL *path* are removed. If given three arguments, then the cookie with the specified *domain*, *path* and *name* is removed.

Raises `KeyError` if no matching cookie exists.

`CookieJar.clear_session_cookies()`

Discard all session cookies.

Discards all contained cookies that have a true `discard` attribute (usually because they had either no `max-age` or `expires` cookie-attribute, or an explicit `discard` cookie-attribute). For interactive browsers, the end of a session usually corresponds to closing the browser window.

Note that the `save()` method won't save session cookies anyway, unless you ask otherwise by passing a true `ignore_discard` argument.

`FileCookieJar` implements the following additional methods:

`FileCookieJar.save(filename=None, ignore_discard=False, ignore_expires=False)`

Save cookies to a file.

This base class raises `NotImplementedError`. Subclasses may leave this method unimplemented.

filename is the name of file in which to save cookies. If *filename* is not specified, `self.filename` is used (whose default is the value passed to the constructor, if any); if `self.filename` is `None`, `ValueError` is raised.

ignore_discard: save even cookies set to be discarded. *ignore_expires*: save even cookies that have expired

The file is overwritten if it already exists, thus wiping all the cookies it contains. Saved cookies can be restored later using the `load()` or `revert()` methods.

`FileCookieJar.load(filename=None, ignore_discard=False, ignore_expires=False)`

Load cookies from a file.

Old cookies are kept unless overwritten by newly loaded ones.

Arguments are as for `save()`.

The named file must be in the format understood by the class, or `LoadError` will be raised. Also, `IOError` may be raised, for example if the file does not exist.

참고: For backwards-compatibility with Python 2.4 (which raised an `IOError`), `LoadError` is a subclass of `IOError`.

`FileCookieJar.revert(filename=None, ignore_discard=False, ignore_expires=False)`

Clear all cookies and reload cookies from a saved file.

`revert()` can raise the same exceptions as `load()`. If there is a failure, the object's state will not be altered.

`FileCookieJar` instances have the following public attributes:

`FileCookieJar.filename`

Filename of default file in which to keep cookies. This attribute may be assigned to.

`FileCookieJar.delayload`

If true, load cookies lazily from disk. This attribute should not be assigned to. This is only a hint, since this only affects performance, not behaviour (unless the cookies on disk are changing). A `CookieJar` object may ignore it. None of the `FileCookieJar` classes included in the standard library lazily loads cookies.

20.21.2 FileCookieJar subclasses and co-operation with web browsers

The following *CookieJar* subclasses are provided for reading and writing.

class `cookielib.MozillaCookieJar` (*filename*, *delayload=None*, *policy=None*)

A *FileCookieJar* that can load from and save cookies to disk in the Mozilla `cookies.txt` file format (which is also used by the Lynx and Netscape browsers).

참고: Version 3 of the Firefox web browser no longer writes cookies in the `cookies.txt` file format.

참고: This loses information about RFC 2965 cookies, and also about newer or non-standard cookie-attributes such as `port`.

경고: Back up your cookies before saving if you have cookies whose loss / corruption would be inconvenient (there are some subtleties which may lead to slight changes in the file over a load / save round-trip).

Also note that cookies saved while Mozilla is running will get clobbered by Mozilla.

class `cookielib.LWPCookieJar` (*filename*, *delayload=None*, *policy=None*)

A *FileCookieJar* that can load from and save cookies to disk in format compatible with the libwww-perl library's Set-Cookie3 file format. This is convenient if you want to store cookies in a human-readable file.

20.21.3 CookiePolicy Objects

Objects implementing the *CookiePolicy* interface have the following methods:

`CookiePolicy.set_ok(cookie, request)`

Return boolean value indicating whether cookie should be accepted from server.

cookie is a `cookielib.Cookie` instance. *request* is an object implementing the interface defined by the documentation for `CookieJar.extract_cookies()`.

`CookiePolicy.return_ok(cookie, request)`

Return boolean value indicating whether cookie should be returned to server.

cookie is a `cookielib.Cookie` instance. *request* is an object implementing the interface defined by the documentation for `CookieJar.add_cookie_header()`.

`CookiePolicy.domain_return_ok(domain, request)`

Return false if cookies should not be returned, given cookie domain.

This method is an optimization. It removes the need for checking every cookie with a particular domain (which might involve reading many files). Returning true from `domain_return_ok()` and `path_return_ok()` leaves all the work to `return_ok()`.

If `domain_return_ok()` returns true for the cookie domain, `path_return_ok()` is called for the cookie path. Otherwise, `path_return_ok()` and `return_ok()` are never called for that cookie domain. If `path_return_ok()` returns true, `return_ok()` is called with the *Cookie* object itself for a full check. Otherwise, `return_ok()` is never called for that cookie path.

Note that `domain_return_ok()` is called for every *cookie* domain, not just for the *request* domain. For example, the function might be called with both `".example.com"` and `"www.example.com"` if the request domain is `"www.example.com"`. The same goes for `path_return_ok()`.

The *request* argument is as documented for `return_ok()`.

`CookiePolicy.path_return_ok(path, request)`

Return false if cookies should not be returned, given cookie path.

See the documentation for `domain_return_ok()`.

In addition to implementing the methods above, implementations of the `CookiePolicy` interface must also supply the following attributes, indicating which protocols should be used, and how. All of these attributes may be assigned to.

`CookiePolicy.netscape`

Implement Netscape protocol.

`CookiePolicy.rfc2965`

Implement RFC 2965 protocol.

`CookiePolicy.hide_cookie2`

Don't add `Cookie2` header to requests (the presence of this header indicates to the server that we understand RFC 2965 cookies).

The most useful way to define a `CookiePolicy` class is by subclassing from `DefaultCookiePolicy` and overriding some or all of the methods above. `CookiePolicy` itself may be used as a `<null policy>` to allow setting and receiving any and all cookies (this is unlikely to be useful).

20.21.4 DefaultCookiePolicy Objects

Implements the standard rules for accepting and returning cookies.

Both RFC 2965 and Netscape cookies are covered. RFC 2965 handling is switched off by default.

The easiest way to provide your own policy is to override this class and call its methods in your overridden implementations before adding your own additional checks:

```
import cookielib
class MyCookiePolicy(cockielib.DefaultCookiePolicy):
    def set_ok(self, cookie, request):
        if not cookielib.DefaultCookiePolicy.set_ok(self, cookie, request):
            return False
        if i_dont_want_to_store_this_cookie(cookie):
            return False
        return True
```

In addition to the features required to implement the `CookiePolicy` interface, this class allows you to block and allow domains from setting and receiving cookies. There are also some strictness switches that allow you to tighten up the rather loose Netscape protocol rules a little bit (at the cost of blocking some benign cookies).

A domain blacklist and whitelist is provided (both off by default). Only domains not in the blacklist and present in the whitelist (if the whitelist is active) participate in cookie setting and returning. Use the `blocked_domains` constructor argument, and `blocked_domains()` and `set_blocked_domains()` methods (and the corresponding argument and methods for `allowed_domains`). If you set a whitelist, you can turn it off again by setting it to `None`.

Domains in block or allow lists that do not start with a dot must equal the cookie domain to be matched. For example, `"example.com"` matches a blacklist entry of `"example.com"`, but `"www.example.com"` does not. Domains that do start with a dot are matched by more specific domains too. For example, both `"www.example.com"` and `"www.coyote.example.com"` match `".example.com"` (but `"example.com"` itself does not). IP addresses are an exception, and must match exactly. For example, if `blocked_domains` contains `"192.168.1.2"` and `".168.1.2"`, `192.168.1.2` is blocked, but `193.168.1.2` is not.

`DefaultCookiePolicy` implements the following additional methods:

`DefaultCookiePolicy.blocked_domains()`

Return the sequence of blocked domains (as a tuple).

`DefaultCookiePolicy.set_blocked_domains(blocked_domains)`

Set the sequence of blocked domains.

`DefaultCookiePolicy.is_blocked(domain)`

Return whether *domain* is on the blacklist for setting or receiving cookies.

`DefaultCookiePolicy.allowed_domains()`

Return *None*, or the sequence of allowed domains (as a tuple).

`DefaultCookiePolicy.set_allowed_domains(allowed_domains)`

Set the sequence of allowed domains, or *None*.

`DefaultCookiePolicy.is_not_allowed(domain)`

Return whether *domain* is not on the whitelist for setting or receiving cookies.

DefaultCookiePolicy instances have the following attributes, which are all initialised from the constructor arguments of the same name, and which may all be assigned to.

`DefaultCookiePolicy.rfc2109_as_netscape`

If true, request that the *CookieJar* instance downgrade RFC 2109 cookies (ie. cookies received in a *Set-Cookie* header with a version cookie-attribute of 1) to Netscape cookies by setting the version attribute of the *Cookie* instance to 0. The default value is *None*, in which case RFC 2109 cookies are downgraded if and only if RFC 2965 handling is turned off. Therefore, RFC 2109 cookies are downgraded by default.

버전 2.5에 추가.

General strictness switches:

`DefaultCookiePolicy.strict_domain`

Don't allow sites to set two-component domains with country-code top-level domains like *.co.uk*, *.gov.uk*, *.co.nz*.etc. This is far from perfect and isn't guaranteed to work!

RFC 2965 protocol strictness switches:

`DefaultCookiePolicy.strict_rfc2965_unverifiable`

Follow RFC 2965 rules on unverifiable transactions (usually, an unverifiable transaction is one resulting from a redirect or a request for an image hosted on another site). If this is false, cookies are *never* blocked on the basis of verifiability

Netscape protocol strictness switches:

`DefaultCookiePolicy.strict_ns_unverifiable`

Apply RFC 2965 rules on unverifiable transactions even to Netscape cookies.

`DefaultCookiePolicy.strict_ns_domain`

Flags indicating how strict to be with domain-matching rules for Netscape cookies. See below for acceptable values.

`DefaultCookiePolicy.strict_ns_set_initial_dollar`

Ignore cookies in Set-Cookie: headers that have names starting with '\$'.

`DefaultCookiePolicy.strict_ns_set_path`

Don't allow setting cookies whose path doesn't path-match request URI.

strict_ns_domain is a collection of flags. Its value is constructed by or-ing together (for example, *DomainStrictNoDots|DomainStrictNonDomain* means both flags are set).

`DefaultCookiePolicy.DomainStrictNoDots`

When setting cookies, the <host prefix> must not contain a dot (eg. *www.foo.bar.com* can't set a cookie for *.bar.com*, because *www.foo* contains a dot).

`DefaultCookiePolicy.DomainStrictNonDomain`

Cookies that did not explicitly specify a domain cookie-attribute can only be returned to a domain equal to the domain that set the cookie (eg. `spam.example.com` won't be returned cookies from `example.com` that had no domain cookie-attribute).

`DefaultCookiePolicy.DomainRFC2965Match`

When setting cookies, require a full RFC 2965 domain-match.

The following attributes are provided for convenience, and are the most useful combinations of the above flags:

`DefaultCookiePolicy.DomainLiberal`

Equivalent to 0 (ie. all of the above Netscape domain strictness flags switched off).

`DefaultCookiePolicy.DomainStrict`

Equivalent to `DomainStrictNoDots|DomainStrictNonDomain`.

20.21.5 Cookie Objects

Cookie instances have Python attributes roughly corresponding to the standard cookie-attributes specified in the various cookie standards. The correspondence is not one-to-one, because there are complicated rules for assigning default values, because the `max-age` and `expires` cookie-attributes contain equivalent information, and because RFC 2109 cookies may be <downgraded> by *cookielib* from version 1 to version 0 (Netscape) cookies.

Assignment to these attributes should not be necessary other than in rare circumstances in a *CookiePolicy* method. The class does not enforce internal consistency, so you should know what you're doing if you do that.

`Cookie.version`

Integer or *None*. Netscape cookies have *version* 0. RFC 2965 and RFC 2109 cookies have a *version* cookie-attribute of 1. However, note that *cookielib* may <downgrade> RFC 2109 cookies to Netscape cookies, in which case *version* is 0.

`Cookie.name`

Cookie name (a string).

`Cookie.value`

Cookie value (a string), or *None*.

`Cookie.port`

String representing a port or a set of ports (eg. `<80>`, or `<80,8080>`), or *None*.

`Cookie.path`

Cookie path (a string, eg. `'/acme/rocket_launchers'`).

`Cookie.secure`

True if cookie should only be returned over a secure connection.

`Cookie.expires`

Integer expiry date in seconds since epoch, or *None*. See also the *is_expired()* method.

`Cookie.discard`

True if this is a session cookie.

`Cookie.comment`

String comment from the server explaining the function of this cookie, or *None*.

`Cookie.comment_url`

URL linking to a comment from the server explaining the function of this cookie, or *None*.

`Cookie.rfc2109`

True if this cookie was received as an RFC 2109 cookie (ie. the cookie arrived in a *Set-Cookie* header, and

the value of the Version cookie-attribute in that header was 1). This attribute is provided because *cookielib* may <downgrade> RFC 2109 cookies to Netscape cookies, in which case *version* is 0.

버전 2.5에 추가.

`Cookie.port_specified`

True if a port or set of ports was explicitly specified by the server (in the *Set-Cookie* / *Set-Cookie2* header).

`Cookie.domain_specified`

True if a domain was explicitly specified by the server.

`Cookie.domain_initial_dot`

True if the domain explicitly specified by the server began with a dot ('.').

Cookies may have additional non-standard cookie-attributes. These may be accessed using the following methods:

`Cookie.has_nonstandard_attr(name)`

Return true if cookie has the named cookie-attribute.

`Cookie.get_nonstandard_attr(name, default=None)`

If cookie has the named cookie-attribute, return its value. Otherwise, return *default*.

`Cookie.set_nonstandard_attr(name, value)`

Set the value of the named cookie-attribute.

The *Cookie* class also defines the following method:

`Cookie.is_expired([now=None])`

True if cookie has passed the time at which the server requested it should expire. If *now* is given (in seconds since the epoch), return whether the cookie has expired at the specified time.

20.21.6 Examples

The first example shows the most common usage of *cookielib*:

```
import cookielib, urllib2
cj = cookielib.CookieJar()
opener = urllib2.build_opener(urllib2.HTTPCookieProcessor(cj))
r = opener.open("http://example.com/")
```

This example illustrates how to open a URL using your Netscape, Mozilla, or Lynx cookies (assumes Unix/Netscape convention for location of the cookies file):

```
import os, cookielib, urllib2
cj = cookielib.MozillaCookieJar()
cj.load(os.path.join(os.path.expanduser("~"), ".netscape", "cookies.txt"))
opener = urllib2.build_opener(urllib2.HTTPCookieProcessor(cj))
r = opener.open("http://example.com/")
```

The next example illustrates the use of *DefaultCookiePolicy*. Turn on RFC 2965 cookies, be more strict about domains when setting and returning Netscape cookies, and block some domains from setting cookies or having them returned:

```
import urllib2
from cookielib import CookieJar, DefaultCookiePolicy
policy = DefaultCookiePolicy(
    rfc2965=True, strict_ns_domain=DefaultCookiePolicy.DomainStrict,
    blocked_domains=["ads.net", ".ads.net"])
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
cj = CookieJar(policy)
opener = urllib2.build_opener(urllib2.HTTPCookieProcessor(cj))
r = opener.open("http://example.com/")
```

20.22 Cookie — HTTP state management

참고: The *Cookie* module has been renamed to `http.cookies` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

Source code: `Lib/Cookie.py`

The *Cookie* module defines classes for abstracting the concept of cookies, an HTTP state management mechanism. It supports both simple string-only cookies, and provides an abstraction for having any serializable data-type as cookie value.

The module formerly strictly applied the parsing rules described in the [RFC 2109](#) and [RFC 2068](#) specifications. It has since been discovered that MSIE 3.0x doesn't follow the character rules outlined in those specs and also many current day browsers and servers have relaxed parsing rules when comes to Cookie handling. As a result, the parsing rules used are a bit less strict.

The character set, `string.ascii_letters`, `string.digits` and `!#$%&'*+-.^_`|~` denote the set of valid characters allowed by this module in Cookie name (as *key*).

참고: On encountering an invalid cookie, *CookieError* is raised, so if your cookie data comes from a browser you should always prepare for invalid data and catch *CookieError* on parsing.

exception `Cookie.CookieError`

Exception failing because of [RFC 2109](#) invalidity: incorrect attributes, incorrect *Set-Cookie* header, etc.

class `Cookie.BaseCookie([input])`

This class is a dictionary-like object whose keys are strings and whose values are *Morsel* instances. Note that upon setting a key to a value, the value is first converted to a *Morsel* containing the key and the value.

If *input* is given, it is passed to the `load()` method.

class `Cookie.SimpleCookie([input])`

This class derives from *BaseCookie* and overrides `value_decode()` and `value_encode()` to be the identity and `str()` respectively.

class `Cookie.SerialCookie([input])`

This class derives from *BaseCookie* and overrides `value_decode()` and `value_encode()` to be the `pickle.loads()` and `pickle.dumps()`.

버전 2.3부터 폐지: Reading pickled values from untrusted cookie data is a huge security hole, as pickle strings can be crafted to cause arbitrary code to execute on your server. It is supported for backwards compatibility only, and may eventually go away.

class `Cookie.SmartCookie([input])`

This class derives from *BaseCookie*. It overrides `value_decode()` to be `pickle.loads()` if it is a valid pickle, and otherwise the value itself. It overrides `value_encode()` to be `pickle.dumps()` unless it is a string, in which case it returns the value itself.

버전 2.3부터 폐지: The same security warning from *SerialCookie* applies here.

A further security note is warranted. For backwards compatibility, the *Cookie* module exports a class named *Cookie* which is just an alias for *SmartCookie*. This is probably a mistake and will likely be removed in a future version. You should not use the *Cookie* class in your applications, for the same reason why you should not use the *SerialCookie* class.

더 보기:

Module *cookielib* HTTP cookie handling for web *clients*. The *cookielib* and *Cookie* modules do not depend on each other.

RFC 2109 - HTTP State Management Mechanism This is the state management specification implemented by this module.

20.22.1 Cookie Objects

BaseCookie.**value_decode**(*val*)

Return a decoded value from a string representation. Return value can be any type. This method does nothing in *BaseCookie* — it exists so it can be overridden.

BaseCookie.**value_encode**(*val*)

Return an encoded value. *val* can be any type, but return value must be a string. This method does nothing in *BaseCookie* — it exists so it can be overridden.

In general, it should be the case that *value_encode()* and *value_decode()* are inverses on the range of *value_decode*.

BaseCookie.**output**(*[attrs[, header[, sep]]]*)

Return a string representation suitable to be sent as HTTP headers. *attrs* and *header* are sent to each *Morsel*'s *output()* method. *sep* is used to join the headers together, and is by default the combination '*\r\n*' (CRLF).

버전 2.5에서 변경: The default separator has been changed from '*\n*' to match the cookie specification.

BaseCookie.**js_output**(*[attrs]*)

Return an embeddable JavaScript snippet, which, if run on a browser which supports JavaScript, will act the same as if the HTTP headers was sent.

The meaning for *attrs* is the same as in *output()*.

BaseCookie.**load**(*rawdata*)

If *rawdata* is a string, parse it as an HTTP_COOKIE and add the values found there as *Morsels*. If it is a dictionary, it is equivalent to:

```
for k, v in rawdata.items():
    cookie[k] = v
```

20.22.2 Morsel Objects

class *Cookie.Morsel*

Abstract a key/value pair, which has some **RFC 2109** attributes.

Morsels are dictionary-like objects, whose set of keys is constant — the valid **RFC 2109** attributes, which are

- expires
- path
- comment

- domain
- max-age
- secure
- version
- httponly

The attribute `httponly` specifies that the cookie is only transferred in HTTP requests, and is not accessible through JavaScript. This is intended to mitigate some forms of cross-site scripting.

The keys are case-insensitive.

버전 2.6에 추가: The `httponly` attribute was added.

Morsel.value

The value of the cookie.

Morsel.coded_value

The encoded value of the cookie — this is what should be sent.

Morsel.key

The name of the cookie.

Morsel.set (*key*, *value*, *coded_value*)

Set the *key*, *value* and *coded_value* attributes.

Morsel.isReservedKey (*K*)

Whether *K* is a member of the set of keys of a *Morsel*.

Morsel.output ([*attrs*, *header*])

Return a string representation of the Morsel, suitable to be sent as an HTTP header. By default, all the attributes are included, unless *attrs* is given, in which case it should be a list of attributes to use. *header* is by default "Set-Cookie:".

Morsel.js_output ([*attrs*])

Return an embeddable JavaScript snippet, which, if run on a browser which supports JavaScript, will act the same as if the HTTP header was sent.

The meaning for *attrs* is the same as in *output* ().

Morsel.OutputString ([*attrs*])

Return a string representing the Morsel, without any surrounding HTTP or JavaScript.

The meaning for *attrs* is the same as in *output* ().

20.22.3 Example

The following example demonstrates how to use the *Cookie* module.

```
>>> import Cookie
>>> C = Cookie.SimpleCookie()
>>> C["fig"] = "newton"
>>> C["sugar"] = "wafer"
>>> print C # generate HTTP headers
Set-Cookie: fig=newton
Set-Cookie: sugar=wafer
>>> print C.output() # same thing
Set-Cookie: fig=newton
Set-Cookie: sugar=wafer
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

>>> C = Cookie.SimpleCookie()
>>> C["rocky"] = "road"
>>> C["rocky"]["path"] = "/cookie"
>>> print C.output(header="Cookie:")
Cookie: rocky=road; Path=/cookie
>>> print C.output(attrs=[], header="Cookie:")
Cookie: rocky=road
>>> C = Cookie.SimpleCookie()
>>> C.load("chips=ahoy; vienna=finger") # load from a string (HTTP header)
>>> print C
Set-Cookie: chips=ahoy
Set-Cookie: vienna=finger
>>> C = Cookie.SimpleCookie()
>>> C.load('keebler="E=everybody; L=\\"Loves\\"; fudge=\012;"')
>>> print C
Set-Cookie: keebler="E=everybody; L=\\"Loves\\"; fudge=\012;"
>>> C = Cookie.SimpleCookie()
>>> C["oreo"] = "doublestuff"
>>> C["oreo"]["path"] = "/"
>>> print C
Set-Cookie: oreo=doublestuff; Path=/
>>> C["twix"] = "none for you"
>>> C["twix"].value
'none for you'
>>> C = Cookie.SimpleCookie()
>>> C["number"] = 7 # equivalent to C["number"] = str(7)
>>> C["string"] = "seven"
>>> C["number"].value
'7'
>>> C["string"].value
'seven'
>>> print C
Set-Cookie: number=7
Set-Cookie: string=seven
>>> # SerialCookie and SmartCookie are deprecated
>>> # using it can cause security loopholes in your code.
>>> C = Cookie.SerialCookie()
>>> C["number"] = 7
>>> C["string"] = "seven"
>>> C["number"].value
7
>>> C["string"].value
'seven'
>>> print C
Set-Cookie: number="I7\012."
Set-Cookie: string="S'seven'\012p1\012."
>>> C = Cookie.SmartCookie()
>>> C["number"] = 7
>>> C["string"] = "seven"
>>> C["number"].value
7
>>> C["string"].value
'seven'
>>> print C
Set-Cookie: number="I7\012."
Set-Cookie: string=seven

```

20.23 xmlrpclib — XML-RPC client access

참고: The `xmlrpclib` module has been renamed to `xmlrpc.client` in Python 3. The [2to3](#) tool will automatically adapt imports when converting your sources to Python 3.

버전 2.2에 추가.

Source code: [Lib/xmlrpclib.py](#)

XML-RPC is a Remote Procedure Call method that uses XML passed via HTTP(S) as a transport. With it, a client can call methods with parameters on a remote server (the server is named by a URI) and get back structured data. This module supports writing XML-RPC client code; it handles all the details of translating between conformable Python objects and XML on the wire.

경고: The `xmlrpclib` module is not secure against maliciously constructed data. If you need to parse untrusted or unauthenticated data see [XML vulnerabilities](#).

버전 2.7.9에서 변경: For HTTPS URIs, `xmlrpclib` now performs all the necessary certificate and hostname checks by default.

class `xmlrpclib.ServerProxy` (`uri`[, `transport`[, `encoding`[, `verbose`[, `allow_none`[, `use_datetime`[, `context`]]]]])

A `ServerProxy` instance is an object that manages communication with a remote XML-RPC server. The required first argument is a URI (Uniform Resource Indicator), and will normally be the URL of the server. The optional second argument is a transport factory instance; by default it is an internal `SafeTransport` instance for https: URLs and an internal `HTTPTransport` instance otherwise. The optional third argument is an encoding, by default UTF-8. The optional fourth argument is a debugging flag.

The following parameters govern the use of the returned proxy instance. If `allow_none` is true, the Python constant `None` will be translated into XML; the default behaviour is for `None` to raise a `TypeError`. This is a commonly-used extension to the XML-RPC specification, but isn't supported by all clients and servers; see <http://ontosys.com/xml-rpc/extensions.php> for a description. The `use_datetime` flag can be used to cause date/time values to be presented as `datetime.datetime` objects; this is false by default. `datetime.datetime` objects may be passed to calls.

Both the HTTP and HTTPS transports support the URL syntax extension for HTTP Basic Authentication: `http://user:pass@host:port/path`. The `user:pass` portion will be base64-encoded as an HTTP `<Authorization>` header, and sent to the remote server as part of the connection process when invoking an XML-RPC method. You only need to use this if the remote server requires a Basic Authentication user and password. If an HTTPS URL is provided, `context` may be `ssl.SSLContext` and configures the SSL settings of the underlying HTTPS connection.

The returned instance is a proxy object with methods that can be used to invoke corresponding RPC calls on the remote server. If the remote server supports the introspection API, the proxy can also be used to query the remote server for the methods it supports (service discovery) and fetch other server-associated metadata.

Types that are conformable (e.g. that can be marshalled through XML), include the following (and except where noted, they are unmarshalled as the same Python type):

XML-RPC type	Python type
boolean	<i>bool</i>
int or i4	<i>int</i> or <i>long</i> in range from -2147483648 to 2147483647.
double	<i>float</i>
string	<i>str</i> or <i>unicode</i>
array	list or <i>tuple</i> containing conformable elements. Arrays are returned as lists.
struct	<i>dict</i> . Keys must be strings, values may be any conformable type. Objects of user-defined classes can be passed in; only their <code>__dict__</code> attribute is transmitted.
<code>dateTime.iso8601</code>	<i>DateTime</i> or <i>datetime.datetime</i> . Returned type depends on values of the <i>use_datetime</i> flags.
base64	<i>Binary</i>
nil	The <code>None</code> constant. Passing is allowed only if <i>allow_none</i> is true.

This is the full set of data types supported by XML-RPC. Method calls may also raise a special *Fault* instance, used to signal XML-RPC server errors, or *ProtocolError* used to signal an error in the HTTP/HTTPS transport layer. Both *Fault* and *ProtocolError* derive from a base class called `Error`. Note that even though starting with Python 2.2 you can subclass built-in types, the `xmlrpclib` module currently does not marshal instances of such subclasses.

When passing strings, characters special to XML such as `<`, `>`, and `&` will be automatically escaped. However, it's the caller's responsibility to ensure that the string is free of characters that aren't allowed in XML, such as the control characters with ASCII values between 0 and 31 (except, of course, tab, newline and carriage return); failing to do this will result in an XML-RPC request that isn't well-formed XML. If you have to pass arbitrary strings via XML-RPC, use the *Binary* wrapper class described below.

`Server` is retained as an alias for *ServerProxy* for backwards compatibility. New code should use *ServerProxy*.

버전 2.5에서 변경: The *use_datetime* flag was added.

버전 2.6에서 변경: Instances of *new-style classes* can be passed in if they have an `__dict__` attribute and don't have a base class that is marshalled in a special way.

버전 2.7.9에서 변경: Added the *context* argument.

더 보기:

XML-RPC HOWTO A good description of XML-RPC operation and client software in several languages. Contains pretty much everything an XML-RPC client developer needs to know.

XML-RPC Introspection Describes the XML-RPC protocol extension for introspection.

XML-RPC Specification The official specification.

Unofficial XML-RPC Errata Fredrik Lundh's «unofficial errata, intended to clarify certain details in the XML-RPC specification, as well as hint at «best practices» to use when designing your own XML-RPC implementations.»

20.23.1 ServerProxy Objects

A *ServerProxy* instance has a method corresponding to each remote procedure call accepted by the XML-RPC server. Calling the method performs an RPC, dispatched by both name and argument signature (e.g. the same method name can be overloaded with multiple argument signatures). The RPC finishes by returning a value, which may be either returned data in a conformant type or a *Fault* or *ProtocolError* object indicating an error.

Servers that support the XML introspection API support some common methods grouped under the reserved `system` attribute:

`ServerProxy.system.listMethods()`

This method returns a list of strings, one for each (non-system) method supported by the XML-RPC server.

`ServerProxy.system.methodSignature(name)`

This method takes one parameter, the name of a method implemented by the XML-RPC server. It returns an array of possible signatures for this method. A signature is an array of types. The first of these types is the return type of the method, the rest are parameters.

Because multiple signatures (ie. overloading) is permitted, this method returns a list of signatures rather than a singleton.

Signatures themselves are restricted to the top level parameters expected by a method. For instance if a method expects one array of structs as a parameter, and it returns a string, its signature is simply `⟨string, array⟩`. If it expects three integers and returns a string, its signature is `⟨string, int, int, int⟩`.

If no signature is defined for the method, a non-array value is returned. In Python this means that the type of the returned value will be something other than list.

`ServerProxy.system.methodHelp(name)`

This method takes one parameter, the name of a method implemented by the XML-RPC server. It returns a documentation string describing the use of that method. If no such string is available, an empty string is returned. The documentation string may contain HTML markup.

20.23.2 Boolean Objects

This class may be initialized from any Python value; the instance returned depends only on its truth value. It supports various Python operators through `__cmp__()`, `__repr__()`, `__int__()`, and `__nonzero__()` methods, all implemented in the obvious ways.

It also has the following method, supported mainly for internal use by the unmarshalling code:

`Boolean.encode(out)`

Write the XML-RPC encoding of this Boolean item to the out stream object.

A working example follows. The server code:

```
import xmlrpclib
from SimpleXMLRPCServer import SimpleXMLRPCServer

def is_even(n):
    return n % 2 == 0

server = SimpleXMLRPCServer(("localhost", 8000))
print "Listening on port 8000..."
server.register_function(is_even, "is_even")
server.serve_forever()
```

The client code for the preceding server:

```
import xmlrpclib

proxy = xmlrpclib.ServerProxy("http://localhost:8000/")
print "3 is even: %s" % str(proxy.is_even(3))
print "100 is even: %s" % str(proxy.is_even(100))
```

20.23.3 DateTime Objects

class xmlrpclib.DateTime

This class may be initialized with seconds since the epoch, a time tuple, an ISO 8601 time/date string, or a *datetime.datetime* instance. It has the following methods, supported mainly for internal use by the marshalling/unmarshalling code:

decode (*string*)

Accept a string as the instance's new time value.

encode (*out*)

Write the XML-RPC encoding of this *DateTime* item to the *out* stream object.

It also supports certain of Python's built-in operators through `__cmp__()` and `__repr__()` methods.

A working example follows. The server code:

```
import datetime
from SimpleXMLRPCServer import SimpleXMLRPCServer
import xmlrpclib

def today():
    today = datetime.datetime.today()
    return xmlrpclib.DateTime(today)

server = SimpleXMLRPCServer(("localhost", 8000))
print "Listening on port 8000..."
server.register_function(today, "today")
server.serve_forever()
```

The client code for the preceding server:

```
import xmlrpclib
import datetime

proxy = xmlrpclib.ServerProxy("http://localhost:8000/")

today = proxy.today()
# convert the ISO8601 string to a datetime object
converted = datetime.datetime.strptime(today.value, "%Y%m%dT%H:%M:%S")
print "Today: %s" % converted.strftime("%d.%m.%Y, %H:%M")
```

20.23.4 Binary Objects

class `xmlrpclib.Binary`

This class may be initialized from string data (which may include NULs). The primary access to the content of a *Binary* object is provided by an attribute:

data

The binary data encapsulated by the *Binary* instance. The data is provided as an 8-bit string.

Binary objects have the following methods, supported mainly for internal use by the marshalling/unmarshalling code:

decode (*string*)

Accept a base64 string and decode it as the instance's new data.

encode (*out*)

Write the XML-RPC base 64 encoding of this binary item to the *out* stream object.

The encoded data will have newlines every 76 characters as per RFC 2045 section 6.8, which was the de facto standard base64 specification when the XML-RPC spec was written.

It also supports certain of Python's built-in operators through a `__cmp__()` method.

Example usage of the binary objects. We're going to transfer an image over XMLRPC:

```
from SimpleXMLRPCServer import SimpleXMLRPCServer
import xmlrpclib

def python_logo():
    with open("python_logo.jpg", "rb") as handle:
        return xmlrpclib.Binary(handle.read())

server = SimpleXMLRPCServer(("localhost", 8000))
print "Listening on port 8000..."
server.register_function(python_logo, 'python_logo')

server.serve_forever()
```

The client gets the image and saves it to a file:

```
import xmlrpclib

proxy = xmlrpclib.ServerProxy("http://localhost:8000/")
with open("fetched_python_logo.jpg", "wb") as handle:
    handle.write(proxy.python_logo().data)
```

20.23.5 Fault Objects

class `xmlrpclib.Fault`

A *Fault* object encapsulates the content of an XML-RPC fault tag. Fault objects have the following attributes:

faultCode

A string indicating the fault type.

faultString

A string containing a diagnostic message associated with the fault.

In the following example we're going to intentionally cause a *Fault* by returning a complex type object. The server code:


```

from SimpleXMLRPCServer import SimpleXMLRPCServer

# A marshallng error is going to occur because we're returning a
# complex number
def add(x, y):
    return x+y+0j

server = SimpleXMLRPCServer(("localhost", 8000))
print "Listening on port 8000..."
server.register_function(add, 'add')

server.serve_forever()

```

The client code for the preceding server:

```

import xmlrpclib

proxy = xmlrpclib.ServerProxy("http://localhost:8000/")
try:
    proxy.add(2, 5)
except xmlrpclib.Fault as err:
    print "A fault occurred"
    print "Fault code: %d" % err.faultCode
    print "Fault string: %s" % err.faultString

```

20.23.6 ProtocolError Objects

class `xmlrpclib.ProtocolError`

A *ProtocolError* object describes a protocol error in the underlying transport layer (such as a 404 <not found> error if the server named by the URI does not exist). It has the following attributes:

url

The URI or URL that triggered the error.

errcode

The error code.

errmsg

The error message or diagnostic string.

headers

A string containing the headers of the HTTP/HTTPS request that triggered the error.

In the following example we're going to intentionally cause a *ProtocolError* by providing a URI that doesn't point to an XMLRPC server:

```

import xmlrpclib

# create a ServerProxy with a URI that doesn't respond to XMLRPC requests
proxy = xmlrpclib.ServerProxy("http://www.google.com/")

try:
    proxy.some_method()
except xmlrpclib.ProtocolError as err:
    print "A protocol error occurred"
    print "URL: %s" % err.url
    print "HTTP/HTTPS headers: %s" % err.headers

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
print "Error code: %d" % err.errcode
print "Error message: %s" % err.errmsg
```

20.23.7 MultiCall Objects

버전 2.4에 추가.

The *MultiCall* object provides a way to encapsulate multiple calls to a remote server into a single request¹.

class xmlrpclib.**MultiCall**(*server*)

Create an object used to boxcar method calls. *server* is the eventual target of the call. Calls can be made to the result object, but they will immediately return *None*, and only store the call name and parameters in the *MultiCall* object. Calling the object itself causes all stored calls to be transmitted as a single `system.multicall` request. The result of this call is a *generator*; iterating over this generator yields the individual results.

A usage example of this class follows. The server code

```
from SimpleXMLRPCServer import SimpleXMLRPCServer

def add(x,y):
    return x+y

def subtract(x, y):
    return x-y

def multiply(x, y):
    return x*y

def divide(x, y):
    return x/y

# A simple server with simple arithmetic functions
server = SimpleXMLRPCServer(("localhost", 8000))
print "Listening on port 8000..."
server.register_multicall_functions()
server.register_function(add, 'add')
server.register_function(subtract, 'subtract')
server.register_function(multiply, 'multiply')
server.register_function(divide, 'divide')
server.serve_forever()
```

The client code for the preceding server:

```
import xmlrpclib

proxy = xmlrpclib.ServerProxy("http://localhost:8000/")
multicall = xmlrpclib.MultiCall(proxy)
multicall.add(7,3)
multicall.subtract(7,3)
multicall.multiply(7,3)
multicall.divide(7,3)
result = multicall()

print "7+3=%d, 7-3=%d, 7*3=%d, 7/3=%d" % tuple(result)
```

¹ This approach has been first presented in a discussion on xmlrpc.com.

20.23.8 Convenience Functions

`xmlrpclib.boolean(value)`

Convert any Python value to one of the XML-RPC Boolean constants, `True` or `False`.

`xmlrpclib.dumps(params[, methodname[, methodresponse[, encoding[, allow_none]]])`

Convert *params* into an XML-RPC request, or into a response if *methodresponse* is true. *params* can be either a tuple of arguments or an instance of the `Fault` exception class. If *methodresponse* is true, only a single value can be returned, meaning that *params* must be of length 1. *encoding*, if supplied, is the encoding to use in the generated XML; the default is UTF-8. Python's `None` value cannot be used in standard XML-RPC; to allow using it via an extension, provide a true value for *allow_none*.

`xmlrpclib.loads(data[, use_datetime])`

Convert an XML-RPC request or response into Python objects, a `(params, methodname)`. *params* is a tuple of argument; *methodname* is a string, or `None` if no method name is present in the packet. If the XML-RPC packet represents a fault condition, this function will raise a `Fault` exception. The *use_datetime* flag can be used to cause date/time values to be presented as `datetime.datetime` objects; this is false by default.

버전 2.5에서 변경: The *use_datetime* flag was added.

20.23.9 Example of Client Usage

```
# simple test program (from the XML-RPC specification)
from xmlrpclib import ServerProxy, Error

# server = ServerProxy("http://localhost:8000") # local server
server = ServerProxy("http://betty.userland.com")

print server

try:
    print server.examples.getStateName(41)
except Error as v:
    print "ERROR", v
```

To access an XML-RPC server through a HTTP proxy, you need to define a custom transport. The following example shows how:

```
import xmlrpclib, httplib

class ProxiedTransport(xmlrpclib.Transport):
    def set_proxy(self, proxy):
        self.proxy = proxy

    def make_connection(self, host):
        self.realhost = host
        h = httplib.HTTPConnection(self.proxy)
        return h

    def send_request(self, connection, handler, request_body):
        connection.putrequest("POST", 'http://%s%s' % (self.realhost, handler))

    def send_host(self, connection, host):
        connection.putheader('Host', self.realhost)

p = ProxiedTransport()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
p.set_proxy('proxy-server:8080')
server = xmlrpclib.ServerProxy('http://time.xmlrpc.com/RPC2', transport=p)
print server.currentTime.getCurrentTime()
```

20.23.10 Example of Client and Server Usage

See *SimpleXMLRPCServer Example*.

20.24 SimpleXMLRPCServer — Basic XML-RPC server

참고: The *SimpleXMLRPCServer* module has been merged into `xmlrpc.server` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

버전 2.2에 추가.

Source code: `Lib/SimpleXMLRPCServer.py`

The *SimpleXMLRPCServer* module provides a basic server framework for XML-RPC servers written in Python. Servers can either be free standing, using *SimpleXMLRPCServer*, or embedded in a CGI environment, using *CGIXMLRPCRequestHandler*.

```
class SimpleXMLRPCServer.SimpleXMLRPCServer(addr[, requestHandler[, logRe-
                                         quests[, allow_none[, encoding[,
                                         bind_and_activate]]]])
```

Create a new server instance. This class provides methods for registration of functions that can be called by the XML-RPC protocol. The *requestHandler* parameter should be a factory for request handler instances; it defaults to *SimpleXMLRPCRequestHandler*. The *addr* and *requestHandler* parameters are passed to the *SocketServer.TCPServer* constructor. If *logRequests* is true (the default), requests will be logged; setting this parameter to false will turn off logging. The *allow_none* and *encoding* parameters are passed on to *xmlrpclib* and control the XML-RPC responses that will be returned from the server. The *bind_and_activate* parameter controls whether *server_bind()* and *server_activate()* are called immediately by the constructor; it defaults to true. Setting it to false allows code to manipulate the *allow_reuse_address* class variable before the address is bound.

버전 2.5에서 변경: The *allow_none* and *encoding* parameters were added.

버전 2.6에서 변경: The *bind_and_activate* parameter was added.

```
class SimpleXMLRPCServer.CGIXMLRPCRequestHandler([allow_none[, encoding]])
```

Create a new instance to handle XML-RPC requests in a CGI environment. The *allow_none* and *encoding* parameters are passed on to *xmlrpclib* and control the XML-RPC responses that will be returned from the server.

버전 2.3에 추가.

버전 2.5에서 변경: The *allow_none* and *encoding* parameters were added.

```
class SimpleXMLRPCServer.SimpleXMLRPCRequestHandler
```

Create a new request handler instance. This request handler supports POST requests and modifies logging so that the *logRequests* parameter to the *SimpleXMLRPCServer* constructor parameter is honored.

20.24.1 SimpleXMLRPCServer Objects

The `SimpleXMLRPCServer` class is based on `SocketServer.TCPServer` and provides a means of creating simple, stand alone XML-RPC servers.

`SimpleXMLRPCServer.register_function(function[, name])`

Register a function that can respond to XML-RPC requests. If *name* is given, it will be the method name associated with *function*, otherwise *function.__name__* will be used. *name* can be either a normal or Unicode string, and may contain characters not legal in Python identifiers, including the period character.

`SimpleXMLRPCServer.register_instance(instance[, allow_dotted_names])`

Register an object which is used to expose method names which have not been registered using `register_function()`. If *instance* contains a `_dispatch()` method, it is called with the requested method name and the parameters from the request. Its API is `def _dispatch(self, method, params)` (note that *params* does not represent a variable argument list). If it calls an underlying function to perform its task, that function is called as `func(*params)`, expanding the parameter list. The return value from `_dispatch()` is returned to the client as the result. If *instance* does not have a `_dispatch()` method, it is searched for an attribute matching the name of the requested method.

If the optional *allow_dotted_names* argument is true and the instance does not have a `_dispatch()` method, then if the requested method name contains periods, each component of the method name is searched for individually, with the effect that a simple hierarchical search is performed. The value found from this search is then called with the parameters from the request, and the return value is passed back to the client.

경고: Enabling the *allow_dotted_names* option allows intruders to access your module's global variables and may allow intruders to execute arbitrary code on your machine. Only use this option on a secure, closed network.

버전 2.3.5, 에서 변경: 2.4.1 *allow_dotted_names* was added to plug a security hole; prior versions are insecure.

`SimpleXMLRPCServer.register_introspection_functions()`

Registers the XML-RPC introspection functions `system.listMethods`, `system.methodHelp` and `system.methodSignature`.

버전 2.3에 추가.

`SimpleXMLRPCServer.register_multicall_functions()`

Registers the XML-RPC multicall function `system.multicall`.

`SimpleXMLRPCRequestHandler.rpc_paths`

An attribute value that must be a tuple listing valid path portions of the URL for receiving XML-RPC requests. Requests posted to other paths will result in a 404 «no such page» HTTP error. If this tuple is empty, all paths will be considered valid. The default value is `('/', '/RPC2')`.

버전 2.5에 추가.

`SimpleXMLRPCRequestHandler.encode_threshold`

If this attribute is not `None`, responses larger than this value will be encoded using the *gzip* transfer encoding, if permitted by the client. The default is 1400 which corresponds roughly to a single TCP packet.

버전 2.7에 추가.

SimpleXMLRPCServer Example

Server code:

```
from SimpleXMLRPCServer import SimpleXMLRPCServer
from SimpleXMLRPCServer import SimpleXMLRPCRequestHandler

# Restrict to a particular path.
class RequestHandler(SimpleXMLRPCRequestHandler):
    rpc_paths = ('/RPC2',)

# Create server
server = SimpleXMLRPCServer(("localhost", 8000),
                            requestHandler=RequestHandler)
server.register_introspection_functions()

# Register pow() function; this will use the value of
# pow.__name__ as the name, which is just 'pow'.
server.register_function(pow)

# Register a function under a different name
def adder_function(x,y):
    return x + y
server.register_function(adder_function, 'add')

# Register an instance; all the methods of the instance are
# published as XML-RPC methods (in this case, just 'div').
class MyFuncs:
    def div(self, x, y):
        return x // y

server.register_instance(MyFuncs())

# Run the server's main loop
server.serve_forever()
```

The following client code will call the methods made available by the preceding server:

```
import xmlrpclib

s = xmlrpclib.ServerProxy('http://localhost:8000')
print s.pow(2,3)  # Returns 2**3 = 8
print s.add(2,3)  # Returns 5
print s.div(5,2)  # Returns 5//2 = 2

# Print list of available methods
print s.system.listMethods()
```

The following *SimpleXMLRPCServer* example is included in the module *Lib/SimpleXMLRPCServer.py*:

```
server = SimpleXMLRPCServer(("localhost", 8000))
server.register_function(pow)
server.register_function(lambda x,y: x+y, 'add')
server.register_multicall_functions()
server.serve_forever()
```

This demo server can be run from the command line as:

```
python -m SimpleXMLRPCServer
```

Example client code which talks to the above server is included with *Lib/xmlrpclib.py*:

```
server = ServerProxy("http://localhost:8000")
print server
multi = MultiCall(server)
multi.pow(2, 9)
multi.add(5, 1)
multi.add(24, 11)
try:
    for response in multi():
        print response
except Error, v:
    print "ERROR", v
```

And the client can be invoked directly using the following command:

```
python -m xmlrpclib
```

20.24.2 CGIXMLRPCRequestHandler

The *CGIXMLRPCRequestHandler* class can be used to handle XML-RPC requests sent to Python CGI scripts.

CGIXMLRPCRequestHandler.register_function (*function* [, *name*])

Register a function that can respond to XML-RPC requests. If *name* is given, it will be the method name associated with function, otherwise *function.__name__* will be used. *name* can be either a normal or Unicode string, and may contain characters not legal in Python identifiers, including the period character.

CGIXMLRPCRequestHandler.register_instance (*instance*)

Register an object which is used to expose method names which have not been registered using *register_function()*. If *instance* contains a *_dispatch()* method, it is called with the requested method name and the parameters from the request; the return value is returned to the client as the result. If *instance* does not have a *_dispatch()* method, it is searched for an attribute matching the name of the requested method; if the requested method name contains periods, each component of the method name is searched for individually, with the effect that a simple hierarchical search is performed. The value found from this search is then called with the parameters from the request, and the return value is passed back to the client.

CGIXMLRPCRequestHandler.register_introspection_functions ()

Register the XML-RPC introspection functions *system.listMethods*, *system.methodHelp* and *system.methodSignature*.

CGIXMLRPCRequestHandler.register_multicall_functions ()

Register the XML-RPC multicall function *system.multicall*.

CGIXMLRPCRequestHandler.handle_request ([*request_text* = None])

Handle an XML-RPC request. If *request_text* is given, it should be the POST data provided by the HTTP server, otherwise the contents of stdin will be used.

Example:

```
class MyFuncs:
    def div(self, x, y): return x // y

handler = CGIXMLRPCRequestHandler()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

handler.register_function(pow)
handler.register_function(lambda x,y: x+y, 'add')
handler.register_introspection_functions()
handler.register_instance(MyFuncs())
handler.handle_request()

```

20.25 DocXMLRPCServer — Self-documenting XML-RPC server

참고: The *DocXMLRPCServer* module has been merged into `xmlrpc.server` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

버전 2.3에 추가.

The *DocXMLRPCServer* module extends the classes found in *SimpleXMLRPCServer* to serve HTML documentation in response to HTTP GET requests. Servers can either be free standing, using *DocXMLRPCServer*, or embedded in a CGI environment, using *DocCGIXMLRPCRequestHandler*.

class `DocXMLRPCServer.DocXMLRPCServer` (*addr*[, *requestHandler*[, *logRequests*[, *allow_none*[, *encoding*[, *bind_and_activate*]]]]])

Create a new server instance. All parameters have the same meaning as for *SimpleXMLRPCServer*. *SimpleXMLRPCServer*; *requestHandler* defaults to *DocXMLRPCRequestHandler*.

class `DocXMLRPCServer.DocCGIXMLRPCRequestHandler`

Create a new instance to handle XML-RPC requests in a CGI environment.

class `DocXMLRPCServer.DocXMLRPCRequestHandler`

Create a new request handler instance. This request handler supports XML-RPC POST requests, documentation GET requests, and modifies logging so that the *logRequests* parameter to the *DocXMLRPCServer* constructor parameter is honored.

20.25.1 DocXMLRPCServer Objects

The *DocXMLRPCServer* class is derived from *SimpleXMLRPCServer*. *SimpleXMLRPCServer* and provides a means of creating self-documenting, stand alone XML-RPC servers. HTTP POST requests are handled as XML-RPC method calls. HTTP GET requests are handled by generating pydoc-style HTML documentation. This allows a server to provide its own web-based documentation.

`DocXMLRPCServer.set_server_title` (*server_title*)

Set the title used in the generated HTML documentation. This title will be used inside the HTML `<title>` element.

`DocXMLRPCServer.set_server_name` (*server_name*)

Set the name used in the generated HTML documentation. This name will appear at the top of the generated documentation inside a `<h1>` element.

`DocXMLRPCServer.set_server_documentation` (*server_documentation*)

Set the description used in the generated HTML documentation. This description will appear as a paragraph, below the server name, in the documentation.

20.25.2 DocCGIXMLRPCRequestHandler

The *DocCGIXMLRPCRequestHandler* class is derived from *SimpleXMLRPCServer.CGIXMLRPCRequestHandler* and provides a means of creating self-documenting, XML-RPC CGI scripts. HTTP POST requests are handled as XML-RPC method calls. HTTP GET requests are handled by generating pydoc-style HTML documentation. This allows a server to provide its own web-based documentation.

`DocCGIXMLRPCRequestHandler.set_server_title(server_title)`

Set the title used in the generated HTML documentation. This title will be used inside the HTML `<title>` element.

`DocCGIXMLRPCRequestHandler.set_server_name(server_name)`

Set the name used in the generated HTML documentation. This name will appear at the top of the generated documentation inside a `<h1>` element.

`DocCGIXMLRPCRequestHandler.set_server_documentation(server_documentation)`

Set the description used in the generated HTML documentation. This description will appear as a paragraph, below the server name, in the documentation.

The modules described in this chapter implement various algorithms or interfaces that are mainly useful for multimedia applications. They are available at the discretion of the installation. Here's an overview:

21.1 `audioop` — Manipulate raw audio data

The `audioop` module contains some useful operations on sound fragments. It operates on sound fragments consisting of signed integer samples 8, 16 or 32 bits wide, stored in Python strings. This is the same format as used by the `al` and `sunaudioev` modules. All scalar items are integers, unless specified otherwise.

This module provides support for a-LAW, u-LAW and Intel/DVI ADPCM encodings.

A few of the more complicated operations only take 16-bit samples, otherwise the sample size (in bytes) is always a parameter of the operation.

The module defines the following variables and functions:

exception `audioop.error`

This exception is raised on all errors, such as unknown number of bytes per sample, etc.

`audioop.add(fragment1, fragment2, width)`

Return a fragment which is the addition of the two samples passed as parameters. *width* is the sample width in bytes, either 1, 2 or 4. Both fragments should have the same length. Samples are truncated in case of overflow.

`audioop.adpcm2lin(adpcmfragment, width, state)`

Decode an Intel/DVI ADPCM coded fragment to a linear fragment. See the description of `lin2adpcm()` for details on ADPCM coding. Return a tuple (*sample*, *newstate*) where the sample has the width specified in *width*.

`audioop.alaw2lin(fragment, width)`

Convert sound fragments in a-LAW encoding to linearly encoded sound fragments. a-LAW encoding always uses 8 bits samples, so *width* refers only to the sample width of the output fragment here.

버전 2.5에 추가.

`audioop.avg(fragment, width)`

Return the average over all samples in the fragment.

`audioop.avgpp(fragment, width)`

Return the average peak-peak value over all samples in the fragment. No filtering is done, so the usefulness of this routine is questionable.

`audioop.bias(fragment, width, bias)`

Return a fragment that is the original fragment with a bias added to each sample. Samples wrap around in case of overflow.

`audioop.cross(fragment, width)`

Return the number of zero crossings in the fragment passed as an argument.

`audioop.findfactor(fragment, reference)`

Return a factor F such that `rms(add(fragment, mul(reference, -F)))` is minimal, i.e., return the factor with which you should multiply *reference* to make it match as well as possible to *fragment*. The fragments should both contain 2-byte samples.

The time taken by this routine is proportional to `len(fragment)`.

`audioop.findfit(fragment, reference)`

Try to match *reference* as well as possible to a portion of *fragment* (which should be the longer fragment). This is (conceptually) done by taking slices out of *fragment*, using `findfactor()` to compute the best match, and minimizing the result. The fragments should both contain 2-byte samples. Return a tuple (*offset*, *factor*) where *offset* is the (integer) offset into *fragment* where the optimal match started and *factor* is the (floating-point) factor as per `findfactor()`.

`audioop.findmax(fragment, length)`

Search *fragment* for a slice of length *length* samples (not bytes!) with maximum energy, i.e., return *i* for which `rms(fragment[i*2:(i+length)*2])` is maximal. The fragments should both contain 2-byte samples.

The routine takes time proportional to `len(fragment)`.

`audioop.getsample(fragment, width, index)`

Return the value of sample *index* from the fragment.

`audioop.lin2adpcm(fragment, width, state)`

Convert samples to 4 bit Intel/DVI ADPCM encoding. ADPCM coding is an adaptive coding scheme, whereby each 4 bit number is the difference between one sample and the next, divided by a (varying) step. The Intel/DVI ADPCM algorithm has been selected for use by the IMA, so it may well become a standard.

state is a tuple containing the state of the coder. The coder returns a tuple (*adpcmfrag*, *newstate*), and the *newstate* should be passed to the next call of `lin2adpcm()`. In the initial call, *None* can be passed as the state. *adpcmfrag* is the ADPCM coded fragment packed 2 4-bit values per byte.

`audioop.lin2alaw(fragment, width)`

Convert samples in the audio fragment to a-LAW encoding and return this as a Python string. a-LAW is an audio encoding format whereby you get a dynamic range of about 13 bits using only 8 bit samples. It is used by the Sun audio hardware, among others.

버전 2.5에 추가.

`audioop.lin2lin(fragment, width, newwidth)`

Convert samples between 1-, 2- and 4-byte formats.

참고: In some audio formats, such as .WAV files, 16 and 32 bit samples are signed, but 8 bit samples are unsigned. So when converting to 8 bit wide samples for these formats, you need to also add 128 to the result:

```
new_frames = audioop.lin2lin(frames, old_width, 1)
new_frames = audioop.bias(new_frames, 1, 128)
```

The same, in reverse, has to be applied when converting from 8 to 16 or 32 bit width samples.

`audioop.lin2ulaw(fragment, width)`

Convert samples in the audio fragment to u-LAW encoding and return this as a Python string. u-LAW is an audio encoding format whereby you get a dynamic range of about 14 bits using only 8 bit samples. It is used by the Sun audio hardware, among others.

`audioop.max(fragment, width)`

Return the maximum of the *absolute value* of all samples in a fragment.

`audioop.maxpp(fragment, width)`

Return the maximum peak-peak value in the sound fragment.

`audioop.minmax(fragment, width)`

Return a tuple consisting of the minimum and maximum values of all samples in the sound fragment.

`audioop.mul(fragment, width, factor)`

Return a fragment that has all samples in the original fragment multiplied by the floating-point value *factor*. Samples are truncated in case of overflow.

`audioop.ratecv(fragment, width, nchannels, inrate, outrate, state[, weightA[, weightB]])`

Convert the frame rate of the input fragment.

state is a tuple containing the state of the converter. The converter returns a tuple (*newfragment*, *newstate*), and *newstate* should be passed to the next call of `ratecv()`. The initial call should pass *None* as the state.

The *weightA* and *weightB* arguments are parameters for a simple digital filter and default to 1 and 0 respectively.

`audioop.reverse(fragment, width)`

Reverse the samples in a fragment and returns the modified fragment.

`audioop.rms(fragment, width)`

Return the root-mean-square of the fragment, i.e. $\sqrt{\sum(S_i^2)/n}$.

This is a measure of the power in an audio signal.

`audioop.tomono(fragment, width, lfactor, rfactor)`

Convert a stereo fragment to a mono fragment. The left channel is multiplied by *lfactor* and the right channel by *rfactor* before adding the two channels to give a mono signal.

`audioop.tostereo(fragment, width, lfactor, rfactor)`

Generate a stereo fragment from a mono fragment. Each pair of samples in the stereo fragment are computed from the mono sample, whereby left channel samples are multiplied by *lfactor* and right channel samples by *rfactor*.

`audioop.ulaw2lin(fragment, width)`

Convert sound fragments in u-LAW encoding to linearly encoded sound fragments. u-LAW encoding always uses 8 bits samples, so *width* refers only to the sample width of the output fragment here.

Note that operations such as `mul()` or `max()` make no distinction between mono and stereo fragments, i.e. all samples are treated equal. If this is a problem the stereo fragment should be split into two mono fragments first and recombined later. Here is an example of how to do that:

```
def mul_stereo(sample, width, lfactor, rfactor):
    lsample = audioop.tomono(sample, width, 1, 0)
    rsample = audioop.tomono(sample, width, 0, 1)
    lsample = audioop.mul(lsample, width, lfactor)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

rsample = audioop.mul(rsample, width, rfactor)
lsample = audioop.tostereo(lsample, width, 1, 0)
rsample = audioop.tostereo(rsample, width, 0, 1)
return audioop.add(lsample, rsample, width)

```

If you use the ADPCM coder to build network packets and you want your protocol to be stateless (i.e. to be able to tolerate packet loss) you should not only transmit the data but also the state. Note that you should send the *initial* state (the one you passed to `lin2adpcm()`) along to the decoder, not the final state (as returned by the coder). If you want to use `struct.Struct` to store the state in binary you can code the first element (the predicted value) in 16 bits and the second (the delta index) in 8.

The ADPCM coders have never been tried against other ADPCM coders, only against themselves. It could well be that I misinterpreted the standards in which case they will not be interoperable with the respective standards.

The `find*()` routines might look a bit funny at first sight. They are primarily meant to do echo cancellation. A reasonably fast way to do this is to pick the most energetic piece of the output sample, locate that in the input sample and subtract the whole output sample from the input sample:

```

def echocancel(outputdata, inputdata):
    pos = audioop.findmax(outputdata, 800)      # one tenth second
    out_test = outputdata[pos*2:]
    in_test = inputdata[pos*2:]
    ipos, factor = audioop.findfit(in_test, out_test)
    # Optional (for better cancellation):
    # factor = audioop.findfactor(in_test[ipos*2:ipos*2+len(out_test)],
    #                             out_test)
    prefill = '\0'*(pos+ipos)*2
    postfill = '\0'*(len(inputdata)-len(prefill)-len(outputdata))
    outputdata = prefill + audioop.mul(outputdata, 2, -factor) + postfill
    return audioop.add(inputdata, outputdata, 2)

```

21.2 imageop — Manipulate raw image data

버전 2.6부터 폐지: The `imageop` module has been removed in Python 3.

The `imageop` module contains some useful operations on images. It operates on images consisting of 8 or 32 bit pixels stored in Python strings. This is the same format as used by `gl.rectwrite()` and the `imgfile` module.

The module defines the following variables and functions:

exception `imageop.error`

This exception is raised on all errors, such as unknown number of bits per pixel, etc.

`imageop.crop` (*image*, *psize*, *width*, *height*, *x0*, *y0*, *x1*, *y1*)

Return the selected part of *image*, which should be *width* by *height* in size and consist of pixels of *psize* bytes. *x0*, *y0*, *x1* and *y1* are like the `gl.rectread()` parameters, i.e. the boundary is included in the new image. The new boundaries need not be inside the picture. Pixels that fall outside the old image will have their value set to zero. If *x0* is bigger than *x1* the new image is mirrored. The same holds for the y coordinates.

`imageop.scale` (*image*, *psize*, *width*, *height*, *newwidth*, *newheight*)

Return *image* scaled to size *newwidth* by *newheight*. No interpolation is done, scaling is done by simple-minded pixel duplication or removal. Therefore, computer-generated images or dithered images will not look nice after scaling.

`imageop.tovideo` (*image*, *psize*, *width*, *height*)

Run a vertical low-pass filter over an image. It does so by computing each destination pixel as the average of two

vertically-aligned source pixels. The main use of this routine is to forestall excessive flicker if the image is displayed on a video device that uses interlacing, hence the name.

`imageop.grey2mono (image, width, height, threshold)`

Convert an 8-bit deep greyscale image to a 1-bit deep image by thresholding all the pixels. The resulting image is tightly packed and is probably only useful as an argument to `mono2grey()`.

`imageop.dither2mono (image, width, height)`

Convert an 8-bit greyscale image to a 1-bit monochrome image using a (simple-minded) dithering algorithm.

`imageop.mono2grey (image, width, height, p0, p1)`

Convert a 1-bit monochrome image to an 8 bit greyscale or color image. All pixels that are zero-valued on input get value *p0* on output and all one-value input pixels get value *p1* on output. To convert a monochrome black-and-white image to greyscale pass the values 0 and 255 respectively.

`imageop.grey2grey4 (image, width, height)`

Convert an 8-bit greyscale image to a 4-bit greyscale image without dithering.

`imageop.grey2grey2 (image, width, height)`

Convert an 8-bit greyscale image to a 2-bit greyscale image without dithering.

`imageop.dither2grey2 (image, width, height)`

Convert an 8-bit greyscale image to a 2-bit greyscale image with dithering. As for `dither2mono()`, the dithering algorithm is currently very simple.

`imageop.grey42grey (image, width, height)`

Convert a 4-bit greyscale image to an 8-bit greyscale image.

`imageop.grey22grey (image, width, height)`

Convert a 2-bit greyscale image to an 8-bit greyscale image.

`imageop.backward_compatible`

If set to 0, the functions in this module use a non-backward compatible way of representing multi-byte pixels on little-endian systems. The SGI for which this module was originally written is a big-endian system, so setting this variable will have no effect. However, the code wasn't originally intended to run on anything else, so it made assumptions about byte order which are not universal. Setting this variable to 0 will cause the byte order to be reversed on little-endian systems, so that it then is the same as on big-endian systems.

21.3 aifc — Read and write AIFF and AIFC files

Source code: [Lib/aifc.py](#)

This module provides support for reading and writing AIFF and AIFF-C files. AIFF is Audio Interchange File Format, a format for storing digital audio samples in a file. AIFF-C is a newer version of the format that includes the ability to compress the audio data.

참고: Some operations may only work under IRIX; these will raise `ImportError` when attempting to import the `c1` module, which is only available on IRIX.

Audio files have a number of parameters that describe the audio data. The sampling rate or frame rate is the number of times per second the sound is sampled. The number of channels indicate if the audio is mono, stereo, or quadro. Each frame consists of one sample per channel. The sample size is the size in bytes of each sample. Thus a frame consists of *nchannels*samplesize* bytes, and a second's worth of audio consists of *nchannels*samplesize*framerate* bytes.

For example, CD quality audio has a sample size of two bytes (16 bits), uses two channels (stereo) and has a frame rate of 44,100 frames/second. This gives a frame size of 4 bytes (2*2), and a second's worth occupies 2*2*44100 bytes (176,400 bytes).

Module `aifc` defines the following function:

`aifc.open(file[, mode])`

Open an AIFF or AIFF-C file and return an object instance with methods that are described below. The argument `file` is either a string naming a file or a file object. `mode` must be 'r' or 'rb' when the file must be opened for reading, or 'w' or 'wb' when the file must be opened for writing. If omitted, `file.mode` is used if it exists, otherwise 'rb' is used. When used for writing, the file object should be seekable, unless you know ahead of time how many samples you are going to write in total and use `writeframesraw()` and `setnframes()`.

Objects returned by `open()` when a file is opened for reading have the following methods:

`aifc.getnchannels()`

Return the number of audio channels (1 for mono, 2 for stereo).

`aifc.getsampwidth()`

Return the size in bytes of individual samples.

`aifc.getframerate()`

Return the sampling rate (number of audio frames per second).

`aifc.getnframes()`

Return the number of audio frames in the file.

`aifc.getcomptype()`

Return a four-character string describing the type of compression used in the audio file. For AIFF files, the returned value is 'NONE'.

`aifc.getcompname()`

Return a human-readable description of the type of compression used in the audio file. For AIFF files, the returned value is 'not compressed'.

`aifc.getparams()`

Return a tuple consisting of all of the above values in the above order.

`aifc.getmarkers()`

Return a list of markers in the audio file. A marker consists of a tuple of three elements. The first is the mark ID (an integer), the second is the mark position in frames from the beginning of the data (an integer), the third is the name of the mark (a string).

`aifc.getmark(id)`

Return the tuple as described in `getmarkers()` for the mark with the given `id`.

`aifc.readframes(nframes)`

Read and return the next `nframes` frames from the audio file. The returned data is a string containing for each frame the uncompressed samples of all channels.

`aifc.rewind()`

Rewind the read pointer. The next `readframes()` will start from the beginning.

`aifc.setpos(pos)`

Seek to the specified frame number.

`aifc.tell()`

Return the current frame number.

`aifc.close()`

Close the AIFF file. After calling this method, the object can no longer be used.

Objects returned by `open()` when a file is opened for writing have all the above methods, except for `readframes()` and `setpos()`. In addition the following methods exist. The `get*()` methods can only be called after the corresponding `set*()` methods have been called. Before the first `writeframes()` or `writeframesraw()`, all parameters except for the number of frames must be filled in.

`aifc.aiff()`
Create an AIFF file. The default is that an AIFF-C file is created, unless the name of the file ends in `'.aiff'` in which case the default is an AIFF file.

`aifc.aifc()`
Create an AIFF-C file. The default is that an AIFF-C file is created, unless the name of the file ends in `'.aiff'` in which case the default is an AIFF file.

`aifc.setnchannels(nchannels)`
Specify the number of channels in the audio file.

`aifc.setsampwidth(width)`
Specify the size in bytes of audio samples.

`aifc.setframerate(rate)`
Specify the sampling frequency in frames per second.

`aifc.setnframes(nframes)`
Specify the number of frames that are to be written to the audio file. If this parameter is not set, or not set correctly, the file needs to support seeking.

`aifc.setcomptype(type, name)`
Specify the compression type. If not specified, the audio data will not be compressed. In AIFF files, compression is not possible. The name parameter should be a human-readable description of the compression type, the type parameter should be a four-character string. Currently the following compression types are supported: NONE, ULAW, ALAW, G722.

`aifc.setparams(nchannels, sampwidth, framerate, comptype, compname)`
Set all the above parameters at once. The argument is a tuple consisting of the various parameters. This means that it is possible to use the result of a `getparams()` call as argument to `setparams()`.

`aifc.setmark(id, pos, name)`
Add a mark with the given id (larger than 0), and the given name at the given position. This method can be called at any time before `close()`.

`aifc.tell()`
Return the current write position in the output file. Useful in combination with `setmark()`.

`aifc.writeframes(data)`
Write data to the output file. This method can only be called after the audio file parameters have been set.

`aifc.writeframesraw(data)`
Like `writeframes()`, except that the header of the audio file is not updated.

`aifc.close()`
Close the AIFF file. The header of the file is updated to reflect the actual size of the audio data. After calling this method, the object can no longer be used.

21.4 sunau — Read and write Sun AU files

Source code: [Lib/sunau.py](#)

The `sunau` module provides a convenient interface to the Sun AU sound format. Note that this module is interface-compatible with the modules `aifc` and `wave`.

An audio file consists of a header followed by the data. The fields of the header are:

Field	Contents
magic word	The four bytes <code>.snd</code> .
header size	Size of the header, including info, in bytes.
data size	Physical size of the data, in bytes.
encoding	Indicates how the audio samples are encoded.
sample rate	The sampling rate.
# of channels	The number of channels in the samples.
info	ASCII string giving a description of the audio file (padded with null bytes).

Apart from the info field, all header fields are 4 bytes in size. They are all 32-bit unsigned integers encoded in big-endian byte order.

The `sunau` module defines the following functions:

`sunau.open(file, mode)`

If *file* is a string, open the file by that name, otherwise treat it as a seekable file-like object. *mode* can be any of

`'r'` Read only mode.

`'w'` Write only mode.

Note that it does not allow read/write files.

A *mode* of `'r'` returns an `AU_read` object, while a *mode* of `'w'` or `'wb'` returns an `AU_write` object.

`sunau.openfp(file, mode)`

A synonym for `open()`, maintained for backwards compatibility.

The `sunau` module defines the following exception:

exception `sunau.Error`

An error raised when something is impossible because of Sun AU specs or implementation deficiency.

The `sunau` module defines the following data items:

`sunau.AUDIO_FILE_MAGIC`

An integer every valid Sun AU file begins with, stored in big-endian form. This is the string `.snd` interpreted as an integer.

`sunau.AUDIO_FILE_ENCODING_MULAW_8`

`sunau.AUDIO_FILE_ENCODING_LINEAR_8`

`sunau.AUDIO_FILE_ENCODING_LINEAR_16`

`sunau.AUDIO_FILE_ENCODING_LINEAR_24`

`sunau.AUDIO_FILE_ENCODING_LINEAR_32`

`sunau.AUDIO_FILE_ENCODING_ALAW_8`

Values of the encoding field from the AU header which are supported by this module.

`sunau.AUDIO_FILE_ENCODING_FLOAT`

`sunau.AUDIO_FILE_ENCODING_DOUBLE`

```

sunau.AUDIO_FILE_ENCODING_ADPCM_G721
sunau.AUDIO_FILE_ENCODING_ADPCM_G722
sunau.AUDIO_FILE_ENCODING_ADPCM_G723_3
sunau.AUDIO_FILE_ENCODING_ADPCM_G723_5

```

Additional known values of the encoding field from the AU header, but which are not supported by this module.

21.4.1 AU_read Objects

AU_read objects, as returned by `open()` above, have the following methods:

```

AU_read.close()
    Close the stream, and make the instance unusable. (This is called automatically on deletion.)

AU_read.getnchannels()
    Returns number of audio channels (1 for mono, 2 for stereo).

AU_read.getsampwidth()
    Returns sample width in bytes.

AU_read.getframerate()
    Returns sampling frequency.

AU_read.getnframes()
    Returns number of audio frames.

AU_read.getcomptype()
    Returns compression type. Supported compression types are 'ULAW', 'ALAW' and 'NONE'.

AU_read.getcompname()
    Human-readable version of getcomptype(). The supported types have the respective names 'CCITT G.711
    u-law', 'CCITT G.711 A-law' and 'not compressed'.

AU_read.getparams()
    Returns a tuple (nchannels, sampwidth, framerate, nframes, comptype, compname),
    equivalent to output of the get*() methods.

AU_read.readframes(n)
    Reads and returns at most n frames of audio, as a string of bytes. The data will be returned in linear format. If the
    original data is in u-LAW format, it will be converted.

AU_read.rewind()
    Rewind the file pointer to the beginning of the audio stream.

```

The following two methods define a term «position» which is compatible between them, and is otherwise implementation dependent.

```

AU_read.setpos(pos)
    Set the file pointer to the specified position. Only values returned from tell() should be used for pos.

AU_read.tell()
    Return current file pointer position. Note that the returned value has nothing to do with the actual position in the
    file.

```

The following two functions are defined for compatibility with the `aifc`, and don't do anything interesting.

```

AU_read.getmarkers()
    Returns None.

AU_read.getmark(id)
    Raise an error.

```

21.4.2 AU_write Objects

AU_write objects, as returned by `open()` above, have the following methods:

`AU_write.setnchannels(n)`

Set the number of channels.

`AU_write.setsampwidth(n)`

Set the sample width (in bytes.)

`AU_write.setframerate(n)`

Set the frame rate.

`AU_write.setnframes(n)`

Set the number of frames. This can be later changed, when and if more frames are written.

`AU_write.setcomptype(type, name)`

Set the compression type and description. Only 'NONE' and 'ULAW' are supported on output.

`AU_write.setparams(tuple)`

The *tuple* should be (nchannels, sampwidth, framerate, nframes, comptype, compname), with values valid for the `set*()` methods. Set all parameters.

`AU_write.tell()`

Return current position in the file, with the same disclaimer for the `AU_read.tell()` and `AU_read.setpos()` methods.

`AU_write.writeframesraw(data)`

Write audio frames, without correcting *nframes*.

`AU_write.writeframes(data)`

Write audio frames and make sure *nframes* is correct.

`AU_write.close()`

Make sure *nframes* is correct, and close the file.

This method is called upon deletion.

Note that it is invalid to set any parameters after calling `writeframes()` or `writeframesraw()`.

21.5 wave — Read and write WAV files

Source code: [Lib/wave.py](#)

The `wave` module provides a convenient interface to the WAV sound format. It does not support compression/decompression, but it does support mono/stereo.

The `wave` module defines the following function and exception:

`wave.open(file[, mode])`

If *file* is a string, open the file by that name, otherwise treat it as a seekable file-like object. *mode* can be any of

'r', 'rb' Read only mode.

'w', 'wb' Write only mode.

Note that it does not allow read/write WAV files.

A *mode* of 'r' or 'rb' returns a `Wave_read` object, while a *mode* of 'w' or 'wb' returns a `Wave_write` object. If *mode* is omitted and a file-like object is passed as *file*, `file.mode` is used as the default value for *mode* (the 'b' flag is still added if necessary).

If you pass in a file-like object, the wave object will not close it when its `close()` method is called; it is the caller's responsibility to close the file object.

`wave.openfp(file, mode)`

A synonym for `open()`, maintained for backwards compatibility.

exception `wave.Error`

An error raised when something is impossible because it violates the WAV specification or hits an implementation deficiency.

21.5.1 Wave_read Objects

`Wave_read` objects, as returned by `open()`, have the following methods:

`Wave_read.close()`

Close the stream if it was opened by `wave`, and make the instance unusable. This is called automatically on object collection.

`Wave_read.getnchannels()`

Returns number of audio channels (1 for mono, 2 for stereo).

`Wave_read.getsampwidth()`

Returns sample width in bytes.

`Wave_read.getframerate()`

Returns sampling frequency.

`Wave_read.getnframes()`

Returns number of audio frames.

`Wave_read.getcomptype()`

Returns compression type ('NONE' is the only supported type).

`Wave_read.getcompname()`

Human-readable version of `getcomptype()`. Usually 'not compressed' parallels 'NONE'.

`Wave_read.getparams()`

Returns a tuple (nchannels, sampwidth, framerate, nframes, comptype, compname), equivalent to output of the `get*()` methods.

`Wave_read.readframes(n)`

Reads and returns at most *n* frames of audio, as a string of bytes.

`Wave_read.rewind()`

Rewind the file pointer to the beginning of the audio stream.

The following two methods are defined for compatibility with the `aifc` module, and don't do anything interesting.

`Wave_read.getmarkers()`

Returns None.

`Wave_read.getmark(id)`

Raise an error.

The following two methods define a term 《position》 which is compatible between them, and is otherwise implementation dependent.

`Wave_read.setpos(pos)`
Set the file pointer to the specified position.

`Wave_read.tell()`
Return current file pointer position.

21.5.2 Wave_write Objects

Wave_write objects, as returned by `open()`, have the following methods:

`Wave_write.close()`
Make sure *nframes* is correct, and close the file if it was opened by `wave`. This method is called upon object collection.

`Wave_write.setnchannels(n)`
Set the number of channels.

`Wave_write.setsampwidth(n)`
Set the sample width to *n* bytes.

`Wave_write.setframerate(n)`
Set the frame rate to *n*.

`Wave_write.setnframes(n)`
Set the number of frames to *n*. This will be changed later if more frames are written.

`Wave_write.setcomptype(type, name)`
Set the compression type and description. At the moment, only compression type `NONE` is supported, meaning no compression.

`Wave_write.setparams(tuple)`
The *tuple* should be (*nchannels*, *sampwidth*, *framerate*, *nframes*, *comptype*, *compname*), with values valid for the `set*()` methods. Sets all parameters.

`Wave_write.tell()`
Return current position in the file, with the same disclaimer for the `Wave_read.tell()` and `Wave_read.setpos()` methods.

`Wave_write.writeframesraw(data)`
Write audio frames, without correcting *nframes*.

`Wave_write.writeframes(data)`
Write audio frames and make sure *nframes* is correct.

Note that it is invalid to set any parameters after calling `writeframes()` or `writeframesraw()`, and any attempt to do so will raise `wave.Error`.

21.6 chunk — Read IFF chunked data

This module provides an interface for reading files that use EA IFF 85 chunks.¹ This format is used in at least the Audio Interchange File Format (AIFF/AIFF-C) and the Real Media File Format (RMFF). The WAVE audio file format is closely related and can also be read using this module.

A chunk has the following structure:

¹ 《EA IFF 85》 Standard for Interchange Format Files, Jerry Morrison, Electronic Arts, January 1985.

Offset	Length	Contents
0	4	Chunk ID
4	4	Size of chunk in big-endian byte order, not including the header
8	<i>n</i>	Data bytes, where <i>n</i> is the size given in the preceding field
8 + <i>n</i>	0 or 1	Pad byte needed if <i>n</i> is odd and chunk alignment is used

The ID is a 4-byte string which identifies the type of chunk.

The size field (a 32-bit value, encoded using big-endian byte order) gives the size of the chunk data, not including the 8-byte header.

Usually an IFF-type file consists of one or more chunks. The proposed usage of the `Chunk` class defined here is to instantiate an instance at the start of each chunk and read from the instance until it reaches the end, after which a new instance can be instantiated. At the end of the file, creating a new instance will fail with an `EOFError` exception.

class `chunk.Chunk` (*file*[, *align*, *bigendian*, *inclheader*])

Class which represents a chunk. The *file* argument is expected to be a file-like object. An instance of this class is specifically allowed. The only method that is needed is `read()`. If the methods `seek()` and `tell()` are present and don't raise an exception, they are also used. If these methods are present and raise an exception, they are expected to not have altered the object. If the optional argument *align* is true, chunks are assumed to be aligned on 2-byte boundaries. If *align* is false, no alignment is assumed. The default value is true. If the optional argument *bigendian* is false, the chunk size is assumed to be in little-endian order. This is needed for WAVE audio files. The default value is true. If the optional argument *inclheader* is true, the size given in the chunk header includes the size of the header. The default value is false.

A `Chunk` object supports the following methods:

getname ()

Returns the name (ID) of the chunk. This is the first 4 bytes of the chunk.

getsize ()

Returns the size of the chunk.

close ()

Close and skip to the end of the chunk. This does not close the underlying file.

The remaining methods will raise `IOError` if called after the `close()` method has been called.

isatty ()

Returns `False`.

seek (*pos*[, *whence*])

Set the chunk's current position. The *whence* argument is optional and defaults to 0 (absolute file positioning); other values are 1 (seek relative to the current position) and 2 (seek relative to the file's end). There is no return value. If the underlying file does not allow seek, only forward seeks are allowed.

tell ()

Return the current position into the chunk.

read ([*size*])

Read at most *size* bytes from the chunk (less if the read hits the end of the chunk before obtaining *size* bytes). If the *size* argument is negative or omitted, read all data until the end of the chunk. The bytes are returned as a string object. An empty string is returned when the end of the chunk is encountered immediately.

skip ()

Skip to the end of the chunk. All further calls to `read()` for the chunk will return ''. If you are not interested in the contents of the chunk, this method should be called so that the file points to the start of the next chunk.

21.7 colorsys — Conversions between color systems

Source code: [Lib/colors.py](#)

The `colorsys` module defines bidirectional conversions of color values between colors expressed in the RGB (Red Green Blue) color space used in computer monitors and three other coordinate systems: YIQ, HLS (Hue Lightness Saturation) and HSV (Hue Saturation Value). Coordinates in all of these color spaces are floating point values. In the YIQ space, the Y coordinate is between 0 and 1, but the I and Q coordinates can be positive or negative. In all other spaces, the coordinates are all between 0 and 1.

더 보기:

More information about color spaces can be found at <https://www.poynton.com/ColorFAQ.html> and <https://www.cambridgeincolour.com/tutorials/color-spaces.htm>.

The `colorsys` module defines the following functions:

```
colorsys.rgb_to_yiq(r, g, b)
    Convert the color from RGB coordinates to YIQ coordinates.

colorsys.yiq_to_rgb(y, i, q)
    Convert the color from YIQ coordinates to RGB coordinates.

colorsys.rgb_to_hls(r, g, b)
    Convert the color from RGB coordinates to HLS coordinates.

colorsys.hls_to_rgb(h, l, s)
    Convert the color from HLS coordinates to RGB coordinates.

colorsys.rgb_to_hsv(r, g, b)
    Convert the color from RGB coordinates to HSV coordinates.

colorsys.hsv_to_rgb(h, s, v)
    Convert the color from HSV coordinates to RGB coordinates.
```

Example:

```
>>> import colorsys
>>> colorsys.rgb_to_hsv(0.2, 0.4, 0.4)
(0.5, 0.5, 0.4)
>>> colorsys.hsv_to_rgb(0.5, 0.5, 0.4)
(0.2, 0.4, 0.4)
```

21.8 imghdr — Determine the type of an image

Source code: [Lib/imghdr.py](#)

The `imghdr` module determines the type of image contained in a file or byte stream.

The `imghdr` module defines the following function:

```
imghdr.what(filename[, h])
    Tests the image data contained in the file named by filename, and returns a string describing the image type. If optional h is provided, the filename is ignored and h is assumed to contain the byte stream to test.
```


The following image types are recognized, as listed below with the return value from `what()`:

Value	Image format
'rgb'	SGI ImgLib Files
'gif'	GIF 87a and 89a Files
'pbm'	Portable Bitmap Files
'pgm'	Portable Graymap Files
'ppm'	Portable Pixmap Files
'tiff'	TIFF Files
'rast'	Sun Raster Files
'xbm'	X Bitmap Files
'jpeg'	JPEG data in JFIF or Exif formats
'bmp'	BMP files
'png'	Portable Network Graphics

버전 2.5에 추가: Exif detection.

You can extend the list of file types `imghdr` can recognize by appending to this variable:

`imghdr.tests`

A list of functions performing the individual tests. Each function takes two arguments: the byte-stream and an open file-like object. When `what()` is called with a byte-stream, the file-like object will be `None`.

The test function should return a string describing the image type if the test succeeded, or `None` if it failed.

Example:

```
>>> import imghdr
>>> imghdr.what('bass.gif')
'gif'
```

21.9 sndhdr — Determine type of sound file

Source code: [Lib/sndhdr.py](#)

The `sndhdr` provides utility functions which attempt to determine the type of sound data which is in a file. When these functions are able to determine what type of sound data is stored in a file, they return a tuple (`type`, `sampling_rate`, `channels`, `frames`, `bits_per_sample`). The value for `type` indicates the data type and will be one of the strings 'aifc', 'aiff', 'au', 'hcom', 'sndr', 'sndt', 'voc', 'wav', '8svx', 'sb', 'ub', or 'ul'. The `sampling_rate` will be either the actual value or 0 if unknown or difficult to decode. Similarly, `channels` will be either the number of channels or 0 if it cannot be determined or if the value is difficult to decode. The value for `frames` will be either the number of frames or -1. The last item in the tuple, `bits_per_sample`, will either be the sample size in bits or 'A' for A-LAW or 'U' for u-LAW.

`sndhdr.what(filename)`

Determines the type of sound data stored in the file `filename` using `whathdr()`. If it succeeds, returns a tuple as described above, otherwise `None` is returned.

`sndhdr.whathdr(filename)`

Determines the type of sound data stored in a file based on the file header. The name of the file is given by `filename`. This function returns a tuple as described above on success, or `None`.

21.10 ossaudiodev — Access to OSS-compatible audio devices

버전 2.3에 추가.

This module allows you to access the OSS (Open Sound System) audio interface. OSS is available for a wide range of open-source and commercial Unices, and is the standard audio interface for Linux and recent versions of FreeBSD.

더 보기:

Open Sound System Programmer's Guide the official documentation for the OSS C API

The module defines a large number of constants supplied by the OSS device driver; see `<sys/soundcard.h>` on either Linux or FreeBSD for a listing.

`ossaudiodev` defines the following variables and functions:

exception `ossaudiodev.OSSAudioError`

This exception is raised on certain errors. The argument is a string describing what went wrong.

(If `ossaudiodev` receives an error from a system call such as `open()`, `write()`, or `ioctl()`, it raises `IOError`. Errors detected directly by `ossaudiodev` result in `OSSAudioError`.)

(For backwards compatibility, the exception class is also available as `ossaudiodev.error`.)

`ossaudiodev.open(mode)`

`ossaudiodev.open(device, mode)`

Open an audio device and return an OSS audio device object. This object supports many file-like methods, such as `read()`, `write()`, and `fileno()` (although there are subtle differences between conventional Unix read/write semantics and those of OSS audio devices). It also supports a number of audio-specific methods; see below for the complete list of methods.

device is the audio device filename to use. If it is not specified, this module first looks in the environment variable `AUDIODEV` for a device to use. If not found, it falls back to `/dev/dsp`.

mode is one of `'r'` for read-only (record) access, `'w'` for write-only (playback) access and `'rw'` for both. Since many sound cards only allow one process to have the recorder or player open at a time, it is a good idea to open the device only for the activity needed. Further, some sound cards are half-duplex: they can be opened for reading or writing, but not both at once.

Note the unusual calling syntax: the *first* argument is optional, and the second is required. This is a historical artifact for compatibility with the older `linuxaudiodev` module which `ossaudiodev` supersedes.

`ossaudiodev.openmixer([device])`

Open a mixer device and return an OSS mixer device object. *device* is the mixer device filename to use. If it is not specified, this module first looks in the environment variable `MIXERDEV` for a device to use. If not found, it falls back to `/dev/mixer`.

21.10.1 Audio Device Objects

Before you can write to or read from an audio device, you must call three methods in the correct order:

1. `setfmt()` to set the output format
2. `channels()` to set the number of channels
3. `speed()` to set the sample rate

Alternately, you can use the `setparameters()` method to set all three audio parameters at once. This is more convenient, but may not be as flexible in all cases.

The audio device objects returned by `open()` define the following methods and (read-only) attributes:

`oss_audio_device.close()`

Explicitly close the audio device. When you are done writing to or reading from an audio device, you should explicitly close it. A closed device cannot be used again.

`oss_audio_device.fileno()`

Return the file descriptor associated with the device.

`oss_audio_device.read(size)`

Read *size* bytes from the audio input and return them as a Python string. Unlike most Unix device drivers, OSS audio devices in blocking mode (the default) will block `read()` until the entire requested amount of data is available.

`oss_audio_device.write(data)`

Write the Python string *data* to the audio device and return the number of bytes written. If the audio device is in blocking mode (the default), the entire string is always written (again, this is different from usual Unix device semantics). If the device is in non-blocking mode, some data may not be written—see `writeall()`.

`oss_audio_device.writeall(data)`

Write the entire Python string *data* to the audio device: waits until the audio device is able to accept data, writes as much data as it will accept, and repeats until *data* has been completely written. If the device is in blocking mode (the default), this has the same effect as `write()`; `writeall()` is only useful in non-blocking mode. Has no return value, since the amount of data written is always equal to the amount of data supplied.

The following methods each map to exactly one `ioctl()` system call. The correspondence is obvious: for example, `setfmt()` corresponds to the `SNDCTL_DSP_SETFMT` `ioctl`, and `sync()` to `SNDCTL_DSP_SYNC` (this can be useful when consulting the OSS documentation). If the underlying `ioctl()` fails, they all raise `IOError`.

`oss_audio_device.nonblock()`

Put the device into non-blocking mode. Once in non-blocking mode, there is no way to return it to blocking mode.

`oss_audio_device.getfmts()`

Return a bitmask of the audio output formats supported by the soundcard. Some of the formats supported by OSS are:

Format	Description
AFMT_MU_LAW	a logarithmic encoding (used by Sun .au files and /dev/audio)
AFMT_A_LAW	a logarithmic encoding
AFMT_IMA_ADPCM	a 4:1 compressed format defined by the Interactive Multimedia Association
AFMT_U8	Unsigned, 8-bit audio
AFMT_S16_LE	Signed, 16-bit audio, little-endian byte order (as used by Intel processors)
AFMT_S16_BE	Signed, 16-bit audio, big-endian byte order (as used by 68k, PowerPC, Sparc)
AFMT_S8	Signed, 8 bit audio
AFMT_U16_LE	Unsigned, 16-bit little-endian audio
AFMT_U16_BE	Unsigned, 16-bit big-endian audio

Consult the OSS documentation for a full list of audio formats, and note that most devices support only a subset of these formats. Some older devices only support `AFMT_U8`; the most common format used today is `AFMT_S16_LE`.

`oss_audio_device.setfmt(format)`

Try to set the current audio format to *format*—see `getfmts()` for a list. Returns the audio format that the device was set to, which may not be the requested format. May also be used to return the current audio format—do this by passing an `audio format` of `AFMT_QUERY`.

`oss_audio_device.channels(nchannels)`

Set the number of output channels to *nchannels*. A value of 1 indicates monophonic sound, 2 stereophonic. Some devices may have more than 2 channels, and some high-end devices may not support mono. Returns the number of channels the device was set to.

`oss_audio_device.speed(samplerate)`

Try to set the audio sampling rate to *samplerate* samples per second. Returns the rate actually set. Most sound devices don't support arbitrary sampling rates. Common rates are:

Rate	Description
8000	default rate for <code>/dev/audio</code>
11025	speech recording
22050	
44100	CD quality audio (at 16 bits/sample and 2 channels)
96000	DVD quality audio (at 24 bits/sample)

`oss_audio_device.sync()`

Wait until the sound device has played every byte in its buffer. (This happens implicitly when the device is closed.) The OSS documentation recommends closing and re-opening the device rather than using `sync()`.

`oss_audio_device.reset()`

Immediately stop playing or recording and return the device to a state where it can accept commands. The OSS documentation recommends closing and re-opening the device after calling `reset()`.

`oss_audio_device.post()`

Tell the driver that there is likely to be a pause in the output, making it possible for the device to handle the pause more intelligently. You might use this after playing a spot sound effect, before waiting for user input, or before doing disk I/O.

The following convenience methods combine several ioctls, or one ioctl and some simple calculations.

`oss_audio_device.setparameters(format, nchannels, samplerate[, strict=False])`

Set the key audio sampling parameters—sample format, number of channels, and sampling rate—in one method call. *format*, *nchannels*, and *samplerate* should be as specified in the `setfmt()`, `channels()`, and `speed()` methods. If *strict* is true, `setparameters()` checks to see if each parameter was actually set to the requested value, and raises `OSSAudioError` if not. Returns a tuple (*format*, *nchannels*, *samplerate*) indicating the parameter values that were actually set by the device driver (i.e., the same as the return values of `setfmt()`, `channels()`, and `speed()`).

For example,

```
(fmt, channels, rate) = dsp.setparameters(fmt, channels, rate)
```

is equivalent to

```
fmt = dsp.setfmt(fmt)
channels = dsp.channels(channels)
rate = dsp.rate(rate)
```

`oss_audio_device.bufsize()`

Returns the size of the hardware buffer, in samples.

`oss_audio_device.obufcount()`

Returns the number of samples that are in the hardware buffer yet to be played.

`oss_audio_device.obuffree()`

Returns the number of samples that could be queued into the hardware buffer to be played without blocking.

Audio device objects also support several read-only attributes:

`oss_audio_device.closed`

Boolean indicating whether the device has been closed.

`oss_audio_device.name`

String containing the name of the device file.

`oss_audio_device.mode`

The I/O mode for the file, either "r", "rw", or "w".

21.10.2 Mixer Device Objects

The mixer object provides two file-like methods:

`oss_mixer_device.close()`

This method closes the open mixer device file. Any further attempts to use the mixer after this file is closed will raise an `IOError`.

`oss_mixer_device.fileno()`

Returns the file handle number of the open mixer device file.

The remaining methods are specific to audio mixing:

`oss_mixer_device.controls()`

This method returns a bitmask specifying the available mixer controls (《Control》 being a specific mixable 《channel》, such as `SOUND_MIXER_PCM` or `SOUND_MIXER_SYNTH`). This bitmask indicates a subset of all available mixer controls—the `SOUND_MIXER_*` constants defined at module level. To determine if, for example, the current mixer object supports a PCM mixer, use the following Python code:

```
mixer=ossaudiodev.openmixer()
if mixer.controls() & (1 << ossaudiodev.SOUND_MIXER_PCM):
    # PCM is supported
    ... code ...
```

For most purposes, the `SOUND_MIXER_VOLUME` (master volume) and `SOUND_MIXER_PCM` controls should suffice—but code that uses the mixer should be flexible when it comes to choosing mixer controls. On the Gravis Ultrasound, for example, `SOUND_MIXER_VOLUME` does not exist.

`oss_mixer_device.stereocontrols()`

Returns a bitmask indicating stereo mixer controls. If a bit is set, the corresponding control is stereo; if it is unset, the control is either monophonic or not supported by the mixer (use in combination with `controls()` to determine which).

See the code example for the `controls()` function for an example of getting data from a bitmask.

`oss_mixer_device.recontrols()`

Returns a bitmask specifying the mixer controls that may be used to record. See the code example for `controls()` for an example of reading from a bitmask.

`oss_mixer_device.get(control)`

Returns the volume of a given mixer control. The returned volume is a 2-tuple (`left_volume`, `right_volume`). Volumes are specified as numbers from 0 (silent) to 100 (full volume). If the control is monophonic, a 2-tuple is still returned, but both volumes are the same.

Raises `OSSAudioError` if an invalid control was specified, or `IOError` if an unsupported control is specified.

`oss_mixer_device.set(control, (left, right))`

Sets the volume for a given mixer control to (`left`, `right`). `left` and `right` must be ints and between 0 (silent) and 100 (full volume). On success, the new volume is returned as a 2-tuple. Note that this may not be exactly the same as the volume specified, because of the limited resolution of some soundcard's mixers.

Raises `OSSAudioError` if an invalid mixer control was specified, or if the specified volumes were out-of-range.

`oss_mixer_device.get_recsrc()`

This method returns a bitmask indicating which control(s) are currently being used as a recording source.

`oss_mixer_device.set_recsrc(bitmask)`

Call this function to specify a recording source. Returns a bitmask indicating the new recording source (or sources) if successful; raises *IOError* if an invalid source was specified. To set the current recording source to the microphone input:

```
mixer.setrecsrc (1 << ossaudiodev.SOUND_MIXER_MIC)
```

The modules described in this chapter help you write software that is independent of language and locale by providing mechanisms for selecting a language to be used in program messages or by tailoring output to match local conventions.

The list of modules described in this chapter is:

22.1 `gettext` — Multilingual internationalization services

Source code: [Lib/gettext.py](#)

The `gettext` module provides internationalization (I18N) and localization (L10N) services for your Python modules and applications. It supports both the GNU `gettext` message catalog API and a higher level, class-based API that may be more appropriate for Python files. The interface described below allows you to write your module and application messages in one natural language, and provide a catalog of translated messages for running under different natural languages.

Some hints on localizing your Python modules and applications are also given.

22.1.1 GNU `gettext` API

The `gettext` module defines the following API, which is very similar to the GNU `gettext` API. If you use this API you will affect the translation of your entire application globally. Often this is what you want if your application is monolingual, with the choice of language dependent on the locale of your user. If you are localizing a Python module, or if your application needs to switch languages on the fly, you probably want to use the class-based API instead.

`gettext.bindtextdomain(domain[, localedir])`

Bind the *domain* to the locale directory *localedir*. More concretely, `gettext` will look for binary `.mo` files for the given domain using the path (on Unix): `localedir/language/LC_MESSAGES/domain.mo`, where *languages* is searched for in the environment variables `LANGUAGE`, `LC_ALL`, `LC_MESSAGES`, and `LANG` respectively.

If *localedir* is omitted or *None*, then the current binding for *domain* is returned.¹

`gettext.bind_textdomain_codeset (domain[, codeset])`

Bind the *domain* to *codeset*, changing the encoding of strings returned by the `gettext()` family of functions. If *codeset* is omitted, then the current binding is returned.

버전 2.4에 추가.

`gettext.textdomain ([domain])`

Change or query the current global domain. If *domain* is *None*, then the current global domain is returned, otherwise the global domain is set to *domain*, which is returned.

`gettext.gettext (message)`

Return the localized translation of *message*, based on the current global domain, language, and locale directory. This function is usually aliased as `_()` in the local namespace (see examples below).

`gettext.lgettext (message)`

Equivalent to `gettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `bind_textdomain_codeset()`.

버전 2.4에 추가.

`gettext.dgettext (domain, message)`

Like `gettext()`, but look the message up in the specified *domain*.

`gettext.ldgettext (domain, message)`

Equivalent to `dgettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `bind_textdomain_codeset()`.

버전 2.4에 추가.

`gettext.ngettext (singular, plural, n)`

Like `gettext()`, but consider plural forms. If a translation is found, apply the plural formula to *n*, and return the resulting message (some languages have more than two plural forms). If no translation is found, return *singular* if *n* is 1; return *plural* otherwise.

The Plural formula is taken from the catalog header. It is a C or Python expression that has a free variable *n*; the expression evaluates to the index of the plural in the catalog. See the GNU gettext documentation for the precise syntax to be used in `.po` files and the formulas for a variety of languages.

버전 2.3에 추가.

`gettext.lngettext (singular, plural, n)`

Equivalent to `ngettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `bind_textdomain_codeset()`.

버전 2.4에 추가.

`gettext.dngettext (domain, singular, plural, n)`

Like `lngettext()`, but look the message up in the specified *domain*.

버전 2.3에 추가.

`gettext.ldngettext (domain, singular, plural, n)`

Equivalent to `dngettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `bind_textdomain_codeset()`.

버전 2.4에 추가.

¹ The default locale directory is system dependent; for example, on RedHat Linux it is `/usr/share/locale`, but on Solaris it is `/usr/lib/locale`. The `gettext` module does not try to support these system dependent defaults; instead its default is `sys.prefix/share/locale`. For this reason, it is always best to call `bindtextdomain()` with an explicit absolute path at the start of your application.

Note that GNU **gettext** also defines a `dcgettext()` method, but this was deemed not useful and so it is currently unimplemented.

Here's an example of typical usage for this API:

```
import gettext
gettext.bindtextdomain('myapplication', '/path/to/my/language/directory')
gettext.textdomain('myapplication')
_ = gettext.gettext
# ...
print _('This is a translatable string.')
```

22.1.2 Class-based API

The class-based API of the `gettext` module gives you more flexibility and greater convenience than the GNU **gettext** API. It is the recommended way of localizing your Python applications and modules. `gettext` defines a `Translations` class which implements the parsing of GNU `.mo` format files, and has methods for returning either standard 8-bit strings or Unicode strings. Instances of this `Translations` class can also install themselves in the built-in namespace as the function `_()`.

`gettext.find(domain[, locale_dir[, languages[, all]]])`

This function implements the standard `.mo` file search algorithm. It takes a *domain*, identical to what `textdomain()` takes. Optional *locale_dir* is as in `bindtextdomain()`. Optional *languages* is a list of strings, where each string is a language code.

If *locale_dir* is not given, then the default system locale directory is used.² If *languages* is not given, then the following environment variables are searched: `LANGUAGE`, `LC_ALL`, `LC_MESSAGES`, and `LANG`. The first one returning a non-empty value is used for the *languages* variable. The environment variables should contain a colon separated list of languages, which will be split on the colon to produce the expected list of language code strings.

`find()` then expands and normalizes the languages, and then iterates through them, searching for an existing file built of these components:

`locale_dir/language/LC_MESSAGES/domain.mo`

The first such file name that exists is returned by `find()`. If no such file is found, then `None` is returned. If *all* is given, it returns a list of all file names, in the order in which they appear in the *languages* list or the environment variables.

`gettext.translation(domain[, locale_dir[, languages[, class_[, fallback[, codeset]]]])`

Return a `Translations` instance based on the *domain*, *locale_dir*, and *languages*, which are first passed to `find()` to get a list of the associated `.mo` file paths. Instances with identical `.mo` file names are cached. The actual class instantiated is either *class_* if provided, otherwise `GNUTranslations`. The class's constructor must take a single file object argument. If provided, *codeset* will change the charset used to encode translated strings.

If multiple files are found, later files are used as fallbacks for earlier ones. To allow setting the fallback, `copy.copy()` is used to clone each translation object from the cache; the actual instance data is still shared with the cache.

If no `.mo` file is found, this function raises `IOError` if *fallback* is false (which is the default), and returns a `NullTranslations` instance if *fallback* is true.

버전 2.4에서 변경: Added the *codeset* parameter.

`gettext.install(domain[, locale_dir[, unicode[, codeset[, names]]])`

This installs the function `_()` in Python's builtins namespace, based on *domain*, *locale_dir*, and *codeset* which

² See the footnote for `bindtextdomain()` above.

are passed to the function `translation()`. The `unicode` flag is passed to the resulting translation object's `install()` method.

For the `names` parameter, please see the description of the translation object's `install()` method.

As seen below, you usually mark the strings in your application that are candidates for translation, by wrapping them in a call to the `_()` function, like this:

```
print _('This string will be translated.')
```

For convenience, you want the `_()` function to be installed in Python's builtins namespace, so it is easily accessible in all modules of your application.

버전 2.4에서 변경: Added the `codeset` parameter.

버전 2.5에서 변경: Added the `names` parameter.

The `NullTranslations` class

Translation classes are what actually implement the translation of original source file message strings to translated message strings. The base class used by all translation classes is `NullTranslations`; this provides the basic interface you can use to write your own specialized translation classes. Here are the methods of `NullTranslations`:

class `gettext.NullTranslations([fp])`

Takes an optional file object `fp`, which is ignored by the base class. Initializes 《protected》 instance variables `_info` and `_charset` which are set by derived classes, as well as `_fallback`, which is set through `add_fallback()`. It then calls `self._parse(fp)` if `fp` is not `None`.

_parse (`fp`)

No-op'd in the base class, this method takes file object `fp`, and reads the data from the file, initializing its message catalog. If you have an unsupported message catalog file format, you should override this method to parse your format.

add_fallback (`fallback`)

Add `fallback` as the fallback object for the current translation object. A translation object should consult the fallback if it cannot provide a translation for a given message.

gettext (`message`)

If a fallback has been set, forward `gettext()` to the fallback. Otherwise, return the translated message. Overridden in derived classes.

lgettext (`message`)

If a fallback has been set, forward `lgettext()` to the fallback. Otherwise, return the translated message. Overridden in derived classes.

버전 2.4에 추가.

ugettext (`message`)

If a fallback has been set, forward `ugettext()` to the fallback. Otherwise, return the translated message as a Unicode string. Overridden in derived classes.

ngettext (`singular`, `plural`, `n`)

If a fallback has been set, forward `ngettext()` to the fallback. Otherwise, return the translated message. Overridden in derived classes.

버전 2.3에 추가.

lngettext (`singular`, `plural`, `n`)

If a fallback has been set, forward `lngettext()` to the fallback. Otherwise, return the translated message. Overridden in derived classes.

버전 2.4에 추가.

ungettext (*singular, plural, n*)

If a fallback has been set, forward `ungettext()` to the fallback. Otherwise, return the translated message as a Unicode string. Overridden in derived classes.

버전 2.3에 추가.

info ()

Return the `__protected__` `_info` variable.

charset ()

Return the `__protected__` `_charset` variable.

output_charset ()

Return the `__protected__` `_output_charset` variable, which defines the encoding used to return translated messages.

버전 2.4에 추가.

set_output_charset (*charset*)

Change the `__protected__` `_output_charset` variable, which defines the encoding used to return translated messages.

버전 2.4에 추가.

install ([*unicode*, *names*])

If the *unicode* flag is false, this method installs `self.gettext()` into the built-in namespace, binding it to `_`. If *unicode* is true, it binds `self.ugettext()` instead. By default, *unicode* is false.

If the *names* parameter is given, it must be a sequence containing the names of functions you want to install in the builtins namespace in addition to `_()`. Supported names are 'gettext' (bound to `self.gettext()` or `self.ugettext()` according to the *unicode* flag), 'ngettext' (bound to `self.ngettext()` or `self.ungettext()` according to the *unicode* flag), 'lgettext' and 'lngettext'.

Note that this is only one way, albeit the most convenient way, to make the `_()` function available to your application. Because it affects the entire application globally, and specifically the built-in namespace, localized modules should never install `_()`. Instead, they should use this code to make `_()` available to their module:

```
import gettext
t = gettext.translation('mymodule', ...)
_ = t.gettext
```

This puts `_()` only in the module's global namespace and so only affects calls within this module.

버전 2.5에서 변경: Added the *names* parameter.

The GNUTranslations class

The `gettext` module provides one additional class derived from `NullTranslations`: `GNUTranslations`. This class overrides `_parse()` to enable reading GNU `gettext` format `.mo` files in both big-endian and little-endian format. It also coerces both message ids and message strings to Unicode.

`GNUTranslations` parses optional meta-data out of the translation catalog. It is convention with GNU `gettext` to include meta-data as the translation for the empty string. This meta-data is in [RFC 822](#)-style `key: value` pairs, and should contain the `Project-Id-Version` key. If the key `Content-Type` is found, then the `charset` property is used to initialize the `__protected__` `_charset` instance variable, defaulting to `None` if not found. If the `charset` encoding is specified, then all message ids and message strings read from the catalog are converted to Unicode using this encoding. The `ugettext()` method always returns a Unicode, while the `gettext()` returns an encoded 8-bit

string. For the message id arguments of both methods, either Unicode strings or 8-bit strings containing only US-ASCII characters are acceptable. Note that the Unicode version of the methods (i.e. `ugettext()` and `ungettext()`) are the recommended interface to use for internationalized Python programs.

The entire set of key/value pairs are placed into a dictionary and set as the 《protected》 `_info` instance variable.

If the `.mo` file's magic number is invalid, or if other problems occur while reading the file, instantiating a `GNUTranslations` class can raise `IOError`.

The following methods are overridden from the base class implementation:

`GNUTranslations.gettext(message)`

Look up the *message* id in the catalog and return the corresponding message string, as an 8-bit string encoded with the catalog's charset encoding, if known. If there is no entry in the catalog for the *message* id, and a fallback has been set, the look up is forwarded to the fallback's *gettext()* method. Otherwise, the *message* id is returned.

`GNUTranslations.lgettext(message)`

Equivalent to *gettext()*, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `set_output_charset()`.

버전 2.4에 추가.

`GNUTranslations.ugettext(message)`

Look up the *message* id in the catalog and return the corresponding message string, as a Unicode string. If there is no entry in the catalog for the *message* id, and a fallback has been set, the look up is forwarded to the fallback's *ugettext()* method. Otherwise, the *message* id is returned.

`GNUTranslations.ngettext(singular, plural, n)`

Do a plural-forms lookup of a message id. *singular* is used as the message id for purposes of lookup in the catalog, while *n* is used to determine which plural form to use. The returned message string is an 8-bit string encoded with the catalog's charset encoding, if known.

If the message id is not found in the catalog, and a fallback is specified, the request is forwarded to the fallback's *ngettext()* method. Otherwise, when *n* is 1 *singular* is returned, and *plural* is returned in all other cases.

버전 2.3에 추가.

`GNUTranslations.lngettext(singular, plural, n)`

Equivalent to *gettext()*, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `set_output_charset()`.

버전 2.4에 추가.

`GNUTranslations.ungettext(singular, plural, n)`

Do a plural-forms lookup of a message id. *singular* is used as the message id for purposes of lookup in the catalog, while *n* is used to determine which plural form to use. The returned message string is a Unicode string.

If the message id is not found in the catalog, and a fallback is specified, the request is forwarded to the fallback's *ungettext()* method. Otherwise, when *n* is 1 *singular* is returned, and *plural* is returned in all other cases.

Here is an example:

```
n = len(os.listdir('.'))
cat = GNUTranslations(somefile)
message = cat.ungettext(
    'There is %(num)d file in this directory',
    'There are %(num)d files in this directory',
    n) % {'num': n}
```

버전 2.3에 추가.

Solaris message catalog support

The Solaris operating system defines its own binary `.mo` file format, but since no documentation can be found on this format, it is not supported at this time.

The Catalog constructor

GNOME uses a version of the `gettext` module by James Henstridge, but this version has a slightly different API. Its documented usage was:

```
import gettext
cat = gettext.Catalog(domain, localedir)
_ = cat.gettext
print _('hello world')
```

For compatibility with this older module, the function `Catalog()` is an alias for the `translation()` function described above.

One difference between this module and Henstridge's: his catalog objects supported access through a mapping API, but this appears to be unused and so is not currently supported.

22.1.3 Internationalizing your programs and modules

Internationalization (I18N) refers to the operation by which a program is made aware of multiple languages. Localization (L10N) refers to the adaptation of your program, once internationalized, to the local language and cultural habits. In order to provide multilingual messages for your Python programs, you need to take the following steps:

1. prepare your program or module by specially marking translatable strings
2. run a suite of tools over your marked files to generate raw messages catalogs
3. create language specific translations of the message catalogs
4. use the `gettext` module so that message strings are properly translated

In order to prepare your code for I18N, you need to look at all the strings in your files. Any string that needs to be translated should be marked by wrapping it in `_('...')` — that is, a call to the function `_()`. For example:

```
filename = 'mylog.txt'
message = _('writing a log message')
fp = open(filename, 'w')
fp.write(message)
fp.close()
```

In this example, the string `'writing a log message'` is marked as a candidate for translation, while the strings `'mylog.txt'` and `'w'` are not.

The Python distribution comes with two tools which help you generate the message catalogs once you've prepared your source code. These may or may not be available from a binary distribution, but they can be found in a source distribution, in the `Tools/i18n` directory.

The `pygettext`³ program scans all your Python source code looking for the strings you previously marked as translatable. It is similar to the GNU `gettext` program except that it understands all the intricacies of Python source code, but knows nothing about C or C++ source code. You don't need GNU `gettext` unless you're also going to be translating C code (such as C extension modules).

³ François Pinard has written a program called `xpot` which does a similar job. It is available as part of his `po-utils` package.

pygettext generates textual Uniform-style human readable message catalog `.pot` files, essentially structured human readable files which contain every marked string in the source code, along with a placeholder for the translation strings. **pygettext** is a command line script that supports a similar command line interface as **xgettext**; for details on its use, run:

```
pygettext.py --help
```

Copies of these `.pot` files are then handed over to the individual human translators who write language-specific versions for every supported natural language. They send you back the filled in language-specific versions as a `.po` file. Using the **msgfmt.py**⁴ program (in the `Tools/i18n` directory), you take the `.po` files from your translators and generate the machine-readable `.mo` binary catalog files. The `.mo` files are what the `gettext` module uses for the actual translation processing during run-time.

How you use the `gettext` module in your code depends on whether you are internationalizing a single module or your entire application. The next two sections will discuss each case.

Localizing your module

If you are localizing your module, you must take care not to make global changes, e.g. to the built-in namespace. You should not use the GNU `gettext` API but instead the class-based API.

Let's say your module is called `spam` and the module's various natural language translation `.mo` files reside in `/usr/share/locale` in GNU **gettext** format. Here's what you would put at the top of your module:

```
import gettext
t = gettext.translation('spam', '/usr/share/locale')
_ = t.gettext
```

If your translators were providing you with Unicode strings in their `.po` files, you'd instead do:

```
import gettext
t = gettext.translation('spam', '/usr/share/locale')
_ = t.ugettext
```

Localizing your application

If you are localizing your application, you can install the `_()` function globally into the built-in namespace, usually in the main driver file of your application. This will let all your application-specific files just use `_('...')` without having to explicitly install it in each file.

In the simple case then, you need only add the following bit of code to the main driver file of your application:

```
import gettext
gettext.install('myapplication')
```

If you need to set the locale directory or the `unicode` flag, you can pass these into the `install()` function:

```
import gettext
gettext.install('myapplication', '/usr/share/locale', unicode=1)
```

⁴ **msgfmt.py** is binary compatible with GNU **msgfmt** except that it provides a simpler, all-Python implementation. With this and **pygettext.py**, you generally won't need to install the GNU **gettext** package to internationalize your Python applications.

Changing languages on the fly

If your program needs to support many languages at the same time, you may want to create multiple translation instances and then switch between them explicitly, like so:

```
import gettext

lang1 = gettext.translation('myapplication', languages=['en'])
lang2 = gettext.translation('myapplication', languages=['fr'])
lang3 = gettext.translation('myapplication', languages=['de'])

# start by using language1
lang1.install()

# ... time goes by, user selects language 2
lang2.install()

# ... more time goes by, user selects language 3
lang3.install()
```

Deferred translations

In most coding situations, strings are translated where they are coded. Occasionally however, you need to mark strings for translation, but defer actual translation until later. A classic example is:

```
animals = ['mollusk',
           'albatross',
           'rat',
           'penguin',
           'python', ]

# ...
for a in animals:
    print a
```

Here, you want to mark the strings in the `animals` list as being translatable, but you don't actually want to translate them until they are printed.

Here is one way you can handle this situation:

```
def _(message): return message

animals = [_('mollusk'),
           _('albatross'),
           _('rat'),
           _('penguin'),
           _('python'), ]

del _

# ...
for a in animals:
    print _(a)
```

This works because the dummy definition of `_()` simply returns the string unchanged. And this dummy definition will temporarily override any definition of `_()` in the built-in namespace (until the `del` command). Take care, though if you have a previous definition of `_()` in the local namespace.

Note that the second use of `_()` will not identify `«a»` as being translatable to the **pygettext** program, since it is not a string.

Another way to handle this is with the following example:

```
def N_(message): return message

animals = [N_('mollusk'),
           N_('albatross'),
           N_('rat'),
           N_('penguin'),
           N_('python'), ]

# ...
for a in animals:
    print _(a)
```

In this case, you are marking translatable strings with the function `N_()`,⁵ which won't conflict with any definition of `_()`. However, you will need to teach your message extraction program to look for translatable strings marked with `N_()`. **pygettext** and **xpot** both support this through the use of command line switches.

gettext () vs. gettext ()

In Python 2.4 the `gettext()` family of functions were introduced. The intention of these functions is to provide an alternative which is more compliant with the current implementation of GNU gettext. Unlike `gettext()`, which returns strings encoded with the same codeset used in the translation file, `gettext()` will return strings encoded with the preferred system encoding, as returned by `locale.getpreferredencoding()`. Also notice that Python 2.4 introduces new functions to explicitly choose the codeset used in translated strings. If a codeset is explicitly set, even `gettext()` will return translated strings in the requested codeset, as would be expected in the GNU gettext implementation.

22.1.4 Acknowledgements

The following people contributed code, feedback, design suggestions, previous implementations, and valuable experience to the creation of this module:

- Peter Funk
- James Henstridge
- Juan David Ibáñez Palomar
- Marc-André Lemburg
- Martin von Löwis
- François Pinard
- Barry Warsaw
- Gustavo Niemeyer

⁵ The choice of `N_()` here is totally arbitrary; it could have just as easily been `MarkThisStringForTranslation()`.

22.2 locale — Internationalization services

The `locale` module opens access to the POSIX locale database and functionality. The POSIX locale mechanism allows programmers to deal with certain cultural issues in an application, without requiring the programmer to know all the specifics of each country where the software is executed.

The `locale` module is implemented on top of the `_locale` module, which in turn uses an ANSI C locale implementation if available.

The `locale` module defines the following exception and functions:

exception `locale.Error`

Exception raised when the locale passed to `setlocale()` is not recognized.

`locale.setlocale(category[, locale])`

If `locale` is given and not `None`, `setlocale()` modifies the locale setting for the `category`. The available categories are listed in the data description below. `locale` may be a string, or an iterable of two strings (language code and encoding). If it's an iterable, it's converted to a locale name using the locale aliasing engine. An empty string specifies the user's default settings. If the modification of the locale fails, the exception `Error` is raised. If successful, the new locale setting is returned.

If `locale` is omitted or `None`, the current setting for `category` is returned.

`setlocale()` is not thread-safe on most systems. Applications typically start with a call of

```
import locale
locale.setlocale(locale.LC_ALL, '')
```

This sets the locale for all categories to the user's default setting (typically specified in the `LANG` environment variable). If the locale is not changed thereafter, using multithreading should not cause problems.

버전 2.0에서 변경: Added support for iterable values of the `locale` parameter.

`locale.localeconv()`

Returns the database of the local conventions as a dictionary. This dictionary has the following strings as keys:

Category	Key	Meaning
<i>LC_NUMERIC</i>	'decimal_point'	Decimal point character.
	'grouping'	Sequence of numbers specifying which relative positions the 'thousands_sep' is expected. If the sequence is terminated with <i>CHAR_MAX</i> , no further grouping is performed. If the sequence terminates with a 0, the last group size is repeatedly used.
	'thousands_sep'	Character used between groups.
<i>LC_MONETARY</i>	'int_curr_symbol'	International currency symbol.
	'currency_symbol'	Local currency symbol.
	'p_cs_precedes/n_cs_precedes'	Whether the currency symbol precedes the value (for positive resp. negative values).
	'p_sep_by_space/n_sep_by_space'	Whether the currency symbol is separated from the value by a space (for positive resp. negative values).
	'mon_decimal_point'	Decimal point used for monetary values.
	'frac_digits'	Number of fractional digits used in local formatting of monetary values.
	'int_frac_digits'	Number of fractional digits used in international formatting of monetary values.
	'mon_thousands_sep'	Group separator used for monetary values.
	'mon_grouping'	Equivalent to 'grouping', used for monetary values.
	'positive_sign'	Symbol used to annotate a positive monetary value.
	'negative_sign'	Symbol used to annotate a negative monetary value.
	'p_sign_posn/n_sign_posn'	The position of the sign (for positive resp. negative values), see below.

All numeric values can be set to *CHAR_MAX* to indicate that there is no value specified in this locale.

The possible values for 'p_sign_posn' and 'n_sign_posn' are given below.

Value	Explanation
0	Currency and value are surrounded by parentheses.
1	The sign should precede the value and currency symbol.
2	The sign should follow the value and currency symbol.
3	The sign should immediately precede the value.
4	The sign should immediately follow the value.
<i>CHAR_MAX</i>	Nothing is specified in this locale.

`locale.nl_langinfo(option)`

Return some locale-specific information as a string. This function is not available on all systems, and the set of possible options might also vary across platforms. The possible argument values are numbers, for which symbolic

constants are available in the `locale` module.

The `nl_langinfo()` function accepts one of the following keys. Most descriptions are taken from the corresponding description in the GNU C library.

`locale.CODESET`

Get a string with the name of the character encoding used in the selected locale.

`locale.D_T_FMT`

Get a string that can be used as a format string for `time.strftime()` to represent date and time in a locale-specific way.

`locale.D_FMT`

Get a string that can be used as a format string for `time.strftime()` to represent a date in a locale-specific way.

`locale.T_FMT`

Get a string that can be used as a format string for `time.strftime()` to represent a time in a locale-specific way.

`locale.T_FMT_AMPM`

Get a format string for `time.strftime()` to represent time in the am/pm format.

`DAY_1 ... DAY_7`

Get the name of the n-th day of the week.

참고: This follows the US convention of `DAY_1` being Sunday, not the international convention (ISO 8601) that Monday is the first day of the week.

`ABDAY_1 ... ABDAY_7`

Get the abbreviated name of the n-th day of the week.

`MON_1 ... MON_12`

Get the name of the n-th month.

`ABMON_1 ... ABMON_12`

Get the abbreviated name of the n-th month.

`locale.RADIXCHAR`

Get the radix character (decimal dot, decimal comma, etc.).

`locale.THOUSEP`

Get the separator character for thousands (groups of three digits).

`locale.YESEXPR`

Get a regular expression that can be used with the `regex` function to recognize a positive response to a yes/no question.

참고: The expression is in the syntax suitable for the `regex()` function from the C library, which might differ from the syntax used in `re`.

`locale.NOEXPR`

Get a regular expression that can be used with the `regex(3)` function to recognize a negative response to a yes/no question.

`locale.CRNCYSTR`

Get the currency symbol, preceded by `<->` if the symbol should appear before the value, `<+>` if the symbol should appear after the value, or `<.>` if the symbol should replace the radix character.

locale.ERA

Get a string that represents the era used in the current locale.

Most locales do not define this value. An example of a locale which does define this value is the Japanese one. In Japan, the traditional representation of dates includes the name of the era corresponding to the then-emperor's reign.

Normally it should not be necessary to use this value directly. Specifying the `E` modifier in their format strings causes the `time.strftime()` function to use this information. The format of the returned string is not specified, and therefore you should not assume knowledge of it on different systems.

locale.ERA_D_T_FMT

Get a format string for `time.strftime()` to represent date and time in a locale-specific era-based way.

locale.ERA_D_FMT

Get a format string for `time.strftime()` to represent a date in a locale-specific era-based way.

locale.ERA_T_FMT

Get a format string for `time.strftime()` to represent a time in a locale-specific era-based way.

locale.ALT_DIGITS

Get a representation of up to 100 values used to represent the values 0 to 99.

locale.getdefaultlocale([envvars])

Tries to determine the default locale settings and returns them as a tuple of the form (language code, encoding).

According to POSIX, a program which has not called `setlocale(LC_ALL, '')` runs using the portable 'C' locale. Calling `setlocale(LC_ALL, '')` lets it use the default locale as defined by the `LANG` variable. Since we do not want to interfere with the current locale setting we thus emulate the behavior in the way described above.

To maintain compatibility with other platforms, not only the `LANG` variable is tested, but a list of variables given as `envvars` parameter. The first found to be defined will be used. `envvars` defaults to the search path used in GNU gettext; it must always contain the variable name `LANG`. The GNU gettext search path contains 'LANGUAGE', 'LC_ALL', 'LC_CTYPE', and 'LANG', in that order.

Except for the code 'C', the language code corresponds to [RFC 1766](#). *language code* and *encoding* may be None if their values cannot be determined.

버전 2.0에 추가.

locale.getlocale([category])

Returns the current setting for the given locale category as sequence containing *language code*, *encoding*. *category* may be one of the `LC_*` values except `LC_ALL`. It defaults to `LC_CTYPE`.

Except for the code 'C', the language code corresponds to [RFC 1766](#). *language code* and *encoding* may be None if their values cannot be determined.

버전 2.0에 추가.

locale.getpreferredencoding([do_setlocale])

Return the encoding used for text data, according to user preferences. User preferences are expressed differently on different systems, and might not be available programmatically on some systems, so this function only returns a guess.

On some systems, it is necessary to invoke `setlocale()` to obtain the user preferences, so this function is not thread-safe. If invoking `setlocale` is not necessary or desired, `do_setlocale` should be set to `False`.

버전 2.3에 추가.

locale.normalize(localename)

Returns a normalized locale code for the given locale name. The returned locale code is formatted for use with `setlocale()`. If normalization fails, the original name is returned unchanged.

If the given encoding is not known, the function defaults to the default encoding for the locale code just like `setlocale()`.

버전 2.0에 추가.

`locale.resetlocale([category])`

Sets the locale for *category* to the default setting.

The default setting is determined by calling `getdefaultlocale()`. *category* defaults to `LC_ALL`.

버전 2.0에 추가.

`locale.strcoll(string1, string2)`

Compares two strings according to the current `LC_COLLATE` setting. As any other compare function, returns a negative, or a positive value, or 0, depending on whether *string1* collates before or after *string2* or is equal to it.

`locale.strxfrm(string)`

Transforms a string to one that can be used for the built-in function `cmp()`, and still returns locale-aware results. This function can be used when the same string is compared repeatedly, e.g. when collating a sequence of strings.

`locale.format(format, val[, grouping[, monetary]])`

Formats a number *val* according to the current `LC_NUMERIC` setting. The format follows the conventions of the `%` operator. For floating point values, the decimal point is modified if appropriate. If *grouping* is true, also takes the grouping into account.

If *monetary* is true, the conversion uses monetary thousands separator and grouping strings.

Please note that this function will only work for exactly one `%char` specifier. For whole format strings, use `format_string()`.

버전 2.5에서 변경: Added the *monetary* parameter.

`locale.format_string(format, val[, grouping])`

Processes formatting specifiers as in `format % val`, but takes the current locale settings into account.

버전 2.5에 추가.

`locale.currency(val[, symbol[, grouping[, international]]])`

Formats a number *val* according to the current `LC_MONETARY` settings.

The returned string includes the currency symbol if *symbol* is true, which is the default. If *grouping* is true (which is not the default), grouping is done with the value. If *international* is true (which is not the default), the international currency symbol is used.

Note that this function will not work with the `<C>` locale, so you have to set a locale via `setlocale()` first.

버전 2.5에 추가.

`locale.str(float)`

Formats a floating point number using the same format as the built-in function `str(float)`, but takes the decimal point into account.

`locale.atof(string)`

Converts a string to a floating point number, following the `LC_NUMERIC` settings.

`locale.atoi(string)`

Converts a string to an integer, following the `LC_NUMERIC` conventions.

`locale.LC_CTYPE`

Locale category for the character type functions. Depending on the settings of this category, the functions of module `string` dealing with case change their behaviour.

locale.LC_COLLATE

Locale category for sorting strings. The functions `strcoll()` and `strxfrm()` of the `locale` module are affected.

locale.LC_TIME

Locale category for the formatting of time. The function `time.strftime()` follows these conventions.

locale.LC_MONETARY

Locale category for formatting of monetary values. The available options are available from the `localeconv()` function.

locale.LC_MESSAGES

Locale category for message display. Python currently does not support application specific locale-aware messages. Messages displayed by the operating system, like those returned by `os.strerror()` might be affected by this category.

locale.LC_NUMERIC

Locale category for formatting numbers. The functions `format()`, `atoi()`, `atof()` and `str()` of the `locale` module are affected by that category. All other numeric formatting operations are not affected.

locale.LC_ALL

Combination of all locale settings. If this flag is used when the locale is changed, setting the locale for all categories is attempted. If that fails for any category, no category is changed at all. When the locale is retrieved using this flag, a string indicating the setting for all categories is returned. This string can be later used to restore the settings.

locale.CHAR_MAX

This is a symbolic constant used for different values returned by `localeconv()`.

Example:

```
>>> import locale
>>> loc = locale.getlocale() # get current locale
# use German locale; name might vary with platform
>>> locale.setlocale(locale.LC_ALL, 'de_DE')
>>> locale.strcoll('f\x4e4n', 'foo') # compare a string containing an umlaut
>>> locale.setlocale(locale.LC_ALL, '') # use user's preferred locale
>>> locale.setlocale(locale.LC_ALL, 'C') # use default (C) locale
>>> locale.setlocale(locale.LC_ALL, loc) # restore saved locale
```

22.2.1 Background, details, hints, tips and caveats

The C standard defines the locale as a program-wide property that may be relatively expensive to change. On top of that, some implementation are broken in such a way that frequent locale changes may cause core dumps. This makes the locale somewhat painful to use correctly.

Initially, when a program is started, the locale is the C locale, no matter what the user's preferred locale is. The program must explicitly say that it wants the user's preferred locale settings by calling `setlocale(LC_ALL, '')`.

It is generally a bad idea to call `setlocale()` in some library routine, since as a side effect it affects the entire program. Saving and restoring it is almost as bad: it is expensive and affects other threads that happen to run before the settings have been restored.

If, when coding a module for general use, you need a locale independent version of an operation that is affected by the locale (such as `string.lower()`, or certain formats used with `time.strftime()`), you will have to find a way to do it without using the standard library routine. Even better is convincing yourself that using locale settings is okay. Only as a last resort should you document that your module is not compatible with non-C locale settings.

The case conversion functions in the `string` module are affected by the locale settings. When a call to the `setlocale()` function changes the `LC_CTYPE` settings, the variables `string.lowercase`, `string.`

uppercase and `string.letters` are recalculated. Note that code that uses these variable through `<from ... import ...>`, e.g. `from string import letters`, is not affected by subsequent `setlocale()` calls.

The only way to perform numeric operations according to the locale is to use the special functions defined by this module: `atof()`, `atoi()`, `format()`, `str()`.

22.2.2 For extension writers and programs that embed Python

Extension modules should never call `setlocale()`, except to find out what the current locale is. But since the return value can only be used portably to restore it, that is not very useful (except perhaps to find out whether or not the locale is C).

When Python code uses the `locale` module to change the locale, this also affects the embedding application. If the embedding application doesn't want this to happen, it should remove the `_locale` extension module (which does all the work) from the table of built-in modules in the `config.c` file, and make sure that the `_locale` module is not accessible as a shared library.

22.2.3 Access to message catalogs

```
locale.gettext(msg)
locale.dgettext(domain, msg)
locale.dcgettext(domain, msg, category)
locale.textdomain(domain)
locale.bindtextdomain(domain, dir)
```

The `locale` module exposes the C library's `gettext` interface on systems that provide this interface. It consists of the functions `gettext()`, `dgettext()`, `dcgettext()`, `textdomain()`, `bindtextdomain()`, and `bind_textdomain_codeset()`. These are similar to the same functions in the `gettext` module, but use the C library's binary format for message catalogs, and the C library's search algorithms for locating message catalogs.

Python applications should normally find no need to invoke these functions, and should use `gettext` instead. A known exception to this rule are applications that link with additional C libraries which internally invoke `gettext()` or `dcgettext()`. For these applications, it may be necessary to bind the text domain, so that the libraries can properly locate their message catalogs.

Program Frameworks

The modules described in this chapter are frameworks that will largely dictate the structure of your program. Currently the modules described here are all oriented toward writing command-line interfaces.

The full list of modules described in this chapter is:

23.1 `cmd` — Support for line-oriented command interpreters

Source code: [Lib/cmd.py](#)

The `Cmd` class provides a simple framework for writing line-oriented command interpreters. These are often useful for test harnesses, administrative tools, and prototypes that will later be wrapped in a more sophisticated interface.

class `cmd.Cmd` (`[completekey[, stdin[, stdout]]`)

A `Cmd` instance or subclass instance is a line-oriented interpreter framework. There is no good reason to instantiate `Cmd` itself; rather, it's useful as a superclass of an interpreter class you define yourself in order to inherit `Cmd`'s methods and encapsulate action methods.

The optional argument `completekey` is the `readline` name of a completion key; it defaults to `Tab`. If `completekey` is not `None` and `readline` is available, command completion is done automatically.

The optional arguments `stdin` and `stdout` specify the input and output file objects that the `Cmd` instance or subclass instance will use for input and output. If not specified, they will default to `sys.stdin` and `sys.stdout`.

If you want a given `stdin` to be used, make sure to set the instance's `use_rawinput` attribute to `False`, otherwise `stdin` will be ignored.

버전 2.3에서 변경 : The `stdin` and `stdout` parameters were added.

23.1.1 Cmd Objects

A *Cmd* instance has the following methods:

Cmd.cmdloop ([*intro*])

Repeatedly issue a prompt, accept input, parse an initial prefix off the received input, and dispatch to action methods, passing them the remainder of the line as argument.

The optional argument is a banner or intro string to be issued before the first prompt (this overrides the *intro* class attribute).

If the *readline* module is loaded, input will automatically inherit **bash**-like history-list editing (e.g. Control-P scrolls back to the last command, Control-N forward to the next one, Control-F moves the cursor to the right non-destructively, Control-B moves the cursor to the left non-destructively, etc.).

An end-of-file on input is passed back as the string 'EOF'.

An interpreter instance will recognize a command name *foo* if and only if it has a method *do_foo()*. As a special case, a line beginning with the character '?' is dispatched to the method *do_help()*. As another special case, a line beginning with the character '!' is dispatched to the method *do_shell()* (if such a method is defined).

This method will return when the *postcmd()* method returns a true value. The *stop* argument to *postcmd()* is the return value from the command's corresponding *do_**() method.

If completion is enabled, completing commands will be done automatically, and completing of commands args is done by calling *complete_foo()* with arguments *text*, *line*, *begidx*, and *endidx*. *text* is the string prefix we are attempting to match: all returned matches must begin with it. *line* is the current input line with leading whitespace removed, *begidx* and *endidx* are the beginning and ending indexes of the prefix text, which could be used to provide different completion depending upon which position the argument is in.

All subclasses of *Cmd* inherit a predefined *do_help()*. This method, called with an argument 'bar', invokes the corresponding method *help_bar()*, and if that is not present, prints the docstring of *do_bar()*, if available. With no argument, *do_help()* lists all available help topics (that is, all commands with corresponding *help_**() methods or commands that have docstrings), and also lists any undocumented commands.

Cmd.onecmd (*str*)

Interpret the argument as though it had been typed in response to the prompt. This may be overridden, but should not normally need to be; see the *precmd()* and *postcmd()* methods for useful execution hooks. The return value is a flag indicating whether interpretation of commands by the interpreter should stop. If there is a *do_**() method for the command *str*, the return value of that method is returned, otherwise the return value from the *default()* method is returned.

Cmd.emptyline ()

Method called when an empty line is entered in response to the prompt. If this method is not overridden, it repeats the last nonempty command entered.

Cmd.default (*line*)

Method called on an input line when the command prefix is not recognized. If this method is not overridden, it prints an error message and returns.

Cmd.completedefault (*text*, *line*, *begidx*, *endidx*)

Method called to complete an input line when no command-specific *complete_**() method is available. By default, it returns an empty list.

Cmd.precmd (*line*)

Hook method executed just before the command line *line* is interpreted, but after the input prompt is generated and issued. This method is a stub in *Cmd*; it exists to be overridden by subclasses. The return value is used as the command which will be executed by the *onecmd()* method; the *precmd()* implementation may re-write the command or simply return *line* unchanged.

`Cmd.postcmd(stop, line)`

Hook method executed just after a command dispatch is finished. This method is a stub in `Cmd`; it exists to be overridden by subclasses. *line* is the command line which was executed, and *stop* is a flag which indicates whether execution will be terminated after the call to `postcmd()`; this will be the return value of the `onecmd()` method. The return value of this method will be used as the new value for the internal flag which corresponds to *stop*; returning false will cause interpretation to continue.

`Cmd.preloop()`

Hook method executed once when `cmdloop()` is called. This method is a stub in `Cmd`; it exists to be overridden by subclasses.

`Cmd.postloop()`

Hook method executed once when `cmdloop()` is about to return. This method is a stub in `Cmd`; it exists to be overridden by subclasses.

Instances of `Cmd` subclasses have some public instance variables:

`Cmd.prompt`

The prompt issued to solicit input.

`Cmd.identchars`

The string of characters accepted for the command prefix.

`Cmd.lastcmd`

The last nonempty command prefix seen.

`Cmd.cmdqueue`

A list of queued input lines. The `cmdqueue` list is checked in `cmdloop()` when new input is needed; if it is nonempty, its elements will be processed in order, as if entered at the prompt.

`Cmd.intro`

A string to issue as an intro or banner. May be overridden by giving the `cmdloop()` method an argument.

`Cmd.doc_header`

The header to issue if the help output has a section for documented commands.

`Cmd.misc_header`

The header to issue if the help output has a section for miscellaneous help topics (that is, there are `help_*()` methods without corresponding `do_*()` methods).

`Cmd.undoc_header`

The header to issue if the help output has a section for undocumented commands (that is, there are `do_*()` methods without corresponding `help_*()` methods).

`Cmd.ruler`

The character used to draw separator lines under the help-message headers. If empty, no ruler line is drawn. It defaults to '='.

`Cmd.use_rawinput`

A flag, defaulting to true. If true, `cmdloop()` uses `raw_input()` to display a prompt and read the next command; if false, `sys.stdout.write()` and `sys.stdin.readline()` are used. (This means that by importing `readline`, on systems that support it, the interpreter will automatically support **Emacs**-like line editing and command-history keystrokes.)

23.2 shlex — Simple lexical analysis

버전 1.5.2에 추가.

Source code: [Lib/shlex.py](#)

The `shlex` class makes it easy to write lexical analyzers for simple syntaxes resembling that of the Unix shell. This will often be useful for writing minilanguages, (for example, in run control files for Python applications) or for parsing quoted strings.

Prior to Python 2.7.3, this module did not support Unicode input.

The `shlex` module defines the following functions:

`shlex.split(s[, comments[, posix]])`

Split the string `s` using shell-like syntax. If `comments` is `False` (the default), the parsing of comments in the given string will be disabled (setting the `commenters` attribute of the `shlex` instance to the empty string). This function operates in POSIX mode by default, but uses non-POSIX mode if the `posix` argument is false.

버전 2.3에 추가.

버전 2.6에서 변경: Added the `posix` parameter.

참고: Since the `split()` function instantiates a `shlex` instance, passing `None` for `s` will read the string to split from standard input.

The `shlex` module defines the following class:

`class shlex.shlex([instream[, infile[, posix]]])`

A `shlex` instance or subclass instance is a lexical analyzer object. The initialization argument, if present, specifies where to read characters from. It must be a file-/stream-like object with `read()` and `readline()` methods, or a string (strings are accepted since Python 2.3). If no argument is given, input will be taken from `sys.stdin`. The second optional argument is a filename string, which sets the initial value of the `infile` attribute. If the `instream` argument is omitted or equal to `sys.stdin`, this second argument defaults to `<stdin>`. The `posix` argument was introduced in Python 2.3, and defines the operational mode. When `posix` is not true (default), the `shlex` instance will operate in compatibility mode. When operating in POSIX mode, `shlex` will try to be as close as possible to the POSIX shell parsing rules.

더 보기:

Module `ConfigParser` Parser for configuration files similar to the Windows `.ini` files.

23.2.1 shlex Objects

A `shlex` instance has the following methods:

`shlex.get_token()`

Return a token. If tokens have been stacked using `push_token()`, pop a token off the stack. Otherwise, read one from the input stream. If reading encounters an immediate end-of-file, `eof` is returned (the empty string `('')` in non-POSIX mode, and `None` in POSIX mode).

`shlex.push_token(str)`

Push the argument onto the token stack.

`shlex.read_token()`

Read a raw token. Ignore the pushback stack, and do not interpret source requests. (This is not ordinarily a useful entry point, and is documented here only for the sake of completeness.)

`shlex.sourcehook(filename)`

When *shlex* detects a source request (see *source* below) this method is given the following token as argument, and expected to return a tuple consisting of a filename and an open file-like object.

Normally, this method first strips any quotes off the argument. If the result is an absolute pathname, or there was no previous source request in effect, or the previous source was a stream (such as `sys.stdin`), the result is left alone. Otherwise, if the result is a relative pathname, the directory part of the name of the file immediately before it on the source inclusion stack is prepended (this behavior is like the way the C preprocessor handles `#include "file.h"`).

The result of the manipulations is treated as a filename, and returned as the first component of the tuple, with *open()* called on it to yield the second component. (Note: this is the reverse of the order of arguments in instance initialization!)

This hook is exposed so that you can use it to implement directory search paths, addition of file extensions, and other namespace hacks. There is no corresponding *<close>* hook, but a *shlex* instance will call the *close()* method of the sourced input stream when it returns EOF.

For more explicit control of source stacking, use the *push_source()* and *pop_source()* methods.

`shlex.push_source(stream[, filename])`

Push an input source stream onto the input stack. If the filename argument is specified it will later be available for use in error messages. This is the same method used internally by the *sourcehook()* method.

버전 2.1에 추가.

`shlex.pop_source()`

Pop the last-pushed input source from the input stack. This is the same method used internally when the lexer reaches EOF on a stacked input stream.

버전 2.1에 추가.

`shlex.error_leader([file[, line]])`

This method generates an error message leader in the format of a Unix C compiler error label; the format is `"%s", line %d: '`, where the `%s` is replaced with the name of the current source file and the `%d` with the current input line number (the optional arguments can be used to override these).

This convenience is provided to encourage *shlex* users to generate error messages in the standard, parseable format understood by Emacs and other Unix tools.

Instances of *shlex* subclasses have some public instance variables which either control lexical analysis or can be used for debugging:

`shlex.commenters`

The string of characters that are recognized as comment beginners. All characters from the comment beginner to end of line are ignored. Includes just `'#'` by default.

`shlex.wordchars`

The string of characters that will accumulate into multi-character tokens. By default, includes all ASCII alphanumerics and underscore.

`shlex.whitespace`

Characters that will be considered whitespace and skipped. Whitespace bounds tokens. By default, includes space, tab, linefeed and carriage-return.

`shlex.escape`

Characters that will be considered as escape. This will be only used in POSIX mode, and includes just `'\'` by default.

버전 2.3에 추가.

shlex.quotes

Characters that will be considered string quotes. The token accumulates until the same quote is encountered again (thus, different quote types protect each other as in the shell.) By default, includes ASCII single and double quotes.

shlex.escapedquotes

Characters in *quotes* that will interpret escape characters defined in *escape*. This is only used in POSIX mode, and includes just ' ' by default.

버전 2.3에 추가.

shlex.whitespace_split

If True, tokens will only be split in whitespaces. This is useful, for example, for parsing command lines with *shlex*, getting tokens in a similar way to shell arguments.

버전 2.3에 추가.

shlex.infile

The name of the current input file, as initially set at class instantiation time or stacked by later source requests. It may be useful to examine this when constructing error messages.

shlex.instream

The input stream from which this *shlex* instance is reading characters.

shlex.source

This attribute is None by default. If you assign a string to it, that string will be recognized as a lexical-level inclusion request similar to the *source* keyword in various shells. That is, the immediately following token will be opened as a filename and input will be taken from that stream until EOF, at which point the *close()* method of that stream will be called and the input source will again become the original input stream. Source requests may be stacked any number of levels deep.

shlex.debug

If this attribute is numeric and 1 or more, a *shlex* instance will print verbose progress output on its behavior. If you need to use this, you can read the module source code to learn the details.

shlex.lineno

Source line number (count of newlines seen so far plus one).

shlex.token

The token buffer. It may be useful to examine this when catching exceptions.

shlex.eof

Token used to determine end of file. This will be set to the empty string (' '), in non-POSIX mode, and to None in POSIX mode.

버전 2.3에 추가.

23.2.2 Parsing Rules

When operating in non-POSIX mode, *shlex* will try to obey to the following rules.

- Quote characters are not recognized within words (Do"Not Separate is parsed as the single word Do"Not Separate);
- Escape characters are not recognized;
- Enclosing characters in quotes preserve the literal value of all characters within the quotes;
- Closing quotes separate words ("Do Separate is parsed as "Do" and Separate);

- If `whitespace_split` is `False`, any character not declared to be a word character, whitespace, or a quote will be returned as a single-character token. If it is `True`, `shlex` will only split words in whitespaces;
- EOF is signaled with an empty string (' ');
- It's not possible to parse empty strings, even if quoted.

When operating in POSIX mode, `shlex` will try to obey to the following parsing rules.

- Quotes are stripped out, and do not separate words ("Do"Not"Separate" is parsed as the single word `DoNotSeparate`);
- Non-quoted escape characters (e.g. ' \ ') preserve the literal value of the next character that follows;
- Enclosing characters in quotes which are not part of `escapedquotes` (e.g. " ' ") preserve the literal value of all characters within the quotes;
- Enclosing characters in quotes which are part of `escapedquotes` (e.g. ' " ') preserves the literal value of all characters within the quotes, with the exception of the characters mentioned in `escape`. The escape characters retain its special meaning only when followed by the quote in use, or the escape character itself. Otherwise the escape character will be considered a normal character.
- EOF is signaled with a `None` value;
- Quoted empty strings (' ') are allowed;

Graphical User Interfaces with Tk

Tk/Tcl has long been an integral part of Python. It provides a robust and platform independent windowing toolkit, that is available to Python programmers using the *Tkinter* module, and its extensions, the *Tix* and the *ttk* modules.

The *Tkinter* module is a thin object-oriented layer on top of Tcl/Tk. To use *Tkinter*, you don't need to write Tcl code, but you will need to consult the Tk documentation, and occasionally the Tcl documentation. *Tkinter* is a set of wrappers that implement the Tk widgets as Python classes. In addition, the internal module `_tkinter` provides a threadsafe mechanism which allows Python and Tcl to interact.

Tkinter's chief virtues are that it is fast, and that it usually comes bundled with Python. Although its standard documentation is weak, good material is available, which includes: references, tutorials, a book and others. *Tkinter* is also famous for having an outdated look and feel, which has been vastly improved in Tk 8.5. Nevertheless, there are many other GUI libraries that you could be interested in. For more information about alternatives, see the *Other Graphical User Interface Packages* section.

24.1 Tkinter — Python interface to Tcl/Tk

The *Tkinter* module (《Tk interface》) is the standard Python interface to the Tk GUI toolkit. Both Tk and *Tkinter* are available on most Unix platforms, as well as on Windows systems. (Tk itself is not part of Python; it is maintained at ActiveState.)

Running `python -m Tkinter` from the command line should open a window demonstrating a simple Tk interface, letting you know that *Tkinter* is properly installed on your system, and also showing what version of Tcl/Tk is installed, so you can read the Tcl/Tk documentation specific to that version.

참고: *Tkinter* has been renamed to `tkinter` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

더 보기:

Tkinter documentation:

Python Tkinter Resources The Python Tkinter Topic Guide provides a great deal of information on using Tk from Python and links to other sources of information on Tk.

TKDocs Extensive tutorial plus friendlier widget pages for some of the widgets.

Tkinter 8.5 reference: a GUI for Python On-line reference material.

Tkinter docs from effbot Online reference for tkinter supported by effbot.org.

Programming Python Book by Mark Lutz, has excellent coverage of Tkinter.

Modern Tkinter for Busy Python Developers Book by Mark Roseman about building attractive and modern graphical user interfaces with Python and Tkinter.

Python and Tkinter Programming Book by John Grayson (ISBN 1-884777-81-3).

Tcl/Tk documentation:

Tk commands Most commands are available as `Tkinter` or `Tkinter.ttk` classes. Change <8.6> to match the version of your Tcl/Tk installation.

Tcl/Tk recent man pages Recent Tcl/Tk manuals on www.tcl.tk.

ActiveState Tcl Home Page The Tk/Tcl development is largely taking place at ActiveState.

Tcl and the Tk Toolkit Book by John Ousterhout, the inventor of Tcl.

Practical Programming in Tcl and Tk Brent Welch's encyclopedic book.

24.1.1 Tkinter Modules

Most of the time, the `Tkinter` module is all you really need, but a number of additional modules are available as well. The Tk interface is located in a binary module named `_tkinter`. This module contains the low-level interface to Tk, and should never be used directly by application programmers. It is usually a shared library (or DLL), but might in some cases be statically linked with the Python interpreter.

In addition to the Tk interface module, `Tkinter` includes a number of Python modules. The two most important modules are the `Tkinter` module itself, and a module called `Tkconstants`. The former automatically imports the latter, so to use Tkinter, all you need to do is to import one module:

```
import Tkinter
```

Or, more often:

```
from Tkinter import *
```

class `Tkinter.Tk` (`screenName=None`, `baseName=None`, `className='Tk'`, `useTk=1`)

The `Tk` class is instantiated without arguments. This creates a toplevel widget of Tk which usually is the main window of an application. Each instance has its own associated Tcl interpreter.

버전 2.4에서 변경: The `useTk` parameter was added.

`Tkinter.Tcl` (`screenName=None`, `baseName=None`, `className='Tk'`, `useTk=0`)

The `Tcl()` function is a factory function which creates an object much like that created by the `Tk` class, except that it does not initialize the Tk subsystem. This is most often useful when driving the Tcl interpreter in an environment where one doesn't want to create extraneous toplevel windows, or where one cannot (such as Unix/Linux systems without an X server). An object created by the `Tcl()` object can have a Toplevel window created (and the Tk subsystem initialized) by calling its `loadtk()` method.

버전 2.4에 추가.

Other modules that provide Tk support include:

ScrolledText Text widget with a vertical scroll bar built in.

tkColorChooser Dialog to let the user choose a color.

tkCommonDialog Base class for the dialogs defined in the other modules listed here.

tkFileDialog Common dialogs to allow the user to specify a file to open or save.

tkFont Utilities to help work with fonts.

tkMessageBox Access to standard Tk dialog boxes.

tkSimpleDialog Basic dialogs and convenience functions.

Tkdnd Drag-and-drop support for *Tkinter*. This is experimental and should become deprecated when it is replaced with the Tk DND.

turtle Turtle graphics in a Tk window.

These have been renamed as well in Python 3; they were all made submodules of the new `tkinter` package.

24.1.2 Tkinter Life Preserver

This section is not designed to be an exhaustive tutorial on either Tk or Tkinter. Rather, it is intended as a stop gap, providing some introductory orientation on the system.

Credits:

- Tkinter was written by Steen Lumholt and Guido van Rossum.
- Tk was written by John Ousterhout while at Berkeley.
- This Life Preserver was written by Matt Conway at the University of Virginia.
- The html rendering, and some liberal editing, was produced from a FrameMaker version by Ken Manheimer.
- Fredrik Lundh elaborated and revised the class interface descriptions, to get them current with Tk 4.2.
- Mike Clarkson converted the documentation to LaTeX, and compiled the User Interface chapter of the reference manual.

How To Use This Section

This section is designed in two parts: the first half (roughly) covers background material, while the second half can be taken to the keyboard as a handy reference.

When trying to answer questions of the form «how do I do blah», it is often best to find out how to do «blah» in straight Tk, and then convert this back into the corresponding *Tkinter* call. Python programmers can often guess at the correct Python command by looking at the Tk documentation. This means that in order to use Tkinter, you will have to know a little bit about Tk. This document can't fulfill that role, so the best we can do is point you to the best documentation that exists. Here are some hints:

- The authors strongly suggest getting a copy of the Tk man pages. Specifically, the man pages in the `mann` directory are most useful. The `man3` man pages describe the C interface to the Tk library and thus are not especially helpful for script writers.
- Addison-Wesley publishes a book called *Tcl and the Tk Toolkit* by John Ousterhout (ISBN 0-201-63337-X) which is a good introduction to Tcl and Tk for the novice. The book is not exhaustive, and for many details it defers to the man pages.
- `Tkinter.py` is a last resort for most, but can be a good place to go when nothing else makes sense.

A Simple Hello World Program

```
from Tkinter import *

class Application(Frame):
    def say_hi(self):
        print "hi there, everyone!"

    def createWidgets(self):
        self.QUIT = Button(self)
        self.QUIT["text"] = "QUIT"
        self.QUIT["fg"] = "red"
        self.QUIT["command"] = self.quit

        self.QUIT.pack({"side": "left"})

        self.hi_there = Button(self)
        self.hi_there["text"] = "Hello",
        self.hi_there["command"] = self.say_hi

        self.hi_there.pack({"side": "left"})

    def __init__(self, master=None):
        Frame.__init__(self, master)
        self.pack()
        self.createWidgets()

root = Tk()
app = Application(master=root)
app.mainloop()
root.destroy()
```

24.1.3 A (Very) Quick Look at Tcl/Tk

The class hierarchy looks complicated, but in actual practice, application programmers almost always refer to the classes at the very bottom of the hierarchy.

Notes:

- These classes are provided for the purposes of organizing certain functions under one namespace. They aren't meant to be instantiated independently.
- The *Tk* class is meant to be instantiated only once in an application. Application programmers need not instantiate one explicitly, the system creates one whenever any of the other classes are instantiated.
- The *Widget* class is not meant to be instantiated, it is meant only for subclassing to make 《real》 widgets (in C++, this is called an 《abstract class》).

To make use of this reference material, there will be times when you will need to know how to read short passages of Tk and how to identify the various parts of a Tk command. (See section *Mapping Basic Tk into Tkinter* for the *Tkinter* equivalents of what's below.)

Tk scripts are Tcl programs. Like all Tcl programs, Tk scripts are just lists of tokens separated by spaces. A Tk widget is just its *class*, the *options* that help configure it, and the *actions* that make it do useful things.

To make a widget in Tk, the command is always of the form:

```
classCommand newPathname options
```

classCommand denotes which kind of widget to make (a button, a label, a menu...)

newPathname is the new name for this widget. All names in Tk must be unique. To help enforce this, widgets in Tk are named with *pathnames*, just like files in a file system. The top level widget, the *root*, is called `.` (period) and children are delimited by more periods. For example, `.myApp.controlPanel.okButton` might be the name of a widget.

options configure the widget's appearance and in some cases, its behavior. The options come in the form of a list of flags and values. Flags are preceded by a `<-<`, like Unix shell command flags, and values are put in quotes if they are more than one word.

For example:

```
button      .fred      -fg red -text "hi there"
  ^          ^          \_____/
  |          |          |
class       new          options
command    widget      (-opt val -opt val ...)
```

Once created, the pathname to the widget becomes a new command. This new *widget command* is the programmer's handle for getting the new widget to perform some *action*. In C, you'd express this as `someAction(fred, someOptions)`, in C++, you would express this as `fred.someAction(someOptions)`, and in Tk, you say:

```
.fred someAction someOptions
```

Note that the object name, `.fred`, starts with a dot.

As you'd expect, the legal values for *someAction* will depend on the widget's class: `.fred disable` works if fred is a button (fred gets greyed out), but does not work if fred is a label (disabling of labels is not supported in Tk).

The legal values of *someOptions* is action dependent. Some actions, like `disable`, require no arguments, others, like a text-entry box's `delete` command, would need arguments to specify what range of text to delete.

24.1.4 Mapping Basic Tk into Tkinter

Class commands in Tk correspond to class constructors in Tkinter.

```
button .fred          =====> fred = Button()
```

The master of an object is implicit in the new name given to it at creation time. In Tkinter, masters are specified explicitly.

```
button .panel.fred     =====> fred = Button(panel)
```

The configuration options in Tk are given in lists of hyphenated tags followed by values. In Tkinter, options are specified as keyword-arguments in the instance constructor, and keyword-args for `configure` calls or as instance indices, in dictionary style, for established instances. See section [Setting Options](#) on setting options.

```
button .fred -fg red    =====> fred = Button(panel, fg = "red")
.fred configure -fg red =====> fred["fg"] = red
OR ==> fred.config(fg = "red")
```

In Tk, to perform an action on a widget, use the widget name as a command, and follow it with an action name, possibly with arguments (options). In Tkinter, you call methods on the class instance to invoke actions on the widget. The actions (methods) that a given widget can perform are listed in the `Tkinter.py` module.

```
.fred invoke          =====> fred.invoke()
```

To give a widget to the packer (geometry manager), you call pack with optional arguments. In Tkinter, the Pack class holds all this functionality, and the various forms of the pack command are implemented as methods. All widgets in *Tkinter* are subclassed from the Packer, and so inherit all the packing methods. See the *Tix* module documentation for additional information on the Form geometry manager.

```
pack .fred -side left  =====> fred.pack(side = "left")
```

24.1.5 How Tk and Tkinter are Related

From the top down:

Your App Here (Python) A Python application makes a *Tkinter* call.

Tkinter (Python Module) This call (say, for example, creating a button widget), is implemented in the *Tkinter* module, which is written in Python. This Python function will parse the commands and the arguments and convert them into a form that makes them look as if they had come from a Tk script instead of a Python script.

tkinter (C) These commands and their arguments will be passed to a C function in the *tkinter* - note the lowercase - extension module.

Tk Widgets (C and Tcl) This C function is able to make calls into other C modules, including the C functions that make up the Tk library. Tk is implemented in C and some Tcl. The Tcl part of the Tk widgets is used to bind certain default behaviors to widgets, and is executed once at the point where the Python *Tkinter* module is imported. (The user never sees this stage).

Tk (C) The Tk part of the Tk Widgets implement the final mapping to ...

Xlib (C) the Xlib library to draw graphics on the screen.

24.1.6 Handy Reference

Setting Options

Options control things like the color and border width of a widget. Options can be set in three ways:

At object creation time, using keyword arguments

```
fred = Button(self, fg = "red", bg = "blue")
```

After object creation, treating the option name like a dictionary index

```
fred["fg"] = "red"
fred["bg"] = "blue"
```

Use the `config()` method to update multiple attrs subsequent to object creation

```
fred.config(fg = "red", bg = "blue")
```

For a complete explanation of a given option and its behavior, see the Tk man pages for the widget in question.

Note that the man pages list 《STANDARD OPTIONS》 and 《WIDGET SPECIFIC OPTIONS》 for each widget. The former is a list of options that are common to many widgets, the latter are the options that are idiosyncratic to that particular widget. The Standard Options are documented on the *options(3)* man page.

No distinction between standard and widget-specific options is made in this document. Some options don't apply to some kinds of widgets. Whether a given widget responds to a particular option depends on the class of the widget; buttons have a `command` option, labels do not.

The options supported by a given widget are listed in that widget's man page, or can be queried at runtime by calling the `config()` method without arguments, or by calling the `keys()` method on that widget. The return value of these calls is a dictionary whose key is the name of the option as a string (for example, `'relief'`) and whose values are 5-tuples.

Some options, like `bg` are synonyms for common options with long names (`bg` is shorthand for `background`). Passing the `config()` method the name of a shorthand option will return a 2-tuple, not 5-tuple. The 2-tuple passed back will contain the name of the synonym and the *real* option (such as `('bg', 'background')`).

Index	Meaning	Example
0	option name	'relief'
1	option name for database lookup	'relief'
2	option class for database lookup	'Relief'
3	default value	'raised'
4	current value	'groove'

Example:

```
>>> print fred.config()
{'relief': ('relief', 'relief', 'Relief', 'raised', 'groove')}
```

Of course, the dictionary printed will include all the options available and their values. This is meant only as an example.

The Packer

The packer is one of Tk's geometry-management mechanisms. Geometry managers are used to specify the relative positioning of the positioning of widgets within their container - their mutual *master*. In contrast to the more cumbersome *placer* (which is used less commonly, and we do not cover here), the packer takes qualitative relationship specification - *above, to the left of, filling*, etc - and works everything out to determine the exact placement coordinates for you.

The size of any *master* widget is determined by the size of the *slave widgets* inside. The packer is used to control where slave widgets appear inside the master into which they are packed. You can pack widgets into frames, and frames into other frames, in order to achieve the kind of layout you desire. Additionally, the arrangement is dynamically adjusted to accommodate incremental changes to the configuration, once it is packed.

Note that widgets do not appear until they have had their geometry specified with a geometry manager. It's a common early mistake to leave out the geometry specification, and then be surprised when the widget is created but nothing appears. A widget will appear only after it has had, for example, the packer's `pack()` method applied to it.

The `pack()` method can be called with keyword-option/value pairs that control where the widget is to appear within its container, and how it is to behave when the main application window is resized. Here are some examples:

```
fred.pack()                                # defaults to side = "top"
fred.pack(side = "left")
fred.pack(expand = 1)
```

Packer Options

For more extensive information on the packer and the options that it can take, see the man pages and page 183 of John Ousterhout's book.

anchor Anchor type. Denotes where the packer is to place each slave in its parcel.

expand Boolean, 0 or 1.

fill Legal values: 'x', 'y', 'both', 'none'.

ipadx and ipady A distance - designating internal padding on each side of the slave widget.

padx and pady A distance - designating external padding on each side of the slave widget.

side Legal values are: 'left', 'right', 'top', 'bottom'.

Coupling Widget Variables

The current-value setting of some widgets (like text entry widgets) can be connected directly to application variables by using special options. These options are `variable`, `textvariable`, `onvalue`, `offvalue`, and `value`. This connection works both ways: if the variable changes for any reason, the widget it's connected to will be updated to reflect the new value.

Unfortunately, in the current implementation of *Tkinter* it is not possible to hand over an arbitrary Python variable to a widget through a `variable` or `textvariable` option. The only kinds of variables for which this works are variables that are subclassed from a class called `Variable`, defined in the *Tkinter* module.

There are many useful subclasses of `Variable` already defined: `StringVar`, `IntVar`, `DoubleVar`, and `BooleanVar`. To read the current value of such a variable, call the `get()` method on it, and to change its value you call the `set()` method. If you follow this protocol, the widget will always track the value of the variable, with no further intervention on your part.

For example:

```
class App(Frame):
    def __init__(self, master=None):
        Frame.__init__(self, master)
        self.pack()

        self.entrythingy = Entry()
        self.entrythingy.pack()

        # here is the application variable
        self.contents = StringVar()
        # set it to some value
        self.contents.set("this is a variable")
        # tell the entry widget to watch this variable
        self.entrythingy["textvariable"] = self.contents

        # and here we get a callback when the user hits return.
        # we will have the program print out the value of the
        # application variable when the user hits return
        self.entrythingy.bind('<Key-Return>',
                              self.print_contents)

    def print_contents(self, event):
        print "hi. contents of entry is now ---->", \
              self.contents.get()
```


The Window Manager

In Tk, there is a utility command, `wm`, for interacting with the window manager. Options to the `wm` command allow you to control things like titles, placement, icon bitmaps, and the like. In *Tkinter*, these commands have been implemented as methods on the `Wm` class. Toplevel widgets are subclassed from the `Wm` class, and so can call the `Wm` methods directly.

To get at the toplevel window that contains a given widget, you can often just refer to the widget's master. Of course if the widget has been packed inside of a frame, the master won't represent a toplevel window. To get at the toplevel window that contains an arbitrary widget, you can call the `_root()` method. This method begins with an underscore to denote the fact that this function is part of the implementation, and not an interface to Tk functionality.

Here are some examples of typical usage:

```
from Tkinter import *
class App(Frame):
    def __init__(self, master=None):
        Frame.__init__(self, master)
        self.pack()

# create the application
myapp = App()

#
# here are method calls to the window manager class
#
myapp.master.title("My Do-Nothing Application")
myapp.master.maxsize(1000, 400)

# start the program
myapp.mainloop()
```

Tk Option Data Types

anchor Legal values are points of the compass: "n", "ne", "e", "se", "s", "sw", "w", "nw", and also "center".

bitmap There are eight built-in, named bitmaps: 'error', 'gray25', 'gray50', 'hourglass', 'info', 'questhead', 'question', 'warning'. To specify an X bitmap filename, give the full path to the file, preceded with an @, as in "@usr/contrib/bitmap/gumby.bit".

boolean You can pass integers 0 or 1 or the strings "yes" or "no".

callback This is any Python function that takes no arguments. For example:

```
def print_it():
    print "hi there"
fred["command"] = print_it
```

color Colors can be given as the names of X colors in the `rgb.txt` file, or as strings representing RGB values in 4 bit: "#RGB", 8 bit: "#RRGGBB", 12 bit: "#RRRGGBBB", or 16 bit: "#RRRRGGGGBBBB" ranges, where R,G,B here represent any legal hex digit. See page 160 of Ousterhout's book for details.

cursor The standard X cursor names from `cursorfont.h` can be used, without the `XC_` prefix. For example to get a hand cursor (`XC_hand2`), use the string "hand2". You can also specify a bitmap and mask file of your own. See page 179 of Ousterhout's book.

distance Screen distances can be specified in either pixels or absolute distances. Pixels are given as numbers and absolute distances as strings, with the trailing character denoting units: *c* for centimetres, *i* for inches, *m* for millimetres, *p* for printer's points. For example, 3.5 inches is expressed as "3.5i".

font Tk uses a list font name format, such as {courier 10 bold}. Font sizes with positive numbers are measured in points; sizes with negative numbers are measured in pixels.

geometry This is a string of the form widthxheight, where width and height are measured in pixels for most widgets (in characters for widgets displaying text). For example: fred["geometry"] = "200x100".

justify Legal values are the strings: "left", "center", "right", and "fill".

region This is a string with four space-delimited elements, each of which is a legal distance (see above). For example: "2 3 4 5" and "3i 2i 4.5i 2i" and "3c 2c 4c 10.43c" are all legal regions.

relief Determines what the border style of a widget will be. Legal values are: "raised", "sunken", "flat", "groove", and "ridge".

scrollcommand This is almost always the set() method of some scrollbar widget, but can be any widget method that takes a single argument. Refer to the file Demo/tkinter/matt/canvas-with-scrollbars.py in the Python source distribution for an example.

wrap: Must be one of: "none", "char", or "word".

Bindings and Events

The bind method from the widget command allows you to watch for certain events and to have a callback function trigger when that event type occurs. The form of the bind method is:

```
def bind(self, sequence, func, add='')
```

where:

sequence is a string that denotes the target kind of event. (See the bind man page and page 201 of John Ousterhout's book for details).

func is a Python function, taking one argument, to be invoked when the event occurs. An Event instance will be passed as the argument. (Functions deployed this way are commonly known as *callbacks*.)

add is optional, either '' or '+'. Passing an empty string denotes that this binding is to replace any other bindings that this event is associated with. Passing a '+' means that this function is to be added to the list of functions bound to this event type.

For example:

```
def turnRed(self, event):
    event.widget["activeforeground"] = "red"

self.button.bind("<Enter>", self.turnRed)
```

Notice how the widget field of the event is being accessed in the turnRed() callback. This field contains the widget that caught the X event. The following table lists the other event fields you can access, and how they are denoted in Tk, which can be useful when referring to the Tk man pages.

Tk	Tkinter Event Field	Tk	Tkinter Event Field
--	-----	--	-----
%f	focus	%A	char
%h	height	%E	send_event
%k	keycode	%K	keysym

(다음 페이지에 계속)

(이전 페이지에서 계속)

%s	state	%N	keysym_num
%t	time	%T	<code>type</code>
%w	width	%W	widget
%x	x	%X	x_root
%y	y	%Y	y_root

The index Parameter

A number of widgets require index parameters to be passed. These are used to point at a specific place in a Text widget, or to particular characters in an Entry widget, or to particular menu items in a Menu widget.

Entry widget indexes (index, view index, etc.) Entry widgets have options that refer to character positions in the text being displayed. You can use these *Tkinter* functions to access these special points in text widgets:

AtEnd() refers to the last position in the text

AtInsert() refers to the point where the text cursor is

AtSelFirst() indicates the beginning point of the selected text

AtSelLast() denotes the last point of the selected text and finally

At(x, y) refers to the character at pixel location *x*, *y* (with *y* not used in the case of a text entry widget, which contains a single line of text).

Text widget indexes The index notation for Text widgets is very rich and is best described in the Tk man pages.

Menu indexes (menu.invoke(), menu.entryconfig(), etc.) Some options and methods for menus manipulate specific menu entries. Anytime a menu index is needed for an option or a parameter, you may pass in:

- an integer which refers to the numeric position of the entry in the widget, counted from the top, starting with 0;
- the string 'active', which refers to the menu position that is currently under the cursor;
- the string "last" which refers to the last menu item;
- An integer preceded by @, as in @6, where the integer is interpreted as a y pixel coordinate in the menu's coordinate system;
- the string "none", which indicates no menu entry at all, most often used with menu.activate() to deactivate all entries, and finally,
- a text string that is pattern matched against the label of the menu entry, as scanned from the top of the menu to the bottom. Note that this index type is considered after all the others, which means that matches for menu items labelled last, active, or none may be interpreted as the above literals, instead.

Images

Images of different formats can be created through the corresponding subclass of `Tkinter.Image`:

- `BitmapImage` for images in XBM format.
- `PhotoImage` for images in PGM, PPM, GIF and PNG formats. The latter is supported starting with Tk 8.6.

Either type of image is created through either the `file` or the `data` option (other options are available as well).

The image object can then be used wherever an `image` option is supported by some widget (e.g. labels, buttons, menus). In these cases, Tk will not keep a reference to the image. When the last Python reference to the image object is deleted, the image data is deleted as well, and Tk will display an empty box wherever the image was used.

더 보기:

The [Pillow](#) package adds support for formats such as BMP, JPEG, TIFF, and WebP, among others.

24.1.7 File Handlers

Tk allows you to register and unregister a callback function which will be called from the Tk mainloop when I/O is possible on a file descriptor. Only one handler may be registered per file descriptor. Example code:

```
import Tkinter
widget = Tkinter.Tk()
mask = Tkinter.READABLE | Tkinter.WRITABLE
widget.tk.createfilehandler(file, mask, callback)
...
widget.tk.deletefilehandler(file)
```

This feature is not available on Windows.

Since you don't know how many bytes are available for reading, you may not want to use the [BufferedIOBase](#) or [TextIOBase](#) [read\(\)](#) or [readline\(\)](#) methods, since these will insist on reading a predefined number of bytes. For sockets, the [recv\(\)](#) or [recvfrom\(\)](#) methods will work fine; for other files, use raw reads or `os.read(file.fileno(), maxbytecount)`.

`Widget.tk.createfilehandler` (*file*, *mask*, *func*)

Registers the file handler callback function *func*. The *file* argument may either be an object with a [fileno\(\)](#) method (such as a file or socket object), or an integer file descriptor. The *mask* argument is an ORed combination of any of the three constants below. The callback is called as follows:

```
callback(file, mask)
```

`Widget.tk.deletefilehandler` (*file*)

Unregisters a file handler.

`Tkinter.READABLE`

`Tkinter.WRITABLE`

`Tkinter.EXCEPTION`

Constants used in the *mask* arguments.

24.2 ttk — Tk themed widgets

The [ttk](#) module provides access to the Tk themed widget set, which has been introduced in Tk 8.5. If Python is not compiled against Tk 8.5 code may still use this module as long as Tk is installed. However, some features provided by the new Tk, like anti-aliased font rendering under X11, window transparency (on X11 you will need a composition window manager) will be missing.

The basic idea of [ttk](#) is to separate, to the extent possible, the code implementing a widget's behavior from the code implementing its appearance.

더 보기:

Tk Widget Styling Support The document which brought up theming support for Tk

24.2.1 Using Ttk

To start using Ttk, import its module:

```
import ttk
```

But code like this:

```
from Tkinter import *
```

may optionally want to use this:

```
from Tkinter import *
from ttk import *
```

And then several *ttk* widgets (Button, Checkbutton, Entry, Frame, Label, LabelFrame, Menubutton, PanedWindow, Radiobutton, Scale and Scrollbar) will automatically substitute for the Tk widgets.

This has the direct benefit of using the new widgets, giving better look & feel across platforms, but be aware that they are not totally compatible. The main difference is that widget options such as `<fg>`, `<bg>` and others related to widget styling are no longer present in Ttk widgets. Use *ttk.Style* to achieve the same (or better) styling.

더 보기:

Converting existing applications to use the Tile widgets A text which talks in Tcl terms about differences typically found when converting applications to use the new widgets.

24.2.2 Ttk Widgets

Ttk comes with 17 widgets, 11 of which already exist in Tkinter: Button, Checkbutton, Entry, Frame, Label, LabelFrame, Menubutton, PanedWindow, Radiobutton, Scale and Scrollbar. The 6 new widget classes are: *Combobox*, *Notebook*, *Progressbar*, *Separator*, *Sizegrip* and *Treeview*. All of these classes are subclasses of *Widget*.

As said previously, you will notice changes in look-and-feel as well in the styling code. To demonstrate the latter, a very simple example is shown below.

Tk code:

```
l1 = Tkinter.Label(text="Test", fg="black", bg="white")
l2 = Tkinter.Label(text="Test", fg="black", bg="white")
```

Corresponding Ttk code:

```
style = ttk.Style()
style.configure("BW.TLabel", foreground="black", background="white")

l1 = ttk.Label(text="Test", style="BW.TLabel")
l2 = ttk.Label(text="Test", style="BW.TLabel")
```

For more information about *TtkStyling* read the *Style* class documentation.

24.2.3 Widget

`ttk.Widget` defines standard options and methods supported by Tk themed widgets and is not supposed to be directly instantiated.

Standard Options

All the `ttk` widgets accept the following options:

Option	Description
class	Specifies the window class. The class is used when querying the option database for the window's other options, to determine the default bindtags for the window, and to select the widget's default layout and style. This is a read-only option which may only be specified when the window is created.
cursor	Specifies the mouse cursor to be used for the widget. If set to the empty string (the default), the cursor is inherited from the parent widget.
takefocus	Determines whether the window accepts the focus during keyboard traversal. 0, 1 or an empty string is returned. If 0, the window should be skipped entirely during keyboard traversal. If 1, the window should receive the input focus as long as it is viewable. An empty string means that the traversal scripts make the decision about whether or not to focus on the window.
style	May be used to specify a custom widget style.

Scrollable Widget Options

The following options are supported by widgets that are controlled by a scrollbar.

option	description
xscrollcommand	- Used to communicate with horizontal scrollbars. When the view in the widget's window changes, the widget will generate a Tcl command based on the scrollcommand. Usually this option consists of the <code>Scrollbar.set()</code> method of some scrollbar. This will cause the scrollbar to be updated whenever the view in the window changes.
yscrollcommand	- Used to communicate with vertical scrollbars. For more information, see above.

Label Options

The following options are supported by labels, buttons and other button-like widgets.

option	description
text	Specifies a text string to be displayed inside the widget.
textvariable	Specifies a name whose value will be used in place of the text option resource.
underline	If set, specifies the index (0-based) of a character to underline in the text string. The underline character is used for mnemonic activation.
image	Specifies an image to display. This is a list of 1 or more elements. The first element is the default image name. The rest of the list is a sequence of statespec/value pairs as defined by <code>Style.map()</code> , specifying different images to use when the widget is in a particular state or a combination of states. All images in the list should have the same size.
compound	Specifies how to display the image relative to the text, in the case both text and image options are present. Valid values are: <ul style="list-style-type: none"> • text: display text only • image: display image only • top, bottom, left, right: display image above, below, left of, or right of the text, respectively. • none: the default. display the image if present, otherwise the text.
width	If greater than zero, specifies how much space, in character widths, to allocate for the text label; if less than zero, specifies a minimum width. If zero or unspecified, the natural width of the text label is used.

Compatibility Options

option	description
state	May be set to «normal» or «disabled» to control the «disabled» state bit. This is a write-only option: setting it changes the widget state, but the <code>Widget.state()</code> method does not affect this option.

Widget States

The widget state is a bitmap of independent state flags.

flag	description
active	The mouse cursor is over the widget and pressing a mouse button will cause some action to occur.
disabled	Widget is disabled under program control.
focus	Widget has keyboard focus.
pressed	Widget is being pressed.
selected	《 On 》, 《 true 》, or 《 current 》 for things like Checkbuttons and radiobuttons.
background	Windows and Mac have a notion of an 《 active 》 or foreground window. The <i>background</i> state is set for widgets in a background window, and cleared for those in the foreground window.
read-only	Widget should not allow user modification.
alternate	A widget-specific alternate display format.
invalid	The widget's value is invalid.

A state specification is a sequence of state names, optionally prefixed with an exclamation point indicating that the bit is off.

ttk.Widget

Besides the methods described below, the `ttk.Widget` class supports the `Tkinter.Widget.cget()` and `Tkinter.Widget.configure()` methods.

class `ttk.Widget`

identify (*x*, *y*)

Returns the name of the element at position *x* *y*, or the empty string if the point does not lie within any element.

x and *y* are pixel coordinates relative to the widget.

instate (*statespec*, *callback=None*, **args*, ***kw*)

Test the widget's state. If a callback is not specified, returns `True` if the widget state matches *statespec* and `False` otherwise. If callback is specified then it is called with *args* if widget state matches *statespec*.

state ([*statespec=None*])

Modify or read widget state. If *statespec* is specified, sets the widget state accordingly and returns a new *statespec* indicating which flags were changed. If *statespec* is not specified, returns the currently-enabled state flags.

statespec will usually be a list or a tuple.

24.2.4 Combobox

The `ttk.Combobox` widget combines a text field with a pop-down list of values. This widget is a subclass of `Entry`.

Besides the methods inherited from `Widget` (`Widget.cget()`, `Widget.configure()`, `Widget.identify()`, `Widget.instate()` and `Widget.state()`) and those inherited from `Entry` (`Entry.bbox()`, `Entry.delete()`, `Entry.icursor()`, `Entry.index()`, `Entry.insert()`, `Entry.selection()`, `Entry.xview()`), this class has some other methods, described at `ttk.Combobox`.

Options

This widget accepts the following options:

option	description
export-selection	Boolean value. If set, the widget selection is linked to the Window Manager selection (which can be returned by invoking <code>Misc.selection_get()</code> , for example).
justify	Specifies how the text is aligned within the widget. One of <code>«left»</code> , <code>«center»</code> , or <code>«right»</code> .
height	Specifies the height of the pop-down listbox, in rows.
post-command	A script (possibly registered with <code>Misc.register()</code>) that is called immediately before displaying the values. It may specify which values to display.
state	One of <code>«normal»</code> , <code>«readonly»</code> , or <code>«disabled»</code> . In the <code>«readonly»</code> state, the value may not be edited directly, and the user can only select one of the values from the dropdown list. In the <code>«normal»</code> state, the text field is directly editable. In the <code>«disabled»</code> state, no interaction is possible.
textvariable	Specifies a name whose value is linked to the widget value. Whenever the value associated with that name changes, the widget value is updated, and vice versa. See <code>Tkinter.StringVar</code> .
values	Specifies the list of values to display in the drop-down listbox.
width	Specifies an integer value indicating the desired width of the entry window, in average-size characters of the widget's font.

Virtual events

The combobox widget generates a «**ComboboxSelected**» virtual event when the user selects an element from the list of values.

ttk.Combobox

class `ttk.Combobox`

current (*[newindex=None]*)

If *newindex* is specified, sets the combobox value to the element position *newindex*. Otherwise, returns the index of the current value or -1 if the current value is not in the values list.

get ()

Returns the current value of the combobox.

set (*value*)

Sets the value of the combobox to *value*.

24.2.5 Notebook

The Ttk Notebook widget manages a collection of windows and displays a single one at a time. Each child window is associated with a tab, which the user may select to change the currently-displayed window.

Options

This widget accepts the following specific options:

option	description
<code>height</code>	If present and greater than zero, specifies the desired height of the pane area (not including internal padding or tabs). Otherwise, the maximum height of all panes is used.
<code>padding</code>	Specifies the amount of extra space to add around the outside of the notebook. The padding is a list of up to four length specifications: left top right bottom. If fewer than four elements are specified, bottom defaults to top, right defaults to left, and top defaults to left.
<code>width</code>	If present and greater than zero, specifies the desired width of the pane area (not including internal padding). Otherwise, the maximum width of all panes is used.

Tab Options

There are also specific options for tabs:

op- tion	description
state	Either «normal», «disabled» or «hidden». If «disabled», then the tab is not selectable. If «hidden», then the tab is not shown.
sticky	Specifies how the child window is positioned within the pane area. Value is a string containing zero or more of the characters «n», «s», «e» or «w». Each letter refers to a side (north, south, east or west) that the child window will stick to, as per the <code>grid()</code> geometry manager.
padding	Specifies the amount of extra space to add between the notebook and this pane. Syntax is the same as for the option padding used by this widget.
text	Specifies a text to be displayed in the tab.
im- age	Specifies an image to display in the tab. See the option image described in <i>Widget</i> .
com- pound	Specifies how to display the image relative to the text, in the case both text and image options are present. See <i>Label Options</i> for legal values.
un- der- line	Specifies the index (0-based) of a character to underline in the text string. The underlined character is used for mnemonic activation if <code>Notebook.enable_traversal()</code> is called.

Tab Identifiers

The `tab_id` present in several methods of `ttk.Notebook` may take any of the following forms:

- An integer between zero and the number of tabs.
- The name of a child window.
- A positional specification of the form «@x,y», which identifies the tab.
- The literal string «current», which identifies the currently-selected tab.
- The literal string «end», which returns the number of tabs (only valid for `Notebook.index()`).

Virtual Events

This widget generates a «**NotebookTabChanged**» virtual event after a new tab is selected.

ttk.Notebook

class `ttk.Notebook`

add (*child*, ***kw*)

Adds a new tab to the notebook.

If window is currently managed by the notebook but hidden, it is restored to its previous position.

See *Tab Options* for the list of available options.

forget (*tab_id*)

Removes the tab specified by *tab_id*, unmaps and unmanages the associated window.

hide (*tab_id*)

Hides the tab specified by *tab_id*.

The tab will not be displayed, but the associated window remains managed by the notebook and its configuration remembered. Hidden tabs may be restored with the `add()` command.

identify (*x*, *y*)

Returns the name of the tab element at position *x*, *y*, or the empty string if none.

index (*tab_id*)

Returns the numeric index of the tab specified by *tab_id*, or the total number of tabs if *tab_id* is the string `«end»`.

insert (*pos*, *child*, ****kw**)

Inserts a pane at the specified position.

pos is either the string `«end»`, an integer index, or the name of a managed child. If *child* is already managed by the notebook, moves it to the specified position.

See *Tab Options* for the list of available options.

select ([*tab_id*])

Selects the specified *tab_id*.

The associated child window will be displayed, and the previously-selected window (if different) is unmapped. If *tab_id* is omitted, returns the widget name of the currently selected pane.

tab (*tab_id*, *option*=None, ****kw**)

Query or modify the options of the specific *tab_id*.

If *kw* is not given, returns a dictionary of the tab option values. If *option* is specified, returns the value of that *option*. Otherwise, sets the options to the corresponding values.

tabs ()

Returns a list of windows managed by the notebook.

enable_traversal ()

Enable keyboard traversal for a toplevel window containing this notebook.

This will extend the bindings for the toplevel window containing the notebook as follows:

- Control-Tab: selects the tab following the currently selected one.
- Shift-Control-Tab: selects the tab preceding the currently selected one.
- Alt-K: where *K* is the mnemonic (underlined) character of any tab, will select that tab.

Multiple notebooks in a single toplevel may be enabled for traversal, including nested notebooks. However, notebook traversal only works properly if all panes have the notebook they are in as master.

24.2.6 Progressbar

The `ttk.Progressbar` widget shows the status of a long-running operation. It can operate in two modes: determinate mode shows the amount completed relative to the total amount of work to be done, and indeterminate mode provides an animated display to let the user know that something is happening.

Options

This widget accepts the following specific options:

option	description
orient	One of «horizontal» or «vertical». Specifies the orientation of the progress bar.
length	Specifies the length of the long axis of the progress bar (width if horizontal, height if vertical).
mode	One of «determinate» or «indeterminate».
maximum	A number specifying the maximum value. Defaults to 100.
value	The current value of the progress bar. In «determinate» mode, this represents the amount of work completed. In «indeterminate» mode, it is interpreted as modulo <i>maximum</i> ; that is, the progress bar completes one «cycle» when its value increases by <i>maximum</i> .
variable	A name which is linked to the option value. If specified, the value of the progress bar is automatically set to the value of this name whenever the latter is modified.
phase	Read-only option. The widget periodically increments the value of this option whenever its value is greater than 0 and, in determinate mode, less than maximum. This option may be used by the current theme to provide additional animation effects.

ttk.Progressbar

class `ttk.Progressbar`

start (`[interval]`)

Begin autoincrement mode: schedules a recurring timer event that calls `Progressbar.step()` every *interval* milliseconds. If omitted, *interval* defaults to 50 milliseconds.

step (`[amount]`)

Increments the progress bar's value by *amount*.

amount defaults to 1.0 if omitted.

stop ()

Stop autoincrement mode: cancels any recurring timer event initiated by `Progressbar.start()` for this progress bar.

24.2.7 Separator

The `ttk.Separator` widget displays a horizontal or vertical separator bar.

It has no other methods besides the ones inherited from `ttk.Widget`.

Options

This widget accepts the following specific option:

option	description
orient	One of <code>horizontal</code> or <code>vertical</code> . Specifies the orientation of the separator.

24.2.8 Sizegrip

The `ttk.Sizegrip` widget (also known as a grow box) allows the user to resize the containing toplevel window by pressing and dragging the grip.

This widget has neither specific options nor specific methods, besides the ones inherited from `ttk.Widget`.

Platform-specific notes

- On Mac OS X, toplevel windows automatically include a built-in size grip by default. Adding a `Sizegrip` is harmless, since the built-in grip will just mask the widget.

Bugs

- If the containing toplevel's position was specified relative to the right or bottom of the screen (e.g. `right`), the `Sizegrip` widget will not resize the window.
- This widget supports only `southeast` resizing.

24.2.9 Treeview

The `ttk.Treeview` widget displays a hierarchical collection of items. Each item has a textual label, an optional image, and an optional list of data values. The data values are displayed in successive columns after the tree label.

The order in which data values are displayed may be controlled by setting the widget option `displaycolumns`. The tree widget can also display column headings. Columns may be accessed by number or symbolic names listed in the widget option `columns`. See [Column Identifiers](#).

Each item is identified by a unique name. The widget will generate item IDs if they are not supplied by the caller. There is a distinguished root item, named `{ }`. The root item itself is not displayed; its children appear at the top level of the hierarchy.

Each item also has a list of tags, which can be used to associate event bindings with individual items and control the appearance of the item.

The `Treeview` widget supports horizontal and vertical scrolling, according to the options described in [Scrollable Widget Options](#) and the methods `Treeview.xview()` and `Treeview.yview()`.

Options

This widget accepts the following specific options:

option	description
columns	A list of column identifiers, specifying the number of columns and their names.
displaycolumns	A list of column identifiers (either symbolic or integer indices) specifying which data columns are displayed and the order in which they appear, or the string <code><#all></code> .
height	Specifies the number of rows which should be visible. Note: the requested width is determined from the sum of the column widths.
padding	Specifies the internal padding for the widget. The padding is a list of up to four length specifications.
selectmode	Controls how the built-in class bindings manage the selection. One of <code><extended></code> , <code><browse></code> or <code><none></code> . If set to <code><extended></code> (the default), multiple items may be selected. If <code><browse></code> , only a single item will be selected at a time. If <code><none></code> , the selection will not be changed. Note that the application code and tag bindings can set the selection however they wish, regardless of the value of this option.
show	A list containing zero or more of the following values, specifying which elements of the tree to display. <ul style="list-style-type: none"> <code>tree</code>: display tree labels in column #0. <code>headings</code>: display the heading row. The default is <code><tree headings></code> , i.e., show all elements. Note: Column #0 always refers to the tree column, even if <code>show=>tree</code> is not specified.

Item Options

The following item options may be specified for items in the insert and item widget commands.

option	description
text	The textual label to display for the item.
image	A Tk Image, displayed to the left of the label.
values	The list of values associated with the item. Each item should have the same number of values as the widget option columns. If there are fewer values than columns, the remaining values are assumed empty. If there are more values than columns, the extra values are ignored.
open	True/False value indicating whether the item's children should be displayed or hidden.
tags	A list of tags associated with this item.

Tag Options

The following options may be specified on tags:

option	description
foreground	Specifies the text foreground color.
background	Specifies the cell or item background color.
font	Specifies the font to use when drawing text.
image	Specifies the item image, in case the item's image option is empty.

Column Identifiers

Column identifiers take any of the following forms:

- A symbolic name from the list of columns option.
- An integer *n*, specifying the *n*th data column.
- A string of the form *#n*, where *n* is an integer, specifying the *n*th display column.

Notes:

- Item's option values may be displayed in a different order than the order in which they are stored.
- Column *#0* always refers to the tree column, even if `show=» tree »` is not specified.

A data column number is an index into an item's option values list; a display column number is the column number in the tree where the values are displayed. Tree labels are displayed in column *#0*. If option `displaycolumns` is not set, then data column *n* is displayed in column *#n+1*. Again, **column *#0* always refers to the tree column.**

Virtual Events

The Treeview widget generates the following virtual events.

event	description
«TreeviewSelect»	Generated whenever the selection changes.
«TreeviewOpen»	Generated just before settings the focus item to <code>open=True</code> .
«TreeviewClose»	Generated just after setting the focus item to <code>open=False</code> .

The `Treeview.focus()` and `Treeview.selection()` methods can be used to determine the affected item or items.

ttk.Treeview

```
class ttk.Treeview
```

bbox (*item*, *column=None*)

Returns the bounding box (relative to the treeview widget's window) of the specified *item* in the form (x, y, width, height).

If *column* is specified, returns the bounding box of that cell. If the *item* is not visible (i.e., if it is a descendant of a closed item or is scrolled offscreen), returns an empty string.

get_children ([*item*])

Returns the list of children belonging to *item*.

If *item* is not specified, returns root children.

set_children (*item*, **newchildren*)

Replaces *item*'s child with *newchildren*.

Children present in *item* that are not present in *newchildren* are detached from the tree. No items in *newchildren* may be an ancestor of *item*. Note that not specifying *newchildren* results in detaching *item*'s children.

column (*column*, *option*=None, ***kw*)

Query or modify the options for the specified *column*.

If *kw* is not given, returns a dict of the column option values. If *option* is specified then the value for that *option* is returned. Otherwise, sets the options to the corresponding values.

The valid options/values are:

- **id** Returns the column name. This is a read-only option.
- **anchor: One of the standard Tk anchor values.** Specifies how the text in this column should be aligned with respect to the cell.
- **minwidth: width** The minimum width of the column in pixels. The treeview widget will not make the column any smaller than specified by this option when the widget is resized or the user drags a column.
- **stretch: True/False** Specifies whether the column's width should be adjusted when the widget is resized.
- **width: width** The width of the column in pixels.

To configure the tree column, call this with *column* = <#0>

delete (**items*)

Delete all specified *items* and all their descendants.

The root item may not be deleted.

detach (**items*)

Unlinks all of the specified *items* from the tree.

The items and all of their descendants are still present, and may be reinserted at another point in the tree, but will not be displayed.

The root item may not be detached.

exists (*item*)

Returns `True` if the specified *item* is present in the tree.

focus ([*item*=None])

If *item* is specified, sets the focus item to *item*. Otherwise, returns the current focus item, or <> if there is none.

heading (*column*, *option*=None, ***kw*)

Query or modify the heading options for the specified *column*.

If *kw* is not given, returns a dict of the heading option values. If *option* is specified then the value for that *option* is returned. Otherwise, sets the options to the corresponding values.

The valid options/values are:

- **text: text** The text to display in the column heading.
- **image: imageName** Specifies an image to display to the right of the column heading.

- **anchor:** **anchor** Specifies how the heading text should be aligned. One of the standard Tk anchor values.
- **command:** **callback** A callback to be invoked when the heading label is pressed.

To configure the tree column heading, call this with `column = «#0»`.

identify (*component*, *x*, *y*)

Returns a description of the specified *component* under the point given by *x* and *y*, or the empty string if no such *component* is present at that position.

identify_row (*y*)

Returns the item ID of the item at position *y*.

identify_column (*x*)

Returns the data column identifier of the cell at position *x*.

The tree column has ID #0.

identify_region (*x*, *y*)

Returns one of:

region	meaning
heading	Tree heading area.
separator	Space between two columns headings.
tree	The tree area.
cell	A data cell.

Availability: Tk 8.6.

identify_element (*x*, *y*)

Returns the element at position *x*, *y*.

Availability: Tk 8.6.

index (*item*)

Returns the integer index of *item* within its parent's list of children.

insert (*parent*, *index*, *iid=None*, ***kw*)

Creates a new item and returns the item identifier of the newly created item.

parent is the item ID of the parent item, or the empty string to create a new top-level item. *index* is an integer, or the value «end», specifying where in the list of parent's children to insert the new item. If *index* is less than or equal to zero, the new node is inserted at the beginning; if *index* is greater than or equal to the current number of children, it is inserted at the end. If *iid* is specified, it is used as the item identifier; *iid* must not already exist in the tree. Otherwise, a new unique identifier is generated.

See [Item Options](#) for the list of available points.

item (*item*[, *option*[, ***kw*]])

Query or modify the options for the specified *item*.

If no options are given, a dict with options/values for the item is returned. If *option* is specified then the value for that option is returned. Otherwise, sets the options to the corresponding values as given by *kw*.

move (*item*, *parent*, *index*)

Moves *item* to position *index* in *parent*'s list of children.

It is illegal to move an item under one of its descendants. If *index* is less than or equal to zero, *item* is moved to the beginning; if greater than or equal to the number of children, it is moved to the end. If *item* was detached it is reattached.

next (*item*)

Returns the identifier of *item*'s next sibling, or `<` if *item* is the last child of its parent.

parent (*item*)

Returns the ID of the parent of *item*, or `<` if *item* is at the top level of the hierarchy.

prev (*item*)

Returns the identifier of *item*'s previous sibling, or `<` if *item* is the first child of its parent.

reattach (*item*, *parent*, *index*)

An alias for `Treeview.move()`.

see (*item*)

Ensure that *item* is visible.

Sets all of *item*'s ancestors open option to `True`, and scrolls the widget if necessary so that *item* is within the visible portion of the tree.

selection ([*selop*=None[, *items*=None]])

If *selop* is not specified, returns selected items. Otherwise, it will act according to the following selection methods.

selection_set (*items*)

items becomes the new selection.

selection_add (*items*)

Add *items* to the selection.

selection_remove (*items*)

Remove *items* from the selection.

selection_toggle (*items*)

Toggle the selection state of each item in *items*.

set (*item*, *column*=None, *value*=None)

With one argument, returns a dictionary of column/value pairs for the specified *item*. With two arguments, returns the current value of the specified *column*. With three arguments, sets the value of given *column* in given *item* to the specified *value*.

tag_bind (*tagname*, *sequence*=None, *callback*=None)

Bind a callback for the given event *sequence* to the tag *tagname*. When an event is delivered to an item, the callbacks for each of the item's tags option are called.

tag_configure (*tagname*, *option*=None, ***kw*)

Query or modify the options for the specified *tagname*.

If *kw* is not given, returns a dict of the option settings for *tagname*. If *option* is specified, returns the value for that *option* for the specified *tagname*. Otherwise, sets the options to the corresponding values for the given *tagname*.

tag_has (*tagname*[, *item*])

If *item* is specified, returns 1 or 0 depending on whether the specified *item* has the given *tagname*. Otherwise, returns a list of all items that have the specified tag.

Availability: Tk 8.6

xview (**args*)

Query or modify horizontal position of the treeview.

yview (**args*)

Query or modify vertical position of the treeview.

24.2.10 Ttk Styling

Each widget in `ttk` is assigned a style, which specifies the set of elements making up the widget and how they are arranged, along with dynamic and default settings for element options. By default the style name is the same as the widget's class name, but it may be overridden by the widget's style option. If the class name of a widget is unknown, use the method `Misc.winfo_class()` (`somewidget.winfo_class()`).

더 보기:

Tcl'2004 conference presentation This document explains how the theme engine works

class `ttk.Style`

This class is used to manipulate the style database.

configure (*style*, *query_opt=None*, ***kw*)

Query or set the default value of the specified option(s) in *style*.

Each key in *kw* is an option and each value is a string identifying the value for that option.

For example, to change every default button to be a flat button with some padding and a different background color do:

```
import ttk
import Tkinter

root = Tkinter.Tk()

ttk.Style().configure("TButton", padding=6, relief="flat",
                     background="#ccc")

btn = ttk.Button(text="Sample")
btn.pack()

root.mainloop()
```

map (*style*, *query_opt=None*, ***kw*)

Query or sets dynamic values of the specified option(s) in *style*.

Each key in *kw* is an option and each value should be a list or a tuple (usually) containing statespecs grouped in tuples, lists, or something else of your preference. A statespec is a compound of one or more states and then a value.

An example:

```
import Tkinter
import ttk

root = Tkinter.Tk()

style = ttk.Style()
style.map("C.TButton",
        foreground=[('pressed', 'red'), ('active', 'blue')],
        background=[('pressed', '!disabled', 'black'), ('active', 'white')]
)

colored_btn = ttk.Button(text="Test", style="C.TButton").pack()

root.mainloop()
```

Note that the order of the (states, value) sequences for an option matters. In the previous example, if you change the order to `[('active', 'blue'), ('pressed', 'red')]` in the foreground option, for example, you would get a blue foreground when the widget is in the active or pressed states.

lookup (*style, option, state=None, default=None*)

Returns the value specified for *option* in *style*.

If *state* is specified, it is expected to be a sequence of one or more states. If the *default* argument is set, it is used as a fallback value in case no specification for option is found.

To check what font a Button uses by default, do:

```
import ttk

print ttk.Style().lookup("TButton", "font")
```

layout (*style, layoutspec=None*)

Define the widget layout for given *style*. If *layoutspec* is omitted, return the layout specification for given style.

layoutspec, if specified, is expected to be a list or some other sequence type (excluding strings), where each item should be a tuple and the first item is the layout name and the second item should have the format described in [Layouts](#).

To understand the format, see the following example (it is not intended to do anything useful):

```
import ttk
import Tkinter

root = Tkinter.Tk()

style = ttk.Style()
style.layout("TMenubutton", [
    ("Menubutton.background", None),
    ("Menubutton.button", {"children":
        [ ("Menubutton.focus", {"children":
            [ ("Menubutton.padding", {"children":
                [ ("Menubutton.label", {"side": "left", "expand": 1})]
            })]
        })]
    })],
])

mbtn = ttk.Menubutton(text='Text')
mbtn.pack()
root.mainloop()
```

element_create (*elementname, etype, *args, **kw*)

Create a new element in the current theme, of the given *etype* which is expected to be either `«image»`, `«from»` or `«vsapi»`. The latter is only available in Tk 8.6a for Windows XP and Vista and is not described here.

If `«image»` is used, *args* should contain the default image name followed by statespec/value pairs (this is the `imagespec`), and *kw* may have the following options:

- **border=padding** padding is a list of up to four integers, specifying the left, top, right, and bottom borders, respectively.
- **height=height** Specifies a minimum height for the element. If less than zero, the base image's height is used as a default.
- **padding=padding** Specifies the element's interior padding. Defaults to border's value if not specified.

- **sticky=spec** Specifies how the image is placed within the final parcel. *spec* contains zero or more characters `<n>`, `<s>`, `<w>`, or `<e>`.
- **width=width** Specifies a minimum width for the element. If less than zero, the base image's width is used as a default.

If `<from>` is used as the value of *etype*, `element_create()` will clone an existing element. *args* is expected to contain a themename, from which the element will be cloned, and optionally an element to clone from. If this element to clone from is not specified, an empty element will be used. *kw* is discarded.

element_names()

Returns the list of elements defined in the current theme.

element_options(*elementname*)

Returns the list of *elementname*'s options.

theme_create(*themename*, *parent=None*, *settings=None*)

Create a new theme.

It is an error if *themename* already exists. If *parent* is specified, the new theme will inherit styles, elements and layouts from the parent theme. If *settings* are present they are expected to have the same syntax used for `theme_settings()`.

theme_settings(*themename*, *settings*)

Temporarily sets the current theme to *themename*, apply specified *settings* and then restore the previous theme.

Each key in *settings* is a style and each value may contain the keys `<configure>`, `<map>`, `<layout>` and `<element create>` and they are expected to have the same format as specified by the methods `Style.configure()`, `Style.map()`, `Style.layout()` and `Style.element_create()` respectively.

As an example, let's change the Combobox for the default theme a bit:

```
import ttk
import Tkinter

root = Tkinter.Tk()

style = ttk.Style()
style.theme_settings("default", {
    "TCombobox": {
        "configure": {"padding": 5},
        "map": {
            "background": [("active", "green2"),
                           ("!disabled", "green4")],
            "fieldbackground": [("!disabled", "green3")],
            "foreground": [("focus", "OliveDrab1"),
                           ("!disabled", "OliveDrab2")]
        }
    }
})

combo = ttk.Combobox().pack()

root.mainloop()
```

theme_names()

Returns a list of all known themes.

theme_use([*themename*])

If *themename* is not given, returns the theme in use. Otherwise, sets the current theme to *themename*, refreshes

all widgets and emits a «ThemeChanged» event.

Layouts

A layout can be just `None`, if it takes no options, or a dict of options specifying how to arrange the element. The layout mechanism uses a simplified version of the pack geometry manager: given an initial cavity, each element is allocated a parcel. Valid options/values are:

- **side: whichside** Specifies which side of the cavity to place the element; one of top, right, bottom or left. If omitted, the element occupies the entire cavity.
- **sticky: nswe** Specifies where the element is placed inside its allocated parcel.
- **unit: 0 or 1** If set to 1, causes the element and all of its descendants to be treated as a single element for the purposes of `Widget.identify()` et al. It's used for things like scrollbar thumbs with grips.
- **children: [sublayout...]** Specifies a list of elements to place inside the element. Each element is a tuple (or other sequence type) where the first item is the layout name, and the other is a *Layout*.

24.3 Tix — Extension widgets for Tk

The *Tix* (Tk Interface Extension) module provides an additional rich set of widgets. Although the standard Tk library has many useful widgets, they are far from complete. The *Tix* library provides most of the commonly needed widgets that are missing from standard Tk: *HList*, *ComboBox*, *Control* (a.k.a. *SpinBox*) and an assortment of scrollable widgets. *Tix* also includes many more widgets that are generally useful in a wide range of applications: *NoteBook*, *FileEntry*, *PanedWindow*, etc; there are more than 40 of them.

With all these new widgets, you can introduce new interaction techniques into applications, creating more useful and more intuitive user interfaces. You can design your application by choosing the most appropriate widgets to match the special needs of your application and users.

참고: *Tix* has been renamed to `tkinter.tix` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

더 보기:

Tix Homepage The home page for *Tix*. This includes links to additional documentation and downloads.

Tix Man Pages On-line version of the man pages and reference material.

Tix Programming Guide On-line version of the programmer's reference material.

Tix Development Applications Tix applications for development of Tix and Tkinter programs. Tide applications work under Tk or Tkinter, and include **TixInspect**, an inspector to remotely modify and debug Tix/Tk/Tkinter applications.

24.3.1 Using Tix

class `Tix.Tix`(`screenName`[, `baseName`[, `className`]])

Toplevel widget of Tix which represents mostly the main window of an application. It has an associated Tcl interpreter.

Classes in the `Tix` module subclasses the classes in the `Tkinter` module. The former imports the latter, so to use `Tix` with Tkinter, all you need to do is to import one module. In general, you can just import `Tix`, and replace the toplevel call to `Tkinter.Tk` with `Tix.Tk`:

```
import Tix
from Tkconstants import *
root = Tix.Tk()
```

To use `Tix`, you must have the `Tix` widgets installed, usually alongside your installation of the Tk widgets. To test your installation, try the following:

```
import Tix
root = Tix.Tk()
root.tk.eval('package require Tix')
```

If this fails, you have a Tk installation problem which must be resolved before proceeding. Use the environment variable `TIX_LIBRARY` to point to the installed `Tix` library directory, and make sure you have the dynamic object library (`tix8183.dll` or `libtix8183.so`) in the same directory that contains your Tk dynamic object library (`tk8183.dll` or `libtk8183.so`). The directory with the dynamic object library should also have a file called `pkgIndex.tcl` (case sensitive), which contains the line:

```
package ifneeded Tix 8.1 [list load "[file join $dir tix8183.dll]" Tix]
```

24.3.2 Tix Widgets

`Tix` introduces over 40 widget classes to the `Tkinter` repertoire. There is a demo of all the `Tix` widgets in the `Demo/tix` directory of the standard distribution.

Basic Widgets

class `Tix.Balloon`

A `Balloon` that pops up over a widget to provide help. When the user moves the cursor inside a widget to which a `Balloon` widget has been bound, a small pop-up window with a descriptive message will be shown on the screen.

class `Tix.ButtonBox`

The `ButtonBox` widget creates a box of buttons, such as is commonly used for `Ok Cancel`.

class `Tix.ComboBox`

The `ComboBox` widget is similar to the combo box control in MS Windows. The user can select a choice by either typing in the entry subwidget or selecting from the listbox subwidget.

class `Tix.Control`

The `Control` widget is also known as the `SpinBox` widget. The user can adjust the value by pressing the two arrow buttons or by entering the value directly into the entry. The new value will be checked against the user-defined upper and lower limits.

class `Tix.LabelEntry`

The `LabelEntry` widget packages an entry widget and a label into one mega widget. It can be used to simplify the creation of 《entry-form》 type of interface.

class `Tix.LabelFrame`

The `LabelFrame` widget packages a frame widget and a label into one mega widget. To create widgets inside a `LabelFrame` widget, one creates the new widgets relative to the `frame` subwidget and manage them inside the `frame` subwidget.

class `Tix.Meter`

The `Meter` widget can be used to show the progress of a background job which may take a long time to execute.

class `Tix.OptionMenu`

The `OptionMenu` creates a menu button of options.

class `Tix.PopupMenu`

The `PopupMenu` widget can be used as a replacement of the `tk_popup` command. The advantage of the `Tix.PopupMenu` widget is it requires less application code to manipulate.

class `Tix.Select`

The `Select` widget is a container of button subwidgets. It can be used to provide radio-box or check-box style of selection options for the user.

class `Tix.StdButtonBox`

The `StdButtonBox` widget is a group of standard buttons for Motif-like dialog boxes.

File Selectors

class `Tix.DirList`

The `DirList` widget displays a list view of a directory, its previous directories and its sub-directories. The user can choose one of the directories displayed in the list or change to another directory.

class `Tix.DirTree`

The `DirTree` widget displays a tree view of a directory, its previous directories and its sub-directories. The user can choose one of the directories displayed in the list or change to another directory.

class `Tix.DirSelectDialog`

The `DirSelectDialog` widget presents the directories in the file system in a dialog window. The user can use this dialog window to navigate through the file system to select the desired directory.

class `Tix.DirSelectBox`

The `DirSelectBox` is similar to the standard Motif(TM) directory-selection box. It is generally used for the user to choose a directory. `DirSelectBox` stores the directories mostly recently selected into a `ComboBox` widget so that they can be quickly selected again.

class `Tix.ExFileSelectBox`

The `ExFileSelectBox` widget is usually embedded in a `tixExFileSelectDialog` widget. It provides a convenient method for the user to select files. The style of the `ExFileSelectBox` widget is very similar to the standard file dialog on MS Windows 3.1.

class `Tix.FileSelectBox`

The `FileSelectBox` is similar to the standard Motif(TM) file-selection box. It is generally used for the user to choose a file. `FileSelectBox` stores the files mostly recently selected into a `ComboBox` widget so that they can be quickly selected again.

class `Tix.FileEntry`

The `FileEntry` widget can be used to input a filename. The user can type in the filename manually. Alternatively, the user can press the button widget that sits next to the entry, which will bring up a file selection dialog.

Hierarchical ListBox

class `Tix.HList`

The `HList` widget can be used to display any data that have a hierarchical structure, for example, file system directory trees. The list entries are indented and connected by branch lines according to their places in the hierarchy.

class `Tix.CheckList`

The `CheckList` widget displays a list of items to be selected by the user. `CheckList` acts similarly to the Tk `checkbutton` or `radiobutton` widgets, except it is capable of handling many more items than `checkbuttons` or `radiobuttons`.

class `Tix.Tree`

The `Tree` widget can be used to display hierarchical data in a tree form. The user can adjust the view of the tree by opening or closing parts of the tree.

Tabular ListBox

class `Tix.TList`

The `TList` widget can be used to display data in a tabular format. The list entries of a `TList` widget are similar to the entries in the Tk listbox widget. The main differences are (1) the `TList` widget can display the list entries in a two dimensional format and (2) you can use graphical images as well as multiple colors and fonts for the list entries.

Manager Widgets

class `Tix.PanedWindow`

The `PanedWindow` widget allows the user to interactively manipulate the sizes of several panes. The panes can be arranged either vertically or horizontally. The user changes the sizes of the panes by dragging the resize handle between two panes.

class `Tix.ListNoteBook`

The `ListNoteBook` widget is very similar to the `TixNoteBook` widget: it can be used to display many windows in a limited space using a notebook metaphor. The notebook is divided into a stack of pages (windows). At one time only one of these pages can be shown. The user can navigate through these pages by choosing the name of the desired page in the `hlist` subwidget.

class `Tix.NoteBook`

The `NoteBook` widget can be used to display many windows in a limited space using a notebook metaphor. The notebook is divided into a stack of pages. At one time only one of these pages can be shown. The user can navigate through these pages by choosing the visual « tabs » at the top of the `NoteBook` widget.

Image Types

The `Tix` module adds:

- `pixmap` capabilities to all `Tix` and `Tkinter` widgets to create color images from XPM files.
- `Compound` image types can be used to create images that consists of multiple horizontal lines; each line is composed of a series of items (texts, bitmaps, images or spaces) arranged from left to right. For example, a compound image can be used to display a bitmap and a text string simultaneously in a Tk `Button` widget.

Miscellaneous Widgets

`class Tix.InputOnly`

The `InputOnly` widgets are to accept inputs from the user, which can be done with the `bind` command (Unix only).

Form Geometry Manager

In addition, `Tix` augments `Tkinter` by providing:

`class Tix.Form`

The `Form` geometry manager based on attachment rules for all Tk widgets.

24.3.3 Tix Commands

`class Tix.tixCommand`

The `tix` commands provide access to miscellaneous elements of `Tix`'s internal state and the `Tix` application context. Most of the information manipulated by these methods pertains to the application as a whole, or to a screen or display, rather than to a particular window.

To view the current settings, the common usage is:

```
import Tix
root = Tix.Tk()
print root.tix_configure()
```

`tixCommand.tix_configure` (*cnf=None **kw*)

Query or modify the configuration options of the `Tix` application context. If no option is specified, returns a dictionary all of the available options. If option is specified with no value, then the method returns a list describing the one named option (this list will be identical to the corresponding sublist of the value returned if no option is specified). If one or more option-value pairs are specified, then the method modifies the given option(s) to have the given value(s); in this case the method returns an empty string. Option may be any of the configuration options.

`tixCommand.tix_cget` (*option*)

Returns the current value of the configuration option given by *option*. Option may be any of the configuration options.

`tixCommand.tix_getbitmap` (*name*)

Locates a bitmap file of the name *name*.xpm or *name* in one of the bitmap directories (see the `tix_addbitmapdir()` method). By using `tix_getbitmap()`, you can avoid hard coding the pathnames of the bitmap files in your application. When successful, it returns the complete pathname of the bitmap file, prefixed with the character @. The returned value can be used to configure the `bitmap` option of the Tk and Tix widgets.

`tixCommand.tix_addbitmapdir` (*directory*)

`Tix` maintains a list of directories under which the `tix_getimage()` and `tix_getbitmap()` methods will search for image files. The standard bitmap directory is `$TIX_LIBRARY/bitmaps`. The `tix_addbitmapdir()` method adds *directory* into this list. By using this method, the image files of an applications can also be located using the `tix_getimage()` or `tix_getbitmap()` method.

`tixCommand.tix_filedialog` (*[dlgclass]*)

Returns the file selection dialog that may be shared among different calls from this application. This method will create a file selection dialog widget when it is called the first time. This dialog will be returned by all subsequent calls to `tix_filedialog()`. An optional *dlgclass* parameter can be passed as a string to specify what type of file selection dialog widget is desired. Possible options are `tix`, `FileSelectDialog` or `tixExFileSelectDialog`.

`tixCommand.tix_getimage (self, name)`

Locates an image file of the name `name.xpm`, `name.xbm` or `name.ppm` in one of the bitmap directories (see the `tix_addbitmapdir()` method above). If more than one file with the same name (but different extensions) exist, then the image type is chosen according to the depth of the X display: xbm images are chosen on monochrome displays and color images are chosen on color displays. By using `tix_getimage()`, you can avoid hard coding the pathnames of the image files in your application. When successful, this method returns the name of the newly created image, which can be used to configure the `image` option of the Tk and Tix widgets.

`tixCommand.tix_option_get (name)`

Gets the options maintained by the Tix scheme mechanism.

`tixCommand.tix_resetoptions (newScheme, newFontSet[, newScmPrio])`

Resets the scheme and fontset of the Tix application to `newScheme` and `newFontSet`, respectively. This affects only those widgets created after this call. Therefore, it is best to call the `resetoptions` method before the creation of any widgets in a Tix application.

The optional parameter `newScmPrio` can be given to reset the priority level of the Tk options set by the Tix schemes.

Because of the way Tk handles the X option database, after Tix has been imported and initied, it is not possible to reset the color schemes and font sets using the `tix_config()` method. Instead, the `tix_resetoptions()` method must be used.

24.4 ScrolledText — Scrolled Text Widget

The `ScrolledText` module provides a class of the same name which implements a basic text widget which has a vertical scroll bar configured to do the «right thing.» Using the `ScrolledText` class is a lot easier than setting up a text widget and scroll bar directly. The constructor is the same as that of the `Tkinter.Text` class.

참고: `ScrolledText` has been renamed to `tkinter.scrolledtext` in Python 3. The *2to3* tool will automatically adapt imports when converting your sources to Python 3.

The text widget and scrollbar are packed together in a `Frame`, and the methods of the `Grid` and `Pack` geometry managers are acquired from the `Frame` object. This allows the `ScrolledText` widget to be used directly to achieve most normal geometry management behavior.

Should more specific control be necessary, the following attributes are available:

`ScrolledText.frame`

The frame which surrounds the text and scroll bar widgets.

`ScrolledText.vbar`

The scroll bar widget.

24.5 turtle — Turtle graphics for Tk

24.5.1 Introduction

Turtle graphics is a popular way for introducing programming to kids. It was part of the original Logo programming language developed by Wally Feurzig and Seymour Papert in 1966.

Imagine a robotic turtle starting at (0, 0) in the x-y plane. After an `import turtle`, give it the command `turtle.forward(15)`, and it moves (on-screen!) 15 pixels in the direction it is facing, drawing a line as it moves. Give it the command `turtle.right(25)`, and it rotates in-place 25 degrees clockwise.

By combining together these and similar commands, intricate shapes and pictures can easily be drawn.

The `turtle` module is an extended reimplementaion of the same-named module from the Python standard distribution up to version Python 2.5.

It tries to keep the merits of the old turtle module and to be (nearly) 100% compatible with it. This means in the first place to enable the learning programmer to use all the commands, classes and methods interactively when using the module from within IDLE run with the `-n` switch.

The turtle module provides turtle graphics primitives, in both object-oriented and procedure-oriented ways. Because it uses `Tkinter` for the underlying graphics, it needs a version of Python installed with Tk support.

The object-oriented interface uses essentially two+two classes:

1. The `TurtleScreen` class defines graphics windows as a playground for the drawing turtles. Its constructor needs a `Tkinter.Canvas` or a `ScrolledCanvas` as argument. It should be used when `turtle` is used as part of some application.

The function `Screen()` returns a singleton object of a `TurtleScreen` subclass. This function should be used when `turtle` is used as a standalone tool for doing graphics. As a singleton object, inheriting from its class is not possible.

All methods of `TurtleScreen/Screen` also exist as functions, i.e. as part of the procedure-oriented interface.

2. `RawTurtle` (alias: `RawPen`) defines Turtle objects which draw on a `TurtleScreen`. Its constructor needs a `Canvas`, `ScrolledCanvas` or `TurtleScreen` as argument, so the `RawTurtle` objects know where to draw.

Derived from `RawTurtle` is the subclass `Turtle` (alias: `Pen`), which draws on 《the》 `Screen` - instance which is automatically created, if not already present.

All methods of `RawTurtle/Turtle` also exist as functions, i.e. part of the procedure-oriented interface.

The procedural interface provides functions which are derived from the methods of the classes `Screen` and `Turtle`. They have the same names as the corresponding methods. A screen object is automatically created whenever a function derived from a `Screen` method is called. An (unnamed) turtle object is automatically created whenever any of the functions derived from a `Turtle` method is called.

To use multiple turtles an a screen one has to use the object-oriented interface.

참고: In the following documentation the argument list for functions is given. Methods, of course, have the additional first argument `self` which is omitted here.

24.5.2 Overview over available Turtle and Screen methods

Turtle methods

Turtle motion

Move and draw

```
forward() | fd()
backward() | bk() | back()
right() | rt()
left() | lt()
goto() | setpos() | setposition()
setx()
sety()
```

```
setheading() | seth()  
home()  
circle()  
dot()  
stamp()  
clearstamp()  
clearstamps()  
undo()  
speed()
```

Tell Turtle's state

```
position() | pos()  
towards()  
xcor()  
ycor()  
heading()  
distance()
```

Setting and measurement

```
degrees()  
radians()
```

Pen control

Drawing state

```
pendown() | pd() | down()  
penup() | pu() | up()  
pensize() | width()  
pen()  
isdown()
```

Color control

```
color()  
pencolor()  
fillcolor()
```

Filling

```
fill()  
begin_fill()  
end_fill()
```

More drawing control

```
reset()  
clear()  
write()
```

Turtle state

Visibility

```
showturtle() | st()  
hideturtle() | ht()
```

`isvisible()`

Appearance

`shape()`
`resizemode()`
`shapeseize()` | `turtlesize()`
`settiltangle()`
`tiltangle()`
`tilt()`

Using events

`onclick()`
`onrelease()`
`ondrag()`
`mainloop()` | `done()`

Special Turtle methods

`begin_poly()`
`end_poly()`
`get_poly()`
`clone()`
`getturtle()` | `getpen()`
`getscreen()`
`setundobuffer()`
`undobufferentries()`
`tracer()`
`window_width()`
`window_height()`

Methods of TurtleScreen/Screen

Window control

`bgcolor()`
`bgpic()`
`clear()` | `clearscreen()`
`reset()` | `resetscreen()`
`screensize()`
`setworldcoordinates()`

Animation control

`delay()`
`tracer()`
`update()`

Using screen events

`listen()`
`onkey()`
`onclick()` | `onscreenclick()`

```
ontimer()
```

Settings and special methods

```
mode()  
colormode()  
getcanvas()  
getshapes()  
register_shape() | addshape()  
turtles()  
window_height()  
window_width()
```

Methods specific to Screen

```
bye()  
exitonclick()  
setup()  
title()
```

24.5.3 Methods of RawTurtle/Turtle and corresponding functions

Most of the examples in this section refer to a Turtle instance called `turtle`.

Turtle motion

```
turtle.forward(distance)  
turtle.fd(distance)
```

매개변수 **distance** – a number (integer or float)

Move the turtle forward by the specified *distance*, in the direction the turtle is headed.

```
>>> turtle.position()  
(0.00,0.00)  
>>> turtle.forward(25)  
>>> turtle.position()  
(25.00,0.00)  
>>> turtle.forward(-75)  
>>> turtle.position()  
(-50.00,0.00)
```

```
turtle.back(distance)  
turtle.bk(distance)  
turtle.backward(distance)
```

매개변수 **distance** – a number

Move the turtle backward by *distance*, opposite to the direction the turtle is headed. Do not change the turtle's heading.

```
>>> turtle.position()  
(0.00,0.00)  
>>> turtle.backward(30)  
>>> turtle.position()  
(-30.00,0.00)
```


`turtle.right(angle)`
`turtle.rt(angle)`

매개변수 **angle** – a number (integer or float)

Turn turtle right by *angle* units. (Units are by default degrees, but can be set via the `degrees()` and `radians()` functions.) Angle orientation depends on the turtle mode, see `mode()`.

```
>>> turtle.heading()
22.0
>>> turtle.right(45)
>>> turtle.heading()
337.0
```

`turtle.left(angle)`
`turtle.lt(angle)`

매개변수 **angle** – a number (integer or float)

Turn turtle left by *angle* units. (Units are by default degrees, but can be set via the `degrees()` and `radians()` functions.) Angle orientation depends on the turtle mode, see `mode()`.

```
>>> turtle.heading()
22.0
>>> turtle.left(45)
>>> turtle.heading()
67.0
```

`turtle.goto(x, y=None)`
`turtle.setpos(x, y=None)`
`turtle.setposition(x, y=None)`

매개변수

- **x** – a number or a pair/vector of numbers
- **y** – a number or None

If *y* is None, *x* must be a pair of coordinates or a `Vec2D` (e.g. as returned by `pos()`).

Move turtle to an absolute position. If the pen is down, draw line. Do not change the turtle's orientation.

```
>>> tp = turtle.pos()
>>> tp
(0.00, 0.00)
>>> turtle.setpos(60, 30)
>>> turtle.pos()
(60.00, 30.00)
>>> turtle.setpos((20, 80))
>>> turtle.pos()
(20.00, 80.00)
>>> turtle.setpos(tp)
>>> turtle.pos()
(0.00, 0.00)
```

`turtle.setx(x)`

매개변수 **x** – a number (integer or float)

Set the turtle's first coordinate to *x*, leave second coordinate unchanged.

```
>>> turtle.position()
(0.00, 240.00)
>>> turtle.setx(10)
>>> turtle.position()
(10.00, 240.00)
```

`turtle.sety(y)`

매개변수 **y** – a number (integer or float)

Set the turtle's second coordinate to *y*, leave first coordinate unchanged.

```
>>> turtle.position()
(0.00, 40.00)
>>> turtle.sety(-10)
>>> turtle.position()
(0.00, -10.00)
```

`turtle.setheading(to_angle)`

`turtle.seth(to_angle)`

매개변수 **to_angle** – a number (integer or float)

Set the orientation of the turtle to *to_angle*. Here are some common directions in degrees:

standard mode	logo mode
0 - east	0 - north
90 - north	90 - east
180 - west	180 - south
270 - south	270 - west

```
>>> turtle.setheading(90)
>>> turtle.heading()
90.0
```

`turtle.home()`

Move turtle to the origin – coordinates (0,0) – and set its heading to its start-orientation (which depends on the mode, see *mode()*).

```
>>> turtle.heading()
90.0
>>> turtle.position()
(0.00, -10.00)
>>> turtle.home()
>>> turtle.position()
(0.00, 0.00)
>>> turtle.heading()
0.0
```

`turtle.circle(radius, extent=None, steps=None)`

매개변수

- **radius** – a number
- **extent** – a number (or None)
- **steps** – an integer (or None)

Draw a circle with given *radius*. The center is *radius* units left of the turtle; *extent* – an angle – determines which part of the circle is drawn. If *extent* is not given, draw the entire circle. If *extent* is not a full circle, one endpoint of the arc is the current pen position. Draw the arc in counterclockwise direction if *radius* is positive, otherwise in clockwise direction. Finally the direction of the turtle is changed by the amount of *extent*.

As the circle is approximated by an inscribed regular polygon, *steps* determines the number of steps to use. If not given, it will be calculated automatically. May be used to draw regular polygons.

```
>>> turtle.home()
>>> turtle.position()
(0.00,0.00)
>>> turtle.heading()
0.0
>>> turtle.circle(50)
>>> turtle.position()
(-0.00,0.00)
>>> turtle.heading()
0.0
>>> turtle.circle(120, 180) # draw a semicircle
>>> turtle.position()
(0.00,240.00)
>>> turtle.heading()
180.0
```

`turtle.dot (size=None, *color)`

매개변수

- **size** – an integer ≥ 1 (if given)
- **color** – a colorstring or a numeric color tuple

Draw a circular dot with diameter *size*, using *color*. If *size* is not given, the maximum of pensize+4 and 2*pensize is used.

```
>>> turtle.home()
>>> turtle.dot()
>>> turtle.fd(50); turtle.dot(20, "blue"); turtle.fd(50)
>>> turtle.position()
(100.00,-0.00)
>>> turtle.heading()
0.0
```

`turtle.stamp()`

Stamp a copy of the turtle shape onto the canvas at the current turtle position. Return a `stamp_id` for that stamp, which can be used to delete it by calling `clearstamp(stamp_id)`.

```
>>> turtle.color("blue")
>>> turtle.stamp()
11
>>> turtle.fd(50)
```

`turtle.clearstamp (stampid)`

매개변수 **stampid** – an integer, must be return value of previous `stamp()` call

Delete stamp with given *stampid*.

```
>>> turtle.position()
(150.00,-0.00)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

>>> turtle.color("blue")
>>> astamp = turtle.stamp()
>>> turtle.fd(50)
>>> turtle.position()
(200.00,-0.00)
>>> turtle.clearstamp(astamp)
>>> turtle.position()
(200.00,-0.00)

```

`turtle.clearstamps` (*n=None*)

매개변수 **n** – an integer (or None)

Delete all or first/last *n* of turtle's stamps. If *n* is None, delete all stamps, if *n* > 0 delete first *n* stamps, else if *n* < 0 delete last *n* stamps.

```

>>> for i in range(8):
...     turtle.stamp(); turtle.fd(30)
13
14
15
16
17
18
19
20
>>> turtle.clearstamps(2)
>>> turtle.clearstamps(-2)
>>> turtle.clearstamps()

```

`turtle.undo` ()

Undo (repeatedly) the last turtle action(s). Number of available undo actions is determined by the size of the undobuffer.

```

>>> for i in range(4):
...     turtle.fd(50); turtle.lt(80)
...
>>> for i in range(8):
...     turtle.undo()

```

`turtle.speed` (*speed=None*)

매개변수 **speed** – an integer in the range 0..10 or a speedstring (see below)

Set the turtle's speed to an integer value in the range 0..10. If no argument is given, return current speed.

If input is a number greater than 10 or smaller than 0.5, speed is set to 0. Speedstrings are mapped to speedvalues as follows:

- 《fastest》: 0
- 《fast》: 10
- 《normal》: 6
- 《slow》: 3
- 《slowest》: 1

Speeds from 1 to 10 enforce increasingly faster animation of line drawing and turtle turning.

Attention: *speed* = 0 means that *no* animation takes place. *forward/back* makes turtle jump and likewise *left/right* make the turtle turn instantly.

```
>>> turtle.speed()
3
>>> turtle.speed('normal')
>>> turtle.speed()
6
>>> turtle.speed(9)
>>> turtle.speed()
9
```

Tell Turtle's state

`turtle.position()`

`turtle.pos()`

Return the turtle's current location (x,y) (as a *Vec2D* vector).

```
>>> turtle.pos()
(440.00, -0.00)
```

`turtle.towards(x, y=None)`

매개변수

- **x** – a number or a pair/vector of numbers or a turtle instance
- **y** – a number if *x* is a number, else None

Return the angle between the line from turtle position to position specified by (x,y), the vector or the other turtle. This depends on the turtle's start orientation which depends on the mode - 《standard》/《world》 or 《logo》).

```
>>> turtle.goto(10, 10)
>>> turtle.towards(0, 0)
225.0
```

`turtle.xcor()`

Return the turtle's x coordinate.

```
>>> turtle.home()
>>> turtle.left(50)
>>> turtle.forward(100)
>>> turtle.pos()
(64.28, 76.60)
>>> print turtle.xcor()
64.2787609687
```

`turtle.ycor()`

Return the turtle's y coordinate.

```
>>> turtle.home()
>>> turtle.left(60)
>>> turtle.forward(100)
>>> print turtle.pos()
(50.00, 86.60)
>>> print turtle.ycor()
86.6025403784
```

`turtle.heading()`

Return the turtle's current heading (value depends on the turtle mode, see [mode\(\)](#)).

```
>>> turtle.home()
>>> turtle.left(67)
>>> turtle.heading()
67.0
```

`turtle.distance(x, y=None)`

매개변수

- **x** – a number or a pair/vector of numbers or a turtle instance
- **y** – a number if *x* is a number, else None

Return the distance from the turtle to (x,y), the given vector, or the given other turtle, in turtle step units.

```
>>> turtle.home()
>>> turtle.distance(30,40)
50.0
>>> turtle.distance((30,40))
50.0
>>> joe = Turtle()
>>> joe.forward(77)
>>> turtle.distance(joe)
77.0
```

Settings for measurement

`turtle.degrees(fullcircle=360.0)`

매개변수 **fullcircle** – a number

Set angle measurement units, i.e. set number of 《degrees》 for a full circle. Default value is 360 degrees.

```
>>> turtle.home()
>>> turtle.left(90)
>>> turtle.heading()
90.0

Change angle measurement unit to grad (also known as gon,
grade, or gradian and equals 1/100-th of the right angle.)
>>> turtle.degrees(400.0)
>>> turtle.heading()
100.0
>>> turtle.degrees(360)
>>> turtle.heading()
90.0
```

`turtle.radians()`

Set the angle measurement units to radians. Equivalent to `degrees(2*math.pi)`.

```
>>> turtle.home()
>>> turtle.left(90)
>>> turtle.heading()
90.0
>>> turtle.radians()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> turtle.heading()
1.5707963267948966
```

Pen control

Drawing state

```
turtle.pendown()
```

```
turtle.pd()
```

```
turtle.down()
```

Pull the pen down – drawing when moving.

```
turtle.penup()
```

```
turtle.pu()
```

```
turtle.up()
```

Pull the pen up – no drawing when moving.

```
turtle.pensize(width=None)
```

```
turtle.width(width=None)
```

매개변수 **width** – a positive number

Set the line thickness to *width* or return it. If *resizemode* is set to `《auto》` and *turtleshape* is a polygon, that polygon is drawn with the same line thickness. If no argument is given, the current pensize is returned.

```
>>> turtle.pensize()
1
>>> turtle.pensize(10)    # from here on lines of width 10 are drawn
```

```
turtle.pen(pen=None, **pendict)
```

매개변수

- **pen** – a dictionary with some or all of the below listed keys
- **pendict** – one or more keyword-arguments with the below listed keys as keywords

Return or set the pen's attributes in a `《pen-dictionary》` with the following key/value pairs:

- `《shown》`: True/False
- `《pendown》`: True/False
- `《pencolor》`: color-string or color-tuple
- `《fillcolor》`: color-string or color-tuple
- `《pensize》`: positive number
- `《speed》`: number in range 0..10
- `《resizemode》`: `《auto》` or `《user》` or `《noresize》`
- `《stretchfactor》`: (positive number, positive number)
- `《outline》`: positive number
- `《tilt》`: number

This dictionary can be used as argument for a subsequent call to `pen()` to restore the former pen-state. Moreover one or more of these attributes can be provided as keyword-arguments. This can be used to set several pen attributes in one statement.

```
>>> turtle.pen(fillcolor="black", pencolor="red", pensize=10)
>>> sorted(turtle.pen().items())
[('fillcolor', 'black'), ('outline', 1), ('pencolor', 'red'),
 ('pendown', True), ('pensize', 10), ('resizemode', 'noresize'),
 ('shown', True), ('speed', 9), ('stretchfactor', (1, 1)), ('tilt', 0)]
>>> penstate=turtle.pen()
>>> turtle.color("yellow", "")
>>> turtle.penup()
>>> sorted(turtle.pen().items())
[('fillcolor', ''), ('outline', 1), ('pencolor', 'yellow'),
 ('pendown', False), ('pensize', 10), ('resizemode', 'noresize'),
 ('shown', True), ('speed', 9), ('stretchfactor', (1, 1)), ('tilt', 0)]
>>> turtle.pen(penstate, fillcolor="green")
>>> sorted(turtle.pen().items())
[('fillcolor', 'green'), ('outline', 1), ('pencolor', 'red'),
 ('pendown', True), ('pensize', 10), ('resizemode', 'noresize'),
 ('shown', True), ('speed', 9), ('stretchfactor', (1, 1)), ('tilt', 0)]
```

`turtle.isdown()`

Return True if pen is down, False if it's up.

```
>>> turtle.penup()
>>> turtle.isdown()
False
>>> turtle.pendown()
>>> turtle.isdown()
True
```

Color control

`turtle.pencolor(*args)`

Return or set the pencolor.

Four input formats are allowed:

pencolor() Return the current pencolor as color specification string or as a tuple (see example). May be used as input to another color/pencolor/fillcolor call.

pencolor(colorstring) Set pencolor to *colorstring*, which is a Tk color specification string, such as "red", "yellow", or "#33cc8c".

pencolor(r, g, b) Set pencolor to the RGB color represented by the tuple of *r*, *g*, and *b*. Each of *r*, *g*, and *b* must be in the range 0..colormode, where colormode is either 1.0 or 255 (see `colormode()`).

pencolor(r, g, b)

Set pencolor to the RGB color represented by *r*, *g*, and *b*. Each of *r*, *g*, and *b* must be in the range 0..colormode.

If `turtleshape` is a polygon, the outline of that polygon is drawn with the newly set pencolor.

```
>>> colormode()
1.0
>>> turtle.pencolor()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
'red'
>>> turtle.pencolor("brown")
>>> turtle.pencolor()
'brown'
>>> tup = (0.2, 0.8, 0.55)
>>> turtle.pencolor(tup)
>>> turtle.pencolor()
(0.2, 0.8, 0.5490196078431373)
>>> colormode(255)
>>> turtle.pencolor()
(51, 204, 140)
>>> turtle.pencolor('#32c18f')
>>> turtle.pencolor()
(50, 193, 143)
```

turtle.fillcolor(*args)

Return or set the fillcolor.

Four input formats are allowed:

fillcolor() Return the current fillcolor as color specification string, possibly in tuple format (see example). May be used as input to another color/pencolor/fillcolor call.

fillcolor(colorstring) Set fillcolor to *colorstring*, which is a Tk color specification string, such as "red", "yellow", or "#33cc8c".

fillcolor(r, g, b) Set fillcolor to the RGB color represented by the tuple of *r*, *g*, and *b*. Each of *r*, *g*, and *b* must be in the range 0..colormode, where colormode is either 1.0 or 255 (see [colormode\(\)](#)).

fillcolor(r, g, b)

Set fillcolor to the RGB color represented by *r*, *g*, and *b*. Each of *r*, *g*, and *b* must be in the range 0..colormode.

If turtleshape is a polygon, the interior of that polygon is drawn with the newly set fillcolor.

```
>>> turtle.fillcolor("violet")
>>> turtle.fillcolor()
'violet'
>>> col = turtle.pencolor()
>>> col
(50, 193, 143)
>>> turtle.fillcolor(col)
>>> turtle.fillcolor()
(50, 193, 143)
>>> turtle.fillcolor('#ffffff')
>>> turtle.fillcolor()
(255, 255, 255)
```

turtle.color(*args)

Return or set pencolor and fillcolor.

Several input formats are allowed. They use 0 to 3 arguments as follows:

color() Return the current pencolor and the current fillcolor as a pair of color specification strings or tuples as returned by [pencolor\(\)](#) and [fillcolor\(\)](#).

color(colorstring), color((r,g,b)), color(r,g,b) Inputs as in [pencolor\(\)](#), set both, fillcolor and pencolor, to the given value.

```
color(colorstring1, colorstring2), color((r1,g1,b1), (r2,g2,b2))
```

Equivalent to `pencolor(colorstring1)` and `fillcolor(colorstring2)` and analogously if the other input format is used.

If `turtleshape` is a polygon, outline and interior of that polygon is drawn with the newly set colors.

```
>>> turtle.color("red", "green")
>>> turtle.color()
('red', 'green')
>>> color("#285078", "#a0c8f0")
>>> color()
((40, 80, 120), (160, 200, 240))
```

See also: Screen method `colormode()`.

Filling

`turtle.fill(flag)`

매개변수 **flag** – True/False (or 1/0 respectively)

Call `fill(True)` before drawing the shape you want to fill, and `fill(False)` when done. When used without argument: return fillstate (True if filling, False else).

```
>>> turtle.fill(True)
>>> for _ in range(3):
...     turtle.forward(100)
...     turtle.left(120)
...
>>> turtle.fill(False)
```

`turtle.begin_fill()`

Call just before drawing a shape to be filled. Equivalent to `fill(True)`.

`turtle.end_fill()`

Fill the shape drawn after the last call to `begin_fill()`. Equivalent to `fill(False)`.

```
>>> turtle.color("black", "red")
>>> turtle.begin_fill()
>>> turtle.circle(80)
>>> turtle.end_fill()
```

More drawing control

`turtle.reset()`

Delete the turtle's drawings from the screen, re-center the turtle and set variables to the default values.

```
>>> turtle.goto(0,-22)
>>> turtle.left(100)
>>> turtle.position()
(0.00,-22.00)
>>> turtle.heading()
100.0
>>> turtle.reset()
>>> turtle.position()
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
(0.00,0.00)
>>> turtle.heading()
0.0
```

`turtle.clear()`

Delete the turtle's drawings from the screen. Do not move turtle. State and position of the turtle as well as drawings of other turtles are not affected.

`turtle.write(arg, move=False, align="left", font=("Arial", 8, "normal"))`

매개변수

- **arg** – object to be written to the TurtleScreen
- **move** – True/False
- **align** – one of the strings 《left》, 《center》 or right》
- **font** – a triple (fontname, fontsize, fonttype)

Write text - the string representation of *arg* - at the current turtle position according to *align* (《left》, 《center》 or right》) and with the given font. If *move* is true, the pen is moved to the bottom-right corner of the text. By default, *move* is False.

```
>>> turtle.write("Home = ", True, align="center")
>>> turtle.write((0,0), True)
```

Turtle state

Visibility

`turtle.hideturtle()`

`turtle.ht()`

Make the turtle invisible. It's a good idea to do this while you're in the middle of doing some complex drawing, because hiding the turtle speeds up the drawing observably.

```
>>> turtle.hideturtle()
```

`turtle.showturtle()`

`turtle.st()`

Make the turtle visible.

```
>>> turtle.showturtle()
```

`turtle.isvisible()`

Return True if the Turtle is shown, False if it's hidden.

```
>>> turtle.hideturtle()
>>> turtle.isvisible()
False
>>> turtle.showturtle()
>>> turtle.isvisible()
True
```

Appearance

`turtle.shape(name=None)`

매개변수 **name** – a string which is a valid shapename

Set turtle shape to shape with given *name* or, if name is not given, return name of current shape. Shape with *name* must exist in the TurtleScreen's shape dictionary. Initially there are the following polygon shapes: 《arrow》, 《turtle》, 《circle》, 《square》, 《triangle》, 《classic》. To learn about how to deal with shapes see Screen method `register_shape()`.

```
>>> turtle.shape()
'classic'
>>> turtle.shape("turtle")
>>> turtle.shape()
'turtle'
```

`turtle.resizemode(rmode=None)`

매개변수 **rmode** – one of the strings 《auto》, 《user》, 《noresize》

Set `resizemode` to one of the values: 《auto》, 《user》, 《noresize》. If *rmode* is not given, return current `resizemode`. Different `resizemodes` have the following effects:

- 《auto》: adapts the appearance of the turtle corresponding to the value of `pensize`.
- 《user》: adapts the appearance of the turtle according to the values of `stretchfactor` and `outlinewidth` (outline), which are set by `shapessize()`.
- 《noresize》: no adaption of the turtle's appearance takes place.

`resizemode(《user》)` is called by `shapessize()` when used with arguments.

```
>>> turtle.resizemode()
'noresize'
>>> turtle.resizemode("auto")
>>> turtle.resizemode()
'auto'
```

`turtle.shapesize(stretch_wid=None, stretch_len=None, outline=None)`

`turtle.turtlesize(stretch_wid=None, stretch_len=None, outline=None)`

매개변수

- **stretch_wid** – positive number
- **stretch_len** – positive number
- **outline** – positive number

Return or set the pen's attributes x/y-stretchfactors and/or outline. Set `resizemode` to 《user》. If and only if `resizemode` is set to 《user》, the turtle will be displayed stretched according to its stretchfactors: *stretch_wid* is stretchfactor perpendicular to its orientation, *stretch_len* is stretchfactor in direction of its orientation, *outline* determines the width of the shapes's outline.

```
>>> turtle.shapesize()
(1, 1, 1)
>>> turtle.resizemode("user")
>>> turtle.shapesize(5, 5, 12)
>>> turtle.shapesize()
(5, 5, 12)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> turtle.shapesize(outline=8)
>>> turtle.shapesize()
(5, 5, 8)
```

`turtle.tilt(angle)`

매개변수 **angle** – a number

Rotate the turtleshape by *angle* from its current tilt-angle, but do *not* change the turtle's heading (direction of movement).

```
>>> turtle.reset()
>>> turtle.shape("circle")
>>> turtle.shapesize(5,2)
>>> turtle.tilt(30)
>>> turtle.fd(50)
>>> turtle.tilt(30)
>>> turtle.fd(50)
```

`turtle.settiltangle(angle)`

매개변수 **angle** – a number

Rotate the turtleshape to point in the direction specified by *angle*, regardless of its current tilt-angle. *Do not* change the turtle's heading (direction of movement).

```
>>> turtle.reset()
>>> turtle.shape("circle")
>>> turtle.shapesize(5,2)
>>> turtle.settiltangle(45)
>>> turtle.fd(50)
>>> turtle.settiltangle(-45)
>>> turtle.fd(50)
```

`turtle.tiltangle()`

Return the current tilt-angle, i.e. the angle between the orientation of the turtleshape and the heading of the turtle (its direction of movement).

```
>>> turtle.reset()
>>> turtle.shape("circle")
>>> turtle.shapesize(5,2)
>>> turtle.tilt(45)
>>> turtle.tiltangle()
45.0
```

Using events

`turtle.onclick(fun, btn=1, add=None)`

매개변수

- **fun** – a function with two arguments which will be called with the coordinates of the clicked point on the canvas
- **btn** – number of the mouse-button, defaults to 1 (left mouse button)
- **add** – True or False – if True, a new binding will be added, otherwise it will replace a former binding

Bind *fun* to mouse-click events on this turtle. If *fun* is *None*, existing bindings are removed. Example for the anonymous turtle, i.e. the procedural way:

```
>>> def turn(x, y):
...     left(180)
...
>>> onclick(turn)  # Now clicking into the turtle will turn it.
>>> onclick(None)  # event-binding will be removed
```

`turtle.onrelease(fun, btn=1, add=None)`

매개변수

- **fun** – a function with two arguments which will be called with the coordinates of the clicked point on the canvas
- **btn** – number of the mouse-button, defaults to 1 (left mouse button)
- **add** – True or False – if True, a new binding will be added, otherwise it will replace a former binding

Bind *fun* to mouse-button-release events on this turtle. If *fun* is *None*, existing bindings are removed.

```
>>> class MyTurtle(Turtle):
...     def glow(self, x, y):
...         self.fillcolor("red")
...     def unglow(self, x, y):
...         self.fillcolor("")
...
>>> turtle = MyTurtle()
>>> turtle.onclick(turtle.glow)  # clicking on turtle turns fillcolor red,
>>> turtle.onrelease(turtle.unglow) # releasing turns it to transparent.
```

`turtle.ondrag(fun, btn=1, add=None)`

매개변수

- **fun** – a function with two arguments which will be called with the coordinates of the clicked point on the canvas
- **btn** – number of the mouse-button, defaults to 1 (left mouse button)
- **add** – True or False – if True, a new binding will be added, otherwise it will replace a former binding

Bind *fun* to mouse-move events on this turtle. If *fun* is *None*, existing bindings are removed.

Remark: Every sequence of mouse-move-events on a turtle is preceded by a mouse-click event on that turtle.

```
>>> turtle.ondrag(turtle.goto)
```

Subsequently, clicking and dragging the Turtle will move it across the screen thereby producing handdrawings (if pen is down).

`turtle.mainloop()`

`turtle.done()`

Starts event loop - calling Tkinter's `mainloop` function. Must be the last statement in a turtle graphics program.

```
>>> turtle.mainloop()
```

Special Turtle methods

`turtle.begin_poly()`

Start recording the vertices of a polygon. Current turtle position is first vertex of polygon.

`turtle.end_poly()`

Stop recording the vertices of a polygon. Current turtle position is last vertex of polygon. This will be connected with the first vertex.

`turtle.get_poly()`

Return the last recorded polygon.

```

>>> turtle.home()
>>> turtle.begin_poly()
>>> turtle.fd(100)
>>> turtle.left(20)
>>> turtle.fd(30)
>>> turtle.left(60)
>>> turtle.fd(50)
>>> turtle.end_poly()
>>> p = turtle.get_poly()
>>> register_shape("myFavouriteShape", p)

```

`turtle.clone()`

Create and return a clone of the turtle with same position, heading and turtle properties.

```

>>> mick = Turtle()
>>> joe = mick.clone()

```

`turtle.getturtle()`

`turtle.getpen()`

Return the Turtle object itself. Only reasonable use: as a function to return the 《anonymous turtle》:

```

>>> pet = getturtle()
>>> pet.fd(50)
>>> pet
<turtle.Turtle object at 0x...>

```

`turtle.getscreen()`

Return the *TurtleScreen* object the turtle is drawing on. *TurtleScreen* methods can then be called for that object.

```

>>> ts = turtle.getscreen()
>>> ts
<turtle._Screen object at 0x...>
>>> ts.bgcolor("pink")

```

`turtle.setundobuffer(size)`

매개변수 **size** – an integer or None

Set or disable undobuffer. If *size* is an integer an empty undobuffer of given size is installed. *size* gives the maximum number of turtle actions that can be undone by the *undo()* method/function. If *size* is None, the undobuffer is disabled.

```

>>> turtle.setundobuffer(42)

```

`turtle.undobufferentries()`

Return number of entries in the undobuffer.

```
>>> while undobufferentries():
...     undo()
```

`turtle.tracer(flag=None, delay=None)`

A replica of the corresponding TurtleScreen method.

버전 2.6부터 폐지.

`turtle.window_width()`

`turtle.window_height()`

Both are replicas of the corresponding TurtleScreen methods.

버전 2.6부터 폐지.

Excursus about the use of compound shapes

To use compound turtle shapes, which consist of several polygons of different color, you must use the helper class *Shape* explicitly as described below:

1. Create an empty Shape object of type `Shape`.
2. Add as many components to this object as desired, using the `addcomponent()` method.

For example:

```
>>> s = Shape("compound")
>>> poly1 = ((0,0), (10,-5), (0,10), (-10,-5))
>>> s.addcomponent(poly1, "red", "blue")
>>> poly2 = ((0,0), (10,-5), (-10,-5))
>>> s.addcomponent(poly2, "blue", "red")
```

3. Now add the Shape to the Screen's shapelist and use it:

```
>>> register_shape("myshape", s)
>>> shape("myshape")
```

참고: The *Shape* class is used internally by the `register_shape()` method in different ways. The application programmer has to deal with the Shape class *only* when using compound shapes like shown above!

24.5.4 Methods of TurtleScreen/Screen and corresponding functions

Most of the examples in this section refer to a TurtleScreen instance called `screen`.

Window control

`turtle.bgcolor(*args)`

매개변수 **args** – a color string or three numbers in the range 0..colormode or a 3-tuple of such numbers

Set or return background color of the TurtleScreen.


```
>>> screen.bgcolor("orange")
>>> screen.bgcolor()
'orange'
>>> screen.bgcolor("#800080")
>>> screen.bgcolor()
(128, 0, 128)
```

`turtle.bgpic(picname=None)`

매개변수 **picname** – a string, name of a gif-file or "nopic", or None

Set background image or return name of current backgroundimage. If *picname* is a filename, set the corresponding image as background. If *picname* is "nopic", delete background image, if present. If *picname* is None, return the filename of the current backgroundimage.

```
>>> screen.bgpic()
'nopic'
>>> screen.bgpic("landscape.gif")
>>> screen.bgpic()
"landscape.gif"
```

`turtle.clear()`

`turtle.clearscreen()`

Delete all drawings and all turtles from the TurtleScreen. Reset the now empty TurtleScreen to its initial state: white background, no background image, no event bindings and tracing on.

참고: This TurtleScreen method is available as a global function only under the name `clearscreen`. The global function `clear` is another one derived from the Turtle method `clear`.

`turtle.reset()`

`turtle.resetscreen()`

Reset all Turtles on the Screen to their initial state.

참고: This TurtleScreen method is available as a global function only under the name `resetscreen`. The global function `reset` is another one derived from the Turtle method `reset`.

`turtle.screensize(canvwidth=None, canvheight=None, bg=None)`

매개변수

- **canvwidth** – positive integer, new width of canvas in pixels
- **canvheight** – positive integer, new height of canvas in pixels
- **bg** – colorstring or color-tuple, new background color

If no arguments are given, return current (canvaswidth, canvasheight). Else resize the canvas the turtles are drawing on. Do not alter the drawing window. To observe hidden parts of the canvas, use the scrollbars. With this method, one can make visible those parts of a drawing which were outside the canvas before.

```
>>> screen.screensize()
(400, 300)
>>> screen.screensize(2000,1500)
>>> screen.screensize()
(2000, 1500)
```

e.g. to search for an erroneously escaped turtle ;-)

`turtle.setworldcoordinates` (*llx, lly, urx, ury*)

매개변수

- **llx** – a number, x-coordinate of lower left corner of canvas
- **lly** – a number, y-coordinate of lower left corner of canvas
- **urx** – a number, x-coordinate of upper right corner of canvas
- **ury** – a number, y-coordinate of upper right corner of canvas

Set up user-defined coordinate system and switch to mode 《world》 if necessary. This performs a `screen.reset()`. If mode 《world》 is already active, all drawings are redrawn according to the new coordinates.

ATTENTION: in user-defined coordinate systems angles may appear distorted.

```
>>> screen.reset()
>>> screen.setworldcoordinates(-50, -7.5, 50, 7.5)
>>> for _ in range(72):
...     left(10)
...
>>> for _ in range(8):
...     left(45); fd(2)    # a regular octagon
```

Animation control

`turtle.delay` (*delay=None*)

매개변수 **delay** – positive integer

Set or return the drawing *delay* in milliseconds. (This is approximately the time interval between two consecutive canvas updates.) The longer the drawing delay, the slower the animation.

Optional argument:

```
>>> screen.delay()
10
>>> screen.delay(5)
>>> screen.delay()
5
```

`turtle.tracer` (*n=None, delay=None*)

매개변수

- **n** – nonnegative integer
- **delay** – nonnegative integer

Turn turtle animation on/off and set delay for update drawings. If *n* is given, only each *n*-th regular screen update is really performed. (Can be used to accelerate the drawing of complex graphics.) Second argument sets delay value (see `delay()`).

```
>>> screen.tracer(8, 25)
>>> dist = 2
>>> for i in range(200):
...     fd(dist)
...     rt(90)
...     dist += 2
```

`turtle.update()`

Perform a TurtleScreen update. To be used when tracer is turned off.

See also the RawTurtle/Turtle method `speed()`.

Using screen events

`turtle.listen(xdummy=None, ydummy=None)`

Set focus on TurtleScreen (in order to collect key-events). Dummy arguments are provided in order to be able to pass `listen()` to the onclick method.

`turtle.onkey(fun, key)`

매개변수

- **fun** – a function with no arguments or None
- **key** – a string: key (e.g. `«a»`) or key-symbol (e.g. `«space»`)

Bind *fun* to key-release event of key. If *fun* is None, event bindings are removed. Remark: in order to be able to register key-events, TurtleScreen must have the focus. (See method `listen()`.)

```
>>> def f():
...     fd(50)
...     lt(60)
...
>>> screen.onkey(f, "Up")
>>> screen.listen()
```

`turtle.onclick(fun, btn=1, add=None)`

`turtle.onscreenclick(fun, btn=1, add=None)`

매개변수

- **fun** – a function with two arguments which will be called with the coordinates of the clicked point on the canvas
- **btn** – number of the mouse-button, defaults to 1 (left mouse button)
- **add** – True or False – if True, a new binding will be added, otherwise it will replace a former binding

Bind *fun* to mouse-click events on this screen. If *fun* is None, existing bindings are removed.

Example for a TurtleScreen instance named `screen` and a Turtle instance named `turtle`:

```
>>> screen.onclick(turtle.goto) # Subsequently clicking into the TurtleScreen will
>>>                               # make the turtle move to the clicked point.
>>> screen.onclick(None)        # remove event binding again
```

참고: This TurtleScreen method is available as a global function only under the name `onscreenclick`. The global function `onclick` is another one derived from the Turtle method `onclick`.

`turtle.ontimer(fun, t=0)`

매개변수

- **fun** – a function with no arguments
- **t** – a number ≥ 0

Install a timer that calls *fun* after *t* milliseconds.

```
>>> running = True
>>> def f():
...     if running:
...         fd(50)
...         lt(60)
...         screen.ontimer(f, 250)
>>> f()    ### makes the turtle march around
>>> running = False
```

Settings and special methods

`turtle.mode(mode=None)`

매개변수 **mode** – one of the strings 《standard》, 《logo》 or 《world》

Set turtle mode (《standard》, 《logo》 or 《world》) and perform reset. If mode is not given, current mode is returned.

Mode 《standard》 is compatible with old *turtle*. Mode 《logo》 is compatible with most Logo turtle graphics. Mode 《world》 uses user-defined 《world coordinates》. **Attention:** in this mode angles appear distorted if *x/y* unit-ratio doesn't equal 1.

Mode	Initial turtle heading	positive angles
《standard》	to the right (east)	counterclockwise
《logo》	upward (north)	clockwise

```
>>> mode("logo")    # resets turtle heading to north
>>> mode()
'logo'
```

`turtle.colormode(cmode=None)`

매개변수 **cmode** – one of the values 1.0 or 255

Return the colormode or set it to 1.0 or 255. Subsequently *r*, *g*, *b* values of color triples have to be in the range 0..*cmode*.

```
>>> screen.colormode(1)
>>> turtle.pencolor(240, 160, 80)
Traceback (most recent call last):
...
TurtleGraphicsError: bad color sequence: (240, 160, 80)
>>> screen.colormode()
1.0
>>> screen.colormode(255)
>>> screen.colormode()
255
>>> turtle.pencolor(240,160,80)
```

`turtle.getcanvas()`

Return the Canvas of this TurtleScreen. Useful for insiders who know what to do with a Tkinter Canvas.

```
>>> cv = screen.getcanvas()
>>> cv
<turtle.ScrolledCanvas instance at 0x...>
```

`turtle.getshapes()`

Return a list of names of all currently available turtle shapes.

```
>>> screen.getshapes()
['arrow', 'blank', 'circle', ..., 'turtle']
```

`turtle.register_shape(name, shape=None)`

`turtle.addshape(name, shape=None)`

There are three different ways to call this function:

- (1) *name* is the name of a gif-file and *shape* is None: Install the corresponding image shape.

```
>>> screen.register_shape("turtle.gif")
```

참고: Image shapes *do not* rotate when turning the turtle, so they do not display the heading of the turtle!

- (2) *name* is an arbitrary string and *shape* is a tuple of pairs of coordinates: Install the corresponding polygon shape.

```
>>> screen.register_shape("triangle", ((5,-3), (0,5), (-5,-3)))
```

- (3) *name* is an arbitrary string and *shape* is a (compound) *Shape* object: Install the corresponding compound shape.

Add a turtle shape to TurtleScreen's shapelist. Only thusly registered shapes can be used by issuing the command `shape(shapename)`.

`turtle.turtles()`

Return the list of turtles on the screen.

```
>>> for turtle in screen.turtles():
...     turtle.color("red")
```

`turtle.window_height()`

Return the height of the turtle window.

```
>>> screen.window_height()
480
```

`turtle.window_width()`

Return the width of the turtle window.

```
>>> screen.window_width()
640
```

Methods specific to Screen, not inherited from TurtleScreen

`turtle.bye()`

Shut the turtlegraphics window.

`turtle.exitonclick()`

Bind `bye()` method to mouse clicks on the Screen.

If the value `《using_IDLE》` in the configuration dictionary is `False` (default value), also enter `mainloop`. Remark: If IDLE with the `-n` switch (no subprocess) is used, this value should be set to `True` in `turtle.cfg`. In this case IDLE's own `mainloop` is active also for the client script.

```
turtle.setup (width=_CFG["width"],          height=_CFG["height"],          startx=_CFG["leftright"],
              starty=_CFG["topbottom"])
```

Set the size and position of the main window. Default values of arguments are stored in the configuration dictionary and can be changed via a `turtle.cfg` file.

매개변수

- **width** – if an integer, a size in pixels, if a float, a fraction of the screen; default is 50% of screen
- **height** – if an integer, the height in pixels, if a float, a fraction of the screen; default is 75% of screen
- **startx** – if positive, starting position in pixels from the left edge of the screen, if negative from the right edge, if `None`, center window horizontally
- **starty** – if positive, starting position in pixels from the top edge of the screen, if negative from the bottom edge, if `None`, center window vertically

```
>>> screen.setup (width=200, height=200, startx=0, starty=0)
>>>             # sets window to 200x200 pixels, in upper left of screen
>>> screen.setup (width=.75, height=0.5, startx=None, starty=None)
>>>             # sets window to 75% of screen by 50% of screen and centers
```

```
turtle.title (titlestring)
```

매개변수 **titlestring** – a string that is shown in the titlebar of the turtle graphics window

Set title of turtle window to *titlestring*.

```
>>> screen.title("Welcome to the turtle zoo!")
```

24.5.5 The public classes of the module `turtle`

```
class turtle.RawTurtle (canvas)
```

```
class turtle.RawPen (canvas)
```

매개변수 **canvas** – a `Tkinter.Canvas`, a *ScrolledCanvas* or a *TurtleScreen*

Create a turtle. The turtle has all methods described above as 《methods of Turtle/RawTurtle》.

```
class turtle.Turtle
```

Subclass of `RawTurtle`, has the same interface but draws on a default *Screen* object created automatically when needed for the first time.

```
class turtle.TurtleScreen (cv)
```

매개변수 **cv** – a `Tkinter.Canvas`

Provides screen oriented methods like `setbg()` etc. that are described above.

```
class turtle.Screen
```

Subclass of `TurtleScreen`, with *four methods added*.

```
class turtle.ScrolledCanvas (master)
```

매개변수 **master** – some `Tkinter` widget to contain the `ScrolledCanvas`, i.e. a `Tkinter-canvas` with scrollbars added

Used by class `Screen`, which thus automatically provides a `ScrolledCanvas` as playground for the turtles.

```
class turtle.Shape (type_, data)
```

매개변수 **type_** – one of the strings `⟨polygon⟩`, `⟨image⟩`, `⟨compound⟩`

Data structure modeling shapes. The pair `(type_, data)` must follow this specification:

<i>type_</i>	<i>data</i>
<code>⟨polygon⟩</code>	a polygon-tuple, i.e. a tuple of pairs of coordinates
<code>⟨image⟩</code>	an image (in this form only used internally!)
<code>⟨compound⟩</code>	None (a compound shape has to be constructed using the <code>addcomponent()</code> method)

addcomponent (*poly*, *fill*, *outline=None*)

매개변수

- **poly** – a polygon, i.e. a tuple of pairs of numbers
- **fill** – a color the *poly* will be filled with
- **outline** – a color for the poly's outline (if given)

Example:

```
>>> poly = ((0,0), (10,-5), (0,10), (-10,-5))
>>> s = Shape("compound")
>>> s.addcomponent(poly, "red", "blue")
>>> # ... add more components and then use register_shape()
```

See *Excursus about the use of compound shapes*.

class `turtle.Vec2D` (*x*, *y*)

A two-dimensional vector class, used as a helper class for implementing turtle graphics. May be useful for turtle graphics programs too. Derived from tuple, so a vector is a tuple!

Provides (for *a*, *b* vectors, *k* number):

- `a + b` vector addition
- `a - b` vector subtraction
- `a * b` inner product
- `k * a` and `a * k` multiplication with scalar
- `abs(a)` absolute value of *a*
- `a.rotate(angle)` rotation

24.5.6 Help and configuration

How to use help

The public methods of the `Screen` and `Turtle` classes are documented extensively via docstrings. So these can be used as online-help via the Python help facilities:

- When using IDLE, tooltips show the signatures and first lines of the docstrings of typed in function-/method calls.
- Calling `help()` on methods or functions displays the docstrings:

```
>>> help(Screen.bgcolor)
Help on method bgcolor in module turtle:
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

bgcolor(self, *args) unbound turtle.Screen method
    Set or return backgroundcolor of the TurtleScreen.

Arguments (if given): a color string or three numbers
in the range 0..colormode or a 3-tuple of such numbers.

    >>> screen.bgcolor("orange")
    >>> screen.bgcolor()
    "orange"
    >>> screen.bgcolor(0.5,0,0.5)
    >>> screen.bgcolor()
    "#800080"

>>> help(Turtle.penup)
Help on method penup in module turtle:

penup(self) unbound turtle.Turtle method
    Pull the pen up -- no drawing when moving.

Aliases: penup | pu | up

No argument

    >>> turtle.penup()

```

- The docstrings of the functions which are derived from methods have a modified form:

```

>>> help(bgcolor)
Help on function bgcolor in module turtle:

bgcolor(*args)
    Set or return backgroundcolor of the TurtleScreen.

Arguments (if given): a color string or three numbers
in the range 0..colormode or a 3-tuple of such numbers.

Example::

    >>> bgcolor("orange")
    >>> bgcolor()
    "orange"
    >>> bgcolor(0.5,0,0.5)
    >>> bgcolor()
    "#800080"

>>> help(penup)
Help on function penup in module turtle:

penup()
    Pull the pen up -- no drawing when moving.

Aliases: penup | pu | up

No argument

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
Example:
>>> penup()
```

These modified docstrings are created automatically together with the function definitions that are derived from the methods at import time.

Translation of docstrings into different languages

There is a utility to create a dictionary the keys of which are the method names and the values of which are the docstrings of the public methods of the classes `Screen` and `Turtle`.

```
turtle.write_docstringdict (filename="turtle_docstringdict")
```

매개변수 **filename** – a string, used as filename

Create and write docstring-dictionary to a Python script with the given filename. This function has to be called explicitly (it is not used by the turtle graphics classes). The docstring dictionary will be written to the Python script `filename.py`. It is intended to serve as a template for translation of the docstrings into different languages.

If you (or your students) want to use `turtle` with online help in your native language, you have to translate the docstrings and save the resulting file as e.g. `turtle_docstringdict_german.py`.

If you have an appropriate entry in your `turtle.cfg` file this dictionary will be read in at import time and will replace the original English docstrings.

At the time of this writing there are docstring dictionaries in German and in Italian. (Requests please to glngl@aon.at.)

How to configure Screen and Turtles

The built-in default configuration mimics the appearance and behaviour of the old turtle module in order to retain best possible compatibility with it.

If you want to use a different configuration which better reflects the features of this module or which better fits to your needs, e.g. for use in a classroom, you can prepare a configuration file `turtle.cfg` which will be read at import time and modify the configuration according to its settings.

The built in configuration would correspond to the following `turtle.cfg`:

```
width = 0.5
height = 0.75
leftright = None
topbottom = None
canvwidth = 400
canvheight = 300
mode = standard
colormode = 1.0
delay = 10
undobuffersize = 1000
shape = classic
pencolor = black
fillcolor = black
resizemode = noresize
visible = True
language = english
exampleturtle = turtle
examplescreen = screen
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
title = Python Turtle Graphics
using_IDLE = False
```

Short explanation of selected entries:

- The first four lines correspond to the arguments of the `Screen.setup()` method.
- Line 5 and 6 correspond to the arguments of the method `Screen.screensize()`.
- *shape* can be any of the built-in shapes, e.g: arrow, turtle, etc. For more info try `help(shape)`.
- If you want to use no fillcolor (i.e. make the turtle transparent), you have to write `fillcolor = ""` (but all nonempty strings must not have quotes in the `cfg`-file).
- If you want to reflect the turtle its state, you have to use `resizemode = auto`.
- If you set e.g. `language = italian` the docstringdict `turtle_docstringdict_italian.py` will be loaded at import time (if present on the import path, e.g. in the same directory as `turtle`).
- The entries *exampleturtle* and *examplescreen* define the names of these objects as they occur in the docstrings. The transformation of method-docstrings to function-docstrings will delete these names from the docstrings.
- *using_IDLE*: Set this to `True` if you regularly work with IDLE and its `-n` switch (《no subprocess》). This will prevent `exitonclick()` to enter the mainloop.

There can be a `turtle.cfg` file in the directory where `turtle` is stored and an additional one in the current working directory. The latter will override the settings of the first one.

The `Demo/turtle` directory contains a `turtle.cfg` file. You can study it as an example and see its effects when running the demos (preferably not from within the demo-viewer).

24.5.7 Demo scripts

There is a set of demo scripts in the `turtledemo` directory located in the `Demo/turtle` directory in the source distribution.

It contains:

- a set of 15 demo scripts demonstrating different features of the new module `turtle`
- a demo viewer `turtleDemo.py` which can be used to view the sourcecode of the scripts and run them at the same time. 14 of the examples can be accessed via the Examples menu; all of them can also be run standalone.
- The example `turtledemo_two_c canvases.py` demonstrates the simultaneous use of two canvases with the turtle module. Therefore it only can be run standalone.
- There is a `turtle.cfg` file in this directory, which also serves as an example for how to write and use such files.

The demoscripts are:

Name	Description	Features
bytedesign	complex classical turtlegraphics pattern	<code>tracer()</code> , <code>delay()</code> , <code>update()</code>
chaos	graphs Verhulst dynamics, shows that computer's computations can generate results sometimes against the common sense expectations	world coordinates
clock	analog clock showing time of your computer	turtles as clock's hands, <code>ontimer</code>
colormixer	experiment with r, g, b	<code>ondrag()</code>
fractalcurves	Hilbert & Koch curves	recursion
lindenmayer	ethnomathematics (indian kolams)	L-System
minimal_hanoi	Towers of Hanoi	Rectangular Turtles as Hanoi discs (shape, shapesize)
paint	super minimalistic drawing program	<code>onclick()</code>
peace	elementary	turtle: appearance and animation
penrose	aperiodic tiling with kites and darts	<code>stamp()</code>
planet_and_moon	simulation of gravitational system	compound shapes, <code>Vec2D</code>
tree	a (graphical) breadth first tree (using generators)	<code>clone()</code>
wikipedia	a pattern from the wikipedia article on turtle graphics	<code>clone()</code> , <code>undo()</code>
yinyang	another elementary example	<code>circle()</code>

Have fun!

24.6 IDLE

IDLE is Python's Integrated Development and Learning Environment.

IDLE has the following features:

- coded in 100% pure Python, using the `tkinter` GUI toolkit
- cross-platform: works mostly the same on Windows, Unix, and Mac OS X
- Python shell window (interactive interpreter) with colorizing of code input, output, and error messages
- multi-window text editor with multiple undo, Python colorizing, smart indent, call tips, auto completion, and other features
- search within any window, replace within editor windows, and search through multiple files (`grep`)
- debugger with persistent breakpoints, stepping, and viewing of global and local namespaces
- configuration, browsers, and other dialogs

24.6.1 Menus

IDLE has two main window types, the Shell window and the Editor window. It is possible to have multiple editor windows simultaneously. Output windows, such as used for Edit / Find in Files, are a subtype of edit window. They currently have the same top menu as Editor windows but a different default title and context menu.

IDLE's menus dynamically change based on which window is currently selected. Each menu documented below indicates which window type it is associated with.

File menu (Shell and Editor)

New File Create a new file editing window.

Open... Open an existing file with an Open dialog.

Recent Files Open a list of recent files. Click one to open it.

Open Module... Open an existing module (searches sys.path).

Class Browser Show functions, classes, and methods in the current Editor file in a tree structure. In the shell, open a module first.

Path Browser Show sys.path directories, modules, functions, classes and methods in a tree structure.

Save Save the current window to the associated file, if there is one. Windows that have been changed since being opened or last saved have a * before and after the window title. If there is no associated file, do Save As instead.

Save As... Save the current window with a Save As dialog. The file saved becomes the new associated file for the window.

Save Copy As... Save the current window to different file without changing the associated file.

Print Window Print the current window to the default printer.

Close Close the current window (ask to save if unsaved).

Exit Close all windows and quit IDLE (ask to save unsaved windows).

Edit menu (Shell and Editor)

Undo Undo the last change to the current window. A maximum of 1000 changes may be undone.

Redo Redo the last undone change to the current window.

Cut Copy selection into the system-wide clipboard; then delete the selection.

Copy Copy selection into the system-wide clipboard.

Paste Insert contents of the system-wide clipboard into the current window.

The clipboard functions are also available in context menus.

Select All Select the entire contents of the current window.

Find... Open a search dialog with many options

Find Again Repeat the last search, if there is one.

Find Selection Search for the currently selected string, if there is one.

Find in Files... Open a file search dialog. Put results in a new output window.

Replace... Open a search-and-replace dialog.

Go to Line Move cursor to the line number requested and make that line visible.

Show Completions Open a scrollable list allowing selection of keywords and attributes. See Completions in the Tips sections below.

Expand Word Expand a prefix you have typed to match a full word in the same window; repeat to get a different expansion.

Show call tip After an unclosed parenthesis for a function, open a small window with function parameter hints.

Show surrounding parens Highlight the surrounding parenthesis.

Format menu (Editor window only)

Indent Region Shift selected lines right by the indent width (default 4 spaces).

Dedent Region Shift selected lines left by the indent width (default 4 spaces).

Comment Out Region Insert `##` in front of selected lines.

Uncomment Region Remove leading `#` or `##` from selected lines.

Tabify Region Turn *leading* stretches of spaces into tabs. (Note: We recommend using 4 space blocks to indent Python code.)

Untabify Region Turn *all* tabs into the correct number of spaces.

Toggle Tabs Open a dialog to switch between indenting with spaces and tabs.

New Indent Width Open a dialog to change indent width. The accepted default by the Python community is 4 spaces.

Format Paragraph Reformat the current blank-line-delimited paragraph in comment block or multiline string or selected line in a string. All lines in the paragraph will be formatted to less than N columns, where N defaults to 72.

Strip trailing whitespace Remove any space characters after the last non-space character of a line.

Run menu (Editor window only)

Python Shell Open or wake up the Python Shell window.

Check Module Check the syntax of the module currently open in the Editor window. If the module has not been saved IDLE will either prompt the user to save or autosave, as selected in the General tab of the Idle Settings dialog. If there is a syntax error, the approximate location is indicated in the Editor window.

Run Module Do Check Module (above). If no error, restart the shell to clean the environment, then execute the module. Output is displayed in the Shell window. Note that output requires use of `print` or `write`. When execution is complete, the Shell retains focus and displays a prompt. At this point, one may interactively explore the result of execution. This is similar to executing a file with `python -i file` at a command line.

Shell menu (Shell window only)

View Last Restart Scroll the shell window to the last Shell restart.

Restart Shell Restart the shell to clean the environment.

Interrupt Execution Stop a running program.

Debug menu (Shell window only)

Go to File/Line Look on the current line, with the cursor, and the line above for a filename and line number. If found, open the file if not already open, and show the line. Use this to view source lines referenced in an exception traceback and lines found by Find in Files. Also available in the context menu of the Shell window and Output windows.

Debugger (toggle) When activated, code entered in the Shell or run from an Editor will run under the debugger. In the Editor, breakpoints can be set with the context menu. This feature is still incomplete and somewhat experimental.

Stack Viewer Show the stack traceback of the last exception in a tree widget, with access to locals and globals.

Auto-open Stack Viewer Toggle automatically opening the stack viewer on an unhandled exception.

Options menu (Shell and Editor)

Configure IDLE Open a configuration dialog and change preferences for the following: fonts, indentation, keybindings, text color themes, startup windows and size, additional help sources, and extensions (see below). On OS X, open the configuration dialog by selecting Preferences in the application menu. To use a new built-in color theme (IDLE Dark) with older IDLEs, save it as a new custom theme.

Non-default user settings are saved in a .idlerc directory in the user's home directory. Problems caused by bad user configuration files are solved by editing or deleting one or more of the files in .idlerc.

Code Context (toggle)(Editor Window only) Open a pane at the top of the edit window which shows the block context of the code which has scrolled above the top of the window.

Window menu (Shell and Editor)

Zoom Height Toggles the window between normal size and maximum height. The initial size defaults to 40 lines by 80 chars unless changed on the General tab of the Configure IDLE dialog.

The rest of this menu lists the names of all open windows; select one to bring it to the foreground (deiconifying it if necessary).

Help menu (Shell and Editor)

About IDLE Display version, copyright, license, credits, and more.

IDLE Help Display a help file for IDLE detailing the menu options, basic editing and navigation, and other tips.

Python Docs Access local Python documentation, if installed, or start a web browser and open docs.python.org showing the latest Python documentation.

Turtle Demo Run the turtledemo module with example python code and turtle drawings.

Additional help sources may be added here with the Configure IDLE dialog under the General tab.

Context Menus

Open a context menu by right-clicking in a window (Control-click on OS X). Context menus have the standard clipboard functions also on the Edit menu.

Cut Copy selection into the system-wide clipboard; then delete the selection.

Copy Copy selection into the system-wide clipboard.

Paste Insert contents of the system-wide clipboard into the current window.

Editor windows also have breakpoint functions. Lines with a breakpoint set are specially marked. Breakpoints only have an effect when running under the debugger. Breakpoints for a file are saved in the user's .idlerc directory.

Set Breakpoint Set a breakpoint on the current line.

Clear Breakpoint Clear the breakpoint on that line.

Shell and Output windows have the following.

Go to file/line Same as in Debug menu.

24.6.2 Editing and navigation

In this section, <C> refers to the Control key on Windows and Unix and the Command key on Mac OSX.

- Backspace deletes to the left; Del deletes to the right
- C-Backspace delete word left; C-Del delete word to the right
- Arrow keys and Page Up/Page Down to move around
- C-LeftArrow and C-RightArrow moves by words
- Home/End go to begin/end of line
- C-Home/C-End go to begin/end of file
- Some useful Emacs bindings are inherited from Tcl/Tk:
 - C-a beginning of line
 - C-e end of line
 - C-k kill line (but doesn't put it in clipboard)
 - C-l center window around the insertion point
 - C-b go backward one character without deleting (usually you can also use the cursor key for this)
 - C-f go forward one character without deleting (usually you can also use the cursor key for this)
 - C-p go up one line (usually you can also use the cursor key for this)
 - C-d delete next character

Standard keybindings (like C-c to copy and C-v to paste) may work. Keybindings are selected in the Configure IDLE dialog.

Automatic indentation

After a block-opening statement, the next line is indented by 4 spaces (in the Python Shell window by one tab). After certain keywords (break, return etc.) the next line is dedented. In leading indentation, `Backspace` deletes up to 4 spaces if they are there. `Tab` inserts spaces (in the Python Shell window one tab), number depends on Indent width. Currently, tabs are restricted to four spaces due to Tcl/Tk limitations.

See also the indent/dedent region commands in the edit menu.

Completions

Completions are supplied for functions, classes, and attributes of classes, both built-in and user-defined. Completions are also provided for filenames.

The `AutoCompleteWindow` (ACW) will open after a predefined delay (default is two seconds) after a `<.>` or (in a string) an `os.sep` is typed. If after one of those characters (plus zero or more other characters) a tab is typed the ACW will open immediately if a possible continuation is found.

If there is only one possible completion for the characters entered, a `Tab` will supply that completion without opening the ACW.

`<Show Completions>` will force open a completions window, by default the `C-space` will open a completions window. In an empty string, this will contain the files in the current directory. On a blank line, it will contain the built-in and user-defined functions and classes in the current namespaces, plus any modules imported. If some characters have been entered, the ACW will attempt to be more specific.

If a string of characters is typed, the ACW selection will jump to the entry most closely matching those characters. Entering a `tab` will cause the longest non-ambiguous match to be entered in the Editor window or Shell. Two `tab` in a row will supply the current ACW selection, as will return or a double click. Cursor keys, Page Up/Down, mouse selection, and the scroll wheel all operate on the ACW.

`<<Hidden>` attributes can be accessed by typing the beginning of hidden name after a `<.>`, e.g. `<_>`. This allows access to modules with `__all__` set, or to class-private attributes.

Completions and the `<Expand Word>` facility can save a lot of typing!

Completions are currently limited to those in the namespaces. Names in an Editor window which are not via `__main__` and `sys.modules` will not be found. Run the module once with your imports to correct this situation. Note that IDLE itself places quite a few modules in `sys.modules`, so much can be found by default, e.g. the `re` module.

If you don't like the ACW popping up unbidden, simply make the delay longer or disable the extension.

Calltips

A calltip is shown when one types `(` after the name of an *accessible* function. A name expression may include dots and subscripts. A calltip remains until it is clicked, the cursor is moved out of the argument area, or `)` is typed. When the cursor is in the argument part of a definition, the menu or shortcut display a calltip.

A calltip consists of the function signature and the first line of the docstring. For builtins without an accessible signature, the calltip consists of all lines up the fifth line or the first blank line. These details may change.

The set of *accessible* functions depends on what modules have been imported into the user process, including those imported by Idle itself, and what definitions have been run, all since the last restart.

For example, restart the Shell and enter `itertools.count(`. A calltip appears because Idle imports `itertools` into the user process for its own use. (This could change.) Enter `turtle.write(` and nothing appears. Idle does not import `turtle`. The menu or shortcut do nothing either. Enter `import turtle` and then `turtle.write(` will work.

In an editor, import statements have no effect until one runs the file. One might want to run a file after writing the import statements at the top, or immediately run an existing file before editing.

Python Shell window

- C-c interrupts executing command
- C-d sends end-of-file; closes window if typed at a >>> prompt
- Alt-/ (Expand word) is also useful to reduce typing

Command history

- Alt-p retrieves previous command matching what you have typed. On OS X use C-p.
- Alt-n retrieves next. On OS X use C-n.
- Return while on any previous command retrieves that command

Text colors

Idle defaults to black on white text, but colors text with special meanings. For the shell, these are shell output, shell error, user output, and user error. For Python code, at the shell prompt or in an editor, these are keywords, builtin class and function names, names following `class` and `def`, strings, and comments. For any text window, these are the cursor (when present), found text (when possible), and selected text.

Text coloring is done in the background, so uncolored text is occasionally visible. To change the color scheme, use the Configure IDLE dialog Highlighting tab. The marking of debugger breakpoint lines in the editor and text in popups and dialogs is not user-configurable.

24.6.3 Startup and code execution

Upon startup with the `-s` option, IDLE will execute the file referenced by the environment variables `IDLESTARTUP` or `PYTHONSTARTUP`. IDLE first checks for `IDLESTARTUP`; if `IDLESTARTUP` is present the file referenced is run. If `IDLESTARTUP` is not present, IDLE checks for `PYTHONSTARTUP`. Files referenced by these environment variables are convenient places to store functions that are used frequently from the IDLE shell, or for executing import statements to import common modules.

In addition, Tk also loads a startup file if it is present. Note that the Tk file is loaded unconditionally. This additional file is `.Idle.py` and is looked for in the user's home directory. Statements in this file will be executed in the Tk namespace, so this file is not useful for importing functions to be used from IDLE's Python shell.

Command line usage

```
idle.py [-c command] [-d] [-e] [-h] [-i] [-r file] [-s] [-t title] [-] [arg] ...

-c command  run command in the shell window
-d          enable debugger and open shell window
-e          open editor window
-h          print help message with legal combinations and exit
-i          open shell window
-r file     run file in shell window
-s          run $IDLESTARTUP or $PYTHONSTARTUP first, in shell window
-t title    set title of shell window
-          run stdin in shell (- must be last option before args)
```

If there are arguments:

- If `-`, `-c`, or `-r` is used, all arguments are placed in `sys.argv[1:...]` and `sys.argv[0]` is set to `' '`, `'-c'`, or `'-r'`. No editor window is opened, even if that is the default set in the Options dialog.
- Otherwise, arguments are files opened for editing and `sys.argv` reflects the arguments passed to IDLE itself.

IDLE-console differences

As much as possible, the result of executing Python code with IDLE is the same as executing the same code in a console window. However, the different interface and operation occasionally affect visible results. For instance, `sys.modules` starts with more entries.

IDLE also replaces `sys.stdin`, `sys.stdout`, and `sys.stderr` with objects that get input from and send output to the Shell window. When this window has the focus, it controls the keyboard and screen. This is normally transparent, but functions that directly access the keyboard and screen will not work. If `sys` is reset with `reload(sys)`, IDLE's changes are lost and things like `input`, `raw_input`, and `print` will not work correctly.

With IDLE's Shell, one enters, edits, and recalls complete statements. Some consoles only work with a single physical line at a time. IDLE uses `exec` to run each statement. As a result, `'__builtins__'` is always defined for each statement.

Running without a subprocess

By default, IDLE executes user code in a separate subprocess via a socket, which uses the internal loopback interface. This connection is not externally visible and no data is sent to or received from the Internet. If firewall software complains anyway, you can ignore it.

If the attempt to make the socket connection fails, Idle will notify you. Such failures are sometimes transient, but if persistent, the problem may be either a firewall blocking the connection or misconfiguration of a particular system. Until the problem is fixed, one can run Idle with the `-n` command line switch.

If IDLE is started with the `-n` command line switch it will run in a single process and will not create the subprocess which runs the RPC Python execution server. This can be useful if Python cannot create the subprocess or the RPC socket interface on your platform. However, in this mode user code is not isolated from IDLE itself. Also, the environment is not restarted when Run/Run Module (F5) is selected. If your code has been modified, you must `reload()` the affected modules and re-import any specific items (e.g. `from foo import baz`) if the changes are to take effect. For these reasons, it is preferable to run IDLE with the default subprocess if at all possible.

버전 3.4부터 폐지.

24.6.4 Help and preferences

Additional help sources

IDLE includes a help menu entry called 《Python Docs》 that will open the extensive sources of help, including tutorials, available at docs.python.org. Selected URLs can be added or removed from the help menu at any time using the Configure IDLE dialog. See the IDLE help option in the help menu of IDLE for more information.

Setting preferences

The font preferences, highlighting, keys, and general preferences can be changed via Configure IDLE on the Option menu. Keys can be user defined; IDLE ships with four built-in key sets. In addition, a user can create a custom key set in the Configure IDLE dialog under the keys tab.

Extensions

IDLE contains an extension facility. Preferences for extensions can be changed with Configure Extensions. See the beginning of `config-extensions.def` in the `idlelib` directory for further information. The default extensions are currently:

- `FormatParagraph`
- `AutoExpand`
- `ZoomHeight`
- `ScriptBinding`
- `CallTips`
- `ParenMatch`
- `AutoComplete`
- `CodeContext`
- `RstripExtension`

24.7 Other Graphical User Interface Packages

Major cross-platform (Windows, Mac OS X, Unix-like) GUI toolkits are available for Python:

더 보기:

PyGTK is a set of bindings for the [GTK](#) widget set. It provides an object oriented interface that is slightly higher level than the C one. It comes with many more widgets than Tkinter provides, and has good Python-specific reference documentation. There are also bindings to [GNOME](#). An online [tutorial](#) is available.

PyQt PyQt is a **sip**-wrapped binding to the Qt toolkit. Qt is an extensive C++ GUI application development framework that is available for Unix, Windows and Mac OS X. **sip** is a tool for generating bindings for C++ libraries as Python classes, and is specifically designed for Python. The *PyQt3* bindings have a book, [GUI Programming with Python: QT Edition](#) by Boudewijn Rempt. The *PyQt4* bindings also have a book, [Rapid GUI Programming with Python and Qt](#), by Mark Summerfield.

wxPython wxPython is a cross-platform GUI toolkit for Python that is built around the popular [wxWidgets](#) (formerly wxWindows) C++ toolkit. It provides a native look and feel for applications on Windows, Mac OS X, and Unix systems by using each platform's native widgets where ever possible, (GTK+ on Unix-like systems). In addition to an extensive set of widgets, wxPython provides classes for online documentation and context sensitive help, printing, HTML viewing, low-level device context drawing, drag and drop, system clipboard access, an XML-based resource format and more, including an ever growing library of user-contributed modules. wxPython has a book, [wxPython in Action](#), by Noel Rappin and Robin Dunn.

PyGTK, PyQt, and wxPython, all have a modern look and feel and more widgets than Tkinter. In addition, there are many other GUI toolkits for Python, both cross-platform, and platform-specific. See the [GUI Programming](#) page in the Python Wiki for a much more complete list, and also for links to documents where the different GUI toolkits are compared.

The modules described in this chapter help you write software. For example, the *pydoc* module takes a module and generates documentation based on the module's contents. The *doctest* and *unittest* modules contains frameworks for writing unit tests that automatically exercise code and verify that the expected output is produced. **2to3** can translate Python 2.x source code into valid Python 3.x code.

The list of modules described in this chapter is:

25.1 *pydoc* — Documentation generator and online help system

버전 2.1에 추가.

Source code: [Lib/pydoc.py](#)

The *pydoc* module automatically generates documentation from Python modules. The documentation can be presented as pages of text on the console, served to a Web browser, or saved to HTML files.

For modules, classes, functions and methods, the displayed documentation is derived from the docstring (i.e. the `__doc__` attribute) of the object, and recursively of its documentable members. If there is no docstring, *pydoc* tries to obtain a description from the block of comment lines just above the definition of the class, function or method in the source file, or at the top of the module (see *inspect.getcomments()*).

The built-in function *help()* invokes the online help system in the interactive interpreter, which uses *pydoc* to generate its documentation as text on the console. The same text documentation can also be viewed from outside the Python interpreter by running **pydoc** as a script at the operating system's command prompt. For example, running

```
pydoc sys
```

at a shell prompt will display documentation on the *sys* module, in a style similar to the manual pages shown by the Unix **man** command. The argument to **pydoc** can be the name of a function, module, or package, or a dotted reference to a class, method, or function within a module or module in a package. If the argument to **pydoc** looks like a path (that is, it contains the path separator for your operating system, such as a slash in Unix), and refers to an existing Python source file, then documentation is produced for that file.

참고: In order to find objects and their documentation, `pydoc` imports the module(s) to be documented. Therefore, any code on module level will be executed on that occasion. Use an `if __name__ == '__main__':` guard to only execute code when a file is invoked as a script and not just imported.

When printing output to the console, **pydoc** attempts to paginate the output for easier reading. If the `PAGER` environment variable is set, **pydoc** will use its value as a pagination program.

Specifying a `-w` flag before the argument will cause HTML documentation to be written out to a file in the current directory, instead of displaying text on the console.

Specifying a `-k` flag before the argument will search the synopsis lines of all available modules for the keyword given as the argument, again in a manner similar to the Unix **man** command. The synopsis line of a module is the first line of its documentation string.

You can also use **pydoc** to start an HTTP server on the local machine that will serve documentation to visiting Web browsers. **pydoc -p 1234** will start a HTTP server on port 1234, allowing you to browse the documentation at `http://localhost:1234/` in your preferred Web browser. **pydoc -g** will start the server and additionally bring up a small *Tkinter*-based graphical interface to help you search for documentation pages.

When **pydoc** generates documentation, it uses the current environment and path to locate modules. Thus, invoking **pydoc spam** documents precisely the version of the module you would get if you started the Python interpreter and typed `import spam`.

Module docs for core modules are assumed to reside in <https://docs.python.org/library/>. This can be overridden by setting the `PYTHONDOCS` environment variable to a different URL or to a local directory containing the Library Reference Manual pages.

25.2 doctest — Test interactive Python examples

The `doctest` module searches for pieces of text that look like interactive Python sessions, and then executes those sessions to verify that they work exactly as shown. There are several common ways to use doctest:

- To check that a module's docstrings are up-to-date by verifying that all interactive examples still work as documented.
- To perform regression testing by verifying that interactive examples from a test file or a test object work as expected.
- To write tutorial documentation for a package, liberally illustrated with input-output examples. Depending on whether the examples or the expository text are emphasized, this has the flavor of 《literate testing》 or 《executable documentation》.

Here's a complete but small example module:

```
"""
This is the "example" module.

The example module supplies one function, factorial(). For example,

>>> factorial(5)
120
"""

def factorial(n):
    """Return the factorial of n, an exact integer >= 0.

    If the result is small enough to fit in an int, return an int.
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

Else return a long.

>>> [factorial(n) for n in range(6)]
[1, 1, 2, 6, 24, 120]
>>> [factorial(long(n)) for n in range(6)]
[1, 1, 2, 6, 24, 120]
>>> factorial(30)
2652528598121910586363084800000000L
>>> factorial(30L)
2652528598121910586363084800000000L
>>> factorial(-1)
Traceback (most recent call last):
...
ValueError: n must be >= 0

Factorials of floats are OK, but the float must be an exact integer:
>>> factorial(30.1)
Traceback (most recent call last):
...
ValueError: n must be exact integer
>>> factorial(30.0)
2652528598121910586363084800000000L

It must also not be ridiculously large:
>>> factorial(1e100)
Traceback (most recent call last):
...
OverflowError: n too large
"""

import math
if not n >= 0:
    raise ValueError("n must be >= 0")
if math.floor(n) != n:
    raise ValueError("n must be exact integer")
if n+1 == n: # catch a value like 1e300
    raise OverflowError("n too large")
result = 1
factor = 2
while factor <= n:
    result *= factor
    factor += 1
return result

if __name__ == "__main__":
    import doctest
    doctest.testmod()

```

If you run `example.py` directly from the command line, `doctest` works its magic:

```

$ python example.py
$

```

There's no output! That's normal, and it means all the examples worked. Pass `-v` to the script, and `doctest` prints a detailed log of what it's trying, and prints a summary at the end:

```
$ python example.py -v
Trying:
    factorial(5)
Expecting:
    120
ok
Trying:
    [factorial(n) for n in range(6)]
Expecting:
    [1, 1, 2, 6, 24, 120]
ok
Trying:
    [factorial(long(n)) for n in range(6)]
Expecting:
    [1, 1, 2, 6, 24, 120]
ok
```

And so on, eventually ending with:

```
Trying:
    factorial(1e100)
Expecting:
    Traceback (most recent call last):
      ...
    OverflowError: n too large
ok
2 items passed all tests:
  1 tests in __main__
  8 tests in __main__.factorial
9 tests in 2 items.
9 passed and 0 failed.
Test passed.
$
```

That's all you need to know to start making productive use of *doctest*! Jump in. The following sections provide full details. Note that there are many examples of doctests in the standard Python test suite and libraries. Especially useful examples can be found in the standard test file `Lib/test/test_doctest.py`.

25.2.1 Simple Usage: Checking Examples in Docstrings

The simplest way to start using doctest (but not necessarily the way you'll continue to do it) is to end each module *M* with:

```
if __name__ == "__main__":
    import doctest
    doctest.testmod()
```

doctest then examines docstrings in module *M*.

Running the module as a script causes the examples in the docstrings to get executed and verified:

```
python M.py
```

This won't display anything unless an example fails, in which case the failing example(s) and the cause(s) of the failure(s) are printed to stdout, and the final line of output is `***Test Failed*** N failures.`, where *N* is the number of examples that failed.

Run it with the `-v` switch instead:


```
python M.py -v
```

and a detailed report of all examples tried is printed to standard output, along with assorted summaries at the end.

You can force verbose mode by passing `verbose=True` to `testmod()`, or prohibit it by passing `verbose=False`. In either of those cases, `sys.argv` is not examined by `testmod()` (so passing `-v` or not has no effect).

Since Python 2.6, there is also a command line shortcut for running `testmod()`. You can instruct the Python interpreter to run the doctest module directly from the standard library and pass the module name(s) on the command line:

```
python -m doctest -v example.py
```

This will import `example.py` as a standalone module and run `testmod()` on it. Note that this may not work correctly if the file is part of a package and imports other submodules from that package.

For more information on `testmod()`, see section *Basic API*.

25.2.2 Simple Usage: Checking Examples in a Text File

Another simple application of doctest is testing interactive examples in a text file. This can be done with the `testfile()` function:

```
import doctest
doctest.testfile("example.txt")
```

That short script executes and verifies any interactive Python examples contained in the file `example.txt`. The file content is treated as if it were a single giant docstring; the file doesn't need to contain a Python program! For example, perhaps `example.txt` contains this:

```
The ``example`` module
=====

Using ``factorial``
-----

This is an example text file in reStructuredText format.  First import
``factorial`` from the ``example`` module:

    >>> from example import factorial

Now use it:

    >>> factorial(6)
    120
```

Running `doctest.testfile("example.txt")` then finds the error in this documentation:

```
File "./example.txt", line 14, in example.txt
Failed example:
    factorial(6)
Expected:
    120
Got:
    720
```

As with `testmod()`, `testfile()` won't display anything unless an example fails. If an example does fail, then the failing example(s) and the cause(s) of the failure(s) are printed to stdout, using the same format as `testmod()`.

By default, `testfile()` looks for files in the calling module's directory. See section [Basic API](#) for a description of the optional arguments that can be used to tell it to look for files in other locations.

Like `testmod()`, `testfile()`'s verbosity can be set with the `-v` command-line switch or with the optional keyword argument `verbose`.

Since Python 2.6, there is also a command line shortcut for running `testfile()`. You can instruct the Python interpreter to run the doctest module directly from the standard library and pass the file name(s) on the command line:

```
python -m doctest -v example.txt
```

Because the file name does not end with `.py`, `doctest` infers that it must be run with `testfile()`, not `testmod()`.

For more information on `testfile()`, see section [Basic API](#).

25.2.3 How It Works

This section examines in detail how doctest works: which docstrings it looks at, how it finds interactive examples, what execution context it uses, how it handles exceptions, and how option flags can be used to control its behavior. This is the information that you need to know to write doctest examples; for information about actually running doctest on these examples, see the following sections.

Which Docstrings Are Examined?

The module docstring, and all function, class and method docstrings are searched. Objects imported into the module are not searched.

In addition, if `M.__test__` exists and `is true`, it must be a dict, and each entry maps a (string) name to a function object, class object, or string. Function and class object docstrings found from `M.__test__` are searched, and strings are treated as if they were docstrings. In output, a key `K` in `M.__test__` appears with name

```
<name of M>.__test__.K
```

Any classes found are recursively searched similarly, to test docstrings in their contained methods and nested classes.

버전 2.4에서 변경: A `private name` concept is deprecated and no longer documented.

How are Docstring Examples Recognized?

In most cases a copy-and-paste of an interactive console session works fine, but doctest isn't trying to do an exact emulation of any specific Python shell.

```
>>> # comments are ignored
>>> x = 12
>>> x
12
>>> if x == 13:
...     print "yes"
... else:
...     print "no"
...     print "NO"
...     print "NO!!!"
...
no
NO
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
NO!!!
>>>
```

Any expected output must immediately follow the final '>>>' or '...' line containing the code, and the expected output (if any) extends to the next '>>>' or all-whitespace line.

The fine print:

- Expected output cannot contain an all-whitespace line, since such a line is taken to signal the end of expected output. If expected output does contain a blank line, put `<BLANKLINE>` in your doctest example each place a blank line is expected.

버전 2.4에 추가: `<BLANKLINE>` was added; there was no way to use expected output containing empty lines in previous versions.

- All hard tab characters are expanded to spaces, using 8-column tab stops. Tabs in output generated by the tested code are not modified. Because any hard tabs in the sample output *are* expanded, this means that if the code output includes hard tabs, the only way the doctest can pass is if the `NORMALIZE_WHITESPACE` option or *directive* is in effect. Alternatively, the test can be rewritten to capture the output and compare it to an expected value as part of the test. This handling of tabs in the source was arrived at through trial and error, and has proven to be the least error prone way of handling them. It is possible to use a different algorithm for handling tabs by writing a custom `DocTestParser` class.

버전 2.4에서 변경: Expanding tabs to spaces is new; previous versions tried to preserve hard tabs, with confusing results.

- Output to stdout is captured, but not output to stderr (exception tracebacks are captured via a different means).
- If you continue a line via backslashing in an interactive session, or for any other reason use a backslash, you should use a raw docstring, which will preserve your backslashes exactly as you type them:

```
>>> def f(x):
...     r'''Backslashes in a raw docstring: m\n'''
>>> print f.__doc__
Backslashes in a raw docstring: m\n
```

Otherwise, the backslash will be interpreted as part of the string. For example, the `\n` above would be interpreted as a newline character. Alternatively, you can double each backslash in the doctest version (and not use a raw string):

```
>>> def f(x):
...     '''Backslashes in a raw docstring: m\\n'''
>>> print f.__doc__
Backslashes in a raw docstring: m\n
```

- The starting column doesn't matter:

```
>>> assert "Easy!"
>>> import math
>>> math.floor(1.9)
1.0
```

and as many leading whitespace characters are stripped from the expected output as appeared in the initial '>>>' line that started the example.

What's the Execution Context?

By default, each time `doctest` finds a docstring to test, it uses a *shallow copy* of `M`'s globals, so that running tests doesn't change the module's real globals, and so that one test in `M` can't leave behind crumbs that accidentally allow another test to work. This means examples can freely use any names defined at top-level in `M`, and names defined earlier in the docstring being run. Examples cannot see names defined in other docstrings.

You can force use of your own dict as the execution context by passing `globs=your_dict` to `testmod()` or `testfile()` instead.

What About Exceptions?

No problem, provided that the traceback is the only output produced by the example: just paste in the traceback.¹ Since tracebacks contain details that are likely to change rapidly (for example, exact file paths and line numbers), this is one case where `doctest` works hard to be flexible in what it accepts.

Simple example:

```
>>> [1, 2, 3].remove(42)
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ValueError: list.remove(x): x not in list
```

That `doctest` succeeds if `ValueError` is raised, with the `list.remove(x): x not in list` detail as shown.

The expected output for an exception must start with a traceback header, which may be either of the following two lines, indented the same as the first line of the example:

```
Traceback (most recent call last):
Traceback (innermost last):
```

The traceback header is followed by an optional traceback stack, whose contents are ignored by `doctest`. The traceback stack is typically omitted, or copied verbatim from an interactive session.

The traceback stack is followed by the most interesting part: the line(s) containing the exception type and detail. This is usually the last line of a traceback, but can extend across multiple lines if the exception has a multi-line detail:

```
>>> raise ValueError('multi\n    line\ndetail')
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
ValueError: multi
    line
detail
```

The last three lines (starting with `ValueError`) are compared against the exception's type and detail, and the rest are ignored.

버전 2.4에서 변경: Previous versions were unable to handle multi-line exception details.

Best practice is to omit the traceback stack, unless it adds significant documentation value to the example. So the last example is probably better as:

```
>>> raise ValueError('multi\n    line\ndetail')
Traceback (most recent call last):
    ...
```

(다음 페이지에 계속)

¹ Examples containing both expected output and an exception are not supported. Trying to guess where one ends and the other begins is too error-prone, and that also makes for a confusing test.

(이전 페이지에서 계속)

```

ValueError: multi
    line
detail

```

Note that tracebacks are treated very specially. In particular, in the rewritten example, the use of `...` is independent of doctest's *ELLIPSIS* option. The ellipsis in that example could be left out, or could just as well be three (or three hundred) commas or digits, or an indented transcript of a Monty Python skit.

Some details you should read once, but won't need to remember:

- Doctest can't guess whether your expected output came from an exception traceback or from ordinary printing. So, e.g., an example that expects `ValueError: 42 is prime` will pass whether `ValueError` is actually raised or if the example merely prints that traceback text. In practice, ordinary output rarely begins with a traceback header line, so this doesn't create real problems.
- Each line of the traceback stack (if present) must be indented further than the first line of the example, *or* start with a non-alphanumeric character. The first line following the traceback header indented the same and starting with an alphanumeric is taken to be the start of the exception detail. Of course this does the right thing for genuine tracebacks.
- When the *IGNORE_EXCEPTION_DETAIL* doctest option is specified, everything following the leftmost colon and any module information in the exception name is ignored.
- The interactive shell omits the traceback header line for some *SyntaxErrors*. But doctest uses the traceback header line to distinguish exceptions from non-exceptions. So in the rare case where you need to test a *SyntaxError* that omits the traceback header, you will need to manually add the traceback header line to your test example.
- For some *SyntaxErrors*, Python displays the character position of the syntax error, using a `^` marker:

```

>>> 1 1
      File "<stdin>", line 1
        1 1
         ^
SyntaxError: invalid syntax

```

Since the lines showing the position of the error come before the exception type and detail, they are not checked by doctest. For example, the following test would pass, even though it puts the `^` marker in the wrong location:

```

>>> 1 1
      File "<stdin>", line 1
        1 1
         ^
SyntaxError: invalid syntax

```

Option Flags

A number of option flags control various aspects of doctest's behavior. Symbolic names for the flags are supplied as module constants, which can be bitwise ORed together and passed to various functions. The names can also be used in *doctest directives*.

The first group of options define test semantics, controlling aspects of how doctest decides whether actual output matches an example's expected output:

`doctest.DONT_ACCEPT_TRUE_FOR_1`

By default, if an expected output block contains just `1`, an actual output block containing just `1` or just `True` is considered to be a match, and similarly for `0` versus `False`. When *DONT_ACCEPT_TRUE_FOR_1* is specified,

neither substitution is allowed. The default behavior caters to that Python changed the return type of many functions from integer to boolean; doctests expecting 《little integer》 output still work in these cases. This option will probably go away, but not for several years.

doctest.**DONT_ACCEPT_BLANKLINE**

By default, if an expected output block contains a line containing only the string `<BLANKLINE>`, then that line will match a blank line in the actual output. Because a genuinely blank line delimits the expected output, this is the only way to communicate that a blank line is expected. When `DONT_ACCEPT_BLANKLINE` is specified, this substitution is not allowed.

doctest.**NORMALIZE_WHITESPACE**

When specified, all sequences of whitespace (blanks and newlines) are treated as equal. Any sequence of whitespace within the expected output will match any sequence of whitespace within the actual output. By default, whitespace must match exactly. `NORMALIZE_WHITESPACE` is especially useful when a line of expected output is very long, and you want to wrap it across multiple lines in your source.

doctest.**ELLIPSIS**

When specified, an ellipsis marker (`. . .`) in the expected output can match any substring in the actual output. This includes substrings that span line boundaries, and empty substrings, so it's best to keep usage of this simple. Complicated uses can lead to the same kinds of 《oops, it matched too much!》 surprises that `*` is prone to in regular expressions.

doctest.**IGNORE_EXCEPTION_DETAIL**

When specified, an example that expects an exception passes if an exception of the expected type is raised, even if the exception detail does not match. For example, an example expecting `ValueError: 42` will pass if the actual exception raised is `ValueError: 3*14`, but will fail, e.g., if `TypeError` is raised.

It will also ignore the module name used in Python 3 doctest reports. Hence both of these variations will work with the flag specified, regardless of whether the test is run under Python 2.7 or Python 3.2 (or later versions):

```
>>> raise CustomError('message')
Traceback (most recent call last):
CustomError: message

>>> raise CustomError('message')
Traceback (most recent call last):
my_module.CustomError: message
```

Note that `ELLIPSIS` can also be used to ignore the details of the exception message, but such a test may still fail based on whether or not the module details are printed as part of the exception name. Using `IGNORE_EXCEPTION_DETAIL` and the details from Python 2.3 is also the only clear way to write a doctest that doesn't care about the exception detail yet continues to pass under Python 2.3 or earlier (those releases do not support *doctest directives* and ignore them as irrelevant comments). For example:

```
>>> (1, 2)[3] = 'moo'
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
TypeError: object doesn't support item assignment
```

passes under Python 2.3 and later Python versions with the flag specified, even though the detail changed in Python 2.4 to say 《does not》 instead of 《doesn't》.

버전 2.7에서 변경: `IGNORE_EXCEPTION_DETAIL` now also ignores any information relating to the module containing the exception under test

doctest.**SKIP**

When specified, do not run the example at all. This can be useful in contexts where doctest examples serve as both documentation and test cases, and an example should be included for documentation purposes, but should not be

checked. E.g., the example's output might be random; or the example might depend on resources which would be unavailable to the test driver.

The SKIP flag can also be used for temporarily 《commenting out》 examples.

버전 2.5에 추가.

`doctest.COMPARISON_FLAGS`

A bitmask or'ing together all the comparison flags above.

The second group of options controls how test failures are reported:

`doctest.REPORT_UDIFF`

When specified, failures that involve multi-line expected and actual outputs are displayed using a unified diff.

`doctest.REPORT_CDIFF`

When specified, failures that involve multi-line expected and actual outputs will be displayed using a context diff.

`doctest.REPORT_NDIFF`

When specified, differences are computed by `diff.lib.Differ`, using the same algorithm as the popular `ndiff.py` utility. This is the only method that marks differences within lines as well as across lines. For example, if a line of expected output contains digit 1 where actual output contains letter l, a line is inserted with a caret marking the mismatching column positions.

`doctest.REPORT_ONLY_FIRST_FAILURE`

When specified, display the first failing example in each doctest, but suppress output for all remaining examples. This will prevent doctest from reporting correct examples that break because of earlier failures; but it might also hide incorrect examples that fail independently of the first failure. When `REPORT_ONLY_FIRST_FAILURE` is specified, the remaining examples are still run, and still count towards the total number of failures reported; only the output is suppressed.

`doctest.REPORTING_FLAGS`

A bitmask or'ing together all the reporting flags above.

버전 2.4에 추가: The constants `DONT_ACCEPT_BLANKLINE`, `NORMALIZE_WHITESPACE`, `ELLIPSIS`, `IGNORE_EXCEPTION_DETAIL`, `REPORT_UDIFF`, `REPORT_CDIFF`, `REPORT_NDIFF`, `REPORT_ONLY_FIRST_FAILURE`, `COMPARISON_FLAGS` and `REPORTING_FLAGS` were added.

There's also a way to register new option flag names, although this isn't useful unless you intend to extend `doctest` internals via subclassing:

`doctest.register_optionflag(name)`

Create a new option flag with a given name, and return the new flag's integer value. `register_optionflag()` can be used when subclassing `OutputChecker` or `DocTestRunner` to create new options that are supported by your subclasses. `register_optionflag()` should always be called using the following idiom:

```
MY_FLAG = register_optionflag('MY_FLAG')
```

버전 2.4에 추가.

Directives

Doctest directives may be used to modify the *option flags* for an individual example. Doctest directives are special Python comments following an example's source code:

```
directive          ::=  "#" "doctest:" directive_options
directive_options  ::=  directive_option ("," directive_option)*
directive_option   ::=  on_or_off directive_option_name
on_or_off          ::=  "+" \| "-"
directive_option_name ::=  "DONT_ACCEPT_BLANKLINE" \| "NORMALIZE_WHITESPACE" \| ...
```

Whitespace is not allowed between the + or - and the directive option name. The directive option name can be any of the option flag names explained above.

An example's doctest directives modify doctest's behavior for that single example. Use + to enable the named behavior, or - to disable it.

For example, this test passes:

```
>>> print range(20)
[0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
10, 11, 12, 13, 14, 15, 16, 17, 18, 19]
```

Without the directive it would fail, both because the actual output doesn't have two blanks before the single-digit list elements, and because the actual output is on a single line. This test also passes, and also requires a directive to do so:

```
>>> print range(20)
[0, 1, ..., 18, 19]
```

Multiple directives can be used on a single physical line, separated by commas:

```
>>> print range(20)
[0, 1, ..., 18, 19]
```

If multiple directive comments are used for a single example, then they are combined:

```
>>> print range(20)
...
[0, 1, ..., 18, 19]
```

As the previous example shows, you can add ... lines to your example containing only directives. This can be useful when an example is too long for a directive to comfortably fit on the same line:

```
>>> print range(5) + range(10,20) + range(30,40) + range(50,60)
...
[0, ..., 4, 10, ..., 19, 30, ..., 39, 50, ..., 59]
```

Note that since all options are disabled by default, and directives apply only to the example they appear in, enabling options (via + in a directive) is usually the only meaningful choice. However, option flags can also be passed to functions that run doctests, establishing different defaults. In such cases, disabling an option via - in a directive can be useful.

버전 2.4에 추가: Support for doctest directives was added.

Warnings

`doctest` is serious about requiring exact matches in expected output. If even a single character doesn't match, the test fails. This will probably surprise you a few times, as you learn exactly what Python does and doesn't guarantee about output. For example, when printing a dict, Python doesn't guarantee that the key-value pairs will be printed in any particular order, so a test like

```
>>> foo()
{"Hermione": "hippogryph", "Harry": "broomstick"}
```

is vulnerable! One workaround is to do

```
>>> foo() == {"Hermione": "hippogryph", "Harry": "broomstick"}
True
```

instead. Another is to do

```
>>> d = foo().items()
>>> d.sort()
>>> d
[('Harry', 'broomstick'), ('Hermione', 'hippogryph')]
```

There are others, but you get the idea.

Another bad idea is to print things that embed an object address, like

```
>>> id(1.0) # certain to fail some of the time
7948648
>>> class C: pass
>>> C() # the default repr() for instances embeds an address
<__main__.C instance at 0x00AC18F0>
```

The *ELLIPSIS* directive gives a nice approach for the last example:

```
>>> C()
<__main__.C instance at 0x...>
```

Floating-point numbers are also subject to small output variations across platforms, because Python defers to the platform C library for float formatting, and C libraries vary widely in quality here.

```
>>> 1./7 # risky
0.14285714285714285
>>> print 1./7 # safer
0.142857142857
>>> print round(1./7, 6) # much safer
0.142857
```

Numbers of the form $I/2.**J$ are safe across all platforms, and I often contrive doctest examples to produce numbers of that form:

```
>>> 3./4 # utterly safe
0.75
```

Simple fractions are also easier for people to understand, and that makes for better documentation.

25.2.4 Basic API

The functions `testmod()` and `testfile()` provide a simple interface to doctest that should be sufficient for most basic uses. For a less formal introduction to these two functions, see sections *Simple Usage: Checking Examples in Docstrings* and *Simple Usage: Checking Examples in a Text File*.

`doctest.testfile(filename[, module_relative[, name[, package[, globs[, verbose[, report[, optionflags[, extraglobs[, raise_on_error[, parser[, encoding]]]]]]]]])`

All arguments except `filename` are optional, and should be specified in keyword form.

Test examples in the file named `filename`. Return `(failure_count, test_count)`.

Optional argument `module_relative` specifies how the filename should be interpreted:

- If `module_relative` is `True` (the default), then `filename` specifies an OS-independent module-relative path. By default, this path is relative to the calling module's directory; but if the `package` argument is specified, then it is relative to that package. To ensure OS-independence, `filename` should use `/` characters to separate path segments, and may not be an absolute path (i.e., it may not begin with `/`).
- If `module_relative` is `False`, then `filename` specifies an OS-specific path. The path may be absolute or relative; relative paths are resolved with respect to the current working directory.

Optional argument `name` gives the name of the test; by default, or if `None`, `os.path.basename(filename)` is used.

Optional argument `package` is a Python package or the name of a Python package whose directory should be used as the base directory for a module-relative filename. If no package is specified, then the calling module's directory is used as the base directory for module-relative filenames. It is an error to specify `package` if `module_relative` is `False`.

Optional argument `globs` gives a dict to be used as the globals when executing examples. A new shallow copy of this dict is created for the doctest, so its examples start with a clean slate. By default, or if `None`, a new empty dict is used.

Optional argument `extraglobs` gives a dict merged into the globals used to execute examples. This works like `dict.update()`: if `globs` and `extraglobs` have a common key, the associated value in `extraglobs` appears in the combined dict. By default, or if `None`, no extra globals are used. This is an advanced feature that allows parameterization of doctests. For example, a doctest can be written for a base class, using a generic name for the class, then reused to test any number of subclasses by passing an `extraglobs` dict mapping the generic name to the subclass to be tested.

Optional argument `verbose` prints lots of stuff if true, and prints only failures if false; by default, or if `None`, it's true if and only if `'-v'` is in `sys.argv`.

Optional argument `report` prints a summary at the end when true, else prints nothing at the end. In verbose mode, the summary is detailed, else the summary is very brief (in fact, empty if all tests passed).

Optional argument `optionflags` or `'s'` together option flags. See section *Option Flags*.

Optional argument `raise_on_error` defaults to false. If true, an exception is raised upon the first failure or unexpected exception in an example. This allows failures to be post-mortem debugged. Default behavior is to continue running examples.

Optional argument `parser` specifies a `DocTestParser` (or subclass) that should be used to extract tests from the files. It defaults to a normal parser (i.e., `DocTestParser()`).

Optional argument `encoding` specifies an encoding that should be used to convert the file to unicode.

버전 2.4에 추가.

버전 2.5에서 변경: The parameter `encoding` was added.

```
doctest.testmod([m][, name][, globs][, verbose][, report][, optionflags][, extraglobs][, raise_on_error][,
                exclude_empty])
```

All arguments are optional, and all except for *m* should be specified in keyword form.

Test examples in docstrings in functions and classes reachable from module *m* (or module `__main__` if *m* is not supplied or is `None`), starting with `m.__doc__`.

Also test examples reachable from dict `m.__test__`, if it exists and is not `None`. `m.__test__` maps names (strings) to functions, classes and strings; function and class docstrings are searched for examples; strings are searched directly, as if they were docstrings.

Only docstrings attached to objects belonging to module *m* are searched.

Return (failure_count, test_count).

Optional argument *name* gives the name of the module; by default, or if `None`, `m.__name__` is used.

Optional argument *exclude_empty* defaults to `false`. If `true`, objects for which no doctests are found are excluded from consideration. The default is a backward compatibility hack, so that code still using `doctest.master.summarize()` in conjunction with `testmod()` continues to get output for objects with no tests. The *exclude_empty* argument to the newer `DocTestFinder` constructor defaults to `true`.

Optional arguments *extraglobs*, *verbose*, *report*, *optionflags*, *raise_on_error*, and *globs* are the same as for function `testfile()` above, except that *globs* defaults to `m.__dict__`.

버전 2.3에서 변경: The parameter *optionflags* was added.

버전 2.4에서 변경: The parameters *extraglobs*, *raise_on_error* and *exclude_empty* were added.

버전 2.5에서 변경: The optional argument *isprivate*, deprecated in 2.4, was removed.

```
doctest.run_docstring_examples(f, globs[, verbose][, name][, compileflags][, optionflags])
```

Test examples associated with object *f*; for example, *f* may be a string, a module, a function, or a class object.

A shallow copy of dictionary argument *globs* is used for the execution context.

Optional argument *name* is used in failure messages, and defaults to `"NoName"`.

If optional argument *verbose* is `true`, output is generated even if there are no failures. By default, output is generated only in case of an example failure.

Optional argument *compileflags* gives the set of flags that should be used by the Python compiler when running the examples. By default, or if `None`, flags are deduced corresponding to the set of future features found in *globs*.

Optional argument *optionflags* works as for function `testfile()` above.

25.2.5 unittest API

As your collection of doctest'ed modules grows, you'll want a way to run all their doctests systematically. Prior to Python 2.4, `doctest` had a barely documented `Tester` class that supplied a rudimentary way to combine doctests from multiple modules. `Tester` was feeble, and in practice most serious Python testing frameworks build on the `unittest` module, which supplies many flexible ways to combine tests from multiple sources. So, in Python 2.4, `doctest`'s `Tester` class is deprecated, and `doctest` provides two functions that can be used to create `unittest` test suites from modules and text files containing doctests. To integrate with `unittest` test discovery, include a `load_tests()` function in your test module:

```
import unittest
import doctest
import my_module_with_doctests

def load_tests(loader, tests, ignore):
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
tests.addTests(doctest.DocTestSuite(my_module_with_doctests))
return tests
```

There are two main functions for creating `unittest.TestSuite` instances from text files and modules with doctests:

`doctest.DocFileSuite(*paths, [module_relative][, package][, setUp][, tearDown][, globs][, optionflags][, parser][, encoding])`

Convert doctest tests from one or more text files to a `unittest.TestSuite`.

The returned `unittest.TestSuite` is to be run by the unittest framework and runs the interactive examples in each file. If an example in any file fails, then the synthesized unit test fails, and a `failureException` exception is raised showing the name of the file containing the test and a (sometimes approximate) line number.

Pass one or more paths (as strings) to text files to be examined.

Options may be provided as keyword arguments:

Optional argument `module_relative` specifies how the filenames in `paths` should be interpreted:

- If `module_relative` is `True` (the default), then each filename in `paths` specifies an OS-independent module-relative path. By default, this path is relative to the calling module's directory; but if the `package` argument is specified, then it is relative to that package. To ensure OS-independence, each filename should use `/` characters to separate path segments, and may not be an absolute path (i.e., it may not begin with `/`).
- If `module_relative` is `False`, then each filename in `paths` specifies an OS-specific path. The path may be absolute or relative; relative paths are resolved with respect to the current working directory.

Optional argument `package` is a Python package or the name of a Python package whose directory should be used as the base directory for module-relative filenames in `paths`. If no package is specified, then the calling module's directory is used as the base directory for module-relative filenames. It is an error to specify `package` if `module_relative` is `False`.

Optional argument `setUp` specifies a set-up function for the test suite. This is called before running the tests in each file. The `setUp` function will be passed a `DocTest` object. The `setUp` function can access the test globals as the `globs` attribute of the test passed.

Optional argument `tearDown` specifies a tear-down function for the test suite. This is called after running the tests in each file. The `tearDown` function will be passed a `DocTest` object. The `setUp` function can access the test globals as the `globs` attribute of the test passed.

Optional argument `globs` is a dictionary containing the initial global variables for the tests. A new copy of this dictionary is created for each test. By default, `globs` is a new empty dictionary.

Optional argument `optionflags` specifies the default doctest options for the tests, created by or-ing together individual option flags. See section [Option Flags](#). See function `set_unittest_reportflags()` below for a better way to set reporting options.

Optional argument `parser` specifies a `DocTestParser` (or subclass) that should be used to extract tests from the files. It defaults to a normal parser (i.e., `DocTestParser()`).

Optional argument `encoding` specifies an encoding that should be used to convert the file to unicode.

버전 2.4에 추가.

버전 2.5에서 변경: The global `__file__` was added to the globals provided to doctests loaded from a text file using `DocFileSuite()`.

버전 2.5에서 변경: The parameter `encoding` was added.

참고: Unlike `testmod()` and `DocTestFinder`, this function raises a `ValueError` if `module` contains no docstrings. You can prevent this error by passing a `DocTestFinder` instance as the `test_finder` argument with its `exclude_empty` keyword argument set to `False`:

```
>>> finder = doctest.DocTestFinder(exclude_empty=False)
>>> suite = doctest.DocTestSuite(test_finder=finder)
```

`doctest.DocTestSuite([module][, globs][, extraglobs][, test_finder][, setUp][, tearDown][, checker])`

Convert doctest tests for a module to a `unittest.TestSuite`.

The returned `unittest.TestSuite` is to be run by the unittest framework and runs each doctest in the module. If any of the doctests fail, then the synthesized unit test fails, and a `failureException` exception is raised showing the name of the file containing the test and a (sometimes approximate) line number.

Optional argument `module` provides the module to be tested. It can be a module object or a (possibly dotted) module name. If not specified, the module calling this function is used.

Optional argument `globs` is a dictionary containing the initial global variables for the tests. A new copy of this dictionary is created for each test. By default, `globs` is a new empty dictionary.

Optional argument `extraglobs` specifies an extra set of global variables, which is merged into `globs`. By default, no extra globals are used.

Optional argument `test_finder` is the `DocTestFinder` object (or a drop-in replacement) that is used to extract doctests from the module.

Optional arguments `setUp`, `tearDown`, and `optionflags` are the same as for function `DocFileSuite()` above.

버전 2.3에 추가.

버전 2.4에서 변경: The parameters `globs`, `extraglobs`, `test_finder`, `setUp`, `tearDown`, and `optionflags` were added; this function now uses the same search technique as `testmod()`.

Under the covers, `DocTestSuite()` creates a `unittest.TestSuite` out of `doctest.DocTestCase` instances, and `DocTestCase` is a subclass of `unittest.TestCase`. `DocTestCase` isn't documented here (it's an internal detail), but studying its code can answer questions about the exact details of `unittest` integration.

Similarly, `DocFileSuite()` creates a `unittest.TestSuite` out of `doctest.DocFileCase` instances, and `DocFileCase` is a subclass of `DocTestCase`.

So both ways of creating a `unittest.TestSuite` run instances of `DocTestCase`. This is important for a subtle reason: when you run `doctest` functions yourself, you can control the `doctest` options in use directly, by passing option flags to `doctest` functions. However, if you're writing a `unittest` framework, `unittest` ultimately controls when and how tests get run. The framework author typically wants to control `doctest` reporting options (perhaps, e.g., specified by command line options), but there's no way to pass options through `unittest` to `doctest` test runners.

For this reason, `doctest` also supports a notion of `doctest` reporting flags specific to `unittest` support, via this function:

`doctest.set_unittest_reportflags(flags)`

Set the `doctest` reporting flags to use.

Argument `flags` or's together option flags. See section [Option Flags](#). Only 《reporting flags》 can be used.

This is a module-global setting, and affects all future doctests run by module `unittest`: the `runTest()` method of `DocTestCase` looks at the option flags specified for the test case when the `DocTestCase` instance was constructed. If no reporting flags were specified (which is the typical and expected case), `doctest's` `unittest` reporting flags are bitwise ORed into the option flags, and the option flags so augmented are passed to the `DocTestRunner` instance created to run the doctest. If any reporting flags were specified when the `DocTestCase` instance was constructed, `doctest's` `unittest` reporting flags are ignored.

The value of the `unittest` reporting flags in effect before the function was called is returned by the function.

버전 2.4에 추가.

25.2.6 Advanced API

The basic API is a simple wrapper that's intended to make doctest easy to use. It is fairly flexible, and should meet most users' needs; however, if you require more fine-grained control over testing, or wish to extend doctest's capabilities, then you should use the advanced API.


The advanced API revolves around two container classes, which are used to store the interactive examples extracted from doctest cases:

- *Example*: A single Python *statement*, paired with its expected output.
- *DocTest*: A collection of *Examples*, typically extracted from a single docstring or text file.

Additional processing classes are defined to find, parse, and run, and check doctest examples:

- *DocTestFinder*: Finds all docstrings in a given module, and uses a *DocTestParser* to create a *DocTest* from every docstring that contains interactive examples.
- *DocTestParser*: Creates a *DocTest* object from a string (such as an object's docstring).
- *DocTestRunner*: Executes the examples in a *DocTest*, and uses an *OutputChecker* to verify their output.
- *OutputChecker*: Compares the actual output from a doctest example with the expected output, and decides whether they match.

The relationships among these processing classes are summarized in the following diagram:



DocTest Objects

class `doctest.DocTest` (*examples, globs, name, filename, lineno, docstring*)

A collection of doctest examples that should be run in a single namespace. The constructor arguments are used to initialize the attributes of the same names.

버전 2.4에 추가.

DocTest defines the following attributes. They are initialized by the constructor, and should not be modified directly.

examples

A list of *Example* objects encoding the individual interactive Python examples that should be run by this test.

globs

The namespace (aka globals) that the examples should be run in. This is a dictionary mapping names to values. Any changes to the namespace made by the examples (such as binding new variables) will be reflected in *globs* after the test is run.

name

A string name identifying the *DocTest*. Typically, this is the name of the object or file that the test was extracted from.

filename

The name of the file that this *DocTest* was extracted from; or *None* if the filename is unknown, or if the *DocTest* was not extracted from a file.

lineno

The line number within *filename* where this *DocTest* begins, or *None* if the line number is unavailable. This line number is zero-based with respect to the beginning of the file.

docstring

The string that the test was extracted from, or *None* if the string is unavailable, or if the test was not extracted from a string.

Example Objects

class `doctest.Example` (*source*, *want*[, *exc_msg*][, *lineno*][, *indent*][, *options*])

A single interactive example, consisting of a Python statement and its expected output. The constructor arguments are used to initialize the attributes of the same names.

버전 2.4에 추가.

Example defines the following attributes. They are initialized by the constructor, and should not be modified directly.

source

A string containing the example's source code. This source code consists of a single Python statement, and always ends with a newline; the constructor adds a newline when necessary.

want

The expected output from running the example's source code (either from stdout, or a traceback in case of exception). *want* ends with a newline unless no output is expected, in which case it's an empty string. The constructor adds a newline when necessary.

exc_msg

The exception message generated by the example, if the example is expected to generate an exception; or *None* if it is not expected to generate an exception. This exception message is compared against the return value of `traceback.format_exception_only()`. *exc_msg* ends with a newline unless it's *None*. The constructor adds a newline if needed.

lineno

The line number within the string containing this example where the example begins. This line number is zero-based with respect to the beginning of the containing string.

indent

The example's indentation in the containing string, i.e., the number of space characters that precede the example's first prompt.

options

A dictionary mapping from option flags to *True* or *False*, which is used to override default options for this example. Any option flags not contained in this dictionary are left at their default value (as specified by the *DocTestRunner*'s *optionflags*). By default, no options are set.

DocTestFinder objects

class `doctest.DocTestFinder` (*[verbose][, parser][, recurse][, exclude_empty]*)

A processing class used to extract the *DocTests* that are relevant to a given object, from its docstring and the docstrings of its contained objects. *DocTests* can currently be extracted from the following object types: modules, functions, classes, methods, staticmethods, classmethods, and properties.

The optional argument *verbose* can be used to display the objects searched by the finder. It defaults to `False` (no output).

The optional argument *parser* specifies the *DocTestParser* object (or a drop-in replacement) that is used to extract doctests from docstrings.

If the optional argument *recurse* is false, then *DocTestFinder.find()* will only examine the given object, and not any contained objects.

If the optional argument *exclude_empty* is false, then *DocTestFinder.find()* will include tests for objects with empty docstrings.

버전 2.4에 추가.

DocTestFinder defines the following method:

find (*obj[, name][, module][, globs][, extraglobs]*)

Return a list of the *DocTests* that are defined by *obj*'s docstring, or by any of its contained objects' docstrings.

The optional argument *name* specifies the object's name; this name will be used to construct names for the returned *DocTests*. If *name* is not specified, then *obj.__name__* is used.

The optional parameter *module* is the module that contains the given object. If the module is not specified or is `None`, then the test finder will attempt to automatically determine the correct module. The object's module is used:

- As a default namespace, if *globs* is not specified.
- To prevent the *DocTestFinder* from extracting *DocTests* from objects that are imported from other modules. (Contained objects with modules other than *module* are ignored.)
- To find the name of the file containing the object.
- To help find the line number of the object within its file.

If *module* is `False`, no attempt to find the module will be made. This is obscure, of use mostly in testing *doctest* itself: if *module* is `False`, or is `None` but cannot be found automatically, then all objects are considered to belong to the (non-existent) module, so all contained objects will (recursively) be searched for doctests.

The globals for each *DocTest* is formed by combining *globs* and *extraglobs* (bindings in *extraglobs* override bindings in *globs*). A new shallow copy of the globals dictionary is created for each *DocTest*. If *globs* is not specified, then it defaults to the module's `__dict__`, if specified, or `{}` otherwise. If *extraglobs* is not specified, then it defaults to `{}`.

DocTestParser objects

class doctest.DocTestParser

A processing class used to extract interactive examples from a string, and use them to create a *DocTest* object.

버전 2.4에 추가.

DocTestParser defines the following methods:

get_doctest (*string*, *globs*, *name*, *filename*, *lineno*)

Extract all doctest examples from the given string, and collect them into a *DocTest* object.

globs, *name*, *filename*, and *lineno* are attributes for the new *DocTest* object. See the documentation for *DocTest* for more information.

get_examples (*string*[, *name*])

Extract all doctest examples from the given string, and return them as a list of *Example* objects. Line numbers are 0-based. The optional argument *name* is a name identifying this string, and is only used for error messages.

parse (*string*[, *name*])

Divide the given string into examples and intervening text, and return them as a list of alternating *Examples* and strings. Line numbers for the *Examples* are 0-based. The optional argument *name* is a name identifying this string, and is only used for error messages.

DocTestRunner objects

class doctest.DocTestRunner ([*checker*][, *verbose*][, *optionflags*])

A processing class used to execute and verify the interactive examples in a *DocTest*.

The comparison between expected outputs and actual outputs is done by an *OutputChecker*. This comparison may be customized with a number of option flags; see section *Option Flags* for more information. If the option flags are insufficient, then the comparison may also be customized by passing a subclass of *OutputChecker* to the constructor.

The test runner's display output can be controlled in two ways. First, an output function can be passed to *TestRunner.run()*; this function will be called with strings that should be displayed. It defaults to `sys.stdout.write`. If capturing the output is not sufficient, then the display output can be also customized by subclassing *DocTestRunner*, and overriding the methods *report_start()*, *report_success()*, *report_unexpected_exception()*, and *report_failure()*.

The optional keyword argument *checker* specifies the *OutputChecker* object (or drop-in replacement) that should be used to compare the expected outputs to the actual outputs of doctest examples.

The optional keyword argument *verbose* controls the *DocTestRunner*'s verbosity. If *verbose* is `True`, then information is printed about each example, as it is run. If *verbose* is `False`, then only failures are printed. If *verbose* is unspecified, or `None`, then verbose output is used iff the command-line switch `-v` is used.

The optional keyword argument *optionflags* can be used to control how the test runner compares expected output to actual output, and how it displays failures. For more information, see section *Option Flags*.

버전 2.4에 추가.

DocTestParser defines the following methods:

report_start (*out*, *test*, *example*)

Report that the test runner is about to process the given example. This method is provided to allow subclasses of *DocTestRunner* to customize their output; it should not be called directly.

example is the example about to be processed. *test* is the test containing *example*. *out* is the output function that was passed to *DocTestRunner.run()*.

report_success (*out, test, example, got*)

Report that the given example ran successfully. This method is provided to allow subclasses of *DocTestRunner* to customize their output; it should not be called directly.

example is the example about to be processed. *got* is the actual output from the example. *test* is the test containing *example*. *out* is the output function that was passed to *DocTestRunner.run()*.

report_failure (*out, test, example, got*)

Report that the given example failed. This method is provided to allow subclasses of *DocTestRunner* to customize their output; it should not be called directly.

example is the example about to be processed. *got* is the actual output from the example. *test* is the test containing *example*. *out* is the output function that was passed to *DocTestRunner.run()*.

report_unexpected_exception (*out, test, example, exc_info*)

Report that the given example raised an unexpected exception. This method is provided to allow subclasses of *DocTestRunner* to customize their output; it should not be called directly.

example is the example about to be processed. *exc_info* is a tuple containing information about the unexpected exception (as returned by *sys.exc_info()*). *test* is the test containing *example*. *out* is the output function that was passed to *DocTestRunner.run()*.

run (*test[, compileflags[, out[, clear_globs]*])

Run the examples in *test* (a *DocTest* object), and display the results using the writer function *out*.

The examples are run in the namespace *test.globs*. If *clear_globs* is true (the default), then this namespace will be cleared after the test runs, to help with garbage collection. If you would like to examine the namespace after the test completes, then use *clear_globs=False*.

compileflags gives the set of flags that should be used by the Python compiler when running the examples. If not specified, then it will default to the set of future-import flags that apply to *globs*.

The output of each example is checked using the *DocTestRunner*'s output checker, and the results are formatted by the *DocTestRunner.report_**() methods.

summarize (*[verbose]*)

Print a summary of all the test cases that have been run by this *DocTestRunner*, and return a *named tuple* *TestResults(failed, attempted)*.

The optional *verbose* argument controls how detailed the summary is. If the verbosity is not specified, then the *DocTestRunner*'s verbosity is used.

버전 2.6에서 변경: Use a named tuple.

OutputChecker objects

class *doctest.OutputChecker*

A class used to check the whether the actual output from a doctest example matches the expected output. *OutputChecker* defines two methods: *check_output()*, which compares a given pair of outputs, and returns true if they match; and *output_difference()*, which returns a string describing the differences between two outputs.

버전 2.4에 추가.

OutputChecker defines the following methods:

check_output (*want, got, optionflags*)

Return True iff the actual output from an example (*got*) matches the expected output (*want*). These strings are always considered to match if they are identical; but depending on what option flags the test runner is using, several non-exact match types are also possible. See section *Option Flags* for more information about option flags.

output_difference (*example*, *got*, *optionflags*)

Return a string describing the differences between the expected output for a given example (*example*) and the actual output (*got*). *optionflags* is the set of option flags used to compare *want* and *got*.

25.2.7 Debugging

Doctest provides several mechanisms for debugging doctest examples:

- Several functions convert doctests to executable Python programs, which can be run under the Python debugger, `pdb`.
- The `DebugRunner` class is a subclass of `DocTestRunner` that raises an exception for the first failing example, containing information about that example. This information can be used to perform post-mortem debugging on the example.
- The `unittest` cases generated by `DocTestSuite()` support the `debug()` method defined by `unittest.TestCase`.
- You can add a call to `pdb.set_trace()` in a doctest example, and you'll drop into the Python debugger when that line is executed. Then you can inspect current values of variables, and so on. For example, suppose `a.py` contains just this module docstring:

```
"""
>>> def f(x):
...     g(x*2)
>>> def g(x):
...     print x+3
...     import pdb; pdb.set_trace()
>>> f(3)
9
"""
```

Then an interactive Python session may look like this:

```
>>> import a, doctest
>>> doctest.testmod(a)
--Return--
> <doctest a[1]>(3)g()->None
-> import pdb; pdb.set_trace()
(Pdb) list
1      def g(x):
2          print x+3
3  ->      import pdb; pdb.set_trace()
[EOF]
(Pdb) print x
6
(Pdb) step
--Return--
> <doctest a[0]>(2)f()->None
-> g(x*2)
(Pdb) list
1      def f(x):
2  ->      g(x*2)
[EOF]
(Pdb) print x
3
(Pdb) step
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
--Return--
> <doctest a[2]>(1)?()->None
-> f(3)
(Pdb) cont
(0, 3)
>>>
```

버전 2.4에서 변경: The ability to use `pdb.set_trace()` usefully inside doctests was added.

Functions that convert doctests to Python code, and possibly run the synthesized code under the debugger:

`doctest.script_from_examples(s)`

Convert text with examples to a script.

Argument *s* is a string containing doctest examples. The string is converted to a Python script, where doctest examples in *s* are converted to regular code, and everything else is converted to Python comments. The generated script is returned as a string. For example,

```
import doctest
print doctest.script_from_examples(r"""
    Set x and y to 1 and 2.
    >>> x, y = 1, 2

    Print their sum:
    >>> print x+y
    3
    """)
```

displays:

```
# Set x and y to 1 and 2.
x, y = 1, 2
#
# Print their sum:
print x+y
# Expected:
## 3
```

This function is used internally by other functions (see below), but can also be useful when you want to transform an interactive Python session into a Python script.

버전 2.4에 추가.

`doctest.testsource(module, name)`

Convert the doctest for an object to a script.

Argument *module* is a module object, or dotted name of a module, containing the object whose doctests are of interest. Argument *name* is the name (within the module) of the object with the doctests of interest. The result is a string, containing the object's docstring converted to a Python script, as described for `script_from_examples()` above. For example, if module `a.py` contains a top-level function `f()`, then

```
import a, doctest
print doctest.testsource(a, "a.f")
```

prints a script version of function `f()`'s docstring, with doctests converted to code, and the rest placed in comments.

버전 2.3에 추가.

`doctest.debug(module, name[, pm])`

Debug the doctests for an object.

The *module* and *name* arguments are the same as for function `testsource()` above. The synthesized Python script for the named object's docstring is written to a temporary file, and then that file is run under the control of the Python debugger, `pdb`.

A shallow copy of `module.__dict__` is used for both local and global execution context.

Optional argument *pm* controls whether post-mortem debugging is used. If *pm* has a true value, the script file is run directly, and the debugger gets involved only if the script terminates via raising an unhandled exception. If it does, then post-mortem debugging is invoked, via `pdb.post_mortem()`, passing the traceback object from the unhandled exception. If *pm* is not specified, or is false, the script is run under the debugger from the start, via passing an appropriate `execfile()` call to `pdb.run()`.

버전 2.3에 추가.

버전 2.4에서 변경: The *pm* argument was added.

`doctest.debug_src(src[, pm][, globs])`

Debug the doctests in a string.

This is like function `debug()` above, except that a string containing doctest examples is specified directly, via the *src* argument.

Optional argument *pm* has the same meaning as in function `debug()` above.

Optional argument *globs* gives a dictionary to use as both local and global execution context. If not specified, or None, an empty dictionary is used. If specified, a shallow copy of the dictionary is used.

버전 2.4에 추가.

The `DebugRunner` class, and the special exceptions it may raise, are of most interest to testing framework authors, and will only be sketched here. See the source code, and especially `DebugRunner`'s docstring (which is a doctest!) for more details:

class `doctest.DebugRunner([checker][, verbose][, optionflags])`

A subclass of `DocTestRunner` that raises an exception as soon as a failure is encountered. If an unexpected exception occurs, an `UnexpectedException` exception is raised, containing the test, the example, and the original exception. If the output doesn't match, then a `DocTestFailure` exception is raised, containing the test, the example, and the actual output.

For information about the constructor parameters and methods, see the documentation for `DocTestRunner` in section *Advanced API*.

There are two exceptions that may be raised by `DebugRunner` instances:

exception `doctest.DocTestFailure(test, example, got)`

An exception raised by `DocTestRunner` to signal that a doctest example's actual output did not match its expected output. The constructor arguments are used to initialize the attributes of the same names.

`DocTestFailure` defines the following attributes:

`DocTestFailure.test`

The `DocTest` object that was being run when the example failed.

`DocTestFailure.example`

The `Example` that failed.

`DocTestFailure.got`

The example's actual output.

exception `doctest.UnexpectedException` (*test*, *example*, *exc_info*)

An exception raised by `DocTestRunner` to signal that a doctest example raised an unexpected exception. The constructor arguments are used to initialize the attributes of the same names.

`UnexpectedException` defines the following attributes:

`UnexpectedException.test`

The `DocTest` object that was being run when the example failed.

`UnexpectedException.example`

The `Example` that failed.

`UnexpectedException.exc_info`

A tuple containing information about the unexpected exception, as returned by `sys.exc_info()`.

25.2.8 Soapbox

As mentioned in the introduction, `doctest` has grown to have three primary uses:

1. Checking examples in docstrings.
2. Regression testing.
3. Executable documentation / literate testing.

These uses have different requirements, and it is important to distinguish them. In particular, filling your docstrings with obscure test cases makes for bad documentation.

When writing a docstring, choose docstring examples with care. There's an art to this that needs to be learned—it may not be natural at first. Examples should add genuine value to the documentation. A good example can often be worth many words. If done with care, the examples will be invaluable for your users, and will pay back the time it takes to collect them many times over as the years go by and things change. I'm still amazed at how often one of my `doctest` examples stops working after a 《harmless》 change.

Doctest also makes an excellent tool for regression testing, especially if you don't skimp on explanatory text. By interleaving prose and examples, it becomes much easier to keep track of what's actually being tested, and why. When a test fails, good prose can make it much easier to figure out what the problem is, and how it should be fixed. It's true that you could write extensive comments in code-based testing, but few programmers do. Many have found that using doctest approaches instead leads to much clearer tests. Perhaps this is simply because doctest makes writing prose a little easier than writing code, while writing comments in code is a little harder. I think it goes deeper than just that: the natural attitude when writing a doctest-based test is that you want to explain the fine points of your software, and illustrate them with examples. This in turn naturally leads to test files that start with the simplest features, and logically progress to complications and edge cases. A coherent narrative is the result, instead of a collection of isolated functions that test isolated bits of functionality seemingly at random. It's a different attitude, and produces different results, blurring the distinction between testing and explaining.

Regression testing is best confined to dedicated objects or files. There are several options for organizing tests:

- Write text files containing test cases as interactive examples, and test the files using `testfile()` or `DocFileSuite()`. This is recommended, although is easiest to do for new projects, designed from the start to use doctest.
- Define functions named `_regtest_topic` that consist of single docstrings, containing test cases for the named topics. These functions can be included in the same file as the module, or separated out into a separate test file.
- Define a `__test__` dictionary mapping from regression test topics to docstrings containing test cases.

When you have placed your tests in a module, the module can itself be the test runner. When a test fails, you can arrange for your test runner to re-run only the failing doctest while you debug the problem. Here is a minimal example of such a test runner:

```

if __name__ == '__main__':
    import doctest
    flags = doctest.REPORT_NDIFF|doctest.REPORT_ONLY_FIRST_FAILURE
    if len(sys.argv) > 1:
        name = sys.argv[1]
        if name in globals():
            obj = globals()[name]
        else:
            obj = __test__[name]
        doctest.run_docstring_examples(obj, globals(), name=name,
                                       optionflags=flags)
    else:
        fail, total = doctest.testmod(optionflags=flags)
        print("{} failures out of {} tests".format(fail, total))

```

25.3 unittest — Unit testing framework

버전 2.1에 추가.

(If you are already familiar with the basic concepts of testing, you might want to skip to [the list of assert methods](#).)

The Python unit testing framework, sometimes referred to as «PyUnit,» is a Python language version of JUnit, by Kent Beck and Erich Gamma. JUnit is, in turn, a Java version of Kent’s Smalltalk testing framework. Each is the de facto standard unit testing framework for its respective language.

`unittest` supports test automation, sharing of setup and shutdown code for tests, aggregation of tests into collections, and independence of the tests from the reporting framework. The `unittest` module provides classes that make it easy to support these qualities for a set of tests.

To achieve this, `unittest` supports some important concepts:

test fixture A *test fixture* represents the preparation needed to perform one or more tests, and any associated cleanup actions. This may involve, for example, creating temporary or proxy databases, directories, or starting a server process.

test case A *test case* is the smallest unit of testing. It checks for a specific response to a particular set of inputs. `unittest` provides a base class, `TestCase`, which may be used to create new test cases.

test suite A *test suite* is a collection of test cases, test suites, or both. It is used to aggregate tests that should be executed together.

test runner A *test runner* is a component which orchestrates the execution of tests and provides the outcome to the user. The runner may use a graphical interface, a textual interface, or return a special value to indicate the results of executing the tests.

The test case and test fixture concepts are supported through the `TestCase` and `FunctionTestCase` classes; the former should be used when creating new tests, and the latter can be used when integrating existing test code with a `unittest`-driven framework. When building test fixtures using `TestCase`, the `setUp()` and `tearDown()` methods can be overridden to provide initialization and cleanup for the fixture. With `FunctionTestCase`, existing functions can be passed to the constructor for these purposes. When the test is run, the fixture initialization is run first; if it succeeds, the cleanup method is run after the test has been executed, regardless of the outcome of the test. Each instance of the `TestCase` will only be used to run a single test method, so a new fixture is created for each test.

Test suites are implemented by the `TestSuite` class. This class allows individual tests and test suites to be aggregated; when the suite is executed, all tests added directly to the suite and in «child» test suites are run.

A test runner is an object that provides a single method, `run()`, which accepts a `TestCase` or `TestSuite` object as a parameter, and returns a result object. The class `TestResult` is provided for use as the result object. `unittest`

provides the `TextTestRunner` as an example test runner which reports test results on the standard error stream by default. Alternate runners can be implemented for other environments (such as graphical environments) without any need to derive from a specific class.

더 보기:

Module `doctest` Another test-support module with a very different flavor.

unittest2: A backport of new unittest features for Python 2.4-2.6 Many new features were added to unittest in Python 2.7, including test discovery. unittest2 allows you to use these features with earlier versions of Python.

Simple Smalltalk Testing: With Patterns Kent Beck’s original paper on testing frameworks using the pattern shared by `unittest`.

Nose and pytest Third-party unittest frameworks with a lighter-weight syntax for writing tests. For example, `assert func(10) == 42`.

The Python Testing Tools Taxonomy An extensive list of Python testing tools including functional testing frameworks and mock object libraries.

Testing in Python Mailing List A special-interest-group for discussion of testing, and testing tools, in Python.

25.3.1 Basic example

The `unittest` module provides a rich set of tools for constructing and running tests. This section demonstrates that a small subset of the tools suffice to meet the needs of most users.

Here is a short script to test three string methods:

```
import unittest

class TestStringMethods(unittest.TestCase):

    def test_upper(self):
        self.assertEqual('foo'.upper(), 'FOO')

    def test_isupper(self):
        self.assertTrue('FOO'.isupper())
        self.assertFalse('Foo'.isupper())

    def test_split(self):
        s = 'hello world'
        self.assertEqual(s.split(), ['hello', 'world'])
        # check that s.split fails when the separator is not a string
        with self.assertRaises(TypeError):
            s.split(2)

if __name__ == '__main__':
    unittest.main()
```

A testcase is created by subclassing `unittest.TestCase`. The three individual tests are defined with methods whose names start with the letters `test`. This naming convention informs the test runner about which methods represent tests.

The crux of each test is a call to `assertEqual()` to check for an expected result; `assertTrue()` or `assertFalse()` to verify a condition; or `assertRaises()` to verify that a specific exception gets raised. These methods are used instead of the `assert` statement so the test runner can accumulate all test results and produce a report.

The `setUp()` and `tearDown()` methods allow you to define instructions that will be executed before and after each test method. They are covered in more detail in the section *Organizing test code*.

The final block shows a simple way to run the tests. `unittest.main()` provides a command-line interface to the test script. When run from the command line, the above script produces an output that looks like this:

```
...
-----
Ran 3 tests in 0.000s

OK
```

Instead of `unittest.main()`, there are other ways to run the tests with a finer level of control, less terse output, and no requirement to be run from the command line. For example, the last two lines may be replaced with:

```
suite = unittest.TestLoader().loadTestsFromTestCase(TestStringMethods)
unittest.TextTestRunner(verbosity=2).run(suite)
```

Running the revised script from the interpreter or another script produces the following output:

```
test_isupper (__main__.TestStringMethods) ... ok
test_split (__main__.TestStringMethods) ... ok
test_upper (__main__.TestStringMethods) ... ok

-----
Ran 3 tests in 0.001s

OK
```

The above examples show the most commonly used `unittest` features which are sufficient to meet many everyday testing needs. The remainder of the documentation explores the full feature set from first principles.

25.3.2 Command-Line Interface

The `unittest` module can be used from the command line to run tests from modules, classes or even individual test methods:

```
python -m unittest test_module1 test_module2
python -m unittest test_module.TestClass
python -m unittest test_module.TestClass.test_method
```

You can pass in a list with any combination of module names, and fully qualified class or method names.

You can run tests with more detail (higher verbosity) by passing in the `-v` flag:

```
python -m unittest -v test_module
```

For a list of all the command-line options:

```
python -m unittest -h
```

버전 2.7에서 변경: In earlier versions it was only possible to run individual test methods and not modules or classes.

Command-line options

unittest supports these command-line options:

-b, --buffer

The standard output and standard error streams are buffered during the test run. Output during a passing test is discarded. Output is echoed normally on test fail or error and is added to the failure messages.

-c, --catch

Control-C during the test run waits for the current test to end and then reports all the results so far. A second Control-C raises the normal *KeyboardInterrupt* exception.

See *Signal Handling* for the functions that provide this functionality.

-f, --failfast

Stop the test run on the first error or failure.

버전 2.7에 추가: The command-line options `-b`, `-c` and `-f` were added.

The command line can also be used for test discovery, for running all of the tests in a project or just a subset.

25.3.3 Test Discovery

버전 2.7에 추가.

Unittest supports simple test discovery. In order to be compatible with test discovery, all of the test files must be modules or packages importable from the top-level directory of the project (this means that their filenames must be valid identifiers).

Test discovery is implemented in *TestLoader.discover()*, but can also be used from the command line. The basic command-line usage is:

```
cd project_directory
python -m unittest discover
```

The *discover* sub-command has the following options:

-v, --verbose

Verbose output

-s, --start-directory directory

Directory to start discovery (`.` default)

-p, --pattern pattern

Pattern to match test files (`test*.py` default)

-t, --top-level-directory directory

Top level directory of project (defaults to start directory)

The `-s`, `-p`, and `-t` options can be passed in as positional arguments in that order. The following two command lines are equivalent:

```
python -m unittest discover -s project_directory -p "*_test.py"
python -m unittest discover project_directory "*_test.py"
```

As well as being a path it is possible to pass a package name, for example `myproject.subpackage.test`, as the start directory. The package name you supply will then be imported and its location on the filesystem will be used as the start directory.

조심: Test discovery loads tests by importing them. Once test discovery has found all the test files from the start directory you specify it turns the paths into package names to import. For example `foo/bar/baz.py` will be imported as `foo.bar.baz`.

If you have a package installed globally and attempt test discovery on a different copy of the package then the import *could* happen from the wrong place. If this happens test discovery will warn you and exit.

If you supply the start directory as a package name rather than a path to a directory then discover assumes that whichever location it imports from is the location you intended, so you will not get the warning.

Test modules and packages can customize test loading and discovery by through the *load_tests protocol*.

25.3.4 Organizing test code

The basic building blocks of unit testing are *test cases* — single scenarios that must be set up and checked for correctness. In *unittest*, test cases are represented by instances of *unittest*'s *TestCase* class. To make your own test cases you must write subclasses of *TestCase*, or use *FunctionTestCase*.

An instance of a *TestCase*-derived class is an object that can completely run a single test method, together with optional set-up and tidy-up code.

The testing code of a *TestCase* instance should be entirely self contained, such that it can be run either in isolation or in arbitrary combination with any number of other test cases.

The simplest *TestCase* subclass will simply override the `runTest()` method in order to perform specific testing code:

```
import unittest

class DefaultWidgetSizeTestCase(unittest.TestCase):
    def runTest(self):
        widget = Widget('The widget')
        self.assertEqual(widget.size(), (50, 50), 'incorrect default size')
```

Note that in order to test something, we use one of the `assert*`() methods provided by the *TestCase* base class. If the test fails, an exception will be raised, and *unittest* will identify the test case as a *failure*. Any other exceptions will be treated as *errors*. This helps you identify where the problem is: *failures* are caused by incorrect results - a 5 where you expected a 6. *Errors* are caused by incorrect code - e.g., a *TypeError* caused by an incorrect function call.

The way to run a test case will be described later. For now, note that to construct an instance of such a test case, we call its constructor without arguments:

```
testCase = DefaultWidgetSizeTestCase()
```

Now, such test cases can be numerous, and their set-up can be repetitive. In the above case, constructing a *Widget* in each of 100 *Widget* test case subclasses would mean unsightly duplication.

Luckily, we can factor out such set-up code by implementing a method called `setUp()`, which the testing framework will automatically call for us when we run the test:

```
import unittest

class SimpleWidgetTestCase(unittest.TestCase):
    def setUp(self):
        self.widget = Widget('The widget')
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

class DefaultWidgetSizeTestCase(SimpleWidgetTestCase):
    def runTest(self):
        self.assertEqual(self.widget.size(), (50,50),
                          'incorrect default size')

class WidgetResizeTestCase(SimpleWidgetTestCase):
    def runTest(self):
        self.widget.resize(100,150)
        self.assertEqual(self.widget.size(), (100,150),
                          'wrong size after resize')

```

If the `setUp()` method raises an exception while the test is running, the framework will consider the test to have suffered an error, and the `runTest()` method will not be executed.

Similarly, we can provide a `tearDown()` method that tidies up after the `runTest()` method has been run:

```

import unittest

class SimpleWidgetTestCase(unittest.TestCase):
    def setUp(self):
        self.widget = Widget('The widget')

    def tearDown(self):
        self.widget.dispose()
        self.widget = None

```

If `setUp()` succeeded, the `tearDown()` method will be run whether `runTest()` succeeded or not.

Such a working environment for the testing code is called a *fixture*.

Often, many small test cases will use the same fixture. In this case, we would end up subclassing `SimpleWidgetTestCase` into many small one-method classes such as `DefaultWidgetSizeTestCase`. This is time-consuming and discouraging, so in the same vein as JUnit, *unittest* provides a simpler mechanism:

```

import unittest

class WidgetTestCase(unittest.TestCase):
    def setUp(self):
        self.widget = Widget('The widget')

    def tearDown(self):
        self.widget.dispose()
        self.widget = None

    def test_default_size(self):
        self.assertEqual(self.widget.size(), (50,50),
                          'incorrect default size')

    def test_resize(self):
        self.widget.resize(100,150)
        self.assertEqual(self.widget.size(), (100,150),
                          'wrong size after resize')

```

Here we have not provided a `runTest()` method, but have instead provided two different test methods. Class instances will now each run one of the `test_*`() methods, with `self.widget` created and destroyed separately for each instance. When creating an instance we must specify the test method it is to run. We do this by passing the method name in the constructor:

```
defaultSizeTestCase = WidgetTestCase('test_default_size')
resizeTestCase = WidgetTestCase('test_resize')
```

Test case instances are grouped together according to the features they test. *unittest* provides a mechanism for this: the *test suite*, represented by *unittest*'s *TestSuite* class:

```
widgetTestSuite = unittest.TestSuite()
widgetTestSuite.addTest(WidgetTestCase('test_default_size'))
widgetTestSuite.addTest(WidgetTestCase('test_resize'))
```

For the ease of running tests, as we will see later, it is a good idea to provide in each test module a callable object that returns a pre-built test suite:

```
def suite():
    suite = unittest.TestSuite()
    suite.addTest(WidgetTestCase('test_default_size'))
    suite.addTest(WidgetTestCase('test_resize'))
    return suite
```

or even:

```
def suite():
    tests = ['test_default_size', 'test_resize']

    return unittest.TestSuite(map(WidgetTestCase, tests))
```

Since it is a common pattern to create a *TestCase* subclass with many similarly named test functions, *unittest* provides a *TestLoader* class that can be used to automate the process of creating a test suite and populating it with individual tests. For example,

```
suite = unittest.TestLoader().loadTestsFromTestCase(WidgetTestCase)
```

will create a test suite that will run `WidgetTestCase.test_default_size()` and `WidgetTestCase.test_resize`. *TestLoader* uses the 'test' method name prefix to identify test methods automatically.

Note that the order in which the various test cases will be run is determined by sorting the test function names with respect to the built-in ordering for strings.

Often it is desirable to group suites of test cases together, so as to run tests for the whole system at once. This is easy, since *TestSuite* instances can be added to a *TestSuite* just as *TestCase* instances can be added to a *TestSuite*:

```
suite1 = module1.TheTestSuite()
suite2 = module2.TheTestSuite()
alltests = unittest.TestSuite([suite1, suite2])
```

You can place the definitions of test cases and test suites in the same modules as the code they are to test (such as `widget.py`), but there are several advantages to placing the test code in a separate module, such as `test_widget.py`:

- The test module can be run standalone from the command line.
- The test code can more easily be separated from shipped code.
- There is less temptation to change test code to fit the code it tests without a good reason.
- Test code should be modified much less frequently than the code it tests.
- Tested code can be refactored more easily.
- Tests for modules written in C must be in separate modules anyway, so why not be consistent?

- If the testing strategy changes, there is no need to change the source code.

25.3.5 Re-using old test code

Some users will find that they have existing test code that they would like to run from `unittest`, without converting every old test function to a `TestCase` subclass.

For this reason, `unittest` provides a `FunctionTestCase` class. This subclass of `TestCase` can be used to wrap an existing test function. Set-up and tear-down functions can also be provided.

Given the following test function:

```
def testSomething():
    something = makeSomething()
    assert something.name is not None
    # ...
```

one can create an equivalent test case instance as follows:

```
testcase = unittest.FunctionTestCase(testSomething)
```

If there are additional set-up and tear-down methods that should be called as part of the test case's operation, they can also be provided like so:

```
testcase = unittest.FunctionTestCase(testSomething,
                                     setUp=makeSomethingDB,
                                     tearDown=deleteSomethingDB)
```

To make migrating existing test suites easier, `unittest` supports tests raising `AssertionError` to indicate test failure. However, it is recommended that you use the explicit `TestCase.fail*()` and `TestCase.assert*()` methods instead, as future versions of `unittest` may treat `AssertionError` differently.

참고: Even though `FunctionTestCase` can be used to quickly convert an existing test base over to a `unittest`-based system, this approach is not recommended. Taking the time to set up proper `TestCase` subclasses will make future test refactorings infinitely easier.

In some cases, the existing tests may have been written using the `doctest` module. If so, `doctest` provides a `DocTestSuite` class that can automatically build `unittest.TestSuite` instances from the existing `doctest`-based tests.

25.3.6 Skipping tests and expected failures

버전 2.7에 추가.

Unittest supports skipping individual test methods and even whole classes of tests. In addition, it supports marking a test as an «expected failure,» a test that is broken and will fail, but shouldn't be counted as a failure on a `TestResult`.

Skipping a test is simply a matter of using the `skip() decorator` or one of its conditional variants.

Basic skipping looks like this:

```
class MyTestCase(unittest.TestCase):

    @unittest.skip("demonstrating skipping")
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

def test_nothing(self):
    self.fail("shouldn't happen")

@unittest.skipIf(mylib.__version__ < (1, 3),
                 "not supported in this library version")
def test_format(self):
    # Tests that work for only a certain version of the library.
    pass

@unittest.skipUnless(sys.platform.startswith("win"), "requires Windows")
def test_windows_support(self):
    # windows specific testing code
    pass

```

This is the output of running the example above in verbose mode:

```

test_format (__main__.MyTestCase) ... skipped 'not supported in this library version'
test_nothing (__main__.MyTestCase) ... skipped 'demonstrating skipping'
test_windows_support (__main__.MyTestCase) ... skipped 'requires Windows'

-----
Ran 3 tests in 0.005s

OK (skipped=3)

```

Classes can be skipped just like methods:

```

@unittest.skip("showing class skipping")
class MySkippedTestCase(unittest.TestCase):
    def test_not_run(self):
        pass

```

`TestCase.setUp()` can also skip the test. This is useful when a resource that needs to be set up is not available.

Expected failures use the `expectedFailure()` decorator.

```

class ExpectedFailureTestCase(unittest.TestCase):
    @unittest.expectedFailure
    def test_fail(self):
        self.assertEqual(1, 0, "broken")

```

It's easy to roll your own skipping decorators by making a decorator that calls `skip()` on the test when it wants it to be skipped. This decorator skips the test unless the passed object has a certain attribute:

```

def skipUnlessHasattr(obj, attr):
    if hasattr(obj, attr):
        return lambda func: func
    return unittest.skip("{!r} doesn't have {!r}".format(obj, attr))

```

The following decorators implement test skipping and expected failures:

`unittest.skip(reason)`

Unconditionally skip the decorated test. *reason* should describe why the test is being skipped.

`unittest.skipIf(condition, reason)`

Skip the decorated test if *condition* is true.

`unittest.skipUnless(condition, reason)`

Skip the decorated test unless *condition* is true.

`unittest.expectedFailure()`

Mark the test as an expected failure. If the test fails when run, the test is not counted as a failure.

exception `unittest.SkipTest(reason)`

This exception is raised to skip a test.

Usually you can use `TestCase.skipTest()` or one of the skipping decorators instead of raising this directly.

Skipped tests will not have `setUp()` or `tearDown()` run around them. Skipped classes will not have `setUpClass()` or `tearDownClass()` run.

25.3.7 Classes and functions

This section describes in depth the API of `unittest`.

Test cases

class `unittest.TestCase(methodName='runTest')`

Instances of the `TestCase` class represent the smallest testable units in the `unittest` universe. This class is intended to be used as a base class, with specific tests being implemented by concrete subclasses. This class implements the interface needed by the test runner to allow it to drive the test, and methods that the test code can use to check for and report various kinds of failure.

Each instance of `TestCase` will run a single test method: the method named *methodName*. If you remember, we had an earlier example that went something like this:

```
def suite():
    suite = unittest.TestSuite()
    suite.addTest(WidgetTestCase('test_default_size'))
    suite.addTest(WidgetTestCase('test_resize'))
    return suite
```

Here, we create two instances of `WidgetTestCase`, each of which runs a single test.

methodName defaults to `runTest()`.

`TestCase` instances provide three groups of methods: one group used to run the test, another used by the test implementation to check conditions and report failures, and some inquiry methods allowing information about the test itself to be gathered.

Methods in the first group (running the test) are:

setUp()

Method called to prepare the test fixture. This is called immediately before calling the test method; other than `AssertionError` or `SkipTest`, any exception raised by this method will be considered an error rather than a test failure. The default implementation does nothing.

tearDown()

Method called immediately after the test method has been called and the result recorded. This is called even if the test method raised an exception, so the implementation in subclasses may need to be particularly careful about checking internal state. Any exception, other than `AssertionError` or `SkipTest`, raised by this method will be considered an additional error rather than a test failure (thus increasing the total number of reported errors). This method will only be called if the `setUp()` succeeds, regardless of the outcome of the test method. The default implementation does nothing.

setUpClass()

A class method called before tests in an individual class are run. `setUpClass` is called with the class as the only argument and must be decorated as a `classmethod()`:

```
@classmethod
def setUpClass(cls):
    ...
```

See *Class and Module Fixtures* for more details.

버전 2.7에 추가.

tearDownClass()

A class method called after tests in an individual class have run. `tearDownClass` is called with the class as the only argument and must be decorated as a `classmethod()`:

```
@classmethod
def tearDownClass(cls):
    ...
```

See *Class and Module Fixtures* for more details.

버전 2.7에 추가.

run(result=None)

Run the test, collecting the result into the test result object passed as *result*. If *result* is omitted or `None`, a temporary result object is created (by calling the `defaultTestResult()` method) and used. The result object is not returned to `run()`'s caller.

The same effect may be had by simply calling the `TestCase` instance.

skipTest(reason)

Calling this during a test method or `setUp()` skips the current test. See *Skipping tests and expected failures* for more information.

버전 2.7에 추가.

debug()

Run the test without collecting the result. This allows exceptions raised by the test to be propagated to the caller, and can be used to support running tests under a debugger.

The `TestCase` class provides several assert methods to check for and report failures. The following table lists the most commonly used methods (see the tables below for more assert methods):

Method	Checks that	New in
<code>assertEqual(a, b)</code>	<code>a == b</code>	
<code>assertNotEqual(a, b)</code>	<code>a != b</code>	
<code>assertTrue(x)</code>	<code>bool(x) is True</code>	
<code>assertFalse(x)</code>	<code>bool(x) is False</code>	
<code>assertIs(a, b)</code>	<code>a is b</code>	2.7
<code>assertIsNot(a, b)</code>	<code>a is not b</code>	2.7
<code>assertIsNone(x)</code>	<code>x is None</code>	2.7
<code>assertIsNotNone(x)</code>	<code>x is not None</code>	2.7
<code>assertIn(a, b)</code>	<code>a in b</code>	2.7
<code>assertNotIn(a, b)</code>	<code>a not in b</code>	2.7
<code>assertIsInstance(a, b)</code>	<code>isinstance(a, b)</code>	2.7
<code>assertNotIsInstance(a, b)</code>	<code>not isinstance(a, b)</code>	2.7

All the assert methods (except `assertRaises()`, `assertRaisesRegexp()`) accept a `msg` argument that, if specified, is used as the error message on failure (see also `longMessage`).

assertEqual (*first, second, msg=None*)

Test that *first* and *second* are equal. If the values do not compare equal, the test will fail.

In addition, if *first* and *second* are the exact same type and one of list, tuple, dict, set, frozenset or unicode or any type that a subclass registers with `addTypeEqualityFunc()` the type-specific equality function will be called in order to generate a more useful default error message (see also the [list of type-specific methods](#)).

버전 2.7에서 변경: Added the automatic calling of type-specific equality function.

assertNotEqual (*first, second, msg=None*)

Test that *first* and *second* are not equal. If the values do compare equal, the test will fail.

assertTrue (*expr, msg=None*)

assertFalse (*expr, msg=None*)

Test that *expr* is true (or false).

Note that this is equivalent to `bool(expr) is True` and `not to expr is True` (use `assertIs(expr, True)` for the latter). This method should also be avoided when more specific methods are available (e.g. `assertEqual(a, b)` instead of `assertTrue(a == b)`), because they provide a better error message in case of failure.

assertIs (*first, second, msg=None*)

assertIsNot (*first, second, msg=None*)

Test that *first* and *second* evaluate (or don't evaluate) to the same object.

버전 2.7에 추가.

assertIsNone (*expr, msg=None*)

assertIsNotNone (*expr, msg=None*)

Test that *expr* is (or is not) None.

버전 2.7에 추가.

assertIn (*first, second, msg=None*)

assertNotIn (*first, second, msg=None*)

Test that *first* is (or is not) in *second*.

버전 2.7에 추가.

assertIsInstance (*obj, cls, msg=None*)

assertNotIsInstance (*obj, cls, msg=None*)

Test that *obj* is (or is not) an instance of *cls* (which can be a class or a tuple of classes, as supported by `isinstance()`). To check for the exact type, use `assertIs(type(obj), cls)`.

버전 2.7에 추가.

It is also possible to check that exceptions and warnings are raised using the following methods:

Method	Checks that	New in
<code>assertRaises(exc, fun, *args, **kwargs)</code>	<code>fun(*args, **kwargs)</code> raises <i>exc</i>	
<code>assertRaisesRegexp(exc, r, fun, *args, **kwargs)</code>	<code>fun(*args, **kwargs)</code> raises <i>exc</i> and the message matches regex <i>r</i>	2.7

assertRaises (*exception, callable, *args, **kwargs*)

assertRaises (*exception*)

Test that an exception is raised when *callable* is called with any positional or keyword arguments that are also passed to `assertRaises()`. The test passes if *exception* is raised, is an error if another exception is raised, or fails if no exception is raised. To catch any of a group of exceptions, a tuple containing the exception classes may be passed as *exception*.

If only the *exception* argument is given, returns a context manager so that the code under test can be written inline rather than as a function:

```
with self.assertRaises(SomeException):
    do_something()
```

The context manager will store the caught exception object in its `exception` attribute. This can be useful if the intention is to perform additional checks on the exception raised:

```
with self.assertRaises(SomeException) as cm:
    do_something()

the_exception = cm.exception
self.assertEqual(the_exception.error_code, 3)
```

버전 2.7에서 변경: Added the ability to use `assertRaises()` as a context manager.

assertRaisesRegexp (*exception, regexp, callable, *args, **kwargs*)**assertRaisesRegexp** (*exception, regexp*)

Like `assertRaises()` but also tests that *regexp* matches on the string representation of the raised exception. *regexp* may be a regular expression object or a string containing a regular expression suitable for use by `re.search()`. Examples:

```
self.assertRaisesRegexp(ValueError, "invalid literal for.*XYZ'",
                        int, 'XYZ')
```

or:

```
with self.assertRaisesRegexp(ValueError, 'literal'):
    int('XYZ')
```

버전 2.7에 추가.

There are also other methods used to perform more specific checks, such as:

Method	Checks that	New in
<code>assertAlmostEqual(a, b)</code>	<code>round(a-b, 7) == 0</code>	
<code>assertNotAlmostEqual(a, b)</code>	<code>round(a-b, 7) != 0</code>	
<code>assertGreater(a, b)</code>	<code>a > b</code>	2.7
<code>assertGreaterEqual(a, b)</code>	<code>a >= b</code>	2.7
<code>assertLess(a, b)</code>	<code>a < b</code>	2.7
<code>assertLessEqual(a, b)</code>	<code>a <= b</code>	2.7
<code>assertRegexpMatches(s, r)</code>	<code>r.search(s)</code>	2.7
<code>assertNotRegexpMatches(s, r)</code>	<code>not r.search(s)</code>	2.7
<code>assertItemsEqual(a, b)</code>	<code>sorted(a) == sorted(b)</code> and works with unhashable objs	2.7
<code>assertDictContainsSubset(a, b)</code>	all the key/value pairs in <i>a</i> exist in <i>b</i>	2.7

assertAlmostEqual (*first, second, places=7, msg=None, delta=None*)

assertNotAlmostEqual (*first, second, places=7, msg=None, delta=None*)

Test that *first* and *second* are approximately (or not approximately) equal by computing the difference, rounding to the given number of decimal *places* (default 7), and comparing to zero. Note that these methods round the values to the given number of *decimal places* (i.e. like the `round()` function) and not *significant digits*.

If *delta* is supplied instead of *places* then the difference between *first* and *second* must be less or equal to (or greater than) *delta*.

Supplying both *delta* and *places* raises a `TypeError`.

버전 2.7에서 변경: `assertAlmostEqual()` automatically considers almost equal objects that compare equal. `assertNotAlmostEqual()` automatically fails if the objects compare equal. Added the *delta* keyword argument.

assertGreater (*first, second, msg=None*)

assertGreaterEqual (*first, second, msg=None*)

assertLess (*first, second, msg=None*)

assertLessEqual (*first, second, msg=None*)

Test that *first* is respectively `>`, `>=`, `<` or `<=` than *second* depending on the method name. If not, the test will fail:

```
>>> self.assertGreaterEqual(3, 4)
AssertionError: "3" unexpectedly not greater than or equal to "4"
```

버전 2.7에 추가.

assertRegexpMatches (*text, regexp, msg=None*)

Test that a *regexp* search matches *text*. In case of failure, the error message will include the pattern and the *text* (or the pattern and the part of *text* that unexpectedly matched). *regexp* may be a regular expression object or a string containing a regular expression suitable for use by `re.search()`.

버전 2.7에 추가.

assertNotRegexpMatches (*text, regexp, msg=None*)

Verifies that a *regexp* search does not match *text*. Fails with an error message including the pattern and the part of *text* that matches. *regexp* may be a regular expression object or a string containing a regular expression suitable for use by `re.search()`.

버전 2.7에 추가.

assertItemsEqual (*actual, expected, msg=None*)

Test that sequence *expected* contains the same elements as *actual*, regardless of their order. When they don't, an error message listing the differences between the sequences will be generated.

Duplicate elements are *not* ignored when comparing *actual* and *expected*. It verifies if each element has the same count in both sequences. It is the equivalent of `assertEqual(sorted(expected), sorted(actual))` but it works with sequences of unhashable objects as well.

In Python 3, this method is named `assertCountEqual`.

버전 2.7에 추가.

assertDictContainsSubset (*expected, actual, msg=None*)

Tests whether the key/value pairs in dictionary *actual* are a superset of those in *expected*. If not, an error message listing the missing keys and mismatched values is generated.

버전 2.7에 추가.

버전 3.2부터 폐지.

The `assertEqual()` method dispatches the equality check for objects of the same type to different type-specific methods. These methods are already implemented for most of the built-in types, but it's also possible to register new methods using `addTypeEqualityFunc()`:

addTypeEqualityFunc (*typeobj*, *function*)

Registers a type-specific method called by `assertEqual()` to check if two objects of exactly the same *typeobj* (not subclasses) compare equal. *function* must take two positional arguments and a third `msg=None` keyword argument just as `assertEqual()` does. It must raise `self.failureException(msg)` when inequality between the first two parameters is detected – possibly providing useful information and explaining the inequalities in details in the error message.

버전 2.7에 추가.

The list of type-specific methods automatically used by `assertEqual()` are summarized in the following table. Note that it's usually not necessary to invoke these methods directly.

Method	Used to compare	New in
<code>assertMultiLineEqual(a, b)</code>	strings	2.7
<code>assertSequenceEqual(a, b)</code>	sequences	2.7
<code>assertListEqual(a, b)</code>	lists	2.7
<code>assertTupleEqual(a, b)</code>	tuples	2.7
<code>assertSetEqual(a, b)</code>	sets or frozensets	2.7
<code>assertDictEqual(a, b)</code>	dicts	2.7

assertMultiLineEqual (*first*, *second*, *msg=None*)

Test that the multiline string *first* is equal to the string *second*. When not equal a diff of the two strings highlighting the differences will be included in the error message. This method is used by default when comparing Unicode strings with `assertEqual()`.

버전 2.7에 추가.

assertSequenceEqual (*seq1*, *seq2*, *msg=None*, *seq_type=None*)

Tests that two sequences are equal. If a *seq_type* is supplied, both *seq1* and *seq2* must be instances of *seq_type* or a failure will be raised. If the sequences are different an error message is constructed that shows the difference between the two.

This method is not called directly by `assertEqual()`, but it's used to implement `assertListEqual()` and `assertTupleEqual()`.

버전 2.7에 추가.

assertListEqual (*list1*, *list2*, *msg=None*)

assertTupleEqual (*tuple1*, *tuple2*, *msg=None*)

Tests that two lists or tuples are equal. If not, an error message is constructed that shows only the differences between the two. An error is also raised if either of the parameters are of the wrong type. These methods are used by default when comparing lists or tuples with `assertEqual()`.

버전 2.7에 추가.

assertSetEqual (*set1*, *set2*, *msg=None*)

Tests that two sets are equal. If not, an error message is constructed that lists the differences between the sets. This method is used by default when comparing sets or frozensets with `assertEqual()`.

Fails if either of *set1* or *set2* does not have a `set.difference()` method.

버전 2.7에 추가.

assertDictEqual (*expected*, *actual*, *msg=None*)

Test that two dictionaries are equal. If not, an error message is constructed that shows the differences in the dictionaries. This method will be used by default to compare dictionaries in calls to `assertEqual()`.

버전 2.7에 추가.

Finally the `TestCase` provides the following methods and attributes:

fail (*msg=None*)

Signals a test failure unconditionally, with *msg* or `None` for the error message.

failureException

This class attribute gives the exception raised by the test method. If a test framework needs to use a specialized exception, possibly to carry additional information, it must subclass this exception in order to 《play fair》 with the framework. The initial value of this attribute is `AssertionError`.

longMessage

If set to `True` then any explicit failure message you pass in to the *assert methods* will be appended to the end of the normal failure message. The normal messages contain useful information about the objects involved, for example the message from `assertEqual` shows you the repr of the two unequal objects. Setting this attribute to `True` allows you to have a custom error message in addition to the normal one.

This attribute defaults to `False`, meaning that a custom message passed to an assert method will silence the normal message.

The class setting can be overridden in individual tests by assigning an instance attribute to `True` or `False` before calling the assert methods.

버전 2.7에 추가.

maxDiff

This attribute controls the maximum length of diffs output by assert methods that report diffs on failure. It defaults to 80*8 characters. Assert methods affected by this attribute are *assertSequenceEqual()* (including all the sequence comparison methods that delegate to it), *assertDictEqual()* and *assertMultiLineEqual()*.

Setting `maxDiff` to `None` means that there is no maximum length of diffs.

버전 2.7에 추가.

Testing frameworks can use the following methods to collect information on the test:

countTestCases ()

Return the number of tests represented by this test object. For `TestCase` instances, this will always be 1.

defaultTestResult ()

Return an instance of the test result class that should be used for this test case class (if no other result instance is provided to the *run()* method).

For `TestCase` instances, this will always be an instance of `TestResult`; subclasses of `TestCase` should override this as necessary.

id ()

Return a string identifying the specific test case. This is usually the full name of the test method, including the module and class name.

shortDescription ()

Returns a description of the test, or `None` if no description has been provided. The default implementation of this method returns the first line of the test method's docstring, if available, or `None`.

addCleanup (*function, *args, **kwargs*)

Add a function to be called after *tearDown()* to cleanup resources used during the test. Functions will be called in reverse order to the order they are added (LIFO). They are called with any arguments and keyword arguments passed into *addCleanup()* when they are added.

If *setUp()* fails, meaning that *tearDown()* is not called, then any cleanup functions added will still be called.

버전 2.7에 추가.

doCleanups()

This method is called unconditionally after `tearDown()`, or after `setUp()` if `setUp()` raises an exception.

It is responsible for calling all the cleanup functions added by `addCleanup()`. If you need cleanup functions to be called *prior* to `tearDown()` then you can call `doCleanups()` yourself.

`doCleanups()` pops methods off the stack of cleanup functions one at a time, so it can be called at any time.

버전 2.7에 추가.

class unittest.FunctionTestCase (*testFunc, setUp=None, tearDown=None, description=None*)

This class implements the portion of the `TestCase` interface which allows the test runner to drive the test, but does not provide the methods which test code can use to check and report errors. This is used to create test cases using legacy test code, allowing it to be integrated into a `unittest`-based test framework.

Deprecated aliases

For historical reasons, some of the `TestCase` methods had one or more aliases that are now deprecated. The following table lists the correct names along with their deprecated aliases:

Method Name	Deprecated alias(es)
<code>assertEqual()</code>	<code>failUnlessEqual</code> , <code>assertEquals</code>
<code>assertNotEqual()</code>	<code>failIfEqual</code>
<code>assertTrue()</code>	<code>failUnless</code> , <code>assert_</code>
<code>assertFalse()</code>	<code>failIf</code>
<code>assertRaises()</code>	<code>failUnlessRaises</code>
<code>assertAlmostEqual()</code>	<code>failUnlessAlmostEqual</code>
<code>assertNotAlmostEqual()</code>	<code>failIfAlmostEqual</code>

버전 2.7부터 폐지: the aliases listed in the second column

Grouping tests

class unittest.TestSuite (*tests=()*)

This class represents an aggregation of individual test cases and test suites. The class presents the interface needed by the test runner to allow it to be run as any other test case. Running a `TestSuite` instance is the same as iterating over the suite, running each test individually.

If `tests` is given, it must be an iterable of individual test cases or other test suites that will be used to build the suite initially. Additional methods are provided to add test cases and suites to the collection later on.

`TestSuite` objects behave much like `TestCase` objects, except they do not actually implement a test. Instead, they are used to aggregate tests into groups of tests that should be run together. Some additional methods are available to add tests to `TestSuite` instances:

addTest (*test*)

Add a `TestCase` or `TestSuite` to the suite.

addTests (*tests*)

Add all the tests from an iterable of `TestCase` and `TestSuite` instances to this test suite.

This is equivalent to iterating over `tests`, calling `addTest()` for each element.

TestSuite shares the following methods with *TestCase*:

run (*result*)

Run the tests associated with this suite, collecting the result into the test result object passed as *result*. Note that unlike *TestCase.run()*, *TestSuite.run()* requires the result object to be passed in.

debug ()

Run the tests associated with this suite without collecting the result. This allows exceptions raised by the test to be propagated to the caller and can be used to support running tests under a debugger.

countTestCases ()

Return the number of tests represented by this test object, including all individual tests and sub-suites.

__iter__ ()

Tests grouped by a *TestSuite* are always accessed by iteration. Subclasses can lazily provide tests by overriding *__iter__()*. Note that this method maybe called several times on a single suite (for example when counting tests or comparing for equality) so the tests returned must be the same for repeated iterations.

버전 2.7에서 변경: In earlier versions the *TestSuite* accessed tests directly rather than through iteration, so overriding *__iter__()* wasn't sufficient for providing tests.

In the typical usage of a *TestSuite* object, the *run()* method is invoked by a *TestRunner* rather than by the end-user test harness.

Loading and running tests

class unittest.**TestLoader**

The *TestLoader* class is used to create test suites from classes and modules. Normally, there is no need to create an instance of this class; the *unittest* module provides an instance that can be shared as *unittest.defaultTestLoader*. Using a subclass or instance, however, allows customization of some configurable properties.

TestLoader objects have the following methods:

loadTestsFromTestCase (*testCaseClass*)

Return a suite of all test cases contained in the *TestCase*-derived *testCaseClass*.

loadTestsFromModule (*module*)

Return a suite of all test cases contained in the given module. This method searches *module* for classes derived from *TestCase* and creates an instance of the class for each test method defined for the class.

참고: While using a hierarchy of *TestCase*-derived classes can be convenient in sharing fixtures and helper functions, defining test methods on base classes that are not intended to be instantiated directly does not play well with this method. Doing so, however, can be useful when the fixtures are different and defined in subclasses.

If a module provides a *load_tests* function it will be called to load the tests. This allows modules to customize test loading. This is the *load_tests protocol*.

버전 2.7에서 변경: Support for *load_tests* added.

loadTestsFromName (*name*, *module=None*)

Return a suite of all test cases given a string specifier.

The specifier *name* is a «dotted name» that may resolve either to a module, a test case class, a test method within a test case class, a *TestSuite* instance, or a callable object which returns a *TestCase* or *TestSuite* instance. These checks are applied in the order listed here; that is, a method on a possible test case class will be picked up as «a test method within a test case class», rather than «a callable object».

For example, if you have a module `SampleTests` containing a `TestCase`-derived class `SampleTestCase` with three test methods (`test_one()`, `test_two()`, and `test_three()`), the specifier `'SampleTests.SampleTestCase'` would cause this method to return a suite which will run all three test methods. Using the specifier `'SampleTests.SampleTestCase.test_two'` would cause it to return a test suite which will run only the `test_two()` test method. The specifier can refer to modules and packages which have not been imported; they will be imported as a side-effect.

The method optionally resolves *name* relative to the given *module*.

loadTestsFromNames (*names*, *module=None*)

Similar to `loadTestsFromName()`, but takes a sequence of names rather than a single name. The return value is a test suite which supports all the tests defined for each name.

getTestCaseNames (*testCaseClass*)

Return a sorted sequence of method names found within *testCaseClass*; this should be a subclass of `TestCase`.

discover (*start_dir*, *pattern='test*.py'*, *top_level_dir=None*)

Find all the test modules by recursing into subdirectories from the specified start directory, and return a `TestSuite` object containing them. Only test files that match *pattern* will be loaded. (Using shell style pattern matching.) Only module names that are importable (i.e. are valid Python identifiers) will be loaded.

All test modules must be importable from the top level of the project. If the start directory is not the top level directory then the top level directory must be specified separately.

If importing a module fails, for example due to a syntax error, then this will be recorded as a single error and discovery will continue.

If a test package name (directory with `__init__.py`) matches the pattern then the package will be checked for a `load_tests` function. If this exists then it will be called with *loader*, *tests*, *pattern*.

If `load_tests` exists then discovery does *not* recurse into the package, `load_tests` is responsible for loading all tests in the package.

The pattern is deliberately not stored as a loader attribute so that packages can continue discovery themselves. *top_level_dir* is stored so `load_tests` does not need to pass this argument in to `loader.discover()`.

start_dir can be a dotted module name as well as a directory.

버전 2.7에 추가.

The following attributes of a `TestLoader` can be configured either by subclassing or assignment on an instance:

testMethodPrefix

String giving the prefix of method names which will be interpreted as test methods. The default value is `'test'`.

This affects `getTestCaseNames()` and all the `loadTestsFrom*()` methods.

sortTestMethodsUsing

Function to be used to compare method names when sorting them in `getTestCaseNames()` and all the `loadTestsFrom*()` methods. The default value is the built-in `cmp()` function; the attribute can also be set to `None` to disable the sort.

suiteClass

Callable object that constructs a test suite from a list of tests. No methods on the resulting object are needed. The default value is the `TestSuite` class.

This affects all the `loadTestsFrom*()` methods.

class `unittest.TestResult`

This class is used to compile information about which tests have succeeded and which have failed.

A `TestResult` object stores the results of a set of tests. The `TestCase` and `TestSuite` classes ensure that results are properly recorded; test authors do not need to worry about recording the outcome of tests.

Testing frameworks built on top of `unittest` may want access to the `TestResult` object generated by running a set of tests for reporting purposes; a `TestResult` instance is returned by the `TestRunner.run()` method for this purpose.

`TestResult` instances have the following attributes that will be of interest when inspecting the results of running a set of tests:

errors

A list containing 2-tuples of `TestCase` instances and strings holding formatted tracebacks. Each tuple represents a test which raised an unexpected exception.

버전 2.2에서 변경: Contains formatted tracebacks instead of `sys.exc_info()` results.

failures

A list containing 2-tuples of `TestCase` instances and strings holding formatted tracebacks. Each tuple represents a test where a failure was explicitly signalled using the `TestCase.assert*()` methods.

버전 2.2에서 변경: Contains formatted tracebacks instead of `sys.exc_info()` results.

skipped

A list containing 2-tuples of `TestCase` instances and strings holding the reason for skipping the test.

버전 2.7에 추가.

expectedFailures

A list containing 2-tuples of `TestCase` instances and strings holding formatted tracebacks. Each tuple represents an expected failure of the test case.

unexpectedSuccesses

A list containing `TestCase` instances that were marked as expected failures, but succeeded.

shouldStop

Set to `True` when the execution of tests should stop by `stop()`.

testsRun

The total number of tests run so far.

buffer

If set to `true`, `sys.stdout` and `sys.stderr` will be buffered in between `startTest()` and `stopTest()` being called. Collected output will only be echoed onto the real `sys.stdout` and `sys.stderr` if the test fails or errors. Any output is also attached to the failure / error message.

버전 2.7에 추가.

failfast

If set to `true` `stop()` will be called on the first failure or error, halting the test run.

버전 2.7에 추가.

wasSuccessful()

Return `True` if all tests run so far have passed, otherwise returns `False`.

stop()

This method can be called to signal that the set of tests being run should be aborted by setting the `shouldStop` attribute to `True`. `TestRunner` objects should respect this flag and return without running any additional tests.

For example, this feature is used by the `TextTestRunner` class to stop the test framework when the user signals an interrupt from the keyboard. Interactive tools which provide `TestRunner` implementations can use this in a similar manner.

The following methods of the `TestResult` class are used to maintain the internal data structures, and may be extended in subclasses to support additional reporting requirements. This is particularly useful in building tools which support interactive reporting while tests are being run.

startTest (*test*)

Called when the test case *test* is about to be run.

stopTest (*test*)

Called after the test case *test* has been executed, regardless of the outcome.

startTestRun ()

Called once before any tests are executed.

버전 2.7에 추가.

stopTestRun ()

Called once after all tests are executed.

버전 2.7에 추가.

addError (*test*, *err*)

Called when the test case *test* raises an unexpected exception. *err* is a tuple of the form returned by `sys.exc_info()`: (type, value, traceback).

The default implementation appends a tuple (*test*, *formatted_err*) to the instance's *errors* attribute, where *formatted_err* is a formatted traceback derived from *err*.

addFailure (*test*, *err*)

Called when the test case *test* signals a failure. *err* is a tuple of the form returned by `sys.exc_info()`: (type, value, traceback).

The default implementation appends a tuple (*test*, *formatted_err*) to the instance's *failures* attribute, where *formatted_err* is a formatted traceback derived from *err*.

addSuccess (*test*)

Called when the test case *test* succeeds.

The default implementation does nothing.

addSkip (*test*, *reason*)

Called when the test case *test* is skipped. *reason* is the reason the test gave for skipping.

The default implementation appends a tuple (*test*, *reason*) to the instance's *skipped* attribute.

addExpectedFailure (*test*, *err*)

Called when the test case *test* fails, but was marked with the `expectedFailure()` decorator.

The default implementation appends a tuple (*test*, *formatted_err*) to the instance's *expectedFailures* attribute, where *formatted_err* is a formatted traceback derived from *err*.

addUnexpectedSuccess (*test*)

Called when the test case *test* was marked with the `expectedFailure()` decorator, but succeeded.

The default implementation appends the test to the instance's *unexpectedSuccesses* attribute.

class `unittest.TextTestResult` (*stream*, *descriptions*, *verbosity*)

A concrete implementation of `TestResult` used by the `TextTestRunner`.

버전 2.7에 추가: This class was previously named `_TextTestResult`. The old name still exists as an alias but is deprecated.

`unittest.defaultTestLoader`

Instance of the `TestLoader` class intended to be shared. If no customization of the `TestLoader` is needed, this instance can be used instead of repeatedly creating new instances.

```
class unittest.TextTestRunner (stream=sys.stderr, descriptions=True, verbosity=1, failfast=False,
                                buffer=False, resultclass=None)
```

A basic test runner implementation which prints results on standard error. It has a few configurable parameters, but is essentially very simple. Graphical applications which run test suites should provide alternate implementations.

_makeResult()

This method returns the instance of `TestResult` used by `run()`. It is not intended to be called directly, but can be overridden in subclasses to provide a custom `TestResult`.

`_makeResult()` instantiates the class or callable passed in the `TextTestRunner` constructor as the `resultclass` argument. It defaults to `TextTestResult` if no `resultclass` is provided. The result class is instantiated with the following arguments:

```
stream, descriptions, verbosity
```

```
unittest.main([module[, defaultTest[, argv[, testRunner[, testLoader[, exit[, verbosity[, failfast[, catch-
break[, buffer]]]]]]]]]])
```

A command-line program that loads a set of tests from *module* and runs them; this is primarily for making test modules conveniently executable. The simplest use for this function is to include the following line at the end of a test script:

```
if __name__ == '__main__':
    unittest.main()
```

You can run tests with more detailed information by passing in the `verbosity` argument:

```
if __name__ == '__main__':
    unittest.main(verbosity=2)
```

The *defaultTest* argument is the name of the test to run if no test names are specified via *argv*. If not specified or `None` and no test names are provided via *argv*, all tests found in *module* are run.

The *argv* argument can be a list of options passed to the program, with the first element being the program name. If not specified or `None`, the values of `sys.argv` are used.

The *testRunner* argument can either be a test runner class or an already created instance of it. By default `main` calls `sys.exit()` with an exit code indicating success or failure of the tests run.

The *testLoader* argument has to be a `TestLoader` instance, and defaults to `defaultTestLoader`.

`main` supports being used from the interactive interpreter by passing in the argument `exit=False`. This displays the result on standard output without calling `sys.exit()`:

```
>>> from unittest import main
>>> main(module='test_module', exit=False)
```

The *failfast*, *catchbreak* and *buffer* parameters have the same effect as the same-name *command-line options*.

Calling `main` actually returns an instance of the `TestProgram` class. This stores the result of the tests run as the `result` attribute.

버전 2.7에서 변경: The *exit*, *verbosity*, *failfast*, *catchbreak* and *buffer* parameters were added.

load_tests Protocol

버전 2.7에 추가.

Modules or packages can customize how tests are loaded from them during normal test runs or test discovery by implementing a function called `load_tests`.

If a test module defines `load_tests` it will be called by `TestLoader.loadTestsFromModule()` with the following arguments:

```
load_tests(loader, standard_tests, None)
```

It should return a `TestSuite`.

`loader` is the instance of `TestLoader` doing the loading. `standard_tests` are the tests that would be loaded by default from the module. It is common for test modules to only want to add or remove tests from the standard set of tests. The third argument is used when loading packages as part of test discovery.

A typical `load_tests` function that loads tests from a specific set of `TestCase` classes may look like:

```
test_cases = (TestCase1, TestCase2, TestCase3)

def load_tests(loader, tests, pattern):
    suite = TestSuite()
    for test_class in test_cases:
        tests = loader.loadTestsFromTestCase(test_class)
        suite.addTests(tests)
    return suite
```

If discovery is started, either from the command line or by calling `TestLoader.discover()`, with a pattern that matches a package name then the package `__init__.py` will be checked for `load_tests`.

참고: The default pattern is `'test*.py'`. This matches all Python files that start with `'test '` but *won't* match any test directories.

A pattern like `'test*'` will match test packages as well as modules.

If the package `__init__.py` defines `load_tests` then it will be called and discovery not continued into the package. `load_tests` is called with the following arguments:

```
load_tests(loader, standard_tests, pattern)
```

This should return a `TestSuite` representing all the tests from the package. (`standard_tests` will only contain tests collected from `__init__.py`.)

Because the pattern is passed into `load_tests` the package is free to continue (and potentially modify) test discovery. A (do nothing) `load_tests` function for a test package would look like:

```
def load_tests(loader, standard_tests, pattern):
    # top level directory cached on loader instance
    this_dir = os.path.dirname(__file__)
    package_tests = loader.discover(start_dir=this_dir, pattern=pattern)
    standard_tests.addTests(package_tests)
    return standard_tests
```

25.3.8 Class and Module Fixtures

Class and module level fixtures are implemented in *TestSuite*. When the test suite encounters a test from a new class then `tearDownClass()` from the previous class (if there is one) is called, followed by `setUpClass()` from the new class.

Similarly if a test is from a different module from the previous test then `tearDownModule` from the previous module is run, followed by `setUpModule` from the new module.

After all the tests have run the final `tearDownClass` and `tearDownModule` are run.

Note that shared fixtures do not play well with [potential] features like test parallelization and they break test isolation. They should be used with care.

The default ordering of tests created by the unittest test loaders is to group all tests from the same modules and classes together. This will lead to `setUpClass` / `setUpModule` (etc) being called exactly once per class and module. If you randomize the order, so that tests from different modules and classes are adjacent to each other, then these shared fixture functions may be called multiple times in a single test run.

Shared fixtures are not intended to work with suites with non-standard ordering. A *BaseTestSuite* still exists for frameworks that don't want to support shared fixtures.

If there are any exceptions raised during one of the shared fixture functions the test is reported as an error. Because there is no corresponding test instance an `_ErrorHolder` object (that has the same interface as a *TestCase*) is created to represent the error. If you are just using the standard unittest test runner then this detail doesn't matter, but if you are a framework author it may be relevant.

`setUpClass` and `tearDownClass`

These must be implemented as class methods:

```
import unittest

class Test(unittest.TestCase):
    @classmethod
    def setUpClass(cls):
        cls._connection = createExpensiveConnectionObject()

    @classmethod
    def tearDownClass(cls):
        cls._connection.destroy()
```

If you want the `setUpClass` and `tearDownClass` on base classes called then you must call up to them yourself. The implementations in *TestCase* are empty.

If an exception is raised during a `setUpClass` then the tests in the class are not run and the `tearDownClass` is not run. Skipped classes will not have `setUpClass` or `tearDownClass` run. If the exception is a *SkipTest* exception then the class will be reported as having been skipped instead of as an error.

setUpModule and tearDownModule

These should be implemented as functions:

```
def setUpModule():
    createConnection()

def tearDownModule():
    closeConnection()
```

If an exception is raised in a `setUpModule` then none of the tests in the module will be run and the `tearDownModule` will not be run. If the exception is a `SkipTest` exception then the module will be reported as having been skipped instead of as an error.

25.3.9 Signal Handling

The `-c/--catch` command-line option to `unittest`, along with the `catchbreak` parameter to `unittest.main()`, provide more friendly handling of control-C during a test run. With catch break behavior enabled control-C will allow the currently running test to complete, and the test run will then end and report all the results so far. A second control-c will raise a `KeyboardInterrupt` in the usual way.

The control-c handling signal handler attempts to remain compatible with code or tests that install their own `signal.SIGINT` handler. If the `unittest` handler is called but *isn't* the installed `signal.SIGINT` handler, i.e. it has been replaced by the system under test and delegated to, then it calls the default handler. This will normally be the expected behavior by code that replaces an installed handler and delegates to it. For individual tests that need `unittest` control-c handling disabled the `removeHandler()` decorator can be used.

There are a few utility functions for framework authors to enable control-c handling functionality within test frameworks.

`unittest.installHandler()`

Install the control-c handler. When a `signal.SIGINT` is received (usually in response to the user pressing control-c) all registered results have `stop()` called.

버전 2.7에 추가.

`unittest.registerResult(result)`

Register a `TestResult` object for control-c handling. Registering a result stores a weak reference to it, so it doesn't prevent the result from being garbage collected.

Registering a `TestResult` object has no side-effects if control-c handling is not enabled, so test frameworks can unconditionally register all results they create independently of whether or not handling is enabled.

버전 2.7에 추가.

`unittest.removeResult(result)`

Remove a registered result. Once a result has been removed then `stop()` will no longer be called on that result object in response to a control-c.

버전 2.7에 추가.

`unittest.removeHandler(function=None)`

When called without arguments this function removes the control-c handler if it has been installed. This function can also be used as a test decorator to temporarily remove the handler while the test is being executed:

```
@unittest.removeHandler
def test_signal_handling(self):
    ...
```

버전 2.7에 추가.

25.4 2to3 - Automated Python 2 to 3 code translation

2to3 is a Python program that reads Python 2.x source code and applies a series of *fixers* to transform it into valid Python 3.x code. The standard library contains a rich set of fixers that will handle almost all code. 2to3 supporting library *lib2to3* is, however, a flexible and generic library, so it is possible to write your own fixers for 2to3. *lib2to3* could also be adapted to custom applications in which Python code needs to be edited automatically.

25.4.1 Using 2to3

2to3 will usually be installed with the Python interpreter as a script. It is also located in the `Tools/scripts` directory of the Python root.

2to3's basic arguments are a list of files or directories to transform. The directories are recursively traversed for Python sources.

Here is a sample Python 2.x source file, `example.py`:

```
def greet(name):
    print "Hello, {0}!".format(name)
print "What's your name?"
name = raw_input()
greet(name)
```

It can be converted to Python 3.x code via 2to3 on the command line:

```
$ 2to3 example.py
```

A diff against the original source file is printed. 2to3 can also write the needed modifications right back to the source file. (A backup of the original file is made unless `-n` is also given.) Writing the changes back is enabled with the `-w` flag:

```
$ 2to3 -w example.py
```

After transformation, `example.py` looks like this:

```
def greet(name):
    print("Hello, {0}!".format(name))
print("What's your name?")
name = input()
greet(name)
```

Comments and exact indentation are preserved throughout the translation process.

By default, 2to3 runs a set of *predefined fixers*. The `-l` flag lists all available fixers. An explicit set of fixers to run can be given with `-f`. Likewise the `-x` explicitly disables a fixer. The following example runs only the `imports` and `has_key` fixers:

```
$ 2to3 -f imports -f has_key example.py
```

This command runs every fixer except the `apply` fixer:

```
$ 2to3 -x apply example.py
```


Some fixers are *explicit*, meaning they aren't run by default and must be listed on the command line to be run. Here, in addition to the default fixers, the `idioms` fixer is run:

```
$ 2to3 -f all -f idioms example.py
```

Notice how passing `all` enables all default fixers.

Sometimes 2to3 will find a place in your source code that needs to be changed, but 2to3 cannot fix automatically. In this case, 2to3 will print a warning beneath the diff for a file. You should address the warning in order to have compliant 3.x code.

2to3 can also refactor doctests. To enable this mode, use the `-d` flag. Note that *only* doctests will be refactored. This also doesn't require the module to be valid Python. For example, doctest like examples in a reST document could also be refactored with this option.

The `-v` option enables output of more information on the translation process.

Since some print statements can be parsed as function calls or statements, 2to3 cannot always read files containing the print function. When 2to3 detects the presence of the `from __future__ import print_function` compiler directive, it modifies its internal grammar to interpret `print()` as a function. This change can also be enabled manually with the `-p` flag. Use `-p` to run fixers on code that already has had its print statements converted.

The `-o` or `--output-dir` option allows specification of an alternate directory for processed output files to be written to. The `-n` flag is required when using this as backup files do not make sense when not overwriting the input files.

버전 2.7.3에 추가: The `-o` option was added.

The `-W` or `--write-unchanged-files` flag tells 2to3 to always write output files even if no changes were required to the file. This is most useful with `-o` so that an entire Python source tree is copied with translation from one directory to another. This option implies the `-w` flag as it would not make sense otherwise.

버전 2.7.3에 추가: The `-W` flag was added.

The `--add-suffix` option specifies a string to append to all output filenames. The `-n` flag is required when specifying this as backups are not necessary when writing to different filenames. Example:

```
$ 2to3 -n -W --add-suffix=3 example.py
```

Will cause a converted file named `example.py3` to be written.

버전 2.7.3에 추가: The `--add-suffix` option was added.

To translate an entire project from one directory tree to another use:

```
$ 2to3 --output-dir=python3-version/mycode -W -n python2-version/mycode
```

25.4.2 Fixers

Each step of transforming code is encapsulated in a fixer. The command `2to3 -l` lists them. As *documented above*, each can be turned on and off individually. They are described here in more detail.

apply

Removes usage of `apply()`. For example `apply(function, *args, **kwargs)` is converted to `function(*args, **kwargs)`.

asserts

Replaces deprecated `unittest` method names with the correct ones.

From	To
<code>failUnlessEqual(a, b)</code>	<code>assertEqual(a, b)</code>
<code>assertEquals(a, b)</code>	<code>assertEqual(a, b)</code>
<code>failIfEqual(a, b)</code>	<code>assertNotEqual(a, b)</code>
<code>assertNotEquals(a, b)</code>	<code>assertNotEqual(a, b)</code>
<code>failUnless(a)</code>	<code>assertTrue(a)</code>
<code>assert_(a)</code>	<code>assertTrue(a)</code>
<code>failIf(a)</code>	<code>assertFalse(a)</code>
<code>failUnlessRaises(exc, cal)</code>	<code>assertRaises(exc, cal)</code>
<code>failUnlessAlmostEqual(a, b)</code>	<code>assertAlmostEqual(a, b)</code>
<code>assertAlmostEquals(a, b)</code>	<code>assertAlmostEqual(a, b)</code>
<code>failIfAlmostEqual(a, b)</code>	<code>assertNotAlmostEqual(a, b)</code>
<code>assertNotAlmostEquals(a, b)</code>	<code>assertNotAlmostEqual(a, b)</code>

basestring

Converts *basestring* to *str*.

buffer

Converts *buffer* to *memoryview*. This fixer is optional because the *memoryview* API is similar but not exactly the same as that of *buffer*.

dict

Fixes dictionary iteration methods. *dict.iteritems()* is converted to *dict.items()*, *dict.iterkeys()* to *dict.keys()*, and *dict.itervalues()* to *dict.values()*. Similarly, *dict.viewitems()*, *dict.viewkeys()* and *dict.viewvalues()* are converted respectively to *dict.items()*, *dict.keys()* and *dict.values()*. It also wraps existing usages of *dict.items()*, *dict.keys()*, and *dict.values()* in a call to *list*.

except

Converts `except X, T` to `except X as T`.

exec

Converts the `exec` statement to the `exec()` function.

execfile

Removes usage of *execfile()*. The argument to *execfile()* is wrapped in calls to *open()*, *compile()*, and *exec()*.

exitfunc

Changes assignment of *sys.exitfunc* to use of the *atexit* module.

filter

Wraps *filter()* usage in a *list* call.

funcattrs

Fixes function attributes that have been renamed. For example, *my_function.func_closure* is converted to *my_function.__closure__*.

future

Removes from `__future__ import new_feature` statements.

getcwdu

Renames *os.getcwdu()* to *os.getcwd()*.

has_key

Changes *dict.has_key(key)* to *key in dict*.

idioms

This optional fixer performs several transformations that make Python code more idiomatic. Type comparisons like `type(x) is SomeClass` and `type(x) == SomeClass` are converted to `isinstance(x, SomeClass)`. `while 1` becomes `while True`. This fixer also tries to make use of `sorted()` in appropriate places. For example, this block

```
L = list(some_iterable)
L.sort()
```

is changed to

```
L = sorted(some_iterable)
```

import

Detects sibling imports and converts them to relative imports.

imports

Handles module renames in the standard library.

imports2

Handles other modules renames in the standard library. It is separate from the `imports` fixer only because of technical limitations.

input

Converts `input(prompt)` to `eval(input(prompt))`.

intern

Converts `intern()` to `sys.intern()`.

isinstance

Fixes duplicate types in the second argument of `isinstance()`. For example, `isinstance(x, (int, int))` is converted to `isinstance(x, (int))`.

itertools_imports

Removes imports of `itertools.ifilter()`, `itertools.izip()`, and `itertools.imap()`. Imports of `itertools.ifilterfalse()` are also changed to `itertools.filterfalse()`.

itertools

Changes usage of `itertools.ifilter()`, `itertools.izip()`, and `itertools.imap()` to their built-in equivalents. `itertools.ifilterfalse()` is changed to `itertools.filterfalse()`.

long

Renames `long` to `int`.

map

Wraps `map()` in a list call. It also changes `map(None, x)` to `list(x)`. Using `from future_builtins import map` disables this fixer.

metaclass

Converts the old metaclass syntax (`__metaclass__ = Meta` in the class body) to the new (`class X(metaclass=Meta)`).

methodattrs

Fixes old method attribute names. For example, `meth.im_func` is converted to `meth.__func__`.

ne

Converts the old not-equal syntax, `<>`, to `!=`.

next

Converts the use of iterator's `next()` methods to the `next()` function. It also renames `next()` methods to `__next__()`.

nonzero

Renames `__nonzero__()` to `__bool__()`.

numliterals

Converts octal literals into the new syntax.

paren

Add extra parenthesis where they are required in list comprehensions. For example, `[x for x in 1, 2]` becomes `[x for x in (1, 2)]`.

print

Converts the `print` statement to the `print()` function.

raise

Converts `raise E, V` to `raise E(V)`, and `raise E, V, T` to `raise E(V).with_traceback(T)`. If `E` is a tuple, the translation will be incorrect because substituting tuples for exceptions has been removed in Python 3.

raw_input

Converts `raw_input()` to `input()`.

reduce

Handles the move of `reduce()` to `functools.reduce()`.

renames

Changes `sys.maxint` to `sys.maxsize`.

repr

Replaces backtick `repr` with the `repr()` function.

set_literal

Replaces use of the `set` constructor with set literals. This fixer is optional.

standarderror

Renames `StandardError` to `Exception`.

sys_exc

Changes the deprecated `sys.exc_value`, `sys.exc_type`, `sys.exc_traceback` to use `sys.exc_info()`.

throw

Fixes the API change in generator's `throw()` method.

tuple_params

Removes implicit tuple parameter unpacking. This fixer inserts temporary variables.

types

Fixes code broken from the removal of some members in the `types` module.

unicode

Renames `unicode` to `str`.

urllib

Handles the rename of `urllib` and `urllib2` to the `urllib` package.

ws_comma

Removes excess whitespace from comma separated items. This fixer is optional.

xrange

Renames `xrange()` to `range()` and wraps existing `range()` calls with `list`.

xreadlines

Changes `for x in file.xreadlines()` to `for x in file`.

zip

Wraps `zip()` usage in a list call. This is disabled when `from future_builtins import zip` appears.

25.4.3 lib2to3 - 2to3's library

참고: The `lib2to3` API should be considered unstable and may change drastically in the future.

25.5 test — Regression tests package for Python

참고: The `test` package is meant for internal use by Python only. It is documented for the benefit of the core developers of Python. Any use of this package outside of Python's standard library is discouraged as code mentioned here can change or be removed without notice between releases of Python.

The `test` package contains all regression tests for Python as well as the modules `test.support` and `test.regrtest`. `test.support` is used to enhance your tests while `test.regrtest` drives the testing suite.

Each module in the `test` package whose name starts with `test_` is a testing suite for a specific module or feature. All new tests should be written using the `unittest` or `doctest` module. Some older tests are written using a «traditional» testing style that compares output printed to `sys.stdout`; this style of test is considered deprecated.

더 보기:

Module `unittest` Writing PyUnit regression tests.

Module `doctest` Tests embedded in documentation strings.

25.5.1 Writing Unit Tests for the test package

It is preferred that tests that use the `unittest` module follow a few guidelines. One is to name the test module by starting it with `test_` and end it with the name of the module being tested. The test methods in the test module should start with `test_` and end with a description of what the method is testing. This is needed so that the methods are recognized by the test driver as test methods. Also, no documentation string for the method should be included. A comment (such as `# Tests function returns only True or False`) should be used to provide documentation for test methods. This is done because documentation strings get printed out if they exist and thus what test is being run is not stated.

A basic boilerplate is often used:

```
import unittest
from test import support

class MyTestCase1(unittest.TestCase):

    # Only use setUp() and tearDown() if necessary

    def setUp(self):
        ... code to execute in preparation for tests ...

    def tearDown(self):
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    ... code to execute to clean up after tests ...

    def test_feature_one(self):
        # Test feature one.
        ... testing code ...

    def test_feature_two(self):
        # Test feature two.
        ... testing code ...

    ... more test methods ...

class MyTestCase2(unittest.TestCase):
    ... same structure as MyTestCase1 ...

... more test classes ...

def test_main():
    support.run_unittest(MyTestCase1,
                        MyTestCase2,
                        ... list other tests ...
                        )

if __name__ == '__main__':
    test_main()

```

This boilerplate code allows the testing suite to be run by `test.regrtest` as well as on its own as a script.

The goal for regression testing is to try to break code. This leads to a few guidelines to be followed:

- The testing suite should exercise all classes, functions, and constants. This includes not just the external API that is to be presented to the outside world but also 《private》 code.
- Whitebox testing (examining the code being tested when the tests are being written) is preferred. Blackbox testing (testing only the published user interface) is not complete enough to make sure all boundary and edge cases are tested.
- Make sure all possible values are tested including invalid ones. This makes sure that not only all valid values are acceptable but also that improper values are handled correctly.
- Exhaust as many code paths as possible. Test where branching occurs and thus tailor input to make sure as many different paths through the code are taken.
- Add an explicit test for any bugs discovered for the tested code. This will make sure that the error does not crop up again if the code is changed in the future.
- Make sure to clean up after your tests (such as close and remove all temporary files).
- If a test is dependent on a specific condition of the operating system then verify the condition already exists before attempting the test.
- Import as few modules as possible and do it as soon as possible. This minimizes external dependencies of tests and also minimizes possible anomalous behavior from side-effects of importing a module.
- Try to maximize code reuse. On occasion, tests will vary by something as small as what type of input is used. Minimize code duplication by subclassing a basic test class with a class that specifies the input:

```
class TestFuncAcceptsSequences(unittest.TestCase):
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

func = mySuperWhammyFunction

def test_func(self):
    self.func(self.arg)

class AcceptLists(TestFuncAcceptsSequences):
    arg = [1, 2, 3]

class AcceptStrings(TestFuncAcceptsSequences):
    arg = 'abc'

class AcceptTuples(TestFuncAcceptsSequences):
    arg = (1, 2, 3)

```

더 보기:

Test Driven Development A book by Kent Beck on writing tests before code.

25.5.2 Running tests using the command-line interface

The `test.regrtest` module can be run as a script to drive Python's regression test suite, thanks to the `-m` option: **python -m test.regrtest**. Running the script by itself automatically starts running all regression tests in the `test` package. It does this by finding all modules in the package whose name starts with `test_`, importing them, and executing the function `test_main()` if present. The names of tests to execute may also be passed to the script. Specifying a single regression test (**python -m test.regrtest test_spam**) will minimize output and only print whether the test passed or failed and thus minimize output.

Running `test.regrtest` directly allows what resources are available for tests to use to be set. You do this by using the `-u` command-line option. Specifying `all` as the value for the `-u` option enables all possible resources: **python -m test.regrtest -uall**. If all but one resource is desired (a more common case), a comma-separated list of resources that are not desired may be listed after `all`. The command **python -m test.regrtest -uall, -audio, -largefile** will run `test.regrtest` with all resources except the `audio` and `largefile` resources. For a list of all resources and more command-line options, run **python -m test.regrtest -h**.

Some other ways to execute the regression tests depend on what platform the tests are being executed on. On Unix, you can run **make test** at the top-level directory where Python was built. On Windows, executing **rt.bat** from your PCBuild directory will run all regression tests.

버전 2.7.14에서 변경: The `test` package can be run as a script: **python -m test**. This works the same as running the `test.regrtest` module.

25.6 test.support — Utility functions for tests

참고: The `test.test_support` module has been renamed to `test.support` in Python 3.x and 2.7.14. The name `test.test_support` has been retained as an alias in 2.7.

The `test.support` module provides support for Python's regression tests.

This module defines the following exceptions:

exception `test.support.TestFailed`

Exception to be raised when a test fails. This is deprecated in favor of `unittest`-based tests and `unittest.TestCase`'s assertion methods.

exception `test.support.ResourceDenied`

Subclass of `unittest.SkipTest`. Raised when a resource (such as a network connection) is not available. Raised by the `requires()` function.

The `test.support` module defines the following constants:

`test.support.verbose`

`True` when verbose output is enabled. Should be checked when more detailed information is desired about a running test. `verbose` is set by `test.regrtest`.

`test.support.have_unicode`

`True` when Unicode support is available.

`test.support.is_jython`

`True` if the running interpreter is Jython.

`test.support.TESTFN`

Set to a name that is safe to use as the name of a temporary file. Any temporary file that is created should be closed and unlinked (removed).

`test.support.TEST_HTTP_URL`

Define the URL of a dedicated HTTP server for the network tests.

The `test.support` module defines the following functions:

`test.support.forget(module_name)`

Remove the module named `module_name` from `sys.modules` and delete any byte-compiled files of the module.

`test.support.is_resource_enabled(resource)`

Return `True` if `resource` is enabled and available. The list of available resources is only set when `test.regrtest` is executing the tests.

`test.support.requires(resource[, msg])`

Raise `ResourceDenied` if `resource` is not available. `msg` is the argument to `ResourceDenied` if it is raised. Always returns `True` if called by a function whose `__name__` is `'__main__'`. Used when tests are executed by `test.regrtest`.

`test.support.findfile(filename)`

Return the path to the file named `filename`. If no match is found `filename` is returned. This does not equal a failure since it could be the path to the file.

`test.support.run_unittest(*classes)`

Execute `unittest.TestCase` subclasses passed to the function. The function scans the classes for methods starting with the prefix `test_` and executes the tests individually.

It is also legal to pass strings as parameters; these should be keys in `sys.modules`. Each associated module will be scanned by `unittest.TestLoader.loadTestsFromModule()`. This is usually seen in the following `test_main()` function:

```
def test_main():
    support.run_unittest(__name__)
```

This will run all tests defined in the named module.

`test.support.check_warnings(*filters, quiet=True)`

A convenience wrapper for `warnings.catch_warnings()` that makes it easier to test that a warning was correctly raised. It is approximately equivalent to calling `warnings.catch_warnings(record=True)` with `warnings.simplefilter()` set to `always` and with the option to automatically validate the results that are recorded.

`check_warnings` accepts 2-tuples of the form `("message regexp", WarningCategory)` as positional arguments. If one or more `filters` are provided, or if the optional keyword argument `quiet` is `False`, it checks

to make sure the warnings are as expected: each specified filter must match at least one of the warnings raised by the enclosed code or the test fails, and if any warnings are raised that do not match any of the specified filters the test fails. To disable the first of these checks, set *quiet* to *True*.

If no arguments are specified, it defaults to:

```
check_warnings(("", Warning), quiet=True)
```

In this case all warnings are caught and no errors are raised.

On entry to the context manager, a `WarningRecorder` instance is returned. The underlying warnings list from `catch_warnings()` is available via the recorder object's `warnings` attribute. As a convenience, the attributes of the object representing the most recent warning can also be accessed directly through the recorder object (see example below). If no warning has been raised, then any of the attributes that would otherwise be expected on an object representing a warning will return *None*.

The recorder object also has a `reset()` method, which clears the warnings list.

The context manager is designed to be used like this:

```
with check_warnings(("assertion is always true", SyntaxWarning),
                    ("", UserWarning)):
    exec('assert(False, "Hey!")')
    warnings.warn(UserWarning("Hide me!"))
```

In this case if either warning was not raised, or some other warning was raised, `check_warnings()` would raise an error.

When a test needs to look more deeply into the warnings, rather than just checking whether or not they occurred, code like this can be used:

```
with check_warnings(quiet=True) as w:
    warnings.warn("foo")
    assert str(w.args[0]) == "foo"
    warnings.warn("bar")
    assert str(w.args[0]) == "bar"
    assert str(w.warnings[0].args[0]) == "foo"
    assert str(w.warnings[1].args[0]) == "bar"
    w.reset()
    assert len(w.warnings) == 0
```

Here all warnings will be caught, and the test code tests the captured warnings directly.

버전 2.6에 추가.

버전 2.7에서 변경: New optional arguments *filters* and *quiet*.

`test.support.check_py3k_warnings(*filters, quiet=False)`

Similar to `check_warnings()`, but for Python 3 compatibility warnings. If `sys.py3kwarning == 1`, it checks if the warning is effectively raised. If `sys.py3kwarning == 0`, it checks that no warning is raised. It accepts 2-tuples of the form ("message regexp", `WarningCategory`) as positional arguments. When the optional keyword argument *quiet* is *True*, it does not fail if a filter catches nothing. Without arguments, it defaults to:

```
check_py3k_warnings(("", DeprecationWarning), quiet=False)
```

버전 2.7에 추가.

`test.support.captured_stdout()`

This is a context manager that runs the `with` statement body using a `StringIO.StringIO` object as `sys.stdout`. That object can be retrieved using the `as` clause of the `with` statement.

Example use:

```
with captured_stdout() as s:
    print "hello"
assert s.getvalue() == "hello\n"
```

버전 2.6에 추가.

`test.support.import_module(name, deprecated=False)`

This function imports and returns the named module. Unlike a normal import, this function raises `unittest.SkipTest` if the module cannot be imported.

Module and package deprecation messages are suppressed during this import if `deprecated` is `True`.

버전 2.7에 추가.

`test.support.import_fresh_module(name, fresh=(), blocked=(), deprecated=False)`

This function imports and returns a fresh copy of the named Python module by removing the named module from `sys.modules` before doing the import. Note that unlike `reload()`, the original module is not affected by this operation.

`fresh` is an iterable of additional module names that are also removed from the `sys.modules` cache before doing the import.

`blocked` is an iterable of module names that are replaced with 0 in the module cache during the import to ensure that attempts to import them raise `ImportError`.

The named module and any modules named in the `fresh` and `blocked` parameters are saved before starting the import and then reinserted into `sys.modules` when the fresh import is complete.

Module and package deprecation messages are suppressed during this import if `deprecated` is `True`.

This function will raise `unittest.SkipTest` if the named module cannot be imported.

Example use:

```
# Get copies of the warnings module for testing without
# affecting the version being used by the rest of the test suite
# One copy uses the C implementation, the other is forced to use
# the pure Python fallback implementation
py_warnings = import_fresh_module('warnings', blocked=['_warnings'])
c_warnings = import_fresh_module('warnings', fresh=['_warnings'])
```

버전 2.7에 추가.

The `test.support` module defines the following classes:

class `test.support.TransientResource` (`exc[, **kwargs]`)

Instances are a context manager that raises `ResourceDenied` if the specified exception type is raised. Any keyword arguments are treated as attribute/value pairs to be compared against any exception raised within the `with` statement. Only if all pairs match properly against attributes on the exception is `ResourceDenied` raised.

버전 2.6에 추가.

class `test.support.EnvironmentVarGuard`

Class used to temporarily set or unset environment variables. Instances can be used as a context manager and have a complete dictionary interface for querying/modifying the underlying `os.environ`. After exit from the context manager all changes to environment variables done through this instance will be rolled back.

버전 2.6에 추가.

버전 2.7에서 변경: Added dictionary interface.

`EnvironmentVarGuard.set(envvar, value)`

Temporarily set the environment variable `envvar` to the value of `value`.

`EnvironmentVarGuard.unset(envvar)`

Temporarily unset the environment variable `envvar`.

class `test.support.WarningsRecorder`

Class used to record warnings for unit tests. See documentation of `check_warnings()` above for more details.

버전 2.6에 추가.

Debugging and Profiling

These libraries help you with Python development: the debugger enables you to step through code, analyze stack frames and set breakpoints etc., and the profilers run code and give you a detailed breakdown of execution times, allowing you to identify bottlenecks in your programs.

26.1 `bdb` — Debugger framework

Source code: [Lib/bdb.py](#)

The `bdb` module handles basic debugger functions, like setting breakpoints or managing execution via the debugger.

The following exception is defined:

exception `bdb.BdbQuit`

Exception raised by the `Bdb` class for quitting the debugger.

The `bdb` module also defines two classes:

class `bdb.Breakpoint` (*self, file, line, temporary=0, cond=None, funcname=None*)

This class implements temporary breakpoints, ignore counts, disabling and (re-)enabling, and conditionals.

Breakpoints are indexed by number through a list called `bpbynumber` and by (`file`, `line`) pairs through `bplist`. The former points to a single instance of class `Breakpoint`. The latter points to a list of such instances since there may be more than one breakpoint per line.

When creating a breakpoint, its associated filename should be in canonical form. If a *funcname* is defined, a breakpoint hit will be counted when the first line of that function is executed. A conditional breakpoint always counts a hit.

`Breakpoint` instances have the following methods:

deleteMe ()

Delete the breakpoint from the list associated to a file/line. If it is the last breakpoint in that position, it also deletes the entry for the file/line.

enable()

Mark the breakpoint as enabled.

disable()

Mark the breakpoint as disabled.

pprint([out])

Print all the information about the breakpoint:

- The breakpoint number.
- If it is temporary or not.
- Its file, line position.
- The condition that causes a break.
- If it must be ignored the next N times.
- The breakpoint hit count.

class bdb.Bdb(skip=None)

The *Bdb* class acts as a generic Python debugger base class.

This class takes care of the details of the trace facility; a derived class should implement user interaction. The standard debugger class (*pdb.Pdb*) is an example.

The *skip* argument, if given, must be an iterable of glob-style module name patterns. The debugger will not step into frames that originate in a module that matches one of these patterns. Whether a frame is considered to originate in a certain module is determined by the `__name__` in the frame globals.

버전 2.7에 추가: The *skip* argument.

The following methods of *Bdb* normally don't need to be overridden.

canonic(filename)

Auxiliary method for getting a filename in a canonical form, that is, as a case-normalized (on case-insensitive filesystems) absolute path, stripped of surrounding angle brackets.

reset()

Set the `botframe`, `stopframe`, `returnframe` and `quitting` attributes with values ready to start debugging.

trace_dispatch(frame, event, arg)

This function is installed as the trace function of debugged frames. Its return value is the new trace function (in most cases, that is, itself).

The default implementation decides how to dispatch a frame, depending on the type of event (passed as a string) that is about to be executed. *event* can be one of the following:

- "line": A new line of code is going to be executed.
- "call": A function is about to be called, or another code block entered.
- "return": A function or other code block is about to return.
- "exception": An exception has occurred.
- "c_call": A C function is about to be called.
- "c_return": A C function has returned.
- "c_exception": A C function has raised an exception.

For the Python events, specialized functions (see below) are called. For the C events, no action is taken.

The *arg* parameter depends on the previous event.

See the documentation for `sys.settrace()` for more information on the trace function. For more information on code and frame objects, refer to types.

dispatch_line (*frame*)

If the debugger should stop on the current line, invoke the `user_line()` method (which should be overridden in subclasses). Raise a `BdbQuit` exception if the `Bdb.quitting` flag is set (which can be set from `user_line()`). Return a reference to the `trace_dispatch()` method for further tracing in that scope.

dispatch_call (*frame*, *arg*)

If the debugger should stop on this function call, invoke the `user_call()` method (which should be overridden in subclasses). Raise a `BdbQuit` exception if the `Bdb.quitting` flag is set (which can be set from `user_call()`). Return a reference to the `trace_dispatch()` method for further tracing in that scope.

dispatch_return (*frame*, *arg*)

If the debugger should stop on this function return, invoke the `user_return()` method (which should be overridden in subclasses). Raise a `BdbQuit` exception if the `Bdb.quitting` flag is set (which can be set from `user_return()`). Return a reference to the `trace_dispatch()` method for further tracing in that scope.

dispatch_exception (*frame*, *arg*)

If the debugger should stop at this exception, invokes the `user_exception()` method (which should be overridden in subclasses). Raise a `BdbQuit` exception if the `Bdb.quitting` flag is set (which can be set from `user_exception()`). Return a reference to the `trace_dispatch()` method for further tracing in that scope.

Normally derived classes don't override the following methods, but they may if they want to redefine the definition of stopping and breakpoints.

stop_here (*frame*)

This method checks if the *frame* is somewhere below `botframe` in the call stack. `botframe` is the frame in which debugging started.

break_here (*frame*)

This method checks if there is a breakpoint in the filename and line belonging to *frame* or, at least, in the current function. If the breakpoint is a temporary one, this method deletes it.

break_anywhere (*frame*)

This method checks if there is a breakpoint in the filename of the current frame.

Derived classes should override these methods to gain control over debugger operation.

user_call (*frame*, *argument_list*)

This method is called from `dispatch_call()` when there is the possibility that a break might be necessary anywhere inside the called function.

user_line (*frame*)

This method is called from `dispatch_line()` when either `stop_here()` or `break_here()` yields True.

user_return (*frame*, *return_value*)

This method is called from `dispatch_return()` when `stop_here()` yields True.

user_exception (*frame*, *exc_info*)

This method is called from `dispatch_exception()` when `stop_here()` yields True.

do_clear (*arg*)

Handle how a breakpoint must be removed when it is a temporary one.

This method must be implemented by derived classes.

Derived classes and clients can call the following methods to affect the stepping state.

set_step ()

Stop after one line of code.

set_next (*frame*)

Stop on the next line in or below the given frame.

set_return (*frame*)

Stop when returning from the given frame.

set_until (*frame*)

Stop when the line with the line no greater than the current one is reached or when returning from current frame.

set_trace ([*frame*])

Start debugging from *frame*. If *frame* is not specified, debugging starts from caller's frame.

set_continue ()

Stop only at breakpoints or when finished. If there are no breakpoints, set the system trace function to `None`.

set_quit ()

Set the `quitting` attribute to `True`. This raises `BdbQuit` in the next call to one of the `dispatch_*` () methods.

Derived classes and clients can call the following methods to manipulate breakpoints. These methods return a string containing an error message if something went wrong, or `None` if all is well.

set_break (*filename*, *lineno*, *temporary=0*, *cond=None*, *funcname=None*)

Set a new breakpoint. If the *lineno* line doesn't exist for the *filename* passed as argument, return an error message. The *filename* should be in canonical form, as described in the `canonic` () method.

clear_break (*filename*, *lineno*)

Delete the breakpoints in *filename* and *lineno*. If none were set, an error message is returned.

clear_bpbynumber (*arg*)

Delete the breakpoint which has the index *arg* in the `Breakpoint.bpbynumber`. If *arg* is not numeric or out of range, return an error message.

clear_all_file_breaks (*filename*)

Delete all breakpoints in *filename*. If none were set, an error message is returned.

clear_all_breaks ()

Delete all existing breakpoints.

get_break (*filename*, *lineno*)

Check if there is a breakpoint for *lineno* of *filename*.

get_breaks (*filename*, *lineno*)

Return all breakpoints for *lineno* in *filename*, or an empty list if none are set.

get_file_breaks (*filename*)

Return all breakpoints in *filename*, or an empty list if none are set.

get_all_breaks ()

Return all breakpoints that are set.

Derived classes and clients can call the following methods to get a data structure representing a stack trace.

get_stack (*f*, *t*)

Get a list of records for a frame and all higher (calling) and lower frames, and the size of the higher part.

format_stack_entry (*frame_lineno*[, *lprefix*=' '])

Return a string with information about a stack entry, identified by a (*frame*, *lineno*) tuple:

- The canonical form of the filename which contains the frame.
- The function name, or "<lambda>".
- The input arguments.
- The return value.
- The line of code (if it exists).

The following two methods can be called by clients to use a debugger to debug a *statement*, given as a string.

run (*cmd* [, *globals* [, *locals*]])

Debug a statement executed via the `exec` statement. *globals* defaults to `__main__.__dict__`, *locals* defaults to *globals*.

runeval (*expr* [, *globals* [, *locals*]])

Debug an expression executed via the `eval()` function. *globals* and *locals* have the same meaning as in `run()`.

runtcx (*cmd*, *globals*, *locals*)

For backwards compatibility. Calls the `run()` method.

runcall (*func*, **args*, ***kwds*)

Debug a single function call, and return its result.

Finally, the module defines the following functions:

`bdb.checkfuncname` (*b*, *frame*)

Check whether we should break here, depending on the way the breakpoint *b* was set.

If it was set via line number, it checks if `b.line` is the same as the one in the frame also passed as argument. If the breakpoint was set via function name, we have to check we are in the right frame (the right function) and if we are in its first executable line.

`bdb.effective` (*file*, *line*, *frame*)

Determine if there is an effective (active) breakpoint at this line of code. Return a tuple of the breakpoint and a boolean that indicates if it is ok to delete a temporary breakpoint. Return `(None, None)` if there is no matching breakpoint.

`bdb.set_trace` ()

Start debugging with a `Bdb` instance from caller's frame.

26.2 pdb — The Python Debugger

Source code: [Lib/pdb.py](#)

The module `pdb` defines an interactive source code debugger for Python programs. It supports setting (conditional) breakpoints and single stepping at the source line level, inspection of stack frames, source code listing, and evaluation of arbitrary Python code in the context of any stack frame. It also supports post-mortem debugging and can be called under program control.

The debugger is extensible — it is actually defined as the class `Pdb`. This is currently undocumented but easily understood by reading the source. The extension interface uses the modules `bdb` and `cmd`.

The debugger's prompt is `(Pdb)`. Typical usage to run a program under control of the debugger is:

```
>>> import pdb
>>> import mymodule
>>> pdb.run('mymodule.test()')
> <string>(0)?()
(Pdb) continue
> <string>(1)?()
(Pdb) continue
NameError: 'spam'
> <string>(1)?()
(Pdb)
```

`pdb.py` can also be invoked as a script to debug other scripts. For example:

```
python -m pdb myscript.py
```

When invoked as a script, `pdb` will automatically enter post-mortem debugging if the program being debugged exits abnormally. After post-mortem debugging (or after normal exit of the program), `pdb` will restart the program. Automatic restarting preserves `pdb`'s state (such as breakpoints) and in most cases is more useful than quitting the debugger upon program's exit.

버전 2.4에 추가: Restarting post-mortem behavior added.

The typical usage to break into the debugger from a running program is to insert

```
import pdb; pdb.set_trace()
```

at the location you want to break into the debugger. You can then step through the code following this statement, and continue running without the debugger using the `c` command.

The typical usage to inspect a crashed program is:

```
>>> import pdb
>>> import mymodule
>>> mymodule.test()
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
  File "./mymodule.py", line 4, in test
    test2()
  File "./mymodule.py", line 3, in test2
    print spam
NameError: spam
>>> pdb.pm()
> ./mymodule.py(3)test2()
-> print spam
(Pdb)
```

The module defines the following functions; each enters the debugger in a slightly different way:

`pdb.run(statement[, globals[, locals]])`

Execute the *statement* (given as a string) under debugger control. The debugger prompt appears before any code is executed; you can set breakpoints and type `continue`, or you can step through the statement using `step` or `next` (all these commands are explained below). The optional *globals* and *locals* arguments specify the environment in which the code is executed; by default the dictionary of the module `__main__` is used. (See the explanation of the `exec` statement or the `eval()` built-in function.)

`pdb.runeval(expression[, globals[, locals]])`

Evaluate the *expression* (given as a string) under debugger control. When `runeval()` returns, it returns the value of the expression. Otherwise this function is similar to `run()`.

`pdb.runcall (function[, argument, ...])`
 Call the *function* (a function or method object, not a string) with the given arguments. When `runcall()` returns, it returns whatever the function call returned. The debugger prompt appears as soon as the function is entered.

`pdb.set_trace ()`
 Enter the debugger at the calling stack frame. This is useful to hard-code a breakpoint at a given point in a program, even if the code is not otherwise being debugged (e.g. when an assertion fails).

`pdb.post_mortem ([traceback])`
 Enter post-mortem debugging of the given *traceback* object. If no *traceback* is given, it uses the one of the exception that is currently being handled (an exception must be being handled if the default is to be used).

`pdb.pm ()`
 Enter post-mortem debugging of the traceback found in `sys.last_traceback`.

The `run*` functions and `set_trace()` are aliases for instantiating the `Pdb` class and calling the method of the same name. If you want to access further features, you have to do this yourself:

class `pdb.Pdb (completekey='tab', stdin=None, stdout=None, skip=None)`
Pdb is the debugger class.

The *completekey*, *stdin* and *stdout* arguments are passed to the underlying `cmd.Cmd` class; see the description there.

The *skip* argument, if given, must be an iterable of glob-style module name patterns. The debugger will not step into frames that originate in a module that matches one of these patterns.¹

Example call to enable tracing with *skip*:

```
import pdb; pdb.Pdb(skip=['django.*']).set_trace()
```

버전 2.7에 추가: The *skip* argument.

`run (statement[, globals[, locals]])`
`runeval (expression[, globals[, locals]])`
`runcall (function[, argument, ...])`
`set_trace ()`

See the documentation for the functions explained above.

26.3 Debugger Commands

The debugger recognizes the following commands. Most commands can be abbreviated to one or two letters; e.g. `h(elp)` means that either `h` or `help` can be used to enter the help command (but not `he` or `hel`, nor `H` or `Help` or `HELP`). Arguments to commands must be separated by whitespace (spaces or tabs). Optional arguments are enclosed in square brackets (`[]`) in the command syntax; the square brackets must not be typed. Alternatives in the command syntax are separated by a vertical bar (`|`).

Entering a blank line repeats the last command entered. Exception: if the last command was a `list` command, the next 11 lines are listed.

Commands that the debugger doesn't recognize are assumed to be Python statements and are executed in the context of the program being debugged. Python statements can also be prefixed with an exclamation point (`!`). This is a powerful way to inspect the program being debugged; it is even possible to change a variable or call a function. When an exception occurs in such a statement, the exception name is printed but the debugger's state is not changed.

Multiple commands may be entered on a single line, separated by `;;`. (A single `;` is not used as it is the separator for multiple commands in a line that is passed to the Python parser.) No intelligence is applied to separating the commands; the input is split at the first `;;` pair, even if it is in the middle of a quoted string.

¹ Whether a frame is considered to originate in a certain module is determined by the `__name__` in the frame `globals`.

The debugger supports aliases. Aliases can have parameters which allows one a certain level of adaptability to the context under examination.

If a file `.pdbrc` exists in the user's home directory or in the current directory, it is read in and executed as if it had been typed at the debugger prompt. This is particularly useful for aliases. If both files exist, the one in the home directory is read first and aliases defined there can be overridden by the local file.

h(elp) [command] Without argument, print the list of available commands. With a *command* as argument, print help about that command. `help pdb` displays the full documentation file; if the environment variable `PAGER` is defined, the file is piped through that command instead. Since the *command* argument must be an identifier, `help exec` must be entered to get help on the `!` command.

w(here) Print a stack trace, with the most recent frame at the bottom. An arrow indicates the current frame, which determines the context of most commands.

d(own) Move the current frame one level down in the stack trace (to a newer frame).

u(p) Move the current frame one level up in the stack trace (to an older frame).

b(reak) [[filename:]lineno | function[, condition]] With a *lineno* argument, set a break there in the current file. With a *function* argument, set a break at the first executable statement within that function. The line number may be prefixed with a filename and a colon, to specify a breakpoint in another file (probably one that hasn't been loaded yet). The file is searched on `sys.path`. Note that each breakpoint is assigned a number to which all the other breakpoint commands refer.

If a second argument is present, it is an expression which must evaluate to true before the breakpoint is honored.

Without argument, list all breaks, including for each breakpoint, the number of times that breakpoint has been hit, the current ignore count, and the associated condition if any.

tbreak [[filename:]lineno | function[, condition]] Temporary breakpoint, which is removed automatically when it is first hit. The arguments are the same as `break`.

cl(ear) [filename:lineno | bnumber [bnumber ...]] With a *filename:lineno* argument, clear all the breakpoints at this line. With a space separated list of breakpoint numbers, clear those breakpoints. Without argument, clear all breaks (but first ask confirmation).

disable [bnumber [bnumber ...]] Disables the breakpoints given as a space separated list of breakpoint numbers. Disabling a breakpoint means it cannot cause the program to stop execution, but unlike clearing a breakpoint, it remains in the list of breakpoints and can be (re-)enabled.

enable [bnumber [bnumber ...]] Enables the breakpoints specified.

ignore bnumber [count] Sets the ignore count for the given breakpoint number. If count is omitted, the ignore count is set to 0. A breakpoint becomes active when the ignore count is zero. When non-zero, the count is decremented each time the breakpoint is reached and the breakpoint is not disabled and any associated condition evaluates to true.

condition bnumber [condition] Condition is an expression which must evaluate to true before the breakpoint is honored. If condition is absent, any existing condition is removed; i.e., the breakpoint is made unconditional.

commands [bnumber] Specify a list of commands for breakpoint number *bnumber*. The commands themselves appear on the following lines. Type a line containing just `<end>` to terminate the commands. An example:

```
(Pdb) commands 1
(com) print some_variable
(com) end
(Pdb)
```

To remove all commands from a breakpoint, type `commands` and follow it immediately with `end`; that is, give no commands.

With no *bpnumber* argument, *commands* refers to the last breakpoint set.

You can use breakpoint commands to start your program up again. Simply use the *continue* command, or *step*, or any other command that resumes execution.

Specifying any command resuming execution (currently *continue*, *step*, *next*, *return*, *jump*, *quit* and their abbreviations) terminates the command list (as if that command was immediately followed by *end*). This is because any time you resume execution (even with a simple *next* or *step*), you may encounter another breakpoint—which could have its own command list, leading to ambiguities about which list to execute.

If you use the `<silent>` command in the command list, the usual message about stopping at a breakpoint is not printed. This may be desirable for breakpoints that are to print a specific message and then *continue*. If none of the other commands print anything, you see no sign that the breakpoint was reached.

버전 2.5에 추가.

s(step) Execute the current line, stop at the first possible occasion (either in a function that is called or on the next line in the current function).

n(ext) Continue execution until the next line in the current function is reached or it returns. (The difference between *next* and *step* is that *step* stops inside a called function, while *next* executes called functions at (nearly) full speed, only stopping at the next line in the current function.)

unt(il) Continue execution until the line with the line number greater than the current one is reached or when returning from current frame.

버전 2.6에 추가.

r(eturn) Continue execution until the current function returns.

c(ontinue) Continue execution, only stop when a breakpoint is encountered.

j(ump) lineno Set the next line that will be executed. Only available in the bottom-most frame. This lets you jump back and execute code again, or jump forward to skip code that you don't want to run.

It should be noted that not all jumps are allowed — for instance it is not possible to jump into the middle of a *for* loop or out of a *finally* clause.

l(list) [first[, last]] List source code for the current file. Without arguments, list 11 lines around the current line or continue the previous listing. With one argument, list 11 lines around at that line. With two arguments, list the given range; if the second argument is less than the first, it is interpreted as a count.

a(rgs) Print the argument list of the current function.

p expression Evaluate the *expression* in the current context and print its value.

참고: `print` can also be used, but is not a debugger command — this executes the Python `print` statement.

pp expression Like the *p* command, except the value of the expression is pretty-printed using the *pprint* module.

alias [name [command]] Creates an alias called *name* that executes *command*. The command must *not* be enclosed in quotes. Replaceable parameters can be indicated by `%1`, `%2`, and so on, while `.*` is replaced by all the parameters. If no command is given, the current alias for *name* is shown. If no arguments are given, all aliases are listed.

Aliases may be nested and can contain anything that can be legally typed at the *pdb* prompt. Note that internal *pdb* commands *can* be overridden by aliases. Such a command is then hidden until the alias is removed. Aliasing is recursively applied to the first word of the command line; all other words in the line are left alone.

As an example, here are two useful aliases (especially when placed in the `.pdbrc` file):

```
#Print instance variables (usage "pi classInst")
alias pi for k in %1.__dict__.keys(): print "%1.",k,"=",%1.__dict__[k]
#Print instance variables in self
alias ps pi self
```

unalias *name* Deletes the specified alias.

[!]statement Execute the (one-line) *statement* in the context of the current stack frame. The exclamation point can be omitted unless the first word of the statement resembles a debugger command. To set a global variable, you can prefix the assignment command with a `global` command on the same line, e.g.:

```
(Pdb) global list_options; list_options = ['-l']
(Pdb)
```

run [*args* ...] Restart the debugged Python program. If an argument is supplied, it is split with `shlex` and the result is used as the new `sys.argv`. History, breakpoints, actions and debugger options are preserved. `restart` is an alias for `run`.

버전 2.6에 추가.

q(uit) Quit from the debugger. The program being executed is aborted.

26.4 The Python Profilers

Source code: [Lib/profile.py](#) and [Lib/pstats.py](#)

26.4.1 Introduction to the profilers

`cProfile` and `profile` provide *deterministic profiling* of Python programs. A *profile* is a set of statistics that describes how often and for how long various parts of the program executed. These statistics can be formatted into reports via the `pstats` module.

The Python standard library provides three different implementations of the same profiling interface:

1. `cProfile` is recommended for most users; it's a C extension with reasonable overhead that makes it suitable for profiling long-running programs. Based on `lsprof`, contributed by Brett Rosen and Ted Czotter.

버전 2.5에 추가.

2. `profile`, a pure Python module whose interface is imitated by `cProfile`, but which adds significant overhead to profiled programs. If you're trying to extend the profiler in some way, the task might be easier with this module. Originally designed and written by Jim Roskind.

버전 2.4에서 변경: Now also reports the time spent in calls to built-in functions and methods.

3. `hotshot` was an experimental C module that focused on minimizing the overhead of profiling, at the expense of longer data post-processing times. It is no longer maintained and may be dropped in a future version of Python.

버전 2.5에서 변경: The results should be more meaningful than in the past: the timing core contained a critical bug.

The `profile` and `cProfile` modules export the same interface, so they are mostly interchangeable; `cProfile` has a much lower overhead but is newer and might not be available on all systems. `cProfile` is really a compatibility layer on top of the internal `_lsprof` module. The `hotshot` module is reserved for specialized usage.

참고: The profiler modules are designed to provide an execution profile for a given program, not for benchmarking purposes (for that, there is `timeit` for reasonably accurate results). This particularly applies to benchmarking Python code against C code: the profilers introduce overhead for Python code, but not for C-level functions, and so the C code would seem faster than any Python one.

26.4.2 Instant User's Manual

This section is provided for users that 《don't want to read the manual.》 It provides a very brief overview, and allows a user to rapidly perform profiling on an existing application.

To profile a function that takes a single argument, you can do:

```
import cProfile
import re
cProfile.run('re.compile("foo|bar")')
```

(Use `profile` instead of `cProfile` if the latter is not available on your system.)

The above action would run `re.compile()` and print profile results like the following:

```
197 function calls (192 primitive calls) in 0.002 seconds

Ordered by: standard name
```

ncalls	tottime	percall	cumtime	percall	filename:lineno(function)
1	0.000	0.000	0.001	0.001	<string>:1(<module>)
1	0.000	0.000	0.001	0.001	re.py:212(compile)
1	0.000	0.000	0.001	0.001	re.py:268(_compile)
1	0.000	0.000	0.000	0.000	sre_compile.py:172(_compile_charset)
1	0.000	0.000	0.000	0.000	sre_compile.py:201(_optimize_charset)
4	0.000	0.000	0.000	0.000	sre_compile.py:25(_identityfunction)
3/1	0.000	0.000	0.000	0.000	sre_compile.py:33(_compile)

The first line indicates that 197 calls were monitored. Of those calls, 192 were *primitive*, meaning that the call was not induced via recursion. The next line: `Ordered by: standard name`, indicates that the text string in the far right column was used to sort the output. The column headings include:

ncalls for the number of calls,

tottime for the total time spent in the given function (and excluding time made in calls to sub-functions)

percall is the quotient of `tottime` divided by `ncalls`

cumtime is the cumulative time spent in this and all subfunctions (from invocation till exit). This figure is accurate *even* for recursive functions.

percall is the quotient of `cumtime` divided by primitive calls

filename:lineno(function) provides the respective data of each function

When there are two numbers in the first column (for example 3/1), it means that the function recursed. The second value is the number of primitive calls and the former is the total number of calls. Note that when the function does not recurse, these two values are the same, and only the single figure is printed.

Instead of printing the output at the end of the profile run, you can save the results to a file by specifying a filename to the `run()` function:

```
import cProfile
import re
cProfile.run('re.compile("foo|bar")', 'restats')
```

The `pstats.Stats` class reads profile results from a file and formats them in various ways.

The file `cProfile` can also be invoked as a script to profile another script. For example:

```
python -m cProfile [-o output_file] [-s sort_order] myscript.py
```

`-o` writes the profile results to a file instead of to stdout

`-s` specifies one of the `sort_stats()` sort values to sort the output by. This only applies when `-o` is not supplied.

The `pstats` module's `Stats` class has a variety of methods for manipulating and printing the data saved into a profile results file:

```
import pstats
p = pstats.Stats('restats')
p.strip_dirs().sort_stats(-1).print_stats()
```

The `strip_dirs()` method removed the extraneous path from all the module names. The `sort_stats()` method sorted all the entries according to the standard module/line/name string that is printed. The `print_stats()` method printed out all the statistics. You might try the following sort calls:

```
p.sort_stats('name')
p.print_stats()
```

The first call will actually sort the list by function name, and the second call will print out the statistics. The following are some interesting calls to experiment with:

```
p.sort_stats('cumulative').print_stats(10)
```

This sorts the profile by cumulative time in a function, and then only prints the ten most significant lines. If you want to understand what algorithms are taking time, the above line is what you would use.

If you were looking to see what functions were looping a lot, and taking a lot of time, you would do:

```
p.sort_stats('time').print_stats(10)
```

to sort according to time spent within each function, and then print the statistics for the top ten functions.

You might also try:

```
p.sort_stats('file').print_stats('__init__')
```

This will sort all the statistics by file name, and then print out statistics for only the class init methods (since they are spelled with `__init__` in them). As one final example, you could try:

```
p.sort_stats('time', 'cum').print_stats(.5, 'init')
```

This line sorts statistics with a primary key of time, and a secondary key of cumulative time, and then prints out some of the statistics. To be specific, the list is first culled down to 50% (re: `.5`) of its original size, then only lines containing `init` are maintained, and that sub-sub-list is printed.

If you wondered what functions called the above functions, you could now (`p` is still sorted according to the last criteria) do:


```
p.print_callers(.5, 'init')
```

and you would get a list of callers for each of the listed functions.

If you want more functionality, you're going to have to read the manual, or guess what the following functions do:

```
p.print_callees()
p.add('restats')
```

Invoked as a script, the `pstats` module is a statistics browser for reading and examining profile dumps. It has a simple line-oriented interface (implemented using `cmd`) and interactive help.

26.4.3 profile and cProfile Module Reference

Both the `profile` and `cProfile` modules provide the following functions:

`profile.run(command, filename=None, sort=-1)`

This function takes a single argument that can be passed to the `exec()` function, and an optional file name. In all cases this routine executes:

```
exec(command, __main__.__dict__, __main__.__dict__)
```

and gathers profiling statistics from the execution. If no file name is present, then this function automatically creates a `Stats` instance and prints a simple profiling report. If the sort value is specified it is passed to this `Stats` instance to control how the results are sorted.

`profile.runctx(command, globals, locals, filename=None)`

This function is similar to `run()`, with added arguments to supply the globals and locals dictionaries for the `command` string. This routine executes:

```
exec(command, globals, locals)
```

and gathers profiling statistics as in the `run()` function above.

class `profile.Profile(timer=None, timeunit=0.0, subcalls=True, builtins=True)`

This class is normally only used if more precise control over profiling is needed than what the `cProfile.run()` function provides.

A custom timer can be supplied for measuring how long code takes to run via the `timer` argument. This must be a function that returns a single number representing the current time. If the number is an integer, the `timeunit` specifies a multiplier that specifies the duration of each unit of time. For example, if the timer returns times measured in thousands of seconds, the time unit would be `.001`.

Directly using the `Profile` class allows formatting profile results without writing the profile data to a file:

```
import cProfile, pstats, StringIO
pr = cProfile.Profile()
pr.enable()
# ... do something ...
pr.disable()
s = StringIO.StringIO()
sortby = 'cumulative'
ps = pstats.Stats(pr, stream=s).sort_stats(sortby)
ps.print_stats()
print s.getvalue()
```

enable()

Start collecting profiling data.

disable()
Stop collecting profiling data.

create_stats()
Stop collecting profiling data and record the results internally as the current profile.

print_stats(sort=-1)
Create a *Stats* object based on the current profile and print the results to stdout.

dump_stats(filename)
Write the results of the current profile to *filename*.

run(cmd)
Profile the *cmd* via `exec()`.

runctx(cmd, globals, locals)
Profile the *cmd* via `exec()` with the specified global and local environment.

runcall(func, *args, **kwargs)
Profile `func(*args, **kwargs)`

26.4.4 The Stats Class

Analysis of the profiler data is done using the *Stats* class.

class `pstats.Stats(*filenames or profile, stream=sys.stdout)`
This class constructor creates an instance of a 《statistics object》 from a *filename* (or list of filenames) or from a *Profile* instance. Output will be printed to the stream specified by *stream*.

The file selected by the above constructor must have been created by the corresponding version of *profile* or *cProfile*. To be specific, there is *no* file compatibility guaranteed with future versions of this profiler, and there is no compatibility with files produced by other profilers, or the same profiler run on a different operating system. If several files are provided, all the statistics for identical functions will be coalesced, so that an overall view of several processes can be considered in a single report. If additional files need to be combined with data in an existing *Stats* object, the `add()` method can be used.

Instead of reading the profile data from a file, a *cProfile.Profile* or *profile.Profile* object can be used as the profile data source.

Stats objects have the following methods:

strip_dirs()
This method for the *Stats* class removes all leading path information from file names. It is very useful in reducing the size of the printout to fit within (close to) 80 columns. This method modifies the object, and the stripped information is lost. After performing a strip operation, the object is considered to have its entries in a 《random》 order, as it was just after object initialization and loading. If `strip_dirs()` causes two function names to be indistinguishable (they are on the same line of the same filename, and have the same function name), then the statistics for these two entries are accumulated into a single entry.

add(*filenames)
This method of the *Stats* class accumulates additional profiling information into the current profiling object. Its arguments should refer to filenames created by the corresponding version of *profile.run()* or *cProfile.run()*. Statistics for identically named (re: file, line, name) functions are automatically accumulated into single function statistics.

dump_stats(filename)
Save the data loaded into the *Stats* object to a file named *filename*. The file is created if it does not exist, and is overwritten if it already exists. This is equivalent to the method of the same name on the *profile.Profile* and *cProfile.Profile* classes.

버전 2.3에 추가.

sort_stats (*keys)

This method modifies the *Stats* object by sorting it according to the supplied criteria. The argument is typically a string identifying the basis of a sort (example: 'time' or 'name').

When more than one key is provided, then additional keys are used as secondary criteria when there is equality in all keys selected before them. For example, `sort_stats('name', 'file')` will sort all the entries according to their function name, and resolve all ties (identical function names) by sorting by file name.

Abbreviations can be used for any key names, as long as the abbreviation is unambiguous. The following are the keys currently defined:

Valid Arg	Meaning
'calls'	call count
'cumulative'	cumulative time
'cumtime'	cumulative time
'file'	file name
'filename'	file name
'module'	file name
'ncalls'	call count
'pcalls'	primitive call count
'line'	line number
'name'	function name
'nfl'	name/file/line
'stdname'	standard name
'time'	internal time
'tottime'	internal time

Note that all sorts on statistics are in descending order (placing most time consuming items first), where as name, file, and line number searches are in ascending order (alphabetical). The subtle distinction between 'nfl' and 'stdname' is that the standard name is a sort of the name as printed, which means that the embedded line numbers get compared in an odd way. For example, lines 3, 20, and 40 would (if the file names were the same) appear in the string order 20, 3 and 40. In contrast, 'nfl' does a numeric compare of the line numbers. In fact, `sort_stats('nfl')` is the same as `sort_stats('name', 'file', 'line')`.

For backward-compatibility reasons, the numeric arguments -1, 0, 1, and 2 are permitted. They are interpreted as 'stdname', 'calls', 'time', and 'cumulative' respectively. If this old style format (numeric) is used, only one sort key (the numeric key) will be used, and additional arguments will be silently ignored.

reverse_order ()

This method for the *Stats* class reverses the ordering of the basic list within the object. Note that by default ascending vs descending order is properly selected based on the sort key of choice.

print_stats (*restrictions)

This method for the *Stats* class prints out a report as described in the `profile.run()` definition.

The order of the printing is based on the last `sort_stats()` operation done on the object (subject to caveats in `add()` and `strip_dirs()`).

The arguments provided (if any) can be used to limit the list down to the significant entries. Initially, the list is taken to be the complete set of profiled functions. Each restriction is either an integer (to select a count of lines), or a decimal fraction between 0.0 and 1.0 inclusive (to select a percentage of lines), or a regular expression (to pattern match the standard name that is printed. If several restrictions are provided, then they are applied sequentially. For example:

```
print_stats(.1, 'foo:')
```

would first limit the printing to first 10% of list, and then only print functions that were part of filename `.foo:`. In contrast, the command:

```
print_stats('foo:', .1)
```

would limit the list to all functions having file names `.foo:`, and then proceed to only print the first 10% of them.

print_callers (*restrictions)

This method for the *Stats* class prints a list of all functions that called each function in the profiled database. The ordering is identical to that provided by *print_stats()*, and the definition of the restricting argument is also identical. Each caller is reported on its own line. The format differs slightly depending on the profiler that produced the stats:

- With *profile*, a number is shown in parentheses after each caller to show how many times this specific call was made. For convenience, a second non-parenthesized number repeats the cumulative time spent in the function at the right.
- With *cProfile*, each caller is preceded by three numbers: the number of times this specific call was made, and the total and cumulative times spent in the current function while it was invoked by this specific caller.

print_callees (*restrictions)

This method for the *Stats* class prints a list of all function that were called by the indicated function. Aside from this reversal of direction of calls (re: called vs was called by), the arguments and ordering are identical to the *print_callers()* method.

26.4.5 What Is Deterministic Profiling?

Deterministic profiling is meant to reflect the fact that all *function call*, *function return*, and *exception* events are monitored, and precise timings are made for the intervals between these events (during which time the user's code is executing). In contrast, *statistical profiling* (which is not done by this module) randomly samples the effective instruction pointer, and deduces where time is being spent. The latter technique traditionally involves less overhead (as the code does not need to be instrumented), but provides only relative indications of where time is being spent.

In Python, since there is an interpreter active during execution, the presence of instrumented code is not required to do deterministic profiling. Python automatically provides a *hook* (optional callback) for each event. In addition, the interpreted nature of Python tends to add so much overhead to execution, that deterministic profiling tends to only add small processing overhead in typical applications. The result is that deterministic profiling is not that expensive, yet provides extensive run time statistics about the execution of a Python program.

Call count statistics can be used to identify bugs in code (surprising counts), and to identify possible inline-expansion points (high call counts). Internal time statistics can be used to identify 《hot loops》 that should be carefully optimized. Cumulative time statistics should be used to identify high level errors in the selection of algorithms. Note that the unusual handling of cumulative times in this profiler allows statistics for recursive implementations of algorithms to be directly compared to iterative implementations.

26.4.6 Limitations

One limitation has to do with accuracy of timing information. There is a fundamental problem with deterministic profilers involving accuracy. The most obvious restriction is that the underlying `clock` is only ticking at a rate (typically) of about .001 seconds. Hence no measurements will be more accurate than the underlying clock. If enough measurements are taken, then the `error` will tend to average out. Unfortunately, removing this first error induces a second source of error.

The second problem is that it `takes a while` from when an event is dispatched until the profiler's call to get the time actually *gets* the state of the clock. Similarly, there is a certain lag when exiting the profiler event handler from the time that the clock's value was obtained (and then squirreled away), until the user's code is once again executing. As a result, functions that are called many times, or call many functions, will typically accumulate this error. The error that accumulates in this fashion is typically less than the accuracy of the clock (less than one clock tick), but it *can* accumulate and become very significant.

The problem is more important with `profile` than with the lower-overhead `cProfile`. For this reason, `profile` provides a means of calibrating itself for a given platform so that this error can be probabilistically (on the average) removed. After the profiler is calibrated, it will be more accurate (in a least square sense), but it will sometimes produce negative numbers (when call counts are exceptionally low, and the gods of probability work against you :-).) Do *not* be alarmed by negative numbers in the profile. They should *only* appear if you have calibrated your profiler, and the results are actually better than without calibration.

26.4.7 Calibration

The profiler of the `profile` module subtracts a constant from each event handling time to compensate for the overhead of calling the time function, and socking away the results. By default, the constant is 0. The following procedure can be used to obtain a better constant for a given platform (see [Limitations](#)).

```
import profile
pr = profile.Profile()
for i in range(5):
    print pr.calibrate(10000)
```

The method executes the number of Python calls given by the argument, directly and again under the profiler, measuring the time for both. It then computes the hidden overhead per profiler event, and returns that as a float. For example, on a 1.8Ghz Intel Core i5 running Mac OS X, and using Python's `time.clock()` as the timer, the magical number is about 4.04e-6.

The object of this exercise is to get a fairly consistent result. If your computer is *very* fast, or your timer function has poor resolution, you might have to pass 100000, or even 1000000, to get consistent results.

When you have a consistent answer, there are three ways you can use it:¹

```
import profile

# 1. Apply computed bias to all Profile instances created hereafter.
profile.Profile.bias = your_computed_bias

# 2. Apply computed bias to a specific Profile instance.
pr = profile.Profile()
pr.bias = your_computed_bias

# 3. Specify computed bias in instance constructor.
pr = profile.Profile(bias=your_computed_bias)
```

¹ Prior to Python 2.2, it was necessary to edit the profiler source code to embed the bias as a literal number. You still can, but that method is no longer described, because no longer needed.

If you have a choice, you are better off choosing a smaller constant, and then your results will 《less often》 show up as negative in profile statistics.

26.4.8 Using a custom timer

If you want to change how current time is determined (for example, to force use of wall-clock time or elapsed process time), pass the timing function you want to the `Profile` class constructor:

```
pr = profile.Profile(your_time_func)
```

The resulting profiler will then call `your_time_func`. Depending on whether you are using `profile.Profile` or `cProfile.Profile`, `your_time_func`'s return value will be interpreted differently:

`profile.Profile` `your_time_func` should return a single number, or a list of numbers whose sum is the current time (like what `os.times()` returns). If the function returns a single time number, or the list of returned numbers has length 2, then you will get an especially fast version of the dispatch routine.

Be warned that you should calibrate the profiler class for the timer function that you choose (see [Calibration](#)). For most machines, a timer that returns a lone integer value will provide the best results in terms of low overhead during profiling. (`os.times()` is *pretty* bad, as it returns a tuple of floating point values). If you want to substitute a better timer in the cleanest fashion, derive a class and hardwire a replacement dispatch method that best handles your timer call, along with the appropriate calibration constant.

`cProfile.Profile` `your_time_func` should return a single number. If it returns integers, you can also invoke the class constructor with a second argument specifying the real duration of one unit of time. For example, if `your_integer_time_func` returns times measured in thousands of seconds, you would construct the `Profile` instance as follows:

```
pr = cProfile.Profile(your_integer_time_func, 0.001)
```

As the `cProfile.Profile` class cannot be calibrated, custom timer functions should be used with care and should be as fast as possible. For the best results with a custom timer, it might be necessary to hard-code it in the C source of the internal `_lsprof` module.

26.5 hotshot — High performance logging profiler

버전 2.2에 추가.

This module provides a nicer interface to the `_hotshot` C module. Hotshot is a replacement for the existing `profile` module. As it's written mostly in C, it should result in a much smaller performance impact than the existing `profile` module.

참고: The `hotshot` module focuses on minimizing the overhead while profiling, at the expense of long data post-processing times. For common usage it is recommended to use `cProfile` instead. `hotshot` is not maintained and might be removed from the standard library in the future.

버전 2.5에서 변경: The results should be more meaningful than in the past: the timing core contained a critical bug.

참고: The `hotshot` profiler does not yet work well with threads. It is useful to use an unthreaded script to run the profiler over the code you're interested in measuring if at all possible.

class `hotshot.Profile` (*logfile* [, *lineevents* [, *linetimings*]])

The profiler object. The argument *logfile* is the name of a log file to use for logged profile data. The argument *lineevents* specifies whether to generate events for every source line, or just on function call/return. It defaults to 0 (only log function call/return). The argument *linetimings* specifies whether to record timing information. It defaults to 1 (store timing information).

26.5.1 Profile Objects

Profile objects have the following methods:

`Profile.addinfo` (*key*, *value*)

Add an arbitrary labelled value to the profile output.

`Profile.close` ()

Close the logfile and terminate the profiler.

`Profile.fileno` ()

Return the file descriptor of the profiler's log file.

`Profile.run` (*cmd*)

Profile an `exec`-compatible string in the script environment. The globals from the `__main__` module are used as both the globals and locals for the script.

`Profile.runcall` (*func*, **args*, ***keywords*)

Profile a single call of a callable. Additional positional and keyword arguments may be passed along; the result of the call is returned, and exceptions are allowed to propagate cleanly, while ensuring that profiling is disabled on the way out.

`Profile.runctx` (*cmd*, *globals*, *locals*)

Evaluate an `exec`-compatible string in a specific environment. The string is compiled before profiling begins.

`Profile.start` ()

Start the profiler.

`Profile.stop` ()

Stop the profiler.

26.5.2 Using hotshot data

버전 2.2에 추가.

This module loads hotshot profiling data into the standard `pstats` Stats objects.

`hotshot.stats.load` (*filename*)

Load hotshot data from *filename*. Returns an instance of the `pstats.Stats` class.

더 보기:

Module `profile` The `profile` module's Stats class

26.5.3 Example Usage

Note that this example runs the Python 《benchmark》 `pystones`. It can take some time to run, and will produce large output files.

```
>>> import hotshot, hotshot.stats, test.pystone
>>> prof = hotshot.Profile("stones.prof")
>>> benchtime, stones = prof.runcall(test.pystone.pystones)
>>> prof.close()
>>> stats = hotshot.stats.load("stones.prof")
>>> stats.strip_dirs()
>>> stats.sort_stats('time', 'calls')
>>> stats.print_stats(20)
      850004 function calls in 10.090 CPU seconds

Ordered by: internal time, call count

ncalls  tottime  percall  cumtime  percall filename:lineno(function)
      1    3.295    3.295    10.090    10.090 pystone.py:79(Proc0)
150000    1.315    0.000     1.315     0.000 pystone.py:203(Proc7)
 50000    1.313    0.000     1.463     0.000 pystone.py:229(Func2)
.
.
.
```

26.6 `timeit` — Measure execution time of small code snippets

버전 2.3에 추가.

Source code: [Lib/timeit.py](#)

This module provides a simple way to time small bits of Python code. It has both a *Command-Line Interface* as well as a *callable* one. It avoids a number of common traps for measuring execution times. See also Tim Peters' introduction to the 《Algorithms》 chapter in the *Python Cookbook*, published by O'Reilly.

26.6.1 Basic Examples

The following example shows how the *Command-Line Interface* can be used to compare three different expressions:

```
$ python -m timeit '"-".join(str(n) for n in range(100))'
10000 loops, best of 3: 40.3 usec per loop
$ python -m timeit '"-".join([str(n) for n in range(100)])'
10000 loops, best of 3: 33.4 usec per loop
$ python -m timeit '"-".join(map(str, range(100)))'
10000 loops, best of 3: 25.2 usec per loop
```

This can be achieved from the *Python Interface* with:

```
>>> import timeit
>>> timeit.timeit('"-".join(str(n) for n in range(100))', number=10000)
0.8187260627746582
>>> timeit.timeit('"-".join([str(n) for n in range(100)])', number=10000)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
0.7288308143615723
>>> timeit.timeit('"-".join(map(str, range(100)))', number=10000)
0.5858950614929199
```

Note however that `timeit` will automatically determine the number of repetitions only when the command-line interface is used. In the [Examples](#) section you can find more advanced examples.

26.6.2 Python Interface

The module defines three convenience functions and a public class:

`timeit.timeit(stmt='pass', setup='pass', timer=<default timer>, number=1000000)`

Create a `Timer` instance with the given statement, `setup` code and `timer` function and run its `timeit()` method with `number` executions.

버전 2.6에 추가.

`timeit.repeat(stmt='pass', setup='pass', timer=<default timer>, repeat=3, number=1000000)`

Create a `Timer` instance with the given statement, `setup` code and `timer` function and run its `repeat()` method with the given `repeat` count and `number` executions.

버전 2.6에 추가.

`timeit.default_timer()`

Define a default timer, in a platform-specific manner. On Windows, `time.clock()` has microsecond granularity, but `time.time()`'s granularity is 1/60th of a second. On Unix, `time.clock()` has 1/100th of a second granularity, and `time.time()` is much more precise. On either platform, `default_timer()` measures wall clock time, not the CPU time. This means that other processes running on the same computer may interfere with the timing.

class `timeit.Timer(stmt='pass', setup='pass', timer=<timer function>)`

Class for timing execution speed of small code snippets.

The constructor takes a statement to be timed, an additional statement used for setup, and a timer function. Both statements default to `'pass'`; the timer function is platform-dependent (see the module doc string). `stmt` and `setup` may also contain multiple statements separated by `;` or newlines, as long as they don't contain multi-line string literals.

To measure the execution time of the first statement, use the `timeit()` method. The `repeat()` method is a convenience to call `timeit()` multiple times and return a list of results.

버전 2.6에서 변경: The `stmt` and `setup` parameters can now also take objects that are callable without arguments. This will embed calls to them in a timer function that will then be executed by `timeit()`. Note that the timing overhead is a little larger in this case because of the extra function calls.

timeit (`number=1000000`)

Time `number` executions of the main statement. This executes the setup statement once, and then returns the time it takes to execute the main statement a number of times, measured in seconds as a float. The argument is the number of times through the loop, defaulting to one million. The main statement, the setup statement and the timer function to be used are passed to the constructor.

참고: By default, `timeit()` temporarily turns off [garbage collection](#) during the timing. The advantage of this approach is that it makes independent timings more comparable. This disadvantage is that GC may be an important component of the performance of the function being measured. If so, GC can be re-enabled as the first statement in the `setup` string. For example:

```
timeit.Timer('for i in xrange(10): oct(i)', 'gc.enable()').timeit()
```

repeat (*repeat=3, number=1000000*)

Call `timeit()` a few times.

This is a convenience function that calls the `timeit()` repeatedly, returning a list of results. The first argument specifies how many times to call `timeit()`. The second argument specifies the *number* argument for `timeit()`.

참고: It's tempting to calculate mean and standard deviation from the result vector and report these. However, this is not very useful. In a typical case, the lowest value gives a lower bound for how fast your machine can run the given code snippet; higher values in the result vector are typically not caused by variability in Python's speed, but by other processes interfering with your timing accuracy. So the `min()` of the result is probably the only number you should be interested in. After that, you should look at the entire vector and apply common sense rather than statistics.

print_exc (*file=None*)

Helper to print a traceback from the timed code.

Typical use:

```
t = Timer(...)          # outside the try/except
try:
    t.timeit(...)        # or t.repeat(...)
except:
    t.print_exc()
```

The advantage over the standard traceback is that source lines in the compiled template will be displayed. The optional *file* argument directs where the traceback is sent; it defaults to `sys.stderr`.

26.6.3 Command-Line Interface

When called as a program from the command line, the following form is used:

```
python -m timeit [-n N] [-r N] [-s S] [-t] [-c] [-h] [statement ...]
```

Where the following options are understood:

- n N, --number=N**
how many times to execute <statement>
- r N, --repeat=N**
how many times to repeat the timer (default 3)
- s S, --setup=S**
statement to be executed once initially (default pass)
- t, --time**
use `time.time()` (default on all platforms but Windows)
- c, --clock**
use `time.clock()` (default on Windows)
- v, --verbose**
print raw timing results; repeat for more digits precision

-h, --help

print a short usage message and exit

A multi-line statement may be given by specifying each line as a separate statement argument; indented lines are possible by enclosing an argument in quotes and using leading spaces. Multiple `-s` options are treated similarly.

If `-n` is not given, a suitable number of loops is calculated by trying successive powers of 10 until the total time is at least 0.2 seconds.

`default_timer()` measurements can be affected by other programs running on the same machine, so the best thing to do when accurate timing is necessary is to repeat the timing a few times and use the best time. The `-r` option is good for this; the default of 3 repetitions is probably enough in most cases. On Unix, you can use `time.clock()` to measure CPU time.

참고: There is a certain baseline overhead associated with executing a pass statement. The code here doesn't try to hide it, but you should be aware of it. The baseline overhead can be measured by invoking the program without arguments, and it might differ between Python versions. Also, to fairly compare older Python versions to Python 2.3, you may want to use Python's `-O` option (see Optimizations) for the older versions to avoid timing `SET_LINENO` instructions.

26.6.4 Examples

It is possible to provide a setup statement that is executed only once at the beginning:

```
$ python -m timeit -s 'text = "sample string"; char = "g"' 'char in text'
1000000 loops, best of 3: 0.0877 usec per loop
$ python -m timeit -s 'text = "sample string"; char = "g"' 'text.find(char)'
1000000 loops, best of 3: 0.342 usec per loop
```

```
>>> import timeit
>>> timeit.timeit('char in text', setup='text = "sample string"; char = "g"')
0.41440500499993504
>>> timeit.timeit('text.find(char)', setup='text = "sample string"; char = "g"')
1.7246671520006203
```

The same can be done using the `Timer` class and its methods:

```
>>> import timeit
>>> t = timeit.Timer('char in text', setup='text = "sample string"; char = "g"')
>>> t.timeit()
0.3955516149999312
>>> t.repeat()
[0.40193588800002544, 0.3960157959998014, 0.39594301399984033]
```

The following examples show how to time expressions that contain multiple lines. Here we compare the cost of using `hasattr()` vs. `try/except` to test for missing and present object attributes:

```
$ python -m timeit 'try: ' ' str.__nonzero__ 'except AttributeError: ' ' pass'
100000 loops, best of 3: 15.7 usec per loop
$ python -m timeit 'if hasattr(str, "__nonzero__"): pass'
100000 loops, best of 3: 4.26 usec per loop

$ python -m timeit 'try: ' ' int.__nonzero__ 'except AttributeError: ' ' pass'
1000000 loops, best of 3: 1.43 usec per loop
$ python -m timeit 'if hasattr(int, "__nonzero__"): pass'
100000 loops, best of 3: 2.23 usec per loop
```

```
>>> import timeit
>>> # attribute is missing
>>> s = """\
... try:
...     str.__nonzero__
... except AttributeError:
...     pass
... """
>>> timeit.timeit(stmt=s, number=100000)
0.9138244460009446
>>> s = "if hasattr(str, '__bool__'): pass"
>>> timeit.timeit(stmt=s, number=100000)
0.5829014980008651
>>>
>>> # attribute is present
>>> s = """\
... try:
...     int.__nonzero__
... except AttributeError:
...     pass
... """
>>> timeit.timeit(stmt=s, number=100000)
0.04215312199994514
>>> s = "if hasattr(int, '__bool__'): pass"
>>> timeit.timeit(stmt=s, number=100000)
0.08588060699912603
```

To give the `timeit` module access to functions you define, you can pass a `setup` parameter which contains an import statement:

```
def test():
    """Stupid test function"""
    L = []
    for i in range(100):
        L.append(i)

if __name__ == '__main__':
    import timeit
    print(timeit.timeit("test()", setup="from __main__ import test"))
```

26.7 `trace` — Trace or track Python statement execution

Source code: `Lib/trace.py`

The `trace` module allows you to trace program execution, generate annotated statement coverage listings, print caller/callee relationships and list functions executed during a program run. It can be used in another program or from the command line.

26.7.1 Command-Line Usage

The `trace` module can be invoked from the command line. It can be as simple as

```
python -m trace --count -C . somefile.py ...
```

The above will execute `somefile.py` and generate annotated listings of all Python modules imported during the execution into the current directory.

--help

Display usage and exit.

--version

Display the version of the module and exit.

Main options

At least one of the following options must be specified when invoking `trace`. The `--listfuncs` option is mutually exclusive with the `--trace` and `--count` options. When `--listfuncs` is provided, neither `--count` nor `--trace` are accepted, and vice versa.

-c, --count

Produce a set of annotated listing files upon program completion that shows how many times each statement was executed. See also `--coverdir`, `--file` and `--no-report` below.

-t, --trace

Display lines as they are executed.

-l, --listfuncs

Display the functions executed by running the program.

-r, --report

Produce an annotated list from an earlier program run that used the `--count` and `--file` option. This does not execute any code.

-T, --trackcalls

Display the calling relationships exposed by running the program.

Modifiers

-f, --file=<file>

Name of a file to accumulate counts over several tracing runs. Should be used with the `--count` option.

-C, --coverdir=<dir>

Directory where the report files go. The coverage report for `package.module` is written to file `dir/package/module.cover`.

-m, --missing

When generating annotated listings, mark lines which were not executed with `>>>>>>`.

-s, --summary

When using `--count` or `--report`, write a brief summary to stdout for each file processed.

-R, --no-report

Do not generate annotated listings. This is useful if you intend to make several runs with `--count`, and then produce a single set of annotated listings at the end.

-g, --timing

Prefix each line with the time since the program started. Only used while tracing.

Filters

These options may be repeated multiple times.

--ignore-module=<mod>

Ignore each of the given module names and its submodules (if it is a package). The argument can be a list of names separated by a comma.

--ignore-dir=<dir>

Ignore all modules and packages in the named directory and subdirectories. The argument can be a list of directories separated by `os.pathsep`.

26.7.2 Programmatic Interface

class `trace.Trace` (`count=1`, `trace=1`, `countfuncs=0`, `countcallers=0`, `ignoremods=()`, `ignoredirs=()`, `infile=None`, `outfile=None`, `timing=False`)

Create an object to trace execution of a single statement or expression. All parameters are optional. `count` enables counting of line numbers. `trace` enables line execution tracing. `countfuncs` enables listing of the functions called during the run. `countcallers` enables call relationship tracking. `ignoremods` is a list of modules or packages to ignore. `ignoredirs` is a list of directories whose modules or packages should be ignored. `infile` is the name of the file from which to read stored count information. `outfile` is the name of the file in which to write updated count information. `timing` enables a timestamp relative to when tracing was started to be displayed.

run (`cmd`)

Execute the command and gather statistics from the execution with the current tracing parameters. `cmd` must be a string or code object, suitable for passing into `exec()`.

runctx (`cmd`, `globals=None`, `locals=None`)

Execute the command and gather statistics from the execution with the current tracing parameters, in the defined global and local environments. If not defined, `globals` and `locals` default to empty dictionaries.

runfunc (`func`, `*args`, `**kwargs`)

Call `func` with the given arguments under control of the `Trace` object with the current tracing parameters.

results ()

Return a `CoverageResults` object that contains the cumulative results of all previous calls to `run`, `runctx` and `runfunc` for the given `Trace` instance. Does not reset the accumulated trace results.

class `trace.CoverageResults`

A container for coverage results, created by `Trace.results()`. Should not be created directly by the user.

update (`other`)

Merge in data from another `CoverageResults` object.

write_results (`show_missing=True`, `summary=False`, `coverdir=None`)

Write coverage results. Set `show_missing` to show lines that had no hits. Set `summary` to include in the output the coverage summary per module. `coverdir` specifies the directory into which the coverage result files will be output. If `None`, the results for each source file are placed in its directory.

A simple example demonstrating the use of the programmatic interface:

```
import sys
import trace
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
# create a Trace object, telling it what to ignore, and whether to
# do tracing or line-counting or both.
tracer = trace.Trace(
    ignoredirs=[sys.prefix, sys.exec_prefix],
    trace=0,
    count=1)

# run the new command using the given tracer
tracer.run('main() ')

# make a report, placing output in the current directory
r = tracer.results()
r.write_results(show_missing=True, coverdir=".")
```

Software Packaging and Distribution

These libraries help you with publishing and installing Python software. While these modules are designed to work in conjunction with the [Python Package Index](#), they can also be used with a local index server, or without any index server at all.

27.1 `distutils` — Building and installing Python modules

The `distutils` package provides support for building and installing additional modules into a Python installation. The new modules may be either 100%-pure Python, or may be extension modules written in C, or may be collections of Python packages which include modules coded in both Python and C.

Most Python users will *not* want to use this module directly, but instead use the cross-version tools maintained by the Python Packaging Authority. In particular, `setuptools` is an enhanced alternative to `distutils` that provides:

- support for declaring project dependencies
- additional mechanisms for configuring which files to include in source releases (including plugins for integration with version control systems)
- the ability to declare project «entry points», which can be used as the basis for application plugin systems
- the ability to automatically generate Windows command line executables at installation time rather than needing to prebuild them
- consistent behaviour across all supported Python versions

The recommended `pip` installer runs all `setup.py` scripts with `setuptools`, even if the script itself only imports `distutils`. Refer to the [Python Packaging User Guide](#) for more information.

For the benefits of packaging tool authors and users seeking a deeper understanding of the details of the current packaging and distribution system, the legacy `distutils` based user documentation and API reference remain available:

- [install-index](#)
- [distutils-index](#)

27.2 ensurepip — Bootstrapping the pip installer

버전 2.7.9에 추가.

The `ensurepip` package provides support for bootstrapping the `pip` installer into an existing Python installation or virtual environment. This bootstrapping approach reflects the fact that `pip` is an independent project with its own release cycle, and the latest available stable version is bundled with maintenance and feature releases of the CPython reference interpreter.

In most cases, end users of Python shouldn't need to invoke this module directly (as `pip` should be bootstrapped by default), but it may be needed if installing `pip` was skipped when installing Python (or when creating a virtual environment) or after explicitly uninstalling `pip`.

참고: This module *does not* access the internet. All of the components needed to bootstrap `pip` are included as internal parts of the package.

더 보기:

installing-index The end user guide for installing Python packages

PEP 453: Explicit bootstrapping of pip in Python installations The original rationale and specification for this module.

PEP 477: Backport ensurepip (PEP 453) to Python 2.7 The rationale and specification for backporting PEP 453 to Python 2.7.

27.2.1 Command line interface

The command line interface is invoked using the interpreter's `-m` switch.

The simplest possible invocation is:

```
python -m ensurepip
```

This invocation will install `pip` if it is not already installed, but otherwise does nothing. To ensure the installed version of `pip` is at least as recent as the one bundled with `ensurepip`, pass the `--upgrade` option:

```
python -m ensurepip --upgrade
```

By default, `pip` is installed into the current virtual environment (if one is active) or into the system site packages (if there is no active virtual environment). The installation location can be controlled through two additional command line options:

- `--root <dir>`: Installs `pip` relative to the given root directory rather than the root of the currently active virtual environment (if any) or the default root for the current Python installation.
- `--user`: Installs `pip` into the user site packages directory rather than globally for the current Python installation (this option is not permitted inside an active virtual environment).

By default, the scripts `pip`, `pipX`, and `pipX.Y` will be installed (where `X.Y` stands for the version of Python used to invoke `ensurepip`). The scripts installed can be controlled through two additional command line options:

- `--altinstall`: if an alternate installation is requested, the `pip` and `pipX` script will *not* be installed.
- `--no-default-pip`: if a non-default installation is request, the `pip` script will *not* be installed.

버전 2.7.15에서 변경: The exit status is non-zero if the command fails.

27.2.2 Module API

`ensurepip` exposes two functions for programmatic use:

`ensurepip.version()`

Returns a string specifying the bundled version of pip that will be installed when bootstrapping an environment.

`ensurepip.bootstrap(root=None, upgrade=False, user=False, altinstall=False, default_pip=True, verbosity=0)`

Bootstraps pip into the current or designated environment.

root specifies an alternative root directory to install relative to. If *root* is `None`, then installation uses the default install location for the current environment.

upgrade indicates whether or not to upgrade an existing installation of an earlier version of pip to the bundled version.

user indicates whether to use the user scheme rather than installing globally.

By default, the scripts `pip`, `pipX`, and `pipX.Y` will be installed (where `X.Y` stands for the current version of Python).

If *altinstall* is set, then `pip` and `pipX` will *not* be installed.

If *default_pip* is set to `False`, then `pip` will *not* be installed.

Setting both *altinstall* and *default_pip* will trigger `ValueError`.

verbosity controls the level of output to `sys.stdout` from the bootstrapping operation.

참고: The bootstrapping process has side effects on both `sys.path` and `os.environ`. Invoking the command line interface in a subprocess instead allows these side effects to be avoided.

참고: The bootstrapping process may install additional modules required by pip, but other software should not assume those dependencies will always be present by default (as the dependencies may be removed in a future version of pip).

이 장에서 설명하는 모듈들은 파이썬 인터프리터와 그 환경과의 상호 작용과 관련된 다양한 서비스를 제공합니다. 다음은 개요입니다:

28.1 `sys` — System-specific parameters and functions

This module provides access to some variables used or maintained by the interpreter and to functions that interact strongly with the interpreter. It is always available.

`sys.argv`

The list of command line arguments passed to a Python script. `argv[0]` is the script name (it is operating system dependent whether this is a full pathname or not). If the command was executed using the `-c` command line option to the interpreter, `argv[0]` is set to the string `'-c'`. If no script name was passed to the Python interpreter, `argv[0]` is the empty string.

To loop over the standard input, or the list of files given on the command line, see the [`fileinput`](#) module.

`sys.byteorder`

An indicator of the native byte order. This will have the value `'big'` on big-endian (most-significant byte first) platforms, and `'little'` on little-endian (least-significant byte first) platforms.

버전 2.0에 추가.

`sys.builtin_module_names`

A tuple of strings giving the names of all modules that are compiled into this Python interpreter. (This information is not available in any other way — `modules.keys()` only lists the imported modules.)

`sys.call_tracing(func, args)`

Call `func(*args)`, while tracing is enabled. The tracing state is saved, and restored afterwards. This is intended to be called from a debugger from a checkpoint, to recursively debug some other code.

`sys.copyright`

A string containing the copyright pertaining to the Python interpreter.

`sys._clear_type_cache()`

Clear the internal type cache. The type cache is used to speed up attribute and method lookups. Use the function *only* to drop unnecessary references during reference leak debugging.

This function should be used for internal and specialized purposes only.

버전 2.6에 추가.

`sys._current_frames()`

Return a dictionary mapping each thread's identifier to the topmost stack frame currently active in that thread at the time the function is called. Note that functions in the `traceback` module can build the call stack given such a frame.

This is most useful for debugging deadlock: this function does not require the deadlocked threads' cooperation, and such threads' call stacks are frozen for as long as they remain deadlocked. The frame returned for a non-deadlocked thread may bear no relationship to that thread's current activity by the time calling code examines the frame.

This function should be used for internal and specialized purposes only.

버전 2.5에 추가.

`sys.dllhandle`

Integer specifying the handle of the Python DLL. Availability: Windows.

`sys.displayhook(value)`

If *value* is not None, this function prints it to `sys.stdout`, and saves it in `__builtin__._`.

`sys.displayhook` is called on the result of evaluating an *expression* entered in an interactive Python session. The display of these values can be customized by assigning another one-argument function to `sys.displayhook`.

`sys.dont_write_bytecode`

If this is true, Python won't try to write `.pyc` or `.pyo` files on the import of source modules. This value is initially set to True or False depending on the `-B` command line option and the `PYTHONDONTWRITEBYTECODE` environment variable, but you can set it yourself to control bytecode file generation.

버전 2.6에 추가.

`sys.excepthook(type, value, traceback)`

This function prints out a given traceback and exception to `sys.stderr`.

When an exception is raised and uncaught, the interpreter calls `sys.excepthook` with three arguments, the exception class, exception instance, and a traceback object. In an interactive session this happens just before control is returned to the prompt; in a Python program this happens just before the program exits. The handling of such top-level exceptions can be customized by assigning another three-argument function to `sys.excepthook`.

`sys.__displayhook__`

`sys.__excepthook__`

These objects contain the original values of `displayhook` and `excepthook` at the start of the program. They are saved so that `displayhook` and `excepthook` can be restored in case they happen to get replaced with broken objects.

`sys.exc_info()`

This function returns a tuple of three values that give information about the exception that is currently being handled. The information returned is specific both to the current thread and to the current stack frame. If the current stack frame is not handling an exception, the information is taken from the calling stack frame, or its caller, and so on until a stack frame is found that is handling an exception. Here, «handling an exception» is defined as «executing or having executed an except clause.» For any stack frame, only information about the most recently handled exception is accessible.

If no exception is being handled anywhere on the stack, a tuple containing three `None` values is returned. Otherwise, the values returned are `(type, value, traceback)`. Their meaning is: *type* gets the exception type of the exception being handled (a class object); *value* gets the exception parameter (its *associated value* or the second argument to `raise`, which is always a class instance if the exception type is a class object); *traceback* gets a traceback object (see the Reference Manual) which encapsulates the call stack at the point where the exception originally occurred.

If `exc_clear()` is called, this function will return three `None` values until either another exception is raised in the current thread or the execution stack returns to a frame where another exception is being handled.

경고: Assigning the *traceback* return value to a local variable in a function that is handling an exception will cause a circular reference. This will prevent anything referenced by a local variable in the same function or by the traceback from being garbage collected. Since most functions don't need access to the traceback, the best solution is to use something like `exctype, value = sys.exc_info()[:2]` to extract only the exception type and value. If you do need the traceback, make sure to delete it after use (best done with a `try ... finally` statement) or to call `exc_info()` in a function that does not itself handle an exception.

참고: Beginning with Python 2.2, such cycles are automatically reclaimed when garbage collection is enabled and they become unreachable, but it remains more efficient to avoid creating cycles.

`sys.exc_clear()`

This function clears all information relating to the current or last exception that occurred in the current thread. After calling this function, `exc_info()` will return three `None` values until another exception is raised in the current thread or the execution stack returns to a frame where another exception is being handled.

This function is only needed in only a few obscure situations. These include logging and error handling systems that report information on the last or current exception. This function can also be used to try to free resources and trigger object finalization, though no guarantee is made as to what objects will be freed, if any.

버전 2.3에 추가.

`sys.exc_type`
`sys.exc_value`
`sys.exc_traceback`

버전 1.5부터 폐지: Use `exc_info()` instead.

Since they are global variables, they are not specific to the current thread, so their use is not safe in a multi-threaded program. When no exception is being handled, `exc_type` is set to `None` and the other two are undefined.

`sys.exec_prefix`

A string giving the site-specific directory prefix where the platform-dependent Python files are installed; by default, this is also `'/usr/local'`. This can be set at build time with the `--exec-prefix` argument to the **configure** script. Specifically, all configuration files (e.g. the `pyconfig.h` header file) are installed in the directory `exec_prefix/lib/pythonX.Y/config`, and shared library modules are installed in `exec_prefix/lib/pythonX.Y/lib-dynload`, where `X.Y` is the version number of Python, for example 2.7.

`sys.executable`

A string giving the absolute path of the executable binary for the Python interpreter, on systems where this makes sense. If Python is unable to retrieve the real path to its executable, `sys.executable` will be an empty string or `None`.

`sys.exit([arg])`

Exit from Python. This is implemented by raising the `SystemExit` exception, so cleanup actions specified by finally clauses of `try` statements are honored, and it is possible to intercept the exit attempt at an outer level.

The optional argument *arg* can be an integer giving the exit status (defaulting to zero), or another type of object. If it is an integer, zero is considered 《successful termination》 and any nonzero value is considered 《abnormal termination》 by shells and the like. Most systems require it to be in the range 0–127, and produce undefined results otherwise. Some systems have a convention for assigning specific meanings to specific exit codes, but these are generally underdeveloped; Unix programs generally use 2 for command line syntax errors and 1 for all other kind of errors. If another type of object is passed, `None` is equivalent to passing zero, and any other object is printed to `stderr` and results in an exit code of 1. In particular, `sys.exit("some error message")` is a quick way to exit a program when an error occurs.

Since `exit()` ultimately 《only》 raises an exception, it will only exit the process when called from the main thread, and the exception is not intercepted.

`sys.exitfunc`

This value is not actually defined by the module, but can be set by the user (or by a program) to specify a clean-up action at program exit. When set, it should be a parameterless function. This function will be called when the interpreter exits. Only one function may be installed in this way; to allow multiple functions which will be called at termination, use the `atexit` module.

참고: The exit function is not called when the program is killed by a signal, when a Python fatal internal error is detected, or when `os._exit()` is called.

버전 2.4부터 폐지: Use `atexit` instead.

`sys.flags`

The struct sequence *flags* exposes the status of command line flags. The attributes are read only.

attribute	flag
debug	-d
py3k_warning	-3
division_warning	-Q
division_new	-Qnew
<i>inspect</i>	-i
interactive	-i
optimize	-O or -OO
<i>dont_write_bytecode</i>	-B
no_user_site	-s
no_site	-S
ignore_environment	-E
tabcheck	-t or -tt
verbose	-v
<i>unicode</i>	-U
bytes_warning	-b
hash_randomization	-R

버전 2.6에 추가.

버전 2.7.3에 추가: The `hash_randomization` attribute.

`sys.float_info`

A structseq holding information about the float type. It contains low level information about the precision and internal representation. The values correspond to the various floating-point constants defined in the standard header file `float.h` for the ⟨C⟩ programming language; see section 5.2.4.2.2 of the 1999 ISO/IEC C standard [C99], ⟨Characteristics of floating types⟩, for details.

attribute	float.h macro	explanation
<code>epsilon</code>	<code>DBL_EPSILON</code>	difference between 1 and the least value greater than 1 that is representable as a float
<code>dig</code>	<code>DBL_DIG</code>	maximum number of decimal digits that can be faithfully represented in a float; see below
<code>mant_dig</code>	<code>DBL_MANT_DIG</code>	float precision: the number of base-radix digits in the significand of a float
<code>max</code>	<code>DBL_MAX</code>	maximum representable finite float
<code>max_exp</code>	<code>DBL_MAX_EXP</code>	maximum integer e such that <code>radix**(e-1)</code> is a representable finite float
<code>max_10_exp</code>	<code>DBL_MAX_10_EXP</code>	maximum integer e such that <code>10**e</code> is in the range of representable finite floats
<code>min</code>	<code>DBL_MIN</code>	minimum positive normalized float
<code>min_exp</code>	<code>DBL_MIN_EXP</code>	minimum integer e such that <code>radix**(e-1)</code> is a normalized float
<code>min_10_exp</code>	<code>DBL_MIN_10_EXP</code>	minimum integer e such that <code>10**e</code> is a normalized float
<code>radix</code>	<code>FLT_RADIX</code>	radix of exponent representation
<code>rounds</code>	<code>FLT_ROUNDS</code>	integer constant representing the rounding mode used for arithmetic operations. This reflects the value of the system <code>FLT_ROUNDS</code> macro at interpreter startup time. See section 5.2.4.2.2 of the C99 standard for an explanation of the possible values and their meanings.

The attribute `sys.float_info.dig` needs further explanation. If `s` is any string representing a decimal number with at most `sys.float_info.dig` significant digits, then converting `s` to a float and back again will recover a string representing the same decimal value:

```
>>> import sys
>>> sys.float_info.dig
15
>>> s = '3.14159265358979'      # decimal string with 15 significant digits
>>> format(float(s), '.15g')    # convert to float and back -> same value
'3.14159265358979'
```

But for strings with more than `sys.float_info.dig` significant digits, this isn't always true:

```
>>> s = '9876543211234567'     # 16 significant digits is too many!
>>> format(float(s), '.16g')    # conversion changes value
'9876543211234568'
```

버전 2.6에 추가.

`sys.float_repr_style`

A string indicating how the `repr()` function behaves for floats. If the string has value `'short'` then for a finite float `x`, `repr(x)` aims to produce a short string with the property that `float(repr(x)) == x`. This is the usual behaviour in Python 2.7 and later. Otherwise, `float_repr_style` has value `'legacy'` and `repr(x)` behaves in the same way as it did in versions of Python prior to 2.7.

버전 2.7에 추가.

`sys.getcheckinterval()`

Return the interpreter's `check interval`; see `setcheckinterval()`.

버전 2.3에 추가.

`sys.getdefaultencoding()`

Return the name of the current default string encoding used by the Unicode implementation.

버전 2.0에 추가.

`sys.getdlopenflags()`

Return the current value of the flags that are used for `dlopen()` calls. The flag constants are defined in the `dl` and `DLFCN` modules. Availability: Unix.

버전 2.2에 추가.

`sys.getfilesystemencoding()`

Return the name of the encoding used to convert Unicode filenames into system file names, or `None` if the system default encoding is used. The result value depends on the operating system:

- On Mac OS X, the encoding is `'utf-8'`.
- On Unix, the encoding is the user's preference according to the result of `nl_langinfo(CODESET)`, or `None` if the `nl_langinfo(CODESET)` failed.
- On Windows NT+, file names are Unicode natively, so no conversion is performed. `getfilesystemencoding()` still returns `'mbcs'`, as this is the encoding that applications should use when they explicitly want to convert Unicode strings to byte strings that are equivalent when used as file names.
- On Windows 9x, the encoding is `'mbcs'`.

버전 2.3에 추가.

`sys.getrefcount(object)`

Return the reference count of the *object*. The count returned is generally one higher than you might expect, because it includes the (temporary) reference as an argument to `getrefcount()`.

`sys.getrecursionlimit()`

Return the current value of the recursion limit, the maximum depth of the Python interpreter stack. This limit prevents infinite recursion from causing an overflow of the C stack and crashing Python. It can be set by `setrecursionlimit()`.

`sys.getsizeof(object[, default])`

Return the size of an object in bytes. The object can be any type of object. All built-in objects will return correct results, but this does not have to hold true for third-party extensions as it is implementation specific.

If given, *default* will be returned if the object does not provide means to retrieve the size. Otherwise a `TypeError` will be raised.

`getsizeof()` calls the object's `__sizeof__` method and adds an additional garbage collector overhead if the object is managed by the garbage collector.

버전 2.6에 추가.

`sys._getframe([depth])`

Return a frame object from the call stack. If optional integer *depth* is given, return the frame object that many calls below the top of the stack. If that is deeper than the call stack, `ValueError` is raised. The default for *depth* is zero, returning the frame at the top of the call stack.

CPython implementation detail: This function should be used for internal and specialized purposes only. It is not guaranteed to exist in all implementations of Python.

`sys.getprofile()`

Get the profiler function as set by `setprofile()`.

버전 2.6에 추가.

`sys.gettrace()`

Get the trace function as set by `settrace()`.

CPython implementation detail: The `gettrace()` function is intended only for implementing debuggers, profilers, coverage tools and the like. Its behavior is part of the implementation platform, rather than part of the language definition, and thus may not be available in all Python implementations.

버전 2.6에 추가.

`sys.getwindowsversion()`

Return a named tuple describing the Windows version currently running. The named elements are *major*, *minor*, *build*, *platform*, *service_pack*, *service_pack_minor*, *service_pack_major*, *suite_mask*, and *product_type*. *service_pack* contains a string while all other values are integers. The components can also be accessed by name, so `sys.getwindowsversion()[0]` is equivalent to `sys.getwindowsversion().major`. For compatibility with prior versions, only the first 5 elements are retrievable by indexing.

platform may be one of the following values:

Constant	Platform
0 (VER_PLATFORM_WIN32s)	Win32s on Windows 3.1
1 (VER_PLATFORM_WIN32_WINDOWS)	Windows 95/98/ME
2 (VER_PLATFORM_WIN32_NT)	Windows NT/2000/XP/x64
3 (VER_PLATFORM_WIN32_CE)	Windows CE

product_type may be one of the following values:

Constant	Meaning
1 (VER_NT_WORKSTATION)	The system is a workstation.
2 (VER_NT_DOMAIN_CONTROLLER)	The system is a domain controller.
3 (VER_NT_SERVER)	The system is a server, but not a domain controller.

This function wraps the Win32 `GetVersionEx()` function; see the Microsoft documentation on `OSVERSIONINFOEX()` for more information about these fields.

Availability: Windows.

버전 2.3에 추가.

버전 2.7에서 변경: Changed to a named tuple and added *service_pack_minor*, *service_pack_major*, *suite_mask*, and *product_type*.

`sys.hexversion`

The version number encoded as a single integer. This is guaranteed to increase with each version, including proper support for non-production releases. For example, to test that the Python interpreter is at least version 1.5.2, use:

```
if sys.hexversion >= 0x010502F0:
    # use some advanced feature
    ...
else:
    # use an alternative implementation or warn the user
    ...
```

This is called `hexversion` since it only really looks meaningful when viewed as the result of passing it to the built-in `hex()` function. The `version_info` value may be used for a more human-friendly encoding of the same information.

The `hexversion` is a 32-bit number with the following layout:

Bits (big endian order)	Meaning
1–8	PY_MAJOR_VERSION (the 2 in 2.1.0a3)
9–16	PY_MINOR_VERSION (the 1 in 2.1.0a3)
17–24	PY_MICRO_VERSION (the 0 in 2.1.0a3)
25–28	PY_RELEASE_LEVEL (0xA for alpha, 0xB for beta, 0xC for release candidate and 0xF for final)
29–32	PY_RELEASE_SERIAL (the 3 in 2.1.0a3, zero for final releases)

Thus 2.1.0a3 is hexversion 0x020100a3.

버전 1.5.2에 추가.

`sys.long_info`

A struct sequence that holds information about Python’s internal representation of integers. The attributes are read only.

Attribute	Explanation
<code>bits_per_digit</code>	number of bits held in each digit. Python integers are stored internally in base <code>2**long_info.bits_per_digit</code>
<code>sizeof_digit</code>	size in bytes of the C type used to represent a digit

버전 2.7에 추가.

`sys.last_type`

`sys.last_value`

`sys.last_traceback`

These three variables are not always defined; they are set when an exception is not handled and the interpreter prints an error message and a stack traceback. Their intended use is to allow an interactive user to import a debugger module and engage in post-mortem debugging without having to re-execute the command that caused the error. (Typical use is `import pdb; pdb.pm()` to enter the post-mortem debugger; see chapter [pdb — The Python Debugger](#) for more information.)

The meaning of the variables is the same as that of the return values from `exc_info()` above. (Since there is only one interactive thread, thread-safety is not a concern for these variables, unlike for `exc_type` etc.)

`sys.maxint`

The largest positive integer supported by Python’s regular integer type. This is at least `2**31-1`. The largest negative integer is `-maxint-1` — the asymmetry results from the use of 2’s complement binary arithmetic.

`sys.maxsize`

The largest positive integer supported by the platform’s `Py_ssize_t` type, and thus the maximum size lists, strings, dicts, and many other containers can have.

`sys.maxunicode`

An integer giving the largest supported code point for a Unicode character. The value of this depends on the configuration option that specifies whether Unicode characters are stored as UCS-2 or UCS-4.

`sys.meta_path`

A list of *finder* objects that have their `find_module()` methods called to see if one of the objects can find the module to be imported. The `find_module()` method is called at least with the absolute name of the module being imported. If the module to be imported is contained in package then the parent package’s `__path__` attribute is passed in as a second argument. The method returns `None` if the module cannot be found, else returns a *loader*.

`sys.meta_path` is searched before any implicit default finders or `sys.path`.

See [PEP 302](#) for the original specification.

`sys.modules`

This is a dictionary that maps module names to modules which have already been loaded. This can be manipulated to force reloading of modules and other tricks. Note that removing a module from this dictionary is *not* the same as calling `reload()` on the corresponding module object.

`sys.path`

A list of strings that specifies the search path for modules. Initialized from the environment variable `PYTHONPATH`, plus an installation-dependent default.

As initialized upon program startup, the first item of this list, `path[0]`, is the directory containing the script that was used to invoke the Python interpreter. If the script directory is not available (e.g. if the interpreter is invoked interactively or if the script is read from standard input), `path[0]` is the empty string, which directs Python to search modules in the current directory first. Notice that the script directory is inserted *before* the entries inserted as a result of `PYTHONPATH`.

A program is free to modify this list for its own purposes.

버전 2.3에서 변경: Unicode strings are no longer ignored.

더 보기:

Module `site` This describes how to use `.pth` files to extend `sys.path`.

`sys.path_hooks`

A list of callables that take a path argument to try to create a *finder* for the path. If a finder can be created, it is to be returned by the callable, else raise `ImportError`.

Originally specified in [PEP 302](#).

`sys.path_importer_cache`

A dictionary acting as a cache for *finder* objects. The keys are paths that have been passed to `sys.path_hooks` and the values are the finders that are found. If a path is a valid file system path but no explicit finder is found on `sys.path_hooks` then `None` is stored to represent the implicit default finder should be used. If the path is not an existing path then `imp.NullImporter` is set.

Originally specified in [PEP 302](#).

`sys.platform`

This string contains a platform identifier that can be used to append platform-specific components to `sys.path`, for instance.

For most Unix systems, this is the lowercased OS name as returned by `uname -s` with the first part of the version as returned by `uname -r` appended, e.g. `'sunos5'`, *at the time when Python was built*. Unless you want to test for a specific system version, it is therefore recommended to use the following idiom:

```
if sys.platform.startswith('freebsd'):
    # FreeBSD-specific code here...
elif sys.platform.startswith('linux'):
    # Linux-specific code here...
```

버전 2.7.3에서 변경: Since lots of code check for `sys.platform == 'linux2'`, and there is no essential change between Linux 2.x and 3.x, `sys.platform` is always set to `'linux2'`, even on Linux 3.x. In Python 3.3 and later, the value will always be set to `'linux'`, so it is recommended to always use the `startswith` idiom presented above.

For other systems, the values are:

System	<i>platform</i> value
Linux (2.x and 3.x)	'linux2'
Windows	'win32'
Windows/Cygwin	'cygwin'
Mac OS X	'darwin'
OS/2	'os2'
OS/2 EMX	'os2emx'
RiscOS	'riscos'
AtheOS	'atheos'

더 보기:

`os.name` has a coarser granularity. `os.uname()` gives system-dependent version information.

The `platform` module provides detailed checks for the system's identity.

`sys.prefix`

A string giving the site-specific directory prefix where the platform independent Python files are installed; by default, this is the string `'/usr/local'`. This can be set at build time with the `--prefix` argument to the **configure** script. The main collection of Python library modules is installed in the directory `prefix/lib/pythonX.Y` while the platform independent header files (all except `pyconfig.h`) are stored in `prefix/include/pythonX.Y`, where `X.Y` is the version number of Python, for example `2.7`.

`sys.ps1`

`sys.ps2`

Strings specifying the primary and secondary prompt of the interpreter. These are only defined if the interpreter is in interactive mode. Their initial values in this case are `'>>> '` and `'... '`. If a non-string object is assigned to either variable, its `str()` is re-evaluated each time the interpreter prepares to read a new interactive command; this can be used to implement a dynamic prompt.

`sys.py3kwarning`

Bool containing the status of the Python 3 warning flag. It's `True` when Python is started with the `-3` option. (This should be considered read-only; setting it to a different value doesn't have an effect on Python 3 warnings.)

버전 2.6에 추가.

`sys.setcheckinterval(interval)`

Set the interpreter's «check interval». This integer value determines how often the interpreter checks for periodic things such as thread switches and signal handlers. The default is `100`, meaning the check is performed every 100 Python virtual instructions. Setting it to a larger value may increase performance for programs using threads. Setting it to a value `<= 0` checks every virtual instruction, maximizing responsiveness as well as overhead.

`sys.setdefaultencoding(name)`

Set the current default string encoding used by the Unicode implementation. If `name` does not match any available encoding, `LookupError` is raised. This function is only intended to be used by the `site` module implementation and, where needed, by `sitecustomize`. Once used by the `site` module, it is removed from the `sys` module's namespace.

버전 2.0에 추가.

`sys.setdlopenflags(n)`

Set the flags used by the interpreter for `dlopen()` calls, such as when the interpreter loads extension modules. Among other things, this will enable a lazy resolving of symbols when importing a module, if called as `sys.setdlopenflags(0)`. To share symbols across extension modules, call as `sys.setdlopenflags(dl.RTLD_NOW | dl.RTLD_GLOBAL)`. Symbolic names for the flag modules can be either found in the `dl` module, or in the `DLFCN` module. If `DLFCN` is not available, it can be generated from `/usr/include/dlfcn.h` using the **h2py** script. Availability: Unix.

버전 2.2에 추가.

`sys.setprofile(profilefunc)`

Set the system's profile function, which allows you to implement a Python source code profiler in Python. See chapter *The Python Profilers* for more information on the Python profiler. The system's profile function is called similarly to the system's trace function (see `settrace()`), but it is called with different events, for example it isn't called for each executed line of code (only on call and return, but the return event is reported even when an exception has been set). The function is thread-specific, but there is no way for the profiler to know about context switches between threads, so it does not make sense to use this in the presence of multiple threads. Also, its return value is not used, so it can simply return `None`.

Profile functions should have three arguments: *frame*, *event*, and *arg*. *frame* is the current stack frame. *event* is a string: 'call', 'return', 'c_call', 'c_return', or 'c_exception'. *arg* depends on the event type.

The events have the following meaning:

'call' A function is called (or some other code block entered). The profile function is called; *arg* is `None`.

'return' A function (or other code block) is about to return. The profile function is called; *arg* is the value that will be returned, or `None` if the event is caused by an exception being raised.

'c_call' A C function is about to be called. This may be an extension function or a built-in. *arg* is the C function object.

'c_return' A C function has returned. *arg* is the C function object.

'c_exception' A C function has raised an exception. *arg* is the C function object.

`sys.setrecursionlimit(limit)`

Set the maximum depth of the Python interpreter stack to *limit*. This limit prevents infinite recursion from causing an overflow of the C stack and crashing Python.

The highest possible limit is platform-dependent. A user may need to set the limit higher when she has a program that requires deep recursion and a platform that supports a higher limit. This should be done with care, because a too-high limit can lead to a crash.

`sys.settrace(tracefunc)`

Set the system's trace function, which allows you to implement a Python source code debugger in Python. The function is thread-specific; for a debugger to support multiple threads, it must be registered using `settrace()` for each thread being debugged.

Trace functions should have three arguments: *frame*, *event*, and *arg*. *frame* is the current stack frame. *event* is a string: 'call', 'line', 'return' or 'exception'. *arg* depends on the event type.

The trace function is invoked (with *event* set to 'call') whenever a new local scope is entered; it should return a reference to a local trace function to be used that scope, or `None` if the scope shouldn't be traced.

The local trace function should return a reference to itself (or to another function for further tracing in that scope), or `None` to turn off tracing in that scope.

The events have the following meaning:

'call' A function is called (or some other code block entered). The global trace function is called; *arg* is `None`; the return value specifies the local trace function.

'line' The interpreter is about to execute a new line of code or re-execute the condition of a loop. The local trace function is called; *arg* is `None`; the return value specifies the new local trace function. See `Objects/lnotab_notes.txt` for a detailed explanation of how this works.

'return' A function (or other code block) is about to return. The local trace function is called; *arg* is the value that will be returned, or `None` if the event is caused by an exception being raised. The trace function's return value is ignored.

'exception' An exception has occurred. The local trace function is called; *arg* is a tuple (exception, value, traceback); the return value specifies the new local trace function.

Note that as an exception is propagated down the chain of callers, an 'exception' event is generated at each level.

For more information on code and frame objects, refer to types.

CPython implementation detail: The `settrace()` function is intended only for implementing debuggers, profilers, coverage tools and the like. Its behavior is part of the implementation platform, rather than part of the language definition, and thus may not be available in all Python implementations.

`sys.settsdump(on_flag)`

Activate dumping of VM measurements using the Pentium timestamp counter, if *on_flag* is true. Deactivate these dumps if *on_flag* is off. The function is available only if Python was compiled with `--with-tsc`. To understand the output of this dump, read `Python/ceval.c` in the Python sources.

버전 2.4에 추가.

CPython implementation detail: This function is intimately bound to CPython implementation details and thus not likely to be implemented elsewhere.

`sys.stdin`

`sys.stdout`

`sys.stderr`

File objects corresponding to the interpreter's standard input, output and error streams. `stdin` is used for all interpreter input except for scripts but including calls to `input()` and `raw_input()`. `stdout` is used for the output of `print` and `expression` statements and for the prompts of `input()` and `raw_input()`. The interpreter's own prompts and (almost all of) its error messages go to `stderr`. `stdout` and `stderr` needn't be built-in file objects: any object is acceptable as long as it has a `write()` method that takes a string argument. (Changing these objects doesn't affect the standard I/O streams of processes executed by `os.popen()`, `os.system()` or the `exec*()` family of functions in the `os` module.)

`sys.__stdin__`

`sys.__stdout__`

`sys.__stderr__`

These objects contain the original values of `stdin`, `stderr` and `stdout` at the start of the program. They are used during finalization, and could be useful to print to the actual standard stream no matter if the `sys.std*` object has been redirected.

It can also be used to restore the actual files to known working file objects in case they have been overwritten with a broken object. However, the preferred way to do this is to explicitly save the previous stream before replacing it, and restore the saved object.

`sys.subversion`

A triple (repo, branch, version) representing the Subversion information of the Python interpreter. *repo* is the name of the repository, 'CPython'. *branch* is a string of one of the forms 'trunk', 'branches/name' or 'tags/name'. *version* is the output of `svnversion`, if the interpreter was built from a Subversion checkout; it contains the revision number (range) and possibly a trailing <M> if there were local modifications. If the tree was exported (or `svnversion` was not available), it is the revision of `Include/patchlevel.h` if the branch is a tag. Otherwise, it is `None`.

버전 2.5에 추가.

참고: Python is now `developed` using Git. In recent Python 2.7 bugfix releases, `subversion` therefore contains placeholder information. It is removed in Python 3.3.

sys.tracebacklimit

When this variable is set to an integer value, it determines the maximum number of levels of traceback information printed when an unhandled exception occurs. The default is 1000. When set to 0 or less, all traceback information is suppressed and only the exception type and value are printed.

sys.version

A string containing the version number of the Python interpreter plus additional information on the build number and compiler used. This string is displayed when the interactive interpreter is started. Do not extract version information out of it, rather, use `version_info` and the functions provided by the `platform` module.

sys.api_version

The C API version for this interpreter. Programmers may find this useful when debugging version conflicts between Python and extension modules.

버전 2.3에 추가.

sys.version_info

A tuple containing the five components of the version number: *major*, *minor*, *micro*, *releaselevel*, and *serial*. All values except *releaselevel* are integers; the release level is 'alpha', 'beta', 'candidate', or 'final'. The `version_info` value corresponding to the Python version 2.0 is (2, 0, 0, 'final', 0). The components can also be accessed by name, so `sys.version_info[0]` is equivalent to `sys.version_info.major` and so on.

버전 2.0에 추가.

버전 2.7에서 변경: Added named component attributes

sys.warnoptions

This is an implementation detail of the warnings framework; do not modify this value. Refer to the `warnings` module for more information on the warnings framework.

sys.winver

The version number used to form registry keys on Windows platforms. This is stored as string resource 1000 in the Python DLL. The value is normally the first three characters of `version`. It is provided in the `sys` module for informational purposes; modifying this value has no effect on the registry keys used by Python. Availability: Windows.

Citations

28.2 sysconfig — Provide access to Python’s configuration information

버전 2.7에 추가.

Source code: [Lib/sysconfig.py](#)

The `sysconfig` module provides access to Python’s configuration information like the list of installation paths and the configuration variables relevant for the current platform.

28.2.1 Configuration variables

A Python distribution contains a `Makefile` and a `pyconfig.h` header file that are necessary to build both the Python binary itself and third-party C extensions compiled using `distutils`.

`sysconfig` puts all variables found in these files in a dictionary that can be accessed using `get_config_vars()` or `get_config_var()`.

Notice that on Windows, it's a much smaller set.

`sysconfig.get_config_vars(*args)`

With no arguments, return a dictionary of all configuration variables relevant for the current platform.

With arguments, return a list of values that result from looking up each argument in the configuration variable dictionary.

For each argument, if the value is not found, return `None`.

`sysconfig.get_config_var(name)`

Return the value of a single variable `name`. Equivalent to `get_config_vars().get(name)`.

If `name` is not found, return `None`.

Example of usage:

```
>>> import sysconfig
>>> sysconfig.get_config_var('Py_ENABLE_SHARED')
0
>>> sysconfig.get_config_var('LIBDIR')
'/usr/local/lib'
>>> sysconfig.get_config_vars('AR', 'CXX')
['ar', 'g++']
```

28.2.2 Installation paths

Python uses an installation scheme that differs depending on the platform and on the installation options. These schemes are stored in `sysconfig` under unique identifiers based on the value returned by `os.name`.

Every new component that is installed using `distutils` or a Distutils-based system will follow the same scheme to copy its file in the right places.

Python currently supports seven schemes:

- `posix_prefix`: scheme for Posix platforms like Linux or Mac OS X. This is the default scheme used when Python or a component is installed.
- `posix_home`: scheme for Posix platforms used when a `home` option is used upon installation. This scheme is used when a component is installed through Distutils with a specific home prefix.
- `posix_user`: scheme for Posix platforms used when a component is installed through Distutils and the `user` option is used. This scheme defines paths located under the user home directory.
- `nt`: scheme for NT platforms like Windows.
- `nt_user`: scheme for NT platforms, when the `user` option is used.
- `os2`: scheme for OS/2 platforms.
- `os2_home`: scheme for OS/2 platforms, when the `user` option is used.

Each scheme is itself composed of a series of paths and each path has a unique identifier. Python currently uses eight paths:

- *stdlib*: directory containing the standard Python library files that are not platform-specific.
- *platstdlib*: directory containing the standard Python library files that are platform-specific.
- *platlib*: directory for site-specific, platform-specific files.
- *purelib*: directory for site-specific, non-platform-specific files.
- *include*: directory for non-platform-specific header files.
- *platinclude*: directory for platform-specific header files.
- *scripts*: directory for script files.
- *data*: directory for data files.

sysconfig provides some functions to determine these paths.

`sysconfig.get_scheme_names()`

Return a tuple containing all schemes currently supported in *sysconfig*.

`sysconfig.get_path_names()`

Return a tuple containing all path names currently supported in *sysconfig*.

`sysconfig.get_path(name[, scheme[, vars[, expand]]])`

Return an installation path corresponding to the path *name*, from the install scheme named *scheme*.

name has to be a value from the list returned by *get_path_names()*.

sysconfig stores installation paths corresponding to each path name, for each platform, with variables to be expanded. For instance the *stdlib* path for the *nt* scheme is: {base}/Lib.

get_path() will use the variables returned by *get_config_vars()* to expand the path. All variables have default values for each platform so one may call this function and get the default value.

If *scheme* is provided, it must be a value from the list returned by *get_scheme_names()*. Otherwise, the default scheme for the current platform is used.

If *vars* is provided, it must be a dictionary of variables that will update the dictionary return by *get_config_vars()*.

If *expand* is set to `False`, the path will not be expanded using the variables.

If *name* is not found, return `None`.

`sysconfig.get_paths([scheme[, vars[, expand]]])`

Return a dictionary containing all installation paths corresponding to an installation scheme. See *get_path()* for more information.

If *scheme* is not provided, will use the default scheme for the current platform.

If *vars* is provided, it must be a dictionary of variables that will update the dictionary used to expand the paths.

If *expand* is set to `false`, the paths will not be expanded.

If *scheme* is not an existing scheme, *get_paths()* will raise a *KeyError*.

28.2.3 Other functions

`sysconfig.get_python_version()`

Return the MAJOR.MINOR Python version number as a string. Similar to `sys.version[:3]`.

`sysconfig.get_platform()`

Return a string that identifies the current platform.

This is used mainly to distinguish platform-specific build directories and platform-specific built distributions. Typically includes the OS name and version and the architecture (as supplied by `os.uname()`), although the exact information included depends on the OS; e.g. for IRIX the architecture isn't particularly important (IRIX only runs on SGI hardware), but for Linux the kernel version isn't particularly important.

Examples of returned values:

- linux-i586
- linux-alpha (?)
- solaris-2.6-sun4u
- irix-5.3
- irix64-6.2

Windows will return one of:

- win-amd64 (64bit Windows on AMD64, aka x86_64, Intel64, and EM64T)
- win-ia64 (64bit Windows on Itanium)
- win32 (all others - specifically, `sys.platform` is returned)

Mac OS X can return:

- macosx-10.6-ppc
- macosx-10.4-ppc64
- macosx-10.3-i386
- macosx-10.4-fat

For other non-POSIX platforms, currently just returns `sys.platform`.

`sysconfig.is_python_build()`

Return True if the current Python installation was built from source.

`sysconfig.parse_config_h(fp[, vars])`

Parse a `config.h`-style file.

fp is a file-like object pointing to the `config.h`-like file.

A dictionary containing name/value pairs is returned. If an optional dictionary is passed in as the second argument, it is used instead of a new dictionary, and updated with the values read in the file.

`sysconfig.get_config_h_filename()`

Return the path of `pyconfig.h`.

`sysconfig.get_makefile_filename()`

Return the path of `Makefile`.

28.3 `__builtin__` — Built-in objects

This module provides direct access to all <built-in> identifiers of Python; for example, `__builtin__.open` is the full name for the built-in function `open()`. See [내장 함수](#) and [내장 상수](#) for documentation.

This module is not normally accessed explicitly by most applications, but can be useful in modules that provide objects with the same name as a built-in value, but in which the built-in of that name is also needed. For example, in a module that wants to implement an `open()` function that wraps the built-in `open()`, this module can be used directly:

```
import __builtin__

def open(path):
    f = __builtin__.open(path, 'r')
    return UpperCaser(f)

class UpperCaser:
    '''Wrapper around a file that converts output to upper-case.'''

    def __init__(self, f):
        self._f = f

    def read(self, count=-1):
        return self._f.read(count).upper()

    # ...
```

CPython implementation detail: Most modules have the name `__builtins__` (note the 's') made available as part of their globals. The value of `__builtins__` is normally either this module or the value of this module's `__dict__` attribute. Since this is an implementation detail, it may not be used by alternate implementations of Python.

28.4 `future_builtins` — Python 3 builtins

버전 2.6에 추가.

This module provides functions that exist in 2.x, but have different behavior in Python 3, so they cannot be put into the 2.x builtins namespace.

Instead, if you want to write code compatible with Python 3 builtins, import them from this module, like this:

```
from future_builtins import map, filter

... code using Python 3-style map and filter ...
```

The [2to3](#) tool that ports Python 2 code to Python 3 will recognize this usage and leave the new builtins alone.

참고: The Python 3 `print()` function is already in the builtins, but cannot be accessed from Python 2 code unless you use the appropriate future statement:

```
from __future__ import print_function
```

Available builtins are:

`future_builtins.ascii` (object)

Returns the same as `repr()`. In Python 3, `repr()` will return printable Unicode characters unescaped, while

`ascii()` will always backslash-escape them. Using `future_builtins.ascii()` instead of `repr()` in 2.6 code makes it clear that you need a pure ASCII return value.

`future_builtins.filter(function, iterable)`

Works like `itertools.ifilter()`.

`future_builtins.hex(object)`

Works like the built-in `hex()`, but instead of `__hex__()` it will use the `__index__()` method on its argument to get an integer that is then converted to hexadecimal.

`future_builtins.map(function, iterable, ...)`

Works like `itertools.imap()`.

참고: In Python 3, `map()` does not accept `None` for the function argument.

`future_builtins.oct(object)`

Works like the built-in `oct()`, but instead of `__oct__()` it will use the `__index__()` method on its argument to get an integer that is then converted to octal.

`future_builtins.zip(*iterables)`

Works like `itertools.izip()`.

28.5 `__main__` — 최상위 스크립트 환경

This module represents the (otherwise anonymous) scope in which the interpreter's main program executes — commands read either from standard input, from a script file, or from an interactive prompt. It is this environment in which the idiomatic 《conditional script》 stanza causes a script to run:

```
if __name__ == "__main__":
    main()
```

28.6 warnings — Warning control

버전 2.1에 추가.

Source code: [Lib/warnings.py](#)

Warning messages are typically issued in situations where it is useful to alert the user of some condition in a program, where that condition (normally) doesn't warrant raising an exception and terminating the program. For example, one might want to issue a warning when a program uses an obsolete module.

Python programmers issue warnings by calling the `warn()` function defined in this module. (C programmers use `PyErr_WarnEx()`; see exceptionhandling for details).

Warning messages are normally written to `sys.stderr`, but their disposition can be changed flexibly, from ignoring all warnings to turning them into exceptions. The disposition of warnings can vary based on the warning category (see below), the text of the warning message, and the source location where it is issued. Repetitions of a particular warning for the same source location are typically suppressed.

There are two stages in warning control: first, each time a warning is issued, a determination is made whether a message should be issued or not; next, if a message is to be issued, it is formatted and printed using a user-settable hook.

The determination whether to issue a warning message is controlled by the warning filter, which is a sequence of matching rules and actions. Rules can be added to the filter by calling `filterwarnings()` and reset to its default state by calling `resetwarnings()`.

The printing of warning messages is done by calling `showwarning()`, which may be overridden; the default implementation of this function formats the message by calling `formatwarning()`, which is also available for use by custom implementations.

더 보기:

`logging.captureWarnings()` allows you to handle all warnings with the standard logging infrastructure.

28.6.1 Warning Categories

There are a number of built-in exceptions that represent warning categories. This categorization is useful to be able to filter out groups of warnings. The following warnings category classes are currently defined:

Class	Description
<code>Warning</code>	This is the base class of all warning category classes. It is a subclass of <code>Exception</code> .
<code>UserWarning</code>	The default category for <code>warn()</code> .
<code>DeprecationWarning</code>	Base category for warnings about deprecated features (ignored by default).
<code>SyntaxWarning</code>	Base category for warnings about dubious syntactic features.
<code>RuntimeWarning</code>	Base category for warnings about dubious runtime features.
<code>FutureWarning</code>	Base category for warnings about constructs that will change semantically in the future.
<code>PendingDeprecationWarning</code>	Base category for warnings about features that will be deprecated in the future (ignored by default).
<code>ImportWarning</code>	Base category for warnings triggered during the process of importing a module (ignored by default).
<code>UnicodeWarning</code>	Base category for warnings related to Unicode.
<code>BytesWarning</code>	Base category for warnings related to bytes and bytearray.

While these are technically built-in exceptions, they are documented here, because conceptually they belong to the warnings mechanism.

User code can define additional warning categories by subclassing one of the standard warning categories. A warning category must always be a subclass of the `Warning` class.

버전 2.7에서 변경: `DeprecationWarning` is ignored by default.

28.6.2 The Warnings Filter

The warnings filter controls whether warnings are ignored, displayed, or turned into errors (raising an exception).

Conceptually, the warnings filter maintains an ordered list of filter specifications; any specific warning is matched against each filter specification in the list in turn until a match is found; the match determines the disposition of the match. Each entry is a tuple of the form `(action, message, category, module, lineno)`, where:

- `action` is one of the following strings:

Value	Disposition
"error"	turn matching warnings into exceptions
"ignore"	never print matching warnings
"always"	always print matching warnings
"default"	print the first occurrence of matching warnings for each location where the warning is issued
"module"	print the first occurrence of matching warnings for each module where the warning is issued
"once"	print only the first occurrence of matching warnings, regardless of location

- *message* is a string containing a regular expression that the start of the warning message must match. The expression is compiled to always be case-insensitive.
- *category* is a class (a subclass of *Warning*) of which the warning category must be a subclass in order to match.
- *module* is a string containing a regular expression that the module name must match. The expression is compiled to be case-sensitive.
- *lineno* is an integer that the line number where the warning occurred must match, or 0 to match all line numbers.

Since the *Warning* class is derived from the built-in *Exception* class, to turn a warning into an error we simply raise *category* (*message*).

The warnings filter is initialized by `-W` options passed to the Python interpreter command line. The interpreter saves the arguments for all `-W` options without interpretation in `sys.warnoptions`; the *warnings* module parses these when it is first imported (invalid options are ignored, after printing a message to `sys.stderr`).

Default Warning Filters

By default, Python installs several warning filters, which can be overridden by the command-line options passed to `-W` and calls to *filterwarnings()*.

- *DeprecationWarning* and *PendingDeprecationWarning*, and *ImportWarning* are ignored.
- *BytesWarning* is ignored unless the `-b` option is given once or twice; in this case this warning is either printed (`-b`) or turned into an exception (`-bb`).

28.6.3 Temporarily Suppressing Warnings

If you are using code that you know will raise a warning, such as a deprecated function, but do not want to see the warning, then it is possible to suppress the warning using the *catch_warnings* context manager:

```
import warnings

def fxn():
    warnings.warn("deprecated", DeprecationWarning)

with warnings.catch_warnings():
    warnings.simplefilter("ignore")
    fxn()
```

While within the context manager all warnings will simply be ignored. This allows you to use known-deprecated code without having to see the warning while not suppressing the warning for other code that might not be aware of its use of deprecated code. Note: this can only be guaranteed in a single-threaded application. If two or more threads use the *catch_warnings* context manager at the same time, the behavior is undefined.

28.6.4 Testing Warnings

To test warnings raised by code, use the `catch_warnings` context manager. With it you can temporarily mutate the warnings filter to facilitate your testing. For instance, do the following to capture all raised warnings to check:

```
import warnings

def fxn():
    warnings.warn("deprecated", DeprecationWarning)

with warnings.catch_warnings(record=True) as w:
    # Cause all warnings to always be triggered.
    warnings.simplefilter("always")
    # Trigger a warning.
    fxn()
    # Verify some things
    assert len(w) == 1
    assert isinstance(w[-1].category, DeprecationWarning)
    assert "deprecated" in str(w[-1].message)
```

One can also cause all warnings to be exceptions by using `error` instead of `always`. One thing to be aware of is that if a warning has already been raised because of a `once/default` rule, then no matter what filters are set the warning will not be seen again unless the warnings registry related to the warning has been cleared.

Once the context manager exits, the warnings filter is restored to its state when the context was entered. This prevents tests from changing the warnings filter in unexpected ways between tests and leading to indeterminate test results. The `showwarning()` function in the module is also restored to its original value. Note: this can only be guaranteed in a single-threaded application. If two or more threads use the `catch_warnings` context manager at the same time, the behavior is undefined.

When testing multiple operations that raise the same kind of warning, it is important to test them in a manner that confirms each operation is raising a new warning (e.g. set warnings to be raised as exceptions and check the operations raise exceptions, check that the length of the warning list continues to increase after each operation, or else delete the previous entries from the warnings list before each new operation).

28.6.5 Updating Code For New Versions of Python

Warnings that are only of interest to the developer are ignored by default. As such you should make sure to test your code with typically ignored warnings made visible. You can do this from the command-line by passing `-Wd` to the interpreter (this is shorthand for `-W default`). This enables default handling for all warnings, including those that are ignored by default. To change what action is taken for encountered warnings you simply change what argument is passed to `-W`, e.g. `-W error`. See the `-W` flag for more details on what is possible.

To programmatically do the same as `-Wd`, use:

```
warnings.simplefilter('default')
```

Make sure to execute this code as soon as possible. This prevents the registering of what warnings have been raised from unexpectedly influencing how future warnings are treated.

Having certain warnings ignored by default is done to prevent a user from seeing warnings that are only of interest to the developer. As you do not necessarily have control over what interpreter a user uses to run their code, it is possible that a new version of Python will be released between your release cycles. The new interpreter release could trigger new warnings in your code that were not there in an older interpreter, e.g. `DeprecationWarning` for a module that you are using. While you as a developer want to be notified that your code is using a deprecated module, to a user this information is essentially noise and provides no benefit to them.

28.6.6 Available Functions

`warnings.warn(message[, category[, stacklevel]])`

Issue a warning, or maybe ignore it or raise an exception. The *category* argument, if given, must be a warning category class (see above); it defaults to `UserWarning`. Alternatively *message* can be a `Warning` instance, in which case *category* will be ignored and `message.__class__` will be used. In this case the message text will be `str(message)`. This function raises an exception if the particular warning issued is changed into an error by the warnings filter see above. The *stacklevel* argument can be used by wrapper functions written in Python, like this:

```
def deprecation(message):
    warnings.warn(message, DeprecationWarning, stacklevel=2)
```

This makes the warning refer to `deprecation()`'s caller, rather than to the source of `deprecation()` itself (since the latter would defeat the purpose of the warning message).

`warnings.warn_explicit(message, category, filename, lineno[, module[, registry[, module_globals]]])`

This is a low-level interface to the functionality of `warn()`, passing in explicitly the message, category, filename and line number, and optionally the module name and the registry (which should be the `__warningregistry__` dictionary of the module). The module name defaults to the filename with `.py` stripped; if no registry is passed, the warning is never suppressed. *message* must be a string and *category* a subclass of `Warning` or *message* may be a `Warning` instance, in which case *category* will be ignored.

module_globals, if supplied, should be the global namespace in use by the code for which the warning is issued. (This argument is used to support displaying source for modules found in zipfiles or other non-filesystem import sources).

버전 2.5에서 변경: Added the *module_globals* parameter.

`warnings.warnpy3k(message[, category[, stacklevel]])`

Issue a warning related to Python 3.x deprecation. Warnings are only shown when Python is started with the `-3` option. Like `warn()` *message* must be a string and *category* a subclass of `Warning`. `warnpy3k()` is using `DeprecationWarning` as default warning class.

버전 2.6에 추가.

`warnings.showwarning(message, category, filename, lineno[, file[, line]])`

Write a warning to a file. The default implementation calls `formatwarning(message, category, filename, lineno, line)` and writes the resulting string to *file*, which defaults to `sys.stderr`. You may replace this function with an alternative implementation by assigning to `warnings.showwarning`. *line* is a line of source code to be included in the warning message; if *line* is not supplied, `showwarning()` will try to read the line specified by *filename* and *lineno*.

버전 2.7에서 변경: The *line* argument is required to be supported.

`warnings.formatwarning(message, category, filename, lineno[, line])`

Format a warning the standard way. This returns a string which may contain embedded newlines and ends in a newline. *line* is a line of source code to be included in the warning message; if *line* is not supplied, `formatwarning()` will try to read the line specified by *filename* and *lineno*.

버전 2.6에서 변경: Added the *line* argument.

`warnings.filterwarnings(action[, message[, category[, module[, lineno[, append]]]])`

Insert an entry into the list of *warnings filter specifications*. The entry is inserted at the front by default; if *append* is true, it is inserted at the end. This checks the types of the arguments, compiles the *message* and *module* regular expressions, and inserts them as a tuple in the list of warnings filters. Entries closer to the front of the list override entries later in the list, if both match a particular warning. Omitted arguments default to a value that matches everything.

`warnings.simplefilter(action[, category[, lineno[, append]]])`

Insert a simple entry into the list of *warnings filter specifications*. The meaning of the function parameters is as for *filterwarnings()*, but regular expressions are not needed as the filter inserted always matches any message in any module as long as the category and line number match.

`warnings.resetwarnings()`

Reset the warnings filter. This discards the effect of all previous calls to *filterwarnings()*, including that of the `-W` command line options and calls to *simplefilter()*.

28.6.7 Available Context Managers

`class warnings.catch_warnings(*[, record=False, module=None])`

A context manager that copies and, upon exit, restores the warnings filter and the *showwarning()* function. If the *record* argument is *False* (the default) the context manager returns *None* on entry. If *record* is *True*, a list is returned that is progressively populated with objects as seen by a custom *showwarning()* function (which also suppresses output to `sys.stdout`). Each object in the list has attributes with the same names as the arguments to *showwarning()*.

The *module* argument takes a module that will be used instead of the module returned when you import *warnings* whose filter will be protected. This argument exists primarily for testing the *warnings* module itself.

참고: The *catch_warnings* manager works by replacing and then later restoring the module's *showwarning()* function and internal list of filter specifications. This means the context manager is modifying global state and therefore is not thread-safe.

참고: In Python 3, the arguments to the constructor for *catch_warnings* are keyword-only arguments.

버전 2.6에 추가.

28.7 contextlib — Utilities for with-statement contexts

버전 2.5에 추가.

Source code: [Lib/contextlib.py](#)

This module provides utilities for common tasks involving the `with` statement. For more information see also [컨텍스트 관리자 형](#) and context-managers.

Functions provided:

`contextlib.contextmanager(func)`

This function is a *decorator* that can be used to define a factory function for `with` statement context managers, without needing to create a class or separate `__enter__()` and `__exit__()` methods.

While many objects natively support use in `with` statements, sometimes a resource needs to be managed that isn't a context manager in its own right, and doesn't implement a `close()` method for use with `contextlib.closing`

An abstract example would be the following to ensure correct resource management:

```

from contextlib import contextmanager

@contextmanager
def managed_resource(*args, **kwargs):
    # Code to acquire resource, e.g.:
    resource = acquire_resource(*args, **kwargs)
    try:
        yield resource
    finally:
        # Code to release resource, e.g.:
        release_resource(resource)

>>> with managed_resource(timeout=3600) as resource:
...     # Resource is released at the end of this block,
...     # even if code in the block raises an exception

```

The function being decorated must return a *generator*-iterator when called. This iterator must yield exactly one value, which will be bound to the targets in the `with` statement's `as` clause, if any.

At the point where the generator yields, the block nested in the `with` statement is executed. The generator is then resumed after the block is exited. If an unhandled exception occurs in the block, it is reraised inside the generator at the point where the `yield` occurred. Thus, you can use a `try...except...finally` statement to trap the error (if any), or ensure that some cleanup takes place. If an exception is trapped merely in order to log it or to perform some action (rather than to suppress it entirely), the generator must reraise that exception. Otherwise the generator context manager will indicate to the `with` statement that the exception has been handled, and execution will resume with the statement immediately following the `with` statement.

`contextlib.nested(mgr1[, mgr2[, ...]])`

Combine multiple context managers into a single nested context manager.

This function has been deprecated in favour of the multiple manager form of the `with` statement.

The one advantage of this function over the multiple manager form of the `with` statement is that argument unpacking allows it to be used with a variable number of context managers as follows:

```

from contextlib import nested

with nested(*managers):
    do_something()

```

Note that if the `__exit__()` method of one of the nested context managers indicates an exception should be suppressed, no exception information will be passed to any remaining outer context managers. Similarly, if the `__exit__()` method of one of the nested managers raises an exception, any previous exception state will be lost; the new exception will be passed to the `__exit__()` methods of any remaining outer context managers. In general, `__exit__()` methods should avoid raising exceptions, and in particular they should not re-raise a passed-in exception.

This function has two major quirks that have led to it being deprecated. Firstly, as the context managers are all constructed before the function is invoked, the `__new__()` and `__init__()` methods of the inner context managers are not actually covered by the scope of the outer context managers. That means, for example, that using `nested()` to open two files is a programming error as the first file will not be closed promptly if an exception is thrown when opening the second file.

Secondly, if the `__enter__()` method of one of the inner context managers raises an exception that is caught and suppressed by the `__exit__()` method of one of the outer context managers, this construct will raise `RuntimeError` rather than skipping the body of the `with` statement.

Developers that need to support nesting of a variable number of context managers can either use the `warnings` module to suppress the `DeprecationWarning` raised by this function or else use this function as a model for an

application specific implementation.

버전 2.7부터 폐지: The with-statement now supports this functionality directly (without the confusing error prone quirks).

`contextlib.closing(thing)`

Return a context manager that closes *thing* upon completion of the block. This is basically equivalent to:

```
from contextlib import contextmanager

@contextmanager
def closing(thing):
    try:
        yield thing
    finally:
        thing.close()
```

And lets you write code like this:

```
from contextlib import closing
import urllib

with closing(urllib.urlopen('http://www.python.org')) as page:
    for line in page:
        print line
```

without needing to explicitly close `page`. Even if an error occurs, `page.close()` will be called when the with block is exited.

더 보기:

PEP 343 - The `<with>` statement The specification, background, and examples for the Python `with` statement.

28.8 abc — Abstract Base Classes

버전 2.6에 추가.

Source code: [Lib/abc.py](#)

This module provides the infrastructure for defining *abstract base classes* (ABCs) in Python, as outlined in **PEP 3119**; see the PEP for why this was added to Python. (See also **PEP 3141** and the *numbers* module regarding a type hierarchy for numbers based on ABCs.)

The *collections* module has some concrete classes that derive from ABCs; these can, of course, be further derived. In addition, the *collections* module has some ABCs that can be used to test whether a class or instance provides a particular interface, for example, if it is hashable or if it is a mapping.

This module provides the following class:

class `abc.ABCMeta`

Metaclass for defining Abstract Base Classes (ABCs).

Use this metaclass to create an ABC. An ABC can be subclassed directly, and then acts as a mix-in class. You can also register unrelated concrete classes (even built-in classes) and unrelated ABCs as «virtual subclasses» – these and their descendants will be considered subclasses of the registering ABC by the built-in *issubclass()*

function, but the registering ABC won't show up in their MRO (Method Resolution Order) nor will method implementations defined by the registering ABC be callable (not even via `super()`).¹

Classes created with a metaclass of `ABCMeta` have the following method:

register (*subclass*)

Register *subclass* as a 《virtual subclass》 of this ABC. For example:

```
from abc import ABCMeta

class MyABC:
    __metaclass__ = ABCMeta

MyABC.register(tuple)

assert issubclass(tuple, MyABC)
assert isinstance((), MyABC)
```

You can also override this method in an abstract base class:

__subclasshook__ (*subclass*)

(Must be defined as a class method.)

Check whether *subclass* is considered a subclass of this ABC. This means that you can customize the behavior of `issubclass` further without the need to call `register()` on every class you want to consider a subclass of the ABC. (This class method is called from the `__subclasscheck__()` method of the ABC.)

This method should return `True`, `False` or `NotImplemented`. If it returns `True`, the *subclass* is considered a subclass of this ABC. If it returns `False`, the *subclass* is not considered a subclass of this ABC, even if it would normally be one. If it returns `NotImplemented`, the subclass check is continued with the usual mechanism.

For a demonstration of these concepts, look at this example ABC definition:

```
class Foo(object):
    def __getitem__(self, index):
        ...
    def __len__(self):
        ...
    def get_iterator(self):
        return iter(self)

class MyIterable:
    __metaclass__ = ABCMeta

    @abstractmethod
    def __iter__(self):
        while False:
            yield None

    def get_iterator(self):
        return self.__iter__()

    @classmethod
    def __subclasshook__(cls, C):
        if cls is MyIterable:
            if any("__iter__" in B.__dict__ for B in C.__mro__):
```

(다음 페이지에 계속)

¹ C++ programmers should note that Python's virtual base class concept is not the same as C++'s.

(이전 페이지에서 계속)

```

        return True
    return NotImplemented

MyIterable.register(Foo)

```

The ABC `MyIterable` defines the standard iterable method, `__iter__()`, as an abstract method. The implementation given here can still be called from subclasses. The `get_iterator()` method is also part of the `MyIterable` abstract base class, but it does not have to be overridden in non-abstract derived classes.

The `__subclasshook__()` class method defined here says that any class that has an `__iter__()` method in its `__dict__` (or in that of one of its base classes, accessed via the `__mro__` list) is considered a `MyIterable` too.

Finally, the last line makes `Foo` a virtual subclass of `MyIterable`, even though it does not define an `__iter__()` method (it uses the old-style iterable protocol, defined in terms of `__len__()` and `__getitem__()`). Note that this will not make `get_iterator` available as a method of `Foo`, so it is provided separately.

It also provides the following decorators:

`abc.abstractmethod(function)`

A decorator indicating abstract methods.

Using this decorator requires that the class's metaclass is `ABCMeta` or is derived from it. A class that has a metaclass derived from `ABCMeta` cannot be instantiated unless all of its abstract methods and properties are overridden. The abstract methods can be called using any of the normal `<super>` call mechanisms.

Dynamically adding abstract methods to a class, or attempting to modify the abstraction status of a method or class once it is created, are not supported. The `abstractmethod()` only affects subclasses derived using regular inheritance; `<virtual subclasses>` registered with the ABC's `register()` method are not affected.

Usage:

```

class C:
    __metaclass__ = ABCMeta
    @abstractmethod
    def my_abstract_method(self, ...):
        ...

```

참고: Unlike Java abstract methods, these abstract methods may have an implementation. This implementation can be called via the `super()` mechanism from the class that overrides it. This could be useful as an end-point for a super-call in a framework that uses cooperative multiple-inheritance.

`abc.abstractproperty([fget[, fset[, fdel[, doc]]]])`

A subclass of the built-in `property()`, indicating an abstract property.

Using this function requires that the class's metaclass is `ABCMeta` or is derived from it. A class that has a metaclass derived from `ABCMeta` cannot be instantiated unless all of its abstract methods and properties are overridden. The abstract properties can be called using any of the normal `<super>` call mechanisms.

Usage:

```

class C:
    __metaclass__ = ABCMeta
    @abstractproperty
    def my_abstract_property(self):
        ...

```

This defines a read-only property; you can also define a read-write abstract property using the <long> form of property declaration:

```
class C:
    __metaclass__ = ABCMeta
    def getx(self): ...
    def setx(self, value): ...
    x = abstractproperty(getx, setx)
```

28.9 atexit — Exit handlers

버전 2.0에 추가.

Source code: [Lib/atexit.py](#)

The `atexit` module defines a single function to register cleanup functions. Functions thus registered are automatically executed upon normal interpreter termination. `atexit` runs these functions in the *reverse* order in which they were registered; if you register A, B, and C, at interpreter termination time they will be run in the order C, B, A.

Note: The functions registered via this module are not called when the program is killed by a signal not handled by Python, when a Python fatal internal error is detected, or when `os._exit()` is called.

This is an alternate interface to the functionality provided by the `sys.exitfunc()` variable.

Note: This module is unlikely to work correctly when used with other code that sets `sys.exitfunc`. In particular, other core Python modules are free to use `atexit` without the programmer's knowledge. Authors who use `sys.exitfunc` should convert their code to use `atexit` instead. The simplest way to convert code that sets `sys.exitfunc` is to import `atexit` and register the function that had been bound to `sys.exitfunc`.

`atexit.register(func[, *args[, **kwargs]])`

Register `func` as a function to be executed at termination. Any optional arguments that are to be passed to `func` must be passed as arguments to `register()`. It is possible to register the same function and arguments more than once.

At normal program termination (for instance, if `sys.exit()` is called or the main module's execution completes), all functions registered are called in last in, first out order. The assumption is that lower level modules will normally be imported before higher level modules and thus must be cleaned up later.

If an exception is raised during execution of the exit handlers, a traceback is printed (unless `SystemExit` is raised) and the exception information is saved. After all exit handlers have had a chance to run the last exception to be raised is re-raised.

버전 2.6에서 변경: This function now returns `func`, which makes it possible to use it as a decorator.

더 보기:

Module `readline` Useful example of `atexit` to read and write `readline` history files.

28.9.1 atexit Example

The following simple example demonstrates how a module can initialize a counter from a file when it is imported and save the counter's updated value automatically when the program terminates without relying on the application making an explicit call into this module at termination.

```
try:
    _count = int(open("counter").read())
except IOError:
    _count = 0

def incrcounter(n):
    global _count
    _count = _count + n

def savecounter():
    open("counter", "w").write("%d" % _count)

import atexit
atexit.register(savecounter)
```

Positional and keyword arguments may also be passed to `register()` to be passed along to the registered function when it is called:

```
def goodbye(name, adjective):
    print 'Goodbye, %s, it was %s to meet you.' % (name, adjective)

import atexit
atexit.register(goodbye, 'Donny', 'nice')

# or:
atexit.register(goodbye, adjective='nice', name='Donny')
```

Usage as a *decorator*:

```
import atexit

@atexit.register
def goodbye():
    print "You are now leaving the Python sector."
```

This only works with functions that can be called without arguments.

28.10 traceback — Print or retrieve a stack traceback

This module provides a standard interface to extract, format and print stack traces of Python programs. It exactly mimics the behavior of the Python interpreter when it prints a stack trace. This is useful when you want to print stack traces under program control, such as in a 《wrapper》 around the interpreter.

The module uses traceback objects — this is the object type that is stored in the variables `sys.exc_traceback` (deprecated) and `sys.last_traceback` and returned as the third item from `sys.exc_info()`.

The module defines the following functions:

`traceback.print_tb(tb[, limit[, file]])`

Print up to *limit* stack trace entries from the traceback object *tb*. If *limit* is omitted or `None`, all entries are printed.

If *file* is omitted or `None`, the output goes to `sys.stderr`; otherwise it should be an open file or file-like object to receive the output.

`traceback.print_exception(etype, value, tb[, limit[, file]])`

Print exception information and up to *limit* stack trace entries from the traceback *tb* to *file*. This differs from `print_tb()` in the following ways: (1) if *tb* is not `None`, it prints a header `Traceback (most recent call last):`; (2) it prints the exception *etype* and *value* after the stack trace; (3) if *etype* is `SyntaxError` and *value* has the appropriate format, it prints the line where the syntax error occurred with a caret indicating the approximate position of the error.

`traceback.print_exc([limit[, file]])`

This is a shorthand for `print_exception(sys.exc_type, sys.exc_value, sys.exc_traceback, limit, file)`. (In fact, it uses `sys.exc_info()` to retrieve the same information in a thread-safe way instead of using the deprecated variables.)

`traceback.format_exc([limit])`

This is like `print_exc(limit)` but returns a string instead of printing to a file.

버전 2.4에 추가.

`traceback.print_last([limit[, file]])`

This is a shorthand for `print_exception(sys.last_type, sys.last_value, sys.last_traceback, limit, file)`. In general it will work only after an exception has reached an interactive prompt (see `sys.last_type`).

`traceback.print_stack([f[, limit[, file]]])`

This function prints a stack trace from its invocation point. The optional *f* argument can be used to specify an alternate stack frame to start. The optional *limit* and *file* arguments have the same meaning as for `print_exception()`.

`traceback.extract_tb(tb[, limit])`

Return a list of up to *limit* «pre-processed» stack trace entries extracted from the traceback object *tb*. It is useful for alternate formatting of stack traces. If *limit* is omitted or `None`, all entries are extracted. A «pre-processed» stack trace entry is a 4-tuple (*filename*, *line number*, *function name**, *text*) representing the information that is usually printed for a stack trace. The *text* is a string with leading and trailing whitespace stripped; if the source is not available it is `None`.

`traceback.extract_stack([f[, limit]])`

Extract the raw traceback from the current stack frame. The return value has the same format as for `extract_tb()`. The optional *f* and *limit* arguments have the same meaning as for `print_stack()`.

`traceback.format_list(extracted_list)`

Given a list of tuples as returned by `extract_tb()` or `extract_stack()`, return a list of strings ready for printing. Each string in the resulting list corresponds to the item with the same index in the argument list. Each string ends in a newline; the strings may contain internal newlines as well, for those items whose source text line is not `None`.

`traceback.format_exception_only(etype, value)`

Format the exception part of a traceback. The arguments are the exception type, *etype* and *value* such as given by `sys.last_type` and `sys.last_value`. The return value is a list of strings, each ending in a newline. Normally, the list contains a single string; however, for `SyntaxError` exceptions, it contains several lines that (when printed) display detailed information about where the syntax error occurred. The message indicating which exception occurred is the always last string in the list.

`traceback.format_exception(etype, value, tb[, limit])`

Format a stack trace and the exception information. The arguments have the same meaning as the corresponding arguments to `print_exception()`. The return value is a list of strings, each ending in a newline and some containing internal newlines. When these lines are concatenated and printed, exactly the same text is printed as does `print_exception()`.

```
traceback.format_tb(tb[, limit])
```

A shorthand for `format_list(extract_tb(tb, limit))`.

```
traceback.format_stack([f[, limit]])
```

A shorthand for `format_list(extract_stack(f, limit))`.

```
traceback.tb_lineno(tb)
```

This function returns the current line number set in the traceback object. This function was necessary because in versions of Python prior to 2.3 when the `-O` flag was passed to Python the `tb.tb_lineno` was not updated correctly. This function has no use in versions past 2.3.

28.10.1 Traceback Examples

This simple example implements a basic read-eval-print loop, similar to (but less useful than) the standard Python interactive interpreter loop. For a more complete implementation of the interpreter loop, refer to the [code](#) module.

```
import sys, traceback

def run_user_code(envdir):
    source = raw_input(">>> ")
    try:
        exec source in envdir
    except:
        print "Exception in user code:"
        print '-'*60
        traceback.print_exc(file=sys.stdout)
        print '-'*60

envdir = {}
while 1:
    run_user_code(envdir)
```

The following example demonstrates the different ways to print and format the exception and traceback:

```
import sys, traceback

def lumberjack():
    bright_side_of_death()

def bright_side_of_death():
    return tuple()[0]

try:
    lumberjack()
except IndexError:
    exc_type, exc_value, exc_traceback = sys.exc_info()
    print "**** print_tb:"
    traceback.print_tb(exc_traceback, limit=1, file=sys.stdout)
    print "**** print_exception:"
    traceback.print_exception(exc_type, exc_value, exc_traceback,
                             limit=2, file=sys.stdout)

    print "**** print_exc:"
    traceback.print_exc()
    print "**** format_exc, first and last line:"
    formatted_lines = traceback.format_exc().splitlines()
    print formatted_lines[0]
    print formatted_lines[-1]
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

print """ format_exception:
print repr(traceback.format_exception(exc_type, exc_value,
                                     exc_traceback))

print """ extract_tb:
print repr(traceback.extract_tb(exc_traceback))
print """ format_tb:
print repr(traceback.format_tb(exc_traceback))
print """ tb_lineno: ", exc_traceback.tb_lineno

```

The output for the example would look similar to this:

```

*** print_tb:
File "<doctest...>", line 10, in <module>
    lumberjack()
*** print_exception:
Traceback (most recent call last):
  File "<doctest...>", line 10, in <module>
    lumberjack()
  File "<doctest...>", line 4, in lumberjack
    bright_side_of_death()
IndexError: tuple index out of range
*** print_exc:
Traceback (most recent call last):
  File "<doctest...>", line 10, in <module>
    lumberjack()
  File "<doctest...>", line 4, in lumberjack
    bright_side_of_death()
IndexError: tuple index out of range
*** format_exc, first and last line:
Traceback (most recent call last):
IndexError: tuple index out of range
*** format_exception:
['Traceback (most recent call last):\n',
 '  File "<doctest...>", line 10, in <module>\n    lumberjack()\n',
 '  File "<doctest...>", line 4, in lumberjack\n    bright_side_of_death()\n',
 '  File "<doctest...>", line 7, in bright_side_of_death\n    return tuple()[0]\n',
 'IndexError: tuple index out of range\n']
*** extract_tb:
[('<doctest...>', 10, '<module>', 'lumberjack()'),
 ('<doctest...>', 4, 'lumberjack', 'bright_side_of_death()'),
 ('<doctest...>', 7, 'bright_side_of_death', 'return tuple()[0]')]
*** format_tb:
['  File "<doctest...>", line 10, in <module>\n    lumberjack()\n',
 '  File "<doctest...>", line 4, in lumberjack\n    bright_side_of_death()\n',
 '  File "<doctest...>", line 7, in bright_side_of_death\n    return tuple()[0]\n']
*** tb_lineno: 10

```

The following example shows the different ways to print and format the stack:

```

>>> import traceback
>>> def another_function():
...     lumberstack()
...
>>> def lumberstack():
...     traceback.print_stack()
...     print repr(traceback.extract_stack())

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

...     print repr(traceback.format_stack())
...
>>> another_function()
File "<doctest>", line 10, in <module>
    another_function()
File "<doctest>", line 3, in another_function
    lumberstack()
File "<doctest>", line 6, in lumberstack
    traceback.print_stack()
[('<doctest>', 10, '<module>', 'another_function()'),
 ('<doctest>', 3, 'another_function', 'lumberstack()'),
 ('<doctest>', 7, 'lumberstack', 'print repr(traceback.extract_stack())')]
['  File "<doctest>", line 10, in <module>\n    another_function()\n',
 '  File "<doctest>", line 3, in another_function\n    lumberstack()\n',
 '  File "<doctest>", line 8, in lumberstack\n    print repr(traceback.format_
↪stack())\n']

```

This last example demonstrates the final few formatting functions:

```

>>> import traceback
>>> traceback.format_list([('spam.py', 3, '<module>', 'spam.eggs()'),
...                       ('eggs.py', 42, 'eggs', 'return "bacon"')])
['  File "spam.py", line 3, in <module>\n    spam.eggs()\n',
 '  File "eggs.py", line 42, in eggs\n    return "bacon"\n']
>>> an_error = IndexError('tuple index out of range')
>>> traceback.format_exception_only(type(an_error), an_error)
['IndexError: tuple index out of range\n']

```

28.11 `__future__` — Future statement definitions

Source code: [Lib/__future__.py](#)

`__future__` is a real module, and serves three purposes:

- To avoid confusing existing tools that analyze import statements and expect to find the modules they're importing.
- To ensure that future statements run under releases prior to 2.1 at least yield runtime exceptions (the import of `__future__` will fail, because there was no module of that name prior to 2.1).
- To document when incompatible changes were introduced, and when they will be — or were — made mandatory. This is a form of executable documentation, and can be inspected programmatically via importing `__future__` and examining its contents.

Each statement in `__future__.py` is of the form:

```

FeatureName = _Feature(OptionalRelease, MandatoryRelease,
                        CompilerFlag)

```

where, normally, *OptionalRelease* is less than *MandatoryRelease*, and both are 5-tuples of the same form as `sys.version_info`:

```

(PY_MAJOR_VERSION, # the 2 in 2.1.0a3; an int
 PY_MINOR_VERSION, # the 1; an int

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

PY_MICRO_VERSION, # the 0; an int
PY_RELEASE_LEVEL, # "alpha", "beta", "candidate" or "final"; string
PY_RELEASE_SERIAL # the 3; an int
)

```

OptionalRelease records the first release in which the feature was accepted.

In the case of a *MandatoryRelease* that has not yet occurred, *MandatoryRelease* predicts the release in which the feature will become part of the language.

Else *MandatoryRelease* records when the feature became part of the language; in releases at or after that, modules no longer need a future statement to use the feature in question, but may continue to use such imports.

MandatoryRelease may also be `None`, meaning that a planned feature got dropped.

Instances of class `_Feature` have two corresponding methods, `getOptionalRelease()` and `getMandatoryRelease()`.

CompilerFlag is the (bitfield) flag that should be passed in the fourth argument to the built-in function `compile()` to enable the feature in dynamically compiled code. This flag is stored in the `compiler_flag` attribute on `_Feature` instances.

No feature description will ever be deleted from `__future__`. Since its introduction in Python 2.1 the following features have found their way into the language using this mechanism:

feature	optional in	mandatory in	effect
nested_scopes	2.1.0b1	2.2	PEP 227 : <i>Statically Nested Scopes</i>
generators	2.2.0a1	2.3	PEP 255 : <i>Simple Generators</i>
division	2.2.0a2	3.0	PEP 238 : <i>Changing the Division Operator</i>
absolute_import	2.5.0a1	3.0	PEP 328 : <i>Imports: Multi-Line and Absolute/Relative</i>
with_statement	2.5.0a1	2.6	PEP 343 : <i>The «with» Statement</i>
print_function	2.6.0a2	3.0	PEP 3105 : <i>Make print a function</i>
unicode_literals	2.6.0a2	3.0	PEP 3112 : <i>Bytes literals in Python 3000</i>

더 보기:

future How the compiler treats future imports.

28.12 gc — Garbage Collector interface

This module provides an interface to the optional garbage collector. It provides the ability to disable the collector, tune the collection frequency, and set debugging options. It also provides access to unreachable objects that the collector found but cannot free. Since the collector supplements the reference counting already used in Python, you can disable the collector if you are sure your program does not create reference cycles. Automatic collection can be disabled by calling `gc.disable()`. To debug a leaking program call `gc.set_debug(gc.DEBUG_LEAK)`. Notice that this includes `gc.DEBUG_SAVEALL`, causing garbage-collected objects to be saved in `gc.garbage` for inspection.

The `gc` module provides the following functions:

`gc.enable()`
Enable automatic garbage collection.

`gc.disable()`

Disable automatic garbage collection.

`gc.isenabled()`

Returns true if automatic collection is enabled.

`gc.collect([generation])`

With no arguments, run a full collection. The optional argument *generation* may be an integer specifying which generation to collect (from 0 to 2). A `ValueError` is raised if the generation number is invalid. The number of unreachable objects found is returned.

버전 2.5에서 변경: The optional *generation* argument was added.

버전 2.6에서 변경: The free lists maintained for a number of built-in types are cleared whenever a full collection or collection of the highest generation (2) is run. Not all items in some free lists may be freed due to the particular implementation, in particular `int` and `float`.

`gc.set_debug(flags)`

Set the garbage collection debugging flags. Debugging information will be written to `sys.stderr`. See below for a list of debugging flags which can be combined using bit operations to control debugging.

`gc.get_debug()`

Return the debugging flags currently set.

`gc.get_objects()`

Returns a list of all objects tracked by the collector, excluding the list returned.

버전 2.2에 추가.

`gc.set_threshold(threshold0[, threshold1[, threshold2]])`

Set the garbage collection thresholds (the collection frequency). Setting *threshold0* to zero disables collection.

The GC classifies objects into three generations depending on how many collection sweeps they have survived. New objects are placed in the youngest generation (generation 0). If an object survives a collection it is moved into the next older generation. Since generation 2 is the oldest generation, objects in that generation remain there after a collection. In order to decide when to run, the collector keeps track of the number object allocations and deallocations since the last collection. When the number of allocations minus the number of deallocations exceeds *threshold0*, collection starts. Initially only generation 0 is examined. If generation 0 has been examined more than *threshold1* times since generation 1 has been examined, then generation 1 is examined as well. Similarly, *threshold2* controls the number of collections of generation 1 before collecting generation 2.

`gc.get_count()`

Return the current collection counts as a tuple of (*count0*, *count1*, *count2*).

버전 2.5에 추가.

`gc.get_threshold()`

Return the current collection thresholds as a tuple of (*threshold0*, *threshold1*, *threshold2*).

`gc.get_referrers(*objs)`

Return the list of objects that directly refer to any of *objs*. This function will only locate those containers which support garbage collection; extension types which do refer to other objects but do not support garbage collection will not be found.

Note that objects which have already been dereferenced, but which live in cycles and have not yet been collected by the garbage collector can be listed among the resulting referrers. To get only currently live objects, call `collect()` before calling `get_referrers()`.

Care must be taken when using objects returned by `get_referrers()` because some of them could still be under construction and hence in a temporarily invalid state. Avoid using `get_referrers()` for any purpose other than debugging.

버전 2.2에 추가.

`gc.get_referents(*objs)`

Return a list of objects directly referred to by any of the arguments. The referents returned are those objects visited by the arguments' C-level `tp_traverse` methods (if any), and may not be all objects actually directly reachable. `tp_traverse` methods are supported only by objects that support garbage collection, and are only required to visit objects that may be involved in a cycle. So, for example, if an integer is directly reachable from an argument, that integer object may or may not appear in the result list.

버전 2.3에 추가.

`gc.is_tracked(obj)`

Returns `True` if the object is currently tracked by the garbage collector, `False` otherwise. As a general rule, instances of atomic types aren't tracked and instances of non-atomic types (containers, user-defined objects...) are. However, some type-specific optimizations can be present in order to suppress the garbage collector footprint of simple instances (e.g. dicts containing only atomic keys and values):

```
>>> gc.is_tracked(0)
False
>>> gc.is_tracked("a")
False
>>> gc.is_tracked([])
True
>>> gc.is_tracked({})
False
>>> gc.is_tracked({"a": 1})
False
>>> gc.is_tracked({"a": []})
True
```

버전 2.7에 추가.

The following variable is provided for read-only access (you can mutate its value but should not rebind it):

`gc.garbage`

A list of objects which the collector found to be unreachable but could not be freed (uncollectable objects). By default, this list contains only objects with `__del__()` methods.¹ Objects that have `__del__()` methods and are part of a reference cycle cause the entire reference cycle to be uncollectable, including objects not necessarily in the cycle but reachable only from it. Python doesn't collect such cycles automatically because, in general, it isn't possible for Python to guess a safe order in which to run the `__del__()` methods. If you know a safe order, you can force the issue by examining the *garbage* list, and explicitly breaking cycles due to your objects within the list. Note that these objects are kept alive even so by virtue of being in the *garbage* list, so they should be removed from *garbage* too. For example, after breaking cycles, do `del gc.garbage[:]` to empty the list. It's generally better to avoid the issue by not creating cycles containing objects with `__del__()` methods, and *garbage* can be examined in that case to verify that no such cycles are being created.

If `DEBUG_SAVEALL` is set, then all unreachable objects will be added to this list rather than freed.

The following constants are provided for use with `set_debug()`:

`gc.DEBUG_STATS`

Print statistics during collection. This information can be useful when tuning the collection frequency.

`gc.DEBUG_COLLECTABLE`

Print information on collectable objects found.

`gc.DEBUG_UNCOLLECTABLE`

Print information of uncollectable objects found (objects which are not reachable but cannot be freed by the collector). These objects will be added to the *garbage* list.

¹ Prior to Python 2.2, the list contained all instance objects in unreachable cycles, not only those with `__del__()` methods.

gc.DEBUG_INSTANCES

When `DEBUG_COLLECTABLE` or `DEBUG_UNCOLLECTABLE` is set, print information about instance objects found.

gc.DEBUG_OBJECTS

When `DEBUG_COLLECTABLE` or `DEBUG_UNCOLLECTABLE` is set, print information about objects other than instance objects found.

gc.DEBUG_SAVEALL

When set, all unreachable objects found will be appended to *garbage* rather than being freed. This can be useful for debugging a leaking program.

gc.DEBUG_LEAK

The debugging flags necessary for the collector to print information about a leaking program (equal to `DEBUG_COLLECTABLE | DEBUG_UNCOLLECTABLE | DEBUG_INSTANCES | DEBUG_OBJECTS | DEBUG_SAVEALL`).

28.13 inspect — Inspect live objects

버전 2.1에 추가.

Source code: [Lib/inspect.py](#)

The *inspect* module provides several useful functions to help get information about live objects such as modules, classes, methods, functions, tracebacks, frame objects, and code objects. For example, it can help you examine the contents of a class, retrieve the source code of a method, extract and format the argument list for a function, or get all the information you need to display a detailed traceback.

There are four main kinds of services provided by this module: type checking, getting source code, inspecting classes and functions, and examining the interpreter stack.

28.13.1 Types and members

The *getmembers()* function retrieves the members of an object such as a class or module. The sixteen functions whose names begin with `《is》` are mainly provided as convenient choices for the second argument to *getmembers()*. They also help you determine when you can expect to find the following special attributes:

Type	Attribute	Description
module	<code>__doc__</code>	documentation string
	<code>__file__</code>	filename (missing for built-in modules)
class	<code>__doc__</code>	documentation string
	<code>__module__</code>	name of module in which this class was defined
method	<code>__doc__</code>	documentation string
	<code>__name__</code>	name with which this method was defined
	<code>im_class</code>	class object that asked for this method
	<code>im_func</code> or <code>__func__</code>	function object containing implementation of method
	<code>im_self</code> or <code>__self__</code>	instance to which this method is bound, or <code>None</code>
function	<code>__doc__</code>	documentation string
	<code>__name__</code>	name with which this function was defined
	<code>func_code</code>	code object containing compiled function <i>bytecode</i>
	<code>func_defaults</code>	tuple of any default values for arguments

다음 페이지

표 1 - 이전 페이지에서 계속

Type	Attribute	Description
	func_doc	(same as <code>__doc__</code>)
	func_globals	global namespace in which this function was defined
	func_name	(same as <code>__name__</code>)
generator	<code>__iter__</code>	defined to support iteration over container
	close	raises new <code>GeneratorExit</code> exception inside the generator to terminate the iteration
	gi_code	code object
	gi_frame	frame object or possibly <code>None</code> once the generator has been exhausted
	gi_running	set to 1 when generator is executing, 0 otherwise
	next	return the next item from the container
	send	resumes the generator and <code><< sends >></code> a value that becomes the result of the current yield-expression
	throw	used to raise an exception inside the generator
traceback	tb_frame	frame object at this level
	tb_lasti	index of last attempted instruction in bytecode
	tb_lineno	current line number in Python source code
	tb_next	next inner traceback object (called by this level)
frame	f_back	next outer frame object (this frame's caller)
	f_builtins	builtins namespace seen by this frame
	f_code	code object being executed in this frame
	f_exc_traceback	traceback if raised in this frame, or <code>None</code>
	f_exc_type	exception type if raised in this frame, or <code>None</code>
	f_exc_value	exception value if raised in this frame, or <code>None</code>
	f_globals	global namespace seen by this frame
	f_lasti	index of last attempted instruction in bytecode
	f_lineno	current line number in Python source code
	f_locals	local namespace seen by this frame
	f_restricted	0 or 1 if frame is in restricted execution mode
	f_trace	tracing function for this frame, or <code>None</code>
code	co_argcount	number of arguments (not including <code>*</code> or <code>**</code> args)
	co_code	string of raw compiled bytecode
	co_consts	tuple of constants used in the bytecode
	co_filename	name of file in which this code object was created
	co_firstlineno	number of first line in Python source code
	co_flags	bitmap: 1=optimized 2=newlocals 4= <code>*arg</code> 8= <code>**arg</code>
	co_inotab	encoded mapping of line numbers to bytecode indices
	co_name	name with which this code object was defined
	co_names	tuple of names of local variables
	co_nlocals	number of local variables
	co_stacksize	virtual machine stack space required
	co_varnames	tuple of names of arguments and local variables
builtin	<code>__doc__</code>	documentation string
	<code>__name__</code>	original name of this function or method
	<code>__self__</code>	instance to which a method is bound, or <code>None</code>

Note:

(1) 버전 2.2에서 변경: `im_class` used to refer to the class that defined the method.

`inspect.getmembers(object[, predicate])`

Return all the members of an object in a list of (name, value) pairs sorted by name. If the optional *predicate* argument is supplied, only members for which the predicate returns a true value are included.

참고: `getmembers()` does not return metaclass attributes when the argument is a class (this behavior is inherited from the `dir()` function).

`inspect.getmoduleinfo(path)`

Return a tuple of values that describe how Python will interpret the file identified by *path* if it is a module, or `None` if it would not be identified as a module. The return tuple is `(name, suffix, mode, module_type)`, where *name* is the name of the module without the name of any enclosing package, *suffix* is the trailing part of the file name (which may not be a dot-delimited extension), *mode* is the `open()` mode that would be used (`'r'` or `'rb'`), and *module_type* is an integer giving the type of the module. *module_type* will have a value which can be compared to the constants defined in the `imp` module; see the documentation for that module for more information on module types.

버전 2.6에서 변경: Returns a *named tuple* `ModuleInfo(name, suffix, mode, module_type)`.

`inspect.getmodulename(path)`

Return the name of the module named by the file *path*, without including the names of enclosing packages. This uses the same algorithm as the interpreter uses when searching for modules. If the name cannot be matched according to the interpreter's rules, `None` is returned.

`inspect.ismodule(object)`

Return true if the object is a module.

`inspect.isclass(object)`

Return true if the object is a class, whether built-in or created in Python code.

`inspect.ismethod(object)`

Return true if the object is a bound or unbound method written in Python.

`inspect.isfunction(object)`

Return true if the object is a Python function, which includes functions created by a *lambda* expression.

`inspect.isgeneratorfunction(object)`

Return true if the object is a Python generator function.

버전 2.6에 추가.

`inspect.isgenerator(object)`

Return true if the object is a generator.

버전 2.6에 추가.

`inspect.istraceback(object)`

Return true if the object is a traceback.

`inspect.isframe(object)`

Return true if the object is a frame.

`inspect.iscode(object)`

Return true if the object is a code.

`inspect.isbuiltin(object)`

Return true if the object is a built-in function or a bound built-in method.

`inspect.isroutine(object)`

Return true if the object is a user-defined or built-in function or method.

`inspect.isabstract(object)`

Return true if the object is an abstract base class.

버전 2.6에 추가.

`inspect.ismethoddescriptor(object)`

Return true if the object is a method descriptor, but not if `ismethod()`, `isclass()`, `isfunction()` or `isbuiltin()` are true.

This is new as of Python 2.2, and, for example, is true of `int.__add__`. An object passing this test has a `__get__()` method but not a `__set__()` method, but beyond that the set of attributes varies. A `__name__` attribute is usually sensible, and `__doc__` often is.

Methods implemented via descriptors that also pass one of the other tests return false from the `ismethoddescriptor()` test, simply because the other tests promise more – you can, e.g., count on having the `im_func` attribute (etc) when an object passes `ismethod()`.

`inspect.isdatadescriptor(object)`

Return true if the object is a data descriptor.

Data descriptors have both a `__get__` and a `__set__` method. Examples are properties (defined in Python), getsets, and members. The latter two are defined in C and there are more specific tests available for those types, which is robust across Python implementations. Typically, data descriptors will also have `__name__` and `__doc__` attributes (properties, getsets, and members have both of these attributes), but this is not guaranteed.

버전 2.3에 추가.

`inspect.isgetsetdescriptor(object)`

Return true if the object is a getset descriptor.

CPython implementation detail: getsets are attributes defined in extension modules via `PyGetSetDef` structures. For Python implementations without such types, this method will always return `False`.

버전 2.5에 추가.

`inspect.ismemberdescriptor(object)`

Return true if the object is a member descriptor.

CPython implementation detail: Member descriptors are attributes defined in extension modules via `PyMemberDef` structures. For Python implementations without such types, this method will always return `False`.

버전 2.5에 추가.

28.13.2 Retrieving source code

`inspect.getdoc(object)`

Get the documentation string for an object, cleaned up with `cleandoc()`.

`inspect.getcomments(object)`

Return in a single string any lines of comments immediately preceding the object's source code (for a class, function, or method), or at the top of the Python source file (if the object is a module).

`inspect.getfile(object)`

Return the name of the (text or binary) file in which an object was defined. This will fail with a `TypeError` if the object is a built-in module, class, or function.

`inspect.getmodule(object)`

Try to guess which module an object was defined in.

`inspect.getsourcefile(object)`

Return the name of the Python source file in which an object was defined. This will fail with a `TypeError` if the object is a built-in module, class, or function.

`inspect.getsourcelines(object)`

Return a list of source lines and starting line number for an object. The argument may be a module, class, method,

function, traceback, frame, or code object. The source code is returned as a list of the lines corresponding to the object and the line number indicates where in the original source file the first line of code was found. An *IOError* is raised if the source code cannot be retrieved.

`inspect.getsource(object)`

Return the text of the source code for an object. The argument may be a module, class, method, function, traceback, frame, or code object. The source code is returned as a single string. An *IOError* is raised if the source code cannot be retrieved.

`inspect.cleandoc(doc)`

Clean up indentation from docstrings that are indented to line up with blocks of code.

All leading whitespace is removed from the first line. Any leading whitespace that can be uniformly removed from the second line onwards is removed. Empty lines at the beginning and end are subsequently removed. Also, all tabs are expanded to spaces.

버전 2.6에 추가.

28.13.3 Classes and functions

`inspect.getclasstree(classes[, unique])`

Arrange the given list of classes into a hierarchy of nested lists. Where a nested list appears, it contains classes derived from the class whose entry immediately precedes the list. Each entry is a 2-tuple containing a class and a tuple of its base classes. If the *unique* argument is true, exactly one entry appears in the returned structure for each class in the given list. Otherwise, classes using multiple inheritance and their descendants will appear multiple times.

`inspect.getargspec(func)`

Get the names and default values of a Python function's arguments. A tuple of four things is returned: (*args*, *varargs*, *keywords*, *defaults*). *args* is a list of the argument names (it may contain nested lists). *varargs* and *keywords* are the names of the * and ** arguments or None. *defaults* is a tuple of default argument values or None if there are no default arguments; if this tuple has *n* elements, they correspond to the last *n* elements listed in *args*.

버전 2.6에서 변경: Returns a *named tuple* `ArgSpec(args, varargs, keywords, defaults)`.

`inspect.getargvalues(frame)`

Get information about arguments passed into a particular frame. A tuple of four things is returned: (*args*, *varargs*, *keywords*, *locals*). *args* is a list of the argument names (it may contain nested lists). *varargs* and *keywords* are the names of the * and ** arguments or None. *locals* is the locals dictionary of the given frame.

버전 2.6에서 변경: Returns a *named tuple* `ArgInfo(args, varargs, keywords, locals)`.

`inspect.formatargspec(args[, varargs, varkw, defaults, formatarg, formatvarargs, formatvarkw, formatvalue, join])`

Format a pretty argument spec from the four values returned by `getargspec()`. The *format** arguments are the corresponding optional formatting functions that are called to turn names and values into strings.

`inspect.formatargvalues(args[, varargs, varkw, locals, formatarg, formatvarargs, formatvarkw, formatvalue, join])`

Format a pretty argument spec from the four values returned by `getargvalues()`. The *format** arguments are the corresponding optional formatting functions that are called to turn names and values into strings.

`inspect.getmro(cls)`

Return a tuple of class *cls*'s base classes, including *cls*, in method resolution order. No class appears more than once in this tuple. Note that the method resolution order depends on *cls*'s type. Unless a very peculiar user-defined metatype is in use, *cls* will be the first element of the tuple.

`inspect.getcallargs(func[, *args][, **kwargs])`

Bind the *args* and *kwargs* to the argument names of the Python function or method *func*, as if it was called with them. For bound methods, bind also the first argument (typically named `self`) to the associated instance. A dict is returned, mapping the argument names (including the names of the `*` and `**` arguments, if any) to their values from *args* and *kwargs*. In case of invoking *func* incorrectly, i.e. whenever `func(*args, **kwargs)` would raise an exception because of incompatible signature, an exception of the same type and the same or similar message is raised. For example:

```
>>> from inspect import getcallargs
>>> def f(a, b=1, *pos, **named):
...     pass
>>> getcallargs(f, 1, 2, 3)
{'a': 1, 'named': {}, 'b': 2, 'pos': (3,)}
>>> getcallargs(f, a=2, x=4)
{'a': 2, 'named': {'x': 4}, 'b': 1, 'pos': ()}
>>> getcallargs(f)
Traceback (most recent call last):
...
TypeError: f() takes at least 1 argument (0 given)
```

버전 2.7에 추가.

28.13.4 The interpreter stack

When the following functions return 《frame records,》 each record is a tuple of six items: the frame object, the filename, the line number of the current line, the function name, a list of lines of context from the source code, and the index of the current line within that list.

참고: Keeping references to frame objects, as found in the first element of the frame records these functions return, can cause your program to create reference cycles. Once a reference cycle has been created, the lifespan of all objects which can be accessed from the objects which form the cycle can become much longer even if Python's optional cycle detector is enabled. If such cycles must be created, it is important to ensure they are explicitly broken to avoid the delayed destruction of objects and increased memory consumption which occurs.

Though the cycle detector will catch these, destruction of the frames (and local variables) can be made deterministic by removing the cycle in a `finally` clause. This is also important if the cycle detector was disabled when Python was compiled or using `gc.disable()`. For example:

```
def handle_stackframe_without_leak():
    frame = inspect.currentframe()
    try:
        # do something with the frame
    finally:
        del frame
```

The optional *context* argument supported by most of these functions specifies the number of lines of context to return, which are centered around the current line.

`inspect.getframeinfo(frame[, context])`

Get information about a frame or traceback object. A 5-tuple is returned, the last five elements of the frame's frame record.

버전 2.6에서 변경: Returns a *named tuple* `Traceback(filename, lineno, function, code_context, index)`.

`inspect.getouterframes (frame[, context])`

Get a list of frame records for a frame and all outer frames. These frames represent the calls that lead to the creation of *frame*. The first entry in the returned list represents *frame*; the last entry represents the outermost call on *frame*'s stack.

`inspect.getinnerframes (traceback[, context])`

Get a list of frame records for a traceback's frame and all inner frames. These frames represent calls made as a consequence of *frame*. The first entry in the list represents *traceback*; the last entry represents where the exception was raised.

`inspect.currentframe ()`

Return the frame object for the caller's stack frame.

CPython implementation detail: This function relies on Python stack frame support in the interpreter, which isn't guaranteed to exist in all implementations of Python. If running in an implementation without Python stack frame support this function returns `None`.

`inspect.stack ([context])`

Return a list of frame records for the caller's stack. The first entry in the returned list represents the caller; the last entry represents the outermost call on the stack.

`inspect.trace ([context])`

Return a list of frame records for the stack between the current frame and the frame in which an exception currently being handled was raised in. The first entry in the list represents the caller; the last entry represents where the exception was raised.

28.14 site — Site-specific configuration hook

Source code: [Lib/site.py](#)

This module is automatically imported during initialization. The automatic import can be suppressed using the interpreter's `-S` option.

Importing this module will append site-specific paths to the module search path and add a few builtins.

It starts by constructing up to four directories from a head and a tail part. For the head part, it uses `sys.prefix` and `sys.exec_prefix`; empty heads are skipped. For the tail part, it uses the empty string and then `lib/site-packages` (on Windows) or `lib/pythonX.Y/site-packages` and then `lib/site-python` (on Unix and Macintosh). For each of the distinct head-tail combinations, it sees if it refers to an existing directory, and if so, adds it to `sys.path` and also inspects the newly added path for configuration files.

A path configuration file is a file whose name has the form `name.pth` and exists in one of the four directories mentioned above; its contents are additional items (one per line) to be added to `sys.path`. Non-existing items are never added to `sys.path`, and no check is made that the item refers to a directory rather than a file. No item is added to `sys.path` more than once. Blank lines and lines beginning with `#` are skipped. Lines starting with `import` (followed by space or tab) are executed.

버전 2.6에서 변경: A space or tab is now required after the `import` keyword.

For example, suppose `sys.prefix` and `sys.exec_prefix` are set to `/usr/local`. The Python X.Y library is then installed in `/usr/local/lib/pythonX.Y`. Suppose this has a subdirectory `/usr/local/lib/pythonX.Y/site-packages` with three subsubdirectories, `foo`, `bar` and `spam`, and two path configuration files, `foo.pth` and `bar.pth`. Assume `foo.pth` contains the following:

```
# foo package configuration

foo
bar
bletch
```

and `bar.pth` contains:

```
# bar package configuration

bar
```

Then the following version-specific directories are added to `sys.path`, in this order:

```
/usr/local/lib/pythonX.Y/site-packages/bar
/usr/local/lib/pythonX.Y/site-packages/foo
```

Note that `bletch` is omitted because it doesn't exist; the `bar` directory precedes the `foo` directory because `bar.pth` comes alphabetically before `foo.pth`; and `spam` is omitted because it is not mentioned in either path configuration file.

After these path manipulations, an attempt is made to import a module named `sitecustomize`, which can perform arbitrary site-specific customizations. It is typically created by a system administrator in the `site-packages` directory. If this import fails with an `ImportError` exception, it is silently ignored. If Python is started without output streams available, as with `pythonw.exe` on Windows (which is used by default to start IDLE), attempted output from `sitecustomize` is ignored. Any exception other than `ImportError` causes a silent and perhaps mysterious failure of the process.

After this, an attempt is made to import a module named `usercustomize`, which can perform arbitrary user-specific customizations, if `ENABLE_USER_SITE` is true. This file is intended to be created in the user `site-packages` directory (see below), which is part of `sys.path` unless disabled by `-s`. An `ImportError` will be silently ignored.

Note that for some non-Unix systems, `sys.prefix` and `sys.exec_prefix` are empty, and the path manipulations are skipped; however the import of `sitecustomize` and `usercustomize` is still attempted.

`site.PREFIXES`

A list of prefixes for `site-packages` directories.

버전 2.6에 추가.

`site.ENABLE_USER_SITE`

Flag showing the status of the user `site-packages` directory. True means that it is enabled and was added to `sys.path`. False means that it was disabled by user request (with `-s` or `PYTHONNOUSERSITE`). None means it was disabled for security reasons (mismatch between user or group id and effective id) or by an administrator.

버전 2.6에 추가.

`site.USER_SITE`

Path to the user `site-packages` for the running Python. Can be None if `getusersitepackages()` hasn't been called yet. Default value is `~/local/lib/pythonX.Y/site-packages` for UNIX and non-framework Mac OS X builds, `~/Library/Python/X.Y/lib/python/site-packages` for Mac framework builds, and `%APPDATA%\Python\PythonXY\site-packages` on Windows. This directory is a `site` directory, which means that `.pth` files in it will be processed.

버전 2.6에 추가.

`site.USER_BASE`

Path to the base directory for the user `site-packages`. Can be None if `getuserbase()` hasn't been called yet. Default value is `~/local` for UNIX and Mac OS X non-framework builds, `~/Library/Python/X.Y` for Mac framework builds, and `%APPDATA%\Python` for Windows. This value is used by Distutils to compute the installation directories for scripts, data files, Python modules, etc. for the user installation scheme. See also `PYTHONUSERBASE`.

버전 2.6에 추가.

`site.addsitedir(sitedir, known_paths=None)`

Add a directory to `sys.path` and process its `.pth` files. Typically used in `sitecustomize` or `usercustomize` (see above).

`site.getsitepackages()`

Return a list containing all global site-packages directories (and possibly site-python).

버전 2.7에 추가.

`site.getuserbase()`

Return the path of the user base directory, `USER_BASE`. If it is not initialized yet, this function will also set it, respecting `PYTHONUSERBASE`.

버전 2.7에 추가.

`site.getusersitepackages()`

Return the path of the user-specific site-packages directory, `USER_SITE`. If it is not initialized yet, this function will also set it, respecting `PYTHONNOUSERSITE` and `USER_BASE`.

버전 2.7에 추가.

The `site` module also provides a way to get the user directories from the command line:

```
$ python -m site --user-site
/home/user/.local/lib/python2.7/site-packages
```

If it is called without arguments, it will print the contents of `sys.path` on the standard output, followed by the value of `USER_BASE` and whether the directory exists, then the same thing for `USER_SITE`, and finally the value of `ENABLE_USER_SITE`.

--user-base

Print the path to the user base directory.

--user-site

Print the path to the user site-packages directory.

If both options are given, user base and user site will be printed (always in this order), separated by `os.pathsep`.

If any option is given, the script will exit with one of these values: 0 if the user site-packages directory is enabled, 1 if it was disabled by the user, 2 if it is disabled for security reasons or by an administrator, and a value greater than 2 if there is an error.

더 보기:

PEP 370 – Per user site-packages directory

28.15 user — User-specific configuration hook

버전 2.6부터 폐지: The `user` module has been removed in Python 3.

As a policy, Python doesn't run user-specified code on startup of Python programs. (Only interactive sessions execute the script specified in the `PYTHONSTARTUP` environment variable if it exists).

However, some programs or sites may find it convenient to allow users to have a standard customization file, which gets run when a program requests it. This module implements such a mechanism. A program that wishes to use the mechanism must execute the statement

```
import user
```

The `user` module looks for a file `.pythonrc.py` in the user's home directory and if it can be opened, executes it (using `execfile()`) in its own (the module `user`'s) global namespace. Errors during this phase are not caught; that's up to the program that imports the `user` module, if it wishes. The home directory is assumed to be named by the `HOME` environment variable; if this is not set, the current directory is used.

The user's `.pythonrc.py` could conceivably test for `sys.version` if it wishes to do different things depending on the Python version.

A warning to users: be very conservative in what you place in your `.pythonrc.py` file. Since you don't know which programs will use it, changing the behavior of standard modules or functions is generally not a good idea.

A suggestion for programmers who wish to use this mechanism: a simple way to let users specify options for your package is to have them define variables in their `.pythonrc.py` file that you test in your module. For example, a module `spam` that has a verbosity level can look for a variable `user.spam_verbosity`, as follows:

```
import user

verbosity = bool(getattr(user, "spam_verbosity", 0))
```

(The three-argument form of `getattr()` is used in case the user has not defined `spam_verbosity` in their `.pythonrc.py` file.)

Programs with extensive customization needs are better off reading a program-specific customization file.

Programs with security or privacy concerns should *not* import this module; a user can easily break into a program by placing arbitrary code in the `.pythonrc.py` file.

Modules for general use should *not* import this module; it may interfere with the operation of the importing program.

더 보기:

Module `site` Site-wide customization mechanism.

28.16 `fpectl` — Floating point exception control

참고: The `fpectl` module is not built by default, and its usage is discouraged and may be dangerous except in the hands of experts. See also the section *Limitations and other considerations* on limitations for more details.

Most computers carry out floating point operations in conformance with the so-called IEEE-754 standard. On any real computer, some floating point operations produce results that cannot be expressed as a normal floating point value. For example, try

```
>>> import math
>>> math.exp(1000)
inf
>>> math.exp(1000) / math.exp(1000)
nan
```

(The example above will work on many platforms. DEC Alpha may be one exception.) `Inf` is a special, non-numeric value in IEEE-754 that stands for `infinity`, and `nan` means `not a number`. Note that, other than the non-numeric results, nothing special happened when you asked Python to carry out those calculations. That is in fact the default behaviour prescribed in the IEEE-754 standard, and if it works for you, stop reading now.

In some circumstances, it would be better to raise an exception and stop processing at the point where the faulty operation was attempted. The `fpectl` module is for use in that situation. It provides control over floating point units from several hardware manufacturers, allowing the user to turn on the generation of `SIGFPE` whenever any of the IEEE-754 exceptions

Division by Zero, Overflow, or Invalid Operation occurs. In tandem with a pair of wrapper macros that are inserted into the C code comprising your python system, SIGFPE is trapped and converted into the Python `FloatingPointError` exception.

The `fpectl` module defines the following functions and may raise the given exception:

`fpectl.turnon_sigfpe()`

Turn on the generation of SIGFPE, and set up an appropriate signal handler.

`fpectl.turnoff_sigfpe()`

Reset default handling of floating point exceptions.

exception `fpectl.FloatingPointError`

After `turnon_sigfpe()` has been executed, a floating point operation that raises one of the IEEE-754 exceptions Division by Zero, Overflow, or Invalid operation will in turn raise this standard Python exception.

28.16.1 Example

The following example demonstrates how to start up and test operation of the `fpectl` module.

```
>>> import fpectl
>>> import fpetest
>>> fpectl.turnon_sigfpe()
>>> fpetest.test()
overflow          PASS
FloatingPointError: Overflow

div by 0          PASS
FloatingPointError: Division by zero
[ more output from test elided ]
>>> import math
>>> math.exp(1000)
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
FloatingPointError: in math_1
```

28.16.2 Limitations and other considerations

Setting up a given processor to trap IEEE-754 floating point errors currently requires custom code on a per-architecture basis. You may have to modify `fpectl` to control your particular hardware.

Conversion of an IEEE-754 exception to a Python exception requires that the wrapper macros `PyFPE_START_PROTECT` and `PyFPE_END_PROTECT` be inserted into your code in an appropriate fashion. Python itself has been modified to support the `fpectl` module, but many other codes of interest to numerical analysts have not.

The `fpectl` module is not thread-safe.

더 보기:

Some files in the source distribution may be interesting in learning more about how this module operates. The include file `Include/pyfpe.h` discusses the implementation of this module at some length. `Modules/fpetestmodule.c` gives several examples of use. Many additional examples can be found in `Objects/floatobject.c`.

Custom Python Interpreters

The modules described in this chapter allow writing interfaces similar to Python's interactive interpreter. If you want a Python interpreter that supports some special feature in addition to the Python language, you should look at the `code` module. (The `codeop` module is lower-level, used to support compiling a possibly-incomplete chunk of Python code.)

The full list of modules described in this chapter is:

29.1 `code` — Interpreter base classes

The `code` module provides facilities to implement read-eval-print loops in Python. Two classes and convenience functions are included which can be used to build applications which provide an interactive interpreter prompt.

class `code.InteractiveInterpreter` (`[locals]`)

This class deals with parsing and interpreter state (the user's namespace); it does not deal with input buffering or prompting or input file naming (the filename is always passed in explicitly). The optional `locals` argument specifies the dictionary in which code will be executed; it defaults to a newly created dictionary with key `'__name__'` set to `'__console__'` and key `'__doc__'` set to `None`.

class `code.InteractiveConsole` (`[locals[, filename]]`)

Closely emulate the behavior of the interactive Python interpreter. This class builds on `InteractiveInterpreter` and adds prompting using the familiar `sys.ps1` and `sys.ps2`, and input buffering.

`code.interact` (`[banner[, readfunc[, local]]]`)

Convenience function to run a read-eval-print loop. This creates a new instance of `InteractiveConsole` and sets `readfunc` to be used as the `InteractiveConsole.raw_input()` method, if provided. If `local` is provided, it is passed to the `InteractiveConsole` constructor for use as the default namespace for the interpreter loop. The `interact()` method of the instance is then run with `banner` passed as the banner to use, if provided. The console object is discarded after use.

`code.compile_command` (`source[, filename[, symbol]]`)

This function is useful for programs that want to emulate Python's interpreter main loop (a.k.a. the read-eval-print loop). The tricky part is to determine when the user has entered an incomplete command that can be completed

by entering more text (as opposed to a complete command or a syntax error). This function *almost* always makes the same decision as the real interpreter main loop.

source is the source string; *filename* is the optional filename from which source was read, defaulting to '<input>'; and *symbol* is the optional grammar start symbol, which should be either 'single' (the default) or 'eval'.

Returns a code object (the same as `compile(source, filename, symbol)`) if the command is complete and valid; None if the command is incomplete; raises `SyntaxError` if the command is complete and contains a syntax error, or raises `OverflowError` or `ValueError` if the command contains an invalid literal.

29.1.1 Interactive Interpreter Objects

`InteractiveInterpreter.runsource(source[, filename[, symbol]])`

Compile and run some source in the interpreter. Arguments are the same as for `compile_command()`; the default for *filename* is '<input>', and for *symbol* is 'single'. One several things can happen:

- The input is incorrect; `compile_command()` raised an exception (`SyntaxError` or `OverflowError`). A syntax traceback will be printed by calling the `showsyntaxerror()` method. `runsource()` returns False.
- The input is incomplete, and more input is required; `compile_command()` returned None. `runsource()` returns True.
- The input is complete; `compile_command()` returned a code object. The code is executed by calling the `runcode()` (which also handles run-time exceptions, except for `SystemExit`). `runsource()` returns False.

The return value can be used to decide whether to use `sys.ps1` or `sys.ps2` to prompt the next line.

`InteractiveInterpreter.runcode(code)`

Execute a code object. When an exception occurs, `showtraceback()` is called to display a traceback. All exceptions are caught except `SystemExit`, which is allowed to propagate.

A note about `KeyboardInterrupt`: this exception may occur elsewhere in this code, and may not always be caught. The caller should be prepared to deal with it.

`InteractiveInterpreter.showsyntaxerror([filename])`

Display the syntax error that just occurred. This does not display a stack trace because there isn't one for syntax errors. If *filename* is given, it is stuffed into the exception instead of the default filename provided by Python's parser, because it always uses '<string>' when reading from a string. The output is written by the `write()` method.

`InteractiveInterpreter.showtraceback()`

Display the exception that just occurred. We remove the first stack item because it is within the interpreter object implementation. The output is written by the `write()` method.

`InteractiveInterpreter.write(data)`

Write a string to the standard error stream (`sys.stderr`). Derived classes should override this to provide the appropriate output handling as needed.

29.1.2 Interactive Console Objects

The *InteractiveConsole* class is a subclass of *InteractiveInterpreter*, and so offers all the methods of the interpreter objects as well as the following additions.

`InteractiveConsole.interact([banner])`

Closely emulate the interactive Python console. The optional *banner* argument specifies the banner to print before the first interaction; by default it prints a banner similar to the one printed by the standard Python interpreter, followed by the class name of the console object in parentheses (so as not to confuse this with the real interpreter – since it’s so close!).

`InteractiveConsole.push(line)`

Push a line of source text to the interpreter. The line should not have a trailing newline; it may have internal newlines. The line is appended to a buffer and the interpreter’s `runsource()` method is called with the concatenated contents of the buffer as source. If this indicates that the command was executed or invalid, the buffer is reset; otherwise, the command is incomplete, and the buffer is left as it was after the line was appended. The return value is `True` if more input is required, `False` if the line was dealt with in some way (this is the same as `runsource()`).

`InteractiveConsole.resetbuffer()`

Remove any unhandled source text from the input buffer.

`InteractiveConsole.raw_input([prompt])`

Write a *prompt* and read a line. The returned line does not include the trailing newline. When the user enters the EOF key sequence, *EOFError* is raised. The base implementation uses the built-in function `raw_input()`; a subclass may replace this with a different implementation.

29.2 codeop — Compile Python code

The *codeop* module provides utilities upon which the Python read-eval-print loop can be emulated, as is done in the *code* module. As a result, you probably don’t want to use the module directly; if you want to include such a loop in your program you probably want to use the *code* module instead.

There are two parts to this job:

1. Being able to tell if a line of input completes a Python statement: in short, telling whether to print `<>>>` or `<...>` next.
2. Remembering which future statements the user has entered, so subsequent input can be compiled with these in effect.

The *codeop* module provides a way of doing each of these things, and a way of doing them both.

To do just the former:

`codeop.compile_command(source[, filename[, symbol]])`

Tries to compile *source*, which should be a string of Python code and return a code object if *source* is valid Python code. In that case, the *filename* attribute of the code object will be *filename*, which defaults to `'<input>'`. Returns `None` if *source* is *not* valid Python code, but is a prefix of valid Python code.

If there is a problem with *source*, an exception will be raised. *SyntaxError* is raised if there is invalid Python syntax, and *OverflowError* or *ValueError* if there is an invalid literal.

The *symbol* argument determines whether *source* is compiled as a statement (`'single'`, the default) or as an *expression* (`'eval'`). Any other value will cause *ValueError* to be raised.

참고: It is possible (but not likely) that the parser stops parsing with a successful outcome before reaching the end of the source; in this case, trailing symbols may be ignored instead of causing an error. For example, a backslash

followed by two newlines may be followed by arbitrary garbage. This will be fixed once the API for the parser is better.

class `codeop.Compile`

Instances of this class have `__call__()` methods identical in signature to the built-in function `compile()`, but with the difference that if the instance compiles program text containing a `__future__` statement, the instance `<remembers>` and compiles all subsequent program texts with the statement in force.

class `codeop.CommandCompiler`

Instances of this class have `__call__()` methods identical in signature to `compile_command()`; the difference is that if the instance compiles program text containing a `__future__` statement, the instance `<remembers>` and compiles all subsequent program texts with the statement in force.

A note on version compatibility: the `Compile` and `CommandCompiler` are new in Python 2.2. If you want to enable the future-tracking features of 2.2 but also retain compatibility with 2.1 and earlier versions of Python you can either write

```
try:
    from codeop import CommandCompiler
    compile_command = CommandCompiler()
    del CommandCompiler
except ImportError:
    from codeop import compile_command
```

which is a low-impact change, but introduces possibly unwanted global state into your program, or you can write:

```
try:
    from codeop import CommandCompiler
except ImportError:
    def CommandCompiler():
        from codeop import compile_command
        return compile_command
```

and then call `CommandCompiler` every time you need a fresh compiler object.

Restricted Execution

경고: In Python 2.3 these modules have been disabled due to various known and not readily fixable security holes. The modules are still documented here to help in reading old code that uses the *rexec* and *Bastion* modules.

Restricted execution is the basic framework in Python that allows for the segregation of trusted and untrusted code. The framework is based on the notion that trusted Python code (a *supervisor*) can create a «padded cell» (or environment) with limited permissions, and run the untrusted code within this cell. The untrusted code cannot break out of its cell, and can only interact with sensitive system resources through interfaces defined and managed by the trusted code. The term «restricted execution» is favored over «safe-Python» since true safety is hard to define, and is determined by the way the restricted environment is created. Note that the restricted environments can be nested, with inner cells creating subcells of lesser, but never greater, privilege.

An interesting aspect of Python's restricted execution model is that the interfaces presented to untrusted code usually have the same names as those presented to trusted code. Therefore no special interfaces need to be learned to write code designed to run in a restricted environment. And because the exact nature of the padded cell is determined by the supervisor, different restrictions can be imposed, depending on the application. For example, it might be deemed «safe» for untrusted code to read any file within a specified directory, but never to write a file. In this case, the supervisor may redefine the built-in *open()* function so that it raises an exception whenever the *mode* parameter is 'w'. It might also perform a *chroot()*-like operation on the *filename* parameter, such that root is always relative to some safe «sandbox» area of the filesystem. In this case, the untrusted code would still see a built-in *open()* function in its environment, with the same calling interface. The semantics would be identical too, with *IOErrors* being raised when the supervisor determined that an unallowable parameter is being used.

The Python run-time determines whether a particular code block is executing in restricted execution mode based on the identity of the `__builtins__` object in its global variables: if this is (the dictionary of) the standard `__builtin__` module, the code is deemed to be unrestricted, else it is deemed to be restricted.

Python code executing in restricted mode faces a number of limitations that are designed to prevent it from escaping from the padded cell. For instance, the function object attribute `func_globals` and the class and instance object attribute `__dict__` are unavailable.

Two modules provide the framework for setting up restricted execution environments:

30.1 `rexec` — Restricted execution framework

버전 2.6부터 폐지: The `rexec` module has been removed in Python 3.

버전 2.3에서 변경: Disabled module.

경고: The documentation has been left in place to help in reading old code that uses the module.

This module contains the `RExec` class, which supports `r_eval()`, `r_execfile()`, `r_exec()`, and `r_import()` methods, which are restricted versions of the standard Python functions `eval()`, `execfile()` and the `exec` and `import` statements. Code executed in this restricted environment will only have access to modules and functions that are deemed safe; you can subclass `RExec` to add or remove capabilities as desired.

경고: While the `rexec` module is designed to perform as described below, it does have a few known vulnerabilities which could be exploited by carefully written code. Thus it should not be relied upon in situations requiring 《production ready》 security. In such situations, execution via sub-processes or very careful 《cleansing》 of both code and data to be processed may be necessary. Alternatively, help in patching known `rexec` vulnerabilities would be welcomed.

참고: The `RExec` class can prevent code from performing unsafe operations like reading or writing disk files, or using TCP/IP sockets. However, it does not protect against code using extremely large amounts of memory or processor time.

```
class rexec.RExec ([hooks[, verbose]])
```

Returns an instance of the `RExec` class.

`hooks` is an instance of the `RHooks` class or a subclass of it. If it is omitted or `None`, the default `RHooks` class is instantiated. Whenever the `rexec` module searches for a module (even a built-in one) or reads a module's code, it doesn't actually go out to the file system itself. Rather, it calls methods of an `RHooks` instance that was passed to or created by its constructor. (Actually, the `RExec` object doesn't make these calls — they are made by a module loader object that's part of the `RExec` object. This allows another level of flexibility, which can be useful when changing the mechanics of `import` within the restricted environment.)

By providing an alternate `RHooks` object, we can control the file system accesses made to import a module, without changing the actual algorithm that controls the order in which those accesses are made. For instance, we could substitute an `RHooks` object that passes all filesystem requests to a file server elsewhere, via some RPC mechanism such as ILU. Grail's applet loader uses this to support importing applets from a URL for a directory.

If `verbose` is true, additional debugging output may be sent to standard output.

It is important to be aware that code running in a restricted environment can still call the `sys.exit()` function. To disallow restricted code from exiting the interpreter, always protect calls that cause restricted code to run with a `try/except` statement that catches the `SystemExit` exception. Removing the `sys.exit()` function from the restricted environment is not sufficient — the restricted code could still use `raise SystemExit`. Removing `SystemExit` is not a reasonable option; some library code makes use of this and would break were it not available.

더 보기:

Grail Home Page Grail is a Web browser written entirely in Python. It uses the `rexec` module as a foundation for supporting Python applets, and can be used as an example usage of this module.

30.1.1 RExec Objects

RExec instances support the following methods:

`RExec.r_eval (code)`

code must either be a string containing a Python expression, or a compiled code object, which will be evaluated in the restricted environment's `__main__` module. The value of the expression or code object will be returned.

`RExec.r_exec (code)`

code must either be a string containing one or more lines of Python code, or a compiled code object, which will be executed in the restricted environment's `__main__` module.

`RExec.r_execfile (filename)`

Execute the Python code contained in the file *filename* in the restricted environment's `__main__` module.

Methods whose names begin with `s_` are similar to the functions beginning with `r_`, but the code will be granted access to restricted versions of the standard I/O streams `sys.stdin`, `sys.stderr`, and `sys.stdout`.

`RExec.s_eval (code)`

code must be a string containing a Python expression, which will be evaluated in the restricted environment.

`RExec.s_exec (code)`

code must be a string containing one or more lines of Python code, which will be executed in the restricted environment.

`RExec.s_execfile (code)`

Execute the Python code contained in the file *filename* in the restricted environment.

RExec objects must also support various methods which will be implicitly called by code executing in the restricted environment. Overriding these methods in a subclass is used to change the policies enforced by a restricted environment.

`RExec.r_import (modulename[, globals[, locals[, fromlist]]])`

Import the module *modulename*, raising an *ImportError* exception if the module is considered unsafe.

`RExec.r_open (filename[, mode[, bufsize]])`

Method called when `open()` is called in the restricted environment. The arguments are identical to those of `open()`, and a file object (or a class instance compatible with file objects) should be returned. *RExec*'s default behaviour is allow opening any file for reading, but forbidding any attempt to write a file. See the example below for an implementation of a less restrictive `r_open()`.

`RExec.r_reload (module)`

Reload the module object *module*, re-parsing and re-initializing it.

`RExec.r_unload (module)`

Unload the module object *module* (remove it from the restricted environment's `sys.modules` dictionary).

And their equivalents with access to restricted standard I/O streams:

`RExec.s_import (modulename[, globals[, locals[, fromlist]]])`

Import the module *modulename*, raising an *ImportError* exception if the module is considered unsafe.

`RExec.s_reload (module)`

Reload the module object *module*, re-parsing and re-initializing it.

`RExec.s_unload (module)`

Unload the module object *module*.

30.1.2 Defining restricted environments

The `RExec` class has the following class attributes, which are used by the `__init__()` method. Changing them on an existing instance won't have any effect; instead, create a subclass of `RExec` and assign them new values in the class definition. Instances of the new class will then use those new values. All these attributes are tuples of strings.

`RExec.nok_builtin_names`

Contains the names of built-in functions which will *not* be available to programs running in the restricted environment. The value for `RExec` is `('open', 'reload', '__import__')`. (This gives the exceptions, because by far the majority of built-in functions are harmless. A subclass that wants to override this variable should probably start with the value from the base class and concatenate additional forbidden functions — when new dangerous built-in functions are added to Python, they will also be added to this module.)

`RExec.ok_builtin_modules`

Contains the names of built-in modules which can be safely imported. The value for `RExec` is `('audioop', 'array', 'binascii', 'cmath', 'errno', 'imageop', 'marshal', 'math', 'md5', 'operator', 'parser', 'regex', 'select', 'sha', '_sre', 'strop', 'struct', 'time')`. A similar remark about overriding this variable applies — use the value from the base class as a starting point.

`RExec.ok_path`

Contains the directories which will be searched when an `import` is performed in the restricted environment. The value for `RExec` is the same as `sys.path` (at the time the module is loaded) for unrestricted code.

`RExec.ok_posix_names`

Contains the names of the functions in the `os` module which will be available to programs running in the restricted environment. The value for `RExec` is `('error', 'fstat', 'listdir', 'lstat', 'readlink', 'stat', 'times', 'uname', 'getpid', 'getppid', 'getcwd', 'getuid', 'getgid', 'geteuid', 'getegid')`.

`RExec.ok_sys_names`

Contains the names of the functions and variables in the `sys` module which will be available to programs running in the restricted environment. The value for `RExec` is `('ps1', 'ps2', 'copyright', 'version', 'platform', 'exit', 'maxint')`.

`RExec.ok_file_types`

Contains the file types from which modules are allowed to be loaded. Each file type is an integer constant defined in the `imp` module. The meaningful values are `PY_SOURCE`, `PY_COMPILED`, and `C_EXTENSION`. The value for `RExec` is `(C_EXTENSION, PY_SOURCE)`. Adding `PY_COMPILED` in subclasses is not recommended; an attacker could exit the restricted execution mode by putting a forged byte-compiled file (`.pyc`) anywhere in your file system, for example by writing it to `/tmp` or uploading it to the `/incoming` directory of your public FTP server.

30.1.3 An example

Let us say that we want a slightly more relaxed policy than the standard `RExec` class. For example, if we're willing to allow files in `/tmp` to be written, we can subclass the `RExec` class:

```
class TmpWriterRExec(rexec.RExec):
    def r_open(self, file, mode='r', buf=-1):
        if mode in ('r', 'rb'):
            pass
        elif mode in ('w', 'wb', 'a', 'ab'):
            # check filename: must begin with /tmp/
            if file[:5] != '/tmp/':
                raise IOError("can't write outside /tmp")
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    elif (string.find(file, '/../') >= 0 or
          file[:3] == '../' or file[-3:] == '/../'):
        raise IOError("'..' in filename forbidden")
    else: raise IOError("Illegal open() mode")
    return open(file, mode, buf)

```

Notice that the above code will occasionally forbid a perfectly valid filename; for example, code in the restricted environment won't be able to open a file called `/tmp/foo/../../bar`. To fix this, the `r_open()` method would have to simplify the filename to `/tmp/bar`, which would require splitting apart the filename and performing various operations on it. In cases where security is at stake, it may be preferable to write simple code which is sometimes overly restrictive, instead of more general code that is also more complex and may harbor a subtle security hole.

30.2 Bastion — Restricting access to objects

버전 2.6부터 폐지: The *Bastion* module has been removed in Python 3.

버전 2.3에서 변경: Disabled module.

참고: The documentation has been left in place to help in reading old code that uses the module.

According to the dictionary, a bastion is «a fortified area or position», or «something that is considered a stronghold.» It's a suitable name for this module, which provides a way to forbid access to certain attributes of an object. It must always be used with the *rexec* module, in order to allow restricted-mode programs access to certain safe attributes of an object, while denying access to other, unsafe attributes.

Bastion.Bastion(*object*[, *filter*[, *name*[, *class*]]])

Protect the object *object*, returning a bastion for the object. Any attempt to access one of the object's attributes will have to be approved by the *filter* function; if the access is denied an *AttributeError* exception will be raised.

If present, *filter* must be a function that accepts a string containing an attribute name, and returns true if access to that attribute will be permitted; if *filter* returns false, the access is denied. The default filter denies access to any function beginning with an underscore ('_'). The bastion's string representation will be `<Bastion for name>` if a value for *name* is provided; otherwise, `repr(object)` will be used.

class, if present, should be a subclass of *BastionClass*; see the code in `bastion.py` for the details. Overriding the default *BastionClass* will rarely be required.

class Bastion.BastionClass(*getfunc*, *name*)

Class which actually implements bastion objects. This is the default class used by *Bastion()*. The *getfunc* parameter is a function which returns the value of an attribute which should be exposed to the restricted execution environment when called with the name of the attribute as the only parameter. *name* is used to construct the `repr()` of the *BastionClass* instance.

더 보기:

Grail Home Page Grail, an Internet browser written in Python, uses these modules to support Python applets. More information on the use of Python's restricted execution mode in Grail is available on the Web site.

Importing Modules

The modules described in this chapter provide new ways to import other Python modules and hooks for customizing the import process.

The full list of modules described in this chapter is:

31.1 `imp` — Access the `import` internals

This module provides an interface to the mechanisms used to implement the `import` statement. It defines the following constants and functions:

`imp.get_magic()`
Return the magic string value used to recognize byte-compiled code files (`.pyc` files). (This value may be different for each Python version.)

`imp.get_suffixes()`
Return a list of 3-element tuples, each describing a particular type of module. Each triple has the form `(suffix, mode, type)`, where *suffix* is a string to be appended to the module name to form the filename to search for, *mode* is the mode string to pass to the built-in `open()` function to open the file (this can be `'r'` for text files or `'rb'` for binary files), and *type* is the file type, which has one of the values `PY_SOURCE`, `PY_COMPILED`, or `C_EXTENSION`, described below.

`imp.find_module(name[, path])`
Try to find the module *name*. If *path* is omitted or `None`, the list of directory names given by `sys.path` is searched, but first a few special places are searched: the function tries to find a built-in module with the given name (`C_BUILTIN`), then a frozen module (`PY_FROZEN`), and on some systems some other places are looked in as well (on Windows, it looks in the registry which may point to a specific file).

Otherwise, *path* must be a list of directory names; each directory is searched for files with any of the suffixes returned by `get_suffixes()` above. Invalid names in the list are silently ignored (but all list items must be strings).

If search is successful, the return value is a 3-element tuple `(file, pathname, description)`:

file is an open file object positioned at the beginning, *pathname* is the pathname of the file found, and *description* is a 3-element tuple as contained in the list returned by `get_suffixes()` describing the kind of module found.

If the module does not live in a file, the returned *file* is `None`, *pathname* is the empty string, and the *description* tuple contains empty strings for its suffix and mode; the module type is indicated as given in parentheses above. If the search is unsuccessful, `ImportError` is raised. Other exceptions indicate problems with the arguments or environment.

If the module is a package, *file* is `None`, *pathname* is the package path and the last item in the *description* tuple is `PKG_DIRECTORY`.

This function does not handle hierarchical module names (names containing dots). In order to find *P.M*, that is, submodule *M* of package *P*, use `find_module()` and `load_module()` to find and load package *P*, and then use `find_module()` with the *path* argument set to `P.__path__`. When *P* itself has a dotted name, apply this recipe recursively.

`imp.load_module(name, file, pathname, description)`

Load a module that was previously found by `find_module()` (or by an otherwise conducted search yielding compatible results). This function does more than importing the module: if the module was already imported, it is equivalent to a `reload()`! The *name* argument indicates the full module name (including the package name, if this is a submodule of a package). The *file* argument is an open file, and *pathname* is the corresponding file name; these can be `None` and `' '`, respectively, when the module is a package or not being loaded from a file. The *description* argument is a tuple, as would be returned by `get_suffixes()`, describing what kind of module must be loaded.

If the load is successful, the return value is the module object; otherwise, an exception (usually `ImportError`) is raised.

Important: the caller is responsible for closing the *file* argument, if it was not `None`, even when an exception is raised. This is best done using a `try ... finally` statement.

`imp.new_module(name)`

Return a new empty module object called *name*. This object is *not* inserted in `sys.modules`.

`imp.lock_held()`

Return `True` if the import lock is currently held, else `False`. On platforms without threads, always return `False`.

On platforms with threads, a thread executing an import holds an internal lock until the import is complete. This lock blocks other threads from doing an import until the original import completes, which in turn prevents other threads from seeing incomplete module objects constructed by the original thread while in the process of completing its import (and the imports, if any, triggered by that).

`imp.acquire_lock()`

Acquire the interpreter's import lock for the current thread. This lock should be used by import hooks to ensure thread-safety when importing modules.

Once a thread has acquired the import lock, the same thread may acquire it again without blocking; the thread must release it once for each time it has acquired it.

On platforms without threads, this function does nothing.

버전 2.3에 추가.

`imp.release_lock()`

Release the interpreter's import lock. On platforms without threads, this function does nothing.

버전 2.3에 추가.

The following constants with integer values, defined in this module, are used to indicate the search result of `find_module()`.

`imp.PY_SOURCE`

The module was found as a source file.

`imp.PY_COMPILED`

The module was found as a compiled code object file.

`imp.C_EXTENSION`

The module was found as dynamically loadable shared library.

`imp.PKG_DIRECTORY`

The module was found as a package directory.

`imp.C_BUILTIN`

The module was found as a built-in module.

`imp.PY_FROZEN`

The module was found as a frozen module (see `init_frozen()`).

The following constant and functions are obsolete; their functionality is available through `find_module()` or `load_module()`. They are kept around for backward compatibility:

`imp.SEARCH_ERROR`

Unused.

`imp.init_builtin(name)`

Initialize the built-in module called *name* and return its module object along with storing it in `sys.modules`. If the module was already initialized, it will be initialized *again*. Re-initialization involves the copying of the built-in module's `__dict__` from the cached module over the module's entry in `sys.modules`. If there is no built-in module called *name*, `None` is returned.

`imp.init_frozen(name)`

Initialize the frozen module called *name* and return its module object. If the module was already initialized, it will be initialized *again*. If there is no frozen module called *name*, `None` is returned. (Frozen modules are modules written in Python whose compiled byte-code object is incorporated into a custom-built Python interpreter by Python's **freeze** utility. See `Tools/freeze/` for now.)

`imp.is_builtin(name)`

Return 1 if there is a built-in module called *name* which can be initialized again. Return -1 if there is a built-in module called *name* which cannot be initialized again (see `init_builtin()`). Return 0 if there is no built-in module called *name*.

`imp.is_frozen(name)`

Return `True` if there is a frozen module (see `init_frozen()`) called *name*, or `False` if there is no such module.

`imp.load_compiled(name, pathname[, file])`

Load and initialize a module implemented as a byte-compiled code file and return its module object. If the module was already initialized, it will be initialized *again*. The *name* argument is used to create or access a module object. The *pathname* argument points to the byte-compiled code file. The *file* argument is the byte-compiled code file, open for reading in binary mode, from the beginning. It must currently be a real file object, not a user-defined class emulating a file.

`imp.load_dynamic(name, pathname[, file])`

Load and initialize a module implemented as a dynamically loadable shared library and return its module object. If the module was already initialized, it will be initialized *again*. Re-initialization involves copying the `__dict__` attribute of the cached instance of the module over the value used in the module cached in `sys.modules`. The *pathname* argument must point to the shared library. The *name* argument is used to construct the name of the initialization function: an external C function called `initname()` in the shared library is called. The optional *file* argument is ignored. (Note: using shared libraries is highly system dependent, and not all systems support it.)

CPython implementation detail: The import internals identify extension modules by filename, so doing `foo = load_dynamic("foo", "mod.so")` and `bar = load_dynamic("bar", "mod.so")` will result in both `foo` and `bar` referring to the same module, regardless of whether or not `mod.so` exports an `initbar` function. On systems which support them, symlinks can be used to import multiple modules from the same shared library, as each reference to the module will use a different file name.

`imp.load_source(name, pathname[, file])`

Load and initialize a module implemented as a Python source file and return its module object. If the module was already initialized, it will be initialized *again*. The *name* argument is used to create or access a module object. The *pathname* argument points to the source file. The *file* argument is the source file, open for reading as text, from the beginning. It must currently be a real file object, not a user-defined class emulating a file. Note that if a properly matching byte-compiled file (with suffix `.pyc` or `.pyo`) exists, it will be used instead of parsing the given source file.

`class imp.NullImporter(path_string)`

The `NullImporter` type is a [PEP 302](#) import hook that handles non-directory path strings by failing to find any modules. Calling this type with an existing directory or empty string raises `ImportError`. Otherwise, a `NullImporter` instance is returned.

Python adds instances of this type to `sys.path_importer_cache` for any path entries that are not directories and are not handled by any other path hooks on `sys.path_hooks`. Instances have only one method:

`find_module(fullname[, path])`

This method always returns `None`, indicating that the requested module could not be found.

버전 2.5에 추가.

31.1.1 Examples

The following function emulates what was the standard import statement up to Python 1.4 (no hierarchical module names). (This *implementation* wouldn't work in that version, since `find_module()` has been extended and `load_module()` has been added in 1.4.)

```
import imp
import sys

def __import__(name, globals=None, locals=None, fromlist=None):
    # Fast path: see if the module has already been imported.
    try:
        return sys.modules[name]
    except KeyError:
        pass

    # If any of the following calls raises an exception,
    # there's a problem we can't handle -- let the caller handle it.

    fp, pathname, description = imp.find_module(name)

    try:
        return imp.load_module(name, fp, pathname, description)
    finally:
        # Since we may exit via an exception, close fp explicitly.
        if fp:
            fp.close()
```

A more complete example that implements hierarchical module names and includes a `reload()` function can be found in the module `knee`. The `knee` module can be found in `Demo/imputil/` in the Python source distribution.

31.2 `importlib` — Convenience wrappers for `__import__()`

버전 2.7에 추가.

This module is a minor subset of what is available in the more full-featured package of the same name from Python 3.1 that provides a complete implementation of `import`. What is here has been provided to help ease in transitioning from 2.7 to 3.1.

`importlib.import_module(name, package=None)`

Import a module. The *name* argument specifies what module to import in absolute or relative terms (e.g. either `pkg.mod` or `..mod`). If the name is specified in relative terms, then the *package* argument must be specified to the package which is to act as the anchor for resolving the package name (e.g. `import_module('..mod', 'pkg.subpkg')` will import `pkg.mod`). The specified module will be inserted into `sys.modules` and returned.

31.3 `importlib` — Import utilities

버전 2.6부터 폐지: The `importlib` module has been removed in Python 3.

This module provides a very handy and useful mechanism for custom `import` hooks. Compared to the older `ihooks` module, `importlib` takes a dramatically simpler and more straight-forward approach to custom `import` functions.

class `importlib.ImportManager([fs_imp])`

Manage the import process.

install([namespace])

Install this ImportManager into the specified namespace.

uninstall()

Restore the previous import mechanism.

add_suffix(suffix, importFunc)

Undocumented.

class `importlib.Importer`

Base class for replacing standard import functions.

import_top(name)

Import a top-level module.

get_code(parent, modname, fqname)

Find and retrieve the code for the given module.

parent specifies a parent module to define a context for importing. It may be `None`, indicating no particular context for the search.

modname specifies a single module (not dotted) within the parent.

fqname specifies the fully-qualified module name. This is a (potentially) dotted name from the `⟨root⟩` of the module namespace down to the *modname*.

If there is no parent, then *modname*==*fqname*.

This method should return `None`, or a 3-tuple.

- If the module was not found, then `None` should be returned.
- The first item of the 2- or 3-tuple should be the integer 0 or 1, specifying whether the module that was found is a package or not.

- The second item is the code object for the module (it will be executed within the new module's namespace). This item can also be a fully-loaded module object (e.g. loaded from a shared lib).
- The third item is a dictionary of name/value pairs that will be inserted into new module before the code object is executed. This is provided in case the module's code expects certain values (such as where the module was found). When the second item is a module object, then these names/values will be inserted *after* the module has been loaded/initialized.

class `importlib.BuiltinImporter`

Emulate the import mechanism for built-in and frozen modules. This is a sub-class of the `Importer` class.

get_code (*parent, modname, fqname*)
Undocumented.

`importlib.py_suffix_importer` (*filename, finfo, fqname*)
Undocumented.

class `importlib.DynLoadSuffixImporter` (*[desc]*)
Undocumented.

import_file (*filename, finfo, fqname*)
Undocumented.

31.3.1 Examples

This is a re-implementation of hierarchical module import.

This code is intended to be read, not executed. However, it does work – all you need to do to enable it is `《import knee》`.

(The name is a pun on the clunkier predecessor of this module, `《ni》`.)

```
import sys, imp, __builtin__

# Replacement for __import__()
def import_hook(name, globals=None, locals=None, fromlist=None):
    parent = determine_parent(globals)
    q, tail = find_head_package(parent, name)
    m = load_tail(q, tail)
    if not fromlist:
        return q
    if hasattr(m, "__path__"):
        ensure_fromlist(m, fromlist)
    return m

def determine_parent(globals):
    if not globals or not globals.has_key("__name__"):
        return None
    pname = globals['__name__']
    if globals.has_key("__path__"):
        parent = sys.modules[pname]
        assert globals is parent.__dict__
        return parent
    if '.' in pname:
        i = pname.rfind('.')
        pname = pname[:i]
        parent = sys.modules[pname]
        assert parent.__name__ == pname
        return parent
    return None
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

def find_head_package(parent, name):
    if '.' in name:
        i = name.find('.')
        head = name[:i]
        tail = name[i+1:]
    else:
        head = name
        tail = ""
    if parent:
        qname = "%s.%s" % (parent.__name__, head)
    else:
        qname = head
    q = import_module(head, qname, parent)
    if q: return q, tail
    if parent:
        qname = head
        parent = None
        q = import_module(head, qname, parent)
        if q: return q, tail
    raise ImportError("No module named " + qname)

def load_tail(q, tail):
    m = q
    while tail:
        i = tail.find('.')
        if i < 0: i = len(tail)
        head, tail = tail[:i], tail[i+1:]
        mname = "%s.%s" % (m.__name__, head)
        m = import_module(head, mname, m)
        if not m:
            raise ImportError("No module named " + mname)
    return m

def ensure_fromlist(m, fromlist, recursive=0):
    for sub in fromlist:
        if sub == "*":
            if not recursive:
                try:
                    all = m.__all__
                except AttributeError:
                    pass
            else:
                ensure_fromlist(m, all, 1)
            continue
        if sub != "*" and not hasattr(m, sub):
            subname = "%s.%s" % (m.__name__, sub)
            submod = import_module(sub, subname, m)
            if not submod:
                raise ImportError("No module named " + subname)

def import_module(partname, fqname, parent):
    try:
        return sys.modules[fqname]
    except KeyError:
        pass

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    try:
        fp, pathname, stuff = imp.find_module(partname,
                                                parent and parent.__path__)
    except ImportError:
        return None
    try:
        m = imp.load_module(fqname, fp, pathname, stuff)
    finally:
        if fp: fp.close()
    if parent:
        setattr(parent, partname, m)
    return m

# Replacement for reload()
def reload_hook(module):
    name = module.__name__
    if '.' not in name:
        return import_module(name, name, None)
    i = name.rfind('.')
    pname = name[:i]
    parent = sys.modules[pname]
    return import_module(name[i+1:], name, parent)

# Save the original hooks
original_import = __builtin__.__import__
original_reload = __builtin__.reload

# Now install our hooks
__builtin__.__import__ = import_hook
__builtin__.reload = reload_hook

```

Also see the `importers` module (which can be found in `Demo/importutil/` in the Python source distribution) for additional examples.

31.4 zipimport — Import modules from Zip archives

버전 2.3에 추가.

This module adds the ability to import Python modules (`*.py`, `*.py[co]`) and packages from ZIP-format archives. It is usually not needed to use the `zipimport` module explicitly; it is automatically used by the built-in `import` mechanism for `sys.path` items that are paths to ZIP archives.

Typically, `sys.path` is a list of directory names as strings. This module also allows an item of `sys.path` to be a string naming a ZIP file archive. The ZIP archive can contain a subdirectory structure to support package imports, and a path within the archive can be specified to only import from a subdirectory. For example, the path `example.zip/lib/` would only import from the `lib/` subdirectory within the archive.

Any files may be present in the ZIP archive, but only files `.py` and `.py[co]` are available for import. ZIP import of dynamic modules (`.pyd`, `.so`) is disallowed. Note that if an archive only contains `.py` files, Python will not attempt to modify the archive by adding the corresponding `.pyc` or `.pyo` file, meaning that if a ZIP archive doesn't contain `.pyc` files, importing may be rather slow.

Using the built-in `reload()` function will fail if called on a module loaded from a ZIP archive; it is unlikely that

`reload()` would be needed, since this would imply that the ZIP has been altered during runtime.

ZIP archives with an archive comment are currently not supported.

더 보기:

PKZIP Application Note Documentation on the ZIP file format by Phil Katz, the creator of the format and algorithms used.

PEP 273 - Import Modules from Zip Archives Written by James C. Ahlstrom, who also provided an implementation. Python 2.3 follows the specification in PEP 273, but uses an implementation written by Just van Rossum that uses the import hooks described in PEP 302.

PEP 302 - New Import Hooks The PEP to add the import hooks that help this module work.

This module defines an exception:

exception `zipimport.ZipImportError`

Exception raised by zipimporter objects. It's a subclass of `ImportError`, so it can be caught as `ImportError`, too.

31.4.1 zipimporter Objects

`zipimporter` is the class for importing ZIP files.

class `zipimport.zipimporter (archivepath)`

Create a new zipimporter instance. *archivepath* must be a path to a ZIP file, or to a specific path within a ZIP file. For example, an *archivepath* of `foo/bar.zip/lib` will look for modules in the `lib` directory inside the ZIP file `foo/bar.zip` (provided that it exists).

`ZipImportError` is raised if *archivepath* doesn't point to a valid ZIP archive.

find_module (*fullname* [, *path*])

Search for a module specified by *fullname*. *fullname* must be the fully qualified (dotted) module name. It returns the zipimporter instance itself if the module was found, or `None` if it wasn't. The optional *path* argument is ignored—it's there for compatibility with the importer protocol.

get_code (*fullname*)

Return the code object for the specified module. Raise `ZipImportError` if the module couldn't be found.

get_data (*pathname*)

Return the data associated with *pathname*. Raise `IOError` if the file wasn't found.

get_filename (*fullname*)

Return the value `__file__` would be set to if the specified module was imported. Raise `ZipImportError` if the module couldn't be found.

버전 2.7에 추가.

get_source (*fullname*)

Return the source code for the specified module. Raise `ZipImportError` if the module couldn't be found, return `None` if the archive does contain the module, but has no source for it.

is_package (*fullname*)

Return True if the module specified by *fullname* is a package. Raise `ZipImportError` if the module couldn't be found.

load_module (*fullname*)

Load the module specified by *fullname*. *fullname* must be the fully qualified (dotted) module name. It returns the imported module, or raises `ZipImportError` if it wasn't found.

archive

The file name of the importer's associated ZIP file, without a possible subpath.

prefix

The subpath within the ZIP file where modules are searched. This is the empty string for `zipimporter` objects which point to the root of the ZIP file.

The `archive` and `prefix` attributes, when combined with a slash, equal the original `archivepath` argument given to the `zipimporter` constructor.

31.4.2 Examples

Here is an example that imports a module from a ZIP archive - note that the `zipimport` module is not explicitly used.

```
$ unzip -l example.zip
Archive:  example.zip
  Length      Date    Time    Name
-----
      8467   11-26-02  22:30   jwzthreading.py
-----
      8467                   1 file
$ ./python
Python 2.3 (#1, Aug 1 2003, 19:54:32)
>>> import sys
>>> sys.path.insert(0, 'example.zip')  # Add .zip file to front of path
>>> import jwzthreading
>>> jwzthreading.__file__
'example.zip/jwzthreading.py'
```

31.5 pkgutil — Package extension utility

버전 2.3에 추가.

Source code: [Lib/pkgutil.py](#)

This module provides utilities for the import system, in particular package support.

`pkgutil.extend_path(path, name)`

Extend the search path for the modules which comprise a package. Intended use is to place the following code in a package's `__init__.py`:

```
from pkgutil import extend_path
__path__ = extend_path(__path__, __name__)
```

This will add to the package's `__path__` all subdirectories of directories on `sys.path` named after the package. This is useful if one wants to distribute different parts of a single logical package as multiple directories.

It also looks for `*.pkg` files beginning where `*` matches the `name` argument. This feature is similar to `*.pth` files (see the [site](#) module for more information), except that it doesn't special-case lines starting with `import`. A `*.pkg` file is trusted at face value: apart from checking for duplicates, all entries found in a `*.pkg` file are added to the path, regardless of whether they exist on the filesystem. (This is a feature.)

If the input path is not a list (as is the case for frozen packages) it is returned unchanged. The input path is not modified; an extended copy is returned. Items are only appended to the copy at the end.

It is assumed that `sys.path` is a sequence. Items of `sys.path` that are not (Unicode or 8-bit) strings referring to existing directories are ignored. Unicode items on `sys.path` that cause errors when used as filenames may cause this function to raise an exception (in line with `os.path.isdir()` behavior).

class `pkgutil.ImpImporter` (*dirname=None*)

PEP 302 Importer that wraps Python's «classic» import algorithm.

If *dirname* is a string, a **PEP 302** importer is created that searches that directory. If *dirname* is `None`, a **PEP 302** importer is created that searches the current `sys.path`, plus any modules that are frozen or built-in.

Note that `ImpImporter` does not currently support being used by placement on `sys.meta_path`.

class `pkgutil.ImpLoader` (*fullname, file, filename, etc*)

PEP 302 Loader that wraps Python's «classic» import algorithm.

`pkgutil.find_loader` (*fullname*)

Find a **PEP 302** «loader» object for *fullname*.

If *fullname* contains dots, path must be the containing package's `__path__`. Returns `None` if the module cannot be found or imported. This function uses `iter_importers()`, and is thus subject to the same limitations regarding platform-specific special import locations such as the Windows registry.

`pkgutil.get_importer` (*path_item*)

Retrieve a **PEP 302** importer for the given *path_item*.

The returned importer is cached in `sys.path_importer_cache` if it was newly created by a path hook.

If there is no importer, a wrapper around the basic import machinery is returned. This wrapper is never inserted into the importer cache (`None` is inserted instead).

The cache (or part of it) can be cleared manually if a rescan of `sys.path_hooks` is necessary.

`pkgutil.get_loader` (*module_or_name*)

Get a **PEP 302** «loader» object for *module_or_name*.

If the module or package is accessible via the normal import mechanism, a wrapper around the relevant part of that machinery is returned. Returns `None` if the module cannot be found or imported. If the named module is not already imported, its containing package (if any) is imported, in order to establish the package `__path__`.

This function uses `iter_importers()`, and is thus subject to the same limitations regarding platform-specific special import locations such as the Windows registry.

`pkgutil.iter_importers` (*fullname=""*)

Yield **PEP 302** importers for the given module name.

If *fullname* contains a `<.>`, the importers will be for the package containing *fullname*, otherwise they will be importers for `sys.meta_path`, `sys.path`, and Python's «classic» import machinery, in that order. If the named module is in a package, that package is imported as a side effect of invoking this function.

Non-**PEP 302** mechanisms (e.g. the Windows registry) used by the standard import machinery to find files in alternative locations are partially supported, but are searched *after* `sys.path`. Normally, these locations are searched *before* `sys.path`, preventing `sys.path` entries from shadowing them.

For this to cause a visible difference in behaviour, there must be a module or package name that is accessible via both `sys.path` and one of the non-**PEP 302** file system mechanisms. In this case, the emulation will find the former version, while the builtin import mechanism will find the latter.

Items of the following types can be affected by this discrepancy: `imp.C_EXTENSION`, `imp.PY_SOURCE`, `imp.PY_COMPILED`, `imp.PKG_DIRECTORY`.

`pkgutil.iter_modules` (*path=None, prefix=""*)

Yields (*module_loader*, *name*, *ispkg*) for all submodules on *path*, or, if *path* is `None`, all top-level modules on `sys.path`.

path should be either `None` or a list of paths to look for modules in.

prefix is a string to output on the front of every module name on output.

`pkgutil.walk_packages` (*path*=`None`, *prefix*=`"`, *onerror*=`None`)

Yields (*module_loader*, *name*, *ispkg*) for all modules recursively on *path*, or, if *path* is `None`, all accessible modules.

path should be either `None` or a list of paths to look for modules in.

prefix is a string to output on the front of every module name on output.

Note that this function must import all *packages* (not all modules!) on the given *path*, in order to access the `__path__` attribute to find submodules.

onerror is a function which gets called with one argument (the name of the package which was being imported) if any exception occurs while trying to import a package. If no *onerror* function is supplied, `ImportErrors` are caught and ignored, while all other exceptions are propagated, terminating the search.

Examples:

```
# list all modules python can access
walk_packages()

# list all submodules of ctypes
walk_packages(ctypes.__path__, ctypes.__name__ + '.')
```

`pkgutil.get_data` (*package*, *resource*)

Get a resource from a package.

This is a wrapper for the **PEP 302** loader `get_data()` API. The *package* argument should be the name of a package, in standard module format (`foo.bar`). The *resource* argument should be in the form of a relative filename, using `/` as the path separator. The parent directory name `..` is not allowed, and nor is a rooted name (starting with a `/`).

The function returns a binary string that is the contents of the specified resource.

For packages located in the filesystem, which have already been imported, this is the rough equivalent of:

```
d = os.path.dirname(sys.modules[package].__file__)
data = open(os.path.join(d, resource), 'rb').read()
```

If the package cannot be located or loaded, or it uses a **PEP 302** loader which does not support `get_data()`, then `None` is returned.

버전 2.6에 추가.

31.6 modulefinder — Find modules used by a script

버전 2.3에 추가.

Source code: [Lib/modulefinder.py](#)

This module provides a `ModuleFinder` class that can be used to determine the set of modules imported by a script. `modulefinder.py` can also be run as a script, giving the filename of a Python script as its argument, after which a report of the imported modules will be printed.

`modulefinder.AddPackagePath` (*pkg_name*, *path*)

Record that the package named *pkg_name* can be found in the specified *path*.

`modulefinder.ReplacePackage (oldname, newname)`

Allows specifying that the module named *oldname* is in fact the package named *newname*. The most common usage would be to handle how the `_xmlplus` package replaces the `xml` package.

class `modulefinder.ModuleFinder ([path=None, debug=0, excludes=[], replace_paths=[]])`

This class provides `run_script()` and `report()` methods to determine the set of modules imported by a script. *path* can be a list of directories to search for modules; if not specified, `sys.path` is used. *debug* sets the debugging level; higher values make the class print debugging messages about what it's doing. *excludes* is a list of module names to exclude from the analysis. *replace_paths* is a list of (oldpath, newpath) tuples that will be replaced in module paths.

report ()

Print a report to standard output that lists the modules imported by the script and their paths, as well as modules that are missing or seem to be missing.

run_script (pathname)

Analyze the contents of the *pathname* file, which must contain Python code.

modules

A dictionary mapping module names to modules. See *Example usage of ModuleFinder*.

31.6.1 Example usage of ModuleFinder

The script that is going to get analyzed later on (bacon.py):

```
import re, itertools

try:
    import baconhammeggs
except ImportError:
    pass

try:
    import guido.python.ham
except ImportError:
    pass
```

The script that will output the report of bacon.py:

```
from modulefinder import ModuleFinder

finder = ModuleFinder()
finder.run_script('bacon.py')

print 'Loaded modules:'
for name, mod in finder.modules.iteritems():
    print '%s: ' % name,
    print ','.join(mod.globalnames.keys()[:3])

print '-'*50
print 'Modules not imported:'
print '\n'.join(finder.badmodules.iterkeys())
```

Sample output (may vary depending on the architecture):

```
Loaded modules:
_types:
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

copy_reg:  _inverted_registry, _slotnames, __all__
sre_compile:  isstring, _sre, _optimize_unicode
_sre:
sre_constants:  REPEAT_ONE, makedict, AT_END_LINE
sys:
re:  __module__, finditer, _expand
itertools:
__main__:  re, itertools, baconhameggs
sre_parse:  __getslice__, _PATTERNENDERS, SRE_FLAG_UNICODE
array:
types:  __module__, IntType, TypeType
-----
Modules not imported:
guido.python.ham
baconhameggs

```

31.7 runpy — Locating and executing Python modules

버전 2.5에 추가.

Source code: [Lib/runpy.py](#)

The *runpy* module is used to locate and run Python modules without importing them first. Its main use is to implement the `-m` command line switch that allows scripts to be located using the Python module namespace rather than the filesystem.

The *runpy* module provides two functions:

`runpy.run_module(mod_name, init_globals=None, run_name=None, alter_sys=False)`

Execute the code of the specified module and return the resulting module globals dictionary. The module's code is first located using the standard import mechanism (refer to [PEP 302](#) for details) and then executed in a fresh module namespace.

If the supplied module name refers to a package rather than a normal module, then that package is imported and the `__main__` submodule within that package is then executed and the resulting module globals dictionary returned.

The optional dictionary argument `init_globals` may be used to pre-populate the module's globals dictionary before the code is executed. The supplied dictionary will not be modified. If any of the special global variables below are defined in the supplied dictionary, those definitions are overridden by `run_module()`.

The special global variables `__name__`, `__file__`, `__loader__` and `__package__` are set in the globals dictionary before the module code is executed (Note that this is a minimal set of variables - other variables may be set implicitly as an interpreter implementation detail).

`__name__` is set to `run_name` if this optional argument is not `None`, to `mod_name + '.__main__'` if the named module is a package and to the `mod_name` argument otherwise.

`__file__` is set to the name provided by the module loader. If the loader does not make filename information available, this variable is set to `None`.

`__loader__` is set to the [PEP 302](#) module loader used to retrieve the code for the module (This loader may be a wrapper around the standard import mechanism).

`__package__` is set to `mod_name` if the named module is a package and to `mod_name.rpartition('.')[0]` otherwise.

If the argument `alter_sys` is supplied and evaluates to `True`, then `sys.argv[0]` is updated with the value of `__file__` and `sys.modules[__name__]` is updated with a temporary module object for the module being executed. Both `sys.argv[0]` and `sys.modules[__name__]` are restored to their original values before the function returns.

Note that this manipulation of `sys` is not thread-safe. Other threads may see the partially initialised module, as well as the altered list of arguments. It is recommended that the `sys` module be left alone when invoking this function from threaded code.

더 보기:

The `-m` option offering equivalent functionality from the command line.

버전 2.7에서 변경: Added ability to execute packages by looking for a `__main__` submodule

`runpy.run_path(file_path, init_globals=None, run_name=None)`

Execute the code at the named filesystem location and return the resulting module globals dictionary. As with a script name supplied to the CPython command line, the supplied path may refer to a Python source file, a compiled bytecode file or a valid `sys.path` entry containing a `__main__` module (e.g. a zipfile containing a top-level `__main__.py` file).

For a simple script, the specified code is simply executed in a fresh module namespace. For a valid `sys.path` entry (typically a zipfile or directory), the entry is first added to the beginning of `sys.path`. The function then looks for and executes a `__main__` module using the updated path. Note that there is no special protection against invoking an existing `__main__` entry located elsewhere on `sys.path` if there is no such module at the specified location.

The optional dictionary argument `init_globals` may be used to pre-populate the module's globals dictionary before the code is executed. The supplied dictionary will not be modified. If any of the special global variables below are defined in the supplied dictionary, those definitions are overridden by `run_path()`.

The special global variables `__name__`, `__file__`, `__loader__` and `__package__` are set in the globals dictionary before the module code is executed (Note that this is a minimal set of variables - other variables may be set implicitly as an interpreter implementation detail).

`__name__` is set to `run_name` if this optional argument is not `None` and to `'<run_path>'` otherwise.

`__file__` is set to the name provided by the module loader. If the loader does not make filename information available, this variable is set to `None`. For a simple script, this will be set to `file_path`.

`__loader__` is set to the **PEP 302** module loader used to retrieve the code for the module (This loader may be a wrapper around the standard import mechanism). For a simple script, this will be set to `None`.

`__package__` is set to `__name__.rpartition('.')[0]`.

A number of alterations are also made to the `sys` module. Firstly, `sys.path` may be altered as described above. `sys.argv[0]` is updated with the value of `file_path` and `sys.modules[__name__]` is updated with a temporary module object for the module being executed. All modifications to items in `sys` are reverted before the function returns.

Note that, unlike `run_module()`, the alterations made to `sys` are not optional in this function as these adjustments are essential to allowing the execution of `sys.path` entries. As the thread-safety limitations still apply, use of this function in threaded code should be either serialised with the import lock or delegated to a separate process.

더 보기:

using-on-interface-options for equivalent functionality on the command line (`python path/to/script`).

버전 2.7에 추가.

더 보기:

PEP 338 – Executing modules as scripts PEP written and implemented by Nick Coghlan.

PEP 366 – Main module explicit relative imports PEP written and implemented by Nick Coghlan.
using-on-general - CPython command line details

Python Language Services

Python provides a number of modules to assist in working with the Python language. These modules support tokenizing, parsing, syntax analysis, bytecode disassembly, and various other facilities.

These modules include:

32.1 `parser` — Access Python parse trees

The `parser` module provides an interface to Python's internal parser and byte-code compiler. The primary purpose for this interface is to allow Python code to edit the parse tree of a Python expression and create executable code from this. This is better than trying to parse and modify an arbitrary Python code fragment as a string because parsing is performed in a manner identical to the code forming the application. It is also faster.

참고: From Python 2.5 onward, it's much more convenient to cut in at the Abstract Syntax Tree (AST) generation and compilation stage, using the `ast` module.

The `parser` module exports the names documented here also with `<st>` replaced by `<ast>`; this is a legacy from the time when there was no other AST and has nothing to do with the AST found in Python 2.5. This is also the reason for the functions' keyword arguments being called `ast`, not `st`. The `<ast>` functions have been removed in Python 3.

There are a few things to note about this module which are important to making use of the data structures created. This is not a tutorial on editing the parse trees for Python code, but some examples of using the `parser` module are presented.

Most importantly, a good understanding of the Python grammar processed by the internal parser is required. For full information on the language syntax, refer to reference-index. The parser itself is created from a grammar specification defined in the file `Grammar/Grammar` in the standard Python distribution. The parse trees stored in the ST objects created by this module are the actual output from the internal parser when created by the `expr()` or `suite()` functions, described below. The ST objects created by `sequence2st()` faithfully simulate those structures. Be aware that the values of the sequences which are considered `<correct>` will vary from one version of Python to another as the formal grammar for the language is revised. However, transporting code from one Python version to another as source text will always allow correct parse trees to be created in the target version, with the only restriction being that migrating to an older

version of the interpreter will not support more recent language constructs. The parse trees are not typically compatible from one version to another, whereas source code has always been forward-compatible.

Each element of the sequences returned by `st2list()` or `st2tuple()` has a simple form. Sequences representing non-terminal elements in the grammar always have a length greater than one. The first element is an integer which identifies a production in the grammar. These integers are given symbolic names in the C header file `Include/graminit.h` and the Python module `symbol`. Each additional element of the sequence represents a component of the production as recognized in the input string: these are always sequences which have the same form as the parent. An important aspect of this structure which should be noted is that keywords used to identify the parent node type, such as the keyword `if` in an `if_stmt`, are included in the node tree without any special treatment. For example, the `if` keyword is represented by the tuple `(1, 'if')`, where 1 is the numeric value associated with all `NAME` tokens, including variable and function names defined by the user. In an alternate form returned when line number information is requested, the same token might be represented as `(1, 'if', 12)`, where the 12 represents the line number at which the terminal symbol was found.

Terminal elements are represented in much the same way, but without any child elements and the addition of the source text which was identified. The example of the `if` keyword above is representative. The various types of terminal symbols are defined in the C header file `Include/token.h` and the Python module `token`.

The ST objects are not required to support the functionality of this module, but are provided for three purposes: to allow an application to amortize the cost of processing complex parse trees, to provide a parse tree representation which conserves memory space when compared to the Python list or tuple representation, and to ease the creation of additional modules in C which manipulate parse trees. A simple `«wrapper»` class may be created in Python to hide the use of ST objects.

The `parser` module defines functions for a few distinct purposes. The most important purposes are to create ST objects and to convert ST objects to other representations such as parse trees and compiled code objects, but there are also functions which serve to query the type of parse tree represented by an ST object.

더 보기:

Module `symbol` Useful constants representing internal nodes of the parse tree.

Module `token` Useful constants representing leaf nodes of the parse tree and functions for testing node values.

32.1.1 Creating ST Objects

ST objects may be created from source code or from a parse tree. When creating an ST object from source, different functions are used to create the `'eval'` and `'exec'` forms.

`parser.expr(source)`

The `expr()` function parses the parameter `source` as if it were an input to `compile(source, 'file.py', 'eval')`. If the parse succeeds, an ST object is created to hold the internal parse tree representation, otherwise an appropriate exception is raised.

`parser.suite(source)`

The `suite()` function parses the parameter `source` as if it were an input to `compile(source, 'file.py', 'exec')`. If the parse succeeds, an ST object is created to hold the internal parse tree representation, otherwise an appropriate exception is raised.

`parser.sequence2st(sequence)`

This function accepts a parse tree represented as a sequence and builds an internal representation if possible. If it can validate that the tree conforms to the Python grammar and all nodes are valid node types in the host version of Python, an ST object is created from the internal representation and returned to the caller. If there is a problem creating the internal representation, or if the tree cannot be validated, a `ParserError` exception is raised. An ST object created this way should not be assumed to compile correctly; normal exceptions raised by compilation may still be initiated when the ST object is passed to `compilest()`. This may indicate problems not related to syntax (such as a `MemoryError` exception), but may also be due to constructs such as the result of parsing `del f(0)`, which escapes the Python parser but is checked by the bytecode compiler.

Sequences representing terminal tokens may be represented as either two-element lists of the form `(1, 'name')` or as three-element lists of the form `(1, 'name', 56)`. If the third element is present, it is assumed to be a valid line number. The line number may be specified for any subset of the terminal symbols in the input tree.

`parser.tuple2st(sequence)`

This is the same function as `sequence2st()`. This entry point is maintained for backward compatibility.

32.1.2 Converting ST Objects

ST objects, regardless of the input used to create them, may be converted to parse trees represented as list- or tuple-trees, or may be compiled into executable code objects. Parse trees may be extracted with or without line numbering information.

`parser.st2list(ast[, line_info])`

This function accepts an ST object from the caller in *ast* and returns a Python list representing the equivalent parse tree. The resulting list representation can be used for inspection or the creation of a new parse tree in list form. This function does not fail so long as memory is available to build the list representation. If the parse tree will only be used for inspection, `st2tuple()` should be used instead to reduce memory consumption and fragmentation. When the list representation is required, this function is significantly faster than retrieving a tuple representation and converting that to nested lists.

If *line_info* is true, line number information will be included for all terminal tokens as a third element of the list representing the token. Note that the line number provided specifies the line on which the token *ends*. This information is omitted if the flag is false or omitted.

`parser.st2tuple(ast[, line_info])`

This function accepts an ST object from the caller in *ast* and returns a Python tuple representing the equivalent parse tree. Other than returning a tuple instead of a list, this function is identical to `st2list()`.

If *line_info* is true, line number information will be included for all terminal tokens as a third element of the list representing the token. This information is omitted if the flag is false or omitted.

`parser.compilest(ast, filename='<syntax-tree>')`

The Python byte compiler can be invoked on an ST object to produce code objects which can be used as part of an `exec` statement or a call to the built-in `eval()` function. This function provides the interface to the compiler, passing the internal parse tree from *ast* to the parser, using the source file name specified by the *filename* parameter. The default value supplied for *filename* indicates that the source was an ST object.

Compiling an ST object may result in exceptions related to compilation; an example would be a `SyntaxError` caused by the parse tree for `del f(0)`: this statement is considered legal within the formal grammar for Python but is not a legal language construct. The `SyntaxError` raised for this condition is actually generated by the Python byte-compiler normally, which is why it can be raised at this point by the `parser` module. Most causes of compilation failure can be diagnosed programmatically by inspection of the parse tree.

32.1.3 Queries on ST Objects

Two functions are provided which allow an application to determine if an ST was created as an expression or a suite. Neither of these functions can be used to determine if an ST was created from source code via `expr()` or `suite()` or from a parse tree via `sequence2st()`.

`parser.isexpr(ast)`

When *ast* represents an 'eval' form, this function returns true, otherwise it returns false. This is useful, since code objects normally cannot be queried for this information using existing built-in functions. Note that the code objects created by `compilest()` cannot be queried like this either, and are identical to those created by the built-in `compile()` function.

`parser.issuite(ast)`

This function mirrors `isexpr()` in that it reports whether an ST object represents an 'exec' form, commonly known as a 《suite.》 It is not safe to assume that this function is equivalent to `not isexpr(ast)`, as additional syntactic fragments may be supported in the future.

32.1.4 Exceptions and Error Handling

The parser module defines a single exception, but may also pass other built-in exceptions from other portions of the Python runtime environment. See each function for information about the exceptions it can raise.

exception `parser.ParserError`

Exception raised when a failure occurs within the parser module. This is generally produced for validation failures rather than the built-in `SyntaxError` raised during normal parsing. The exception argument is either a string describing the reason of the failure or a tuple containing a sequence causing the failure from a parse tree passed to `sequence2st()` and an explanatory string. Calls to `sequence2st()` need to be able to handle either type of exception, while calls to other functions in the module will only need to be aware of the simple string values.

Note that the functions `compilest()`, `expr()`, and `suite()` may raise exceptions which are normally raised by the parsing and compilation process. These include the built in exceptions `MemoryError`, `OverflowError`, `SyntaxError`, and `SystemError`. In these cases, these exceptions carry all the meaning normally associated with them. Refer to the descriptions of each function for detailed information.

32.1.5 ST Objects

Ordered and equality comparisons are supported between ST objects. Pickling of ST objects (using the `pickle` module) is also supported.

`parser.STType`

The type of the objects returned by `expr()`, `suite()` and `sequence2st()`.

ST objects have the following methods:

`ST.compile([filename])`

Same as `compilest(st, filename)`.

`ST.isexpr()`

Same as `isexpr(st)`.

`ST.issuite()`

Same as `issuite(st)`.

`ST.tolist([line_info])`

Same as `st2list(st, line_info)`.

`ST.totuple([line_info])`

Same as `st2tuple(st, line_info)`.

32.1.6 Example: Emulation of `compile()`

While many useful operations may take place between parsing and bytecode generation, the simplest operation is to do nothing. For this purpose, using the `parser` module to produce an intermediate data structure is equivalent to the code

```
>>> code = compile('a + 5', 'file.py', 'eval')
>>> a = 5
>>> eval(code)
10
```

The equivalent operation using the `parser` module is somewhat longer, and allows the intermediate internal parse tree to be retained as an ST object:

```
>>> import parser
>>> st = parser.expr('a + 5')
>>> code = st.compile('file.py')
>>> a = 5
>>> eval(code)
10
```

An application which needs both ST and code objects can package this code into readily available functions:

```
import parser

def load_suite(source_string):
    st = parser.suite(source_string)
    return st, st.compile()

def load_expression(source_string):
    st = parser.expr(source_string)
    return st, st.compile()
```

32.2 `ast` — Abstract Syntax Trees

버전 2.5에 추가: The low-level `_ast` module containing only the node classes.

버전 2.6에 추가: The high-level `ast` module containing all helpers.

Source code: [Lib/ast.py](#)

The `ast` module helps Python applications to process trees of the Python abstract syntax grammar. The abstract syntax itself might change with each Python release; this module helps to find out programmatically what the current grammar looks like.

An abstract syntax tree can be generated by passing `ast.PyCF_ONLY_AST` as a flag to the `compile()` built-in function, or using the `parse()` helper provided in this module. The result will be a tree of objects whose classes all inherit from `ast.AST`. An abstract syntax tree can be compiled into a Python code object using the built-in `compile()` function.

32.2.1 Node classes

class `ast.AST`

This is the base of all AST node classes. The actual node classes are derived from the `Parser/Python.asdl` file, which is reproduced [below](#). They are defined in the `_ast` C module and re-exported in `ast`.

There is one class defined for each left-hand side symbol in the abstract grammar (for example, `ast.stmt` or `ast.expr`). In addition, there is one class defined for each constructor on the right-hand side; these classes inherit from the classes for the left-hand side trees. For example, `ast.BinOp` inherits from `ast.expr`. For production rules with alternatives (aka `《sums》`), the left-hand side class is abstract: only instances of specific constructor nodes are ever created.

`_fields`

Each concrete class has an attribute `_fields` which gives the names of all child nodes.

Each instance of a concrete class has one attribute for each child node, of the type as defined in the grammar. For example, `ast.BinOp` instances have an attribute `left` of type `ast.expr`.

If these attributes are marked as optional in the grammar (using a question mark), the value might be `None`. If the attributes can have zero-or-more values (marked with an asterisk), the values are represented as Python lists. All possible attributes must be present and have valid values when compiling an AST with `compile()`.

`lineno`

`col_offset`

Instances of `ast.expr` and `ast.stmt` subclasses have `lineno` and `col_offset` attributes. The `lineno` is the line number of source text (1-indexed so the first line is line 1) and the `col_offset` is the UTF-8 byte offset of the first token that generated the node. The UTF-8 offset is recorded because the parser uses UTF-8 internally.

The constructor of a class `ast.T` parses its arguments as follows:

- If there are positional arguments, there must be as many as there are items in `T._fields`; they will be assigned as attributes of these names.
- If there are keyword arguments, they will set the attributes of the same names to the given values.

For example, to create and populate an `ast.UnaryOp` node, you could use

```
node = ast.UnaryOp()
node.op = ast.USub()
node.operand = ast.Num()
node.operand.n = 5
node.operand.lineno = 0
node.operand.col_offset = 0
node.lineno = 0
node.col_offset = 0
```

or the more compact

```
node = ast.UnaryOp(ast.USub(), ast.Num(5, lineno=0, col_offset=0),
                  lineno=0, col_offset=0)
```

버전 2.6에 추가: The constructor as explained above was added. In Python 2.5 nodes had to be created by calling the class constructor without arguments and setting the attributes afterwards.

32.2.2 Abstract Grammar

The module defines a string constant `__version__` which is the decimal Subversion revision number of the file shown below.

The abstract grammar is currently defined as follows:

```
-- ASDL's five builtin types are identifier, int, string, object, bool

module Python version "$Revision$"
{
    mod = Module(stmt* body)
        | Interactive(stmt* body)
        | Expression(expr body)

    -- not really an actual node but useful in Jython's typesystem.
    | Suite(stmt* body)

    stmt = FunctionDef(identifier name, arguments args,
                        stmt* body, expr* decorator_list)
        | ClassDef(identifier name, expr* bases, stmt* body, expr* decorator_
→list)
        | Return(expr? value)

        | Delete(expr* targets)
        | Assign(expr* targets, expr value)
        | AugAssign(expr target, operator op, expr value)

    -- not sure if bool is allowed, can always use int
    | Print(expr? dest, expr* values, bool nl)

    -- use 'orelse' because else is a keyword in target languages
    | For(expr target, expr iter, stmt* body, stmt* orelse)
    | While(expr test, stmt* body, stmt* orelse)
    | If(expr test, stmt* body, stmt* orelse)
    | With(expr context_expr, expr? optional_vars, stmt* body)

    -- 'type' is a bad name
    | Raise(expr? type, expr? inst, expr? tback)
    | TryExcept(stmt* body, excepthandler* handlers, stmt* orelse)
    | TryFinally(stmt* body, stmt* finalbody)
    | Assert(expr test, expr? msg)

    | Import(alias* names)
    | ImportFrom(identifier? module, alias* names, int? level)

    -- Doesn't capture requirement that locals must be
    -- defined if globals is
    -- still supports use as a function!
    | Exec(expr body, expr? globals, expr? locals)

    | Global(identifier* names)
    | Expr(expr value)
    | Pass | Break | Continue

    -- XXX Jython will be different
    -- col_offset is the byte offset in the utf8 string the parser uses
    attributes (int lineno, int col_offset)
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

    -- BoolOp() can use left & right?
    expr = BoolOp(boolop op, expr* values)
    | BinOp(expr left, operator op, expr right)
    | UnaryOp(unaryop op, expr operand)
    | Lambda(arguments args, expr body)
    | IfExp(expr test, expr body, expr orelse)
    | Dict(expr* keys, expr* values)
    | Set(expr* elts)
    | ListComp(expr elt, comprehension* generators)
    | SetComp(expr elt, comprehension* generators)
    | DictComp(expr key, expr value, comprehension* generators)
    | GeneratorExp(expr elt, comprehension* generators)
    -- the grammar constrains where yield expressions can occur
    | Yield(expr? value)
    -- need sequences for compare to distinguish between
    -- x < 4 < 3 and (x < 4) < 3
    | Compare(expr left, cmpop* ops, expr* comparators)
    | Call(expr func, expr* args, keyword* keywords,
           expr? starargs, expr? kwargs)
    | Repr(expr value)
    | Num(object n) -- a number as a PyObject.
    | Str(string s) -- need to specify raw, unicode, etc?
    -- other literals? bools?

    -- the following expression can appear in assignment context
    | Attribute(expr value, identifier attr, expr_context ctx)
    | Subscript(expr value, slice slice, expr_context ctx)
    | Name(identifier id, expr_context ctx)
    | List(expr* elts, expr_context ctx)
    | Tuple(expr* elts, expr_context ctx)

    -- col_offset is the byte offset in the utf8 string the parser uses
    attributes (int lineno, int col_offset)

    expr_context = Load | Store | Del | AugLoad | AugStore | Param

    slice = Ellipsis | Slice(expr? lower, expr? upper, expr? step)
    | ExtSlice(slice* dims)
    | Index(expr value)

    boolop = And | Or

    operator = Add | Sub | Mult | Div | Mod | Pow | LShift
    | RShift | BitOr | BitXor | BitAnd | FloorDiv

    unaryop = Invert | Not | UAdd | USub

    cmpop = Eq | NotEq | Lt | LtE | Gt | GtE | Is | IsNot | In | NotIn

    comprehension = (expr target, expr iter, expr* ifs)

    -- not sure what to call the first argument for raise and except
    excepthandler = ExceptHandler(expr? type, expr? name, stmt* body)
    attributes (int lineno, int col_offset)

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

arguments = (expr* args, identifier? vararg,
             identifier? kwarg, expr* defaults)

-- keyword arguments supplied to call
keyword = (identifier arg, expr value)

-- import name with optional 'as' alias.
alias = (identifier name, identifier? asname)
}

```

32.2.3 ast Helpers

버전 2.6에 추가.

Apart from the node classes, `ast` module defines these utility functions and classes for traversing abstract syntax trees:

`ast.parse(source, filename='<unknown>', mode='exec')`
 Parse the source into an AST node. Equivalent to `compile(source, filename, mode, ast.PyCF_ONLY_AST)`.

경고: It is possible to crash the Python interpreter with a sufficiently large/complex string due to stack depth limitations in Python's AST compiler.

`ast.literal_eval(node_or_string)`

Safely evaluate an expression node or a Unicode or *Latin-1* encoded string containing a Python literal or container display. The string or node provided may only consist of the following Python literal structures: strings, numbers, tuples, lists, dicts, booleans, and `None`.

This can be used for safely evaluating strings containing Python values from untrusted sources without the need to parse the values oneself. It is not capable of evaluating arbitrarily complex expressions, for example involving operators or indexing.

경고: It is possible to crash the Python interpreter with a sufficiently large/complex string due to stack depth limitations in Python's AST compiler.

`ast.get_docstring(node, clean=True)`

Return the docstring of the given `node` (which must be a `FunctionDef`, `ClassDef` or `Module` node), or `None` if it has no docstring. If `clean` is true, clean up the docstring's indentation with `inspect.cleandoc()`.

`ast.fix_missing_locations(node)`

When you compile a node tree with `compile()`, the compiler expects `lineno` and `col_offset` attributes for every node that supports them. This is rather tedious to fill in for generated nodes, so this helper adds these attributes recursively where not already set, by setting them to the values of the parent node. It works recursively starting at `node`.

`ast.increment_lineno(node, n=1)`

Increment the line number of each node in the tree starting at `node` by `n`. This is useful to «move code» to a different location in a file.

`ast.copy_location(new_node, old_node)`

Copy source location (`lineno` and `col_offset`) from `old_node` to `new_node` if possible, and return `new_node`.

`ast.iter_fields(node)`

Yield a tuple of (fieldname, value) for each field in `node._fields` that is present on `node`.

`ast.iter_child_nodes(node)`

Yield all direct child nodes of `node`, that is, all fields that are nodes and all items of fields that are lists of nodes.

`ast.walk(node)`

Recursively yield all descendant nodes in the tree starting at `node` (including `node` itself), in no specified order. This is useful if you only want to modify nodes in place and don't care about the context.

class `ast.NodeVisitor`

A node visitor base class that walks the abstract syntax tree and calls a visitor function for every node found. This function may return a value which is forwarded by the `visit()` method.

This class is meant to be subclassed, with the subclass adding visitor methods.

visit (`node`)

Visit a node. The default implementation calls the method called `self.visit_classname` where *classname* is the name of the node class, or `generic_visit()` if that method doesn't exist.

generic_visit (`node`)

This visitor calls `visit()` on all children of the node.

Note that child nodes of nodes that have a custom visitor method won't be visited unless the visitor calls `generic_visit()` or visits them itself.

Don't use the `NodeVisitor` if you want to apply changes to nodes during traversal. For this a special visitor exists (`NodeTransformer`) that allows modifications.

class `ast.NodeTransformer`

A `NodeVisitor` subclass that walks the abstract syntax tree and allows modification of nodes.

The `NodeTransformer` will walk the AST and use the return value of the visitor methods to replace or remove the old node. If the return value of the visitor method is `None`, the node will be removed from its location, otherwise it is replaced with the return value. The return value may be the original node in which case no replacement takes place.

Here is an example transformer that rewrites all occurrences of name lookups (`foo`) to `data['foo']`:

```
class RewriteName(NodeTransformer):

    def visit_Name(self, node):
        return copy_location(Subscript(
            value=Name(id='data', ctx=Load()),
            slice=Index(value=Str(s=node.id)),
            ctx=node.ctx
        ), node)
```

Keep in mind that if the node you're operating on has child nodes you must either transform the child nodes yourself or call the `generic_visit()` method for the node first.

For nodes that were part of a collection of statements (that applies to all statement nodes), the visitor may also return a list of nodes rather than just a single node.

Usually you use the transformer like this:

```
node = YourTransformer().visit(node)
```

`ast.dump(node, annotate_fields=True, include_attributes=False)`

Return a formatted dump of the tree in `node`. This is mainly useful for debugging purposes. The returned string will show the names and the values for fields. This makes the code impossible to evaluate, so if evaluation is wanted

`annotate_fields` must be set to `False`. Attributes such as line numbers and column offsets are not dumped by default. If this is wanted, `include_attributes` can be set to `True`.

32.3 `symtable` — Access to the compiler’s symbol tables

Source code: [Lib/symtable.py](#)

Symbol tables are generated by the compiler from AST just before bytecode is generated. The symbol table is responsible for calculating the scope of every identifier in the code. `symtable` provides an interface to examine these tables.

32.3.1 Generating Symbol Tables

`symtable.symtable (code, filename, compile_type)`

Return the toplevel `SymbolTable` for the Python source `code`. `filename` is the name of the file containing the code. `compile_type` is like the `mode` argument to `compile()`.

32.3.2 Examining Symbol Tables

class `symtable.SymbolTable`

A namespace table for a block. The constructor is not public.

`get_type()`

Return the type of the symbol table. Possible values are 'class', 'module', and 'function'.

`get_id()`

Return the table’s identifier.

`get_name()`

Return the table’s name. This is the name of the class if the table is for a class, the name of the function if the table is for a function, or 'top' if the table is global (`get_type()` returns 'module').

`get_lineno()`

Return the number of the first line in the block this table represents.

`is_optimized()`

Return `True` if the locals in this table can be optimized.

`is_nested()`

Return `True` if the block is a nested class or function.

`has_children()`

Return `True` if the block has nested namespaces within it. These can be obtained with `get_children()`.

`has_exec()`

Return `True` if the block uses `exec`.

`has_import_star()`

Return `True` if the block uses a starred from-import.

`get_identifiers()`

Return a list of names of symbols in this table.

`lookup (name)`

Lookup `name` in the table and return a `Symbol` instance.

get_symbols()
Return a list of *Symbol* instances for names in the table.

get_children()
Return a list of the nested symbol tables.

class symtable.Function
A namespace for a function or method. This class inherits *SymbolTable*.

get_parameters()
Return a tuple containing names of parameters to this function.

get_locals()
Return a tuple containing names of locals in this function.

get_globals()
Return a tuple containing names of globals in this function.

get_frees()
Return a tuple containing names of free variables in this function.

class symtable.Class
A namespace of a class. This class inherits *SymbolTable*.

get_methods()
Return a tuple containing the names of methods declared in the class.

class symtable.Symbol
An entry in a *SymbolTable* corresponding to an identifier in the source. The constructor is not public.

get_name()
Return the symbol's name.

is_referenced()
Return True if the symbol is used in its block.

is_imported()
Return True if the symbol is created from an import statement.

is_parameter()
Return True if the symbol is a parameter.

is_global()
Return True if the symbol is global.

is_declared_global()
Return True if the symbol is declared global with a global statement.

is_local()
Return True if the symbol is local to its block.

is_free()
Return True if the symbol is referenced in its block, but not assigned to.

is_assigned()
Return True if the symbol is assigned to in its block.

is_namespace()
Return True if name binding introduces new namespace.

If the name is used as the target of a function or class statement, this will be true.

For example:

```
>>> table = symtable.symtable("def some_func(): pass", "string", "exec")
>>> table.lookup("some_func").is_namespace()
True
```

Note that a single name can be bound to multiple objects. If the result is `True`, the name may also be bound to other objects, like an `int` or `list`, that does not introduce a new namespace.

get_namespaces()

Return a list of namespaces bound to this name.

get_namespace()

Return the namespace bound to this name. If more than one namespace is bound, a `ValueError` is raised.

32.4 `symbol` — Constants used with Python parse trees

Source code: [Lib/symbol.py](#)

This module provides constants which represent the numeric values of internal nodes of the parse tree. Unlike most Python constants, these use lower-case names. Refer to the file `Grammar/Grammar` in the Python distribution for the definitions of the names in the context of the language grammar. The specific numeric values which the names map to may change between Python versions.

This module also provides one additional data object:

`symbol.sym_name`

Dictionary mapping the numeric values of the constants defined in this module back to name strings, allowing more human-readable representation of parse trees to be generated.

32.5 `token` — Constants used with Python parse trees

Source code: [Lib/token.py](#)

This module provides constants which represent the numeric values of leaf nodes of the parse tree (terminal tokens). Refer to the file `Grammar/Grammar` in the Python distribution for the definitions of the names in the context of the language grammar. The specific numeric values which the names map to may change between Python versions.

The module also provides a mapping from numeric codes to names and some functions. The functions mirror definitions in the Python C header files.

`token.tok_name`

Dictionary mapping the numeric values of the constants defined in this module back to name strings, allowing more human-readable representation of parse trees to be generated.

`token.ISTERMINAL(x)`

Return true for terminal token values.

`token.ISNONTERMINAL(x)`

Return true for non-terminal token values.

`token.ISEOF(x)`

Return true if `x` is the marker indicating the end of input.

The token constants are:

`token.ENDMARKER`
`token.NAME`
`token.NUMBER`
`token.STRING`
`token.NEWLINE`
`token.INDENT`
`token.DEDENT`
`token.LPAR`
`token.RPAR`
`token.LSQB`
`token.RSQB`
`token.COLON`
`token.COMMA`
`token.SEMI`
`token.PLUS`
`token.MINUS`
`token.STAR`
`token.SLASH`
`token.VBAR`
`token.AMPER`
`token.LESS`
`token.GREATER`
`token.EQUAL`
`token.DOT`
`token.PERCENT`
`token.BACKQUOTE`
`token.LBRACE`
`token.RBRACE`
`token.EQEQUAL`
`token.NOTEQUAL`
`token.LESSEQUAL`
`token.GREATEREQUAL`
`token.TILDE`
`token.CIRCUMFLEX`
`token.LEFTSHIFT`
`token.RIGHTSHIFT`
`token.DOUBLESTAR`
`token.PLUSEQUAL`
`token.MINEQUAL`
`token.STAREQUAL`
`token.SLASHEQUAL`
`token.PERCENTEQUAL`
`token.AMPEREQUAL`
`token.VBAREQUAL`
`token.CIRCUMFLEXEQUAL`
`token.LEFTSHIFTEQUAL`
`token.RIGHTSHIFTEQUAL`
`token.DOUBLESTAREQUAL`
`token.DOUBLESASH`
`token.DOUBLESASHEQUAL`
`token.AT`
`token.OP`
`token.ERRORTOKEN`
`token.N_TOKENS`

`token.NT_OFFSET`

더 보기:

Module `parser` The second example for the `parser` module shows how to use the `symbol` module.

32.6 keyword — Testing for Python keywords

Source code: `Lib/keyword.py`

This module allows a Python program to determine if a string is a keyword.

`keyword.iskeyword(s)`

Return true if *s* is a Python keyword.

`keyword.kwlist`

Sequence containing all the keywords defined for the interpreter. If any keywords are defined to only be active when particular `__future__` statements are in effect, these will be included as well.

32.7 tokenize — Tokenizer for Python source

Source code: `Lib/tokenize.py`

The `tokenize` module provides a lexical scanner for Python source code, implemented in Python. The scanner in this module returns comments as tokens as well, making it useful for implementing 《pretty-printers,》 including colorizers for on-screen displays.

To simplify token stream handling, all operators and delimiters tokens are returned using the generic `token.OP` token type. The exact type can be determined by checking the second field (containing the actual token string matched) of the tuple returned from `tokenize.generate_tokens()` for the character sequence that identifies a specific operator token.

The primary entry point is a *generator*:

`tokenize.generate_tokens(readline)`

The `generate_tokens()` generator requires one argument, *readline*, which must be a callable object which provides the same interface as the `readline()` method of built-in file objects (see section *File Objects*). Each call to the function should return one line of input as a string. Alternately, *readline* may be a callable object that signals completion by raising `StopIteration`.

The generator produces 5-tuples with these members: the token type; the token string; a 2-tuple (*srow*, *scol*) of ints specifying the row and column where the token begins in the source; a 2-tuple (*erow*, *ecol*) of ints specifying the row and column where the token ends in the source; and the line on which the token was found. The line passed (the last tuple item) is the *logical* line; continuation lines are included.

버전 2.2에 추가.

An older entry point is retained for backward compatibility:

`tokenize.tokenize(readline[, tokeneater])`

The `tokenize()` function accepts two parameters: one representing the input stream, and one providing an output mechanism for `tokenize()`.

The first parameter, *readline*, must be a callable object which provides the same interface as the *readline()* method of built-in file objects (see section *File Objects*). Each call to the function should return one line of input as a string. Alternately, *readline* may be a callable object that signals completion by raising *StopIteration*.

버전 2.5에서 변경: Added *StopIteration* support.

The second parameter, *tokeneater*, must also be a callable object. It is called once for each token, with five arguments, corresponding to the tuples generated by *generate_tokens()*.

All constants from the *token* module are also exported from *tokenize*, as are two additional token type values that might be passed to the *tokeneater* function by *tokenize()*:

`tokenize.COMMENT`

Token value used to indicate a comment.

`tokenize.NL`

Token value used to indicate a non-terminating newline. The NEWLINE token indicates the end of a logical line of Python code; NL tokens are generated when a logical line of code is continued over multiple physical lines.

Another function is provided to reverse the tokenization process. This is useful for creating tools that tokenize a script, modify the token stream, and write back the modified script.

`tokenize.untokenize(iterable)`

Converts tokens back into Python source code. The *iterable* must return sequences with at least two elements, the token type and the token string. Any additional sequence elements are ignored.

The reconstructed script is returned as a single string. The result is guaranteed to tokenize back to match the input so that the conversion is lossless and round-trips are assured. The guarantee applies only to the token type and token string as the spacing between tokens (column positions) may change.

버전 2.5에 추가.

exception `tokenize.TokenError`

Raised when either a docstring or expression that may be split over several lines is not completed anywhere in the file, for example:

```
"""Beginning of
docstring
```

or:

```
[1,
 2,
 3
```

Note that unclosed single-quoted strings do not cause an error to be raised. They are tokenized as *ERRORTOKEN*, followed by the tokenization of their contents.

Example of a script re-writer that transforms float literals into *Decimal* objects:

```
def decistmt(s):
    """Substitute Decimals for floats in a string of statements.

    >>> from decimal import Decimal
    >>> s = 'print +21.3e-5*-.1234/81.7'
    >>> decistmt(s)
    "print +Decimal ('21.3e-5')*-Decimal ('.1234')/Decimal ('81.7')"
```

>>> exec(s)

```
-3.21716034272e-007
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
>>> exec(decistmt(s))
-3.217160342717258261933904529E-7

"""
result = []
g = generate_tokens(StringIO(s).readline) # tokenize the string
for toknum, tokval, _, _, _ in g:
    if toknum == NUMBER and '.' in tokval: # replace NUMBER tokens
        result.extend([
            (NAME, 'Decimal'),
            (OP, '('),
            (STRING, repr(tokval)),
            (OP, ')')
        ])
    else:
        result.append((toknum, tokval))
return untokenize(result)
```

32.8 tabnanny — Detection of ambiguous indentation

Source code: [Lib/tabnanny.py](#)

For the time being this module is intended to be called as a script. However it is possible to import it into an IDE and use the function `check()` described below.

참고: The API provided by this module is likely to change in future releases; such changes may not be backward compatible.

`tabnanny.check(file_or_dir)`

If `file_or_dir` is a directory and not a symbolic link, then recursively descend the directory tree named by `file_or_dir`, checking all `.py` files along the way. If `file_or_dir` is an ordinary Python source file, it is checked for whitespace related problems. The diagnostic messages are written to standard output using the `print` statement.

`tabnanny.verbose`

Flag indicating whether to print verbose messages. This is incremented by the `-v` option if called as a script.

`tabnanny.filename_only`

Flag indicating whether to print only the filenames of files containing whitespace related problems. This is set to `true` by the `-q` option if called as a script.

exception `tabnanny.NannyNag`

Raised by `process_tokens()` if detecting an ambiguous indent. Captured and handled in `check()`.

`tabnanny.process_tokens(tokens)`

This function is used by `check()` to process tokens generated by the `tokenize` module.

더 보기:

Module `tokenize` Lexical scanner for Python source code.

32.9 pyc1br — Python class browser support

Source code: [Lib/pyc1br.py](#)

The `pyc1br` module can be used to determine some limited information about the classes, methods and top-level functions defined in a module. The information provided is sufficient to implement a traditional three-pane class browser. The information is extracted from the source code rather than by importing the module, so this module is safe to use with untrusted code. This restriction makes it impossible to use this module with modules not implemented in Python, including all standard and optional extension modules.

`pyc1br.readmodule(module, path=None)`

Read a module and return a dictionary mapping class names to class descriptor objects. The parameter *module* should be the name of a module as a string; it may be the name of a module within a package. The *path* parameter should be a sequence, and is used to augment the value of `sys.path`, which is used to locate module source code.

`pyc1br.readmodule_ex(module, path=None)`

Like `readmodule()`, but the returned dictionary, in addition to mapping class names to class descriptor objects, also maps top-level function names to function descriptor objects. Moreover, if the module being read is a package, the key `'__path__'` in the returned dictionary has as its value a list which contains the package search path.

32.9.1 Class Objects

The `Class` objects used as values in the dictionary returned by `readmodule()` and `readmodule_ex()` provide the following data attributes:

`Class.module`

The name of the module defining the class described by the class descriptor.

`Class.name`

The name of the class.

`Class.super`

A list of `Class` objects which describe the immediate base classes of the class being described. Classes which are named as superclasses but which are not discoverable by `readmodule()` are listed as a string with the class name instead of as `Class` objects.

`Class.methods`

A dictionary mapping method names to line numbers.

`Class.file`

Name of the file containing the `class` statement defining the class.

`Class.lineno`

The line number of the `class` statement within the file named by *file*.

32.9.2 Function Objects

The `Function` objects used as values in the dictionary returned by `readmodule_ex()` provide the following attributes:

`Function.module`

The name of the module defining the function described by the function descriptor.

`Function.name`

The name of the function.

Function.`file`Name of the file containing the `def` statement defining the function.**Function.**`lineno`The line number of the `def` statement within the file named by *file*.

32.10 `py_compile` — Compile Python source files

Source code: [Lib/py_compile.py](#)

The `py_compile` module provides a function to generate a byte-code file from a source file, and another function used when the module source file is invoked as a script.

Though not often needed, this function can be useful when installing modules for shared use, especially if some of the users may not have permission to write the byte-code cache files in the directory containing the source code.

exception `py_compile.PyCompileError`

Exception raised when an error occurs while attempting to compile the file.

`py_compile.compile(file[, cfile[, dfile[, doraise]]])`

Compile a source file to byte-code and write out the byte-code cache file. The source code is loaded from the file named *file*. The byte-code is written to *cfile*, which defaults to *file* + `'c'` (`'o'` if optimization is enabled in the current interpreter). If *dfile* is specified, it is used as the name of the source file in error messages instead of *file*. If *doraise* is true, a `PyCompileError` is raised when an error is encountered while compiling *file*. If *doraise* is false (the default), an error string is written to `sys.stderr`, but no exception is raised.

`py_compile.main([args])`

Compile several source files. The files named in *args* (or on the command line, if *args* is not specified) are compiled and the resulting bytecode is cached in the normal manner. This function does not search a directory structure to locate source files; it only compiles files named explicitly. If `'-'` is the only parameter in *args*, the list of files is taken from standard input.

버전 2.7에서 변경: Added support for `'-'`.

When this module is run as a script, the `main()` is used to compile all the files named on the command line. The exit status is nonzero if one of the files could not be compiled.

버전 2.6에서 변경: Added the nonzero exit status when module is run as a script.

더 보기:

Module `compileall` Utilities to compile all Python source files in a directory tree.

32.11 `compileall` — Byte-compile Python libraries

Source code: [Lib/compileall.py](#)

This module provides some utility functions to support installing Python libraries. These functions compile Python source files in a directory tree. This module can be used to create the cached byte-code files at library installation time, which makes them available for use even by users who don't have write permission to the library directories.

32.11.1 Command-line use

This module can work as a script (using `python -m compileall`) to compile Python sources.

directory ...

file ...

Positional arguments are files to compile or directories that contain source files, traversed recursively. If no argument is given, behave as if the command line was `-l <directories from sys.path>`.

-l

Do not recurse into subdirectories, only compile source code files directly contained in the named or implied directories.

-f

Force rebuild even if timestamps are up-to-date.

-q

Do not print the list of files compiled, print only error messages.

-d `destdir`

Directory prepended to the path to each file being compiled. This will appear in compilation time tracebacks, and is also compiled in to the byte-code file, where it will be used in tracebacks and other messages in cases where the source file does not exist at the time the byte-code file is executed.

-x `regex`

`regex` is used to search the full path to each file considered for compilation, and if the regex produces a match, the file is skipped.

-i `list`

Read the file `list` and add each line that it contains to the list of files and directories to compile. If `list` is `-`, read lines from `stdin`.

버전 2.7에서 변경: Added the `-i` option.

32.11.2 Public functions

`compileall.compile_dir(dir[, maxlevels[, ddir[, force[, rx[, quiet]]]])`

Recursively descend the directory tree named by *dir*, compiling all `.py` files along the way.

The *maxlevels* parameter is used to limit the depth of the recursion; it defaults to 10.

If *ddir* is given, it is prepended to the path to each file being compiled for use in compilation time tracebacks, and is also compiled in to the byte-code file, where it will be used in tracebacks and other messages in cases where the source file does not exist at the time the byte-code file is executed.

If *force* is true, modules are re-compiled even if the timestamps are up to date.

If *rx* is given, its search method is called on the complete path to each file considered for compilation, and if it returns a true value, the file is skipped.

If *quiet* is true, nothing is printed to the standard output unless errors occur.

`compileall.compile_file(fullname[, ddir[, force[, rx[, quiet]]]])`

Compile the file with path *fullname*.

If *ddir* is given, it is prepended to the path to the file being compiled for use in compilation time tracebacks, and is also compiled in to the byte-code file, where it will be used in tracebacks and other messages in cases where the source file does not exist at the time the byte-code file is executed.

If *rx* is given, its search method is passed the full path name to the file being compiled, and if it returns a true value, the file is not compiled and `True` is returned.

If *quiet* is true, nothing is printed to the standard output unless errors occur.

버전 2.7에 추가.

```
compileall.compile_path([skip_cudir[, maxlevels[, force]]])
```

Byte-compile all the .py files found along `sys.path`. If *skip_cudir* is true (the default), the current directory is not included in the search. All other parameters are passed to the `compile_dir()` function. Note that unlike the other compile functions, *maxlevels* defaults to 0.

To force a recompile of all the .py files in the `Lib/` subdirectory and all its subdirectories:

```
import compileall

compileall.compile_dir('Lib/', force=True)

# Perform same compilation, excluding files in .svn directories.
import re
compileall.compile_dir('Lib/', rx=re.compile(r'[/\\](.)svn'), force=True)
```

더 보기:

Module `py_compile` Byte-compile a single source file.

32.12 `dis` — Disassembler for Python bytecode

Source code: [Lib/dis.py](#)

The `dis` module supports the analysis of CPython *bytecode* by disassembling it. The CPython bytecode which this module takes as an input is defined in the file `Include/opcode.h` and used by the compiler and the interpreter.

CPython implementation detail: Bytecode is an implementation detail of the CPython interpreter! No guarantees are made that bytecode will not be added, removed, or changed between versions of Python. Use of this module should not be considered to work across Python VMs or Python releases.

Example: Given the function `myfunc()`:

```
def myfunc(alist):
    return len(alist)
```

the following command can be used to get the disassembly of `myfunc()`:

```
>>> dis.dis(myfunc)
2          0 LOAD_GLOBAL              0 (len)
          3 LOAD_FAST                    0 (alist)
          6 CALL_FUNCTION                1
          9 RETURN_VALUE
```

(The «2» is a line number).

The `dis` module defines the following functions and constants:

`dis.dis([bytestr])`

Disassemble the *bytestr* object. *bytestr* can denote either a module, a class, a method, a function, or a code object. For a module, it disassembles all functions. For a class, it disassembles all methods. For a single code sequence, it prints one line per bytecode instruction. If no object is provided, it disassembles the last traceback.

`dis.distb([tb])`

Disassembles the top-of-stack function of a traceback, using the last traceback if none was passed. The instruction causing the exception is indicated.

`dis.disassemble(code[, lasti])`

Disassembles a code object, indicating the last instruction if *lasti* was provided. The output is divided in the following columns:

1. the line number, for the first instruction of each line
2. the current instruction, indicated as `-->`,
3. a labelled instruction, indicated with `>>`,
4. the address of the instruction,
5. the operation code name,
6. operation parameters, and
7. interpretation of the parameters in parentheses.

The parameter interpretation recognizes local and global variable names, constant values, branch targets, and compare operators.

`dis.disco(code[, lasti])`

A synonym for `disassemble()`. It is more convenient to type, and kept for compatibility with earlier Python releases.

`dis.findlinestarts(code)`

This generator function uses the `co_firstlineno` and `co_lnotab` attributes of the code object *code* to find the offsets which are starts of lines in the source code. They are generated as `(offset, lineno)` pairs.

`dis.findlabels(code)`

Detect all offsets in the code object *code* which are jump targets, and return a list of these offsets.

`dis.opname`

Sequence of operation names, indexable using the bytecode.

`dis.opmap`

Dictionary mapping operation names to bytecodes.

`dis.cmp_op`

Sequence of all compare operation names.

`dis.hasconst`

Sequence of bytecodes that access a constant.

`dis.hasfree`

Sequence of bytecodes that access a free variable.

`dis.hasname`

Sequence of bytecodes that access an attribute by name.

`dis.hasjrel`

Sequence of bytecodes that have a relative jump target.

`dis.hasjabs`

Sequence of bytecodes that have an absolute jump target.

`dis.haslocal`

Sequence of bytecodes that access a local variable.

`dis.hascompare`

Sequence of bytecodes of Boolean operations.

32.12.1 Python Bytecode Instructions

The Python compiler currently generates the following bytecode instructions.

STOP_CODE ()

Indicates end-of-code to the compiler, not used by the interpreter.

NOP ()

Do nothing code. Used as a placeholder by the bytecode optimizer.

POP_TOP ()

Removes the top-of-stack (TOS) item.

ROT_TWO ()

Swaps the two top-most stack items.

ROT_THREE ()

Lifts second and third stack item one position up, moves top down to position three.

ROT_FOUR ()

Lifts second, third and forth stack item one position up, moves top down to position four.

DUP_TOP ()

Duplicates the reference on top of the stack.

Unary Operations take the top of the stack, apply the operation, and push the result back on the stack.

UNARY_POSITIVE ()

Implements `TOS = +TOS`.

UNARY_NEGATIVE ()

Implements `TOS = -TOS`.

UNARY_NOT ()

Implements `TOS = not TOS`.

UNARY_CONVERT ()

Implements `TOS = `TOS``.

UNARY_INVERT ()

Implements `TOS = ~TOS`.

GET_ITER ()

Implements `TOS = iter(TOS)`.

Binary operations remove the top of the stack (TOS) and the second top-most stack item (TOS1) from the stack. They perform the operation, and put the result back on the stack.

BINARY_POWER ()

Implements `TOS = TOS1 ** TOS`.

BINARY_MULTIPLY ()

Implements `TOS = TOS1 * TOS`.

BINARY_DIVIDE ()

Implements `TOS = TOS1 / TOS` when from `__future__` import `division` is not in effect.

BINARY_FLOOR_DIVIDE ()

Implements `TOS = TOS1 // TOS`.

BINARY_TRUE_DIVIDE ()

Implements `TOS = TOS1 / TOS` when from `__future__` import `division` is in effect.

BINARY_MODULO()

Implements $TOS = TOS1 \% TOS$.

BINARY_ADD()

Implements $TOS = TOS1 + TOS$.

BINARY_SUBTRACT()

Implements $TOS = TOS1 - TOS$.

BINARY_SUBSCR()

Implements $TOS = TOS1[TOS]$.

BINARY_LSHIFT()

Implements $TOS = TOS1 \ll TOS$.

BINARY_RSHIFT()

Implements $TOS = TOS1 \gg TOS$.

BINARY_AND()

Implements $TOS = TOS1 \& TOS$.

BINARY_XOR()

Implements $TOS = TOS1 \wedge TOS$.

BINARY_OR()

Implements $TOS = TOS1 | TOS$.

In-place operations are like binary operations, in that they remove TOS and TOS1, and push the result back on the stack, but the operation is done in-place when TOS1 supports it, and the resulting TOS may be (but does not have to be) the original TOS1.

INPLACE_POWER()

Implements in-place $TOS = TOS1 ** TOS$.

INPLACE_MULTIPLY()

Implements in-place $TOS = TOS1 * TOS$.

INPLACE_DIVIDE()

Implements in-place $TOS = TOS1 / TOS$ when `from __future__ import division` is not in effect.

INPLACE_FLOOR_DIVIDE()

Implements in-place $TOS = TOS1 // TOS$.

INPLACE_TRUE_DIVIDE()

Implements in-place $TOS = TOS1 / TOS$ when `from __future__ import division` is in effect.

INPLACE_MODULO()

Implements in-place $TOS = TOS1 \% TOS$.

INPLACE_ADD()

Implements in-place $TOS = TOS1 + TOS$.

INPLACE_SUBTRACT()

Implements in-place $TOS = TOS1 - TOS$.

INPLACE_LSHIFT()

Implements in-place $TOS = TOS1 \ll TOS$.

INPLACE_RSHIFT()

Implements in-place $TOS = TOS1 \gg TOS$.

INPLACE_AND()

Implements in-place $TOS = TOS1 \& TOS$.

INPLACE_XOR()

Implements in-place `TOS = TOS1 ^ TOS`.

INPLACE_OR()

Implements in-place `TOS = TOS1 | TOS`.

The slice opcodes take up to three parameters.

SLICE+0()

Implements `TOS = TOS[:]`.

SLICE+1()

Implements `TOS = TOS1[TOS:]`.

SLICE+2()

Implements `TOS = TOS1[:TOS]`.

SLICE+3()

Implements `TOS = TOS2[TOS1:TOS]`.

Slice assignment needs even an additional parameter. As any statement, they put nothing on the stack.

STORE_SLICE+0()

Implements `TOS[:] = TOS1`.

STORE_SLICE+1()

Implements `TOS1[TOS:] = TOS2`.

STORE_SLICE+2()

Implements `TOS1[:TOS] = TOS2`.

STORE_SLICE+3()

Implements `TOS2[TOS1:TOS] = TOS3`.

DELETE_SLICE+0()

Implements `del TOS[:]`.

DELETE_SLICE+1()

Implements `del TOS1[TOS:]`.

DELETE_SLICE+2()

Implements `del TOS1[:TOS]`.

DELETE_SLICE+3()

Implements `del TOS2[TOS1:TOS]`.

STORE_SUBSCR()

Implements `TOS1[TOS] = TOS2`.

DELETE_SUBSCR()

Implements `del TOS1[TOS]`.

Miscellaneous opcodes.

PRINT_EXPR()

Implements the expression statement for the interactive mode. TOS is removed from the stack and printed. In non-interactive mode, an expression statement is terminated with `POP_TOP`.

PRINT_ITEM()

Prints TOS to the file-like object bound to `sys.stdout`. There is one such instruction for each item in the `print` statement.

PRINT_ITEM_TO()

Like `PRINT_ITEM`, but prints the item second from TOS to the file-like object at TOS. This is used by the extended print statement.

PRINT_NEWLINE()

Prints a new line on `sys.stdout`. This is generated as the last operation of a `print` statement, unless the statement ends with a comma.

PRINT_NEWLINE_TO()

Like `PRINT_NEWLINE`, but prints the new line on the file-like object on the TOS. This is used by the extended print statement.

BREAK_LOOP()

Terminates a loop due to a `break` statement.

CONTINUE_LOOP(*target*)

Continues a loop due to a `continue` statement. *target* is the address to jump to (which should be a [FOR_ITER](#) instruction).

LIST_APPEND(*i*)

Calls `list.append(TOS[-i], TOS)`. Used to implement list comprehensions. While the appended value is popped off, the list object remains on the stack so that it is available for further iterations of the loop.

LOAD_LOCALS()

Pushes a reference to the locals of the current scope on the stack. This is used in the code for a class definition: After the class body is evaluated, the locals are passed to the class definition.

RETURN_VALUE()

Returns with TOS to the caller of the function.

YIELD_VALUE()

Pops TOS and yields it from a [generator](#).

IMPORT_STAR()

Loads all symbols not starting with `'_'` directly from the module TOS to the local namespace. The module is popped after loading all names. This opcode implements `from module import *`.

EXEC_STMT()

Implements `exec TOS2, TOS1, TOS`. The compiler fills missing optional parameters with `None`.

POP_BLOCK()

Removes one block from the block stack. Per frame, there is a stack of blocks, denoting nested loops, try statements, and such.

END_FINALLY()

Terminates a `finally` clause. The interpreter recalls whether the exception has to be re-raised, or whether the function returns, and continues with the outer-next block.

BUILD_CLASS()

Creates a new class object. TOS is the methods dictionary, TOS1 the tuple of the names of the base classes, and TOS2 the class name.

SETUP_WITH(*delta*)

This opcode performs several operations before a `with` block starts. First, it loads `__exit__()` from the context manager and pushes it onto the stack for later use by [WITH_CLEANUP](#). Then, `__enter__()` is called, and a finally block pointing to *delta* is pushed. Finally, the result of calling the enter method is pushed onto the stack. The next opcode will either ignore it ([POP_TOP](#)), or store it in (a) variable(s) ([STORE_FAST](#), [STORE_NAME](#), or [UNPACK_SEQUENCE](#)).

WITH_CLEANUP()

Cleans up the stack when a `with` statement block exits. On top of the stack are 1–3 values indicating how/why

the finally clause was entered:

- `TOP = None`
- `(TOP, SECOND) = (WHY_{RETURN, CONTINUE}), retval`
- `TOP = WHY_*`; no `retval` below it
- `(TOP, SECOND, THIRD) = exc_info()`

Under them is `EXIT`, the context manager's `__exit__()` bound method.

In the last case, `EXIT(TOP, SECOND, THIRD)` is called, otherwise `EXIT(None, None, None)`.

`EXIT` is removed from the stack, leaving the values above it in the same order. In addition, if the stack represents an exception, *and* the function call returns a `<true>` value, this information is *zapped*, to prevent `END_FINALLY` from re-raising the exception. (But non-local `gotos` should still be resumed.)

All of the following opcodes expect arguments. An argument is two bytes, with the more significant byte last.

STORE_NAME (*namei*)

Implements `name = TOS`. *namei* is the index of *name* in the attribute `co_names` of the code object. The compiler tries to use `STORE_FAST` or `STORE_GLOBAL` if possible.

DELETE_NAME (*namei*)

Implements `del name`, where *namei* is the index into `co_names` attribute of the code object.

UNPACK_SEQUENCE (*count*)

Unpacks `TOS` into *count* individual values, which are put onto the stack right-to-left.

DUP_TOPX (*count*)

Duplicate *count* items, keeping them in the same order. Due to implementation limits, *count* should be between 1 and 5 inclusive.

STORE_ATTR (*namei*)

Implements `TOS.name = TOS1`, where *namei* is the index of *name* in `co_names`.

DELETE_ATTR (*namei*)

Implements `del TOS.name`, using *namei* as index into `co_names`.

STORE_GLOBAL (*namei*)

Works as `STORE_NAME`, but stores the name as a global.

DELETE_GLOBAL (*namei*)

Works as `DELETE_NAME`, but deletes a global name.

LOAD_CONST (*consti*)

Pushes `co_consts[consti]` onto the stack.

LOAD_NAME (*namei*)

Pushes the value associated with `co_names[namei]` onto the stack.

BUILD_TUPLE (*count*)

Creates a tuple consuming *count* items from the stack, and pushes the resulting tuple onto the stack.

BUILD_LIST (*count*)

Works as `BUILD_TUPLE`, but creates a list.

BUILD_SET (*count*)

Works as `BUILD_TUPLE`, but creates a set.

버전 2.7에 추가.

BUILD_MAP (*count*)

Pushes a new dictionary object onto the stack. The dictionary is pre-sized to hold *count* entries.

LOAD_ATTR (*namei*)

Replaces TOS with `getattr(TOS, co_names[namei])`.

COMPARE_OP (*opname*)

Performs a Boolean operation. The operation name can be found in `cmp_op[opname]`.

IMPORT_NAME (*namei*)

Imports the module `co_names[namei]`. TOS and TOS1 are popped and provide the *fromlist* and *level* arguments of `__import__()`. The module object is pushed onto the stack. The current namespace is not affected: for a proper import statement, a subsequent `STORE_FAST` instruction modifies the namespace.

IMPORT_FROM (*namei*)

Loads the attribute `co_names[namei]` from the module found in TOS. The resulting object is pushed onto the stack, to be subsequently stored by a `STORE_FAST` instruction.

JUMP_FORWARD (*delta*)

Increments bytecode counter by *delta*.

POP_JUMP_IF_TRUE (*target*)

If TOS is true, sets the bytecode counter to *target*. TOS is popped.

POP_JUMP_IF_FALSE (*target*)

If TOS is false, sets the bytecode counter to *target*. TOS is popped.

JUMP_IF_TRUE_OR_POP (*target*)

If TOS is true, sets the bytecode counter to *target* and leaves TOS on the stack. Otherwise (TOS is false), TOS is popped.

JUMP_IF_FALSE_OR_POP (*target*)

If TOS is false, sets the bytecode counter to *target* and leaves TOS on the stack. Otherwise (TOS is true), TOS is popped.

JUMP_ABSOLUTE (*target*)

Set bytecode counter to *target*.

FOR_ITER (*delta*)

TOS is an *iterator*. Call its `next()` method. If this yields a new value, push it on the stack (leaving the iterator below it). If the iterator indicates it is exhausted TOS is popped, and the bytecode counter is incremented by *delta*.

LOAD_GLOBAL (*namei*)

Loads the global named `co_names[namei]` onto the stack.

SETUP_LOOP (*delta*)

Pushes a block for a loop onto the block stack. The block spans from the current instruction with a size of *delta* bytes.

SETUP_EXCEPT (*delta*)

Pushes a try block from a try-except clause onto the block stack. *delta* points to the first except block.

SETUP_FINALLY (*delta*)

Pushes a try block from a try-except clause onto the block stack. *delta* points to the finally block.

STORE_MAP ()

Store a key and value pair in a dictionary. Pops the key and value while leaving the dictionary on the stack.

LOAD_FAST (*var_num*)

Pushes a reference to the local `co_varnames[var_num]` onto the stack.

STORE_FAST (*var_num*)

Stores TOS into the local `co_varnames[var_num]`.

DELETE_FAST (*var_num*)

Deletes local `co_varnames[var_num]`.

LOAD_CLOSURE (*i*)

Pushes a reference to the cell contained in slot *i* of the cell and free variable storage. The name of the variable is `co_cellvars[i]` if *i* is less than the length of `co_cellvars`. Otherwise it is `co_freevars[i - len(co_cellvars)]`.

LOAD_DEREF (*i*)

Loads the cell contained in slot *i* of the cell and free variable storage. Pushes a reference to the object the cell contains on the stack.

STORE_DEREF (*i*)

Stores TOS into the cell contained in slot *i* of the cell and free variable storage.

SET_LINENO (*lineno*)

This opcode is obsolete.

RAISE_VARARGS (*argc*)

Raises an exception. *argc* indicates the number of arguments to the raise statement, ranging from 0 to 3. The handler will find the traceback as TOS2, the parameter as TOS1, and the exception as TOS.

CALL_FUNCTION (*argc*)

Calls a callable object. The low byte of *argc* indicates the number of positional arguments, the high byte the number of keyword arguments. The stack contains keyword arguments on top (if any), then the positional arguments below that (if any), then the callable object to call below that. Each keyword argument is represented with two values on the stack: the argument's name, and its value, with the argument's value above the name on the stack. The positional arguments are pushed in the order that they are passed in to the callable object, with the right-most positional argument on top. `CALL_FUNCTION` pops all arguments and the callable object off the stack, calls the callable object with those arguments, and pushes the return value returned by the callable object.

MAKE_FUNCTION (*argc*)

Pushes a new function object on the stack. TOS is the code associated with the function. The function object is defined to have *argc* default parameters, which are found below TOS.

MAKE_CLOSURE (*argc*)

Creates a new function object, sets its `func_closure` slot, and pushes it on the stack. TOS is the code associated with the function, TOS1 the tuple containing cells for the closure's free variables. The function also has *argc* default parameters, which are found below the cells.

BUILD_SLICE (*argc*)

Pushes a slice object on the stack. *argc* must be 2 or 3. If it is 2, `slice(TOS1, TOS)` is pushed; if it is 3, `slice(TOS2, TOS1, TOS)` is pushed. See the `slice()` built-in function for more information.

EXTENDED_ARG (*ext*)

Prefixes any opcode which has an argument too big to fit into the default two bytes. *ext* holds two additional bytes which, taken together with the subsequent opcode's argument, comprise a four-byte argument, *ext* being the two most-significant bytes.

CALL_FUNCTION_VAR (*argc*)

Calls a callable object, similarly to `CALL_FUNCTION`. *argc* represents the number of keyword and positional arguments, identically to `CALL_FUNCTION`. The top of the stack contains an iterable object containing additional positional arguments. Below that are keyword arguments (if any), positional arguments (if any) and a callable object, identically to `CALL_FUNCTION`. Before the callable object is called, the iterable object is «unpacked» and its contents are appended to the positional arguments passed in. The iterable object is ignored when computing the value of *argc*.

CALL_FUNCTION_KW (*argc*)

Calls a callable object, similarly to `CALL_FUNCTION`. *argc* represents the number of keyword and positional arguments, identically to `CALL_FUNCTION`. The top of the stack contains a mapping object containing additional keyword arguments. Below that are keyword arguments (if any), positional arguments (if any) and a callable object, identically to `CALL_FUNCTION`. Before the callable is called, the mapping object at the top of the stack is

《unpacked》 and its contents are appended to the keyword arguments passed in. The mapping object at the top of the stack is ignored when computing the value of `argc`.

CALL_FUNCTION_VAR_KW (*argc*)

Calls a callable object, similarly to `CALL_FUNCTION_VAR` and `CALL_FUNCTION_KW`. *argc* represents the number of keyword and positional arguments, identically to `CALL_FUNCTION`. The top of the stack contains a mapping object, as per `CALL_FUNCTION_KW`. Below that is an iterable object, as per `CALL_FUNCTION_VAR`. Below that are keyword arguments (if any), positional arguments (if any) and a callable object, identically to `CALL_FUNCTION`. Before the callable is called, the mapping object and iterable object are each 《unpacked》 and their contents passed in as keyword and positional arguments respectively, identically to `CALL_FUNCTION_VAR` and `CALL_FUNCTION_KW`. The mapping object and iterable object are both ignored when computing the value of `argc`.

HAVE_ARGUMENT ()

This is not really an opcode. It identifies the dividing line between opcodes which don't take arguments < HAVE_ARGUMENT and those which do >= HAVE_ARGUMENT.

32.13 pickletools — Tools for pickle developers

버전 2.3에 추가.

Source code: [Lib/pickletools.py](#)

This module contains various constants relating to the intimate details of the `pickle` module, some lengthy comments about the implementation, and a few useful functions for analyzing pickled data. The contents of this module are useful for Python core developers who are working on the `pickle` and `cPickle` implementations; ordinary users of the `pickle` module probably won't find the `pickletools` module relevant.

`pickletools.dis` (*pickle*, *out=None*, *memo=None*, *indentlevel=4*)

Outputs a symbolic disassembly of the pickle to the file-like object *out*, defaulting to `sys.stdout`. *pickle* can be a string or a file-like object. *memo* can be a Python dictionary that will be used as the pickle's memo; it can be used to perform disassemblies across multiple pickles created by the same pickler. Successive levels, indicated by MARK opcodes in the stream, are indented by *indentlevel* spaces.

`pickletools.genops` (*pickle*)

Provides an *iterator* over all of the opcodes in a pickle, returning a sequence of (*opcode*, *arg*, *pos*) triples. *opcode* is an instance of an `OpcodeInfo` class; *arg* is the decoded value, as a Python object, of the opcode's argument; *pos* is the position at which this opcode is located. *pickle* can be a string or a file-like object.

`pickletools.optimize` (*picklestring*)

Returns a new equivalent pickle string after eliminating unused PUT opcodes. The optimized pickle is shorter, takes less transmission time, requires less storage space, and unpickles more efficiently.

버전 2.6에 추가.

Python compiler package

버전 2.6부터 폐지: The `compiler` package has been removed in Python 3.

The Python compiler package is a tool for analyzing Python source code and generating Python bytecode. The compiler contains libraries to generate an abstract syntax tree from Python source code and to generate Python *bytecode* from the tree.

The `compiler` package is a Python source to bytecode translator written in Python. It uses the built-in parser and standard `parser` module to generate a concrete syntax tree. This tree is used to generate an abstract syntax tree (AST) and then Python bytecode.

The full functionality of the package duplicates the built-in compiler provided with the Python interpreter. It is intended to match its behavior almost exactly. Why implement another compiler that does the same thing? The package is useful for a variety of purposes. It can be modified more easily than the built-in compiler. The AST it generates is useful for analyzing Python source code.

This chapter explains how the various components of the `compiler` package work. It blends reference material with a tutorial.

33.1 The basic interface

The top-level of the package defines four functions. If you import `compiler`, you will get these functions and a collection of modules contained in the package.

`compiler.parse(buf)`

Returns an abstract syntax tree for the Python source code in *buf*. The function raises `SyntaxError` if there is an error in the source code. The return value is a `compiler.ast.Module` instance that contains the tree.

`compiler.parseFile(path)`

Return an abstract syntax tree for the Python source code in the file specified by *path*. It is equivalent to `parse(open(path).read())`.

`compiler.walk(ast, visitor[, verbose])`

Do a pre-order walk over the abstract syntax tree *ast*. Call the appropriate method on the *visitor* instance for each node encountered.

`compiler.compile(source, filename, mode, flags=None, dont_inherit=None)`

Compile the string *source*, a Python module, statement or expression, into a code object that can be executed by the `exec` statement or `eval()`. This function is a replacement for the built-in `compile()` function.

The *filename* will be used for run-time error messages.

The *mode* must be `<exec>` to compile a module, `<single>` to compile a single (interactive) statement, or `<eval>` to compile an expression.

The *flags* and *dont_inherit* arguments affect future-related statements, but are not supported yet.

`compiler.compileFile(source)`

Compiles the file *source* and generates a .pyc file.

The `compiler` package contains the following modules: `ast`, `consts`, `future`, `misc`, `pyassem`, `pycodegen`, `symbols`, `transformer`, and `visitor`.

33.2 Limitations

There are some problems with the error checking of the compiler package. The interpreter detects syntax errors in two distinct phases. One set of errors is detected by the interpreter's parser, the other set by the compiler. The compiler package relies on the interpreter's parser, so it gets the first phases of error checking for free. It implements the second phase itself, and that implementation is incomplete. For example, the compiler package does not raise an error if a name appears more than once in an argument list: `def f(x, x): ...`

A future version of the compiler should fix these problems.

33.3 Python Abstract Syntax

The `compiler.ast` module defines an abstract syntax for Python. In the abstract syntax tree, each node represents a syntactic construct. The root of the tree is `Module` object.

The abstract syntax offers a higher level interface to parsed Python source code. The `parser` module and the compiler written in C for the Python interpreter use a concrete syntax tree. The concrete syntax is tied closely to the grammar description used for the Python parser. Instead of a single node for a construct, there are often several levels of nested nodes that are introduced by Python's precedence rules.

The abstract syntax tree is created by the `compiler.transformer` module. The transformer relies on the built-in Python parser to generate a concrete syntax tree. It generates an abstract syntax tree from the concrete tree.

The `transformer` module was created by Greg Stein and Bill Tutt for an experimental Python-to-C compiler. The current version contains a number of modifications and improvements, but the basic form of the abstract syntax and of the transformer are due to Stein and Tutt.

33.3.1 AST Nodes

The `compiler.ast` module is generated from a text file that describes each node type and its elements. Each node type is represented as a class that inherits from the abstract base class `compiler.ast.Node` and defines a set of named attributes for child nodes.

class `compiler.ast.Node`

The `Node` instances are created automatically by the parser generator. The recommended interface for specific `Node` instances is to use the public attributes to access child nodes. A public attribute may be bound to a single

node or to a sequence of nodes, depending on the *Node* type. For example, the `bases` attribute of the `Class` node, is bound to a list of base class nodes, and the `doc` attribute is bound to a single node.

Each *Node* instance has a `lineno` attribute which may be `None`. XXX Not sure what the rules are for which nodes will have a useful `lineno`.

All *Node* objects offer the following methods:

getChildren()

Returns a flattened list of the child nodes and objects in the order they occur. Specifically, the order of the nodes is the order in which they appear in the Python grammar. Not all of the children are *Node* instances. The names of functions and classes, for example, are plain strings.

getChildNodes()

Returns a flattened list of the child nodes in the order they occur. This method is like *getChildren()*, except that it only returns those children that are *Node* instances.

Two examples illustrate the general structure of *Node* classes. The `while` statement is defined by the following grammar production:

```
while_stmt:      "while" expression ":" suite
               ["else" ":" suite]
```

The `While` node has three attributes: `test`, `body`, and `else_`. (If the natural name for an attribute is also a Python reserved word, it can't be used as an attribute name. An underscore is appended to the word to make it a legal identifier, hence `else_` instead of `else`.)

The `if` statement is more complicated because it can include several tests.

```
if_stmt: 'if' test ':' suite ('elif' test ':' suite)* ['else' ':' suite]
```

The `If` node only defines two attributes: `tests` and `else_`. The `tests` attribute is a sequence of test expression, consequent body pairs. There is one pair for each `if/elif` clause. The first element of the pair is the test expression. The second elements is a `Stmt` node that contains the code to execute if the test is true.

The *getChildren()* method of `If` returns a flat list of child nodes. If there are three `if/elif` clauses and no `else` clause, then *getChildren()* will return a list of six elements: the first test expression, the first `Stmt`, the second test expression, etc.

The following table lists each of the *Node* subclasses defined in *compiler.ast* and each of the public attributes available on their instances. The values of most of the attributes are themselves *Node* instances or sequences of instances. When the value is something other than an instance, the type is noted in the comment. The attributes are listed in the order in which they are returned by *getChildren()* and *getChildNodes()*.

Node type	Attribute	Value
Add	<code>left</code>	left operand
	<code>right</code>	right operand
And	<code>nodes</code>	list of operands
AssAttr		<i>attribute as target of assignment</i>
	<code>expr</code>	expression on the left-hand side of the dot
	<code>attrname</code>	the attribute name, a string
	<code>flags</code>	XXX
AssList	<code>nodes</code>	list of list elements being assigned to
AssName	<code>name</code>	name being assigned to
	<code>flags</code>	XXX
AssTuple	<code>nodes</code>	list of tuple elements being assigned to
Assert	<code>test</code>	the expression to be tested

다음 페이지에 계속

표 1 - 이전 페이지에서 계속

Node type	Attribute	Value
	fail	the value of the <i>AssertionError</i>
Assign	nodes	a list of assignment targets, one per equal sign
	expr	the value being assigned
AugAssign	node	
	op	
	expr	
Backquote	expr	
Bitand	nodes	
Bitor	nodes	
Bitxor	nodes	
Break		
CallFunc	node	expression for the callee
	args	a list of arguments
	star_args	the extended *-arg value
	dstar_args	the extended **-arg value
Class	name	the name of the class, a string
	bases	a list of base classes
	doc	doc string, a string or None
	<i>code</i>	the body of the class statement
Compare	expr	
	ops	
Const	value	
Continue		
Decorators	nodes	List of function decorator expressions
Dict	items	
Discard	expr	
Div	left	
	right	
<i>Ellipsis</i>		
Expression	node	
Exec	expr	
	<i>locals</i>	
	<i>globals</i>	
FloorDiv	left	
	right	
For	assign	
	list	
	body	
	else_	
From	modname	
	names	
Function	decorators	Decorators or None
	name	name used in def, a string
	argnames	list of argument names, as strings
	defaults	list of default values
	flags	xxx
	doc	doc string, a string or None
	<i>code</i>	the body of the function
GenExpr	<i>code</i>	

다음 페이지에 계속

표 1 - 이전 페이지에서 계속

Node type	Attribute	Value
GenExprFor	assign	
	<i>iter</i>	
	ifs	
GenExprIf	<i>test</i>	
GenExprInner	expr	
	quals	
Getattr	expr	
	attrname	
Global	names	
If	tests	
	else_	
Import	names	
Invert	expr	
Keyword	name	
	expr	
Lambda	argnames	
	defaults	
	flags	
	<i>code</i>	
LeftShift	left	
	right	
List	nodes	
ListComp	expr	
	quals	
	assign	
ListCompFor	list	
	ifs	
	<i>test</i>	
Mod	left	
	right	
Module	doc	doc string, a string or None
	node	body of the module, a Stmt
Mul	left	
	right	
Name	name	
Not	expr	
Or	nodes	
Pass		
Power	left	
	right	
Print	nodes	
	dest	
Printnl	nodes	
	dest	
Raise	expr1	
	expr2	
	expr3	
Return	value	
RightShift	left	

다음 페이지에 계속

표 1 – 이전 페이지에서 계속

Node type	Attribute	Value
	right	
Slice	expr	
	flags	
	lower	
	upper	
Sliceobj	nodes	list of statements
Stmt	nodes	
Sub	left	
	right	
Subscript	expr	
	flags	
	subs	
TryExcept	body	
	handlers	
	else_	
TryFinally	body	
	final	
Tuple	nodes	
UnaryAdd	expr	
UnarySub	expr	
While	<i>test</i>	
	body	
	else_	
With	expr	
	<i>vars</i>	
	body	
Yield	value	

33.3.2 Assignment nodes

There is a collection of nodes used to represent assignments. Each assignment statement in the source code becomes a single `Assign` node in the AST. The `nodes` attribute is a list that contains a node for each assignment target. This is necessary because assignment can be chained, e.g. `a = b = 2`. Each *Node* in the list will be one of the following classes: `AssAttr`, `AssList`, `AssName`, or `AssTuple`.

Each target assignment node will describe the kind of object being assigned to: `AssName` for a simple name, e.g. `a = 1`. `AssAttr` for an attribute assigned, e.g. `a.x = 1`. `AssList` and `AssTuple` for list and tuple expansion respectively, e.g. `a, b, c = a_tuple`.

The target assignment nodes also have a `flags` attribute that indicates whether the node is being used for assignment or in a delete statement. The `AssName` is also used to represent a delete statement, e.g. `del x`.

When an expression contains several attribute references, an assignment or delete statement will contain only one `AssAttr` node – for the final attribute reference. The other attribute references will be represented as `Getattr` nodes in the `expr` attribute of the `AssAttr` instance.

33.3.3 Examples

This section shows several simple examples of ASTs for Python source code. The examples demonstrate how to use the `parse()` function, what the repr of an AST looks like, and how to access attributes of an AST node.

The first module defines a single function. Assume it is stored in `doublelib.py`.

```
"""This is an example module.

This is the docstring.
"""

def double(x):
    "Return twice the argument"
    return x * 2
```

In the interactive interpreter session below, I have reformatted the long AST reprs for readability. The AST reprs use unqualified class names. If you want to create an instance from a repr, you must import the class names from the `compiler.ast` module.

```
>>> import compiler
>>> mod = compiler.parseFile("doublelib.py")
>>> mod
Module('This is an example module.\n\nThis is the docstring.\n',
      Stmt([Function(None, 'double', ['x'], [], 0,
                    'Return twice the argument',
                    Stmt([Return(Mul((Name('x'), Const(2))))]))]))
>>> from compiler.ast import *
>>> Module('This is an example module.\n\nThis is the docstring.\n',
...      Stmt([Function(None, 'double', ['x'], [], 0,
...                    'Return twice the argument',
...                    Stmt([Return(Mul((Name('x'), Const(2))))]))]))
Module('This is an example module.\n\nThis is the docstring.\n',
      Stmt([Function(None, 'double', ['x'], [], 0,
                    'Return twice the argument',
                    Stmt([Return(Mul((Name('x'), Const(2))))]))]))
>>> mod.doc
'This is an example module.\n\nThis is the docstring.\n'
>>> for node in mod.node.nodes:
...     print node
...
Function(None, 'double', ['x'], [], 0, 'Return twice the argument',
      Stmt([Return(Mul((Name('x'), Const(2))))]))
>>> func = mod.node.nodes[0]
>>> func.code
Stmt([Return(Mul((Name('x'), Const(2))))])
```

33.4 Using Visitors to Walk ASTs

The visitor pattern is ... The `compiler` package uses a variant on the visitor pattern that takes advantage of Python's introspection features to eliminate the need for much of the visitor's infrastructure.

The classes being visited do not need to be programmed to accept visitors. The visitor need only define visit methods for classes it is specifically interested in; a default visit method can handle the rest.

XXX The magic `visit()` method for visitors.

```
compiler.visitor.walk(tree, visitor[, verbose])
```

class `compiler.visitor.ASTVisitor`

The `ASTVisitor` is responsible for walking over the tree in the correct order. A walk begins with a call to `preorder()`. For each node, it checks the `visitor` argument to `preorder()` for a method named `<visitNodeType,>` where `NodeType` is the name of the node's class, e.g. for a `While` node a `visitWhile()` would be called. If the method exists, it is called with the node as its first argument.

The visitor method for a particular node type can control how child nodes are visited during the walk. The `ASTVisitor` modifies the visitor argument by adding a visit method to the visitor; this method can be used to visit a particular child node. If no visitor is found for a particular node type, the `default()` method is called.

`ASTVisitor` objects have the following methods:

XXX describe extra arguments

```
default(node[, ...])
```

```
dispatch(node[, ...])
```

```
preorder(tree, visitor)
```

33.5 Bytecode Generation

The code generator is a visitor that emits bytecodes. Each visit method can call the `emit()` method to emit a new bytecode. The basic code generator is specialized for modules, classes, and functions. An assembler converts that emitted instructions to the low-level bytecode format. It handles things like generation of constant lists of code objects and calculation of jump offsets.

Miscellaneous Services

The modules described in this chapter provide miscellaneous services that are available in all Python versions. Here's an overview:

34.1 `formatter` — Generic output formatting

This module supports two interface definitions, each with multiple implementations. The *formatter* interface is used by the `HTMLParser` class of the `htmllib` module, and the *writer* interface is required by the `formatter` interface.

Formatter objects transform an abstract flow of formatting events into specific output events on writer objects. Formatters manage several stack structures to allow various properties of a writer object to be changed and restored; writers need not be able to handle relative changes nor any sort of «change back» operation. Specific writer properties which may be controlled via formatter objects are horizontal alignment, font, and left margin indentations. A mechanism is provided which supports providing arbitrary, non-exclusive style settings to a writer as well. Additional interfaces facilitate formatting events which are not reversible, such as paragraph separation.

Writer objects encapsulate device interfaces. Abstract devices, such as file formats, are supported as well as physical devices. The provided implementations all work with abstract devices. The interface makes available mechanisms for setting the properties which formatter objects manage and inserting data into the output.

34.1.1 The Formatter Interface

Interfaces to create formatters are dependent on the specific formatter class being instantiated. The interfaces described below are the required interfaces which all formatters must support once initialized.

One data element is defined at the module level:

`formatter.AS_IS`

Value which can be used in the font specification passed to the `push_font()` method described below, or as the new value to any other `push_property()` method. Pushing the `AS_IS` value allows the corresponding `pop_property()` method to be called without having to track whether the property was changed.

The following attributes are defined for formatter instance objects:

`formatter.writer`

The writer instance with which the formatter interacts.

`formatter.end_paragraph(blanklines)`

Close any open paragraphs and insert at least *blanklines* before the next paragraph.

`formatter.add_line_break()`

Add a hard line break if one does not already exist. This does not break the logical paragraph.

`formatter.add_hor_rule(*args, **kw)`

Insert a horizontal rule in the output. A hard break is inserted if there is data in the current paragraph, but the logical paragraph is not broken. The arguments and keywords are passed on to the writer's `send_line_break()` method.

`formatter.add_flow_data(data)`

Provide data which should be formatted with collapsed whitespace. Whitespace from preceding and successive calls to `add_flow_data()` is considered as well when the whitespace collapse is performed. The data which is passed to this method is expected to be word-wrapped by the output device. Note that any word-wrapping still must be performed by the writer object due to the need to rely on device and font information.

`formatter.add_literal_data(data)`

Provide data which should be passed to the writer unchanged. Whitespace, including newline and tab characters, are considered legal in the value of *data*.

`formatter.add_label_data(format, counter)`

Insert a label which should be placed to the left of the current left margin. This should be used for constructing bulleted or numbered lists. If the *format* value is a string, it is interpreted as a format specification for *counter*, which should be an integer. The result of this formatting becomes the value of the label; if *format* is not a string it is used as the label value directly. The label value is passed as the only argument to the writer's `send_label_data()` method. Interpretation of non-string label values is dependent on the associated writer.

Format specifications are strings which, in combination with a counter value, are used to compute label values. Each character in the format string is copied to the label value, with some characters recognized to indicate a transform on the counter value. Specifically, the character 'l' represents the counter value formatter as an Arabic number, the characters 'A' and 'a' represent alphabetic representations of the counter value in upper and lower case, respectively, and 'I' and 'i' represent the counter value in Roman numerals, in upper and lower case. Note that the alphabetic and roman transforms require that the counter value be greater than zero.

`formatter.flush_softspace()`

Send any pending whitespace buffered from a previous call to `add_flow_data()` to the associated writer object. This should be called before any direct manipulation of the writer object.

`formatter.push_alignment(align)`

Push a new alignment setting onto the alignment stack. This may be `AS_IS` if no change is desired. If the alignment value is changed from the previous setting, the writer's `new_alignment()` method is called with the *align* value.

`formatter.pop_alignment()`

Restore the previous alignment.

`formatter.push_font((size, italic, bold, teletype))`

Change some or all font properties of the writer object. Properties which are not set to `AS_IS` are set to the values passed in while others are maintained at their current settings. The writer's `new_font()` method is called with the fully resolved font specification.

`formatter.pop_font()`

Restore the previous font.

`formatter.push_margin(margin)`

Increase the number of left margin indentations by one, associating the logical tag *margin* with the new indentation.

The initial margin level is 0. Changed values of the logical tag must be true values; false values other than `AS_IS` are not sufficient to change the margin.

`formatter.pop_margin()`
Restore the previous margin.

`formatter.push_style(*styles)`
Push any number of arbitrary style specifications. All styles are pushed onto the styles stack in order. A tuple representing the entire stack, including `AS_IS` values, is passed to the writer's `new_styles()` method.

`formatter.pop_style([n=1])`
Pop the last *n* style specifications passed to `push_style()`. A tuple representing the revised stack, including `AS_IS` values, is passed to the writer's `new_styles()` method.

`formatter.set_spacing(spacing)`
Set the spacing style for the writer.

`formatter.assert_line_data([flag=1])`
Inform the formatter that data has been added to the current paragraph out-of-band. This should be used when the writer has been manipulated directly. The optional *flag* argument can be set to false if the writer manipulations produced a hard line break at the end of the output.

34.1.2 Formatter Implementations

Two implementations of formatter objects are provided by this module. Most applications may use one of these classes without modification or subclassing.

class `formatter.NullFormatter([writer])`
A formatter which does nothing. If *writer* is omitted, a `NullWriter` instance is created. No methods of the writer are called by `NullFormatter` instances. Implementations should inherit from this class if implementing a writer interface but don't need to inherit any implementation.

class `formatter.AbstractFormatter(writer)`
The standard formatter. This implementation has demonstrated wide applicability to many writers, and may be used directly in most circumstances. It has been used to implement a full-featured World Wide Web browser.

34.1.3 The Writer Interface

Interfaces to create writers are dependent on the specific writer class being instantiated. The interfaces described below are the required interfaces which all writers must support once initialized. Note that while most applications can use the `AbstractFormatter` class as a formatter, the writer must typically be provided by the application.

`writer.flush()`
Flush any buffered output or device control events.

`writer.new_alignment(alignment)`
Set the alignment style. The *align* value can be any object, but by convention is a string or None, where None indicates that the writer's «preferred» alignment should be used. Conventional *align* values are 'left', 'center', 'right', and 'justify'.

`writer.new_font(font)`
Set the font style. The value of *font* will be None, indicating that the device's default font should be used, or a tuple of the form (size, italic, bold, teletype). Size will be a string indicating the size of font that should be used; specific strings and their interpretation must be defined by the application. The *italic*, *bold*, and *teletype* values are Boolean values specifying which of those font attributes should be used.

`writer.new_margin (margin, level)`

Set the margin level to the integer *level* and the logical tag to *margin*. Interpretation of the logical tag is at the writer's discretion; the only restriction on the value of the logical tag is that it not be a false value for non-zero values of *level*.

`writer.new_spacing (spacing)`

Set the spacing style to *spacing*.

`writer.new_styles (styles)`

Set additional styles. The *styles* value is a tuple of arbitrary values; the value *AS_IS* should be ignored. The *styles* tuple may be interpreted either as a set or as a stack depending on the requirements of the application and writer implementation.

`writer.send_line_break ()`

Break the current line.

`writer.send_paragraph (blankline)`

Produce a paragraph separation of at least *blankline* blank lines, or the equivalent. The *blankline* value will be an integer. Note that the implementation will receive a call to `send_line_break()` before this call if a line break is needed; this method should not include ending the last line of the paragraph. It is only responsible for vertical spacing between paragraphs.

`writer.send_hor_rule (*args, **kw)`

Display a horizontal rule on the output device. The arguments to this method are entirely application- and writer-specific, and should be interpreted with care. The method implementation may assume that a line break has already been issued via `send_line_break()`.

`writer.send_flowling_data (data)`

Output character data which may be word-wrapped and re-flowed as needed. Within any sequence of calls to this method, the writer may assume that spans of multiple whitespace characters have been collapsed to single space characters.

`writer.send_literal_data (data)`

Output character data which has already been formatted for display. Generally, this should be interpreted to mean that line breaks indicated by newline characters should be preserved and no new line breaks should be introduced. The data may contain embedded newline and tab characters, unlike data provided to the `send_formatted_data()` interface.

`writer.send_label_data (data)`

Set *data* to the left of the current left margin, if possible. The value of *data* is not restricted; treatment of non-string values is entirely application- and writer-dependent. This method will only be called at the beginning of a line.

34.1.4 Writer Implementations

Three implementations of the writer object interface are provided as examples by this module. Most applications will need to derive new writer classes from the `NullWriter` class.

class `formatter.NullWriter`

A writer which only provides the interface definition; no actions are taken on any methods. This should be the base class for all writers which do not need to inherit any implementation methods.

class `formatter.AbstractWriter`

A writer which can be used in debugging formatters, but not much else. Each method simply announces itself by printing its name and arguments on standard output.

class `formatter.DumbWriter (file=None, maxcol=72)`

Simple writer class which writes output on the file object passed in as *file* or, if *file* is `None`, on standard output. The

output is simply word-wrapped to the number of columns specified by *maxcol*. This class is suitable for reflowing a sequence of paragraphs.

MS Windows Specific Services

This chapter describes modules that are only available on MS Windows platforms.

35.1 `msilib` — Read and write Microsoft Installer files

버전 2.5에 추가.

The `msilib` supports the creation of Microsoft Installer (`.msi`) files. Because these files often contain an embedded «cabinet» file (`.cab`), it also exposes an API to create CAB files. Support for reading `.cab` files is currently not implemented; read support for the `.msi` database is possible.

This package aims to provide complete access to all tables in an `.msi` file, therefore, it is a fairly low-level API. Two primary applications of this package are the `distutils` command `bdist_msi`, and the creation of Python installer package itself (although that currently uses a different version of `msilib`).

The package contents can be roughly split into four parts: low-level CAB routines, low-level MSI routines, higher-level MSI routines, and standard table structures.

`msilib.FCICreate` (*cabname*, *files*)

Create a new CAB file named *cabname*. *files* must be a list of tuples, each containing the name of the file on disk, and the name of the file inside the CAB file.

The files are added to the CAB file in the order they appear in the list. All files are added into a single CAB file, using the MSZIP compression algorithm.

Callbacks to Python for the various steps of MSI creation are currently not exposed.

`msilib.UuidCreate` ()

Return the string representation of a new unique identifier. This wraps the Windows API functions `UuidCreate` () and `UuidToString` ().

`msilib.OpenDatabase` (*path*, *persist*)

Return a new database object by calling `MsiOpenDatabase`. *path* is the file name of the MSI file; *persist* can be one of the constants `MSIDBOPEN_CREATEDIRECT`, `MSIDBOPEN_CREATE`, `MSIDBOPEN_DIRECT`, `MSIDBOPEN_READONLY`, or `MSIDBOPEN_TRANSACT`, and may include the

flag `MSIDBOPEN_PATCHFILE`. See the Microsoft documentation for the meaning of these flags; depending on the flags, an existing database is opened, or a new one created.

`msilib.CreateRecord(count)`

Return a new record object by calling `MSICreateRecord()`. *count* is the number of fields of the record.

`msilib.init_database(name, schema, ProductName, ProductCode, ProductVersion, Manufacturer)`

Create and return a new database *name*, initialize it with *schema*, and set the properties *ProductName*, *ProductCode*, *ProductVersion*, and *Manufacturer*.

schema must be a module object containing `tables` and `_Validation_records` attributes; typically, `msilib.schema` should be used.

The database will contain just the schema and the validation records when this function returns.

`msilib.add_data(database, table, records)`

Add all *records* to the table named *table* in *database*.

The *table* argument must be one of the predefined tables in the MSI schema, e.g. 'Feature', 'File', 'Component', 'Dialog', 'Control', etc.

records should be a list of tuples, each one containing all fields of a record according to the schema of the table. For optional fields, `None` can be passed.

Field values can be int or long numbers, strings, or instances of the `Binary` class.

class `msilib.Binary(filename)`

Represents entries in the Binary table; inserting such an object using `add_data()` reads the file named *filename* into the table.

`msilib.add_tables(database, module)`

Add all table content from *module* to *database*. *module* must contain an attribute `tables` listing all tables for which content should be added, and one attribute per table that has the actual content.

This is typically used to install the sequence tables.

`msilib.add_stream(database, name, path)`

Add the file *path* into the `_Stream` table of *database*, with the stream name *name*.

`msilib.gen_uuid()`

Return a new UUID, in the format that MSI typically requires (i.e. in curly braces, and with all hexdigits in upper-case).

더 보기:

[FCICreateFile](#) [UuidCreate](#) [UuidToString](#)

35.1.1 Database Objects

`Database.OpenView(sql)`

Return a view object, by calling `MSIDatabaseOpenView()`. *sql* is the SQL statement to execute.

`Database.Commit()`

Commit the changes pending in the current transaction, by calling `MSIDatabaseCommit()`.

`Database.GetSummaryInformation(count)`

Return a new summary information object, by calling `MsiGetSummaryInformation()`. *count* is the maximum number of updated values.

더 보기:

[MSIDatabaseOpenView](#) [MSIDatabaseCommit](#) [MsiGetSummaryInformation](#)

35.1.2 View Objects

`View.Execute(params)`

Execute the SQL query of the view, through `MsiViewExecute()`. If *params* is not `None`, it is a record describing actual values of the parameter tokens in the query.

`View.GetColumnInfo(kind)`

Return a record describing the columns of the view, through calling `MsiViewGetColumnInfo()`. *kind* can be either `MSICOLINFO_NAMES` or `MSICOLINFO_TYPES`.

`View.Fetch()`

Return a result record of the query, through calling `MsiViewFetch()`.

`View.Modify(kind, data)`

Modify the view, by calling `MsiViewModify()`. *kind* can be one of `MSIMODIFY_SEEK`, `MSIMODIFY_REFRESH`, `MSIMODIFY_INSERT`, `MSIMODIFY_UPDATE`, `MSIMODIFY_ASSIGN`, `MSIMODIFY_REPLACE`, `MSIMODIFY_MERGE`, `MSIMODIFY_DELETE`, `MSIMODIFY_INSERT_TEMPORARY`, `MSIMODIFY_VALIDATE`, `MSIMODIFY_VALIDATE_NEW`, `MSIMODIFY_VALIDATE_FIELD`, or `MSIMODIFY_VALIDATE_DELETE`.

data must be a record describing the new data.

`View.Close()`

Close the view, through `MsiViewClose()`.

더 보기:

`MsiViewExecute` `MsiViewGetColumnInfo` `MsiViewFetch` `MsiViewModify` `MsiViewClose`

35.1.3 Summary Information Objects

`SummaryInformation.GetProperty(field)`

Return a property of the summary, through `MsiSummaryInfoGetProperty()`. *field* is the name of the property, and can be one of the constants `PID_CODEPAGE`, `PID_TITLE`, `PID_SUBJECT`, `PID_AUTHOR`, `PID_KEYWORDS`, `PID_COMMENTS`, `PID_TEMPLATE`, `PID_LASTAUTHOR`, `PID_REVNUMBER`, `PID_LASTPRINTED`, `PID_CREATE_DTM`, `PID_LASTSAVE_DTM`, `PID_PAGECOUNT`, `PID_WORDCOUNT`, `PID_CHARCOUNT`, `PID_APPNAME`, or `PID_SECURITY`.

`SummaryInformation.GetPropertyCount()`

Return the number of summary properties, through `MsiSummaryInfoGetPropertyCount()`.

`SummaryInformation.SetProperty(field, value)`

Set a property through `MsiSummaryInfoSetProperty()`. *field* can have the same values as in `GetProperty()`, *value* is the new value of the property. Possible value types are integer and string.

`SummaryInformation.Persist()`

Write the modified properties to the summary information stream, using `MsiSummaryInfoPersist()`.

더 보기:

`MsiSummaryInfoGetProperty` `MsiSummaryInfoGetPropertyCount` `MsiSummaryInfoSetProperty` `MsiSummaryInfoPersist`

35.1.4 Record Objects

`Record.GetFieldCount()`

Return the number of fields of the record, through `MsiRecordGetFieldCount()`.

`Record.GetInteger(field)`

Return the value of *field* as an integer where possible. *field* must be an integer.

`Record.GetString(field)`

Return the value of *field* as a string where possible. *field* must be an integer.

`Record.SetString(field, value)`

Set *field* to *value* through `MsiRecordSetString()`. *field* must be an integer; *value* a string.

`Record.SetStream(field, value)`

Set *field* to the contents of the file named *value*, through `MsiRecordSetStream()`. *field* must be an integer; *value* a string.

`Record.SetInteger(field, value)`

Set *field* to *value* through `MsiRecordSetInteger()`. Both *field* and *value* must be an integer.

`Record.ClearData()`

Set all fields of the record to 0, through `MsiRecordClearData()`.

더 보기:

`MsiRecordGetFieldCount` `MsiRecordSetString` `MsiRecordSetStream` `MsiRecordSetInteger` `MsiRecordClear`

35.1.5 Errors

All wrappers around MSI functions raise `MSIError`; the string inside the exception will contain more detail.

35.1.6 CAB Objects

class `msilib.CAB(name)`

The class `CAB` represents a CAB file. During MSI construction, files will be added simultaneously to the `Files` table, and to a CAB file. Then, when all files have been added, the CAB file can be written, then added to the MSI file.

name is the name of the CAB file in the MSI file.

append (*full, file, logical*)

Add the file with the pathname *full* to the CAB file, under the name *logical*. If there is already a file named *logical*, a new file name is created.

Return the index of the file in the CAB file, and the new name of the file inside the CAB file.

commit (*database*)

Generate a CAB file, add it as a stream to the MSI file, put it into the `Media` table, and remove the generated file from the disk.

35.1.7 Directory Objects

class `msilib.Directory` (*database, cab, basedir, physical, logical, default* [, *componentflags*])

Create a new directory in the Directory table. There is a current component at each point in time for the directory, which is either explicitly created through `start_component()`, or implicitly when files are added for the first time. Files are added into the current component, and into the cab file. To create a directory, a base directory object needs to be specified (can be `None`), the path to the physical directory, and a logical directory name. *default* specifies the DefaultDir slot in the directory table. *componentflags* specifies the default flags that new components get.

start_component ([*component* [, *feature* [, *flags* [, *keyfile* [, *uuid*]]]]])

Add an entry to the Component table, and make this component the current component for this directory. If no component name is given, the directory name is used. If no *feature* is given, the current feature is used. If no *flags* are given, the directory's default flags are used. If no *keyfile* is given, the KeyPath is left null in the Component table.

add_file (*file* [, *src* [, *version* [, *language*]]])

Add a file to the current component of the directory, starting a new one if there is no current component. By default, the file name in the source and the file table will be identical. If the *src* file is specified, it is interpreted relative to the current directory. Optionally, a *version* and a *language* can be specified for the entry in the File table.

glob (*pattern* [, *exclude*])

Add a list of files to the current component as specified in the glob pattern. Individual files can be excluded in the *exclude* list.

remove_pyc ()

Remove `.pyc/.pyo` files on uninstall.

더 보기:

[Directory Table](#) [File Table](#) [Component Table](#) [FeatureComponents Table](#)

35.1.8 Features

class `msilib.Feature` (*database, id, title, desc, display* [, *level=1* [, *parent* [, *directory* [, *attributes=0*]]]])

Add a new record to the Feature table, using the values *id*, *parent.id*, *title*, *desc*, *display*, *level*, *directory*, and *attributes*. The resulting feature object can be passed to the `start_component()` method of `Directory`.

set_current ()

Make this feature the current feature of `msilib`. New components are automatically added to the default feature, unless a feature is explicitly specified.

더 보기:

[Feature Table](#)

35.1.9 GUI classes

msilib provides several classes that wrap the GUI tables in an MSI database. However, no standard user interface is provided; use *bdist_msi* to create MSI files with a user-interface for installing Python packages.

class *msilib.Control* (*dlg, name*)

Base class of the dialog controls. *dlg* is the dialog object the control belongs to, and *name* is the control's name.

event (*event, argument* [, *condition=1* [, *ordering*]])

Make an entry into the *ControlEvent* table for this control.

mapping (*event, attribute*)

Make an entry into the *EventMapping* table for this control.

condition (*action, condition*)

Make an entry into the *ControlCondition* table for this control.

class *msilib.RadioButtonGroup* (*dlg, name, property*)

Create a radio button control named *name*. *property* is the installer property that gets set when a radio button is selected.

add (*name, x, y, width, height, text* [, *value*])

Add a radio button named *name* to the group, at the coordinates *x, y, width, height*, and with the label *text*. If *value* is omitted, it defaults to *name*.

class *msilib.Dialog* (*db, name, x, y, w, h, attr, title, first, default, cancel*)

Return a new *Dialog* object. An entry in the *Dialog* table is made, with the specified coordinates, dialog attributes, title, name of the first, default, and cancel controls.

control (*name, type, x, y, width, height, attributes, property, text, control_next, help*)

Return a new *Control* object. An entry in the *Control* table is made with the specified parameters.

This is a generic method; for specific types, specialized methods are provided.

text (*name, x, y, width, height, attributes, text*)

Add and return a *Text* control.

bitmap (*name, x, y, width, height, text*)

Add and return a *Bitmap* control.

line (*name, x, y, width, height*)

Add and return a *Line* control.

pushbutton (*name, x, y, width, height, attributes, text, next_control*)

Add and return a *PushButton* control.

radiogroup (*name, x, y, width, height, attributes, property, text, next_control*)

Add and return a *RadioButtonGroup* control.

checkbox (*name, x, y, width, height, attributes, property, text, next_control*)

Add and return a *CheckBox* control.

더 보기:

[Dialog Table](#) [Control Table](#) [Control Types](#) [ControlCondition Table](#) [ControlEvent Table](#) [EventMapping Table](#) [RadioButton Table](#)

35.1.10 Precomputed tables

`msilib` provides a few subpackages that contain only schema and table definitions. Currently, these definitions are based on MSI version 2.0.

`msilib.schema`

This is the standard MSI schema for MSI 2.0, with the `tables` variable providing a list of table definitions, and `_Validation_records` providing the data for MSI validation.

`msilib.sequence`

This module contains table contents for the standard sequence tables: *AdminExecuteSequence*, *AdminUISequence*, *AdvtExecuteSequence*, *InstallExecuteSequence*, and *InstallUISequence*.

`msilib.text`

This module contains definitions for the `UIText` and `ActionText` tables, for the standard installer actions.

35.2 msvcrt — Useful routines from the MS VC++ runtime

These functions provide access to some useful capabilities on Windows platforms. Some higher-level modules use these functions to build the Windows implementations of their services. For example, the `getpass` module uses this in the implementation of the `getpass()` function.

Further documentation on these functions can be found in the Platform API documentation.

The module implements both the normal and wide char variants of the console I/O api. The normal API deals only with ASCII characters and is of limited use for internationalized applications. The wide char API should be used where ever possible.

35.2.1 File Operations

`msvcrt.locking` (*fd, mode, nbytes*)

Lock part of a file based on file descriptor *fd* from the C runtime. Raises `IOError` on failure. The locked region of the file extends from the current file position for *nbytes* bytes, and may continue beyond the end of the file. *mode* must be one of the `LK_*` constants listed below. Multiple regions in a file may be locked at the same time, but may not overlap. Adjacent regions are not merged; they must be unlocked individually.

`msvcrt.LK_LOCK`

`msvcrt.LK_RLCK`

Locks the specified bytes. If the bytes cannot be locked, the program immediately tries again after 1 second. If, after 10 attempts, the bytes cannot be locked, `IOError` is raised.

`msvcrt.LK_NBLCK`

`msvcrt.LK_NBRLCK`

Locks the specified bytes. If the bytes cannot be locked, `IOError` is raised.

`msvcrt.LK_UNLCK`

Unlocks the specified bytes, which must have been previously locked.

`msvcrt.setmode` (*fd, flags*)

Set the line-end translation mode for the file descriptor *fd*. To set it to text mode, *flags* should be `os.O_TEXT`; for binary, it should be `os.O_BINARY`.

`msvcrt.open_osfhandle` (*handle, flags*)

Create a C runtime file descriptor from the file handle *handle*. The *flags* parameter should be a bitwise OR of `os.O_APPEND`, `os.O_RDONLY`, and `os.O_TEXT`. The returned file descriptor may be used as a parameter to `os.fdopen()` to create a file object.

`msvcrt.get_osfhandle (fd)`

Return the file handle for the file descriptor *fd*. Raises *IOError* if *fd* is not recognized.

35.2.2 Console I/O

`msvcrt.kbhit ()`

Return true if a keypress is waiting to be read.

`msvcrt.getch ()`

Read a keypress and return the resulting character. Nothing is echoed to the console. This call will block if a keypress is not already available, but will not wait for `Enter` to be pressed. If the pressed key was a special function key, this will return `'\000'` or `'\xe0'`; the next call will return the keycode. The `Control-C` keypress cannot be read with this function.

`msvcrt.getwch ()`

Wide char variant of `getch ()`, returning a Unicode value.

버전 2.6에 추가.

`msvcrt.getche ()`

Similar to `getch ()`, but the keypress will be echoed if it represents a printable character.

`msvcrt.getwche ()`

Wide char variant of `getche ()`, returning a Unicode value.

버전 2.6에 추가.

`msvcrt.putch (char)`

Print the character *char* to the console without buffering.

`msvcrt.putwch (unicode_char)`

Wide char variant of `putch ()`, accepting a Unicode value.

버전 2.6에 추가.

`msvcrt.ungetch (char)`

Cause the character *char* to be 《pushed back》 into the console buffer; it will be the next character read by `getch ()` or `getche ()`.

`msvcrt.ungetwch (unicode_char)`

Wide char variant of `ungetch ()`, accepting a Unicode value.

버전 2.6에 추가.

35.2.3 Other Functions

`msvcrt.heapmin ()`

Force the `malloc ()` heap to clean itself up and return unused blocks to the operating system. On failure, this raises *IOError*.

35.3 _winreg — Windows registry access

참고: The `_winreg` module has been renamed to `winreg` in Python 3. The `2to3` tool will automatically adapt imports when converting your sources to Python 3.

버전 2.0에 추가.

These functions expose the Windows registry API to Python. Instead of using an integer as the registry handle, a *handle object* is used to ensure that the handles are closed correctly, even if the programmer neglects to explicitly close them.

This module offers the following functions:

`_winreg.CloseKey(hkey)`

Closes a previously opened registry key. The *hkey* argument specifies a previously opened key.

참고: If *hkey* is not closed using this method (or via *hkey.Close()*), it is closed when the *hkey* object is destroyed by Python.

`_winreg.ConnectRegistry(computer_name, key)`

Establishes a connection to a predefined registry handle on another computer, and returns a *handle object*.

computer_name is the name of the remote computer, of the form `r"\\computername"`. If `None`, the local computer is used.

key is the predefined handle to connect to.

The return value is the handle of the opened key. If the function fails, a `WindowsError` exception is raised.

`_winreg.CreateKey(key, sub_key)`

Creates or opens the specified key, returning a *handle object*.

key is an already open key, or one of the predefined `HKEY_* constants`.

sub_key is a string that names the key this method opens or creates.

If *key* is one of the predefined keys, *sub_key* may be `None`. In that case, the handle returned is the same key handle passed in to the function.

If the key already exists, this function opens the existing key.

The return value is the handle of the opened key. If the function fails, a `WindowsError` exception is raised.

`_winreg.CreateKeyEx(key, sub_key[, res[, sam]])`

Creates or opens the specified key, returning a *handle object*.

key is an already open key, or one of the predefined `HKEY_* constants`.

sub_key is a string that names the key this method opens or creates.

res is a reserved integer, and must be zero. The default is zero.

sam is an integer that specifies an access mask that describes the desired security access for the key. Default is `KEY_ALL_ACCESS`. See *Access Rights* for other allowed values.

If *key* is one of the predefined keys, *sub_key* may be `None`. In that case, the handle returned is the same key handle passed in to the function.

If the key already exists, this function opens the existing key.

The return value is the handle of the opened key. If the function fails, a `WindowsError` exception is raised.

버전 2.7에 추가.

`_winreg.DeleteKey(key, sub_key)`

Deletes the specified key.

key is an already open key, or any one of the predefined [HKEY_* constants](#).

sub_key is a string that must be a subkey of the key identified by the *key* parameter. This value must not be `None`, and the key may not have subkeys.

This method can not delete keys with subkeys.

If the method succeeds, the entire key, including all of its values, is removed. If the method fails, a [WindowsError](#) exception is raised.

`_winreg.DeleteKeyEx(key, sub_key[, sam[, res]])`

Deletes the specified key.

참고: The [DeleteKeyEx\(\)](#) function is implemented with the `RegDeleteKeyEx` Windows API function, which is specific to 64-bit versions of Windows. See the [RegDeleteKeyEx documentation](#).

key is an already open key, or any one of the predefined [HKEY_* constants](#).

sub_key is a string that must be a subkey of the key identified by the *key* parameter. This value must not be `None`, and the key may not have subkeys.

res is a reserved integer, and must be zero. The default is zero.

sam is an integer that specifies an access mask that describes the desired security access for the key. Default is [KEY_WOW64_64KEY](#). See [Access Rights](#) for other allowed values.

This method can not delete keys with subkeys.

If the method succeeds, the entire key, including all of its values, is removed. If the method fails, a [WindowsError](#) exception is raised.

On unsupported Windows versions, [NotImplementedError](#) is raised.

버전 2.7에 추가.

`_winreg.DeleteValue(key, value)`

Removes a named value from a registry key.

key is an already open key, or one of the predefined [HKEY_* constants](#).

value is a string that identifies the value to remove.

`_winreg.EnumKey(key, index)`

Enumerates subkeys of an open registry key, returning a string.

key is an already open key, or any one of the predefined [HKEY_* constants](#).

index is an integer that identifies the index of the key to retrieve.

The function retrieves the name of one subkey each time it is called. It is typically called repeatedly until a [WindowsError](#) exception is raised, indicating, no more values are available.

`_winreg.EnumValue(key, index)`

Enumerates values of an open registry key, returning a tuple.

key is an already open key, or any one of the predefined [HKEY_* constants](#).

index is an integer that identifies the index of the value to retrieve.

The function retrieves the name of one subkey each time it is called. It is typically called repeatedly, until a `WindowsError` exception is raised, indicating no more values.

The result is a tuple of 3 items:

Index	Meaning
0	A string that identifies the value name
1	An object that holds the value data, and whose type depends on the underlying registry type
2	An integer that identifies the type of the value data (see table in docs for <code>SetValueEx()</code>)

`_winreg.ExpandEnvironmentStrings(unicode)`

Expands environment variable placeholders `%NAME%` in unicode strings like `REG_EXPAND_SZ`:

```
>>> ExpandEnvironmentStrings(u"%windir%")
u"C:\\Windows"
```

버전 2.6에 추가.

`_winreg.FlushKey(key)`

Writes all the attributes of a key to the registry.

`key` is an already open key, or one of the predefined `HKEY_* constants`.

It is not necessary to call `FlushKey()` to change a key. Registry changes are flushed to disk by the registry using its lazy flusher. Registry changes are also flushed to disk at system shutdown. Unlike `CloseKey()`, the `FlushKey()` method returns only when all the data has been written to the registry. An application should only call `FlushKey()` if it requires absolute certainty that registry changes are on disk.

참고: If you don't know whether a `FlushKey()` call is required, it probably isn't.

`_winreg.LoadKey(key, sub_key, file_name)`

Creates a subkey under the specified key and stores registration information from a specified file into that subkey.

`key` is a handle returned by `ConnectRegistry()` or one of the constants `HKEY_USERS` or `HKEY_LOCAL_MACHINE`.

`sub_key` is a string that identifies the subkey to load.

`file_name` is the name of the file to load registry data from. This file must have been created with the `SaveKey()` function. Under the file allocation table (FAT) file system, the filename may not have an extension.

A call to `LoadKey()` fails if the calling process does not have the `SE_RESTORE_PRIVILEGE` privilege. Note that privileges are different from permissions – see the [RegLoadKey documentation](#) for more details.

If `key` is a handle returned by `ConnectRegistry()`, then the path specified in `file_name` is relative to the remote computer.

`_winreg.OpenKey(key, sub_key[, res[, sam]])`

Opens the specified key, returning a *handle object*.

`key` is an already open key, or any one of the predefined `HKEY_* constants`.

`sub_key` is a string that identifies the sub_key to open.

`res` is a reserved integer, and must be zero. The default is zero.

`sam` is an integer that specifies an access mask that describes the desired security access for the key. Default is `KEY_READ`. See [Access Rights](#) for other allowed values.

The result is a new handle to the specified key.

If the function fails, `WindowsError` is raised.

`_winreg.OpenKeyEx()`

The functionality of `OpenKeyEx()` is provided via `OpenKey()`, by the use of default arguments.

`_winreg.QueryInfoKey(key)`

Returns information about a key, as a tuple.

`key` is an already open key, or one of the predefined `HKEY_* constants`.

The result is a tuple of 3 items:

In-dex	Meaning
0	An integer giving the number of sub keys this key has.
1	An integer giving the number of values this key has.
2	A long integer giving when the key was last modified (if available) as 100's of nanoseconds since Jan 1, 1601.

`_winreg.QueryValue(key, sub_key)`

Retrieves the unnamed value for a key, as a string.

`key` is an already open key, or one of the predefined `HKEY_* constants`.

`sub_key` is a string that holds the name of the subkey with which the value is associated. If this parameter is `None` or empty, the function retrieves the value set by the `SetValue()` method for the key identified by `key`.

Values in the registry have name, type, and data components. This method retrieves the data for a key's first value that has a `NULL` name. But the underlying API call doesn't return the type, so always use `QueryValueEx()` if possible.

`_winreg.QueryValueEx(key, value_name)`

Retrieves the type and data for a specified value name associated with an open registry key.

`key` is an already open key, or one of the predefined `HKEY_* constants`.

`value_name` is a string indicating the value to query.

The result is a tuple of 2 items:

Index	Meaning
0	The value of the registry item.
1	An integer giving the registry type for this value (see table in docs for <code>SetValueEx()</code>)

`_winreg.SaveKey(key, file_name)`

Saves the specified key, and all its subkeys to the specified file.

`key` is an already open key, or one of the predefined `HKEY_* constants`.

`file_name` is the name of the file to save registry data to. This file cannot already exist. If this filename includes an extension, it cannot be used on file allocation table (FAT) file systems by the `LoadKey()` method.

If `key` represents a key on a remote computer, the path described by `file_name` is relative to the remote computer. The caller of this method must possess the `SeBackupPrivilege` security privilege. Note that privileges are different than permissions – see the [Conflicts Between User Rights and Permissions](#) documentation for more details.

This function passes `NULL` for `security_attributes` to the API.

`_winreg.SetValue(key, sub_key, type, value)`

Associates a value with a specified key.

key is an already open key, or one of the predefined *HKEY_* constants*.

sub_key is a string that names the subkey with which the value is associated.

type is an integer that specifies the type of the data. Currently this must be *REG_SZ*, meaning only strings are supported. Use the *SetValueEx()* function for support for other data types.

value is a string that specifies the new value.

If the key specified by the *sub_key* parameter does not exist, the *SetValue* function creates it.

Value lengths are limited by available memory. Long values (more than 2048 bytes) should be stored as files with the filenames stored in the configuration registry. This helps the registry perform efficiently.

The key identified by the *key* parameter must have been opened with *KEY_SET_VALUE* access.

`_winreg.SetValueEx(key, value_name, reserved, type, value)`

Stores data in the value field of an open registry key.

key is an already open key, or one of the predefined *HKEY_* constants*.

value_name is a string that names the subkey with which the value is associated.

type is an integer that specifies the type of the data. See *Value Types* for the available types.

reserved can be anything – zero is always passed to the API.

value is a string that specifies the new value.

This method can also set additional value and type information for the specified key. The key identified by the *key* parameter must have been opened with *KEY_SET_VALUE* access.

To open the key, use the *CreateKey()* or *OpenKey()* methods.

Value lengths are limited by available memory. Long values (more than 2048 bytes) should be stored as files with the filenames stored in the configuration registry. This helps the registry perform efficiently.

`_winreg.DisableReflectionKey(key)`

Disables registry reflection for 32-bit processes running on a 64-bit operating system.

key is an already open key, or one of the predefined *HKEY_* constants*.

Will generally raise *NotImplementedError* if executed on a 32-bit operating system.

If the key is not on the reflection list, the function succeeds but has no effect. Disabling reflection for a key does not affect reflection of any subkeys.

`_winreg.EnableReflectionKey(key)`

Restores registry reflection for the specified disabled key.

key is an already open key, or one of the predefined *HKEY_* constants*.

Will generally raise *NotImplementedError* if executed on a 32-bit operating system.

Restoring reflection for a key does not affect reflection of any subkeys.

`_winreg.QueryReflectionKey(key)`

Determines the reflection state for the specified key.

key is an already open key, or one of the predefined *HKEY_* constants*.

Returns *True* if reflection is disabled.

Will generally raise *NotImplementedError* if executed on a 32-bit operating system.

35.3.1 Constants

The following constants are defined for use in many `_winreg` functions.

HKEY_* Constants

`_winreg.HKEY_CLASSES_ROOT`

Registry entries subordinate to this key define types (or classes) of documents and the properties associated with those types. Shell and COM applications use the information stored under this key.

`_winreg.HKEY_CURRENT_USER`

Registry entries subordinate to this key define the preferences of the current user. These preferences include the settings of environment variables, data about program groups, colors, printers, network connections, and application preferences.

`_winreg.HKEY_LOCAL_MACHINE`

Registry entries subordinate to this key define the physical state of the computer, including data about the bus type, system memory, and installed hardware and software.

`_winreg.HKEY_USERS`

Registry entries subordinate to this key define the default user configuration for new users on the local computer and the user configuration for the current user.

`_winreg.HKEY_PERFORMANCE_DATA`

Registry entries subordinate to this key allow you to access performance data. The data is not actually stored in the registry; the registry functions cause the system to collect the data from its source.

`_winreg.HKEY_CURRENT_CONFIG`

Contains information about the current hardware profile of the local computer system.

`_winreg.HKEY_DYN_DATA`

This key is not used in versions of Windows after 98.

Access Rights

For more information, see [Registry Key Security and Access](#).

`_winreg.KEY_ALL_ACCESS`

Combines the `STANDARD_RIGHTS_REQUIRED`, `KEY_QUERY_VALUE`, `KEY_SET_VALUE`, `KEY_CREATE_SUB_KEY`, `KEY_ENUMERATE_SUB_KEYS`, `KEY_NOTIFY`, and `KEY_CREATE_LINK` access rights.

`_winreg.KEY_WRITE`

Combines the `STANDARD_RIGHTS_WRITE`, `KEY_SET_VALUE`, and `KEY_CREATE_SUB_KEY` access rights.

`_winreg.KEY_READ`

Combines the `STANDARD_RIGHTS_READ`, `KEY_QUERY_VALUE`, `KEY_ENUMERATE_SUB_KEYS`, and `KEY_NOTIFY` values.

`_winreg.KEY_EXECUTE`

Equivalent to `KEY_READ`.

`_winreg.KEY_QUERY_VALUE`

Required to query the values of a registry key.

`_winreg.KEY_SET_VALUE`

Required to create, delete, or set a registry value.

`_winreg.KEY_CREATE_SUB_KEY`

Required to create a subkey of a registry key.

`_winreg.KEY_ENUMERATE_SUB_KEYS`

Required to enumerate the subkeys of a registry key.

`_winreg.KEY_NOTIFY`

Required to request change notifications for a registry key or for subkeys of a registry key.

`_winreg.KEY_CREATE_LINK`

Reserved for system use.

64-bit Specific

For more information, see [Accessing an Alternate Registry View](#).

`_winreg.KEY_WOW64_64KEY`

Indicates that an application on 64-bit Windows should operate on the 64-bit registry view.

`_winreg.KEY_WOW64_32KEY`

Indicates that an application on 64-bit Windows should operate on the 32-bit registry view.

Value Types

For more information, see [Registry Value Types](#).

`_winreg.REG_BINARY`

Binary data in any form.

`_winreg.REG_DWORD`

32-bit number.

`_winreg.REG_DWORD_LITTLE_ENDIAN`

A 32-bit number in little-endian format.

`_winreg.REG_DWORD_BIG_ENDIAN`

A 32-bit number in big-endian format.

`_winreg.REG_EXPAND_SZ`

Null-terminated string containing references to environment variables (%PATH%).

`_winreg.REG_LINK`

A Unicode symbolic link.

`_winreg.REG_MULTI_SZ`

A sequence of null-terminated strings, terminated by two null characters. (Python handles this termination automatically.)

`_winreg.REG_NONE`

No defined value type.

`_winreg.REG_RESOURCE_LIST`

A device-driver resource list.

`_winreg.REG_FULL_RESOURCE_DESCRIPTOR`

A hardware setting.

`_winreg.REG_RESOURCE_REQUIREMENTS_LIST`

A hardware resource list.

`_winreg.REG_SZ`

A null-terminated string.

35.3.2 Registry Handle Objects

This object wraps a Windows HKEY object, automatically closing it when the object is destroyed. To guarantee cleanup, you can call either the `Close()` method on the object, or the `CloseKey()` function.

All registry functions in this module return one of these objects.

All registry functions in this module which accept a handle object also accept an integer, however, use of the handle object is encouraged.

Handle objects provide semantics for `__nonzero__()` – thus:

```
if handle:
    print "Yes"
```

will print `Yes` if the handle is currently valid (has not been closed or detached).

The object also support comparison semantics, so handle objects will compare true if they both reference the same underlying Windows handle value.

Handle objects can be converted to an integer (e.g., using the built-in `int()` function), in which case the underlying Windows handle value is returned. You can also use the `Detach()` method to return the integer handle, and also disconnect the Windows handle from the handle object.

`PyHKEY.Close()`

Closes the underlying Windows handle.

If the handle is already closed, no error is raised.

`PyHKEY.Detach()`

Detaches the Windows handle from the handle object.

The result is an integer (or long on 64 bit Windows) that holds the value of the handle before it is detached. If the handle is already detached or closed, this will return zero.

After calling this function, the handle is effectively invalidated, but the handle is not closed. You would call this function when you need the underlying Win32 handle to exist beyond the lifetime of the handle object.

`PyHKEY.__enter__()`

`PyHKEY.__exit__(*exc_info)`

The HKEY object implements `__enter__()` and `__exit__()` and thus supports the context protocol for the `with` statement:

```
with OpenKey(HKEY_LOCAL_MACHINE, "foo") as key:
    ... # work with key
```

will automatically close `key` when control leaves the `with` block.

버전 2.6에 추가.

35.4 winsound — Sound-playing interface for Windows

버전 1.5.2에 추가.

The `winsound` module provides access to the basic sound-playing machinery provided by Windows platforms. It includes functions and several constants.

`winsound.Beep` (*frequency*, *duration*)

Beep the PC's speaker. The *frequency* parameter specifies frequency, in hertz, of the sound, and must be in the range 37 through 32,767. The *duration* parameter specifies the number of milliseconds the sound should last. If the system is not able to beep the speaker, `RuntimeError` is raised.

버전 1.6에 추가.

`winsound.PlaySound` (*sound*, *flags*)

Call the underlying `PlaySound()` function from the Platform API. The *sound* parameter may be a filename, audio data as a string, or `None`. Its interpretation depends on the value of *flags*, which can be a bitwise ORed combination of the constants described below. If the *sound* parameter is `None`, any currently playing waveform sound is stopped. If the system indicates an error, `RuntimeError` is raised.

`winsound.MessageBeep` ([*type*=`MB_OK`])

Call the underlying `MessageBeep()` function from the Platform API. This plays a sound as specified in the registry. The *type* argument specifies which sound to play; possible values are `-1`, `MB_ICONASTERISK`, `MB_ICONEXCLAMATION`, `MB_ICONHAND`, `MB_ICONQUESTION`, and `MB_OK`, all described below. The value `-1` produces a «simple beep»; this is the final fallback if a sound cannot be played otherwise.

버전 2.3에 추가.

`winsound.SND_FILENAME`

The *sound* parameter is the name of a WAV file. Do not use with `SND_ALIAS`.

`winsound.SND_ALIAS`

The *sound* parameter is a sound association name from the registry. If the registry contains no such name, play the system default sound unless `SND_NODEFAULT` is also specified. If no default sound is registered, raise `RuntimeError`. Do not use with `SND_FILENAME`.

All Win32 systems support at least the following; most systems support many more:

<i>PlaySound()</i> name	Corresponding Control Panel Sound name
'SystemAsterisk'	Asterisk
'SystemExclamation'	Exclamation
'SystemExit'	Exit Windows
'SystemHand'	Critical Stop
'SystemQuestion'	Question

For example:

```
import winsound
# Play Windows exit sound.
winsound.PlaySound("SystemExit", winsound.SND_ALIAS)

# Probably play Windows default sound, if any is registered (because
# "" probably isn't the registered name of any sound).
winsound.PlaySound("", winsound.SND_ALIAS)
```

`winsound.SND_LOOP`

Play the sound repeatedly. The `SND_ASYNC` flag must also be used to avoid blocking. Cannot be used with `SND_MEMORY`.

`winsound.SND_MEMORY`

The *sound* parameter to `PlaySound()` is a memory image of a WAV file, as a string.

참고: This module does not support playing from a memory image asynchronously, so a combination of this flag and `SND_ASYNC` will raise *RuntimeError*.

`winsound.SND_PURGE`

Stop playing all instances of the specified sound.

참고: This flag is not supported on modern Windows platforms.

`winsound.SND_ASYNC`

Return immediately, allowing sounds to play asynchronously.

`winsound.SND_NODEFAULT`

If the specified sound cannot be found, do not play the system default sound.

`winsound.SND_NOSTOP`

Do not interrupt sounds currently playing.

`winsound.SND_NOWAIT`

Return immediately if the sound driver is busy.

참고: This flag is not supported on modern Windows platforms.

`winsound.MB_ICONASTERISK`

Play the `SystemDefault` sound.

`winsound.MB_ICONEXCLAMATION`

Play the `SystemExclamation` sound.

`winsound.MB_ICONHAND`

Play the `SystemHand` sound.

`winsound.MB_ICONQUESTION`

Play the `SystemQuestion` sound.

`winsound.MB_OK`

Play the `SystemDefault` sound.

Unix Specific Services

The modules described in this chapter provide interfaces to features that are unique to the Unix operating system, or in some cases to some or many variants of it. Here's an overview:

36.1 `posix` — The most common POSIX system calls

This module provides access to operating system functionality that is standardized by the C Standard and the POSIX standard (a thinly disguised Unix interface).

Do not import this module directly. Instead, import the module `os`, which provides a *portable* version of this interface. On Unix, the `os` module provides a superset of the `posix` interface. On non-Unix operating systems the `posix` module is not available, but a subset is always available through the `os` interface. Once `os` is imported, there is *no* performance penalty in using it instead of `posix`. In addition, `os` provides some additional functionality, such as automatically calling `putenv()` when an entry in `os.environ` is changed.

Errors are reported as exceptions; the usual exceptions are given for type errors, while errors reported by the system calls raise `OSError`.

36.1.1 Large File Support

Several operating systems (including AIX, HP-UX, Irix and Solaris) provide support for files that are larger than 2 GB from a C programming model where `int` and `long` are 32-bit values. This is typically accomplished by defining the relevant size and offset types as 64-bit values. Such files are sometimes referred to as *large files*.

Large file support is enabled in Python when the size of an `off_t` is larger than a `long` and the `long long` type is available and is at least as large as an `off_t`. Python longs are then used to represent file sizes, offsets and other values that can exceed the range of a Python `int`. It may be necessary to configure and compile Python with certain compiler flags to enable this mode. For example, it is enabled by default with recent versions of Irix, but with Solaris 2.6 and 2.7 you need to do something like:

```
CFLAGS="`getconf LFS_CFLAGS`" OPT="-g -O2 $CFLAGS" \  
./configure
```

On large-file-capable Linux systems, this might work:

```
CFLAGS='-D_LARGEFILE64_SOURCE -D_FILE_OFFSET_BITS=64' OPT="-g -O2 $CFLAGS" \  
./configure
```

36.1.2 Notable Module Contents

In addition to many functions described in the *os* module documentation, *posix* defines the following data item:

`posix.environ`

A dictionary representing the string environment at the time the interpreter was started. For example, `environ['HOME']` is the pathname of your home directory, equivalent to `getenv("HOME")` in C.

Modifying this dictionary does not affect the string environment passed on by *execv()*, *popen()* or *system()*; if you need to change the environment, pass `environ` to *execve()* or add variable assignments and export statements to the command string for *system()* or *popen()*.

참고: The *os* module provides an alternate implementation of `environ` which updates the environment on modification. Note also that updating `os.environ` will render this dictionary obsolete. Use of the *os* module version of this is recommended over direct access to the *posix* module.

36.2 pwd — The password database

This module provides access to the Unix user account and password database. It is available on all Unix versions.

Password database entries are reported as a tuple-like object, whose attributes correspond to the members of the `passwd` structure (Attribute field below, see `<pwd.h>`):

Index	Attribute	Meaning
0	<code>pw_name</code>	Login name
1	<code>pw_passwd</code>	Optional encrypted password
2	<code>pw_uid</code>	Numerical user ID
3	<code>pw_gid</code>	Numerical group ID
4	<code>pw_gecos</code>	User name or comment field
5	<code>pw_dir</code>	User home directory
6	<code>pw_shell</code>	User command interpreter

The `uid` and `gid` items are integers, all others are strings. *KeyError* is raised if the entry asked for cannot be found.

참고: In traditional Unix the field `pw_passwd` usually contains a password encrypted with a DES derived algorithm (see module *crypt*). However most modern unices use a so-called *shadow password* system. On those unices the `pw_passwd` field only contains an asterisk (`'*'`) or the letter `'x'` where the encrypted password is stored in a file `/etc/shadow` which is not world readable. Whether the `pw_passwd` field contains anything useful is system-dependent. If available, the *spwd* module should be used where access to the encrypted password is required.

It defines the following items:

`pwd.getpwuid(uid)`

Return the password database entry for the given numeric user ID.

`pwd.getpwnam(name)`

Return the password database entry for the given user name.

`pwd.getpwall()`

Return a list of all available password database entries, in arbitrary order.

더 보기:

Module `grp` An interface to the group database, similar to this.

Module `spwd` An interface to the shadow password database, similar to this.

36.3 spwd — The shadow password database

버전 2.5에 추가.

This module provides access to the Unix shadow password database. It is available on various Unix versions.

You must have enough privileges to access the shadow password database (this usually means you have to be root).

Shadow password database entries are reported as a tuple-like object, whose attributes correspond to the members of the `spwd` structure (Attribute field below, see `<shadow.h>`):

Index	Attribute	Meaning
0	<code>sp_nam</code>	Login name
1	<code>sp_pwd</code>	Encrypted password
2	<code>sp_lstchg</code>	Date of last change
3	<code>sp_min</code>	Minimal number of days between changes
4	<code>sp_max</code>	Maximum number of days between changes
5	<code>sp_warn</code>	Number of days before password expires to warn user about it
6	<code>sp_inact</code>	Number of days after password expires until account is blocked
7	<code>sp_expire</code>	Number of days since 1970-01-01 until account is disabled
8	<code>sp_flag</code>	Reserved

The `sp_nam` and `sp_pwd` items are strings, all others are integers. `KeyError` is raised if the entry asked for cannot be found.

It defines the following items:

`spwd.getspnam(name)`

Return the shadow password database entry for the given user name.

`spwd.getspall()`

Return a list of all available shadow password database entries, in arbitrary order.

더 보기:

Module `grp` An interface to the group database, similar to this.

Module `pwd` An interface to the normal password database, similar to this.

36.4 grp — The group database

This module provides access to the Unix group database. It is available on all Unix versions.

Group database entries are reported as a tuple-like object, whose attributes correspond to the members of the `group` structure (Attribute field below, see `<pwd.h>`):

Index	Attribute	Meaning
0	<code>gr_name</code>	the name of the group
1	<code>gr_passwd</code>	the (encrypted) group password; often empty
2	<code>gr_gid</code>	the numerical group ID
3	<code>gr_mem</code>	all the group member's user names

The `gid` is an integer, name and password are strings, and the member list is a list of strings. (Note that most users are not explicitly listed as members of the group they are in according to the password database. Check both databases to get complete membership information. Also note that a `gr_name` that starts with a `+` or `-` is likely to be a YP/NIS reference and may not be accessible via `getgrnam()` or `getgrgid()`.)

It defines the following items:

`grp.getgrgid(gid)`

Return the group database entry for the given numeric group ID. `KeyError` is raised if the entry asked for cannot be found.

`grp.getgrnam(name)`

Return the group database entry for the given group name. `KeyError` is raised if the entry asked for cannot be found.

`grp.getgrall()`

Return a list of all available group entries, in arbitrary order.

더 보기:

Module `pwd` An interface to the user database, similar to this.

Module `spwd` An interface to the shadow password database, similar to this.

36.5 crypt — Function to check Unix passwords

This module implements an interface to the `crypt(3)` routine, which is a one-way hash function based upon a modified DES algorithm; see the Unix man page for further details. Possible uses include allowing Python scripts to accept typed passwords from the user, or attempting to crack Unix passwords with a dictionary.

Notice that the behavior of this module depends on the actual implementation of the `crypt(3)` routine in the running system. Therefore, any extensions available on the current implementation will also be available on this module.

`crypt.crypt(word, salt)`

`word` will usually be a user's password as typed at a prompt or in a graphical interface. `salt` is usually a random two-character string which will be used to perturb the DES algorithm in one of 4096 ways. The characters in `salt` must be in the set `[./a-zA-Z0-9]`. Returns the hashed password as a string, which will be composed of characters from the same alphabet as the salt (the first two characters represent the salt itself).

Since a few `crypt(3)` extensions allow different values, with different sizes in the `salt`, it is recommended to use the full crypt password as salt when checking for a password.

A simple example illustrating typical use:


```
import crypt, getpass, pwd

def login():
    username = raw_input('Python login:')
    cryptpasswd = pwd.getpwnam(username)[1]
    if cryptpasswd:
        if cryptpasswd == 'x' or cryptpasswd == '*':
            raise NotImplementedError(
                "Sorry, currently no support for shadow passwords")
        cleartext = getpass.getpass()
        return crypt.crypt(cleartext, cryptpasswd) == cryptpasswd
    else:
        return 1
```

36.6 dl — Call C functions in shared objects

버전 2.6부터 폐지: The `dl` module has been removed in Python 3. Use the `ctypes` module instead.

The `dl` module defines an interface to the `dlopen()` function, which is the most common interface on Unix platforms for handling dynamically linked libraries. It allows the program to call arbitrary functions in such a library.

경고: The `dl` module bypasses the Python type system and error handling. If used incorrectly it may cause segmentation faults, crashes or other incorrect behaviour.

참고: This module will not work unless `sizeof(int) == sizeof(long) == sizeof(char *)`. If this is not the case, `SystemError` will be raised on import.

The `dl` module defines the following function:

`dl.open(name[, mode=RTLD_LAZY])`

Open a shared object file, and return a handle. Mode signifies late binding (`RTLD_LAZY`) or immediate binding (`RTLD_NOW`). Default is `RTLD_LAZY`. Note that some systems do not support `RTLD_NOW`.

Return value is a `dlobj`ect.

The `dl` module defines the following constants:

`dl.RTLD_LAZY`

Useful as an argument to `open()`.

`dl.RTLD_NOW`

Useful as an argument to `open()`. Note that on systems which do not support immediate binding, this constant will not appear in the module. For maximum portability, use `hasattr()` to determine if the system supports immediate binding.

The `dl` module defines the following exception:

exception `dl.error`

Exception raised when an error has occurred inside the dynamic loading and linking routines.

Example:

```
>>> import dl, time
>>> a=dl.open('/lib/libc.so.6')
>>> a.call('time'), time.time()
(929723914, 929723914.498)
```

This example was tried on a Debian GNU/Linux system, and is a good example of the fact that using this module is usually a bad alternative.

36.6.1 DL Objects

DL objects, as returned by `open()` above, have the following methods:

`dl.close()`

Free all resources, except the memory.

`dl.sym(name)`

Return the pointer for the function named *name*, as a number, if it exists in the referenced shared object, otherwise *None*. This is useful in code like:

```
>>> if a.sym('time'):
...     a.call('time')
... else:
...     time.time()
```

(Note that this function will return a non-zero number, as zero is the *NULL* pointer)

`dl.call(name[, arg1[, arg2...]])`

Call the function named *name* in the referenced shared object. The arguments must be either Python integers, which will be passed as is, Python strings, to which a pointer will be passed, or *None*, which will be passed as *NULL*. Note that strings should only be passed to functions as `const char*`, as Python will not like its string mutated.

There must be at most 10 arguments, and arguments not given will be treated as *None*. The function's return value must be a C long, which is a Python integer.

36.7 termios — POSIX style tty control

This module provides an interface to the POSIX calls for tty I/O control. For a complete description of these calls, see *termios(2)* Unix manual page. It is only available for those Unix versions that support POSIX *termios* style tty I/O control configured during installation.

All functions in this module take a file descriptor *fd* as their first argument. This can be an integer file descriptor, such as returned by `sys.stdin.fileno()`, or a file object, such as `sys.stdin` itself.

This module also defines all the constants needed to work with the functions provided here; these have the same name as their counterparts in C. Please refer to your system documentation for more information on using these terminal control interfaces.

The module defines the following functions:

`termios.tcgetattr(fd)`

Return a list containing the tty attributes for file descriptor *fd*, as follows: `[iflag, oflag, cflag, lflag, ispeed, ospeed, cc]` where *cc* is a list of the tty special characters (each a string of length 1, except the items with indices `VMIN` and `VTIME`, which are integers when these fields are defined). The interpretation of the flags and the speeds as well as the indexing in the *cc* array must be done using the symbolic constants defined in the *termios* module.

`termios.tcsetattr(fd, when, attributes)`

Set the tty attributes for file descriptor *fd* from the *attributes*, which is a list like the one returned by `tcgetattr()`. The *when* argument determines when the attributes are changed: TCSANOW to change immediately, TCSADRAIN to change after transmitting all queued output, or TCSAFLUSH to change after transmitting all queued output and discarding all queued input.

`termios.tcsendbreak(fd, duration)`

Send a break on file descriptor *fd*. A zero *duration* sends a break for 0.25 –0.5 seconds; a nonzero *duration* has a system dependent meaning.

`termios.tcdrain(fd)`

Wait until all output written to file descriptor *fd* has been transmitted.

`termios.tcflush(fd, queue)`

Discard queued data on file descriptor *fd*. The *queue* selector specifies which queue: TCIFLUSH for the input queue, TCOFLUSH for the output queue, or TCIOFLUSH for both queues.

`termios.tcflow(fd, action)`

Suspend or resume input or output on file descriptor *fd*. The *action* argument can be TCOOFF to suspend output, TCOON to restart output, TCIOFF to suspend input, or TCION to restart input.

더 보기:

Module `tty` Convenience functions for common terminal control operations.

36.7.1 Example

Here's a function that prompts for a password with echoing turned off. Note the technique using a separate `tcgetattr()` call and a `try ... finally` statement to ensure that the old tty attributes are restored exactly no matter what happens:

```
def getpass(prompt="Password: "):
    import termios, sys
    fd = sys.stdin.fileno()
    old = termios.tcgetattr(fd)
    new = termios.tcgetattr(fd)
    new[3] = new[3] & ~termios.ECHO          # lflags
    try:
        termios.tcsetattr(fd, termios.TCSADRAIN, new)
        passwd = raw_input(prompt)
    finally:
        termios.tcsetattr(fd, termios.TCSADRAIN, old)
    return passwd
```

36.8 `tty` — Terminal control functions

The `tty` module defines functions for putting the tty into cbreak and raw modes.

Because it requires the `termios` module, it will work only on Unix.

The `tty` module defines the following functions:

`tty.setraw(fd[, when])`

Change the mode of the file descriptor *fd* to raw. If *when* is omitted, it defaults to `termios.TCSAFLUSH`, and is passed to `termios.tcsetattr()`.

`tty.setcbreak(fd[, when])`

Change the mode of file descriptor *fd* to cbreak. If *when* is omitted, it defaults to `termios.TCSAFLUSH`, and is passed to `termios.tcsetattr()`.

더 보기:

Module `termios` Low-level terminal control interface.

36.9 pty — Pseudo-terminal utilities

The `pty` module defines operations for handling the pseudo-terminal concept: starting another process and being able to write to and read from its controlling terminal programmatically.

Because pseudo-terminal handling is highly platform dependent, there is code to do it only for Linux. (The Linux code is supposed to work on other platforms, but hasn't been tested yet.)

The `pty` module defines the following functions:

`pty.fork()`

Fork. Connect the child's controlling terminal to a pseudo-terminal. Return value is (*pid*, *fd*). Note that the child gets *pid* 0, and the *fd* is *invalid*. The parent's return value is the *pid* of the child, and *fd* is a file descriptor connected to the child's controlling terminal (and also to the child's standard input and output).

`pty.openpty()`

Open a new pseudo-terminal pair, using `os.openpty()` if possible, or emulation code for generic Unix systems. Return a pair of file descriptors (*master*, *slave*), for the master and the slave end, respectively.

`pty.spawn(argv[, master_read[, stdin_read]])`

Spawn a process, and connect its controlling terminal with the current process's standard io. This is often used to baffle programs which insist on reading from the controlling terminal.

The functions *master_read* and *stdin_read* should be functions which read from a file descriptor. The defaults try to read 1024 bytes each time they are called.

36.10 fcntl — The fcntl and ioctl system calls

This module performs file control and I/O control on file descriptors. It is an interface to the `fcntl()` and `ioctl()` Unix routines. For a complete description of these calls, see `fcntl(2)` and `ioctl(2)` Unix manual pages.

All functions in this module take a file descriptor *fd* as their first argument. This can be an integer file descriptor, such as returned by `sys.stdin.fileno()`, or a file object, such as `sys.stdin` itself, which provides a `fileno()` which returns a genuine file descriptor.

The module defines the following functions:

`fcntl.fcntl(fd, op[, arg])`

Perform the operation *op* on file descriptor *fd* (file objects providing a `fileno()` method are accepted as well). The values used for *op* are operating system dependent, and are available as constants in the `fcntl` module, using the same names as used in the relevant C header files. The argument *arg* is optional, and defaults to the integer value 0. When present, it can either be an integer value, or a string. With the argument missing or an integer value, the return value of this function is the integer return value of the C `fcntl()` call. When the argument is a string it represents a binary structure, e.g. created by `struct.pack()`. The binary data is copied to a buffer whose address is passed to the C `fcntl()` call. The return value after a successful call is the contents of the buffer, converted to a string object. The length of the returned string will be the same as the length of the *arg* argument. This is limited to 1024 bytes. If the information returned in the buffer by the operating system is larger than 1024 bytes, this is most likely to result in a segmentation violation or a more subtle data corruption.

If the `fcntl()` fails, an `IOError` is raised.

`fcntl.ioctl(fd, op[, arg[, mutate_flag]])`

This function is identical to the `fcntl()` function, except that the operations are typically defined in the library module `termios` and the argument handling is even more complicated.

The `op` parameter is limited to values that can fit in 32-bits. Additional constants of interest for use as the `op` argument can be found in the `termios` module, under the same names as used in the relevant C header files.

The parameter `arg` can be one of an integer, absent (treated identically to the integer 0), an object supporting the read-only buffer interface (most likely a plain Python string) or an object supporting the read-write buffer interface.

In all but the last case, behaviour is as for the `fcntl()` function.

If a mutable buffer is passed, then the behaviour is determined by the value of the `mutate_flag` parameter.

If it is false, the buffer's mutability is ignored and behaviour is as for a read-only buffer, except that the 1024 byte limit mentioned above is avoided – so long as the buffer you pass is at least as long as what the operating system wants to put there, things should work.

If `mutate_flag` is true, then the buffer is (in effect) passed to the underlying `ioctl()` system call, the latter's return code is passed back to the calling Python, and the buffer's new contents reflect the action of the `ioctl()`. This is a slight simplification, because if the supplied buffer is less than 1024 bytes long it is first copied into a static buffer 1024 bytes long which is then passed to `ioctl()` and copied back into the supplied buffer.

If `mutate_flag` is not supplied, then from Python 2.5 it defaults to true, which is a change from versions 2.3 and 2.4. Supply the argument explicitly if version portability is a priority.

If the `ioctl()` fails, an `IOError` exception is raised.

An example:

```
>>> import array, fcntl, struct, termios, os
>>> os.getpgrp()
13341
>>> struct.unpack('h', fcntl.ioctl(0, termios.TIOCGPGRP, "  ")[0])
13341
>>> buf = array.array('h', [0])
>>> fcntl.ioctl(0, termios.TIOCGPGRP, buf, 1)
0
>>> buf
array('h', [13341])
```

`fcntl.flock(fd, op)`

Perform the lock operation `op` on file descriptor `fd` (file objects providing a `fileno()` method are accepted as well). See the Unix manual `flock(2)` for details. (On some systems, this function is emulated using `fcntl()`.)

If the `flock()` fails, an `IOError` exception is raised.

`fcntl.lockf(fd, operation[, length[, start[, whence]]])`

This is essentially a wrapper around the `fcntl()` locking calls. `fd` is the file descriptor of the file to lock or unlock, and `operation` is one of the following values:

- `LOCK_UN` – unlock
- `LOCK_SH` – acquire a shared lock
- `LOCK_EX` – acquire an exclusive lock

When `operation` is `LOCK_SH` or `LOCK_EX`, it can also be bitwise ORed with `LOCK_NB` to avoid blocking on lock acquisition. If `LOCK_NB` is used and the lock cannot be acquired, an `IOError` will be raised and the exception will have an `errno` attribute set to `EACCES` or `EAGAIN` (depending on the operating system; for portability, check

for both values). On at least some systems, `LOCK_EX` can only be used if the file descriptor refers to a file opened for writing.

length is the number of bytes to lock, *start* is the byte offset at which the lock starts, relative to *whence*, and *whence* is as with `io.IOBase.seek()`, specifically:

- 0 – relative to the start of the file (`os.SEEK_SET`)
- 1 – relative to the current buffer position (`os.SEEK_CUR`)
- 2 – relative to the end of the file (`os.SEEK_END`)

The default for *start* is 0, which means to start at the beginning of the file. The default for *length* is 0 which means to lock to the end of the file. The default for *whence* is also 0.

Examples (all on a SVR4 compliant system):

```
import struct, fcntl, os

f = open(...)
rv = fcntl.fcntl(f, fcntl.F_SETFL, os.O_NDELAY)

lockdata = struct.pack('hhllhh', fcntl.F_WRLCK, 0, 0, 0, 0, 0)
rv = fcntl.fcntl(f, fcntl.F_SETLKW, lockdata)
```

Note that in the first example the return value variable *rv* will hold an integer value; in the second example it will hold a string value. The structure lay-out for the *lockdata* variable is system dependent — therefore using the `flock()` call may be better.

더 보기:

Module `os` If the locking flags `O_SHLOCK` and `O_EXLOCK` are present in the `os` module (on BSD only), the `os.open()` function provides an alternative to the `lockf()` and `flock()` functions.

36.11 pipes — Interface to shell pipelines

Source code: [Lib/pipes.py](#)

The `pipes` module defines a class to abstract the concept of a *pipeline* — a sequence of converters from one file to another.

Because the module uses `/bin/sh` command lines, a POSIX or compatible shell for `os.system()` and `os.popen()` is required.

class `pipes.Template`
An abstraction of a pipeline.

Example:

```
>>> import pipes
>>> t = pipes.Template()
>>> t.append('tr a-z A-Z', '--')
>>> f = t.open('pipefile', 'w')
>>> f.write('hello world')
>>> f.close()
>>> open('pipefile').read()
'HELLO WORLD'
```

`pipes.quote(s)`

버전 2.7부터 폐지: Prior to Python 2.7, this function was not publicly documented. It is finally exposed publicly in Python 3.3 as the `quote` function in the `shlex` module.

Return a shell-escaped version of the string *s*. The returned value is a string that can safely be used as one token in a shell command line, for cases where you cannot use a list.

This idiom would be unsafe:

```
>>> filename = 'somefile; rm -rf ~'
>>> command = 'ls -l {}'.format(filename)
>>> print command # executed by a shell: boom!
ls -l somefile; rm -rf ~
```

`quote()` lets you plug the security hole:

```
>>> command = 'ls -l {}'.format(quote(filename))
>>> print command
ls -l 'somefile; rm -rf ~'
>>> remote_command = 'ssh home {}'.format(quote(command))
>>> print remote_command
ssh home 'ls -l \''somefile; rm -rf ~\''
```

The quoting is compatible with UNIX shells and with `shlex.split()`:

```
>>> remote_command = shlex.split(remote_command)
>>> remote_command
['ssh', 'home', 'ls -l 'somefile; rm -rf ~']
>>> command = shlex.split(remote_command[-1])
>>> command
['ls', '-l', 'somefile; rm -rf ~']
```

36.11.1 Template Objects

Template objects following methods:

`Template.reset()`

Restore a pipeline template to its initial state.

`Template.clone()`

Return a new, equivalent, pipeline template.

`Template.debug(flag)`

If *flag* is true, turn debugging on. Otherwise, turn debugging off. When debugging is on, commands to be executed are printed, and the shell is given `set -x` command to be more verbose.

`Template.append(cmd, kind)`

Append a new action at the end. The *cmd* variable must be a valid bourne shell command. The *kind* variable consists of two letters.

The first letter can be either of `'-'` (which means the command reads its standard input), `'f'` (which means the commands reads a given file on the command line) or `'.'` (which means the commands reads no input, and hence must be first.)

Similarly, the second letter can be either of `'-'` (which means the command writes to standard output), `'f'` (which means the command writes a file on the command line) or `'.'` (which means the command does not write anything, and hence must be last.)

Template.**prepend** (*cmd*, *kind*)

Add a new action at the beginning. See [append\(\)](#) for explanations of the arguments.

Template.**open** (*file*, *mode*)

Return a file-like object, open to *file*, but read from or written to by the pipeline. Note that only one of 'r', 'w' may be given.

Template.**copy** (*infile*, *outfile*)

Copy *infile* to *outfile* through the pipe.

36.12 posixfile — File-like objects with locking support

버전 1.5부터 폐지: The locking operation that this module provides is done better and more portably by the [fcntl.lockf\(\)](#) call.

This module implements some additional functionality over the built-in file objects. In particular, it implements file locking, control over the file flags, and an easy interface to duplicate the file object. The module defines a new file object, the `posixfile` object. It has all the standard file object methods and adds the methods described below. This module only works for certain flavors of Unix, since it uses [fcntl.fcntl\(\)](#) for file locking.

To instantiate a `posixfile` object, use the [posixfile.open\(\)](#) function. The resulting object looks and feels roughly the same as a standard file object.

The [posixfile](#) module defines the following constants:

`posixfile.SEEK_SET`

Offset is calculated from the start of the file.

`posixfile.SEEK_CUR`

Offset is calculated from the current position in the file.

`posixfile.SEEK_END`

Offset is calculated from the end of the file.

The [posixfile](#) module defines the following functions:

`posixfile.open` (*filename*[, *mode*[, *bufsize*]])

Create a new `posixfile` object with the given filename and mode. The *filename*, *mode* and *bufsize* arguments are interpreted the same way as by the built-in [open\(\)](#) function.

`posixfile.fileopen` (*fileobject*)

Create a new `posixfile` object with the given standard file object. The resulting object has the same filename and mode as the original file object.

The `posixfile` object defines the following additional methods:

`posixfile.lock` (*fmt*[, *len*[, *start*[, *whence*]]])

Lock the specified section of the file that the file object is referring to. The format is explained below in a table. The *len* argument specifies the length of the section that should be locked. The default is 0. *start* specifies the starting offset of the section, where the default is 0. The *whence* argument specifies where the offset is relative to. It accepts one of the constants `SEEK_SET`, `SEEK_CUR` or `SEEK_END`. The default is `SEEK_SET`. For more information about the arguments refer to the [fcntl\(2\)](#) manual page on your system.

`posixfile.flags` ([*flags*])

Set the specified flags for the file that the file object is referring to. The new flags are ORed with the old flags, unless specified otherwise. The format is explained below in a table. Without the *flags* argument a string indicating the current flags is returned (this is the same as the ? modifier). For more information about the flags refer to the [fcntl\(2\)](#) manual page on your system.

`posixfile.dup()`

Duplicate the file object and the underlying file pointer and file descriptor. The resulting object behaves as if it were newly opened.

`posixfile.dup2(fd)`

Duplicate the file object and the underlying file pointer and file descriptor. The new object will have the given file descriptor. Otherwise the resulting object behaves as if it were newly opened.

`posixfile.file()`

Return the standard file object that the `posixfile` object is based on. This is sometimes necessary for functions that insist on a standard file object.

All methods raise `IOError` when the request fails.

Format characters for the `lock()` method have the following meaning:

Format	Meaning
u	unlock the specified region
r	request a read lock for the specified section
w	request a write lock for the specified section

In addition the following modifiers can be added to the format:

Modifier	Meaning	Notes
	wait until the lock has been granted	
?	return the first lock conflicting with the requested lock, or <code>None</code> if there is no conflict.	(1)

Note:

- (1) The lock returned is in the format `(mode, len, start, whence, pid)` where *mode* is a character representing the type of lock (`<r>` or `<w>`). This modifier prevents a request from being granted; it is for query purposes only.

Format characters for the `flags()` method have the following meanings:

Format	Meaning
a	append only flag
c	close on exec flag
n	no delay flag (also called non-blocking flag)
s	synchronization flag

In addition the following modifiers can be added to the format:

Modifier	Meaning	Notes
!	turn the specified flags <code><off></code> , instead of the default <code><on></code>	(1)
=	replace the flags, instead of the default <code><OR></code> operation	(1)
?	return a string in which the characters represent the flags that are set.	(2)

Notes:

- (1) The `!` and `=` modifiers are mutually exclusive.
- (2) This string represents the flags after they may have been altered by the same call.

Examples:

```
import posixfile

file = posixfile.open('testfile', 'w')
file.lock('w|')
...
file.lock('u')
file.close()
```

36.13 resource — Resource usage information

This module provides basic mechanisms for measuring and controlling system resources utilized by a program.

Symbolic constants are used to specify particular system resources and to request usage information about either the current process or its children.

A single exception is defined for errors:

exception `resource.error`

The functions described below may raise this error if the underlying system call failures unexpectedly.

36.13.1 Resource Limits

Resources usage can be limited using the `setrlimit()` function described below. Each resource is controlled by a pair of limits: a soft limit and a hard limit. The soft limit is the current limit, and may be lowered or raised by a process over time. The soft limit can never exceed the hard limit. The hard limit can be lowered to any value greater than the soft limit, but not raised. (Only processes with the effective UID of the super-user can raise a hard limit.)

The specific resources that can be limited are system dependent. They are described in the `getrlimit(2)` man page. The resources listed below are supported when the underlying operating system supports them; resources which cannot be checked or controlled by the operating system are not defined in this module for those platforms.

`resource.RLIM_INFINITY`

Constant used to represent the limit for an unlimited resource.

`resource.getrlimit(resource)`

Returns a tuple (soft, hard) with the current soft and hard limits of *resource*. Raises `ValueError` if an invalid resource is specified, or `error` if the underlying system call fails unexpectedly.

`resource.setrlimit(resource, limits)`

Sets new limits of consumption of *resource*. The *limits* argument must be a tuple (soft, hard) of two integers describing the new limits. A value of `RLIM_INFINITY` can be used to request a limit that is unlimited.

Raises `ValueError` if an invalid resource is specified, if the new soft limit exceeds the hard limit, or if a process tries to raise its hard limit. Specifying a limit of `RLIM_INFINITY` when the hard or system limit for that resource is not unlimited will result in a `ValueError`. A process with the effective UID of super-user can request any valid limit value, including unlimited, but `ValueError` will still be raised if the requested limit exceeds the system imposed limit.

`setrlimit` may also raise `error` if the underlying system call fails.

These symbols define resources whose consumption can be controlled using the `setrlimit()` and `getrlimit()` functions described below. The values of these symbols are exactly the constants used by C programs.

The Unix man page for `getrlimit(2)` lists the available resources. Note that not all systems use the same symbol or same value to denote the same resource. This module does not attempt to mask platform differences — symbols not defined for a platform will not be available from this module on that platform.

resource.RLIMIT_CORE

The maximum size (in bytes) of a core file that the current process can create. This may result in the creation of a partial core file if a larger core would be required to contain the entire process image.

resource.RLIMIT_CPU

The maximum amount of processor time (in seconds) that a process can use. If this limit is exceeded, a SIGXCPU signal is sent to the process. (See the [signal](#) module documentation for information about how to catch this signal and do something useful, e.g. flush open files to disk.)

resource.RLIMIT_FSIZE

The maximum size of a file which the process may create.

resource.RLIMIT_DATA

The maximum size (in bytes) of the process's heap.

resource.RLIMIT_STACK

The maximum size (in bytes) of the call stack for the current process. This only affects the stack of the main thread in a multi-threaded process.

resource.RLIMIT_RSS

The maximum resident set size that should be made available to the process.

resource.RLIMIT_NPROC

The maximum number of processes the current process may create.

resource.RLIMIT_NOFILE

The maximum number of open file descriptors for the current process.

resource.RLIMIT_OFILE

The BSD name for [RLIMIT_NOFILE](#).

resource.RLIMIT_MEMLOCK

The maximum address space which may be locked in memory.

resource.RLIMIT_VMEM

The largest area of mapped memory which the process may occupy.

resource.RLIMIT_AS

The maximum area (in bytes) of address space which may be taken by the process.

36.13.2 Resource Usage

These functions are used to retrieve resource usage information:

resource.getrusage (*who*)

This function returns an object that describes the resources consumed by either the current process or its children, as specified by the *who* parameter. The *who* parameter should be specified using one of the `RUSAGE_*` constants described below.

The fields of the return value each describe how a particular system resource has been used, e.g. amount of time spent running in user mode or number of times the process was swapped out of main memory. Some values are dependent on the clock tick interval, e.g. the amount of memory the process is using.

For backward compatibility, the return value is also accessible as a tuple of 16 elements.

The fields `ru_utime` and `ru_stime` of the return value are floating point values representing the amount of time spent executing in user mode and the amount of time spent executing in system mode, respectively. The remaining values are integers. Consult the [getrusage\(2\)](#) man page for detailed information about these values. A brief summary is presented here:

Index	Field	Resource
0	ru_utime	time in user mode (float)
1	ru_stime	time in system mode (float)
2	ru_maxrss	maximum resident set size
3	ru_ixrss	shared memory size
4	ru_idrss	unshared memory size
5	ru_isrss	unshared stack size
6	ru_minflt	page faults not requiring I/O
7	ru_majflt	page faults requiring I/O
8	ru_nswap	number of swap outs
9	ru_inblock	block input operations
10	ru_oublock	block output operations
11	ru_msgsnd	messages sent
12	ru_msgrcv	messages received
13	ru_nsignals	signals received
14	ru_nvcsw	voluntary context switches
15	ru_nivcsw	involuntary context switches

This function will raise a `ValueError` if an invalid *who* parameter is specified. It may also raise `error` exception in unusual circumstances.

버전 2.3에서 변경: Added access to values as attributes of the returned object.

`resource.getpagesize()`

Returns the number of bytes in a system page. (This need not be the same as the hardware page size.)

The following `RUSAGE_*` symbols are passed to the `getrusage()` function to specify which processes information should be provided for.

`resource.RUSAGE_SELF`

`RUSAGE_SELF` should be used to request information pertaining only to the process itself.

`resource.RUSAGE_CHILDREN`

Pass to `getrusage()` to request resource information for child processes of the calling process.

`resource.RUSAGE_BOTH`

Pass to `getrusage()` to request resources consumed by both the current process and child processes. May not be available on all systems.

36.14 nis — Interface to Sun's NIS (Yellow Pages)

The `nis` module gives a thin wrapper around the NIS library, useful for central administration of several hosts.

Because NIS exists only on Unix systems, this module is only available for Unix.

The `nis` module defines the following functions:

`nis.match(key, mapname[, domain=default_domain])`

Return the match for *key* in map *mapname*, or raise an error (`nis.error`) if there is none. Both should be strings, *key* is 8-bit clean. Return value is an arbitrary array of bytes (may contain NULL and other joys).

Note that *mapname* is first checked if it is an alias to another name.

버전 2.5에서 변경: The *domain* argument allows overriding the NIS domain used for the lookup. If unspecified, lookup is in the default NIS domain.

`nis.cat (mapname[, domain=default_domain])`

Return a dictionary mapping *key* to *value* such that `match(key, mapname) == value`. Note that both keys and values of the dictionary are arbitrary arrays of bytes.

Note that *mapname* is first checked if it is an alias to another name.

버전 2.5에서 변경: The *domain* argument allows overriding the NIS domain used for the lookup. If unspecified, lookup is in the default NIS domain.

`nis.maps ([domain=default_domain])`

Return a list of all valid maps.

버전 2.5에서 변경: The *domain* argument allows overriding the NIS domain used for the lookup. If unspecified, lookup is in the default NIS domain.

`nis.get_default_domain ()`

Return the system default NIS domain.

버전 2.5에 추가.

The *nis* module defines the following exception:

exception `nis.error`

An error raised when a NIS function returns an error code.

36.15 syslog — Unix syslog library routines

This module provides an interface to the Unix *syslog* library routines. Refer to the Unix manual pages for a detailed description of the *syslog* facility.

This module wraps the system *syslog* family of routines. A pure Python library that can speak to a syslog server is available in the *logging.handlers* module as *SysLogHandler*.

The module defines the following functions:

`syslog.syslog (message)`

`syslog.syslog (priority, message)`

Send the string *message* to the system logger. A trailing newline is added if necessary. Each message is tagged with a priority composed of a *facility* and a *level*. The optional *priority* argument, which defaults to `LOG_INFO`, determines the message priority. If the facility is not encoded in *priority* using logical-or (`LOG_INFO | LOG_USER`), the value given in the *openlog()* call is used.

If *openlog()* has not been called prior to the call to *syslog()*, *openlog()* will be called with no arguments.

`syslog.openlog ([ident[, logoption[, facility]]])`

Logging options of subsequent *syslog()* calls can be set by calling *openlog()*. *syslog()* will call *openlog()* with no arguments if the log is not currently open.

The optional *ident* keyword argument is a string which is prepended to every message, and defaults to `sys.argv[0]` with leading path components stripped. The optional *logoption* keyword argument (default is 0) is a bit field – see below for possible values to combine. The optional *facility* keyword argument (default is `LOG_USER`) sets the default facility for messages which do not have a facility explicitly encoded.

`syslog.closelog ()`

Reset the syslog module values and call the system library *closelog()*.

This causes the module to behave as it does when initially imported. For example, *openlog()* will be called on the first *syslog()* call (if *openlog()* hasn't already been called), and *ident* and other *openlog()* parameters are reset to defaults.

`syslog.setlogmask(maskpri)`

Set the priority mask to *maskpri* and return the previous mask value. Calls to `syslog()` with a priority level not set in *maskpri* are ignored. The default is to log all priorities. The function `LOG_MASK(pri)` calculates the mask for the individual priority *pri*. The function `LOG_UPTO(pri)` calculates the mask for all priorities up to and including *pri*.

The module defines the following constants:

Priority levels (high to low): `LOG_EMERG`, `LOG_ALERT`, `LOG_CRIT`, `LOG_ERR`, `LOG_WARNING`, `LOG_NOTICE`, `LOG_INFO`, `LOG_DEBUG`.

Facilities: `LOG_KERN`, `LOG_USER`, `LOG_MAIL`, `LOG_DAEMON`, `LOG_AUTH`, `LOG_LPR`, `LOG_NEWS`, `LOG_UUCP`, `LOG_CRON`, `LOG_SYSLOG` and `LOG_LOCAL0` to `LOG_LOCAL7`.

Log options: `LOG_PID`, `LOG_CONS`, `LOG_NDELAY`, `LOG_NOWAIT` and `LOG_PERROR` if defined in `<syslog.h>`.

36.15.1 Examples

Simple example

A simple set of examples:

```
import syslog

syslog.syslog('Processing started')
if error:
    syslog.syslog(syslog.LOG_ERR, 'Processing started')
```

An example of setting some log options, these would include the process ID in logged messages, and write the messages to the destination facility used for mail logging:

```
syslog.openlog(logoption=syslog.LOG_PID, facility=syslog.LOG_MAIL)
syslog.syslog('E-mail processing initiated...')
```

36.16 commands — Utilities for running commands

버전 2.6부터 폐지: The `commands` module has been removed in Python 3. Use the `subprocess` module instead.

The `commands` module contains wrapper functions for `os.popen()` which take a system command as a string and return any output generated by the command and, optionally, the exit status.

The `subprocess` module provides more powerful facilities for spawning new processes and retrieving their results. Using the `subprocess` module is preferable to using the `commands` module.

참고: In Python 3.x, `getstatus()` and two undocumented functions (`mk2arg()` and `mkarg()`) have been removed. Also, `getstatusoutput()` and `getoutput()` have been moved to the `subprocess` module.

The `commands` module defines the following functions:

`commands.getstatusoutput(cmd)`

Execute the string *cmd* in a shell with `os.popen()` and return a 2-tuple (*status*, *output*). *cmd* is actually run as { *cmd* ; } 2>&1, so that the returned output will contain output or error messages. A trailing newline

is stripped from the output. The exit status for the command can be interpreted according to the rules for the C function `wait()`.

`commands.getoutput(cmd)`

Like `getstatusoutput()`, except the exit status is ignored and the return value is a string containing the command's output.

`commands.getstatus(file)`

Return the output of `ls -ld file` as a string. This function uses the `getoutput()` function, and properly escapes backslashes and dollar signs in the argument.

버전 2.6부터 폐지: This function is nonobvious and useless. The name is also misleading in the presence of `getstatusoutput()`.

Example:

```
>>> import commands
>>> commands.getstatusoutput('ls /bin/ls')
(0, '/bin/ls')
>>> commands.getstatusoutput('cat /bin/junk')
(256, 'cat: /bin/junk: No such file or directory')
>>> commands.getstatusoutput('/bin/junk')
(256, 'sh: /bin/junk: not found')
>>> commands.getoutput('ls /bin/ls')
'/bin/ls'
>>> commands.getstatus('/bin/ls')
'-rwxr-xr-x 1 root          13352 Oct 14  1994 /bin/ls'
```

더 보기:

Module `subprocess` Module for spawning and managing subprocesses.

Mac OS X specific services

This chapter describes modules that are only available on the Mac OS X platform.

See the chapters *MacPython OSA Modules* and *Undocumented Mac OS modules* for more modules, and the HOWTO using-on-mac for a general introduction to Mac-specific Python programming.

참고: Most of the OS X APIs that these modules use are deprecated or removed in recent versions of OS X. Many are not available when Python is executing in 64-bit mode. These modules have been removed in Python 3. You should avoid using them in Python 2.

37.1 `ic` — Access to the Mac OS X Internet Config

This module provides access to various internet-related preferences set through **System Preferences** or the **Finder**.

참고: This module has been removed in Python 3.x.

There is a low-level companion module `icglue` which provides the basic Internet Config access functionality. This low-level module is not documented, but the docstrings of the routines document the parameters and the routine names are the same as for the Pascal or C API to Internet Config, so the standard IC programmers' documentation can be used if this module is needed.

The `ic` module defines the `error` exception and symbolic names for all error codes Internet Config can produce; see the source for details.

exception `ic.error`

Exception raised on errors in the `ic` module.

The `ic` module defines the following class and function:

class `ic.IC` (*[signature*, *ic*])

Create an Internet Config object. The signature is a 4-character creator code of the current application (default 'Pyth') which may influence some of ICs settings. The optional *ic* argument is a low-level `icglue.icinstance` created beforehand, this may be useful if you want to get preferences from a different config file, etc.

`ic.launchurl` (*url* [, *hint*])

`ic.parseurl` (*data* [, *start* [, *end* [, *hint*]]])

`ic.mapfile` (*file*)

`ic.maptypescreator` (*type*, *creator* [, *filename*])

`ic.settypescreator` (*file*)

These functions are 《shortcuts》 to the methods of the same name, described below.

37.1.1 IC Objects

`IC` objects have a mapping interface, hence to obtain the mail address you simply get `ic['MailAddress']`. Assignment also works, and changes the option in the configuration file.

The module knows about various datatypes, and converts the internal IC representation to a 《logical》 Python data structure. Running the `ic` module standalone will run a test program that lists all keys and values in your IC database, this will have to serve as documentation.

If the module does not know how to represent the data it returns an instance of the `ICOpaqueData` type, with the raw data in its `data` attribute. Objects of this type are also acceptable values for assignment.

Besides the dictionary interface, `IC` objects have the following methods:

`IC.launchurl` (*url* [, *hint*])

Parse the given URL, launch the correct application and pass it the URL. The optional *hint* can be a scheme name such as 'mailto:', in which case incomplete URLs are completed with this scheme. If *hint* is not provided, incomplete URLs are invalid.

`IC.parseurl` (*data* [, *start* [, *end* [, *hint*]]])

Find a URL somewhere in *data* and return start position, end position and the URL. The optional *start* and *end* can be used to limit the search, so for instance if a user clicks in a long text field you can pass the whole text field and the click-position in *start* and this routine will return the whole URL in which the user clicked. As above, *hint* is an optional scheme used to complete incomplete URLs.

`IC.mapfile` (*file*)

Return the mapping entry for the given *file*, which can be passed as either a filename or an `FSSpec()` result, and which need not exist.

The mapping entry is returned as a tuple (*version*, *type*, *creator*, *postcreator*, *flags*, *extension*, *appname*, *postappname*, *mimetype*, *entryname*), where *version* is the entry version number, *type* is the 4-character filetype, *creator* is the 4-character creator type, *postcreator* is the 4-character creator code of an optional application to post-process the file after downloading, *flags* are various bits specifying whether to transfer in binary or ascii and such, *extension* is the filename extension for this file type, *appname* is the printable name of the application to which this file belongs, *postappname* is the name of the postprocessing application, *mimetype* is the MIME type of this file and *entryname* is the name of this entry.

`IC.maptypescreator` (*type*, *creator* [, *filename*])

Return the mapping entry for files with given 4-character *type* and *creator* codes. The optional *filename* may be specified to further help finding the correct entry (if the creator code is '????', for instance).

The mapping entry is returned in the same format as for *mapfile*.

`IC.settypescreator` (*file*)

Given an existing *file*, specified either as a filename or as an `FSSpec()` result, set its creator and type correctly

based on its extension. The finder is told about the change, so the finder icon will be updated quickly.

37.2 MacOS — Access to Mac OS interpreter features

This module provides access to MacOS specific functionality in the Python interpreter, such as how the interpreter event-loop functions and the like. Use with care.

참고: This module has been removed in Python 3.x.

Note the capitalization of the module name; this is a historical artifact.

`MacOS.runtimeModel`

Always 'macho', from Python 2.4 on. In earlier versions of Python the value could also be 'ppc' for the classic Mac OS 8 runtime model or 'carbon' for the Mac OS 9 runtime model.

`MacOS.linkModel`

The way the interpreter has been linked. As extension modules may be incompatible between linking models, packages could use this information to give more decent error messages. The value is one of 'static' for a statically linked Python, 'framework' for Python in a Mac OS X framework, 'shared' for Python in a standard Unix shared library. Older Pythons could also have the value 'cfm' for Mac OS 9-compatible Python.

exception `MacOS.Error`

This exception is raised on MacOS generated errors, either from functions in this module or from other mac-specific modules like the toolbox interfaces. The arguments are the integer error code (the `OSERR` value) and a textual description of the error code. Symbolic names for all known error codes are defined in the standard module `macerrors`.

`MacOS.GetErrorString(errno)`

Return the textual description of MacOS error code *errno*.

`MacOS.DebugStr(message[, object])`

On Mac OS X the string is simply printed to stderr (on older Mac OS systems more elaborate functionality was available), but it provides a convenient location to attach a breakpoint in a low-level debugger like **gdb**.

참고: Not available in 64-bit mode.

`MacOS.SysBeep()`

Ring the bell.

참고: Not available in 64-bit mode.

`MacOS.GetTicks()`

Get the number of clock ticks (1/60th of a second) since system boot.

`MacOS.GetCreatorAndType(file)`

Return the file creator and file type as two four-character strings. The *file* parameter can be a pathname or an `FSSpec` or `FSRef` object.

참고: It is not possible to use an `FSSpec` in 64-bit mode.

MacOS.**SetCreatorAndType** (*file*, *creator*, *type*)

Set the file creator and file type. The *file* parameter can be a pathname or an FSSpec or FSRef object. *creator* and *type* must be four character strings.

참고: It is not possible to use an FSSpec in 64-bit mode.

MacOS.**openrf** (*name*[, *mode*])

Open the resource fork of a file. Arguments are the same as for the built-in function `open()`. The object returned has file-like semantics, but it is not a Python file object, so there may be subtle differences.

MacOS.**WMAvailable** ()

Checks whether the current process has access to the window manager. The method will return `False` if the window manager is not available, for instance when running on Mac OS X Server or when logged in via ssh, or when the current interpreter is not running from a fullblown application bundle. A script runs from an application bundle either when it has been started with **pythonw** instead of **python** or when running as an applet.

MacOS.**splash** ([*resourceid*])

Opens a splash screen by resource id. Use resourceid 0 to close the splash screen.

참고: Not available in 64-bit mode.

37.3 macostools — Convenience routines for file manipulation

This module contains some convenience routines for file-manipulation on the Macintosh. All file parameters can be specified as pathnames, FSRef or FSSpec objects. This module expects a filesystem which supports forked files, so it should not be used on UFS partitions.

참고: This module has been removed in Python 3.

The `macostools` module defines the following functions:

`macostools.copy` (*src*, *dst*[, *createpath*[, *copytimes*]])

Copy file *src* to *dst*. If *createpath* is non-zero the folders leading to *dst* are created if necessary. The method copies data and resource fork and some finder information (creator, type, flags) and optionally the creation, modification and backup times (default is to copy them). Custom icons, comments and icon position are not copied.

참고: This function does not work in 64-bit code because it uses APIs that are not available in 64-bit mode.

`macostools.copytree` (*src*, *dst*)

Recursively copy a file tree from *src* to *dst*, creating folders as needed. *src* and *dst* should be specified as pathnames.

참고: This function does not work in 64-bit code because it uses APIs that are not available in 64-bit mode.

`macostools.mkalias` (*src*, *dst*)

Create a finder alias *dst* pointing to *src*.

참고: This function does not work in 64-bit code because it uses APIs that are not available in 64-bit mode.

`macostools.touched(dst)`

Tell the finder that some bits of finder-information such as creator or type for file *dst* has changed. The file can be specified by pathname or `fsspec`. This call should tell the finder to redraw the files icon.

버전 2.6부터 폐지: The function is a no-op on OS X.

`macostools.BUFSIZ`

The buffer size for `copy`, default 1 megabyte.

Note that the process of creating finder aliases is not specified in the Apple documentation. Hence, aliases created with `mkalias()` could conceivably have incompatible behaviour in some cases.

37.4 findertools — The finder’s Apple Events interface

This module contains routines that give Python programs access to some functionality provided by the finder. They are implemented as wrappers around the AppleEvent interface to the finder.

All file and folder parameters can be specified either as full pathnames, or as `FSRef` or `FSSpec` objects.

The `findertools` module defines the following functions:

`findertools.launch(file)`

Tell the finder to launch *file*. What launching means depends on the file: applications are started, folders are opened and documents are opened in the correct application.

`findertools.Print(file)`

Tell the finder to print a file. The behaviour is identical to selecting the file and using the print command in the finder’s file menu.

`findertools.copy(file, destdir)`

Tell the finder to copy a file or folder *file* to folder *destdir*. The function returns an `Alias` object pointing to the new file.

`findertools.move(file, destdir)`

Tell the finder to move a file or folder *file* to folder *destdir*. The function returns an `Alias` object pointing to the new file.

`findertools.sleep()`

Tell the finder to put the Macintosh to sleep, if your machine supports it.

`findertools.restart()`

Tell the finder to perform an orderly restart of the machine.

`findertools.shutdown()`

Tell the finder to perform an orderly shutdown of the machine.

37.5 EasyDialogs — Basic Macintosh dialogs

The `EasyDialogs` module contains some simple dialogs for the Macintosh. The dialogs get launched in a separate application which appears in the dock and must be clicked on for the dialogs be displayed. All routines take an optional resource ID parameter *id* with which one can override the `DLOG` resource used for the dialog, provided that the dialog items correspond (both type and item number) to those in the default `DLOG` resource. See source code for details.

참고: This module has been removed in Python 3.x.

The *EasyDialogs* module defines the following functions:

`EasyDialogs.Message(str[, id[, ok]])`

Displays a modal dialog with the message text *str*, which should be at most 255 characters long. The button text defaults to «OK», but is set to the string argument *ok* if the latter is supplied. Control is returned when the user clicks the «OK» button.

`EasyDialogs.AskString(prompt[, default[, id[, ok[, cancel]]]])`

Asks the user to input a string value via a modal dialog. *prompt* is the prompt message, and the optional *default* supplies the initial value for the string (otherwise "" is used). The text of the «OK» and «Cancel» buttons can be changed with the *ok* and *cancel* arguments. All strings can be at most 255 bytes long. *AskString()* returns the string entered or *None* in case the user cancelled.

`EasyDialogs.AskPassword(prompt[, default[, id[, ok[, cancel]]]])`

Asks the user to input a string value via a modal dialog. Like *AskString()*, but with the text shown as bullets. The arguments have the same meaning as for *AskString()*.

`EasyDialogs.AskYesNoCancel(question[, default[, yes[, no[, cancel[, id]]]])`

Presents a dialog with prompt *question* and three buttons labelled «Yes», «No», and «Cancel». Returns 1 for «Yes», 0 for «No» and -1 for «Cancel». The value of *default* (or 0 if *default* is not supplied) is returned when the RETURN key is pressed. The text of the buttons can be changed with the *yes*, *no*, and *cancel* arguments; to prevent a button from appearing, supply "" for the corresponding argument.

`EasyDialogs.ProgressBar([title[, maxval[, label[, id]]]])`

Displays a modeless progress-bar dialog. This is the constructor for the *ProgressBar* class described below. *title* is the text string displayed (default «Working...»), *maxval* is the value at which progress is complete (default 0, indicating that an indeterminate amount of work remains to be done), and *label* is the text that is displayed above the progress bar itself.

`EasyDialogs.GetArgv([optionlist[commandlist[, addoldfile[, addnewfile[, addfolder[, id]]]])`

Displays a dialog which aids the user in constructing a command-line argument list. Returns the list in `sys.argv` format, suitable for passing as an argument to `getopt.getopt()`. *addoldfile*, *addnewfile*, and *addfolder* are boolean arguments. When nonzero, they enable the user to insert into the command line paths to an existing file, a (possibly) not-yet-existent file, and a folder, respectively. (Note: Option arguments must appear in the command line before file and folder arguments in order to be recognized by `getopt.getopt()`.) Arguments containing spaces can be specified by enclosing them within single or double quotes. A *SystemExit* exception is raised if the user presses the «Cancel» button.

optionlist is a list that determines a popup menu from which the allowed options are selected. Its items can take one of two forms: *optstr* or (*optstr*, *descr*). When present, *descr* is a short descriptive string that is displayed in the dialog while this option is selected in the popup menu. The correspondence between *optstrs* and command-line arguments is:

<i>optstr</i> format	Command-line format
x	-x (short option)
x: or x=	-x (short option with value)
xyz	--xyz (long option)
xyz: or xyz=	--xyz (long option with value)

commandlist is a list of items of the form *cmdstr* or (*cmdstr*, *descr*), where *descr* is as above. The *cmdstrs* will appear in a popup menu. When chosen, the text of *cmdstr* will be appended to the command line as is, except that a trailing ':' or '=' (if present) will be trimmed off.

버전 2.0에 추가.

```
EasyDialogs.AskFileForOpen ([message] [, typeList] [, defaultLocation] [, defaultOptionFlags] [, location] [, clientName] [, windowTitle] [, actionButtonLabel] [, cancelButtonLabel] [, preferenceKey] [, popupExtension] [, eventProc] [, previewProc] [, filterProc] [, wanted] )
```

Post a dialog asking the user for a file to open, and return the file selected or *None* if the user cancelled. *message* is a text message to display, *typeList* is a list of 4-char filetypes allowable, *defaultLocation* is the pathname, FSSpec or FSRef of the folder to show initially, *location* is the (x, y) position on the screen where the dialog is shown, *actionButtonLabel* is a string to show instead of 《Open》 in the OK button, *cancelButtonLabel* is a string to show instead of 《Cancel》 in the cancel button, *wanted* is the type of value wanted as a return: *str*, *unicode*, FSSpec, FSRef and subtypes thereof are acceptable.

For a description of the other arguments please see the Apple Navigation Services documentation and the *EasyDialogs* source code.

```
EasyDialogs.AskFileForSave ([message] [, savedFileName] [, defaultLocation] [, defaultOptionFlags] [, location] [, clientName] [, windowTitle] [, actionButtonLabel] [, cancelButtonLabel] [, preferenceKey] [, popupExtension] [, fileType] [, fileCreator] [, eventProc] [, wanted] )
```

Post a dialog asking the user for a file to save to, and return the file selected or *None* if the user cancelled. *savedFileName* is the default for the file name to save to (the return value). See *AskFileForOpen()* for a description of the other arguments.

```
EasyDialogs.AskFolder ([message] [, defaultLocation] [, defaultOptionFlags] [, location] [, clientName] [, windowTitle] [, actionButtonLabel] [, cancelButtonLabel] [, preferenceKey] [, popupExtension] [, eventProc] [, filterProc] [, wanted] )
```

Post a dialog asking the user to select a folder, and return the folder selected or *None* if the user cancelled. See *AskFileForOpen()* for a description of the arguments.

더 보기:

Navigation Services Reference Programmer's reference documentation for the Navigation Services, a part of the Carbon framework.

37.5.1 ProgressBar Objects

ProgressBar objects provide support for modeless progress-bar dialogs. Both determinate (thermometer style) and indeterminate (barber-pole style) progress bars are supported. The bar will be determinate if its maximum value is greater than zero; otherwise it will be indeterminate.

버전 2.2에서 변경: Support for indeterminate-style progress bars was added.

The dialog is displayed immediately after creation. If the dialog's 《Cancel》 button is pressed, or if Cmd- . or ESC is typed, the dialog window is hidden and *KeyboardInterrupt* is raised (but note that this response does not occur until the progress bar is next updated, typically via a call to *inc()* or *set()*). Otherwise, the bar remains visible until the *ProgressBar* object is discarded.

ProgressBar objects possess the following attributes and methods:

ProgressBar.**curval**

The current value (of type integer or long integer) of the progress bar. The normal access methods coerce *curval* between 0 and *maxval*. This attribute should not be altered directly.

ProgressBar.**maxval**

The maximum value (of type integer or long integer) of the progress bar; the progress bar (thermometer style) is full when *curval* equals *maxval*. If *maxval* is 0, the bar will be indeterminate (barber-pole). This attribute should not be altered directly.

ProgressBar.**title** ([*newstr*])

Sets the text in the title bar of the progress dialog to *newstr*.

`ProgressBar.label([newstr])`

Sets the text in the progress box of the progress dialog to *newstr*.

`ProgressBar.set(value[, max])`

Sets the progress bar's *curval* to *value*, and also *maxval* to *max* if the latter is provided. *value* is first coerced between 0 and *maxval*. The thermometer bar is updated to reflect the changes, including a change from indeterminate to determinate or vice versa.

`ProgressBar.inc([n])`

Increments the progress bar's *curval* by *n*, or by 1 if *n* is not provided. (Note that *n* may be negative, in which case the effect is a decrement.) The progress bar is updated to reflect the change. If the bar is indeterminate, this causes one «spin» of the barber pole. The resulting *curval* is coerced between 0 and *maxval* if incrementing causes it to fall outside this range.

37.6 Framework — Interactive application framework

The *Framework* module contains classes that together provide a framework for an interactive Macintosh application. The programmer builds an application by creating subclasses that override various methods of the bases classes, thereby implementing the functionality wanted. Overriding functionality can often be done on various different levels, i.e. to handle clicks in a single dialog window in a non-standard way it is not necessary to override the complete event handling.

참고: This module has been removed in Python 3.x.

Work on the *Framework* has pretty much stopped, now that PyObjC is available for full Cocoa access from Python, and the documentation describes only the most important functionality, and not in the most logical manner at that. Examine the source or the examples for more details. The following are some comments posted on the MacPython newsgroup about the strengths and limitations of *Framework*:

The strong point of *Framework* is that it allows you to break into the control-flow at many different places. *W*, for instance, uses a different way to enable/disable menus and that plugs right in leaving the rest intact. The weak points of *Framework* are that it has no abstract command interface (but that shouldn't be difficult), that its dialog support is minimal and that its control/toolbar support is non-existent.

The *Framework* module defines the following functions:

`Framework.Application()`

An object representing the complete application. See below for a description of the methods. The default `__init__()` routine creates an empty window dictionary and a menu bar with an apple menu.

`Framework.MenuBar()`

An object representing the menubar. This object is usually not created by the user.

`Framework.Menu(bar, title[, after])`

An object representing a menu. Upon creation you pass the *MenuBar* the menu appears in, the *title* string and a position (1-based) *after* where the menu should appear (default: at the end).

`Framework.MenuItem(menu, title[, shortcut, callback])`

Create a menu item object. The arguments are the menu to create, the item title string and optionally the keyboard shortcut and a callback routine. The callback is called with the arguments menu-id, item number within menu (1-based), current front window and the event record.

Instead of a callable object the callback can also be a string. In this case menu selection causes the lookup of a method in the topmost window and the application. The method name is the callback string with 'domenu_' prepended.

Calling the `MenuBar.fixmenudimstate()` method sets the correct dimming for all menu items based on the current front window.

`FrameWork.Separator(menu)`

Add a separator to the end of a menu.

`FrameWork.SubMenu(menu, label)`

Create a submenu named *label* under menu *menu*. The menu object is returned.

`FrameWork.Window(parent)`

Creates a (modeless) window. *Parent* is the application object to which the window belongs. The window is not displayed until later.

`FrameWork.DialogWindow(parent)`

Creates a modeless dialog window.

`FrameWork.windowbounds(width, height)`

Return a (left, top, right, bottom) tuple suitable for creation of a window of given width and height. The window will be staggered with respect to previous windows, and an attempt is made to keep the whole window on-screen. However, the window will however always be the exact size given, so parts may be offscreen.

`FrameWork.setwatchcursor()`

Set the mouse cursor to a watch.

`FrameWork.setarrowcursor()`

Set the mouse cursor to an arrow.

37.6.1 Application Objects

Application objects have the following methods, among others:

`Application.makeusermenus()`

Override this method if you need menus in your application. Append the menus to the attribute `menubar`.

`Application.getabouttext()`

Override this method to return a text string describing your application. Alternatively, override the `do_about()` method for more elaborate 《about》 messages.

`Application.mainloop([mask[, wait]])`

This routine is the main event loop, call it to set your application rolling. *Mask* is the mask of events you want to handle, *wait* is the number of ticks you want to leave to other concurrent application (default 0, which is probably not a good idea). While raising *self* to exit the mainloop is still supported it is not recommended: call `self._quit()` instead.

The event loop is split into many small parts, each of which can be overridden. The default methods take care of dispatching events to windows and dialogs, handling drags and resizes, Apple Events, events for non-FrameWork windows, etc.

In general, all event handlers should return 1 if the event is fully handled and 0 otherwise (because the front window was not a FrameWork window, for instance). This is needed so that update events and such can be passed on to other windows like the Sioux console window. Calling `MacOS.HandleEvent()` is not allowed within *our_dispatch* or its callees, since this may result in an infinite loop if the code is called through the Python inner-loop event handler.

`Application.asyncevents(onoff)`

Call this method with a nonzero parameter to enable asynchronous event handling. This will tell the inner interpreter loop to call the application event handler *async_dispatch* whenever events are available. This will cause FrameWork window updates and the user interface to remain working during long computations, but will slow the interpreter down and may cause surprising results in non-reentrant code (such as FrameWork itself). By default *async_dispatch*

will immediately call *our_dispatch* but you may override this to handle only certain events asynchronously. Events you do not handle will be passed to *Sioux* and such.

The old on/off value is returned.

`Application._quit()`

Terminate the running *mainloop()* call at the next convenient moment.

`Application.do_char(c, event)`

The user typed character *c*. The complete details of the event can be found in the *event* structure. This method can also be provided in a *Window* object, which overrides the application-wide handler if the window is frontmost.

`Application.do_dialogevent(event)`

Called early in the event loop to handle modeless dialog events. The default method simply dispatches the event to the relevant dialog (not through the *DialogWindow* object involved). Override if you need special handling of dialog events (keyboard shortcuts, etc).

`Application.idle(event)`

Called by the main event loop when no events are available. The null-event is passed (so you can look at mouse position, etc).

37.6.2 Window Objects

Window objects have the following methods, among others:

`Window.open()`

Override this method to open a window. Store the Mac OS window-id in *self.wid* and call the *do_postopen()* method to register the window with the parent application.

`Window.close()`

Override this method to do any special processing on window close. Call the *do_postclose()* method to cleanup the parent state.

`Window.do_postresize(width, height, macoswindowid)`

Called after the window is resized. Override if more needs to be done than calling *InvalidRect*.

`Window.do_contentclick(local, modifiers, event)`

The user clicked in the content part of a window. The arguments are the coordinates (window-relative), the key modifiers and the raw event.

`Window.do_update(macoswindowid, event)`

An update event for the window was received. Redraw the window.

`Window.do_activate(activate, event)`

The window was activated (*activate* == 1) or deactivated (*activate* == 0). Handle things like focus highlighting, etc.

37.6.3 ControlsWindow Object

ControlsWindow objects have the following methods besides those of *Window* objects:

`ControlsWindow.do_controlhit(window, control, pcode, event)`

Part *pcode* of control *control* was hit by the user. Tracking and such has already been taken care of.

37.6.4 ScrolledWindow Object

ScrolledWindow objects are ControlsWindow objects with the following extra methods:

`ScrolledWindow.scrollbars([wantx[, wanty]])`

Create (or destroy) horizontal and vertical scrollbars. The arguments specify which you want (default: both). The scrollbars always have minimum 0 and maximum 32767.

`ScrolledWindow.getscrollbarvalues()`

You must supply this method. It should return a tuple (*x*, *y*) giving the current position of the scrollbars (between 0 and 32767). You can return None for either to indicate the whole document is visible in that direction.

`ScrolledWindow.updatescrollbars()`

Call this method when the document has changed. It will call `getscrollbarvalues()` and update the scrollbars.

`ScrolledWindow.scrollbar_callback(which, what, value)`

Supplied by you and called after user interaction. *which* will be 'x' or 'y', *what* will be '-', '--', 'set', '++' or '+'. For 'set', *value* will contain the new scrollbar position.

`ScrolledWindow.scalebarvalues(absmin, absmax, curmin, curmax)`

Auxiliary method to help you calculate values to return from `getscrollbarvalues()`. You pass document minimum and maximum value and topmost (leftmost) and bottommost (rightmost) visible values and it returns the correct number or None.

`ScrolledWindow.do_activate(onoff, event)`

Takes care of dimming/highlighting scrollbars when a window becomes frontmost. If you override this method, call this one at the end of your method.

`ScrolledWindow.do_postresize(width, height, window)`

Moves scrollbars to the correct position. Call this method initially if you override it.

`ScrolledWindow.do_controlhit(window, control, pcode, event)`

Handles scrollbar interaction. If you override it call this method first, a nonzero return value indicates the hit was in the scrollbars and has been handled.

37.6.5 DialogWindow Objects

DialogWindow objects have the following methods besides those of Window objects:

`DialogWindow.open(resid)`

Create the dialog window, from the DLOG resource with id *resid*. The dialog object is stored in `self.wid`.

`DialogWindow.do_itemhit(item, event)`

Item number *item* was hit. You are responsible for redrawing toggle buttons, etc.

37.7 autoGIL — Global Interpreter Lock handling in event loops

The `autoGIL` module provides a function `installAutoGIL()` that automatically locks and unlocks Python's *Global Interpreter Lock* when running an event loop.

참고: This module has been removed in Python 3.x.

exception `autoGIL.AutoGILError`

Raised if the observer callback cannot be installed, for example because the current thread does not have a run loop.

`autoGIL.installAutoGIL()`

Install an observer callback in the event loop (CFRunLoop) for the current thread, that will lock and unlock the Global Interpreter Lock (GIL) at appropriate times, allowing other Python threads to run while the event loop is idle.

Availability: OSX 10.1 or later.

37.8 Mac OS Toolbox Modules

These are a set of modules that provide interfaces to various legacy Mac OS toolboxes. If applicable the module will define a number of Python objects for the various structures declared by the toolbox, and operations will be implemented as methods of the object. Other operations will be implemented as functions in the module. Not all operations possible in C will also be possible in Python (callbacks are often a problem), and parameters will occasionally be different in Python (input and output buffers, especially). All methods and functions have a `__doc__` string describing their arguments and return values, and for additional description you are referred to [Inside Macintosh](#) or similar works.

These modules all live in a package called `Carbon`. Despite that name they are not all part of the Carbon framework: CF is really in the CoreFoundation framework and Qt is in the QuickTime framework. The normal use pattern is

```
from Carbon import AE
```

참고: Most of the OS X APIs that these modules use are deprecated or removed in recent versions of OS X. Many are not available when Python is executing in 64-bit mode. The Carbon modules have been removed in Python 3. You should avoid using them in Python 2.

37.8.1 `Carbon.AE` — Apple Events

37.8.2 `Carbon.AH` — Apple Help

37.8.3 `Carbon.App` — Appearance Manager

37.8.4 `Carbon.Appearance` — Appearance Manager constants

37.8.5 `Carbon.CF` — Core Foundation

The `CFBase`, `CFArray`, `CFData`, `CFDictionary`, `CFString` and `CFURL` objects are supported, some only partially.

37.8.6 Carbon.CG — Core Graphics

37.8.7 Carbon.CarbonEvt — Carbon Event Manager

37.8.8 Carbon.CarbonEvents — Carbon Event Manager constants

37.8.9 Carbon.Cm — Component Manager

37.8.10 Carbon.Components — Component Manager constants

37.8.11 Carbon.ControlAccessor — Control Manager accssors

37.8.12 Carbon.Controls — Control Manager constants

37.8.13 Carbon.CoreFounation — CoreFounation constants

37.8.14 Carbon.CoreGraphics — CoreGraphics constants

37.8.15 Carbon.Ctl — Control Manager

37.8.16 Carbon.Dialogs — Dialog Manager constants

37.8.17 Carbon.Dlg — Dialog Manager

37.8.18 Carbon.Drag — Drag and Drop Manager

37.8.19 Carbon.Dragconst — Drag and Drop Manager constants

37.8.20 Carbon.Events — Event Manager constants

37.8.21 Carbon.Evt — Event Manager

37.8.22 Carbon.File — File Manager

37.8.23 Carbon.Files — File Manager constants

37.8.24 Carbon.Fm — Font Manager

37.8.25 Carbon.Folder — Folder Manager

37.8.26 Carbon.Folders — Folder Manager constants

37.8.27 Carbon.Fonts — Font Manager constants

37.8.28 Carbon.Help — Help Manager

37.8.29 Carbon.IBCarbon — Carbon InterfaceBuilder

37.8.30 Carbon.IBCarbonRuntime — Carbon InterfaceBuilder constants

37.8.31 Carbon.Icn — Carbon Icon Manager Chapter 37. Mac OS X specific services

37.8.32 Carbon.Icons — Carbon Icon Manager constants

The Scrap Manager supports the simplest form of cut & paste operations on the Macintosh. It can be use for both inter- and intra-application clipboard operations.

The `Scrap` module provides low-level access to the functions of the Scrap Manager. It contains the following functions:

`Carbon.Scrap.InfoScrap()`

Return current information about the scrap. The information is encoded as a tuple containing the fields (`size`, `handle`, `count`, `state`, `path`).

Field	Meaning
<i>size</i>	Size of the scrap in bytes.
<i>handle</i>	Resource object representing the scrap.
<i>count</i>	Serial number of the scrap contents.
<i>state</i>	Integer; positive if in memory, 0 if on disk, negative if uninitialized.
<i>path</i>	Filename of the scrap when stored on disk.

더 보기:

Scrap Manager Apple’s documentation for the Scrap Manager gives a lot of useful information about using the Scrap Manager in applications.

37.8.53 `Carbon.Snd` — Sound Manager

37.8.54 `Carbon.Sound` — Sound Manager constants

37.8.55 `Carbon.TE` — TextEdit

37.8.56 `Carbon.TextEdit` — TextEdit constants

37.8.57 `Carbon.Win` — Window Manager

37.8.58 `Carbon.Windows` — Window Manager constants

37.9 `ColorPicker` — Color selection dialog

The `ColorPicker` module provides access to the standard color picker dialog.

참고: This module has been removed in Python 3.x.

`ColorPicker.GetColor(prompt, rgb)`

Show a standard color selection dialog and allow the user to select a color. The user is given instruction by the *prompt* string, and the default color is set to *rgb*. *rgb* must be a tuple giving the red, green, and blue components of the color. `GetColor()` returns a tuple giving the user’s selected color and a flag indicating whether they accepted the selection of cancelled.

MacPython OSA Modules

This chapter describes the current implementation of the Open Scripting Architecture (OSA, also commonly referred to as AppleScript) for Python, allowing you to control scriptable applications from your Python program, and with a fairly pythonic interface. Development on this set of modules has stopped.

For a description of the various components of AppleScript and OSA, and to get an understanding of the architecture and terminology, you should read Apple's documentation. The 《Applescript Language Guide》 explains the conceptual model and the terminology, and documents the standard suite. The 《Open Scripting Architecture》 document explains how to use OSA from an application programmers point of view. In the Apple Help Viewer these books are located in the Developer Documentation, Core Technologies section.

As an example of scripting an application, the following piece of AppleScript will get the name of the frontmost **Finder** window and print it:

```
tell application "Finder"
    get name of window 1
end tell
```

In Python, the following code fragment will do the same:

```
import Finder

f = Finder.Finder()
print f.get(f.window(1).name)
```

As distributed the Python library includes packages that implement the standard suites, plus packages that interface to a small number of common applications.

To send AppleEvents to an application you must first create the Python package interfacing to the terminology of the application (what **Script Editor** calls the 《Dictionary》). This can be done from within the **PythonIDE** or by running the `gensuitemodule.py` module as a standalone program from the command line.

The generated output is a package with a number of modules, one for every suite used in the program plus an `__init__` module to glue it all together. The Python inheritance graph follows the AppleScript inheritance graph, so if a program's dictionary specifies that it includes support for the Standard Suite, but extends one or two verbs with extra arguments then

the output suite will contain a module `Standard_Suite` that imports and re-exports everything from `StdSuites`. `Standard_Suite` but overrides the methods that have extra functionality. The output of `gensuitemodule` is pretty readable, and contains the documentation that was in the original AppleScript dictionary in Python docstrings, so reading it is a good source of documentation.

The output package implements a main class with the same name as the package which contains all the AppleScript verbs as methods, with the direct object as the first argument and all optional parameters as keyword arguments. AppleScript classes are also implemented as Python classes, as are comparisons and all the other things.

The main Python class implementing the verbs also allows access to the properties and elements declared in the AppleScript class `«application»`. In the current release that is as far as the object orientation goes, so in the example above we need to use `f.get(f.window(1).name)` instead of the more Pythonic `f.window(1).name.get()`.

If an AppleScript identifier is not a Python identifier the name is mangled according to a small number of rules:

- spaces are replaced with underscores
- other non-alphanumeric characters are replaced with `_xx_` where `xx` is the hexadecimal character value
- any Python reserved word gets an underscore appended

Python also has support for creating scriptable applications in Python, but The following modules are relevant to MacPython AppleScript support:

38.1 gensuitemodule — Generate OSA stub packages

The `gensuitemodule` module creates a Python package implementing stub code for the AppleScript suites that are implemented by a specific application, according to its AppleScript dictionary.

It is usually invoked by the user through the **PythonIDE**, but it can also be run as a script from the command line (pass `--help` for help on the options) or imported from Python code. For an example of its use see `Mac/scripts/genallsuites.py` in a source distribution, which generates the stub packages that are included in the standard library.

It defines the following public functions:

`gensuitemodule.is_scriptable(application)`

Returns true if `application`, which should be passed as a pathname, appears to be scriptable. Take the return value with a grain of salt: **Internet Explorer** appears not to be scriptable but definitely is.

`gensuitemodule.processfile(application[, output, basepkgname, edit_modnames, creatorsignature, dump, verbose])`

Create a stub package for `application`, which should be passed as a full pathname. For a `.app` bundle this is the pathname to the bundle, not to the executable inside the bundle; for an unbundled CFM application you pass the filename of the application binary.

This function asks the application for its OSA terminology resources, decodes these resources and uses the resultant data to create the Python code for the package implementing the client stubs.

`output` is the pathname where the resulting package is stored, if not specified a standard `«save file as»` dialog is presented to the user. `basepkgname` is the base package on which this package will build, and defaults to `StdSuites`. Only when generating `StdSuites` itself do you need to specify this. `edit_modnames` is a dictionary that can be used to change modulenames that are too ugly after name mangling. `creator_signature` can be used to override the 4-char creator code, which is normally obtained from the `PkgInfo` file in the package or from the CFM file creator signature. When `dump` is given it should refer to a file object, and `processfile` will stop after decoding the resources and dump the Python representation of the terminology resources to this file. `verbose` should also be a file object, and specifying it will cause `processfile` to tell you what it is doing.

`gensuitemodule.processfile_fromresource` (*application* [, *output*, *basepkgname*, *edit_modnames*, *creatorsignature*, *dump*, *verbose*])

This function does the same as `processfile`, except that it uses a different method to get the terminology resources. It opens *application* as a resource file and reads all "aete" and "aet" resources from this file.

38.2 aetools — OSA client support

The `aetools` module contains the basic functionality on which Python AppleScript client support is built. It also imports and re-exports the core functionality of the `aetypes` and `aepack` modules. The stub packages generated by `gensuitemodule` import the relevant portions of `aetools`, so usually you do not need to import it yourself. The exception to this is when you cannot use a generated suite package and need lower-level access to scripting.

The `aetools` module itself uses the AppleEvent support provided by the `Carbon.AE` module. This has one drawback: you need access to the window manager, see section `osx-gui-scripts` for details. This restriction may be lifted in future releases.

참고: This module has been removed in Python 3.x.

The `aetools` module defines the following functions:

`aetools.packevent` (*ae*, *parameters*, *attributes*)

Stores parameters and attributes in a pre-created `Carbon.AE.AEDesc` object. *parameters* and *attributes* are dictionaries mapping 4-character OSA parameter keys to Python objects. The objects are packed using `aepack.pack()`.

`aetools.unpackevent` (*ae* [, *formodulename*])

Recursively unpacks a `Carbon.AE.AEDesc` event to Python objects. The function returns the parameter dictionary and the attribute dictionary. The *formodulename* argument is used by generated stub packages to control where AppleScript classes are looked up.

`aetools.keysubst` (*arguments*, *keydict*)

Converts a Python keyword argument dictionary *arguments* to the format required by `packevent` by replacing the keys, which are Python identifiers, by the four-character OSA keys according to the mapping specified in *keydict*. Used by the generated suite packages.

`aetools.enumsbst` (*arguments*, *key*, *edict*)

If the *arguments* dictionary contains an entry for *key* convert the value for that entry according to dictionary *edict*. This converts human-readable Python enumeration names to the OSA 4-character codes. Used by the generated suite packages.

The `aetools` module defines the following class:

class `aetools.TalkTo` ([*signature=None*, *start=0*, *timeout=0*])

Base class for the proxy used to talk to an application. *signature* overrides the class attribute `_signature` (which is usually set by subclasses) and is the 4-char creator code defining the application to talk to. *start* can be set to true to enable running the application on class instantiation. *timeout* can be specified to change the default timeout used while waiting for an AppleEvent reply.

`TalkTo._start` ()

Test whether the application is running, and attempt to start it if not.

`TalkTo.send` (*code*, *subcode* [, *parameters*, *attributes*])

Create the AppleEvent `Carbon.AE.AEDesc` for the verb with the OSA designation code, *subcode* (which are the usual 4-character strings), pack the *parameters* and *attributes* into it, send it to the target application, wait for the reply, unpack the reply with `unpackevent` and return the reply appleevent, the unpacked return values as a dictionary and the return attributes.

38.3 aepack — Conversion between Python variables and AppleEvent data containers

The *aepack* module defines functions for converting (packing) Python variables to AppleEvent descriptors and back (unpacking). Within Python the AppleEvent descriptor is handled by Python objects of built-in type *AEDesc*, defined in module *Carbon.AE*.

참고: This module has been removed in Python 3.x.

The *aepack* module defines the following functions:

aepack.pack (*x*[, *forcetype*])

Returns an *AEDesc* object containing a conversion of Python value *x*. If *forcetype* is provided it specifies the descriptor type of the result. Otherwise, a default mapping of Python types to Apple Event descriptor types is used, as follows:

Python type	descriptor type
<i>FSSpec</i>	<i>typeFSS</i>
<i>FSRef</i>	<i>typeFSRef</i>
<i>Alias</i>	<i>typeAlias</i>
<i>integer</i>	<i>typeLong</i> (32 bit integer)
<i>float</i>	<i>typeFloat</i> (64 bit floating point)
<i>string</i>	<i>typeText</i>
<i>unicode</i>	<i>typeUnicodeText</i>
<i>list</i>	<i>typeAEList</i>
<i>dictionary</i>	<i>typeAERecord</i>
<i>instance</i>	<i>see below</i>

If *x* is a Python instance then this function attempts to call an `__aepack__()` method. This method should return an *AEDesc* object.

If the conversion *x* is not defined above, this function returns the Python string representation of a value (the `repr()` function) encoded as a text descriptor.

aepack.unpack (*x*[, *formodulename*])

x must be an object of type *AEDesc*. This function returns a Python object representation of the data in the Apple Event descriptor *x*. Simple AppleEvent data types (integer, text, float) are returned as their obvious Python counterparts. Apple Event lists are returned as Python lists, and the list elements are recursively unpacked. Object references (ex. line 3 of document 1) are returned as instances of *aetypes.ObjectSpecifier*, unless *formodulename* is specified. AppleEvent descriptors with descriptor type *typeFSS* are returned as *FSSpec* objects. AppleEvent record descriptors are returned as Python dictionaries, with 4-character string keys and elements recursively unpacked.

The optional *formodulename* argument is used by the stub packages generated by *gensuitemodule*, and ensures that the OSA classes for object specifiers are looked up in the correct module. This ensures that if, say, the Finder returns an object specifier for a window you get an instance of *Finder.Window* and not a generic *aetypes.Window*. The former knows about all the properties and elements a window has in the Finder, while the latter knows no such things.

더 보기:

Module *Carbon.AE* Built-in access to Apple Event Manager routines.

Module *aetypes* Python definitions of codes for Apple Event descriptor types.

38.4 aetypes — AppleEvent objects

The *aetypes* defines classes used to represent Apple Event data descriptors and Apple Event object specifiers.

Apple Event data is contained in descriptors, and these descriptors are typed. For many descriptors the Python representation is simply the corresponding Python type: `typeText` in OSA is a Python string, `typeFloat` is a float, etc. For OSA types that have no direct Python counterpart this module declares classes. Packing and unpacking instances of these classes is handled automatically by *aepack*.

An object specifier is essentially an address of an object implemented in an Apple Event server. An Apple Event specifier is used as the direct object for an Apple Event or as the argument of an optional parameter. The *aetypes* module contains the base classes for OSA classes and properties, which are used by the packages generated by *gensuitemodule* to populate the classes and properties in a given suite.

For reasons of backward compatibility, and for cases where you need to script an application for which you have not generated the stub package this module also contains object specifiers for a number of common OSA classes such as `Document`, `Window`, `Character`, etc.

참고: This module has been removed in Python 3.x.

The `AEObjects` module defines the following classes to represent Apple Event descriptor data:

```
class aetypes.Unknown(type, data)
    The representation of OSA descriptor data for which the aepack and aetypes modules have no support, i.e.
    anything that is not represented by the other classes here and that is not equivalent to a simple Python value.

class aetypes.Enum(enum)
    An enumeration value with the given 4-character string value.

class aetypes.InsertionLoc(of, pos)
    Position pos in object of.

class aetypes.Boolean(bool)
    A boolean.

class aetypes.StyledText(style, text)
    Text with style information (font, face, etc) included.

class aetypes.AEText(script, style, text)
    Text with script system and style information included.

class aetypes.IntlText(script, language, text)
    Text with script system and language information included.

class aetypes.IntlWritingCode(script, language)
    Script system and language information.

class aetypes.QDPoint(v, h)
    A quickdraw point.

class aetypes.QDRectangle(v0, h0, v1, h1)
    A quickdraw rectangle.

class aetypes.RGBColor(r, g, b)
    A color.

class aetypes.Type(type)
    An OSA type value with the given 4-character name.
```

class `aetypes.Keyword` (*name*)
An OSA keyword with the given 4-character name.

class `aetypes.Range` (*start, stop*)
A range.

class `aetypes.Ordinal` (*abso*)
Non-numeric absolute positions, such as "firs", first, or "midd", middle.

class `aetypes.Logical` (*logc, term*)
The logical expression of applying operator `logc` to `term`.

class `aetypes.Comparison` (*obj1, relo, obj2*)
The comparison `relo` of `obj1` to `obj2`.

The following classes are used as base classes by the generated stub packages to represent AppleScript classes and properties in Python:

class `aetypes.ComponentItem` (*which[, fr]*)
Abstract baseclass for an OSA class. The subclass should set the class attribute `want` to the 4-character OSA class code. Instances of subclasses of this class are equivalent to AppleScript Object Specifiers. Upon instantiation you should pass a selector in `which`, and optionally a parent object in `fr`.

class `aetypes.NProperty` (*fr*)
Abstract baseclass for an OSA property. The subclass should set the class attributes `want` and `which` to designate which property we are talking about. Instances of subclasses of this class are Object Specifiers.

class `aetypes.ObjectSpecifier` (*want, form, seld[, fr]*)
Base class of `ComponentItem` and `NProperty`, a general OSA Object Specifier. See the Apple Open Scripting Architecture documentation for the parameters. Note that this class is not abstract.

38.5 MiniAEFrame — Open Scripting Architecture server support

The module `MiniAEFrame` provides a framework for an application that can function as an Open Scripting Architecture (OSA) server, i.e. receive and process `AppleEvents`. It can be used in conjunction with `FrameWork` or standalone. As an example, it is used in `PythonCGISlave`.

The `MiniAEFrame` module defines the following classes:

class `MiniAEFrame.AEServer`
A class that handles `AppleEvent` dispatch. Your application should subclass this class together with either `MiniApplication` or `FrameWork.Application`. Your `__init__()` method should call the `__init__()` method for both classes.

class `MiniAEFrame.MinApplication`
A class that is more or less compatible with `FrameWork.Application` but with less functionality. Its event loop supports the apple menu, command-dot and `AppleEvents`; other events are passed on to the Python interpreter and/or `Sioux`. Useful if your application wants to use `AEServer` but does not provide its own windows, etc.

38.5.1 AEServer Objects

`AEServer.installaehandler` (*classe*, *type*, *callback*)

Installs an AppleEvent handler. *classe* and *type* are the four-character OSA Class and Type designators, '****' wildcards are allowed. When a matching AppleEvent is received the parameters are decoded and your callback is invoked.

`AEServer.callback` (*_object*, ***kwargs*)

Your callback is called with the OSA Direct Object as first positional parameter. The other parameters are passed as keyword arguments, with the 4-character designator as name. Three extra keyword parameters are passed: `_class` and `_type` are the Class and Type designators and `_attributes` is a dictionary with the AppleEvent attributes.

The return value of your method is packed with `aetools.packevent()` and sent as reply.

Note that there are some serious problems with the current design. AppleEvents which have non-identifier 4-character designators for arguments are not implementable, and it is not possible to return an error to the originator. This will be addressed in a future release.

In addition, support modules have been pre-generated for Finder, Terminal, Explorer, Netscape, CodeWarrior, SystemEvents and StdSuites.

SGI IRIX Specific Services

The modules described in this chapter provide interfaces to features that are unique to SGI's IRIX operating system (versions 4 and 5).

39.1 `al` — Audio functions on the SGI

버전 2.6부터 폐지: The `al` module has been removed in Python 3.

This module provides access to the audio facilities of the SGI Indy and Indigo workstations. See section 3A of the IRIX man pages for details. You'll need to read those man pages to understand what these functions do! Some of the functions are not available in IRIX releases before 4.0.5. Again, see the manual to check whether a specific function is available on your platform.

All functions and methods defined in this module are equivalent to the C functions with `AL` prefixed to their name.

Symbolic constants from the C header file `<audio.h>` are defined in the standard module `AL`, see below.

경고: The current version of the audio library may dump core when bad argument values are passed rather than returning an error status. Unfortunately, since the precise circumstances under which this may happen are undocumented and hard to check, the Python interface can provide no protection against this kind of problems. (One example is specifying an excessive queue size — there is no documented upper limit.)

The module defines the following functions:

`al.openport(name, direction[, config])`

The name and direction arguments are strings. The optional `config` argument is a configuration object as returned by `newconfig()`. The return value is an *audio port object*; methods of audio port objects are described below.

`al.newconfig()`

The return value is a new *audio configuration object*; methods of audio configuration objects are described below.

al.**queryparams** (*device*)

The *device* argument is an integer. The return value is a list of integers containing the data returned by `ALqueryparams()`.

al.**getparams** (*device*, *list*)

The *device* argument is an integer. The *list* argument is a list such as returned by `queryparams()`; it is modified in place (!).

al.**setparams** (*device*, *list*)

The *device* argument is an integer. The *list* argument is a list such as returned by `queryparams()`.

39.1.1 Configuration Objects

Configuration objects returned by `newconfig()` have the following methods:

audio configuration.getqueuesize()

Return the queue size.

audio configuration.setqueuesize(size)

Set the queue size.

audio configuration.getwidth()

Get the sample width.

audio configuration.setwidth(width)

Set the sample width.

audio configuration.getchannels()

Get the channel count.

audio configuration.setchannels(nchannels)

Set the channel count.

audio configuration.getsampfmt()

Get the sample format.

audio configuration.setsampfmt(sampfmt)

Set the sample format.

audio configuration.getfloatmax()

Get the maximum value for floating sample formats.

audio configuration.setfloatmax(floatmax)

Set the maximum value for floating sample formats.

39.1.2 Port Objects

Port objects, as returned by `openport()`, have the following methods:

audio port.closeport()

Close the port.

audio port.getfd()

Return the file descriptor as an int.

audio port.getfilled()

Return the number of filled samples.

audio port.getfillable()

Return the number of fillable samples.

audio.port.readsamps(nsamples)

Read a number of samples from the queue, blocking if necessary. Return the data as a string containing the raw data, (e.g., 2 bytes per sample in big-endian byte order (high byte, low byte) if you have set the sample width to 2 bytes).

audio.port.writesamps(samples)

Write samples into the queue, blocking if necessary. The samples are encoded as described for the `readsamps()` return value.

audio.port.getfillpoint()

Return the <fill point>.

audio.port.setfillpoint(fillpoint)

Set the <fill point>.

audio.port.getconfig()

Return a configuration object containing the current configuration of the port.

audio.port.setconfig(config)

Set the configuration from the argument, a configuration object.

audio.port.getstatus(list)

Get status information on last error.

39.2 AL — Constants used with the a1 module

버전 2.6부터 폐지: The `AL` module has been removed in Python 3.

This module defines symbolic constants needed to use the built-in module `a1` (see above); they are equivalent to those defined in the C header file `<audio.h>` except that the name prefix `AL_` is omitted. Read the module source for a complete list of the defined names. Suggested use:

```
import a1
from AL import *
```

39.3 cd — CD-ROM access on SGI systems

버전 2.6부터 폐지: The `cd` module has been removed in Python 3.

This module provides an interface to the Silicon Graphics CD library. It is available only on Silicon Graphics systems.

The way the library works is as follows. A program opens the CD-ROM device with `open()` and creates a parser to parse the data from the CD with `createparser()`. The object returned by `open()` can be used to read data from the CD, but also to get status information for the CD-ROM device, and to get information about the CD, such as the table of contents. Data from the CD is passed to the parser, which parses the frames, and calls any callback functions that have previously been added.

An audio CD is divided into *tracks* or *programs* (the terms are used interchangeably). Tracks can be subdivided into *indices*. An audio CD contains a *table of contents* which gives the starts of the tracks on the CD. Index 0 is usually the pause before the start of a track. The start of the track as given by the table of contents is normally the start of index 1.

Positions on a CD can be represented in two ways. Either a frame number or a tuple of three values, minutes, seconds and frames. Most functions use the latter representation. Positions can be both relative to the beginning of the CD, and to the beginning of the track.

Module `cd` defines the following functions and constants:

`cd.createparser()`

Create and return an opaque parser object. The methods of the parser object are described below.

`cd.msftoframe(minutes, seconds, frames)`

Converts a (minutes, seconds, frames) triple representing time in absolute time code into the corresponding CD frame number.

`cd.open([device[, mode]])`

Open the CD-ROM device. The return value is an opaque player object; methods of the player object are described below. The device is the name of the SCSI device file, e.g. `'/dev/scsi/sc0d410 '`, or `None`. If omitted or `None`, the hardware inventory is consulted to locate a CD-ROM drive. The *mode*, if not omitted, should be the string `'r'`.

The module defines the following variables:

exception `cd.error`

Exception raised on various errors.

`cd.DATASIZE`

The size of one frame's worth of audio data. This is the size of the audio data as passed to the callback of type `audio`.

`cd.BLOCKSIZE`

The size of one uninterpreted frame of audio data.

The following variables are states as returned by `getstatus()`:

`cd.READY`

The drive is ready for operation loaded with an audio CD.

`cd.NODISC`

The drive does not have a CD loaded.

`cd.CDROM`

The drive is loaded with a CD-ROM. Subsequent play or read operations will return I/O errors.

`cd.ERROR`

An error occurred while trying to read the disc or its table of contents.

`cd.PLAYING`

The drive is in CD player mode playing an audio CD through its audio jacks.

`cd.PAUSED`

The drive is in CD layer mode with play paused.

`cd.STILL`

The equivalent of *PAUSED* on older (non 3301) model Toshiba CD-ROM drives. Such drives have never been shipped by SGI.

`cd.audio`

`cd.pnum`

`cd.index`

`cd.ptime`

`cd.atime`

`cd.catalog`

`cd.ident`

`cd.control`

Integer constants describing the various types of parser callbacks that can be set by the `addcallback()` method of CD parser objects (see below).

39.3.1 Player Objects

Player objects (returned by `open()`) have the following methods:

CD `player.allowremoval()`

Unlocks the eject button on the CD-ROM drive permitting the user to eject the caddy if desired.

CD `player.bestreadsize()`

Returns the best value to use for the `num_frames` parameter of the `reada()` method. Best is defined as the value that permits a continuous flow of data from the CD-ROM drive.

CD `player.close()`

Frees the resources associated with the player object. After calling `close()`, the methods of the object should no longer be used.

CD `player.eject()`

Ejects the caddy from the CD-ROM drive.

CD `player.getstatus()`

Returns information pertaining to the current state of the CD-ROM drive. The returned information is a tuple with the following values: `state`, `track`, `rtime`, `atime`, `ttime`, `first`, `last`, `scsi_audio`, `cur_block`. `rtime` is the time relative to the start of the current track; `atime` is the time relative to the beginning of the disc; `ttime` is the total time on the disc. For more information on the meaning of the values, see the man page `CDgetstatus(3dm)`. The value of `state` is one of the following: `ERROR`, `NODISC`, `READY`, `PLAYING`, `PAUSED`, `STILL`, or `CDROM`.

CD `player.gettrackinfo(track)`

Returns information about the specified track. The returned information is a tuple consisting of two elements, the start time of the track and the duration of the track.

CD `player.msftoblock(min, sec, frame)`

Converts a minutes, seconds, frames triple representing a time in absolute time code into the corresponding logical block number for the given CD-ROM drive. You should use `msftoframe()` rather than `msftoblock()` for comparing times. The logical block number differs from the frame number by an offset required by certain CD-ROM drives.

CD `player.play(start, play)`

Starts playback of an audio CD in the CD-ROM drive at the specified track. The audio output appears on the CD-ROM drive's headphone and audio jacks (if fitted). Play stops at the end of the disc. `start` is the number of the track at which to start playing the CD; if `play` is 0, the CD will be set to an initial paused state. The method `togglepause()` can then be used to commence play.

CD `player.playabs(minutes, seconds, frames, play)`

Like `play()`, except that the start is given in minutes, seconds, and frames instead of a track number.

CD `player.playtrack(start, play)`

Like `play()`, except that playing stops at the end of the track.

CD `player.playtrackabs(track, minutes, seconds, frames, play)`

Like `play()`, except that playing begins at the specified absolute time and ends at the end of the specified track.

CD `player.preventremoval()`

Locks the eject button on the CD-ROM drive thus preventing the user from arbitrarily ejecting the caddy.

CD `player.reada(num_frames)`

Reads the specified number of frames from an audio CD mounted in the CD-ROM drive. The return value is a string representing the audio frames. This string can be passed unaltered to the `parseframe()` method of the parser object.

CD `player.seek(minutes, seconds, frames)`

Sets the pointer that indicates the starting point of the next read of digital audio data from a CD-ROM. The pointer

is set to an absolute time code location specified in *minutes*, *seconds*, and *frames*. The return value is the logical block number to which the pointer has been set.

CD `player.seekblock(block)`

Sets the pointer that indicates the starting point of the next read of digital audio data from a CD-ROM. The pointer is set to the specified logical block number. The return value is the logical block number to which the pointer has been set.

CD `player.seektrack(track)`

Sets the pointer that indicates the starting point of the next read of digital audio data from a CD-ROM. The pointer is set to the specified track. The return value is the logical block number to which the pointer has been set.

CD `player.stop()`

Stops the current playing operation.

CD `player.togglepause()`

Pauses the CD if it is playing, and makes it play if it is paused.

39.3.2 Parser Objects

Parser objects (returned by `createparser()`) have the following methods:

CD `parser.addcallback(type, func, arg)`

Adds a callback for the parser. The parser has callbacks for eight different types of data in the digital audio data stream. Constants for these types are defined at the `cd` module level (see above). The callback is called as follows: `func(arg, type, data)`, where *arg* is the user supplied argument, *type* is the particular type of callback, and *data* is the data returned for this *type* of callback. The type of the data depends on the *type* of callback as follows:

Type	Value
<code>audio</code>	String which can be passed unmodified to <code>al.writesamps()</code> .
<code>pnum</code>	Integer giving the program (track) number.
<code>index</code>	Integer giving the index number.
<code>ptime</code>	Tuple consisting of the program time in minutes, seconds, and frames.
<code>atime</code>	Tuple consisting of the absolute time in minutes, seconds, and frames.
<code>catal</code>	String of 13 characters, giving the catalog number of the CD.
<code>ident</code>	String of 12 characters, giving the ISRC identification number of the recording. The string consists of two characters country code, three characters owner code, two characters giving the year, and five characters giving a serial number.
<code>control</code>	Integer giving the control bits from the CD subcode data

CD `parser.deleteparser()`

Deletes the parser and frees the memory it was using. The object should not be used after this call. This call is done automatically when the last reference to the object is removed.

CD `parser.parseframe(frame)`

Parses one or more frames of digital audio data from a CD such as returned by `readda()`. It determines which subcodes are present in the data. If these subcodes have changed since the last frame, then `parseframe()` executes a callback of the appropriate type passing to it the subcode data found in the frame. Unlike the C function, more than one frame of digital audio data can be passed to this method.

CD `parser.removecallback(type)`

Removes the callback for the given *type*.

CD `parser.resetparser()`

Resets the fields of the parser used for tracking subcodes to an initial state. `resetparser()` should be called after the disc has been changed.

39.4 fl — FORMS library for graphical user interfaces

버전 2.6부터 폐지: The `fl` module has been removed in Python 3.

This module provides an interface to the FORMS Library by Mark Overmars. The source for the library can be retrieved by anonymous FTP from host `ftp.cs.ruu.nl`, directory `SGI/FORMS`. It was last tested with version 2.0b.

Most functions are literal translations of their C equivalents, dropping the initial `fl_` from their name. Constants used by the library are defined in module `FL` described below.

The creation of objects is a little different in Python than in C: instead of the `<current form>` maintained by the library to which new FORMS objects are added, all functions that add a FORMS object to a form are methods of the Python object representing the form. Consequently, there are no Python equivalents for the C functions `fl_addto_form()` and `fl_end_form()`, and the equivalent of `fl_bgn_form()` is called `fl.make_form()`.

Watch out for the somewhat confusing terminology: FORMS uses the word *object* for the buttons, sliders etc. that you can place in a form. In Python, `<object>` means any value. The Python interface to FORMS introduces two new Python object types: form objects (representing an entire form) and FORMS objects (representing one button, slider etc.). Hopefully this isn't too confusing.

There are no `<free objects>` in the Python interface to FORMS, nor is there an easy way to add object classes written in Python. The FORMS interface to GL event handling is available, though, so you can mix FORMS with pure GL windows.

Please note: importing `fl` implies a call to the GL function `foreground()` and to the FORMS routine `fl_init()`.

39.4.1 Functions Defined in Module `fl`

Module `fl` defines the following functions. For more information about what they do, see the description of the equivalent C function in the FORMS documentation:

`fl.make_form(type, width, height)`

Create a form with given type, width and height. This returns a *form* object, whose methods are described below.

`fl.do_forms()`

The standard FORMS main loop. Returns a Python object representing the FORMS object needing interaction, or the special value `FL.EVENT`.

`fl.check_forms()`

Check for FORMS events. Returns what `do_forms()` above returns, or `None` if there is no event that immediately needs interaction.

`fl.set_event_call_back(function)`

Set the event callback function.

`fl.set_graphics_mode(rgbmode, doublebuffering)`

Set the graphics modes.

`fl.get_rgbmode()`

Return the current rgb mode. This is the value of the C global variable `fl_rgbmode`.

`fl.show_message(str1, str2, str3)`

Show a dialog box with a three-line message and an OK button.

`fl.show_question(str1, str2, str3)`

Show a dialog box with a three-line message and YES and NO buttons. It returns 1 if the user pressed YES, 0 if NO.

`fl.show_choice(str1, str2, str3, but1[, but2[, but3]])`

Show a dialog box with a three-line message and up to three buttons. It returns the number of the button clicked by the user (1, 2 or 3).

`fl.show_input(prompt, default)`

Show a dialog box with a one-line prompt message and text field in which the user can enter a string. The second argument is the default input string. It returns the string value as edited by the user.

`fl.show_file_selector(message, directory, pattern, default)`

Show a dialog box in which the user can select a file. It returns the absolute filename selected by the user, or `None` if the user presses Cancel.

`fl.get_directory()`

`fl.get_pattern()`

`fl.get_filename()`

These functions return the directory, pattern and filename (the tail part only) selected by the user in the last `show_file_selector()` call.

`fl.qdevice(dev)`

`fl.unqdevice(dev)`

`fl.isqueued(dev)`

`fl.qtest()`

`fl.qread()`

`fl.qreset()`

`fl.qenter(dev, val)`

`fl.get_mouse()`

`fl.tie(button, valuator1, valuator2)`

These functions are the FORMS interfaces to the corresponding GL functions. Use these if you want to handle some GL events yourself when using `fl.do_events()`. When a GL event is detected that FORMS cannot handle, `fl.do_forms()` returns the special value `FL.EVENT` and you should call `fl.qread()` to read the event from the queue. Don't use the equivalent GL functions!

`fl.color()`

`fl.mapcolor()`

`fl.getmcolor()`

See the description in the FORMS documentation of `fl_color()`, `fl_mapcolor()` and `fl_getmcolor()`.

39.4.2 Form Objects

Form objects (returned by `make_form()` above) have the following methods. Each method corresponds to a C function whose name is prefixed with `fl_`; and whose first argument is a form pointer; please refer to the official FORMS documentation for descriptions.

All the `add_*()` methods return a Python object representing the FORMS object. Methods of FORMS objects are described below. Most kinds of FORMS object also have some methods specific to that kind; these methods are listed here.

`form.show_form(placement, bordertype, name)`

Show the form.

`form.hide_form()`

Hide the form.

`form.redraw_form()`

Redraw the form.

`form.set_form_position(x, y)`

Set the form's position.

`form.freeze_form()`

Freeze the form.

`form.unfreeze_form()`
Unfreeze the form.

`form.activate_form()`
Activate the form.

`form.deactivate_form()`
Deactivate the form.

`form.bgn_group()`
Begin a new group of objects; return a group object.

`form.end_group()`
End the current group of objects.

`form.find_first()`
Find the first object in the form.

`form.find_last()`
Find the last object in the form.

`form.add_box(type, x, y, w, h, name)`
Add a box object to the form. No extra methods.

`form.add_text(type, x, y, w, h, name)`
Add a text object to the form. No extra methods.

`form.add_clock(type, x, y, w, h, name)`
Add a clock object to the form. — Method: `get_clock()`.

`form.add_button(type, x, y, w, h, name)`
Add a button object to the form. — Methods: `get_button()`, `set_button()`.

`form.add_lightbutton(type, x, y, w, h, name)`
Add a lightbutton object to the form. — Methods: `get_button()`, `set_button()`.

`form.add_roundbutton(type, x, y, w, h, name)`
Add a roundbutton object to the form. — Methods: `get_button()`, `set_button()`.

`form.add_slider(type, x, y, w, h, name)`
Add a slider object to the form. — Methods: `set_slider_value()`, `get_slider_value()`, `set_slider_bounds()`, `get_slider_bounds()`, `set_slider_return()`, `set_slider_size()`, `set_slider_precision()`, `set_slider_step()`.

`form.add_valslider(type, x, y, w, h, name)`
Add a valslider object to the form. — Methods: `set_slider_value()`, `get_slider_value()`, `set_slider_bounds()`, `get_slider_bounds()`, `set_slider_return()`, `set_slider_size()`, `set_slider_precision()`, `set_slider_step()`.

`form.add_dial(type, x, y, w, h, name)`
Add a dial object to the form. — Methods: `set_dial_value()`, `get_dial_value()`, `set_dial_bounds()`, `get_dial_bounds()`.

`form.add_positioner(type, x, y, w, h, name)`
Add a positioner object to the form. — Methods: `set_positioner_xvalue()`, `set_positioner_yvalue()`, `set_positioner_xbounds()`, `set_positioner_ybounds()`, `get_positioner_xvalue()`, `get_positioner_yvalue()`, `get_positioner_xbounds()`, `get_positioner_ybounds()`.

`form.add_counter(type, x, y, w, h, name)`
Add a counter object to the form. — Methods: `set_counter_value()`, `get_counter_value()`,

```
set_counter_bounds(),      set_counter_step(),      set_counter_precision(),
set_counter_return().
```

form.add_input (*type, x, y, w, h, name*)

Add an input object to the form. — Methods: `set_input()`, `get_input()`, `set_input_color()`, `set_input_return()`.

form.add_menu (*type, x, y, w, h, name*)

Add a menu object to the form. — Methods: `set_menu()`, `get_menu()`, `addto_menu()`.

form.add_choice (*type, x, y, w, h, name*)

Add a choice object to the form. — Methods: `set_choice()`, `get_choice()`, `clear_choice()`, `addto_choice()`, `replace_choice()`, `delete_choice()`, `get_choice_text()`, `set_choice_fontsize()`, `set_choice_fontstyle()`.

form.add_browser (*type, x, y, w, h, name*)

Add a browser object to the form. — Methods: `set_browser_topline()`, `clear_browser()`, `add_browser_line()`, `addto_browser()`, `insert_browser_line()`, `delete_browser_line()`, `replace_browser_line()`, `get_browser_line()`, `load_browser()`, `get_browser_maxline()`, `select_browser_line()`, `deselect_browser_line()`, `deselect_browser()`, `isselected_browser_line()`, `get_browser()`, `set_browser_fontsize()`, `set_browser_fontstyle()`, `set_browser_specialkey()`.

form.add_timer (*type, x, y, w, h, name*)

Add a timer object to the form. — Methods: `set_timer()`, `get_timer()`.

Form objects have the following data attributes; see the FORMS documentation:

Name	C Type	Meaning
<code>window</code>	int (read-only)	GL window id
<code>w</code>	float	form width
<code>h</code>	float	form height
<code>x</code>	float	form x origin
<code>y</code>	float	form y origin
<code>deactivated</code>	int	nonzero if form is deactivated
<code>visible</code>	int	nonzero if form is visible
<code>frozen</code>	int	nonzero if form is frozen
<code>doublebuf</code>	int	nonzero if double buffering on

39.4.3 FORMS Objects

Besides methods specific to particular kinds of FORMS objects, all FORMS objects also have the following methods:

FORMS object.set_call_back(*function, argument*)

Set the object's callback function and argument. When the object needs interaction, the callback function will be called with two arguments: the object, and the callback argument. (FORMS objects without a callback function are returned by `fl.do_forms()` or `fl.check_forms()` when they need interaction.) Call this method without arguments to remove the callback function.

FORMS object.delete_object()

Delete the object.

FORMS object.show_object()

Show the object.

FORMS `object.hide_object()`

Hide the object.

FORMS `object.redraw_object()`

Redraw the object.

FORMS `object.freeze_object()`

Freeze the object.

FORMS `object.unfreeze_object()`

Unfreeze the object.

FORMS objects have these data attributes; see the FORMS documentation:

Name	C Type	Meaning
<code>objclass</code>	int (read-only)	object class
<code>type</code>	int (read-only)	object type
<code>boxtype</code>	int	box type
<code>x</code>	float	x origin
<code>y</code>	float	y origin
<code>w</code>	float	width
<code>h</code>	float	height
<code>col1</code>	int	primary color
<code>col2</code>	int	secondary color
<code>align</code>	int	alignment
<code>lcol</code>	int	label color
<code>lsize</code>	float	label font size
<code>label</code>	string	label string
<code>lstyle</code>	int	label style
<code>pushed</code>	int (read-only)	(see FORMS docs)
<code>focus</code>	int (read-only)	(see FORMS docs)
<code>belowmouse</code>	int (read-only)	(see FORMS docs)
<code>frozen</code>	int (read-only)	(see FORMS docs)
<code>active</code>	int (read-only)	(see FORMS docs)
<code>input</code>	int (read-only)	(see FORMS docs)
<code>visible</code>	int (read-only)	(see FORMS docs)
<code>radio</code>	int (read-only)	(see FORMS docs)
<code>automatic</code>	int (read-only)	(see FORMS docs)

39.5 FL — Constants used with the `fl` module

버전 2.6부터 폐지: The `FL` module has been removed in Python 3.

This module defines symbolic constants needed to use the built-in module `fl` (see above); they are equivalent to those defined in the C header file `<forms.h>` except that the name prefix `FL_` is omitted. Read the module source for a complete list of the defined names. Suggested use:

```
import fl
from FL import *
```

39.6 flp — Functions for loading stored FORMS designs

버전 2.6부터 폐지: The `flp` module has been removed in Python 3.

This module defines functions that can read form definitions created by the <form designer> (**fdesign**) program that comes with the FORMS library (see module `fl` above).

For now, see the file `flp.doc` in the Python library source directory for a description.

XXX A complete description should be inserted here!

39.7 fm — Font Manager interface

버전 2.6부터 폐지: The `fm` module has been removed in Python 3.

This module provides access to the IRIS *Font Manager* library. It is available only on Silicon Graphics machines. See also: *4Sight User's Guide*, section 1, chapter 5: «Using the IRIS Font Manager.»

This is not yet a full interface to the IRIS Font Manager. Among the unsupported features are: matrix operations; cache operations; character operations (use string operations instead); some details of font info; individual glyph metrics; and printer matching.

It supports the following operations:

`fm.init()`

Initialization function. Calls `fminit()`. It is normally not necessary to call this function, since it is called automatically the first time the `fm` module is imported.

`fm.findfont(fontname)`

Return a font handle object. Calls `fmfindfont(fontname)`.

`fm.enumerate()`

Returns a list of available font names. This is an interface to `fmenumerate()`.

`fm.prstr(string)`

Render a string using the current font (see the `setfont()` font handle method below). Calls `fmprstr(string)`.

`fm.setpath(string)`

Sets the font search path. Calls `fmsetpath(string)`. (XXX Does not work!?)

`fm.fontpath()`

Returns the current font search path.

Font handle objects support the following operations:

font handle.scalefont(factor)

Returns a handle for a scaled version of this font. Calls `fmscalefont(fh, factor)`.

font handle.setfont()

Makes this font the current font. Note: the effect is undone silently when the font handle object is deleted. Calls `fmsetfont(fh)`.

font handle.getfontname()

Returns this font's name. Calls `fmgetfontname(fh)`.

font handle.getcomment()

Returns the comment string associated with this font. Raises an exception if there is none. Calls `fmgetcomment(fh)`.

font handle.getFontinfo()

Returns a tuple giving some pertinent data about this font. This is an interface to `fmgetfontinfo()`. The returned tuple contains the following numbers: (`printermatched`, `fixed_width`, `xorig`, `yorig`, `xsize`, `ysize`, `height`, `nglyphs`).

font handle.getstrwidth(string)

Returns the width, in pixels, of *string* when drawn in this font. Calls `fmgetstrwidth(fh, string)`.

39.8 gl — Graphics Library interface

버전 2.6부터 폐지: The *gl* module has been removed in Python 3.

This module provides access to the Silicon Graphics *Graphics Library*. It is available only on Silicon Graphics machines.

경고: Some illegal calls to the GL library cause the Python interpreter to dump core. In particular, the use of most GL calls is unsafe before the first window is opened.

The module is too large to document here in its entirety, but the following should help you to get started. The parameter conventions for the C functions are translated to Python as follows:

- All (short, long, unsigned) int values are represented by Python integers.
- All float and double values are represented by Python floating point numbers. In most cases, Python integers are also allowed.
- All arrays are represented by one-dimensional Python lists. In most cases, tuples are also allowed.
- All string and character arguments are represented by Python strings, for instance, `winopen('Hi There!')` and `rotate(900, 'z')`.
- All (short, long, unsigned) integer arguments or return values that are only used to specify the length of an array argument are omitted. For example, the C call

```
lmdef(deftype, index, np, props)
```

is translated to Python as

```
lmdef(deftype, index, props)
```

- Output arguments are omitted from the argument list; they are transmitted as function return values instead. If more than one value must be returned, the return value is a tuple. If the C function has both a regular return value (that is not omitted because of the previous rule) and an output argument, the return value comes first in the tuple. Examples: the C call

```
getmcolor(i, &red, &green, &blue)
```

is translated to Python as

```
red, green, blue = getmcolor(i)
```

The following functions are non-standard or have special argument conventions:

gl.varray (argument)

Equivalent to but faster than a number of `v3d()` calls. The *argument* is a list (or tuple) of points. Each point must be a tuple of coordinates (`x`, `y`, `z`) or (`x`, `y`). The points may be 2- or 3-dimensional but must all have the same dimension. Float and int values may be mixed however. The points are always converted to 3D double

precision points by assuming $z = 0.0$ if necessary (as indicated in the man page), and for each point `v3d()` is called.

`gl.nvarray()`

Equivalent to but faster than a number of `n3f` and `v3f` calls. The argument is an array (list or tuple) of pairs of normals and points. Each pair is a tuple of a point and a normal for that point. Each point or normal must be a tuple of coordinates (x, y, z) . Three coordinates must be given. Float and int values may be mixed. For each pair, `n3f()` is called for the normal, and then `v3f()` is called for the point.

`gl.vnarray()`

Similar to `nvarray()` but the pairs have the point first and the normal second.

`gl.nurbssurface(s_k, t_k, ctl, s_ord, t_ord, type)`

Defines a nurbs surface. The dimensions of `ctl[][]` are computed as follows: `[len(s_k) - s_ord]`, `[len(t_k) - t_ord]`.

`gl.nurbscurve(knots, ctlpoints, order, type)`

Defines a nurbs curve. The length of `ctlpoints` is `len(knots) - order`.

`gl.pwlcurve(points, type)`

Defines a piecewise-linear curve. *points* is a list of points. *type* must be `N_ST`.

`gl.pick(n)`

`gl.select(n)`

The only argument to these functions specifies the desired size of the pick or select buffer.

`gl.endpick()`

`gl.endselect()`

These functions have no arguments. They return a list of integers representing the used part of the pick/select buffer. No method is provided to detect buffer overrun.

Here is a tiny but complete example GL program in Python:

```
import gl, GL, time

def main():
    gl.foreground()
    gl.prefposition(500, 900, 500, 900)
    w = gl.winopen('CrissCross')
    gl.ortho2(0.0, 400.0, 0.0, 400.0)
    gl.color(GL.WHITE)
    gl.clear()
    gl.color(GL.RED)
    gl.bgnline()
    gl.v2f(0.0, 0.0)
    gl.v2f(400.0, 400.0)
    gl.endline()
    gl.bgnline()
    gl.v2f(400.0, 0.0)
    gl.v2f(0.0, 400.0)
    gl.endline()
    time.sleep(5)

main()
```

더 보기:

PyOpenGL: The Python OpenGL Binding An interface to OpenGL is also available; see information about the **PyOpenGL** project online at <http://pyopengl.sourceforge.net/>. This may be a better option if support for SGI hardware from before about 1996 is not required.

39.9 DEVICE — Constants used with the gl module

버전 2.6부터 폐지: The *DEVICE* module has been removed in Python 3.

This module defines the constants used by the Silicon Graphics *Graphics Library* that C programmers find in the header file `<gl/device.h>`. Read the module source file for details.

39.10 GL — Constants used with the gl module

버전 2.6부터 폐지: The *GL* module has been removed in Python 3.

This module contains constants used by the Silicon Graphics *Graphics Library* from the C header file `<gl/gl.h>`. Read the module source file for details.

39.11 imgfile — Support for SGI imglib files

버전 2.6부터 폐지: The *imgfile* module has been removed in Python 3.

The *imgfile* module allows Python programs to access SGI imglib image files (also known as `.rgb` files). The module is far from complete, but is provided anyway since the functionality that there is enough in some cases. Currently, colormap files are not supported.

The module defines the following variables and functions:

exception `imgfile.error`

This exception is raised on all errors, such as unsupported file type, etc.

`imgfile.getsizes(file)`

This function returns a tuple `(x, y, z)` where `x` and `y` are the size of the image in pixels and `z` is the number of bytes per pixel. Only 3 byte RGB pixels and 1 byte greyscale pixels are currently supported.

`imgfile.read(file)`

This function reads and decodes the image on the specified file, and returns it as a Python string. The string has either 1 byte greyscale pixels or 4 byte RGBA pixels. The bottom left pixel is the first in the string. This format is suitable to pass to `gl.rectwrite()`, for instance.

`imgfile.readscaled(file, x, y, filter[, blur])`

This function is identical to `read` but it returns an image that is scaled to the given `x` and `y` sizes. If the *filter* and *blur* parameters are omitted scaling is done by simply dropping or duplicating pixels, so the result will be less than perfect, especially for computer-generated images.

Alternatively, you can specify a filter to use to smooth the image after scaling. The filter forms supported are 'impulse', 'box', 'triangle', 'quadratic' and 'gaussian'. If a filter is specified *blur* is an optional parameter specifying the blurriness of the filter. It defaults to 1.0.

`readscaled()` makes no attempt to keep the aspect ratio correct, so that is the users' responsibility.

`imgfile.ttob(flag)`

This function sets a global flag which defines whether the scan lines of the image are read or written from bottom to top (flag is zero, compatible with SGI GL) or from top to bottom (flag is one, compatible with X). The default is zero.

`imgfile.write(file, data, x, y, z)`

This function writes the RGB or greyscale data in *data* to image file *file*. `x` and `y` give the size of the image, `z` is 1 for 1 byte greyscale images or 3 for RGB images (which are stored as 4 byte values of which only the lower three bytes are used). These are the formats returned by `gl.rectread()`.

39.12 jpeg — Read and write JPEG files

버전 2.6부터 폐지: The `jpeg` module has been removed in Python 3.

The module `jpeg` provides access to the jpeg compressor and decompressor written by the Independent JPEG Group (IJG). JPEG is a standard for compressing pictures; it is defined in ISO 10918. For details on JPEG or the Independent JPEG Group software refer to the JPEG standard or the documentation provided with the software.

A portable interface to JPEG image files is available with the Python Imaging Library (PIL) by Fredrik Lundh. Information on PIL is available at <http://www.pythonware.com/products/pil/>.

The `jpeg` module defines an exception and some functions.

exception `jpeg.error`

Exception raised by `compress()` and `decompress()` in case of errors.

`jpeg.compress(data, w, h, b)`

Treat data as a pixmap of width `w` and height `h`, with `b` bytes per pixel. The data is in SGI GL order, so the first pixel is in the lower-left corner. This means that `gl.rectread()` return data can immediately be passed to `compress()`. Currently only 1 byte and 4 byte pixels are allowed, the former being treated as grayscale and the latter as RGB color. `compress()` returns a string that contains the compressed picture, in JFIF format.

`jpeg.decompress(data)`

Data is a string containing a picture in JFIF format. It returns a tuple (`data`, `width`, `height`, `bytesperpixel`). Again, the data is suitable to pass to `gl.rectwrite()`.

`jpeg.setoption(name, value)`

Set various options. Subsequent `compress()` and `decompress()` calls will use these options. The following options are available:

Option	Effect
'forcegray'	Force output to be grayscale, even if input is RGB.
'quality'	Set the quality of the compressed image to a value between 0 and 100 (default is 75). This only affects compression.
'optimize'	Perform Huffman table optimization. Takes longer, but results in smaller compressed image. This only affects compression.
'smooth'	Perform inter-block smoothing on uncompressed image. Only useful for low- quality images. This only affects decompression.

더 보기:

JPEG Still Image Data Compression Standard The canonical reference for the JPEG image format, by Pennebaker and Mitchell.

Information Technology - Digital Compression and Coding of Continuous-tone Still Images - Requirements and Guidelines

The ISO standard for JPEG is also published as ITU T.81. This is available online in PDF form.

The modules described in this chapter provide interfaces to features that are unique to SunOS 5 (also known as Solaris version 2).

40.1 `sunaudiodev` — Access to Sun audio hardware

버전 2.6부터 폐지: The `sunaudiodev` module has been removed in Python 3.

This module allows you to access the Sun audio interface. The Sun audio hardware is capable of recording and playing back audio data in u-LAW format with a sample rate of 8K per second. A full description can be found in the `audio(7I)` manual page.

The module `SUNAUDIODEV` defines constants which may be used with this module.

This module defines the following variables and functions:

exception `sunaudiodev.error`

This exception is raised on all errors. The argument is a string describing what went wrong.

`sunaudiodev.open(mode)`

This function opens the audio device and returns a Sun audio device object. This object can then be used to do I/O on. The `mode` parameter is one of `'r'` for record-only access, `'w'` for play-only access, `'rw'` for both and `'control'` for access to the control device. Since only one process is allowed to have the recorder or player open at the same time it is a good idea to open the device only for the activity needed. See `audio(7I)` for details.

As per the manpage, this module first looks in the environment variable `AUDIODEV` for the base audio device filename. If not found, it falls back to `/dev/audio`. The control device is calculated by appending `<ctl>` to the base audio device.

40.1.1 Audio Device Objects

The audio device objects are returned by `open()` define the following methods (except `control` objects which only provide `getinfo()`, `setinfo()`, `fileno()`, and `drain()`):

`audio device.close()`

This method explicitly closes the device. It is useful in situations where deleting the object does not immediately close it since there are other references to it. A closed device should not be used again.

`audio device.fileno()`

Returns the file descriptor associated with the device. This can be used to set up `SIGPOLL` notification, as described below.

`audio device.drain()`

This method waits until all pending output is processed and then returns. Calling this method is often not necessary: destroying the object will automatically close the audio device and this will do an implicit drain.

`audio device.flush()`

This method discards all pending output. It can be used avoid the slow response to a user's stop request (due to buffering of up to one second of sound).

`audio device.getinfo()`

This method retrieves status information like input and output volume, etc. and returns it in the form of an audio status object. This object has no methods but it contains a number of attributes describing the current device status. The names and meanings of the attributes are described in `<sun/audioio.h>` and in the *audio(7I)* manual page. Member names are slightly different from their C counterparts: a status object is only a single structure. Members of the `play` substructure have `o_` prepended to their name and members of the `record` structure have `i_`. So, the C member `play.sample_rate` is accessed as `o_sample_rate`, `record.gain` as `i_gain` and `monitor_gain` plainly as `monitor_gain`.

`audio device.ibufcount()`

This method returns the number of samples that are buffered on the recording side, i.e. the program will not block on a `read()` call of so many samples.

`audio device.obufcount()`

This method returns the number of samples buffered on the playback side. Unfortunately, this number cannot be used to determine a number of samples that can be written without blocking since the kernel output queue length seems to be variable.

`audio device.read(size)`

This method reads *size* samples from the audio input and returns them as a Python string. The function blocks until enough data is available.

`audio device.setinfo(status)`

This method sets the audio device status parameters. The *status* parameter is a device status object as returned by `getinfo()` and possibly modified by the program.

`audio device.write(samples)`

Write is passed a Python string containing audio samples to be played. If there is enough buffer space free it will immediately return, otherwise it will block.

The audio device supports asynchronous notification of various events, through the `SIGPOLL` signal. Here's an example of how you might enable this in Python:

```
def handle_sigpoll(signum, frame):
    print 'I got a SIGPOLL update'

import fcntl, signal, STROPTS
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
signal.signal(signal.SIGPOLL, handle_sigpoll)
fcntl.ioctl(audio_obj.fileno(), STROPTS.I_SETSIG, STROPTS.S_MSG)
```

40.2 SUNAUDIODEV — Constants used with sunaudiodev

버전 2.6부터 폐지: The *SUNAUDIODEV* module has been removed in Python 3.

This is a companion module to *sunaudiodev* which defines useful symbolic constants like `MIN_GAIN`, `MAX_GAIN`, `SPEAKER`, etc. The names of the constants are the same names as used in the C include file `<sun/audioio.h>`, with the leading string `AUDIO_` stripped.

Undocumented Modules

Here's a quick listing of modules that are currently undocumented, but that should be documented. Feel free to contribute documentation for them! (Send via email to docs@python.org.)

The idea and original contents for this chapter were taken from a posting by Fredrik Lundh; the specific contents of this chapter have been substantially revised.

41.1 Miscellaneous useful utilities

Some of these are very old and/or not very robust; marked with `⟨hmm.⟩`

ihooks — Import hook support (for `rexec`; may become obsolete). Removed in Python 3.x.

41.2 Platform specific modules

These modules are used to implement the `os.path` module, and are not documented beyond this mention. There's little need to document these.

ntpath — Implementation of `os.path` on Win32, Win64, WinCE, and OS/2 platforms.

posixpath — Implementation of `os.path` on POSIX.

bsddb185 — Backwards compatibility module for systems which still use the Berkeley DB 1.85 module. It is normally only available on certain BSD Unix-based systems. It should never be used directly.

41.3 Multimedia

audiodev — Platform-independent API for playing audio data. Removed in Python 3.x.

linuxaudiodev — Play audio data on the Linux audio device. Replaced in Python 2.3 by the *ossaudiodev* module. Removed in Python 3.x.

sunaudio — Interpret Sun audio headers (may become obsolete or a tool/demo). Removed in Python 3.x.

toaiiff — Convert 《arbitrary》 sound files to AIFF files; should probably become a tool or demo. Requires the external program **sox**. Removed in Python 3.x.

41.4 Undocumented Mac OS modules

41.4.1 applesingle — AppleSingle decoder

버전 2.6부터 폐지.

41.4.2 buildtools — Helper module for BuildApplet and Friends

버전 2.4부터 폐지.

41.4.3 cfmfile — Code Fragment Resource module

cfmfile is a module that understands Code Fragments and the accompanying 《cfrg》 resources. It can parse them and merge them, and is used by BuildApplication to combine all plugin modules to a single executable.

버전 2.4부터 폐지.

41.4.4 icopen — Internet Config replacement for open ()

Importing *icopen* will replace the built-in *open ()* with a version that uses Internet Config to set file type and creator for new files.

버전 2.6부터 폐지.

41.4.5 macerrors — Mac OS Errors

macerrors contains constant definitions for many Mac OS error codes.

버전 2.6부터 폐지.

41.4.6 `macresource` — Locate script resources

`macresource` helps scripts finding their resources, such as dialogs and menus, without requiring special case code for when the script is run under MacPython, as a MacPython applet or under OSX Python.

버전 2.6부터 폐지.

41.4.7 `Nav` — `NavServices` calls

A low-level interface to Navigation Services.

버전 2.6부터 폐지.

41.4.8 `PixmapWrapper` — Wrapper for `Pixmap` objects

`PixmapWrapper` wraps a `Pixmap` object with a Python object that allows access to the fields by name. It also has methods to convert to and from `PIL` images.

버전 2.6부터 폐지.

41.4.9 `videoreader` — Read QuickTime movies

`videoreader` reads and decodes QuickTime movies and passes a stream of images to your program. It also provides some support for audio tracks.

버전 2.6부터 폐지.

41.4.10 `w` — Widgets built on `FrameWork`

The `W` widgets are used extensively in the `IDE`.

버전 2.6부터 폐지.

41.5 Obsolete

These modules are not normally available for import; additional work must be done to make them available.

These extension modules written in C are not built by default. Under Unix, these must be enabled by uncommenting the appropriate lines in `Modules/Setup` in the build tree and either rebuilding Python if the modules are statically linked, or building and installing the shared object if using dynamically-loaded extensions.

timing — Measure time intervals to high resolution (use `time.clock()` instead). Removed in Python 3.x.

41.6 SGI-specific Extension modules

The following are SGI specific, and may be out of touch with the current version of reality.

c1 — Interface to the SGI compression library.

sv — Interface to the 《simple video》 board on SGI Indigo (obsolete hardware). Removed in Python 3.x.

>>> 대화형 셸의 기본 파이썬 프롬프트. 인터프리터에서 대화형으로 실행될 수 있는 코드 예에서 자주 볼 수 있다.

... The default Python prompt of the interactive shell when entering code for an indented code block, when within a pair of matching left and right delimiters (parentheses, square brackets, curly braces or triple quotes), or after specifying a decorator.

2to3 파이썬 2.x 코드를 파이썬 3.x 코드로 변환하려고 시도하는 도구인데, 소스를 파싱하고 파스 트리를 탐색해서 감지할 수 있는 대부분의 비호환성을 다룬다.

2to3 는 표준 라이브러리에서 *lib2to3* 로 제공된다; 독립적으로 실행할 수 있는 스크립트는 `Tools/scripts/2to3` 로 제공된다. *2to3 - Automated Python 2 to 3 code translation* 를 보세요.

abstract base class (추상 베이스 클래스) Abstract base classes complement *duck-typing* by providing a way to define interfaces when other techniques like *hasattr()* would be clumsy or subtly wrong (for example with magic methods). ABCs introduce virtual subclasses, which are classes that don't inherit from a class but are still recognized by *isinstance()* and *issubclass()*; see the *abc* module documentation. Python comes with many built-in ABCs for data structures (in the *collections* module), numbers (in the *numbers* module), and streams (in the *io* module). You can create your own ABCs with the *abc* module.

argument (인자) A value passed to a *function* (or *method*) when calling the function. There are two types of arguments:

- 키워드 인자 (*keyword argument*): 함수 호출 때 식별자가 앞에 붙은 인자(예를 들어, `name=`) 또는 `**` 를 앞에 붙인 딕셔너리로 전달되는 인자. 예를 들어, 다음과 같은 *complex()* 호출에서 3 과 5 는 모두 키워드 인자다:

```
complex(real=3, imag=5)
complex(**{'real': 3, 'imag': 5})
```

- 위치 인자 (*positional argument*): 키워드 인자가 아닌 인자. 위치 인자들은 인자 목록의 처음에 나오거나 이터러블 의 앞에 `*` 를 붙여 전달할 수 있다. 예를 들어, 다음과 같은 호출에서 3 과 5 는 모두 위치 인자다.

```
complex(3, 5)
complex(*(3, 5))
```

인자는 함수 바의 이름 붙은 지역 변수에 대입된다. 이 대입에 적용되는 규칙들에 대해서는 [calls](#) 섹션을 보세요. 문법적으로, 어떤 표현식이건 인자로 사용될 수 있다; 구해진 값이 지역 변수에 대입된다.

See also the [parameter](#) glossary entry and the FAQ question on the difference between arguments and parameters.

attribute (어트리뷰트) 점표현식을 사용하는 이름으로 참조되는 객체와 결합한 값. 예를 들어, 객체 *o* 가 어트리뷰트 *a* 를 가지면, *o.a* 처럼 참조된다.

BDFL 자비로운 종신 독재자 (Benevolent Dictator For Life), 즉 [Guido van Rossum](#), 파이썬의 창시자.

bytes-like object (바이트열류 객체) An object that supports the buffer protocol, like [str](#), [bytearray](#) or [memoryview](#). Bytes-like objects can be used for various operations that expect binary data, such as compression, saving to a binary file or sending over a socket. Some operations need the binary data to be mutable, in which case not all bytes-like objects can apply.

bytecode (바이트 코드) Python source code is compiled into bytecode, the internal representation of a Python program in the CPython interpreter. The bytecode is also cached in [.pyc](#) and [.pyo](#) files so that executing the same file is faster the second time (recompilation from source to bytecode can be avoided). This 《intermediate language》 is said to run on a [virtual machine](#) that executes the machine code corresponding to each bytecode. Do note that bytecodes are not expected to work between different Python virtual machines, nor to be stable between Python releases.

바이트 코드 명령어들의 목록은 [dis](#) 모듈 문서에 나온다.

class (클래스) 사용자 정의 객체들을 만들기 위한 주형. 클래스 정의는 보통 클래스의 인스턴스를 대상으로 연산하는 메서드 정의들을 포함한다.

classic class Any class which does not inherit from [object](#). See [new-style class](#). Classic classes have been removed in Python 3.

coercion (코어션) The implicit conversion of an instance of one type to another during an operation which involves two arguments of the same type. For example, `int(3.15)` converts the floating point number to the integer 3, but in `3+4.5`, each argument is of a different type (one int, one float), and both must be converted to the same type before they can be added or it will raise a `TypeError`. Coercion between two operands can be performed with the `coerce` built-in function; thus, `3+4.5` is equivalent to calling `operator.add(*coerce(3, 4.5))` and results in `operator.add(3.0, 4.5)`. Without coercion, all arguments of even compatible types would have to be normalized to the same value by the programmer, e.g., `float(3)+4.5` rather than just `3+4.5`.

complex number (복소수) 익숙한 실수 시스템의 확장인데, 모든 숫자가 실수부와 허수부의 합으로 표현된다. 허수부는 실수에 허수 단위 (-1의 제곱근)를 곱한 것인데, 종종 수학에서는 *i* 로, 공학에서는 *j* 로 표기한다. 파이썬은 후자의 표기법을 쓰는 복소수를 기본 지원한다; 허수부는 *j* 접미사를 붙여서 표기한다, 예를 들어, `3+1j`. [math](#) 모듈의 복소수 버전이 필요하다면, [cmath](#) 를 사용한다. 복소수의 활용은 꽤 수준 높은 수학적 기능이다. 필요하다고 느끼지 못한다면, 거의 확실히 무시해도 좋다.

context manager (컨텍스트 관리자) `__enter__()` 와 `__exit__()` 메서드를 정의함으로써 `with` 문에서 보이는 환경을 제어하는 객체. [PEP 343](#) 로 도입되었다.

CPython 파이썬 프로그래밍 언어의 규범적인 구현인데, [python.org](#) 에서 배포된다. 이 구현을 Jython 이나 IronPython 과 같은 다른 것들과 구별할 필요가 있을 때 용어 《CPython》이 사용된다.

decorator (데코레이터) 다른 함수를 돌려주는 함수인데, 보통 `@wrapper` 문법을 사용한 함수 변환으로 적용된다. 데코레이터의 흔한 예는 `classmethod()` 과 `staticmethod()` 다.

데코레이터 문법은 단지 편의 문법일 뿐이다. 다음 두 함수 정의는 의미상으로 동등하다:

```
def f(...):
    ...
f = staticmethod(f)

@staticmethod
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
def f(...):
    ...
```

같은 개념이 클래스에도 존재하지만, 덜 자주 쓰인다. 데코레이터에 대한 더 자세한 내용은 함수 정의와 클래스 정의의 문서화를 보면 된다.

descriptor (디스크립터) Any *new-style* object which defines the methods `__get__()`, `__set__()`, or `__delete__()`. When a class attribute is a descriptor, its special binding behavior is triggered upon attribute lookup. Normally, using `a.b` to get, set or delete an attribute looks up the object named `b` in the class dictionary for `a`, but if `b` is a descriptor, the respective descriptor method gets called. Understanding descriptors is a key to a deep understanding of Python because they are the basis for many features including functions, methods, properties, class methods, static methods, and reference to super classes.

디스크립터의 메서드들에 대한 자세한 내용은 `descriptors` 에 나온다.

dictionary (딕셔너리) An associative array, where arbitrary keys are mapped to values. The keys can be any object with `__hash__()` and `__eq__()` methods. Called a hash in Perl.

dictionary view (딕셔너리 뷰) The objects returned from `dict.viewkeys()`, `dict.viewvalues()`, and `dict.viewitems()` are called dictionary views. They provide a dynamic view on the dictionary's entries, which means that when the dictionary changes, the view reflects these changes. To force the dictionary view to become a full list use `list(dictview)`. See [딕셔너리 뷰 객체](#).

docstring (독스트링) 클래스, 함수, 모듈에서 첫 번째 표현식으로 나타나는 문자열 리터럴. 스위트가 실행될 때는 무시되지만, 컴파일러에 의해 인지되어 둘러싼 클래스, 함수, 모듈의 `__doc__` 어트리뷰트로 삽입된다. 인트로스펙션을 통해 사용할 수 있으므로, 객체의 문서화를 위한 규범적인 장소다.

duck-typing (덕 타이핑) 올바른 인터페이스를 가졌는지 판단하는데 객체의 형을 보지 않는 프로그래밍 스타일; 대신, 단순히 메서드나 어트리뷰트가 호출되거나 사용된다 (《오리처럼 보이고 오리처럼 꺾꺾댄다면, 그것은 오리다.》) 특정한 형 대신에 인터페이스를 강조함으로써, 잘 설계된 코드는 다형적인 치환을 허락함으로써 유연성을 개선할 수 있다. 덕 타이핑은 `type()` 이나 `isinstance()` 을 사용한 검사를 피한다. (하지만, 덕 타이핑이 *추상 베이스 클래스*로 보완될 수 있음에 유의해야 한다.) 대신에, `hasattr()` 검사나 *EAFP* 프로그래밍을 쓴다.

EAFP 허락보다는 용서를 구하기가 쉽다 (Easier to ask for forgiveness than permission). 이 흔히 볼 수 있는 과이즌 코딩 스타일은, 올바른 키나 어트리뷰트의 존재를 가정하고, 그 가정이 틀리면 예외를 잡는다. 이 깔끔하고 빠른 스타일은 많은 `try` 와 `except` 문의 존재로 특징지어진다. 이 테크닉은 C와 같은 다른 많은 언어에서 자주 사용되는 *LBYL* 스타일과 대비된다.

expression (표현식) A piece of syntax which can be evaluated to some value. In other words, an expression is an accumulation of expression elements like literals, names, attribute access, operators or function calls which all return a value. In contrast to many other languages, not all language constructs are expressions. There are also *statements* which cannot be used as expressions, such as `print` or `if`. Assignments are also statements, not expressions.

extension module (확장 모듈) C 나 C++ 로 작성된 모듈인데, 파이썬의 C API를 사용해서 핵심이나 사용자 코드와 상호 작용한다.

file object (파일 객체) 하부 자원에 대해 파일 지향적 API (`read()` 나 `write()` 같은 메서드들) 를 드러내는 객체. 만들어진 방법에 따라, 파일 객체는 실제 디스크 상의 파일이나 다른 저장장치나 통신 장치 (예를 들어, 표준 입출력, 인-메모리 버퍼, 소켓, 파이프, 등등) 에 대한 액세스를 중계할 수 있다. 파일 객체는 파일류 객체 (*file-like objects*) 나 스트림 (*streams*) 이라고도 불린다.

There are actually three categories of file objects: raw binary files, buffered binary files and text files. Their interfaces are defined in the `io` module. The canonical way to create a file object is by using the `open()` function.

file-like object (파일류 객체) 파일 객체 의 비슷한 말.

finder (파인더) An object that tries to find the *loader* for a module. It must implement a method named `find_module()`. See [PEP 302](#) for details.

floor division (정수 나눗셈) 가장 가까운 정수로 내림하는 수학적 나눗셈. 정수 나눗셈 연산자는 `//` 다. 예를 들어, 표현식 `11 // 4` 의 값은 2 가 되지만, 실수 나눗셈은 2.75 를 돌려준다. `(-11) // 4` 가 -2.75 를 내림 한 -3 이 됨에 유의해야 한다. [PEP 238](#) 를 보세요.

function (함수) 호출자에게 어떤 값을 돌려주는 일련의 문장들. 없거나 그 이상의 인자가 전달될 수 있는데, 바디의 실행에 사용될 수 있다. [파라미터](#) 와 [메서드](#) 와 [function](#) 섹션도 보세요.

__future__ A pseudo-module which programmers can use to enable new language features which are not compatible with the current interpreter. For example, the expression `11/4` currently evaluates to 2. If the module in which it is executed had enabled *true division* by executing:

```
from __future__ import division
```

the expression `11/4` would evaluate to 2.75. By importing the `__future__` module and evaluating its variables, you can see when a new feature was first added to the language and when it will become the default:

```
>>> import __future__
>>> __future__.division
_Feature((2, 2, 0, 'alpha', 2), (3, 0, 0, 'alpha', 0), 8192)
```

garbage collection (가비지 수거) The process of freeing memory when it is not used anymore. Python performs garbage collection via reference counting and a cyclic garbage collector that is able to detect and break reference cycles.

generator (제너레이터) A function which returns an iterator. It looks like a normal function except that it contains `yield` statements for producing a series of values usable in a for-loop or that can be retrieved one at a time with the `next()` function. Each `yield` temporarily suspends processing, remembering the location execution state (including local variables and pending try-statements). When the generator resumes, it picks up where it left off (in contrast to functions which start fresh on every invocation).

generator expression (제너레이터 표현식) 이터레이터를 돌려주는 표현식. 루프 변수와 범위를 정의하는 for 표현식과 생략 가능한 if 표현식이 뒤에 붙는 일반 표현식 처럼 보인다. 결합한 표현식은 둘러싼 함수를 위한 값들을 만들어낸다:

```
>>> sum(i*i for i in range(10))           # sum of squares 0, 1, 4, ... 81
285
```

GIL [전역 인터프리터 록](#) 을 보세요.

global interpreter lock (전역 인터프리터 록) 한 번에 오직 하나의 스레드가 파이썬 [바이트 코드](#) 를 실행하도록 보장하기 위해 [CPython](#) 인터프리터가 사용하는 메커니즘. (`dict` 와 같은 중요한 내장형들을 포함하는) 객체 모델이 묵시적으로 동시 액세스에 대해 안전하도록 만들어서 [CPython](#) 구현을 단순하게 만든다. 인터프리터 전체를 로킹하는 것은 인터프리터를 다중스레드화하기 쉽게 만드는 대신, 다중 프로세서 기계가 제공하는 병렬성의 많은 부분을 희생한다.

하지만, 어떤 확장 모듈들은, 표준이나 제삼자 모두, 압축이나 해싱 같은 계산 집약적인 작업을 수행할 때는 GIL 을 반납하도록 설계되었다. 또한, I/O를 할 때는 항상 GIL 을 반납한다.

(훨씬 더 미세하게 공유 데이터를 로킹하는) 《스레드에 자유로운([free-threaded](#))》 인터프리터를 만들고자 하는 과거의 노력은 성공적이지 못했는데, 혼한 단일 프로세서 경우의 성능 저하가 심하기 때문이다. 이 성능 이슈를 극복하는 것은 구현을 훨씬 복잡하게 만들어서 유지 비용이 더 들어갈 것으로 여겨지고 있다.

hashable (해시 가능) An object is *hashable* if it has a hash value which never changes during its lifetime (it needs a `__hash__()` method), and can be compared to other objects (it needs an `__eq__()` or `__cmp__()` method). Hashable objects which compare equal must have the same hash value.

해시 가능성은 객체를 딕셔너리의 키나 집합의 멤버로 사용할 수 있게 하는데, 이 자료 구조들이 내부적으로 해시값을 사용하기 때문이다.

All of Python's immutable built-in objects are hashable, while no mutable containers (such as lists or dictionaries) are. Objects which are instances of user-defined classes are hashable by default; they all compare unequal (except with themselves), and their hash value is derived from their `id()`.

IDLE 파이썬을 위한 통합 개발 환경 (Integrated Development Environment). IDLE은 파이썬의 표준 배포판에 따라오는 기초적인 편집기와 인터프리터 환경이다.

immutable (불변) 고정된 값을 갖는 객체. 불변 객체는 숫자, 문자열, 튜플을 포함한다. 이런 객체들은 변경될 수 없다. 새 값을 저장하려면 새 객체를 만들어야 한다. 변하지 않는 해시값이 있어야 하는 곳에서 중요한 역할을 한다, 예를 들어, 딕셔너리의 키.

integer division Mathematical division discarding any remainder. For example, the expression `11 / 4` currently evaluates to 2 in contrast to the `2.75` returned by float division. Also called *floor division*. When dividing two integers the outcome will always be another integer (having the floor function applied to it). However, if one of the operands is another numeric type (such as a *float*), the result will be coerced (see *coercion*) to a common type. For example, an integer divided by a float will result in a float value, possibly with a decimal fraction. Integer division can be forced by using the `//` operator instead of the `/` operator. See also `__future__`.

importing (임포트) 한 모듈의 파이썬 코드가 다른 모듈의 파이썬 코드에서 사용될 수 있도록 하는 절차.

importer (임포터) 모듈을 찾기도 하고 로드 하기도 하는 객체; 동시에 **파인더** 이자 **로더** 객체다.

interactive (대화형) 파이썬은 대화형 인터프리터를 갖고 있는데, 인터프리터 프롬프트에서 문장과 표현식을 입력할 수 있고, 즉각 실행된 결과를 볼 수 있다는 뜻이다. 인자 없이 단지 `python` 을 실행하라 (컴퓨터의 주메뉴에서 선택하는 것도 가능할 수 있다). 새 아이디어를 검사하거나 모듈과 패키지를 들여다보는 매우 강력한 방법이다 (`help(x)` 를 기억하세요).

interpreted (인터프리티드) 바이트 코드 컴파일러의 존재 때문에 그 구분이 흐릿해지기는 하지만, 파이썬은 컴파일 언어가 아니라 인터프리터 언어다. 이것은 명시적으로 실행 파일을 만들지 않고도, 소스 파일을 직접 실행할 수 있다는 뜻이다. 그 프로그램이 좀 더 천천히 실행되기는 하지만, 인터프리터 언어는 보통 컴파일 언어보다 짧은 개발/디버깅 주기를 갖는다. **대화형** 도 보세요.

iterable (이터러블) An object capable of returning its members one at a time. Examples of iterables include all sequence types (such as `list`, *str*, and *tuple*) and some non-sequence types like *dict* and *file* and objects of any classes you define with an `__iter__()` or `__getitem__()` method. Iterables can be used in a `for` loop and in many other places where a sequence is needed (`zip()`, `map()`, ...). When an iterable object is passed as an argument to the built-in function `iter()`, it returns an iterator for the object. This iterator is good for one pass over the set of values. When using iterables, it is usually not necessary to call `iter()` or deal with iterator objects yourself. The `for` statement does that automatically for you, creating a temporary unnamed variable to hold the iterator for the duration of the loop. See also *iterator*, *sequence*, and *generator*.

iterator (이터레이터) An object representing a stream of data. Repeated calls to the iterator's `next()` method return successive items in the stream. When no more data are available a *StopIteration* exception is raised instead. At this point, the iterator object is exhausted and any further calls to its `next()` method just raise *StopIteration* again. Iterators are required to have an `__iter__()` method that returns the iterator object itself so every iterator is also iterable and may be used in most places where other iterables are accepted. One notable exception is code which attempts multiple iteration passes. A container object (such as a `list`) produces a fresh new iterator each time you pass it to the `iter()` function or use it in a `for` loop. Attempting this with an iterator will just return the same exhausted iterator object used in the previous iteration pass, making it appear like an empty container.

이터레이터 형 에 더 자세한 내용이 있다.

key function (키 함수) 키 함수 또는 콜레이션 (collation) 함수는 정렬 (sorting) 이나 배열 (ordering) 에 사용되는 값을 돌려주는 콜러블이다. 예를 들어, `locale.strxfrm()` 은 로케일 특정 방식을 따르는 정렬 키를 만드는 데 사용된다.

A number of tools in Python accept key functions to control how elements are ordered or grouped. They include `min()`, `max()`, `sorted()`, `list.sort()`, `heapq.nsmallest()`, `heapq.nlargest()`, and `itertools.groupby()`.

There are several ways to create a key function. For example, the `str.lower()` method can serve as a key function for case insensitive sorts. Alternatively, an ad-hoc key function can be built from a `lambda` expression such as `lambda r: (r[0], r[2])`. Also, the `operator` module provides three key function constructors: `attrgetter()`, `itemgetter()`, and `methodcaller()`. See the Sorting HOW TO for examples of how to create and use key functions.

keyword argument (키워드 인자) 인자를 보세요.

lambda (람다) 호출될 때 값이 구해지는 하나의 표현식으로 구성된 이름 없는 인라인 함수. 람다 함수를 만드는 문법은 `lambda [parameters]: expression` 이다.

LBYL 뛰기 전에 보라 (Look before you leap). 이 코딩 스타일은 호출이나 조회를 하기 전에 명시적으로 사전 조건들을 검사한다. 이 스타일은 *EAFP* 접근법과 대비되고, 많은 `if` 문의 존재로 특징지어진다.

다중 스레드 환경에서, LBYL 접근법은 《보기》와 《뛰기》 간에 경쟁 조건을 만들게 될 위험이 있다. 예를 들어, 코드 `if key in mapping: return mapping[key]` 는 검사 후에, 하지만 조회 전에, 다른 스레드가 `key` 를 `mapping` 에서 제거하면 실패할 수 있다. 이런 이슈는 록이나 *EAFP* 접근법을 사용함으로써 해결될 수 있다.

list (리스트) A built-in Python *sequence*. Despite its name it is more akin to an array in other languages than to a linked list since access to elements is $O(1)$.

list comprehension (리스트 컴프리헨션) A compact way to process all or part of the elements in a sequence and return a list with the results. `result = ["0x%02x" % x for x in range(256) if x % 2 == 0]` generates a list of strings containing even hex numbers (0x..) in the range from 0 to 255. The `if` clause is optional. If omitted, all elements in `range(256)` are processed.

loader (로더) An object that loads a module. It must define a method named `load_module()`. A loader is typically returned by a *finder*. See **PEP 302** for details.

magic method An informal synonym for *special method*.

mapping (매핑) A container object that supports arbitrary key lookups and implements the methods specified in the *Mapping* or *MutableMapping abstract base classes*. Examples include `dict`, `collections.defaultdict`, `collections.OrderedDict` and `collections.Counter`.

metaclass (메타 클래스) 클래스의 클래스. 클래스 정의는 클래스 이름, 클래스 디렉터리, 베이스 클래스들의 목록을 만든다. 메타 클래스는 이 세 인자를 받아서 클래스를 만드는 책임을 진다. 대부분의 객체 지향형 프로그래밍 언어들은 기본 구현을 제공한다. 파이썬을 특별하게 만드는 것은 커스텀 메타 클래스를 만들 수 있다는 것이다. 대부분 사용자에게는 이 도구가 전혀 필요 없지만, 필요가 생길 때, 메타 클래스는 강력하고 우아한 해법을 제공한다. 어트리뷰트 액세스의 로깅 (logging), 스레드 안전성의 추가, 객체 생성 추적, 싱글톤 구현과 많은 다른 작업에 사용됐다.

metaclasses 에서 더 자세한 내용을 찾을 수 있다.

method (메서드) 클래스 바디 안에서 정의되는 함수. 그 클래스의 인스턴스의 어트리뷰트로서 호출되면, 그 메서드는 첫 번째 인자 (보통 `self` 라고 불린다) 로 인스턴스 객체를 받는다. 함수와 중첩된 스코프를 보세요.

method resolution order (메서드 결정 순서) 메서드 결정 순서는 조회하는 동안 멤버를 검색하는 베이스 클래스들의 순서다. 2.3 릴리스부터 파이썬 인터프리터에 사용된 알고리즘의 상세한 내용은 *The Python 2.3 Method Resolution Order* 를 보면 된다.

module (모듈) 파이썬 코드의 조직화 단위를 담당하는 객체. 모듈은 임의의 파이썬 객체들을 담는 이름 공간을 갖는다. 모듈은 임포트 절차에 의해 파이썬으로 로드된다.

패키지 도 보세요.

MRO 메서드 결정 순서를 보세요.

mutable (가변) 가변 객체는 값이 변할 수 있지만 `id()` 는 일정하게 유지한다. 불변도 보세요.

named tuple (네임드 튜플) 인덱싱할 수 있는 요소들을 이름 붙은 어트리뷰트로도 액세스할 수 있는 모든 튜플류 클래스(예를 들어, `time.localtime()` 은 `year` 가 `t[0]` 처럼 인덱스로도, `t.tm_year` 처럼 어트리뷰트로도 액세스할 수 있는 튜플류 객체를 돌려준다.)

네임드 튜플은 `time.struct_time` 같은 내장형일 수도, 일반 클래스 정의로 만들 수도 있다. 모든 기능이 구현된 네임드 튜플을 팩토리 함수 `collections.namedtuple()` 로도 만들 수 있다. 마지막 접근법은 `Employee(name='jones', title='programmer')` 와 같은 스스로 문서로 만드는 `repr` 과 같은 확장 기능도 자동 제공한다.

namespace (이름 공간) The place where a variable is stored. Namespaces are implemented as dictionaries. There are the local, global and built-in namespaces as well as nested namespaces in objects (in methods). Namespaces support modularity by preventing naming conflicts. For instance, the functions `__builtin__.open()` and `os.open()` are distinguished by their namespaces. Namespaces also aid readability and maintainability by making it clear which module implements a function. For instance, writing `random.seed()` or `itertools.izip()` makes it clear that those functions are implemented by the `random` and `itertools` modules, respectively.

nested scope (중첩된 스코프) The ability to refer to a variable in an enclosing definition. For instance, a function defined inside another function can refer to variables in the outer function. Note that nested scopes work only for reference and not for assignment which will always write to the innermost scope. In contrast, local variables both read and write in the innermost scope. Likewise, global variables read and write to the global namespace.

new-style class (뉴스타일 클래스) Any class which inherits from `object`. This includes all built-in types like `list` and `dict`. Only new-style classes can use Python's newer, versatile features like `__slots__`, descriptors, properties, and `__getattr__()`.

More information can be found in newstyle.

object (객체) 상태(어트리뷰트나 값)를 갖고 동작(메서드)이 정의된 모든 데이터. 또한, 모든 뉴스타일 클래스의 최종적인 베이스 클래스다.

package (패키지) 서브 모듈들이나, 재귀적으로 서브 패키지들을 포함할 수 있는 파이썬 모듈. 기술적으로, 패키지는 `__path__` 어트리뷰트가 있는 파이썬 모듈이다.

parameter (파라미터) A named entity in a *function* (or method) definition that specifies an *argument* (or in some cases, arguments) that the function can accept. There are four types of parameters:

- 위치-키워드 (*positional-or-keyword*): 위치 인자 나 키워드 인자로 전달될 수 있는 인자를 지정한다. 이것이 기본 형태의 파라미터다, 예를 들어 다음에서 `foo` 와 `bar`:

```
def func(foo, bar=None): ...
```

- 위치-전용 (*positional-only*): 위치로만 제공될 수 있는 인자를 지정한다. 파이썬은 위치-전용 파라미터를 정의하는 문법을 갖고 있지 않다. 하지만, 어떤 매장 함수들은 위치-전용 파라미터를 갖는다(예를 들어, `abs()`).
- 가변-위치 (*var-positional*): (다른 파라미터들에 의해서 이미 받아들여진 위치 인자들에 더해) 제공될 수 있는 위치 인자들의 임의의 시퀀스를 지정한다. 이런 파라미터는 파라미터 이름에 `*` 를 앞에 붙여서 정의될 수 있다, 예를 들어 다음에서 `args`:

```
def func(*args, **kwargs): ...
```

- 가변-키워드 (*var-keyword*): (다른 파라미터들에 의해서 이미 받아들여진 키워드 인자들에 더해) 제공될 수 있는 임의의 개수 키워드 인자들을 지정한다. 이런 파라미터는 파라미터 이름에 `**` 를 앞에 붙여서 정의될 수 있다, 예를 들어 위의 예에서 `kwargs`.

파라미터는 선택적 인자들을 위한 기본값뿐만 아니라 선택적이거나 필수 인자들을 지정할 수 있다.

See also the [argument](#) glossary entry, the FAQ question on the difference between arguments and parameters, and the function section.

PEP 파이썬 개선 제안. PEP는 파이썬 커뮤니티에 정보를 제공하거나 파이썬 또는 그 프로세스 또는 환경에 대한 새로운 기능을 설명하는 설계 문서다. PEP는 제안된 기능에 대한 간결한 기술 사양 및 근거를 제공해야 한다.

PEP는 주요 새로운 기능을 제안하고 문제에 대한 커뮤니티 입력을 수집하며 파이썬에 들어간 설계 결정을 문서로 만들기 위한 기본 메커니즘이다. PEP 작성자는 커뮤니티 내에서 합의를 구축하고 반대 의견을 문서화 할 책임이 있다.

PEP 1 참조하세요.

positional argument (위치 인자) [인자](#)를 보세요.

Python 3000 (파이썬 3000) 파이썬 3.x 배포 라인의 별명 (버전 3의 배포가 먼 미래의 이야기던 시절에 만들어진 이름이다.) 이것을 《Py3k》로 줄여 쓰기도 한다.

Pythonic (파이썬다운) 다른 언어들에서 일반적인 개념들을 사용해서 코드를 구현하는 대신, 파이썬 언어에서 가장 자주 사용되는 이디엄들을 가까이 따르는 아이디어나 코드 조작. 예를 들어, 파이썬에서 자주 쓰는 이디엄은 `for` 문을 사용해서 이터러블의 모든 요소로 루핑하는 것이다. 다른 많은 언어에는 이런 종류의 구성물이 없으므로, 파이썬에 익숙하지 않은 사람들은 대신에 숫자 카운터를 사용하기도 한다:

```
for i in range(len(food)):
    print food[i]
```

더 깔끔한, 파이썬다운 방법은 이렇다:

```
for piece in food:
    print piece
```

reference count (참조 횟수) 객체에 대한 참조의 개수. 객체의 참조 횟수가 0으로 떨어지면, 메모리가 반납된다. 참조 횟수 추적은 일반적으로 파이썬 코드에 노출되지 않지만, *CPython* 구현의 핵심 요소다. `sys` 모듈은 특정 객체의 참조 횟수를 돌려주는 `getrefcount()` 을 정의한다.

__slots__ A declaration inside a *new-style class* that saves memory by pre-declaring space for instance attributes and eliminating instance dictionaries. Though popular, the technique is somewhat tricky to get right and is best reserved for rare cases where there are large numbers of instances in a memory-critical application.

sequence (시퀀스) An *iterable* which supports efficient element access using integer indices via the `__getitem__()` special method and defines a `len()` method that returns the length of the sequence. Some built-in sequence types are `list`, `str`, `tuple`, and `unicode`. Note that `dict` also supports `__getitem__()` and `__len__()`, but is considered a mapping rather than a sequence because the lookups use arbitrary *immutable* keys rather than integers.

slice (슬라이스) An object usually containing a portion of a *sequence*. A slice is created using the subscript notation, `[]` with colons between numbers when several are given, such as in `variable_name[1:3:5]`. The bracket (subscript) notation uses *slice* objects internally (or in older versions, `__getslice__()` and `__setslice__()`).

special method (특수 메서드) 파이썬이 형에 어떤 연산을, 덧셈 같은, 실행할 때 묵시적으로 호출되는 메서드. 이런 메서드는 두 개의 밑줄로 시작하고 끝나는 이름을 갖고 있다. 특수 메서드는 `specialnames` 에 문서로 만들어져 있다.

statement (문장) 문장은 스위트(코드의 《블록(block)》)를 구성하는 부분이다. 문장은 *표현식* 이거나 키워드를 사용하는 여러 가지 구조물 중의 하나다. 가령 `if`, `while`, `for`.

struct sequence (구조체 시퀀스) A tuple with named elements. Struct sequences expose an interface similar to *named tuple* in that elements can be accessed either by index or as an attribute. However, they do not have any of the named tuple methods like `_make()` or `_asdict()`. Examples of struct sequences include `sys.float_info` and the return value of `os.stat()`.

triple-quoted string (삼중 따옴표 된 문자열) 따옴표 (《) 나 작은따옴표 (〈) 세 개로 둘러싸인 문자열. 그냥 따옴표 하나로 둘러싸인 문자열에 없는 기능을 제공하지는 않지만, 여러 가지 이유에서 쓸모가 있다. 이스케이프 되지 않은 작은따옴표나 큰따옴표를 문자열 안에 포함할 수 있도록 하고, 연결 문자를 쓰지 않고도 여러 줄에 걸쳐 쓸 수 있는데, 독스트링을 쓸 때 특히 쓸모 있다.

type (형) 파이썬 객체의 형은 그것이 어떤 종류의 객체인지를 결정한다; 모든 객체는 형이 있다. 객체의 형은 `__class__` 어트리뷰트로 액세스할 수 있거나 `type(obj)` 로 얻을 수 있다.

universal newlines (유니버설 줄 넘김) A manner of interpreting text streams in which all of the following are recognized as ending a line: the Unix end-of-line convention `'\n'`, the Windows convention `'\r\n'`, and the old Macintosh convention `'\r'`. See [PEP 278](#) and [PEP 3116](#), as well as `str.splitlines()` for an additional use.

virtual environment (가상 환경) 파이썬 사용자와 응용 프로그램이, 같은 시스템에서 실행되는 다른 파이썬 응용 프로그램들의 동작에 영향을 주지 않으면서, 파이썬 배포 패키지들을 설치하거나 업그레이드하는 것을 가능하게 하는, 협력적으로 격리된 실행 환경.

virtual machine (가상 기계) 소프트웨어만으로 정의된 컴퓨터. 파이썬의 가상 기계는 바이트 코드 컴파일러가 출력하는 [바이트 코드](#) 를 실행한다.

Zen of Python (파이썬 젠) 파이썬 디자인 원리와 철학들의 목록인데, 언어를 이해하고 사용하는 데 도움이 된다. 이 목록은 대화형 프롬프트에서 `《import this》` 를 입력하면 보인다.

About these documents

These documents are generated from [reStructuredText](#) sources by [Sphinx](#), a document processor specifically written for the Python documentation.

Development of the documentation and its toolchain is an entirely volunteer effort, just like Python itself. If you want to contribute, please take a look at the [reporting-bugs](#) page for information on how to do so. New volunteers are always welcome!

Many thanks go to:

- Fred L. Drake, Jr., the creator of the original Python documentation toolset and writer of much of the content;
- the [Docutils](#) project for creating reStructuredText and the Docutils suite;
- Fredrik Lundh for his [Alternative Python Reference](#) project from which Sphinx got many good ideas.

B.1 Contributors to the Python Documentation

Many people have contributed to the Python language, the Python standard library, and the Python documentation. See [Misc/ACKS](#) in the Python source distribution for a partial list of contributors.

It is only with the input and contributions of the Python community that Python has such wonderful documentation – Thank You!

History and License

C.1 History of the software

Python was created in the early 1990s by Guido van Rossum at Stichting Mathematisch Centrum (CWI, see <https://www.cwi.nl/>) in the Netherlands as a successor of a language called ABC. Guido remains Python's principal author, although it includes many contributions from others.

In 1995, Guido continued his work on Python at the Corporation for National Research Initiatives (CNRI, see <https://www.cnri.reston.va.us/>) in Reston, Virginia where he released several versions of the software.

In May 2000, Guido and the Python core development team moved to BeOpen.com to form the BeOpen PythonLabs team. In October of the same year, the PythonLabs team moved to Digital Creations (now Zope Corporation; see <https://www.zope.org/>). In 2001, the Python Software Foundation (PSF, see <https://www.python.org/psf/>) was formed, a non-profit organization created specifically to own Python-related Intellectual Property. Zope Corporation is a sponsoring member of the PSF.

All Python releases are Open Source (see <https://opensource.org/> for the Open Source Definition). Historically, most, but not all, Python releases have also been GPL-compatible; the table below summarizes the various releases.

Release	Derived from	Year	Owner	GPL compatible?
0.9.0 thru 1.2	n/a	1991-1995	CWI	yes
1.3 thru 1.5.2	1.2	1995-1999	CNRI	yes
1.6	1.5.2	2000	CNRI	no
2.0	1.6	2000	BeOpen.com	no
1.6.1	1.6	2001	CNRI	no
2.1	2.0+1.6.1	2001	PSF	no
2.0.1	2.0+1.6.1	2001	PSF	yes
2.1.1	2.1+2.0.1	2001	PSF	yes
2.1.2	2.1.1	2002	PSF	yes
2.1.3	2.1.2	2002	PSF	yes
2.2 and above	2.1.1	2001-now	PSF	yes

참고: GPL-compatible doesn't mean that we're distributing Python under the GPL. All Python licenses, unlike the GPL, let you distribute a modified version without making your changes open source. The GPL-compatible licenses make it possible to combine Python with other software that is released under the GPL; the others don't.

Thanks to the many outside volunteers who have worked under Guido's direction to make these releases possible.

C.2 Terms and conditions for accessing or otherwise using Python

C.2.1 PSF LICENSE AGREEMENT FOR PYTHON 2.7.17

1. This LICENSE AGREEMENT is between the Python Software Foundation ("PSF"),
→and
the Individual or Organization ("Licensee") accessing and otherwise using
→Python
2.7.17 software in source or binary form and its associated documentation.
2. Subject to the terms and conditions of this License Agreement, PSF hereby
grants Licensee a nonexclusive, royalty-free, world-wide license to
→reproduce,
analyze, test, perform and/or display publicly, prepare derivative works,
distribute, and otherwise use Python 2.7.17 alone or in any derivative
version, provided, however, that PSF's License Agreement and PSF's notice
→of
copyright, i.e., "Copyright © 2001-2020 Python Software Foundation; All
→Rights
Reserved" are retained in Python 2.7.17 alone or in any derivative version
prepared by Licensee.
3. In the event Licensee prepares a derivative work that is based on or
incorporates Python 2.7.17 or any part thereof, and wants to make the
derivative work available to others as provided herein, then Licensee
→hereby
agrees to include in any such work a brief summary of the changes made to
→Python
2.7.17.
4. PSF is making Python 2.7.17 available to Licensee on an "AS IS" basis.
PSF MAKES NO REPRESENTATIONS OR WARRANTIES, EXPRESS OR IMPLIED. BY WAY OF
EXAMPLE, BUT NOT LIMITATION, PSF MAKES NO AND DISCLAIMS ANY REPRESENTATION
→OR
WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE OR THAT
→THE
USE OF PYTHON 2.7.17 WILL NOT INFRINGE ANY THIRD PARTY RIGHTS.
5. PSF SHALL NOT BE LIABLE TO LICENSEE OR ANY OTHER USERS OF PYTHON 2.7.17
FOR ANY INCIDENTAL, SPECIAL, OR CONSEQUENTIAL DAMAGES OR LOSS AS A RESULT
→OF
MODIFYING, DISTRIBUTING, OR OTHERWISE USING PYTHON 2.7.17, OR ANY
→DERIVATIVE
THEREOF, EVEN IF ADVISED OF THE POSSIBILITY THEREOF.

6. This License Agreement will automatically terminate upon a material breach_↵
 ↪ of
 its terms and conditions.
7. Nothing in this License Agreement shall be deemed to create any_↵
 ↪ relationship
 of agency, partnership, or joint venture between PSF and Licensee. This_↵
 ↪ License
 Agreement does not grant permission to use PSF trademarks or trade name in_↵
 ↪ a
 trademark sense to endorse or promote products or services of Licensee, or_↵
 ↪ any
 third party.
8. By copying, installing or otherwise using Python 2.7.17, Licensee agrees
 to be bound by the terms and conditions of this License Agreement.

C.2.2 BEOPEN.COM LICENSE AGREEMENT FOR PYTHON 2.0

BEOPEN PYTHON OPEN SOURCE LICENSE AGREEMENT VERSION 1

1. This LICENSE AGREEMENT is between BeOpen.com ("BeOpen"), having an office at 160 Saratoga Avenue, Santa Clara, CA 95051, and the Individual or Organization ("Licensee") accessing and otherwise using this software in source or binary form and its associated documentation ("the Software").
2. Subject to the terms and conditions of this BeOpen Python License Agreement, BeOpen hereby grants Licensee a non-exclusive, royalty-free, world-wide license to reproduce, analyze, test, perform and/or display publicly, prepare derivative works, distribute, and otherwise use the Software alone or in any derivative version, provided, however, that the BeOpen Python License is retained in the Software, alone or in any derivative version prepared by Licensee.
3. BeOpen is making the Software available to Licensee on an "AS IS" basis. BEOPEN MAKES NO REPRESENTATIONS OR WARRANTIES, EXPRESS OR IMPLIED. BY WAY OF EXAMPLE, BUT NOT LIMITATION, BEOPEN MAKES NO AND DISCLAIMS ANY REPRESENTATION OR WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE OR THAT THE USE OF THE SOFTWARE WILL NOT INFRINGE ANY THIRD PARTY RIGHTS.
4. BEOPEN SHALL NOT BE LIABLE TO LICENSEE OR ANY OTHER USERS OF THE SOFTWARE FOR ANY INCIDENTAL, SPECIAL, OR CONSEQUENTIAL DAMAGES OR LOSS AS A RESULT OF USING, MODIFYING OR DISTRIBUTING THE SOFTWARE, OR ANY DERIVATIVE THEREOF, EVEN IF ADVISED OF THE POSSIBILITY THEREOF.
5. This License Agreement will automatically terminate upon a material breach of its terms and conditions.
6. This License Agreement shall be governed by and interpreted in all respects by the law of the State of California, excluding conflict of law provisions. Nothing in this License Agreement shall be deemed to create any relationship of agency, partnership, or joint venture between BeOpen and Licensee. This License Agreement does not grant permission to use BeOpen trademarks or trade names in a trademark sense to endorse or promote products or services of Licensee, or any third party. As an exception, the "BeOpen Python" logos available at

(다음 페이지에 계속)

(이전 페이지에서 계속)

`http://www.pythonlabs.com/logos.html` may be used according to the permissions granted on that web page.

7. By copying, installing or otherwise using the software, Licensee agrees to be bound by the terms and conditions of this License Agreement.

C.2.3 CNRI LICENSE AGREEMENT FOR PYTHON 1.6.1

1. This LICENSE AGREEMENT is between the Corporation for National Research Initiatives, having an office at 1895 Preston White Drive, Reston, VA 20191 ("CNRI"), and the Individual or Organization ("Licensee") accessing and otherwise using Python 1.6.1 software in source or binary form and its associated documentation.
2. Subject to the terms and conditions of this License Agreement, CNRI hereby grants Licensee a nonexclusive, royalty-free, world-wide license to reproduce, analyze, test, perform and/or display publicly, prepare derivative works, distribute, and otherwise use Python 1.6.1 alone or in any derivative version, provided, however, that CNRI's License Agreement and CNRI's notice of copyright, i.e., "Copyright © 1995-2001 Corporation for National Research Initiatives; All Rights Reserved" are retained in Python 1.6.1 alone or in any derivative version prepared by Licensee. Alternately, in lieu of CNRI's License Agreement, Licensee may substitute the following text (omitting the quotes): "Python 1.6.1 is made available subject to the terms and conditions in CNRI's License Agreement. This Agreement together with Python 1.6.1 may be located on the Internet using the following unique, persistent identifier (known as a handle): 1895.22/1013. This Agreement may also be obtained from a proxy server on the Internet using the following URL: `http://hdl.handle.net/1895.22/1013`."
3. In the event Licensee prepares a derivative work that is based on or incorporates Python 1.6.1 or any part thereof, and wants to make the derivative work available to others as provided herein, then Licensee hereby agrees to include in any such work a brief summary of the changes made to Python 1.6.1.
4. CNRI is making Python 1.6.1 available to Licensee on an "AS IS" basis. CNRI MAKES NO REPRESENTATIONS OR WARRANTIES, EXPRESS OR IMPLIED. BY WAY OF EXAMPLE, BUT NOT LIMITATION, CNRI MAKES NO AND DISCLAIMS ANY REPRESENTATION OR WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE OR THAT THE USE OF PYTHON 1.6.1 WILL NOT INFRINGE ANY THIRD PARTY RIGHTS.
5. CNRI SHALL NOT BE LIABLE TO LICENSEE OR ANY OTHER USERS OF PYTHON 1.6.1 FOR ANY INCIDENTAL, SPECIAL, OR CONSEQUENTIAL DAMAGES OR LOSS AS A RESULT OF MODIFYING, DISTRIBUTING, OR OTHERWISE USING PYTHON 1.6.1, OR ANY DERIVATIVE THEREOF, EVEN IF ADVISED OF THE POSSIBILITY THEREOF.
6. This License Agreement will automatically terminate upon a material breach of its terms and conditions.
7. This License Agreement shall be governed by the federal intellectual property law of the United States, including without limitation the federal copyright law, and, to the extent such U.S. federal law does not apply, by the law of the Commonwealth of Virginia, excluding Virginia's conflict of law provisions. Notwithstanding the foregoing, with regard to derivative works based on Python 1.6.1 that incorporate non-separable material that was previously distributed

(다음 페이지에 계속)

(이전 페이지에서 계속)

under the GNU General Public License (GPL), the law of the Commonwealth of Virginia shall govern this License Agreement only as to issues arising under or with respect to Paragraphs 4, 5, and 7 of this License Agreement. Nothing in this License Agreement shall be deemed to create any relationship of agency, partnership, or joint venture between CNRI and Licensee. This License Agreement does not grant permission to use CNRI trademarks or trade name in a trademark sense to endorse or promote products or services of Licensee, or any third party.

8. By clicking on the "ACCEPT" button where indicated, or by copying, installing or otherwise using Python 1.6.1, Licensee agrees to be bound by the terms and conditions of this License Agreement.

C.2.4 CWI LICENSE AGREEMENT FOR PYTHON 0.9.0 THROUGH 1.2

Copyright © 1991 - 1995, Stichting Mathematisch Centrum Amsterdam, The Netherlands. All rights reserved.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Stichting Mathematisch Centrum or CWI not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission.

STICHTING MATHEMATISCH CENTRUM DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS, IN NO EVENT SHALL STICHTING MATHEMATISCH CENTRUM BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

C.3 Licenses and Acknowledgements for Incorporated Software

This section is an incomplete, but growing list of licenses and acknowledgements for third-party software incorporated in the Python distribution.

C.3.1 Mersenne Twister

The `_random` module includes code based on a download from <http://www.math.sci.hiroshima-u.ac.jp/~m-mat/MT/MT2002/emt19937ar.html>. The following are the verbatim comments from the original code:

A C-program for MT19937, with initialization improved 2002/1/26.
Coded by Takuji Nishimura and Makoto Matsumoto.

Before using, initialize the state by using `init_genrand(seed)`
or `init_by_array(init_key, key_length)`.

(다음 페이지에 계속)

(이전 페이지에서 계속)

Copyright (C) 1997 - 2002, Makoto Matsumoto and Takuji Nishimura,
All rights reserved.

Redistribution and use in source and binary forms, with or without
modification, are permitted provided that the following conditions
are met:

1. Redistributions of source code must retain the above copyright
notice, this list of conditions and the following disclaimer.
2. Redistributions in binary form must reproduce the above copyright
notice, this list of conditions and the following disclaimer in the
documentation and/or other materials provided with the distribution.
3. The names of its contributors may not be used to endorse or promote
products derived from this software without specific prior written
permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS
"AS IS" AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT
LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR
A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE COPYRIGHT OWNER OR
CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL,
EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO,
PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR
PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF
LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING
NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS
SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

Any feedback is very welcome.

<http://www.math.sci.hiroshima-u.ac.jp/~m-mat/MT/emt.html>

email: m-mat @ math.sci.hiroshima-u.ac.jp (remove space)

C.3.2 Sockets

The *socket* module uses the functions, `getaddrinfo()`, and `getnameinfo()`, which are coded in separate
source files from the WIDE Project, <http://www.wide.ad.jp/>.

Copyright (C) 1995, 1996, 1997, and 1998 WIDE Project.
All rights reserved.

Redistribution and use in source and binary forms, with or without
modification, are permitted provided that the following conditions
are met:

1. Redistributions of source code must retain the above copyright
notice, this list of conditions and the following disclaimer.
2. Redistributions in binary form must reproduce the above copyright
notice, this list of conditions and the following disclaimer in the
documentation and/or other materials provided with the distribution.
3. Neither the name of the project nor the names of its contributors
may be used to endorse or promote products derived from this software
without specific prior written permission.

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
THIS SOFTWARE IS PROVIDED BY THE PROJECT AND CONTRIBUTORS ``AS IS'' AND
ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE
IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE
ARE DISCLAIMED.  IN NO EVENT SHALL THE PROJECT OR CONTRIBUTORS BE LIABLE
FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL
DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS
OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION)
HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT
LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY
OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF
SUCH DAMAGE.
```

C.3.3 Floating point exception control

The source for the *fpectl* module includes the following notice:

```
-----
/                               Copyright (c) 1996.                               \
|                               The Regents of the University of California.          |
|                               All rights reserved.                                |
|                                                                                 |
|  Permission to use, copy, modify, and distribute this software for               |
|  any purpose without fee is hereby granted, provided that this en-               |
|  tire notice is included in all copies of any software which is or               |
|  includes a copy or modification of this software and in all                     |
|  copies of the supporting documentation for such software.                       |
|                                                                                 |
|  This work was produced at the University of California, Lawrence                  |
|  Livermore National Laboratory under contract no. W-7405-ENG-48                   |
|  between the U.S. Department of Energy and The Regents of the                    |
|  University of California for the operation of UC LLNL.                          |
|                                                                                 |
|                               DISCLAIMER                                           |
|                                                                                 |
|  This software was prepared as an account of work sponsored by an                 |
|  agency of the United States Government. Neither the United States               |
|  Government nor the University of California nor any of their em-                 |
|  ployees, makes any warranty, express or implied, or assumes any                 |
|  liability or responsibility for the accuracy, completeness, or                   |
|  usefulness of any information, apparatus, product, or process                    |
|  disclosed, or represents that its use would not infringe                       |
|  privately-owned rights. Reference herein to any specific commer-                 |
|  cial products, process, or service by trade name, trademark,                    |
|  manufacturer, or otherwise, does not necessarily constitute or                  |
|  imply its endorsement, recommendation, or favoring by the United               |
|  States Government or the University of California. The views and                 |
|  opinions of authors expressed herein do not necessarily state or                 |
|  reflect those of the United States Government or the University                  |
|  of California, and shall not be used for advertising or product                 |
|  endorsement purposes.                                                           |
\-----
```

C.3.4 MD5 message digest algorithm

The source code for the `md5` module contains the following notice:

```
Copyright (C) 1999, 2002 Aladdin Enterprises. All rights reserved.

This software is provided 'as-is', without any express or implied
warranty. In no event will the authors be held liable for any damages
arising from the use of this software.

Permission is granted to anyone to use this software for any purpose,
including commercial applications, and to alter it and redistribute it
freely, subject to the following restrictions:

1. The origin of this software must not be misrepresented; you must not
   claim that you wrote the original software. If you use this software
   in a product, an acknowledgment in the product documentation would be
   appreciated but is not required.
2. Altered source versions must be plainly marked as such, and must not be
   misrepresented as being the original software.
3. This notice may not be removed or altered from any source distribution.

L. Peter Deutsch
ghost@aladdin.com

Independent implementation of MD5 (RFC 1321).

This code implements the MD5 Algorithm defined in RFC 1321, whose
text is available at
    http://www.ietf.org/rfc/rfc1321.txt
The code is derived from the text of the RFC, including the test suite
(section A.5) but excluding the rest of Appendix A. It does not include
any code or documentation that is identified in the RFC as being
copyrighted.

The original and principal author of md5.h is L. Peter Deutsch
<ghost@aladdin.com>. Other authors are noted in the change history
that follows (in reverse chronological order):

2002-04-13 lpd Removed support for non-ANSI compilers; removed
           references to Ghostscript; clarified derivation from RFC 1321;
           now handles byte order either statically or dynamically.
1999-11-04 lpd Edited comments slightly for automatic TOC extraction.
1999-10-18 lpd Fixed typo in header comment (ansi2knr rather than md5);
           added conditionalization for C++ compilation from Martin
           Porschke <porschke@bnl.gov>.
1999-05-03 lpd Original version.
```

C.3.5 Asynchronous socket services

The *asynchat* and *asyncore* modules contain the following notice:

Copyright 1996 by Sam Rushing

All Rights Reserved

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Sam Rushing not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission.

SAM RUSHING DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS, IN NO EVENT SHALL SAM RUSHING BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

C.3.6 Cookie management

The *Cookie* module contains the following notice:

Copyright 2000 by Timothy O'Malley <timo@alum.mit.edu>

All Rights Reserved

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Timothy O'Malley not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission.

Timothy O'Malley DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS, IN NO EVENT SHALL Timothy O'Malley BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

C.3.7 Execution tracing

The `trace` module contains the following notice:

```
portions copyright 2001, Autonomous Zones Industries, Inc., all rights...
err... reserved and offered to the public under the terms of the
Python 2.2 license.
Author: Zooko O'Whielacronx
http://zooko.com/
mailto:zooko@zooko.com

Copyright 2000, Mojam Media, Inc., all rights reserved.
Author: Skip Montanaro

Copyright 1999, Bioreason, Inc., all rights reserved.
Author: Andrew Dalke

Copyright 1995-1997, Automatrix, Inc., all rights reserved.
Author: Skip Montanaro

Copyright 1991-1995, Stichting Mathematisch Centrum, all rights reserved.

Permission to use, copy, modify, and distribute this Python software and
its associated documentation for any purpose without fee is hereby
granted, provided that the above copyright notice appears in all copies,
and that both that copyright notice and this permission notice appear in
supporting documentation, and that the name of neither Automatrix,
Bioreason or Mojam Media be used in advertising or publicity pertaining to
distribution of the software without specific, written prior permission.
```

C.3.8 UUencode and UUdecode functions

The `uu` module contains the following notice:

```
Copyright 1994 by Lance Ellinghouse
Cathedral City, California Republic, United States of America.
    All Rights Reserved
Permission to use, copy, modify, and distribute this software and its
documentation for any purpose and without fee is hereby granted,
provided that the above copyright notice appear in all copies and that
both that copyright notice and this permission notice appear in
supporting documentation, and that the name of Lance Ellinghouse
not be used in advertising or publicity pertaining to distribution
of the software without specific, written prior permission.
LANCE ELLINGHOUSE DISCLAIMS ALL WARRANTIES WITH REGARD TO
THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND
FITNESS, IN NO EVENT SHALL LANCE ELLINGHOUSE CENTRUM BE LIABLE
FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES
WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN
ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT
OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

Modified by Jack Jansen, CWI, July 1995:
- Use binascii module to do the actual line-by-line conversion
  between ascii and binary. This results in a 1000-fold speedup. The C
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
version is still 5 times faster, though.
- Arguments more compliant with Python standard
```

C.3.9 XML Remote Procedure Calls

The `xmlrpclib` module contains the following notice:

```
The XML-RPC client interface is

Copyright (c) 1999-2002 by Secret Labs AB
Copyright (c) 1999-2002 by Fredrik Lundh

By obtaining, using, and/or copying this software and/or its
associated documentation, you agree that you have read, understood,
and will comply with the following terms and conditions:

Permission to use, copy, modify, and distribute this software and
its associated documentation for any purpose and without fee is
hereby granted, provided that the above copyright notice appears in
all copies, and that both that copyright notice and this permission
notice appear in supporting documentation, and that the name of
Secret Labs AB or the author not be used in advertising or publicity
pertaining to distribution of the software without specific, written
prior permission.

SECRET LABS AB AND THE AUTHOR DISCLAIMS ALL WARRANTIES WITH REGARD
TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANT-
ABILITY AND FITNESS.  IN NO EVENT SHALL SECRET LABS AB OR THE AUTHOR
BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY
DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS,
WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS
ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE
OF THIS SOFTWARE.
```

C.3.10 test_epoll

The `test_epoll` contains the following notice:

```
Copyright (c) 2001-2006 Twisted Matrix Laboratories.

Permission is hereby granted, free of charge, to any person obtaining
a copy of this software and associated documentation files (the
"Software"), to deal in the Software without restriction, including
without limitation the rights to use, copy, modify, merge, publish,
distribute, sublicense, and/or sell copies of the Software, and to
permit persons to whom the Software is furnished to do so, subject to
the following conditions:

The above copyright notice and this permission notice shall be
included in all copies or substantial portions of the Software.

THE SOFTWARE IS PROVIDED "AS IS", WITHOUT WARRANTY OF ANY KIND,
EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO THE WARRANTIES OF
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE AND
NONINFRINGEMENT. IN NO EVENT SHALL THE AUTHORS OR COPYRIGHT HOLDERS BE
LIABLE FOR ANY CLAIM, DAMAGES OR OTHER LIABILITY, WHETHER IN AN ACTION
OF CONTRACT, TORT OR OTHERWISE, ARISING FROM, OUT OF OR IN CONNECTION
WITH THE SOFTWARE OR THE USE OR OTHER DEALINGS IN THE SOFTWARE.
```

C.3.11 Select queue

The `select` and contains the following notice for the `kqueue` interface:

```
Copyright (c) 2000 Doug White, 2006 James Knight, 2007 Christian Heimes
All rights reserved.
```

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

1. Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.
2. Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.

```
THIS SOFTWARE IS PROVIDED BY THE AUTHOR AND CONTRIBUTORS ``AS IS'' AND
ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE
IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE
ARE DISCLAIMED. IN NO EVENT SHALL THE AUTHOR OR CONTRIBUTORS BE LIABLE
FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL
DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS
OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION)
HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT
LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY
OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF
SUCH DAMAGE.
```

C.3.12 strtod and dtoa

The file `Python/dtoa.c`, which supplies C functions `dtoa` and `strtod` for conversion of C doubles to and from strings, is derived from the file of the same name by David M. Gay, currently available from <http://www.netlib.org/fp/>. The original file, as retrieved on March 16, 2009, contains the following copyright and licensing notice:

```
/* *****
 *
 * The author of this software is David M. Gay.
 *
 * Copyright (c) 1991, 2000, 2001 by Lucent Technologies.
 *
 * Permission to use, copy, modify, and distribute this software for any
 * purpose without fee is hereby granted, provided that this entire notice
 * is included in all copies of any software which is or includes a copy
 * or modification of this software and in all copies of the supporting
 * documentation for such software.
 *
 * THIS SOFTWARE IS BEING PROVIDED "AS IS", WITHOUT ANY EXPRESS OR IMPLIED
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```
* WARRANTY.  IN PARTICULAR, NEITHER THE AUTHOR NOR LUCENT MAKES ANY
* REPRESENTATION OR WARRANTY OF ANY KIND CONCERNING THE MERCHANTABILITY
* OF THIS SOFTWARE OR ITS FITNESS FOR ANY PARTICULAR PURPOSE.
*
*****/
```

C.3.13 OpenSSL

The modules *hashlib*, *posix*, *ssl*, *crypt* use the OpenSSL library for added performance if made available by the operating system. Additionally, the Windows and Mac OS X installers for Python may include a copy of the OpenSSL libraries, so we include a copy of the OpenSSL license here:

```
LICENSE ISSUES
=====
```

The OpenSSL toolkit stays under a dual license, i.e. both the conditions of the OpenSSL License and the original SSLeay license apply to the toolkit. See below for the actual license texts. Actually both licenses are BSD-style Open Source licenses. In case of any license issues related to OpenSSL please contact openssl-core@openssl.org.

```
OpenSSL License
-----
```

```
/* =====
 * Copyright (c) 1998-2008 The OpenSSL Project.  All rights reserved.
 *
 * Redistribution and use in source and binary forms, with or without
 * modification, are permitted provided that the following conditions
 * are met:
 *
 * 1. Redistributions of source code must retain the above copyright
 *    notice, this list of conditions and the following disclaimer.
 *
 * 2. Redistributions in binary form must reproduce the above copyright
 *    notice, this list of conditions and the following disclaimer in
 *    the documentation and/or other materials provided with the
 *    distribution.
 *
 * 3. All advertising materials mentioning features or use of this
 *    software must display the following acknowledgment:
 *    "This product includes software developed by the OpenSSL Project
 *    for use in the OpenSSL Toolkit. (http://www.openssl.org/)"
 *
 * 4. The names "OpenSSL Toolkit" and "OpenSSL Project" must not be used to
 *    endorse or promote products derived from this software without
 *    prior written permission. For written permission, please contact
 *    openssl-core@openssl.org.
 *
 * 5. Products derived from this software may not be called "OpenSSL"
 *    nor may "OpenSSL" appear in their names without prior written
 *    permission of the OpenSSL Project.
 *
 * 6. Redistributions of any form whatsoever must retain the following
 *    acknowledgment:
```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

*      "This product includes software developed by the OpenSSL Project
*      for use in the OpenSSL Toolkit (http://www.openssl.org/)"
*
* THIS SOFTWARE IS PROVIDED BY THE OpenSSL PROJECT ``AS IS'' AND ANY
* EXPRESSED OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE
* IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR
* PURPOSE ARE DISCLAIMED.  IN NO EVENT SHALL THE OpenSSL PROJECT OR
* ITS CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL,
* SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT
* NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES;
* LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION)
* HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT,
* STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE)
* ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED
* OF THE POSSIBILITY OF SUCH DAMAGE.
* =====
*
* This product includes cryptographic software written by Eric Young
* (eay@cryptsoft.com).  This product includes software written by Tim
* Hudson (tjh@cryptsoft.com).
*
*/

```

Original SSLeay License

```

/* Copyright (C) 1995-1998 Eric Young (eay@cryptsoft.com)
 * All rights reserved.
 *
 * This package is an SSL implementation written
 * by Eric Young (eay@cryptsoft.com).
 * The implementation was written so as to conform with Netscapes SSL.
 *
 * This library is free for commercial and non-commercial use as long as
 * the following conditions are aheared to.  The following conditions
 * apply to all code found in this distribution, be it the RC4, RSA,
 * lhash, DES, etc., code; not just the SSL code.  The SSL documentation
 * included with this distribution is covered by the same copyright terms
 * except that the holder is Tim Hudson (tjh@cryptsoft.com).
 *
 * Copyright remains Eric Young's, and as such any Copyright notices in
 * the code are not to be removed.
 * If this package is used in a product, Eric Young should be given attribution
 * as the author of the parts of the library used.
 * This can be in the form of a textual message at program startup or
 * in documentation (online or textual) provided with the package.
 *
 * Redistribution and use in source and binary forms, with or without
 * modification, are permitted provided that the following conditions
 * are met:
 * 1. Redistributions of source code must retain the copyright
 *    notice, this list of conditions and the following disclaimer.
 * 2. Redistributions in binary form must reproduce the above copyright
 *    notice, this list of conditions and the following disclaimer in the
 *    documentation and/or other materials provided with the distribution.
 * 3. All advertising materials mentioning features or use of this software

```

(다음 페이지에 계속)

(이전 페이지에서 계속)

```

* must display the following acknowledgement:
* "This product includes cryptographic software written by
*   Eric Young (eay@cryptsoft.com)"
* The word 'cryptographic' can be left out if the routines from the library
* being used are not cryptographic related :-).
* 4. If you include any Windows specific code (or a derivative thereof) from
* the apps directory (application code) you must include an acknowledgement:
* "This product includes software written by Tim Hudson (tjh@cryptsoft.com)"
*
* THIS SOFTWARE IS PROVIDED BY ERIC YOUNG ``AS IS'' AND
* ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE
* IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE
* ARE DISCLAIMED. IN NO EVENT SHALL THE AUTHOR OR CONTRIBUTORS BE LIABLE
* FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL
* DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS
* OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION)
* HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT
* LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY
* OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF
* SUCH DAMAGE.
*
* The licence and distribution terms for any publically available version or
* derivative of this code cannot be changed. i.e. this code cannot simply be
* copied and put under another distribution licence
* [including the GNU Public Licence.]
*/

```

C.3.14 expat

The pyexpat extension is built using an included copy of the expat sources unless the build is configured `--with-system-expat`:

```

Copyright (c) 1998, 1999, 2000 Thai Open Source Software Center Ltd
and Clark Cooper

Permission is hereby granted, free of charge, to any person obtaining
a copy of this software and associated documentation files (the
"Software"), to deal in the Software without restriction, including
without limitation the rights to use, copy, modify, merge, publish,
distribute, sublicense, and/or sell copies of the Software, and to
permit persons to whom the Software is furnished to do so, subject to
the following conditions:

The above copyright notice and this permission notice shall be included
in all copies or substantial portions of the Software.

THE SOFTWARE IS PROVIDED "AS IS", WITHOUT WARRANTY OF ANY KIND,
EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO THE WARRANTIES OF
MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE AND NONINFRINGEMENT.
IN NO EVENT SHALL THE AUTHORS OR COPYRIGHT HOLDERS BE LIABLE FOR ANY
CLAIM, DAMAGES OR OTHER LIABILITY, WHETHER IN AN ACTION OF CONTRACT,
TORT OR OTHERWISE, ARISING FROM, OUT OF OR IN CONNECTION WITH THE
SOFTWARE OR THE USE OR OTHER DEALINGS IN THE SOFTWARE.

```

C.3.15 libffi

The `_ctypes` extension is built using an included copy of the libffi sources unless the build is configured `--with-system-libffi`:

```
Copyright (c) 1996-2008 Red Hat, Inc and others.

Permission is hereby granted, free of charge, to any person obtaining
a copy of this software and associated documentation files (the
``Software''), to deal in the Software without restriction, including
without limitation the rights to use, copy, modify, merge, publish,
distribute, sublicense, and/or sell copies of the Software, and to
permit persons to whom the Software is furnished to do so, subject to
the following conditions:

The above copyright notice and this permission notice shall be included
in all copies or substantial portions of the Software.

THE SOFTWARE IS PROVIDED ``AS IS'', WITHOUT WARRANTY OF ANY KIND,
EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO THE WARRANTIES OF
MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE AND
NONINFRINGEMENT. IN NO EVENT SHALL THE AUTHORS OR COPYRIGHT
HOLDERS BE LIABLE FOR ANY CLAIM, DAMAGES OR OTHER LIABILITY,
WHETHER IN AN ACTION OF CONTRACT, TORT OR OTHERWISE, ARISING FROM,
OUT OF OR IN CONNECTION WITH THE SOFTWARE OR THE USE OR OTHER
DEALINGS IN THE SOFTWARE.
```

C.3.16 zlib

The `zlib` extension is built using an included copy of the zlib sources if the zlib version found on the system is too old to be used for the build:

```
Copyright (C) 1995-2010 Jean-loup Gailly and Mark Adler

This software is provided 'as-is', without any express or implied
warranty. In no event will the authors be held liable for any damages
arising from the use of this software.

Permission is granted to anyone to use this software for any purpose,
including commercial applications, and to alter it and redistribute it
freely, subject to the following restrictions:

1. The origin of this software must not be misrepresented; you must not
   claim that you wrote the original software. If you use this software
   in a product, an acknowledgment in the product documentation would be
   appreciated but is not required.

2. Altered source versions must be plainly marked as such, and must not be
   misrepresented as being the original software.

3. This notice may not be removed or altered from any source distribution.

Jean-loup Gailly          Mark Adler
jloup@gzip.org            madler@alumni.caltech.edu
```

APPENDIX D

저작권

파이썬과 이 도큐멘테이션은:

Copyright © 2001-2020 Python Software Foundation. All rights reserved.

Copyright © 2000 BeOpen.com. All rights reserved.

Copyright © 1995-2000 Corporation for National Research Initiatives. All rights reserved.

Copyright © 1991-1995 Stichting Mathematisch Centrum. All rights reserved.

전체 라이선스 및 사용 권한 정보는 [History and License](#) 에서 제공한다.

Bibliography

- [C99] ISO/IEC 9899:1999. 《Programming languages – C.》 A public draft of this standard is available at <http://www.open-std.org/jtc1/sc22/wg14/www/docs/n1256.pdf>.

—
__builtin__, 1251
__future__, 1267
__main__, 1252
_winreg (*Windows*), 1361

a

abc, 1259
aepack (*Mac*), 1410
aetools (*Mac*), 1409
aetypes (*Mac*), 1411
aifc, 1021
al (*IRIX*), 1415
AL (*IRIX*), 1417
anydbm, 329
applesingle (*Mac*), 1436
argparse, 458
array, 193
ast, 1313
asynchat, 753
asyncore, 749
atexit, 1262
audioop, 1017
autoGIL (*Mac*), 1401

b

base64, 831
BaseHTTPServer, 983
Bastion, 1291
bdb, 1203
binascii, 833
binhex, 833
bisect, 191
bsddb, 334
buildtools (*Mac*), 1436
bz2, 364

C

calendar, 168

Carbon.AE (*Mac*), 1402
Carbon.AH (*Mac*), 1402
Carbon.App (*Mac*), 1402
Carbon.Appearance (*Mac*), 1402
Carbon.CarbonEvents (*Mac*), 1404
Carbon.CarbonEvt (*Mac*), 1404
Carbon.CF (*Mac*), 1402
Carbon.CG (*Mac*), 1404
Carbon.Cm (*Mac*), 1404
Carbon.Components (*Mac*), 1404
Carbon.ControlAccessor (*Mac*), 1404
Carbon.Controls (*Mac*), 1404
Carbon.CoreFoundation (*Mac*), 1404
Carbon.CoreGraphics (*Mac*), 1404
Carbon.Ctl (*Mac*), 1404
Carbon.Dialogs (*Mac*), 1404
Carbon.Dlg (*Mac*), 1404
Carbon.Drag (*Mac*), 1404
Carbon.Dragconst (*Mac*), 1404
Carbon.Events (*Mac*), 1404
Carbon.Evt (*Mac*), 1404
Carbon.File (*Mac*), 1404
Carbon.Files (*Mac*), 1404
Carbon.Fm (*Mac*), 1404
Carbon.Folder (*Mac*), 1404
Carbon.Folders (*Mac*), 1404
Carbon.Fonts (*Mac*), 1404
Carbon.Help (*Mac*), 1404
Carbon.IBCarbon (*Mac*), 1404
Carbon.IBCarbonRuntime (*Mac*), 1404
Carbon.Icns (*Mac*), 1404
Carbon.Icons (*Mac*), 1404
Carbon.Launch (*Mac*), 1404
Carbon.LaunchServices (*Mac*), 1404
Carbon.List (*Mac*), 1404
Carbon.Lists (*Mac*), 1404
Carbon.MacHelp (*Mac*), 1404
Carbon.MediaDescr (*Mac*), 1404
Carbon.Menu (*Mac*), 1404
Carbon.Menus (*Mac*), 1404

Carbon.Mlte (*Mac*), 1404
Carbon.OSA (*Mac*), 1404
Carbon.OSAconst (*Mac*), 1404
Carbon.Qd (*Mac*), 1404
Carbon.Qdoffs (*Mac*), 1404
Carbon.QDOffscreen (*Mac*), 1404
Carbon.Qt (*Mac*), 1404
Carbon.QuickDraw (*Mac*), 1404
Carbon.QuickTime (*Mac*), 1404
Carbon.Res (*Mac*), 1404
Carbon.Resources (*Mac*), 1404
Carbon.Scrap (*Mac*), 1404
Carbon.Snd (*Mac*), 1405
Carbon.Sound (*Mac*), 1405
Carbon.TE (*Mac*), 1405
Carbon.TextEdit (*Mac*), 1405
Carbon.Win (*Mac*), 1405
Carbon.Windows (*Mac*), 1405
cd (*IRIX*), 1417
cfmfile (*Mac*), 1436
cgi, 902
CGIHTTPServer, 988
cgitb, 909
chunk, 1028
cmath, 229
cmd, 1055
code, 1283
codecs, 123
codeop, 1285
collections, 172
ColorPicker (*Mac*), 1405
colorsys, 1030
commands (*Unix*), 1388
compileall, 1327
compiler, 1339
compiler.ast, 1340
compiler.visitor, 1346
ConfigParser, 391
contextlib, 1257
Cookie, 998
cookielib, 989
copy, 214
copy_reg, 324
cPickle, 324
cProfile, 1215
crypt (*Unix*), 1374
cStringIO, 120
csv, 383
ctypes, 580
curses (*Unix*), 548
curses.ascii, 567
curses.panel, 569
curses.textpad, 565

d

datetime, 143
dbhash, 333
dbm (*Unix*), 331
decimal, 231
DEVICE (*IRIX*), 1429
difflib, 109
dircache, 312
dis, 1329
distutils, 1231
dl (*Unix*), 1375
doctest, 1140
DocXMLRPCServer, 1014
dumbdbm, 337
dummy_thread, 632
dummy_threading, 632

e

EasyDialogs (*Mac*), 1395
email, 757
email.charset, 772
email.encoders, 775
email.errors, 776
email.generator, 767
email.header, 770
email.iterators, 778
email.message, 758
email.mime, 768
email.parser, 764
email.utils, 777
encodings.idna, 137
encodings.utf_8_sig, 137
ensurepip, 1232
errno, 574
exceptions, 67

f

fcntl (*Unix*), 1378
filecmp, 300
fileinput, 293
findertools (*Mac*), 1395
fl (*IRIX*), 1421
FL (*IRIX*), 1425
flp (*IRIX*), 1426
fm (*IRIX*), 1426
fnmatch, 306
formatter, 1347
fpectl (*Unix*), 1280
fpformat, 141
fractions, 257
FrameWork (*Mac*), 1398
ftplib, 943
functools, 277
future_builtins, 1251

g

gc, 1268
 gdbm (*Unix*), 332
 gensuitemodule (*Mac*), 1408
 getopt, 515
 getpass, 548
 gettext, 1037
 gl (*IRIX*), 1427
 GL (*IRIX*), 1429
 glob, 305
 grp (*Unix*), 1374
 gzip, 362

h

hashlib, 405
 heapq, 187
 hmac, 408
 hotshot, 1220
 hotshot.stats, 1221
 htmlentitydefs, 847
 htllib, 845
 HTMLParser, 837
 httpplib, 937

i

ic (*Mac*), 1391
 icopen (*Mac*), 1436
 imageop, 1020
 imaplib, 950
 imgfile (*IRIX*), 1429
 imghdr, 1030
 imp, 1293
 importlib, 1297
 imputil, 1297
 inspect, 1271
 io, 440
 itertools, 263

j

jpeg (*IRIX*), 1430
 json, 788

k

keyword, 1323

l

lib2to3, 1195
 linecache, 307
 locale, 1047
 logging, 517
 logging.config, 529
 logging.handlers, 539

m

macerrors (*Mac*), 1436
 MacOS (*Mac*), 1393
 macostools (*Mac*), 1394
 macpath, 312
 macresource (*Mac*), 1437
 mailbox, 797
 mailcap, 796
 marshal, 328
 math, 224
 md5, 409
 mllib, 817
 mimetools, 819
 mimetypes, 820
 MimeWriter, 823
 mimify, 824
 MiniAEFrame (*Mac*), 1412
 mmap, 686
 modulefinder, 1304
 msilib (*Windows*), 1353
 msvcrt (*Windows*), 1359
 multifile, 825
 multiprocessing, 633
 multiprocessing.connection, 659
 multiprocessing.dummy, 663
 multiprocessing.managers, 651
 multiprocessing.pool, 657
 multiprocessing.sharedctypes, 649
 mutex, 201

n

Nav (*Mac*), 1437
 netrc, 399
 new, 213
 nis (*Unix*), 1386
 nntplib, 956
 numbers, 221

o

operator, 280
 optparse, 487
 os, 411
 os.path, 289
 ossaudiodev (*Linux, FreeBSD*), 1032

p

parser, 1309
 pdb, 1207
 pickle, 313
 pickletools, 1338
 pipes (*Unix*), 1380
 PixMapWrapper (*Mac*), 1437
 pkgutil, 1302
 platform, 570

plistlib, 403
popen2, 747
poplib, 948
posix (*Unix*), 1371
posixfile (*Unix*), 1382
pprint, 215
profile, 1215
pstats, 1216
pty (*Linux*), 1378
pwd (*Unix*), 1372
py_compile, 1327
pyclbr, 1326
pydoc, 1139

q

Queue, 202
quopri, 835

r

random, 259
re, 88
readline (*Unix*), 689
resource (*Unix*), 1384
rexec, 1288
rfc822, 827
rlcompleter, 693
robotparser, 398
runpy, 1306

s

sched, 199
ScrolledText (*Tk*), 1098
select, 615
sets, 196
sgmllib, 842
sha, 410
shelve, 325
shlex, 1058
shutil, 307
signal, 744
SimpleHTTPServer, 987
SimpleXMLRPCServer, 1010
site, 1277
smtpd, 964
smtplib, 960
sndhdr, 1031
socket, 707
SocketServer, 975
spwd (*Unix*), 1373
sqlite3, 338
ssl, 719
stat, 295
statvfs, 299
string, 75

StringIO, 119
stringprep, 139
struct, 104
subprocess, 695
sunau, 1024
sunaudio dev (*SunOS*), 1431
SUNAUDIODEV (*SunOS*), 1433
symbol, 1321
symtable, 1319
sys, 1235
sysconfig, 1247
syslog (*Unix*), 1387

t

tabnanny, 1325
tarfile, 372
telnetlib, 965
tempfile, 302
termios (*Unix*), 1376
test, 1195
test.support, 1197
textwrap, 120
thread, 630
threading, 620
time, 452
timeit, 1222
Tix, 1093
Tkinter, 1063
token, 1321
tokenize, 1323
trace, 1226
traceback, 1263
ttk, 1074
tty (*Unix*), 1377
turtle, 1098
types, 211

u

unicodedata, 138
unittest, 1165
urllib, 918
urllib2, 925
urlparse, 971
user, 1279
UserDict, 208
UserList, 209
UserString, 210
uu, 836
uuid, 968

v

videoreader (*Mac*), 1437

W

`W (Mac)`, 1437
`warnings`, 1252
`wave`, 1026
`weakref`, 204
`webbrowser`, 899
`whichdb`, 330
`winsound (Windows)`, 1369
`wsgiref`, 910
`wsgiref.handlers`, 915
`wsgiref.headers`, 912
`wsgiref.simple_server`, 913
`wsgiref.util`, 910
`wsgiref.validate`, 914

X

`xdrlib`, 400
`xml`, 847
`xml.dom`, 862
`xml.dom.minidom`, 873
`xml.dom.pulldom`, 878
`xml.etree.ElementTree`, 849
`xml.parsers.expat`, 890
`xml.sax`, 878
`xml.sax.handler`, 880
`xml.sax.saxutils`, 885
`xml.sax.xmlreader`, 886
`xmlrpclib`, 1002

Z

`zipfile`, 366
`zipimport`, 1300
`zlib`, 359

Non-alphabetical

..., 1439

%

연산자, 33

% formatting, 46

% interpolation, 46

&

연산자, 35

*

연산자, 33

**

연산자, 33

+

연산자, 33

-

연산자, 33

/

연산자, 33

//

연산자, 33

2to3, 1439

<

연산자, 32

<<

연산자, 35

<=

연산자, 32

<protocol>_proxy, 927

!=

연산자, 32

==

연산자, 32

>

연산자, 32

>=

연산자, 32

>>

연산자, 35

>>>, 1439

^

연산자, 35

__abs__() (operator 모듈), 280

__add__() (operator 모듈), 280

__add__() (rfc822.AddressList 메서드), 830

__and__() (operator 모듈), 281

__bases__ (class의 속성), 65

__builtin__ (모듈), 1251

__class__ (instance의 속성), 65

__cmp__() (instance method), 32

__concat__() (operator 모듈), 282

__contains__() (email.message.Message 메서드), 760

__contains__() (mailbox.Mailbox 메서드), 799

__contains__() (operator 모듈), 282

__copy__() (copy protocol), 215

__debug__ (내장 변수), 29

__deepcopy__() (copy protocol), 215

__del__() (io.IOBase 메서드), 444

__delitem__() (email.message.Message 메서드), 760

__delitem__() (mailbox.Mailbox 메서드), 798

__delitem__() (mailbox.MH 메서드), 803

__delitem__() (operator 모듈), 282

__delslice__() (operator 모듈), 282

__dict__ (object의 속성), 65

__displayhook__ (sys 모듈), 1236

__div__() (operator 모듈), 281

__enter__() (_winreg.PyHKEY 메서드), 1368

__enter__() (contextmanager 메서드), 61

__eq__() (email.charset.Charset 메서드), 774

__eq__() (email.header.Header 메서드), 772

__eq__() (instance method), 32

__eq__() (operator 모듈), 280

__excepthook__ (sys 모듈), 1236

__exit__() (_winreg.PyHKEY 메서드), 1368

__exit__() (contextmanager 메서드), 62

__floordiv__() (operator 모듈), 281

__format__, 11

__format__() (datetime.date 메서드), 149

__format__() (datetime.datetime 메서드), 155

- `__format__()` (*datetime.time* 메서드), 158
- `__future__`, 1442
- `__future__` (모듈), 1267
- `__ge__()` (*instance method*), 32
- `__ge__()` (*operator* 모듈), 280
- `__getinitargs__()` (*object* 메서드), 318
- `__getitem__()` (*email.message.Message* 메서드), 760
- `__getitem__()` (*mailbox.Mailbox* 메서드), 799
- `__getitem__()` (*operator* 모듈), 282
- `__getnewargs__()` (*object* 메서드), 318
- `__getslice__()` (*operator* 모듈), 282
- `__getstate__()` (*object* 메서드), 318
- `__gt__()` (*instance method*), 32
- `__gt__()` (*operator* 모듈), 280
- `__iadd__()` (*operator* 모듈), 283
- `__iadd__()` (*rfc822.AddressList* 메서드), 830
- `__iand__()` (*operator* 모듈), 283
- `__iconcat__()` (*operator* 모듈), 283
- `__idiv__()` (*operator* 모듈), 283
- `__ifloordiv__()` (*operator* 모듈), 283
- `__ilshift__()` (*operator* 모듈), 283
- `__imod__()` (*operator* 모듈), 283
- `__import__()` (내장 함수), 24
- `__imul__()` (*operator* 모듈), 284
- `__index__()` (*operator* 모듈), 281
- `__init__()` (*logging.Handler* 메서드), 521
- `__inv__()` (*operator* 모듈), 281
- `__invert__()` (*operator* 모듈), 281
- `__ior__()` (*operator* 모듈), 284
- `__ipow__()` (*operator* 모듈), 284
- `__irepeat__()` (*operator* 모듈), 284
- `__irshift__()` (*operator* 모듈), 284
- `__isub__()` (*operator* 모듈), 284
- `__isub__()` (*rfc822.AddressList* 메서드), 830
- `__iter__()` (*container* 메서드), 37
- `__iter__()` (*iterator* 메서드), 37
- `__iter__()` (*mailbox.Mailbox* 메서드), 799
- `__iter__()` (*unittest.TestSuite* 메서드), 1182
- `__itruediv__()` (*operator* 모듈), 284
- `__ixor__()` (*operator* 모듈), 284
- `__le__()` (*instance method*), 32
- `__le__()` (*operator* 모듈), 280
- `__len__()` (*email.message.Message* 메서드), 759
- `__len__()` (*mailbox.Mailbox* 메서드), 799
- `__len__()` (*rfc822.AddressList* 메서드), 830
- `__lshift__()` (*operator* 모듈), 281
- `__lt__()` (*instance method*), 32
- `__lt__()` (*operator* 모듈), 280
- `__main__`
 - 모듈, 1306, 1307
- `__main__` (모듈), 1252
- `__members__` (*object*의 속성), 65
- `__methods__` (*object*의 속성), 65
- `__missing__()`, 53
- `__missing__()` (*collections.defaultdict* 메서드), 178
- `__mod__()` (*operator* 모듈), 281
- `__mro__` (*class*의 속성), 65
- `__mul__()` (*operator* 모듈), 281
- `__name__` (*definition*의 속성), 65
- `__ne__()` (*email.charset.Charset* 메서드), 774
- `__ne__()` (*email.header.Header* 메서드), 772
- `__ne__()` (*instance method*), 32
- `__ne__()` (*operator* 모듈), 280
- `__neg__()` (*operator* 모듈), 281
- `__not__()` (*operator* 모듈), 280
- `__or__()` (*operator* 모듈), 281
- `__pos__()` (*operator* 모듈), 281
- `__pow__()` (*operator* 모듈), 281
- `__reduce__()` (*object* 메서드), 319
- `__reduce_ex__()` (*object* 메서드), 319
- `__repeat__()` (*operator* 모듈), 282
- `__repr__()` (*multiprocessing.managers.BaseProxy* 메서드), 656
- `__repr__()` (*netrc.netrc* 메서드), 399
- `__rshift__()` (*operator* 모듈), 281
- `__setitem__()` (*email.message.Message* 메서드), 760
- `__setitem__()` (*mailbox.Mailbox* 메서드), 798
- `__setitem__()` (*mailbox.Maildir* 메서드), 801
- `__setitem__()` (*operator* 모듈), 283
- `__setslice__()` (*operator* 모듈), 283
- `__setstate__()` (*object* 메서드), 318
- `__slots__`, 1446
- `__stderr__` (*sys* 모듈), 1246
- `__stdin__` (*sys* 모듈), 1246
- `__stdout__` (*sys* 모듈), 1246
- `__str__()` (*datetime.date* 메서드), 149
- `__str__()` (*datetime.datetime* 메서드), 155
- `__str__()` (*datetime.time* 메서드), 158
- `__str__()` (*email.charset.Charset* 메서드), 774
- `__str__()` (*email.header.Header* 메서드), 772
- `__str__()` (*email.message.Message* 메서드), 758
- `__str__()` (*multiprocessing.managers.BaseProxy* 메서드), 656
- `__str__()` (*rfc822.AddressList* 메서드), 830
- `__sub__()` (*operator* 모듈), 282
- `__sub__()` (*rfc822.AddressList* 메서드), 830
- `__subclasses__()` (*class* 메서드), 65
- `__subclasshook__()` (*abc.ABCMeta* 메서드), 1260
- `__truediv__()` (*operator* 모듈), 282
- `__unicode__()` (*email.header.Header* 메서드), 772
- `__xor__()` (*operator* 모듈), 282
- `_anonymous_` (*ctypes.Structure*의 속성), 612
- `_asdict()` (*collections.somenamedtuple* 메서드), 181
- `_b_base_` (*ctypes._CData*의 속성), 608
- `_b_needsfree_` (*ctypes._CData*의 속성), 608
- `_callmethod()` (*multiprocessing.managers.BaseProxy* 메서드), 656
- `_CData` (*ctypes* 클래스), 608

_clear_type_cache() (sys 모듈), 1235
 _current_frames() (sys 모듈), 1236
 _exit() (os 모듈), 431
 _fields (ast.AST의 속성), 1314
 _fields (collections.somenamedtuple의 속성), 181
 fields (ctypes.Structure의 속성), 611
 _flush() (wsgiref.handlers.BaseHandler 메서드), 916
 _FuncPtr (ctypes 클래스), 602
 _getframe() (sys 모듈), 1240
 _getvalue() (multiprocessing.managers.BaseProxy 메서드), 656
 _handle (ctypes.PyDLL의 속성), 601
 _https_verify_certificates() (ssl 모듈), 723
 length (ctypes.Array의 속성), 613
 _locale
 모듈, 1047
 _make() (collections.somenamedtuple의 클래스 메서드), 181
 _makeResult() (unittest.TextTestRunner 메서드), 1186
 _name (ctypes.PyDLL의 속성), 601
 _objects (ctypes._CData의 속성), 608
 pack (ctypes.Structure의 속성), 612
 _parse() (gettext.NullTranslations 메서드), 1040
 _Pointer (ctypes 클래스), 613
 _quit() (FrameWork.Application 메서드), 1400
 _replace() (collections.somenamedtuple 메서드), 181
 _setroot() (xml.etree.ElementTree.ElementTree 메서드), 859
 _SimpleCData (ctypes 클래스), 609
 _start() (aetools.TalkTo 메서드), 1409
 _structure() (email.iterators 모듈), 779
 type (ctypes._Pointer의 속성), 613
 type (ctypes.Array의 속성), 613
 _urlopener (urllib 모듈), 920
 _winreg (모듈), 1361
 _write() (wsgiref.handlers.BaseHandler 메서드), 915
 |

연산자, 35

~

연산자, 35

객체

Boolean, 33
 buffer, 37
 bytearray, 37
 complex number, 33
 dictionary, 52
 file, 56
 floating point, 33
 integer, 33
 list, 37, 48
 long integer, 33
 mapping, 52
 method, 63

numeric, 33
 sequence, 37
 set, 49
 socket, 707
 string, 37
 traceback, 1236, 1263
 tuple, 37
 type, 22
 Unicode, 37
 xrange, 37, 48

글

assert, 68
 del, 48, 52
 except, 67
 exec, 64
 if, 31
 import, 24, 1293, 1297
 print, 31
 raise, 67
 try, 67
 while, 31

연산자

%, 33
 &, 35
 *, 33
 **, 33
 +, 33
 -, 33
 /, 33
 //, 33
 <, 32
 <=, 32
 <<, 35
 <=, 32
 !=, 32
 ==, 32
 >, 32
 >=, 32
 >>, 35
 ^, 35
 |, 35
 ~, 35
 and, 32
 in, 33, 38
 is, 32
 is not, 32
 not, 32
 not in, 33, 38
 or, 32

A

a2b_base64() (binascii 모듈), 833
 a2b_hex() (binascii 모듈), 835
 a2b_hqx() (binascii 모듈), 834
 a2b_qp() (binascii 모듈), 834

- `a2b_uu()` (*binascii* 모듈), 833
- `abc` (모듈), 1259
- `ABCMeta` (*abc* 클래스), 1259
- `abort()` (*ftplib.FTP* 메서드), 945
- `abort()` (*os* 모듈), 431
- `above()` (*curses.panel.Panel* 메서드), 569
- `abs()` (*decimal.Context* 메서드), 246
- `abs()` (*operator* 모듈), 280
- `abs()` (내장 함수), 5
- `abspath()` (*os.path* 모듈), 289
- `abstract base class` (추상 베이스 클래스), 1439
- `AbstractBasicAuthHandler` (*urllib2* 클래스), 928
- `AbstractDigestAuthHandler` (*urllib2* 클래스), 928
- `AbstractFormatter` (*formatter* 클래스), 1349
- `abstractmethod()` (*abc* 모듈), 1261
- `abstractproperty()` (*abc* 모듈), 1261
- `AbstractWriter` (*formatter* 클래스), 1350
- `accept()` (*asyncore.dispatcher* 메서드), 751
- `accept()` (*multiprocessing.connection.Listener* 메서드), 660
- `accept()` (*socket.socket* 메서드), 713
- `accept2dyear` (*time* 모듈), 453
- `access()` (*os* 모듈), 421
- `acos()` (*cmath* 모듈), 230
- `acos()` (*math* 모듈), 227
- `acosh()` (*cmath* 모듈), 230
- `acosh()` (*math* 모듈), 227
- `acquire()` (*logging.Handler* 메서드), 521
- `acquire()` (*multiprocessing.Lock* 메서드), 646
- `acquire()` (*multiprocessing.RLock* 메서드), 647
- `acquire()` (*threading.Condition* 메서드), 627
- `acquire()` (*threading.Lock* 메서드), 625
- `acquire()` (*threading.RLock* 메서드), 625
- `acquire()` (*threading.Semaphore* 메서드), 628
- `acquire()` (*thread.lock* 메서드), 631
- `acquire_lock()` (*imp* 모듈), 1294
- `Action` (*argparse* 클래스), 476
- `action` (*optparse.Option*의 속성), 501
- `ACTIONS` (*optparse.Option*의 속성), 513
- `activate_form()` (*fl.form* 메서드), 1423
- `active_children()` (*multiprocessing* 모듈), 643
- `active_count()` (*threading* 모듈), 621
- `activeCount()` (*threading* 모듈), 621
- `add()` (*audioop* 모듈), 1017
- `add()` (*decimal.Context* 메서드), 246
- `add()` (*frozenset* 메서드), 51
- `add()` (*mailbox.Mailbox* 메서드), 798
- `add()` (*mailbox.Maildir* 메서드), 801
- `add()` (*msilib.RadioButtonGroup* 메서드), 1358
- `add()` (*operator* 모듈), 280
- `add()` (*pstats.Stats* 메서드), 1216
- `add()` (*tarfile.TarFile* 메서드), 376
- `add()` (*ttk.Notebook* 메서드), 1081
- `add_alias()` (*email.charset* 모듈), 775
- `add_argument()` (*argparse.ArgumentParser* 메서드), 467
- `add_argument_group()` (*argparse.ArgumentParser* 메서드), 483
- `add_box()` (*fl.form* 메서드), 1423
- `add_browser()` (*fl.form* 메서드), 1424
- `add_button()` (*fl.form* 메서드), 1423
- `add_cgi_vars()` (*wsgiref.handlers.BaseHandler* 메서드), 916
- `add_charset()` (*email.charset* 모듈), 774
- `add_choice()` (*fl.form* 메서드), 1424
- `add_clock()` (*fl.form* 메서드), 1423
- `add_codec()` (*email.charset* 모듈), 775
- `add_cookie_header()` (*cookielib.CookieJar* 메서드), 991
- `add_counter()` (*fl.form* 메서드), 1423
- `add_data()` (*msilib* 모듈), 1354
- `add_data()` (*urllib2.Request* 메서드), 929
- `add_dial()` (*fl.form* 메서드), 1423
- `add_fallback()` (*gettext.NullTranslations* 메서드), 1040
- `add_file()` (*msilib.Directory* 메서드), 1357
- `add_flag()` (*mailbox.MaildirMessage* 메서드), 806
- `add_flag()` (*mailbox.mboxMessage* 메서드), 808
- `add_flag()` (*mailbox.MMDFMessage* 메서드), 812
- `add_flow_data()` (*formatter.formatter* 메서드), 1348
- `add_folder()` (*mailbox.Maildir* 메서드), 801
- `add_folder()` (*mailbox.MH* 메서드), 803
- `add_handler()` (*urllib2.OpenerDirector* 메서드), 930
- `add_header()` (*email.message.Message* 메서드), 760
- `add_header()` (*urllib2.Request* 메서드), 929
- `add_header()` (*wsgiref.headers.Headers* 메서드), 912
- `add_history()` (*readline* 모듈), 690
- `add_hor_rule()` (*formatter.formatter* 메서드), 1348
- `add_input()` (*fl.form* 메서드), 1424
- `add_label()` (*mailbox.BabylMessage* 메서드), 811
- `add_label_data()` (*formatter.formatter* 메서드), 1348
- `add_lightbutton()` (*fl.form* 메서드), 1423
- `add_line_break()` (*formatter.formatter* 메서드), 1348
- `add_literal_data()` (*formatter.formatter* 메서드), 1348
- `add_menu()` (*fl.form* 메서드), 1424
- `add_mutually_exclusive_group()` (*argparse.ArgumentParser* 메서드), 484
- `add_option()` (*optparse.OptionParser* 메서드), 500
- `add_parent()` (*urllib2.BaseHandler* 메서드), 931
- `add_password()` (*urllib2.HTTPPasswordMgr* 메서드), 933
- `add_positioner()` (*fl.form* 메서드), 1423
- `add_roundbutton()` (*fl.form* 메서드), 1423

- `add_section()` (*ConfigParser.RawConfigParser* 메서드), 393
- `add_sequence()` (*mailbox.MHMessage* 메서드), 810
- `add_slider()` (*fl.form* 메서드), 1423
- `add_stream()` (*msilib* 모듈), 1354
- `add_subparsers()` (*argparse.ArgumentParser* 메서드), 480
- `add_suffix()` (*imputil.ImportManager* 메서드), 1297
- `add_tables()` (*msilib* 모듈), 1354
- `add_text()` (*fl.form* 메서드), 1423
- `add_timer()` (*fl.form* 메서드), 1424
- `add_type()` (*mimetypes* 모듈), 821
- `add_unredirected_header()` (*urllib2.Request* 메서드), 929
- `add_valslider()` (*fl.form* 메서드), 1423
- `addch()` (*curses.window* 메서드), 555
- `addCleanup()` (*unittest.TestCase* 메서드), 1180
- `addcomponent()` (*turtle.Shape* 메서드), 1125
- `addError()` (*unittest.TestResult* 메서드), 1185
- `addExpectedFailure()` (*unittest.TestResult* 메서드), 1185
- `addFailure()` (*unittest.TestResult* 메서드), 1185
- `addfile()` (*tarfile.TarFile* 메서드), 377
- `addFilter()` (*logging.Handler* 메서드), 521
- `addFilter()` (*logging.Logger* 메서드), 520
- `addHandler()` (*logging.Logger* 메서드), 520
- `addheader()` (*MimeWriter.MimeWriter* 메서드), 823
- `addinfo()` (*hotshot.Profile* 메서드), 1221
- `addLevelName()` (*logging* 모듈), 528
- `addnstr()` (*curses.window* 메서드), 555
- `AddPackagePath()` (*modulefinder* 모듈), 1304
- `address` (*multiprocessing.connection.Listener*의 속성), 660
- `address` (*multiprocessing.managers.BaseManager*의 속성), 652
- `address_family` (*SocketServer.BaseServer*의 속성), 978
- `address_string()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 986
- `AddressList` (*rfc822* 클래스), 827
- `addresslist` (*rfc822.AddressList*의 속성), 830
- `addressof()` (*ctypes* 모듈), 605
- `addshape()` (*turtle* 모듈), 1123
- `addsitedir()` (*site* 모듈), 1279
- `addSkip()` (*unittest.TestResult* 메서드), 1185
- `addstr()` (*curses.window* 메서드), 555
- `addSuccess()` (*unittest.TestResult* 메서드), 1185
- `addTest()` (*unittest.TestSuite* 메서드), 1181
- `addTests()` (*unittest.TestSuite* 메서드), 1181
- `addTypeEqualityFunc()` (*unittest.TestCase* 메서드), 1179
- `addUnexpectedSuccess()` (*unittest.TestResult* 메서드), 1185
- `adjusted()` (*decimal.Decimal* 메서드), 237
- `adler32()` (*zlib* 모듈), 359
- `ADPCM, Intel/DVI`, 1017
- `adpcm2lin()` (*audioop* 모듈), 1017
- `aepack` (모듈), 1410
- `AESEServer` (*MiniAEFrame* 클래스), 1412
- `AEText` (*aetypes* 클래스), 1411
- `aetools` (모듈), 1409
- `aetypes` (모듈), 1411
- `AF_INET` (*socket* 모듈), 709
- `AF_INET6` (*socket* 모듈), 709
- `AF_UNIX` (*socket* 모듈), 709
- `aifc` (모듈), 1021
- `aifc()` (*aifc.aifc* 메서드), 1023
- `AIFF`, 1021, 1028
- `aiff()` (*aifc.aifc* 메서드), 1023
- `AIFF-C`, 1021, 1028
- `AL`
모듈, 1415
- `AL` (모듈), 1417
- `al` (모듈), 1415
- `alarm()` (*signal* 모듈), 745
- `A-LAW`, 1023, 1031
- `a-LAW`, 1017
- `alaw2lin()` (*audioop* 모듈), 1017
- `ALERT_DESCRIPTION_HANDSHAKE_FAILURE` (*ssl* 모듈), 729
- `ALERT_DESCRIPTION_INTERNAL_ERROR` (*ssl* 모듈), 729
- `algorithms_available` (*hashlib* 모듈), 406
- `algorithms_guaranteed` (*hashlib* 모듈), 406
- `alignment()` (*ctypes* 모듈), 605
- `all()` (내장 함수), 5
- `all_errors` (*ftplib* 모듈), 945
- `all_features` (*xml.sax.handler* 모듈), 881
- `all_properties` (*xml.sax.handler* 모듈), 882
- `allocate_lock()` (*thread* 모듈), 631
- `allow_reuse_address` (*SocketServer.BaseServer*의 속성), 978
- `allowed_domains()` (*cookielib.DefaultCookiePolicy* 메서드), 995
- `alt()` (*curses.ascii* 모듈), 568
- `ALT_DIGITS` (*locale* 모듈), 1050
- `altsep` (*os* 모듈), 439
- `altzone` (*time* 모듈), 453
- `ALWAYS_TYPED_ACTIONS` (*optparse.Option*의 속성), 513
- `AMPER` (*token* 모듈), 1321
- `AMPEREQUAL` (*token* 모듈), 1321
- `anchor_bgn()` (*htmlib.HTMLParser* 메서드), 846
- `anchor_end()` (*htmlib.HTMLParser* 메서드), 846
- `and`
연산자, 32
- `and_()` (*operator* 모듈), 281

- `annotate()` (*dircache* 모듈), 312
- `answer_challenge()` (*multiprocessing.connection* 모듈), 659
- `any()` (내장 함수), 6
- `anydbm` (모듈), 329
- `api_version` (*sys* 모듈), 1247
- `apop()` (*poplib.POP3* 메서드), 949
- `append()` (*array.array* 메서드), 194
- `append()` (*collections.deque* 메서드), 175
- `append()` (*email.header.Header* 메서드), 771
- `append()` (*imaplib.IMAP4* 메서드), 951
- `append()` (*list* method), 48
- `append()` (*msilib.CAB* 메서드), 1356
- `append()` (*pipes.Template* 메서드), 1381
- `append()` (*xml.etree.ElementTree.Element* 메서드), 858
- `appendChild()` (*xml.dom.Node* 메서드), 866
- `appendleft()` (*collections.deque* 메서드), 175
- `AppleEvents`, 1395, 1412
- `applesingle` (모듈), 1436
- `Application()` (*FrameWork* 모듈), 1398
- `application_uri()` (*wsgiref.util* 모듈), 910
- `apply (2to3 fixer)`, 1191
- `apply()` (*multiprocessing.pool.multiprocessing.Pool* 메서드), 657
- `apply()` (내장 함수), 27
- `apply_async()` (*multiprocessing.pool.multiprocessing.Pool* 메서드), 657
- `architecture()` (*platform* 모듈), 570
- `archive` (*zipimport.zipimporter*의 속성), 1301
- `aRepr` (*repr* 모듈), 218
- `argparse` (모듈), 458
- `args` (*exceptions.BaseException*의 속성), 67
- `args` (*functools.partial*의 속성), 279
- `argtypes` (*ctypes._FuncPtr*의 속성), 602
- `argument` (인자), 1439
- `ArgumentDefaultsHelpFormatter` (*argparse* 클래스), 463
- `ArgumentError`, 602
- `ArgumentParser` (*argparse* 클래스), 460
- `argv` (*sys* 모듈), 1235
- `arithmetic`, 33
- `ArithmeticError`, 68
- `array` (*array* 클래스), 193
- `Array` (*ctypes* 클래스), 613
- `array` (모듈), 193
- `Array()` (*multiprocessing* 모듈), 648
- `Array()` (*multiprocessing.managers.SyncManager* 메서드), 652
- `Array()` (*multiprocessing.sharedctypes* 모듈), 649
- `arrays`, 193
- `ArrayType` (*array* 모듈), 194
- `article()` (*nntplib.NNTP* 메서드), 958
- `as_integer_ratio()` (*float* 메서드), 36
- `AS_IS` (*formatter* 모듈), 1347
- `as_string()` (*email.message.Message* 메서드), 758
- `as_tuple()` (*decimal.Decimal* 메서드), 237
- `ascii()` (*curses.ascii* 모듈), 568
- `ascii()` (*future_builtins* 모듈), 1251
- `ascii_letters` (*string* 모듈), 75
- `ascii_lowercase` (*string* 모듈), 75
- `ascii_uppercase` (*string* 모듈), 75
- `asctime()` (*time* 모듈), 453
- `asin()` (*cmath* 모듈), 230
- `asin()` (*math* 모듈), 227
- `asinh()` (*cmath* 모듈), 230
- `asinh()` (*math* 모듈), 227
- `AskFileForOpen()` (*EasyDialogs* 모듈), 1396
- `AskFileForSave()` (*EasyDialogs* 모듈), 1397
- `AskFolder()` (*EasyDialogs* 모듈), 1397
- `AskPassword()` (*EasyDialogs* 모듈), 1396
- `AskString()` (*EasyDialogs* 모듈), 1396
- `AskYesNoCancel()` (*EasyDialogs* 모듈), 1396
- `assert`
글, 68
- `assert_line_data()` (*formatter.formatter* 메서드), 1349
- `assertAlmostEqual()` (*unittest.TestCase* 메서드), 1177
- `assertDictContainsSubset()` (*unittest.TestCase* 메서드), 1178
- `assertDictEqual()` (*unittest.TestCase* 메서드), 1179
- `assertEqual()` (*unittest.TestCase* 메서드), 1176
- `assertFalse()` (*unittest.TestCase* 메서드), 1176
- `assertGreater()` (*unittest.TestCase* 메서드), 1178
- `assertGreaterEqual()` (*unittest.TestCase* 메서드), 1178
- `assertIn()` (*unittest.TestCase* 메서드), 1176
- `AssertionError`, 68
- `assertIs()` (*unittest.TestCase* 메서드), 1176
- `assertIsInstance()` (*unittest.TestCase* 메서드), 1176
- `assertIsNone()` (*unittest.TestCase* 메서드), 1176
- `assertIsNot()` (*unittest.TestCase* 메서드), 1176
- `assertIsNotNone()` (*unittest.TestCase* 메서드), 1176
- `assertItemsEqual()` (*unittest.TestCase* 메서드), 1178
- `assertLess()` (*unittest.TestCase* 메서드), 1178
- `assertLessEqual()` (*unittest.TestCase* 메서드), 1178
- `assertListEqual()` (*unittest.TestCase* 메서드), 1179
- `assertMultiLineEqual()` (*unittest.TestCase* 메서드), 1179
- `assertNotAlmostEqual()` (*unittest.TestCase* 메서드), 1177
- `assertNotEqual()` (*unittest.TestCase* 메서드), 1176
- `assertNotIn()` (*unittest.TestCase* 메서드), 1176
- `assertNotIsInstance()` (*unittest.TestCase* 메서드), 1176

- assertNotRegexpMatches() (*unittest.TestCase* 메서드), 1178
- assertRaises() (*unittest.TestCase* 메서드), 1176
- assertRaisesRegexp() (*unittest.TestCase* 메서드), 1177
- assertRegexpMatches() (*unittest.TestCase* 메서드), 1178
- asserts (*2to3 fixer*), 1191
- assertSequenceEqual() (*unittest.TestCase* 메서드), 1179
- assertSetEqual() (*unittest.TestCase* 메서드), 1179
- assertTrue() (*unittest.TestCase* 메서드), 1176
- assertTupleEqual() (*unittest.TestCase* 메서드), 1179
- assignment
- extended slice, 48
 - slice, 48
 - subscript, 48
- AST (*ast* 클래스), 1314
- ast (모듈), 1313
- astimezone() (*datetime.datetime* 메서드), 153
- ASTVisitor (*compiler.visitor* 클래스), 1346
- async_chat (*asynchat* 클래스), 753
- async_chat.ac_in_buffer_size (*asynchat* 모듈), 753
- async_chat.ac_out_buffer_size (*asynchat* 모듈), 753
- asyncevents() (*Framework.Application* 메서드), 1399
- asynchat (모듈), 753
- asyncore (모듈), 749
- AsyncResult (*multiprocessing.pool* 클래스), 658
- AT (*token* 모듈), 1321
- atan() (*cmath* 모듈), 230
- atan() (*math* 모듈), 227
- atan2() (*math* 모듈), 227
- atanh() (*cmath* 모듈), 230
- atanh() (*math* 모듈), 227
- atexit (모듈), 1262
- atime (*cd* 모듈), 1418
- atof() (*locale* 모듈), 1051
- atof() (*string* 모듈), 85
- atoi() (*locale* 모듈), 1051
- atoi() (*string* 모듈), 86
- atol() (*string* 모듈), 86
- attach() (*email.message.Message* 메서드), 758
- AttlistDeclHandler() (*xml.parsers.expat.xmlparser* 메서드), 893
- attrgetter() (*operator* 모듈), 285
- attrib (*xml.etree.ElementTree.Element*의 속성), 857
- attribute (어트리뷰트), 1440
- AttributeError, 68
- attributes (*xml.dom.Node*의 속성), 865
- AttributesImpl (*xml.sax.xmlreader* 클래스), 886
- AttributesNSImpl (*xml.sax.xmlreader* 클래스), 886
- attroff() (*curses.window* 메서드), 555
- attron() (*curses.window* 메서드), 555
- attrset() (*curses.window* 메서드), 555
- audio (*cd* 모듈), 1418
- Audio Interchange File Format, 1021, 1028
- AUDIO_FILE_ENCODING_ADPCM_G721 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_ADPCM_G722 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_ADPCM_G723_3 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_ADPCM_G723_5 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_ALAW_8 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_DOUBLE (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_FLOAT (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_LINEAR_8 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_LINEAR_16 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_LINEAR_24 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_LINEAR_32 (*sunau* 모듈), 1024
- AUDIO_FILE_ENCODING_MULAW_8 (*sunau* 모듈), 1024
- AUDIO_FILE_MAGIC (*sunau* 모듈), 1024
- AUDIODEV, 1032
- audioop (모듈), 1017
- auth() (*ftplib.FTP_TLS* 메서드), 947
- authenticate() (*imaplib.IMAP4* 메서드), 951
- AuthenticationError, 660
- authenticators() (*netrc.netrc* 메서드), 399
- authkey (*multiprocessing.Process*의 속성), 639
- autoGIL (모듈), 1401
- AutoGILError, 1401
- avg() (*audioop* 모듈), 1017
- avgpp() (*audioop* 모듈), 1018
- ## B
- b
- unittest command line option, 1168
- b2a_base64() (*binascii* 모듈), 834
- b2a_hex() (*binascii* 모듈), 835
- b2a_hqx() (*binascii* 모듈), 834
- b2a_qp() (*binascii* 모듈), 834
- b2a_uu() (*binascii* 모듈), 833
- b16decode() (*base64* 모듈), 832
- b16encode() (*base64* 모듈), 831
- b32decode() (*base64* 모듈), 831
- b32encode() (*base64* 모듈), 831

- b64decode() (*base64* 모듈), 831
- b64encode() (*base64* 모듈), 831
- Babyl (*mailbox* 클래스), 804
- BabylMailbox (*mailbox* 클래스), 815
- BabylMessage (*mailbox* 클래스), 810
- back() (*turtle* 모듈), 1102
- BACKQUOTE (*token* 모듈), 1321
- backslashreplace_errors() (*codecs* 모듈), 125
- backward() (*turtle* 모듈), 1102
- backward_compatible (*imageop* 모듈), 1021
- BadStatusLine, 939
- BadZipfile, 366
- Balloon (*Tix* 클래스), 1094
- base64
 - encoding, 831
 - 모듈, 833
- base64 (모듈), 831
- BaseCGIHandler (*wsgiref.handlers* 클래스), 915
- BaseCookie (*Cookie* 클래스), 998
- BaseException, 67
- BaseHandler (*urllib2* 클래스), 927
- BaseHandler (*wsgiref.handlers* 클래스), 915
- BaseHTTPRequestHandler (*BaseHTTPServer* 클래스), 984
- BaseHTTPServer (모듈), 983
- BaseManager (*multiprocessing.managers* 클래스), 651
- basename() (*os.path* 모듈), 290
- BaseProxy (*multiprocessing.managers* 클래스), 656
- BaseRequestHandler (*SocketServer* 클래스), 979
- BaseServer (*SocketServer* 클래스), 977
- basestring (*2to3 fixer*), 1192
- basestring() (내장 함수), 6
- basicConfig() (*logging* 모듈), 528
- BasicContext (*decimal* 클래스), 244
- Bastion (모듈), 1291
- Bastion() (*Bastion* 모듈), 1291
- BastionClass (*Bastion* 클래스), 1291
- baudrate() (*curses* 모듈), 549
- bbox() (*tk.Treeview* 메서드), 1086
- bdb
 - 모듈, 1207
- Bdb (*bdb* 클래스), 1204
- bdb (모듈), 1203
- BdbQuit, 1203
- BDFL, 1440
- beep() (*curses* 모듈), 549
- Beep() (*winsound* 모듈), 1369
- begin_fill() (*turtle* 모듈), 1112
- begin_poly() (*turtle* 모듈), 1117
- below() (*curses.panel.Panel* 메서드), 569
- Benchmarking, 1222
- benchmarking, 453
- betavariate() (*random* 모듈), 262
- bgcolor() (*turtle* 모듈), 1118
- bgn_group() (*fl.form* 메서드), 1423
- bgpic() (*turtle* 모듈), 1119
- bias() (*audioop* 모듈), 1018
- bidirectional() (*unicodedata* 모듈), 138
- BigEndianStructure (*ctypes* 클래스), 611
- bin() (내장 함수), 6
- binary
 - data, packing, 104
- Binary (*msilib* 클래스), 1354
- Binary (*xmlrpclib* 클래스), 1006
- binary semaphores, 630
- BINARY_ADD (*opcode*), 1332
- BINARY_AND (*opcode*), 1332
- BINARY_DIVIDE (*opcode*), 1331
- BINARY_FLOOR_DIVIDE (*opcode*), 1331
- BINARY_LSHIFT (*opcode*), 1332
- BINARY_MODULO (*opcode*), 1331
- BINARY_MULTIPLY (*opcode*), 1331
- BINARY_OR (*opcode*), 1332
- BINARY_POWER (*opcode*), 1331
- BINARY_RSHIFT (*opcode*), 1332
- BINARY_SUBSCR (*opcode*), 1332
- BINARY_SUBTRACT (*opcode*), 1332
- BINARY_TRUE_DIVIDE (*opcode*), 1331
- BINARY_XOR (*opcode*), 1332
- binascii (모듈), 833
- bind (*widgets*), 1072
- bind() (*asyncore.dispatcher* 메서드), 751
- bind() (*socket.socket* 메서드), 713
- bind_textdomain_codeset() (*gettext* 모듈), 1038
- bindtextdomain() (*gettext* 모듈), 1037
- bindtextdomain() (*locale* 모듈), 1053
- binhex
 - 모듈, 833
- binhex (모듈), 833
- binhex() (*binhex* 모듈), 833
- bisect (모듈), 191
- bisect() (*bisect* 모듈), 191
- bisect_left() (*bisect* 모듈), 191
- bisect_right() (*bisect* 모듈), 191
- bit_length() (*int* 메서드), 35
- bit_length() (*long* 메서드), 35
- bitmap() (*msilib.Dialog* 메서드), 1358
- bitwise
 - operations, 35
- bk() (*turtle* 모듈), 1102
- bkgd() (*curses.window* 메서드), 555
- bkgdset() (*curses.window* 메서드), 556
- blocked_domains() (*cookielib.DefaultCookiePolicy* 메서드), 994
- BlockingIOError, 442
- BLOCKSIZE (*cd* 모듈), 1418
- blocksize (*sha* 모듈), 410
- body() (*nntplib.NNTP* 메서드), 958

- body_encode() (*email.charset.Charset* 메서드), 774
body_encoding (*email.charset.Charset*의 속성), 773
body_line_iterator() (*email.iterators* 모듈), 778
BOM (*codecs* 모듈), 126
BOM_BE (*codecs* 모듈), 126
BOM_LE (*codecs* 모듈), 126
BOM_UTF8 (*codecs* 모듈), 126
BOM_UTF16 (*codecs* 모듈), 126
BOM_UTF16_BE (*codecs* 모듈), 126
BOM_UTF16_LE (*codecs* 모듈), 126
BOM_UTF32 (*codecs* 모듈), 126
BOM_UTF32_BE (*codecs* 모듈), 126
BOM_UTF32_LE (*codecs* 모듈), 126
bool (내장 클래스), 6
Boolean
 operations, 31, 32
 type, 6
 values, 64
 객체, 33
Boolean (*aetypes* 클래스), 1411
boolean() (*xmlrpclib* 모듈), 1009
BooleanType (*types* 모듈), 211
bootstrap() (*ensurepip* 모듈), 1233
border() (*curses.window* 메서드), 556
bottom() (*curses.panel.Panel* 메서드), 569
bottom_panel() (*curses.panel* 모듈), 569
BoundaryError, 776
BoundedSemaphore (*multiprocessing* 클래스), 646
BoundedSemaphore() (*multiprocessing.managers.SyncManager* 메서드), 652
BoundedSemaphore() (*threading* 모듈), 622
box() (*curses.window* 메서드), 556
break_anywhere() (*bdb.Bdb* 메서드), 1205
break_here() (*bdb.Bdb* 메서드), 1205
break_long_words (*textwrap.TextWrapper*의 속성), 122
BREAK_LOOP (*opcode*), 1334
break_on_hyphens (*textwrap.TextWrapper*의 속성), 123
Breakpoint (*bdb* 클래스), 1203
breakpoints, 1132
BROWSER, 899, 900
bsddb
 모듈, 326, 329, 333
bsddb (모듈), 334
BsdDbShelf (*shelve* 클래스), 326
btopen() (*bsddb* 모듈), 335
buffer
 객체, 37
 내장 함수, 213
--buffer
 unittest command line option, 1168
buffer (2to3 fixer), 1192
buffer (*io.TextIOBase*의 속성), 448
buffer (*unittest.TestResult*의 속성), 1184
buffer size, I/O, 15
buffer() (내장 함수), 27
buffer_info() (*array.array* 메서드), 194
buffer_size (*xml.parsers.expat.xmlparser*의 속성), 892
buffer_text (*xml.parsers.expat.xmlparser*의 속성), 892
buffer_used (*xml.parsers.expat.xmlparser*의 속성), 892
BufferedIOBase (*io* 클래스), 445
BufferedRandom (*io* 클래스), 448
BufferedReader (*io* 클래스), 447
BufferedRWPair (*io* 클래스), 448
BufferedWriter (*io* 클래스), 447
BufferError, 68
BufferingHandler (*logging.handlers* 클래스), 547
BufferTooShort, 640, 660
BufferType (*types* 모듈), 213
BUFSIZ (*macostools* 모듈), 1395
bufsize() (*ossaudiodev.oss_audio_device* 메서드), 1034
BUILD_CLASS (*opcode*), 1334
BUILD_LIST (*opcode*), 1335
BUILD_MAP (*opcode*), 1335
build_opener() (*urllib2* 모듈), 926
BUILD_SET (*opcode*), 1335
BUILD_SLICE (*opcode*), 1337
BUILD_TUPLE (*opcode*), 1335
buildtools (모듈), 1436
built-in
 types, 31
builtin_module_names (*sys* 모듈), 1235
BuiltinFunctionType (*types* 모듈), 212
BuiltinImporter (*imputil* 클래스), 1298
BuiltinMethodType (*types* 모듈), 212
ButtonBox (*Tix* 클래스), 1094
bye() (*turtle* 모듈), 1123
byref() (*ctypes* 모듈), 605
bytearray
 객체, 37
bytearray (내장 클래스), 6
byte-code
 file, 1293, 1295, 1327
bytecode (바이트 코드), 1440
byteorder (*sys* 모듈), 1235
bytes (*uuid.UUID*의 속성), 968
bytes-like object (바이트열류 객체), 1440
bytes_le (*uuid.UUID*의 속성), 968
BytesIO (*io* 클래스), 447
byteswap() (*array.array* 메서드), 194
BytesWarning, 72
bz2 (모듈), 364
BZ2Compressor (*bz2* 클래스), 365

BZ2Decompressor (*bz2* 클래스), 366

BZ2File (*bz2* 클래스), 364

C

C

language, 33

structures, 104

-C

trace command line option, 1227

-c

timeit command line option, 1224

trace command line option, 1227

unittest command line option, 1168

-c <zipfile> <source1> ... <sourceN>

zipfile command line option, 372

c_bool (*ctypes* 클래스), 611

C_BUILTIN (*imp* 모듈), 1295

c_byte (*ctypes* 클래스), 609

c_char (*ctypes* 클래스), 609

c_char_p (*ctypes* 클래스), 609

c_double (*ctypes* 클래스), 609

C_EXTENSION (*imp* 모듈), 1295

c_float (*ctypes* 클래스), 609

c_int (*ctypes* 클래스), 609

c_int8 (*ctypes* 클래스), 609

c_int16 (*ctypes* 클래스), 609

c_int32 (*ctypes* 클래스), 610

c_int64 (*ctypes* 클래스), 610

c_long (*ctypes* 클래스), 610

c_longdouble (*ctypes* 클래스), 609

c_longlong (*ctypes* 클래스), 610

c_short (*ctypes* 클래스), 610

c_size_t (*ctypes* 클래스), 610

c_ssize_t (*ctypes* 클래스), 610

c_ubyte (*ctypes* 클래스), 610

c_uint (*ctypes* 클래스), 610

c_uint8 (*ctypes* 클래스), 610

c_uint16 (*ctypes* 클래스), 610

c_uint32 (*ctypes* 클래스), 610

c_uint64 (*ctypes* 클래스), 610

c_ulong (*ctypes* 클래스), 610

c_ulonglong (*ctypes* 클래스), 610

c_ushort (*ctypes* 클래스), 610

c_void_p (*ctypes* 클래스), 610

c_wchar (*ctypes* 클래스), 611

c_wchar_p (*ctypes* 클래스), 611

CAB (*msilib* 클래스), 1356

CacheFTPHandler (*urllib2* 클래스), 928

calcsizex() (*struct* 모듈), 105

Calendar (*calendar* 클래스), 168

calendar (모듈), 168

calendar() (*calendar* 모듈), 171

call() (*dl.dl* 메서드), 1376

call() (*subprocess* 모듈), 696

CALL_FUNCTION (*opcode*), 1337

CALL_FUNCTION_KW (*opcode*), 1337

CALL_FUNCTION_VAR (*opcode*), 1337

CALL_FUNCTION_VAR_KW (*opcode*), 1338

call_tracing() (*sys* 모듈), 1235

Callable (*collections* 클래스), 185

callable() (내장 함수), 7

CallableProxyType (*weakref* 모듈), 206

callback (*optparse.Option*의 속성), 501

callback() (*MiniAEFrame.AEServer* 메서드), 1413

callback_args (*optparse.Option*의 속성), 501

callback_kwarg (*optparse.Option*의 속성), 501

CalledProcessError, 697

can_change_color() (*curses* 모듈), 549

can_fetch() (*robotparser.RobotFileParser* 메서드), 398

cancel() (*sched.scheduler* 메서드), 200

cancel() (*threading.Timer* 메서드), 629

cancel_join_thread() (*multiprocessing.Queue* 메서드), 642

CannotSendHeader, 939

CannotSendRequest, 939

canonic() (*bdb.Bdb* 메서드), 1204

canonical() (*decimal.Context* 메서드), 246

canonical() (*decimal.Decimal* 메서드), 237

capitalize() (*str* 메서드), 39

capitalize() (*string* 모듈), 86

captured_stdout() (*test.support* 모듈), 1199

captureWarnings() (*logging* 모듈), 529

capwords() (*string* 모듈), 85

Carbon.AE (모듈), 1402

Carbon.AH (모듈), 1402

Carbon.App (모듈), 1402

Carbon.Appearance (모듈), 1402

Carbon.CarbonEvents (모듈), 1404

Carbon.CarbonEvt (모듈), 1404

Carbon.CF (모듈), 1402

Carbon.CG (모듈), 1404

Carbon.Cm (모듈), 1404

Carbon.Components (모듈), 1404

Carbon.ControlAccessor (모듈), 1404

Carbon.Controls (모듈), 1404

Carbon.CoreFoundation (모듈), 1404

Carbon.CoreGraphics (모듈), 1404

Carbon.Ctl (모듈), 1404

Carbon.Dialogs (모듈), 1404

Carbon.Dlg (모듈), 1404

Carbon.Drag (모듈), 1404

Carbon.Dragconst (모듈), 1404

Carbon.Events (모듈), 1404

Carbon.Evt (모듈), 1404

Carbon.File (모듈), 1404

Carbon.Files (모듈), 1404

Carbon.Fm (모듈), 1404

- Carbon.Folder (모듈), 1404
- Carbon.Folders (모듈), 1404
- Carbon.Fonts (모듈), 1404
- Carbon.Help (모듈), 1404
- Carbon.IBCarbon (모듈), 1404
- Carbon.IBCarbonRuntime (모듈), 1404
- Carbon.Icns (모듈), 1404
- Carbon.Icons (모듈), 1404
- Carbon.Launch (모듈), 1404
- Carbon.LaunchServices (모듈), 1404
- Carbon.List (모듈), 1404
- Carbon.Lists (모듈), 1404
- Carbon.MacHelp (모듈), 1404
- Carbon.MediaDescr (모듈), 1404
- Carbon.Menu (모듈), 1404
- Carbon.Menus (모듈), 1404
- Carbon.Mlte (모듈), 1404
- Carbon.OSA (모듈), 1404
- Carbon.OSAconst (모듈), 1404
- Carbon.Qd (모듈), 1404
- Carbon.Qdoffs (모듈), 1404
- Carbon.QDOffscreen (모듈), 1404
- Carbon.Qt (모듈), 1404
- Carbon.QuickDraw (모듈), 1404
- Carbon.QuickTime (모듈), 1404
- Carbon.Res (모듈), 1404
- Carbon.Resources (모듈), 1404
- Carbon.Scrap (모듈), 1404
- Carbon.Snd (모듈), 1405
- Carbon.Sound (모듈), 1405
- Carbon.TE (모듈), 1405
- Carbon.TextEdit (모듈), 1405
- Carbon.Win (모듈), 1405
- Carbon.Windows (모듈), 1405
- cast () (*ctypes* 모듈), 605
- cat () (*nis* 모듈), 1386
- catalog (*cd* 모듈), 1418
- catch
 - unittest command line option, 1168
- catch_warnings (*warnings* 클래스), 1257
- category () (*unicodedata* 모듈), 138
- cbreak () (*curses* 모듈), 549
- cd (모듈), 1417
- CDLL (*ctypes* 클래스), 600
- CDROM (*cd* 모듈), 1418
- ceil () (*in module math*), 34
- ceil () (*math* 모듈), 225
- center () (*str* 메서드), 39
- center () (*string* 모듈), 87
- CERT_NONE (*ssl* 모듈), 725
- CERT_OPTIONAL (*ssl* 모듈), 725
- CERT_REQUIRED (*ssl* 모듈), 726
- cert_store_stats () (*ssl.SSLContext* 메서드), 732
- cert_time_to_seconds () (*ssl* 모듈), 724
- CertificateError, 721
- certificates, 736
- cfmfile (모듈), 1436
- CFUNCTYPE () (*ctypes* 모듈), 603
- CGI
 - debugging, 908
 - exceptions, 909
 - protocol, 902
 - security, 907
 - tracebacks, 909
- cgi (모듈), 902
- cgi_directories (*CGI-HTTPServer.CGIHTTPRequestHandler* 의 속성), 989
- CGIHandler (*wsgiref.handlers* 클래스), 915
- CGIHTTPRequestHandler (*CGIHTTPServer* 클래스), 988
- CGIHTTPServer
 - 모듈, 983
- CGIHTTPServer (모듈), 988
- cgitb (모듈), 909
- CGIXMLRPCRequestHandler (*SimpleXMLRPC-Server* 클래스), 1010
- chain () (*itertools* 모듈), 265
- chaining
 - comparisons, 32
- CHANNEL_BINDING_TYPES (*ssl* 모듈), 729
- channels () (*ossaudiodev.oss_audio_device* 메서드), 1033
- CHAR_MAX (*locale* 모듈), 1052
- character, 138
- CharacterDataHandler ()
 - (*xml.parsers.expat.xmlparser* 메서드), 894
- characters () (*xml.sax.handler.ContentHandler* 메서드), 883
- characters_written (*io.BlockingIOError*의 속성), 442
- Charset (*email.charset* 클래스), 772
- CHARSET (*mimify* 모듈), 824
- charset () (*gettext.NullTranslations* 메서드), 1041
- chdir () (*os* 모듈), 422
- check () (*imaplib.IMAP4* 메서드), 952
- check () (*tabnanny* 모듈), 1325
- check_call () (*subprocess* 모듈), 696
- check_forms () (*fl* 모듈), 1421
- check_hostname (*ssl.SSLContext*의 속성), 736
- check_output () (*doctest.OutputChecker* 메서드), 1160
- check_output () (*subprocess* 모듈), 697
- check_py3k_warnings () (*test.support* 모듈), 1199
- check_unused_args () (*string.Formatter* 메서드), 77
- check_warnings () (*test.support* 모듈), 1198
- checkbox () (*msilib.Dialog* 메서드), 1358
- checkcache () (*linecache* 모듈), 307

checkfuncname() (*bdb* 모듈), 1207
 CheckList (*Tix* 클래스), 1096
 checksum
 Cyclic Redundancy Check, 360
 MD5, 409
 SHA, 410
 chflags() (*os* 모듈), 422
 chgat() (*curses.window* 메서드), 556
 childerr (*popen2.Popen3*의 속성), 748
 childNodes (*xml.dom.Node*의 속성), 865
 chmod() (*os* 모듈), 423
 choice() (*random* 모듈), 261
 choices (*optparse.Option*의 속성), 501
 choose_boundary() (*mimetools* 모듈), 819
 chown() (*os* 모듈), 424
 chr() (내장 함수), 7
 chroot() (*os* 모듈), 423
 Chunk (*chunk* 클래스), 1029
 chunk (모듈), 1028
 cipher
 DES, 1374
 cipher() (*ssl.SSLSocket* 메서드), 731
 circle() (*turtle* 모듈), 1104
 CIRCUMFLEX (*token* 모듈), 1321
 CIRCUMFLEXEQUAL (*token* 모듈), 1321
 Clamped (*decimal* 클래스), 249
 Class (*syntable* 클래스), 1320
 class (클래스), 1440
 Class browser, 1130
 classic class, 1440
 classmethod() (내장 함수), 7
 classobj() (*new* 모듈), 214
 ClassType (*types* 모듈), 212
 clean() (*mailbox.Maildir* 메서드), 801
 cleandoc() (*inspect* 모듈), 1275
 Clear Breakpoint, 1132
 clear() (*collections.deque* 메서드), 175
 clear() (*cookielib.CookieJar* 메서드), 991
 clear() (*curses.window* 메서드), 556
 clear() (*dict* 메서드), 53
 clear() (*frozenset* 메서드), 51
 clear() (*mailbox.Mailbox* 메서드), 800
 clear() (*threading.Event* 메서드), 629
 clear() (*turtle* 모듈), 1113, 1119
 clear() (*xml.etree.ElementTree.Element* 메서드), 857
 clear_all_breaks() (*bdb.Bdb* 메서드), 1206
 clear_all_file_breaks() (*bdb.Bdb* 메서드), 1206
 clear_bpbynumber() (*bdb.Bdb* 메서드), 1206
 clear_break() (*bdb.Bdb* 메서드), 1206
 clear_flags() (*decimal.Context* 메서드), 245
 clear_history() (*readline* 모듈), 690
 clear_memo() (*pickle.Pickler* 메서드), 316
 clear_session_cookies() (*cookielib.CookieJar* 메서드), 992
 clearcache() (*linecache* 모듈), 307
 ClearData() (*msilib.Record* 메서드), 1356
 clearok() (*curses.window* 메서드), 556
 clearscreen() (*turtle* 모듈), 1119
 clearstamp() (*turtle* 모듈), 1105
 clearstamps() (*turtle* 모듈), 1106
 Client() (*multiprocessing.connection* 모듈), 659
 client_address (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
 --clock
 timeit command line option, 1224
 clock() (*time* 모듈), 453
 clone() (*email.generator.Generator* 메서드), 767
 clone() (*pipes.Template* 메서드), 1381
 clone() (*turtle* 모듈), 1117
 cloneNode() (*xml.dom.minidom.Node* 메서드), 875
 cloneNode() (*xml.dom.Node* 메서드), 866
 Close() (*_winreg.PyHKEY* 메서드), 1368
 close() (*aifc.aifc* 메서드), 1022, 1023
 close() (*anydbm* 모듈), 330
 close() (*asyncore.dispatcher* 메서드), 751
 close() (*bsddb.bsddbobject* 메서드), 335
 close() (*bz2.BZ2File* 메서드), 364
 close() (*chunk.Chunk* 메서드), 1029
 close() (*Connection* 메서드), 644
 close() (*dbm* 모듈), 331
 close() (*dl.dl* 메서드), 1376
 close() (*dumbdbm* 모듈), 337
 close() (*email.parser.FeedParser* 메서드), 765
 close() (*file* 메서드), 56
 close() (*fileinput* 모듈), 294
 close() (*FrameWork.Window* 메서드), 1400
 close() (*ftplib.FTP* 메서드), 947
 close() (*gdbm* 모듈), 333
 close() (*hotshot.Profile* 메서드), 1221
 close() (*HTMLParser.HTMLParser* 메서드), 839
 close() (*httplib.HTTPConnection* 메서드), 941
 close() (*imaplib.IMAP4* 메서드), 952
 close() (*io.IOBase* 메서드), 443
 close() (*logging.FileHandler* 메서드), 540
 close() (*logging.Handler* 메서드), 521
 close() (*logging.handlers.MemoryHandler* 메서드), 547
 close() (*logging.handlers.NTEventLogHandler* 메서드), 546
 close() (*logging.handlers.SocketHandler* 메서드), 543
 close() (*logging.handlers.SysLogHandler* 메서드), 544
 close() (*mailbox.Mailbox* 메서드), 800
 close() (*mailbox.Maildir* 메서드), 802
 close() (*mailbox.MH* 메서드), 804
 close() (*mmap.mmap* 메서드), 688

- Close() (*msilib.View* 메서드), 1355
- close() (*multiprocessing.connection.Listener* 메서드), 660
- close() (*multiprocessing.pool.multiprocessing.Pool* 메서드), 658
- close() (*multiprocessing.Queue* 메서드), 642
- close() (*os* 모듈), 417
- close() (*ossaudiodev.oss_audio_device* 메서드), 1032
- close() (*ossaudiodev.oss_mixer_device* 메서드), 1035
- close() (*select.epoll* 메서드), 617
- close() (*select.kqueue* 메서드), 618
- close() (*sgmlib.SGMLParser* 메서드), 843
- close() (*shelve.Shelf* 메서드), 326
- close() (*socket.socket* 메서드), 713
- close() (*sqlite3.Connection* 메서드), 342
- close() (*StringIO.StringIO* 메서드), 119
- close() (*sunau.AU_read* 메서드), 1025
- close() (*sunau.AU_write* 메서드), 1026
- close() (*tarfile.TarFile* 메서드), 377
- close() (*telnetlib.Telnet* 메서드), 966
- close() (*urllib2.BaseHandler* 메서드), 931
- close() (*wave.Wave_read* 메서드), 1027
- close() (*wave.Wave_write* 메서드), 1028
- close() (*xml.etree.ElementTree.TreeBuilder* 메서드), 860
- close() (*xml.etree.ElementTree.XMLParser* 메서드), 861
- close() (*xml.sax.xmlreader.IncrementalParser* 메서드), 888
- close() (*zipfile.ZipFile* 메서드), 367
- close_when_done() (*asynchat.async_chat* 메서드), 754
- closed (*file*의 속성), 59
- closed (*io.IOBase*의 속성), 443
- closed (*ossaudiodev.oss_audio_device*의 속성), 1034
- CloseKey() (*_winreg* 모듈), 1361
- closelog() (*syslog* 모듈), 1387
- closerange() (*os* 모듈), 418
- closing() (*contextlib* 모듈), 1259
- clrtoebot() (*curses.window* 메서드), 556
- clrtoeol() (*curses.window* 메서드), 556
- cmath (모듈), 229
- cmd
 - 모듈, 1207
- Cmd (*cmd* 클래스), 1055
- cmd (*subprocess.CalledProcessError*의 속성), 697
- cmd (모듈), 1055
- cmdloop() (*cmd.Cmd* 메서드), 1056
- cmdqueue (*cmd.Cmd*의 속성), 1057
- cmp
 - 내장 함수, 1051
- cmp() (*filecmp* 모듈), 300
- cmp() (내장 함수), 7
- cmp_op (*dis* 모듈), 1330
- cmp_to_key() (*functools* 모듈), 277
- cmpfiles() (*filecmp* 모듈), 300
- code (*urllib2.HTTPError*의 속성), 926
- code (모듈), 1283
- code (*xml.parsers.expat.ExpatError*의 속성), 895
- code object, 63, 328
- code() (*new* 모듈), 214
- Codecs, 123
 - decode, 123
 - encode, 123
- codecs (모듈), 123
- coded_value (*Cookie.Morsel*의 속성), 1000
- codeop (모듈), 1285
- codepoint2name (*htmlentitydefs* 모듈), 847
- CODESET (*locale* 모듈), 1049
- CodeType (*types* 모듈), 212
- coerce() (내장 함수), 27
- coercion (코어션), 1440
- col_offset (*ast.AST*의 속성), 1314
- collapse_rfc2231_value() (*email.utils* 모듈), 778
- collect() (*gc* 모듈), 1269
- collect_incoming_data() (*asynchat.async_chat* 메서드), 754
- collections (모듈), 172
- COLON (*token* 모듈), 1321
- color() (*ft* 모듈), 1422
- color() (*turtle* 모듈), 1111
- color_content() (*curses* 모듈), 549
- color_pair() (*curses* 모듈), 549
- colormode() (*turtle* 모듈), 1122
- ColorPicker (모듈), 1405
- colorsys (모듈), 1030
- column() (*tk.Treeview* 메서드), 1087
- COLUMNS, 554
- combinations() (*itertools* 모듈), 265
- combinations_with_replacement() (*itertools* 모듈), 266
- combine() (*datetime.datetime*의 클래스 메서드), 151
- combining() (*unicodedata* 모듈), 138
- ComboBox (*Tix* 클래스), 1094
- Combobox (*tk* 클래스), 1080
- COMMA (*token* 모듈), 1321
- command (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
- CommandCompiler (*codeop* 클래스), 1286
- commands (모듈), 1388
- comment (*cookielib.Cookie*의 속성), 996
- COMMENT (*tokenize* 모듈), 1324
- comment (*zipfile.ZipFile*의 속성), 370
- comment (*zipfile.ZipInfo*의 속성), 371
- Comment() (*xml.etree.ElementTree* 모듈), 855
- comment_url (*cookielib.Cookie*의 속성), 996
- commenters (*shlex.shlex*의 속성), 1059

- `CommentHandler()` (*xml.parsers.expat.xmlparser* 메서드), 894
- `commit()` (*msilib.CAB* 메서드), 1356
- `Commit()` (*msilib.Database* 메서드), 1354
- `commit()` (*sqlite3.Connection* 메서드), 341
- `common` (*filecmp.dircmp*의 속성), 301
- Common Gateway Interface, 902
- `common_dirs` (*filecmp.dircmp*의 속성), 301
- `common_files` (*filecmp.dircmp*의 속성), 301
- `common_funny` (*filecmp.dircmp*의 속성), 301
- `common_types` (*mimetypes* 모듈), 821
- `commonprefix()` (*os.path* 모듈), 290
- `communicate()` (*subprocess.Popen* 메서드), 701
- `compare()` (*decimal.Context* 메서드), 246
- `compare()` (*decimal.Decimal* 메서드), 237
- `compare()` (*difflib.Differ* 메서드), 116
- `compare_digest()` (*hmac* 모듈), 408
- `COMPARE_OP` (*opcode*), 1336
- `compare_signal()` (*decimal.Context* 메서드), 246
- `compare_signal()` (*decimal.Decimal* 메서드), 237
- `compare_total()` (*decimal.Context* 메서드), 246
- `compare_total()` (*decimal.Decimal* 메서드), 237
- `compare_total_mag()` (*decimal.Context* 메서드), 246
- `compare_total_mag()` (*decimal.Decimal* 메서드), 237
- comparing
 - objects, 32
- comparison
 - operator, 32
- `Comparison` (*aetypes* 클래스), 1412
- `COMPARISON_FLAGS` (*doctest* 모듈), 1149
- comparisons
 - chaining, 32
- compile
 - 내장 함수, 64, 212, 1311
- `Compile` (*codeop* 클래스), 1286
- `compile()` (*compiler* 모듈), 1339
- `compile()` (*parser.ST* 메서드), 1312
- `compile()` (*py_compile* 모듈), 1327
- `compile()` (*re* 모듈), 93
- `compile()` (내장 함수), 7
- `compile_command()` (*code* 모듈), 1283
- `compile_command()` (*codeop* 모듈), 1285
- `compile_dir()` (*compileall* 모듈), 1328
- `compile_file()` (*compileall* 모듈), 1328
- `compile_path()` (*compileall* 모듈), 1329
- `compileall` (모듈), 1327
- `compileall` command line option
 - d destdir, 1328
 - directory ..., 1328
 - f, 1328
 - file ..., 1328
 - i list, 1328
 - l, 1328
 - q, 1328
 - x regex, 1328
- `compileFile()` (*compiler* 모듈), 1340
- `compiler` (모듈), 1339
- `compiler.ast` (모듈), 1340
- `compiler.visitor` (모듈), 1346
- `compilest()` (*parser* 모듈), 1311
- `complete()` (*rlcompleter.Completer* 메서드), 693
- `complete_statement()` (*sqlite3* 모듈), 340
- `completedefault()` (*cmd.Cmd* 메서드), 1056
- complex
 - 내장 함수, 33
- `Complex` (*numbers* 클래스), 221
- `complex` (내장 클래스), 8
- complex number
 - literals, 33
 - 객체, 33
- complex number (복소수), 1440
- `ComplexType` (*types* 모듈), 211
- `ComponentItem` (*aetypes* 클래스), 1412
- `compress()` (*bz2* 모듈), 366
- `compress()` (*bz2.BZ2Compressor* 메서드), 365
- `compress()` (*itertools* 모듈), 267
- `compress()` (*jpeg* 모듈), 1430
- `compress()` (*zlib* 모듈), 360
- `compress()` (*zlib.Compress* 메서드), 361
- `compress_size` (*zipfile.ZipInfo*의 속성), 371
- `compress_type` (*zipfile.ZipInfo*의 속성), 371
- `compression()` (*ssl.SSLSocket* 메서드), 731
- `CompressionError`, 374
- `compressobj()` (*zlib* 모듈), 360
- `COMSPEC`, 436, 699
- `concat()` (*operator* 모듈), 282
- concatenation
 - operation, 38
- `Condition` (*multiprocessing* 클래스), 646
- `Condition` (*threading* 클래스), 627
- `condition()` (*msilib.Control* 메서드), 1358
- `Condition()` (*multiprocessing.managers.SyncManager* 메서드), 652
- `ConfigParser` (*ConfigParser* 클래스), 392
- `ConfigParser` (모듈), 391
- configuration
 - file, 391
 - file, debugger, 1210
 - file, path, 1277
 - file, user, 1279
- configuration information, 1247
- `configure()` (*tk.Style* 메서드), 1090
- `confstr()` (*os* 모듈), 439
- `confstr_names` (*os* 모듈), 439
- `conjugate()` (*complex number method*), 34
- `conjugate()` (*decimal.Decimal* 메서드), 238

- `conjugate()` (*numbers.Complex* 메서드), 221
- `connect()` (*asyncore.dispatcher* 메서드), 751
- `connect()` (*ftplib.FTP* 메서드), 945
- `connect()` (*httplib.HTTPConnection* 메서드), 941
- `connect()` (*multiprocessing.managers.BaseManager* 메서드), 651
- `connect()` (*smtplib.SMTP* 메서드), 961
- `connect()` (*socket.socket* 메서드), 713
- `connect()` (*sqlite3* 모듈), 340
- `connect_ex()` (*socket.socket* 메서드), 714
- `Connection` (*sqlite3* 클래스), 341
- `connection` (*sqlite3.Cursor*의 속성), 349
- `Connection` (내장 클래스), 644
- `ConnectRegistry()` (*_winreg* 모듈), 1361
- `const` (*optparse.Option*의 속성), 501
- `constructor()` (*copy_reg* 모듈), 324
- `container`
 - iteration over, 37
- `Container` (*collections* 클래스), 185
- `contains()` (*operator* 모듈), 282
- `content type`
 - MIME, 820
- `ContentHandler` (*xml.sax.handler* 클래스), 880
- `contents` (*ctypes._Pointer*의 속성), 613
- `ContentTooShortError`, 923
- `Context` (*decimal* 클래스), 244
- `context` (*ssl.SSLSocket*의 속성), 732
- `context management protocol`, 61
- `context manager`, 61
- `context manager` (컨텍스트 관리자), 1440
- `context_diff()` (*difflib* 모듈), 110
- `contextlib` (모듈), 1257
- `contextmanager()` (*contextlib* 모듈), 1257
- `CONTINUE_LOOP` (*opcode*), 1334
- `control` (*cd* 모듈), 1418
- `Control` (*msilib* 클래스), 1358
- `Control` (*Tix* 클래스), 1094
- `control()` (*msilib.Dialog* 메서드), 1358
- `control()` (*select.kqueue* 메서드), 618
- `controlnames` (*curses.ascii* 모듈), 569
- `controls()` (*ossaudiodev.oss_mixer_device* 메서드), 1035
- `ConversionError`, 402
- `conversions`
 - numeric, 34
- `convert()` (*email.charset.Charset* 메서드), 773
- `convert_arg_line_to_args()` (*argparse.ArgumentParser* 메서드), 486
- `convert_charref()` (*sgmlib.SGMLParser* 메서드), 843
- `convert_codepoint()` (*sgmlib.SGMLParser* 메서드), 844
- `convert_entityref()` (*sgmlib.SGMLParser* 메서드), 844
- `convert_field()` (*string.Formatter* 메서드), 77
- `Cookie` (*cookielib* 클래스), 990
- `Cookie` (모듈), 998
- `CookieError`, 998
- `CookieJar` (*cookielib* 클래스), 990
- `cookiejar` (*urllib2.HTTPCookieProcessor*의 속성), 933
- `cookielib` (모듈), 989
- `CookiePolicy` (*cookielib* 클래스), 990
- `Coordinated Universal Time`, 452
- `Copy`, 1132
- `copy`
 - 모듈, 324
- `copy` (모듈), 214
- `copy()` (*copy* 모듈), 214
- `copy()` (*decimal.Context* 메서드), 245
- `copy()` (*dict* 메서드), 53
- `copy()` (*findertools* 모듈), 1395
- `copy()` (*frozenset* 메서드), 50
- `copy()` (*hashlib.hash* 메서드), 407
- `copy()` (*hmac.HMAC* 메서드), 408
- `copy()` (*imaplib.IMAP4* 메서드), 952
- `copy()` (*macostools* 모듈), 1394
- `copy()` (*md5.md5* 메서드), 409
- `copy()` (*multiprocessing.sharedctypes* 모듈), 649
- `copy()` (*pipes.Template* 메서드), 1382
- `copy()` (*sha.sha* 메서드), 410
- `copy()` (*shutil* 모듈), 308
- `copy()` (*zlib.Compress* 메서드), 361
- `copy()` (*zlib.Decompress* 메서드), 362
- `copy2()` (*shutil* 모듈), 308
- `copy_abs()` (*decimal.Context* 메서드), 246
- `copy_abs()` (*decimal.Decimal* 메서드), 238
- `copy_decimal()` (*decimal.Context* 메서드), 245
- `copy_location()` (*ast* 모듈), 1317
- `copy_negate()` (*decimal.Context* 메서드), 246
- `copy_negate()` (*decimal.Decimal* 메서드), 238
- `copy_reg` (모듈), 324
- `copy_sign()` (*decimal.Context* 메서드), 246
- `copy_sign()` (*decimal.Decimal* 메서드), 238
- `copybinary()` (*mimetools* 모듈), 819
- `copyfile()` (*shutil* 모듈), 308
- `copyfileobj()` (*shutil* 모듈), 308
- `copying files`, 307
- `copyliteral()` (*mimetools* 모듈), 819
- `copymessage()` (*mhlib.Folder* 메서드), 818
- `copymode()` (*shutil* 모듈), 308
- `copyright` (*sys* 모듈), 1235
- `copyright` (내장 변수), 30
- `copysign()` (*math* 모듈), 225
- `copystat()` (*shutil* 모듈), 308
- `copytree()` (*macostools* 모듈), 1394
- `copytree()` (*shutil* 모듈), 308
- `cos()` (*cmath* 모듈), 230
- `cos()` (*math* 모듈), 227

`cosh()` (*cmath* 모듈), 230
`cosh()` (*math* 모듈), 227
`--count`
 trace command line option, 1227
`count()` (*array.array* 메서드), 194
`count()` (*collections.deque* 메서드), 175
`count()` (*itertools* 모듈), 267
`count()` (*list* method), 48
`count()` (*str* 메서드), 39
`count()` (*string* 모듈), 86
`Counter` (*collections* 클래스), 172
`countOf()` (*operator* 모듈), 282
`countTestCases()` (*unittest.TestCase* 메서드), 1180
`countTestCases()` (*unittest.TestSuite* 메서드), 1182
`CoverageResults` (*trace* 클래스), 1228
`--coverdir=<dir>`
 trace command line option, 1227
`cPickle`
 모듈, 324
`cPickle` (모듈), 324
`cProfile` (모듈), 1215
CPU time, 453
`cpu_count()` (*multiprocessing* 모듈), 643
`CPython`, 1440
`CRC` (*zipfile.ZipInfo*의 속성), 371
`crc32()` (*binascii* 모듈), 834
`crc32()` (*zlib* 모듈), 360
`crc_hqx()` (*binascii* 모듈), 834
`create()` (*imaplib.IMAP4* 메서드), 952
`create_aggregate()` (*sqlite3.Connection* 메서드), 342
`create_collation()` (*sqlite3.Connection* 메서드), 343
`create_connection()` (*socket* 모듈), 709
`create_decimal()` (*decimal.Context* 메서드), 245
`create_decimal_from_float()` (*decimal.Context* 메서드), 245
`create_default_context()` (*ssl* 모듈), 722
`create_function()` (*sqlite3.Connection* 메서드), 342
`CREATE_NEW_CONSOLE` (*subprocess* 모듈), 703
`CREATE_NEW_PROCESS_GROUP` (*subprocess* 모듈), 703
`create_socket()` (*asyncore.dispatcher* 메서드), 751
`create_stats()` (*profile.Profile* 메서드), 1216
`create_string_buffer()` (*ctypes* 모듈), 605
`create_system` (*zipfile.ZipInfo*의 속성), 371
`create_unicode_buffer()` (*ctypes* 모듈), 605
`create_version` (*zipfile.ZipInfo*의 속성), 371
`createAttribute()` (*xml.dom.Document* 메서드), 868
`createAttributeNS()` (*xml.dom.Document* 메서드), 868
`createComment()` (*xml.dom.Document* 메서드), 867
`createDocument()` (*xml.dom.DOMImplementation* 메서드), 864
`createDocumentType()`
 (*xml.dom.DOMImplementation* 메서드), 864
`createElement()` (*xml.dom.Document* 메서드), 867
`createElementNS()` (*xml.dom.Document* 메서드), 867
`createfilehandler()` (*Tkinter.Widget.tk* 메서드), 1074
`CreateKey()` (*_winreg* 모듈), 1361
`CreateKeyEx()` (*_winreg* 모듈), 1361
`createLock()` (*logging.Handler* 메서드), 521
`createLock()` (*logging.NullHandler* 메서드), 540
`createparser()` (*cd* 모듈), 1417
`createProcessingInstruction()`
 (*xml.dom.Document* 메서드), 868
`CreateRecord()` (*msilib* 모듈), 1354
`createSocket()` (*logging.handlers.SocketHandler* 메서드), 543
`createTextNode()` (*xml.dom.Document* 메서드), 867
`credits` (내장 변수), 30
`critical()` (*logging* 모듈), 527
`critical()` (*logging.Logger* 메서드), 519
`CRNCYSTR` (*locale* 모듈), 1049
`crop()` (*imageop* 모듈), 1020
`cross()` (*audioop* 모듈), 1018
`crypt`
 모듈, 1372
`crypt` (모듈), 1374
`crypt()` (*crypt* 모듈), 1374
`crypt(3)`, 1374
`cryptography`, 405
`cStringIO` (모듈), 120
`csv`, 383
`csv` (모듈), 383
`ctermid()` (*os* 모듈), 412
`ctime()` (*datetime.date* 메서드), 149
`ctime()` (*datetime.datetime* 메서드), 155
`ctime()` (*time* 모듈), 453
`ctrl()` (*curses.ascii* 모듈), 568
`CTRL_BREAK_EVENT` (*signal* 모듈), 745
`CTRL_C_EVENT` (*signal* 모듈), 745
`ctypes` (모듈), 580
`curdir` (*os* 모듈), 439
`currency()` (*locale* 모듈), 1051
`current()` (*tk.ComboBox* 메서드), 1080
`current_process()` (*multiprocessing* 모듈), 643
`current_thread()` (*threading* 모듈), 621
`CurrentByteIndex` (*xml.parsers.expat.xmlparser*의 속성), 893
`CurrentColumnNumber` (*xml.parsers.expat.xmlparser*의 속성), 893

currentframe() (*inspect* 모듈), 1277
 CurrentLineNumber (*xml.parsers.expat.xmlparser*의 속성), 893
 currentThread() (*threading* 모듈), 621
 curs_set() (*curses* 모듈), 550
 curses (모듈), 548
 curses.ascii (모듈), 567
 curses.panel (모듈), 569
 curses.textpad (모듈), 565
 Cursor (*sqlite3* 클래스), 347
 cursor() (*sqlite3.Connection* 메서드), 341
 cursyncup() (*curses.window* 메서드), 557
 curval (*EasyDialogs.ProgressBar*의 속성), 1397
 Cut, 1132
 cwd() (*ftplib.FTP* 메서드), 947
 cycle() (*itertools* 모듈), 267
 Cyclic Redundancy Check, 360

D

-d destdir
 compileall command line option, 1328
 D_FMT (*locale* 모듈), 1049
 D_T_FMT (*locale* 모듈), 1049
 daemon (*multiprocessing.Process*의 속성), 639
 daemon (*threading.Thread*의 속성), 624
 data
 packing binary, 104
 tabular, 383
 Data (*plistlib* 클래스), 403
 data (*select.kevent*의 속성), 620
 data (*UserDict.IterableUserDict*의 속성), 209
 data (*UserList.UserList*의 속성), 210
 data (*UserString.MutableString*의 속성), 211
 data (*xml.dom.Comment*의 속성), 870
 data (*xml.dom.ProcessingInstruction*의 속성), 870
 data (*xml.dom.Text*의 속성), 870
 data (*xmlrpclib.Binary*의 속성), 1006
 data() (*xml.etree.ElementTree.TreeBuilder* 메서드), 860
 database
 Unicode, 138
 databases, 337
 DatagramHandler (*logging.handlers* 클래스), 544
 DatagramRequestHandler (*SocketServer* 클래스), 979
 DATASIZE (*cd* 모듈), 1418
 date (*datetime* 클래스), 147
 date() (*datetime.datetime* 메서드), 153
 date() (*nnplib.NNTP* 메서드), 959
 date_time (*zipfile.ZipInfo*의 속성), 370
 date_time_string() (Base-
 HTTPServer.BaseHTTPRequestHandler 메서드), 986
 datetime (*datetime* 클래스), 150
 datetime (모듈), 143

DateTime (*xmlrpclib* 클래스), 1005
 day (*datetime.datetime*의 속성), 152
 day (*datetime.date*의 속성), 148
 day_abbr (*calendar* 모듈), 171
 day_name (*calendar* 모듈), 171
 daylight (*time* 모듈), 453
 Daylight Saving Time, 452
 DbfilenameShelf (*shelve* 클래스), 326
 dbhash
 모듈, 329
 dbhash (모듈), 333
 dbm
 모듈, 326, 329, 332
 dbm (모듈), 331
 dcgettext() (*locale* 모듈), 1053
 deactivate_form() (*fl.form* 메서드), 1423
 debug (*imaplib.IMAP4*의 속성), 955
 DEBUG (*re* 모듈), 93
 debug (*shlex.shlex*의 속성), 1060
 debug (*zipfile.ZipFile*의 속성), 370
 debug() (*doctest* 모듈), 1162
 debug() (*logging* 모듈), 526
 debug() (*logging.Logger* 메서드), 519
 debug() (*pipes.Template* 메서드), 1381
 debug() (*unittest.TestCase* 메서드), 1175
 debug() (*unittest.TestSuite* 메서드), 1182
 DEBUG_COLLECTABLE (*gc* 모듈), 1270
 DEBUG_INSTANCES (*gc* 모듈), 1271
 DEBUG_LEAK (*gc* 모듈), 1271
 DEBUG_OBJECTS (*gc* 모듈), 1271
 DEBUG_SAVEALL (*gc* 모듈), 1271
 debug_src() (*doctest* 모듈), 1163
 DEBUG_STATS (*gc* 모듈), 1270
 DEBUG_UNCOLLECTABLE (*gc* 모듈), 1270
 debugger, 1132, 1241, 1245
 configuration file, 1210
 debugging, 1207
 CGI, 908
 DebuggingServer (*smtpd* 클래스), 965
 DebugRunner (*doctest* 클래스), 1163
 DebugStr() (*MacOS* 모듈), 1393
 Decimal (*decimal* 클래스), 235
 decimal (모듈), 231
 decimal() (*unicodedata* 모듈), 138
 DecimalException (*decimal* 클래스), 249
 decode
 Codecs, 123
 decode() (*base64* 모듈), 832
 decode() (*codecs* 모듈), 123
 decode() (*codecs.Codec* 메서드), 127
 decode() (*codecs.IncrementalDecoder* 메서드), 129
 decode() (*json.JSONDecoder* 메서드), 793
 decode() (*mimetools* 모듈), 819
 decode() (*quopri* 모듈), 835

- `decode()` (*str* 메서드), 39
- `decode()` (*uu* 모듈), 836
- `decode()` (*xmlrpclib.Binary* 메서드), 1006
- `decode()` (*xmlrpclib.DateTime* 메서드), 1005
- `decode_header()` (*email.header* 모듈), 772
- `decode_params()` (*email.utils* 모듈), 778
- `decode_rfc2231()` (*email.utils* 모듈), 778
- `DecodedGenerator` (*email.generator* 클래스), 768
- `decodestring()` (*base64* 모듈), 832
- `decodestring()` (*quopri* 모듈), 835
- `decomposition()` (*unicodedata* 모듈), 138
- `decompress()` (*bz2* 모듈), 366
- `decompress()` (*bz2.BZ2Decompressor* 메서드), 366
- `decompress()` (*jpeg* 모듈), 1430
- `decompress()` (*zlib* 모듈), 360
- `decompress()` (*zlib.Decompress* 메서드), 362
- `decompressobj()` (*zlib* 모듈), 361
- `decorator` (데코레이터), 1440
- `DEDENT` (*token* 모듈), 1321
- `dedent()` (*textwrap* 모듈), 121
- `deepcopy()` (*copy* 모듈), 214
- `def_prog_mode()` (*curses* 모듈), 550
- `def_shell_mode()` (*curses* 모듈), 550
- `default` (*optparse.Option*의 속성), 501
- `default()` (*cmd.Cmd* 메서드), 1056
- `default()` (*compiler.visitor.ASTVisitor* 메서드), 1346
- `default()` (*json.JSONEncoder* 메서드), 794
- `DEFAULT_BUFFER_SIZE` (*io* 모듈), 441
- `default_bufsize` (*xml.dom.pulldom* 모듈), 878
- `default_factory` (*collections.defaultdict*의 속성), 178
- `DEFAULT_FORMAT` (*tarfile* 모듈), 374
- `default_open()` (*urllib2.BaseHandler* 메서드), 931
- `default_timer()` (*timeit* 모듈), 1223
- `DefaultContext` (*decimal* 클래스), 244
- `DefaultCookiePolicy` (*cookielib* 클래스), 990
- `defaultdict` (*collections* 클래스), 178
- `DefaultHandler()` (*xml.parsers.expat.xmlparser* 메서드), 894
- `DefaultHandlerExpand()`
(*xml.parsers.expat.xmlparser* 메서드), 895
- `defaults()` (*ConfigParser.RawConfigParser* 메서드), 393
- `defaultTestLoader` (*unittest* 모듈), 1185
- `defaultTestResult()` (*unittest.TestCase* 메서드), 1180
- `defects` (*email.message.Message*의 속성), 764
- `defpath` (*os* 모듈), 440
- `degrees()` (*math* 모듈), 227
- `degrees()` (*turtle* 모듈), 1108
- `del`
글, 48, 52
- `del_param()` (*email.message.Message* 메서드), 762
- `delattr()` (내장 함수), 8
- `delay()` (*turtle* 모듈), 1120
- `delay_output()` (*curses* 모듈), 550
- `delayload` (*cookielib.FileCookieJar*의 속성), 992
- `delch()` (*curses.window* 메서드), 557
- `dele()` (*poplib.POP3* 메서드), 949
- `delete()` (*ftplib.FTP* 메서드), 947
- `delete()` (*imaplib.IMAP4* 메서드), 952
- `delete()` (*tk.Treeview* 메서드), 1087
- `DELETE_ATTR` (*opcode*), 1335
- `DELETE_FAST` (*opcode*), 1336
- `DELETE_GLOBAL` (*opcode*), 1335
- `DELETE_NAME` (*opcode*), 1335
- `DELETE_SLICE+0` (*opcode*), 1333
- `DELETE_SLICE+1` (*opcode*), 1333
- `DELETE_SLICE+2` (*opcode*), 1333
- `DELETE_SLICE+3` (*opcode*), 1333
- `DELETE_SUBSCR` (*opcode*), 1333
- `deleteacl()` (*imaplib.IMAP4* 메서드), 952
- `deletetextfilehandler()` (*Tkinter.Widget.tk* 메서드), 1074
- `deletetefolder()` (*mhlib.MH* 메서드), 817
- `DeleteKey()` (*_winreg* 모듈), 1362
- `DeleteKeyEx()` (*_winreg* 모듈), 1362
- `deleteln()` (*curses.window* 메서드), 557
- `deleteMe()` (*bdb.Breakpoint* 메서드), 1203
- `DeleteValue()` (*_winreg* 모듈), 1362
- `delimiter` (*csv.Dialect*의 속성), 387
- `delitem()` (*operator* 모듈), 282
- `deliver_challenge()` (*multiprocessing.connection* 모듈), 659
- `delslice()` (*operator* 모듈), 282
- `demo_app()` (*wsgiref.simple_server* 모듈), 913
- `denominator` (*numbers.Rational*의 속성), 222
- `DeprecationWarning`, 72
- `deque` (*collections* 클래스), 175
- `DER_cert_to_PEM_cert()` (*ssl* 모듈), 724
- `derwin()` (*curses.window* 메서드), 557
- `DES`
cipher, 1374
- `description` (*sqlite3.Cursor*의 속성), 349
- `description()` (*nntplib.NNTP* 메서드), 958
- `descriptions()` (*nntplib.NNTP* 메서드), 958
- `descriptor`
file, 57
- `descriptor` (디스크립터), 1441
- `dest` (*optparse.Option*의 속성), 501
- `Detach()` (*_winreg.PyHKEY* 메서드), 1368
- `detach()` (*io.BufferedIOBase* 메서드), 445
- `detach()` (*io.TextIOBase* 메서드), 448
- `detach()` (*tk.Treeview* 메서드), 1087
- `deterministic profiling`, 1212
- `DEVICE` (모듈), 1429
- `devnull` (*os* 모듈), 440
- `dgettext()` (*gettext* 모듈), 1038

- dgettext() (*locale* 모듈), 1053
- Dialect (*csv* 클래스), 386
- dialect (*csv.csvreader*의 속성), 388
- dialect (*csv.csvwriter*의 속성), 388
- Dialog (*msilib* 클래스), 1358
- DialogWindow() (*FrameWork* 모듈), 1399
- dict (2to3 fixer), 1192
- dict (내장 클래스), 52
- dict() (*multiprocessing.managers.SyncManager* 메서드), 652
- dictConfig() (*logging.config* 모듈), 530
- dictionary
 - type, operations on, 52
 - 개체, 52
- dictionary (딕셔너리), 1441
- dictionary view (딕셔너리 뷰), 1441
- DictionaryType (*types* 모듈), 212
- DictMixin (*UserDict* 클래스), 209
- DictProxyType (*types* 모듈), 213
- DictReader (*csv* 클래스), 385
- DictType (*types* 모듈), 212
- DictWriter (*csv* 클래스), 385
- diff_files (*filecmp.dircmp*의 속성), 301
- Differ (*difflib* 클래스), 109, 116
- difference() (*frozenset* 메서드), 50
- difference_update() (*frozenset* 메서드), 51
- difflib (모듈), 109
- digest() (*hashlib.hash* 메서드), 407
- digest() (*hmac.HMAC* 메서드), 408
- digest() (*md5.md5* 메서드), 409
- digest() (*sha.sha* 메서드), 410
- digest_size (*md5* 모듈), 409
- digest_size (*sha* 모듈), 410
- digit() (*unicodedata* 모듈), 138
- digits (*string* 모듈), 76
- dir() (*ftplib.FTP* 메서드), 947
- dir() (내장 함수), 8
- dircache (모듈), 312
- dircmp (*filecmp* 클래스), 300
- directory
 - changing, 422
 - creating, 425
 - deleting, 309, 426
 - site-packages, 1277
 - site-python, 1277
 - traversal, 429
 - walking, 429
- directory ...
 - compileall command line option, 1328
- Directory (*msilib* 클래스), 1357
- DirList (*Tix* 클래스), 1095
- dirname() (*os.path* 모듈), 290
- DirSelectBox (*Tix* 클래스), 1095
- DirSelectDialog (*Tix* 클래스), 1095
- DirTree (*Tix* 클래스), 1095
- dis (모듈), 1329
- dis() (*dis* 모듈), 1329
- dis() (*pickletools* 모듈), 1338
- disable() (*bdb.Breakpoint* 메서드), 1204
- disable() (*gc* 모듈), 1268
- disable() (*logging* 모듈), 528
- disable() (*profile.Profile* 메서드), 1216
- disable_interspersed_args() (*optparse.OptionParser* 메서드), 506
- DisableReflectionKey() (*_winreg* 모듈), 1365
- disassemble() (*dis* 모듈), 1330
- discard (*cookielib.Cookie*의 속성), 996
- discard() (*frozenset* 메서드), 51
- discard() (*mailbox.Mailbox* 메서드), 798
- discard() (*mailbox.MH* 메서드), 803
- discard_buffers() (*asynchat.async_chat* 메서드), 754
- disco() (*dis* 모듈), 1330
- discover() (*unittest.TestLoader* 메서드), 1183
- dispatch() (*compiler.visitor.ASTVisitor* 메서드), 1346
- dispatch_call() (*bdb.Bdb* 메서드), 1205
- dispatch_exception() (*bdb.Bdb* 메서드), 1205
- dispatch_line() (*bdb.Bdb* 메서드), 1205
- dispatch_return() (*bdb.Bdb* 메서드), 1205
- dispatcher (*asyncore* 클래스), 750
- dispatcher_with_send (*asyncore* 클래스), 751
- displayhook() (*sys* 모듈), 1236
- dist() (*platform* 모듈), 573
- distance() (*turtle* 모듈), 1108
- distb() (*dis* 모듈), 1329
- distutils (모듈), 1231
- dither2grey2() (*imageop* 모듈), 1021
- dither2mono() (*imageop* 모듈), 1021
- div() (*operator* 모듈), 281
- divide() (*decimal.Context* 메서드), 246
- divide_int() (*decimal.Context* 메서드), 246
- division
 - integer, 34
 - long integer, 34
- DivisionByZero (*decimal* 클래스), 249
- divmod() (*decimal.Context* 메서드), 246
- divmod() (내장 함수), 9
- dl (모듈), 1375
- DllCanUnloadNow() (*ctypes* 모듈), 606
- DllGetClassObject() (*ctypes* 모듈), 606
- dllhandle (*sys* 모듈), 1236
- dngettext() (*gettext* 모듈), 1038
- do_activate() (*FrameWork.ScrolledWindow* 메서드), 1401
- do_activate() (*FrameWork.Window* 메서드), 1400
- do_char() (*FrameWork.Application* 메서드), 1400
- do_clear() (*bdb.Bdb* 메서드), 1205
- do_command() (*curses.textpad.Textbox* 메서드), 566

- `do_contentclick()` (*FrameWork.Window* 메서드), 1400
- `do_controlhit()` (*FrameWork.ControlsWindow* 메서드), 1400
- `do_controlhit()` (*FrameWork.ScrolledWindow* 메서드), 1401
- `do_dialogevent()` (*FrameWork.Application* 메서드), 1400
- `do_forms()` (*fl* 모듈), 1421
- `do_GET()` (*SimpleHTTPServer.SimpleHTTPRequestHandler* 메서드), 987
- `do_handshake()` (*ssl.SSLSocket* 메서드), 730
- `do_HEAD()` (*SimpleHTTPServer.SimpleHTTPRequestHandler* 메서드), 987
- `do_itemhit()` (*FrameWork.DialogWindow* 메서드), 1401
- `do_POST()` (*CGIHTTPServer.CGIHTTPRequestHandler* 메서드), 989
- `do_postresize()` (*FrameWork.ScrolledWindow* 메서드), 1401
- `do_postresize()` (*FrameWork.Window* 메서드), 1400
- `do_update()` (*FrameWork.Window* 메서드), 1400
- `doc_header()` (*cmd.Cmd*의 속성), 1057
- `DocCGIXMLRPCRequestHandler` (*DocXMLRPCServer* 클래스), 1014
- `DocFileSuite()` (*doctest* 모듈), 1154
- `doCleanups()` (*unittest.TestCase* 메서드), 1181
- `doccmd()` (*smtpplib.SMTP* 메서드), 961
- `docstring()` (*doctest.DocTest*의 속성), 1157
- `docstring()` (독스트링), 1441
- `DocTest` (*doctest* 클래스), 1156
- `doctest` (모듈), 1140
- `DocTestFailure`, 1163
- `DocTestFinder` (*doctest* 클래스), 1158
- `DocTestParser` (*doctest* 클래스), 1159
- `DocTestRunner` (*doctest* 클래스), 1159
- `DocTestSuite()` (*doctest* 모듈), 1155
- `doctype()` (*xml.etree.ElementTree.TreeBuilder* 메서드), 861
- `doctype()` (*xml.etree.ElementTree.XMLParser* 메서드), 861
- `documentation`
 - `generation`, 1139
 - `online`, 1139
- `documentElement` (*xml.dom.Document*의 속성), 867
- `DocXMLRPCRequestHandler` (*DocXMLRPCServer* 클래스), 1014
- `DocXMLRPCServer` (*DocXMLRPCServer* 클래스), 1014
- `DocXMLRPCServer` (모듈), 1014
- `domain_initial_dot` (*cookieilib.Cookie*의 속성), 997
- `domain_return_ok()` (*cookieilib.CookiePolicy* 메서드), 993
- `domain_specified` (*cookieilib.Cookie*의 속성), 997
- `DomainLiberal` (*cookieilib.DefaultCookiePolicy*의 속성), 996
- `DomainRFC2965Match` (*cookieilib.DefaultCookiePolicy*의 속성), 996
- `DomainStrict` (*cookieilib.DefaultCookiePolicy*의 속성), 996
- `DomainStrictNoDots` (*cookieilib.DefaultCookiePolicy*의 속성), 995
- `DomainStrictNonDomain` (*cookieilib.DefaultCookiePolicy*의 속성), 995
- `DOMEventStream` (*xml.dom.pulldom* 클래스), 878
- `DOMException`, 870
- `DomstringSizeErr`, 870
- `done()` (*turtle* 모듈), 1116
- `done()` (*xdrlib.Unpacker* 메서드), 401
- `DONT_ACCEPT_BLANKLINE` (*doctest* 모듈), 1148
- `DONT_ACCEPT_TRUE_FOR_1` (*doctest* 모듈), 1147
- `dont_write_bytecode` (*sys* 모듈), 1236
- `doRollover()` (*logging.handlers.RotatingFileHandler* 메서드), 541
- `doRollover()` (*logging.handlers.TimedRotatingFileHandler* 메서드), 542
- `DOT` (*token* 모듈), 1321
- `dot()` (*turtle* 모듈), 1105
- `DOTALL` (*re* 모듈), 93
- `doublequote` (*csv.Dialect*의 속성), 387
- `DOUBLESASH` (*token* 모듈), 1321
- `DOUBLESASHEQUAL` (*token* 모듈), 1321
- `DOUBLESTAR` (*token* 모듈), 1321
- `DOUBLESTAREQUAL` (*token* 모듈), 1321
- `doupdate()` (*curses* 모듈), 550
- `down()` (*turtle* 모듈), 1109
- `drop_whitespace` (*textwrap.TextWrapper*의 속성), 122
- `dropwhile()` (*itertools* 모듈), 268
- `dst()` (*datetime.datetime* 메서드), 154
- `dst()` (*datetime.time* 메서드), 158
- `dst()` (*datetime.tzinfo* 메서드), 160
- `DTDHandler` (*xml.sax.handler* 클래스), 880
- `duck-typing` (덕 타이핑), 1441
- `dumbdbm`
 - 모듈, 329
- `dumbdbm` (모듈), 337
- `DumbWriter` (*formatter* 클래스), 1350
- `dummy_thread` (모듈), 632
- `dummy_threading` (모듈), 632
- `dump()` (*ast* 모듈), 1318
- `dump()` (*json* 모듈), 790
- `dump()` (*marshal* 모듈), 328
- `dump()` (*pickle* 모듈), 315
- `dump()` (*pickle.Pickler* 메서드), 316
- `dump()` (*xml.etree.ElementTree* 모듈), 855

dump_address_pair() (*rfc822* 모듈), 828
 dump_stats() (*profile.Profile* 메서드), 1216
 dump_stats() (*pstats.Stats* 메서드), 1216
 dumps() (*json* 모듈), 791
 dumps() (*marshal* 모듈), 329
 dumps() (*pickle* 모듈), 315
 dumps() (*xmlrpclib* 모듈), 1009
 dup() (*os* 모듈), 418
 dup() (*posixfile.posixfile* 메서드), 1382
 dup2() (*os* 모듈), 418
 dup2() (*posixfile.posixfile* 메서드), 1383
 DUP_TOP (*opcode*), 1331
 DUP_TOPX (*opcode*), 1335
 DuplicateSectionError, 393
 dwFlags (*subprocess.STARTUPINFO*의 속성), 702
 DynLoadSuffixImporter (*imputil* 클래스), 1298

E

e (*cmath* 모듈), 231
 e (*math* 모듈), 228
 -e <zipfile> <output_dir>
 zipfile command line option, 372
 E2BIG (*errno* 모듈), 574
 EACCES (*errno* 모듈), 574
 EADDRINUSE (*errno* 모듈), 578
 EADDRNOTAVAIL (*errno* 모듈), 578
 EADV (*errno* 모듈), 577
 EAFNOSUPPORT (*errno* 모듈), 578
 EAFP, 1441
 EAGAIN (*errno* 모듈), 574
 EALREADY (*errno* 모듈), 579
 east_asian_width() (*unicodedata* 모듈), 138
 EasyDialogs (모듈), 1395
 EBADE (*errno* 모듈), 576
 EBADF (*errno* 모듈), 574
 EBADFD (*errno* 모듈), 577
 EBADMSG (*errno* 모듈), 577
 EBADR (*errno* 모듈), 576
 EBADRQC (*errno* 모듈), 576
 EBADSLT (*errno* 모듈), 576
 EBFONT (*errno* 모듈), 576
 EBUSY (*errno* 모듈), 574
 ECHILD (*errno* 모듈), 574
 echo() (*curses* 모듈), 550
 echochar() (*curses.window* 메서드), 557
 ECHRNA (*errno* 모듈), 576
 ECOMM (*errno* 모듈), 577
 ECONNABORTED (*errno* 모듈), 579
 ECONNREFUSED (*errno* 모듈), 579
 ECONNRESET (*errno* 모듈), 579
 EDEADLK (*errno* 모듈), 575
 EDEADLOCK (*errno* 모듈), 576
 EDESTADDRREQ (*errno* 모듈), 578
 edit() (*curses.textpad.Textbox* 메서드), 566

EDOM (*errno* 모듈), 575
 EDOTDOT (*errno* 모듈), 577
 EDQUOT (*errno* 모듈), 579
 EEXIST (*errno* 모듈), 574
 EFAULT (*errno* 모듈), 574
 EFBIG (*errno* 모듈), 575
 effective() (*bdb* 모듈), 1207
 ehlo() (*smtpplib.SMTP* 메서드), 962
 ehlo_or_helo_if_needed() (*smtpplib.SMTP* 메서드), 962
 EHOSTDOWN (*errno* 모듈), 579
 EHOSTUNREACH (*errno* 모듈), 579
 EIDRM (*errno* 모듈), 576
 EILSEQ (*errno* 모듈), 578
 EINPROGRESS (*errno* 모듈), 579
 EINTR (*errno* 모듈), 574
 EINVAL (*errno* 모듈), 575
 EIO (*errno* 모듈), 574
 EISCONN (*errno* 모듈), 579
 EISDIR (*errno* 모듈), 575
 EISNAM (*errno* 모듈), 579
 EL2HLT (*errno* 모듈), 576
 EL2NSYNC (*errno* 모듈), 576
 EL3HLT (*errno* 모듈), 576
 EL3RST (*errno* 모듈), 576
 Element (*xml.etree.ElementTree* 클래스), 857
 element_create() (*ttk.Style* 메서드), 1091
 element_names() (*ttk.Style* 메서드), 1092
 element_options() (*ttk.Style* 메서드), 1092
 ElementDeclHandler()
 (*xml.parsers.expat.xmlparser* 메서드), 893
 elements() (*collections.Counter* 메서드), 173
 ElementTree (*xml.etree.ElementTree* 클래스), 859
 ELIBACC (*errno* 모듈), 577
 ELIBBAD (*errno* 모듈), 577
 ELIBEXEC (*errno* 모듈), 578
 ELIBMAX (*errno* 모듈), 578
 ELIBSCN (*errno* 모듈), 578
 Ellinghouse, Lance, 836
 ELLIPSIS (*doctest* 모듈), 1148
 Ellipsis (내장 변수), 29
 EllipsisType (*types* 모듈), 212
 ELNRNG (*errno* 모듈), 576
 ELOOP (*errno* 모듈), 576
 email (모듈), 757
 email.charset (모듈), 772
 email.encoders (모듈), 775
 email.errors (모듈), 776
 email.generator (모듈), 767
 email.header (모듈), 770
 email.iterators (모듈), 778
 email.message (모듈), 758
 email.mime (모듈), 768
 email.parser (모듈), 764

- email.utils (모듈), 777
 EMFILE (errno 모듈), 575
 emit () (logging.FileHandler 메서드), 540
 emit () (logging.Handler 메서드), 522
 emit () (logging.handlers.BufferingHandler 메서드), 547
 emit () (logging.handlers.DatagramHandler 메서드), 544
 emit () (logging.handlers.HTTPHandler 메서드), 547
 emit () (logging.handlers.NTEventLogHandler 메서드), 546
 emit () (logging.handlers.RotatingFileHandler 메서드), 541
 emit () (logging.handlers.SMTPHandler 메서드), 546
 emit () (logging.handlers.SocketHandler 메서드), 543
 emit () (logging.handlers.SysLogHandler 메서드), 544
 emit () (logging.handlers.TimedRotatingFileHandler 메서드), 542
 emit () (logging.handlers.WatchedFileHandler 메서드), 541
 emit () (logging.NullHandler 메서드), 540
 emit () (logging.StreamHandler 메서드), 540
 EMLINK (errno 모듈), 575
 Empty, 202
 empty () (multiprocessing.queues.SimpleQueue 메서드), 642
 empty () (multiprocessing.Queue 메서드), 641
 empty () (Queue.Queue 메서드), 203
 empty () (sched.scheduler 메서드), 200
 EMPTY_NAMESPACE (xml.dom 모듈), 863
 emptyline () (cmd.Cmd 메서드), 1056
 EMSGSIZE (errno 모듈), 578
 EMULTIHOP (errno 모듈), 577
 enable () (bdb.Breakpoint 메서드), 1203
 enable () (cgitb 모듈), 909
 enable () (gc 모듈), 1268
 enable () (profile.Profile 메서드), 1215
 enable_callback_tracebacks () (sqlite3 모듈), 341
 enable_interspersed_args () (optparse.OptionParser 메서드), 506
 enable_load_extension () (sqlite3.Connection 메서드), 344
 enable_traversal () (ttk.Notebook 메서드), 1082
 ENABLE_USER_SITE (site 모듈), 1278
 EnableReflectionKey () (_winreg 모듈), 1365
 ENAMETOOLONG (errno 모듈), 575
 ENAVAIL (errno 모듈), 579
 enclose () (curses.window 메서드), 557
 encode
 Codecs, 123
 encode () (base64 모듈), 832
 encode () (codecs 모듈), 123
 encode () (codecs.Codec 메서드), 127
 encode () (codecs.IncrementalEncoder 메서드), 128
 encode () (email.header.Header 메서드), 771
 encode () (json.JSONEncoder 메서드), 794
 encode () (mimetools 모듈), 819
 encode () (quopri 모듈), 835
 encode () (str 메서드), 40
 encode () (uu 모듈), 836
 encode () (xmlrpclib.Binary 메서드), 1006
 encode () (xmlrpclib.Boolean 메서드), 1004
 encode () (xmlrpclib.DateTime 메서드), 1005
 encode_7or8bit () (email.encoders 모듈), 775
 encode_base64 () (email.encoders 모듈), 775
 encode_noop () (email.encoders 모듈), 775
 encode_quopri () (email.encoders 모듈), 775
 encode_rfc2231 () (email.utils 모듈), 778
 encode_threshold (SimpleXMLRPC-Server.SimpleXMLRPCRequestHandler의 속성), 1011
 encoded_header_len () (email.charset.Charset 메서드), 774
 EncodedFile () (codecs 모듈), 126
 encodePriority () (logging.handlers.SysLogHandler 메서드), 544
 encodestring () (base64 모듈), 832
 encodestring () (quopri 모듈), 836
 encoding
 base64, 831
 quoted-printable, 835
 encoding (exceptions.UnicodeError의 속성), 71
 encoding (file의 속성), 59
 encoding (io.TextIOBase의 속성), 448
 ENCODING (tarfile 모듈), 374
 encodings_map (mimetypes 모듈), 821
 encodings_map (mimetypes.MimeTypes의 속성), 822
 encodings.idna (모듈), 137
 encodings.utf_8_sig (모듈), 137
 end (exceptions.UnicodeError의 속성), 71
 end () (re.MatchObject 메서드), 99
 end () (xml.etree.ElementTree.TreeBuilder 메서드), 860
 end_fill () (turtle 모듈), 1112
 END_FINALLY (opcode), 1334
 end_group () (fl.form 메서드), 1423
 end_headers () (BaseHTTPServer.BaseHTTPRequestHandler 메서드), 985
 end_marker () (multifile.MultiFile 메서드), 826
 end_paragraph () (formatter.formatter 메서드), 1348
 end_poly () (turtle 모듈), 1117
 EndCdataSectionHandler () (xml.parsers.expat.xmlparser 메서드), 894
 EndDoctypeDeclHandler () (xml.parsers.expat.xmlparser 메서드), 893
 endDocument () (xml.sax.handler.ContentHandler 메서드), 882

- endElement() (*xml.sax.handler.ContentHandler* 메서드), 883
- EndElementHandler() (*xml.parsers.expat.xmlparser* 메서드), 894
- endElementNS() (*xml.sax.handler.ContentHandler* 메서드), 883
- endheaders() (*httplib.HTTPConnection* 메서드), 941
- ENDMARKER (*token* 모듈), 1321
- EndNamespaceDeclHandler() (*xml.parsers.expat.xmlparser* 메서드), 894
- endpick() (*gl* 모듈), 1428
- endpos (*re.MatchObject*의 속성), 100
- endPrefixMapping() (*xml.sax.handler.ContentHandler* 메서드), 883
- endselect() (*gl* 모듈), 1428
- endswith() (*str* 메서드), 40
- endwin() (*curses* 모듈), 550
- ENETDOWN (*errno* 모듈), 578
- ENETRESET (*errno* 모듈), 579
- ENETUNREACH (*errno* 모듈), 578
- ENFILE (*errno* 모듈), 575
- ENOANO (*errno* 모듈), 576
- ENOBUFFS (*errno* 모듈), 579
- ENOCSS (*errno* 모듈), 576
- ENODATA (*errno* 모듈), 577
- ENODEV (*errno* 모듈), 575
- ENOENT (*errno* 모듈), 574
- ENOEXEC (*errno* 모듈), 574
- ENOLCK (*errno* 모듈), 575
- ENOLINK (*errno* 모듈), 577
- ENOMEM (*errno* 모듈), 574
- ENOMSG (*errno* 모듈), 576
- ENONET (*errno* 모듈), 577
- ENOPKG (*errno* 모듈), 577
- ENOPROTOOPT (*errno* 모듈), 578
- ENOSPC (*errno* 모듈), 575
- ENOSR (*errno* 모듈), 577
- ENOSTR (*errno* 모듈), 577
- ENOSYS (*errno* 모듈), 575
- ENOTBLK (*errno* 모듈), 574
- ENOTCONN (*errno* 모듈), 579
- ENOTDIR (*errno* 모듈), 575
- ENOTEMPTY (*errno* 모듈), 576
- ENOTNAM (*errno* 모듈), 579
- ENOTSOCK (*errno* 모듈), 578
- ENOTTY (*errno* 모듈), 575
- ENOTUNIQ (*errno* 모듈), 577
- ensurepip (모듈), 1232
- enter() (*sched.scheduler* 메서드), 200
- enterabs() (*sched.scheduler* 메서드), 200
- entities (*xml.dom.DocumentType*의 속성), 867
- EntityDeclHandler() (*xml.parsers.expat.xmlparser* 메서드), 894
- entitydefs (*htmlentitydefs* 모듈), 847
- EntityResolver (*xml.sax.handler* 클래스), 880
- Enum (*aetypes* 클래스), 1411
- enum_certificates() (*ssl* 모듈), 725
- enum_crls() (*ssl* 모듈), 725
- enumerate() (*fm* 모듈), 1426
- enumerate() (*threading* 모듈), 621
- enumerate() (내장 함수), 9
- EnumKey() (*_winreg* 모듈), 1362
- enumsbust() (*aetools* 모듈), 1409
- EnumValue() (*_winreg* 모듈), 1362
- environ (*os* 모듈), 412
- environ (*posix* 모듈), 1372
- environment variables
deleting, 416
setting, 414
- EnvironmentError, 68
- EnvironmentVarGuard (*test.support* 클래스), 1200
- ENXIO (*errno* 모듈), 574
- eof (*shlex.shlex*의 속성), 1060
- EOFError, 68
- EOPNOTSUPP (*errno* 모듈), 578
- EOVERFLOW (*errno* 모듈), 577
- EPERM (*errno* 모듈), 574
- EPFNOSUPPORT (*errno* 모듈), 578
- epilogue (*email.message.Message*의 속성), 764
- EPIPE (*errno* 모듈), 575
- epoch, 452
- epoll() (*select* 모듈), 615
- EPROTO (*errno* 모듈), 577
- EPROTONOSUPPORT (*errno* 모듈), 578
- EPROTOTYPE (*errno* 모듈), 578
- eq() (*operator* 모듈), 280
- EQUAL (*token* 모듈), 1321
- EQUAL (*token* 모듈), 1321
- ERA (*locale* 모듈), 1049
- ERA_D_FMT (*locale* 모듈), 1050
- ERA_D_T_FMT (*locale* 모듈), 1050
- ERA_T_FMT (*locale* 모듈), 1050
- ERANGE (*errno* 모듈), 575
- erase() (*curses.window* 메서드), 557
- erasechar() (*curses* 모듈), 550
- EREMCHG (*errno* 모듈), 577
- EREMOTE (*errno* 모듈), 577
- EREMOTEIO (*errno* 모듈), 579
- ERESTART (*errno* 모듈), 578
- erf() (*math* 모듈), 228
- erfc() (*math* 모듈), 228
- EROFS (*errno* 모듈), 575
- ERR (*curses* 모듈), 561
- errcheck (*ctypes._FuncPtr*의 속성), 602
- errcode (*xmlrpclib.ProtocolError*의 속성), 1007
- errmsg (*xmlrpclib.ProtocolError*의 속성), 1007
- errno

- 모듈, 69, 708
- errno (모듈), 574
- Error, 309, 387, 393, 402, 813, 833, 835, 836, 900, 1024, 1027, 1047, 1393
- error, 96, 104, 214, 329, 331333, 337, 359, 411, 516, 549, 615, 630, 708, 890, 1017, 1020, 1375, 1384, 1387, 1391, 1418, 14291431
- ERROR (cd 모듈), 1418
- error() (argparse.ArgumentParser 메서드), 486
- error() (logging 모듈), 527
- error() (logging.Logger 메서드), 519
- error() (mhtml.Folder 메서드), 818
- error() (mhtml.MH 메서드), 817
- error() (urllib2.OpenerDirector 메서드), 930
- error() (xml.sax.handler.ErrorHandler 메서드), 884
- error_body (wsgiref.handlers.BaseHandler의 속성), 917
- error_content_type (BaseHTTPServer.BaseHTTPRequestHandler의 속성), 985
- error_headers (wsgiref.handlers.BaseHandler의 속성), 917
- error_leader() (shlex.shlex 메서드), 1059
- error_message_format (BaseHTTPServer.BaseHTTPRequestHandler의 속성), 985
- error_output() (wsgiref.handlers.BaseHandler 메서드), 917
- error_perm, 945
- error_proto, 945, 948
- error_reply, 944
- error_status (wsgiref.handlers.BaseHandler의 속성), 917
- error_temp, 944
- ErrorByteIndex (xml.parsers.expat.xmlparser의 속성), 893
- errorcode (errno 모듈), 574
- ErrorCode (xml.parsers.expat.xmlparser의 속성), 893
- ErrorColumnNumber (xml.parsers.expat.xmlparser의 속성), 893
- ErrorHandler (xml.sax.handler 클래스), 880
- ErrorLineNumber (xml.parsers.expat.xmlparser의 속성), 893
- Errors
 - logging, 517
- errors (file의 속성), 59
- errors (io.TextIOBase의 속성), 448
- errors (unittest.TestResult의 속성), 1184
- ErrorString() (xml.parsers.expat 모듈), 890
- ERRORTOKEN (token 모듈), 1321
- escape (shlex.shlex의 속성), 1059
- escape() (cgi 모듈), 906
- escape() (re 모듈), 96
- escape() (xml.sax.saxutils 모듈), 885
- escapechar (csv.Dialect의 속성), 387
- escapedquotes (shlex.shlex의 속성), 1060
- ESHUTDOWN (errno 모듈), 579
- ESOCKTNOSUPPORT (errno 모듈), 578
- ESPIPE (errno 모듈), 575
- ESRCH (errno 모듈), 574
- ESRMNT (errno 모듈), 577
- ESTALE (errno 모듈), 579
- ESTRPIPE (errno 모듈), 578
- ETIME (errno 모듈), 577
- ETIMEDOUT (errno 모듈), 579
- Etiny() (decimal.Context 메서드), 246
- ETOOMANYREFS (errno 모듈), 579
- Etop() (decimal.Context 메서드), 246
- ETXTBSY (errno 모듈), 575
- EUCLEAN (errno 모듈), 579
- EUNATCH (errno 모듈), 576
- EUSERS (errno 모듈), 578
- eval
 - 내장 함수, 64, 86, 216, 217, 1311
- eval() (내장 함수), 10
- Event (multiprocessing 클래스), 646
- Event (threading 클래스), 629
- event scheduling, 199
- event() (msilib.Control 메서드), 1358
- Event() (multiprocessing.managers.SyncManager 메서드), 652
- events (widgets), 1072
- EWouldBlock (errno 모듈), 576
- EX_CANTCREAT (os 모듈), 433
- EX_CONFIG (os 모듈), 433
- EX_DATAERR (os 모듈), 432
- EX_IOERR (os 모듈), 433
- EX_NOHOST (os 모듈), 432
- EX_NOINPUT (os 모듈), 432
- EX_NOPERM (os 모듈), 433
- EX_NOTFOUND (os 모듈), 433
- EX_NOUSER (os 모듈), 432
- EX_OK (os 모듈), 432
- EX_OSERR (os 모듈), 433
- EX_OSFILE (os 모듈), 433
- EX_PROTOCOL (os 모듈), 433
- EX_SOFTWARE (os 모듈), 432
- EX_TEMPFAIL (os 모듈), 433
- EX_UNAVAILABLE (os 모듈), 432
- EX_USAGE (os 모듈), 432
- Example (doctest 클래스), 1157
- example (doctest.DocTestFailure의 속성), 1163
- example (doctest.UnexpectedException의 속성), 1164
- examples (doctest.DocTest의 속성), 1156
- exc_clear() (sys 모듈), 1237
- exc_info (doctest.UnexpectedException의 속성), 1164
- exc_info() (sys 모듈), 1236
- exc_msg (doctest.Example의 속성), 1157

- `exc_traceback` (*sys* 모듈), 1237
- `exc_type` (*sys* 모듈), 1237
- `exc_value` (*sys* 모듈), 1237
- `excel` (*csv* 클래스), 386
- `excel_tab` (*csv* 클래스), 386
- `except`
 - 글, 67
- `except (2to3 fixer)`, 1192
- `excepthook()` (*in module sys*), 909
- `excepthook()` (*sys* 모듈), 1236
- `Exception`, 67
- `EXCEPTION` (*Tkinter* 모듈), 1074
- `exception()` (*logging* 모듈), 527
- `exception()` (*logging.Logger* 메서드), 519
- `exceptions`
 - in CGI scripts, 909
- `exceptions` (모듈), 67
- `EXDEV` (*errno* 모듈), 575
- `exec`
 - 글, 64
- `exec (2to3 fixer)`, 1192
- `exec_prefix` (*sys* 모듈), 1237
- `EXEC_STMT` (*opcode*), 1334
- `execfile`
 - 내장 함수, 1280
- `execfile (2to3 fixer)`, 1192
- `execfile()` (내장 함수), 10
- `execl()` (*os* 모듈), 431
- `execle()` (*os* 모듈), 431
- `execlp()` (*os* 모듈), 431
- `execlpe()` (*os* 모듈), 431
- `executable` (*sys* 모듈), 1237
- `Execute()` (*msilib.View* 메서드), 1355
- `execute()` (*sqlite3.Connection* 메서드), 342
- `execute()` (*sqlite3.Cursor* 메서드), 347
- `executemany()` (*sqlite3.Connection* 메서드), 342
- `executemany()` (*sqlite3.Cursor* 메서드), 347
- `executescript()` (*sqlite3.Connection* 메서드), 342
- `executescript()` (*sqlite3.Cursor* 메서드), 348
- `execv()` (*os* 모듈), 431
- `execve()` (*os* 모듈), 431
- `execvp()` (*os* 모듈), 431
- `execvpe()` (*os* 모듈), 431
- `ExFileSelectBox` (*Tix* 클래스), 1095
- `EXFULL` (*errno* 모듈), 576
- `exists()` (*os.path* 모듈), 290
- `exists()` (*tk.Treeview* 메서드), 1087
- `exit` (내장 변수), 30
- `exit()` (*argparse.ArgumentParser* 메서드), 486
- `exit()` (*sys* 모듈), 1237
- `exit()` (*thread* 모듈), 631
- `exitcode` (*multiprocessing.Process*의 속성), 639
- `exitfunc (2to3 fixer)`, 1192
- `exitfunc` (*in sys*), 1262
- `exitfunc` (*sys* 모듈), 1238
- `exitonclick()` (*turtle* 모듈), 1123
- `exp()` (*cmath* 모듈), 230
- `exp()` (*decimal.Context* 메서드), 246
- `exp()` (*decimal.Decimal* 메서드), 238
- `exp()` (*math* 모듈), 226
- `expand()` (*re.MatchObject* 메서드), 98
- `expand_tabs` (*textwrap.TextWrapper*의 속성), 122
- `ExpandEnvironmentStrings()` (*_winreg* 모듈), 1363
- `expandNode()` (*xml.dom.pulldom.DOMEventStream* 메서드), 878
- `expandtabs()` (*str* 메서드), 40
- `expandtabs()` (*string* 모듈), 86
- `expanduser()` (*os.path* 모듈), 290
- `expandvars()` (*os.path* 모듈), 290
- `Expat`, 890
- `ExpatError`, 890
- `expect()` (*telnetlib.Telnet* 메서드), 967
- `expectedFailure()` (*unittest* 모듈), 1174
- `expectedFailures` (*unittest.TestResult*의 속성), 1184
- `expires` (*cookielib.Cookie*의 속성), 996
- `expm1()` (*math* 모듈), 226
- `expovariate()` (*random* 모듈), 262
- `expr()` (*parser* 모듈), 1310
- `expression` (표현식), 1441
- `expunge()` (*imaplib.IMAP4* 메서드), 952
- `extend()` (*array.array* 메서드), 194
- `extend()` (*collections.deque* 메서드), 175
- `extend()` (*list method*), 48
- `extend()` (*xml.etree.ElementTree.Element* 메서드), 858
- `extend_path()` (*pkgutil* 모듈), 1302
- `extended slice`
 - assignment, 48
 - operation, 38
- `EXTENDED_ARG` (*opcode*), 1337
- `ExtendedContext` (*decimal* 클래스), 244
- `extendleft()` (*collections.deque* 메서드), 175
- `extension module` (확장 모듈), 1441
- `extensions_map` (*SimpleHTTPServer.SimpleHTTPRequestHandler*의 속성), 987
- `External Data Representation`, 314, 400
- `external_attr` (*zipfile.ZipInfo*의 속성), 371
- `ExternalClashError`, 813
- `ExternalEntityParserCreate()` (*xml.parsers.expat.xmlparser* 메서드), 891
- `ExternalEntityRefHandler()` (*xml.parsers.expat.xmlparser* 메서드), 895
- `extra` (*zipfile.ZipInfo*의 속성), 371
- `extract()` (*tarfile.TarFile* 메서드), 376
- `extract()` (*zipfile.ZipFile* 메서드), 368
- `extract_cookies()` (*cookielib.CookieJar* 메서드), 991

extract_stack() (*traceback* 모듈), 1264
 extract_tb() (*traceback* 모듈), 1264
 extract_version(*zipfile.ZipInfo*의 속성), 371
 extractall() (*tarfile.TarFile* 메서드), 376
 extractall() (*zipfile.ZipFile* 메서드), 368
 ExtractError, 374
 extractfile() (*tarfile.TarFile* 메서드), 376
 extsep(*os* 모듈), 440

F

-f
 compileall command line option, 1328
 trace command line option, 1227
 unittest command line option, 1168
 F_BAVAIL(*statvfs* 모듈), 299
 F_BFREE(*statvfs* 모듈), 299
 F_BLOCKS(*statvfs* 모듈), 299
 F_BSIZE(*statvfs* 모듈), 299
 F_FAVAIL(*statvfs* 모듈), 299
 F_FFREE(*statvfs* 모듈), 299
 F_FILES(*statvfs* 모듈), 299
 F_FLAG(*statvfs* 모듈), 299
 F_FRSIZE(*statvfs* 모듈), 299
 F_NAMEMAX(*statvfs* 모듈), 299
 F_OK(*os* 모듈), 422
 fabs() (*math* 모듈), 225
 factorial() (*math* 모듈), 225
 fail() (*unittest.TestCase* 메서드), 1180
 --failfast
 unittest command line option, 1168
 failfast(*unittest.TestResult*의 속성), 1184
 failureException(*unittest.TestCase*의 속성), 1180
 failures(*unittest.TestResult*의 속성), 1184
 False, 32, 64
 false, 31
 False (*Built-in object*), 31
 False (내장 변수), 29
 family(*socket.socket*의 속성), 716
 FancyURLopener(*urllib* 클래스), 923
 fatalError() (*xml.sax.handler.ErrorHandler* 메서드), 884
 Fault(*xmlrpclib* 클래스), 1006
 faultCode(*xmlrpclib.Fault*의 속성), 1006
 faultString(*xmlrpclib.Fault*의 속성), 1006
 fchdir() (*os* 모듈), 422
 fchmod() (*os* 모듈), 418
 fchown() (*os* 모듈), 418
 FCICreate() (*msilib* 모듈), 1353
 fcntl
 모듈, 57
 fcntl(모듈), 1378
 fcntl() (*fcntl* 모듈), 1378
 fcntl() (*in module fcntl*), 1382
 fd() (*turtle* 모듈), 1102

fdasyncc() (*os* 모듈), 418
 fdopen() (*os* 모듈), 416
 Feature(*msilib* 클래스), 1357
 feature_external_ges (*xml.sax.handler* 모듈), 881
 feature_external_pes (*xml.sax.handler* 모듈), 881
 feature_namespace_prefixes (*xml.sax.handler* 모듈), 880
 feature_namespaces (*xml.sax.handler* 모듈), 880
 feature_string_interning (*xml.sax.handler* 모듈), 881
 feature_validation(*xml.sax.handler* 모듈), 881
 feed() (*email.parser.FeedParser* 메서드), 765
 feed() (*HTMLParser.HTMLParser* 메서드), 839
 feed() (*sgmlib.SGMLParser* 메서드), 843
 feed() (*xml.etree.ElementTree.XMLParser* 메서드), 861
 feed() (*xml.sax.xmlreader.IncrementalParser* 메서드), 888
 FeedParser(*email.parser* 클래스), 765
 fetch() (*imaplib.IMAP4* 메서드), 952
 Fetch() (*msilib.View* 메서드), 1355
 fetchall() (*sqlite3.Cursor* 메서드), 349
 fetchmany() (*sqlite3.Cursor* 메서드), 349
 fetchone() (*sqlite3.Cursor* 메서드), 348
 fflags(*select.kevent*의 속성), 619
 field_size_limit() (*csv* 모듈), 385
 fieldnames(*csv.csvreader*의 속성), 388
 fields(*uuid.UUID*의 속성), 968
 fifo(*asynchat* 클래스), 754
 file
 byte-code, 1293, 1295, 1327
 configuration, 391
 copying, 307
 debugger configuration, 1210
 descriptor, 57
 .ini, 391
 large files, 1371
 mime.types, 821
 path configuration, 1277
 .pdbrc, 1210
 plist, 403
 .pythonrc.py, 1279
 temporary, 302
 user configuration, 1279
 객체, 56
 내장 함수, 56
 file ...
 compileall command line option, 1328
 file(*pyclbr.Class*의 속성), 1326
 file(*pyclbr.Function*의 속성), 1326
 file control
 UNIX, 1378
 file name

- temporary, 302
- file object
 - POSIX, 1382
- file object (파일 객체), 1441
- file() (*posixfile.posixfile* 메서드), 1383
- file() (내장 함수), 10
- file=<file>
 - trace command line option, 1227
- file-like object (파일류 객체), 1441
- file_dispatcher (*asyncore* 클래스), 751
- file_open() (*urllib2.FileHandler* 메서드), 934
- file_size (*zipfile.ZipInfo*의 속성), 371
- file_wrapper (*asyncore* 클래스), 751
- filecmp (모듈), 300
- fileConfig() (*logging.config* 모듈), 530
- FileCookieJar (*cookielib* 클래스), 990
- FileEntry (*Tix* 클래스), 1095
- FileHandler (*logging* 클래스), 540
- FileHandler (*urllib2* 클래스), 928
- FileInput (*fileinput* 클래스), 294
- fileinput (모듈), 293
- FileIO (*io* 클래스), 446
- filelineno() (*fileinput* 모듈), 294
- filename (*cookielib.FileCookieJar*의 속성), 992
- filename (*doctest.DocTest*의 속성), 1157
- filename (*zipfile.ZipInfo*의 속성), 370
- filename() (*fileinput* 모듈), 294
- filename_only (*tabnanny* 모듈), 1325
- filenames
 - pathname expansion, 305
 - wildcard expansion, 306
- fileno() (*Connection* 메서드), 644
- fileno() (*file* 메서드), 57
- fileno() (*fileinput* 모듈), 294
- fileno() (*hotshot.Profile* 메서드), 1221
- fileno() (*httplib.HTTPResponse* 메서드), 942
- fileno() (*io.IOBase* 메서드), 443
- fileno() (*ossaudiodev.oss_audio_device* 메서드), 1033
- fileno() (*ossaudiodev.oss_mixer_device* 메서드), 1035
- fileno() (*select.epoll* 메서드), 617
- fileno() (*select.kqueue* 메서드), 618
- fileno() (*SocketServer.BaseServer* 메서드), 977
- fileno() (*socket.socket* 메서드), 714
- fileno() (*telnetlib.Telnet* 메서드), 967
- fileopen() (*posixfile* 모듈), 1382
- FileSelectBox (*Tix* 클래스), 1095
- FileType (*argparse* 클래스), 483
- FileType (*types* 모듈), 212
- FileWrapper (*wsgiref.util* 클래스), 911
- fill() (*textwrap* 모듈), 121
- fill() (*textwrap.TextWrapper* 메서드), 123
- fill() (*turtle* 모듈), 1112
- fillcolor() (*turtle* 모듈), 1111
- filter (*2to3 fixer*), 1192
- Filter (*logging* 클래스), 523
- filter (*select.kevent*의 속성), 619
- filter() (*curses* 모듈), 550
- filter() (*fnmatch* 모듈), 306
- filter() (*future_builtins* 모듈), 1252
- filter() (*logging.Filter* 메서드), 523
- filter() (*logging.Handler* 메서드), 521
- filter() (*logging.Logger* 메서드), 520
- filter() (내장 함수), 11
- filterwarnings() (*warnings* 모듈), 1256
- find() (*doctest.DocTestFinder* 메서드), 1158
- find() (*gettext* 모듈), 1039
- find() (*mmap.mmap* 메서드), 688
- find() (*str* 메서드), 40
- find() (*string* 모듈), 86
- find() (*xml.etree.ElementTree.Element* 메서드), 858
- find() (*xml.etree.ElementTree.ElementTree* 메서드), 859
- find_first() (*fl.form* 메서드), 1423
- find_global() (*pickle.protocol*), 321
- find_last() (*fl.form* 메서드), 1423
- find_library() (*ctypes.util* 모듈), 606
- find_loader() (*pkgutil* 모듈), 1303
- find_longest_match() (*difflib.SequenceMatcher* 메서드), 113
- find_module() (*imp* 모듈), 1293
- find_module() (*imp.NullImporter* 메서드), 1296
- find_module() (*zipimport.zipimporter* 메서드), 1301
- find_msvcr() (*ctypes.util* 모듈), 606
- find_user_password() (*urllib2.HTTPPasswordMgr* 메서드), 933
- findall() (*re* 모듈), 95
- findall() (*re.RegexObject* 메서드), 97
- findall() (*xml.etree.ElementTree.Element* 메서드), 858
- findall() (*xml.etree.ElementTree.ElementTree* 메서드), 859
- findCaller() (*logging.Logger* 메서드), 520
- finder (파인더), 1442
- findertools (모듈), 1395
- findfactor() (*audioop* 모듈), 1018
- findfile() (*test.support* 모듈), 1198
- findfit() (*audioop* 모듈), 1018
- findfont() (*fm* 모듈), 1426
- finditer() (*re* 모듈), 95
- finditer() (*re.RegexObject* 메서드), 97
- findlabels() (*dis* 모듈), 1330
- findlinestarts() (*dis* 모듈), 1330
- findmatch() (*mailcap* 모듈), 796
- findmax() (*audioop* 모듈), 1018
- findtext() (*xml.etree.ElementTree.Element* 메서드), 858
- findtext() (*xml.etree.ElementTree.ElementTree* 메서드), 859

- `finish()` (*SocketServer.BaseRequestHandler* 메서드), 979
`finish_request()` (*SocketServer.BaseServer* 메서드), 978
`first()` (*asynchat.fifo* 메서드), 754
`first()` (*bsddb.bsddbobject* 메서드), 335
`first()` (*dbhash.dbhash* 메서드), 334
`firstChild()` (*xml.dom.Node*의 속성), 865
`firstkey()` (*gdbm* 모듈), 332
`firstweekday()` (*calendar* 모듈), 170
`fix()` (*fpformat* 모듈), 141
`fix_missing_locations()` (*ast* 모듈), 1317
`fix_sentence_endings` (*textwrap.TextWrapper*의 속성), 122
`FL` (모듈), 1425
`fl` (모듈), 1421
`flag_bits` (*zipfile.ZipInfo*의 속성), 371
`flags` (*re.RegexObject*의 속성), 97
`flags` (*select.kevent*의 속성), 619
`flags` (*sys* 모듈), 1238
`flags()` (*posixfile.posixfile* 메서드), 1382
`flash()` (*curses* 모듈), 550
`flatten()` (*email.generator.Generator* 메서드), 767
`flattening`
 objects, 313
`float`
 내장 함수, 33, 85
`float` (내장 클래스), 11
`float_info` (*sys* 모듈), 1238
`float_repr_style` (*sys* 모듈), 1239
`floating point`
 literals, 33
 개체, 33
`FloatingPointError`, 68, 1281
`FloatType` (*types* 모듈), 211
`flock()` (*fcntl* 모듈), 1379
`floor division` (정수 나눗셈), 1442
`floor()` (*in module math*), 34
`floor()` (*math* 모듈), 225
`floordiv()` (*operator* 모듈), 281
`flp` (모듈), 1426
`flush()` (*bz2.BZ2Compressor* 메서드), 365
`flush()` (*file* 메서드), 57
`flush()` (*formatter.writer* 메서드), 1349
`flush()` (*io.BufferedWriter* 메서드), 447
`flush()` (*io.IOBase* 메서드), 443
`flush()` (*logging.Handler* 메서드), 521
`flush()` (*logging.handlers.BufferingHandler* 메서드), 547
`flush()` (*logging.handlers.MemoryHandler* 메서드), 547
`flush()` (*logging.StreamHandler* 메서드), 540
`flush()` (*mailbox.Mailbox* 메서드), 800
`flush()` (*mailbox.Maildir* 메서드), 801
`flush()` (*mailbox.MH* 메서드), 804
`flush()` (*mmap.mmap* 메서드), 688
`flush()` (*zlib.Compress* 메서드), 361
`flush()` (*zlib.Decompress* 메서드), 362
`flush_softspace()` (*formatter.formatter* 메서드), 1348
`flushheaders()` (*MimeWriter.MimeWriter* 메서드), 823
`flushinp()` (*curses* 모듈), 550
`FlushKey()` (*_winreg* 모듈), 1363
`fm` (모듈), 1426
`fma()` (*decimal.Context* 메서드), 246
`fma()` (*decimal.Decimal* 메서드), 239
`fmod()` (*math* 모듈), 225
`fnmatch` (모듈), 306
`fnmatch()` (*fnmatch* 모듈), 306
`fnmatchcase()` (*fnmatch* 모듈), 306
`focus()` (*ttk.Treeview* 메서드), 1087
`Folder` (*mhlib* 클래스), 817
`Font Manager`, IRIS, 1426
`fontpath()` (*fm* 모듈), 1426
`FOR_ITER` (*opcode*), 1336
`forget()` (*test.support* 모듈), 1198
`forget()` (*ttk.Notebook* 메서드), 1081
`fork()` (*os* 모듈), 433
`fork()` (*pty* 모듈), 1378
`ForkingMixIn` (*SocketServer* 클래스), 976
`ForkingTCPServer` (*SocketServer* 클래스), 977
`ForkingUDPServer` (*SocketServer* 클래스), 977
`forkpty()` (*os* 모듈), 434
`Form` (*Tix* 클래스), 1097
`format`
 str, 11
`format` (*memoryview*의 속성), 61
`format` (*struct.Struct*의 속성), 108
`format()` (*locale* 모듈), 1051
`format()` (*logging.Formatter* 메서드), 522
`format()` (*logging.Handler* 메서드), 521
`format()` (*pprint.PrettyPrinter* 메서드), 217
`format()` (*str* 메서드), 40
`format()` (*string.Formatter* 메서드), 76
`format()` (내장 함수), 11
`format_exc()` (*traceback* 모듈), 1264
`format_exception()` (*traceback* 모듈), 1264
`format_exception_only()` (*traceback* 모듈), 1264
`format_field()` (*string.Formatter* 메서드), 77
`format_help()` (*argparse.ArgumentParser* 메서드), 486
`format_list()` (*traceback* 모듈), 1264
`format_stack()` (*traceback* 모듈), 1265
`format_stack_entry()` (*bdb.Bdb* 메서드), 1206
`format_string()` (*locale* 모듈), 1051
`format_tb()` (*traceback* 모듈), 1264

- `format_usage()` (*argparse.ArgumentParser* 메서드), 486
- `formataddr()` (*email.utils* 모듈), 777
- `formatargspec()` (*inspect* 모듈), 1275
- `formatargvalues()` (*inspect* 모듈), 1275
- `formatdate()` (*email.utils* 모듈), 777
- `FormatError`, 813
- `FormatError()` (*ctypes* 모듈), 606
- `FormatException()` (*logging.Formatter* 메서드), 522
- `formatmonth()` (*calendar.HTMLCalendar* 메서드), 170
- `formatmonth()` (*calendar.TextCalendar* 메서드), 169
- `formatter`
 - 모듈, 845
- `formatter` (*htmllib.HTMLParser*의 속성), 846
- `Formatter` (*logging* 클래스), 522
- `Formatter` (*string* 클래스), 76
- `formatter` (모듈), 1347
- `formatTime()` (*logging.Formatter* 메서드), 522
- `formatting, string (%)`, 46
- `formatwarning()` (*warnings* 모듈), 1256
- `formatyear()` (*calendar.HTMLCalendar* 메서드), 170
- `formatyear()` (*calendar.TextCalendar* 메서드), 169
- `formatyearpage()` (*calendar.HTMLCalendar* 메서드), 170
- FORMS Library, 1421
- `forward()` (*turtle* 모듈), 1102
- `found_terminator()` (*asyncio.async_chat* 메서드), 754
- `fp` (*rfc822.Message*의 속성), 830
- `fpathconf()` (*os* 모듈), 418
- `fpectl` (모듈), 1280
- `fpformat` (모듈), 141
- `Fraction` (*fractions* 클래스), 257
- `fractions` (모듈), 257
- `frame` (*ScrolledText.ScrolledText*의 속성), 1098
- `FrameType` (*types* 모듈), 213
- `FrameWork`
 - 모듈, 1412
- `FrameWork` (모듈), 1398
- `freeze_form()` (*fl.form* 메서드), 1422
- `freeze_support()` (*multiprocessing* 모듈), 643
- `frexp()` (*math* 모듈), 225
- `from_address()` (*ctypes._CData* 메서드), 608
- `from_buffer()` (*ctypes._CData* 메서드), 608
- `from_buffer_copy()` (*ctypes._CData* 메서드), 608
- `from_decimal()` (*fractions.Fraction* 메서드), 258
- `from_float()` (*decimal.Decimal* 메서드), 238
- `from_float()` (*fractions.Fraction* 메서드), 258
- `from_iterable()` (*itertools.chain*의 클래스 메서드), 265
- `from_param()` (*ctypes._CData* 메서드), 608
- `from_plittable()` (*email.charset.Charset* 메서드), 774
- `frombuf()` (*tarfile.TarInfo* 메서드), 377
- `fromchild` (*popen2.Popen3*의 속성), 748
- `fromfd()` (*select.epoll* 메서드), 617
- `fromfd()` (*select.kqueue* 메서드), 618
- `fromfd()` (*socket* 모듈), 711
- `fromfile()` (*array.array* 메서드), 194
- `fromhex()` (*float* 메서드), 36
- `fromkeys()` (*collections.Counter* 메서드), 173
- `fromkeys()` (*dict* 메서드), 53
- `fromlist()` (*array.array* 메서드), 194
- `fromordinal()` (*datetime.datetime*의 클래스 메서드), 151
- `fromordinal()` (*datetime.date*의 클래스 메서드), 147
- `fromstring()` (*array.array* 메서드), 194
- `fromstring()` (*xml.etree.ElementTree* 모듈), 855
- `fromstringlist()` (*xml.etree.ElementTree* 모듈), 855
- `fromtarfile()` (*tarfile.TarInfo* 메서드), 378
- `fromtimestamp()` (*datetime.datetime*의 클래스 메서드), 151
- `fromtimestamp()` (*datetime.date*의 클래스 메서드), 147
- `fromunicode()` (*array.array* 메서드), 195
- `fromutc()` (*datetime.tzinfo* 메서드), 161
- `frozenset` (내장 클래스), 49
- `fstat()` (*os* 모듈), 419
- `fstatvfs()` (*os* 모듈), 419
- `fsum()` (*math* 모듈), 225
- `fsync()` (*os* 모듈), 419
- FTP, 924
 - ftplib* (standard module), 943
 - protocol, 924, 943
- FTP (*ftplib* 클래스), 944
- `ftp_open()` (*urllib2.FTPHandler* 메서드), 935
- `ftp_proxy`, 919
- FTP-TLS (*ftplib* 클래스), 944
- `FTPHandler` (*urllib2* 클래스), 928
- `ftplib` (모듈), 943
- `ftpmirror.py`, 945
- `ftruncate()` (*os* 모듈), 419
- Full, 202
- `full()` (*multiprocessing.Queue* 메서드), 642
- `full()` (*Queue.Queue* 메서드), 203
- `func` (*functools.partial*의 속성), 279
- `func_code` (*function object attribute*), 64
- `funcattrs` (*2to3 fixer*), 1192
- `Function` (*symtable* 클래스), 1320
- `function` (함수), 1442
- `function()` (*new* 모듈), 214
- `FunctionTestCase` (*unittest* 클래스), 1181
- `FunctionType` (*types* 모듈), 212
- `functools` (모듈), 277
- `funny_files` (*filecmp.dircmp*의 속성), 301
- `future` (*2to3 fixer*), 1192

future_builtins (모듈), 1251
FutureWarning, 72

G

-g

trace command line option, 1227

G.722, 1023

gaierror, 708

gamma() (math 모듈), 228

gammavariate() (random 모듈), 262

garbage (gc 모듈), 1270

garbage collection (가비지 수거), 1442

gather() (curses.textpad.Textbox 메서드), 566

gauss() (random 모듈), 262

gc (모듈), 1268

gcd() (fractions 모듈), 259

gdbm

모듈, 326, 329

gdbm (모듈), 332

ge() (operator 모듈), 280

gen_uuid() (msilib 모듈), 1354

generate_tokens() (tokenize 모듈), 1323

generator, 1442

Generator (email.generator 클래스), 767

generator (제너레이터), 1442

generator expression, 1442

generator expression (제너레이터 표현식), 1442

GeneratorExit, 68

GeneratorType (types 모듈), 212

generic_visit() (ast.NodeVisitor 메서드), 1318

genops() (pickletools 모듈), 1338

gensuitemodule (모듈), 1408

get() (ConfigParser.ConfigParser 메서드), 395

get() (ConfigParser.RawConfigParser 메서드), 394

get() (dict 메서드), 53

get() (email.message.Message 메서드), 760

get() (mailbox.Mailbox 메서드), 799

get() (multiprocessing.multiprocessing.queues.SimpleQueue 메서드), 643

get() (multiprocessing.pool.AsyncResult 메서드), 658

get() (multiprocessing.Queue 메서드), 642

get() (ossaudiodev.oss_mixer_device 메서드), 1035

get() (Queue.Queue 메서드), 203

get() (rfc822.Message 메서드), 829

get() (tkk.ComboBox 메서드), 1080

get() (webbrowser 모듈), 900

get() (xml.etree.ElementTree.Element 메서드), 857

get_all() (email.message.Message 메서드), 760

get_all() (wsgiref.headers.Headers 메서드), 912

get_all_breaks() (bdb.Bdb 메서드), 1206

get_app() (wsgiref.simple_server.WSGIServer 메서드), 913

get_archive_formats() (shutil 모듈), 311

get_begidx() (readline 모듈), 691

get_body_encoding() (email.charset.Charset 메서드), 773

get_boundary() (email.message.Message 메서드), 763

get_break() (bdb.Bdb 메서드), 1206

get_breaks() (bdb.Bdb 메서드), 1206

get_buffer() (xdrlib.Packer 메서드), 400

get_buffer() (xdrlib.Unpacker 메서드), 401

get_ca_certs() (ssl.SSLContext 메서드), 733

get_channel_binding() (ssl.SSLSocket 메서드), 731

get_charset() (email.message.Message 메서드), 759

get_charsets() (email.message.Message 메서드), 763

get_children() (symtable.SymbolTable 메서드), 1320

get_children() (tkk.Treeview 메서드), 1086

get_close_matches() (difflib 모듈), 111

get_code() (imputil.BuiltinImporter 메서드), 1298

get_code() (imputil.Importer 메서드), 1297

get_code() (zipimport.zipimporter 메서드), 1301

get_completer() (readline 모듈), 691

get_completer_delims() (readline 모듈), 691

get_completion_type() (readline 모듈), 691

get_config_h_filename() (sysconfig 모듈), 1250

get_config_var() (sysconfig 모듈), 1248

get_config_vars() (sysconfig 모듈), 1248

get_content_charset() (email.message.Message 메서드), 763

get_content_maintype() (email.message.Message 메서드), 761

get_content_subtype() (email.message.Message 메서드), 761

get_content_type() (email.message.Message 메서드), 761

get_count() (gc 모듈), 1269

get_current_history_length() (readline 모듈), 690

get_data() (pkgutil 모듈), 1304

get_data() (urllib2.Request 메서드), 929

get_data() (zipimport.zipimporter 메서드), 1301

get_date() (mailbox.MaildirMessage 메서드), 807

get_debug() (gc 모듈), 1269

get_default() (argparse.ArgumentParser 메서드), 485

get_default_domain() (nis 모듈), 1387

get_default_type() (email.message.Message 메서드), 761

get_default_verify_paths() (ssl 모듈), 725

get_dialect() (csv 모듈), 385

get_directory() (fl 모듈), 1422

get_docstring() (ast 모듈), 1317

get_doctest() (doctest.DocTestParser 메서드), 1159

`get_endidx()` (*readline* 모듈), 691
`get_environ()` (*wsgiref.simple_server.WSGIRequestHandler* 메서드), 913
`get_errno()` (*ctypes* 모듈), 606
`get_examples()` (*doctest.DocTestParser* 메서드), 1159
`get_field()` (*string.Formatter* 메서드), 77
`get_file()` (*mailbox.Babyl* 메서드), 804
`get_file()` (*mailbox.Mailbox* 메서드), 799
`get_file()` (*mailbox.Maildir* 메서드), 802
`get_file()` (*mailbox.mbox* 메서드), 802
`get_file()` (*mailbox.MH* 메서드), 804
`get_file()` (*mailbox.MMDF* 메서드), 805
`get_file_breaks()` (*bdb.Bdb* 메서드), 1206
`get_filename()` (*email.message.Message* 메서드), 763
`get_filename()` (*fl* 모듈), 1422
`get_filename()` (*zipimport.zipimporter* 메서드), 1301
`get_flags()` (*mailbox.MaildirMessage* 메서드), 806
`get_flags()` (*mailbox.mboxMessage* 메서드), 808
`get_flags()` (*mailbox.MMDFMessage* 메서드), 812
`get_folder()` (*mailbox.Maildir* 메서드), 801
`get_folder()` (*mailbox.MH* 메서드), 803
`get_frees()` (*symtable.Function* 메서드), 1320
`get_from()` (*mailbox.mboxMessage* 메서드), 808
`get_from()` (*mailbox.MMDFMessage* 메서드), 812
`get_full_url()` (*urllib2.Request* 메서드), 929
`get_globals()` (*symtable.Function* 메서드), 1320
`get_grouped_opcodes()` (*difflib.SequenceMatcher* 메서드), 114
`get_header()` (*urllib2.Request* 메서드), 929
`get_history_item()` (*readline* 모듈), 690
`get_history_length()` (*readline* 모듈), 690
`get_host()` (*urllib2.Request* 메서드), 929
`get_id()` (*symtable.SymbolTable* 메서드), 1319
`get_ident()` (*thread* 모듈), 631
`get_identifiers()` (*symtable.SymbolTable* 메서드), 1319
`get_importer()` (*pkgutil* 모듈), 1303
`get_info()` (*mailbox.MaildirMessage* 메서드), 807
`GET_ITER` (*opcode*), 1331
`get_labels()` (*mailbox.Babyl* 메서드), 804
`get_labels()` (*mailbox.BabylMessage* 메서드), 811
`get_last_error()` (*ctypes* 모듈), 606
`get_line_buffer()` (*readline* 모듈), 689
`get_lineno()` (*symtable.SymbolTable* 메서드), 1319
`get_loader()` (*pkgutil* 모듈), 1303
`get_locals()` (*symtable.Function* 메서드), 1320
`get_logger()` (*multiprocessing* 모듈), 662
`get_magic()` (*imp* 모듈), 1293
`get_makefile_filename()` (*sysconfig* 모듈), 1250
`get_matching_blocks()` (*difflib.SequenceMatcher* 메서드), 114
`get_message()` (*mailbox.Mailbox* 메서드), 799
`get_method()` (*urllib2.Request* 메서드), 929
`get_methods()` (*symtable.Class* 메서드), 1320
`get_mouse()` (*fl* 모듈), 1422
`get_name()` (*symtable.Symbol* 메서드), 1320
`get_name()` (*symtable.SymbolTable* 메서드), 1319
`get_namespace()` (*symtable.Symbol* 메서드), 1321
`get_namespaces()` (*symtable.Symbol* 메서드), 1321
`get_nonstandard_attr()` (*cookielib.Cookie* 메서드), 997
`get_nowait()` (*multiprocessing.Queue* 메서드), 642
`get_nowait()` (*Queue.Queue* 메서드), 203
`get_objects()` (*gc* 모듈), 1269
`get_opcodes()` (*difflib.SequenceMatcher* 메서드), 114
`get_option()` (*optparse.OptionParser* 메서드), 506
`get_option_group()` (*optparse.OptionParser* 메서드), 496
`get_origin_req_host()` (*urllib2.Request* 메서드), 929
`get_osfhandle()` (*msvcrt* 모듈), 1359
`get_output_charset()` (*email.charset.Charset* 메서드), 774
`get_param()` (*email.message.Message* 메서드), 762
`get_parameters()` (*symtable.Function* 메서드), 1320
`get_params()` (*email.message.Message* 메서드), 762
`get_path()` (*sysconfig* 모듈), 1249
`get_path_names()` (*sysconfig* 모듈), 1249
`get_paths()` (*sysconfig* 모듈), 1249
`get_pattern()` (*fl* 모듈), 1422
`get_payload()` (*email.message.Message* 메서드), 758
`get_platform()` (*sysconfig* 모듈), 1250
`get_poly()` (*turtle* 모듈), 1117
`get_position()` (*xdrlib.Unpacker* 메서드), 401
`get_python_version()` (*sysconfig* 모듈), 1250
`get_recsrc()` (*ossaudiodev.oss_mixer_device* 메서드), 1035
`get_referents()` (*gc* 모듈), 1270
`get_referrers()` (*gc* 모듈), 1269
`get_request()` (*SocketServer.BaseServer* 메서드), 978
`get_rgbmode()` (*fl* 모듈), 1421
`get_scheme()` (*wsgiref.handlers.BaseHandler* 메서드), 916
`get_scheme_names()` (*sysconfig* 모듈), 1249
`get_selector()` (*urllib2.Request* 메서드), 929
`get_sequences()` (*mailbox.MH* 메서드), 803
`get_sequences()` (*mailbox.MHMessage* 메서드), 809
`get_server()` (*multiprocessing.managers.BaseManager* 메서드), 651
`get_server_certificate()` (*ssl* 모듈), 724
`get_socket()` (*telnetlib.Telnet* 메서드), 967
`get_source()` (*zipimport.zipimporter* 메서드), 1301
`get_stack()` (*bdb.Bdb* 메서드), 1206

- get_starttag_text() (*HTMLParser.HTMLParser* 메서드), 839
- get_starttag_text() (*sgmlib.SGMLParser* 메서드), 843
- get_stderr() (*wsgiref.handlers.BaseHandler* 메서드), 916
- get_stderr() (*wsgiref.simple_server.WSGIRequestHandler* 메서드), 914
- get_stdin() (*wsgiref.handlers.BaseHandler* 메서드), 916
- get_string() (*mailbox.Mailbox* 메서드), 799
- get_subdir() (*mailbox.MaildirMessage* 메서드), 806
- get_suffixes() (*imp* 모듈), 1293
- get_symbols() (*syntable.SymbolTable* 메서드), 1319
- get_terminator() (*asynchat.async_chat* 메서드), 754
- get_threshold() (*gc* 모듈), 1269
- get_token() (*shlex.shlex* 메서드), 1058
- get_type() (*syntable.SymbolTable* 메서드), 1319
- get_type() (*urllib2.Request* 메서드), 929
- get_unixfrom() (*email.message.Message* 메서드), 758
- get_usage() (*optparse.OptionParser* 메서드), 507
- get_value() (*string.Formatter* 메서드), 77
- get_version() (*optparse.OptionParser* 메서드), 497
- get_visible() (*mailbox.BabylMessage* 메서드), 811
- getabouttext() (*FrameWork.Application* 메서드), 1399
- getacl() (*imaplib.IMAP4* 메서드), 952
- getaddr() (*rfc822.Message* 메서드), 829
- getaddresses() (*email.utils* 모듈), 777
- getaddrinfo() (*socket* 모듈), 710
- getaddrlist() (*rfc822.Message* 메서드), 829
- getallmatchingheaders() (*rfc822.Message* 메서드), 829
- getannotation() (*imaplib.IMAP4* 메서드), 952
- getargspec() (*inspect* 모듈), 1275
- GetArgv() (*EasyDialogs* 모듈), 1396
- getargvalues() (*inspect* 모듈), 1275
- getatime() (*os.path* 모듈), 290
- getattr() (내장 함수), 11
- getAttribute() (*xml.dom.Element* 메서드), 868
- getAttributeNode() (*xml.dom.Element* 메서드), 868
- getAttributeNodeNS() (*xml.dom.Element* 메서드), 868
- getAttributeNS() (*xml.dom.Element* 메서드), 868
- GetBase() (*xml.parsers.expat.xmlparser* 메서드), 891
- getbegyx() (*curses.window* 메서드), 557
- getbkgd() (*curses.window* 메서드), 557
- getboolean() (*ConfigParser.RawConfigParser* 메서드), 394
- getByteStream() (*xml.sax.xmlreader.InputSource* 메서드), 889
- getcallargs() (*inspect* 모듈), 1275
- getcanvas() (*turtle* 모듈), 1122
- getcaps() (*mailcap* 모듈), 797
- getch() (*curses.window* 메서드), 557
- getch() (*msvcrt* 모듈), 1360
- getCharacterStream() (*xml.sax.xmlreader.InputSource* 메서드), 889
- getche() (*msvcrt* 모듈), 1360
- getcheckinterval() (*sys* 모듈), 1239
- getChild() (*logging.Logger* 메서드), 518
- getChildNodes() (*compiler.ast.Node* 메서드), 1341
- getChildren() (*compiler.ast.Node* 메서드), 1341
- getchildren() (*xml.etree.ElementTree.Element* 메서드), 858
- getclasstree() (*inspect* 모듈), 1275
- GetColor() (*ColorPicker* 모듈), 1405
- GetColumnInfo() (*msilib.View* 메서드), 1355
- getColumnNumber() (*xml.sax.xmlreader.Locator* 메서드), 888
- getcomments() (*inspect* 모듈), 1274
- getcompname() (*aifc.aifc* 메서드), 1022
- getcompname() (*sunau.AU_read* 메서드), 1025
- getcompname() (*wave.Wave_read* 메서드), 1027
- getcomptype() (*aifc.aifc* 메서드), 1022
- getcomptype() (*sunau.AU_read* 메서드), 1025
- getcomptype() (*wave.Wave_read* 메서드), 1027
- getContentHandler() (*xml.sax.xmlreader.XMLReader* 메서드), 887
- getcontext() (*decimal* 모듈), 243
- getcontext() (*mhlib.MH* 메서드), 817
- GetCreatorAndType() (*MacOS* 모듈), 1393
- getctime() (*os.path* 모듈), 291
- getcurrent() (*mhlib.Folder* 메서드), 818
- getcwd() (*os* 모듈), 422
- getcwdu (2to3 fixer), 1192
- getcwdu() (*os* 모듈), 422
- getdate() (*rfc822.Message* 메서드), 829
- getdate_tz() (*rfc822.Message* 메서드), 829
- getdecoder() (*codecs* 모듈), 124
- getdefaultencoding() (*sys* 모듈), 1239
- getdefaultlocale() (*locale* 모듈), 1050
- getdefaulttimeout() (*socket* 모듈), 713
- getdlopenflags() (*sys* 모듈), 1240
- getdoc() (*inspect* 모듈), 1274
- getDOMImplementation() (*xml.dom* 모듈), 863
- getDTDHandler() (*xml.sax.xmlreader.XMLReader* 메서드), 887
- getEffectiveLevel() (*logging.Logger* 메서드), 518
- getegid() (*os* 모듈), 412
- getElementsByTagName() (*xml.dom.Document* 메서드), 868

`getElementsByTagName()` (*xml.dom.Element* 메서드), 868
`getElementsByTagNameNS()` (*xml.dom.Document* 메서드), 868
`getElementsByTagNameNS()` (*xml.dom.Element* 메서드), 868
`getencoder()` (*codecs* 모듈), 124
`getencoding()` (*mimetypes.Message* 메서드), 820
`getEncoding()` (*xml.sax.xmlreader.InputSource* 메서드), 888
`getEntityResolver()` (*xml.sax.xmlreader.XMLReader* 메서드), 887
`getenv()` (*os* 모듈), 414
`getErrorHandler()` (*xml.sax.xmlreader.XMLReader* 메서드), 887
`GetErrorString()` (*MacOS* 모듈), 1393
`geteuid()` (*os* 모듈), 412
`getEvent()` (*xml.dom.pulldom.DOMEventStream* 메서드), 878
`getEventCategory()` (*logging.handlers.NTEventLogHandler* 메서드), 546
`getEventType()` (*logging.handlers.NTEventLogHandler* 메서드), 546
`getException()` (*xml.sax.SAXException* 메서드), 880
`getFeature()` (*xml.sax.xmlreader.XMLReader* 메서드), 887
`GetFieldCount()` (*msilib.Record* 메서드), 1356
`getfile()` (*inspect* 모듈), 1274
`getfilesystemencoding()` (*sys* 모듈), 1240
`getfirst()` (*cgi.FieldStorage* 메서드), 905
`getfirstmatchingheader()` (*rfc822.Message* 메서드), 829
`getfloat()` (*ConfigParser.RawConfigParser* 메서드), 394
`getfmts()` (*ossaudiodev.oss_audio_device* 메서드), 1033
`getfqdn()` (*socket* 모듈), 710
`getframeinfo()` (*inspect* 모듈), 1276
`getframerate()` (*aifc.aifc* 메서드), 1022
`getframerate()` (*sunau.AU_read* 메서드), 1025
`getframerate()` (*wave.Wave_read* 메서드), 1027
`getfullname()` (*mhlib.Folder* 메서드), 818
`getgid()` (*os* 모듈), 413
`getgrall()` (*grp* 모듈), 1374
`getgrgid()` (*grp* 모듈), 1374
`getgrnam()` (*grp* 모듈), 1374
`getgroups()` (*os* 모듈), 413
`getheader()` (*httplib.HTTPResponse* 메서드), 942
`getheader()` (*rfc822.Message* 메서드), 829
`getheaders()` (*httplib.HTTPResponse* 메서드), 942
`gethostbyaddr()` (*in module socket*), 416
`gethostbyaddr()` (*socket* 모듈), 711
`gethostbyname()` (*socket* 모듈), 710
`gethostbyname_ex()` (*socket* 모듈), 710
`gethostname()` (*in module socket*), 416
`gethostname()` (*socket* 모듈), 711
`getincrementaldecoder()` (*codecs* 모듈), 124
`getincrementalencoder()` (*codecs* 모듈), 124
`getinfo()` (*zipfile.ZipFile* 메서드), 367
`getinnerframes()` (*inspect* 모듈), 1277
`GetInputContext()` (*xml.parsers.expat.xmlparser* 메서드), 891
`getint()` (*ConfigParser.RawConfigParser* 메서드), 394
`GetInteger()` (*msilib.Record* 메서드), 1356
`getitem()` (*operator* 모듈), 282
`getiterator()` (*xml.etree.ElementTree.Element* 메서드), 858
`getiterator()` (*xml.etree.ElementTree.ElementTree* 메서드), 859
`getitimer()` (*signal* 모듈), 746
`getkey()` (*curses.window* 메서드), 557
`getlast()` (*mhlib.Folder* 메서드), 818
`GetLastError()` (*ctypes* 모듈), 606
`getLength()` (*xml.sax.xmlreader.Attributes* 메서드), 889
`getLevelName()` (*logging* 모듈), 528
`getline()` (*linecache* 모듈), 307
`getLineNumber()` (*xml.sax.xmlreader.Locator* 메서드), 888
`getlist()` (*cgi.FieldStorage* 메서드), 905
`getloadavg()` (*os* 모듈), 439
`getlocale()` (*locale* 모듈), 1050
`getLogger()` (*logging* 모듈), 526
`getLoggerClass()` (*logging* 모듈), 526
`getlogin()` (*os* 모듈), 413
`getmaintype()` (*mimetypes.Message* 메서드), 820
`getmark()` (*aifc.aifc* 메서드), 1022
`getmark()` (*sunau.AU_read* 메서드), 1025
`getmark()` (*wave.Wave_read* 메서드), 1027
`getmarkers()` (*aifc.aifc* 메서드), 1022
`getmarkers()` (*sunau.AU_read* 메서드), 1025
`getmarkers()` (*wave.Wave_read* 메서드), 1027
`getmaxyx()` (*curses.window* 메서드), 557
`getmcolor()` (*fl* 모듈), 1422
`getmember()` (*tarfile.TarFile* 메서드), 375
`getmembers()` (*inspect* 모듈), 1272
`getmembers()` (*tarfile.TarFile* 메서드), 375
`getMessage()` (*logging.LogRecord* 메서드), 524
`getMessage()` (*xml.sax.SAXException* 메서드), 880
`getMessageFilename()` (*mhlib.Folder* 메서드), 818
`getMessageID()` (*logging.handlers.NTEventLogHandler* 메서드), 546
`getmodule()` (*inspect* 모듈), 1274
`getmoduleinfo()` (*inspect* 모듈), 1273

- `getmodulename()` (*inspect* 모듈), 1273
- `getmouse()` (*curses* 모듈), 550
- `getmro()` (*inspect* 모듈), 1275
- `getmtime()` (*os.path* 모듈), 290
- `getname()` (*chunk.Chunk* 메서드), 1029
- `getName()` (*threading.Thread* 메서드), 624
- `getNameByQName()` (*xml.sax.xmlreader.AttributesNS* 메서드), 889
- `getnameinfo()` (*socket* 모듈), 711
- `getnames()` (*tarfile.TarFile* 메서드), 376
- `getNames()` (*xml.sax.xmlreader.Attributes* 메서드), 889
- `getnchannels()` (*aifc.aifc* 메서드), 1022
- `getnchannels()` (*sunau.AU_read* 메서드), 1025
- `getnchannels()` (*wave.Wave_read* 메서드), 1027
- `getnframes()` (*aifc.aifc* 메서드), 1022
- `getnframes()` (*sunau.AU_read* 메서드), 1025
- `getnframes()` (*wave.Wave_read* 메서드), 1027
- `getnode`, 969
- `getnode()` (*uuid* 모듈), 969
- `getopt` (모듈), 515
- `getopt()` (*getopt* 모듈), 515
- `GetoptError`, 515
- `getouterframes()` (*inspect* 모듈), 1276
- `getoutput()` (*commands* 모듈), 1389
- `getpagesize()` (*resource* 모듈), 1386
- `getparam()` (*mimetools.Message* 메서드), 820
- `getparams()` (*aifc.aifc* 메서드), 1022
- `getparams()` (*al* 모듈), 1416
- `getparams()` (*sunau.AU_read* 메서드), 1025
- `getparams()` (*wave.Wave_read* 메서드), 1027
- `getparyx()` (*curses.window* 메서드), 557
- `getpass` (모듈), 548
- `getpass()` (*getpass* 모듈), 548
- `GetPassWarning`, 548
- `getpath()` (*mhlib.MH* 메서드), 817
- `getpeercert()` (*ssl.SSLSocket* 메서드), 730
- `getpeername()` (*socket.socket* 메서드), 714
- `getpen()` (*turtle* 모듈), 1117
- `getpgid()` (*os* 모듈), 413
- `getpgrp()` (*os* 모듈), 413
- `getpid()` (*os* 모듈), 413
- `getplist()` (*mimetools.Message* 메서드), 820
- `getpos()` (*HTMLParser.HTMLParser* 메서드), 839
- `getppid()` (*os* 모듈), 413
- `getpreferredencoding()` (*locale* 모듈), 1050
- `getprofile()` (*mhlib.MH* 메서드), 817
- `getprofile()` (*sys* 모듈), 1240
- `GetProperty()` (*msilib.SummaryInformation* 메서드), 1355
- `getProperty()` (*xml.sax.xmlreader.XMLReader* 메서드), 887
- `GetPropertyCount()` (*msilib.SummaryInformation* 메서드), 1355
- `getprotobyname()` (*socket* 모듈), 711
- `getproxies()` (*urllib* 모듈), 921
- `getPublicId()` (*xml.sax.xmlreader.InputSource* 메서드), 888
- `getPublicId()` (*xml.sax.xmlreader.Locator* 메서드), 888
- `getpwall()` (*pwd* 모듈), 1373
- `getpwnam()` (*pwd* 모듈), 1372
- `getpwuid()` (*pwd* 모듈), 1372
- `getQNameByName()` (*xml.sax.xmlreader.AttributesNS* 메서드), 889
- `getQNames()` (*xml.sax.xmlreader.AttributesNS* 메서드), 889
- `getquota()` (*imaplib.IMAP4* 메서드), 952
- `getquotaroot()` (*imaplib.IMAP4* 메서드), 952
- `getrandbits()` (*random* 모듈), 260
- `getrawheader()` (*rfc822.Message* 메서드), 829
- `getreader()` (*codecs* 모듈), 125
- `getrecursionlimit()` (*sys* 모듈), 1240
- `getrefcount()` (*sys* 모듈), 1240
- `getresgid()` (*os* 모듈), 414
- `getresponse()` (*httplib.HTTPConnection* 메서드), 940
- `getresuid()` (*os* 모듈), 413
- `getrlimit()` (*resource* 모듈), 1384
- `getroot()` (*xml.etree.ElementTree.ElementTree* 메서드), 859
- `getrusage()` (*resource* 모듈), 1385
- `getsample()` (*audioop* 모듈), 1018
- `getsampwidth()` (*aifc.aifc* 메서드), 1022
- `getsampwidth()` (*sunau.AU_read* 메서드), 1025
- `getsampwidth()` (*wave.Wave_read* 메서드), 1027
- `getscreen()` (*turtle* 모듈), 1117
- `getscrollbarvalues()` (*FrameWork.ScrolledWindow* 메서드), 1401
- `getsequences()` (*mhlib.Folder* 메서드), 818
- `getsequencesfilename()` (*mhlib.Folder* 메서드), 818
- `getservbyname()` (*socket* 모듈), 711
- `getservbyport()` (*socket* 모듈), 711
- `GetSetDescriptorType` (*types* 모듈), 213
- `getshapes()` (*turtle* 모듈), 1122
- `getsid()` (*os* 모듈), 415
- `getsignal()` (*signal* 모듈), 745
- `getsitpackages()` (*site* 모듈), 1279
- `getsize()` (*chunk.Chunk* 메서드), 1029
- `getsize()` (*os.path* 모듈), 291
- `getsizeof()` (*sys* 모듈), 1240
- `getsizes()` (*imgfile* 모듈), 1429
- `getslice()` (*operator* 모듈), 282
- `getsockname()` (*socket.socket* 메서드), 714
- `getsockopt()` (*socket.socket* 메서드), 714
- `getsource()` (*inspect* 모듈), 1275
- `getsourcefile()` (*inspect* 모듈), 1274
- `getsourcelines()` (*inspect* 모듈), 1274

- getspall() (*spwd* 모듈), 1373
 getspnam() (*spwd* 모듈), 1373
 getstate() (*random* 모듈), 260
 getstatus() (*commands* 모듈), 1389
 getstatusoutput() (*commands* 모듈), 1388
 getstr() (*curses.window* 메서드), 557
 GetString() (*msilib.Record* 메서드), 1356
 getSubject() (*logging.handlers.SMTPHandler* 메서드), 546
 getsubtype() (*mimetools.Message* 메서드), 820
 GetSummaryInformation() (*msilib.Database* 메서드), 1354
 getSystemId() (*xml.sax.xmlreader.InputSource* 메서드), 888
 getSystemId() (*xml.sax.xmlreader.Locator* 메서드), 888
 getsyx() (*curses* 모듈), 551
 gettarinfo() (*tarfile.TarFile* 메서드), 377
 gettempdir() (*tempfile* 모듈), 304
 gettempprefix() (*tempfile* 모듈), 304
 getTestCaseNames() (*unittest.TestLoader* 메서드), 1183
 gettext (모듈), 1037
 gettext() (*gettext* 모듈), 1038
 gettext() (*gettext.GNUTranslations* 메서드), 1042
 gettext() (*gettext.NullTranslations* 메서드), 1040
 gettext() (*locale* 모듈), 1053
 GetTicks() (*MacOS* 모듈), 1393
 gettimeout() (*socket.socket* 메서드), 716
 gettrace() (*sys* 모듈), 1240
 getturtle() (*turtle* 모듈), 1117
 gettype() (*mimetools.Message* 메서드), 820
 getType() (*xml.sax.xmlreader.Attributes* 메서드), 889
 getuid() (*os* 모듈), 414
 geturl() (*urlparse.ParseResult* 메서드), 975
 getuser() (*getpass* 모듈), 548
 getuserbase() (*site* 모듈), 1279
 getusersitepackages() (*site* 모듈), 1279
 getvalue() (*io.BytesIO* 메서드), 447
 getvalue() (*io.StringIO* 메서드), 450
 getvalue() (*StringIO.StringIO* 메서드), 119
 getValue() (*xml.sax.xmlreader.Attributes* 메서드), 889
 GetValueByQName() (*xml.sax.xmlreader.AttributesNS* 메서드), 889
 getwch() (*msvcrt* 모듈), 1360
 getwche() (*msvcrt* 모듈), 1360
 getweakrefcount() (*weakref* 모듈), 205
 getweakrefs() (*weakref* 모듈), 205
 getwelcome() (*ftplib.FTP* 메서드), 945
 getwelcome() (*nnplib.NNTP* 메서드), 957
 getwelcome() (*poplib.POP3* 메서드), 949
 getwin() (*curses* 모듈), 551
 getwindowsversion() (*sys* 모듈), 1241
 getwriter() (*codecs* 모듈), 125
 getyx() (*curses.window* 메서드), 557
 gid (*tarfile.TarInfo*의 속성), 378
 GIL, 1442
 GL (모듈), 1429
 gl (모듈), 1427
 glob
 모듈, 306
 glob (모듈), 305
 glob() (*glob* 모듈), 305
 glob() (*msilib.Directory* 메서드), 1357
 global interpreter lock (전역 인터프리터 록), 1442
 globals() (내장 함수), 11
 globs (*doctest.DocTest*의 속성), 1156
 gmtime() (*time* 모듈), 453
 gname (*tarfile.TarInfo*의 속성), 378
 GNOME, 1043
 GNU_FORMAT (*tarfile* 모듈), 374
 gnu_getopt() (*getopt* 모듈), 515
 got (*doctest.DocTestFailure*의 속성), 1163
 goto() (*turtle* 모듈), 1103
 Graphical User Interface, 1063
 GREATER (*token* 모듈), 1321
 GREATEREQUAL (*token* 모듈), 1321
 Greenwich Mean Time, 452
 grey2grey2() (*imageop* 모듈), 1021
 grey2grey4() (*imageop* 모듈), 1021
 grey2mono() (*imageop* 모듈), 1021
 grey22grey() (*imageop* 모듈), 1021
 grey42grey() (*imageop* 모듈), 1021
 group() (*nnplib.NNTP* 메서드), 958
 group() (*re.MatchObject* 메서드), 98
 groupby() (*itertools* 모듈), 268
 groupdict() (*re.MatchObject* 메서드), 99
 groupindex (*re.RegexObject*의 속성), 97
 groups (*re.RegexObject*의 속성), 97
 groups() (*re.MatchObject* 메서드), 99
 grp (모듈), 1374
 gt() (*operator* 모듈), 280
 guess_all_extensions() (*mimetypes* 모듈), 821
 guess_all_extensions() (*mimetypes.MimeTypes* 메서드), 822
 guess_extension() (*mimetypes* 모듈), 821
 guess_extension() (*mimetypes.MimeTypes* 메서드), 822
 guess_scheme() (*wsgiref.util* 모듈), 910
 guess_type() (*mimetypes* 모듈), 820
 guess_type() (*mimetypes.MimeTypes* 메서드), 822
 GUI, 1063
 gzip (모듈), 362
 GzipFile (*gzip* 클래스), 362
- ## H
- h

- timeit command line option, 1224
- halfdelay() (*curses* 모듈), 551
- handle() (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 985
- handle() (*logging.Handler* 메서드), 521
- handle() (*logging.Logger* 메서드), 520
- handle() (*logging.NullHandler* 메서드), 540
- handle() (*SocketServer.BaseRequestHandler* 메서드), 979
- handle() (*wsgiref.simple_server.WSGIRequestHandler* 메서드), 914
- handle_accept() (*asyncore.dispatcher* 메서드), 750
- handle_charref() (*HTMLParser.HTMLParser* 메서드), 839
- handle_charref() (*sgmlib.SGMLParser* 메서드), 843
- handle_close() (*asyncore.dispatcher* 메서드), 750
- handle_comment() (*HTMLParser.HTMLParser* 메서드), 839
- handle_comment() (*sgmlib.SGMLParser* 메서드), 844
- handle_connect() (*asyncore.dispatcher* 메서드), 750
- handle_data() (*HTMLParser.HTMLParser* 메서드), 839
- handle_data() (*sgmlib.SGMLParser* 메서드), 843
- handle_decl() (*HTMLParser.HTMLParser* 메서드), 840
- handle_decl() (*sgmlib.SGMLParser* 메서드), 844
- handle_endtag() (*HTMLParser.HTMLParser* 메서드), 839
- handle_endtag() (*sgmlib.SGMLParser* 메서드), 843
- handle_entityref() (*HTMLParser.HTMLParser* 메서드), 839
- handle_entityref() (*sgmlib.SGMLParser* 메서드), 844
- handle_error() (*asyncore.dispatcher* 메서드), 750
- handle_error() (*SocketServer.BaseServer* 메서드), 978
- handle_expt() (*asyncore.dispatcher* 메서드), 750
- handle_image() (*htmlib.HTMLParser* 메서드), 846
- handle_one_request() (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 985
- handle_pi() (*HTMLParser.HTMLParser* 메서드), 840
- handle_read() (*asyncore.dispatcher* 메서드), 750
- handle_request() (*SimpleXMLRPC-Server.CGIXMLRPCRequestHandler* 메서드), 1013
- handle_request() (*SocketServer.BaseServer* 메서드), 977
- handle_startendtag() (*HTMLParser.HTMLParser* 메서드), 839
- handle_starttag() (*HTMLParser.HTMLParser* 메서드), 839
- handle_starttag() (*sgmlib.SGMLParser* 메서드), 843
- handle_timeout() (*SocketServer.BaseServer* 메서드), 978
- handle_write() (*asyncore.dispatcher* 메서드), 750
- handleError() (*logging.Handler* 메서드), 521
- handleError() (*logging.handlers.SocketHandler* 메서드), 543
- handler() (*cgitb* 모듈), 909
- HAS_ALPN (*ssl* 모듈), 728
- has_children() (*symtable.SymbolTable* 메서드), 1319
- has_colors() (*curses* 모듈), 551
- has_data() (*urllib2.Request* 메서드), 929
- HAS_ECDH (*ssl* 모듈), 728
- has_exec() (*symtable.SymbolTable* 메서드), 1319
- has_extn() (*smtplib.SMTP* 메서드), 962
- has_header() (*csv.Sniffer* 메서드), 386
- has_header() (*urllib2.Request* 메서드), 929
- has_ic() (*curses* 모듈), 551
- has_il() (*curses* 모듈), 551
- has_import_star() (*symtable.SymbolTable* 메서드), 1319
- has_ipv6 (*socket* 모듈), 709
- has_key (2to3 fixer), 1192
- has_key() (*bsddb.bsddbobject* 메서드), 335
- has_key() (*curses* 모듈), 551
- has_key() (*dict* 메서드), 54
- has_key() (*email.message.Message* 메서드), 760
- has_key() (*mailbox.Mailbox* 메서드), 799
- has_nonstandard_attr() (*cookielib.Cookie* 메서드), 997
- HAS_NPN (*ssl* 모듈), 729
- has_option() (*ConfigParser.RawConfigParser* 메서드), 394
- has_option() (*optparse.OptionParser* 메서드), 506
- has_section() (*ConfigParser.RawConfigParser* 메서드), 393
- HAS_SNI (*ssl* 모듈), 728
- HAS_TLSv1_3 (*ssl* 모듈), 729
- hasattr() (내장 함수), 11
- hasAttribute() (*xml.dom.Element* 메서드), 868
- hasAttributeNS() (*xml.dom.Element* 메서드), 868
- hasAttributes() (*xml.dom.Node* 메서드), 865
- hasChildNodes() (*xml.dom.Node* 메서드), 865
- hascompare (*dis* 모듈), 1330
- hasconst (*dis* 모듈), 1330
- hasFeature() (*xml.dom.DOMImplementation* 메서드), 864
- hasfree (*dis* 모듈), 1330
- hash() (내장 함수), 12
- Hashable (*collections* 클래스), 185
- hashable (해시 가능), 1442

hash.block_size (*hashlib* 모듈), 406
 hash.digest_size (*hashlib* 모듈), 406
 hashlib (모듈), 405
 hashlib.algorithms (*hashlib* 모듈), 406
 hashopen() (*bsddb* 모듈), 334
 hasjabs (*dis* 모듈), 1330
 hasjrel (*dis* 모듈), 1330
 haslocal (*dis* 모듈), 1330
 hasname (*dis* 모듈), 1330
 HAVE_ARGUMENT (*opcode*), 1338
 have_unicode (*test.support* 모듈), 1198
 head() (*nnplib.NNTP* 메서드), 958
 Header (*email.header* 클래스), 771
 header_encode() (*email.charset.Charset* 메서드), 774
 header_encoding (*email.charset.Charset*의 속성), 773
 header_items() (*urllib2.Request* 메서드), 929
 header_offset (*zipfile.ZipInfo*의 속성), 371
 HeaderError, 374
 HeaderParseError, 776
 headers
 MIME, 820, 902
 headers (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
 headers (*rfc822.Message*의 속성), 830
 Headers (*wsgiref.headers* 클래스), 912
 headers (*xmlrpclib.ProtocolError*의 속성), 1007
 heading() (*tk.Treeview* 메서드), 1087
 heading() (*turtle* 모듈), 1107
 heapify() (*heapq* 모듈), 187
 heapmin() (*msvcrt* 모듈), 1360
 heappop() (*heapq* 모듈), 187
 heappush() (*heapq* 모듈), 187
 heappushpop() (*heapq* 모듈), 187
 heapq (모듈), 187
 heapreplace() (*heapq* 모듈), 187
 hello() (*smtpplib.SMTP* 메서드), 961
 help
 online, 1139
 --help
 timeit command line option, 1224
 trace command line option, 1227
 help (*optparse.Option*의 속성), 501
 help() (*nnplib.NNTP* 메서드), 958
 help() (내장 함수), 12
 horror, 708
 hex (*uuid.UUID*의 속성), 969
 hex() (*float* 메서드), 36
 hex() (*future_builtins* 모듈), 1252
 hex() (내장 함수), 12
 hexadecimal
 literals, 33
 hexbin() (*binhex* 모듈), 833
 hexdigest() (*hashlib.hash* 메서드), 407
 hexdigest() (*hmac.HMAC* 메서드), 408
 hexdigest() (*md5.md5* 메서드), 409
 hexdigest() (*sha.sha* 메서드), 410
 hexdigits (*string* 모듈), 76
 hexlify() (*binascii* 모듈), 835
 hexversion (*sys* 모듈), 1241
 hidden() (*curses.panel.Panel* 메서드), 569
 hide() (*curses.panel.Panel* 메서드), 570
 hide() (*ttk.Notebook* 메서드), 1081
 hide_cookie2 (*cookielib.CookiePolicy*의 속성), 994
 hide_form() (*fl.form* 메서드), 1422
 hideturtle() (*turtle* 모듈), 1113
 HierarchyRequestErr, 870
 HIGHEST_PROTOCOL (*pickle* 모듈), 315
 HKEY_CLASSES_ROOT (*_winreg* 모듈), 1366
 HKEY_CURRENT_CONFIG (*_winreg* 모듈), 1366
 HKEY_CURRENT_USER (*_winreg* 모듈), 1366
 HKEY_DYN_DATA (*_winreg* 모듈), 1366
 HKEY_LOCAL_MACHINE (*_winreg* 모듈), 1366
 HKEY_PERFORMANCE_DATA (*_winreg* 모듈), 1366
 HKEY_USERS (*_winreg* 모듈), 1366
 hline() (*curses.window* 메서드), 557
 HList (*Tix* 클래스), 1096
 hls_to_rgb() (*coloursys* 모듈), 1030
 hmac (모듈), 408
 HOME, 290, 1280
 home() (*turtle* 모듈), 1104
 HOMEDRIVE, 290
 HOMEPATH, 290
 hook_compressed() (*fileinput* 모듈), 295
 hook_encoded() (*fileinput* 모듈), 295
 hosts (*netrc.netrc*의 속성), 399
 hotshot (모듈), 1220
 hotshot.stats (모듈), 1221
 hour (*datetime.datetime*의 속성), 152
 hour (*datetime.time*의 속성), 158
 HRESULT (*ctypes* 클래스), 611
 hStdError (*subprocess.STARTUPINFO*의 속성), 703
 hStdInput (*subprocess.STARTUPINFO*의 속성), 702
 hStdOutput (*subprocess.STARTUPINFO*의 속성), 703
 hsv_to_rgb() (*coloursys* 모듈), 1030
 ht() (*turtle* 모듈), 1113
 HTML, 837, 845, 924
 HTMLCalendar (*calendar* 클래스), 170
 HtmlDiff (*difflib* 클래스), 109
 HtmlDiff.__init__() (*difflib* 모듈), 109
 HtmlDiff.make_file() (*difflib* 모듈), 110
 HtmlDiff.make_table() (*difflib* 모듈), 110
 htmlentitydefs (모듈), 847
 htmllib
 모듈, 924
 htmllib (모듈), 845
 HTMLParseError, 838, 845

- HTMLParser (class in *html*lib), 1347
 HTMLParser (*html*lib 클래스), 845
 HTMLParser (*HTMLParser* 클래스), 837
 HTMLParser (모듈), 837
 htonl () (*socket* 모듈), 712
 htons () (*socket* 모듈), 712
 HTTP
 *http*lib (standard module), 937
 protocol, 902, 924, 937, 983
 http_error_301 () (*urllib2.HTTPRedirectHandler* 메서드), 932
 http_error_302 () (*urllib2.HTTPRedirectHandler* 메서드), 932
 http_error_303 () (*urllib2.HTTPRedirectHandler* 메서드), 932
 http_error_307 () (*urllib2.HTTPRedirectHandler* 메서드), 932
 http_error_401 () (*urllib2.HTTPBasicAuthHandler* 메서드), 934
 http_error_401 () (*urllib2.HTTPDigestAuthHandler* 메서드), 934
 http_error_407 () (*urllib2.ProxyBasicAuthHandler* 메서드), 934
 http_error_407 () (*urllib2.ProxyDigestAuthHandler* 메서드), 934
 http_error_auth_reged () (*urllib2.AbstractBasicAuthHandler* 메서드), 933
 http_error_auth_reged () (*urllib2.AbstractDigestAuthHandler* 메서드), 934
 http_error_default () (*urllib2.BaseHandler* 메서드), 931
 http_error_nnn () (*urllib2.BaseHandler* 메서드), 931
 http_open () (*urllib2.HTTPHandler* 메서드), 934
 HTTP_PORT (*http*lib 모듈), 939
 http_proxy, 919, 926, 936
 http_response () (*urllib2.HTTPErrorProcessor* 메서드), 935
 http_version (*wsgiref.handlers.BaseHandler*의 속성), 917
 HTTPBasicAuthHandler (*urllib2* 클래스), 928
 HTTPConnection (*http*lib 클래스), 937
 HTTPCookieProcessor (*urllib2* 클래스), 927
 httpd, 983
 HTTPDefaultErrorHandler (*urllib2* 클래스), 927
 HTTPDigestAuthHandler (*urllib2* 클래스), 928
 HTTPError, 926
 HTTPErrorProcessor (*urllib2* 클래스), 928
 HTTPException, 938
 HTTPHandler (*logging.handlers* 클래스), 547
 HTTPHandler (*urllib2* 클래스), 928
 httplib (모듈), 937
 HTTPMessage (*http*lib 클래스), 938
 HTTPPasswordMgr (*urllib2* 클래스), 927
 HTTPPasswordMgrWithDefaultRealm (*urllib2* 클래스), 927
 HTTPRedirectHandler (*urllib2* 클래스), 927
 HTTPResponse (*http*lib 클래스), 938
 https_open () (*urllib2.HTTPSHandler* 메서드), 934
 HTTPS_PORT (*http*lib 모듈), 939
 https_response () (*urllib2.HTTPErrorProcessor* 메서드), 935
 HTTPSConnection (*http*lib 클래스), 937
 HTTPServer (*BaseHTTPServer* 클래스), 984
 HTTPSHandler (*urllib2* 클래스), 928
 hypertext, 845
 hypot () (*math* 모듈), 227
 I
 I (*re* 모듈), 93
 -i list
 compileall command line option, 1328
 I/O control
 buffering, 15, 416, 714
 POSIX, 1376
 tty, 1376
 UNIX, 1378
 iadd () (*operator* 모듈), 283
 iand () (*operator* 모듈), 283
 IC (*ic* 클래스), 1391
 ic (모듈), 1391
 icglue
 모듈, 1391
 iconcat () (*operator* 모듈), 283
 icopen (모듈), 1436
 id () (*unittest.TestCase* 메서드), 1180
 id () (내장 함수), 12
 idcok () (*curses.window* 메서드), 557
 ident (*cd* 모듈), 1418
 ident (*select.kevent*의 속성), 619
 ident (*threading.Thread*의 속성), 624
 identchars (*cmd.Cmd*의 속성), 1057
 identify () (*ttk.Notebook* 메서드), 1082
 identify () (*ttk.Treeview* 메서드), 1088
 identify () (*ttk.Widget* 메서드), 1078
 identify_column () (*ttk.Treeview* 메서드), 1088
 identify_element () (*ttk.Treeview* 메서드), 1088
 identify_region () (*ttk.Treeview* 메서드), 1088
 identify_row () (*ttk.Treeview* 메서드), 1088
 idioms (*2to3 fixer*), 1192
 idiv () (*operator* 모듈), 283
 IDLE, 1129, 1443
 idle () (*FrameWork.Application* 메서드), 1400
 IDLESTARTUP, 1135
 idlok () (*curses.window* 메서드), 558
 IEEE-754, 1280

if
 글, 31
 ifilter() (*itertools* 모듈), 269
 ifilterfalse() (*itertools* 모듈), 269
 ifloordiv() (*operator* 모듈), 283
 iglob() (*glob* 모듈), 305
 ignorableWhitespace()
 (*xml.sax.handler.ContentHandler* 메서드), 883
 ignore_errors() (*codecs* 모듈), 125
 IGNORE_EXCEPTION_DETAIL (*doctest* 모듈), 1148
 ignore_patterns() (*shutil* 모듈), 308
 IGNORECASE (*re* 모듈), 93
 --ignore-dir=<dir>
 trace command line option, 1228
 --ignore-module=<mod>
 trace command line option, 1228
 ihave() (*nnplib.NNTP* 메서드), 959
 ilshift() (*operator* 모듈), 283
 imag (*numbers.Complex*의 속성), 221
 imageop (모듈), 1020
 imap() (*itertools* 모듈), 269
 imap() (*multiprocessing.pool.multiprocessing.Pool* 메서드), 657
 IMAP4
 protocol, 950
 IMAP4 (*imaplib* 클래스), 950
 IMAP4_SSL
 protocol, 950
 IMAP4_SSL (*imaplib* 클래스), 950
 IMAP4_stream
 protocol, 950
 IMAP4_stream (*imaplib* 클래스), 950
 IMAP4.abort, 950
 IMAP4.error, 950
 IMAP4.readonly, 950
 imap_unordered() (*multiprocessing.pool.multiprocessing.Pool* 메서드), 658
 imaplib (모듈), 950
 imgfile (모듈), 1429
 imghdr (모듈), 1030
 immedok() (*curses.window* 메서드), 558
 immutable (불변), 1443
 ImmutableSet (*sets* 클래스), 196
 imod() (*operator* 모듈), 283
 imp
 모듈, 24
 imp (모듈), 1293
 ImpImporter (*pkgutil* 클래스), 1303
 ImpLoader (*pkgutil* 클래스), 1303
 import
 글, 24, 1293, 1297
 import (2to3 fixer), 1193
 import_file() (*imputil.DynLoadSuffixImporter* 메서드), 1298
 import_fresh_module() (*test.support* 모듈), 1200
 IMPORT_FROM (*opcode*), 1336
 import_module() (*importlib* 모듈), 1297
 import_module() (*test.support* 모듈), 1200
 IMPORT_NAME (*opcode*), 1336
 IMPORT_STAR (*opcode*), 1334
 import_top() (*imputil.Importer* 메서드), 1297
 Importer (*imputil* 클래스), 1297
 importer (임포터), 1443
 ImportError, 69
 importing (임포팅), 1443
 importlib (모듈), 1297
 ImportManager (*imputil* 클래스), 1297
 imports (2to3 fixer), 1193
 imports2 (2to3 fixer), 1193
 ImportWarning, 72
 ImproperConnectionState, 939
 imputil (모듈), 1297
 imul() (*operator* 모듈), 284
 in
 연산자, 33, 38
 in_dll() (*ctypes._CData* 메서드), 608
 in_table_a1() (*stringprep* 모듈), 140
 in_table_b1() (*stringprep* 모듈), 140
 in_table_c3() (*stringprep* 모듈), 140
 in_table_c4() (*stringprep* 모듈), 140
 in_table_c5() (*stringprep* 모듈), 140
 in_table_c6() (*stringprep* 모듈), 140
 in_table_c7() (*stringprep* 모듈), 140
 in_table_c8() (*stringprep* 모듈), 140
 in_table_c9() (*stringprep* 모듈), 140
 in_table_c11() (*stringprep* 모듈), 140
 in_table_c11_c12() (*stringprep* 모듈), 140
 in_table_c12() (*stringprep* 모듈), 140
 in_table_c21() (*stringprep* 모듈), 140
 in_table_c21_c22() (*stringprep* 모듈), 140
 in_table_c22() (*stringprep* 모듈), 140
 in_table_d1() (*stringprep* 모듈), 141
 in_table_d2() (*stringprep* 모듈), 141
 inc() (*EasyDialogs.ProgressBar* 메서드), 1398
 inch() (*curses.window* 메서드), 558
 Incomplete, 835
 IncompleteRead, 938
 increment_lineno() (*ast* 모듈), 1317
 IncrementalDecoder (*codecs* 클래스), 128
 IncrementalEncoder (*codecs* 클래스), 128
 IncrementalNewlineDecoder (*io* 클래스), 450
 IncrementalParser (*xml.sax.xmlreader* 클래스), 886
 indent (*doctest.Example*의 속성), 1157
 INDENT (*token* 모듈), 1321
 IndentationError, 70

- Independent JPEG Group, 1430
- index (*cd* 모듈), 1418
- index () (*array.array* 메서드), 195
- index () (*list* method), 48
- index () (*operator* 모듈), 281
- index () (*str* 메서드), 41
- index () (*string* 모듈), 86
- index () (*ttk.Notebook* 메서드), 1082
- index () (*ttk.Treeview* 메서드), 1088
- IndexError, 69
- indexOf () (*operator* 모듈), 282
- IndexSizeErr, 871
- inet_aton () (*socket* 모듈), 712
- inet_ntoa () (*socket* 모듈), 712
- inet_ntop () (*socket* 모듈), 712
- inet_pton () (*socket* 모듈), 712
- Inexact (*decimal* 클래스), 249
- infile (*shlex.shlex*의 속성), 1060
- Infinity, 11, 86
- info () (*gettext.NullTranslations* 메서드), 1041
- info () (*logging* 모듈), 527
- info () (*logging.Logger* 메서드), 519
- infolist () (*zipfile.ZipFile* 메서드), 368
- InfoScrap () (*Carbon.Scrap* 모듈), 1405
- .ini
 - file, 391
- ini file, 391
- init () (*fm* 모듈), 1426
- init () (*mimetypes* 모듈), 821
- init_builtin () (*imp* 모듈), 1295
- init_color () (*curses* 모듈), 551
- init_database () (*msilib* 모듈), 1354
- init_frozen () (*imp* 모듈), 1295
- init_pair () (*curses* 모듈), 551
- inited (*mimetypes* 모듈), 821
- initgroups () (*os* 모듈), 413
- initial_indent (*textwrap.TextWrapper*의 속성), 122
- initscr () (*curses* 모듈), 551
- INPLACE_ADD (*opcode*), 1332
- INPLACE_AND (*opcode*), 1332
- INPLACE_DIVIDE (*opcode*), 1332
- INPLACE_FLOOR_DIVIDE (*opcode*), 1332
- INPLACE_LSHIFT (*opcode*), 1332
- INPLACE_MODULO (*opcode*), 1332
- INPLACE_MULTIPLY (*opcode*), 1332
- INPLACE_OR (*opcode*), 1333
- INPLACE_POWER (*opcode*), 1332
- INPLACE_RSHIFT (*opcode*), 1332
- INPLACE_SUBTRACT (*opcode*), 1332
- INPLACE_TRUE_DIVIDE (*opcode*), 1332
- INPLACE_XOR (*opcode*), 1332
- input
 - 내장 함수, 1246
- input (*2to3 fixer*), 1193
- input () (*fileinput* 모듈), 293
- input () (내장 함수), 12
- input_charset (*email.charset.Charset*의 속성), 773
- input_codec (*email.charset.Charset*의 속성), 773
- InputOnly (*Tix* 클래스), 1097
- InputSource (*xml.sax.xmlreader* 클래스), 886
- InputType (*cStringIO* 모듈), 120
- insch () (*curses.window* 메서드), 558
- insdelln () (*curses.window* 메서드), 558
- insert () (*array.array* 메서드), 195
- insert () (*list* method), 48
- insert () (*ttk.Notebook* 메서드), 1082
- insert () (*ttk.Treeview* 메서드), 1088
- insert () (*xml.etree.ElementTree.Element* 메서드), 858
- insert_text () (*readline* 모듈), 689
- insertBefore () (*xml.dom.Node* 메서드), 866
- InsertionLoc (*aetypes* 클래스), 1411
- insertln () (*curses.window* 메서드), 558
- insnstr () (*curses.window* 메서드), 558
- insort () (*bisect* 모듈), 191
- insort_left () (*bisect* 모듈), 191
- insort_right () (*bisect* 모듈), 191
- inspect (모듈), 1271
- insstr () (*curses.window* 메서드), 558
- install () (*gettext* 모듈), 1039
- install () (*gettext.NullTranslations* 메서드), 1041
- install () (*imputil.ImportManager* 메서드), 1297
- install_opener () (*urllib2* 모듈), 926
- installaehandler () (*MiniAEFrame.AEServer* 메서드), 1413
- installAutoGIL () (*autoGIL* 모듈), 1402
- installHandler () (*unittest* 모듈), 1189
- instance () (*new* 모듈), 213
- instancemethod () (*new* 모듈), 213
- InstanceType (*types* 모듈), 212
- instate () (*ttk.Widget* 메서드), 1078
- instr () (*curses.window* 메서드), 558
- instream (*shlex.shlex*의 속성), 1060
- int
 - 내장 함수, 33
- int (*uuid.UUID*의 속성), 969
- int (내장 클래스), 12
- Int2AP () (*imaplib* 모듈), 951
- integer
 - division, 34
 - division, long, 34
 - literals, 33
 - literals, long, 33
 - types, operations on, 35
 - 객체, 33
- integer division, 1443
- Integral (*numbers* 클래스), 222
- Integrated Development Environment, 1129
- Intel/DVI ADPCM, 1017

- `interact()` (*code* 모듈), 1283
- `interact()` (*code.InteractiveConsole* 메서드), 1285
- `interact()` (*telnetlib.Telnet* 메서드), 967
- `interactive` (대화형), 1443
- `InteractiveConsole` (*code* 클래스), 1283
- `InteractiveInterpreter` (*code* 클래스), 1283
- `intern (2to3 fixer)`, 1193
- `intern()` (내장 함수), 27
- `internal_attr` (*zipfile.ZipInfo*의 속성), 371
- `Internaldate2tuple()` (*imaplib* 모듈), 951
- `internalSubset` (*xml.dom.DocumentType*의 속성), 867
- `Internet`, 899
- `Internet Config`, 919
- `interpolation, string (%)`, 46
- `InterpolationDepthError`, 393
- `InterpolationError`, 393
- `InterpolationMissingOptionError`, 393
- `InterpolationSyntaxError`, 393
- `interpreted` (인터프리터드), 1443
- `interpreter prompts`, 1244
- `interrupt()` (*sqlite3.Connection* 메서드), 343
- `interrupt_main()` (*thread* 모듈), 631
- `intersection()` (*frozenset* 메서드), 50
- `intersection_update()` (*frozenset* 메서드), 51
- `IntlText` (*aetypes* 클래스), 1411
- `IntlWritingCode` (*aetypes* 클래스), 1411
- `intro` (*cmd.Cmd*의 속성), 1057
- `IntType` (*types* 모듈), 211
- `InuseAttributeErr`, 871
- `inv()` (*operator* 모듈), 281
- `InvalidAccessErr`, 871
- `InvalidCharacterErr`, 871
- `InvalidModificationErr`, 871
- `InvalidOperation` (*decimal* 클래스), 250
- `InvalidStateErr`, 871
- `InvalidURL`, 938
- `invert()` (*operator* 모듈), 281
- `io` (모듈), 440
- `IOBase` (*io* 클래스), 443
- `ioctl()` (*fcntl* 모듈), 1379
- `ioctl()` (*socket.socket* 메서드), 714
- `IOError`, 69
- `ior()` (*operator* 모듈), 284
- `ipow()` (*operator* 모듈), 284
- `irepeat()` (*operator* 모듈), 284
- `IRIS Font Manager`, 1426
- `IRIX`
 - `threads`, 632
- `irshift()` (*operator* 모듈), 284
- `is`
 - 연산자, 32
- `is not`
 - 연산자, 32
- `is_()` (*operator* 모듈), 280
- `is_alive()` (*multiprocessing.Process* 메서드), 639
- `is_alive()` (*threading.Thread* 메서드), 624
- `is_assigned()` (*symtable.Symbol* 메서드), 1320
- `is_blocked()` (*cookielib.DefaultCookiePolicy* 메서드), 995
- `is_builtin()` (*imp* 모듈), 1295
- `is_canonical()` (*decimal.Context* 메서드), 247
- `is_canonical()` (*decimal.Decimal* 메서드), 239
- `IS_CHARACTER_JUNK()` (*difflib* 모듈), 112
- `is_data()` (*multifile.MultiFile* 메서드), 826
- `is_declared_global()` (*symtable.Symbol* 메서드), 1320
- `is_empty()` (*asynchat.fifo* 메서드), 754
- `is_expired()` (*cookielib.Cookie* 메서드), 997
- `is_finite()` (*decimal.Context* 메서드), 247
- `is_finite()` (*decimal.Decimal* 메서드), 239
- `is_free()` (*symtable.Symbol* 메서드), 1320
- `is_frozen()` (*imp* 모듈), 1295
- `is_global()` (*symtable.Symbol* 메서드), 1320
- `is_hop_by_hop()` (*wsgiref.util* 모듈), 911
- `is_imported()` (*symtable.Symbol* 메서드), 1320
- `is_infinite()` (*decimal.Context* 메서드), 247
- `is_infinite()` (*decimal.Decimal* 메서드), 239
- `is_integer()` (*float* 메서드), 36
- `is_jython` (*test.support* 모듈), 1198
- `IS_LINE_JUNK()` (*difflib* 모듈), 112
- `is_linetouched()` (*curses.window* 메서드), 558
- `is_local()` (*symtable.Symbol* 메서드), 1320
- `is_multipart()` (*email.message.Message* 메서드), 758
- `is_namespace()` (*symtable.Symbol* 메서드), 1320
- `is_nan()` (*decimal.Context* 메서드), 247
- `is_nan()` (*decimal.Decimal* 메서드), 239
- `is_nested()` (*symtable.SymbolTable* 메서드), 1319
- `is_normal()` (*decimal.Context* 메서드), 247
- `is_normal()` (*decimal.Decimal* 메서드), 239
- `is_not()` (*operator* 모듈), 280
- `is_not_allowed()` (*cookielib.DefaultCookiePolicy* 메서드), 995
- `is_optimized()` (*symtable.SymbolTable* 메서드), 1319
- `is_package()` (*zipimport.zipimporter* 메서드), 1301
- `is_parameter()` (*symtable.Symbol* 메서드), 1320
- `is_python_build()` (*sysconfig* 모듈), 1250
- `is_qnan()` (*decimal.Context* 메서드), 247
- `is_qnan()` (*decimal.Decimal* 메서드), 239
- `is_referenced()` (*symtable.Symbol* 메서드), 1320
- `is_resource_enabled()` (*test.support* 모듈), 1198
- `is_scriptable()` (*gensuitemodule* 모듈), 1408
- `is_set()` (*threading.Event* 메서드), 629
- `is_signed()` (*decimal.Context* 메서드), 247
- `is_signed()` (*decimal.Decimal* 메서드), 239
- `is_snan()` (*decimal.Context* 메서드), 247

- `is_snan()` (*decimal.Decimal* 메서드), 239
- `is_subnormal()` (*decimal.Context* 메서드), 247
- `is_subnormal()` (*decimal.Decimal* 메서드), 239
- `is_tarfile()` (*tarfile* 모듈), 373
- `is_term_resized()` (*curses* 모듈), 551
- `is_tracked()` (*gc* 모듈), 1270
- `is_unverifiable()` (*urllib2.Request* 메서드), 929
- `is_wintouched()` (*curses.window* 메서드), 558
- `is_zero()` (*decimal.Context* 메서드), 247
- `is_zero()` (*decimal.Decimal* 메서드), 240
- `is_zipfile()` (*zipfile* 모듈), 367
- `isabs()` (*os.path* 모듈), 291
- `isabstract()` (*inspect* 모듈), 1273
- `isAlive()` (*threading.Thread* 메서드), 624
- `isalnum()` (*curses.ascii* 모듈), 568
- `isalnum()` (*str* 메서드), 41
- `isalpha()` (*curses.ascii* 모듈), 568
- `isalpha()` (*str* 메서드), 41
- `isascii()` (*curses.ascii* 모듈), 568
- `isatty()` (*chunk.Chunk* 메서드), 1029
- `isatty()` (*file* 메서드), 57
- `isatty()` (*io.IOBase* 메서드), 443
- `isatty()` (*os* 모듈), 419
- `isblank()` (*curses.ascii* 모듈), 568
- `isblk()` (*tarfile.TarInfo* 메서드), 379
- `isbuiltin()` (*inspect* 모듈), 1273
- `isCallable()` (*operator* 모듈), 284
- `ischr()` (*tarfile.TarInfo* 메서드), 379
- `isclass()` (*inspect* 모듈), 1273
- `isctrl()` (*curses.ascii* 모듈), 568
- `iscode()` (*inspect* 모듈), 1273
- `iscomment()` (*rfc822.Message* 메서드), 829
- `isctrl()` (*curses.ascii* 모듈), 568
- `isDaemon()` (*threading.Thread* 메서드), 625
- `isdatadescriptor()` (*inspect* 모듈), 1274
- `isdecimal()` (*unicode* 메서드), 45
- `isdev()` (*tarfile.TarInfo* 메서드), 379
- `isdigit()` (*curses.ascii* 모듈), 568
- `isdigit()` (*str* 메서드), 41
- `isdir()` (*os.path* 모듈), 291
- `isdir()` (*tarfile.TarInfo* 메서드), 378
- `isdisjoint()` (*frozenset* 메서드), 50
- `isdown()` (*turtle* 모듈), 1110
- `iselement()` (*xml.etree.ElementTree* 모듈), 855
- `isenabled()` (*gc* 모듈), 1269
- `isEnabledFor()` (*logging.Logger* 메서드), 518
- `isendwin()` (*curses* 모듈), 551
- `ISEOF()` (*token* 모듈), 1321
- `isexpr()` (*parser* 모듈), 1311
- `isexpr()` (*parser.ST* 메서드), 1312
- `isfifo()` (*tarfile.TarInfo* 메서드), 379
- `isfile()` (*os.path* 모듈), 291
- `isfile()` (*tarfile.TarInfo* 메서드), 378
- `isfirstline()` (*fileinput* 모듈), 294
- `isframe()` (*inspect* 모듈), 1273
- `isfunction()` (*inspect* 모듈), 1273
- `isgenerator()` (*inspect* 모듈), 1273
- `isgeneratorfunction()` (*inspect* 모듈), 1273
- `isgetsetdescriptor()` (*inspect* 모듈), 1274
- `isgraph()` (*curses.ascii* 모듈), 568
- `isheader()` (*rfc822.Message* 메서드), 828
- `isinf()` (*cmath* 모듈), 231
- `isinf()` (*math* 모듈), 225
- `isinstance(2to3 fixer)`, 1193
- `isinstance()` (내장 함수), 13
- `iskeyword()` (*keyword* 모듈), 1323
- `islast()` (*rfc822.Message* 메서드), 828
- `isleap()` (*calendar* 모듈), 170
- `islice()` (*itertools* 모듈), 269
- `islink()` (*os.path* 모듈), 291
- `islnk()` (*tarfile.TarInfo* 메서드), 378
- `islower()` (*curses.ascii* 모듈), 568
- `islower()` (*str* 메서드), 41
- `isMappingType()` (*operator* 모듈), 284
- `ismemberdescriptor()` (*inspect* 모듈), 1274
- `ismeta()` (*curses.ascii* 모듈), 568
- `ismethod()` (*inspect* 모듈), 1273
- `ismethoddescriptor()` (*inspect* 모듈), 1273
- `ismodule()` (*inspect* 모듈), 1273
- `ismount()` (*os.path* 모듈), 291
- `isnan()` (*cmath* 모듈), 231
- `isnan()` (*math* 모듈), 225
- `ISNONTERMINAL()` (*token* 모듈), 1321
- `isNumberType()` (*operator* 모듈), 285
- `isnumeric()` (*unicode* 메서드), 45
- `isocalendar()` (*datetime.date* 메서드), 149
- `isocalendar()` (*datetime.datetime* 메서드), 155
- `isoformat()` (*datetime.date* 메서드), 149
- `isoformat()` (*datetime.datetime* 메서드), 155
- `isoformat()` (*datetime.time* 메서드), 158
- `isolation_level` (*sqlite3.Connection*의 속성), 341
- `isowekday()` (*datetime.date* 메서드), 149
- `isowekday()` (*datetime.datetime* 메서드), 154
- `isprint()` (*curses.ascii* 모듈), 568
- `ispunct()` (*curses.ascii* 모듈), 568
- `isqueued()` (*fl* 모듈), 1422
- `isreadable()` (*pprint* 모듈), 216
- `isreadable()` (*pprint.PrettyPrinter* 메서드), 217
- `isrecursive()` (*pprint* 모듈), 216
- `isrecursive()` (*pprint.PrettyPrinter* 메서드), 217
- `isreg()` (*tarfile.TarInfo* 메서드), 378
- `isReservedKey()` (*Cookie.Morsel* 메서드), 1000
- `isroutine()` (*inspect* 모듈), 1273
- `isSameNode()` (*xml.dom.Node* 메서드), 866
- `isSequenceType()` (*operator* 모듈), 285
- `isSet()` (*threading.Event* 메서드), 629
- `isspace()` (*curses.ascii* 모듈), 568
- `isspace()` (*str* 메서드), 41

isstdin() (*fileinput* 모듈), 294
 issubclass() (내장 함수), 13
 issubset() (*frozenset* 메서드), 50
 issuite() (*parser* 모듈), 1311
 issuite() (*parser.ST* 메서드), 1312
 issuperset() (*frozenset* 메서드), 50
 issym() (*tarfile.TarInfo* 메서드), 378
 ISTERMINAL() (*token* 모듈), 1321
 istitle() (*str* 메서드), 41
 istraceback() (*inspect* 모듈), 1273
 isub() (*operator* 모듈), 284
 isupper() (*curses.ascii* 모듈), 568
 isupper() (*str* 메서드), 41
 isvisible() (*turtle* 모듈), 1113
 isxdigit() (*curses.ascii* 모듈), 568
 item() (*tk.Treeview* 메서드), 1088
 item() (*xml.dom.NamedNodeMap* 메서드), 869
 item() (*xml.dom.NodeList* 메서드), 866
 itemgetter() (*operator* 모듈), 285
 items() (*ConfigParser.ConfigParser* 메서드), 395
 items() (*ConfigParser.RawConfigParser* 메서드), 394
 items() (*dict* 메서드), 54
 items() (*email.message.Message* 메서드), 760
 items() (*mailbox.Mailbox* 메서드), 799
 items() (*xml.etree.ElementTree.Element* 메서드), 857
 itemsize(*array.array*의 속성), 194
 itemsize(*memoryview*의 속성), 61
 ItemsView(*collections* 클래스), 186
 iter() (내장 함수), 13
 iter() (*xml.etree.ElementTree.Element* 메서드), 858
 iter() (*xml.etree.ElementTree.ElementTree* 메서드), 859
 iter_child_nodes() (*ast* 모듈), 1318
 iter_fields() (*ast* 모듈), 1317
 iter_importers() (*pkgutil* 모듈), 1303
 iter_modules() (*pkgutil* 모듈), 1303
 Iterable(*collections* 클래스), 185
 iterable(이터러블), 1443
 IterableUserDict(*UserDict* 클래스), 209
 Iterator(*collections* 클래스), 185
 iterator(이터레이터), 1443
 iterator protocol, 37
 iterdecode() (*codecs* 모듈), 126
 iterdump(*sqlite3.Connection*의 속성), 346
 iterencode() (*codecs* 모듈), 126
 iterencode() (*json.JSONEncoder* 메서드), 794
 iterfind() (*xml.etree.ElementTree.Element* 메서드), 858
 iterfind() (*xml.etree.ElementTree.ElementTree* 메서드), 859
 iteritems() (*dict* 메서드), 54
 iteritems() (*mailbox.Mailbox* 메서드), 799
 iterkeyrefs() (*weakref.WeakKeyDictionary* 메서드), 206

iterkeys() (*dict* 메서드), 54
 iterkeys() (*mailbox.Mailbox* 메서드), 799
 itermonthdates() (*calendar.Calendar* 메서드), 169
 itermonthdays() (*calendar.Calendar* 메서드), 169
 itermonthdays2() (*calendar.Calendar* 메서드), 169
 iterparse() (*xml.etree.ElementTree* 모듈), 856
 itertext() (*xml.etree.ElementTree.Element* 메서드), 858
 itertools(*2to3 fixer*), 1193
 itertools(모듈), 263
 itertools_imports(*2to3 fixer*), 1193
 intervaluerefs() (*weakref.WeakValueDictionary* 메서드), 206
 intervals() (*dict* 메서드), 54
 intervals() (*mailbox.Mailbox* 메서드), 799
 iterweekdays() (*calendar.Calendar* 메서드), 168
 ITIMER_PROF(*signal* 모듈), 745
 ITIMER_REAL(*signal* 모듈), 745
 ITIMER_VIRTUAL(*signal* 모듈), 745
 ItimerError, 745
 itruediv() (*operator* 모듈), 284
 ixor() (*operator* 모듈), 284
 izip() (*itertools* 모듈), 270
 izip_longest() (*itertools* 모듈), 270

J

Jansen, Jack, 836
 java_ver() (*platform* 모듈), 572
 JFIF, 1430
 join() (*multiprocessing.JoinableQueue* 메서드), 643
 join() (*multiprocessing.pool.multiprocessing.Pool* 메서드), 658
 join() (*multiprocessing.Process* 메서드), 639
 join() (*os.path* 모듈), 291
 join() (*Queue.Queue* 메서드), 203
 join() (*str* 메서드), 41
 join() (*string* 모듈), 87
 join() (*threading.Thread* 메서드), 624
 join_thread() (*multiprocessing.Queue* 메서드), 642
 JoinableQueue(*multiprocessing* 클래스), 643
 joinfields() (*string* 모듈), 87
 jpeg(모듈), 1430
 js_output() (*Cookie.BaseCookie* 메서드), 999
 js_output() (*Cookie.Morsel* 메서드), 1000
 json(모듈), 788
 JSONDecoder(*json* 클래스), 792
 JSONEncoder(*json* 클래스), 793
 JUMP_ABSOLUTE(*opcode*), 1336
 JUMP_FORWARD(*opcode*), 1336
 JUMP_IF_FALSE_OR_POP(*opcode*), 1336
 JUMP_IF_TRUE_OR_POP(*opcode*), 1336
 jumpahead() (*random* 모듈), 260

K

kbhit() (*msvcrt* 모듈), 1360
 KDEDIR, 901
 kevent() (*select* 모듈), 615
 key (*Cookie.Morsel*의 속성), 1000
 key function (키 함수), 1443
 KEY_ALL_ACCESS (*_winreg* 모듈), 1366
 KEY_CREATE_LINK (*_winreg* 모듈), 1367
 KEY_CREATE_SUB_KEY (*_winreg* 모듈), 1366
 KEY_ENUMERATE_SUB_KEYS (*_winreg* 모듈), 1367
 KEY_EXECUTE (*_winreg* 모듈), 1366
 KEY_NOTIFY (*_winreg* 모듈), 1367
 KEY_QUERY_VALUE (*_winreg* 모듈), 1366
 KEY_READ (*_winreg* 모듈), 1366
 KEY_SET_VALUE (*_winreg* 모듈), 1366
 KEY_WOW64_32KEY (*_winreg* 모듈), 1367
 KEY_WOW64_64KEY (*_winreg* 모듈), 1367
 KEY_WRITE (*_winreg* 모듈), 1366
 KeyboardInterrupt, 69
 KeyError, 69
 keyname() (*curses* 모듈), 551
 keypad() (*curses.window* 메서드), 558
 keyrefs() (*weakref.WeakKeyDictionary* 메서드), 206
 keys() (*bsddb.bsddbobject* 메서드), 335
 keys() (*dict* 메서드), 54
 keys() (*email.message.Message* 메서드), 760
 keys() (*mailbox.Mailbox* 메서드), 799
 keys() (*sqlite3.Row* 메서드), 350
 keys() (*xml.etree.ElementTree.Element* 메서드), 857
 keysubst() (*aetools* 모듈), 1409
 KeysView (*collections* 클래스), 186
 Keyword (*aetypes* 클래스), 1411
 keyword (모듈), 1323
 keyword argument (키워드 인자), 1444
 keywords (*functools.partial*의 속성), 279
 kill() (*os* 모듈), 434
 kill() (*subprocess.Popen* 메서드), 702
 killchar() (*curses* 모듈), 552
 killpg() (*os* 모듈), 434
 knee
 모듈, 1296, 1300
 knownfiles (*mimetypes* 모듈), 821
 kqueue() (*select* 모듈), 615
 kwlist (*keyword* 모듈), 1323

L

-l
 compileall command line option, 1328
 trace command line option, 1227
 L (*re* 모듈), 93
 -l <zipfile>
 zipfile command line option, 372
 label() (*EasyDialogs.ProgressBar* 메서드), 1397
 LabelEntry (*Tix* 클래스), 1094

LabelFrame (*Tix* 클래스), 1094
 lambda (람다), 1444
 LambdaType (*types* 모듈), 212
 LANG, 1037, 1039, 1047, 1050
 LANGUAGE, 1037, 1039
 language
 C, 33
 large files, 1371
 LargeZipFile, 366
 last (*multifile.MultiFile*의 속성), 826
 last() (*bsddb.bsddbobject* 메서드), 336
 last() (*dbhash.dbhash* 메서드), 334
 last() (*nntplib.NNTP* 메서드), 958
 last_accepted (*multiprocessing.connection.Listener*의 속성), 660
 last_traceback (*sys* 모듈), 1242
 last_type (*sys* 모듈), 1242
 last_value (*sys* 모듈), 1242
 lastChild (*xml.dom.Node*의 속성), 865
 lastcmd (*cmd.Cmd*의 속성), 1057
 lastgroup (*re.MatchObject*의 속성), 100
 lastindex (*re.MatchObject*의 속성), 100
 lastpart() (*MimeWriter.MimeWriter* 메서드), 823
 lastrowid (*sqlite3.Cursor*의 속성), 349
 launch() (*findertools* 모듈), 1395
 launchurl() (*ic* 모듈), 1392
 launchurl() (*ic.IC* 메서드), 1392
 layout() (*tk.Style* 메서드), 1091
 LBRACE (*token* 모듈), 1321
 LBYL, 1444
 LC_ALL, 1037, 1039
 LC_ALL (*locale* 모듈), 1052
 LC_COLLATE (*locale* 모듈), 1051
 LC_CTYPE (*locale* 모듈), 1051
 LC_MESSAGES, 1037, 1039
 LC_MESSAGES (*locale* 모듈), 1052
 LC_MONETARY (*locale* 모듈), 1052
 LC_NUMERIC (*locale* 모듈), 1052
 LC_TIME (*locale* 모듈), 1052
 lchflags() (*os* 모듈), 424
 lchmod() (*os* 모듈), 424
 lchown() (*os* 모듈), 424
 ldexp() (*math* 모듈), 226
 ldgettext() (*gettext* 모듈), 1038
 ldnggettext() (*gettext* 모듈), 1038
 le() (*operator* 모듈), 280
 leapdays() (*calendar* 모듈), 170
 leaveok() (*curses.window* 메서드), 558
 left (*filecmp.dircmp*의 속성), 301
 left() (*turtle* 모듈), 1103
 left_list (*filecmp.dircmp*의 속성), 301
 left_only (*filecmp.dircmp*의 속성), 301
 LEFTSHIFT (*token* 모듈), 1321
 LEFTSHIFTEQUAL (*token* 모듈), 1321

- len
 - 내장 함수, 38, 52
- len() (내장 함수), 13
- length (*xml.dom.NamedNodeMap*의 속성), 869
- length (*xml.dom.NodeList*의 속성), 866
- LESS (*token* 모듈), 1321
- LESSEQUAL (*token* 모듈), 1321
- letters (*string* 모듈), 76
- level (*multifile.MultiFile*의 속성), 826
- lexists() (*os.path* 모듈), 290
- lgamma() (*math* 모듈), 228
- lgettext() (*gettext* 모듈), 1038
- lgettext() (*gettext.GNUTranslations* 메서드), 1042
- lgettext() (*gettext.NullTranslations* 메서드), 1040
- lib2to3 (모듈), 1195
- libc_ver() (*platform* 모듈), 573
- library (*dbm* 모듈), 331
- library (*ssl.SSLError*의 속성), 720
- LibraryLoader (*ctypes* 클래스), 601
- license (내장 변수), 30
- LifoQueue (*Queue* 클래스), 202
- light-weight processes, 630
- limit_denominator() (*fractions.Fraction* 메서드), 259
- lin2adpcm() (*audioop* 모듈), 1018
- lin2alaw() (*audioop* 모듈), 1018
- lin2lin() (*audioop* 모듈), 1018
- lin2ulaw() (*audioop* 모듈), 1019
- line() (*msilib.Dialog* 메서드), 1358
- line_buffering (*io.TextIOWrapper*의 속성), 450
- line_num (*csv.csvreader*의 속성), 388
- line-buffered I/O, 15
- linecache (모듈), 307
- lineno (*ast.AST*의 속성), 1314
- lineno (*doctest.DocTest*의 속성), 1157
- lineno (*doctest.Example*의 속성), 1157
- lineno (*pyclbr.Class*의 속성), 1326
- lineno (*pyclbr.Function*의 속성), 1327
- lineno (*shlex.shlex*의 속성), 1060
- lineno (*xml.parsers.expat.ExpatError*의 속성), 895
- lineno() (*fileinput* 모듈), 294
- LINES, 550, 554
- linesep (*os* 모듈), 440
- lineterminator (*csv.Dialect*의 속성), 387
- link() (*os* 모듈), 424
- linkmodel (*MacOS* 모듈), 1393
- linkname (*tarfile.TarInfo*의 속성), 378
- linux_distribution() (*platform* 모듈), 573
- list
 - type, operations on, 48
 - 객체, 37, 48
- list (리스트), 1444
- list comprehension (리스트 컴프리헨션), 1444
- list() (*imaplib.IMAP4* 메서드), 952
- list() (*multiprocessing.managers.SyncManager* 메서드), 653
- list() (*nntplib.NNTP* 메서드), 957
- list() (*poplib.POP3* 메서드), 949
- list() (*tarfile.TarFile* 메서드), 376
- LIST_APPEND (*opcode*), 1334
- list_dialects() (*csv* 모듈), 385
- list_folders() (*mailbox.Maildir* 메서드), 801
- list_folders() (*mailbox.MH* 메서드), 803
- listallfolders() (*mhlib.MH* 메서드), 817
- listallsubfolders() (*mhlib.MH* 메서드), 817
- listdir() (*dircache* 모듈), 312
- listdir() (*os* 모듈), 424
- listen() (*asyncore.dispatcher* 메서드), 751
- listen() (*logging.config* 모듈), 531
- listen() (*socket.socket* 메서드), 714
- listen() (*turtle* 모듈), 1121
- Listener (*multiprocessing.connection* 클래스), 659
- listfolders() (*mhlib.MH* 메서드), 817
- listfuncs
 - trace command line option, 1227
- listmessages() (*mhlib.Folder* 메서드), 818
- listMethods() (*xmlrpclib.ServerProxy.system* 메서드), 1004
- ListNoteBook (*Tix* 클래스), 1096
- listsubfolders() (*mhlib.MH* 메서드), 817
- ListType (*types* 모듈), 212
- literal_eval() (*ast* 모듈), 1317
- literals
 - complex number, 33
 - floating point, 33
 - hexadecimal, 33
 - integer, 33
 - long integer, 33
 - numeric, 33
 - octal, 33
- LittleEndianStructure (*ctypes* 클래스), 611
- ljust() (*str* 메서드), 41
- ljust() (*string* 모듈), 87
- LK_LOCK (*msvcrt* 모듈), 1359
- LK_NBLCK (*msvcrt* 모듈), 1359
- LK_NBRLCK (*msvcrt* 모듈), 1359
- LK_RLCK (*msvcrt* 모듈), 1359
- LK_UNLCK (*msvcrt* 모듈), 1359
- LMTP (*smtpplib* 클래스), 960
- ln() (*decimal.Context* 메서드), 247
- ln() (*decimal.Decimal* 메서드), 240
- LNAME, 548
- lnggettext() (*gettext* 모듈), 1038
- lnggettext() (*gettext.GNUTranslations* 메서드), 1042
- lnggettext() (*gettext.NullTranslations* 메서드), 1040
- load() (*Cookie.BaseCookie* 메서드), 999
- load() (*cookielib.FileCookieJar* 메서드), 992
- load() (*hotshot.stats* 모듈), 1221

- `load()` (*json* 모듈), 791
- `load()` (*marshal* 모듈), 328
- `load()` (*pickle* 모듈), 315
- `load()` (*pickle.Unpickler* 메서드), 317
- `LOAD_ATTR` (*opcode*), 1335
- `load_cert_chain()` (*ssl.SSLContext* 메서드), 733
- `LOAD_CLOSURE` (*opcode*), 1336
- `load_compiled()` (*imp* 모듈), 1295
- `LOAD_CONST` (*opcode*), 1335
- `load_default_certs()` (*ssl.SSLContext* 메서드), 733
- `LOAD_DEREF` (*opcode*), 1337
- `load_dh_params()` (*ssl.SSLContext* 메서드), 735
- `load_dynamic()` (*imp* 모듈), 1295
- `load_extension()` (*sqlite3.Connection* 메서드), 344
- `LOAD_FAST` (*opcode*), 1336
- `LOAD_GLOBAL` (*opcode*), 1336
- `load_global()` (*pickle protocol*), 321
- `LOAD_LOCALS` (*opcode*), 1334
- `load_module()` (*imp* 모듈), 1294
- `load_module()` (*zipimport.zipimporter* 메서드), 1301
- `LOAD_NAME` (*opcode*), 1335
- `load_source()` (*imp* 모듈), 1296
- `load_verify_locations()` (*ssl.SSLContext* 메서드), 733
- `loader` (로더), 1444
- `LoadError`, 989
- `LoadKey()` (*_winreg* 모듈), 1363
- `LoadLibrary()` (*ctypes.LibraryLoader* 메서드), 601
- `loads()` (*json* 모듈), 792
- `loads()` (*marshal* 모듈), 329
- `loads()` (*pickle* 모듈), 315
- `loads()` (*xmlrpclib* 모듈), 1009
- `loadTestsFromModule()` (*unittest.TestLoader* 메서드), 1182
- `loadTestsFromName()` (*unittest.TestLoader* 메서드), 1182
- `loadTestsFromNames()` (*unittest.TestLoader* 메서드), 1183
- `loadTestsFromTestCase()` (*unittest.TestLoader* 메서드), 1182
- `local` (*threading* 클래스), 621
- `localcontext()` (*decimal* 모듈), 243
- `LOCALE` (*re* 모듈), 93
- `locale` (모듈), 1047
- `localeconv()` (*locale* 모듈), 1047
- `LocaleHTMLCalendar` (*calendar* 클래스), 170
- `LocaleTextCalendar` (*calendar* 클래스), 170
- `localName` (*xml.dom.Attr*의 속성), 869
- `localName` (*xml.dom.Node*의 속성), 865
- `locals()` (내장 함수), 13
- `localtime()` (*time* 모듈), 453
- `Locator` (*xml.sax.xmlreader* 클래스), 886
- `Lock` (*multiprocessing* 클래스), 646
- `lock()` (*mailbox.Babyl* 메서드), 804
- `lock()` (*mailbox.Mailbox* 메서드), 800
- `lock()` (*mailbox.Maildir* 메서드), 801
- `lock()` (*mailbox.mbox* 메서드), 802
- `lock()` (*mailbox.MH* 메서드), 803
- `lock()` (*mailbox.MMDF* 메서드), 805
- `Lock()` (*multiprocessing.managers.SyncManager* 메서드), 652
- `lock()` (*mutex.mutex* 메서드), 201
- `lock()` (*posixfile.posixfile* 메서드), 1382
- `Lock()` (*threading* 모듈), 621
- `lock_held()` (*imp* 모듈), 1294
- `locked()` (*threading.Lock* 메서드), 625
- `locked()` (*thread.lock* 메서드), 631
- `lockf()` (*fcntl* 모듈), 1379
- `locking()` (*msvcrt* 모듈), 1359
- `LockType` (*thread* 모듈), 631
- `log()` (*cmath* 모듈), 230
- `log()` (*logging* 모듈), 527
- `log()` (*logging.Logger* 메서드), 519
- `log()` (*math* 모듈), 226
- `log1p()` (*math* 모듈), 226
- `log10()` (*cmath* 모듈), 230
- `log10()` (*decimal.Context* 메서드), 247
- `log10()` (*decimal.Decimal* 메서드), 240
- `log10()` (*math* 모듈), 226
- `log_date_time_string()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 986
- `log_error()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 986
- `log_exception()` (*wsgiref.handlers.BaseHandler* 메서드), 916
- `log_message()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 986
- `log_request()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 986
- `log_to_stderr()` (*multiprocessing* 모듈), 662
- `logb()` (*decimal.Context* 메서드), 247
- `logb()` (*decimal.Decimal* 메서드), 240
- `Logger` (*logging* 클래스), 518
- `LoggerAdapter` (*logging* 클래스), 526
- `logging`
 - `Errors`, 517
- `logging` (모듈), 517
- `logging.config` (모듈), 529
- `logging.handlers` (모듈), 539
- `Logical` (*aetypes* 클래스), 1412
- `logical_and()` (*decimal.Context* 메서드), 247
- `logical_and()` (*decimal.Decimal* 메서드), 240
- `logical_invert()` (*decimal.Context* 메서드), 247
- `logical_invert()` (*decimal.Decimal* 메서드), 240

logical_or() (*decimal.Context* 메서드), 247
 logical_or() (*decimal.Decimal* 메서드), 240
 logical_xor() (*decimal.Context* 메서드), 247
 logical_xor() (*decimal.Decimal* 메서드), 240
 login() (*ftplib.FTP* 메서드), 945
 login() (*imaplib.IMAP4* 메서드), 952
 login() (*smtplib.SMTP* 메서드), 962
 login_cram_md5() (*imaplib.IMAP4* 메서드), 953
 LOGNAME, 413, 548
 lognormvariate() (*random* 모듈), 262
 logout() (*imaplib.IMAP4* 메서드), 953
 LogRecord (*logging* 클래스), 523
 long
 integer division, 34
 integer literals, 33
 내장 함수, 33, 86
 long (2to3 fixer), 1193
 long (내장 클래스), 14
 long integer
 객체, 33
 long_info (sys 모듈), 1242
 longMessage (*unittest.TestCase*의 속성), 1180
 longname() (*curses* 모듈), 552
 LongType (*types* 모듈), 211
 lookup() (*codecs* 모듈), 124
 lookup() (*syntable.SymbolTable* 메서드), 1319
 lookup() (*tk.Style* 메서드), 1091
 lookup() (*unicodedata* 모듈), 138
 lookup_error() (*codecs* 모듈), 125
 LookupError, 68
 loop() (*asyncore* 모듈), 749
 lower() (*str* 메서드), 41
 lower() (*string* 모듈), 86
 lowercase (*string* 모듈), 76
 LPAR (*token* 모듈), 1321
 lseek() (*os* 모듈), 419
 lshift() (*operator* 모듈), 281
 LSQB (*token* 모듈), 1321
 lstat() (*os* 모듈), 424
 lstrip() (*str* 메서드), 42
 lstrip() (*string* 모듈), 87
 lsub() (*imaplib.IMAP4* 메서드), 953
 lt() (*operator* 모듈), 280
 lt() (*turtle* 모듈), 1103
 Lundh, Fredrik, 1430
 LWPCookieJar (*cookielib* 클래스), 993

M

-m
 trace command line option, 1227
 M (*re* 모듈), 93
 mac_ver() (*platform* 모듈), 573
 macerrors
 모듈, 1393

macerrors (모듈), 1436
 machine() (*platform* 모듈), 571
 MacOS (모듈), 1393
 macostools (모듈), 1394
 macpath (모듈), 312
 macresource (모듈), 1437
 macros (*netrc.netrc*의 속성), 399
 magic
 method, 1444
 magic method, 1444
 mailbox
 모듈, 827
 Mailbox (*mailbox* 클래스), 798
 mailbox (모듈), 797
 mailcap (모듈), 796
 Maildir (*mailbox* 클래스), 800
 MaildirMessage (*mailbox* 클래스), 806
 MailmanProxy (*smtplib* 클래스), 965
 main() (*py_compile* 모듈), 1327
 main() (*unittest* 모듈), 1186
 mainloop() (*FrameWork.Application* 메서드), 1399
 mainloop() (*turtle* 모듈), 1116
 major() (*os* 모듈), 425
 make_archive() (*shutil* 모듈), 310
 MAKE_CLOSURE (*opcode*), 1337
 make_cookies() (*cookielib.CookieJar* 메서드), 991
 make_form() (*fl* 모듈), 1421
 MAKE_FUNCTION (*opcode*), 1337
 make_header() (*email.header* 모듈), 772
 make_msgid() (*email.utils* 모듈), 778
 make_parser() (*xml.sax* 모듈), 879
 make_server() (*wsgiref.simple_server* 모듈), 913
 makedev() (*os* 모듈), 425
 makedirs() (*os* 모듈), 425
 makeelement() (*xml.etree.ElementTree.Element* 메서드), 858
 makefile() (*socket.socket* 메서드), 714
 makefolder() (*mhlib.MH* 메서드), 817
 makeLogRecord() (*logging* 모듈), 528
 makePickle() (*logging.handlers.SocketHandler* 메서드), 543
 makeRecord() (*logging.Logger* 메서드), 520
 makeSocket() (*logging.handlers.DatagramHandler* 메서드), 544
 makeSocket() (*logging.handlers.SocketHandler* 메서드), 543
 maketrans() (*string* 모듈), 85
 makeusermenus() (*FrameWork.Application* 메서드), 1399
 map (2to3 fixer), 1193
 map() (*future_builtins* 모듈), 1252
 map() (*multiprocessing.pool.multiprocessing.Pool* 메서드), 657
 map() (*tk.Style* 메서드), 1090

- ul style="list-style-type: none; padding-left: 0;">
- map () (내장 함수), 14
- map_async () (multiprocessing.pool multiprocessing.Pool 메서드), 657
- map_table_b2 () (stringprep 모듈), 140
- map_table_b3 () (stringprep 모듈), 140
- mapcolor () (fl 모듈), 1422
- mapfile () (ic 모듈), 1392
- mapfile () (ic.IC 메서드), 1392
- mapLogRecord () (logging.handlers.HTTPHandler 메서드), 547
- mapping
 - types, operations on, 52
 - 객체, 52
- Mapping (collections 클래스), 185
- mapping (매핑), 1444
- mapping () (msilib.Control 메서드), 1358
- MappingView (collections 클래스), 186
- mapPriority () (logging.handlers.SysLogHandler 메서드), 545
- maps () (nis 모듈), 1387
- maptypecreator () (ic 모듈), 1392
- maptypecreator () (ic.IC 메서드), 1392
- marshal (모듈), 328
- marshalling
 - objects, 313
- masking
 - operations, 35
- match () (nis 모듈), 1386
- match () (re 모듈), 94
- match () (re.RegexObject 메서드), 97
- match_hostname () (ssl 모듈), 724
- MatchObject (re 클래스), 98
- math
 - 모듈, 34, 231
- math (모듈), 224
- max
 - 내장 함수, 38
- max (datetime.datetime의 속성), 152
- max (datetime.date의 속성), 147
- max (datetime.timedelta의 속성), 145
- max (datetime.time의 속성), 157
- max () (audioop 모듈), 1019
- max () (decimal.Context 메서드), 247
- max () (decimal.Decimal 메서드), 240
- max () (내장 함수), 14
- MAX_INTERPOLATION_DEPTH (ConfigParser 모듈), 393
- max_mag () (decimal.Context 메서드), 247
- max_mag () (decimal.Decimal 메서드), 240
- maxarray (repr.Repr의 속성), 219
- maxdeque (repr.Repr의 속성), 219
- maxdict (repr.Repr의 속성), 219
- maxDiff (unittest.TestCase의 속성), 1180
- maxfrozenset (repr.Repr의 속성), 219
- maxint (sys 모듈), 1242
- maxlen (collections.deque의 속성), 176
- MAXLEN (mimify 모듈), 824
- maxlevel (repr.Repr의 속성), 219
- maxlist (repr.Repr의 속성), 219
- maxlong (repr.Repr의 속성), 219
- maxother (repr.Repr의 속성), 219
- maxpp () (audioop 모듈), 1019
- maxset (repr.Repr의 속성), 219
- maxsize (sys 모듈), 1242
- maxstring (repr.Repr의 속성), 219
- maxtuple (repr.Repr의 속성), 219
- maxunicode (sys 모듈), 1242
- maxval (EasyDialogs.ProgressBar의 속성), 1397
- MAXYEAR (datetime 모듈), 144
- MB_ICONASTERISK (winsound 모듈), 1370
- MB_ICONEXCLAMATION (winsound 모듈), 1370
- MB_ICONHAND (winsound 모듈), 1370
- MB_ICONQUESTION (winsound 모듈), 1370
- MB_OK (winsound 모듈), 1370
- mbox (mailbox 클래스), 802
- mboxMessage (mailbox 클래스), 808
- md5 (모듈), 409
- md5 () (md5 모듈), 409
- MemberDescriptorType (types 모듈), 213
- memmove () (ctypes 모듈), 606
- MemoryError, 69
- MemoryHandler (logging.handlers 클래스), 547
- memoryview (내장 클래스), 60
- memset () (ctypes 모듈), 606
- Menu () (FrameWork 모듈), 1398
- MenuBar () (FrameWork 모듈), 1398
- MenuItem () (FrameWork 모듈), 1398
- merge () (heapq 모듈), 187
- Message (email.message 클래스), 758
- Message (in module mimetools), 985
- Message (mailbox 클래스), 805
- Message (mhtml 클래스), 817
- Message (mimetools 클래스), 819
- Message (rfc822 클래스), 827
- message digest, MD5, 405, 409
- Message () (EasyDialogs 모듈), 1396
- message_from_file () (email 모듈), 766
- message_from_string () (email 모듈), 766
- MessageBeep () (winsound 모듈), 1369
- MessageClass (BaseHTTPServer.BaseHTTPRequestHandler의 속성), 985
- MessageError, 776
- MessageParseError, 776
- meta () (curses 모듈), 552
- meta_path (sys 모듈), 1242
- metaclass (2to3 fixer), 1193
- metaclass (메타클래스), 1444

- metavar (*optparse.Option*의 속성), 502
- Meter (*Tix* 클래스), 1095
- method
 - magic, 1444
 - special, 1446
 - 객체, 63
- method (메서드), 1444
- method resolution order (메서드 결정 순서), 1444
- methodattrs (*2to3 fixer*), 1193
- methodcaller() (*operator* 모듈), 286
- methodHelp() (*xmlrpclib.ServerProxy.system* 메서드), 1004
- methods
 - string, 39
- methods (*pyclbr.Class*의 속성), 1326
- methodSignature() (*xmlrpclib.ServerProxy.system* 메서드), 1004
- MethodType (*types* 모듈), 212
- MH (*mailbox* 클래스), 803
- MH (*mhlib* 클래스), 817
- mhlib (모듈), 817
- MHMailbox (*mailbox* 클래스), 815
- MHMessage (*mailbox* 클래스), 809
- microsecond (*datetime.datetime*의 속성), 152
- microsecond (*datetime.time*의 속성), 158
- MIME
 - base64 encoding, 831
 - content type, 820
 - headers, 820, 902
 - quoted-printable encoding, 835
- mime_decode_header() (*mimify* 모듈), 824
- mime_encode_header() (*mimify* 모듈), 824
- MIMEApplication (*email.mime.application* 클래스), 769
- MIMEAudio (*email.mime.audio* 클래스), 769
- MIMEBase (*email.mime.base* 클래스), 768
- MIMEImage (*email.mime.image* 클래스), 769
- MIMEMessage (*email.mime.message* 클래스), 770
- MIMEMultipart (*email.mime.multipart* 클래스), 769
- MIMENonMultipart (*email.mime.nonmultipart* 클래스), 768
- MIMEText (*email.mime.text* 클래스), 770
- mimetools
 - 모듈, 919
- mimetools (모듈), 819
- MimeTypes (*mimetypes* 클래스), 822
- mimetypes (모듈), 820
- MimeWriter (*MimeWriter* 클래스), 823
- MimeWriter (모듈), 823
- mimify (모듈), 824
- mimify() (*mimify* 모듈), 824
- min
 - 내장 함수, 38
- min (*datetime.datetime*의 속성), 152
- min (*datetime.date*의 속성), 147
- min (*datetime.timedelta*의 속성), 145
- min (*datetime.time*의 속성), 157
- min() (*decimal.Context* 메서드), 247
- min() (*decimal.Decimal* 메서드), 240
- min() (내장 함수), 14
- min_mag() (*decimal.Context* 메서드), 247
- min_mag() (*decimal.Decimal* 메서드), 240
- MINEQUAL (*token* 모듈), 1321
- MiniAEFrame (모듈), 1412
- MiniApplication (*MiniAEFrame* 클래스), 1412
- minmax() (*audioop* 모듈), 1019
- minor() (*os* 모듈), 425
- MINUS (*token* 모듈), 1321
- minus() (*decimal.Context* 메서드), 248
- minute (*datetime.datetime*의 속성), 152
- minute (*datetime.time*의 속성), 158
- MINYEAR (*datetime* 모듈), 144
- mirrored() (*unicodedata* 모듈), 138
- misc_header (*cmd.Cmd*의 속성), 1057
- missing
 - trace command line option, 1227
- MissingSectionHeaderError, 393
- MIXERDEV, 1032
- mkalias() (*macostools* 모듈), 1394
- mkd() (*ftplib.FTP* 메서드), 947
- mkdir() (*os* 모듈), 425
- mkdtemp() (*tempfile* 모듈), 303
- mkfifo() (*os* 모듈), 424
- mknod() (*os* 모듈), 425
- mkstemp() (*tempfile* 모듈), 303
- mktemp() (*tempfile* 모듈), 303
- mktime() (*time* 모듈), 453
- mktime_tz() (*email.utils* 모듈), 777
- mktime_tz() (*rfc822* 모듈), 828
- mmap (*mmap* 클래스), 686
- mmap (모듈), 686
- MMDF (*mailbox* 클래스), 805
- MmdfMailbox (*mailbox* 클래스), 814
- MMDFMessage (*mailbox* 클래스), 812
- mod() (*operator* 모듈), 281
- mode (*file*의 속성), 59
- mode (*io.FileIO*의 속성), 446
- mode (*ossaudiodev.oss_audio_device*의 속성), 1035
- mode (*tarfile.TarInfo*의 속성), 378
- mode() (*turtle* 모듈), 1122
- modf() (*math* 모듈), 226
- modified() (*robotparser.RobotFileParser* 메서드), 398
- Modify() (*msilib.View* 메서드), 1355
- modify() (*select.epoll* 메서드), 617
- modify() (*select.poll* 메서드), 618
- module
 - search path, 307, 1243, 1277

- module (*pyclbr.Class*의 속성), 1326
 - module (*pyclbr.Function*의 속성), 1326
 - module (모듈), 1444
 - module() (new 모듈), 214
 - ModuleFinder (*modulefinder* 클래스), 1305
 - modulefinder (모듈), 1304
 - modules (*modulefinder.ModuleFinder*의 속성), 1305
 - modules (*sys* 모듈), 1243
 - ModuleType (*types* 모듈), 212
 - mono2grey() (*imageop* 모듈), 1021
 - month (*datetime.datetime*의 속성), 152
 - month (*datetime.date*의 속성), 148
 - month() (*calendar* 모듈), 171
 - month_abbr (*calendar* 모듈), 171
 - month_name (*calendar* 모듈), 171
 - monthcalendar() (*calendar* 모듈), 171
 - monthdatescalendar() (*calendar.Calendar* 메서드), 169
 - monthdays2calendar() (*calendar.Calendar* 메서드), 169
 - monthdayscalendar() (*calendar.Calendar* 메서드), 169
 - monthrange() (*calendar* 모듈), 171
 - Morsel (*Cookie* 클래스), 999
 - most_common() (*collections.Counter* 메서드), 173
 - mouseinterval() (*curses* 모듈), 552
 - mousemask() (*curses* 모듈), 552
 - move() (*curses.panel.Panel* 메서드), 570
 - move() (*curses.window* 메서드), 559
 - move() (*findertools* 모듈), 1395
 - move() (*mmap.mmap* 메서드), 688
 - move() (*shutil* 모듈), 309
 - move() (*tk.Treeview* 메서드), 1088
 - movemessage() (*mhlib.Folder* 메서드), 818
 - MozillaCookieJar (*cookielib* 클래스), 993
 - MRO, 1445
 - mro() (*class* 메서드), 65
 - msftoframe() (*cd* 모듈), 1418
 - msg (*httplib.HTTPResponse*의 속성), 942
 - msg() (*telnetlib.Telnet* 메서드), 966
 - msi, 1353
 - msilib (모듈), 1353
 - msvcrt (모듈), 1359
 - mt_interact() (*telnetlib.Telnet* 메서드), 967
 - mtime (*tarfile.TarInfo*의 속성), 378
 - mtime() (*robotparser.RobotFileParser* 메서드), 398
 - mul() (*audioop* 모듈), 1019
 - mul() (*operator* 모듈), 281
 - MultiCall (*xmlrpclib* 클래스), 1008
 - MultiFile (*multifile* 클래스), 825
 - multifile (모듈), 825
 - MULTILINE (*re* 모듈), 93
 - MultipartConversionError, 776
 - multiply() (*decimal.Context* 메서드), 248
 - multiprocessing (모듈), 633
 - multiprocessing.connection (모듈), 659
 - multiprocessing.dummy (모듈), 663
 - multiprocessing.Manager() (*multiprocessing.sharedctypes* 모듈), 651
 - multiprocessing.managers (모듈), 651
 - multiprocessing.Pool (*multiprocessing.pool* 클래스), 657
 - multiprocessing.pool (모듈), 657
 - multiprocessing.queues.SimpleQueue (*multiprocessing* 클래스), 642
 - multiprocessing.sharedctypes (모듈), 649
 - mutable
 - sequence types, 48
 - mutable (가변), 1445
 - MutableMapping (*collections* 클래스), 185
 - MutableSequence (*collections* 클래스), 185
 - MutableSet (*collections* 클래스), 185
 - MutableString (*UserString* 클래스), 210
 - mutex (*mutex* 클래스), 201
 - mutex (모듈), 201
 - mvderwin() (*curses.window* 메서드), 559
 - mvwin() (*curses.window* 메서드), 559
 - myrights() (*imaplib.IMAP4* 메서드), 953
- ## N
- n N
 - timeit command line option, 1224
 - N_TOKENS (*token* 모듈), 1321
 - name (*cookielib.Cookie*의 속성), 996
 - name (*doctest.DocTest*의 속성), 1156
 - name (*file*의 속성), 59
 - name (*io.FileIO*의 속성), 446
 - name (*multiprocessing.Process*의 속성), 639
 - name (*os* 모듈), 411
 - name (*ossaudiodev.oss_audio_device*의 속성), 1034
 - name (*pyclbr.Class*의 속성), 1326
 - name (*pyclbr.Function*의 속성), 1326
 - name (*tarfile.TarInfo*의 속성), 378
 - name (*threading.Thread*의 속성), 624
 - NAME (*token* 모듈), 1321
 - name (*xml.dom.Attr*의 속성), 869
 - name (*xml.dom.DocumentType*의 속성), 867
 - name() (*unicodedata* 모듈), 138
 - name2codepoint (*htmlentitydefs* 모듈), 847
 - named tuple (네임드 튜플), 1445
 - NamedTemporaryFile() (*tempfile* 모듈), 302
 - namedtuple() (*collections* 모듈), 179
 - NameError, 69
 - namelist() (*zipfile.ZipFile* 메서드), 368
 - nameprep() (*encodings.idna* 모듈), 137
 - Namespace (*argparse* 클래스), 480
 - Namespace (*multiprocessing.managers* 클래스), 653
 - namespace (이름 공간), 1445

- `namespace()` (*imaplib.IMAP4* 메서드), 953
- `Namespace()` (*multiprocessing.managers.SyncManager* 메서드), 652
- `NAMESPACE_DNS` (*uuid* 모듈), 969
- `NAMESPACE_OID` (*uuid* 모듈), 969
- `NAMESPACE_URL` (*uuid* 모듈), 969
- `NAMESPACE_X500` (*uuid* 모듈), 970
- `NamespaceErr`, 871
- `namespaceURI` (*xml.dom.Node*의 속성), 865
- `NaN`, 11, 86
- `NannyNag`, 1325
- `napms()` (*curses* 모듈), 552
- `nargs` (*optparse.Option*의 속성), 501
- `Nav` (모듈), 1437
- `Navigation Services`, 1397
- `ndiff()` (*difflib* 모듈), 111
- `ndim` (*memoryview*의 속성), 61
- `ne` (*2to3 fixer*), 1193
- `ne()` (*operator* 모듈), 280
- `neg()` (*operator* 모듈), 281
- `nested scope` (중첩된 스코프), 1445
- `nested()` (*contextlib* 모듈), 1258
- `netrc` (*netrc* 클래스), 399
- `netrc` (모듈), 399
- `NetrcParseError`, 399
- `netscape` (*cookielib.CookiePolicy*의 속성), 994
- `Network News Transfer Protocol`, 956
- `new` (모듈), 213
- `new()` (*hmac* 모듈), 408
- `new()` (*md5* 모듈), 409
- `new()` (*sha* 모듈), 410
- `new-style class` (뉴스타일 클래스), 1445
- `new_alignment()` (*formatter.writer* 메서드), 1349
- `new_font()` (*formatter.writer* 메서드), 1349
- `new_margin()` (*formatter.writer* 메서드), 1349
- `new_module()` (*imp* 모듈), 1294
- `new_panel()` (*curses.panel* 모듈), 569
- `new_spacing()` (*formatter.writer* 메서드), 1350
- `new_styles()` (*formatter.writer* 메서드), 1350
- `newconfig()` (*al* 모듈), 1415
- `newgroups()` (*nntplib.NNTP* 메서드), 957
- `NEWLINE` (*token* 모듈), 1321
- `newlines` (*file*의 속성), 59
- `newlines` (*io.TextIOBase*의 속성), 448
- `newnews()` (*nntplib.NNTP* 메서드), 957
- `newpad()` (*curses* 모듈), 552
- `newwin()` (*curses* 모듈), 552
- `next` (*2to3 fixer*), 1193
- `next()` (*bsddb.bsddbobject* 메서드), 336
- `next()` (*csv.csvreader* 메서드), 388
- `next()` (*dbhash.dbhash* 메서드), 334
- `next()` (*file* 메서드), 57
- `next()` (*iterator* 메서드), 37
- `next()` (*mailbox.oldmailbox* 메서드), 814
- `next()` (*multifile.MultiFile* 메서드), 825
- `next()` (*nntplib.NNTP* 메서드), 958
- `next()` (*tarfile.TarFile* 메서드), 376
- `next()` (*tk.Treeview* 메서드), 1088
- `next()` (내장 함수), 14
- `next_minus()` (*decimal.Context* 메서드), 248
- `next_minus()` (*decimal.Decimal* 메서드), 241
- `next_plus()` (*decimal.Context* 메서드), 248
- `next_plus()` (*decimal.Decimal* 메서드), 241
- `next_toward()` (*decimal.Context* 메서드), 248
- `next_toward()` (*decimal.Decimal* 메서드), 241
- `nextfile()` (*fileinput* 모듈), 294
- `nextkey()` (*gdbm* 모듈), 332
- `nextpart()` (*MimeWriter.MimeWriter* 메서드), 823
- `nextSibling` (*xml.dom.Node*의 속성), 865
- `ngettext()` (*gettext* 모듈), 1038
- `ngettext()` (*gettext.GNUTranslations* 메서드), 1042
- `ngettext()` (*gettext.NullTranslations* 메서드), 1040
- `nice()` (*os* 모듈), 434
- `nis` (모듈), 1386
- `NIST`, 410
- `NL` (*tokenize* 모듈), 1324
- `nl()` (*curses* 모듈), 552
- `nl_langinfo()` (*locale* 모듈), 1048
- `nlargest()` (*heapq* 모듈), 188
- `nlst()` (*ftplib.FTP* 메서드), 947
- `NNTP`
 - `protocol`, 956
- `NNTP` (*nntplib* 클래스), 956
- `NNTPDataError`, 957
- `NNTPError`, 956
- `nntplib` (모듈), 956
- `NNTPPermanentError`, 957
- `NNTPProtocolError`, 957
- `NNTPReplyError`, 957
- `NNTPTemporaryError`, 957
- `no_proxy`, 919, 920
- `nocbreak()` (*curses* 모듈), 552
- `NoDataAllowedErr`, 871
- `Node` (*compiler.ast* 클래스), 1340
- `node()` (*platform* 모듈), 571
- `nodelay()` (*curses.window* 메서드), 559
- `nodeName` (*xml.dom.Node*의 속성), 865
- `NodeTransformer` (*ast* 클래스), 1318
- `nodeType` (*xml.dom.Node*의 속성), 865
- `nodeValue` (*xml.dom.Node*의 속성), 865
- `NodeVisitor` (*ast* 클래스), 1318
- `NODISC` (*cd* 모듈), 1418
- `noecho()` (*curses* 모듈), 552
- `NOEXPR` (*locale* 모듈), 1049
- `nofill` (*htmlib.HTMLParser*의 속성), 846
- `nok_builtin_names` (*rexec.RExec*의 속성), 1290
- `noload()` (*pickle.Unpickler* 메서드), 317
- `NoModificationAllowedErr`, 871

- nonblock() (*ossaudiodev.oss_audio_device* 메서드), 1033
 None (*Built-in object*), 31
 None (내장 변수), 29
 NoneType (*types* 모듈), 211
 nonl() (*curses* 모듈), 552
 nonzero (*2to3 fixer*), 1193
 noop() (*imaplib.IMAP4* 메서드), 953
 noop() (*poplib.POP3* 메서드), 949
 NoOptionError, 393
 NOP (*opcode*), 1331
 noqiflush() (*curses* 모듈), 553
 noraw() (*curses* 모듈), 553
 --no-report
 trace command line option, 1227
 normalize() (*decimal.Context* 메서드), 248
 normalize() (*decimal.Decimal* 메서드), 241
 normalize() (*locale* 모듈), 1050
 normalize() (*unicodedata* 모듈), 138
 normalize() (*xml.dom.Node* 메서드), 866
 NORMALIZE_WHITESPACE (*doctest* 모듈), 1148
 normalvariate() (*random* 모듈), 262
 normcase() (*os.path* 모듈), 291
 normpath() (*os.path* 모듈), 291
 NoSectionError, 393
 NoSuchMailboxError, 813
 not
 연산자, 32
 not in
 연산자, 33, 38
 not_() (*operator* 모듈), 280
 NotANumber, 141
 notationDecl() (*xml.sax.handler.DTDHandler* 메서드), 884
 NotationDeclHandler()
 (*xml.parsers.expat.xmlparser* 메서드), 894
 notations (*xml.dom.DocumentType*의 속성), 867
 NotConnected, 938
 Notebook (*Tix* 클래스), 1096
 Notebook (*ttk* 클래스), 1081
 NotEmptyError, 813
 NOTEQUAL (*token* 모듈), 1321
 NotFoundErr, 871
 notify() (*threading.Condition* 메서드), 627
 notify_all() (*threading.Condition* 메서드), 627
 notifyAll() (*threading.Condition* 메서드), 627
 notimeout() (*curses.window* 메서드), 559
 NotImplemented (내장 변수), 29
 NotImplementedError, 69
 NotImplementedType (*types* 모듈), 213
 NotStandaloneHandler()
 (*xml.parsers.expat.xmlparser* 메서드), 895
 NotSupportedErr, 871
 noutrefresh() (*curses.window* 메서드), 559
 now() (*datetime.datetime*의 클래스 메서드), 151
 NProperty (*aetypes* 클래스), 1412
 NSIG (*signal* 모듈), 745
 nsmaallest() (*heapq* 모듈), 188
 NT_OFFSET (*token* 모듈), 1321
 NTEventLogHandler (*logging.handlers* 클래스), 545
 ntohl() (*socket* 모듈), 712
 ntohs() (*socket* 모듈), 712
 ntransfercmd() (*ftplib.FTP* 메서드), 946
 NullFormatter (*formatter* 클래스), 1349
 NullHandler (*logging* 클래스), 540
 NullImporter (*imp* 클래스), 1296
 NullTranslations (*gettext* 클래스), 1040
 NullWriter (*formatter* 클래스), 1350
 Number (*numbers* 클래스), 221
 NUMBER (*token* 모듈), 1321
 --number=N
 timeit command line option, 1224
 number_class() (*decimal.Context* 메서드), 248
 number_class() (*decimal.Decimal* 메서드), 241
 numbers (모듈), 221
 numerator (*numbers.Rational*의 속성), 222
 numeric
 conversions, 34
 literals, 33
 object, 32
 types, operations on, 34
 객체, 33
 numeric() (*unicodedata* 모듈), 138
 Numerical Python, 20
 numliterals (*2to3 fixer*), 1194
 nurbscurve() (*gl* 모듈), 1428
 nurbsurface() (*gl* 모듈), 1428
 ndarray() (*gl* 모듈), 1428
- ## O
- O_APPEND (*os* 모듈), 421
 O_ASYNC (*os* 모듈), 421
 O_BINARY (*os* 모듈), 421
 O_CREAT (*os* 모듈), 421
 O_DIRECT (*os* 모듈), 421
 O_DIRECTORY (*os* 모듈), 421
 O_DSYNC (*os* 모듈), 421
 O_EXCL (*os* 모듈), 421
 O_EXLOCK (*os* 모듈), 421
 O_NDELAY (*os* 모듈), 421
 O_NOATIME (*os* 모듈), 421
 O_NOCTTY (*os* 모듈), 421
 O_NOFOLLOW (*os* 모듈), 421
 O_NOINHERIT (*os* 모듈), 421
 O_NONBLOCK (*os* 모듈), 421
 O_RANDOM (*os* 모듈), 421
 O_RDONLY (*os* 모듈), 421
 O_RDWR (*os* 모듈), 421

- O_RSYNC (*os* 모듈), 421
- O_SEQUENTIAL (*os* 모듈), 421
- O_SHLOCK (*os* 모듈), 421
- O_SHORT_LIVED (*os* 모듈), 421
- O_SYNC (*os* 모듈), 421
- O_TEMPORARY (*os* 모듈), 421
- O_TEXT (*os* 모듈), 421
- O_TRUNC (*os* 모듈), 421
- O_WRONLY (*os* 모듈), 421
- object
 - code, 63, 328
 - numeric, 32
- object (*exceptions.UnicodeError*의 속성), 71
- object (객체), 1445
- object (내장 클래스), 14
- objects
 - comparing, 32
 - flattening, 313
 - marshalling, 313
 - persistent, 313
 - pickling, 313
 - serializing, 313
- ObjectSpecifier (*aetypes* 클래스), 1412
- obufcount () (*ossaudiodev.oss_audio_device* 메서드), 1034
- obuffree () (*ossaudiodev.oss_audio_device* 메서드), 1034
- oct () (*future_builtins* 모듈), 1252
- oct () (내장 함수), 15
- octal
 - literals, 33
- octdigits (*string* 모듈), 76
- offset (*xml.parsers.expat.ExpatError*의 속성), 895
- OK (*curses* 모듈), 561
- ok_builtin_modules (*rexec.RExec*의 속성), 1290
- ok_file_types (*rexec.RExec*의 속성), 1290
- ok_path (*rexec.RExec*의 속성), 1290
- ok_posix_names (*rexec.RExec*의 속성), 1290
- ok_sys_names (*rexec.RExec*의 속성), 1290
- OleDLL (*ctypes* 클래스), 600
- onclick () (*turtle* 모듈), 1115, 1121
- ondrag () (*turtle* 모듈), 1116
- onecmd () (*cmd.Cmd* 메서드), 1056
- onkey () (*turtle* 모듈), 1121
- onrelease () (*turtle* 모듈), 1116
- onscreenclick () (*turtle* 모듈), 1121
- ontimer () (*turtle* 모듈), 1121
- OP (*token* 모듈), 1321
- OP_ALL (*ssl* 모듈), 727
- OP_CIPHER_SERVER_PREFERENCE (*ssl* 모듈), 728
- OP_ENABLE_MIDDLEBOX_COMPAT (*ssl* 모듈), 728
- OP_NO_COMPRESSION (*ssl* 모듈), 728
- OP_NO_SSLv2 (*ssl* 모듈), 727
- OP_NO_SSLv3 (*ssl* 모듈), 727
- OP_NO_TLSv1 (*ssl* 모듈), 727
- OP_NO_TLSv1_1 (*ssl* 모듈), 727
- OP_NO_TLSv1_2 (*ssl* 모듈), 728
- OP_NO_TLSv1_3 (*ssl* 모듈), 728
- OP_SINGLE_DH_USE (*ssl* 모듈), 728
- OP_SINGLE_ECDH_USE (*ssl* 모듈), 728
- Open Scripting Architecture, 1412
- open () (*aifc* 모듈), 1022
- open () (*anydbm* 모듈), 329
- open () (*cd* 모듈), 1418
- open () (*codecs* 모듈), 125
- open () (*dbhash* 모듈), 333
- open () (*dbm* 모듈), 331
- open () (*dl* 모듈), 1375
- open () (*dumbdbm* 모듈), 337
- open () (*FrameWork.DialogWindow* 메서드), 1401
- open () (*FrameWork.Window* 메서드), 1400
- open () (*gdbm* 모듈), 332
- open () (*gzip* 모듈), 363
- open () (*imaplib.IMAP4* 메서드), 953
- open () (*io* 모듈), 441
- open () (*os* 모듈), 419
- open () (*ossaudiodev* 모듈), 1032
- open () (*pipes.Template* 메서드), 1382
- open () (*posixfile* 모듈), 1382
- open () (*shelve* 모듈), 325
- open () (*sunau* 모듈), 1024
- open () (*sunaudiodev* 모듈), 1431
- open () (*tarfile* 모듈), 372
- open () (*tarfile.TarFile*의 클래스 메서드), 375
- open () (*telnetlib.Telnet* 메서드), 966
- open () (*urllib2.OpenerDirector* 메서드), 930
- open () (*urllib.URLopener* 메서드), 922
- open () (*wave* 모듈), 1026
- open () (*webbrowser* 모듈), 900
- open () (*webbrowser.controller* 메서드), 902
- open () (내장 함수), 15
- open () (*zipfile.ZipFile* 메서드), 368
- open_new () (*webbrowser* 모듈), 900
- open_new () (*webbrowser.controller* 메서드), 902
- open_new_tab () (*webbrowser* 모듈), 900
- open_new_tab () (*webbrowser.controller* 메서드), 902
- open_osfhandle () (*msvcrt* 모듈), 1359
- open_unknown () (*urllib.URLopener* 메서드), 922
- OpenDatabase () (*msilib* 모듈), 1353
- opendir () (*dircache* 모듈), 312
- OpenerDirector (*urllib2* 클래스), 927
- openfolder () (*mhlib.MH* 메서드), 817
- openfp () (*sunau* 모듈), 1024
- openfp () (*wave* 모듈), 1027
- OpenGL, 1428
- OpenKey () (*_winreg* 모듈), 1363
- OpenKeyEx () (*_winreg* 모듈), 1364
- openlog () (*syslog* 모듈), 1387

- `openmessage()` (*mhlib.Message* 메서드), 819
 - `openmixer()` (*ossaudiodev* 모듈), 1032
 - `openport()` (*al* 모듈), 1415
 - `openpty()` (*os* 모듈), 420
 - `openpty()` (*pty* 모듈), 1378
 - `openrf()` (*MacOS* 모듈), 1394
 - `OpenSSL`
 - (use in module *hashlib*), 405
 - (use in module *ssl*), 719
 - `OPENSSL_VERSION` (*ssl* 모듈), 729
 - `OPENSSL_VERSION_INFO` (*ssl* 모듈), 729
 - `OPENSSL_VERSION_NUMBER` (*ssl* 모듈), 729
 - `OpenView()` (*msilib.Database* 메서드), 1354
 - `operation`
 - concatenation, 38
 - extended slice, 38
 - repetition, 38
 - slice, 38
 - subscript, 38
 - `operations`
 - bitwise, 35
 - Boolean, 31, 32
 - masking, 35
 - shifting, 35
 - `operations on`
 - dictionary type, 52
 - integer types, 35
 - list type, 48
 - mapping types, 52
 - numeric types, 34
 - sequence types, 38, 48
 - `operator`
 - comparison, 32
 - `operator` (모듈), 280
 - `opmap` (*dis* 모듈), 1330
 - `opname` (*dis* 모듈), 1330
 - `optimize()` (*pickletools* 모듈), 1338
 - `OptionGroup` (*optparse* 클래스), 495
 - `OptionMenu` (*Tix* 클래스), 1095
 - `OptionParser` (*optparse* 클래스), 498
 - `options` (*doctest.Example*의 속성), 1157
 - `options` (*ssl.SSLContext*의 속성), 736
 - `options()` (*ConfigParser.RawConfigParser* 메서드), 393
 - `optionxform()` (*ConfigParser.RawConfigParser* 메서드), 395
 - `optparse` (모듈), 487
 - `or`
 - 연산자, 32
 - `or_()` (*operator* 모듈), 281
 - `ord()` (내장 함수), 15
 - `ordered_attributes` (*xml.parsers.expat.xmlparser*의 속성), 892
 - `OrderedDict` (*collections* 클래스), 183
 - `Ordinal` (*aetypes* 클래스), 1412
 - `origin_server` (*wsgiref.handlers.BaseHandler*의 속성), 917
 - `os`
 - 모듈, 56, 1371
 - `os` (모듈), 411
 - `os_environ` (*wsgiref.handlers.BaseHandler*의 속성), 916
 - `OSError`, 69
 - `os.path` (모듈), 289
 - `ossaudiodev` (모듈), 1032
 - `OSSAudioError`, 1032
 - `output` (*subprocess.CalledProcessError*의 속성), 697
 - `output()` (*Cookie.BaseCookie* 메서드), 999
 - `output()` (*Cookie.Morsel* 메서드), 1000
 - `output_charset` (*email.charset.Charset*의 속성), 773
 - `output_charset()` (*gettext.NullTranslations* 메서드), 1041
 - `output_codec` (*email.charset.Charset*의 속성), 773
 - `output_difference()` (*doctest.OutputChecker* 메서드), 1161
 - `OutputChecker` (*doctest* 클래스), 1160
 - `OutputString()` (*Cookie.Morsel* 메서드), 1000
 - `OutputType` (*cStringIO* 모듈), 120
 - `Overflow` (*decimal* 클래스), 250
 - `OverflowError`, 69
 - `overlay()` (*curses.window* 메서드), 559
 - `Overmars, Mark`, 1421
 - `overwrite()` (*curses.window* 메서드), 559
- ## P
- `-p`
 - `unittest-discover` command line option, 1168
 - `P_DETACH` (*os* 모듈), 436
 - `P_NOWAIT` (*os* 모듈), 435
 - `P_NOWAITO` (*os* 모듈), 435
 - `P_OVERLAY` (*os* 모듈), 436
 - `P_WAIT` (*os* 모듈), 435
 - `pack()` (*aepack* 모듈), 1410
 - `pack()` (*mailbox.MH* 메서드), 803
 - `pack()` (*struct* 모듈), 104
 - `pack()` (*struct.Struct* 메서드), 108
 - `pack_array()` (*xdrlib.Packer* 메서드), 401
 - `pack_bytes()` (*xdrlib.Packer* 메서드), 401
 - `pack_double()` (*xdrlib.Packer* 메서드), 400
 - `pack_farray()` (*xdrlib.Packer* 메서드), 401
 - `pack_float()` (*xdrlib.Packer* 메서드), 400
 - `pack_fopaque()` (*xdrlib.Packer* 메서드), 400
 - `pack_fstring()` (*xdrlib.Packer* 메서드), 400
 - `pack_into()` (*struct* 모듈), 104
 - `pack_into()` (*struct.Struct* 메서드), 108
 - `pack_list()` (*xdrlib.Packer* 메서드), 401
 - `pack_opaque()` (*xdrlib.Packer* 메서드), 400

- `pack_string()` (*xdrlib.Packer* 메서드), 400
- `package`, 1277
- `package` (패키지), 1445
- `Packer` (*xdrlib* 클래스), 400
- `packevent()` (*aetools* 모듈), 1409
- `packing`
 - binary data, 104
- `packing` (*widets*), 1069
- `PAGER`, 1140, 1210
- `pair_content()` (*curses* 모듈), 553
- `pair_number()` (*curses* 모듈), 553
- `PanedWindow` (*Tix* 클래스), 1096
- `parameter` (파라미터), 1445
- `pardir` (*os* 모듈), 439
- `paren` (*2to3 fixer*), 1194
- `parent` (*urllib2.BaseHandler*의 속성), 931
- `parent()` (*ttk.Treeview* 메서드), 1089
- `parentNode` (*xml.dom.Node*의 속성), 865
- `paretovariate()` (*random* 모듈), 262
- `parse()` (*ast* 모듈), 1317
- `parse()` (*cgi* 모듈), 906
- `parse()` (*compiler* 모듈), 1339
- `parse()` (*doctest.DocTestParser* 메서드), 1159
- `parse()` (*email.parser.Parser* 메서드), 766
- `parse()` (*robotparser.RobotFileParser* 메서드), 398
- `parse()` (*string.Formatter* 메서드), 76
- `parse()` (*xml.dom.minidom* 모듈), 873
- `parse()` (*xml.dom.pulldom* 모듈), 878
- `parse()` (*xml.etree.ElementTree* 모듈), 856
- `parse()` (*xml.etree.ElementTree.ElementTree* 메서드), 859
- `Parse()` (*xml.parsers.expat.xmlparser* 메서드), 891
- `parse()` (*xml.sax* 모듈), 879
- `parse()` (*xml.sax.xmlreader.XMLReader* 메서드), 887
- `parse_and_bind()` (*readline* 모듈), 689
- `parse_args()` (*argparse.ArgumentParser* 메서드), 477
- `PARSE_COLNAMES` (*sqlite3* 모듈), 340
- `parse_config_h()` (*sysconfig* 모듈), 1250
- `PARSE_DECLTYPES` (*sqlite3* 모듈), 339
- `parse_header()` (*cgi* 모듈), 906
- `parse_known_args()` (*argparse.ArgumentParser* 메서드), 486
- `parse_multipart()` (*cgi* 모듈), 906
- `parse_qs()` (*cgi* 모듈), 906
- `parse_qs()` (*urlparse* 모듈), 972
- `parse_qsl()` (*cgi* 모듈), 906
- `parse_qsl()` (*urlparse* 모듈), 973
- `parseaddr()` (*email.utils* 모듈), 777
- `parseaddr()` (*rfc822* 모듈), 828
- `parsedate()` (*email.utils* 모듈), 777
- `parsedate()` (*rfc822* 모듈), 828
- `parsedate_tz()` (*email.utils* 모듈), 777
- `parsedate_tz()` (*rfc822* 모듈), 828
- `parseFile()` (*compiler* 모듈), 1339
- `ParseFile()` (*xml.parsers.expat.xmlparser* 메서드), 891
- `ParseFlags()` (*imaplib* 모듈), 951
- `Parser` (*email.parser* 클래스), 765
- `parser` (모듈), 1309
- `ParserCreate()` (*xml.parsers.expat* 모듈), 890
- `ParserError`, 1312
- `ParseResult` (*urlparse* 클래스), 975
- `parsesequence()` (*mhlib.Folder* 메서드), 818
- `parsestr()` (*email.parser.Parser* 메서드), 766
- `parseString()` (*xml.dom.minidom* 모듈), 873
- `parseString()` (*xml.dom.pulldom* 모듈), 878
- `parseString()` (*xml.sax* 모듈), 879
- `parseurl()` (*ic* 모듈), 1392
- `parseurl()` (*ic.IC* 메서드), 1392
- `parsing`
 - Python source code, 1309
 - URL, 971
- `ParsingError`, 393
- `partial()` (*functools* 모듈), 278
- `partial()` (*imaplib.IMAP4* 메서드), 953
- `partition()` (*str* 메서드), 42
- `pass_()` (*poplib.POP3* 메서드), 949
- `Paste`, 1132
- `PATH`, 431, 435, 440, 899, 907, 909
- `path`
 - configuration file, 1277
 - module search, 307, 1243, 1277
 - operations, 289
- `path` (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
- `path` (*cookielib.Cookie*의 속성), 996
- `path` (*sys* 모듈), 1243
- `Path browser`, 1130
- `path_hooks` (*sys* 모듈), 1243
- `path_importer_cache` (*sys* 모듈), 1243
- `path_return_ok()` (*cookielib.CookiePolicy* 메서드), 994
- `pathconf()` (*os* 모듈), 425
- `pathconf_names` (*os* 모듈), 426
- `pathname2url()` (*urllib* 모듈), 921
- `pathsep` (*os* 모듈), 440
- `pattern` (*re.RegexObject*의 속성), 97
- `--pattern pattern`
 - unittest-discover command line option, 1168
- `pause()` (*signal* 모듈), 745
- `PAUSED` (*cd* 모듈), 1418
- `PAX_FORMAT` (*tarfile* 모듈), 374
- `pax_headers` (*tarfile.TarFile*의 속성), 377
- `pax_headers` (*tarfile.TarInfo*의 속성), 378
- `pbkdf2_hmac()` (*hashlib* 모듈), 407
- `pd()` (*turtle* 모듈), 1109
- `Pdb` (class in *pdb*), 1207

- Pdb (*pdb* 클래스), 1209
- pdb (모듈), 1207
- .pdbrc
 - file, 1210
- peek () (*io.BufferedReader* 메서드), 447
- PEM_cert_to_DER_cert () (*ssl* 모듈), 724
- pen () (*turtle* 모듈), 1109
- pencolor () (*turtle* 모듈), 1110
- PendingDeprecationWarning, 72
- pendown () (*turtle* 모듈), 1109
- pensize () (*turtle* 모듈), 1109
- penup () (*turtle* 모듈), 1109
- PEP, 1446
- PERCENT (*token* 모듈), 1321
- PERCENTEQUAL (*token* 모듈), 1321
- Performance, 1222
- permutations () (*itertools* 모듈), 271
- Persist () (*msilib.SummaryInformation* 메서드), 1355
- persistence, 313
- persistent
 - objects, 313
- persistent_id (*pickle protocol*), 320
- persistent_load (*pickle protocol*), 320
- pformat () (*pprint* 모듈), 216
- pformat () (*pprint.PrettyPrinter* 메서드), 217
- phase () (*cmath* 모듈), 229
- pi (*cmath* 모듈), 231
- pi (*math* 모듈), 228
- pick () (*gl* 모듈), 1428
- pickle
 - 모듈, 215, 324, 325, 328
- pickle (모듈), 313
- pickle () (*copy_reg* 모듈), 324
- PickleError, 316
- Pickler (*pickle* 클래스), 316
- pickletools (모듈), 1338
- pickling
 - objects, 313
- PicklingError, 316
- pid (*multiprocessing.Process*의 속성), 639
- pid (*popen2.Popen3*의 속성), 748
- pid (*subprocess.Popen*의 속성), 702
- PIL (*the Python Imaging Library*), 1430
- PIPE (*subprocess* 모듈), 697
- Pipe () (*multiprocessing* 모듈), 641
- pipe () (*os* 모듈), 420
- PIPE_BUF (*select.select*의 속성), 616
- pipes (모듈), 1380
- PixmapWrapper (모듈), 1437
- PKG_DIRECTORY (*imp* 모듈), 1295
- pkgutil (모듈), 1302
- platform (*sys* 모듈), 1243
- platform (모듈), 570
- platform () (*platform* 모듈), 571
- PLAYING (*cd* 모듈), 1418
- PlaySound () (*winsound* 모듈), 1369
- plist
 - file, 403
- plistlib (모듈), 403
- plock () (*os* 모듈), 434
- PLUS (*token* 모듈), 1321
- plus () (*decimal.Context* 메서드), 248
- PLUSEQUAL (*token* 모듈), 1321
- pm () (*pdb* 모듈), 1209
- pnum (*cd* 모듈), 1418
- POINTER () (*ctypes* 모듈), 607
- pointer () (*ctypes* 모듈), 607
- polar () (*cmath* 모듈), 229
- poll () (*Connection* 메서드), 644
- poll () (*popen2.Popen3* 메서드), 748
- poll () (*select* 모듈), 615
- poll () (*select.epoll* 메서드), 617
- poll () (*select.poll* 메서드), 618
- poll () (*subprocess.Popen* 메서드), 701
- pop () (*array.array* 메서드), 195
- pop () (*asynchat.fifo* 메서드), 755
- pop () (*collections.deque* 메서드), 175
- pop () (*dict* 메서드), 54
- pop () (*frozenset* 메서드), 51
- pop () (*list method*), 48
- pop () (*mailbox.Mailbox* 메서드), 800
- pop () (*multifile.MultiFile* 메서드), 826
- POP3
 - protocol, 948
- POP3 (*poplib* 클래스), 948
- POP3_SSL (*poplib* 클래스), 948
- pop_alignment () (*formatter.formatter* 메서드), 1348
- POP_BLOCK (*opcode*), 1334
- pop_font () (*formatter.formatter* 메서드), 1348
- POP_JUMP_IF_FALSE (*opcode*), 1336
- POP_JUMP_IF_TRUE (*opcode*), 1336
- pop_margin () (*formatter.formatter* 메서드), 1349
- pop_source () (*shlex.shlex* 메서드), 1059
- pop_style () (*formatter.formatter* 메서드), 1349
- POP_TOP (*opcode*), 1331
- Popen (*subprocess* 클래스), 699
- popen () (*in module os*), 616
- popen () (*os* 모듈), 416
- popen () (*platform* 모듈), 573
- popen2 (모듈), 747
- popen2 () (*os* 모듈), 417
- popen2 () (*popen2* 모듈), 747
- Popen3 (*popen2* 클래스), 747
- popen3 () (*os* 모듈), 417
- popen3 () (*popen2* 모듈), 747
- Popen4 (*popen2* 클래스), 747
- popen4 () (*os* 모듈), 417
- popen4 () (*popen2* 모듈), 747

- popitem() (*collections.OrderedDict* 메서드), 183
- popitem() (*dict* 메서드), 54
- popitem() (*mailbox.Mailbox* 메서드), 800
- popleft() (*collections.deque* 메서드), 175
- poplib(모듈), 948
- PopupMenu(*Tix* 클래스), 1095
- port(*cookielib.Cookie*의 속성), 996
- port_specified(*cookielib.Cookie*의 속성), 997
- PortableUnixMailbox(*mailbox* 클래스), 814
- pos(*re.MatchObject*의 속성), 100
- pos() (*operator* 모듈), 281
- pos() (*turtle* 모듈), 1107
- position() (*turtle* 모듈), 1107
- positional argument(위치 인자), 1446
- POSIX
 - file object, 1382
 - I/O control, 1376
 - threads, 630
- posix(*tarfile.TarFile*의 속성), 377
- posix(모듈), 1371
- posixfile(모듈), 1382
- POSIXLY_CORRECT, 515
- post() (*nnplib.NNTP* 메서드), 959
- post() (*ossaudiodev.oss_audio_device* 메서드), 1034
- post_mortem() (*pdb* 모듈), 1209
- postcmd() (*cmd.Cmd* 메서드), 1056
- postloop() (*cmd.Cmd* 메서드), 1057
- pow() (*math* 모듈), 226
- pow() (*operator* 모듈), 281
- pow() (내장 함수), 16
- power() (*decimal.Context* 메서드), 248
- pprint(모듈), 215
- pprint() (*bdb.Breakpoint* 메서드), 1204
- pprint() (*pprint* 모듈), 216
- pprint() (*pprint.PrettyPrinter* 메서드), 217
- prcal() (*calendar* 모듈), 171
- preamble(*email.message.Message*의 속성), 764
- precmd() (*cmd.Cmd* 메서드), 1056
- prefix(*sys* 모듈), 1244
- prefix(*xml.dom.Attr*의 속성), 869
- prefix(*xml.dom.Node*의 속성), 865
- prefix(*zipimport.zipimporter*의 속성), 1302
- PREFIXES(*site* 모듈), 1278
- preloop() (*cmd.Cmd* 메서드), 1057
- preorder() (*compiler.visitor.ASTVisitor* 메서드), 1346
- prepare_input_source() (*xml.sax.saxutils* 모듈), 885
- prepend() (*pipes.Template* 메서드), 1381
- PrettyPrinter(*pprint* 클래스), 215
- prev() (*ttk.Treeview* 메서드), 1089
- previous() (*bsddb.bsddbobject* 메서드), 336
- previous() (*dbhash.dbhash* 메서드), 334
- previousSibling(*xml.dom.Node*의 속성), 865
- print
 - 글, 31
 - print(2to3 fixer), 1194
 - Print() (*findertools* 모듈), 1395
 - print() (내장 함수), 16
 - print_callees() (*pstats.Stats* 메서드), 1218
 - print_callers() (*pstats.Stats* 메서드), 1218
 - print_directory() (*cgi* 모듈), 906
 - print_environ() (*cgi* 모듈), 906
 - print_environ_usage() (*cgi* 모듈), 906
 - print_exc() (*timeit.Timer* 메서드), 1224
 - print_exc() (*traceback* 모듈), 1264
 - print_exception() (*traceback* 모듈), 1264
 - PRINT_EXPR(*opcode*), 1333
 - print_form() (*cgi* 모듈), 906
 - print_help() (*argparse.ArgumentParser* 메서드), 485
 - PRINT_ITEM(*opcode*), 1333
 - PRINT_ITEM_TO(*opcode*), 1333
 - print_last() (*traceback* 모듈), 1264
 - PRINT_NEWLINE(*opcode*), 1334
 - PRINT_NEWLINE_TO(*opcode*), 1334
 - print_stack() (*traceback* 모듈), 1264
 - print_stats() (*profile.Profile* 메서드), 1216
 - print_stats() (*pstats.Stats* 메서드), 1217
 - print_tb() (*traceback* 모듈), 1263
 - print_usage() (*argparse.ArgumentParser* 메서드), 485
 - print_usage() (*optparse.OptionParser* 메서드), 507
 - print_version() (*optparse.OptionParser* 메서드), 497
 - printable(*string* 모듈), 76
 - printdir() (*zipfile.ZipFile* 메서드), 369
 - printf-style formatting, 46
 - PriorityQueue(*Queue* 클래스), 202
 - prmonth() (*calendar* 모듈), 171
 - prmonth() (*calendar.TextCalendar* 메서드), 169
 - process
 - group, 413
 - id, 413
 - id of parent, 413
 - killing, 434
 - signalling, 434
 - Process(*multiprocessing* 클래스), 638
 - process() (*logging.LoggerAdapter* 메서드), 526
 - process_message() (*smtpd.SMTPServer* 메서드), 964
 - process_request() (*SocketServer.BaseServer* 메서드), 978
 - process_tokens() (*tabnanny* 모듈), 1325
 - ProcessError, 660
 - processes, light-weight, 630
 - processfile() (*gensuitemodule* 모듈), 1408
 - processfile_fromresource() (*gensuitemodule* 모듈), 1408

- ProcessingInstruction() (*xml.etree.ElementTree* 모듈), 856
- processingInstruction() (*xml.sax.handler.ContentHandler* 메서드), 884
- ProcessingInstructionHandler() (*xml.parsers.expat.xmlparser* 메서드), 894
- processor time, 453
- processor() (*platform* 모듈), 571
- product() (*itertools* 모듈), 272
- Profile (*hotshot* 클래스), 1220
- Profile (*profile* 클래스), 1215
- profile (모듈), 1215
- profile function, 622, 1240, 1245
- profiler, 1240, 1245
- profiling, deterministic, 1212
- Progressbar (*tk* 클래스), 1083
- ProgressBar() (*EasyDialogs* 모듈), 1396
- prompt (*cmd.Cmd*의 속성), 1057
- prompt_user_passwd() (*urllib.FancyURLopener* 메서드), 923
- prompts, interpreter, 1244
- propagate (*logging.Logger*의 속성), 518
- property (내장 클래스), 16
- property list, 403
- property_declaration_handler (*xml.sax.handler* 모듈), 881
- property_dom_node (*xml.sax.handler* 모듈), 881
- property_lexical_handler (*xml.sax.handler* 모듈), 881
- property_xml_string (*xml.sax.handler* 모듈), 882
- prot_c() (*ftplib.FTP_TLS* 메서드), 947
- prot_p() (*ftplib.FTP_TLS* 메서드), 947
- proto (*socket.socket*의 속성), 716
- protocol
- CGI, 902
 - context management, 61
 - FTP, 924, 943
 - HTTP, 902, 924, 937, 983
 - IMAP4, 950
 - IMAP4_SSL, 950
 - IMAP4_stream, 950
 - iterator, 37
 - NNTP, 956
 - POP3, 948
 - SMTP, 960
 - Telnet, 965
- protocol (*ssl.SSLContext*의 속성), 736
- PROTOCOL_SSLv2 (*ssl* 모듈), 726
- PROTOCOL_SSLv3 (*ssl* 모듈), 727
- PROTOCOL_SSLv23 (*ssl* 모듈), 726
- PROTOCOL_TLS (*ssl* 모듈), 726
- PROTOCOL_TLSv1 (*ssl* 모듈), 727
- PROTOCOL_TLSv1_1 (*ssl* 모듈), 727
- PROTOCOL_TLSv1_2 (*ssl* 모듈), 727
- protocol_version (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 985
- PROTOCOL_VERSION (*imaplib.IMAP4*의 속성), 955
- ProtocolError (*xmlrpclib* 클래스), 1007
- proxy() (*weakref* 모듈), 205
- proxyauth() (*imaplib.IMAP4* 메서드), 953
- ProxyBasicAuthHandler (*urllib2* 클래스), 928
- ProxyDigestAuthHandler (*urllib2* 클래스), 928
- ProxyHandler (*urllib2* 클래스), 927
- ProxyType (*weakref* 모듈), 206
- ProxyTypes (*weakref* 모듈), 206
- prstr() (*fm* 모듈), 1426
- pryear() (*calendar.TextCalendar* 메서드), 169
- ps1 (*sys* 모듈), 1244
- ps2 (*sys* 모듈), 1244
- pstats (모듈), 1216
- pthreads, 630
- ptime (*cd* 모듈), 1418
- pty
- 모듈, 420
- pty (모듈), 1378
- pu() (*turtle* 모듈), 1109
- publicId (*xml.dom.DocumentType*의 속성), 867
- PullDOM (*xml.dom.pulldom* 클래스), 878
- punctuation (*string* 모듈), 76
- PureProxy (*smtpd* 클래스), 965
- purge() (*re* 모듈), 96
- Purpose.CLIENT_AUTH (*ssl* 모듈), 729
- Purpose.SERVER_AUTH (*ssl* 모듈), 729
- push() (*asynchat.async_chat* 메서드), 754
- push() (*asynchat.fifo* 메서드), 754
- push() (*code.InteractiveConsole* 메서드), 1285
- push() (*multifile.MultiFile* 메서드), 826
- push_alignment() (*formatter.formatter* 메서드), 1348
- push_font() (*formatter.formatter* 메서드), 1348
- push_margin() (*formatter.formatter* 메서드), 1348
- push_source() (*shlex.shlex* 메서드), 1059
- push_style() (*formatter.formatter* 메서드), 1349
- push_token() (*shlex.shlex* 메서드), 1058
- push_with_producer() (*asynchat.async_chat* 메서드), 754
- pushbutton() (*msilib.Dialog* 메서드), 1358
- put() (*multiprocessing.multiprocessing.queues.SimpleQueue* 메서드), 643
- put() (*multiprocessing.Queue* 메서드), 642
- put() (*Queue.Queue* 메서드), 203
- put_nowait() (*multiprocessing.Queue* 메서드), 642
- put_nowait() (*Queue.Queue* 메서드), 203
- putch() (*msvcrt* 모듈), 1360
- putenv() (*os* 모듈), 414
- putheader() (*httplib.HTTPConnection* 메서드), 941

putp() (*curses* 모듈), 553
 putrequest() (*httplib.HTTPConnection* 메서드), 941
 putsequences() (*mhlib.Folder* 메서드), 818
 putwch() (*msvcrt* 모듈), 1360
 putwin() (*curses.window* 메서드), 559
 pwd
 모듈, 290
 pwd(모듈), 1372
 pwd() (*ftplib.FTP* 메서드), 947
 pwlcurve() (*gl* 모듈), 1428
 py3kwarning(*sys* 모듈), 1244
 py_compile(모듈), 1327
 PY_COMPILED(*imp* 모듈), 1295
 PY_FROZEN(*imp* 모듈), 1295
 py_object(*ctypes* 클래스), 611
 PY_SOURCE(*imp* 모듈), 1294
 py_suffix_importer() (*imputil* 모듈), 1298
 pycldr(모듈), 1326
 PyCompileError, 1327
 PyDLL(*ctypes* 클래스), 600
 pydoc(모듈), 1139
 pyexpat
 모듈, 890
 PYFUNCTYPE() (*ctypes* 모듈), 603
 PyOpenGL, 1428
 Python 3000 (파이썬 3000), 1446
 Python Editor, 1129
 Python Imaging Library, 1430
 python_branch() (*platform* 모듈), 571
 python_build() (*platform* 모듈), 571
 python_compiler() (*platform* 모듈), 571
 PYTHON_DOM, 863
 python_implementation() (*platform* 모듈), 571
 python_revision() (*platform* 모듈), 571
 python_version() (*platform* 모듈), 571
 python_version_tuple() (*platform* 모듈), 571
 PYTHONDOCS, 1140
 PYTHONDONTWRITEBYTECODE, 1236
 PYTHONHASHSEED, 260
 Pythonic (파이썬다운), 1446
 PYTHONNOUSERSITE, 1278, 1279
 PYTHONPATH, 907, 1243
 .pythonrc.py
 file, 1279
 PYTHONSTARTUP, 692, 693, 1135, 1279
 PYTHONUSERBASE, 1278, 1279
 PYTHONY2K, 452, 453
 PyZipFile(*zipfile* 클래스), 366

Q

-q
 compileall command line option, 1328
 qdevice() (*fl* 모듈), 1422
 QDPoint(*aetypes* 클래스), 1411

QDRectangle(*aetypes* 클래스), 1411
 qenter() (*fl* 모듈), 1422
 qiflush() (*curses* 모듈), 553
 QName(*xml.etree.ElementTree* 클래스), 860
 qread() (*fl* 모듈), 1422
 qreset() (*fl* 모듈), 1422
 qsize() (*multiprocessing.Queue* 메서드), 641
 qsize() (*Queue.Queue* 메서드), 203
 qtest() (*fl* 모듈), 1422
 quantize() (*decimal.Context* 메서드), 248
 quantize() (*decimal.Decimal* 메서드), 241
 QueryInfoKey() (*_winreg* 모듈), 1364
 queryparams() (*al* 모듈), 1415
 QueryReflectionKey() (*_winreg* 모듈), 1365
 QueryValue() (*_winreg* 모듈), 1364
 QueryValueEx() (*_winreg* 모듈), 1364
 Queue(*multiprocessing* 클래스), 641
 Queue(*Queue* 클래스), 202
 queue(*sched.scheduler*의 속성), 201
 Queue(모듈), 202
 Queue() (*multiprocessing.managers.SyncManager* 메서드), 652
 quick_ratio() (*difflib.SequenceMatcher* 메서드), 115
 quit(내장 변수), 30
 quit() (*ftplib.FTP* 메서드), 947
 quit() (*nntplib.NNTP* 메서드), 959
 quit() (*poplib.POP3* 메서드), 949
 quit() (*smtplib.SMTP* 메서드), 963
 quopri(모듈), 835
 quote() (*email.utils* 모듈), 777
 quote() (*pipes* 모듈), 1380
 quote() (*rfc822* 모듈), 827
 quote() (*urllib* 모듈), 921
 QUOTE_ALL(*csv* 모듈), 386
 QUOTE_MINIMAL(*csv* 모듈), 386
 QUOTE_NONE(*csv* 모듈), 386
 QUOTE_NONNUMERIC(*csv* 모듈), 386
 quote_plus() (*urllib* 모듈), 921
 quoteattr() (*xml.sax.saxutils* 모듈), 885
 quotechar(*csv.Dialect*의 속성), 387
 quoted-printable
 encoding, 835
 quotes(*shlex.shlex*의 속성), 1060
 quoting(*csv.Dialect*의 속성), 387

R

-R
 trace command line option, 1227
 -r
 trace command line option, 1227
 -r N
 timeit command line option, 1224
 r_eval() (*rexec.RExec* 메서드), 1289
 r_exec() (*rexec.RExec* 메서드), 1289

- `r_execfile()` (*rexec.RExec* 메서드), 1289
- `r_import()` (*rexec.RExec* 메서드), 1289
- `R_OK` (*os* 모듈), 422
- `r_open()` (*rexec.RExec* 메서드), 1289
- `r_reload()` (*rexec.RExec* 메서드), 1289
- `r_unload()` (*rexec.RExec* 메서드), 1289
- `radians()` (*math* 모듈), 227
- `radians()` (*turtle* 모듈), 1108
- `RadioButtonGroup` (*msilib* 클래스), 1358
- `radiogroup()` (*msilib.Dialog* 메서드), 1358
- `radix()` (*decimal.Context* 메서드), 248
- `radix()` (*decimal.Decimal* 메서드), 242
- `RADIXCHAR` (*locale* 모듈), 1049
- `raise`
 - 글, 67
- `raise (2to3 fixer)`, 1194
- `RAISE_VARARGS` (*opcode*), 1337
- `RAND_add()` (*ssl* 모듈), 723
- `RAND_egd()` (*ssl* 모듈), 723
- `RAND_status()` (*ssl* 모듈), 723
- `randint()` (*random* 모듈), 261
- `random` (모듈), 259
- `random()` (*random* 모듈), 261
- `randrange()` (*random* 모듈), 261
- `Range` (*aetypes* 클래스), 1412
- `range()` (내장 함수), 17
- `ratecv()` (*audioop* 모듈), 1019
- `ratio()` (*difflib.SequenceMatcher* 메서드), 115
- `Rational` (*numbers* 클래스), 222
- `raw` (*io.BufferedIOBase*의 속성), 445
- `raw()` (*curses* 모듈), 553
- `raw_decode()` (*json.JSONDecoder* 메서드), 793
- `raw_input`
 - 내장 함수, 1246
- `raw_input (2to3 fixer)`, 1194
- `raw_input()` (*code.InteractiveConsole* 메서드), 1285
- `raw_input()` (내장 함수), 18
- `RawArray()` (*multiprocessing.sharedctypes* 모듈), 649
- `RawConfigParser` (*ConfigParser* 클래스), 392
- `RawDescriptionHelpFormatter` (*argparse* 클래스), 463
- `RawIOBase` (*io* 클래스), 444
- `RawPen` (*turtle* 클래스), 1124
- `RawTextHelpFormatter` (*argparse* 클래스), 463
- `RawTurtle` (*turtle* 클래스), 1124
- `RawValue()` (*multiprocessing.sharedctypes* 모듈), 649
- `RBRACE` (*token* 모듈), 1321
- `re`
 - 모듈, 47, 75, 306
- `re` (*re.MatchObject*의 속성), 100
- `re` (모듈), 88
- `read()` (*array.array* 메서드), 195
- `read()` (*bz2.BZ2File* 메서드), 365
- `read()` (*chunk.Chunk* 메서드), 1029
- `read()` (*codecs.StreamReader* 메서드), 130
- `read()` (*ConfigParser.RawConfigParser* 메서드), 394
- `read()` (*file* 메서드), 57
- `read()` (*httplib.HTTPResponse* 메서드), 942
- `read()` (*imaplib.IMAP4* 메서드), 953
- `read()` (*imgfile* 모듈), 1429
- `read()` (*io.BufferedIOBase* 메서드), 445
- `read()` (*io.BufferedReader* 메서드), 447
- `read()` (*io.RawIOBase* 메서드), 444
- `read()` (*io.TextIOBase* 메서드), 449
- `read()` (*mimetypes.MimeTypes* 메서드), 822
- `read()` (*mmap.mmap* 메서드), 688
- `read()` (*multifile.MultiFile* 메서드), 825
- `read()` (*os* 모듈), 420
- `read()` (*ossaudiodev.oss_audio_device* 메서드), 1033
- `read()` (*robotparser.RobotFileParser* 메서드), 398
- `read()` (*zipfile.ZipFile* 메서드), 369
- `read1()` (*io.BufferedIOBase* 메서드), 445
- `read1()` (*io.BufferedReader* 메서드), 447
- `read1()` (*io.BytesIO* 메서드), 447
- `read_all()` (*telnetlib.Telnet* 메서드), 966
- `read_byte()` (*mmap.mmap* 메서드), 688
- `read_eager()` (*telnetlib.Telnet* 메서드), 966
- `read_history_file()` (*readline* 모듈), 690
- `read_init_file()` (*readline* 모듈), 689
- `read_lazy()` (*telnetlib.Telnet* 메서드), 966
- `read_mime_types()` (*mimetypes* 모듈), 821
- `read_sb_data()` (*telnetlib.Telnet* 메서드), 966
- `read_some()` (*telnetlib.Telnet* 메서드), 966
- `read_token()` (*shlex.shlex* 메서드), 1058
- `read_until()` (*telnetlib.Telnet* 메서드), 966
- `read_very_eager()` (*telnetlib.Telnet* 메서드), 966
- `read_very_lazy()` (*telnetlib.Telnet* 메서드), 966
- `read_windows_registry()` (*mimetypes.MimeTypes* 메서드), 823
- `READABLE` (*Tkinter* 모듈), 1074
- `readable()` (*asyncore.dispatcher* 메서드), 750
- `readable()` (*io.IOBase* 메서드), 443
- `readall()` (*io.RawIOBase* 메서드), 445
- `reader()` (*csv* 모듈), 384
- `ReadError`, 374
- `readfp()` (*ConfigParser.RawConfigParser* 메서드), 394
- `readfp()` (*mimetypes.MimeTypes* 메서드), 823
- `readframes()` (*aifc.aifc* 메서드), 1022
- `readframes()` (*sunau.AU_read* 메서드), 1025
- `readframes()` (*wave.Wave_read* 메서드), 1027
- `readinto()` (*io.BufferedIOBase* 메서드), 446
- `readinto()` (*io.RawIOBase* 메서드), 445
- `readline` (모듈), 689
- `readline()` (*bz2.BZ2File* 메서드), 365
- `readline()` (*codecs.StreamReader* 메서드), 130
- `readline()` (*file* 메서드), 58
- `readline()` (*imaplib.IMAP4* 메서드), 953
- `readline()` (*io.IOBase* 메서드), 443

- `readline()` (*io.TextIOBase* 메서드), 449
`readline()` (*mmap.mmap* 메서드), 688
`readline()` (*multifile.MultiFile* 메서드), 825
`readlines()` (*bz2.BZ2File* 메서드), 365
`readlines()` (*codecs.StreamReader* 메서드), 130
`readlines()` (*file* 메서드), 58
`readlines()` (*io.IOBase* 메서드), 444
`readlines()` (*multifile.MultiFile* 메서드), 825
`readlink()` (*os* 모듈), 426
`readmodule()` (*pyclbr* 모듈), 1326
`readmodule_ex()` (*pyclbr* 모듈), 1326
`readonly` (*memoryview*의 속성), 61
`readPlist()` (*plistlib* 모듈), 403
`readPlistFromResource()` (*plistlib* 모듈), 403
`readPlistFromString()` (*plistlib* 모듈), 403
`readscaled()` (*imgfile* 모듈), 1429
`READY` (*cd* 모듈), 1418
`ready()` (*multiprocessing.pool.AsyncResult* 메서드), 658
`Real` (*numbers* 클래스), 222
`real` (*numbers.Complex*의 속성), 221
`Real Media File Format`, 1028
`real_quick_ratio()` (*difflib.SequenceMatcher* 메서드), 115
`realpath()` (*os.path* 모듈), 291
`reason` (*exceptions.UnicodeError*의 속성), 71
`reason` (*httplib.HTTPResponse*의 속성), 942
`reason` (*ssl.SSLError*의 속성), 720
`reason` (*urllib2.HTTPError*의 속성), 926
`reason` (*urllib2.URLError*의 속성), 926
`reattach()` (*ttk.Treeview* 메서드), 1089
`reccontrols()` (*ossaudiodev.oss_mixer_device* 메서드), 1035
`recent()` (*imaplib.IMAP4* 메서드), 953
`rect()` (*cmath* 모듈), 229
`rectangle()` (*curses.textpad* 모듈), 565
`recv()` (*asyncore.dispatcher* 메서드), 751
`recv()` (*Connection* 메서드), 644
`recv()` (*socket.socket* 메서드), 715
`recv_bytes()` (*Connection* 메서드), 644
`recv_bytes_into()` (*Connection* 메서드), 645
`recv_into()` (*socket.socket* 메서드), 715
`recvfrom()` (*socket.socket* 메서드), 715
`recvfrom_into()` (*socket.socket* 메서드), 715
`redirect_request()` (*urllib2.HTTPRedirectHandler* 메서드), 932
`redisplay()` (*readline* 모듈), 689
`redraw_form()` (*fl.form* 메서드), 1422
`redrawln()` (*curses.window* 메서드), 559
`redrawwin()` (*curses.window* 메서드), 559
`reduce` (*2to3 fixer*), 1194
`reduce()` (*functools* 모듈), 278
`reduce()` (내장 함수), 18
`ref` (*weakref* 클래스), 205
`reference count` (참조 횟수), 1446
`ReferenceError`, 70, 206
`ReferenceType` (*weakref* 모듈), 206
`refilemessages()` (*mhlib.Folder* 메서드), 818
`refresh()` (*curses.window* 메서드), 559
`REG_BINARY` (*_winreg* 모듈), 1367
`REG_DWORD` (*_winreg* 모듈), 1367
`REG_DWORD_BIG_ENDIAN` (*_winreg* 모듈), 1367
`REG_DWORD_LITTLE_ENDIAN` (*_winreg* 모듈), 1367
`REG_EXPAND_SZ` (*_winreg* 모듈), 1367
`REG_FULL_RESOURCE_DESCRIPTOR` (*_winreg* 모듈), 1367
`REG_LINK` (*_winreg* 모듈), 1367
`REG_MULTI_SZ` (*_winreg* 모듈), 1367
`REG_NONE` (*_winreg* 모듈), 1367
`REG_RESOURCE_LIST` (*_winreg* 모듈), 1367
`REG_RESOURCE_REQUIREMENTS_LIST` (*_winreg* 모듈), 1367
`REG_SZ` (*_winreg* 모듈), 1367
`RegexObject` (*re* 클래스), 96
`register()` (*abc.ABCMeta* 메서드), 1260
`register()` (*atexit* 모듈), 1262
`register()` (*codecs* 모듈), 123
`register()` (*multiprocessing.managers.BaseManager* 메서드), 651
`register()` (*select.epoll* 메서드), 617
`register()` (*select.poll* 메서드), 617
`register()` (*webbrowser* 모듈), 900
`register_adapter()` (*sqlite3* 모듈), 340
`register_archive_format()` (*shutil* 모듈), 311
`register_converter()` (*sqlite3* 모듈), 340
`register_dialect()` (*csv* 모듈), 384
`register_error()` (*codecs* 모듈), 125
`register_function()` (*SimpleXMLRPC-Server.CGIXMLRPCRequestHandler* 메서드), 1013
`register_function()` (*SimpleXMLRPC-Server.SimpleXMLRPCServer* 메서드), 1011
`register_instance()` (*SimpleXMLRPC-Server.CGIXMLRPCRequestHandler* 메서드), 1013
`register_instance()` (*SimpleXMLRPC-Server.SimpleXMLRPCServer* 메서드), 1011
`register_introspection_functions()` (*SimpleXMLRPC-Server.CGIXMLRPCRequestHandler* 메서드), 1013
`register_introspection_functions()` (*SimpleXMLRPCServer.SimpleXMLRPCServer* 메서드), 1011
`register_multicall_functions()` (*SimpleXMLRPC-Server.CGIXMLRPCRequestHandler* 메서드), 1013
`register_multicall_functions()` (*Sim-*

- `SimpleXMLRPCServer` 메서드, 1011
- `register_namespace()` (`xml.etree.ElementTree` 모듈), 856
- `register_optionflag()` (`doctest` 모듈), 1149
- `register_shape()` (`turtle` 모듈), 1123
- `registerDOMImplementation()` (`xml.dom` 모듈), 863
- `registerResult()` (`unittest` 모듈), 1189
- `relative`
 - URL, 971
- `release()` (`logging.Handler` 메서드), 521
- `release()` (`multiprocessing.Lock` 메서드), 646
- `release()` (`multiprocessing.RLock` 메서드), 647
- `release()` (`platform` 모듈), 571
- `release()` (`threading.Condition` 메서드), 627
- `release()` (`threading.Lock` 메서드), 625
- `release()` (`threading.RLock` 메서드), 626
- `release()` (`threading.Semaphore` 메서드), 628
- `release()` (`thread.lock` 메서드), 631
- `release_lock()` (`imp` 모듈), 1294
- `reload`
 - 내장 함수, 1243, 1294, 1296
- `reload()` (내장 함수), 18
- `relpath()` (`os.path` 모듈), 292
- `remainder()` (`decimal.Context` 메서드), 248
- `remainder_near()` (`decimal.Context` 메서드), 248
- `remainder_near()` (`decimal.Decimal` 메서드), 242
- `remove()` (`array.array` 메서드), 195
- `remove()` (`collections.deque` 메서드), 175
- `remove()` (`frozenset` 메서드), 51
- `remove()` (`list` method), 48
- `remove()` (`mailbox.Mailbox` 메서드), 798
- `remove()` (`mailbox.MH` 메서드), 803
- `remove()` (`os` 모듈), 426
- `remove()` (`xml.etree.ElementTree.Element` 메서드), 858
- `remove_flag()` (`mailbox.MaildirMessage` 메서드), 806
- `remove_flag()` (`mailbox.mboxMessage` 메서드), 808
- `remove_flag()` (`mailbox.MMDFMessage` 메서드), 812
- `remove_folder()` (`mailbox.Maildir` 메서드), 801
- `remove_folder()` (`mailbox.MH` 메서드), 803
- `remove_history_item()` (`readline` 모듈), 690
- `remove_label()` (`mailbox.BabylMessage` 메서드), 811
- `remove_option()` (`ConfigParser.RawConfigParser` 메서드), 394
- `remove_option()` (`optparse.OptionParser` 메서드), 506
- `remove_pyc()` (`msilib.Directory` 메서드), 1357
- `remove_section()` (`ConfigParser.RawConfigParser` 메서드), 395
- `remove_sequence()` (`mailbox.MHMessage` 메서드), 810
- `removeAttribute()` (`xml.dom.Element` 메서드), 868
- `removeAttributeNode()` (`xml.dom.Element` 메서드), 868
- `removeAttributeNS()` (`xml.dom.Element` 메서드), 869
- `removeChild()` (`xml.dom.Node` 메서드), 866
- `removedirs()` (`os` 모듈), 426
- `removeFilter()` (`logging.Handler` 메서드), 521
- `removeFilter()` (`logging.Logger` 메서드), 520
- `removeHandler()` (`logging.Logger` 메서드), 520
- `removeHandler()` (`unittest` 모듈), 1189
- `removemessages()` (`mhlib.Folder` 메서드), 818
- `removeResult()` (`unittest` 모듈), 1189
- `rename()` (`ftplib.FTP` 메서드), 947
- `rename()` (`imaplib.IMAP4` 메서드), 953
- `rename()` (`os` 모듈), 426
- `renames(2to3 fixer)`, 1194
- `renames()` (`os` 모듈), 426
- `reorganize()` (`gdbm` 모듈), 333
- `repeat()` (`itertools` 모듈), 272
- `repeat()` (`operator` 모듈), 282
- `repeat()` (`timeit` 모듈), 1223
- `repeat()` (`timeit.Timer` 메서드), 1224
- `--repeat=N`
 - `timeit` command line option, 1224
- `repetition`
 - operation, 38
- `replace()` (`curses.panel.Panel` 메서드), 570
- `replace()` (`datetime.date` 메서드), 148
- `replace()` (`datetime.datetime` 메서드), 153
- `replace()` (`datetime.time` 메서드), 158
- `replace()` (`str` 메서드), 42
- `replace()` (`string` 모듈), 88
- `replace_errors()` (`codecs` 모듈), 125
- `replace_header()` (`email.message.Message` 메서드), 761
- `replace_history_item()` (`readline` 모듈), 690
- `replace_whitespace` (`textwrap.TextWrapper`의 속성), 122
- `replaceChild()` (`xml.dom.Node` 메서드), 866
- `ReplacePackage()` (`modulefinder` 모듈), 1305
- `--report`
 - `trace` command line option, 1227
- `report()` (`filecmp.dircmp` 메서드), 300
- `report()` (`modulefinder.ModuleFinder` 메서드), 1305
- `REPORT_CDIF` (`doctest` 모듈), 1149
- `report_failure()` (`doctest.DocTestRunner` 메서드), 1160
- `report_full_closure()` (`filecmp.dircmp` 메서드), 300
- `REPORT_NDIFF` (`doctest` 모듈), 1149

- REPORT_ONLY_FIRST_FAILURE (*doctest* 모듈), 1149
- report_partial_closure() (*filecmp.dircmp* 메서드), 300
- report_start() (*doctest.DocTestRunner* 메서드), 1159
- report_success() (*doctest.DocTestRunner* 메서드), 1160
- REPORT_UDIFF (*doctest* 모듈), 1149
- report_unbalanced() (*sgmlib.SGMLParser* 메서드), 844
- report_unexpected_exception() (*doctest.DocTestRunner* 메서드), 1160
- REPORTING_FLAGS (*doctest* 모듈), 1149
- repr (2to3 fixer), 1194
- Repr (*repr* 클래스), 218
- repr() (*repr* 모듈), 218
- repr() (*repr.Repr* 메서드), 219
- repr() (내장 함수), 19
- repr1() (*repr.Repr* 메서드), 219
- Request (*urllib2* 클래스), 926
- request() (*httplib.HTTPConnection* 메서드), 940
- request_queue_size (*SocketServer.BaseServer*의 속성), 978
- request_uri() (*wsgiref.util* 모듈), 910
- request_version (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
- RequestHandlerClass (*SocketServer.BaseServer*의 속성), 978
- requires() (*test.support* 모듈), 1198
- reserved (*zipfile.ZipInfo*의 속성), 371
- RESERVED_FUTURE (*uuid* 모듈), 970
- RESERVED_MICROSOFT (*uuid* 모듈), 970
- RESERVED_NCS (*uuid* 모듈), 970
- reset() (*bdb.Bdb* 메서드), 1204
- reset() (*codecs.IncrementalDecoder* 메서드), 129
- reset() (*codecs.IncrementalEncoder* 메서드), 128
- reset() (*codecs.StreamReader* 메서드), 131
- reset() (*codecs.StreamWriter* 메서드), 129
- reset() (*dircache* 모듈), 312
- reset() (*HTMLParser.HTMLParser* 메서드), 839
- reset() (*ossaudiodev.oss_audio_device* 메서드), 1034
- reset() (*pipes.Template* 메서드), 1381
- reset() (*sgmlib.SGMLParser* 메서드), 842
- reset() (*turtle* 모듈), 1112, 1119
- reset() (*xdrlib.Packer* 메서드), 400
- reset() (*xdrlib.Unpacker* 메서드), 401
- reset() (*xml.dom.pulldom.DOMEventStream* 메서드), 878
- reset() (*xml.sax.xmlreader.IncrementalParser* 메서드), 888
- reset_prog_mode() (*curses* 모듈), 553
- reset_shell_mode() (*curses* 모듈), 553
- resetbuffer() (*code.InteractiveConsole* 메서드), 1285
- resetlocale() (*locale* 모듈), 1051
- resetscreen() (*turtle* 모듈), 1119
- resetty() (*curses* 모듈), 553
- resetwarnings() (*warnings* 모듈), 1257
- resize() (*ctypes* 모듈), 607
- resize() (*curses.window* 메서드), 560
- resize() (*mmap.mmap* 메서드), 688
- resize_term() (*curses* 모듈), 553
- resizemode() (*turtle* 모듈), 1114
- resizeterm() (*curses* 모듈), 553
- resolution (*datetime.datetime*의 속성), 152
- resolution (*datetime.date*의 속성), 148
- resolution (*datetime.timedelta*의 속성), 145
- resolution (*datetime.time*의 속성), 157
- resolveEntity() (*xml.sax.handler.EntityResolver* 메서드), 884
- resource (모듈), 1384
- ResourceDenied, 1197
- response() (*imaplib.IMAP4* 메서드), 953
- ResponseNotReady, 939
- responses (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 985
- responses (*httplib* 모듈), 940
- restart() (*findertools* 모듈), 1395
- restore() (*difflib* 모듈), 111
- restype (*ctypes._FuncPtr*의 속성), 602
- results() (*trace.Trace* 메서드), 1228
- retr() (*poplib.POP3* 메서드), 949
- retrbinary() (*ftplib.FTP* 메서드), 946
- retrieve() (*urllib.URLopener* 메서드), 922
- retrlines() (*ftplib.FTP* 메서드), 946
- return_ok() (*cookielib.CookiePolicy* 메서드), 993
- RETURN_VALUE (*opcode*), 1334
- returncode (*subprocess.CalledProcessError*의 속성), 697
- returncode (*subprocess.Popen*의 속성), 702
- returns_unicode (*xml.parsers.expat.xmlparser*의 속성), 892
- reverse() (*array.array* 메서드), 195
- reverse() (*audioop* 모듈), 1019
- reverse() (*collections.deque* 메서드), 175
- reverse() (*list method*), 48
- reverse_order() (*pstats.Stats* 메서드), 1217
- reversed() (내장 함수), 19
- revert() (*cookielib.FileCookieJar* 메서드), 992
- rewind() (*aifc.aifc* 메서드), 1022
- rewind() (*sunau.AU_read* 메서드), 1025
- rewind() (*wave.Wave_read* 메서드), 1027
- rewindbody() (*rfc822.Message* 메서드), 828
- RExec (*rexec* 클래스), 1288
- rexec (모듈), 1288
- RFC

- RFC 821, 960, 961
 RFC 822, 391, 455, 770, 827, 941, 962, 963, 1041
 RFC 854, 965
 RFC 959, 943
 RFC 977, 956
 RFC 1014, 400
 RFC 1123, 455
 RFC 1321, 405, 409
 RFC 1422, 737
 RFC 1521, 832, 835
 RFC 1522, 835
 RFC 1524, 796, 797
 RFC 1725, 948
 RFC 1730, 950
 RFC 1738, 974
 RFC 1750, 724
 RFC 1766, 1050
 RFC 1808, 971, 974
 RFC 1832, 400
 RFC 1866, 845
 RFC 1869, 960, 961
 RFC 1894, 788
 RFC 2045, 757, 761, 762, 770, 826
 RFC 2046, 757, 770
 RFC 2047, 757, 770772
 RFC 2060, 950, 954
 RFC 2068, 998
 RFC 2104, 408
 RFC 2109, 989, 991, 998, 999
 RFC 2231, 757, 761, 762, 770, 778, 786
 RFC 2368, 974
 RFC 2396, 973, 974
 RFC 2616, 911, 923, 932
 RFC 2732, 974
 RFC 2774, 940
 RFC 2817, 940
 RFC 2818, 724
 RFC 2821, 757
 RFC 2822, 455, 757759, 766, 767, 770772, 776778, 805, 827, 828, 964
 RFC 2964, 991
 RFC 2965, 927, 929, 989, 991
 RFC 3229, 939
 RFC 3280, 730
 RFC 3454, 139
 RFC 3490, 136, 137
 RFC 3492, 136, 137
 RFC 3493, 707
 RFC 3548, 831, 834
 RFC 3986, 974
 RFC 4122, 968, 970
 RFC 4217, 944
 RFC 4366, 728
 RFC 4627, 788, 796
 RFC 5246, 729
 RFC 5280, 724
 RFC 5929, 731
 RFC 6066, 734
 RFC 6125, 724
 RFC 7159, 788, 795, 796
 RFC 7301, 728, 734
 rfc822
 모듈, 819
 rfc822 (모듈), 827
 rfc2109 (*cookielib.Cookie*의 속성), 996
 rfc2109_as_netscape (*cookielib.DefaultCookiePolicy*의 속성), 995
 rfc2965 (*cookielib.CookiePolicy*의 속성), 994
 RFC_4122 (*uuid* 모듈), 970
 rfile (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
 rfind() (*mmap.mmap* 메서드), 688
 rfind() (*str* 메서드), 42
 rfind() (*string* 모듈), 86
 rgb_to_hls() (*colorsys* 모듈), 1030
 rgb_to_hsv() (*colorsys* 모듈), 1030
 rgb_to_yiq() (*colorsys* 모듈), 1030
 RGBColor (*aetypes* 클래스), 1411
 right (*filecmp.dircmp*의 속성), 301
 right() (*turtle* 모듈), 1102
 right_list (*filecmp.dircmp*의 속성), 301
 right_only (*filecmp.dircmp*의 속성), 301
 RIGHTSHIFT (*token* 모듈), 1321
 RIGHTSHIFTEQUAL (*token* 모듈), 1321
 rindex() (*str* 메서드), 42
 rindex() (*string* 모듈), 86
 rjust() (*str* 메서드), 42
 rjust() (*string* 모듈), 87
 rlcompleter (모듈), 693
 rlecode_hqx() (*binascii* 모듈), 834
 rledecode_hqx() (*binascii* 모듈), 834
 RLIM_INFINITY (*resource* 모듈), 1384
 RLIMIT_AS (*resource* 모듈), 1385
 RLIMIT_CORE (*resource* 모듈), 1384
 RLIMIT_CPU (*resource* 모듈), 1385
 RLIMIT_DATA (*resource* 모듈), 1385
 RLIMIT_FSIZE (*resource* 모듈), 1385
 RLIMIT_MEMLOCK (*resource* 모듈), 1385
 RLIMIT_NOFILE (*resource* 모듈), 1385
 RLIMIT_NPROC (*resource* 모듈), 1385
 RLIMIT_OFIL (resource 모듈), 1385
 RLIMIT_RSS (*resource* 모듈), 1385
 RLIMIT_STACK (*resource* 모듈), 1385
 RLIMIT_VMEM (*resource* 모듈), 1385
 RLock (*multiprocessing* 클래스), 647
 RLock() (*multiprocessing.managers.SyncManager* 메서드), 652
 RLock() (*threading* 모듈), 621

- `rmd()` (*ftplib.FTP* 메서드), 947
 - `rmdir()` (*os* 모듈), 426
 - `RMFF`, 1028
 - `rms()` (*audioop* 모듈), 1019
 - `rmtree()` (*shutil* 모듈), 309
 - `rnopen()` (*bsddb* 모듈), 335
 - `RobotFileParser` (*robotparser* 클래스), 398
 - `robotparser` (모듈), 398
 - `robots.txt`, 398
 - `rollback()` (*sqlite3.Connection* 메서드), 342
 - `ROT_FOUR` (*opcode*), 1331
 - `ROT_THREE` (*opcode*), 1331
 - `ROT_TWO` (*opcode*), 1331
 - `rotate()` (*collections.deque* 메서드), 176
 - `rotate()` (*decimal.Context* 메서드), 249
 - `rotate()` (*decimal.Decimal* 메서드), 242
 - `RotatingFileHandler` (*logging.handlers* 클래스), 541
 - `round()` (내장 함수), 19
 - `Rounded` (*decimal* 클래스), 250
 - `Row` (*sqlite3* 클래스), 350
 - `row_factory` (*sqlite3.Connection*의 속성), 345
 - `rowcount` (*sqlite3.Cursor*의 속성), 349
 - `RPAR` (*token* 모듈), 1321
 - `rpartition()` (*str* 메서드), 42
 - `rpc_paths` (*SimpleXMLRPC-Server.SimpleXMLRPCRequestHandler*의 속성), 1011
 - `rpop()` (*poplib.POP3* 메서드), 949
 - `rset()` (*poplib.POP3* 메서드), 949
 - `rshift()` (*operator* 모듈), 281
 - `rsplit()` (*str* 메서드), 42
 - `rsplit()` (*string* 모듈), 87
 - `RSQB` (*token* 모듈), 1321
 - `rstrip()` (*str* 메서드), 42
 - `rstrip()` (*string* 모듈), 87
 - `rt()` (*turtle* 모듈), 1102
 - `RTLD_LAZY` (*dl* 모듈), 1375
 - `RTLD_NOW` (*dl* 모듈), 1375
 - `ruler` (*cmd.Cmd*의 속성), 1057
 - `Run script`, 1131
 - `run()` (*bdb.Bdb* 메서드), 1207
 - `run()` (*doctest.DocTestRunner* 메서드), 1160
 - `run()` (*hotshot.Profile* 메서드), 1221
 - `run()` (*multiprocessing.Process* 메서드), 638
 - `run()` (*pdb* 모듈), 1208
 - `run()` (*pdb.Pdb* 메서드), 1209
 - `run()` (*profile* 모듈), 1215
 - `run()` (*profile.Profile* 메서드), 1216
 - `run()` (*sched.scheduler* 메서드), 200
 - `run()` (*threading.Thread* 메서드), 624
 - `run()` (*trace.Trace* 메서드), 1228
 - `run()` (*unittest.TestCase* 메서드), 1175
 - `run()` (*unittest.TestSuite* 메서드), 1182
 - `run()` (*wsgiref.handlers.BaseHandler* 메서드), 915
 - `run_docstring_examples()` (*doctest* 모듈), 1153
 - `run_module()` (*runpy* 모듈), 1306
 - `run_path()` (*runpy* 모듈), 1307
 - `run_script()` (*modulefinder.ModuleFinder* 메서드), 1305
 - `run_unittest()` (*test.support* 모듈), 1198
 - `runcall()` (*bdb.Bdb* 메서드), 1207
 - `runcall()` (*hotshot.Profile* 메서드), 1221
 - `runcall()` (*pdb* 모듈), 1208
 - `runcall()` (*pdb.Pdb* 메서드), 1209
 - `runcall()` (*profile.Profile* 메서드), 1216
 - `runcode()` (*code.InteractiveInterpreter* 메서드), 1284
 - `runtcx()` (*bdb.Bdb* 메서드), 1207
 - `runtcx()` (*hotshot.Profile* 메서드), 1221
 - `runtcx()` (*profile* 모듈), 1215
 - `runtcx()` (*profile.Profile* 메서드), 1216
 - `runtcx()` (*trace.Trace* 메서드), 1228
 - `runeval()` (*bdb.Bdb* 메서드), 1207
 - `runeval()` (*pdb* 모듈), 1208
 - `runeval()` (*pdb.Pdb* 메서드), 1209
 - `runfunc()` (*trace.Trace* 메서드), 1228
 - `runpy` (모듈), 1306
 - `runsource()` (*code.InteractiveInterpreter* 메서드), 1284
 - `RuntimeError`, 70
 - `runtimemodel` (*MacOS* 모듈), 1393
 - `RuntimeWarning`, 72
 - `RUSAGE_BOTH` (*resource* 모듈), 1386
 - `RUSAGE_CHILDREN` (*resource* 모듈), 1386
 - `RUSAGE_SELF` (*resource* 모듈), 1386
- ## S
- `-s`
 - `trace` command line option, 1227
 - `unittest-discover` command line option, 1168
 - `S` (*re* 모듈), 93
 - `-s S`
 - `timeit` command line option, 1224
 - `S_ENFMT` (*stat* 모듈), 298
 - `s_eval()` (*rexec.RExec* 메서드), 1289
 - `s_exec()` (*rexec.RExec* 메서드), 1289
 - `s_execfile()` (*rexec.RExec* 메서드), 1289
 - `S_IEXEC` (*stat* 모듈), 298
 - `S_IFBLK` (*stat* 모듈), 297
 - `S_IFCHR` (*stat* 모듈), 297
 - `S_IFDIR` (*stat* 모듈), 297
 - `S_IFIFO` (*stat* 모듈), 297
 - `S_IFLNK` (*stat* 모듈), 297
 - `S_IFMT` (*stat* 모듈), 296
 - `S_IFREG` (*stat* 모듈), 297
 - `S_IFSOCK` (*stat* 모듈), 297
 - `S_IMODE` (*stat* 모듈), 295

- `s_import()` (*rexec.RExec* 메서드), 1289
- `S_IREAD` (*stat* 모듈), 298
- `S_IRGRP` (*stat* 모듈), 298
- `S_IROTH` (*stat* 모듈), 298
- `S_IRUSR` (*stat* 모듈), 297
- `S_IRWXG` (*stat* 모듈), 298
- `S_IRWXO` (*stat* 모듈), 298
- `S_IRWXU` (*stat* 모듈), 297
- `S_ISBLK` (*stat* 모듈), 295
- `S_ISCHR` (*stat* 모듈), 295
- `S_ISDIR` (*stat* 모듈), 295
- `S_ISFIFO` (*stat* 모듈), 295
- `S_ISGID` (*stat* 모듈), 297
- `S_ISLNK` (*stat* 모듈), 295
- `S_ISREG` (*stat* 모듈), 295
- `S_ISSOCK` (*stat* 모듈), 295
- `S_ISUID` (*stat* 모듈), 297
- `S_ISVTX` (*stat* 모듈), 297
- `S_IWGRP` (*stat* 모듈), 298
- `S_IWOTH` (*stat* 모듈), 298
- `S_IWRITE` (*stat* 모듈), 298
- `S_IWUSR` (*stat* 모듈), 298
- `S_IXGRP` (*stat* 모듈), 298
- `S_IXOTH` (*stat* 모듈), 298
- `S_IXUSR` (*stat* 모듈), 298
- `s_reload()` (*rexec.RExec* 메서드), 1289
- `s_unload()` (*rexec.RExec* 메서드), 1289
- `safe_substitute()` (*string.Template* 메서드), 84
- `SafeConfigParser` (*ConfigParser* 클래스), 392
- `saferepr()` (*pprint* 모듈), 216
- `same_files` (*filecmp.dircmp*의 속성), 301
- `same_quantum()` (*decimal.Context* 메서드), 249
- `same_quantum()` (*decimal.Decimal* 메서드), 242
- `samefile()` (*os.path* 모듈), 292
- `sameopenfile()` (*os.path* 모듈), 292
- `samestat()` (*os.path* 모듈), 292
- `sample()` (*random* 모듈), 261
- `save()` (*cookielib.FileCookieJar* 메서드), 992
- `save_bgn()` (*htmlib.HTMLParser* 메서드), 846
- `save_end()` (*htmlib.HTMLParser* 메서드), 846
- `SaveKey()` (*_winreg* 모듈), 1364
- `savetty()` (*curses* 모듈), 553
- `SAX2DOM` (*xml.dom.pulldom* 클래스), 878
- `SAXException`, 879
- `SAXNotRecognizedException`, 879
- `SAXNotSupportedException`, 879
- `SAXParseException`, 879
- `scale()` (*imageop* 모듈), 1020
- `scaleb()` (*decimal.Context* 메서드), 249
- `scaleb()` (*decimal.Decimal* 메서드), 242
- `scalebarvalues()` (*FrameWork.ScrolledWindow* 메서드), 1401
- `scanf()`, 101
- `sched` (모듈), 199
- `scheduler` (*sched* 클래스), 199
- `schema` (*msilib* 모듈), 1359
- `sci()` (*fpformat* 모듈), 141
- `Scrap Manager`, 1404
- `Screen` (*turtle* 클래스), 1124
- `screenize()` (*turtle* 모듈), 1119
- `script_from_examples()` (*doctest* 모듈), 1162
- `scroll()` (*curses.window* 메서드), 560
- `scrollbar_callback()` (*FrameWork.ScrolledWindow* 메서드), 1401
- `scrollbars()` (*FrameWork.ScrolledWindow* 메서드), 1401
- `ScrolledCanvas` (*turtle* 클래스), 1124
- `ScrolledText` (모듈), 1098
- `scrollok()` (*curses.window* 메서드), 560
- `search`
 - `path, module`, 307, 1243, 1277
- `search()` (*imaplib.IMAP4* 메서드), 953
- `search()` (*re* 모듈), 94
- `search()` (*re.RegexObject* 메서드), 96
- `SEARCH_ERROR` (*imp* 모듈), 1295
- `second` (*datetime.datetime*의 속성), 152
- `second` (*datetime.time*의 속성), 158
- `section_divider()` (*multifile.MultiFile* 메서드), 826
- `sections()` (*ConfigParser.RawConfigParser* 메서드), 393
- `secure` (*cookielib.Cookie*의 속성), 996
- `Secure Hash Algorithm`, 410
- `secure hash algorithm`, SHA1, SHA224, SHA256, SHA384, SHA512, 405
- `Secure Sockets Layer`, 719
- `security`
 - `CGI`, 907
- `see()` (*tk.Treeview* 메서드), 1089
- `seed()` (*random* 모듈), 260
- `seek()` (*bz2.BZ2File* 메서드), 365
- `seek()` (*chunk.Chunk* 메서드), 1029
- `seek()` (*file* 메서드), 58
- `seek()` (*io.IOBBase* 메서드), 444
- `seek()` (*io.TextIOBase* 메서드), 449
- `seek()` (*mmap.mmap* 메서드), 688
- `seek()` (*multifile.MultiFile* 메서드), 825
- `SEEK_CUR` (*os* 모듈), 419
- `SEEK_CUR` (*posixfile* 모듈), 1382
- `SEEK_END` (*os* 모듈), 419
- `SEEK_END` (*posixfile* 모듈), 1382
- `SEEK_SET` (*os* 모듈), 419
- `SEEK_SET` (*posixfile* 모듈), 1382
- `seekable()` (*io.IOBBase* 메서드), 444
- `Select` (*Tix* 클래스), 1095
- `select` (모듈), 615
- `select()` (*gl* 모듈), 1428
- `select()` (*imaplib.IMAP4* 메서드), 954
- `select()` (*select* 모듈), 616

- `select()` (*ttk.Notebook* 메서드), 1082
`selected_alpn_protocol()` (*ssl.SSLSocket* 메서드), 731
`selected_npn_protocol()` (*ssl.SSLSocket* 메서드), 732
`selection()` (*ttk.Treeview* 메서드), 1089
`selection_add()` (*ttk.Treeview* 메서드), 1089
`selection_remove()` (*ttk.Treeview* 메서드), 1089
`selection_set()` (*ttk.Treeview* 메서드), 1089
`selection_toggle()` (*ttk.Treeview* 메서드), 1089
`Semaphore` (*multiprocessing* 클래스), 647
`Semaphore` (*threading* 클래스), 628
`Semaphore()` (*multiprocessing.managers.SyncManager* 메서드), 652
`semaphores`, binary, 630
`SEMI` (*token* 모듈), 1321
`send()` (*aetools.TalkTo* 메서드), 1409
`send()` (*asyncore.dispatcher* 메서드), 751
`send()` (*Connection* 메서드), 644
`send()` (*httplib.HTTPConnection* 메서드), 941
`send()` (*imaplib.IMAP4* 메서드), 954
`send()` (*logging.handlers.DatagramHandler* 메서드), 544
`send()` (*logging.handlers.SocketHandler* 메서드), 543
`send()` (*socket.socket* 메서드), 715
`send_bytes()` (*Connection* 메서드), 644
`send_error()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 985
`send_flowling_data()` (*formatter.writer* 메서드), 1350
`send_header()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 985
`send_hor_rule()` (*formatter.writer* 메서드), 1350
`send_label_data()` (*formatter.writer* 메서드), 1350
`send_line_break()` (*formatter.writer* 메서드), 1350
`send_literal_data()` (*formatter.writer* 메서드), 1350
`send_paragraph()` (*formatter.writer* 메서드), 1350
`send_response()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 985
`send_signal()` (*subprocess.Popen* 메서드), 701
`sendall()` (*socket.socket* 메서드), 715
`sendcmd()` (*ftplib.FTP* 메서드), 945
`sendfile()` (*wsgiref.handlers.BaseHandler* 메서드), 917
`sendmail()` (*smtplib.SMTP* 메서드), 962
`sendto()` (*socket.socket* 메서드), 715
`sep` (*os* 모듈), 439
`Separator()` (*FrameWork* 모듈), 1399
`sequence`
 iteration, 37
 types, mutable, 48
 types, operations on, 38, 48
 객체, 37
`Sequence` (*collections* 클래스), 185
`sequence` (*msilib* 모듈), 1359
`sequence` (시퀀스), 1446
`sequence2st()` (*parser* 모듈), 1310
`sequenceIncludes()` (*operator* 모듈), 282
`SequenceMatcher` (*difflib* 클래스), 109, 113
`SerialCookie` (*Cookie* 클래스), 998
`serializing`
 objects, 313
`serve_forever()` (*SocketServer.BaseServer* 메서드), 977
`server`
 WWW, 902, 983
`server` (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
`server_activate()` (*SocketServer.BaseServer* 메서드), 979
`server_address` (*SocketServer.BaseServer*의 속성), 978
`server_bind()` (*SocketServer.BaseServer* 메서드), 979
`server_close()` (*SocketServer.BaseServer* 메서드), 978
`server_software` (*wsgiref.handlers.BaseHandler*의 속성), 916
`server_version` (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
`server_version` (*SimpleHTTPServer.SimpleHTTPRequestHandler*의 속성), 987
`ServerProxy` (*xmlrpclib* 클래스), 1002
`session_stats()` (*ssl.SSLContext* 메서드), 735
`set`
 객체, 49
`Set` (*collections* 클래스), 185
`Set` (*sets* 클래스), 196
`set` (내장 클래스), 49
`Set Breakpoint`, 1132
`set()` (*ConfigParser.RawConfigParser* 메서드), 394
`set()` (*ConfigParser.SafeConfigParser* 메서드), 395
`set()` (*Cookie.Morsel* 메서드), 1000
`set()` (*EasyDialogs.ProgressBar* 메서드), 1398
`set()` (*ossaudiodev.oss_mixer_device* 메서드), 1035
`set()` (*test.support.EnvironmentVarGuard* 메서드), 1200
`set()` (*threading.Event* 메서드), 629
`set()` (*ttk.Combobox* 메서드), 1080
`set()` (*ttk.Treeview* 메서드), 1089
`set()` (*xml.etree.ElementTree.Element* 메서드), 857
`set_allowed_domains()` (*cookielib.DefaultCookiePolicy* 메서드), 995

`set_alpn_protocols()` (*ssl.SSLContext* 메서드), 734
`set_app()` (*wsgiref.simple_server.WSGIServer* 메서드), 913
`set_authorizer()` (*sqlite3.Connection* 메서드), 343
`set_blocked_domains()` (*cookielib.DefaultCookiePolicy* 메서드), 995
`set_boundary()` (*email.message.Message* 메서드), 763
`set_break()` (*bdb.Bdb* 메서드), 1206
`set_charset()` (*email.message.Message* 메서드), 759
`set_children()` (*ttk.Treeview* 메서드), 1087
`set_ciphers()` (*ssl.SSLContext* 메서드), 734
`set_completer()` (*readline* 모듈), 691
`set_completer_delims()` (*readline* 모듈), 691
`set_completion_display_matches_hook()` (*readline* 모듈), 691
`set_continue()` (*bdb.Bdb* 메서드), 1206
`set_conversion_mode()` (*ctypes* 모듈), 607
`set_cookie()` (*cookielib.CookieJar* 메서드), 991
`set_cookie_if_ok()` (*cookielib.CookieJar* 메서드), 991
`set_current()` (*msilib.Feature* 메서드), 1357
`set_date()` (*mailbox.MaildirMessage* 메서드), 807
`set_debug()` (*gc* 모듈), 1269
`set_debuglevel()` (*ftplib.FTP* 메서드), 945
`set_debuglevel()` (*httplib.HTTPConnection* 메서드), 941
`set_debuglevel()` (*nntplib.NNTP* 메서드), 957
`set_debuglevel()` (*poplib.POP3* 메서드), 948
`set_debuglevel()` (*smtpplib.SMTP* 메서드), 961
`set_debuglevel()` (*telnetlib.Telnet* 메서드), 966
`set_default_type()` (*email.message.Message* 메서드), 761
`set_default_verify_paths()` (*ssl.SSLContext* 메서드), 734
`set_defaults()` (*argparse.ArgumentParser* 메서드), 485
`set_defaults()` (*optparse.OptionParser* 메서드), 507
`set_ecdh_curve()` (*ssl.SSLContext* 메서드), 735
`set_errno()` (*ctypes* 모듈), 607
`set_event_call_back()` (*fl* 모듈), 1421
`set_executable()` (*multiprocessing* 모듈), 644
`set_flags()` (*mailbox.MaildirMessage* 메서드), 806
`set_flags()` (*mailbox.mboxMessage* 메서드), 808
`set_flags()` (*mailbox.MMDfMessage* 메서드), 812
`set_form_position()` (*fl.form* 메서드), 1422
`set_from()` (*mailbox.mboxMessage* 메서드), 808
`set_from()` (*mailbox.MMDfMessage* 메서드), 812
`set_graphics_mode()` (*fl* 모듈), 1421
`set_history_length()` (*readline* 모듈), 690
`set_info()` (*mailbox.MaildirMessage* 메서드), 807
`set_labels()` (*mailbox.BabylMessage* 메서드), 811
`set_last_error()` (*ctypes* 모듈), 607
`SET_LINENO(opcode)`, 1337
`set_literal(2to3 fixer)`, 1194
`set_location()` (*bsddb.bsddbobject* 메서드), 335
`set_next()` (*bdb.Bdb* 메서드), 1206
`set_nonstandard_attr()` (*cookielib.Cookie* 메서드), 997
`set_npn_protocols()` (*ssl.SSLContext* 메서드), 734
`set_ok()` (*cookielib.CookiePolicy* 메서드), 993
`set_option_negotiation_callback()` (*telnetlib.Telnet* 메서드), 967
`set_output_charset()` (*gettext.NullTranslations* 메서드), 1041
`set_param()` (*email.message.Message* 메서드), 762
`set_pasv()` (*ftplib.FTP* 메서드), 946
`set_payload()` (*email.message.Message* 메서드), 759
`set_policy()` (*cookielib.CookieJar* 메서드), 991
`set_position()` (*xdrlib.Unpacker* 메서드), 401
`set_pre_input_hook()` (*readline* 모듈), 691
`set_progress_handler()` (*sqlite3.Connection* 메서드), 344
`set_proxy()` (*urllib2.Request* 메서드), 929
`set_quit()` (*bdb.Bdb* 메서드), 1206
`set_recsrc()` (*ossaudiodev.oss_mixer_device* 메서드), 1036
`set_return()` (*bdb.Bdb* 메서드), 1206
`set_seq1()` (*difflib.SequenceMatcher* 메서드), 113
`set_seq2()` (*difflib.SequenceMatcher* 메서드), 113
`set_seqs()` (*difflib.SequenceMatcher* 메서드), 113
`set_sequences()` (*mailbox.MH* 메서드), 803
`set_sequences()` (*mailbox.MHMessage* 메서드), 810
`set_server_documentation()` (*DocXMLRPCServer.DocXMLRPCRequestHandler* 메서드), 1015
`set_server_documentation()` (*DocXMLRPCServer.DocXMLRPCServer* 메서드), 1014
`set_server_name()` (*DocXMLRPCServer.DocXMLRPCRequestHandler* 메서드), 1015
`set_server_name()` (*DocXMLRPCServer.DocXMLRPCServer* 메서드), 1014
`set_server_title()` (*DocXMLRPCServer.DocXMLRPCRequestHandler* 메서드), 1015
`set_server_title()` (*DocXMLRPCServer.DocXMLRPCServer* 메서드), 1014
`set_servername_callback()` (*ssl.SSLContext* 메서드), 734
`set_spacing()` (*formatter.formatter* 메서드), 1349
`set_startup_hook()` (*readline* 모듈), 691
`set_step()` (*bdb.Bdb* 메서드), 1206
`set_subdir()` (*mailbox.MaildirMessage* 메서드), 806
`set_terminator()` (*asynchat.async_chat* 메서드), 754
`set_threshold()` (*gc* 모듈), 1269

set_trace() (*bdb* 모듈), 1207
 set_trace() (*bdb.Bdb* 메서드), 1206
 set_trace() (*pdb* 모듈), 1209
 set_trace() (*pdb.Pdb* 메서드), 1209
 set_tunnel() (*httplib.HTTPConnection* 메서드), 941
 set_type() (*email.message.Message* 메서드), 762
 set_unittest_reportflags() (*doctest* 모듈), 1155
 set_unixfrom() (*email.message.Message* 메서드), 758
 set_until() (*bdb.Bdb* 메서드), 1206
 set_url() (*robotparser.RobotFileParser* 메서드), 398
 set_usage() (*optparse.OptionParser* 메서드), 507
 set_userptr() (*curses.panel.Panel* 메서드), 570
 set_visible() (*mailbox.BabylMessage* 메서드), 811
 set_wakeup_fd() (*signal* 모듈), 746
 setacl() (*imaplib.IMAP4* 메서드), 954
 setannotation() (*imaplib.IMAP4* 메서드), 954
 setarrowcursor() (*FrameWork* 모듈), 1399
 setattr() (내장 함수), 20
 setAttribute() (*xml.dom.Element* 메서드), 869
 setAttributeNode() (*xml.dom.Element* 메서드), 869
 setAttributeNodeNS() (*xml.dom.Element* 메서드), 869
 setAttributeNS() (*xml.dom.Element* 메서드), 869
 SetBase() (*xml.parsers.expat.xmlparser* 메서드), 891
 setblocking() (*socket.socket* 메서드), 715
 setBytesStream() (*xml.sax.xmlreader.InputSource* 메서드), 889
 setcbreak() (*tty* 모듈), 1377
 setCharacterStream() (*xml.sax.xmlreader.InputSource* 메서드), 889
 setcheckinterval() (*sys* 모듈), 1244
 setcomptype() (*aiifc.aiifc* 메서드), 1023
 setcomptype() (*sunau.AU_write* 메서드), 1026
 setcomptype() (*wave.Wave_write* 메서드), 1028
 setContentHandler() (*xml.sax.xmlreader.XMLReader* 메서드), 887
 setcontext() (*decimal* 모듈), 243
 setcontext() (*mhlib.MH* 메서드), 817
 SetCreatorAndType() (*MacOS* 모듈), 1393
 setcurrent() (*mhlib.Folder* 메서드), 818
 setDaemon() (*threading.Thread* 메서드), 625
 setdefault() (*dict* 메서드), 54
 setdefaultencoding() (*sys* 모듈), 1244
 setdefaulttimeout() (*socket* 모듈), 713
 setdlopenflags() (*sys* 모듈), 1244
 setDocumentLocator() (*xml.sax.handler.ContentHandler* 메서드), 882
 setDTDHandler() (*xml.sax.xmlreader.XMLReader* 메서드), 887
 setegid() (*os* 모듈), 414
 setEncoding() (*xml.sax.xmlreader.InputSource* 메서드), 888
 setEntityResolver() (*xml.sax.xmlreader.XMLReader* 메서드), 887
 setErrorHandler() (*xml.sax.xmlreader.XMLReader* 메서드), 887
 seteuid() (*os* 모듈), 414
 setFeature() (*xml.sax.xmlreader.XMLReader* 메서드), 887
 setfirstweekday() (*calendar* 모듈), 170
 setfmt() (*ossaudiodev.oss_audio_device* 메서드), 1033
 setFormatter() (*logging.Handler* 메서드), 521
 setframerate() (*aiifc.aiifc* 메서드), 1023
 setframerate() (*sunau.AU_write* 메서드), 1026
 setframerate() (*wave.Wave_write* 메서드), 1028
 setgid() (*os* 모듈), 414
 setgroups() (*os* 모듈), 414
 seth() (*turtle* 모듈), 1104
 setheading() (*turtle* 모듈), 1104
 SetInteger() (*msilib.Record* 메서드), 1356
 setitem() (*operator* 모듈), 283
 setitimer() (*signal* 모듈), 745
 setlast() (*mhlib.Folder* 메서드), 818
 setLevel() (*logging.Handler* 메서드), 521
 setLevel() (*logging.Logger* 메서드), 518
 setliteral() (*sgmlib.SGMLParser* 메서드), 843
 setlocale() (*locale* 모듈), 1047
 setLocale() (*xml.sax.xmlreader.XMLReader* 메서드), 887
 setLoggerClass() (*logging* 모듈), 529
 setlogmask() (*syslog* 모듈), 1387
 setmark() (*aiifc.aiifc* 메서드), 1023
 setMaxConns() (*urllib2.CacheFTPHandler* 메서드), 935
 setmode() (*msvcrt* 모듈), 1359
 setName() (*threading.Thread* 메서드), 624
 setnchannels() (*aiifc.aiifc* 메서드), 1023
 setnchannels() (*sunau.AU_write* 메서드), 1026
 setnchannels() (*wave.Wave_write* 메서드), 1028
 setnframes() (*aiifc.aiifc* 메서드), 1023
 setnframes() (*sunau.AU_write* 메서드), 1026
 setnframes() (*wave.Wave_write* 메서드), 1028
 setnomoretags() (*sgmlib.SGMLParser* 메서드), 843
 setoption() (*jpeg* 모듈), 1430
 SetParamEntityParsing() (*xml.parsers.expat.xmlparser* 메서드), 891
 setparameters() (*ossaudiodev.oss_audio_device* 메서드), 1034
 setparams() (*aiifc.aiifc* 메서드), 1023
 setparams() (*al* 모듈), 1416

- setparams() (*sunau.AU_write* 메서드), 1026
- setparams() (*wave.Wave_write* 메서드), 1028
- setpassword() (*zipfile.ZipFile* 메서드), 369
- setpath() (*fm* 모듈), 1426
- setpgid() (*os* 모듈), 415
- setpgrp() (*os* 모듈), 415
- setpos() (*aifc.aifc* 메서드), 1022
- setpos() (*sunau.AU_read* 메서드), 1025
- setpos() (*turtle* 모듈), 1103
- setpos() (*wave.Wave_read* 메서드), 1027
- setposition() (*turtle* 모듈), 1103
- setprofile() (*sys* 모듈), 1245
- setprofile() (*threading* 모듈), 622
- SetProperty() (*msilib.SummaryInformation* 메서드), 1355
- setProperty() (*xml.sax.xmlreader.XMLReader* 메서드), 887
- setPublicId() (*xml.sax.xmlreader.InputSource* 메서드), 888
- setquota() (*imaplib.IMAP4* 메서드), 954
- setraw() (*tty* 모듈), 1377
- setrecursionlimit() (*sys* 모듈), 1245
- setregid() (*os* 모듈), 415
- setresgid() (*os* 모듈), 415
- setresuid() (*os* 모듈), 415
- setreuid() (*os* 모듈), 415
- setrlimit() (*resource* 모듈), 1384
- sets(모듈), 196
- setsampwidth() (*aifc.aifc* 메서드), 1023
- setsampwidth() (*sunau.AU_write* 메서드), 1026
- setsampwidth() (*wave.Wave_write* 메서드), 1028
- setscrreg() (*curses.window* 메서드), 560
- setsid() (*os* 모듈), 415
- setslice() (*operator* 모듈), 283
- setsockopt() (*socket.socket* 메서드), 716
- setstate() (*random* 모듈), 260
- SetStream() (*msilib.Record* 메서드), 1356
- SetString() (*msilib.Record* 메서드), 1356
- setSystemId() (*xml.sax.xmlreader.InputSource* 메서드), 888
- setsyx() (*curses* 모듈), 553
- setTarget() (*logging.handlers.MemoryHandler* 메서드), 547
- settiltangle() (*turtle* 모듈), 1115
- settimeout() (*socket.socket* 메서드), 716
- setTimeout() (*urllib2.CacheFTPHandler* 메서드), 935
- settrace() (*sys* 모듈), 1245
- settrace() (*threading* 모듈), 622
- settsdump() (*sys* 모듈), 1246
- settypecreator() (*ic* 모듈), 1392
- settypecreator() (*ic.IC* 메서드), 1392
- setuid() (*os* 모듈), 415
- setundobuffer() (*turtle* 모듈), 1117
- setup() (*SocketServer.BaseRequestHandler* 메서드), 979
- setup() (*turtle* 모듈), 1124
- setUp() (*unittest.TestCase* 메서드), 1174
- setup=S
 timeit command line option, 1224
- setup_environ() (*wsgiref.handlers.BaseHandler* 메서드), 916
- SETUP_EXCEPT(*opcode*), 1336
- SETUP_FINALLY(*opcode*), 1336
- SETUP_LOOP(*opcode*), 1336
- setup_testing_defaults() (*wsgiref.util* 모듈), 911
- SETUP_WITH(*opcode*), 1334
- setUpClass() (*unittest.TestCase* 메서드), 1174
- setupterm() (*curses* 모듈), 553
- SetValue() (*_winreg* 모듈), 1364
- SetValueEx() (*_winreg* 모듈), 1365
- setwatchcursor() (*FrameWork* 모듈), 1399
- setworldcoordinates() (*turtle* 모듈), 1120
- setx() (*turtle* 모듈), 1103
- sety() (*turtle* 모듈), 1104
- SF_APPEND(*stat* 모듈), 299
- SF_ARCHIVED(*stat* 모듈), 299
- SF_IMMUTABLE(*stat* 모듈), 299
- SF_NOUNLINK(*stat* 모듈), 299
- SF_SNAPSHOT(*stat* 모듈), 299
- SGML, 842
- sgmlib
 모듈, 845
- sgmlib(모듈), 842
- SGMLParseError, 842
- SGMLParser(*in module sgmlib*), 845
- SGMLParser(*sgmlib* 클래스), 842
- sha(모듈), 410
- shape(*memoryview*의 속성), 61
- Shape(*turtle* 클래스), 1124
- shape() (*turtle* 모듈), 1114
- shapesize() (*turtle* 모듈), 1114
- Shelf(*shelve* 클래스), 326
- shelve
 모듈, 328
- shelve(모듈), 325
- shift() (*decimal.Context* 메서드), 249
- shift() (*decimal.Decimal* 메서드), 242
- shift_path_info() (*wsgiref.util* 모듈), 910
- shifting
 operations, 35
- shlex(*shlex* 클래스), 1058
- shlex(모듈), 1058
- shortDescription() (*unittest.TestCase* 메서드), 1180
- shouldFlush() (*logging.handlers.BufferingHandler* 메서드), 547

- `shouldFlush()` (*logging.handlers.MemoryHandler* 메서드), 547
- `shouldStop` (*unittest.TestResult*의 속성), 1184
- `show()` (*curses.panel.Panel* 메서드), 570
- `show_choice()` (*fl* 모듈), 1421
- `show_file_selector()` (*fl* 모듈), 1422
- `show_form()` (*fl.form* 메서드), 1422
- `show_input()` (*fl* 모듈), 1422
- `show_message()` (*fl* 모듈), 1421
- `show_question()` (*fl* 모듈), 1421
- `showsyntaxerror()` (*code.InteractiveInterpreter* 메서드), 1284
- `showtraceback()` (*code.InteractiveInterpreter* 메서드), 1284
- `showturtle()` (*turtle* 모듈), 1113
- `showwarning()` (*warnings* 모듈), 1256
- `shuffle()` (*random* 모듈), 261
- `shutdown()` (*findertools* 모듈), 1395
- `shutdown()` (*imaplib.IMAP4* 메서드), 954
- `shutdown()` (*logging* 모듈), 529
- `shutdown()` (*multiprocessing.managers.BaseManager* 메서드), 651
- `shutdown()` (*SocketServer.BaseServer* 메서드), 977
- `shutdown()` (*socket.socket* 메서드), 716
- `shutil` (모듈), 307
- `SIG_DFL` (*signal* 모듈), 744
- `SIG_IGN` (*signal* 모듈), 744
- `siginterrupt()` (*signal* 모듈), 746
- `signal`
 - 모듈, 632
- `signal` (모듈), 744
- `signal()` (*signal* 모듈), 746
- Simple Mail Transfer Protocol, 960
- SimpleCookie (*Cookie* 클래스), 998
- `simplefilter()` (*warnings* 모듈), 1256
- SimpleHandler (*wsgiref.handlers* 클래스), 915
- SimpleHTTPRequestHandler (*SimpleHTTPServer* 클래스), 987
- SimpleHTTPServer
 - 모듈, 983
- SimpleHTTPServer (모듈), 987
- SimpleXMLRPCRequestHandler (*SimpleXMLRPCServer* 클래스), 1010
- SimpleXMLRPCServer (*SimpleXMLRPCServer* 클래스), 1010
- SimpleXMLRPCServer (모듈), 1010
- `sin()` (*cmath* 모듈), 230
- `sin()` (*math* 모듈), 227
- `sinh()` (*cmath* 모듈), 231
- `sinh()` (*math* 모듈), 228
- `site` (모듈), 1277
- site command line option
 - `--user-base`, 1279
 - `--user-site`, 1279
- `sitecustomize`
 - 모듈, 1278
- site-packages
 - directory, 1277
- site-python
 - directory, 1277
- `size` (*struct.Struct*의 속성), 108
- `size` (*tarfile.TarInfo*의 속성), 378
- `size()` (*ftplib.FTP* 메서드), 947
- `size()` (*mmap.mmap* 메서드), 688
- Sized (*collections* 클래스), 185
- `sizeof()` (*ctypes* 모듈), 607
- SKIP (*doctest* 모듈), 1148
- `skip()` (*chunk.Chunk* 메서드), 1029
- `skip()` (*unittest* 모듈), 1173
- `skipIf()` (*unittest* 모듈), 1173
- `skipinitialspace` (*csv.Dialect*의 속성), 387
- `skipped` (*unittest.TestResult*의 속성), 1184
- `skippedEntity()` (*xml.sax.handler.ContentHandler* 메서드), 884
- SkipTest, 1174
- `skipTest()` (*unittest.TestCase* 메서드), 1175
- `skipUnless()` (*unittest* 모듈), 1173
- SLASH (*token* 모듈), 1321
- SLASHEQUAL (*token* 모듈), 1321
- `slave()` (*nntplib.NNTP* 메서드), 958
- `sleep()` (*findertools* 모듈), 1395
- `sleep()` (*time* 모듈), 454
- `slice`
 - assignment, 48
 - operation, 38
 - 내장 함수, 212, 1337
- `slice` (내장 클래스), 20
- `slice` (슬라이스), 1446
- SLICE+0 (*opcode*), 1333
- SLICE+1 (*opcode*), 1333
- SLICE+2 (*opcode*), 1333
- SLICE+3 (*opcode*), 1333
- SliceType (*types* 모듈), 212
- SmartCookie (*Cookie* 클래스), 998
- SMTP
 - protocol, 960
- SMTP (*smtplib* 클래스), 960
- SMTP_SSL (*smtplib* 클래스), 960
- SMTPAuthenticationError, 961
- SMTPConnectError, 961
- smtplib (모듈), 964
- SMTPDataError, 961
- SMTPException, 960
- SMTPHandler (*logging.handlers* 클래스), 546
- SMTPHeloError, 961
- smtplib (모듈), 960
- SMTPRecipientsRefused, 961
- SMTPResponseException, 960

- SMTPSenderRefused, 960
- SMTPServer (*smtpd* 클래스), 964
- SMTPServerDisconnected, 960
- SND_ALIAS (*winsound* 모듈), 1369
- SND_ASYNC (*winsound* 모듈), 1370
- SND_FILENAME (*winsound* 모듈), 1369
- SND_LOOP (*winsound* 모듈), 1369
- SND_MEMORY (*winsound* 모듈), 1369
- SND_NODEFAULT (*winsound* 모듈), 1370
- SND_NOSTOP (*winsound* 모듈), 1370
- SND_NOWAIT (*winsound* 모듈), 1370
- SND_PURGE (*winsound* 모듈), 1370
- sndhdr (모듈), 1031
- sniff() (*csv.Sniffer* 메서드), 386
- Sniffer (*csv* 클래스), 386
- SOCK_DGRAM (*socket* 모듈), 709
- SOCK_RAW (*socket* 모듈), 709
- SOCK_RDM (*socket* 모듈), 709
- SOCK_SEQPACKET (*socket* 모듈), 709
- SOCK_STREAM (*socket* 모듈), 709
- socket
 - 개체, 707
 - 모듈, 56, 899
- socket (*SocketServer.BaseServer*의 속성), 978
- socket (모듈), 707
- socket() (*imaplib.IMAP4* 메서드), 954
- socket() (*in module socket*), 616
- socket() (*socket* 모듈), 711
- socket_type (*SocketServer.BaseServer*의 속성), 978
- SocketHandler (*logging.handlers* 클래스), 543
- socketpair() (*socket* 모듈), 711
- SocketServer (모듈), 975
- SocketType (*socket* 모듈), 713
- softspace (*file*의 속성), 59
- SOMAXCONN (*socket* 모듈), 709
- sort() (*imaplib.IMAP4* 메서드), 954
- sort() (*list method*), 48
- sort_stats() (*pstats.Stats* 메서드), 1217
- sorted() (내장 함수), 20
- sortTestMethodsUsing (*unittest.TestLoader*의 속성), 1183
- source (*doctest.Example*의 속성), 1157
- source (*shlex.shlex*의 속성), 1060
- sourcehook() (*shlex.shlex* 메서드), 1059
- span() (*re.MatchObject* 메서드), 99
- spawn() (*pty* 모듈), 1378
- spawnl() (*os* 모듈), 434
- spawnle() (*os* 모듈), 434
- spawnlp() (*os* 모듈), 434
- spawnlpe() (*os* 모듈), 434
- spawnv() (*os* 모듈), 434
- spawnve() (*os* 모듈), 434
- spawnvp() (*os* 모듈), 434
- spawnvpe() (*os* 모듈), 434
- special
 - method, 1446
- special method (특수 메서드), 1446
- specified_attributes
 - (*xml.parsers.expat.xmlparser*의 속성), 892
- speed() (*ossaudiodev.oss_audio_device* 메서드), 1033
- speed() (*turtle* 모듈), 1106
- splash() (*MacOS* 모듈), 1394
- split() (*os.path* 모듈), 292
- split() (*re* 모듈), 94
- split() (*re.RegexObject* 메서드), 97
- split() (*shlex* 모듈), 1058
- split() (*str* 메서드), 43
- split() (*string* 모듈), 86
- splitdrive() (*os.path* 모듈), 292
- splitext() (*os.path* 모듈), 292
- splitfields() (*string* 모듈), 87
- splitlines() (*str* 메서드), 43
- splitlines() (*unicode* 메서드), 43
- SplitResult (*urlparse* 클래스), 975
- splitunc() (*os.path* 모듈), 292
- SpooledTemporaryFile() (*tempfile* 모듈), 302
- sprintf-style formatting, 46
- spwd (모듈), 1373
- sqlite3 (모듈), 338
- sqlite_version (*sqlite3* 모듈), 339
- sqlite_version_info (*sqlite3* 모듈), 339
- sqrt() (*cmath* 모듈), 230
- sqrt() (*decimal.Context* 메서드), 249
- sqrt() (*decimal.Decimal* 메서드), 242
- sqrt() (*math* 모듈), 227
- SSL, 719
- ssl (모듈), 719
- ssl() (*imaplib.IMAP4_SSL* 메서드), 955
- SSL_CERT_FILE, 743
- SSL_CERT_PATH, 743
- ssl_version (*ftplib.FTP_TLS*의 속성), 947
- SSLContext (*ssl* 클래스), 732
- SSLError, 720
- SSLError, 720
- SSLSyscallError, 720
- SSLWantReadError, 720
- SSLWantWriteError, 720
- SSLZeroReturnError, 720
- st() (*turtle* 모듈), 1113
- st2list() (*parser* 모듈), 1311
- st2tuple() (*parser* 모듈), 1311
- ST_ETIME (*stat* 모듈), 297
- ST_ETIME (*stat* 모듈), 297
- ST_DEV (*stat* 모듈), 296
- ST_GID (*stat* 모듈), 296
- ST_INO (*stat* 모듈), 296
- ST_MODE (*stat* 모듈), 296
- ST_MTIME (*stat* 모듈), 297

- ST_NLINK (*stat* 모듈), 296
 ST_SIZE (*stat* 모듈), 296
 ST_UID (*stat* 모듈), 296
 stack viewer, 1132
 stack () (*inspect* 모듈), 1277
 stack_size () (*thread* 모듈), 631
 stack_size () (*threading* 모듈), 622
 stackable
 streams, 123
 stamp () (*turtle* 모듈), 1105
 standard_b64decode () (*base64* 모듈), 831
 standard_b64encode () (*base64* 모듈), 831
 StandardError, 68
 standarderror (2to3 fixer), 1194
 standend () (*curses.window* 메서드), 560
 standout () (*curses.window* 메서드), 560
 STAR (*token* 모듈), 1321
 STAREQUAL (*token* 모듈), 1321
 starmap () (*itertools* 모듈), 273
 start (*exceptions.UnicodeError*의 속성), 71
 start () (*hotshot.Profile* 메서드), 1221
 start () (*multiprocessing.managers.BaseManager* 메서드), 651
 start () (*multiprocessing.Process* 메서드), 639
 start () (*re.MatchObject* 메서드), 99
 start () (*threading.Thread* 메서드), 623
 start () (*ttk.Progressbar* 메서드), 1083
 start () (*xml.etree.ElementTree.TreeBuilder* 메서드), 860
 start_color () (*curses* 모듈), 553
 start_component () (*msilib.Directory* 메서드), 1357
 start_new_thread () (*thread* 모듈), 631
 startbody () (*MimeWriter.MimeWriter* 메서드), 823
 StartCdataSectionHandler ()
 (*xml.parsers.expat.xmlparser* 메서드), 894
 --start-directory directory
 unittest-discover command line
 option, 1168
 StartDoctypeDeclHandler ()
 (*xml.parsers.expat.xmlparser* 메서드), 893
 startDocument () (*xml.sax.handler.ContentHandler*
 메서드), 882
 startElement () (*xml.sax.handler.ContentHandler* 메
 서드), 883
 StartElementHandler ()
 (*xml.parsers.expat.xmlparser* 메서드), 894
 startElementNS () (*xml.sax.handler.ContentHandler*
 메서드), 883
 STARTF_USESHOWWINDOW (*subprocess* 모듈), 703
 STARTF_USESTDHANDLES (*subprocess* 모듈), 703
 startfile () (*os* 모듈), 436
 startmultipartbody () (*MimeWriter.MimeWriter*
 메서드), 823
 StartNamespaceDeclHandler ()
 (*xml.parsers.expat.xmlparser* 메서드), 894
 startPrefixMapping ()
 (*xml.sax.handler.ContentHandler* 메서드),
 882
 startswith () (*str* 메서드), 44
 startTest () (*unittest.TestResult* 메서드), 1185
 startTestRun () (*unittest.TestResult* 메서드), 1185
 starttls () (*smtpplib.SMTP* 메서드), 962
 STARTUPINFO (*subprocess* 클래스), 702
 stat
 모듈, 428
 stat (모듈), 295
 stat () (*nntplib.NNTP* 메서드), 958
 stat () (*os* 모듈), 427
 stat () (*poplib.POP3* 메서드), 949
 stat_float_times () (*os* 모듈), 428
 state () (*ttk.Widget* 메서드), 1078
 statement (문장), 1446
 staticmethod () (내장 함수), 20
 Stats (*pstats* 클래스), 1216
 status (*httplib.HTTPResponse*의 속성), 942
 status () (*imaplib.IMAP4* 메서드), 954
 statvfs
 모듈, 428
 statvfs (모듈), 299
 statvfs () (*os* 모듈), 428
 STD_ERROR_HANDLE (*subprocess* 모듈), 703
 STD_INPUT_HANDLE (*subprocess* 모듈), 703
 STD_OUTPUT_HANDLE (*subprocess* 모듈), 703
 StdMessageBox (*Tix* 클래스), 1095
 stderr (*subprocess.Popen*의 속성), 702
 stderr (*sys* 모듈), 1246
 stdin (*subprocess.Popen*의 속성), 702
 stdin (*sys* 모듈), 1246
 STDOUT (*subprocess* 모듈), 697
 stdout (*subprocess.Popen*의 속성), 702
 stdout (*sys* 모듈), 1246
 Stein, Greg, 1340
 step () (*ttk.Progressbar* 메서드), 1083
 stereocontrols () (*ossaudiodev.oss_mixer_device* 메
 서드), 1035
 STILL (*cd* 모듈), 1418
 stop () (*hotshot.Profile* 메서드), 1221
 stop () (*ttk.Progressbar* 메서드), 1083
 stop () (*unittest.TestResult* 메서드), 1184
 STOP_CODE (*opcode*), 1331
 stop_here () (*bdb.Bdb* 메서드), 1205
 StopIteration, 70
 stopListening () (*logging.config* 모듈), 531
 stopTest () (*unittest.TestResult* 메서드), 1185
 stopTestRun () (*unittest.TestResult* 메서드), 1185
 storbinary () (*ftplib.FTP* 메서드), 946
 store () (*imaplib.IMAP4* 메서드), 954

- STORE_ACTIONS (*optparse.Option*의 속성), 513
- STORE_ATTR (*opcode*), 1335
- STORE_DEREF (*opcode*), 1337
- STORE_FAST (*opcode*), 1336
- STORE_GLOBAL (*opcode*), 1335
- STORE_MAP (*opcode*), 1336
- STORE_NAME (*opcode*), 1335
- STORE_SLICE+0 (*opcode*), 1333
- STORE_SLICE+1 (*opcode*), 1333
- STORE_SLICE+2 (*opcode*), 1333
- STORE_SLICE+3 (*opcode*), 1333
- STORE_SUBSCR (*opcode*), 1333
- storlines() (*ftplib.FTP* 메서드), 946
- str
 - format, 11
- str (내장 클래스), 21
- str() (*locale* 모듈), 1051
- strcoll() (*locale* 모듈), 1051
- StreamError, 374
- StreamHandler (*logging* 클래스), 540
- StreamReader (*codecs* 클래스), 130
- StreamReaderWriter (*codecs* 클래스), 131
- StreamRecoder (*codecs* 클래스), 131
- StreamRequestHandler (*SocketServer* 클래스), 979
- streams, 123
 - stackable, 123
- StreamWriter (*codecs* 클래스), 129
- strerror() (*os* 모듈), 415
- strftime() (*datetime.date* 메서드), 149
- strftime() (*datetime.datetime* 메서드), 155
- strftime() (*datetime.time* 메서드), 158
- strftime() (*time* 모듈), 454
- strict (*csv.Dialect*의 속성), 387
- strict_domain (*cookiecrlib.DefaultCookiePolicy*의 속성), 995
- strict_errors() (*codecs* 모듈), 125
- strict_ns_domain (*cookiecrlib.DefaultCookiePolicy*의 속성), 995
- strict_ns_set_initial_dollar (*cookiecrlib.DefaultCookiePolicy*의 속성), 995
- strict_ns_set_path (*cookiecrlib.DefaultCookiePolicy*의 속성), 995
- strict_ns_unverifiable (*cookiecrlib.DefaultCookiePolicy*의 속성), 995
- strict_rfc2965_unverifiable (*cookiecrlib.DefaultCookiePolicy*의 속성), 995
- strides (*memoryview*의 속성), 61
- string
 - formatting, 46
 - interpolation, 46
 - methods, 39
 - 객체, 37
 - 모듈, 47, 1051, 1052
- string (*re.MatchObject*의 속성), 100
- STRING (*token* 모듈), 1321
- string (모듈), 75
- string_at() (*ctypes* 모듈), 607
- StringIO (*io* 클래스), 450
- StringIO (*StringIO* 클래스), 119
- StringIO (모듈), 119
- StringIO() (*cStringIO* 모듈), 120
- stringprep (모듈), 139
- StringType (*types* 모듈), 212
- StringTypes (*types* 모듈), 213
- strip() (*str* 메서드), 44
- strip() (*string* 모듈), 87
- strip_dirs() (*pstats.Stats* 메서드), 1216
- stripspaces (*curses.textpad.Textbox*의 속성), 566
- strptime() (*datetime.datetime*의 클래스 메서드), 152
- strptime() (*time* 모듈), 455
- struct
 - 모듈, 716
- Struct (*struct* 클래스), 108
- struct (모듈), 104
- struct sequence (구조체 시퀀스), 1446
- struct_time (*time* 클래스), 455
- Structure (*ctypes* 클래스), 611
- structures
 - C, 104
- strxfrm() (*locale* 모듈), 1051
- SType (*parser* 모듈), 1312
- Style (*tk* 클래스), 1090
- StyledText (*aetypes* 클래스), 1411
- sub() (*operator* 모듈), 282
- sub() (*re* 모듈), 95
- sub() (*re.RegexObject* 메서드), 97
- subdirs (*filecmp.dircmp*의 속성), 301
- SubElement() (*xml.etree.ElementTree* 모듈), 856
- SubMenu() (*FrameWork* 모듈), 1399
- subn() (*re* 모듈), 96
- subn() (*re.RegexObject* 메서드), 97
- Subnormal (*decimal* 클래스), 250
- subpad() (*curses.window* 메서드), 560
- subprocess (모듈), 695
- subscribe() (*imaplib.IMAP4* 메서드), 954
- subscript
 - assignment, 48
 - operation, 38
- subsequent_indent (*textwrap.TextWrapper*의 속성), 122
- substitute() (*string.Template* 메서드), 84
- subtract() (*collections.Counter* 메서드), 173
- subtract() (*decimal.Context* 메서드), 249
- subversion (*sys* 모듈), 1246
- subwin() (*curses.window* 메서드), 560
- successful() (*multiprocessing.pool.AsyncResult* 메서드), 658
- suffix_map (*mimetypes* 모듈), 821

suffix_map (*mimetypes.MimeTypes*의 속성), 822
 suite() (*parser* 모듈), 1310
 suiteClass (*unittest.TestLoader*의 속성), 1183
 sum() (내장 함수), 21
 summarize() (*doctest.DocTestRunner* 메서드), 1160
 --summary
 trace command line option, 1227
 sunau (모듈), 1024
 SUNAUDIODEV
 모듈, 1431
 sunaudiodev
 모듈, 1433
 SUNAUDIODEV (모듈), 1433
 sunaudiodev (모듈), 1431
 super (*pyclbr.Class*의 속성), 1326
 super() (내장 함수), 21
 supports_unicode_filenames (*os.path* 모듈), 293
 SW_HIDE (*subprocess* 모듈), 703
 swapcase() (*str* 메서드), 44
 swapcase() (*string* 모듈), 87
 sym() (*dl.dl* 메서드), 1376
 sym_name (*symbol* 모듈), 1321
 Symbol (*syntable* 클래스), 1320
 symbol (모듈), 1321
 SymbolTable (*syntable* 클래스), 1319
 symlink() (*os* 모듈), 428
 symmetric_difference() (*frozenset* 메서드), 50
 symmetric_difference_update() (*frozenset* 메서드), 51
 syntable (모듈), 1319
 syntable() (*syntable* 모듈), 1319
 sync() (*bsddb.bsddbobject* 메서드), 336
 sync() (*dbhash.dbhash* 메서드), 334
 sync() (*dumbdbm.dumbdbm* 메서드), 338
 sync() (*gdbm* 모듈), 333
 sync() (*ossaudiodev.oss_audio_device* 메서드), 1034
 sync() (*shelve.Shelf* 메서드), 326
 syncdown() (*curses.window* 메서드), 560
 synchronized() (*multiprocessing.sharedctypes* 모듈), 649
 SyncManager (*multiprocessing.managers* 클래스), 652
 syncok() (*curses.window* 메서드), 560
 syncup() (*curses.window* 메서드), 560
 SyntaxErr, 871
 SyntaxError, 70
 SyntaxWarning, 72
 sys (모듈), 1235
 sys_exc (*2to3 fixer*), 1194
 sys_version (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
 SysBeep() (*MacOS* 모듈), 1393
 sysconf() (*os* 모듈), 439
 sysconf_names (*os* 모듈), 439

sysconfig (모듈), 1247
 syslog (모듈), 1387
 syslog() (*syslog* 모듈), 1387
 SysLogHandler (*logging.handlers* 클래스), 544
 system() (*os* 모듈), 436
 system() (*platform* 모듈), 572
 system_alias() (*platform* 모듈), 572
 SystemError, 70
 SystemExit, 70
 systemId (*xml.dom.DocumentType*의 속성), 867
 SystemRandom (*random* 클래스), 262
 SystemRoot, 700

T

-T
 trace command line option, 1227
 -t
 timeit command line option, 1224
 trace command line option, 1227
 unittest-discover command line option, 1168
 -t <zipfile>
 zipfile command line option, 372
 T_FMT (*locale* 모듈), 1049
 T_FMT_AMPM (*locale* 모듈), 1049
 tab() (*ttk.Notebook* 메서드), 1082
 TabError, 70
 tabnanny (모듈), 1325
 tabs() (*ttk.Notebook* 메서드), 1082
 tabular
 data, 383
 tag (*xml.etree.ElementTree.Element*의 속성), 857
 tag_bind() (*ttk.Treeview* 메서드), 1089
 tag_configure() (*ttk.Treeview* 메서드), 1089
 tag_has() (*ttk.Treeview* 메서드), 1089
 tagName (*xml.dom.Element*의 속성), 868
 tail (*xml.etree.ElementTree.Element*의 속성), 857
 takewhile() (*itertools* 모듈), 273
 TalkTo (*aetools* 클래스), 1409
 tan() (*cmath* 모듈), 230
 tan() (*math* 모듈), 227
 tanh() (*cmath* 모듈), 231
 tanh() (*math* 모듈), 228
 TarError, 373
 TarFile (*tarfile* 클래스), 373, 374
 tarfile (모듈), 372
 TarFileCompat (*tarfile* 클래스), 373
 TarFileCompat.TAR_GZIPPED (*tarfile* 모듈), 373
 TarFileCompat.TAR_PLAIN (*tarfile* 모듈), 373
 target (*xml.dom.ProcessingInstruction*의 속성), 870
 TarInfo (*tarfile* 클래스), 377
 task_done() (*multiprocessing.JoinableQueue* 메서드), 643
 task_done() (*Queue.Queue* 메서드), 203

- `tb_lineno()` (*traceback* 모듈), 1265
- `tcdrain()` (*termios* 모듈), 1377
- `tcflow()` (*termios* 모듈), 1377
- `tcflush()` (*termios* 모듈), 1377
- `tcgetattr()` (*termios* 모듈), 1376
- `tcgetpgrp()` (*os* 모듈), 420
- `Tcl()` (*Tkinter* 모듈), 1064
- `TCPServer` (*SocketServer* 클래스), 975
- `tcsendbreak()` (*termios* 모듈), 1377
- `tcsetattr()` (*termios* 모듈), 1377
- `tcsetpgrp()` (*os* 모듈), 420
- `tearDown()` (*unittest.TestCase* 메서드), 1174
- `tearDownClass()` (*unittest.TestCase* 메서드), 1175
- `tee()` (*itertools* 모듈), 273
- `tell()` (*aifc.aifc* 메서드), 1022, 1023
- `tell()` (*bz2.BZ2File* 메서드), 365
- `tell()` (*chunk.Chunk* 메서드), 1029
- `tell()` (*file* 메서드), 58
- `tell()` (*io.IOBase* 메서드), 444
- `tell()` (*io.TextIOBase* 메서드), 449
- `tell()` (*mmap.mmap* 메서드), 688
- `tell()` (*multifile.MultiFile* 메서드), 825
- `tell()` (*sunau.AU_read* 메서드), 1025
- `tell()` (*sunau.AU_write* 메서드), 1026
- `tell()` (*wave.Wave_read* 메서드), 1028
- `tell()` (*wave.Wave_write* 메서드), 1028
- `Telnet` (*telnetlib* 클래스), 965
- `telnetlib` (모듈), 965
- `TEMP`, 304
- `tempdir` (*tempfile* 모듈), 304
- `tempfile` (모듈), 302
- `Template` (*pipes* 클래스), 1380
- `Template` (*string* 클래스), 84
- `template` (*string.Template*의 속성), 84
- `template` (*tempfile* 모듈), 304
- `tempnam()` (*os* 모듈), 428
- `temporary`
 - `file`, 302
 - `file name`, 302
- `TemporaryFile()` (*tempfile* 모듈), 302
- `TERM`, 553, 554
- `termattrs()` (*curses* 모듈), 554
- `terminate()` (*multiprocessing.pool.multiprocessing.Pool* 메서드), 658
- `terminate()` (*multiprocessing.Process* 메서드), 640
- `terminate()` (*subprocess.Popen* 메서드), 702
- `termios` (모듈), 1376
- `termname()` (*curses* 모듈), 554
- `test` (*doctest.DocTestFailure*의 속성), 1163
- `test` (*doctest.UnexpectedException*의 속성), 1164
- `test` (모듈), 1195
- `test()` (*cgi* 모듈), 906
- `test()` (*mutex.mutex* 메서드), 201
- `TEST_HTTP_URL` (*test.support* 모듈), 1198
- `testandset()` (*mutex.mutex* 메서드), 201
- `TestCase` (*unittest* 클래스), 1174
- `TestFailed`, 1197
- `testfile()` (*doctest* 모듈), 1152
- `TESTFN` (*test.support* 모듈), 1198
- `TestLoader` (*unittest* 클래스), 1182
- `testMethodPrefix` (*unittest.TestLoader*의 속성), 1183
- `testmod()` (*doctest* 모듈), 1152
- `TestResult` (*unittest* 클래스), 1183
- `tests` (*imghdr* 모듈), 1031
- `testsource()` (*doctest* 모듈), 1162
- `testsRun` (*unittest.TestResult*의 속성), 1184
- `TestSuite` (*unittest* 클래스), 1181
- `test.support` (모듈), 1197
- `testzip()` (*zipfile.ZipFile* 메서드), 369
- `text` (*msilib* 모듈), 1359
- `text` (*xml.etree.ElementTree.Element*의 속성), 857
- `text()` (*msilib.Dialog* 메서드), 1358
- `text_factory` (*sqlite3.Connection*의 속성), 345
- `Textbox` (*curses.textpad* 클래스), 566
- `TextCalendar` (*calendar* 클래스), 169
- `textdomain()` (*gettext* 모듈), 1038
- `textdomain()` (*locale* 모듈), 1053
- `TextIOBase` (*io* 클래스), 448
- `TextIOWrapper` (*io* 클래스), 449
- `TextTestResult` (*unittest* 클래스), 1185
- `TextTestRunner` (*unittest* 클래스), 1185
- `textwrap` (모듈), 120
- `TextWrapper` (*textwrap* 클래스), 121
- `theme_create()` (*tk.Style* 메서드), 1092
- `theme_names()` (*tk.Style* 메서드), 1092
- `theme_settings()` (*tk.Style* 메서드), 1092
- `theme_use()` (*tk.Style* 메서드), 1092
- `THOUSEP` (*locale* 모듈), 1049
- `Thread` (*threading* 클래스), 623
- `thread` (모듈), 630
- `thread()` (*imaplib.IMAP4* 메서드), 954
- `ThreadError`, 622
- `threading` (모듈), 620
- `ThreadingMixIn` (*SocketServer* 클래스), 976
- `ThreadingTCPServer` (*SocketServer* 클래스), 977
- `ThreadingUDPServer` (*SocketServer* 클래스), 977
- `threads`
 - `IRIX`, 632
 - `POSIX`, 630
- `throw` (*2to3 fixer*), 1194
- `tie()` (*fl* 모듈), 1422
- `tigetflag()` (*curses* 모듈), 554
- `tigetnum()` (*curses* 모듈), 554
- `tigetstr()` (*curses* 모듈), 554
- `TILDE` (*token* 모듈), 1321
- `tilt()` (*turtle* 모듈), 1115
- `tiltangle()` (*turtle* 모듈), 1115

--time
 timeit command line option, 1224
time (*datetime* 클래스), 157
time (모듈), 452
time () (*datetime.datetime* 메서드), 153
time () (*time* 모듈), 456
Time2Internaldate () (*imaplib* 모듈), 951
timedelta (*datetime* 클래스), 145
TimedRotatingFileHandler (*logging.handlers* 클래스), 542
timegm () (*calendar* 모듈), 171
timeit (모듈), 1222
timeit command line option
 -c, 1224
 --clock, 1224
 -h, 1224
 --help, 1224
 -n N, 1224
 --number=N, 1224
 -r N, 1224
 --repeat=N, 1224
 -s S, 1224
 --setup=S, 1224
 -t, 1224
 --time, 1224
 -v, 1224
 --verbose, 1224
timeit () (*timeit* 모듈), 1223
timeit () (*timeit.Timer* 메서드), 1223
timeout, 709
timeout (*SocketServer.BaseServer*의 속성), 978
timeout () (*curses.window* 메서드), 560
TimeoutError, 660
Timer (*threading* 클래스), 629
Timer (*timeit* 클래스), 1223
times () (*os* 모듈), 436
timetuple () (*datetime.date* 메서드), 148
timetuple () (*datetime.datetime* 메서드), 154
timetz () (*datetime.datetime* 메서드), 153
timezone (*time* 모듈), 456
--timing
 trace command line option, 1227
title () (*EasyDialogs.ProgressBar* 메서드), 1397
title () (*str* 메서드), 44
title () (*turtle* 모듈), 1124
Tix, 1093
Tix (*Tix* 클래스), 1094
Tix (모듈), 1093
tix_addbitmapdir () (*Tix.tixCommand* 메서드), 1097
tix_cget () (*Tix.tixCommand* 메서드), 1097
tix_configure () (*Tix.tixCommand* 메서드), 1097
tix_filedialog () (*Tix.tixCommand* 메서드), 1097
tix_getbitmap () (*Tix.tixCommand* 메서드), 1097
tix_getimage () (*Tix.tixCommand* 메서드), 1097
TIX_LIBRARY, 1094
tix_option_get () (*Tix.tixCommand* 메서드), 1098
tix_resetoptions () (*Tix.tixCommand* 메서드), 1098
tixCommand (*Tix* 클래스), 1097
Tk, 1063
Tk (*Tkinter* 클래스), 1064
Tk Option Data Types, 1071
Tkinter, 1063
Tkinter (모듈), 1063
TList (*Tix* 클래스), 1096
TLS, 719
TMP, 304, 429
TMP_MAX (*os* 모듈), 429
TMPDIR, 304, 429
tmpfile () (*os* 모듈), 416
tmpnam () (*os* 모듈), 429
to_eng_string () (*decimal.Context* 메서드), 249
to_eng_string () (*decimal.Decimal* 메서드), 242
to_integral () (*decimal.Decimal* 메서드), 243
to_integral_exact () (*decimal.Context* 메서드), 249
to_integral_exact () (*decimal.Decimal* 메서드), 243
to_integral_value () (*decimal.Decimal* 메서드), 243
to_sci_string () (*decimal.Context* 메서드), 249
to_plittable () (*email.charset.Charset* 메서드), 773
ToASCII () (*encodings.idna* 모듈), 137
tobuf () (*tarfile.TarInfo* 메서드), 378
tobytes () (*memoryview* 메서드), 61
tochild (*popen2.Popen3*의 속성), 748
today () (*datetime.datetime*의 클래스 메서드), 151
today () (*datetime.date*의 클래스 메서드), 147
tofile () (*array.array* 메서드), 195
tok_name (*token* 모듈), 1321
token (*shlex.shlex*의 속성), 1060
token (모듈), 1321
TokenError, 1324
tokenize (모듈), 1323
tokenize () (*tokenize* 모듈), 1323
tolist () (*array.array* 메서드), 195
tolist () (*memoryview* 메서드), 61
tolist () (*parser.ST* 메서드), 1312
tomono () (*audioop* 모듈), 1019
toordinal () (*datetime.date* 메서드), 149
toordinal () (*datetime.datetime* 메서드), 154
top () (*curses.panel.Panel* 메서드), 570
top () (*poplib.POP3* 메서드), 949
top_panel () (*curses.panel* 모듈), 569
--top-level-directory directory

- unittest-discover command line option, 1168
- toprettyxml() (*xml.dom.minidom.Node* 메서드), 875
- tostereo() (*audioop* 모듈), 1019
- tostring() (*array.array* 메서드), 195
- tostring() (*xml.etree.ElementTree* 모듈), 856
- tostringlist() (*xml.etree.ElementTree* 모듈), 856
- total_changes (*sqlite3.Connection*의 속성), 346
- total_ordering() (*functools* 모듈), 277
- total_seconds() (*datetime.timedelta* 메서드), 146
- totuple() (*parser.ST* 메서드), 1312
- touched() (*macostools* 모듈), 1394
- touchline() (*curses.window* 메서드), 560
- touchwin() (*curses.window* 메서드), 561
- tounicode() (*array.array* 메서드), 195
- ToUnicode() (*encodings.idna* 모듈), 137
- tovideo() (*imageop* 모듈), 1020
- towards() (*turtle* 모듈), 1107
- toxml() (*xml.dom.minidom.Node* 메서드), 875
- tparm() (*curses* 모듈), 554
- trace
 - trace command line option, 1227
- Trace (*trace* 클래스), 1228
- trace (모듈), 1226
- trace command line option
 - C, 1227
 - c, 1227
 - count, 1227
 - coverdir=<dir>, 1227
 - f, 1227
 - file=<file>, 1227
 - g, 1227
 - help, 1227
 - ignore-dir=<dir>, 1228
 - ignore-module=<mod>, 1228
 - l, 1227
 - listfuncs, 1227
 - m, 1227
 - missing, 1227
 - no-report, 1227
 - R, 1227
 - r, 1227
 - report, 1227
 - s, 1227
 - summary, 1227
 - T, 1227
 - t, 1227
 - timing, 1227
 - trace, 1227
 - trackcalls, 1227
 - version, 1227
- trace function, 622, 1241, 1245
- trace() (*inspect* 모듈), 1277
- trace_dispatch() (*bdb.Bdb* 메서드), 1204
- traceback
 - 객체, 1236, 1263
- traceback (모듈), 1263
- traceback_limit (*wsgiref.handlers.BaseHandler*의 속성), 917
- tracebacklimit (*sys* 모듈), 1246
- tracebacks
 - in CGI scripts, 909
- TracebackType (*types* 모듈), 213
- tracer() (*turtle* 모듈), 1118, 1120
- trackcalls
 - trace command line option, 1227
- transfercmd() (*ftplib.FTP* 메서드), 946
- TransientResource (*test.support* 클래스), 1200
- translate() (*fnmatch* 모듈), 306
- translate() (*str* 메서드), 45
- translate() (*string* 모듈), 87
- translation() (*gettext* 모듈), 1039
- Transport Layer Security, 719
- Tree (*Tix* 클래스), 1096
- TreeBuilder (*xml.etree.ElementTree* 클래스), 860
- Treeview (*tk* 클래스), 1086
- triangular() (*random* 모듈), 261
- triple-quoted string (삼중 따옴표 된 문자열), 1447
- True, 32, 64
- true, 32
- True (내장 변수), 29
- truediv() (*operator* 모듈), 282
- trunc() (*in module math*), 34
- trunc() (*math* 모듈), 226
- truncate() (*file* 메서드), 59
- truncate() (*io.IOBase* 메서드), 444
- truth
 - value, 31
- truth() (*operator* 모듈), 280
- try
 - 글, 67
- ttk, 1074
- ttk (모듈), 1074
- ttob() (*imgfile* 모듈), 1429
- tty
 - I/O control, 1376
- tty (모듈), 1377
- ttyname() (*os* 모듈), 420
- tuple
 - 객체, 37
- tuple() (내장 함수), 22
- tuple2st() (*parser* 모듈), 1311
- tuple_params (*2to3 fixer*), 1194
- TupleType (*types* 모듈), 212
- turnoff_sigfpe() (*fpectl* 모듈), 1281
- turnon_sigfpe() (*fpectl* 모듈), 1281
- Turtle (*turtle* 클래스), 1124

- turtle (모듈), 1098
- turtles () (*turtle* 모듈), 1123
- TurtleScreen (*turtle* 클래스), 1124
- turtlesize () (*turtle* 모듈), 1114
- Tutt, Bill, 1340
- type
 - Boolean, 6
 - operations on dictionary, 52
 - operations on list, 48
 - 객체, 22
 - 내장 함수, 64, 211
- Type (*aetypes* 클래스), 1411
- type (*optparse.Option*의 속성), 501
- type (*socket.socket*의 속성), 716
- type (*tarfile.TarInfo*의 속성), 378
- type (내장 클래스), 22
- type (형), 1447
- TYPE_CHECKER (*optparse.Option*의 속성), 512
- typeahead () (*curses* 모듈), 554
- typecode (*array.array*의 속성), 194
- TYPED_ACTIONS (*optparse.Option*의 속성), 513
- typed_subpart_iterator () (*email.iterators* 모듈), 778
- TypeError, 71
- types
 - built-in, 31
 - mutable sequence, 48
 - operations on integer, 35
 - operations on mapping, 52
 - operations on numeric, 34
 - operations on sequence, 38, 48
 - 모듈, 64
- types (2to3 fixer), 1194
- TYPES (*optparse.Option*의 속성), 512
- types (모듈), 211
- types_map (*mimetypes* 모듈), 821
- types_map (*mimetypes.MimeTypes*의 속성), 822
- types_map_inv (*mimetypes.MimeTypes*의 속성), 822
- TypeType (*types* 모듈), 211
- TZ, 456, 457
- tzinfo (*datetime* 클래스), 159
- tzinfo (*datetime.datetime*의 속성), 152
- tzinfo (*datetime.time*의 속성), 158
- tzname (*time* 모듈), 456
- tzname () (*datetime.datetime* 메서드), 154
- tzname () (*datetime.time* 메서드), 159
- tzname () (*datetime.tzinfo* 메서드), 160
- tzset () (*time* 모듈), 456
- UF_APPEND (*stat* 모듈), 298
- UF_COMPRESSED (*stat* 모듈), 298
- UF_HIDDEN (*stat* 모듈), 299
- UF_IMMUTABLE (*stat* 모듈), 298
- UF_NODUMP (*stat* 모듈), 298
- UF_NOUNLINK (*stat* 모듈), 298
- UF_OPAQUE (*stat* 모듈), 298
- ugettext () (*gettext.GNUTranslations* 메서드), 1042
- ugettext () (*gettext.NullTranslations* 메서드), 1040
- uid (*tarfile.TarInfo*의 속성), 378
- uid () (*imaplib.IMAP4* 메서드), 955
- uidl () (*poplib.POP3* 메서드), 949
- u-LAW, 1017, 1023, 1031, 1431
- ulaw2lin () (*audioop* 모듈), 1019
- umask () (*os* 모듈), 415
- uname (*tarfile.TarInfo*의 속성), 378
- uname () (*os* 모듈), 415
- uname () (*platform* 모듈), 572
- UNARY_CONVERT (*opcode*), 1331
- UNARY_INVERT (*opcode*), 1331
- UNARY_NEGATIVE (*opcode*), 1331
- UNARY_NOT (*opcode*), 1331
- UNARY_POSITIVE (*opcode*), 1331
- UnboundLocalError, 71
- UnboundMethodType (*types* 모듈), 212
- unbuffered I/O, 15
- UNC paths
 - and *os.makedirs* (), 425
- unconsumed_tail (*zlib.Decompress*의 속성), 361
- unctrl () (*curses* 모듈), 554
- unctrl () (*curses.ascii* 모듈), 569
- Underflow (*decimal* 클래스), 250
- undo () (*turtle* 모듈), 1106
- undobufferentries () (*turtle* 모듈), 1117
- undoc_header (*cmd.Cmd*의 속성), 1057
- unescape () (*xml.sax.saxutils* 모듈), 885
- UnexpectedException, 1163
- unexpectedSuccesses (*unittest.TestResult*의 속성), 1184
- unfreeze_form () (*fl.form* 메서드), 1422
- ungetch () (*curses* 모듈), 554
- ungetch () (*msvcrt* 모듈), 1360
- ungetmouse () (*curses* 모듈), 554
- ungettext () (*gettext.GNUTranslations* 메서드), 1042
- ungettext () (*gettext.NullTranslations* 메서드), 1041
- ungetwch () (*msvcrt* 모듈), 1360
- unhexlify () (*binascii* 모듈), 835
- unichr () (내장 함수), 22
- Unicode, 123, 138
 - database, 138
 - 객체, 37
- unicode (2to3 fixer), 1194
- UNICODE (*re* 모듈), 94
- unicode () (내장 함수), 22

- unicodedata (모듈), 138
- UnicodeDecodeError, 71
- UnicodeEncodeError, 71
- UnicodeError, 71
- UnicodeTranslateError, 71
- UnicodeType (*types* 모듈), 212
- UnicodeWarning, 72
- unidata_version (*unicodedata* 모듈), 139
- unified_diff() (*difflib* 모듈), 112
- uniform() (*random* 모듈), 261
- UnimplementedFileMode, 938
- uninstall() (*imputil.ImportManager* 메서드), 1297
- Union (*ctypes* 클래스), 611
- union() (*frozenset* 메서드), 50
- unittest (모듈), 1165
- unittest command line option
 - b, 1168
 - buffer, 1168
 - c, 1168
 - catch, 1168
 - f, 1168
 - failfast, 1168
- unittest-discover command line option
 - p, 1168
 - pattern pattern, 1168
 - s, 1168
 - start-directory directory, 1168
 - t, 1168
 - top-level-directory directory, 1168
 - v, 1168
 - verbose, 1168
- universal newlines
 - bz2.BZ2File class, 364
 - file.newlines attribute, 59
 - io.IncrementalNewlineDecoder class, 450
 - io.TextIOWrapper class, 449
 - open() (*in module io*), 442
 - open() built-in function, 15
 - str.splitlines method, 43
 - subprocess module, 698
 - zipfile.ZipFile.open method, 368
- universal newlines (유니버설 줄 넘김), 1447
- UNIX
 - file control, 1378
 - I/O control, 1378
- UnixDatagramServer (*SocketServer* 클래스), 975
- unixfrom(*rfc822.Message*의 속성), 830
- UnixMailbox (*mailbox* 클래스), 814
- UnixStreamServer (*SocketServer* 클래스), 975
- Unknown (*aetypes* 클래스), 1411
- unknown_charref() (*sgmlib.SGMLParser* 메서드), 844
- unknown_decl() (*HTMLParser.HTMLParser* 메서드), 840
- unknown_endtag() (*sgmlib.SGMLParser* 메서드), 844
- unknown_entityref() (*sgmlib.SGMLParser* 메서드), 844
- unknown_open() (*urllib2.BaseHandler* 메서드), 931
- unknown_open() (*urllib2.UnknownHandler* 메서드), 935
- unknown_starttag() (*sgmlib.SGMLParser* 메서드), 844
- UnknownHandler (*urllib2* 클래스), 928
- UnknownProtocol, 938
- UnknownTransferEncoding, 938
- unlink() (*os* 모듈), 429
- unlink() (*xml.dom.minidom.Node* 메서드), 874
- unlock() (*mailbox.Babyl* 메서드), 804
- unlock() (*mailbox.Mailbox* 메서드), 800
- unlock() (*mailbox.Maildir* 메서드), 801
- unlock() (*mailbox.mbox* 메서드), 802
- unlock() (*mailbox.MH* 메서드), 803
- unlock() (*mailbox.MMDF* 메서드), 805
- unlock() (*mutex.mutex* 메서드), 201
- unmimify() (*mimify* 모듈), 824
- unpack() (*aepack* 모듈), 1410
- unpack() (*struct* 모듈), 104
- unpack() (*struct.Struct* 메서드), 108
- unpack_array() (*xdrlib.Unpacker* 메서드), 402
- unpack_bytes() (*xdrlib.Unpacker* 메서드), 402
- unpack_double() (*xdrlib.Unpacker* 메서드), 401
- unpack_farray() (*xdrlib.Unpacker* 메서드), 402
- unpack_float() (*xdrlib.Unpacker* 메서드), 401
- unpack_fopaque() (*xdrlib.Unpacker* 메서드), 402
- unpack_from() (*struct* 모듈), 105
- unpack_from() (*struct.Struct* 메서드), 108
- unpack_fstring() (*xdrlib.Unpacker* 메서드), 401
- unpack_list() (*xdrlib.Unpacker* 메서드), 402
- unpack_opaque() (*xdrlib.Unpacker* 메서드), 402
- UNPACK_SEQUENCE (*opcode*), 1335
- unpack_string() (*xdrlib.Unpacker* 메서드), 402
- Unpacker (*xdrlib* 클래스), 400
- unpackevent() (*aetools* 모듈), 1409
- unparsedEntityDecl()
 - (*xml.sax.handler.DTDHandler* 메서드), 884
- UnparsedEntityDeclHandler()
 - (*xml.parsers.expat.xmlparser* 메서드), 894
- Unpickler (*pickle* 클래스), 316
- UnpicklingError, 316
- unqdevice() (*fl* 모듈), 1422
- unquote() (*email.utils* 모듈), 777
- unquote() (*rfc822* 모듈), 828
- unquote() (*urllib* 모듈), 921
- unquote_plus() (*urllib* 모듈), 921
- unregister() (*select.epoll* 메서드), 617

unregister() (*select.poll* 메서드), 618
 unregister_archive_format() (*shutil* 모듈), 311
 unregister_dialect() (*csv* 모듈), 385
 unset() (*test.support.EnvironmentVarGuard* 메서드), 1201
 unsetenv() (*os* 모듈), 416
 unsubscribe() (*imaplib.IMAP4* 메서드), 955
 UnsupportedOperation, 442
 untokenize() (*tokenize* 모듈), 1324
 untouchwin() (*curses.window* 메서드), 561
 unused_data (*zlib.Decompress*의 속성), 361
 unwrap() (*ssl.SSLSocket* 메서드), 732
 up() (*turtle* 모듈), 1109
 update() (*collections.Counter* 메서드), 173
 update() (*dict* 메서드), 54
 update() (*frozenset* 메서드), 51
 update() (*hashlib.hash* 메서드), 406
 update() (*hmac.HMAC* 메서드), 408
 update() (*mailbox.Mailbox* 메서드), 800
 update() (*mailbox.Maildir* 메서드), 801
 update() (*md5.md5* 메서드), 409
 update() (*sha.sha* 메서드), 410
 update() (*trace.CoverageResults* 메서드), 1228
 update() (*turtle* 모듈), 1120
 update_panels() (*curses.panel* 모듈), 569
 update_visible() (*mailbox.BabylMessage* 메서드), 811
 update_wrapper() (*functools* 모듈), 278
 updatescrollbars() (*FrameWork.ScrolledWindow* 메서드), 1401
 upper() (*str* 메서드), 45
 upper() (*string* 모듈), 87
 uppercase(*string* 모듈), 76
 urandom() (*os* 모듈), 440
 URL, 398, 902, 918, 971, 983
 parsing, 971
 relative, 971
 url (*xmlrpclib.ProtocolError*의 속성), 1007
 url2pathname() (*urllib* 모듈), 921
 urlcleanup() (*urllib* 모듈), 921
 urldefrag() (*urlparse* 모듈), 974
 urlencode() (*urllib* 모듈), 921
 URLError, 926
 urljoin() (*urlparse* 모듈), 974
 urllib
 모듈, 937
 urllib (2to3 fixer), 1194
 urllib(모듈), 918
 urllib2(모듈), 925
 urlopen() (*urllib* 모듈), 919
 urlopen() (*urllib2* 모듈), 925
 URLOpener (*urllib* 클래스), 922
 urlparse
 모듈, 924
 urlparse(모듈), 971
 urlparse() (*urlparse* 모듈), 971
 urlretrieve() (*urllib* 모듈), 920
 urlsafe_b64decode() (*base64* 모듈), 831
 urlsafe_b64encode() (*base64* 모듈), 831
 urlsplit() (*urlparse* 모듈), 973
 urlunparse() (*urlparse* 모듈), 973
 urlunsplit() (*urlparse* 모듈), 973
 urn (*uuid.UUID*의 속성), 969
 use_default_colors() (*curses* 모듈), 554
 use_env() (*curses* 모듈), 554
 use_rawinput (*cmd.Cmd*의 속성), 1057
 UseForeignDTD() (*xml.parsers.expat.xmlparser* 메서드), 892
 USER, 548
 user
 configuration file, 1279
 effective id, 413
 id, 414
 id, setting, 415
 user(모듈), 1279
 user() (*poplib.POP3* 메서드), 949
 USER_BASE (*site* 모듈), 1278
 user_call() (*bdb.Bdb* 메서드), 1205
 user_exception() (*bdb.Bdb* 메서드), 1205
 user_line() (*bdb.Bdb* 메서드), 1205
 user_return() (*bdb.Bdb* 메서드), 1205
 USER_SITE (*site* 모듈), 1278
 --user-base
 site command line option, 1279
 usercustomize
 모듈, 1278
 UserDict (*UserDict* 클래스), 208
 UserDict(모듈), 208
 UserList (*UserList* 클래스), 209
 UserList(모듈), 209
 USERNAME, 548
 USERPROFILE, 290
 userptr() (*curses.panel.Panel* 메서드), 570
 --user-site
 site command line option, 1279
 UserString (*UserString* 클래스), 210
 UserString(모듈), 210
 UserWarning, 72
 USTAR_FORMAT (*tarfile* 모듈), 374
 UTC, 452
 utcfromtimestamp() (*datetime.datetime*의 클래스 메서드), 151
 utcnow() (*datetime.datetime*의 클래스 메서드), 151
 utcoffset() (*datetime.datetime* 메서드), 154
 utcoffset() (*datetime.time* 메서드), 158
 utcoffset() (*datetime.tzinfo* 메서드), 159
 utctimetuple() (*datetime.datetime* 메서드), 154

`utime()` (*os* 모듈), 429`uu`

모듈, 833

`uu` (모듈), 836`UUID` (*uuid* 클래스), 968`uuid` (모듈), 968`uuid1`, 969`uuid1()` (*uuid* 모듈), 969`uuid3`, 969`uuid3()` (*uuid* 모듈), 969`uuid4`, 969`uuid4()` (*uuid* 모듈), 969`uuid5`, 969`uuid5()` (*uuid* 모듈), 969`UuidCreate()` (*msilib* 모듈), 1353

V

`-v`

timeit command line option, 1224

unittest-discover command line option, 1168

`validator()` (*wsgiref.validate* 모듈), 914`value`

truth, 31

`value` (*cookielib.Cookie*의 속성), 996`value` (*Cookie.Morsel*의 속성), 1000`value` (*ctypes._SimpleCData*의 속성), 609`value` (*xml.dom.Attr*의 속성), 869`Value()` (*multiprocessing* 모듈), 648`Value()` (*multiprocessing.managers.SyncManager* 메서드), 652`Value()` (*multiprocessing.sharedctypes* 모듈), 649`value_decode()` (*Cookie.BaseCookie* 메서드), 999`value_encode()` (*Cookie.BaseCookie* 메서드), 999`ValueError`, 71`valuerefs()` (*weakref.WeakValueDictionary* 메서드), 206`values`

Boolean, 64

`values()` (*dict* 메서드), 55`values()` (*email.message.Message* 메서드), 760`values()` (*mailbox.Mailbox* 메서드), 799`ValuesView` (*collections* 클래스), 186`variant` (*uuid.UUID*의 속성), 969`varray()` (*gl* 모듈), 1427`vars()` (내장 함수), 23`vbar` (*ScrolledText.ScrolledText*의 속성), 1098`VBAR` (*token* 모듈), 1321`VBAREQUAL` (*token* 모듈), 1321`Vec2D` (*turtle* 클래스), 1125`--verbose`

timeit command line option, 1224

unittest-discover command line option, 1168

`VERBOSE` (*re* 모듈), 94`verbose` (*tabnanny* 모듈), 1325`verbose` (*test.support* 모듈), 1198`verify()` (*smtplib.SMTP* 메서드), 962`VERIFY_CRL_CHECK_CHAIN` (*ssl* 모듈), 726`VERIFY_CRL_CHECK_LEAF` (*ssl* 모듈), 726`VERIFY_DEFAULT` (*ssl* 모듈), 726`verify_flags` (*ssl.SSLContext*의 속성), 736`verify_mode` (*ssl.SSLContext*의 속성), 736`verify_request()` (*SocketServer.BaseServer* 메서드), 979`VERIFY_X509_STRICT` (*ssl* 모듈), 726`VERIFY_X509_TRUSTED_FIRST` (*ssl* 모듈), 726`--version`

trace command line option, 1227

`version` (*cookielib.Cookie*의 속성), 996`version` (*curses* 모듈), 561`version` (*httplib.HTTPResponse*의 속성), 942`version` (*marshal* 모듈), 329`version` (*sqlite3* 모듈), 339`version` (*sys* 모듈), 1247`version` (*urllib.URLopener*의 속성), 923`version` (*uuid.UUID*의 속성), 969`version()` (*ensurepip* 모듈), 1233`version()` (*platform* 모듈), 572`version()` (*ssl.SSLSocket* 메서드), 732`version_info` (*sqlite3* 모듈), 339`version_info` (*sys* 모듈), 1247`version_string()` (*BaseHTTPServer.BaseHTTPRequestHandler* 메서드), 986`vformat()` (*string.Formatter* 메서드), 76`videoreader` (모듈), 1437`viewitems()` (*dict* 메서드), 55`viewkeys()` (*dict* 메서드), 55`viewvalues()` (*dict* 메서드), 55

virtual environment (가상 환경), 1447

virtual machine (가상 기계), 1447

`visit()` (*ast.NodeVisitor* 메서드), 1318`vline()` (*curses.window* 메서드), 561`VMSError`, 71`vnarray()` (*gl* 모듈), 1428`voidcmd()` (*ftplib.FTP* 메서드), 946`volume` (*zipfile.ZipInfo*의 속성), 371`vonmisesvariate()` (*random* 모듈), 262

W

`W` (모듈), 1437`W_OK` (*os* 모듈), 422`wait()` (*multiprocessing.pool.AsyncResult* 메서드), 658`wait()` (*os* 모듈), 437`wait()` (*popen2.Popen3* 메서드), 748`wait()` (*subprocess.Popen* 메서드), 701`wait()` (*threading.Condition* 메서드), 627

- `wait()` (*threading.Event* 메서드), 629
- `wait3()` (*os* 모듈), 437
- `wait4()` (*os* 모듈), 437
- `waitpid()` (*os* 모듈), 437
- `walk()` (*ast* 모듈), 1318
- `walk()` (*compiler* 모듈), 1339
- `walk()` (*compiler.visitor* 모듈), 1346
- `walk()` (*email.message.Message* 메서드), 763
- `walk()` (*os* 모듈), 429
- `walk()` (*os.path* 모듈), 292
- `walk_packages()` (*pkgutil* 모듈), 1304
- `want` (*doctest.Example*의 속성), 1157
- `warn()` (*warnings* 모듈), 1256
- `warn_explicit()` (*warnings* 모듈), 1256
- `Warning`, 72
- `warning()` (*logging* 모듈), 527
- `warning()` (*logging.Logger* 메서드), 519
- `warning()` (*xml.sax.handler.ErrorHandler* 메서드), 885
- `warnings`, 1252
- `warnings` (모듈), 1252
- `WarningsRecorder` (*test.support* 클래스), 1201
- `warnoptions` (*sys* 모듈), 1247
- `warnpy3k()` (*warnings* 모듈), 1256
- `wasSuccessful()` (*unittest.TestResult* 메서드), 1184
- `WatchedFileHandler` (*logging.handlers* 클래스), 541
- `wave` (모듈), 1026
- `WCONTINUED` (*os* 모듈), 437
- `WCOREDUMP()` (*os* 모듈), 438
- `WeakKeyDictionary` (*weakref* 클래스), 205
- `weakref` (모듈), 204
- `WeakSet` (*weakref* 클래스), 206
- `WeakValueDictionary` (*weakref* 클래스), 206
- `webbrowser` (모듈), 899
- `weekday()` (*calendar* 모듈), 171
- `weekday()` (*datetime.date* 메서드), 149
- `weekday()` (*datetime.datetime* 메서드), 154
- `weekheader()` (*calendar* 모듈), 171
- `weibullvariate()` (*random* 모듈), 262
- `WEXITSTATUS()` (*os* 모듈), 438
- `wfile` (*BaseHTTPServer.BaseHTTPRequestHandler*의 속성), 984
- `what()` (*imghdr* 모듈), 1030
- `what()` (*sndhdr* 모듈), 1031
- `whathdr()` (*sndhdr* 모듈), 1031
- `whichdb` (모듈), 330
- `whichdb()` (*whichdb* 모듈), 330
- `while`
 - 글, 31
- `whitespace` (*shlex.shlex*의 속성), 1059
- `whitespace` (*string* 모듈), 76
- `whitespace_split` (*shlex.shlex*의 속성), 1060
- `whseed()` (*random* 모듈), 262
- `WichmannHill` (*random* 클래스), 262
- `Widget` (*tk* 클래스), 1078
- `width` (*textwrap.TextWrapper*의 속성), 121
- `width()` (*turtle* 모듈), 1109
- `WIFCONTINUED()` (*os* 모듈), 438
- `WIFEXITED()` (*os* 모듈), 438
- `WIFSIGNALED()` (*os* 모듈), 438
- `WIFSTOPPED()` (*os* 모듈), 438
- `Wimp$ScrapDir`, 304
- `win32_ver()` (*platform* 모듈), 572
- `WinDLL` (*ctypes* 클래스), 600
- `window manager` (*widgets*), 1071
- `window()` (*curses.panel.Panel* 메서드), 570
- `Window()` (*FrameWork* 모듈), 1399
- `window_height()` (*turtle* 모듈), 1118, 1123
- `window_width()` (*turtle* 모듈), 1118, 1123
- `windowbounds()` (*FrameWork* 모듈), 1399
- `Windows ini file`, 391
- `WindowsError`, 71
- `WinError()` (*ctypes* 모듈), 607
- `WINFUNCTYPE()` (*ctypes* 모듈), 603
- `WinSock`, 616
- `winsound` (모듈), 1369
- `winver` (*sys* 모듈), 1247
- `WITH_CLEANUP` (*opcode*), 1334
- `WMAvailable()` (*MacOS* 모듈), 1394
- `WNOHANG` (*os* 모듈), 437
- `wordchars` (*shlex.shlex*의 속성), 1059
- `World Wide Web`, 398, 899, 918, 971
- `wrap()` (*textwrap* 모듈), 120
- `wrap()` (*textwrap.TextWrapper* 메서드), 123
- `wrap_socket()` (*ssl* 모듈), 721
- `wrap_socket()` (*ssl.SSLContext* 메서드), 735
- `wrapper()` (*curses* 모듈), 555
- `wraps()` (*functools* 모듈), 279
- `WRITABLE` (*Tkinter* 모듈), 1074
- `writable()` (*asyncore.dispatcher* 메서드), 751
- `writable()` (*io.IOBase* 메서드), 444
- `write()` (*array.array* 메서드), 195
- `write()` (*bz2.BZ2File* 메서드), 365
- `write()` (*codecs.StreamWriter* 메서드), 129
- `write()` (*code.InteractiveInterpreter* 메서드), 1284
- `write()` (*ConfigParser.RawConfigParser* 메서드), 394
- `write()` (*email.generator.Generator* 메서드), 767
- `write()` (*file* 메서드), 59
- `write()` (*imgfile* 모듈), 1429
- `write()` (*io.BufferedIOBase* 메서드), 446
- `write()` (*io.BufferedWriter* 메서드), 448
- `write()` (*io.RawIOBase* 메서드), 445
- `write()` (*io.TextIOBase* 메서드), 449
- `write()` (*mmap.mmap* 메서드), 688
- `write()` (*os* 모듈), 420
- `write()` (*ossaudiodev.oss_audio_device* 메서드), 1033
- `write()` (*telnetlib.Telnet* 메서드), 967

`write()` (*turtle* 모듈), 1113
`write()` (*xml.etree.ElementTree.ElementTree* 메서드), 859
`write()` (*zipfile.ZipFile* 메서드), 369
`write_byte()` (*mmap.mmap* 메서드), 689
`write_docstringdict()` (*turtle* 모듈), 1127
`write_history_file()` (*readline* 모듈), 690
`write_results()` (*trace.CoverageResults* 메서드), 1228
`writeall()` (*ossaudiodev.oss_audio_device* 메서드), 1033
`writeframes()` (*aifc.aifc* 메서드), 1023
`writeframes()` (*sunau.AU_write* 메서드), 1026
`writeframes()` (*wave.Wave_write* 메서드), 1028
`writeframesraw()` (*aifc.aifc* 메서드), 1023
`writeframesraw()` (*sunau.AU_write* 메서드), 1026
`writeframesraw()` (*wave.Wave_write* 메서드), 1028
`writeheader()` (*csv.DictWriter* 메서드), 388
`writelines()` (*bz2.BZ2File* 메서드), 365
`writelines()` (*codecs.StreamWriter* 메서드), 129
`writelines()` (*file* 메서드), 59
`writelines()` (*io.IOWrapper* 메서드), 444
`writePlist()` (*plistlib* 모듈), 403
`writePlistToResource()` (*plistlib* 모듈), 403
`writePlistToString()` (*plistlib* 모듈), 403
`writepy()` (*zipfile.PyZipFile* 메서드), 370
`writer()` (*formatter.formatter*의 속성), 1347
`writer()` (*csv* 모듈), 384
`writerow()` (*csv.csvwriter* 메서드), 388
`writerows()` (*csv.csvwriter* 메서드), 388
`writestr()` (*zipfile.ZipFile* 메서드), 369
`writexml()` (*xml.dom.minidom.Node* 메서드), 874
`WrongDocumentErr`, 871
`ws_comma` (*2to3 fixer*), 1194
`wsgi_file_wrapper` (*wsgiref.handlers.BaseHandler*의 속성), 917
`wsgi_multiprocess` (*wsgiref.handlers.BaseHandler*의 속성), 916
`wsgi_multithread` (*wsgiref.handlers.BaseHandler*의 속성), 916
`wsgi_run_once` (*wsgiref.handlers.BaseHandler*의 속성), 916
`wsgiref` (모듈), 910
`wsgiref.handlers` (모듈), 915
`wsgiref.headers` (모듈), 912
`wsgiref.simple_server` (모듈), 913
`wsgiref.util` (모듈), 910
`wsgiref.validate` (모듈), 914
`WSGIRequestHandler` (*wsgiref.simple_server* 클래스), 913
`WSGIServer` (*wsgiref.simple_server* 클래스), 913
`wShowWindow` (*subprocess.STARTUPINFO*의 속성), 703
`WSTOPSIG()` (*os* 모듈), 438
`wstring_at()` (*ctypes* 모듈), 607

`WTERMSIG()` (*os* 모듈), 438
`WUNTRACED` (*os* 모듈), 437
`WWW`, 398, 899, 918, 971
server, 902, 983

X

`X` (*re* 모듈), 94
`-x` `regex`
compileall command line option, 1328
`X509` certificate, 736
`X_OK` (*os* 모듈), 422
`xatom()` (*imaplib.IMAP4* 메서드), 955

내장 함수

buffer, 213
cmp, 1051
compile, 64, 212, 1311
complex, 33
eval, 64, 86, 216, 217, 1311
execfile, 1280
file, 56
float, 33, 85
input, 1246
int, 33
len, 38, 52
long, 33, 86
max, 38
min, 38
raw_input, 1246
reload, 1243, 1294, 1296
slice, 212, 1337
type, 64, 211
xrange, 212
`xcor()` (*turtle* 모듈), 1107
`XDR`, 314, 400
`xdrlib` (모듈), 400
`xgtitle()` (*nntplib.NNTP* 메서드), 959
`xhdr()` (*nntplib.NNTP* 메서드), 958
`XHTML`, 837
`XHTML_NAMESPACE` (*xml.dom* 모듈), 863

모듈

__main__, 1306, 1307
_locale, 1047
AL, 1415
base64, 833
bdb, 1207
binhex, 833
bsddb, 326, 329, 333
CGIHTTPServer, 983
cmd, 1207
copy, 324
cPickle, 324
crypt, 1372
dbhash, 329
dbm, 326, 329, 332

- dumbdbm, 329
 - errno, 69, 708
 - fcntl, 57
 - formatter, 845
 - FrameWork, 1412
 - gdbm, 326, 329
 - glob, 306
 - htmllib, 924
 - icglue, 1391
 - imp, 24
 - knee, 1296, 1300
 - macerrors, 1393
 - mailbox, 827
 - math, 34, 231
 - metatools, 919
 - os, 56, 1371
 - pickle, 215, 324, 325, 328
 - pty, 420
 - pwd, 290
 - pyexpat, 890
 - re, 47, 75, 306
 - rfc822, 819
 - sgmlib, 845
 - shelve, 328
 - signal, 632
 - SimpleHTTPServer, 983
 - sitecustomize, 1278
 - socket, 56, 899
 - stat, 428
 - statvfs, 428
 - string, 47, 1051, 1052
 - struct, 716
 - SUNAUDIODEV, 1431
 - sunaudiodev, 1433
 - types, 64
 - urllib, 937
 - urlparse, 924
 - usercustomize, 1278
 - uu, 833
 - xml (모듈), 847
 - XML() (*xml.etree.ElementTree* 모듈), 856
 - XML_NAMESPACE (*xml.dom* 모듈), 863
 - xmlcharrefreplace_errors() (*codecs* 모듈), 125
 - XmlDeclHandler() (*xml.parsers.expat.xmlparser* 메서드), 893
 - xml.dom (모듈), 862
 - xml.dom.minidom (모듈), 873
 - xml.dom.pulldom (모듈), 878
 - xml.etree.ElementTree (모듈), 849
 - XMLFilterBase (*xml.sax.saxutils* 클래스), 885
 - XMLGenerator (*xml.sax.saxutils* 클래스), 885
 - XMLID() (*xml.etree.ElementTree* 모듈), 857
 - XMLNS_NAMESPACE (*xml.dom* 모듈), 863
 - XMLParser (*xml.etree.ElementTree* 클래스), 861
 - xml.parsers.expat (모듈), 890
 - XMLParserType (*xml.parsers.expat* 모듈), 890
 - XMLReader (*xml.sax.xmlreader* 클래스), 886
 - xmlrpclib (모듈), 1002
 - xml.sax (모듈), 878
 - xml.sax.handler (모듈), 880
 - xml.sax.saxutils (모듈), 885
 - xml.sax.xmlreader (모듈), 886
 - xor() (*operator* 모듈), 282
 - xover() (*nntplib.NNTP* 메서드), 959
 - xpath() (*nntplib.NNTP* 메서드), 959
 - xrange
 - 객체, 37, 48
 - 내장 함수, 212
 - xrange (2to3 fixer), 1194
 - xrange() (내장 함수), 23
 - XRangeType (*types* 모듈), 212
 - xreadlines (2to3 fixer), 1194
 - xreadlines() (*bz2.BZ2File* 메서드), 365
 - xreadlines() (*file* 메서드), 58
 - xview() (*tk.Treeview* 메서드), 1089
- ## Y
- Y2K, 452
 - ycor() (*turtle* 모듈), 1107
 - 딱이썬 향상 제안
 - PEP 1, 1446
 - PEP 8, 620, 785
 - PEP 205, 207
 - PEP 227, 1268
 - PEP 236, 7
 - PEP 237, 47
 - PEP 238, 1268, 1442
 - PEP 249, 338, 339
 - PEP 255, 1268
 - PEP 273, 1301
 - PEP 278, 1447
 - PEP 282, 311, 529
 - PEP 292, 84
 - PEP 302, 24, 307, 1243, 1296, 1301, 1303, 1304, 1306, 1307, 1442, 1444
 - PEP 305, 383
 - PEP 307, 315
 - PEP 324, 695
 - PEP 328, 1268
 - PEP 333, 910914, 917
 - PEP 338, 1307
 - PEP 343, 1259, 1268, 1440
 - PEP 366, 1308
 - PEP 370, 1279
 - PEP 378, 80
 - PEP 453, 1232
 - PEP 476, 723

PEP 477, 1232
 PEP 493, 723
 PEP 3101, 76, 77
 PEP 3105, 1268
 PEP 3112, 1268
 PEP 3116, 1447
 PEP 3119, 187, 1259
 PEP 3141, 221, 1259
 year (*datetime.datetime*의 속성), 152
 year (*datetime.date*의 속성), 148
 Year 2000, 452
 Year 2038, 452
 yeardatescalendar() (*calendar.Calendar* 메서드), 169
 yeardays2calendar() (*calendar.Calendar* 메서드), 169
 yeardayscalendar() (*calendar.Calendar* 메서드), 169
 YESEXPR (*locale* 모듈), 1049
 환경 변수
 <protocol>_proxy, 927
 AUDIODEV, 1032
 BROWSER, 899, 900
 COLUMNS, 554
 COMSPEC, 436, 699
 ftp_proxy, 919
 HOME, 290, 1280
 HOMEDRIVE, 290
 HOMEPATH, 290
 http_proxy, 919, 926, 936
 IDLESTARTUP, 1135
 KDEDIR, 901
 LANG, 1037, 1039, 1047, 1050
 LANGUAGE, 1037, 1039
 LC_ALL, 1037, 1039
 LC_MESSAGES, 1037, 1039
 LINES, 550, 554
 LNAME, 548
 LOGNAME, 413, 548
 MIXERDEV, 1032
 no_proxy, 919, 920
 PAGER, 1140, 1210
 PATH, 431, 435, 440, 899, 907, 909
 POSIXLY_CORRECT, 515
 PYTHON_DOM, 863
 PYTHONDOCS, 1140
 PYTHONDONTWRITEBYTECODE, 1236
 PYTHONHASHSEED, 260
 PYTHONNOUSERSITE, 1278, 1279
 PYTHONPATH, 907, 1243
 PYTHONSTARTUP, 692, 693, 1135, 1279
 PYTHONUSERBASE, 1278, 1279
 PYTHON2K, 452, 453
 SSL_CERT_FILE, 743

SSL_CERT_PATH, 743
 SystemRoot, 700
 TEMP, 304
 TERM, 553, 554
 TIX_LIBRARY, 1094
 TMP, 304, 429
 TMPDIR, 304, 429
 TZ, 456, 457
 USER, 548
 USERNAME, 548
 USERPROFILE, 290
 Wimp\$ScrapDir, 304
 YIELD_VALUE (*opcode*), 1334
 yiq_to_rgb() (*colorsys* 모듈), 1030
 yview() (*tk.Treeview* 메서드), 1089

Z

Zen of Python (과이썬 젠), 1447
 ZeroDivisionError, 72
 zfill() (*str* 메서드), 45
 zfill() (*string* 모듈), 88
 zip (*2to3 fixer*), 1194
 zip() (*future_builtins* 모듈), 1252
 zip() (내장 함수), 23
 ZIP_DEFLATED (*zipfile* 모듈), 367
 ZIP_STORED (*zipfile* 모듈), 367
 zipfile (모듈), 366
 ZipFile (*zipfile* 클래스), 367
 zipfile command line option
 -c <zipfile> <source1> ...
 <sourceN>, 372
 -e <zipfile> <output_dir>, 372
 -l <zipfile>, 372
 -t <zipfile>, 372
 zipimport (모듈), 1300
 zipimporter (*zipimport* 클래스), 1301
 ZipImportError, 1301
 ZipInfo (*zipfile* 클래스), 366
 zlib (모듈), 359